

ORIGINAL

**BEFORE THE FLORIDA PUBLIC
SERVICE COMMISSION**

DOCKET NO. 981246-EI

**FLORIDA POWER & LIGHT
COMPANY**

1998 DECOMMISSIONING STUDY

ST. LUCIE NUCLEAR UNIT NOS. 1 & 2

October, 1998

DOCUMENT NUMBER-DATE

10792 OCT 18

FPSC-RECORDS/REPORTING

**Florida Power & Light Company
1998 Decommissioning Study
St Lucie Unit Nos. 1 & 2
Table of Contents**

<u>Section</u>	<u>Page Numbers</u>
Executive Summary	1 - 5
• Background Information	1
• Spent Nuclear Fuel	2
• Decommissioning Study	2
• Funding Method	3
• Materials and Supplies Inventories	4
• Annual Accrual Requirements	4
• Major Assumptions	5
General Discussion	6 –13
• Decommissioning Alternatives	6
• Alternatives Considered in Study	6 - 7
• Dismantlement Alternative Selected	7
• Study Methodology	7 - 8
• Funding Alternatives – Qualified vs. Nonqualified	8 - 9
• Spent Fuel Related Costs	9 – 12
• Materials and Supplies Inventories	12
• Reserve Deficiencies	13
Annual Accrual and Revenue Requirements	14
Base Case Assumptions	15 – 21
• Base Case Assumptions Summary	15
• Decommissioning Costs	16
• Funding Method	16
• Funding Period	17
• Fund Earnings Rate	17
• Revenue Expansion Factor	18
• Escalation Rate	19
• FPL/Participants' Ownership Share of Nuclear Units	20
• FPSC Jurisdictional Factor	20
• Fund Balances	21
• Material and Supplies Inventory Values	21

DOCUMENT NUMBER-DATE
10792 OCT-18
FPSC-RECORDS/REPORTING

**Florida Power & Light Company
1998 Decommissioning Study
St Lucie Unit Nos. 1 & 2
Table of Contents**

Support Schedules	22 – 45
A. Nuclear Decommissioning Reserve Balances December 31, 1995 through August 31, 1998	22 –23
B. Nuclear Decommissioning Fund Balances December 31, 1995 through August 31, 1998	24 –25
C. Projected Fund and Reserve Balances at December 31, 1998	26 – 27
D. Reconciliation of Projected Fund and Reserve Balances at December 31, 1998	28
E. Nuclear decommissioning Theoretical Reserves	29 – 33
F. End of Life Materials and Supplies Inventories	34
G. Inflation and Funding Analysis	35 – 40
H. Calculation of Qualifying Percentages	41 – 42
I. Cost Allocation Analysis (St. Lucie Unit 2)	43 – 45
 Decommissioning Cost Study	
Prepared by - TLG Services, Inc.	46 – 224

**Florida Power & Light Company
1998 Decommissioning Study
St. Lucie Nuclear Units
Executive Summary**

Page 1 of 5

Background Information

By order Nos. 10987 and 12356, entered in Docket No. 810100-EU on July 13, 1982 and August 12, 1983, respectively, the Florida Public Service Commission (FPSC) concluded its investigation concerning the accounting for and recovery of the costs of decommissioning nuclear units. In Docket No. 810100-EU, the FPSC concluded, among other matters, that: decommissioning costs should be accrued in equal annual amounts; decommissioning costs should be accounted for separately; and decommissioning costs should be reviewed and, if necessary, changed no less often than every five years.

By Order No. 21928, entered in Docket No. 870098-EI on September 21, 1989, the FPSC considered the petitions by Florida Power and Light Company (FPL) for an increase in the accrual of nuclear decommissioning costs for the Turkey Point and St. Lucie units. Based upon its decisions regarding decommissioning methodology, the contingency allowance, escalation rates and an assumed fund earnings rate, the FPSC approved an annual accrual and associated jurisdictional revenue requirements for each of FPL's nuclear units. Order No. 21928 also provided that the approved accrual would be subject to subsequent review every five years

By Order Nos. PSC-95-1531-FOF-EI and PSC-95-1531A-FOF-EI, entered in Docket No. 941350-EI on December 12, 1995 and December 19, 1995 respectively, the FPSC considered the petitions by FPL for an increase in the accrual of nuclear decommissioning costs for the Turkey Point and St. Lucie units. Based upon its decisions regarding decommissioning methodology, including assumptions regarding extended on-site fuel storage, the contingency allowance, escalation rates and an assumed fund earnings rate, the FPSC approved an annual accrual and funding requirements for each of FPL's nuclear units with an effective date of January 1, 1995.

By Order No. PSC-98-0027-FOF-EI, Docket No. 970410-EI issued January 5, 1998, the FPSC authorized FPL to record additional decommissioning expenses to correct historical reserve deficiencies. In addition, FPL was ordered to file updated nuclear decommissioning studies by October 1, 1998.

FPL has now completed new decommissioning cost studies, prepared by TLG Services, Inc. (TLG), and prepared an updated funding and accrual analysis and an updated theoretical reserve calculation as of December 31, 1998. The information contained in this 1998 Decommissioning Study is presented in compliance with the FPSC prior Orders.

**Florida Power & Light Company
1998 Decommissioning Study
St. Lucie Nuclear Units
Executive Summary**

Page 2 of 5

Spent Nuclear Fuel Storage

The Nuclear Waste Policy Act of 1982 assigns to the Federal Government responsibility to provide for the permanent disposal of spent nuclear fuel (SNF) and high-level radioactive waste (HLW), and committed the DOE to begin acceptance of SNF/HLW not later than January 31, 1998 under terms of its Standard Disposal Contracts with waste generators. The DOE has not yet provided for SNF storage and is not accepting SNF as committed to under the contract.

In Docket No. 941350-EI, the FPSC previously recognized the impact on the decommissioning process and the potential costs of on-site dry fuel storage resulting from the inability of the DOE to provide for the timely removal of SNF. In Order No. PSC-95-1531-FOF-EI, the FPSC specifically approved the inclusion of costs associated with the dry storage of spent nuclear fuel following the end of each units operating license which were considered necessary to accommodate the timely decommissioning of each unit.

Consistent with the Commission's prior findings, this updated 1998 decommissioning study includes the costs relating to the construction, operation, and dismantlement of an on-site independent spent fuel storage installation (ISFSI) that is required to accommodate the timely decommissioning of the St. Lucie units. The potential cost impact of extended spent fuel storage beyond the current DOE five year minimum that will exist subsequent to the license expiration of the St. Lucie nuclear units is presented in Appendix D of the 1998 Decommissioning Cost Study for the St. Lucie Plant and further discussed in the "General Discussion" section of this filing.

Decommissioning Study

For purposes of this analysis, decommissioning is defined as the activity whereby nuclear facilities are removed safely from service and residual radioactivity is reduced to a level that permits release of the property for unrestricted use and termination of the operating license granted under Title 10 CFR Part 50. Decommissioning also includes the dismantlement, disposal and site restoration activities associated with the non-contaminated portion of the facilities. These activities are not required for termination of the operating license, but are required to address other non-radiological requirements associated with the release of the site.

The Nuclear Regulatory Commission (NRC) has defined three acceptable decommissioning methods: Prompt Removal/Dismantling (DECON); Safe

**Florida Power & Light Company
1998 Decommissioning Study
St. Lucie Nuclear Units
Executive Summary**

Page 3 of 5

Storage/Deferred Decontamination (SAFSTOR); and Entombment (ENTOMB). The study utilizes the NRC terminology, but also includes the additional activities required to accommodate the non-contaminated portion of the facilities.

The DECON and SAFSTOR alternatives were both examined and presented in the (TLG) St. Lucie Study. The ENTOMB alternative was not considered, because it is considered impractical for a facility which generates significant amounts of long-lived radioactive material due to neutron activation. FPL selected an integrated DECON decommissioning option for St. Lucie Units 1 and 2. Due to the difference in the operating license period of Units 1 and 2, this option entails approximately 7 years of dormancy (SAFSTOR) for Unit 1 followed by prompt dismantlement (DECON) of both Units 1 and 2. This method which is consistent with the integrated dismantlement method last approved by the FPSC in Docket No. 970410-EI, provides not only a lower cost, but also enables a sequence of events, which allows for a one-time mobilization of contractor personnel and equipment.

Funding Method

In Docket No. 810100-EU, Order No. 10987 issued July 13, 1982, the FPSC ordered FPL to establish a funded reserve. Beginning in 1983 FPL began making contributions, on a net of tax basis, to an externally funded reserve. In 1986, the Treasury Department issued temporary regulations under Internal Revenue Code Section 468A relating to the deductibility of contributions made to a qualified decommissioning fund. These regulations, which were finalized in March of 1988, provide for an annual election by the taxpayer to make tax-deductible contributions to a qualified nuclear decommissioning fund. Qualified nuclear decommissioning funds have been established by FPL for each of the four nuclear units. FPL elected to make contributions to the qualified funds, to the maximum allowed, for the years 1984 through 1987, 1992 through 1997 and is currently making maximum contributions to the qualified funds for the year 1998. For purposes of the funding analysis, maximum contributions to the qualified funds are assumed to continue for each unit through the remainder of the projected funding period that ends with the expiration of the unit's operating license.

In compliance with Order No. PSC-98-0027-FOF-EI, any additional expenses recorded to correct reserve deficiencies will be funded on an after tax basis.

000003

**Florida Power & Light Company
1998 Decommissioning Study
St. Lucie Nuclear Units
Executive Summary**

Page 4 of 5

Materials and Supplies Inventories

The decommissioning cost estimates contained in the TLG Decommissioning Cost Estimate section of this study and in the funding analysis contained in Support Schedule G of this filing do not take into consideration the unrecovered value of any Materials and Supplies Inventories that will ultimately exist at the site following shut down of both units. FPL does recognize however that there will be a level of inventories that will remain at the end of life of Unit No. 2, the last unit to reach end of license, that must be recovered prior to the end of site operations. These inventories are unique and will have little value other than scrap value when the units are decommissioned. As such, FPL has included in Support Schedule F of this filing the annual expense accrual and theoretical reserve deficiency calculations associated with the estimated End of Life inventory values.

Since the annual expense/reserve accrual associated with End of Life Inventories represents the recovery of amounts already expended, there is no need to fund these amounts and therefore amounts recorded should be accounted for in a separate (unfunded) decommissioning reserve sub-account.

Annual Accrual Requirements

Listed below are the current annual expense accrual requirements for St. Lucie Nuclear Plant Decommissioning costs, including recovery of End of Life Inventory values. Amounts are jurisdictional and exclude the participants' ownership interest in St. Lucie Unit No. 2.

	Last Approved Annual Accrual (1)	Annual Accrual Based on Est./Actual Reserves	Increase (Decrease) in Annual Accrual	Annual Accrual Based on Theoretical Reserve	Increase (Decrease) in Annual Accrual
St. Lucie Unit 1	\$24,241,074	\$29,043,992	\$ 4,802,918	\$12,310,301	\$(11,930,773)
St. Lucie Unit 2	\$19,401,261	\$23,751,299	\$ 4,350,038	\$15,327,767	\$(4,073,494)
Total	\$43,642,335	\$52,795,291	\$ 9,152,956	\$27,638,068	\$(16,004,267)

(1) As approved in Docket No. 941350-EI, Order No. PSC-95-1531-FOF-EI

000004

**Florida Power & Light Company
1998 Decommissioning Study
St. Lucie Nuclear Units
Executive Summary**

Major Assumptions

Following is a brief summary of the major assumptions used in our analysis. The "Base Case Assumptions Section" of this filing contains additional detail regarding these and other assumptions used.

	<u>ST Lucie Unit No. 1</u>	<u>ST. Lucie Unit No. 2</u>
DECOMMISSIONING FUNDS		
A. Decommissioning Method	SAFSTOR/ Integrated DECON (Prompt Removal/ Dismantling)	DECON (Prompt Removal/ Dismantling)
B. Total Decommissioning Cost Per TLG Services, Inc. (Present value @ 12/31/98)	\$ 428,917,221	\$453,151,198
C. FPL's Cost of Decommissioning (Jurisdictional and net of Participants' obligation)	\$ 425,734,655	\$383,141,043
D. Method of Funding (1999 - End)	Qualified	Qualified
E. Qualified Fund Percentage	77.14%	97.56%
F. Funding Periods (Years)	17.167	24.25
G. Assumed Fund Earnings Rate	4.9%	4.9%
H. Escalation rate for Decommissioning Costs (1999 - End)	6.4%	6.2%
I. FPL Ownership Allocation	100%	85.18243%
MATERIALS & SUPPLIES INVENTORIES		
J. Inventory Value at End of Life (net of Participants' obligation)	N/A	\$ 16,216,455
RESERVE DEFICIENCIES @ 12/31/98		
K. 1. Decommissioning	\$ 171,482,861	\$ 97,820,512
2. Inventories	\$ -	\$ 6,281,742
L. Method of Funding (1999 - End)		
1. Decommissioning	Non Qualified	Non Qualified
2. Inventories	Non Funded Reserve	Non Funded Reserve

000005

**Florida Power & Light Company
1998 Decommissioning Study
St. Lucie Nuclear Units
General Discussion**

Page 1 of 8

DECOMMISSIONING ALTERNATIVES

The Nuclear Regulatory Commission's (NRC) "General Requirements for Decommissioning Nuclear Facilities" defines three decommissioning alternatives acceptable to the NRC, i.e., DECON, SAFSTOR and ENTOMB.

DECON is defined by the NRC as "the alternative in which equipment, structures, and the portions of a facility and site containing radioactive contaminants are removed or decontaminated to a level that permits the property to be released for unrestricted use shortly after cessation of operations."

SAFSTOR is defined as "the alternative in which the nuclear facility is placed and maintained in a condition that allows the nuclear facility to be safely stored and subsequently decontaminated (deferred decontamination) to levels that permit release for unrestricted use."

ENTOMB is defined as "the alternative in which radioactive contaminants are encased in a structurally long-lived material, such as concrete; the entombed structure is appropriately maintained and continued surveillance is carried out until the radioactive material decays to a level permitting unrestricted release of the property."

Currently, all three alternatives are limited to an overall duration of 60 years per Title 10 CFR Part 50.82 (a)(3) unless the utility can demonstrate that a longer period is necessary to protect the public health and safety.

On April 3, 1997 the NRC Commissioners requested that the NRC staff provide it with an analysis of whether or not the staff views entombment as a viable decommissioning option and how this option has been dealt with previously by the Commission. The Staff Requirements Memorandum (SRM) state that if the staff concludes that entombment is not a viable option, then the staff should describe the technical requirements and regulatory actions which would be necessary for entombment to become a viable decommissioning option, and that the staff analysis should include the resources involved, potential decommissioning cost savings, and vulnerabilities. To date, the NRC staff has delivered a status report on this effort (SECY-98-099).

ALTERNATIVES CONSIDERED IN STUDY

The DECON and SAFSTOR alternatives were examined for the St. Lucie Study. The ENTOMB alternative was not considered, because it is considered impractical for a facility which generates significant amounts of long-lived radioactive material due to

**Florida Power & Light Company
1998 Decommissioning Study
St. Lucie Nuclear Units
General Discussion**

Page 2 of 8

neutron activation. Specific attributes of the ENTOMB alternative which make it uneconomical when compared to the DECON and SAFSTOR alternatives are:

- a large up-front expenditure is required to encase the contaminated portion of the facility;
- workers incur greater levels of occupational exposure (compared to SAFSTOR);
- the plant must still be decontaminated and dismantled to complete decommissioning prior to the end of the 60 year period; and
- no significant reductions in low level radioactive waste (LLRW) volumes are achieved due to the 60-year time limitation.

DISMANTLEMENT ALTERNATIVE SELECTED

FPL selected an integrated DECON decommissioning option for St. Lucie Units 1 and 2. Due to the difference in the operating license period for St. Lucie Unit 1 and Unit 2, this option entails approximately 7 years of dormancy for Unit 1 followed by prompt dismantlement of both Units 1 and 2. This option was selected for three reasons.

1. Integrated dismantlement provides the lowest estimated cost in current dollars and enables a sequence of events which allows for a one-time mobilization of contractor personnel and equipment.
2. This method results in the lowest estimated revenue requirement.
3. Given the current uncertainty of future decommissioning costs, the integrated dismantlement option exposes ratepayers and FPL Group shareholders to the least amount of risk. FPL recommends decontamination and dismantlement of facilities in the shortest practical period of time following the end of commercial operation of St. Lucie Unit 2 in 2023.

Additionally, the integrated DECON decommissioning option selected is consistent with integrated dismantling method last approved by the Commission for the St. Lucie Units in Docket No. 941350-EI.

STUDY METHODOLOGY

The TLG study for St. Lucie follows the basic approach originally presented in the Atomic Industrial Forum/National Environmental Studies Project report AIF/NESP-036, "Guidelines for Producing Commercial Nuclear Power Plant Decommissioning Cost Estimates". The contents of those guidelines were prepared under the review of a task force consisting of representatives from utilities, state regulatory commissions, architect/engineering firms, the Federal Energy Regulatory Commission, the NRC, and

**Florida Power & Light Company
1998 Decommissioning Study
St. Lucie Nuclear Units
General Discussion**

Page 3 of 8

the National Association of Regulatory Utility Commissioners. The study also utilizes guidance provided in the Department of Energy (DOE) "Decommissioning Handbook".

These references utilize a unit cost factor method for estimating decommissioning activity costs to simplify the estimating calculations. Unit cost factors for concrete removal, steel removal and cutting costs were developed from labor and material cost information provided by FPL. With the item quantity developed from plant drawings, inventory documents and equipment databases, the activity-dependent costs are estimated. The unit cost factors used in the study reflect the latest available information about worker productivity in decommissioning projects, including the Shippingport, Pathfinder, Shoreham, Yankee Rowe and Trojan reactors.

The activity duration critical path was used to determine the total decommissioning program schedule. The program schedule is used to determine the period-dependent costs for program management, administration, engineering, equipment rental, quality assurance and security costs.

The activity and period-dependent costs are combined to develop the total decommissioning costs. Contingency factors are then applied to major cost activities to provide for the types of unforeseeable events that are likely to occur in decommissioning.

FUNDING ALTERNATIVES
QUALIFIED vs NONQUALIFIED

Prior to 1989

In Docket No. 810100-EU, Order No. 10987 issued July 13, 1982, the Florida public Service Commission ordered FPL to establish an internally funded reserve. FPL made net of tax contributions to the fund from 1983 through 1987. In January 1988, FPL made qualified contributions for tax years 1984 through 1986 and funds were transferred from the nonqualified fund to the qualified funds. The qualified contributions for tax year 1987 were made in March 1988. FPL elected to make contributions to qualified decommissioning funds for the tax years 1984 through 1987 since it believed the advantages of a qualified fund outweighed any disadvantages in those years. The reduction in corporate Federal income tax rates effective July 1, 1987 was a major consideration in reaching this conclusion. The decision to make qualified election for these years was reviewed and approved by the Commission in Order No. 21928.

000008

**Florida Power & Light Company
1998 Decommissioning Study
St. Lucie Nuclear Units
General Discussion**

Page 4 of 8

Present Company Treatment - 1989 to Date

Subsequent to 1988 the Company elected to make qualified contributions for the years 1992 through 1997, and is currently making qualified contributions, to the maximum allowed, for the year 1998. The increase in the corporate Federal income tax rate effective 1/1/93 and the introduction of tax legislation which ultimately resulted in the reduction in the Federal income tax rate applicable to the earnings of the qualified funds from the maximum corporate Federal income tax rate to a rate of 22% for 1994 and 1995 and to 20% for years thereafter, were primary considerations which led to the election of qualified contributions for the years subsequent to 1991.

SPENT FUEL-RELATED COSTS

Background and Regulatory Guidance

Nuclear Waste Policy Act of 1982

The Nuclear Waste Policy Act of 1982 (NWPAA) assigns to the Federal Government responsibility to provide for the permanent disposal of spent nuclear fuel (SNF) and high-level radioactive waste (HLW), and committed the DOE to begin acceptance of SNF/HLW not later than January 31, 1998 under the terms of its Standard Disposal Contracts with waste generators. The DOE has not yet provided for SNF storage and is not accepting SNF as committed to under the contract.

The generators of waste are expected to bear the cost of disposal. The operators of commercial reactors fund DOE's efforts through the 1.0 mil per kilowatt-hour charge assessed on the electricity generated by the SNF.

Specific Regulations

Three provisions of current regulations affect decommissioning and SNF storage options.

1. Current NRC policy requires removal of all SNF from a facility licensed under Title 10 CFR Part 50 before decommissioning can be accomplished.
2. Title 10 CFR Part 50.54 (bb) requires the licensee, within 2 years following permanent cessation of operation of the reactor or 5 years before expiration of the reactor operating license, whichever occurs first, to submit written notification to the NRC for its review and preliminary approval of the program by which the licensee intends to manage and provide funding for the management of all irradiated fuel at

**Florida Power & Light Company
1998 Decommissioning Study
St. Lucie Nuclear Units
General Discussion**

Page 5 of 8

the reactor following permanent cessation of operation of the reactor until title to the irradiated fuel and possession of the fuel is transferred to the Secretary of Energy for its ultimate disposal in a repository. However, the NRC does not currently consider SNF management costs after expiration of the operating license, to be decommissioning costs.

3. Title 10 CFR Part 961, Appendix E requires SNF to be cooled in the spent fuel pools for at least five years before DOE can accept it.

Litigation

FPL, along with a number of electric utilities, sued DOE over DOE's denial of its obligation to accept SNF beginning in 1998. On July 23, 1996, the U.S. Court of Appeals for the District of Columbia Circuit (D.C. Circuit) held that DOE is required by the Nuclear Waste Policy Act (NWPA) to take title and dispose of SNF from nuclear power plants beginning on January 31, 1998 (Indiana Michigan Power Co. v. Department of Energy). DOE declined to seek further review of the decision, which was remanded to DOE for further proceedings. On December 17, 1996, DOE advised the electric utilities that it would not begin to dispose of SNF by the unconditional deadline.

In response to DOE's letter, FPL, other electric utilities, and state utility commissions filed suit on January 31, 1997 in the D.C. Circuit (Northern States Power Co. v. DOE) requesting that the court authorize the utilities to suspend payments into the Nuclear Waste Fund (NWF) until DOE performs on its unconditional obligation to take title to and dispose of SNF.

On November 14, 1997, a panel of the D.C. Circuit found that DOE did not abide by the Court's earlier ruling that the NWPA imposes an unconditional obligation on DOE to begin disposal of spent fuel by January 31, 1998. The Court's order precludes DOE from excusing its own delay on the grounds that it has not yet prepared a permanent repository or interim storage facility. The Court did not grant the other requests for relief.

On February 19, 1998, 41 utility petitioners asked the federal appellate court to enforce its November 14, 1997 ruling. The utilities requested an enforcement order because DOE had demonstrated that it would manipulate the remedial provisions of its disposal contract with the utilities in a manner that would make the Standard Contract remedy meaningless. Specifically, DOE had indicated intent to pay damages out of the NWF.

On May 5, 1998, a panel of the D.C. Circuit issued a decision that denied the enforcement motion along with other motions and petitions in the proceeding.

**Florida Power & Light Company
1998 Decommissioning Study
St. Lucie Nuclear Units
General Discussion**

Page 6 of 8

On June 8, 1998, FPL filed suit in the United States Court of Federal Claims seeking damages from the United States in excess of \$300,000,000 for DOE's failure to comply with its statutory obligation to take title to and dispose of SNF. A major element of the damages is the additional decommissioning accrual necessary as a result of DOE's delayed acceptance of SNF.

On August 3, 1998 a number of states and utility commissions petitioned the U. S. Supreme Court to review the November 14, 1997 decision of the D. C. Circuit that it lacked authority to order DOE to begin spent fuel disposal. On September 1, 1998, DOE asked the U. S. Supreme Court to review the November 14, 1997 decision of the D. C. Circuit precluding DOE from excusing its own delay on grounds that it has not prepared a permanent repository or interim storage facility.

1998 Decommissioning Study Assumptions

The decommissioning study assumes that FPL will incur additional costs for the storage of SNF. A separate appendix in the study estimates FPL's decommissioning costs if DOE had met its obligation to begin accepting fuel in January 1998.

Impact Of Delay In DOE's Acceptance Of SNF

FPL assumes the following in the delayed SNF acceptance scenario.

- Dry storage of SNF is more cost effective than wet storage.
- DOE will not supply multipurpose canisters (MPCs) for on-site storage of SNF. The DOE terminated the MPC program in 1996 due to reduced appropriations for the waste program.
- FPL will pay for storage canisters.
- DOE's geologic repository will begin accepting SNF in 2010.
- The geologic repository will accept fuel at the receipt/emplacement rate projected in the "Analysis of the Total System Life Cycle Cost of the Civilian Radioactive Waste Management Program" (DOE/RW-0479, September 1995). This projection assumes that the repository will reach an annual acceptance rate of 3,000 Metric Tons of Uranium (MTU) in the fifth year of operation.

FPL expects that an independent spent fuel storage installation (ISFSI) will be developed under the provisions of Title 10 CFR Part 72 between 2002 to 2004. Since the St. Lucie units have inadequate spent fuel pool capacity to accommodate expected SNF discharges through the end of commercial operation, a dry storage facility will be required to reach the end of the operating licenses. Approximately 27% of the ISFSI

**Florida Power & Light Company
1998 Decommissioning Study
St. Lucie Nuclear Units
General Discussion**

Page 7 of 8

capacity will be required to enable operation of the St. Lucie units to the end of their respective operating licenses. The remaining 73% of facility capacity will be required to permit transfer of SNF from the spent fuel pools to dry storage from 2016 through 2028. The ISFSI is expected to operate until 2040, when all SNF is expected to be off-site. Ultimately, the ISFSI will be decommissioned and the Part 72 license associated with the facility will be terminated.

SNF Impact on Decommissioning Schedule and Cost

The movement of the SNF to an ISFSI permits the termination of the Title 10 CFR Part 50 licenses in 2030 for both units. However, the completion of decommissioning for the entire site is delayed until 2040. The impacts of delayed acceptance of SNF by DOE on decommissioning costs are as follows:

1. Capital expenditures are necessary for the portion of the ISFSI facility required to enable complete transfer of the spent fuel pool inventories to dry storage after the mandated 5 year cooling period. This is expected to be approximately 73% of the total facility capacity.
2. ISFSI operation costs are incurred after the shut down of Unit 2 from 2023 through 2040.
3. ISFSI dismantlement and disposal costs are incurred.

Materials and Supplies Inventories

The decommissioning cost estimates contained in the TLG Decommissioning Cost Estimate section of this study and in the funding analysis contained in Support Schedule G of this filing do not take into consideration the unrecovered value of any Materials and Supplies Inventories that will ultimately exist at the site following shut down of both units. FPL does recognize however that there will be a level of inventories that will remain at the end of life of Unit No. 2, the last unit to reach end of license, that must be recovered prior to the end of site operations. These inventories are unique and will have little value other than scrap value when the units are decommissioned. As such, FPL has included in Support Schedule F of this filing the annual expense accrual and theoretical reserve deficiency calculations associated with the estimated End Of Life (EOL) inventory values.

Since the annual expense/reserve accrual associated with EOL Inventories represents the recovery of amounts already expended, there is no need to fund these amounts and therefore amounts recorded should be accounted for in a separate (unfunded) decommissioning reserve sub-account.

**Florida Power & Light Company
1998 Decommissioning Study
St. Lucie Nuclear Units
General Discussion**

Page 8 of 8

Reserve Deficiencies

By Order No. PSC-98-0027-FOF-EI, Docket No. 9710410-EI issued January 5, 1998, the Commission authorized FPL to record additional decommissioning expenses to correct historical reserve deficiencies. In addition, FPL was ordered to file updated nuclear decommissioning studies by October 1, 1998. The amount of reserve deficiency to be recovered by FPL as additional expense would then be determined based on these updated studies. In compliance with the Commission Order, FPL has included in this 1998 Decommissioning Study (Support Schedule E) filing an updated calculation of the theoretical reserve deficiency as of December 31, 1998.

Florida Power & Light Company
1998 Nuclear Decommissioning Study
St. Lucie Nuclear Units
Annual Accrual and Revenue Requirements

Page 1 of 1

Given below are the estimated costs of decommissioning, annual accruals, and revenue requirements. The assumptions upon which these figures are based are given in the "Base Case Assumptions" section of this filing.

	<u>St Lucie Unit No. 1</u>	<u>St Lucie Unit No. 2</u>
<u>DECOMMISSIONING COSTS</u>		
Total Decommissioning Costs per TLG Services Inc. (Present Value @ 12/31/98)	\$428,917,221	\$453,151,198
FPL's Share of Total Decommissioning Costs	\$428,917,221	\$386,005,202
Participants Share of Total Decommissioning Costs (1)	\$0	\$67,145,996
FPL's Share of Total Decommissioning Costs Jurisdictionalized @ 99.258%	\$425,734,655	\$383,141,043
Inventory Value @ End Of Life	N/A	\$17,521,406
FPL's Share of Inventory Value Jurisdictionalized @ 99.258%	N/A	\$16,096,129
<u>ANNUAL EXPENSE ACCRUALS</u>		
<u>Based on Actual Reserve Balances</u>		
FPL's Total Annual Accrual Including (EOL) Inventories (Net of Participants Obligation)	\$29,261,109	\$23,928,851
FPL's Total Annual Accrual Including (EOL) Inventories (Net of Participants Obligation) Jurisdictionalized @ 99.258%	\$29,043,992	\$23,751,299
<u>Based on Theoretical Reserve</u>		
FPL's Total Annual Accrual Including (EOL) Inventories (Net of Participants Obligation)	\$12,402,326	\$15,442,349
FPL's Total Annual Accrual Including (EOL) Inventories (Net of Participants Obligation) Jurisdictionalized @ 99.258%	\$12,310,301	\$15,327,767
<u>ANNUAL REVENUE REQUIREMENT</u>		
<u>Based on Actual Reserve Balances</u>		
Total Annual Revenue Requirement to Recover FPL's Cost of Decommissioning and (EOL) Inventories (Net of Participants Obligation) Jurisdictionalized @ 99.258%	\$29,591,180	\$24,198,773
<u>Based on Theoretical Reserve</u>		
Total Annual Revenue Requirement to Recover FPL's Cost of Decommissioning and (EOL) Inventories (Net of Participants Obligation) Jurisdictionalized @ 99.258%	\$12,542,227	\$15,616,542

A detailed analysis deriving the annual accruals, and funding may be found in Support Schedule E (Theoretical Reserves) Support Schedule F (M&S Inventories) and Support Schedule G ("Inflation and Funding Analysis"),

- (1) The participants share of total decommissioning costs includes their share of common facility costs. See "FPL/Participant Ownership share of Nuclear Units" on page 6 in the "Base Case Assumptions" Section of this filing.

000014

**Florida Power & Light Company
1998 Decommissioning Study
St. Lucie Nuclear Units
Base case Assumptions**

Page 1 of 7

Following is a summary of the assumptions used to derive the annual accrual, and funding and revenue requirement amounts sought by FPL. These assumptions are more fully developed on the following pages.

1. Base Case Assumptions Summary

	<u>Unit No. 1</u>	<u>Unit No. 2</u>
A. Decommissioning Method	SAFSTOR/ Integrated DECON (Prompt Removal/ Dismantling	DECON (Prompt Removal/ Dismantling)
B. Total Decommissioning Cost Per TLG Services, Inc. (Present value @ 12/31/98)	\$ 428,917,221	\$ 453,151,198
C. FPL's Cost of Decommissioning (Jurisdictional and net of Unit No. 2 Participants' obligation)	\$ 425,734,655	\$ 383,141,043
D. Method of Funding (1999 – End)	Qualified	Qualified
E. Funding Periods (Years)	17.167	24.25
F. Assumed Fund Earnings rate	4.9%	4.9%
G. Escalation Rate for Decommissioning Costs (1999 – End)	6.4%	6.2%
H. FPL Ownership Allocation (%)	100%	85.18243%
I. FPSC Jurisdictional Separation Factor (%)	99.258%	99.258%
J. Estimated Fund Balance - Qualified (1/1/99)	\$ 174,427,000	\$ 157,221,000
K. Estimated fund Balance - Nonqualified (1/1/99)	\$ 68,197,000	\$ 39,552,000
L. M & S Inventory Value (Net Of Participants' obligation)	N/A	\$16,216,455

000015

**Florida Power & Light Company
1998 Decommissioning Study
St. Lucie Nuclear Units
Base case Assumptions**

Page 2 of 7

2. Decommissioning Costs

Below are the estimated costs of Decommissioning the St. Lucie facility as provided by TLG in 1998 dollars.

St. Lucie Unit No. 1

Labor	\$	230,838,470
Materials		70,724,459
Shipping		4,223,851
Burial		97,920,869
Other		<u>25,209,572</u>
Total		428,917,221

St. Lucie Unit No. 2

Labor	\$	258,689,160
Materials		82,136,889
Shipping		3,964,998
Burial		88,700,599
Other		<u>19,659,552</u>
Total		453,151,198

3. Funding Method

Beginning in 1999, it is assumed for both units, contributions will be made to the Qualified Funds for the maximum allowed by the IRS. The Internal Revenue Code and Regulations limit future qualified fund contributions. The Qualified Percentage for any unit is defined as the percentage of that unit's life for which there is established a qualified fund. This Qualified Percentage is applied to the unit's total estimated decommissioning cost to calculate the portion of the decommissioning cost the Internal Revenue (IRS) will consider qualified for a deduction for the tax year. However, after the IRS determines such amounts, they will, in addition, be limited to the amount included in cost of service in each year. The qualifying percentages for each of the two units are:

	<u>Qualifying Percentage</u>
St. Lucie Unit No. 1	77.14%
St. Lucie Unit No. 2	97.56%

The Qualifying Percentage Calculations can be found in Support Schedule F "Calculation of Qualifying Percentages".

**Florida Power & Light Company
1998 Decommissioning Study
St. Lucie Nuclear Units
Base case Assumptions**

Page 3 of 7

4. Funding Period

The funding period is that period over which revenues are collected from ratepayers for purposes of decommissioning the St. Lucie Units.

The funding period over which the new funding and revenue requirement figures are computed for St. Lucie No. 1 and No. 2 is assumed to begin in 1999.

Funding periods for both units will end on the last day of the month preceding the month in which the operating license for the unit is due to expire. License expiration dates for the St. Lucie units are as follows.

- St. Lucie Unit No. 1 - March 1, 2016
- St. Lucie unit No. 2 - April 6, 2023

5. Fund Earnings Rate

In Order No. PSC-95-1531-FOF-EI, Docket No. 941350-EI the Commission found the appropriate fund earnings rate, net of taxes and all other administrative costs charged to the trust fund, to be 4.90%. This rate represented the long term average CPI rate of change as forecasted by DRI for the period over which the funds will be invested, plus an additional 1.10 basis points (3.80% + 1.10%).

For purposes of this 1998 study update the projected annual funds earnings rate, net of taxes and all other administrative costs charged to the trust funds, for Units 1 and 2 qualified and nonqualified fund investments, is assumed to be 4.9%. Consistent with the Commission's prior findings, this rate is 1.10 basis points above the forecasted average annual rate of change in the CPI for the period 1999 through the end of the decommissioning period for each unit. The annual rates of change were taken from the most recently published DRI forecast (Fall/Winter 1997-1998).

Florida Power & Light Company
1998 Nuclear Decommissioning Study
St. Lucie Nuclear Units
Base Case Assumptions

Page 4 of 7

6. Revenue Expansion Factor

	<u>Qualified</u>	<u>Non-Qualified</u>
Decommissioning Revenue Requirement	100.0000%	100.0000%
Less:		
Gross Receipts Tax	1.5000%	
Regulatory Assessment Fee	0.0833%	
Uncollectible Accounts	<u>0.2656%</u>	
	<u>1.8489%</u>	<u>1.8489%</u>
Net Before Income Taxes	98.1511%	98.1511%
Less:		
State Income Tax Rate at 5.5%	<u>0</u>	<u>5.3983%</u>
Net Before Federal Income Taxes	98.1511%	92.7528%
Less:		
Federal Income Tax Rate at 35.0%	<u>0</u>	<u>32.4635%</u>
Net After State and Federal Income Taxes	98.1511%	60.2893%
Revenue Expansion Factor (Revenue Requirements/Net After State and Federal Income Taxes)	<u>1.01884 (a)</u>	<u>1.65867 (b)</u>

(a) Revenue Expansion Factor/Multiplier applicable to funding requirement and accrual.

(b) Revenue Expansion Factor/Multiplier applicable to (after tax) funding requirement.

Revenue Expansion Factor/Multiplier applicable to (before tax) accrual requirement
is the same as shown for the Qualified fund.

**Florida Power & Light Company
1998 Decommissioning Study
St. Lucie Nuclear Units
Base case Assumptions**

Page 5 of 7

7. Escalation Rate

The annual escalation rates used to estimate total future dismantlement costs from January 1, 1999 through the final year of decommissioning are as follows:

	<u>Average Annual Escalation Rate</u>
St. Lucie Unit No. 1	6.4%
St. Lucie Unit No. 2	6.2%

The above rates were derived by applying separate inflation indices to each of the major cost components of Labor, Materials and Equipment, Shipping, Burial, and Other.

<u>Cost Component</u>	<u>Inflation Index</u>
Labor	Compensation per Hour
Materials and Equip.	PPI - Intermediate Materials, Supplies, and Components
Shipping	GDP Deflator-Transportation
Burial	FPL Analysis & CPI
Other	GDP (Implicit)

A near-term (assumed for 1999) escalation rate of 138.20% for Low Level Radioactive Waste Disposal was developed based on an estimated increase in burial rates required to bring the price at the existing Barnwell S.C. burial facility to a level necessary to reach equilibrium (i.e., to generate sufficient revenues to cover anticipated fixed and variable costs). Burial costs for the years 2000 through the end of the decommissioning period are assumed to increase at a rate similar to general inflation, adjusted for variability historically exhibited by LLRW disposal costs (Forecasted CPI + 3.50%). The rate of increase in LLRW burial cannot be predicted with exact certainty, however, the resulting annual increase is considered reasonable and is below the average annual increase experienced since 1986.

For a more detail calculation of the weighted average Escalation rate and annual rate of change for each component please refer to Support Schedule G ("Inflation and Funding Analysis") on pages 1 through 3.

**Florida Power & Light Company
1998 Decommissioning Study
St. Lucie Nuclear Units
Base case Assumptions**

Page 6 of 7

8. FPL/Participant Ownership Share of Nuclear Units

The participants and their ownership interests in the St. Lucie facility are as follows:

	<u>St. Lucie Unit No. 1</u>	<u>St. Lucie Unit No. 2</u>
Florida Power & Light Company	100.0%	85.10449%
Orlando Utilities Commission	0.0	6.08951
Florida Municipal Power Agency	0.0	8.80600
Total	<u>100.0%</u>	<u>100.00000%</u>

For purposes of allocating decommissioning costs between FPL and Participants in the St. Lucie Unit No. 2, an adjustment was made to the ownership percentages to reflect the appropriate Common Facility cost obligation of participants.

This adjustment was necessary because the decommissioning cost study attributes common facility costs to St. Lucie No. 2. Because the Participants contractual obligation currently provides that they pay for only their ownership share times one-half of the common facility costs, to apply their ownership share to the total cost of decommissioning Unit No. 2 would overstate the participants' cost obligation. This adjustment to the ownership percentage is reflected in what is termed a "Cost Allocation Factor" and represents the cost obligation of FPL and participants as a percentage of the total costs of decommissioning. The "Cost Allocation Factor" calculation is given in Support Schedule G "Cost Allocation Analysis".

The Cost Allocation Factors for St. Lucie Unit No. 2 are:

	<u>St. Lucie No. 2</u>
Florida Power & Light Company	85.18243%
Participants	14.81757
Total	<u>100.00000%</u>

9. FPSC Jurisdictional Factors

The factor applicable to both units is 99.258%.

000020

**Florida Power & Light Company
1998 Decommissioning Study
St. Lucie Nuclear Units
Base case Assumptions**

Page 7 of 7

10. Fund Balances

Estimated/actual fund balances (qualified and nonqualified) at December 31, 1998 for each of the two St. Lucie Units are as Follows:

	\$(000)	
	<u>Qualified</u>	<u>Nonqualified</u>
Unit No. 1	\$ 174,427	\$ 68,197
Unit No. 2	\$ 157,221	\$ 39,552

See support Schedule C ("Projected Fund and Reserve Balances") for detail composition and adjustments to the qualified and nonqualified fund balances.

11. Materials and Supplies Inventory Values

The Materials and Supplies inventory balance, less estimated salvage, that is anticipated to remain at the end of life of Unit No. 2, the last unit to reach end of license, is projected to be \$ 16,216,455 (Net of Participants' obligation).

See Support Schedule F ("End-of-Life Materials and Supplies Inventory) for annual expense accrual and reserve deficiency calculations.

Florida Power & Light Company
1998 Decommissioning Study
Support Schedule: Nuclear Decommissioning Reserve Balances
December 31, 1995 through August 31, 1998
\$000

Support Schedule A
Page 1 of 2

<u>December 31, 1995</u>	<u>Beginning Balance</u>	<u>Revenues Collected</u>	<u>Earnings to Reserve</u>	<u>Ending Balance</u>	<u>Interest On Tax Benefits Of Qualified Contribution</u>	<u>Adjusted Ending Balance</u>
<u>NONQUALIFIED</u>						
Turkey Point Unit No. 3	77,959	5,177	5,352	88,488	4,453	92,941
Turkey Point Unit No. 4	83,074	6,420	5,765	95,259	3,341	98,600
St. Lucie Unit No. 1	77,611	4,282	1,200	83,094	9,071	92,165
St. Lucie Unit No. 2	46,752	3,872	7,327	57,950	1,107	59,058
TOTAL	285,396	19,751	19,644	324,791	17,973	342,764

<u>QUALIFIED</u>						
Turkey Point Unit No. 3	51,975	12,780	3,902	68,657		68,657
Turkey Point Unit No. 4	50,925	16,307	3,867	71,100		71,100
St. Lucie Unit No. 1	61,265	20,140	4,584	85,990		85,990
St. Lucie Unit No. 2	57,864	15,675	4,308	77,847		77,847
TOTAL	222,029	64,902	16,662	303,593	0	303,593

<u>TOTAL RESERVES</u>						
Turkey Point Unit No. 3	129,934	17,957	9,254	157,144	4,453	161,598
Turkey Point Unit No. 4	134,000	22,727	9,632	166,359	3,341	169,700
St. Lucie Unit No. 1	138,876	24,422	5,785	169,083	9,071	178,154
St. Lucie Unit No. 2	104,616	19,546	11,636	135,798	1,107	136,905
TOTAL	507,425	84,652	36,306	628,384	17,973	646,357

December 31, 1996

<u>NONQUALIFIED</u>					
Turkey Point Unit No. 3	92,941	501	4,842	98,284	
Turkey Point Unit No. 4	98,600	801	5,663	105,065	
St. Lucie Unit No. 1	92,165	(482)	5,230	96,913	
St. Lucie Unit No. 2	59,058	(3,857)	3,188	58,389	
TOTAL	342,764	(3,037)	18,924	358,651	

<u>QUALIFIED</u>					
Turkey Point Unit No. 3	68,657	17,456	2,459	88,572	
Turkey Point Unit No. 4	71,100	21,927	2,558	95,584	
St. Lucie Unit No. 1	85,990	24,904	3,055	113,949	
St. Lucie Unit No. 2	77,847	23,403	2,843	104,093	
TOTAL	303,593	87,689	10,915	402,198	

<u>TOTAL RESERVES</u>					
Turkey Point Unit No. 3	161,598	17,957	7,302	186,856	
Turkey Point Unit No. 4	169,700	22,727	8,221	200,649	
St. Lucie Unit No. 1	178,154	24,422	8,286	210,862	
St. Lucie Unit No. 2	136,905	19,546	6,031	162,482	
TOTAL	646,357	84,652	29,840	760,849	

000022

Florida Power & Light Company
1998 Decommissioning Study
Support Schedule: Nuclear Decommissioning Reserve Balances
December 31, 1995 through August 31, 1998
\$000

Support Schedule A
Page 2 of 2

<u>December 31, 1997</u>	<u>Beginning Balance</u>	<u>Revenues Collected</u>	<u>Earnings to Reserve</u>	<u>Ending Balance</u>
<u>NONQUALIFIED</u>				
Turkey Point Unit No. 3	98,284	2,839	5,060	106,183
Turkey Point Unit No. 4	105,065	3,610	5,411	114,086
St. Lucie Unit No. 1	96,913	1,900	4,986	103,799
St. Lucie Unit No. 2	58,389	7	3,010	61,407
TOTAL	358,651	8,357	18,466	385,474

<u>QUALIFIED</u>				
Turkey Point Unit No. 3	88,572	15,118	4,013	107,702
Turkey Point Unit No. 4	95,584	19,117	4,330	119,031
St. Lucie Unit No. 1	113,949	22,522	5,122	141,594
St. Lucie Unit No. 2	104,093	19,539	4,678	128,310
TOTAL	402,198	76,296	18,143	496,637

TOTAL RESERVES

Turkey Point Unit No. 3	186,856	17,957	9,072	213,885
Turkey Point Unit No. 4	200,649	22,727	9,740	233,116
St. Lucie Unit No. 1	210,862	24,422	10,108	245,393
St. Lucie Unit No. 2	162,482	19,546	7,688	189,717
TOTAL	760,849	84,652	36,609	882,111

August 31, 1998

<u>NONQUALIFIED</u>				
Turkey Point Unit No. 3	106,183	(3,199)	3,899	106,882
Turkey Point Unit No. 4	114,086	(4,179)	4,144	114,051
St. Lucie Unit No. 1	103,799	(6,275)	3,642	101,165
St. Lucie Unit No. 2	61,407	(6,523)	2,010	56,893
TOTAL	385,474	(20,176)	13,694	378,992

<u>QUALIFIED</u>				
Turkey Point Unit No. 3	107,702	15,170	5,646	128,519
Turkey Point Unit No. 4	119,031	19,330	6,168	144,529
St. Lucie Unit No. 1	141,594	22,557	7,473	171,624
St. Lucie Unit No. 2	128,310	19,554	6,830	154,694
TOTAL	496,637	76,611	26,118	599,366

TOTAL RESERVES

Turkey Point Unit No. 3	213,885	11,971	9,545	235,401
Turkey Point Unit No. 4	233,116	15,152	10,312	258,580
St. Lucie Unit No. 1	245,393	16,282	11,115	272,789
St. Lucie Unit No. 2	189,717	13,031	8,840	211,587
TOTAL	882,111	56,435	39,812	978,358

000023

Florida Power & Light Company
1998 Decommissioning Study
Support Schedule: Nuclear Decommissioning Fund Balances
December 31, 1995 through August 31, 1998
\$000

Support Schedule B
Page 1 of 2

	Beginning Balance	Contribution	Fund Earnings	Ending Balance	Tax Benefits and Interest On Qualified Contribution	Adjusted Ending Balance
<u>December 31, 1995</u>						
<u>NONQUALIFIED</u>						
Turkey Point Unit No. 3	43,327	3,180	3,288	49,795	7,014	56,809
Turkey Point Unit No. 4	47,818	3,944	3,541	55,303	5,263	60,565
St Lucie Unit No. 1	42,967	2,630	3,283	48,880	7,732	56,612
St Lucie Unit No. 2	23,644	2,378	1,955	27,978	8,299	36,276
Total	157,757	12,132	12,067	181,955	28,307	210,262
<u>QUALIFIED</u>						
Turkey Point Unit No. 3	51,975	12,780	3,902	68,657		68,657
Turkey Point Unit No. 4	50,925	16,307	3,867	71,100		71,100
St Lucie Unit No. 1	61,265	20,140	4,584	85,990		85,990
St Lucie Unit No. 2	57,864	15,675	4,308	77,847		77,847
Total	222,029	64,902	16,662	303,593	0	303,593
<u>TOTAL</u>						
Turkey Point Unit No. 3	95,302	15,960	7,190	118,452	7,014	125,466
Turkey Point Unit No. 4	98,744	20,251	7,408	126,402	5,263	131,665
St Lucie Unit No. 1	104,232	22,770	7,868	134,870	7,732	142,602
St Lucie Unit No. 2	81,509	18,053	6,263	105,825	8,299	114,123
Total	379,786	77,034	28,729	485,548	28,307	513,856
<u>December 31, 1996</u>						
<u>NONQUALIFIED</u>						
Turkey Point Unit No. 3	56,809	308	3,255	60,371		
Turkey Point Unit No. 4	60,565	492	3,479	64,536		
St Lucie Unit No. 1	56,612	(296)	3,213	59,529		
St Lucie Unit No. 2	36,276	(2,369)	1,958	35,866		
Total	210,262	(1,865)	11,904	220,301		
<u>QUALIFIED</u>						
Turkey Point Unit No. 3	68,657	17,456	2,459	88,572		
Turkey Point Unit No. 4	71,100	21,927	2,558	95,584		
St Lucie Unit No. 1	85,990	24,904	3,055	113,949		
St Lucie Unit No. 2	77,847	23,403	2,843	104,093		
Total	303,593	87,690	10,915	402,198		
<u>TOTAL</u>						
Turkey Point Unit No. 3	125,466	17,763	5,714	148,943		
Turkey Point Unit No. 4	131,665	22,419	6,037	160,120		
St Lucie Unit No. 1	142,602	24,608	6,268	173,478		
St Lucie Unit No. 2	114,123	21,034	4,801	139,958		
Total	513,856	85,824	22,820	622,499		

000024

Florida Power & Light Company
1998 Decommissioning Study
Support Schedule: Nuclear Decommissioning Fund Balances
December 31, 1995 through August 31, 1998
\$000

Support Schedule B
Page 2 of 2

<u>December 31, 1997</u>	<u>Beginning Balance</u>	<u>Contribution</u>	<u>Fund Earnings</u>	<u>Ending Balance</u>
<u>NONQUALIFIED</u>				
Turkey Point Unit No. 3	60,371	1,744	3,108	65,223
Turkey Point Unit No. 4	64,536	2,218	3,324	70,077
St Lucie Unit No. 1	59,529	1,167	3,063	63,759
St Lucie Unit No. 2	35,866	5	1,849	37,719
Total	220,301	5,133	11,343	236,777

<u>QUALIFIED</u>				
Turkey Point Unit No. 3	88,572	15,118	4,013	107,702
Turkey Point Unit No. 4	95,584	19,117	4,330	119,031
St Lucie Unit No. 1	113,949	22,522	5,122	141,594
St Lucie Unit No. 2	104,093	19,539	4,678	128,310
Total	402,198	76,296	18,143	496,637

<u>TOTAL</u>				
Turkey Point Unit No. 3	148,943	16,861	7,121	172,925
Turkey Point Unit No. 4	160,120	21,335	7,653	189,108
St Lucie Unit No. 1	173,478	23,689	8,185	205,352
St Lucie Unit No. 2	139,958	19,543	6,527	166,029
Total	622,499	81,429	29,486	733,414

August 31, 1998

<u>NONQUALIFIED</u>				
Turkey Point Unit No. 3	65,223	(1,965)	2,395	65,652
Turkey Point Unit No. 4	70,077	(2,567)	2,545	70,056
St Lucie Unit No. 1	63,759	(3,855)	2,237	62,141
St Lucie Unit No. 2	37,719	(4,007)	1,234	34,947
Total	236,777	(12,393)	8,411	232,796

<u>QUALIFIED</u>				
Turkey Point Unit No. 3	107,702	15,170	5,646	128,519
Turkey Point Unit No. 4	119,031	19,330	6,168	144,529
St Lucie Unit No. 1	141,594	22,557	7,473	171,624
St Lucie Unit No. 2	128,310	19,554	6,830	154,694
Total	496,637	76,611	26,118	599,366

<u>TOTAL</u>				
Turkey Point Unit No. 3	172,925	13,205	8,041	194,171
Turkey Point Unit No. 4	189,108	16,763	8,714	214,585
St Lucie Unit No. 1	205,352	18,702	9,710	233,765
St Lucie Unit No. 2	166,029	15,547	8,064	189,641
Total	733,414	64,218	34,530	832,162

000025

Florida Power & Light Company
1998 Decommissioning Study
Support Schedule: Projected Fund and Reserve Balance at December 31, 1998
\$000

Support Schedule C
Page 1 of 2

	TURKEY POINT UNIT 3	TURKEY POINT UNIT 4	ST. LUCIE UNIT 1	ST. LUCIE UNIT 2 (Note 1)	TOTALS
NON-QUALIFIED FUND					
Actual Fund Balance @8/31/98	65,652	70,056	62,141	34,947	232,796
Add: Contributions Sept. - Dec. 1998	3,677	4,653	5,000	4,002	17,333
Income Sept. - Dec. 1998 (after tax) Note (2)	1,102	1,182	1,056	603	3,944
Est./Actual Fund Balance @12/31/98	70,431	75,891	68,197	39,552	254,072
QUALIFIED FUND					
Actual Fund Balance @8/31/98	128,519	144,529	171,624	154,694	599,366
Add: Contributions Sept. - Dec. 1998	0	0	0	0	0
Income Sept. - Dec. 1998 (after tax) Note (2)	2,099	2,361	2,803	2,527	9,790
Est./Actual Fund Balance @12/31/98	130,618	146,890	174,427	157,221	609,156
TOTAL FUND					
Actual Fund Balance @8/31/98	194,171	214,585	233,765	189,641	832,162
Add: Contributions Sept. - Dec. 1998	3,677	4,653	5,000	4,002	17,333
Income Sept. - Dec. 1998 (after tax) Note (2)	3,201	3,543	3,859	3,130	13,734
Est./Actual Fund Balance @12/31/98	201,049	222,781	242,624	196,773	863,228
NON-QUALIFIED RESERVE					
Actual Reserve Balance@8/31/98	106,882	114,051	101,165	56,893	378,992
Add: Contributions Sept. - Dec. 1998	5,986	7,576	8,141	6,515	28,217
Income Sept. - Dec. 1998 Note (2)	1,795	1,925	1,719	982	6,421
Est./Actual Reserve Balance@12/31/98	114,662	123,551	111,025	64,392	413,631
QUALIFIED RESERVE					
Actual Reserve Balance@8/31/98	128,519	144,529	171,624	154,694	599,366
Add: Contributions Sept. - Dec. 1998	0	0	0	0	0
Income Sept. - Dec. 1998 Note (2)	2,099	2,361	2,803	2,527	9,790
Est./Actual Reserve Balance@12/31/98	130,618	146,890	174,427	157,221	609,156
TOTAL RESERVE					
Actual Reserve Balance@8/31/98	235,401	258,580	272,789	211,587	978,358
Add: Contributions Sept. - Dec. 1998	5,986	7,576	8,141	6,515	28,217
Income Sept. - Dec. 1998 Note (2)	3,894	4,285	4,522	3,509	16,210
Est./Actual Reserve Balance@12/31/98	245,280	270,441	285,452	221,612	1,022,785

Note (1): Amounts for St Lucie Common are included with Unit No. 2

Note (2): calculated @ .0490/3 * Average fund balance Sept. - Dec. 1998.

000026

Florida Power & Light Company
1998 Decommissioning Study
Support Schedule: Projected Fund and Reserve Balance at December 31, 1998
\$000

Support Schedule C
Page 2 of 2

FUNDING ASSUMPTIONS (September - December 31, 1998)

<u>Accrual/Funding</u> <u>For the Period Sept. - Dec. 1998</u>		<u>Qualified</u> <u>Fund/Reserve</u>	<u>Non-Qualified</u>		
			<u>Fund</u>	<u>Defrd Tax</u>	<u>Reserve</u>
Turkey Point	Unit No. 3	0	3,677	2,309	5,986
	Unit No. 4	0	4,653	2,922	7,576
St. Lucie	Unit No. 1	0	5,000	3,140	8,141
	Unit No. 2 & Commom	0	4,002	2,513	6,515
Total TPN and PSL		0	17,333	10,885	28,217

Amounts are based on current (1998) requested Ruling Amounts and Qualified Election for 1998.

Assumed Fund (after-tax) Earnings Rate
For the Period Sept. - Dec. 1998

4.9% annual / 12 = .40833% per month

000027

Florida Power & Light Company
1998 Decommissioning Study
Support Schedule: Reconciliation of Projected Fund and Reserve Balance at December 31, 1998
\$000

RECONCILIATION FUND/RESERVE

Projected 12/31/98

	TURKEY POINT UNIT 3	TURKEY POINT UNIT 4	ST. LUCIE UNIT 1	ST. LUCIE UNIT 2 (Note 1)	TOTALS
NON-QUALIFIED					
Projected Fund Balance @12/31/98	70,431	75,891	68,197	39,552	254,072
Deferred Tax @ 12/31/98	44,231	47,660	42,828	24,839	159,558
Projected Reserve Balance @ 12/31/98	114,662	123,551	111,025	64,391	413,630
QUALIFIED					
Projected Fund Balance @12/31/98	130,618	146,890	174,427	157,221	609,156
Deferred Tax @ 12/31/98	0	0	0	0	0
Projected Reserve Balance @ 12/31/98	130,618	146,890	174,427	157,221	609,156
TOTAL					
Projected Fund Balance @12/31/98	201,049	222,781	242,624	196,773	863,228
Deferred Tax @ 12/31/98	44,231	47,660	42,828	24,839	159,558
Projected Reserve Balance @ 12/31/98	245,280	270,441	285,452	221,612	1,022,785

DEFERRED TAXES

Projected Balance At 12/31/98

NON-QUALIFIED FUND

Balance @8/31/98 (Fed. & State)	41,230	43,995	39,024	21,947	146,196
Add: Tax on Gross Contributions Sept. - Dec.	2,309	2,922	3,140	2,513	10,885
Tax on Earnings Sept. - December	692	742	663	379	2,477
Balance @12/31/98 (Fed. & State)	44,231	47,660	42,828	24,839	159,558

Note (1): Amounts for St Lucie Common are included with Unit No. 2

000028

Florida Power & Light Company
1998 Decommissioning Study
Support Schedule: Nuclear Decommissioning Theoretical Reserves

Support Schedule E
Page 1 of 5

Total System Amounts

	Turkey Point Unit 3	Turkey Point Unit 4	St. Lucie Unit 1	St. Lucie Unit 2	Total	FAS 115
Theoretical Reserve Balance @ 12/31/98	382,953,699	427,776,035	482,448,497	339,451,873	1,632,630,104	
Est/Act. Reserve @ 12/98	245,279,783	270,440,672	285,451,827	221,611,720	1,022,784,002	91,969,769
Allocation of Unrealized Gains (FAS 115) @ 8/31/98	<u>22,128,710</u>	<u>24,307,610</u>	<u>25,513,809</u>	<u>20,019,640</u>	<u>91,969,769</u>	<u>(91,969,769)</u>
Funded Reserve Deficiency (Excess)	115,545,207	133,027,754	171,482,861	97,820,512	517,876,334	0
End of Life Inventories Unfunded Reserve Deficiency (Excess)	<u>0</u>	<u>11,623,640</u>	<u>0</u>	<u>6,281,742</u>	<u>17,905,382</u>	<u>0</u>
Total Reserve Deficiencies @ 12/31/98	<u>115,545,207</u>	<u>144,651,394</u>	<u>171,482,861</u>	<u>104,102,254</u>	<u>535,781,716</u>	<u>0</u>

- Assumptions: 1 1998 Decommissioning Costs per TLG Study
2 Discount rate = Assumed after tax earnings of 4.9% (CPI + 110 basis points) approved by
FPSC Order No.PSC-95-1531-FOF-EI
3 Escalation Factors 1999 to End = DRI Fall/Winter 1997-1998
4 Burial = Historical Analysis plus CPI Growth
5 Theoretical Reserve Funding began the month following the In-Service Date
Qualifying percentage = 100%

Annual Accrual

Using Theoretical Reserves

Calculation: - DECOM	7,435,608	8,738,616	12,402,326	15,032,670	43,609,220	
- EOL Inventories		460,342		409,679	870,021	
Less: Last Approved (effective 1/95)	<u>17,956,515</u>	<u>22,727,359</u>	<u>24,422,287</u>	<u>19,546,295</u>	<u>84,652,456</u>	
Difference	(10,520,907)	(13,528,401)	(12,019,961)	(4,103,946)	(40,173,215)	

000029

Florida Power & Light Company
1998 Decommissioning Study
Support Schedule: Nuclear Decommissioning Theoretical Reserves

Support Schedule E
Page 2 of 5

TURKEY POINT UNIT 3 ANNUAL SUMMARY
Using In Service Year

Date in Service Dec. 1972

<u>YEAR</u>	<u>BEG BAL</u>	<u>CONTRIBUTION 100% QUALIFIED</u>	<u>EARNINGS @ 4.900%</u>	<u>EXPENDITURE QUALIFIED NOMINAL \$'s 1,159,092,053</u>	<u>END BAL</u>	<u>CUMULATIVE EARNINGS TO LAST FUNDING YEAR</u>
1973-1995	0	171,018,989	139,999,104		311,018,093	
1996	311,018,093	7,435,608	15,405,436		333,859,137	
1997	333,859,137	7,435,608	16,524,647		357,819,392	
1998	357,819,392	7,435,608	17,698,699		382,953,699	
1999	382,953,699	7,435,608	18,930,280		409,319,588	
2000	409,319,588	7,435,608	20,222,209		436,977,405	
2001	436,977,405	7,435,608	21,577,442		465,990,455	
2002	465,990,455	7,435,608	22,999,081		496,425,145	
2003	496,425,145	7,435,608	24,490,381		528,351,134	
2004	528,351,134	7,435,608	26,054,755		561,841,497	
2005	561,841,497	7,435,608	27,695,782	1,653,595	595,319,293	
2006	595,319,293	7,435,608	29,336,194	1,754,464	630,336,631	
2007	630,336,631	7,435,608	31,052,044	4,653,716	664,170,567	
2008	664,170,567	7,435,608	32,709,907	7,406,390	696,909,692	
2009	696,909,692	7,435,608	34,314,124	8,905,937	729,753,488	
2010	729,753,488	7,435,608	35,923,470		773,112,566	
2011	773,112,566	7,435,608	38,048,065		818,596,239	
2012	818,596,239	3,717,804	40,239,440	53,737,669	808,815,814	593,221,061
2013	808,815,814	0	39,631,975	119,466,612	728,981,177	
2014	728,981,177	0	35,720,078	129,664,001	635,037,253	
2015	635,037,253	0	31,116,825	127,341,968	538,812,111	
2016	538,812,111	0	26,401,793	113,053,485	452,160,419	
2017	452,160,419	0	22,155,861	104,620,629	369,695,651	
2018	369,695,651	0	18,115,087	110,222,406	277,588,332	
2019	277,588,332	0	13,601,828	116,339,016	174,851,144	
2020	174,851,144	0	8,567,706	43,346,228	140,072,622	
2021	140,072,622	0	6,863,558	10,025,636	136,910,545	
2022	136,910,545	0	6,708,617	4,735,032	138,884,129	
2023	138,884,129	0	6,805,322	5,023,869	140,665,582	
2024	140,665,582	0	6,892,614	5,344,932	142,213,263	
2025	142,213,263	0	6,968,450	5,655,475	143,526,238	
2026	143,526,238	0	7,032,786	6,000,459	144,558,564	
2027	144,558,564	0	7,083,370	6,366,487	145,275,447	
2028	145,275,447	0	7,118,497	6,773,354	145,620,590	
2029	145,620,590	0	7,135,409	7,166,888	145,589,110	
2030	145,589,110	0	7,133,866	7,604,069	145,118,908	
2031	145,118,908	0	7,110,826	152,229,734	0	
		293,706,524	865,385,529	1,159,092,053		593,221,061

000030

Florida Power & Light Company
1998 Decommissioning Study
Support Schedule: Nuclear Decommissioning Theoretical Reserves

Support Schedule E
Page 3 of 5

TURKEY POINT UNIT NO. 4 ANNUAL SUMMARY
Using In Service Year

Date in Service Sept. 1973

<u>YEAR</u>	<u>BEG BAL</u>	<u>CONTRIBUTION 100% QUALIFIED</u>	<u>EARNINGS @ 4.900%</u>	<u>EXPENDITURE QUALIFIED NOMINAL \$'s 1,357,036,010</u>	<u>END BAL</u>	<u>CUMULATIVE EARNINGS TO LAST FUNDING YEAR</u>
1973-1995	0	194,434,208	151,779,717		346,213,925	
1996	346,213,925	8,738,616	17,159,042		372,111,583	
1997	372,111,583	8,738,616	18,428,027		399,278,226	
1998	399,278,226	8,738,616	19,759,193		427,776,035	
1999	427,776,035	8,738,616	21,155,585		457,670,237	
2000	457,670,237	8,738,616	22,620,401		489,029,254	
2001	489,029,254	8,738,616	24,156,993		521,924,863	
2002	521,924,863	8,738,616	25,768,878		556,432,357	
2003	556,432,357	8,738,616	27,459,745		592,630,719	
2004	592,630,719	8,738,616	29,233,465		630,602,800	
2005	630,602,800	8,738,616	31,094,097	1,653,595	668,781,918	
2006	668,781,918	8,738,616	32,964,874	1,754,464	708,730,943	
2007	708,730,943	8,738,616	34,922,376	4,653,716	747,738,219	
2008	747,738,219	8,738,616	36,833,732	7,406,390	785,904,178	
2009	785,904,178	8,738,616	38,703,864	8,905,937	824,440,722	
2010	824,440,722	8,738,616	40,592,155		873,771,493	
2011	873,771,493	8,738,616	43,009,363		925,519,472	
2012	925,519,472	8,738,616	45,545,014		979,803,102	
2013	979,803,102	2,184,654	48,099,213	76,513,199	953,573,771	709,285,735
2014	953,573,771	0	46,725,115	122,390,757	877,908,129	
2015	877,908,129	0	43,017,498	154,052,899	766,872,728	
2016	766,872,728	0	37,576,764	159,569,932	644,879,560	
2017	644,879,560	0	31,599,098	161,103,741	515,374,917	
2018	515,374,917	0	25,253,371	154,873,418	385,754,870	
2019	385,754,870	0	18,901,989	163,477,627	241,179,232	
2020	241,179,232	0	11,817,782	77,488,275	175,508,740	
2021	175,508,740	0	8,599,928	17,789,539	166,319,129	
2022	166,319,129	0	8,149,637	7,761,551	166,707,215	
2023	166,707,215	0	8,168,654	8,235,006	166,640,863	
2024	166,640,863	0	8,165,402	8,761,282	166,044,983	
2025	166,044,983	0	8,136,204	9,270,319	164,910,868	
2026	164,910,868	0	8,080,633	9,835,809	163,155,692	
2027	163,155,692	0	7,994,629	10,435,793	160,714,528	
2028	160,714,528	0	7,875,012	11,102,715	157,486,824	
2029	157,486,824	0	7,716,854	11,747,791	153,455,887	
2030	153,455,887	0	7,519,338	12,464,407	148,510,819	
2031	148,510,819	0	7,277,030	155,787,849	0	
		345,175,336	1,011,860,674	1,357,036,010		709,285,735

000031

Florida Power & Light Company
1998 Decommissioning Study
Support Schedule: Nuclear Decommissioning Theoretical Reserves

Support Schedule E
Page 4 of 5

ST. LUCIE UNIT NO. 1 ANNUAL SUMMARY
Using In Service Year

Date in Service Dec. 1976

<u>YEAR</u>	<u>BEG BAL</u>	<u>CONTRIBUTION 100% QUALIFIED</u>	<u>EARNINGS @ 4.900%</u>	<u>EXPENDITURE QUALIFIED NOMINAL \$'s 2,418,555,683</u>	<u>END BAL</u>	<u>CUMULATIVE EARNINGS TO LAST FUNDING YEAR</u>
1976-1995	0	235,644,185	147,714,596		383,358,781	
1996	383,358,781	12,402,326	19,060,710		414,821,817	
1997	414,821,817	12,402,326	20,602,399		447,826,541	
1998	447,826,541	12,402,326	22,219,630		482,448,497	
1999	482,448,497	12,402,326	23,916,106		518,766,929	
2000	518,766,929	12,402,326	25,695,709	665,276	556,199,688	
2001	556,199,688	12,402,326	27,529,915	707,854	595,424,074	
2002	595,424,074	12,402,326	29,451,909	1,882,891	635,395,417	
2003	635,395,417	12,402,326	31,410,505	3,005,095	676,203,153	
2004	676,203,153	12,402,326	33,410,084	3,623,744	718,391,819	
2005	718,391,819	12,402,326	35,477,329		766,271,473	
2006	766,271,473	12,402,326	37,823,432		816,497,231	
2007	816,497,231	12,402,326	40,284,494		869,184,050	
2008	869,184,050	12,402,326	42,866,148		924,452,524	
2009	924,452,524	12,402,326	45,574,304		982,429,153	
2010	982,429,153	12,402,326	48,415,158		1,043,246,637	
2011	1,043,246,637	12,402,326	51,395,215		1,107,044,178	
2012	1,107,044,178	12,402,326	54,521,295		1,173,967,798	
2013	1,173,967,798	12,402,326	57,800,552		1,244,170,676	
2014	1,244,170,676	12,402,326	61,240,493		1,317,813,494	
2015	1,317,813,494	12,402,326	64,848,991		1,395,064,811	
2016	1,395,064,811	2,067,054	68,446,538	136,758,810	1,328,819,593	989,705,514
2017	1,328,819,593	0	65,112,160	54,786,039	1,339,145,714	
2018	1,339,145,714	0	65,618,140	35,889,952	1,368,873,902	
2019	1,368,873,902	0	67,074,821	36,071,268	1,399,877,455	
2020	1,399,877,455	0	68,593,995	54,223,777	1,414,247,673	
2021	1,414,247,673	0	69,298,136	55,780,177	1,427,765,632	
2022	1,427,765,632	0	69,960,516	161,850,860	1,335,875,288	
2023	1,335,875,288	0	65,457,889	190,414,427	1,210,918,750	
2024	1,210,918,750	0	59,335,019	201,802,174	1,068,451,595	
2025	1,068,451,595	0	52,354,128	167,385,224	953,420,500	
2026	953,420,500	0	46,717,604	115,405,592	884,732,513	
2027	884,732,513	0	43,351,893	118,628,765	809,455,641	
2028	809,455,641	0	39,663,326	126,566,816	722,552,152	
2029	722,552,152	0	35,405,055	134,299,150	623,658,057	
2030	623,658,057	0	30,559,245	197,985,139	456,232,163	
2031	456,232,163	0	22,355,376	129,120,152	349,467,387	
2032	349,467,387	0	17,123,902	46,666,987	319,924,302	
2033	319,924,302	0	15,676,291	13,999,116	321,601,477	
2034	321,601,477	0	15,758,472	14,895,059	322,464,891	
2035	322,464,891	0	15,800,780	15,848,343	322,417,327	
2036	322,417,327	0	15,798,449	16,908,828	321,306,948	
2037	321,306,948	0	15,744,040	17,941,846	319,109,143	
2038	319,109,143	0	15,636,348	19,090,124	315,655,368	
2039	315,655,368	0	15,467,113	20,311,892	310,810,589	
2040	310,810,589	0	15,229,719	326,040,308	0	
		485,757,750	1,932,797,933	2,418,555,683		989,705,514

000032

Florida Power & Light Company
1998 Decommissioning Study
Support Schedule: Nuclear Decommissioning Theoretical Reserves

Support Schedule E
Page 5 of 5

ST. LUCIE UNIT NO. 2 ANNUAL SUMMARY
Using In Service Year

Date in Service Aug., 1983

<u>YEAR</u>	<u>BEG BAL</u>	<u>CONTRIBUTION</u> <u>100%</u> <u>QUALIFIED</u>	<u>EARNINGS @</u> <u>4.900%</u>	<u>QUALIFIED</u> <u>NOMINAL \$'s</u> <u>2,368,707,762</u>	<u>END BAL</u>	<u>CUMULATIVE</u> <u>EARNINGS TO</u> <u>LAST</u> <u>FUNDING YEAR</u>
1976-1995	0	185,402,927	66,740,086		252,143,012	
1996	252,143,012	15,032,670	12,689,700		279,865,383	
1997	279,865,383	15,032,670	14,048,097		308,946,149	
1998	308,946,149	15,032,670	15,473,054		339,451,873	
1999	339,451,873	15,032,670	16,967,835		371,452,377	
2000	371,452,377	15,032,670	18,535,859	1,048,487	403,972,419	
2001	403,972,419	15,032,670	20,129,341	1,113,493	438,020,936	
2002	438,020,936	15,032,670	21,797,719	2,956,325	471,895,000	
2003	471,895,000	15,032,670	23,457,548	4,709,426	505,675,791	
2004	505,675,791	15,032,670	25,112,807	5,668,265	540,153,003	
2005	540,153,003	15,032,670	26,802,190		581,987,862	
2006	581,987,862	15,032,670	28,852,098		625,872,630	
2007	625,872,630	15,032,670	31,002,452		671,907,751	
2008	671,907,751	15,032,670	33,258,173		720,198,594	
2009	720,198,594	15,032,670	35,624,424		770,855,687	
2010	770,855,687	15,032,670	38,106,621		823,994,979	
2011	823,994,979	15,032,670	40,710,447		879,738,095	
2012	879,738,095	15,032,670	43,441,859		938,212,624	
2013	938,212,624	15,032,670	46,307,111		999,552,405	
2014	999,552,405	15,032,670	49,312,761		1,063,897,836	
2015	1,063,897,836	15,032,670	52,465,687		1,131,396,192	
2016	1,131,396,192	15,032,670	55,773,106		1,202,201,968	
2017	1,202,201,968	15,032,670	59,242,589		1,276,477,227	
2018	1,276,477,227	15,032,670	62,882,077		1,354,391,974	
2019	1,354,391,974	15,032,670	66,699,900		1,436,124,543	
2020	1,436,124,543	15,032,670	70,704,795		1,521,862,008	
2021	1,521,862,008	15,032,670	74,905,931		1,611,800,609	
2022	1,611,800,609	15,032,670	79,312,923		1,706,146,202	
2023	1,706,146,202	3,758,167	83,754,028	116,666,837	1,676,991,560	1,214,111,217
2024	1,676,991,560	0	82,172,586	186,282,112	1,572,882,034	
2025	1,572,882,034	0	77,071,220	226,799,994	1,423,153,260	
2026	1,423,153,260	0	69,734,510	233,625,713	1,259,262,057	
2027	1,259,262,057	0	61,703,841	247,700,582	1,073,265,316	
2028	1,073,265,316	0	52,590,000	233,928,911	891,926,405	
2029	891,926,405	0	43,704,394	249,208,962	686,421,837	
2030	686,421,837	0	33,634,670	263,437,453	456,619,054	
2031	456,619,054	0	22,374,334	174,053,472	304,939,916	
2032	304,939,916	0	14,942,056	59,995,267	259,886,705	
2033	259,886,705	0	12,734,449	11,421,280	261,199,873	
2034	261,199,873	0	12,798,794	12,129,399	261,869,268	
2035	261,869,268	0	12,831,594	12,881,422	261,819,440	
2036	261,819,440	0	12,829,153	13,717,548	260,931,045	
2037	260,931,045	0	12,785,621	14,528,234	259,188,431	
2038	259,188,431	0	12,700,233	15,428,985	256,459,679	
2039	256,459,679	0	12,566,524	16,385,582	252,640,622	
2040	252,640,622	0	12,379,390	265,020,011	1	
		595,043,177	1,773,664,585	2,368,707,762		1,214,111,217

000033

Florida Power and Light Company
1998 Decommissioning Study
Support Schedule: End-of-Life Materials and Supplies Inventory
Expense Accrual and Reserve Deficiency

	St. Lucie Unit 2
Adjusted Ending Inventory Value @ End of License	17,744,993
Estimated Salvage	(223,587)
Inventory Subject to Write-off	17,521,406
 FPL's Ownership Share Net of Participants (1)	 16,216,455
 Total Number of Months From:	
In-Service Date to End of Licence	475
In-Service Date to 12/31/98	184
12/31/98 to End of License	291
 Required Accrual From 1/1/99 to End of License	
Monthly	55,727
Annual	668,720
 Theoretical Accrual From In-Service Date to End of License	
Monthly	34,140
Annual	409,679
 Reserve Deficiency at 12/31/98	
Theoretical Reserve at 12/31/98	6,281,742
Actual Reserve at 12/31/98	0
Reserve Deficiency	<u>6,281,742</u>

- (1) The Participants' obligation is assumed to be treated the same as "Common Facility Cost" which is calculated at one-half their ownership percentage. $(0.5 * 14.89551\% = 7.447755\%)$ Therefore, FPL's ownership share is 92.552245%.

**Florida Power & Light Company
1998 Decommissioning Study
St Lucie Nuclear Units
Support Schedule : Inflation and Funding Analysis**

**Support Schedule G
Page 1 of 6**

INFLATION FORECAST

Fall/Winter 1997 - 1998 DRI

YEAR	GDP	HRLY COMP	PPI INT M&S	GDP Transport	Burial	CPI	CPI MULTIPLIER
1998	1.8%	3.8%	-0.5%	2.9%		1.7%	1.000
1999	1.9%	3.2%	0.8%	3.0%	138.2%	2.6%	1.026
2000	2.2%	3.3%	1.3%	3.1%	6.4%	2.9%	1.056
2001	2.1%	3.2%	1.3%	3.1%	6.3%	2.8%	1.085
2002	2.2%	3.1%	1.4%	3.0%	6.3%	2.8%	1.116
2003	2.4%	3.4%	1.8%	3.2%	6.4%	2.9%	1.148
2004	2.5%	3.6%	1.7%	3.3%	6.5%	3.0%	1.183
2005	2.6%	3.6%	1.9%	3.4%	6.6%	3.1%	1.219
2006	2.8%	3.7%	1.8%	3.5%	6.8%	3.3%	1.259
2007	2.8%	3.8%	2.0%	3.6%	6.9%	3.4%	1.302
2008	2.9%	3.9%	2.1%	3.6%	6.9%	3.4%	1.346
2009	3.0%	4.0%	2.1%	3.7%	7.0%	3.5%	1.394
2010	3.1%	4.1%	2.2%	3.8%	7.1%	3.6%	1.444
2011	3.2%	4.2%	2.3%	3.9%	7.2%	3.7%	1.497
2012	3.3%	4.2%	2.3%	3.9%	7.2%	3.7%	1.553
2013	3.3%	4.3%	2.3%	3.9%	7.3%	3.8%	1.612
2014	3.4%	4.3%	2.4%	4.0%	7.3%	3.8%	1.673
2015	3.4%	4.3%	2.5%	4.0%	7.3%	3.8%	1.736
2016	3.5%	4.3%	2.5%	4.1%	7.4%	3.9%	1.804
2017	3.5%	4.3%	2.6%	4.1%	7.4%	3.9%	1.874
2018	3.6%	4.4%	2.7%	4.2%	7.5%	4.0%	1.949
2019	3.7%	4.4%	2.7%	4.2%	7.5%	4.0%	2.027
2020	3.8%	4.5%	2.8%	4.3%	7.6%	4.1%	2.111
2021	3.8%	4.5%	2.8%	4.3%	7.6%	4.1%	2.197
2022	3.9%	4.6%	2.9%	4.4%	7.7%	4.2%	2.289
2023	3.9%	4.6%	2.9%	4.4%	7.7%	4.2%	2.386
2024	3.9%	4.6%	2.9%	4.4%	7.7%	4.2%	2.486
2025	3.9%	4.6%	2.9%	4.4%	7.7%	4.2%	2.590
2026	3.9%	4.6%	2.9%	4.4%	7.7%	4.2%	2.699
2027	3.9%	4.6%	2.9%	4.4%	7.7%	4.2%	2.812
2028	3.9%	4.6%	2.9%	4.4%	7.7%	4.2%	2.930
2029	3.9%	4.6%	2.9%	4.4%	7.7%	4.2%	3.053
2030	3.9%	4.6%	2.9%	4.4%	7.7%	4.2%	3.182
2031	3.9%	4.6%	2.9%	4.4%	7.7%	4.2%	3.315
2032	3.9%	4.6%	2.9%	4.4%	7.7%	4.2%	3.455
2033	3.9%	4.6%	2.9%	4.4%	7.7%	4.2%	3.600
2034	3.9%	4.6%	2.9%	4.4%	7.7%	4.2%	3.751
2035	3.9%	4.6%	2.9%	4.4%	7.7%	4.2%	3.908
2036	3.9%	4.6%	2.9%	4.4%	7.7%	4.2%	4.073
2037	3.9%	4.6%	2.9%	4.4%	7.7%	4.2%	4.244
2038	3.9%	4.6%	2.9%	4.4%	7.7%	4.2%	4.422
2039	3.9%	4.6%	2.9%	4.4%	7.7%	4.2%	4.608
2040	3.9%	4.6%	2.9%	4.4%	7.7%	4.2%	4.801

3.7% = AVERAGE COMPOUND CPI INFLATION MULTILPLIER 1998-2031

3.8% = AVERAGE COMPOUND CPI INFLATION MULTILPLIER 1998-2040

000035

Florida Power & Light Company
1998 Decommissioning Study
St Lucie Nuclear Units
Support Schedule : Inflation and Funding Analysis

Support Schedule G
Page 2 of 6

ST. LUCIE UNIT 1

AVERAGE INFLATION RATE =		4.200%	2.500%	6.400%	9.400%	3.400%	
		LABOR	MATERIAL	SHIPPING	BURIAL	OTHER	TOTAL
		HRLY COMP	PPI INT M&S	GDP Transp		GDP	
1998	230,838,470	70,724,459	4,223,851	97,920,869	25,209,572	428,917,221	
1999	238,225,301	71,290,255	4,350,567	233,247,510	25,688,554	572,802,186	
2000	246,086,736	72,217,028	4,485,434	248,175,351	26,253,702	597,218,251	
2001	253,961,512	73,155,849	4,624,483	263,810,398	26,805,030	622,357,271	
2002	261,834,318	74,180,031	4,763,217	280,430,453	27,394,740	648,602,760	
2003	270,736,685	75,515,272	4,915,640	298,378,002	28,052,214	677,597,813	
2004	280,483,206	76,799,031	5,077,856	317,772,572	28,753,520	708,886,185	
2005	290,580,601	78,258,213	5,250,503	338,745,562	29,501,111	742,335,990	
2006	301,332,084	79,666,861	5,434,271	361,780,260	30,327,142	778,540,617	
2007	312,782,703	81,260,198	5,629,905	386,743,098	31,176,302	817,592,205	
2008	324,981,228	82,966,662	5,832,581	413,428,371	32,080,415	859,289,258	
2009	337,980,477	84,708,962	6,048,387	442,368,357	33,042,827	904,149,011	
2010	351,837,677	86,572,559	6,278,225	473,776,511	34,067,155	952,532,127	
2011	366,614,859	88,563,728	6,523,076	507,888,420	35,157,304	1,004,747,387	
2012	382,012,683	90,600,694	6,777,476	544,456,386	36,317,495	1,060,164,734	
2013	398,439,229	92,684,510	7,041,798	584,201,702	37,515,972	1,119,883,211	
2014	415,572,116	94,908,938	7,323,470	626,848,426	38,791,515	1,183,444,465	
2015	433,441,717	97,281,662	7,616,408	672,608,361	40,110,427	1,251,058,575	
2016	452,079,710	99,713,703	7,928,681	722,381,380	41,514,292	1,323,617,766	
2017	471,519,138	102,306,259	8,253,757	775,837,602	42,967,292	1,400,884,048	
2018	492,265,980	105,068,528	8,600,415	834,025,422	44,514,115	1,484,474,460	
2019	513,925,683	107,905,379	8,961,632	896,577,329	46,161,137	1,573,531,160	
2020	537,052,339	110,926,729	9,346,982	964,717,206	47,915,260	1,669,958,516	
2021	561,219,694	114,032,678	9,748,903	1,038,035,714	49,736,040	1,772,773,028	
2022	587,035,800	117,339,625	10,177,854	1,117,964,464	51,675,746	1,884,193,489	
2023	614,039,447	120,742,474	10,625,680	1,204,047,727	53,691,100	2,003,146,428	
2024	642,285,261	124,244,006	11,093,210	1,296,759,402	55,785,052	2,130,166,932	
2025	671,830,383	127,847,082	11,581,311	1,396,609,876	57,960,670	2,265,829,323	
2026	702,734,581	131,554,648	12,090,889	1,504,148,837	60,221,136	2,410,750,090	
2027	735,060,372	135,369,733	12,622,888	1,619,968,297	62,569,760	2,565,591,049	
2028	768,873,149	139,295,455	13,178,295	1,744,705,856	65,009,981	2,731,062,735	
2029	804,241,314	143,335,023	13,758,140	1,879,048,207	67,545,370	2,907,928,053	
2030	841,236,414	147,491,739	14,363,498	2,023,734,919	70,179,639	3,097,006,209	
2031	879,933,289	151,768,999	14,995,492	2,179,562,508	72,916,645	3,299,176,933	
2032	920,410,220	156,170,300	15,655,294	2,347,388,821	75,760,394	3,515,385,029	
2033	962,749,091	160,699,239	16,344,127	2,528,137,760	78,715,050	3,746,645,265	
2034	1,007,035,549	165,359,517	17,063,268	2,722,804,367	81,784,937	3,994,047,638	
2035	1,053,359,184	170,154,943	17,814,052	2,932,460,304	84,974,549	4,258,763,031	
2036	1,101,813,706	175,089,436	18,597,870	3,158,259,747	88,288,557	4,542,049,316	
2037	1,152,497,137	180,167,030	19,416,177	3,401,445,748	91,731,810	4,845,257,901	
2038	1,205,512,005	185,391,874	20,270,488	3,663,357,070	95,309,351	5,169,840,788	
2039	1,260,965,557	190,768,238	21,162,390	3,945,435,565	99,026,416	5,517,358,165	
2040	1,318,969,973	196,300,517	22,093,535	4,249,234,103	102,888,446	5,889,486,574	

000036

Florida Power & Light Company
1998 Decommissioning Study
St Lucie Nuclear Units
Support Schedule : Inflation and Funding Analysis

Support Schedule G
Page 3 of 6

ST. LUCIE UNIT 2

AVERAGE INFLATION RATE =		6.200%				
		4.200%	2.500%	4.000%	9.400%	3.400%
	LABOR	MATERIAL	SHIPPING	BURIAL	OTHER	TOTAL
	HRLY COMP	PPI INT M&S	GDP Transp		GDP	
1998	258,689,160	82,136,889	3,964,998	88,700,599	19,659,552	453,151,198
1999	266,967,213	82,793,984	4,083,948	211,284,827	20,033,083	585,163,055
2000	275,777,131	83,870,306	4,210,550	224,807,056	20,473,811	609,138,854
2001	284,601,999	84,960,620	4,341,077	238,969,900	20,903,761	633,777,358
2002	293,424,661	86,150,069	4,471,310	254,025,004	21,363,644	659,434,688
2003	303,401,100	87,700,770	4,614,392	270,282,604	21,876,372	687,875,237
2004	314,323,539	89,191,683	4,766,667	287,850,973	22,423,281	718,556,143
2005	325,639,187	90,886,325	4,928,733	306,849,138	23,006,286	751,309,669
2006	337,687,837	92,522,279	5,101,239	327,714,879	23,650,462	786,676,696
2007	350,519,975	94,372,724	5,284,883	350,327,206	24,312,675	824,817,463
2008	364,190,254	96,354,551	5,475,139	374,499,783	25,017,743	865,537,470
2009	378,757,864	98,377,997	5,677,719	400,714,768	25,768,275	909,296,623
2010	394,286,936	100,542,313	5,893,473	429,165,516	26,567,091	956,455,330
2011	410,846,987	102,854,786	6,123,318	460,065,433	27,417,238	1,007,307,764
2012	428,102,561	105,220,446	6,362,128	493,190,145	28,322,007	1,061,197,287
2013	446,510,971	107,640,517	6,610,251	529,193,025	29,256,634	1,119,211,397
2014	465,710,943	110,223,889	6,874,661	567,824,116	30,251,359	1,180,884,967
2015	485,736,513	112,979,486	7,149,647	609,275,277	31,279,905	1,246,420,828
2016	506,623,183	115,803,973	7,442,783	654,361,647	32,374,702	1,316,606,288
2017	528,407,980	118,814,877	7,747,937	702,784,409	33,507,817	1,391,263,019
2018	551,657,931	122,022,878	8,073,350	755,493,240	34,714,098	1,471,961,497
2019	575,930,880	125,317,496	8,412,431	812,155,233	35,998,520	1,557,814,559
2020	601,847,770	128,826,386	8,774,165	873,879,030	37,366,463	1,650,693,815
2021	628,930,920	132,433,525	9,151,454	940,293,836	38,786,389	1,749,596,124
2022	657,861,742	136,274,097	9,554,118	1,012,696,462	40,299,058	1,856,685,477
2023	688,123,382	140,226,046	9,974,500	1,090,674,089	41,870,721	1,970,868,738
2024	719,777,058	144,292,601	10,413,377	1,174,655,994	43,503,679	2,092,642,710
2025	752,886,802	148,477,086	10,871,566	1,265,104,506	45,200,323	2,222,540,284
2026	787,519,595	152,782,922	11,349,915	1,362,517,553	46,963,136	2,361,133,121
2027	823,745,497	157,213,627	11,849,311	1,467,431,404	48,794,698	2,509,034,537
2028	861,637,789	161,772,822	12,370,681	1,580,423,623	50,697,691	2,666,902,606
2029	901,273,128	166,464,234	12,914,991	1,702,116,241	52,674,901	2,835,443,495
2030	942,731,692	171,291,697	13,483,251	1,833,179,192	54,729,222	3,015,415,053
2031	986,097,349	176,259,156	14,076,514	1,974,333,990	56,863,662	3,207,630,670
2032	1,031,457,827	181,370,671	14,695,880	2,126,357,707	59,081,345	3,412,963,431
2033	1,078,904,888	186,630,421	15,342,499	2,290,087,251	61,385,517	3,632,350,575
2034	1,128,534,512	192,042,703	16,017,569	2,466,423,969	63,779,552	3,866,798,305
2035	1,180,447,100	197,611,941	16,722,342	2,656,338,614	66,266,955	4,117,386,952
2036	1,234,747,667	203,342,688	17,458,125	2,860,876,688	68,851,366	4,385,276,533
2037	1,291,546,059	209,239,626	18,226,282	3,081,164,193	71,536,569	4,671,712,729
2038	1,350,957,178	215,307,575	19,028,239	3,318,413,836	74,326,495	4,978,033,322
2039	1,413,101,208	221,551,494	19,865,481	3,573,931,701	77,225,229	5,305,675,113
2040	1,478,103,864	227,976,488	20,739,562	3,849,124,442	80,237,013	5,656,181,368

000037

**Florida Power & Light Company
1998 Decommissioning Study
St Lucie Nuclear Units
Support Schedule : Inflation and Funding Analysis**

**Support Schedule G
Page 4 of 6**

GENERAL ASSUMPTIONS

JURISDICTIONAL FACTOR =	99.258%
FPL'S SHARE OF ST. LUCIE 2 COST (NET OF PARTICIPANTS)	85.18243%
CORPORATE TAX RATE	38.575%

	ANNUAL	MONTHLY
EARNINGS RATE QUALIFIED FUND	4.900%	0.399440%
EARNINGS RATE NON-QUALIFIED FUND	4.900%	0.399440%

	TP3	TP4	SL1	SL2
QUALIFYING %	66.670%	68.570%	77.140%	97.560%
FUND BALANCES (\$000's)				
A. QUALIFIED FUND BALANCE 8/31/98	128,519	144,529	171,624	154,694
B. CONTRIBUTIONS THRU 12/98	-	-	-	-
C. EARNINGS THRU 12/98 (A)*(MONTHLY RATE)	2,099	2,361	2,803	2,527
D.	-	-	-	-
E. QUALIFIED FUND BALANCE 12/31/98	130,618	146,890	174,427	157,221
F. JURISDICTIONAL FACTOR	99.258%	99.258%	99.258%	99.258%
G. JURIS. QUAL. FUND BAL. 12/31/98	129,649	145,800	173,133	156,054
A. NON-QUALIFIED FUND BALANCE 8/31/98	65,652	70,056	62,141	34,947
B. CONTRIBUTIONS THRU 12/98	3,677	4,653	5,000	4,002
C. EARNINGS THRU 12/98 (A)*(MONTHLY RATE)	1,102	1,182	1,056	603
D.	-	-	-	-
E. NON-QUALIFIED FUND BALANCE 12/31/98	70,431	75,891	68,197	39,552
F. JURISDICTIONAL FACTOR	99.258%	99.258%	99.258%	99.258%
G. JURIS. NON-QUAL. FUND BAL. 12/31/98	69,908	75,328	67,691	39,259

000038

Florida Power & Light Company
1998 Decommissioning Study
St Lucie Nuclear Units
Support Schedule : Inflation and Funding Analysis

Support Schedule G
Page 5 of 6

ST. LUCIE UNIT 1

INFLATION RATE 6.400%

	NOMINAL ANNUAL	NOMINAL MONTHLY
EARNINGS RATE QUALIFIED FUND	4.900%	0.399440%
EARNINGS RATE NON-QUALIFIED FUND	4.900%	0.399440%

CORPORATE TAX RATE 38.575%

JURISDICTIONAL FACTOR 99.258%

QUALIFYING % 77.140%

LICENSE ENDS 1-Mar-16
MONTHS TO FUND 206

YEAR	SPENDING CURVE	ESTIMATED COST IN (\$1998)	ESTIMATED COST IN NOMINAL \$	JURISDICTIONAL AMOUNT	QUALIFIED AMOUNT	NON-QUAL AMOUNT	TAX SAVINGS	PV @	
								4.9%	4.9%
								QUALIFIED AMOUNT	NON-QUAL AMOUNT
2000	0.1370%	587,650	665,276	660,340	509,386	92,723	58,230	462,910	84,263
2001	0.1370%	587,650	707,854	702,602	541,987	98,658	61,957	469,529	85,468
2002	0.3425%	1,469,125	1,882,891	1,868,920	1,441,685	262,429	164,806	1,190,607	216,726
2003	0.5138%	2,203,688	3,005,095	2,982,797	2,300,930	418,837	263,030	1,811,448	329,737
2004	0.5823%	2,497,513	3,623,744	3,596,856	2,774,615	505,062	317,180	2,082,331	379,046
2005	0.0000%	-	-	-	-	-	-	-	-
2006	0.0000%	-	-	-	-	-	-	-	-
2007	0.0000%	-	-	-	-	-	-	-	-
2008	0.0000%	-	-	-	-	-	-	-	-
2009	0.0000%	-	-	-	-	-	-	-	-
2010	0.0000%	-	-	-	-	-	-	-	-
2011	0.0000%	-	-	-	-	-	-	-	-
2012	0.0000%	-	-	-	-	-	-	-	-
2013	0.0000%	-	-	-	-	-	-	-	-
2014	0.0000%	-	-	-	-	-	-	-	-
2015	0.0000%	-	-	-	-	-	-	-	-
2016	10.4384%	44,771,950	136,758,810	135,744,060	104,712,968	19,060,848	11,970,244	44,263,085	8,057,187
2017	3.9301%	16,856,949	54,786,039	54,379,527	41,948,367	7,635,840	4,795,320	16,903,661	3,076,965
2018	2.4197%	10,378,637	35,889,952	35,623,649	27,480,083	5,002,186	3,141,381	10,556,216	1,921,543
2019	2.2857%	9,803,637	36,071,268	35,803,619	27,618,912	5,027,456	3,157,251	10,113,962	1,841,039
2020	3.2292%	13,850,771	54,223,777	53,821,436	41,517,856	7,557,474	4,746,106	14,493,530	2,638,250
2021	3.1221%	13,391,291	55,780,177	55,366,288	42,709,555	7,774,399	4,882,335	14,213,100	2,587,203
2022	8.5142%	36,518,753	161,850,860	160,649,926	123,925,353	22,558,069	14,166,504	39,314,110	7,156,327
2023	9.4142%	40,379,334	190,414,427	189,001,552	145,795,797	26,539,135	16,666,620	44,091,797	8,026,007
2024	9.3771%	40,220,134	201,802,174	200,304,802	154,515,124	28,126,310	17,663,368	44,545,958	8,108,678
2025	7.3100%	31,354,015	167,385,224	166,143,225	128,162,884	23,329,425	14,650,917	35,222,817	6,411,592
2026	4.7368%	20,317,079	115,405,592	114,549,282	88,363,316	16,084,730	10,101,236	23,150,391	4,214,054
2027	4.5762%	19,628,305	118,628,765	117,748,539	90,831,223	16,533,961	10,383,355	22,685,377	4,129,408
2028	4.5888%	19,682,081	126,566,816	125,627,690	96,909,200	17,640,332	11,078,157	23,072,803	4,199,931
2029	4.5762%	19,628,305	134,299,150	133,302,650	102,829,665	18,718,032	11,754,954	23,338,787	4,248,348
2030	6.3406%	27,195,716	197,985,139	196,516,089	151,592,511	27,594,308	17,329,270	32,799,115	5,970,406
2031	3.8864%	16,669,413	129,120,152	128,162,081	98,864,229	17,996,205	11,301,646	20,391,448	3,711,845
2032	1.3201%	5,662,320	46,666,987	46,320,718	35,731,802	6,504,242	4,084,674	7,025,679	1,278,881
2033	0.3722%	1,596,407	13,999,116	13,895,242	10,718,790	1,951,136	1,225,317	2,009,110	365,717
2034	0.3722%	1,596,407	14,895,059	14,784,538	11,404,792	2,076,009	1,303,737	2,037,839	370,947
2035	0.3722%	1,596,407	15,848,343	15,730,748	12,134,699	2,208,873	1,387,176	2,066,978	376,251
2036	0.3732%	1,600,780	16,908,828	16,783,365	12,946,688	2,356,679	1,479,998	2,102,278	382,677
2037	0.3722%	1,596,407	17,941,846	17,808,717	13,737,644	2,500,656	1,570,416	2,126,514	387,088
2038	0.3722%	1,596,407	19,090,124	18,948,475	14,616,854	2,660,698	1,670,923	2,156,922	392,623
2039	0.3722%	1,596,407	20,311,892	20,161,177	15,552,332	2,830,983	1,777,862	2,187,764	398,238
2040	5.6150%	24,083,684	326,040,308	323,621,089	249,641,308	45,442,080	28,537,700	33,476,955	6,093,793
100.0000%		428,917,222	2,418,555,683	2,400,610,000	1,851,830,554	337,087,775	211,691,671	480,363,023	87,440,237

	QUALIFIED	NON-QUAL	TOTAL
NPV @12/31/98	480,363,023	87,440,237	567,803,260
LESS BALANCE @ 12/31/98	173,132,752	67,690,978	240,823,730
PV OF FUNDING REQUIREMENTS	307,230,271	19,749,259	326,979,530
MONTHLY FUNDING REQUIREMENT	2,191,039	140,844	2,331,883
ANNUAL FUNDING REQUIREMENT	26,292,472	1,690,123	27,982,594
MONTHLY ACCRUAL	2,191,039	229,294	2,420,333
ANNUAL ACCRUAL	26,292,471	2,751,521	29,043,992

000039

Florida Power & Light Company
1998 Decommissioning Study
St Lucie Nuclear Units
Support Schedule : Inflation and Funding Analysis

Support Schedule G
Page 6 of 6

ST. LUCIE UNIT 2

INFLATION RATE 6.200%

	NOMINAL	NOMINAL
	ANNUAL	MONTHLY
EARNINGS RATE QUALIFIED FUND	4.900%	0.399440%
EARNINGS RATE NON-QUALIFIED FUND	4.900%	0.399440%

CORPORATE TAX RATE 38.575%

FPL'S SHARE OF COST (NET OF PARTICIPANTS)	85.18243%
JURISDICTIONAL FACTOR	99.258%

QUALIFYING % 97.560%

LICENSE ENDS	6-Apr-23
MONTHS TO FUND	291

YEAR	SPENDING CURVE	ESTIMATED COST IN (\$1998)	ESTIMATED COST IN NOMINAL \$	JURISDICTIONAL AMOUNT	QUALIFIED AMOUNT	NON-QUAL AMOUNT	TAX SAVINGS	PV @ 4.9% QUALIFIED AMOUNT	PV @ 4.9% NON-QUAL AMOUNT
2000	0.2408%	1,091,350	1,230,873	1,040,707	1,015,314	15,598	9,795	922,676	14,175
2001	0.2408%	1,091,350	1,307,187	1,105,231	1,078,264	16,565	10,403	934,111	14,350
2002	0.6021%	2,728,375	3,470,581	2,934,389	2,862,790	43,980	27,619	2,364,218	36,320
2003	0.9031%	4,092,563	5,528,635	4,674,482	4,560,425	70,060	43,998	3,590,276	55,156
2004	1.0236%	4,638,238	6,654,266	5,626,207	5,488,927	84,324	52,956	4,119,405	63,285
2005	0.0000%	-	-	-	-	-	-	-	-
2006	0.0000%	-	-	-	-	-	-	-	-
2007	0.0000%	-	-	-	-	-	-	-	-
2008	0.0000%	-	-	-	-	-	-	-	-
2009	0.0000%	-	-	-	-	-	-	-	-
2010	0.0000%	-	-	-	-	-	-	-	-
2011	0.0000%	-	-	-	-	-	-	-	-
2012	0.0000%	-	-	-	-	-	-	-	-
2013	0.0000%	-	-	-	-	-	-	-	-
2014	0.0000%	-	-	-	-	-	-	-	-
2015	0.0000%	-	-	-	-	-	-	-	-
2016	0.0000%	-	-	-	-	-	-	-	-
2017	0.0000%	-	-	-	-	-	-	-	-
2018	0.0000%	-	-	-	-	-	-	-	-
2019	0.0000%	-	-	-	-	-	-	-	-
2020	0.0000%	-	-	-	-	-	-	-	-
2021	0.0000%	-	-	-	-	-	-	-	-
2022	0.0000%	-	-	-	-	-	-	-	-
2023	6.7180%	30,442,792	136,961,152	115,801,169	112,975,621	1,735,593	1,089,955	34,166,267	524,881
2024	10.1004%	45,770,293	218,686,074	184,899,899	180,388,341	2,771,224	1,740,333	52,005,080	798,930
2025	11.5794%	52,472,416	266,252,082	225,117,138	219,624,280	3,373,988	2,118,870	60,359,018	927,268
2026	11.2316%	50,896,058	274,265,143	231,892,211	226,234,041	3,475,531	2,182,639	59,271,277	910,558
2027	11.2130%	50,811,968	290,788,349	245,862,643	239,863,595	3,684,916	2,314,133	59,906,670	920,319
2028	10.0025%	45,185,425	274,621,082	232,193,158	226,527,645	3,480,041	2,185,472	53,933,247	828,552
2029	9.9563%	45,326,649	292,559,114	247,359,832	241,324,252	3,707,355	2,328,225	54,772,282	841,442
2030	6.1941%	45,117,285	309,262,665	261,482,747	255,102,568	3,919,025	2,461,154	55,194,933	847,935
2031	2.0104%	28,068,785	204,330,250	172,761,995	168,546,603	2,589,305	1,626,088	34,763,932	534,063
2032	2.0104%	9,110,315	70,431,504	59,550,102	58,097,079	892,519	560,503	11,423,198	175,489
2033	0.3604%	1,633,077	13,408,023	11,336,534	11,059,923	169,909	106,703	2,073,051	31,847
2034	0.3604%	1,633,077	14,239,320	12,039,399	11,745,638	180,443	113,318	2,098,742	32,242
2035	0.3604%	1,633,077	15,122,158	12,785,842	12,473,867	191,630	120,344	2,124,751	32,642
2036	0.3614%	1,637,551	16,103,730	13,615,764	13,283,539	204,069	128,156	2,156,976	33,137
2037	0.3604%	1,633,077	17,055,436	14,420,435	14,068,576	216,129	135,729	2,177,740	33,456
2038	0.3604%	1,633,077	18,112,873	15,314,502	14,940,828	229,529	144,145	2,204,729	33,870
2039	0.3604%	1,633,077	19,235,871	16,264,001	15,867,159	243,760	153,082	2,232,051	34,290
2040	5.4885%	24,871,326	311,120,511	263,053,563	256,635,056	3,942,568	2,475,939	34,414,818	528,699
92.0391%		453,151,201	2,780,746,877	2,351,131,950	2,293,764,330	35,238,060	22,129,559	537,209,449	8,252,905

	QUALIFIED	NON-QUAL	TOTAL
NPV @12/31/98	537,209,449	8,252,905	545,462,354
LESS BALANCE @ 12/31/98	156,054,420	39,258,524	195,312,944
PV OF FUNDING REQUIREMENTS	381,155,029	(31,005,619)	350,149,410
MONTHLY FUNDING REQUIREMENT	2,217,650	(180,398)	2,037,252
ANNUAL FUNDING REQUIREMENT	26,611,802	(2,164,776)	24,447,025
MONTHLY ACCRUAL	2,217,650	(293,688)	1,923,962
ANNUAL ACCRUAL	26,611,801	(3,524,259)	23,087,541

000040

Florida power & Light Company
1998 Decommissioning Study
St. Lucie Nuclear Units
Support Schedule: Calculation of Qualifying Percentages

Support Schedule H
Page 1 of 2

		<u>St. Lucie Unit No. 1</u>	<u>St. Lucie Unit No. 2</u>
<u>Numerator</u>			
A.	Year for which deductible payment was deemed made to a Qualified Decommissioning Fund	1984	1984
B.	Last year unit is to be included in rate base	2010	2023
	Number of years in numerator	27	40
<u>Denominator</u>			
C.	Year the nuclear unit began commercial operations	1976	1983
D.	Last year the unit is to be included in rate base	2010	2023
	Number of years in denominator	35	41
Qualifying Percentage	$\frac{\text{(Years in Numerator)}}{\text{(Years in Denominator)}}$	<u><u>77.14%</u></u>	<u><u>97.56%</u></u>

000041

Florida power & Light Company
1998 Decommissioning Study
Support Schedule: Calculation of Qualifying Percentages

Under Internal Revenue Code Section 468A, the qualifying percentage for any nuclear decommissioning fund is equal to the fraction in which the numerator is the number of taxable years in the estimated period for which the nuclear decommissioning fund is in effect and the denominator is the number of taxable years in the estimated useful life of the applicable nuclear plant.

The estimated period for which a nuclear decommissioning fund is to be in effect begins on the later of:

- A. The first day of the first taxable year for which a deductible payment is made or deemed made to a nuclear decommissioning fund; or

The first day of the first taxable year that includes the date that the nuclear power plant to which the fund relates begins commercial operations.

The period for which a nuclear decommissioning fund is to be in effect ends:

- B. On the last day of the taxable year that includes the estimated date on which the nuclear power plant to which the fund relates will no longer be included in the Company's rate base for rate making purposes. *

The estimated useful life of the nuclear power plant:

- C. Begins on the first day of the taxable year that includes the date that the nuclear power plant begin commercial operations, and
- D. Ends on the last day of the taxable year that includes the estimated date on which the nuclear power plant will no longer be included in taxpayer's rate base for rate making purposes. *

* The estimated date that the nuclear power plant will not be included in rate base is established in the first rate making proceeding which included the nuclear unit in the taxpayer's rate base.

Florida Power & Light Company
1998 Decommissioning Study
St. Lucie Unit No. 2 - FPL Ownership Percentage
Support Schedule : Cost Allocation Analysis
(1998 Dollars)

Support Schedule I
Page 1 of 3

		<u>Base Case</u>	<u>From Pages 2 & 3</u>
1	St. Lucie Unit No. 2 (Note 1)	453,151,198	4,282,000
2	Common Facilities	<u>4,742,000</u>	2,344,000
			(1,986,000)
3	St. Lucie Unit No. 2 Excluding Costs of Common Facilities	448,409,198	<u>50,000</u>
			<u>52,000</u>
4	St. Lucie Unit No. 2 Share of Costs of Common Facilities (Note 2)	<u>2,371,000</u>	4,742,000
5	Total costs Upon Which Allocation to Participants is Computed	450,780,198	
6	Participants Share of Total Costs (Note 3)	14.89551%	
7	Total Costs Allocated to Participants	67,146,009	
8	Total Costs (line 1 above)	453,151,198	
9	Percent of Total Applicable to Participants	14.81757%	
10	Percent of Total Applicable to FPL Ownership	85.18243%	

Note:

- 1 Common (shared) facilities are expected to be decommissioned at the same time as St. Lucie Unit No. 2 and are included with the decommissioning costs of Unit No. 2.
- 2 The Participants share of the common facilities has been calculated in compliance with the Participation Agreement which provides that the Participants pay for only their ownership share times one-half of the common facility costs.
- 3 Allocation is based on ownership share of 8.80600% for Florida Municipal Power Agency and 6.08951% for Orlando Utilities Commission. (Total = 14.89551%)

000043

TABLE 3.3

**SUMMARY OF COSTS ASSOCIATED WITH
SHARED SYSTEMS AND STRUCTURES**
(thousands of 1998 Dollars) ¹

STRUCTURES	UNIT 1	UNIT 2	TOTAL
East EP Pond	0	1,414	1,414
Shared Miscellaneous Site Structures	0	2,041	2,041
Steam Generator Blowdown Treatment Facility	0	827	827
Subtotal	0	4,282	4,282
SYSTEMS	UNIT 1	UNIT 2	TOTAL
Auxiliary Steam - Insulated	14	10	24
Condensate Polish Filter Demin	14	0	14
Condensate Polish Filter Demin - Ins	43	0	43
Demineralized Makeup Water - RCA	7	4	11
Demineralized Makeup Water	9	4	13
Domestic/Makeup/Service Water	106	5	111
Domestic/Makeup/Service Water-Ins	2	0	2
Domestic/Makeup/Service Water-Ins - RCA	7	1	8
Domestic/Makeup/Service Water - RCA	61	16	77
Fire Protection	41	31	72
Fire Protection - Insulated	4	3	7
Fire Protection - Insulated - RCA	1	3	4
Fire Protection - RCA	14	38	52
Neutralization Basin Recirculation	10	0	10
Primary Water	273	268	541
Primary Water - Insulated	6	7	13
Service & Instrument Air	16	12	28
Service & Instrument Air - Ins	8	6	14
Service & Instrument Air - Ins - RCA	45	37	82
Service & Instrument Air - RCA	32	24	56
SGBTF Blowdown - Insulated	292	1,193	1,485
SGBTF Demin - Ins - RCA	0	29	29
SGBTF Demin - RCA	0	41	41
SGBTF HVAC	468	0	468
SGBTF Misc - RCA	2	0	2
SGBTF Miscellaneous - RCA	0	12	12
SGBTF Waste Management	39	337	376
SGBTF Waste Management - Insulated	411	236	647
Sodium Hypochlorite	0	27	27
Water Treatment - Insulated	39	0	39
Water Treatment	22	0	22
Subtotal	1,986	2,344	4,330

TABLE 3.3

**SUMMARY OF COSTS ASSOCIATED WITH
SHARED SYSTEMS AND STRUCTURES**
(thousands of 1998 Dollars)
(cont'd)

MISCELLANEOUS COMPONENTS - REMOVAL	COST	CONTINGENCY	TOTAL
Shared Refueling Equipment (20)	see below	see below	0
Valves & Piping for Cond Storage Tank Interconnection	see below	see below	0
Turbine Lube Oil Storage Tank	see below	see below	0
Waste Oil Storage Tank	see below	see below	0
Miscellaneous Small Bore Piping	see below	see below	0
Valves & Piping for Holdup Tanks Interconnection	see below	see below	0
Valves & Piping for Aerated Waste Strge Tank Interconnect	see below	see below	0
SGBTF Electrical (9)	see below	see below	0
Tank, Valves, Piping - UHS Valves & Emergency Air	see below	see below	0
Piping for Waste Management System Interconnects	see below	see below	0
Clean Miscellaneous Components	12	1	13
Contaminated Miscellaneous Component - Removal Only	32	5	37
Subtotal	44	6	50
Miscellaneous Components - Decon, Pack, Ship, Bury, Other	38	14	52
TOTAL			8,714

Note 1: Columns may not add due to rounding

DECOMMISSIONING COST STUDY
for the
ST. LUCIE PLANT, UNITS 1 AND 2

Prepared for

Florida Power and Light

prepared by


TLG Services, Inc.
Bridgewater, Connecticut

September, 1998

000046


APPROVALS

Project Manager


Geoffrey M. Griffiths

9/21/98
Date

Technical Manager


William A. Cloutier, Jr.

9/21/98
Date

Quality Assurance Manager


Carolyn A. Palmer

9/21/98
Date

TABLE OF CONTENTS

	SECTION - PAGE
EXECUTIVE SUMMARY	vii-xiii
1. INTRODUCTION	1-1
1.1 Objective of Study	1-1
1.2 Site Description	1-1
1.3 Regulatory Guidance	1-2
1.3.1 Nuclear Waste Policy Act	1-4
1.3.2 Low-Level Radioactive Waste Policy Amendments Act	1-5
1.3.3 Radiological Criteria for License Termination	1-5
2. DECOMMISSIONING ALTERNATIVES	2-1
2.1 DECON	2-1
2.1.1 Period 1 - Preparations	2-2
2.1.2 Period 2 - Operations	2-5
2.1.3 Period 3 - Site Restoration	2-10
2.2 SAFSTOR	2-11
2.2.1 Period 1 - SAFSTOR Operations	2-12
2.2.2 Period 2 - SAFSTOR Dormancy	2-14
2.2.3 Periods 3 & 4 - Deferred Decommissioning	2-16
2.2.4 Period 5 - Site Restoration	2-17
3. COST ESTIMATE	3-1
3.1 Basis of Estimate	3-1
3.2 Methodology	3-1
3.3 Financial Components of the Cost Model	3-2
3.3.1 Contingency	3-3
3.3.2 Financial Risk	3-7
3.4 Site-Specific Considerations	3-8
3.4.1 Spent Fuel Disposition	3-9
3.4.2 Reactor Vessel and Internal Components	3-9
3.4.3 Steam Generators and Other Large System Components	3-10
3.4.4 Transportation Methods	3-12
3.4.5 Low-Level Radioactive Waste Disposal	3-12
3.4.6 Site Conditions Following Decommissioning	3-12
3.5 Assumptions	3-13
3.6 Decommissioning vs. Site Restoration	3-18

TABLE OF CONTENTS
(continued)

	SECTION-PAGE
3.7 Cost Estimate Summary.....	3-19
4. SCHEDULE ESTIMATE	4-1
4.1 Schedule Estimate Assumptions.....	4-1
4.2 Project Schedule	4-2
4.3 Spent Fuel Schedule.....	4-2
5. RADIOACTIVE WASTES.....	5-1
6. RESULTS.....	6-1
7. REFERENCES	7-1

TABLES

Cost and Schedule Estimate Summary.....	xiii
3.1a Schedule of Annual Expenditures DECON Unit 1	3-23
3.1b Schedule of Annual Expenditures DECON Unit 2	3-24
3.2a Schedule of Annual Expenditures SAFSTOR, Unit 1	3-25
3.2b Schedule of Annual Expenditures SAFSTOR, Unit 2	3-27
3.3 Summary of Costs Assoc. with Shared Systems and Structures	3-29
5.1a Decommissioning Radioactive Waste Burial Summary DECON	5-3
5.1b Decommissioning Radioactive Waste Burial Summary SAFSTOR	5-4
6.1a Summary of Decommissioning Cost Contributors DECON, Unit 1.....	6-4
6.1b Summary of Decommissioning Cost Contributors DECON, Unit 2.....	6-5
6.2a Summary of Decommissioning Cost Contributors SAFSTOR, Unit 1	6-6
6.2b Summary of Decommissioning Cost Contributors SAFSTOR, Unit 2	6-7

FIGURES

3.1 Reactor Building Modification for Pressurizer Removal	3-20
3.2 Removal of Steam Generator from Reactor Building	3-21
3.3 Preparation of Steam Generator for Transport	3-21
3.4 Overland Transport of Steam Generator.....	3-22
3.5 Loading of Steam Generator onto Barge	3-22
4.1 DECON Activity Schedule	4-3

TABLE OF CONTENTS
(continued)

	SECTION-PAGE
4.2a DECON Decommissioning Timelines	4-10
4.2b SAFSTOR Decommissioning Timelines	4-11

APPENDICES

A. Unit Cost Factor Development	A-1
B. Unit Cost Factor Listing	B-1
C. Decommissioning Costs: DECON and SAFSTOR Alternatives Long-Term Fuel Storage	C-1
D. Decommissioning Costs: DECON and SAFSTOR Alternatives No On-Site ISFSI Fuel Storage	D-1

REVISION LOG

No.	CRA No.	Date	Item Revised	Reason for Revision
0		9/21/98		Original Issue

EXECUTIVE SUMMARY

This study, prepared for Florida Power and Light by TLG Services, Inc., evaluates four different decommissioning alternatives for the St. Lucie Plant (St. Lucie), following the final cessation of plant operations. The costs associated with the DECON and SAFSTOR scenarios (with on-site dry fuel storage) are provided in a summary table at the end of this section. The major contributors to the overall decommissioning costs are labor, radioactive waste disposal, and on-site fuel storage costs. The costs are based on several key assumptions, including regulatory requirements, contingency provisions, the disposal of low-level radioactive waste, the management of high-level radioactive waste, and the need for site restoration. A complete discussion of the assumptions used in this estimate is presented in Section 3.

A detailed breakdown of the contributors to the decommissioning cost is reported in Section 6. Schedules of annual expenditures are provided in Section 3. The detailed activity costs, waste volumes, and removal man-hours are provided in Appendices C (on-site dry fuel storage) and D (no fuel storage). Unless otherwise noted, the information provided in this report refers to the alternative with on-site dry fuel storage. The four alternatives are defined as follows:

DECON (With On-Site Dry Fuel Storage): This alternative assumes that an on-site Independent Spent Fuel Storage Facility (ISFSI) is constructed with adequate capacity to transfer all fuel to dry storage within 5 years and 2 months of plant shutdown. This allows the fuel handling buildings to be decontaminated and dismantled at an earlier date than would be otherwise possible. On-site storage is assumed to be provided by Dual Purpose Canister and Storage Modules. All fuel is assumed to be transferred to a DOE facility by the year 2040.

DECON (No Fuel Storage): This alternative assumes that an on-site ISFSI facility is not required and that the DOE takes physical possession of the fuel within 5 years and 2 months of plant shutdown. This alternative is intended to provide an "avoided cost" value if there were no requirement for long-term fuel storage. All other DECON assumptions are included in this alternative.

SAFSTOR (With On-Site Dry Fuel Storage): The station is placed in protective storage for a period of approximately 45 years. This alternative assumes that an on-site ISFSI facility is constructed with adequate capacity to transfer all fuel to dry storage within 5 years and 2 months of plant shutdown. This allows the fuel handling buildings to be

decontaminated and dismantled at an earlier date than would be otherwise possible. On-site storage is assumed to be provided by Dual Purpose Canister and Storage Modules. All fuel is assumed to be transferred to a DOE facility by the year 2040.

SAFSTOR (No Fuel Storage): This alternative assumes that an on-site ISFSI facility is not required and that the DOE takes physical possession of the fuel within 5 years and 2 months of plant shutdown. This alternative is intended to provide an "avoided cost" value if there were no requirement for long-term fuel storage. All other SAFSTOR assumptions are included in this alternative.

Alternatives and Regulations

The Nuclear Regulatory Commission (NRC) provided general decommissioning guidance in the rule adopted on June 27, 1988 ¹. In this rule the NRC set forth technical and financial criteria for decommissioning licensed nuclear facilities. The regulations addressed planning needs, timing, funding methods, and environmental review requirements for decommissioning. The rule also defined three decommissioning alternatives as being acceptable to the NRC - DECON, SAFSTOR and ENTOMB.

DECON was defined as "the alternative in which the equipment, structures, and portions of a facility and site containing radioactive contaminants are removed or decontaminated to a level that permits the property to be released for unrestricted use shortly after cessation of operations." ²

SAFSTOR was defined as "the alternative in which the nuclear facility is placed and maintained in a condition that allows the nuclear facility to be safely stored and subsequently decontaminated (deferred decontamination) to levels that permit release for unrestricted use." ³

ENTOMB was defined as "the alternative in which radioactive contaminants are encased in a structurally long-lived material, such as concrete; the entombed structure is appropriately maintained and continued surveillance is carried out until the radioactive material

¹ U.S. Code of Federal Regulations, Title 10, Parts 30, 40, 50, 51, 70 and 72 "General Requirements for Decommissioning Nuclear Facilities," Nuclear Regulatory Commission, Federal Register Volume 53, Number 123 (p 24018+), June 27, 1988.

² Ibid. Page FR24022, Column 3.

³ Ibid.

decays to a level permitting unrestricted release of the property." ⁴ However, this process is restricted in overall duration to 60 years and therefore impractical for use at a Part 50 licensee which generates significant amounts of long-lived radioactive material. Due to neutron activation it cannot be demonstrated that items such as the reactor vessel and internals will decay to unrestricted levels within 60 years of shutdown.

In 1996, the NRC published revisions to the general requirements for decommissioning nuclear power plants to clarify ambiguities and codify procedures and terminology as a means of enhancing efficiency and uniformity in the decommissioning process. The amendments allow for greater public participation and better define the transition process from operations to decommissioning. The costs and schedules presented in this estimate follow the general guidance and sequence in the amended regulations.

Methodology

The methodology used to develop the decommissioning cost estimates for Florida Power and Light follows the basic approach originally presented in the cost estimating guidelines⁵ developed by the Atomic Industrial Forum (now Nuclear Energy Institute). This reference describes a unit cost factor method for estimating decommissioning activity costs. The unit cost factors used in this study reflect site-specific costs, as well as the latest available information about worker productivity in decommissioning. Field experience acquired in the dismantling of the Shippingport and Cintichem reactor facilities, disposition of the Trojan steam generators, as well as experience from TLG's involvement in the planning and engineering for decommissioning the Shoreham, Yankee Rowe, Pathfinder and Rancho Seco nuclear units, is reflected within this estimate.

An activity duration critical path is used to determine the total decommissioning program schedule required for calculating the carrying costs which include program management, administration, field engineering, equipment rental, quality assurance, and security. This systematic approach for assembling decommissioning estimates has ensured a high degree of confidence in the reliability of the resulting costs.

⁴ Ibid. Page FR24023, Column 2.

⁵ T.S. LaGuardia et al., "Guidelines for Producing Commercial Nuclear Power Plant Decommissioning Cost Estimates," AIF/NESP-036, May 1986.

Contingency

Consistent with industry practice, contingencies are applied to the decontamination and dismantling costs developed as, "specific provision for unforeseeable elements of cost within the defined project scope, particularly important where previous experience relating estimates and actual costs has shown that unforeseeable events which will increase costs are likely to occur."⁶ The cost elements in this estimate are based on ideal conditions; therefore, the types of unforeseeable events that are almost certain to occur in decommissioning, based on industry experience, are addressed through a percentage contingency applied on a line-item basis. This contingency factor is a nearly universal element in all large-scale construction and demolition projects. It should be noted that contingency, as used in this estimate, does not account for price escalation and inflation in the cost of decommissioning over the remaining operating life of the units.

The use and role of contingency within decommissioning estimates is not a safety factor issue. Safety factors provide additional security and address situations that may never occur. Contingency funds, by contrast, are expected to be fully expended throughout the program. Inclusion of contingency is necessary to provide assurance that sufficient funding will be available to accomplish the intended tasks.

Low-Level Radioactive Waste Disposal

The contaminated and activated material generated in the decontamination and dismantling of a commercial nuclear reactor is classified as low-level radioactive waste (LLW), although not all of the material is suitable for "shallow-land" disposal. With the passage of the "Low-Level Radioactive Waste Disposal Act" in 1980, and its Amendments of 1985⁷, the states became ultimately responsible for the disposition of low-level radioactive waste generated within their own borders.

Due to the lack of progress in siting the Southeast Compact regional burial facility within the host state of North Carolina, all LLW generated in the decontamination and dismantling of the St. Lucie is assumed destined for disposal at the existing Chem Nuclear Systems, Inc., Barnwell Low-Level Waste Management Facility (Barnwell) in South Carolina. Prior to disposal, much of the metallic radioactive waste shipped from St. Lucie site is assumed to be routed to a recycling vendor. This vendor will apply decontamination and segmentation processes which will release much of the material as clean scrap. Other waste processors may be used, to minimize the total cost of waste disposal.

⁶ Project and Cost Engineers' Handbook, Second Edition, American Association of Cost Engineers, Marcel Dekker, Inc., New York, New York, p. 239.

⁷ "Low-Level Radioactive Waste Policy Amendments Act of 1985," Public Law 99-240, 1/15/86.

High-Level Waste

Congress passed the "Nuclear Waste Policy Act" in 1982⁸, assigning the responsibility for disposal of spent nuclear fuel created by the commercial nuclear generating plants to the Department of Energy (DOE). This legislation also created a Nuclear Waste Fund to cover the cost of the program, which is funded by the sale of electricity from nuclear reactors, and an estimated equivalent for assemblies irradiated prior to April, 1983. The target date for startup of the Federal Waste Management System was originally 1998.

Site Restoration

The efficient removal of the contaminated materials at the site may result in damage to many of the site structures. Blasting, coring, drilling and the other decontamination activities will substantially damage power block structures, potentially weakening the footings and structural supports. Prompt demolition after license termination is clearly the most appropriate and cost-effective option. It is unreasonable to anticipate that these structures would be repaired and preserved after the radiological contamination is removed. The cost to dismantle site structures with a work force already mobilized on site is more efficient and less costly than if the process is deferred. Experience at shutdown generating stations has shown that plant facilities quickly degrade without continual maintenance, adding additional expense and creating potential hazards to the public, as well as to the demolition work force. Consequently, this study assumes that site structures will be removed to a nominal depth of three feet below the local grade level whenever possible. Foundation grade slabs greater than three feet in thickness will be abandoned in place and covered over with a three-foot layer of backfill. The intake and discharge canals will be backfilled to grade with existing rubble and site soil. The site will then be graded and stabilized.

Recommendations

In most situations, the DECON alternative is the preferred mode of decommissioning. This alternative is favored because it eliminates the costs for caretaking and prevents the site from becoming a potential long-term safety hazard. More importantly, the individuals familiar with the operation of the nuclear facility are available to support the dismantling effort; plant systems and services are fully functional; structural integrity is intact; and the licensee has a comprehensive management organization available to oversee/conduct the orderly decontamination and termination of the NRC licenses of the site. For Florida Power and Light, the DECON alternative is a valid

⁸ "Nuclear Waste Policy Act of 1982 and Amendments," U.S. Department of Energy's Office of Civilian Radioactive Management, 1982.

and cost-effective option; it is also the least expensive option on a station basis prior to any time-value of money considerations.

The construction of barriers and the general decontamination of plant areas in preparation for long-term storage (SAFSTOR) does not necessarily alleviate the need for continued surveillance. Therefore SAFSTOR would require a full-time preventive and corrective maintenance staff to maintain essential site services and prevent the deterioration of the facilities. Maintenance would be required on security systems, area lighting, and on-site facilities supporting the fuel storage activity. These facilities include power centers, administrative offices, and fuel transfer/repackaging facilities. Active supporting systems and components include plant fire protection, site drainage/monitoring and sewage, plant transformers and switchyard, plant grounding and lightning protection, communications, liquid collection, sampling and processing, seismic monitoring, etc. The NRC's review of currently dormant facilities has resulted in a general increase in the level of maintenance the agency is requiring, as well as a greater on-site presence by the licensee. As a result, estimates for the caretaking of a dormant facility have increased significantly from earlier projections.

Summary

The DECON alternatives involve removal of all radioactive material from the site following permanent shutdown. The facility operator may then have unrestricted use of the site with no further requirement for a license. This study also assumes that the remainder of the plant systems and structures on site, not previously removed in support of license termination, are dismantled and the site restored. For comparison, SAFSTOR decommissioning alternatives are also evaluated for a 45 year safe-storage period.

This study provides estimates for decommissioning St. Lucie under current requirements and is based on present-day costs and available technology. The schedule and sequence of decommissioning activities for the DECON and SAFSTOR alternatives are identified in Section 4. Cost summaries are provided in Section 6. Detailed cost tables are provided in Appendices C and D.

COST AND SCHEDULE ESTIMATE SUMMARY

	Costs 98\$ (thousands) ¹	Schedule (months)
DECON (WITH ON-SITE DRY FUEL STORAGE)		
Unit 1	428,917	293
Unit 2	<u>453,151</u>	208
Total	882,068	
SAFSTOR (WITH ON-SITE DRY FUEL STORAGE)		
<i>Unit 1</i>		
Preparations	63,890	18
51.98 year maintenance cost	172,497	624
Delayed dismantling	<u>273,418</u>	93
Subtotal Unit 1	509,804	
<i>Unit 2</i>		
Preparations	78,738	18
46.34 year maintenance cost	99,062	556
Delayed dismantling	<u>270,585</u>	75
Subtotal Unit 2	448,385	
TOTAL	958,189	

1. Columns may not add due to rounding.

1. INTRODUCTION

This cost estimate analysis, prepared by TLG Services, Inc., (TLG) is designed to provide Florida Power and Light (FP&L) with sufficient information to prepare financial planning documents required by the Nuclear Regulatory Commission (NRC). It is not a detailed engineering document, but a cost estimate prepared in advance of the detailed engineering preparations required to carry out the decommissioning of St. Lucie Plant (St. Lucie) Units 1 and 2.

1.1 OBJECTIVE OF STUDY

The objective of this study is to prepare an estimate of the cost, schedule, and waste volume generated to decommission St. Lucie, including all common and supporting facilities. The study considers extended on-site, dry fuel storage and the integration of two-unit dismantling, as discussed below. Unless otherwise noted, the information provided in this report refers to the alternative with on-site dry fuel storage.

The operating license for Unit 1 was issued on March 1, 1976, and currently expires at the end of 40 years on March 1, 2016. The operating license for Unit 2 was issued on April 6, 1983, and expires at the end of 40 years on April 6, 2023. For the purposes of this study, final shutdown of each of the two units is assumed to occur on the expiration date of each unit's operating license.

1.2 SITE DESCRIPTION

The St. Lucie Plant is located approximately halfway between the cities of Fort Pierce and Stuart on the east coast of Florida. Units 1 and 2 are two essentially identical 890 and 830 MWe (net electrical output at rated power) pressurized water reactors with supporting facilities. Florida Power & Light Company (FP&L) is the primary owner and operator of the station. St. Lucie Units 1 and 2 were designed and constructed by Ebasco Services, Inc.

The Nuclear Steam Supply Systems (NSSS) consist of pressurized water reactor systems designed by Combustion Engineering, Incorporated. The Reactor Coolant Systems (RCS) consist of two similar heat transfer loops connected in parallel to the reactor pressure vessel. Each loop contains two reactor coolant pumps, one steam generator, and associated piping and valves. In addition, the systems include a pressurizer, a pressurizer relief tank, interconnecting piping, and instrumentation necessary for operational control. All the system equipment, except for the digital pressure indicator, three wide range pressure transmitters, and the containment isolation and process

actuated valves located in the lines connected to the pressurizer relief tank, are located in the Containment Buildings. The total primary heat output is 2700 Megawatts thermal (MWt).

The Containments are a dual containment design comprised of a steel containment vessel surrounded by an annular space and enclosed by reinforced concrete Shield Buildings. The vessel is cylindrical in shape with a hemispherical dome and ellipsoidal bottom.

Heat produced in the reactors is converted to electrical energy by the Steam and Power Conversion System (SPCS). The function of the turbine generators, which serve no safety function, is to receive steam from steam generators, economically convert a portion of the thermal energy contained in the steam to electrical energy, and provide extraction steam for five stages of feedwater heating. Steam is directed from the high pressure turbine element to four combination moisture-separator/reheater assemblies before entering the low pressure turbines. The exhaust steam from the two low pressure turbines is condensed in the condenser.

Heat rejected in the main condensers is removed by the Circulating Water Systems (CWS), which condenses the steam exhaust from the turbine. Cooling water for the condenser is supplied by the Atlantic Ocean.

1.3 REGULATORY GUIDANCE

The NRC provided decommissioning guidance in the rule "General Requirements for Decommissioning Nuclear Facilities," (Ref. 1) published and adopted on June 27, 1988. This rule amended NRC regulations to set forth technical and financial criteria for decommissioning licensed nuclear facilities. The regulation addressed decommissioning planning needs, timing, funding methods, and environmental review requirements. The intent of the rule was to ensure that decommissioning would be accomplished in a safe and timely manner and that adequate licensee funds would be available for this purpose. Subsequent to the rule, the NRC issued Regulatory Guide 1.159, "Assuring the Availability of Funds for Decommissioning Nuclear Reactors," (Ref. 2) which provided guidance to the licensees of nuclear facilities on methods acceptable to the NRC staff for complying with the requirements of the rule. The regulatory guide addressed the funding requirements and provided guidance on the content and form of the financial assurance mechanisms indicated in the rule amendments.

The rule defined three decommissioning alternatives as being acceptable to the NRC: DECON, SAFSTOR and ENTOMB. It also placed limits on the time

allowed to complete the decommissioning process. For SAFSTOR, the process is restricted in overall duration to 60 years unless it can be shown that a longer duration is necessary to protect public health and safety. The guidelines for ENTOMB are similar, providing the NRC with both sufficient leverage and flexibility to ensure that these deferred options are only used in situations where it is reasonable and consistent with the definition of decommissioning. Consequently, with these restrictions, the SAFSTOR and ENTOMB options are no longer decommissioning alternatives in themselves, as neither terminates the license for the site. At the conclusion of a 60-year dormancy period (or longer for ENTOMB if the NRC approves such a case), the site would still require significant remediation to meet the definition of unrestricted release and license termination. Further, the NRC does not believe that ENTOMB is generally a viable option for a power reactor due to the long-lived nature of the radionuclides involved.

In 1996 the NRC published revisions to the general requirements for decommissioning nuclear power plants (Ref. 3). When the decommissioning regulations were adopted in 1988, it was assumed that the majority of licensees would decommission at the end of the operating license life. Since that time, several licensees have permanently and prematurely ceased operations without having submitted a decommissioning plan. In addition, these licensees requested exemptions from certain operating requirements as being unnecessary once the reactor is defueled. Each case has been handled individually without clearly defined generic requirements. The NRC amended the decommissioning regulations in 1996 to clarify ambiguities and codify procedures and terminology as a means of enhancing efficiency and uniformity in the decommissioning process. The new amendments allow for greater public participation and better define the transition process from operations to decommissioning.

Under the revised regulations, licensees would submit written certification to the NRC within 30 days after the decision to cease operations. Certification would also be required once the fuel was permanently removed from the reactor vessel. Submittal of these notices would entitle the licensee to a fee reduction and eliminate the obligation to follow certain requirements needed only during operation of the reactor. Within two years of submitting notice of permanent cessation of operations, the licensee would be required to submit a Post-Shutdown Decommissioning Activities Report (PSDAR) to the NRC. The PSDAR describes the planned decommissioning activities, the associated sequence and schedule, and an estimate of expected costs. Prior to completing decommissioning, the licensee would be required to submit an application to the NRC to terminate the license, along with a license termination plan.

1.3.1 Nuclear Waste Policy Act

Congress passed the Nuclear Waste Policy Act in 1982 (Ref. 4), assigning the responsibility for disposal of spent nuclear fuel from the commercial generating plants to the Department of Energy (DOE). Two permanent disposal facilities were envisioned as well as an interim facility. To recover the cost of permanent spent fuel disposal, this legislation created a Nuclear Waste Fund through which money was to be collected from the consumers of the electricity generated by commercial nuclear power plants. The date targeted for start-up of the Federal Waste Management System was 1998.

After pursuing a national site selection process, the Act was amended in 1987 to designate Yucca Mountain, Nevada, as the only site to be evaluated for geologic disposal of high-level waste. Also in 1987, the DOE announced a five-year delay in the opening date for the repository, from 1998 to 2003. Two years later, in 1989, an additional 7-year delay was announced, primarily due to problems in obtaining the required permits from the state of Nevada to perform the required characterization of the site. The DOE has projected additional delays as a result of proposed Congressional reductions in appropriations for the program.

Utilities have responded to this impasse by initiating legal action and constructing supplemental storage as a means of maintaining operating margins. On November 14, 1997, the U.S. Court of Appeals for the District of Columbia Circuit issued a decision in *Northern States Power Company, et al., v. U.S. Department of Energy*. In the decision, the Court reaffirmed its earlier *Indiana Michigan* ruling that DOE has an unconditional obligation to begin disposal of the utilities' spent nuclear fuel (SNF) by January 31, 1998. Since the agency was not in default at the time the decision was issued, the court declined to prescribe "remedies" in the likely event DOE failed to uphold its obligation. However, even with the ruling, DOE's position has remained unchanged. The agency continues to maintain that its delayed performance is unavoidable because it does not have an operational repository and does not have authority to provide storage in the interim. Consequently, DOE has no plans to receive spent fuel before the year 2010.

Both the DECON and SAFSTOR alternatives assume that the DOE begins accepting spent fuel in 2010. FP&L will therefore incur ISFSI - related construction, canister/module acquisition, and decommissioning

costs. The ISFSI will be sized to accommodate 90 storage modules and will be in operation from 2005 through 2040.

1.3.2 Low-Level Radioactive Waste Policy Amendments Act

Congress passed the "Low-Level Radioactive Waste Disposal Act" in 1980, declaring the states as being ultimately responsible for the disposition of low-level radioactive waste generated within their own borders. The federal law encouraged the formation of regional groups or compacts to implement this objective safely, efficiently and economically, and set a target date of 1986. With little progress, the "Amendments Act" of 1985 (Ref. 5) extended the target, with specific milestones and stiff sanctions for non-compliance. However, more than 10 years later, no new sites have been developed and even the most advanced program is far behind schedule.

Due to the lack of progress in siting the Southeast Compact regional burial facility within the host state of North Carolina, all LLW generated in the decontamination and dismantling of St. Lucie is assumed destined for disposal at the existing Chem Nuclear Systems, Inc., Barnwell LLW Management Facility (Barnwell) in South Carolina. Prior to disposal, much of the metallic radioactive waste shipped from the St. Lucie site is assumed to be routed to a recycling vendor. This vendor will apply decontamination and segmentation processes which will release much of the material as clean scrap. Other waste processors may be used to minimize the total cost of waste disposal.

1.3.3 Radiological Criteria for License Termination

In 1997, 10 CFR 20 Subpart E Radiological Criteria for License Termination (Ref. 6), was published. This subpart provided radiological criteria for releasing a facility for unrestricted use. The criteria specifically defined a basis [Total Effective Dose Equivalent (TEDE) not to exceed 25 mrem per year to an average member of a critical group] by which levels of acceptable established residual radioactivity can be established, provided that residual radioactivity has been reduced to levels that are as low as reasonably achievable.

This subpart provides a well-defined license termination criteria, but does create uncertainties in predicting the total disposal volume of slightly contaminated materials (such as soil and silt which may require removal and disposal). The volume of contaminated soil/silt

required to be decontaminated or disposed of may vary significantly depending on the levels of soil contamination, the radioactive isotopes causing the contamination, and the geographic distribution of the contamination.

2. DECOMMISSIONING ALTERNATIVES

Cost studies were developed to decommission St. Lucie for two of the NRC-approved decommissioning alternatives: DECON and SAFSTOR. The duration of dormancy periods selected for the SAFSTOR alternatives are within the maximum allowable interval (60 years) between cessation of operations and termination of the site license(s). Although the alternatives differ with respect to technique, process, cost, and schedule, the two alternatives attain the same result: removal of all regulated radioactive material from the site and ultimate release of the site for unrestricted and/or alternative use.

The following sections describe the basic activities associated with each alternative. Although detailed procedures for each activity identified are not provided, and the actual sequence of work may vary, these activity descriptions provide a basis not only for estimating, but also for the expected scope of work, i.e., engineering and planning at the time of decommissioning.

2.1 DECON

The DECON alternative, as defined by the NRC, is "the alternative in which the equipment, structures, and portions of a facility and site containing radioactive contaminants are removed or decontaminated to a level that permits the property to be released for unrestricted use shortly after cessation of operations." This study does not address the cost to remove spent fuel from the site; such costs are assumed to be funded through the surcharge on electrical generation (1 mill/kWhr). However, the study does recognize the constraint imposed by the spent fuel residing on site during the decommissioning process and also the costs associated with extended on-site caretaking of the fuel.

The approach that the NRC has chosen in its recently amended regulations is to divide decommissioning into three phases. The initial phase commences with the effective date of permanent cessation of operations and involves the transition of both plant and licensee from reactor operations, i.e., power production to facility de-activation and closure. During Phase I, notification is to be provided to the NRC certifying the permanent cessation of operations and the removal of fuel from the reactor vessel. The licensee is then prohibited from reactor operation. Within two years of notification to cease reactor operations, the licensee is required to provide a Post-Shutdown Decommissioning Activities Report (PSDAR). This report provides a description of the licensee's planned decommissioning activities, a corresponding schedule, and an estimate of expected costs. The PSDAR also addresses whether environmental impacts

associated with the proposed decommissioning scenario have already been considered in a previously prepared environmental statement(s). Ninety days following the NRC's receipt of the PSDAR, the licensee may initiate certain decommissioning activities, without specific NRC approval, under a modified Title 10 of the Code of Federal Regulations, Section 50.59 review process (all subsequent references to Title 10 of the Code will be by section number only, i.e. §50.59). The amended regulations permit the licensee to expend/recover up to 3% of the generic decommissioning cost for planning, with an additional 20% available following the 90-day waiting period and certification of permanent defueling. Remaining funds would be available to the licensee with submittal of a detailed, site-specific cost estimate.

The second phase identified by the NRC addresses licensed activities during a storage period, applicable to the dormancy phases of the deferred decommissioning alternative SAFSTOR.

Phase three pertains to the activities involved in license termination. The submittal of an application to terminate the license, along with a termination plan, marks the commencement of this phase. The termination plan contains a detailed site characterization, i.e., location, type, and amount of radioactivity, a description of any remaining dismantling activities to be accomplished, detailed plans for a final survey, and any planned use of the site. An updated cost to complete is required along with the reporting of any new or altered environmental consequences.

The TLG methodology divides the decommissioning project into periods based upon major milestones in the project. Phase I of the NRC's 1996 amended regulations corresponds roughly to Period 1 of DECON, with Phase III corresponding to Period 2. The NRC Phase II has no corresponding period in the DECON mode, being applicable only to the dormancy period of SAFSTOR (Period 2). DECON Period 3 and SAFSTOR Period 5, Site Restoration, are not addressed in the amended regulations.

Due to the 85 month difference in shutdown dates, a DECON alternative was not prepared for Unit 1; instead a "shortened" SAFSTOR was performed on Unit 1, integrated with a DECON of Unit 2. Therefore the DECON alternative is only directly applicable to Unit 2.

2.1.1 Period 1 - Preparations

In anticipation of the cessation of plant operations, detailed preparations are undertaken to provide a smooth transition from plant operations to site decommissioning. The organization required to

manage the intended decommissioning activities is assembled from available plant staff and outside resources, as required. Preparations include the planning for permanent defueling of the reactor, revision of technical specifications applicable to the operating conditions and requirements, a characterization of the facility and major components, and the development of the PSDAR.

Engineering and Planning

Prior to the commencement of decommissioning operations the licensee will certify the permanent cessation of operations and the removal of fuel from the reactor vessel. The PSDAR, required within two years of the notice to cease operations, provides a description of the licensee's planned decommissioning activities, a timetable, and the associated financial requirements of the decommissioning program. Upon receipt of the PSDAR, the NRC will make the document available to the public for comment in a local hearing to be held in the vicinity of the reactor site. Ninety days following submittal and NRC receipt of the PSDAR, the licensee may begin to perform major decommissioning activities under a modified §50.59 procedure, i.e., without specific NRC approval. Major activities are defined as any activity that results in permanent removal of major radioactive components (primary coolant system components/piping), permanently modifies the structure of the containment (removal of the bioshield), or results in dismantling components containing Greater-than-Class C waste (GTCC as defined under §61). Major radioactively-contaminated components are further defined as comprising the reactor vessel and internals, steam generators, pressurizer, large bore reactor coolant system piping, and other large components. The NRC includes the following additional criteria for use of the §50.59 process in decommissioning: the proposed activity must not 1) foreclose release of the site for possible unrestricted use, 2) significantly increase decommissioning costs, 3) cause any significant environmental impact, or 4) violate the terms of the licensee's existing license. Consequently, in conjunction with the development of the PSDAR, activity specifications, cost-benefit and safety analyses, work packages and procedures, etc. must be assembled in support of the proposed decontamination and dismantling activities.

The decommissioning program outlined in the PSDAR will be designed to accomplish the required tasks within the As-Low-As-Reasonably-Achievable (ALARA, as defined in §20) guidelines for protection of personnel from exposure to radiation hazards. It will also address the

continued protection of the health and safety of the public and the environment during the dismantling activity.

The NRC recognizes that the existing operational technical specifications will require review and modifications to reflect plant conditions and the safety concerns associated with permanent cessation of operations. The environmental impact associated with the planned decommissioning activities must also be considered; an environmental report on specific and unique concerns must be submitted to the NRC for consideration and possible preparation of an environmental impact statement.

Much of the work in preparing the PSDAR is also relevant to the development of the detailed engineering plans and procedures. This work includes, but is not limited to:

1. Site preparation plans for the proposed decommissioning activities.
2. Detailed procedures and sequences for removal of systems and components.
3. Evaluation of the disposition alternatives for the reactor vessel and its internals.
4. Plans for decontamination of structures and systems.
5. Design/procurement and testing of tooling and equipment.
6. Identification/selection of specialty contractors.
7. Procedures for removal and disposal of radioactive materials.
8. Sequential planning of activities to minimize conflicts with simultaneous tasks.

Site Preparations

Following final plant shutdown and in preparation for actual decommissioning activities, the following activities are initiated.

1. Prepare site support and storage facilities, as required.

2. Perform a site characterization study to determine extent of site contamination.
3. Transfer fuel to dry storage at an on-site ISFSI constructed with adequate capacity to transfer all fuel on-site within 5 years and 2 months of plant shutdown. This allows the fuel handling buildings to be decontaminated and dismantled at an earlier date than would be otherwise possible.
4. Clean all plant areas of loose contamination and process all liquid and solid wastes.
5. Conduct radiation surveys of work areas, major components (including the reactor vessel and its internals), sampling of internal piping contamination levels, and primary shield cores.
6. Correlate survey data and normalize for development of packaging and transportation procedures.
7. Determine transport and disposal container requirements for activated materials and/or hazardous materials, including shielding and stabilization. Fabricate or procure such containers.
8. Develop procedures for occupational exposure control, control and release of liquid and gaseous effluent, processing of radwaste including DAW, resins, filter media, metallic and non-metallic components generated in decommissioning, site security and emergency programs, and industrial safety.

Following submittal of the PSDAR and certification of permanent fuel removal from the reactor vessel, the licensee may commence major decommissioning activities. Full access to the decommissioning fund will require the preparation of a detailed site-specific cost estimate for submittal to the NRC. In addition, a license termination plan must be prepared at least two years prior to the license termination date.

2.1.2 Period 2 - Operations

Decommissioning Activities

For the DECON alternative, significant decommissioning activities involve the following steps:

1. Construct temporary facilities and modify existing storage facilities to support the dismantling activities. These may include additional changing rooms and contaminated laundry facilities for increased work force, establishment of laydown areas to facilitate equipment removal and preparation for off-site transfer, upgrading roads to facilitate hauling and transportation, and modifications to the Reactor Building to facilitate access of large/heavy equipment.
2. Design and fabricate shielding in support of removal and transportation activities as well as contamination control envelopes; specify/procure specialty tooling and remotely operated equipment. Modify the refueling facilities to support segmentation activities and prepare rigging for segmentation and extraction of heavy components, including the reactor vessel and its internals.
3. Procure (lease or purchase) required shipping canisters, cask liners, and Industrial Packages (IPs) from suppliers.
4. Conduct decontamination of components and piping systems as required to control (minimize) worker exposure. Remove, package, and dispose of all piping and components that are no longer essential to support decommissioning operations.
5. Remove control rod drive housings and the head service structure from reactor vessel head and package for controlled disposal.
6. Segment reactor vessel closure head and vessel flange for shipment in cask liners. Load overpack liners into shielded casks or place in shielded vans for transport.
7. Segment upper internals assemblies; package segments in shielded casks. These operations are performed remotely by cutting equipment located underwater in the refueling facilities. Package and dispose of items that meet §61 "Class C" criteria or less.
8. Disassemble/segment remaining reactor internals in shielded casks. The operations are also conducted under water using remotely operated tooling and contamination controls. Package and dispose of items that meet §61 "Class C" criteria or less.
9. Package §61 GTCC components into fuel bundle containers for handling and storage along with the spent fuel assemblies.

Transfer fuel bundle containers to the fuel handling facilities or suitable storage location.

10. Segment/section the reactor vessel, placing segments into shielded containers. The operation is performed remotely in air using a contamination control envelope. Sections are placed in containers stored under water (for example in an isolated area of the refueling canal or spent fuel pool) using a remote or shielded crane. Transport the containers using shielded truck casks.
11. Remove the reactor coolant pumps. Package the piping in IPs; the reactor coolant pumps are sealed with steel plate so as to serve as their own containers. Ship piping and pumps for controlled disposal.
12. Remove systems and associated components as they become non-essential to the vessel removal operation, related decommissioning activities, or worker health and safety (e.g., waste collection and processing systems, electrical and ventilation systems, etc.).
13. The station diesel generators will remain available to provide emergency power to the spent fuel cooling and cleanup systems during the required heat decay phase for the last core off-load. The fuel handling buildings' handling and transfer equipment, which supports the transfer of the assemblies either off-site or to dry storage on-site, may also require the station diesel generators to be available.
14. Remove activated concrete biological/sacrificial shield and accessible contaminated concrete (excluding steam generator and pressurizer cubicles). If dictated by the steam generator and pressurizer removal scenarios, remove those portions of the associated cubicles necessary for access and component extraction.
15. Remove steam generators and pressurizer for shipment and controlled disposal. Decontaminate exterior surfaces, as required, and seal-weld openings (nozzles, inspection hatches, and other penetrations). These components can serve as their own burial containers provided that all penetrations are properly sealed and the internal contaminants are stabilized. Add steel shields to those external areas of the steam generators to meet transportation limits and regulations.

License Termination

The preparation of a termination plan is required at least two years prior to the anticipated date of license termination. The plan must include a site characterization, description of the remaining dismantling activities, plans for site remediation, procedures for the final radiation survey, designation of any reuse of the site, an updated cost estimate to complete the decommissioning, and any associated environmental concerns. The NRC will publish notice of a receipt of the plan and make the plan available for public comment. A local hearing will also be scheduled. Plan approval may be subject to conditions and limitations as deemed appropriate by the NRC. The licensee may then commence with the final remediation of site facilities and services, including:

1. Remove steel liners from the refueling canal, and containment, including any contaminated concrete behind liners, and route for controlled disposition.
2. Remove contaminated equipment and material from all the remaining auxiliary structures. Remediate until radiation surveys indicate that the structure can be released for unrestricted access.
3. Remove contaminated equipment and material from the fuel handling facilities following the transfer of all residual spent fuel to the on-site storage facility. Remediate fuel handling facilities areas until radiation surveys indicate that the structure can be released for unrestricted access.
4. Decontaminate remaining site buildings and facilities with residual contaminants. Remove all remaining LLW along with any remaining hazardous and toxic materials. Material removed in the decontamination and dismantling of the nuclear units will be routed to an on-site central processing area. Material certified to be free of contamination will be released for unrestricted disposition, e.g., as scrap, recycle, or general disposal. Contaminated material will be characterized and segregated for additional on-site decontamination, off-site processing (disassembly, chemical cleaning, volume reduction, waste treatment, etc.) and/or packaged for controlled disposal at the regional low-level radioactive waste disposal facility.
5. Remediate site areas which contain concentrations of radionuclides exceeding NRC release limits.

6. Remove remaining components, equipment, and plant services in support of the area release survey(s).
7. Conduct final radiation survey to ensure that all radioactive materials in excess of permissible residual levels have been remediated. This survey may coincide with the confirmatory NRC site inspection. These activities are scheduled at the end of Period 2, the operations phase.
8. Unit 1 decontamination and dismantling activities are assumed to be completed prior to Unit 2 decontamination and dismantling activities. This study assumes that the demolition of the Unit 1 non-contaminated facilities will be delayed such that the demolition effort for the station is integrated. As such, Unit 1 structural demolition will be delayed until the completion of the Unit 2 decontamination and dismantling activities.

Incorporated into the License Termination Plan, the Final Survey Plan details the radiological surveys to be performed once the decontamination activities are completed. The Final Survey Plan is developed using the guidance provided in NUREG/CR-5849, "Manual for Conducting Radiological Surveys in Support of License Termination." This document delineates the statistical approaches to survey design and data interpretation used by the Environmental Protection Agency (EPA). It also identifies state-of-the-art, commercially available, instrumentation and procedures for conducting radiological surveys. Use of this guidance ensures that survey design and implementation are conducted in a manner that provides a high degree of confidence that applicable NRC criteria are satisfied. Once the survey is complete, the results are provided to the NRC in a format that can be verified. The NRC then reviews and evaluates the information, performs an independent confirmation of radiological site conditions, and makes a determination on final termination of the license.

The NRC will terminate the license if it determines that site remediation has been performed in accordance with the license termination plan, and that the terminal radiation survey and associated documentation demonstrate that the facility is suitable for release.

2.1.3 Period 3 - Site Restoration

Following completion of decommissioning operations, site restoration activities may begin. Efficient removal of the contaminated materials and verification that residual radionuclide concentrations are below the NRC limits will result in substantial damage to many of the structures. Blasting, coring, drilling, scarification (surface removal), and the other decontamination activities will substantially damage power block structures including the Reactor, Auxiliary, Radwaste and Turbine Buildings. Verifying that subsurface radionuclide concentrations meet NRC site release requirements may require removal of grade slabs and lower floors, potentially weakening footings and structural supports. This removal activity will be necessary for those facilities and plant areas where historical records, when available, indicate the potential for radionuclides having been present in the soil, where system failures have been recorded, or where it is required to confirm that subsurface process and drain lines were not breached over the operating life of the station.

Prompt dismantling of site structures is clearly the most appropriate and cost-effective option. It is unreasonable to anticipate that these structures would be repaired and preserved after the radiological contamination is removed. The cost to dismantle site structures with a work force already mobilized on site is more efficient and less costly than if the process is deferred. Site facilities quickly degrade without continual maintenance, adding additional expense and creating potential hazards to the public as well as to future workers. Abandonment creates a breeding ground for vermin infestation as well as other biological hazards.

This cost study presumes that non-essential structures and site facilities will be dismantled as a continuation of the decommissioning activity. Foundations and exterior walls are assumed to be removed to a nominal depth of three feet below grade whenever possible. Foundation grade slabs greater than three feet in thickness are abandoned in place and covered over with a three-foot layer of backfill. The three-foot depth allows for the placement of both gravel for drainage, as well as topsoil so that vegetation can be established for erosion control. Site areas affected by the dismantling activities are cleaned and the plant area graded as required to prevent ponding and inhibit the refloating of subsurface materials. Activities include:

1. Perform demolition of the remaining portions of the containment structure and interior portions of the Reactor Building. Internal floors and walls are removed from the lower levels upward, using controlled blasting techniques. Concrete rubble and clean fill produced by demolition activities are used on-site to backfill voids. Suitable materials can be used on site for fill; otherwise the rubble is trucked off-site for disposal as construction debris.
2. Remove remaining buildings using conventional demolition techniques for above ground structures, including the Radwaste Building, Turbine Building, Auxiliary Building, Control Building, Fuel Handling Building, Service Building and other site structures.
3. Throughout Period 3, FP&L will maintain an on-site ISFSI. The transfer of assemblies to a DOE facility is expected to continue until 2040. After all of the spent fuel has been shipped to the DOE, the ISFSI will be decontaminated (if needed) to levels permitting termination of the Part 72 license.
4. Following notification by FP&L, the NRC will verify that the Part 72 license termination criteria are satisfied. When the requirements are deemed satisfactory for the ISFSI, the NRC can terminate the remaining license(s) for the site. The ISFSI would then be dismantled by conventional means.
5. Prepare the final dismantling program report.

2.2 SAFSTOR

The NRC defines SAFSTOR as "the alternative in which the nuclear facility is placed and maintained in a condition that allows the nuclear facility to be safely stored and subsequently decontaminated (deferred decontamination) to levels that permit release for unrestricted use." The facility is left intact, (during the SAFSTOR period) with structures maintained in a sound condition. Systems not required to operate in support of the spent fuel pool or site surveillance and security are drained, de-energized, and secured. Minimal cleaning/removal of loose contamination and/or fixation and sealing of remaining contamination is performed. Access to contaminated areas is secured to provide controlled access for inspection and maintenance.

The engineering and planning requirements are similar to those for the DECON alternative, although a shorter time period is expected for these

activities due to the more limited work scope. Site preparations are also similar to those for the DECON alternative. However, with the exception of the required radiation surveys and site characterizations, the mobilization and preparation of site facilities is less extensive.

The SAFSTOR alternatives is used twice for Unit 1. In both instances the SAFSTOR mode of Unit 1 is integrated with Unit 2 decommissioning operations; the only difference lies in integrating either with Unit 2 DECON, or Unit 2 SAFSTOR. This change affects the duration of the Unit 1 dormancy period.

2.2.1 Period 1 - SAFSTOR Operations

The NRC three phase approach to decommissioning is described in detail in Sections 2.1, 2.1.1, and 2.1.2.

In anticipation of the cessation of plant operations, detailed preparations are undertaken to provide a smooth transition from plant operations to site decommissioning. The organization required to manage the intended decommissioning program is assembled from available plant staff and outside resources, as required. Preparations include the planning for permanent defueling of the reactor, revision of technical specifications appropriate to the operating conditions and requirements, a characterization of the facility and major components, and the development of the PSDAR.

The program outlined in the PSDAR will be designed to accomplish the required tasks within the ALARA guidelines for protection of personnel from exposure to radiation hazards. It also addresses the continued protection of the health and safety of the public and the environment.

The NRC recognizes that the existing operational technical specifications will require review and modifications to reflect plant conditions and the safety concerns associated with permanent cessation of operations. The environmental impact associated with the planned decommissioning activities must be considered; an environmental report on those concerns not already assessed must be submitted to the NRC for consideration and possible preparation of an environmental impact statement.

The process of placing the plant in safe-storage includes, but is not limited to, the following activities:

1. Isolate spent fuel storage services and fuel handling systems located in the fuel handling facilities from the power block so that safe-storage operations may commence on the balance of the plant. This activity may be carried out by plant personnel in accordance with existing operating technical specifications. Activities are assumed to be scheduled around the fuel handling systems to the greatest extent possible. All remaining spent fuel on site will be stored in the existing spent fuel pools until transfer to an on-site ISFSI can be completed.
2. Drain/de-energize/secure all non-contaminated systems not required to support dormancy operations.
3. Dispose of contaminated filter elements and resin beds not required for processing wastes from decontamination activities.
4. Drain reactor vessel; internals will remain in place.
5. Drain/de-energize/secure all contaminated systems. Decontaminate systems as required for future maintenance and inspection.
6. Prepare lighting and alarm systems whose continued use is required. De-energize and/or secure portions of fire protection, electric power, and HVAC systems whose continued use is not required.
7. Clean loose surface contamination from building access pathways.
8. Perform an interim radiation survey of plant; post warning signs as appropriate.
9. Erect physical barriers and/or secure all access to radioactive or contaminated areas, except as required for controlled access, i.e., inspection and maintenance.
10. Transfer spent fuel to the ISFSI, or a DOE or intermediate facility - continuously throughout Period 1 and into the dormancy period.
11. Install security and surveillance monitoring equipment and relocate security fence around secured structures, as required.
12. This study assumes that demolition would be delayed for those structures which are located outside the secured area until after the termination of the license.

2.2.2 Period 2 - SAFSTOR Dormancy

The second phase identified by the NRC in its rule addresses licensed activities during a storage period and is applicable to the dormancy phases of the deferred decommissioning alternative SAFSTOR. After an optional period of storage (such that license termination is accomplished within 60 years of final shutdown), it is required that the licensee submit an application to terminate the license, along with a termination plan (described in Section 2.1.2), thereby initiating the third phase.

Activities required during the planned dormancy period for the SAFSTOR alternative include a 24-hour guard force, preventive and corrective maintenance on security systems, area lighting, general building maintenance, heating and ventilation of buildings, routine radiological inspections of contaminated structures, maintenance of structural integrity, and a site environmental and radiation monitoring program.

The SAFSTOR alternative assumes that an on-site ISFSI facility is constructed with adequate capacity to transfer all fuel to dry storage within 5 years and 2 months of plant shutdown. This allows the fuel handling buildings to be decontaminated and dismantled at an earlier date than would be otherwise possible. All fuel is assumed to be transferred to a DOE facility by the year 2040.

Equipment maintenance, inspection activities and routine service are performed by resident maintenance personnel. This work force will maintain the structures in a safe condition, provide adequate lighting, heating, and ventilation, and perform periodic preventive maintenance on essential site services.

An environmental surveillance program is carried out during the dormancy period to ensure that potential releases of radioactive material to the environment are detected and controlled. Appropriate emergency procedures are established and initiated for potential releases that exceed prescribed limits. The environmental surveillance program constitutes an abbreviated version of the program in effect during normal plant operations.

Security during the dormancy period is conducted primarily to prevent unauthorized entry and to protect the public from the consequences of their own actions. Security will be provided by the security fence, sensors, alarms, surveillance equipment, etc., which must be maintained

in good condition for the duration of this period. Fire and radiation alarms are also to be monitored and maintained. While remote surveillance is an option, it does not offer the immediate response time of a physical presence.

Variations in the length of the dormancy period are expected to have little effect upon the quantities of radioactive wastes generated from system and structure removal operations. While there will be a decrease in the contamination levels present on all surfaces due to radioactive decay over an increased dormancy duration, it is not expected that any material that is non-releasable at the time of shutdown will decay to a releasable state over the permissible time frame (i.e. 60 years maximum). Without detailed contamination characterization information, it is not possible to make any further assumptions concerning contamination levels.

Given the levels of radioactivity and spectrum of radionuclides expected from forty years of plant operation, no plant process system identified as being contaminated upon final shutdown will become releasable due to the decay period alone, i.e., there is no significant reduction in waste volume in delaying decommissioning. In fact, SAFSTOR estimates can show a slight increase in the total projected waste volume, due primarily to initial preparation activities for placing the units in safe-storage, as well as from follow-up housekeeping tasks over the caretaking period for the station. Since the SAFSTOR option does not require system flushes for decontamination purposes, the waste volumes associated with the liquid waste processing have been eliminated. In this case, the cost estimate showed a small increase in the total low-level waste volume in the SAFSTOR mode relative to DECON.

The delay in decommissioning yields lower working area radiation levels. As such, the difference between the prompt and delayed scenarios is moderated by reduced ALARA controls for the SAFSTOR's lower occupational exposure potential. Because this alternative provides a period of decay for the residual radioactive material, lower radiation fields are encountered than with the DECON alternative. Some of the dismantling activities may employ manual techniques rather than remote procedures. Thus, dismantling operations may be simplified for some tasks. However, this study does not attempt to quantify this effect, because it would have an immaterial impact on overall costs.

2.2.3 Periods 3 and 4 - Deferred Decommissioning

A termination plan must be prepared at least two years prior to the anticipated date of license termination. Submitted as a supplement to the FSAR, or equivalent, the plan must include a site characterization, description of the remaining dismantling activities, plans for site remediation, detailed plans for the final radiation survey, designation of the end-use of the site, an updated cost estimate to complete the decommissioning, and any associated environmental concerns. The NRC will publish notice of a receipt of the plan and make the plan available for public comment. A local hearing will also be scheduled. Plan approval will be subject to any conditions and limitations deemed appropriate by the NRC. The licensee may then commence with the final remediation of site facilities and plant services.

Although the initial radiation levels due to ^{60}Co will decrease significantly during the dormancy period, the internal components of the reactor vessel will still exhibit sufficiently high radiation dose rates to require remote sectioning under water due to the presence of long-lived radionuclides such as ^{94}Nb , ^{59}Ni and ^{63}Ni . Therefore, the dismantling procedures described for the DECON alternative would still be employed during SAFSTOR. Portions of the biological shield will still be radioactive due to the presence of activated trace elements with long half-lives (^{152}Eu and ^{154}Eu). Decontamination will require controlled removal and disposal. It is assumed that radioactive corrosion products on inner surfaces of piping and components will not have decayed to levels that will permit unrestricted use or allow conventional removal. These systems and components are surveyed as they are removed and disposed of in accordance with the existing radioactive release criteria.

Prior to the commencement of decommissioning operations, preparations are undertaken to reactivate site services and prepare for decommissioning. Preparations include engineering and planning, a detailed site characterization, as well as the assembly of a decommissioning management organization. Final planning for activities and writing of activity specifications and detailed procedures are also initiated at this time.

Much of the work in developing a termination plan is relevant to the development of the detailed engineering plans and procedures. The activities associated with this phase, as well as the follow-on decontamination and dismantling processes are detailed in Sections 2.1.1 and 2.1.2. The primary difference between the sequences

anticipated for the DECON and SAFSTOR scenarios is the absence, in the latter, of any constraint on the availability of the fuel handling facilities for decommissioning (except from the Unit 1 Intergrated Scenario). The timing for the SAFSTOR scenario is such that the spent fuel inventory has been removed from the site prior to the initiation of decontamination and dismantling activities, eliminating a significant scheduling hindrance. Any GTCC material generated in the segmentation of the reactor vessel internals is assumed to be directly routed to the DOE's geological facility without the need to provide for interim storage on site.

Incorporated into the License Termination Plan, the Final Survey Plan details the radiological surveys to be performed once the decontamination activities are completed. The Final Survey Plan is developed using the guidance provided in NUREG/CR-5849, "Manual for Conducting Radiological Surveys in Support of License Termination." This document delineates the statistical approaches to survey design and data interpretation used by the EPA. It also identifies state-of-the-art, commercially available, instrumentation and procedures for conducting radiological surveys. Use of this guidance ensures that survey design and implementation are conducted in a manner that provides a high degree of confidence that applicable NRC criteria are satisfied. Once the survey is complete, the results are provided to the NRC in a format that can be verified. The NRC then reviews and evaluates the information, performs an independent confirmation of radiological site conditions, and makes a determination on final termination of the license. The NRC will terminate the license if it determines that site remediation has been performed in accordance with the license termination plan, and the terminal radiation survey and associated documentation demonstrate that the facility is suitable for release.

2.2.4 Period 5 - Site Restoration

For the SAFSTOR alternative, the site restoration activities are the same as those for DECON Period 3, without restriction on the availability of the ISFSI for spent fuel or GTCC waste.

3. COST ESTIMATE

The site-specific cost estimate prepared for decommissioning St. Lucie accounts for the unique features of the site, including the primary coolant systems, electric power generation systems, site buildings, and structures. The basis of the estimate and its sources of information, methodology, site-specific considerations, assumptions, and total costs are described in this section.

3.1 BASIS OF ESTIMATE

A site-specific cost estimate was developed using the St. Lucie drawings and plant documents provided by FP&L. Components were inventoried from the mechanical and electrical Piping & Instrument Diagrams (P&ID). Structural drawings and design documents were used to analyze the general arrangement of the facility and to determine estimates of building concrete volumes, steel quantities, numbers and sizes of major components, and areas of the plant to be addressed in remediation of the site.

Representative labor rates for each designated craft and salaried worker were provided by FP&L for use in construction of the unit removal factors, as well as for estimating the carrying costs for site management, worker supervision, and essential support services, e.g., health physics and security.

For estimating purposes, all LLW generated in the decontamination and dismantling of St. Lucie, with the exception of certain metallic waste, is assumed destined for disposal at the existing Barnwell facility. Certain metallic waste is assumed to be sent to an off-site licensed waste processing facility.

3.2 METHODOLOGY

The methodology used to develop this cost estimate follows the basic approach originally presented in the AIF/NESP-036 study report, "Guidelines for Producing Commercial Nuclear Power Plant Decommissioning Cost Estimates," (Ref. 7) and the US DOE "Decommissioning Handbook" (Ref. 8). These documents present a unit cost factor method for estimating decommissioning activity costs, which simplifies the estimating calculations. Unit cost factors for concrete removal (\$/cubic yard), steel removal (\$/ton), and cutting costs (\$/inch) were developed from the labor cost information provided by FP&L. The activity-dependent costs are estimated with the item quantities (cubic yards, tons, inches, etc.) developed from plant drawings and inventory documents.

The unit cost factors used in this study reflect the latest available information about worker productivity in decommissioning, including the Shippingport Station Decommissioning Project completed in 1989, as well as from TLG's involvement in the decommissioning planning and engineering for the Shoreham, Yankee Rowe, Trojan, Rancho Seco, Pathfinder, and Cintichem reactor facilities.

The unit cost factor method provides a demonstrable basis for establishing reliable cost estimates. The detail of activities provided in the unit cost factors for activity time, labor costs (by craft), and equipment and consumable costs provides assurance that cost elements have not been omitted. These detailed unit cost factors, coupled with the plant-specific inventory of piping, components and structures, provide a high degree of confidence in the reliability of the cost estimates.

An activity duration critical path was used to determine the total decommissioning program schedule. The program schedule is used to determine the period-dependent costs for program management, administration, field engineering, equipment rental, quality assurance, and security. The study used typical salary and hourly rates for personnel associated with period-dependent costs for the region in which the station is located. Some of the costs for removal of radioactive components/structures were based on information obtained from the "Building Construction Cost Data," published by R. S. Means (Ref. 9). Examples of unit cost factor development are presented in the AIF/NESP-036 study. Appendix A presents the detailed development of a typical site-specific unit cost factor. Appendix B provides the values contained within one set of factors developed for the St. Lucie analyses.

3.3 FINANCIAL COMPONENTS OF THE COST MODEL

TLG's proprietary decommissioning cost model, DECCER, is composed of a number of distinct cost line items, calculated using the unit cost factor methodology described earlier, as well as additional cost elements in support of the field activities. These calculated costs in and of themselves, however, do not comprise the total cost to accomplish the project goal, i.e., the license termination and site restoration of St. Lucie.

Inherent in any cost estimate that does not rely on historical data is the inability to specify the precise source of costs imposed by factors such as tool breakage, accidents, illnesses, weather delays, labor stoppages, etc. In the DECCER cost model, contingency fulfills this role. Contingency is added to each line item to account for costs that are difficult or impossible to develop

analytically. Such costs are historically inevitable over the duration of a job of this magnitude; therefore, this cost analysis includes moneys to cover these types of expenses. Further discussion of this subject is presented below.

In addition to the routine uncertainties that contingency addresses, another cost element that is necessary to consider when answering the question of decommissioning costs relates to other types and levels of uncertainties. These consist of changes in work scope, pricing, job performance, and other variations that could conceivably, but not necessarily, occur. Consideration of such items may be necessary to address the question concerning how costly the decommissioning project could become, within a range of probabilities. TLG considers these types of costs under the broad term "financial risk." This cost study, however, does not add any additional costs to the estimate for financial risk.

3.3.1 Contingency

The activity- and period-dependent costs are combined to develop the total decommissioning costs. A contingency is then applied on a line-item basis, using one or more of the contingency types listed in the AIF/NESP-036 study. "Contingencies" are defined in the American Association of Cost Engineers "Project and Cost Engineers' Handbook" (Ref. 10) as "specific provision for unforeseeable elements of cost within the defined project scope; particularly important where previous experience relating estimates and actual costs has shown that unforeseeable events which will increase costs are likely to occur." The cost elements in this estimate are based upon ideal conditions and maximum efficiency; therefore, consistent with industry practice, a contingency factor has been applied. In the AIF/NESP-036 study, the types of unforeseeable events that are likely to occur in decommissioning are discussed and guidelines are provided for percentage contingency in each category. It should be noted that contingency, as used in this estimate, does not account for price escalation and inflation in the cost of decommissioning over the remaining operating life of the units.

The use and role of contingency within decommissioning estimates is not a "safety factor issue." Safety factors provide additional security and address situations that may never occur. Contingency funds are expected to be fully expended throughout the program. They also provide assurance that sufficient funding is available to accomplish the intended tasks. Some of the rationale for (and need to incorporate) contingency within any estimate is offered in the following discussion. An estimate without contingency, or from which contingency has been

removed, can disrupt the orderly progression of events and jeopardize a successful conclusion to the decommissioning process.

The most technologically challenging task in decommissioning a commercial nuclear station will be the disposition of the reactor vessel and internal components, which have become highly radioactive after a lifetime of exposure to radiation produced in the core. The disposition of these highly radioactive components forms the basis for the critical path (schedule) for decommissioning operations. Cost and schedule are interdependent and any deviation in schedule has a significant impact on cost for performing a specific activity.

Disposition of the reactor vessel internals involves the underwater cutting of complex components that are highly radioactive. Costs are based upon optimum segmentation, handling, and packaging scenarios. The schedule is primarily dependent upon the turnaround time for the heavily shielded shipping casks, including preparation, loading, and decontamination of the containers for transport. The number of casks required is a function of the pieces generated in the segmentation activity, a value calculated on optimum performance of the tooling employed in cutting the various subassemblies. The risk and uncertainties associated with this task are that the expected optimization may not be achieved, resulting in delays and additional program costs. For this reason, contingency must be included to mitigate the consequences of the expected inefficiencies inherent in this complex activity, along with related concerns associated with specialty tooling modifications and repairs, field changes, discontinuities in the coordination of plant services, system failure, water clarity, lighting, computer-controlled cutting software corrections, etc. Experience in decommissioning other plants in the past has shown that many of these problem areas have occurred during, and in support of, the segmentation process. Contingency dollars are an integral part of the total cost to complete this task. Exclusion of this component puts at risk a successful completion of the intended tasks and, potentially, subsequent related activities.

The following list is a composite of some of the activities, assembled from past decommissioning programs, in which contingency dollars were needed to respond to, compensate for, and/or provide adequate funding of decontamination and dismantling tasks:

Incomplete or Changed Conditions:

- Unavailable/incomplete operational history which led to a recontamination of a work area, because a sealed cubicle (incorrectly identified as being non-contaminated) was breached without controls.
- Surface coatings covering contamination which, due to an incomplete characterization, required additional cost and time to remediate.
- Additional decontamination, controlled removal, and disposition of previously undetected (although at some sites, suspected) contamination due to access gained to formerly inaccessible areas and components.
- Unrecorded construction modifications, facility upgrades, maintenance, enhancements, etc., which precipitated scheduling delays, more costly removal scenarios, additional costs (e.g., for re-engineering, shoring, structural modifications), and compromised worker safety.

Adverse Working Conditions:

- Lower than expected productivity due to high temperature environments, resulting in a change in the working hours (shifting to cooler periods of the day) and additional manpower.
- Confined space, low-oxygen environments where supplied air was necessary and additional safety precautions prolonged the time required to perform required tasks.

Maintenance, Repairs and Modifications

- Facility refurbishment required to support site operations, including those needed to provide new site services, as well as to maintain the integrity of existing structures.
- Damage control, repair, and maintenance from bird nestings and their fouling of equipment and controls.

- Building modification, i.e., re-supporting of floors to enhance loading capacity for heavily shielded casks.
- Roadway upgrades on site to handle heavier and wider loads; roadway rerouting, excavation, and reconstruction.
- Requests for additional safety margins by a vendor.
- Requests to analyze accident scenarios beyond those defined by the removal scenario (requested by the NRC to comply with "total scope of regulation").
- Additional collection of site runoff and processing of such due to disturbance of natural site contours and drainage.
- Concrete coring for removal of embedments and internal conduit, piping, and other potentially contaminated material not originally identified as being contaminated.
- Modifications required to respond to higher than expected worker exposure, water clarity, water disassociation, and hydrogen generation from high temperature cutting operations.
- Additional waste containers needed to accommodate cutting particulates (fines), inefficient waste geometries, and excess material.

Labor

- Turnover of personnel, e.g., craft and health physics. Replacement of labor is costly, involving additional training, badging, medical exams, and associated processing procedures. Recruitment costs are incurred for more experienced personnel and can include relocation and living expense compensation.
- Additional personnel required to comply with NRC mandates and requests.
- Replacement of personnel due to non-qualification and/or incomplete certification (e.g., welders).

Schedule

- Schedule slippage due to a conflict in required resources, i.e., the licensee was forced into a delay until prior (non-licensee) commitments of outside resources were resolved.
- Rejection of material by NRC inspectors, requiring refabrication and causing program delays in activities required to be completed prior to decommissioning operations.

Weather

- Weather-related delays in the construction of facilities required to support site operations (with compensation for delayed mobilization made to vendor).
- Frozen crane hydraulics prior to a major lift.

The cost model incorporates considerations for items such as those described above, generating contingency dollars (at varying percentages of total line-item cost) with every activity.

3.3.2 Financial Risk

Financial risk refers to the possibility and associated probabilities of certain events occurring that could increase or decrease costs for decommissioning.

Included within the category of financial risk are:

- Transition activities and costs: ancillary expenses associated with eliminating 50% to 80% of the site labor force shortly after the cessation of plant operations, added cost for worker separation packages throughout the decommissioning program, state- or company-mandated retraining, and retention incentives for key personnel.
- Delays in approval of the decommissioning plan due to intervention, public participation in local community meetings, legal challenges, state and local hearings, etc.

- Changes in the project work scope from the baseline estimate, involving the discovery of unexpected levels of contaminants, contamination in places not previously expected, contaminated soil previously undiscovered (either radioactive or hazardous material contamination), variations in plant inventory or configuration not indicated by the as-built drawings.
- Regulatory changes, e.g., affecting worker health and safety, site release criteria, waste transportation, and disposal.
- Policy decisions altering federal and state commitments, e.g., in the ability to accommodate certain waste forms for disposition, or in the timetable for such.
- Pricing changes for basic inputs, such as labor, energy, materials, and burial. Some of these inputs may vary slightly, e.g. -10% to +20%; burial could vary from -50% to +200% or more.

It has been TLG's experience that the results of a risk analysis, when compared with the base case estimate for decommissioning, indicate that the chances of the base decommissioning estimate's being too high is a low probability, and the chances that the estimate is too low is a much higher probability. This is mostly due to the pricing uncertainty for LLW burial, and to a lesser extent due to schedule increases from changes in plant conditions and to pricing variations in the cost of labor (both craft and staff). TLG did not perform a risk analysis for the St. Lucie study and therefore the estimates in this report do not include any increase as a result of any risk analysis performed for FP&L or any other TLG client.

3.4 SITE-SPECIFIC CONSIDERATIONS

There are a number of site-specific considerations that affect the method for dismantling and removal of equipment from the site and the degree of restoration required. The cost impact of the considerations identified below is included in this cost study.

3.4.1 Spent Fuel Disposition

The spent fuel assemblies stored in the spent fuel pool and in dry storage at the site will be transferred to the DOE as per the existing contract between FP&L and the DOE.

Both the DECON and SAFSTOR alternatives assume that the DOE begins accepting spent fuel in 2010 at the rates assumed in the "Analysis of the Total System Life Cycle Cost of the Civilian Radioactive Waste Management Program" (DOE/RW-0479) issued in September 1995 (TSLCC). As a result of this acceptance schedule, FP&L will incur ISFSI-related construction, canister/module acquisition and decommissioning costs.

FP&L is assumed to develop an ISFSI at St. Lucie to prevent a loss of full core off-load reserve capacity in 2005 for Unit 1 and 2007 for Unit 2. The ISFSI will be sized to accommodate 90 storage modules and will be in operation from 2005 through 2040. Twenty-four modules (27%) are necessary to permit the plant to operate to the end of the operating licenses of each unit. The remaining capacity (73%) is necessary to facilitate timely decommissioning of the plant. As such, only 73% of the total capital/construction costs have been included in the cost estimates. Likewise, only the canister/module acquisition costs necessary to accommodate the transfer of fuel subsequent to plant shut down have been included. The cost estimates do not include the costs associated with construction and canister/module acquisition which is required to reach end of license.

3.4.2 Reactor Vessel and Internal Components

The reactor pressure vessel and reactor internal components are segmented for disposal in shielded transportation casks. Segmentation and packaging of the internals' packages are performed in the refueling canal where a turntable and remote cutter will be installed. The vessel is segmented in place, using a mast-mounted cutter supported off the lower head and directed from a shielded work platform installed overhead in the reactor cavity. Transportation cask specifications and Department of Transportation (DOT) regulations dictate segmentation and packaging methodology. All packages must meet the current physical and radiological limitations and regulations. Cask shipments will be made in DOT-approved, currently available, truck casks.

The dismantling of reactor internals at St. Lucie will generate radioactive waste generally unsuitable for shallow land disposal (GTCC). Although the material is not classified as high-level waste, the DOE has indicated it will accept title to this waste for disposal at the future high-level waste repository. However, the DOE has not yet established an acceptance criteria or a disposition schedule for this material, and numerous questions remain as to the ultimate disposal cost and waste form requirements. As such, for purposes of this study, the GTCC waste has been packaged and disposed of as high-level waste, at a cost equivalent to that envisioned for the spent fuel.

The reactor coolant pumps and motors are lifted out intact, packaged, and transported for disposal. Reactor coolant piping is cut from the reactor vessel once the water level in the vessel (used for personnel shielding during dismantling and cutting operations in and around the vessel) is dropped below the nozzle zone. The piping is boxed and shipped by shielded van.

3.4.3 Steam Generators and Other Large System Components

The following discussion deals with the steam generators, but the techniques involved are also applicable to other large components, such as feedwater heaters.

The steam generators' size and weight, as well as their configuration and limited access in the Reactor Building itself, place constraints on the intact removal of these components. Determination of the removal strategy requires several different considerations, including modifications to the Reactor Building, for removal of the generators, rigging needed to maneuver and extract the generators from the structure, and the component preparations needed to transport the generators to a disposal site.

A potential method for removal (and the one used as the basis in this estimate) is the extraction of the generators through an opening located in the side of the Reactor Building. Removal of sections of the steam generator cubicle walls, adjoining floor slabs, and floor grating will be accomplished to allow for the generators to be maneuvered to the opening.

A trolley crane will be set up for removal of the generators. By setting the trolley crane first, it can be used to lower portions of the steam generator cubicle walls and floor slab that will have to be removed as

part of the modification effort. Figure 3.1 shows removal of cubicle walls for removal of a primary coolant system component. Figure 3.2 shows the rigging process used for removal of steam generators from the reactor building.

The generators will be rigged for removal, disconnected from the surrounding piping and supports, and maneuvered into the open area where they will be lowered onto a dolly. The dolly will allow the lower end of the steam generator to rotate through the opening as it is being lowered. Nozzles and other openings will be welded closed (see Figure 3.3). When this stage has been completed, the generator will be lifted onto a multi-wheeled transporter (see Figure 3.4) and moved to an on-site steam generator processing area. The remaining steam generators will be removed using the same technique.

Once at the steam generator processing area, final preparations for shipment will be completed. The following is a list of these significant "package preparation activities:

- Install radiation shielding [of sufficient thickness to meet DOT transportation requirements] around the exterior of the primary side.
- Inject low-density cellular concrete into the primary side and secondary side voids to "fix" loose surface contamination.
- Place and secure the "primary side" package onto a transportation cradle, compatible with a public highway transporter and an ocean-going barge.

Each generator will then be loaded onto a multi-wheeled transporter and driven onto an exclusive-use barge located near the site. Figure 3.4 shows the typical overland transport used to move a steam generator on public highways. The generator-transporter package will be secured to the barge for transport to a pier-facility located near the Barnwell burial facility. Figure 3.5 shows a typical steam generator loaded on a barge. The package will be taken off the barge and proceed the short distance by road transport to the burial facility. The generator will remain on the transporter until it is unloaded at the disposal site.

3.4.4 Transportation Methods

For the purposes of the cost estimate, it was assumed that the LLW produced in the decontamination and dismantling of the nuclear units will be moved overland by truck, shielded van, railcar, and/or multi-wheeled transporter to the burial facility. Transport costs were derived assuming Barnwell, SC as the destination for all St. Lucie wastes destined for direct burial from the site. For wastes shipped to an off-site recovery vendor, these transport costs were derived assuming Oak Ridge, TN as the destination for St. Lucie wastes.

3.4.5 Low-Level Radioactive Waste Disposal

All LLW generated in the decontamination and dismantling of St. Lucie is assumed disposed of by:

- direct burial at the existing Barnwell facility at a representative burial charge of \$4.40 per pound.
- off-site processing for metallic wastes by a recovery vendor at a rate of \$1.15 per pound.

To the greatest extent practical, non-compactable LLW is treated to reduce the total volume of radioactive material requiring controlled disposal. The treated material meeting the regulatory and/or site release criteria is released as clean scrap, requiring no further cost consideration.

3.4.6 Site Conditions Following Decommissioning

Following the decommissioning effort, the structures and remaining systems will meet the specified NRC site release limit. The NRC involvement in the decommissioning process typically will end at this point. Local building codes, state environmental regulations, and FP&L's own future plans for the site will dictate the next step in the decommissioning process. TLG assumed the total removal of all plant systems and all of the above-grade structures from the site. These non-radiological costs are a part of this study.

3.4.4 Transportation Methods

For the purposes of the cost estimate, it was assumed that the LLW produced in the decontamination and dismantling of the nuclear units will be moved overland by truck, shielded van, railcar, and/or multi-wheeled transporter to the burial facility. Transport costs were derived assuming Barnwell, SC as the destination for all St. Lucie wastes destined for direct burial from the site. For wastes shipped to an off-site recovery vendor, these transport costs were derived assuming Oak Ridge, TN as the destination for St. Lucie wastes.

3.4.5 Low-Level Radioactive Waste Disposal

All LLW generated in the decontamination and dismantling of St. Lucie is assumed disposed of by:

- direct burial at the existing Barnwell facility at a representative burial charge of \$4.40 per pound.
- off-site processing for metallic wastes by a recovery vendor at a rate of \$1.15 per pound.

To the greatest extent practical, non-compactable LLW is treated to reduce the total volume of radioactive material requiring controlled disposal. The treated material meeting the regulatory and/or site release criteria is released as clean scrap, requiring no further cost consideration.

3.4.6 Site Conditions Following Decommissioning

Following the decommissioning effort, the structures and remaining systems will meet the specified NRC site release limit. The NRC involvement in the decommissioning process typically will end at this point. Local building codes, state environmental regulations, and FP&L's own future plans for the site will dictate the next step in the decommissioning process. TLG assumed the total removal of all plant systems and all of the above-grade structures from the site. These non-radiological costs are a part of this study.

3.5 ASSUMPTIONS

The following are the major assumptions made in the development of the cost estimates for decommissioning St. Lucie.

1. Costs are calculated in 1998 dollars. A present-value economic analysis is not included, nor is escalation or general inflation reflected within the costs reported.
2. Common systems are assumed to be assigned to the unit as shown on the plant drawings (P&ID's). Common structures are assumed to be assigned exclusively to Unit 2. ISFSI-related decontamination and demolition costs are assumed to be equally divided between Unit 1 and Unit 2.
3. Plant drawings, equipment and structural specifications, including construction details, were provided by FP&L.
4. Employee salary and craft labor rates for site administration, operations, construction, and maintenance personnel were provided by FP&L for positions identified by TLG.
5. FP&L provides for any necessary electrical power required to decommission the plant to be brought on site. Energy costs are included in the estimate.
6. Material and heavy equipment rental and operating costs were taken from R.S. Means Building Construction Cost Data.
7. Radioactive contamination is considered to be within selected secondary steam cycle components in Units 1 and 2. FP&L provided the status of contamination by plant process system; TLG used this information to categorize the inventory for removal and disposition.
8. FP&L has identified site areas which contain concentrations of radionuclides which exceed NRC release limits. The volume of contaminated soil/sediment requiring disposal is estimated at 14,688 cubic feet.
9. Radioactively contaminated piping, components, and structures other than the reactor vessel and internals are assumed to meet DOT limits for Low Specific Activity (LSA) or Surface Contaminated Object (SCO) material. For transportation calculations, the trucking distance from the plant site to the Barnwell site is 477 miles and 801 miles to a recycle facility. Rates for shipping radioactive wastes were provided by Tri-State Motor Transit in published tariffs for this cargo (Ref. 11).

10. The reactor vessel and internals' disposal costs were based on remote in-place segmentation, packaging in shielded casks, and shipping by truck to the burial ground. A maximum normal road weight limit of 80,000 pounds is assumed for all truck shipments, with the exception of several overweight cask shipments. Cask shipments may exceed 95,000 pounds, including vessel segment(s), supplementary shielding, cask tie-downs and tractor trailer. The maximum curies per shipment assumed permissible is based upon the license limits of available shielded shipping casks. The number and curie content of vessel segments were selected to meet these limits.
11. The average number of cask shipments out of the Reactor Building is expected to average three every two weeks.
12. Reactor vessel and internals packages' conditions:
Any fuel cladding failure that has occurred or may occur during the lifetime of the plant is assumed:
 - to have released fission products at sufficiently low levels that the buildup of quantities of long-lived isotopes (e.g. cesium-137, strontium-90, or transuranics) has been prevented from reaching levels exceeding those which permit the major primary coolant system components to be shipped as LSA or SCO waste and to be buried within the requirements of 10 CFR 61 or the regional burial ground; or
 - to have necessitated systematic decontamination during the operating life of the plant; therefore, the radionuclide levels will be acceptable for transport as LSA or SCO waste and burial within the requirements of 10 CFR 61.
13. The estimated curie content of the vessel and internals at final shutdown was derived from those listed in NUREG/CR-3474 (Ref. 12). Actual estimates will be derived from the Ci/gram values in NUREG/CR-3474 and adjusted for the different mass of components and projected operating life, as well as for different periods of decay. Additional short-lived isotopes were derived from NUREG/CR-0130 (Ref. 13) and NUREG/CR-0672 (Ref. 14), and benchmarked to the long-lived values from NUREG/CR-3474.
14. This study estimates that there will be some radioactive waste generated which is greater than 10 CFR 61 Class C quantities (GTCC), resulting from disposal of the highly activated sections of the reactor vessel internals. This waste will most likely be disposed of as high-level waste in the DOE's deep geological repository unless an alternative solution is approved by the NRC. The cost of disposal, unlike that for the spent fuel,

is not addressed by the DOE's 1 mill/kWhr surcharge, and has been estimated from equivalent disposal costs for spent nuclear fuel.

15. Reactivity control elements will be removed and disposed of along with the spent fuel assemblies.
16. GTCC waste generated through segmentation of the reactor vessel internals will be transferred to the on-site ISFSI or to the DOE high-level waste repository. If the DOE were to default on its obligations to accept spent fuel and GTCC material, decommissioning costs would almost certainly increase.
17. This study does not address the cost for the removal and disposal of spent fuel from the site. Ultimate disposition of the spent fuel is the province of the DOE's Waste Management System, as defined by the Nuclear Waste Policy Act and funded through the 1 mill/kWhr electrical generation surcharge. If the DOE were to delay its obligations to accept spent fuel later than a time consistent with the DOE initial pickup of spent fuel from St. Lucie, then decommissioning costs would increase.
18. Scrap generated during decommissioning is not included as a salvage credit line item in this study. It is difficult to estimate the potential salvage value of a decommissioned nuclear power plant for the following reasons:
 - The acceptability of nuclear plant equipment to potential salvage equipment buyers is highly speculative, regardless of the ability to free release this material.
 - Much of the equipment at a nuclear plant, especially from older units, is too specific to that plant to be of use to potential salvage buyers.
 - The cost for removal of equipment to a configuration that is attractive to a salvage dealer is variable. Dismantling techniques assumed for equipment by TLG for this estimate are not consistent with removal techniques required for salvage (resale) of equipment. Yankee Rowe experience indicated that some buyers wanted equipment stripped down to very specific requirements before they would consider purchase. This required expensive rework after the equipment had been removed from its installed location.

For these reasons, it has generally been considered that the salvage value inherent in free-releasable nuclear plant equipment is sufficient to pay for the cost of removal of this equipment from the site, (i.e., clean equipment that has been removed from its installed location and placed in a laydown area is considered to be removed from the site at no

additional charge by salvage dealers). This assumption is an implicit recognition of scrap value in the disposal of clean metallic waste at no cost to the project.

19. The FP&L staffing requirements during decommissioning vary with the level of effort associated with the various phases of the project. Once the decommissioning program commences, only those staff positions necessary to support the decommissioning program are included. There are no costs included in this study for staff transition from plant operations to decommissioning.
20. FP&L will hire a Decommissioning Operations Contractor (DOC), providing contract management of the decommissioning labor force and subcontractors. Engineering services for such items as writing activity specifications, detailed procedures, detailed activation analyses, and structural modifications, etc. are assumed to be provided by the DOC.
21. FP&L will remove items such as furniture, tools, forklifts, trucks, bulldozers, other similar mobile equipment and other such items of company property that can be removed without the use of special equipment.
22. FP&L is assumed to purchase or rent 20% of the scaffolding required to support the decommissioning project. The majority of required scaffolding (80%) is available on site.
23. Existing warehouses will remain for use by FP&L and its subcontractors and will be dismantled as they are no longer needed to support the decommissioning program.
24. FP&L will perform the following activities at no cost or credit to the project:
 - Fuel oil tanks will be emptied. Tanks will be cleaned by flushing or steam cleaning as required prior to disposal.
 - Acid and caustic tanks will be emptied through normal usage; any excess acid or caustics removed to support disposal of the storage container(s) are returned to the vendor.
 - Lubricating and transformer oils will be drained and removed from site by a waste disposal vendor.
25. The decommissioning activities will be performed in accordance with current regulations, which are assumed to still be in place at the time of decommissioning. Changes in current regulations may have a cost impact on decommissioning.

26. This study follows the principles of ALARA through the use of work duration adjustment factors which incorporate such items as radiological protection instruction, mock-up training, the use of respiratory protection, and personnel protective clothing. These items lengthen a task's duration, which increases the costs and lengthens the schedule. ALARA planning is considered in the costs for engineering and planning, and in the development of activity specifications and detailed procedures. Changes to §20 worker exposure limits may impact the decommissioning cost and project schedule.
27. Nuclear liability insurance provides coverage for damage or injuries due to radiation exposure from equipment, material, etc. used during decommissioning. Nuclear liability insurance is phased out upon final decontamination of the site. FP&L provided current nuclear liability and property insurance premiums which were factored to reflect lower coverage limits and return of premiums during decommissioning activities.
28. Nuclear property insurance currently carried by FP&L for the site will continue throughout the decommissioning period at a rate discounted from that in effect during operations. The nuclear property insurance will cease for the station upon termination of the §72 license.
29. Only existing site structures will be considered in the decommissioning cost.
30. The perimeter fence and in-plant security barriers will be moved as appropriate to conform with the site's Security Plan in force at the various stages in the project.
31. The existing electrical switchyard will remain after decommissioning in support of the utility's electrical transmission and distribution system.
32. Underground metal and concrete piping will either be surveyed in place and released, or excavated and removed for survey. Any piping that exceeds the site release criteria will be removed.
33. Shallow portions of the concrete circulating water closed-loop piping will be exposed and the roof of the piping will be collapsed and backfilled in place, while deep portions of the piping will be capped and abandoned in place.
34. All railroad tracks on the site will be removed.
35. Water drain holes will be drilled in the bottom of all subgrade structures to be abandoned.
36. Non-contaminated road and parking areas with asphalt or concrete surfacing will be broken up into rubble and used for backfill.

37. Structures and site improvements will be removed to a depth of three feet below local grade wherever possible and backfilled to the local grade level. At-grade foundation slabs greater than three feet thick will be abandoned in place and covered over with a three-foot thick layer of backfill.
38. Property tax costs were supplied by FP&L. Property taxes were assumed to be a constant annual cost as long as the FP&L building or equipment were located on the property.
39. Intake and Discharge canals are back-filled to grade using existing on-site soil and rubble.
40. The ocean discharge header has fourteen steel diffusers attached at seabed elevation. The diffusers will be removed by underwater exothermic torch and the openings secured with a welded-in-place plug.
41. Costs for Steam Generator removal, packaging, shipping and disposal were based on "actual" costs incurred in performing the St. Lucie Unit 1 steam generator replacement project.

3.6 DECOMMISSIONING VERSUS SITE RESTORATION

Approximately 90% of the total cost for the DECON and SAFSTOR cases that were evaluated is attributable to the planning, engineering and the actual disposition of the residual radioactivity at the facility. It should be noted, however, that this accounting of costs includes not only those costs directly attributable to "decommissioning" as defined by the NRC, but those clean "cascading" costs necessary to be expended in order to execute the decontamination processes.

Nuclear power plants are designed to contain the radioactivity inherent in the normal operation of the facility. Accordingly, radioactive and potentially radioactive systems are located in shielded labyrinths, tunnels, and pipe chases. This inaccessibility, while essential during operation, serves to impede decommissioning activities. Consequently, disposition of these components often requires that additional access (and working space) be developed. This access is achieved by dismantling structures and components along the intended path of egress and in the immediate working area; material which in some cases is non-radioactive and therefore not normally perceived as a necessary constituent in facility decontamination. Failure to establish adequate working room will increase the residence times for decontamination and dismantling activities resulting in increases in the incurred occupational exposure. Therefore, the clean "cascading" costs necessary to perform decontamination activities are reported as decommissioning costs.

3.7 COST ESTIMATE SUMMARY

Summaries of the decommissioning costs and annual expenditures are provided in Tables 3.1 through 3.2. Appendix D provides a summary of decommissioning costs similar to Appendix C, with the assumption that long-term spent fuel storage is not required (the DOE acceptance dates and rates permitted unhindered plant decommissioning). These costs were extracted from the detailed cost tables in Appendix C and D. The following should be considered when reviewing these tables:

- “Decon” as used in the headings of these tables, refers to decontamination activities, as opposed to the NRC term DECON, which refers to the prompt removal decommissioning scenario.
- “Total” as used in the headings of these tables, is the sum of Decon, Remove, Pack, Ship, Bury, and Contingency, as well as other miscellaneous items not listed (such as engineering and preparations).
- The subtotal reported for the major cost categories does not include contingency, which is reported in a separate column.
- “Other” includes different types of costs which are not easily categorized. For instance, in systems removal and structures decontamination, the “Other” cost consists of the off-site recycling costs for low-level radioactive waste. In most of the engineering preparatory activities the “Other” cost is strictly engineering labor; however, “Other” also includes taxes, insurance, plant energy budgets, and regulatory fees.
- Decontamination and removal costs associated with common plant systems are assigned to either Unit 1 or Unit 2, in accordance with the component designation shown on plant drawings. Costs associated with common plant buildings were assigned to Unit 2, since these buildings will be required to support Unit 2 operations after the shutdown of Unit 1. Table 3.3 specifically identifies the unit to which common costs have been allocated.

FIGURE 3.1

Reactor Building Modification for Pressurizer Removal




FIGURE 3.2
Removal of Steam Generator from Reactor Building






FIGURE 3.3
Preparation of Steam Generator for Transport



**FIGURE 3.4
Overland Transport of Steam Generator**



**FIGURE 3.5
Loading of Steam Generator onto Barge**



TABLE 3.1a

**SCHEDULE OF ANNUAL EXPENDITURES
DECON UNIT 1
(WITH ON-SITE DRY FUEL STORAGE)
(1998 Dollars) ¹**

Year	Labor	Equipment & Materials	Shipping	Burial	Other	Yearly Totals
2000	293,825	293,825	0	0	0	587,650
2001	293,825	293,825	0	0	0	587,650
2002	734,563	734,563	0	0	0	1,469,125
2003	1,101,844	1,101,844	0	0	0	2,203,688
2004	1,248,756	1,248,756	0	0	0	2,497,513
2005-2015	0	0	0	0	0	0
2016	23,753,284	6,720,619	534,551	11,715,126	2,048,370	44,771,950
2017	11,122,263	2,153,104	104,100	2,308,740	1,168,741	16,856,949
2018	8,090,110	1,331,037	191	36,798	920,502	10,378,637
2019	7,802,610	1,043,537	191	36,798	920,502	9,803,637
2020	9,834,124	3,056,533	192	36,899	923,023	13,850,771
2021	10,726,213	922,016	2,037	427,157	1,313,868	13,391,291
2022	29,944,215	2,819,645	6,766	1,426,858	2,321,270	36,518,753
2023	27,789,205	4,554,729	353,746	6,253,875	1,427,780	40,379,334
2024	25,924,852	5,051,680	451,600	7,618,817	1,173,185	40,220,134
2025	17,179,035	5,037,878	450,366	7,598,000	1,088,736	31,354,015
2026	6,142,099	5,037,878	450,366	7,598,000	1,088,736	20,317,079
2027	5,453,325	5,037,878	450,366	7,598,000	1,088,736	19,628,305
2028	5,468,266	5,051,680	451,600	7,618,817	1,091,719	19,682,081
2029	5,453,325	5,037,878	450,366	7,598,000	1,088,736	19,628,305
2030	13,020,736	5,037,878	450,366	7,598,000	1,088,736	27,195,716
2031	9,034,648	5,988,603	51,132	862,639	732,391	16,669,413
2032	3,075,107	1,919,559	0	0	667,653	5,662,320
2033	884,668	55,179	0	0	656,559	1,596,407
2034	884,668	55,179	0	0	656,559	1,596,407
2035	884,668	55,179	0	0	656,559	1,596,407
2036	887,092	55,331	0	0	658,358	1,600,780
2037	884,668	55,179	0	0	656,559	1,596,407
2038	884,668	55,179	0	0	656,559	1,596,407
2039	884,668	55,179	0	0	656,559	1,596,407
2040	1,157,141	863,105	15,917	21,588,344	459,177	24,083,684
	230,838,470	70,724,459	4,223,851	97,920,869	25,209,572	428,917,221

Note 1: Columns may not add due to rounding

TABLE 3.1b
SCHEDULE OF ANNUAL EXPENDITURES
DECON UNIT 2
(WITH ON-SITE DRY FUEL STORAGE)
(1998 Dollars) ¹

Year	Labor	Equipment & Materials	Shipping	Burial	Other	Yearly Totals
2000	545,675	545,675	0	0	0	1,091,350
2001	545,675	545,675	0	0	0	1,091,350
2002	1,364,188	1,364,188	0	0	0	2,728,375
2003	2,046,281	2,046,281	0	0	0	4,092,563
2004	2,319,119	2,319,119	0	0	0	4,638,238
2005-2022	0	0	0	0	0	0
2023	19,612,444	5,229,975	176,895	3,358,092	2,065,385	30,442,792
2024	30,300,792	6,940,862	318,715	5,750,808	2,459,117	45,770,293
2025	31,728,949	9,308,032	564,642	9,483,545	1,387,247	52,472,416
2026	30,440,091	9,020,532	564,642	9,483,545	1,387,247	50,896,058
2027	29,781,001	9,595,532	564,642	9,483,545	1,387,247	50,811,968
2028	26,979,716	6,738,944	566,189	9,509,528	1,391,048	45,185,425
2029	26,906,001	6,720,532	564,642	9,483,545	1,651,928	45,326,649
2030	26,906,001	6,720,532	564,642	9,483,545	1,442,564	45,117,285
2031	16,400,415	9,770,861	64,070	1,076,101	757,337	28,068,785
2032	5,249,989	3,192,149	0	0	668,177	9,110,315
2033	884,668	91,766	0	0	656,643	1,633,077
2034	884,668	91,766	0	0	656,643	1,633,077
2035	884,668	91,766	0	0	656,643	1,633,077
2036	887,092	92,017	0	0	658,442	1,637,551
2037	884,668	91,766	0	0	656,643	1,633,077
2038	884,668	91,766	0	0	656,643	1,633,077
2039	884,668	91,766	0	0	656,643	1,633,077
2040	1,367,724	1,435,385	15,917	21,588,344	463,955	24,871,326
	258,689,160	82,136,889	3,964,998	88,700,599	19,659,552	453,151,198

Note 1: Columns may not add due to rounding

TABLE 3.2a
SCHEDULE OF ANNUAL EXPENDITURES
SAFSTOR, UNIT 1
(WITH ON-SITE DRY FUEL STORAGE)
(1998 Dollars) ¹

Year	Period 1 SAFSTOR Ops	Period 2 Dormancy	Period 3 D&D Prep	Period 4 Decontamination	Period 5 Site Restoration	ISFSI Eng. & Capital costs	Yearly Totals
2000	0	0	0	0	0	587,650	587,650
2001	0	0	0	0	0	587,650	587,650
2002	0	0	0	0	0	1,469,125	1,469,125
2003	0	0	0	0	0	2,203,688	2,203,688
2004	0	0	0	0	0	2,497,513	2,497,513
2005-2015	0	0	0	0	0	0	0
2016	24,189,070	0	0	0	0	1,725,000	25,914,070
2017	19,129,918	2,461,676	0	0	0	1,725,000	23,316,593
2018	0	7,304,972	0	0	0	2,300,000	9,604,972
2019	0	7,304,972	0	0	0	1,725,000	9,029,972
2020	0	7,324,986	0	0	0	5,750,000	13,074,986
2021	0	4,958,144	0	0	0	0	4,958,144
2022	0	3,808,677	0	0	0	0	3,808,677
2023	0	3,808,677	0	0	0	0	3,808,677
2024	0	3,819,112	0	0	0	0	3,819,112
2025	0	3,808,677	0	0	0	0	3,808,677
2026	0	3,808,677	0	0	0	0	3,808,677
2027	0	3,808,677	0	0	0	0	3,808,677
2028	0	3,819,112	0	0	0	0	3,819,112
2029	0	3,808,677	0	0	0	0	3,808,677
2030	0	3,808,677	0	0	0	0	3,808,677
2031	0	3,808,677	0	0	0	0	3,808,677
2032	0	3,819,112	0	0	0	0	3,819,112
2033	0	3,808,677	0	0	0	0	3,808,677
2034	0	3,808,677	0	0	0	0	3,808,677
2035	0	3,808,677	0	0	0	0	3,808,677
2036	0	3,819,112	0	0	0	0	3,819,112
2037	0	3,808,677	0	0	0	0	3,808,677
2038	0	3,808,677	0	0	0	0	3,808,677
2039	0	3,808,677	0	0	0	0	3,808,677
2040	0	2,623,099	0	0	0	0	2,623,099

TABLE 3.2a
SCHEDULE OF ANNUAL EXPENDITURES
SAFSTOR, UNIT 1
(WITH ON-SITE DRY FUEL STORAGE)
(1998 Dollars)
(cont'd)

Year	Period 1 SAFSTOR Ops	Period 2 Dormancy	Period 3 D&D Prep	Period 4 Decontamination	Period 5 Site Restoration	ISFSI Eng. & Capital costs	Yearly Totals
2041	0	2,509,437	0	0	0	0	2,509,437
2042	0	2,509,437	0	0	0	0	2,509,437
2043	0	2,509,437	0	0	0	0	2,509,437
2044	0	2,516,312	0	0	0	0	2,516,312
2045	0	2,509,437	0	0	0	0	2,509,437
2046	0	2,509,437	0	0	0	0	2,509,437
2047	0	2,509,437	0	0	0	0	2,509,437
2048	0	2,516,312	0	0	0	0	2,516,312
2049	0	2,509,437	0	0	0	0	2,509,437
2050	0	2,509,437	0	0	0	0	2,509,437
2051	0	2,509,437	0	0	0	0	2,509,437
2052	0	2,516,312	0	0	0	0	2,516,312
2053	0	2,509,437	0	0	0	0	2,509,437
2054	0	2,509,437	0	0	0	0	2,509,437
2055	0	2,509,437	0	0	0	0	2,509,437
2056	0	2,516,312	0	0	0	0	2,516,312
2057	0	2,509,437	0	0	0	0	2,509,437
2058	0	2,509,437	0	0	0	0	2,509,437
2059	0	2,509,437	0	0	0	0	2,509,437
2060	0	2,516,312	0	0	0	0	2,516,312
2061	0	2,509,437	0	0	0	0	2,509,437
2062	0	2,509,437	0	0	0	0	2,509,437
2063	0	2,509,437	0	0	0	0	2,509,437
2064	0	2,516,312	0	0	0	0	2,516,312
2065	0	2,509,437	0	0	0	0	2,509,437
2066	0	2,509,437	0	0	0	0	2,509,437
2067	0	2,509,437	0	0	0	0	2,509,437
2068	0	2,516,312	0	0	0	0	2,516,312
2069	0	1,608,790	10,569,217	0	0	0	12,178,007
2070	0	0	34,688,698	0	0	0	34,688,698
2071	0	0	5,263,720	56,925,169	0	0	62,188,888
2072	0	0	0	67,161,809	0	0	67,161,809
2073	0	0	0	53,593,140	0	0	53,593,140
2074	0	0	0	11,301,127	0	0	11,301,127
2075	0	0	0	13,500,961	0	0	13,500,961
2076	0	0	0	2,424,869	12,637,592	0	15,062,461
2077	0	0	0	0	5,351,423	0	5,351,423
	43,318,988	172,496,930	50,521,635	204,907,074	17,989,016	20,570,625	509,804,268

Note 1: Columns may not add due to rounding

TABLE 3.2b
SCHEDULE OF ANNUAL EXPENDITURES
SAFSTOR, UNIT 2
(WITH ON-SITE DRY FUEL STORAGE)
(1998 Dollars) ¹

Year	Period 1 SAFSTOR Ops	Period 2 Dormancy	Period 3 D&D Prep	Period 4 Decontamination	Period 5 Site Restoration	ISFSI Eng. & Capital costs	Yearly Totals
2000	0	0	0	0	0	1,091,350	1,091,350
2001	0	0	0	0	0	1,091,350	1,091,350
2002	0	0	0	0	0	2,728,375	2,728,375
2003	0	0	0	0	0	4,092,563	4,092,563
2004	0	0	0	0	0	4,638,238	4,638,238
2005-2021	0	0	0	0	0	0	0
2022	0	0	0	0	0	4,600,000	4,600,000
2023	19,890,854	0	0	0	0	4,600,000	24,490,854
2024	20,480,213	1,442,586	0	0	0	5,175,000	27,097,799
2025	0	5,983,454	0	0	0	4,600,000	10,583,454
2026	0	5,983,454	0	0	0	5,750,000	11,733,454
2027	0	5,983,454	0	0	0	0	5,983,454
2028	0	4,026,344	0	0	0	0	4,026,344
2029	0	2,536,905	0	0	0	0	2,536,905
2030	0	2,536,905	0	0	0	0	2,536,905
2031	0	2,536,905	0	0	0	0	2,536,905
2032	0	2,543,855	0	0	0	0	2,543,855
2033	0	2,536,905	0	0	0	0	2,536,905
2034	0	2,536,905	0	0	0	0	2,536,905
2035	0	2,536,905	0	0	0	0	2,536,905
2036	0	2,543,855	0	0	0	0	2,543,855
2037	0	2,536,905	0	0	0	0	2,536,905
2038	0	2,536,905	0	0	0	0	2,536,905
2039	0	2,536,905	0	0	0	0	2,536,905
2040	0	1,617,832	0	0	0	0	1,617,832
2041	0	1,530,957	0	0	0	0	1,530,957
2042	0	1,530,957	0	0	0	0	1,530,957
2043	0	1,530,957	0	0	0	0	1,530,957
2044	0	1,535,151	0	0	0	0	1,535,151
2045	0	1,530,957	0	0	0	0	1,530,957
2046	0	1,530,957	0	0	0	0	1,530,957
2047	0	1,530,957	0	0	0	0	1,530,957
2048	0	1,535,151	0	0	0	0	1,535,151
2049	0	1,530,957	0	0	0	0	1,530,957
2050	0	1,530,957	0	0	0	0	1,530,957

TABLE 3.2b
SCHEDULE OF ANNUAL EXPENDITURES
SAFSTOR, UNIT 2
(WITH ON-SITE DRY FUEL STORAGE)
(1998 Dollars)
(cont'd)

Year	Period 1 SAFSTOR Ops	Period 2 Dormancy	Period 3 D&D Prep	Period 4 Decontamination	Period 5 Site Restoration	ISFSI Eng. & Capital costs	Yearly Totals
2051	0	1,530,957	0	0	0	0	1,530,957
2052	0	1,535,151	0	0	0	0	1,535,151
2053	0	1,530,957	0	0	0	0	1,530,957
2054	0	1,530,957	0	0	0	0	1,530,957
2055	0	1,530,957	0	0	0	0	1,530,957
2056	0	1,535,151	0	0	0	0	1,535,151
2057	0	1,530,957	0	0	0	0	1,530,957
2058	0	1,530,957	0	0	0	0	1,530,957
2059	0	1,530,957	0	0	0	0	1,530,957
2060	0	1,535,151	0	0	0	0	1,535,151
2061	0	1,530,957	0	0	0	0	1,530,957
2062	0	1,530,957	0	0	0	0	1,530,957
2063	0	1,530,957	0	0	0	0	1,530,957
2064	0	1,535,151	0	0	0	0	1,535,151
2065	0	1,530,957	0	0	0	0	1,530,957
2066	0	1,530,957	0	0	0	0	1,530,957
2067	0	1,530,957	0	0	0	0	1,530,957
2068	0	1,535,151	0	0	0	0	1,535,151
2069	0	1,530,957	0	0	0	0	1,530,957
2070	0	1,530,957	0	0	0	0	1,530,957
2071	0	146,804	17,978,843	0	0	0	18,125,648
2072	0	0	13,144,539	26,094,983	0	0	39,239,522
2073	0	0	0	63,923,950	0	0	63,923,950
2074	0	0	0	69,961,428	0	0	69,961,428
2075	0	0	0	44,264,919	0	0	44,264,919
2076	0	0	0	3,996,747	21,932,594	0	25,929,341
2077	0	0	0	0	9,287,418	0	9,287,418
	40,371,067	99,061,846	31,123,383	208,242,028	31,220,012	38,366,875	448,385,210

Note 1: Columns may not add due to rounding

TABLE 3.3
SUMMARY OF COSTS ASSOCIATED WITH
SHARED SYSTEMS AND STRUCTURES
(thousands of 1998 Dollars) ¹

STRUCTURES	UNIT 1	UNIT 2	TOTAL
East EP Pond	0	1,414	1,414
Shared Miscellaneous Site Structures	0	2,041	2,041
Steam Generator Blowdown Treatment Facility	0	827	827
Subtotal	0	4,282	4,282
SYSTEMS	UNIT 1	UNIT 2	TOTAL
Auxiliary Steam - Insulated	14	10	24
Condensate Polish Filter Demin	14	0	14
Condensate Polish Filter Demin - Ins	43	0	43
Demineralized Makeup Water - RCA	7	4	11
Demineralized Makeup Water	9	4	13
Domestic/Makeup/Service Water	106	5	111
Domestic/Makeup/Service Water-Ins	2	0	2
Domestic/Makeup/Service Water-Ins - RCA	7	1	8
Domestic/Makeup/Service Water - RCA	61	16	77
Fire Protection	41	31	72
Fire Protection - Insulated	4	3	7
Fire Protection - Insulated - RCA	1	3	4
Fire Protection - RCA	14	38	52
Neutralization Basin Recirculation	10	0	10
Primary Water	273	268	541
Primary Water - Insulated	6	7	13
Service & Instrument Air	16	12	28
Service & Instrument Air - Ins	8	6	14
Service & Instrument Air - Ins - RCA	45	37	82
Service & Instrument Air - RCA	32	24	56
SGBTF Blowdown - Insulated	292	1,193	1,485
SGBTF Demin - Ins - RCA	0	29	29
SGBTF Demin - RCA	0	41	41
SGBTF HVAC	468	0	468
SGBTF Misc - RCA	2	0	2
SGBTF Miscellaneous - RCA	0	12	12
SGBTF Waste Management	39	337	376
SGBTF Waste Management - Insulated	411	236	647
Sodium Hypochlorite	0	27	27
Water Treatment - Insulated	39	0	39
Water Treatment	22	0	22
Subtotal	1,986	2,344	4,330

TABLE 3.3
SUMMARY OF COSTS ASSOCIATED WITH
SHARED SYSTEMS AND STRUCTURES
(thousands of 1998 Dollars)
(cont'd)

MISCELLANEOUS COMPONENTS - REMOVAL	COST	CONTINGENCY	TOTAL
Shared Refueling Equipment (20)	see below	see below	0
Valves & Piping for Cond Storage Tank Interconnection	see below	see below	0
Turbine Lube Oil Storage Tank	see below	see below	0
Waste Oil Storage Tank	see below	see below	0
Miscellaneous Small Bore Piping	see below	see below	0
Valves & Piping for Holdup Tanks Interconnection	see below	see below	0
Valves & Piping for Aerated Waste Strge Tank Interconnect	see below	see below	0
SGBTF Electrical (9)	see below	see below	0
Tank, Valves, Piping - UHS Valves & Emergency Air	see below	see below	0
Piping for Waste Management System Interconnects	see below	see below	0
Clean Miscellaneous Components	12	1	13
Contaminated Miscellaneous Component - Removal Only	32	5	37
Subtotal	44	6	50
Miscellaneous Components - Decon, Pack, Ship, Bury, Other	38	14	52
TOTAL			8,714

Note 1: Columns may not add due to rounding

4. SCHEDULE ESTIMATE

The schedule for the decommissioning scenarios considered in this study follows the sequence presented in the AIF/NESP-036 study, with minor changes to reflect recent experience and site-specific constraints. In addition, the scheduling has been revised to reflect the spent fuel management plan outlined for the St. Lucie inventory.

Figure 4.1 presents a schedule for the DECON decommissioning alternative; the assumptions supporting this schedule are listed in Section 4.1. The key activities listed in the schedule do not reflect a one-to-one correspondence with those activities in the Appendix C and D cost tables, but reflect dividing some activities for clarity and combining others for convenience. The schedule was prepared using the "Microsoft Project for Windows" computer software (Ref. 15).

4.1 SCHEDULE ESTIMATE ASSUMPTIONS

The schedule estimate reflects the results of a precedence network developed for the site decommissioning activities, i.e., a PERT (Program Evaluation and Review Technique) Software Package. The durations used in the precedence network reflect the actual man-hour estimates from the cost tables in Appendix E, adjusted by stretching certain activities over their slack range and shifting the start and end dates of others. The following assumptions were made in the development of the decommissioning schedule.

- All work except vessel and internals removal activities is performed during an 8-hour workday, 5 days per week with no overtime. There are eleven paid holidays per year.
- The Fuel Handling Building will continue to serve as the spent fuel storage building/transfer facility until such time that all spent fuel can be transferred to the ISFSI. Each unit's Fuel Handling Building (spent fuel pool) operation is assumed to last approximately five years and 2 months after the cessation of operations at Unit 1 and Unit 2.
- Reactor and internals removal activities are performed by using separate crews for different activities working on different shifts, with a corresponding backshift charge for the second shift.
- Multiple crews work parallel activities to the maximum extent possible consistent with optimum efficiency, adequate access for cutting, removal and laydown space, and with the stringent safety measures necessary during demolition of heavy components and structures.

- For plant systems removal, the systems with the longest removal durations in areas on the critical path are considered to determine the duration of the activity.

4.2 PROJECT SCHEDULE

The period-dependent costs presented in the Appendix C and D cost tables are based upon the durations developed in the schedule for each decommissioning alternative. Durations are established between several milestones in each project period; these durations are used to establish a critical path for the entire project. In turn, the critical path duration for each period was used as the basis for determining the period-dependent costs.

Project timelines for the DECON and SAFSTOR alternatives are included in this section as Figures 4.2a through 4.2b. Deferred decommissioning in the SAFSTOR scenarios is assumed to commence such that the termination of the site licenses is accomplished within 60 years of final shutdown.

4.3 SPENT FUEL SCHEDULE

FP&L is assumed to develop an ISFSI at St. Lucie to prevent a loss of full core off-load reserve capacity in 2005 for Unit 1 and 2007 for Unit 2. The ISFSI will be sized to accommodate 90 storage modules and will be in operation from 2005 through 2040. Twenty-four modules (27%) are necessary to permit the plant to operate to the end of the operating licenses of each unit. The remaining capacity (73%) is necessary to facilitate timely decommissioning of the plant. As such, only 73% of the total capital/construction costs have been included in the cost estimates. Likewise, only the canister/module acquisition costs necessary to accommodate the transfer of fuel subsequent to plant shut down have been included. The cost estimates do not include the costs associated with construction and canister/module acquisition which are required to reach end of license.

FIGURE 4.1
DECON ACTIVITY SCHEDULE




FIGURE 4.1
DECON ACTIVITY SCHEDULE
(Continued)




FIGURE 4.1
DECON ACTIVITY SCHEDULE
(Continued)




FIGURE 4.1
DECON ACTIVITY SCHEDULE
(Continued)




FIGURE 4.1
DECON ACTIVITY SCHEDULE
(Continued)




FIGURE 4.1
DECON ACTIVITY SCHEDULE
(Continued)




FIGURE 4.1
DECON ACTIVITY SCHEDULE
(Continued)






FIGURE 4.2a

DECON DECOMMISSIONING TIMELINES

ST. LUCIE UNIT 1



ST. LUCIE UNIT 2




NOT TO SCALE


FIGURE 4.2b

SAFSTOR DECOMMISSIONING TIMELINES

ST. LUCIE UNIT 1



ST. LUCIE UNIT 2



NOT TO SCALE

5. RADIOACTIVE WASTES

The goal of the decommissioning program is the removal of all radioactive material from the site which would restrict its future use and termination of the NRC license for the site. This currently requires the remediation of all radioactive material at the site in excess of applicable legal limits. Under the Atomic Energy Act (Ref. 16), the NRC is responsible for protecting the public from sources of ionizing radiation. Title 10 of the Code of Federal Regulations delineates the production, utilization, and disposal of radioactive materials and processes. In particular, §61 controls the burial of low-level radioactive material and §71 defines radioactive material.

With increased competition from the waste recyclers and decreasing volumes (and revenues), the Barnwell facility has recently modified its past pricing policies for controlled disposal from one of volume to one based upon weight. This effectively mitigated the advantages of volume reduction, unless the mass is also reduced, e.g., through decontamination and free-release of the material. The masses and volumes of radioactive waste generated during the various decommissioning activities at the site are shown on a line-item basis in the Appendices C and D cost tables and summarized in Table 5.1. Waste volume summaries, shown in Table 5.1, are quantified consistent with §61 classifications. The volumes are calculated based on the gross container dimensions or, for components serving as their own waste container, the volume is calculated based upon the displaced volume of the component, i.e., steam generators and pressurizer.

Most of the materials being transported for controlled burial are categorized as LSA or SCO material containing Type A quantities, as defined in 49 CFR §173-178 (Ref. 17). Shipping containers are required to be Industrial Packages (IP-1 or IP-2). For this study, commercially available steel containers are presumed to be used for the disposal of piping, small components, and concrete. Larger components can serve as their own containers with proper closure of all openings, access ways, penetrations, etc.

The reactor vessel and internals are categorized as large quantity shipments and, accordingly, will be shipped in reusable shielded truck casks with disposable liners. In calculating disposal costs, the burial fees are applied against the liner volume, as well as the special handling requirements of the payload. Packaging efficiencies are lower for the highly activated materials (greater than Type A quantity waste) where high concentrations of gamma-emitting radionuclides limit the capacity of the shipping canisters. The steam generators are presumed to be shipped intact for disposal.

No process system that contains/handles radioactive substances at shutdown is presumed to meet material release criteria by decay alone, i.e., systems radioactive at shutdown will still be radioactive in a deferred decommissioning alternative due to the presence of long-lived radionuclides. While the dose rates decrease with time, radionuclides such as ^{137}Cs will still control the disposition requirements.

The waste volume generated in the decontamination and dismantling of the St. Lucie units is primarily generated during Period 2 of DECON and Period 4 of SAFSTOR. Contaminated and activated material will be characterized on site with a significant volume routed for additional processing. Components with low levels of removable surface contamination will be decontaminated on site, to the maximum extent possible. Components with low levels of internal contamination will be shipped to a waste recycling center for disassembly, decontamination, volume reduction, and/or repackaging. Heavily contaminated components and activated materials are generally routed for controlled disposal after on-site volume reduction.

Due to the lack of progress in siting the Southeast Compact regional burial facility within the host state of North Carolina, all LLW generated in the decontamination and dismantling of the St. Lucie Site is assumed destined for disposal at the existing Chem Nuclear Systems, Inc., Barnwell LLW Management Facility (Barnwell) in South Carolina. However, much of the radioactive metallic waste shipped from St. Lucie site will eventually be released as clean scrap by a recycling vendor. Other waste processors may be used to minimize the total cost of waste disposal.

Non-compactable (metallic) radioactive waste generated from removal of the plant equipment is assumed to be sent to an off-site vendor for recycling as a means of reducing the ultimate disposal volume. Considering typical plant conditions and industry experience, the inventory of contaminated material at the St. Lucie was segregated based on the likelihood of volume reduction and decontamination for radiological free release. The burial volumes reported in Tables 5.1a and b reflect the savings resulting from reprocessing and recycling. Off-site processing of non-compactable metallic waste appears as an "other" cost in the detailed decommissioning cost tables in Appendices C and D.

TABLE 5.1a
DECOMMISSIONING RADIOACTIVE WASTE BURIAL SUMMARY
(DECON)

	Waste Class¹	Volume² (Cubic feet)	Weight (Pounds)
Unit 1	A	120,260	
	B	14,701	
	C	408	
	>C	650	
Total			13,664,970
Unit 2	A	93,862	
	B	12,352	
	C	408	
	>C	655	
Total			11,165,502

¹ Waste is classified according to the requirements as delineated in Title 10 of the Code of Federal Regulations, Part 61.55

² Columns may not add due to rounding.

TABLE 5.1 b
DECOMMISSIONING RADIOACTIVE WASTE BURIAL SUMMARY
(SAFSTOR)

	Waste Class ¹	Volume ² (Cubic feet)	Weight (Pounds)
Unit 1	A	109,662	
	B	6,128	
	C	408	
	>C	650	
Total			11,040,572
Unit 2	A	94,202	
	B	6,441	
	C	408	
	>C	655	
Total			9,917,512

¹ Waste is classified according to the requirements as delineated in Title 10 of the Code of Federal Regulations, Part 61.55

² Columns may not add due to rounding.

6. RESULTS

The projected costs for the DECON alternative to decommission the St. Lucie Plants, Units 1 and 2, are estimated to be \$428.9 and \$453.2 million, respectively, in 1998 dollars. The projected costs for the SAFSTOR alternatives are estimated to be \$509.8 million and \$448.4 million, respectively. The costs reflect the site-specific features of St. Lucie, the local cost of labor, a schedule for spent fuel receipt, and a projected cost for LLW disposal at the burial site. Analyses of the major activities contributing to the total cost for each of the decommissioning alternatives are provided in Tables 6.1 and 6.2. Appendix C contains a detailed list of cost by "activity description" for each decommissioning alternative (by Unit), based on the requirement that an on-site ISFSI is constructed and maintained. Appendix D contains a detailed list of costs by "activity description" for each decommissioning alternative (by Unit), assuming that an on-site ISFSI is not required.

Staffing, including management, security, and health physics combine with the removal labor cost to represent the majority of the costs to decommission a nuclear station. This is a direct result of the labor-intensive nature of the decommissioning process, as well as the management controls required to ensure a safe and successful program. LLW disposal (burial) represents the next largest cost component. These costs are indicative of the expense incurred in siting, developing, and licensing new disposal facilities. Packaging and transportation costs are most sensitive to the waste volume generated in the decontamination and dismantling process, the volume reduction achieved, transport regulations for LLW, and the final destination (i.e., distance to the disposal site). "Other" costs include off-site waste reprocessing expenses which can also be considered as "decontamination" expenditures, as well as true incidentals such as property taxes, engineering costs, insurance, and fees.

In most situations, the DECON alternative is the preferred mode of decommissioning. This alternative is favored because it eliminates the costs for caretaking and prevents the site from becoming a potential long-term safety hazard. More importantly, the individuals familiar with the operation of the nuclear facility are available to support the dismantling effort; plant systems and services are fully functional; structural integrity is intact; and the licensee has a comprehensive management organization available to oversee/conduct the orderly decontamination and termination of the NRC licenses for the site. For the St. Lucie Station, the DECON alternative is a valid and cost-effective option; it is also the least expensive option prior to any time value of money calculations.

For the SAFSTOR scenario, the construction of barriers and the general decontamination of plant areas in preparation for long-term storage does not alleviate the need for continued surveillance. The structural integrity of facilities must be maintained to support eventual decontamination and dismantling activities. It is

expected that a full-time preventive and corrective maintenance staff will be needed to maintain essential site services and prevent the deterioration of the site facilities. Peripheral structures will have to be maintained or remediated where asbestos and other hazardous and toxic material could enter the environment through degradation, weathering, or insufficient maintenance of site structures.

The NRC has become increasingly concerned over the maintenance, or lack of maintenance, at shutdown facilities. As such, the decommissioning estimates for placing a facility in dormancy have become increasingly more costly. The commitment to maintain fuel storage support facilities at the site for a minimum of five years following the cessation of plant operations is stipulated by the DOE's transfer policy, irrespective of the intended decommissioning plans for the facility. This will require the continued operation of several plant systems and a cognizant operations staff. Considerable progress in the decontamination and dismantling (of systems and facilities nonessential to spent fuel storage) can be made during the initial wet storage period in a program such as DECON. By comparison, at the conclusion of the transfer activity and the placement of the facility into safe storage (SAFSTOR), the physical plant is relatively unchanged, deferring the cleanup and dismantling of the facility to a later time.

The caretaking of a dormant facility has also become more costly. The NRC's review of currently dormant facilities has resulted in a general increase in the level of maintenance required, as well as the on-site presence of the owners/operators of the sites. Currently, licensees are required to complete the decommissioning process (culminating in the termination of the NRC site licenses) within a period of 60 years. This translates into an available safe storage period of approximately 50 years during which the owner/operator would continue to maintain the property, replace roofing, and repair and upgrade surveillance and monitoring systems, lighting and communication equipment, rainwater collection, sampling and treatment equipment, etc. At the conclusion of this phase, release of the facility from the jurisdiction of the NRC will still require remediation of the property. The delay in decommissioning will not dramatically alter the cleanup requirements, i.e., the quantities of waste to be remediated will be comparable to those addressed in the DECON alternative. Although the radiation levels within the plant will have decreased substantially over the period of decay, the presence of long-lived radioisotopes will control the removal and disposal techniques used in the decontamination and dismantling of plant systems and facilities. As such, the cost savings in postponing decommissioning are relatively small and the risk that regulatory and waste disposal requirements will become more restrictive is relatively high.

Thus, for reasons provided above, the SAFSTOR cost estimate is shown to exceed that for a comparable DECON alternative (in the same year's dollars). The magnitude of

the differential is dependent on the length of the dormancy, caretaking, and other utility housekeeping costs, e.g., taxes, insurance and fees.

This study provides an estimate for decommissioning the site under current requirements based on present-day costs and available technology. Individual costs associated with decommissioning activities have increased at rates greater than general inflation. For example, there has been significant volatility in the issues and policies surrounding waste disposal, i.e., access and cost of LLRW disposal has been unpredictable and has escalated at rates historically greater than inflation (over the past ten years). The government's high-level waste program has experienced a series of delays which have impeded the prompt decommissioning of the commercial reactors retired to date. Waste disposal has become the primary driver in the escalation of decommissioning costs. It is therefore appropriate that this cost estimate be reviewed periodically.

TABLE 6.1a
SUMMARY OF DECOMMISSIONING COST CONTRIBUTORS
DECON, UNIT 1
(Thousands of 1998 Dollars) ¹

Work Category	Total Cost	Percent of Total Costs
Staffing	135,313	31.55
LLRW Burial	71,960	16.78
Removal	35,590	8.30
Engineering & planning costs	20,921	4.88
ISFSI Capital Expenditure	20,571	4.80
GTCC disposal	19,935	4.65
Heavy Equipment Rental	16,537	3.86
Decontamination	14,675	3.42
Security Services	12,997	3.03
Fixed Overhead	12,884	3.00
Property Taxes	10,580	2.47
Packaging	7,357	1.72
Insurance	7,093	1.65
License Termination Survey	5,799	1.35
NRC & Emergency Planning Fees	4,610	1.07
Health Physics Supplies	4,475	1.04
Mixed/Hazardous Waste	4,466	1.04
Shipping	4,203	0.98
NRC ISFSI Fees	3,723	0.87
Plant Energy Budget	3,692	0.86
ISFSI Removal	2,928	0.68
Decon Equipment & Supplies	2,442	0.57
Asbestos abatement	2,087	0.49
Waste Conditioning / Recycling	1,902	0.44
Site Characterization	1,269	0.30
Remaining Costs	907	0.21
Total	428,917	100.00

Note 1: Columns may not add due to rounding

TABLE 6.1b
SUMMARY OF DECOMMISSIONING COST CONTRIBUTORS
DECON, UNIT 2
(Thousands of 1998 Dollars) ¹

Work Category	Total Cost	Percent of Total Costs
Staffing	168,232	37.12
LLRW Burial	62,062	13.70
Removal	48,586	10.72
ISFSI Capital Expenditure	38,367	8.47
GTCC disposal	19,935	4.40
Heavy Equipment Rental	13,378	2.95
Decontamination	13,371	2.95
Security Services	11,484	2.53
Engineering & planning costs	9,250	2.04
License Termination Survey	7,929	1.75
Property Taxes	7,505	1.66
Packaging	7,131	1.57
Fixed Overhead	6,768	1.49
Insurance	5,980	1.32
Mixed/Hazardous Waste	4,466	0.99
Health Physics Supplies	4,291	0.95
Plant Energy Budget	4,201	0.93
Shipping	3,944	0.87
NRC & Emergency Planning Fees	3,049	0.67
ISFSI Removal	2,928	0.65
NRC ISFSI Fees	2,618	0.58
Waste Conditioning / Recycling	2,459	0.54
Asbestos abatement	2,087	0.46
Decon Equipment & Supplies	1,925	0.42
Site Characterization	808	0.18
Remaining Costs	396	0.09
Total	453,151	100.00

Note 1: Columns may not add due to rounding

TABLE 6.2a
SUMMARY OF DECOMMISSIONING COST CONTRIBUTORS
SAFSTOR, UNIT 1
(Thousands of 1998 Dollars) ¹

Work Category	Total Cost	Percent of Total Costs
Staffing	201,224	39.47
LLRW Burial	55,988	10.98
Removal	34,678	6.80
Property Taxes	26,517	5.20
Security Services	23,594	4.63
Engineering & planning costs	20,749	4.07
ISFSI Capital Expenditure	20,571	4.04
GTCC disposal	19,935	3.91
NRC & Emergency Planning Fees	12,824	2.52
Heavy Equipment Rental	11,406	2.24
Fixed Overhead	11,391	2.23
Insurance	10,339	2.03
Plant Energy Budget	7,288	1.43
Packaging	6,748	1.32
Health Physics Supplies	6,186	1.21
License Termination Survey	5,799	1.14
Decontamination	4,968	0.97
Mixed/Hazardous Waste	4,466	0.88
NRC ISFSI Fees	3,723	0.73
Shipping	3,414	0.67
ISFSI Removal	2,928	0.57
Decon Equipment & Supplies	2,384	0.47
Asbestos abatement	2,087	0.41
Waste Conditioning / Recycling	1,902	0.37
Site Characterization	806	0.16
Remaining Costs	7,891	1.55
Total	509,804	100.00

Note 1: Columns may not add due to rounding

TABLE 6.2b
SUMMARY OF DECOMMISSIONING COST CONTRIBUTORS
SAFSTOR, UNIT 2
(Thousands of 1998 Dollars) ¹

Work Category	Total Cost	Percent of Total Costs
Staffing	146,031	32.57%
LLRW Burial	50,906	11.35%
Removal	47,052	10.49%
ISFSI Capital Expenditure	38,367	8.56%
Property Taxes	23,442	5.23%
GTCC disposal	19,935	4.45%
Engineering & planning costs	11,176	2.49%
NRC & Emergency Planning Fees	11,046	2.46%
Security Services	9,748	2.17%
Fixed Overhead	9,652	2.15%
Heavy Equipment Rental	8,825	1.97%
Insurance	8,817	1.97%
License Termination Survey	7,929	1.77%
Packaging	6,696	1.49%
Plant Energy Budget	6,462	1.44%
Health Physics Supplies	6,203	1.38%
Decontamination	5,257	1.17%
Mixed/Hazardous Waste	4,466	1.00%
Shipping	3,422	0.76%
ISFSI Removal	2,928	0.65%
NRC ISFSI Fees	2,618	0.58%
Decon Equipment & Supplies	2,468	0.55%
Waste Conditioning / Recycling	2,459	0.55%
Asbestos abatement	2,087	0.47%
Site Characterization	555	0.12%
Remaining Costs	9,836	2.19%
Total	448,385	100.00%

Note 1: Columns may not add due to rounding

7. REFERENCES

1. U.S. Code of Federal Regulations, Title 10, Parts 30, 40, 50, 51, 70 and 72, "General Requirements for Decommissioning Nuclear Facilities," Nuclear Regulatory Commission, Federal Register Volume 53, Number 123 (p 24018+), June 27, 1988.
2. U.S. Nuclear Regulatory Commission, Regulatory Guide 1.159, "Assuring the Availability of Funds for Decommissioning Nuclear Reactors," August, 1990.
3. U.S. Code of Federal Regulations, Title 10, Parts 2, 50 and 51, "Decommissioning of Nuclear Power Reactors," Nuclear Regulatory Commission, Federal Register Volume 61 (p39278+), July 29, 1996.
4. "Nuclear Waste Policy Act of 1982 and Amendments," U.S. Department of Energy's Office of Civilian Radioactive Management, 1982.
5. "Low-Level Radioactive Waste Policy Amendments Act of 1985," Public Law 99-240, January 15, 1986.
6. U.S. Code of Federal Regulations, Title 10, Part 20, Subpart E -"Radiological Criteria for License Termination", Federal Register, Volume 62, Number 139 (p39058t), July 21, 1997.
7. T.S. LaGuardia et al., "Guidelines for Producing Commercial Nuclear Power Plant Decommissioning Cost Estimates," AIF/NESP-036, May, 1986.
8. W.J. Manion and T.S. LaGuardia, "Decommissioning Handbook," U.S. Department of Energy, DOE/EV/10128-1, November, 1980.
9. "Building Construction Cost Data 1998," Robert Snow Means Company, Inc., Kingston, Massachusetts.
10. Project and Cost Engineers' Handbook, Second Edition, p. 239, American Association of Cost Engineers, Marcel Dekker, Inc., New York, New York.
11. Tri-State Motor Transit Company, published tariffs, Interstate Commerce Commission (ICC), Docket No. MC-109397 and Supplements, 1998.

7. REFERENCES

(continued)

12. J.C. Evans et al., "Long-Lived Activation Products in Reactor Materials," NUREG/CR-3474, Pacific Northwest Laboratory for the Nuclear Regulatory Commission, August, 1984.
13. R.I. Smith, G.J. Konzek, W.E. Kennedy, Jr., "Technology, Safety and Costs of Decommissioning a Reference Pressurized Water Reactor Power Station," NUREG/CR-0130 and addenda, Pacific Northwest Laboratory for the Nuclear Regulatory Commission, June, 1978.
14. H.D. Oak, et al., "Technology, Safety and Costs of Decommissioning a Reference Boiling Water Reactor Power Station," NUREG/CR-0672 and addenda, Pacific Northwest Laboratory for the Nuclear Regulatory Commission, June, 1980.
15. "Microsoft Project for Windows," Version 3.0, Microsoft Corporation, Redmond, WA, 1993.
16. "Atomic Energy Act" of 1954," (68 Stat. 919).
17. U.S. Department of Transportation, Section 49 of the Code of Federal Regulations, "Transportation," Parts 173 through 178, 1996.

APPENDIX A
UNIT COST FACTOR DEVELOPMENT

APPENDIX A UNIT COST FACTOR DEVELOPMENT

Example: Unit Factor for Removal of Contaminated Heat Exchanger < 3,000 lbs.

1. SCOPE

Heat exchangers weighing < 3,000 lbs. will be removed in one piece using a crane or small hoist. They will be disconnected from the inlet and outlet piping. The heat exchanger will be sent to the packing area.

2. CALCULATIONS

Act ID	Activity Description	Activity Duration	Critical Duration
a	Remove insulation	60	(b)
b	Mount pipe cutters	60	60
c	Install contamination controls	20	(b)
d	Disconnect inlet and outlet lines	60	60
e	Cap openings	20	(d)
f	Rig for removal	30	30
g	Unbolt from mounts	30	30
h	Remove contamination controls	15	15
i	Remove, wrap in plastic, send to packing area	<u>60</u>	<u>60</u>
	Totals (Activity/Critical)	355	255
Duration adjustment(s):			
+ Respiratory protection adjustment (50% of critical duration)			128
+ Radiation/ALARA adjustment (40% of critical duration)			<u>102</u>
Adjusted work duration			485
+ Protective clothing adjustment (30% of adjusted duration)			<u>146</u>
Productive work duration			631
+ Work break adjustment (8.33 % of productive duration)			<u>53</u>
Total work duration min			684 min

*** Total duration = 11.400 hr ***

APPENDIX A
(continued)

3. LABOR REQUIRED

Crew	Number	Duration (hr)	Rate (\$/hr)	Cost
<hr/>				
Laborers	3.00	11.400	\$16.18	\$553.36
Craftsmen	2.00	11.400	\$26.93	\$614.00
Foreman	1.00	11.400	\$29.51	\$336.41
General Foreman	0.25	11.400	\$30.95	\$88.21
Fire Watch	0.05	11.400	\$16.18	\$9.22
Health Physics Technician	1.00	11.400	\$34.14	<u>\$389.20</u>
Total labor cost				\$1,990.40

4. EQUIPMENT & CONSUMABLES COSTS

Equipment Costs	none
Consumables/Materials Costs	
-Blotting paper 50 @ \$0.36 sq ft {2}	\$18.00
-Plastic sheets/bags 50 @ \$0.08/sq ft {3}	\$4.00
-Gas torch consumables 1 @ \$6.05/hr x 1 hr {1}	<u>\$6.05</u>
Subtotal cost of equipment and materials	\$28.05
Overhead & profit on equipment and materials @ 16.000%	<u>\$4.49</u>
Total costs, equipment & material	\$32.54
TOTAL COST Removal of contaminated heat exchanger <3000 pounds:	\$2,022.94
Total labor cost:	\$1,990.40
Total equipment/material costs:	\$32.54
Total adjusted exposure man-hours incurred:	46.924
Total craft labor man-hours required per unit:	83.220

**APPENDIX A
(continued)**

5. NOTES AND REFERENCES

1. Durations are shown in minutes. The integrated duration accounts for those activities that can be performed in conjunction with other activities, indicated by the alpha designator of the concurrent activity. This results in an overall decrease in the sequenced duration.
2. Work difficulty factors were developed in conjunction with the AIF program to standardize decommissioning cost studies and are delineated in the "Guidelines" study (Vol. 1, Ch. 5).
3. Adjusted for regional material costs for Richmond, VA.
4. References:
 1. R.S. Means (1998) Division 016 Section 420-6360 pg 22
 2. McMaster-Carr Ed. 101
 3. R.S. Means (1998) Division 015 Section 602-0200 pg 16

APPENDIX B
UNIT COST FACTOR LISTING
(DECON: Power Block Structures Only)

APPENDIX B

UNIT COST FACTOR LISTING (Power Block Structures Only)

Unit Cost Factor	Cost/Unit(\$)
Removal of clean instrument and sampling tubing, \$/linear foot	0.20
Removal of clean pipe 0.25 to 2 inches diameter, \$/linear foot	2.44
Removal of clean pipe >2 to 4 inches diameter, \$/linear foot	2.97
Removal of clean pipe >4 to 8 inches diameter, \$/linear foot	6.09
Removal of clean pipe >8 to 14 inches diameter, \$/linear foot	11.45
Removal of clean pipe >14 to 20 inches diameter, \$/linear foot	14.89
Removal of clean pipe >20 to 36 inches diameter, \$/linear foot	21.90
Removal of clean pipe >36 inches diameter, \$/linear foot	26.02
Removal of clean valves >2 to 4 inches	30.89
Removal of clean valves >4 to 8 inches	60.87
Removal of clean valves >8 to 14 inches	114.47
Removal of clean valves >14 to 20 inches	148.85
Removal of clean valves >20 to 36 inches	219.00
Removal of clean valves >36 inches	260.18
Removal of clean pipe hangers for small bore piping	13.14
Removal of clean pipe hangers for large bore piping	45.27
Removal of clean pumps, <300 pound	101.49
Removal of clean pumps, 300-1000 pound	289.39
Removal of clean pumps, 1000-10,000 pound	1,138.49
Removal of clean pumps, >10,000 pound	2,194.58
Removal of clean pump motors, 300-1000 pound	122.34
Removal of clean pump motors, 1000-10,000 pound	475.17
Removal of clean pump motors, >10,000 pound	1,069.12
Removal of clean turbine-driven pumps < 10,000 pound	1,314.65
Removal of clean turbine-driven pumps > 10,000 pounds	2,936.28

APPENDIX B
(continued)

Unit Cost Factor	Cost/Unit(\$)
Removal of clean PWR turbine-generator	72,339.71
Removal of clean heat exchanger <3000 pound	615.63
Removal of clean heat exchanger >3000 pound	1,549.63
Removal of clean feedwater heater/deaerator	4,351.60
Removal of clean moisture separator/reheater	8,924.60
Removal of clean PWR main condenser	199,981.31
Removal of clean tanks, <300 gallons	132.06
Removal of clean tanks, 300-3000 gallon	416.39
Removal of clean tanks, >3000 gallons, \$/square foot surface area	3.58
Removal of clean electrical equipment, <300 pound	55.86
Removal of clean electrical equipment, 300-1000 pound	199.19
Removal of clean electrical equipment, 1000-10,000 pound	398.41
Removal of clean electrical equipment, >10,000 pound	963.05
Removal of clean electrical transformers < 30 tons	668.82
Removal of clean electrical transformers > 30 tons	1,926.11
Removal of clean standby diesel-generator, <100 kW	683.15
Removal of clean standby diesel-generator, 100 kW to 1 MW	1,524.83
Removal of clean standby diesel-generator, >1 MW	3,156.69
Removal of clean electrical cable tray, \$/linear foot	5.23
Removal of clean electrical conduit, \$/linear foot	2.29
Removal of clean mechanical equipment, <300 pound	55.86
Removal of clean mechanical equipment, 300-1000 pound	199.19
Removal of clean mechanical equipment, 1000-10,000 pound	398.41
Removal of clean mechanical equipment, >10,000 pound	963.05
Removal of clean HVAC equipment, <300 pound	55.86

APPENDIX B
(continued)

Unit Cost Factor	Cost/Unit(\$)
Removal of clean HVAC equipment, 300-1000 pound	199.19
Removal of clean HVAC equipment, 1000-10,000 pound	398.41
Removal of clean HVAC equipment, >10,000 pound	963.05
Removal of clean HVAC ductwork, \$/pound	0.42
Removal of contaminated instrument and sampling tubing, \$/linear foot	0.74
Removal of contaminated pipe 0.25 to 2 inches diameter, \$/linear foot	17.29
Removal of contaminated pipe >2 to 4 inches diameter, \$/linear foot	31.09
Removal of contaminated pipe >4 to 8 inches diameter, \$/linear foot	52.54
Removal of contaminated pipe >8 to 14 inches diameter, \$/linear foot	100.71
Removal of contaminated pipe >14 to 20 inches diameter, \$/linear foot	122.44
Removal of contaminated pipe >20 to 36 inches diameter, \$/linear foot	171.18
Removal of contaminated pipe >36 inches diameter, \$/linear foot	203.01
Removal of contaminated valves >2 to 4 inches	147.39
Removal of contaminated valves >4 to 8 inches	253.97
Removal of contaminated valves >8 to 14 inches	503.55
Removal of contaminated valves >14 to 20 inches	642.43
Removal of contaminated valves >20 to 36 inches	855.92
Removal of contaminated valves >36 inches	1,015.03
Removal of contaminated pipe hangers for small bore piping	50.50
Removal of contaminated pipe hangers for large bore piping	155.92
Removal of contaminated pumps, <300 pound	452.43
Removal of contaminated pumps, 300-1000 pound	1,050.51
Removal of contaminated pumps, 1000-10,000 pound	3,276.42
Removal of contaminated pumps, >10,000 pound	7,955.60
Removal of contaminated pump motors, 300-1000 pound	451.73

APPENDIX B
(continued)

Unit Cost Factor	Cost/Unit(\$)
Removal of contaminated pump motors, 1000-10,000 pound	1,334.42
Removal of contaminated pump motors, >10,000 pound	2,999.58
Removal of contaminated turbine-driven pumps < 10,000 pounds	4,033.69
Removal of contaminated turbine-driven pumps > 10,000 pounds	9,200.42
Removal of contaminated heat exchanger <3000 pound	2,022.94
Removal of contaminated heat exchanger >3000 pound	5,845.60
Removal of contaminated tanks, <300 gallons	759.94
Removal of contaminated tanks, >300 gallons, \$/square foot	14.84
Removal of contaminated electrical equipment, <300 pound	351.59
Removal of contaminated electrical equipment, 300-1000 pound	847.78
Removal of contaminated electrical equipment, 1000-10,000 pound	1,630.78
Removal of contaminated electrical equipment, >10,000 pound	3,190.66
Removal of contaminated electrical cable tray, \$/linear foot	25.18
Removal of contaminated electrical conduit, \$/linear foot	31.80
Removal of contaminated mechanical equipment, <300 pound	388.90
Removal of contaminated mechanical equipment, 300-1000 pound	935.87
Removal of contaminated mechanical equipment, 1000-10,000 pound	1,799.91
Removal of contaminated mechanical equipment, >10,000 pound	3,190.66
Removal of contaminated HVAC equipment, <300 pound	388.90
Removal of contaminated HVAC equipment, 300-1000 pound	935.87
Removal of contaminated HVAC equipment, 1000-10,000 pound	1,799.91
Removal of contaminated HVAC equipment, >10,000 pound	3,190.66
Removal of contaminated HVAC ductwork, \$/pound	1.62
Removal/plasma arc cut of contaminated thin metal components, \$/linear in.	1.80
Additional decontamination of surface by washing, \$/square foot	3.74

APPENDIX B
(continued)

Unit Cost Factor	Cost/Unit(\$)
Additional decontamination of surfaces by hydrolasing, \$/square foot	17.86
Decontamination rig hook-up and flush	3,314.89
Chemical flush of components/systems, \$/gallon	7.01
Removal of clean standard reinforced concrete, \$/cubic yard	84.18
Removal of grade slab concrete, \$/cubic yard	113.08
Removal of clean concrete floors, \$/cubic yard	152.18
Removal of sections of clean concrete floors, \$/cubic yard	479.60
Removal of clean heavily rein concrete w/#9 rebar, \$/cubic yard	118.97
Removal of contaminated heavily rein concrete w/#9 rebar, \$/cubic yard	1,035.45
Removal of clean heavily rein concrete w/#18 rebar, \$/cubic yard	151.18
Removal of contaminated heavily rein concrete w/#18 rebar, \$/cubic yard	1,372.06
Removal heavily rein concrete w/#18 rebar & steel embedments, \$/cu yd	217.02
Removal of below-grade suspended floors, \$/square foot	152.18
Removal of clean monolithic concrete structures, \$/cubic yard	419.32
Removal of contaminated monolithic concrete structures, \$/cu yd	1,033.93
Removal of clean foundation concrete, \$/cubic yard	328.42
Removal of contaminated foundation concrete, \$/cubic yard	962.34
Explosive demolition of bulk concrete, \$/cubic yard	16.41
Removal of clean hollow masonry block wall, \$/cubic yard	39.64
Removal of contaminated hollow masonry block wall, \$/cubic yard	150.01
Removal of clean solid masonry block wall, \$/cubic yard	39.64
Removal of contaminated solid masonry block wall, \$/cubic yard	150.01
Backfill of below-grade voids, \$/cubic yard	4.28
Removal of subterranean tunnels/voids, \$/linear foot	64.46
Placement of concrete for below-grade voids, \$/cubic yard	63.31

APPENDIX B
(continued)

Unit Cost Factor	Cost/Unit(\$)
Excavation of clean material, \$/cubic yard	1.95
Excavation of contaminated material, \$/cubic yard	23.02
Excavation of submerged concrete rubble, \$/cubic yard	6.59
Removal of clean concrete rubble, \$/cubic yard	6.32
Removal of contaminated concrete rubble, \$/cubic yard	17.47
Removal of building by volume, \$/cubic foot	0.14
Removal of clean building metal siding, \$/square foot	0.67
Removal of contaminated building metal siding, \$/square foot	2.49
Removal of standard asphalt roofing, \$/square foot	0.92
Removal of transite panels, \$/square foot	1.10
Scarifying contaminated concrete surfaces (drill & spall)	7.54
Scabbling contaminated concrete floors, \$/square foot	1.08
Scabbling contaminated concrete walls, \$/square foot	4.18
Scabbling contaminated ceilings, \$/square foot	41.81
Scabbling structural steel, \$/square foot	3.63
Removal of clean overhead cranes/monorails < 10 ton capacity	288.16
Removal of contaminated overhead cranes/monorails < 10 ton capacity	908.75
Removal of clean overhead cranes/monorails >10-50 ton capacity	691.58
Removal of contaminated overhead cranes/monorails >10-50 ton capacity	2,179.77
Removal of polar cranes > 50 ton capacity, each	2,928.94
Removal of gantry cranes > 50 ton capacity, each	12,038.09
Removal of structural steel, \$/pound	0.16
Removal of clean steel floor grating, \$/square foot	1.49
Removal of contaminated steel floor grating, \$/square foot	5.15
Removal of clean free-standing steel liner, \$/square foot	5.37

APPENDIX B
(continued)

Unit Cost Factor	Cost/Unit(\$)
Removal of contaminated free-standing steel liner, \$/square foot	17.17
Removal of clean concrete-anchored steel liner, \$/square foot	2.68
Removal of contaminated concrete-anchored steel liner, \$/square foot	19.87
Placement of scaffolding in clean areas, \$/square foot	2.83
Placement of scaffolding in contaminated areas, \$/square foot	7.25
Landscaping with topsoil, \$/acre	13,045.41
Cost of CPC B-88 LSA box & preparation for use	653.15
Cost of CPC B-25 LSA box & preparation for use	699.59
Cost of CPC B-12V 12 gauge LSA box & preparation for use	533.83
Cost of CPC B-144 LSA box & preparation for use	3,030.58
Cost of LSA drum & preparation for use	63.13
Cost of cask liner for CNSI 14-195 cask	6,424.90
Cost of cask liner for CNSI 8-120A cask (resins)	6,320.66
Cost of cask liner for CNSI 8-120A cask (filters)	6,320.66
Decontamination of surfaces with vacuuming, \$/square foot	0.31

APPENDIX C

DECOMMISSIONING COSTS: DECON AND SAFSTOR ALTERNATIVES Long-Term Fuel Storage

TABLE C-1
ST LUCIE PLANT - UNIT 1
INTEGRATED STATION DECOMMISSIONING COST ESTIMATE
(Thousands of 1998 Dollars)

ID Number	Activity Description	Decon	Remove	Pack	Ship	Burial	Other	Contingency	Total	NRC LicTerm	Site Restore.	Burial Site			10 CFR 61	
												A CF	B CF	C CF	pounds	GTCC Cu Ft
PERIOD 1: Mothballing Activities																
1	Prepare preliminary decommissioning cost	-	-	-	-		130	20	150	150	-	-	-	-	-	-
2	Notification of Cessation of Operations								Note 1							
3	Remove fuel & source material								Note 2							
4	Notification of Permanent Defueling								Note 1							
5	Deactivate plant systems & process waste								Note 1							
6	Prepare and submit PSDAR	-	-	-	-		200	30	230	230	-	-	-	-	-	-
7	Review plant dwgs & specs.	-	-	-	-		130	20	150	150	-	-	-	-	-	-
8	Perform detailed rad survey								Note 1							
9	Estimate by-product inventory	-	-	-	-		100	15	115	115	-	-	-	-	-	-
10	End product description	-	-	-	-		100	15	115	115	-	-	-	-	-	-
11	Detailed by-product inventory	-	-	-	-		150	23	173	173	-	-	-	-	-	-
12	Define major work sequence	-	-	-	-		100	15	115	115	-	-	-	-	-	-
13	Perform SER and EA	-	-	-	-		310	47	357	357	-	-	-	-	-	-
14	Perform Site-Specific Cost Study	-	-	-	-		500	75	575	575	-	-	-	-	-	-
15	Prepare/submit License Termination Plan	-	-	-	-		410	61	471	471	-	-	-	-	-	-
16	Receive NRC approval of termination plan								Note 1							
Activity Specifications																
17.1	Prepare plant and facilities for SAFSTOR	-	-	-	-		492	74	566	566	-	-	-	-	-	-
17.2	Decontamination Flush of NSSS	-	-	-	-		50	8	58	58	-	-	-	-	-	-
17.3	Plant systems	-	-	-	-		417	63	479	479	-	-	-	-	-	-
17.4	Plant structures and buildings	-	-	-	-		312	47	359	359	-	-	-	-	-	-
17.5	Waste management	-	-	-	-		200	30	230	230	-	-	-	-	-	-
17.6	Facility and site dormancy	-	-	-	-		200	30	230	230	-	-	-	-	-	-
17	Total	-	-	-	-		1,671	251	1,921	1,921	-	-	-	-	-	-
Detailed Work Procedures																
18.1	Decontamination Flush of NSSS	-	-	-	-		100	15	115	115	-	-	-	-	-	-
18.2	Plant systems	-	-	-	-		473	71	544	544	-	-	-	-	-	-
18.3	Facility closeout & dormancy	-	-	-	-		120	18	138	138	-	-	-	-	-	-
18	Total	-	-	-	-		693	104	797	797	-	-	-	-	-	-
19	Procure vacuum drying system	-	-	-	-		10	2	12	12	-	-	-	-	-	-
20	Drain/de-energize non-cont. systems	-	-	-	-		-	-	Note 1	-	-	-	-	-	-	-
21	Drain & dry NSSS	-	-	-	-		-	-	Note 1	-	-	-	-	-	-	-
22	Drain/de-energize contaminated systems	-	-	-	-		-	-	Note 1	-	-	-	-	-	-	-
23	Decon/secure contaminated systems	-	-	-	-		-	-	Note 1	-	-	-	-	-	-	-
24	Decon primary loop	604	-	-	-		-	302	906	906	-	-	-	-	-	-
Decontamination Flush of Contam. Sys																
25.1	Chemical & Volume Control	73	-	-	-	288	-	109	471	471	-	912	-	-	65,546	-
25.2	Chemical & Volume Control - Insulated	614	-	-	-	516	-	436	1,566	1,566	-	894	-	-	117,281	-
25.3	Fuel Pool	75	-	-	-	231	-	95	401	401	-	465	-	-	52,522	-
25.4	Fuel Pool - Insulated	50	-	-	-	66	-	42	157	157	-	119	-	-	14,974	-
25.5	RCP Oil Collection	0	-	-	-	1	0	0	1	1	-	2	-	-	175	-
25.6	Reactor Coolant - Insulated	20	-	-	-	94	-	33	147	147	-	163	-	-	21,388	-
25.7	SGBTF Waste Management	7	-	-	-	6	-	5	17	17	-	10	-	-	1,335	-
25.8	SGBTF Waste Management - Insulated	78	-	-	-	55	-	53	185	185	-	92	-	-	12,527	-
25.9	Waste Management	542	-	-	-	1,759	-	711	3,011	3,011	-	5,390	-	-	399,788	-
25.10	Waste Management - Insulated	1,221	-	-	-	1,016	-	864	3,101	3,101	-	1,751	-	-	230,863	-
25	Totals	2,679	-	-	-	4,032	0	2,348	9,059	9,059	-	9,798	-	-	916,398	-

000150

TABLE C-1
ST LUCIE PLANT - UNIT 1
INTEGRATED STATION DECOMMISSIONING COST ESTIMATE
(Thousands of 1998 Dollars)

ID Number	Activity Description	Decon	Remove	Pack	Ship	Burial	Other	Contingency	Total	NRC LicTerm	Site Restore	Burial Site			10 CFR 61	
												A CF	B CF	C CF	pounds	GTCC Cu Ft
Decontamination of Site Buildings																
26.1	Reactor Building	576	-	-	-	-	-	288	865	865	-	-	-	-	-	-
26.2	Fuel Handling Building	214	-	-	-	-	-	107	322	322	-	-	-	-	-	-
26.3	Reactor Auxiliary	244	-	-	-	-	-	122	366	366	-	-	-	-	-	-
26	Totals	1,035	-	-	-	-	-	517	1,552	1,552	-	-	-	-	-	-
27	Prepare support equipment for storage	-	279	-	-	-	-	42	321	321	-	-	-	-	-	-
28	Install containment pressure equal. lines	-	19	-	-	-	-	3	22	22	-	-	-	-	-	-
29	Interim survey prior to dormancy	-	-	-	-	-	320	48	369	369	-	-	-	-	-	-
30	Secure building accesses	-	-	-	-	-	-	-	Note 1	-	-	-	-	-	-	-
31	Prepare & submit interim report	-	-	-	-	-	58	9	67	67	-	-	-	-	-	-
Period 1 Additional Costs																
32	Mixed/Hazardous Waste	-	-	-	-	-	3,884	583	4,466	4,466	-	-	-	-	-	-
Subtotal Period 1 Activity Costs		4,318	298	-	-	4,032	8,768	4,527	21,941	21,941	-	9,798	-	-	916,398	-
Period 1 Undistributed Costs																
1	Decon equipment	488	-	-	-	-	-	73	561	561	-	-	-	-	-	-
2	Decon supplies	461	-	-	-	-	-	115	576	576	-	-	-	-	-	-
3	Process liquid waste	412	-	483	552	5,679	-	1,757	8,884	8,884	-	-	8,364	-	1,290,689	-
4	Insurance	-	-	-	-	-	1,400	140	1,540	1,540	-	-	-	-	-	-
5	Property taxes	-	-	-	-	-	394	39	434	434	-	-	-	-	-	-
6	Health physics supplies	-	476	-	-	-	-	119	594	594	-	-	-	-	-	-
7	Small tool allowance	-	52	-	-	-	-	8	60	60	-	-	-	-	-	-
8	Disposal of DAW generated	-	-	12	3	590	-	149	754	754	-	1,915	-	-	132,212	-
9	Plant energy budget	-	-	-	-	-	325	49	373	373	-	-	-	-	-	-
10	Fuel storage capital expenditures	-	-	-	-	-	17,888	2,683	20,571	20,571	-	-	-	-	-	-
11	NRC ISFSI Fees	-	-	-	-	-	142	14	156	156	-	-	-	-	-	-
12	NRC Fees	-	-	-	-	-	203	20	223	223	-	-	-	-	-	-
13	Emergency Planning Fees	-	-	-	-	-	51	5	56	56	-	-	-	-	-	-
14	Site Security Cost	-	-	-	-	-	667	100	767	767	-	-	-	-	-	-
15	Fixed Overhead	-	-	-	-	-	750	112	862	862	-	-	-	-	-	-
Subtotal Undistributed Costs Period 1		1,361	528	495	555	6,269	21,817	5,384	36,410	36,410	-	1,915	8,364	-	1,422,901	-
Staff Costs																
DOC Staff Cost		-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
Utility Staff Cost		-	-	-	-	-	11,859	1,779	13,637	13,637	-	-	-	-	-	-
TOTAL COST TO SAFSTOR		5,679	826	495	555	10,301	42,442	11,690	71,988	71,988	-	11,713	8,364	-	2,339,299	-

Total cost to SAFSTOR with 19.39% contingency: 71,987,816

Total site radwaste volume buried 20,077 cubic feet

Total craft labor requirements 151,633 person hours

TABLE C-1
ST LUCIE PLANT - UNIT 1
INTEGRATED STATION DECOMMISSIONING COST ESTIMATE
(Thousands of 1998 Dollars)

ID Number	Activity Description	Decon	Remove	Pack	Ship	Burial	Other	Contingency	Total	NRC LicTerm	Site Restore.	Burial Site			10 CFR 61	
												A CF	B CF	C CF	pounds	GTCC Cu Ft
PERIOD 2: SAFSTOR Dormancy Activities																
1	Quarterly inspection								Note 1							
2	Semi-annual environmental survey								Note 1							
3	Prepare reports								Note 1							
4	Health physics supplies	-	-	-	-		46	11	57	57	-		-	-		-
5	Insurance	-	-	-	-		271	27	298	298	-		-	-		-
6	Property taxes	-	-	-	-		394	39	433	433	-		-	-		-
7	Disposal of contaminated solid waste	-	-	1	0	29	-	7	38	38	-	102	-	-		-
8	Maintenance supplies	-	-	-	-		99	25	123	123	-		-	-		-
9	Plant energy budget	-	-	-	-		78	12	89	89	-		-	-		-
10	NRC ISFSI Fees	-	-	-	-		142	14	156	156	-		-	-		-
11	NRC Fees	-	-	-	-		176	18	194	194	-		-	-		-
12	Emergency Planning Fees	-	-	-	-		51	5	56	56	-		-	-		-
13	Site Security Cost	-	-	-	-		559	84	642	642	-		-	-		-
14	Fixed Overhead	-	-	-	-		749	112	862	862	-		-	-		-
15	Site maintenance staff	-	-	-	-		4,212	632	4,844	4,844	-		-	-		-
PERIOD 2 ANNUAL MAINTENANCE TOTALS		-	-	1	0	29	6,775	987	7,792	7,792	-	102	-	-	-	-
Total cost SAFSTOR dormancy with		4,555,833	years equals	35,499,974												
Total site radwaste volume buried		464 cubic feet														

000152

TABLE C-1
ST LUCIE PLANT - UNIT 1
INTEGRATED STATION DECOMMISSIONING COST ESTIMATE
(Thousands of 1998 Dollars)

ID	Activity Description	Decon	Remove	Pack	Ship	Burial	Other	Contingency	Total	NRC LicTerm	Site Restore	Burial Site			10 CFR 61
Number												A CF	B CF	C CF	pounds GTCC Cu Ft
PERIOD 3															
1	Review plant dwgs & specs.	-	-	-	-		460	69	529	529	-	-	-	-	-
2	Perform detailed rad survey	-	-	-	-				Note 1						
3	End product description	-	-	-	-		100	15	115	115	-	-	-	-	-
4	Detailed by-product inventory	-	-	-	-		130	20	150	150	-	-	-	-	-
5	Define major work sequence	-	-	-	-		750	113	863	863	-	-	-	-	-
6	Perform SER and EA	-	-	-	-		310	47	357	357	-	-	-	-	-
7	Perform Site-Specific Cost Study	-	-	-	-		500	75	575	575	-	-	-	-	-
8	Prepare/submit License Termination Plan	-	-	-	-		410	61	471	471	-	-	-	-	-
9	Receive NRC approval of termination plan	-	-	-	-				Note 1						
Activity Specifications															
10.1	Re-activate plant & temporary facilities	-	-	-	-		737	111	848	763	85	-	-	-	-
10.2	Plant systems	-	-	-	-		417	63	479	431	48	-	-	-	-
10.3	Reactor internals	-	-	-	-		710	107	817	817	-	-	-	-	-
10.4	Reactor vessel	-	-	-	-		650	98	748	748	-	-	-	-	-
10.5	Biological shield	-	-	-	-		50	8	58	58	-	-	-	-	-
10.6	Steam generators	-	-	-	-		312	47	359	359	-	-	-	-	-
10.7	Reinforced concrete	-	-	-	-		160	24	184	92	92	-	-	-	-
10.8	Turbine & condenser	-	-	-	-		80	12	92	-	92	-	-	-	-
10.9	Plant structures & buildings	-	-	-	-		312	47	359	179	179	-	-	-	-
10.10	Waste management	-	-	-	-		460	69	529	529	-	-	-	-	-
10.11	Facility & site closeout	-	-	-	-		90	14	104	52	52	-	-	-	-
10	Total	-	-	-	-		3,978	597	4,574	4,026	548	-	-	-	-
Planning & Site Preparations															
11	Prepare dismantling sequence	-	-	-	-		240	36	276	276	-	-	-	-	-
12	Plant prep. & temp. svces	-	-	-	-		1,895	284	2,180	2,180	-	-	-	-	-
13	Design water clean-up system	-	-	-	-		140	21	161	161	-	-	-	-	-
14	Rigging/Cont. Cntrl Envirps/tooling/etc.	-	-	-	-		1,604	241	1,845	1,845	-	-	-	-	-
15	Procure casks/liners & containers	-	-	-	-		123	18	141	141	-	-	-	-	-
Detailed Work Procedures															
16.1	Plant systems	-	-	-	-		473	71	544	490	54	-	-	-	-
16.2	Reactor internals	-	-	-	-		250	38	288	288	-	-	-	-	-
16.3	Remaining buildings	-	-	-	-		135	20	155	39	116	-	-	-	-
16.4	CRD cooling assembly	-	-	-	-		100	15	115	115	-	-	-	-	-
16.5	CRD housings & ICI tubes	-	-	-	-		100	15	115	115	-	-	-	-	-
16.6	Incore instrumentation	-	-	-	-		100	15	115	115	-	-	-	-	-
16.7	Reactor vessel	-	-	-	-		363	54	417	417	-	-	-	-	-
16.8	Facility closeout	-	-	-	-		120	18	138	69	69	-	-	-	-
16.9	Missile shields	-	-	-	-		45	7	52	52	-	-	-	-	-
16.10	Biological shield	-	-	-	-		120	18	138	138	-	-	-	-	-
16.11	Steam generators	-	-	-	-		460	69	529	529	-	-	-	-	-
16.12	Reinforced concrete	-	-	-	-		100	15	115	58	58	-	-	-	-
16.13	Turbine & condensers	-	-	-	-		312	47	359	-	359	-	-	-	-
16.14	Auxiliary building	-	-	-	-		273	41	314	283	31	-	-	-	-
16.15	Reactor building	-	-	-	-		273	41	314	283	31	-	-	-	-
16	Total	-	-	-	-		3,224	484	3,708	2,989	719	-	-	-	-
17	Asbestos removal program	-	724	129	4	807	23	400	2,087	1,470	617	2,242	-	-	-

TABLE C-1
ST LUCIE PLANT - UNIT 1
INTEGRATED STATION DECOMMISSIONING COST ESTIMATE
(Thousands of 1998 Dollars)

ID	Activity Description	Decon	Remove	Pack	Ship	Burial	Other	Contingency	Total	NRC LicTerm	Site Restore.	Burial Site			10 CFR 61
Number												A CF	B CF	C CF	pounds GTCC Cu Ft
Period 3 Additional Costs															
18	Site Characterization Survey	-	-	-	-	-	403	60	463	463	-	-	-	-	-
Subtotal Period 3 Activity Costs		-	724	129	4	807	14,291	2,540	18,495	16,611	1,884	2,242	-	-	-
Period 3 Undistributed Costs															
1	DOC staff relocation expenses	-	837	-	-	-	-	126	963	963	-	-	-	-	-
2	Insurance	-	-	-	-	-	406	41	447	447	-	-	-	-	-
3	Property taxes	-	-	-	-	-	590	59	649	649	-	-	-	-	-
4	Health physics supplies	-	263	-	-	-	-	66	329	329	-	-	-	-	-
5	Heavy equipment rental	-	441	-	-	-	-	66	507	507	-	-	-	-	-
6	Disposal of DAW generated	-	-	18	5	883	-	223	1,129	1,129	-	2,865	-	-	197,823
7	Plant energy budget	-	-	-	-	-	513	77	590	590	-	-	-	-	-
8	NRC ISFSI Fees	-	-	-	-	-	212	21	233	233	-	-	-	-	-
9	NRC Fees	-	-	-	-	-	303	30	333	333	-	-	-	-	-
10	Emergency Planning Fees	-	-	-	-	-	76	8	83	83	-	-	-	-	-
11	Site Security Cost	-	-	-	-	-	998	150	1,148	1,148	-	-	-	-	-
12	Fixed Overhead	-	-	-	-	-	1,122	168	1,291	1,291	-	-	-	-	-
Subtotal Undistributed Costs Period 3		-	1,542	18	5	883	4,220	1,034	7,702	7,702	-	2,865	-	-	197,823
Staff Costs															
DOC Staff Cost		-	-	-	-	-	5,323	799	6,122	6,122	-	-	-	-	-
Utility Staff Cost		-	-	-	-	-	18,572	2,786	21,358	21,358	-	-	-	-	-
TOTAL PERIOD 3 COST		-	2,266	148	9	1,689	42,406	7,159	53,677	51,793	1,884	5,107	-	-	197,823

000154

TABLE C-1
ST LUCIE PLANT - UNIT 1
INTEGRATED STATION DECOMMISSIONING COST ESTIMATE
(Thousands of 1998 Dollars)

ID	Activity Description	Decon	Remove	Pack	Ship	Burial	Other	Contingency	Total	NRC LicTerm	Site Restore.	Burial Site			10 CFR 61 GTCC Cu Ft
Number												A CF	B CF	C CF	pounds
PERIOD 4															
Nuclear Steam Supply System Removal															
19.1	Reactor Coolant Piping	32	48	4	5	153	-	67	308	308	-	371	-	-	34,669
19.2	Pressurizer Relief Tank	4	18	1	1	26	-	13	62	62	-	89	-	-	5,824
19.3	Reactor Coolant Pumps & Motors	77	41	28	20	2,730	-	737	3,632	3,632	-	5,776	-	-	620,400
19.4	Pressurizer	18	27	4	8	1,053	-	280	1,389	1,389	-	2,134	-	-	239,212
19.5	Steam Generators	104	613	2,045	1,956	4,568	-	1,846	11,133	11,133	-	19,034	-	-	2,524,482
19.6	CRDMs/CIs/Service Structure Removal	84	52	82	12	254	-	126	590	590	-	2,907	-	-	75,041
19.7	Reactor Vessel Internals	52	1,290	2,934	352	3,885	-	3,758	12,271	12,271	-	1,441	612	408	265,498
19.8	Vessel & Internals GTCC Disposal	-	-	-	-	13,290	-	6,645	19,935	19,935	-	-	-	-	650
19.9	Reactor Vessel	126	3,340	217	289	5,703	-	5,546	15,222	15,222	-	4,847	2,096	-	983,277
19	Totals	497	5,429	5,295	2,643	31,660	-	19,018	64,542	64,542	-	36,599	2,708	408	4,748,402
20	Remove spent fuel racks	251	26	-	-	106	201	189	774	774	-	346	-	-	38,385
Removal of Major Equipment															
21	Main Turbine/Generator	-	49	-	-	-	-	7	56	-	56	-	-	-	-
22	Main Condensers	-	199	-	-	-	-	30	229	-	229	-	-	-	-
Disposal of Plant Systems															
23.1	Air Evacuation	-	4	-	-	-	-	1	4	-	4	-	-	-	-
23.2	Air Evacuation - Insulated	-	15	-	-	-	-	2	17	-	17	-	-	-	-
23.3	Auxiliary Steam - Insulated	-	12	-	-	-	-	2	14	-	14	-	-	-	-
23.4	Chemical & Volume Control	59	60	-	-	288	-	122	539	539	-	912	-	-	65,546
23.5	Chemical & Volume Control - Insulated	578	349	-	-	516	-	505	1,948	1,948	-	894	-	-	117,281
23.6	Chemical Feed	-	1	-	-	-	-	0	2	-	2	-	-	-	-
23.7	Chemical Feed - Insulated	-	1	-	-	-	-	0	1	-	1	-	-	-	-
23.8	Circulating & Intake Cooling Water	-	125	-	-	-	-	19	144	-	144	-	-	-	-
23.9	Component Cooling	-	39	-	-	-	-	6	45	-	45	-	-	-	-
23.10	Component Cooling - RCA	47	110	-	-	-	-	40	196	196	-	-	-	-	-
23.11	Condensate	-	81	-	-	-	-	12	93	-	93	-	-	-	-
23.12	Condensate - Insulated	-	46	-	-	-	-	7	52	-	52	-	-	-	-
23.13	Condensate Polish Filter Demin	-	12	-	-	-	-	2	14	-	14	-	-	-	-
23.14	Condensate Polish Filter Demin - Ins	-	37	-	-	-	-	6	43	-	43	-	-	-	-
23.15	Condensate Recovery	-	2	-	-	-	-	0	2	-	2	-	-	-	-
23.16	Condensate Recovery - Insulated	-	0	-	-	-	-	0	0	-	0	-	-	-	-
23.17	Condensate Recovery - Insulated - RCA	0	0	-	-	-	-	0	0	0	-	-	-	-	-
23.18	Condensate Recovery - RCA	1	3	-	-	-	-	1	5	5	-	-	-	-	-
23.19	Condenser Tube Cleaning	-	17	-	-	-	-	3	20	-	20	-	-	-	-
23.20	Contaminant Spray & Refueling Water	-	261	-	-	2,483	-	686	3,431	3,431	-	6,404	-	-	564,410
23.21	Contaminant Spray & Refueling Water - Ins	-	150	-	-	649	-	200	999	999	-	1,259	-	-	147,467
23.22	Demineralized Makeup Water	-	8	-	-	-	-	1	9	-	9	-	-	-	-
23.23	Demineralized Makeup Water - RCA	2	4	-	-	-	-	1	7	7	-	-	-	-	-
23.24	Domestic/Makeup/Service Water	-	92	-	-	-	-	14	106	-	106	-	-	-	-
23.25	Domestic/Makeup/Service Water - RCA	15	34	-	-	-	-	13	61	61	-	-	-	-	-
23.26	Domestic/Makeup/Service Water-Ins	-	2	-	-	-	-	0	2	-	2	-	-	-	-
23.27	Domestic/Makeup/Service Water-Ins-RCA	2	4	-	-	-	-	1	7	7	-	-	-	-	-
23.28	Electrical - Clean	-	1,024	-	-	-	-	154	1,177	-	1,177	-	-	-	-
23.29	Electrical - Contaminated	-	436	-	-	18	72	124	649	649	-	36	-	-	4,061
23.30	Electrical - Decontaminated	112	831	-	-	-	-	181	1,124	1,124	-	-	-	-	-
23.31	Emergency Diesel Generator	-	38	-	-	-	-	6	43	-	43	-	-	-	-
23.32	Emergency Diesel Generator - Insulated	-	3	-	-	-	-	1	4	-	4	-	-	-	-
23.33	Extraction Steam	-	42	-	-	-	-	6	48	-	48	-	-	-	-
23.34	Extraction Steam - Insulated	-	42	-	-	-	-	6	48	-	48	-	-	-	-
23.35	Feedwater - Insulated	-	45	-	-	-	-	7	51	-	51	-	-	-	-
23.36	Feedwater - Insulated - RCA	5	11	-	-	-	-	4	20	20	-	-	-	-	-
23.37	Fire Protection	-	36	-	-	-	-	5	41	-	41	-	-	-	-
23.38	Fire Protection - Insulated	-	3	-	-	-	-	1	4	-	4	-	-	-	-
23.39	Fire Protection - Insulated - RCA	0	1	-	-	-	-	0	1	1	-	-	-	-	-

TABLE C-1
ST LUCIE PLANT - UNIT 1
INTEGRATED STATION DECOMMISSIONING COST ESTIMATE
(Thousands of 1998 Dollars)

ID Number	Activity Description	Decon	Remove	Pack	Ship	Burial	Other	Contingency	Total	NRC LicTerm	Site Restore.	Burial Site			10 CFR 61
												A CF	B CF	C CF	GTCC Cu Ft
Disposal of Plant Systems (continued)															
23.40	Fire Protection - RCA	3	8	-	-	-	-	3	14	14	-	-	-	-	-
23.41	Fuel Pool	71	58	-	-	231	-	108	468	468	-	465	-	-	52,522
23.42	Fuel Pool - Insulated	47	37	-	-	66	-	49	199	199	-	119	-	-	14,974
23.43	HVAC	-	61	-	-	-	-	9	70	-	70	-	-	-	-
23.44	HVAC - Contaminated	-	1,317	-	-	383	787	543	3,030	3,030	-	751	-	-	86,998
23.45	Heater Drain & Vent - Insulated	-	93	-	-	-	-	14	108	-	108	-	-	-	-
23.46	Hydrogen Sampling	-	27	-	-	108	-	34	169	169	-	209	-	-	24,624
23.47	Integrated Leak Rate Testing	-	23	-	-	60	-	21	104	104	-	111	-	-	13,585
23.48	Main Steam - Insulated	-	98	-	-	-	-	15	113	-	113	-	-	-	-
23.49	Main Steam - Insulated - RCA	7	16	-	-	-	-	6	28	28	-	-	-	-	-
23.50	Misc Bulk Gas	-	10	-	-	-	-	1	11	-	11	-	-	-	-
23.51	Misc Bulk Gas - RCA	2	5	-	-	-	-	2	9	9	-	-	-	-	-
23.52	Miscellaneous	-	5	-	-	-	-	1	6	-	6	-	-	-	-
23.53	Miscellaneous - RCA	2	4	-	-	-	-	2	8	8	-	-	-	-	-
23.54	Neutralization Basin Recirculation	-	9	-	-	-	-	1	10	-	10	-	-	-	-
23.55	Post Accident Sampling	-	9	-	-	33	-	10	52	52	-	64	-	-	7,400
23.56	Post Accident Sampling - Insulated	-	27	-	-	24	-	13	65	65	-	41	-	-	5,543
23.57	Primary Water	-	90	-	-	56	78	48	273	273	-	140	-	-	12,728
23.58	Primary Water - Insulated	-	2	-	-	3	-	1	6	6	-	6	-	-	689
23.59	RCP Oil Collection	0	1	-	-	1	0	0	2	2	-	2	-	-	175
23.60	Radiation Monitoring	-	14	-	-	13	-	7	34	34	-	22	-	-	3,004
23.61	Reactor Coolant - Insulated	19	44	-	-	94	-	44	201	201	-	163	-	-	21,388
23.62	Refueling Equipment	-	61	-	-	268	-	82	412	412	-	533	-	-	60,959
23.63	SGBTf Blowdown - Insulated	-	95	-	-	139	-	58	292	292	-	239	-	-	31,555
23.64	SGBTf HVAC	-	209	-	-	36	141	82	468	468	-	71	-	-	8,136
23.65	SGBTf Misc - RCA	1	1	-	-	-	-	0	2	2	-	-	-	-	-
23.66	SGBTf Waste Management	6	4	-	-	8	-	6	22	22	-	10	-	-	1,335
23.67	SGBTf Waste Management - Insulated	73	38	-	-	55	-	60	226	226	-	92	-	-	12,527
23.68	Safety Injection	-	119	-	-	1,443	-	390	1,952	1,952	-	3,247	-	-	327,912
23.69	Safety Injection - Insulated	-	427	-	-	985	-	353	1,765	1,765	-	1,786	-	-	223,859
23.70	Sampling	-	4	-	-	-	-	1	5	-	5	-	-	-	-
23.71	Sampling - Insulated	-	4	-	-	-	-	1	5	-	5	-	-	-	-
23.72	Sampling - Insulated - RCA	3	8	-	-	-	-	3	13	13	-	-	-	-	-
23.73	Sampling - RCA	3	7	-	-	-	-	3	13	13	-	-	-	-	-
23.74	Secondary Side Wet Layup	-	6	-	-	-	-	1	7	-	7	-	-	-	-
23.75	Secondary Side Wet Layup - Ins	-	7	-	-	-	-	1	9	-	9	-	-	-	-
23.76	Secondary Side Wet Layup - Ins - RCA	1	4	-	-	-	-	1	7	7	-	-	-	-	-
23.77	Secondary Side Wet Layup - RCA	1	4	-	-	-	-	1	6	6	-	-	-	-	-
23.78	Service & Instrument Air	-	13	-	-	-	-	2	16	-	16	-	-	-	-
23.79	Service & Instrument Air - Ins	-	7	-	-	-	-	1	8	-	8	-	-	-	-
23.80	Service & Instrument Air - Ins - RCA	10	27	-	-	-	-	9	45	45	-	-	-	-	-
23.81	Service & Instrument Air - RCA	7	19	-	-	-	-	6	32	32	-	-	-	-	-
23.82	Steam Gen Blowdown Cooling	-	8	-	-	-	-	1	9	-	9	-	-	-	-
23.83	Steam Gen Blowdown Cooling - Ins - RCA	7	16	-	-	-	-	8	29	29	-	-	-	-	-
23.84	Steam Gen Blowdown Cooling - Insulated	-	1	-	-	-	-	0	1	-	1	-	-	-	-
23.85	Steam Gen Blowdown Cooling - RCA	10	21	-	-	-	-	8	39	39	-	-	-	-	-
23.86	Steam Generator Blowdown	-	19	-	-	67	-	21	106	106	-	136	-	-	15,145
23.87	Steam Generator Blowdown - Insulated	-	49	-	-	81	-	32	162	162	-	148	-	-	18,323
23.88	Turbine	-	1	-	-	-	-	0	1	-	1	-	-	-	-
23.89	Turbine Cooling Water	-	28	-	-	-	-	4	33	-	33	-	-	-	-
23.90	Turbine Cooling Water - Insulated	-	18	-	-	-	-	3	20	-	20	-	-	-	-
23.91	Turbine Lube Oil & Diesel Oil	-	35	-	-	-	-	5	40	-	40	-	-	-	-
23.92	Waste Management	507	387	-	-	1,759	-	790	3,443	3,443	-	5,390	-	-	399,788
23.93	Waste Management - Insulated	1,148	678	-	-	1,016	-	997	3,839	3,839	-	1,751	-	-	230,863
23.94	Water Treatment	-	34	-	-	-	-	5	39	-	39	-	-	-	-
23.95	Water Treatment - Insulated	-	19	-	-	-	-	3	22	-	22	-	-	-	-
23 Totals		2,758	8,317	-	-	10,880	1,078	6,007	29,040	26,523	2,517	25,000	-	-	2,472,795
24	Erect scaffolding for systems removal	-	735	-	-	21	71	200	1,027	1,027	-	70	-	-	7,726

TABLE C-1
ST LUCIE PLANT - UNIT 1
INTEGRATED STATION DECOMMISSIONING COST ESTIMATE
(Thousands of 1998 Dollars)

ID Number	Activity Description	Decon	Remove	Pack	Ship	Burial	Other	Contingency	Total	NRC LicTerm	Site Restore.	Burial Site			10 CFR 61
												A CF	B CF	C CF	GTCC Cu Ft
Decontamination of Site Buildings															
25 1	Reactor Building	623	352	54	22	3,430	155	1,289	5,924	5,924	-	7,301	-	-	821,464
25 2	Fuel Handling Building	210	200	2	1	92	124	197	827	827	-	298	-	-	31,807
25 3	Primary Water Tank Foundation - Contam	1	11	66	27	2,806	-	715	3,625	3,625	-	8,964	-	-	942,684
25 4	Reactor Auxiliary	290	23	15	6	612	26	310	1,281	1,281	-	1,987	-	-	207,788
25 5	Refueling Water Storage Tank - Contam	1	9	16	7	787	-	202	1,022	1,022	-	2,237	-	-	239,387
25 Totals		1,125	595	153	62	7,727	304	2,713	12,679	12,679	-	20,786	-	-	2,243,130
26	ORISE confirmatory survey	-	-	-	-	-	1,064	319	1,383	1,383	-	-	-	-	-
27	Terminate license	-	-	-	-	-	-	-	Note 1	-	-	-	-	-	-
Period 4 Additional Costs															
28	License Termination Survey	-	-	-	-	-	3,840	576	4,416	4,416	-	-	-	-	-
Subtotal Period 4 Activity Costs		4,632	15,349	5,448	2,705	50,395	6,557	29,060	114,146	111,344	2,802	82,800	2,708	408	9,510,438
Period 4 Undistributed Costs															
1	Decon equipment	488	-	-	-	-	-	73	561	561	-	-	-	-	-
2	Decon supplies	596	-	-	-	-	-	149	745	745	-	-	-	-	-
3	DOC staff relocation expenses	-	837	-	-	-	-	126	963	963	-	-	-	-	-
4	Process liquid waste	421	-	198	308	2,156	-	816	3,899	3,899	-	-	3,629	-	489,929
5	Insurance	-	-	-	-	-	1,631	163	1,794	1,794	-	-	-	-	-
6	Property taxes	-	-	-	-	-	3,110	311	3,421	3,079	342	-	-	-	-
7	Health physics supplies	-	2,633	-	-	-	-	658	3,291	3,291	-	-	-	-	-
8	Heavy equipment rental	-	12,242	-	-	-	-	1,836	14,078	12,671	1,408	-	-	-	-
9	Small tool allowance	-	228	-	-	-	-	34	263	236	26	-	-	-	-
10	Pipe cutting equipment	-	749	-	-	-	-	112	862	862	-	-	-	-	-
11	Disposal of DAW generated	-	-	96	26	4,989	-	1,261	6,371	6,371	-	16,197	-	-	1,097,481
12	Decommissioning Equipment Disposition	-	-	-	-	83	277	62	422	422	-	270	-	-	30,000
13	Plant energy budget	-	-	-	-	-	1,971	296	2,267	2,040	227	-	-	-	-
14	NRC ISFSI Fees	-	-	-	-	-	1,117	112	1,229	1,229	-	-	-	-	-
15	NRC Fees	-	-	-	-	-	1,674	167	1,842	1,842	-	-	-	-	-
16	Emergency Planning Fees	-	-	-	-	-	399	40	439	439	-	-	-	-	-
17	Site Security Cost	-	-	-	-	-	5,059	759	5,818	5,818	-	-	-	-	-
18	Fixed Overhead	-	-	-	-	-	5,917	889	6,805	6,805	-	-	-	-	-
Subtotal Undistributed Costs Period 4		1,505	16,690	294	334	7,228	21,157	7,863	55,070	53,067	2,003	16,467	3,629	-	1,617,410
Staff Costs															
DOC Staff Cost		-	-	-	-	-	16,378	2,457	18,835	18,835	-	-	-	-	-
Utility Staff Cost		-	-	-	-	-	39,655	5,948	45,603	45,603	-	-	-	-	-
TOTAL PERIOD 4		6,137	32,039	5,742	3,039	57,623	83,747	45,327	233,653	228,848	4,805	99,267	6,337	408	11,127,848

TABLE C-1
ST LUCIE PLANT - UNIT 1
INTEGRATED STATION DECOMMISSIONING COST ESTIMATE
(Thousands of 1998 Dollars)

ID Number	Activity Description	Decon	Remove	Pack	Ship	Burial	Other	Contingency	Total	NRC LicTerm	Site Restore.	Burial Site			10 CFR 61
												A CF	B CF	C CF	pounds GTCC Cu Ft
PERIOD 5															
Demolition of Remaining Site Buildings															
29.1	Reactor Building	-	5,108	-	-	-	-	766	5,875	881	4,993	-	-	-	-
29.2	Fuel Handling Building	-	682	-	-	-	-	102	784	78	705	-	-	-	-
29.3	Intake & CWS	-	294	-	-	-	-	44	338	-	338	-	-	-	-
29.4	Miscellaneous Structures	-	798	-	-	-	-	120	918	-	918	-	-	-	-
29.5	Primary Water Tank Foundation - Contam	-	2	-	-	-	-	0	2	-	2	-	-	-	-
29.6	Reactor Auxiliary	-	1,251	-	-	-	-	188	1,439	144	1,295	-	-	-	-
29.7	Refueling Water Storage Tank - Contam	-	5	-	-	-	-	1	5	-	5	-	-	-	-
29.8	Turbine Building	-	834	-	-	-	-	125	959	-	959	-	-	-	-
29.9	Turbine Pedestal	-	440	-	-	-	-	66	506	-	506	-	-	-	-
29	Totals	-	9,414	-	-	-	-	1,412	10,826	1,103	9,722	-	-	-	-
Site Closeout Activities															
30	Grade & landscape site	-	81	-	-	-	-	12	93	-	93	-	-	-	-
31	Final report to NRC	-	-	-	-	-	156	23	179	179	-	-	-	-	-
Period 5 Additional Costs															
32	ISFSI License Termination	-	735	37	14	-	859	452	2,629	2,629	-	3,709	-	-	-
33	ISFSI Demolition and Site Restoration	-	159	-	-	-	87	53	299	299	-	-	-	-	-
Subtotal Period 5 Activity Costs		-	10,389	37	14	-	1,102	1,952	14,026	4,211	9,815	3,709	-	-	-
Period 5 Undistributed Costs															
1	Insurance	-	-	-	-	-	1,775	178	1,953	1,953	-	-	-	-	-
2	Property taxes	-	-	-	-	-	3,729	373	4,102	-	4,102	-	-	-	-
3	Heavy equipment rental	-	1,697	-	-	-	-	255	1,951	-	1,951	-	-	-	-
4	Small tool allowance	-	79	-	-	-	-	12	90	-	90	-	-	-	-
5	Plant energy budget	-	-	-	-	-	47	7	54	-	54	-	-	-	-
6	NRC ISFSI Fees	-	-	-	-	-	1,269	127	1,396	1,396	-	-	-	-	-
7	Emergency Planning Fees	-	-	-	-	-	453	45	498	498	-	-	-	-	-
8	Site Security Cost	-	-	-	-	-	2,033	305	2,338	-	2,338	-	-	-	-
Subtotal Undistributed Costs Period 5		-	1,776	-	-	-	9,306	1,301	12,382	3,847	8,535	-	-	-	-
Staff Costs															
DOC Staff Cost		-	-	-	-	-	2,369	355	2,725	-	2,725	-	-	-	-
Utility Staff Cost		-	-	-	-	-	4,319	648	4,967	4,470	497	-	-	-	-
TOTAL PERIOD 5		-	12,165	37	14	533	17,096	4,256	34,100	12,528	21,572	3,709	-	-	-
TOTAL COST TO DECOMMISSION		11,815	47,295	6,425	3,617	70,280	216,559	72,926	428,917	400,657	28,260	120,260	14,701	408	13,664,970 650

Total cost to decommission with	20.49% contingency:	\$ 428,917,221
Total NRC license termination cost is	93.41% or	\$ 400,656,829
Non-nuclear demolition cost is	6.59% or	\$ 28,260,398
Total site radwaste volume buried		135,369 cubic feet
Total site radwaste weight buried		13,664,970 pounds
Total 10CFR61 greater than class C waste buried		650 cubic feet
Total scrap metal released from St. Lucie Unit 1 site		19,264 tons
Total craft labor requirements		1,172,136 person hours

NOTES:

- 1) This activity is performed by the decommissioning staff following plant shutdown; the costs for this are included in this period's staff cost
- 2) This activity, while performed after final plant shutdown, is considered part of operations and therefore no decommissioning costs are included for this activity.

TABLE C-2
ST. LUCIE PLANT - UNIT 2
DECON DECOMMISSIONING COST ESTIMATE
(Thousands of 1998 Dollars)

ID Number	Activity Description	Decon	Remove	Pack	Ship	Burial	Other	Contingency	Total	NRC LicTerm	Site Restore	Burial site			10 CFR 61	
												A CF	B CF	C CF	pounds	GTCC Cu Ft
PERIOD 1																
1	Prepare preliminary decommissioning cost	-	-	-	-		56	8	64	64	-		-	-		-
2	Notification of Cessation of Operations								Note 1							
3	Remove fuel & source material								Note 2							
4	Notification of Permanent Defueling								Note 1							
5	Deactivate plant systems & process waste								Note 1							
6	Prepare and submit PSDAR	-	-	-	-		86	13	98	98	-		-	-		-
7	Review plant dwgs & specs	-	-	-	-		197	30	226	226	-		-	-		-
8	Perform detailed rad survey								Note 1							
9	Estimate by-product inventory	-	-	-	-		43	6	49	49	-		-	-		-
10	End product description	-	-	-	-		43	6	49	49	-		-	-		-
11	Detailed by-product inventory	-	-	-	-		56	8	64	64	-		-	-		-
12	Define major work sequence	-	-	-	-		321	48	369	369	-		-	-		-
13	Perform SER and EA	-	-	-	-		133	20	152	152	-		-	-		-
14	Perform Site-Specific Cost Study	-	-	-	-		214	32	246	246	-		-	-		-
15	Prepare/submit License Termination Plan	-	-	-	-		175	26	201	201	-		-	-		-
16	Receive NRC approval of termination plan								Note 1							
Activity Specifications																
17.1	Plant & temporary facilities	-	-	-	-		210	32	242	218	24		-	-		-
17.2	Plant systems	-	-	-	-		178	27	205	184	20		-	-		-
17.3	NSSS Decontamination Flush	-	-	-	-		21	3	25	25	-		-	-		-
17.4	Reactor internals	-	-	-	-		304	46	349	349	-		-	-		-
17.5	Reactor vessel	-	-	-	-		278	42	320	320	-		-	-		-
17.6	Biological shield	-	-	-	-		21	3	25	25	-		-	-		-
17.7	Steam generators	-	-	-	-		133	20	153	153	-		-	-		-
17.8	Reinforced concrete	-	-	-	-		68	10	79	-	39		-	-		-
17.9	Turbine & condenser	-	-	-	-		34	5	39	-	39		-	-		-
17.10	Plant structures & buildings	-	-	-	-		133	20	153	77	77		-	-		-
17.11	Waste management	-	-	-	-		197	30	226	226	-		-	-		-
17.12	Facility & site closeout	-	-	-	-		38	6	44	22	22		-	-		-
17	Total	-	-	-	-		1,617	243	1,860	1,638	222		-	-		-
Planning & Site Preparations																
18	Prepare dismantling sequence	-	-	-	-		103	15	118	118	-		-	-		-
19	Plant prep. & temp. svces	-	-	-	-		1,895	284	2,180	2,180	-		-	-		-
20	Design water clean-up system	-	-	-	-		60	9	69	69	-		-	-		-
21	Rigging/Cont. Cntrl Envlps/tooling/etc.	-	-	-	-		1,604	241	1,845	1,845	-		-	-		-
22	Procure casks/liners & containers	-	-	-	-		53	8	60	60	-		-	-		-
Detailed Work Procedures																
23.1	Plant systems	-	-	-	-		202	30	233	209	23		-	-		-
23.2	NSSS Decontamination Flush	-	-	-	-		43	6	49	49	-		-	-		-
23.3	Reactor internals	-	-	-	-		107	16	123	123	-		-	-		-
23.4	Remaining buildings	-	-	-	-		58	9	66	17	50		-	-		-
23.5	CRD cooling assembly	-	-	-	-		43	6	49	49	-		-	-		-
23.6	CRD housings & ICI tubes	-	-	-	-		43	6	49	49	-		-	-		-
23.7	Incore instrumentation	-	-	-	-		43	6	49	49	-		-	-		-
23.8	Reactor vessel	-	-	-	-		155	23	179	179	-		-	-		-
23.9	Facility closeout	-	-	-	-		51	8	59	30	30		-	-		-
23.10	Missile shields	-	-	-	-		19	3	22	22	-		-	-		-
23.11	Biological shield	-	-	-	-		51	8	59	59	-		-	-		-
23.12	Steam generators	-	-	-	-		197	30	226	226	-		-	-		-
23.13	Reinforced concrete	-	-	-	-		43	6	49	25	25		-	-		-
23.14	Turbine & condensers	-	-	-	-		133	20	153	-	153		-	-		-
23.15	Auxiliary building	-	-	-	-		117	18	134	121	13		-	-		-
23.16	Reactor building	-	-	-	-		117	18	134	121	13		-	-		-
23	Total	-	-	-	-		1,421	213	1,635	1,327	307		-	-		-

TABLE C-2
ST. LUCIE PLANT - UNIT 2
DECON DECOMMISSIONING COST ESTIMATE
(Thousands of 1998 Dollars)

ID Number	Activity Description	Decon	Remove	Pack	Ship	Burial	Other	Contingency	Total	NRC LicTerm	Site Restore	Burial site			10 CFR 61	
												A CF	B CF	C CF	pounds	GTCC Cu Ft
24	Decon primary loop	573	-	-	-	-	-	287	860	860	-	-	-	-	-	-
25	Asbestos removal program	-	724	129	4	807	23	400	2,087	1,470	617	2,242	-	-	-	-
Period 1 Additional Costs																
26	Site Characterization Survey	-	-	-	-	-	605	91	695	695	-	-	-	-	-	-
Subtotal Period 1 Activity Costs		573	724	129	4	807	8,703	1,988	12,929	11,782	1,146	2,242	-	-	-	-
Period 1 Undistributed Costs																
1	Decon equipment	488	-	-	-	-	-	73	561	561	-	-	-	-	-	-
2	Decon supplies	29	-	-	-	-	-	7	37	37	-	-	-	-	-	-
3	DOC staff relocation expenses	-	837	-	-	-	-	126	963	963	-	-	-	-	-	-
4	Process liquid waste	99	-	313	303	3,795	-	1,075	5,586	5,586	-	-	5,286	-	862,611	-
5	Insurance	-	-	-	-	-	2,096	210	2,306	2,306	-	-	-	-	-	-
6	Property taxes	-	-	-	-	-	591	59	650	650	-	-	-	-	-	-
7	Health physics supplies	-	265	-	-	-	-	66	332	332	-	-	-	-	-	-
8	Heavy equipment rental	-	209	-	-	-	-	31	240	240	-	-	-	-	-	-
9	Small tool allowance	-	10	-	-	-	-	2	12	12	-	-	-	-	-	-
10	Disposal of DAW generated	-	-	17	4	824	-	208	1,054	1,054	-	2,675	-	-	184,692	-
11	Plant energy budget	-	-	-	-	-	523	78	601	601	-	-	-	-	-	-
12	Fuel storage capital expenditures	-	-	-	-	-	33,363	5,004	38,367	38,367	-	-	-	-	-	-
13	NRC ISFSI Fees	-	-	-	-	-	212	21	233	233	-	-	-	-	-	-
14	NRC Fees	-	-	-	-	-	303	30	334	334	-	-	-	-	-	-
15	Emergency Planning Fees	-	-	-	-	-	76	8	83	83	-	-	-	-	-	-
16	Site Security Cost	-	-	-	-	-	712	107	818	818	-	-	-	-	-	-
17	Fixed Overhead	-	-	-	-	-	1,123	169	1,292	1,292	-	-	-	-	-	-
Subtotal Undistributed Costs Period 1		616	1,321	330	308	4,619	38,998	7,274	53,467	53,467	-	2,675	5,286	-	1,047,303	-
Staff Costs																
DOC Staff Cost		-	-	-	-	-	5,338	801	6,139	6,139	-	-	-	-	-	-
Utility Staff Cost		-	-	-	-	-	18,589	2,788	21,378	21,378	-	-	-	-	-	-
TOTAL PERIOD 1 COST		1,189	2,045	459	312	5,426	71,628	12,852	93,912	92,766	1,146	4,917	5,286	-	1,047,303	-

TABLE C-2
ST. LUCIE PLANT - UNIT 2
DECON DECOMMISSIONING COST ESTIMATE
(Thousands of 1998 Dollars)

ID	Activity Description	Decon	Remove	Pack	Ship	Burial	Other	Contingncy	Total	NRC LicTerm	Site Restore	Burial site			10 CFR 61	
Number												A CF	B CF	C CF	pounds	GTCC Cu Ft
PERIOD 2																
Nuclear Steam Supply System Removal																
27.1	Reactor Coolant Piping	28	41	4	4	137	-	60	274	274	-	332	-	-	31,028	-
27.2	Pressurizer Relief Tank	4	19	1	1	26	-	13	63	63	-	89	-	-	5,824	-
27.3	Reactor Coolant Pumps & Molors	82	44	28	23	3,131	-	841	4,149	4,149	-	5,772	-	-	711,700	-
27.4	Pressurizer	19	27	4	8	1,059	-	283	1,399	1,399	-	2,127	-	-	240,755	-
27.5	Steam Generators	112	613	2,045	1,956	4,568	-	1,850	11,145	11,145	-	19,034	-	-	2,524,482	-
27.6	CRDMs/ClIs/Service Structure Removal	100	60	75	15	301	-	150	700	700	-	3,213	-	-	87,528	-
27.7	Reactor Vessel Internals	56	1,290	2,934	352	4,086	-	3,860	12,579	12,579	-	1,441	612	408	265,498	-
27.8	Vessel & Internals GTCC Disposal	-	-	-	-	13,290	-	6,645	19,935	19,935	-	-	-	-	-	655
27.9	Reactor Vessel	135	3,340	217	289	7,332	-	6,366	17,680	17,680	-	4,847	2,096	-	983,277	-
27	Totals	537	5,434	5,308	2,648	33,931	-	20,067	67,925	67,925	-	36,855	2,708	408	4,850,092	655
28	Remove spent fuel racks	249	24	-	-	99	186	183	742	742	-	321	-	-	35,640	-
Removal of Major Equipment																
29	Main Turbine/Generator	-	46	-	-	-	-	7	53	-	53	-	-	-	-	-
30	Main Condensers	-	199	-	-	-	-	30	229	-	229	-	-	-	-	-
Disposal of Plant Systems																
31.1	Air Evacuation	-	4	-	-	-	-	1	4	-	4	-	-	-	-	-
31.2	Air Evacuation - Insulated	-	16	-	-	-	-	2	19	-	19	-	-	-	-	-
31.3	Auxiliary Steam - Insulated	-	8	-	-	-	-	1	10	-	10	-	-	-	-	-
31.4	Chemical & Volume Control	91	72	-	-	301	-	139	603	603	-	937	-	-	68,497	-
31.5	Chemical & Volume Control - Insulated	923	542	-	-	750	-	785	3,000	3,000	-	1,294	-	-	170,414	-
31.6	Chemical Feed	-	2	-	-	-	-	0	2	-	2	-	-	-	-	-
31.7	Chemical Feed - Insulated	-	1	-	-	-	-	0	1	-	1	-	-	-	-	-
31.8	Circulating & Intake Cooling Water	-	138	-	-	-	-	21	158	-	158	-	-	-	-	-
31.9	Component Cooling	-	46	-	-	-	-	7	53	-	53	-	-	-	-	-
31.10	Component Cooling - RCA	64	147	-	-	-	-	54	266	266	-	-	-	-	-	-
31.11	Condensate	-	101	-	-	-	-	15	116	-	116	-	-	-	-	-
31.12	Condensate - Insulated	-	59	-	-	-	-	9	68	-	68	-	-	-	-	-
31.13	Condensate Recovery	-	2	-	-	-	-	0	3	-	3	-	-	-	-	-
31.14	Condensate Recovery - Insulated	-	0	-	-	-	-	0	0	-	0	-	-	-	-	-
31.15	Condensate Recovery - Insulated - RCA	0	0	-	-	-	-	0	1	1	-	0	-	-	-	-
31.16	Condensate Recovery - RCA	1	4	-	-	-	-	1	6	6	-	-	-	-	-	-
31.17	Condenser Tube Cleaning	-	19	-	-	-	-	3	22	-	22	-	-	-	-	-
31.18	Contnrmnt Spray & Refueling Water	-	283	-	-	318	304	196	1,100	1,100	-	697	-	-	72,173	-
31.19	Contnrmnt Spray & Refueling Water - Ins	-	170	-	-	689	-	215	1,074	1,074	-	1,342	-	-	156,703	-
31.20	Demineralized Makeup Water	-	3	-	-	-	-	0	4	-	4	-	-	-	-	-
31.21	Demineralized Makeup Water - RCA	1	2	-	-	-	-	1	4	4	-	-	-	-	-	-
31.22	Domestic/Makeup/Service Water	-	4	-	-	-	-	1	5	-	5	-	-	-	-	-
31.23	Domestic/Makeup/Service Water - RCA	4	9	-	-	-	-	3	16	16	-	-	-	-	-	-
31.24	Domestic/Makeup/Service Water-Ins	-	0	-	-	-	-	0	0	-	0	-	-	-	-	-
31.25	Domestic/Makeup/Service Water-Ins - RCA	0	1	-	-	-	-	0	1	1	-	-	-	-	-	-
31.28	Electrical - Clean	-	1,799	-	-	-	-	270	2,069	-	2,069	-	-	-	-	-
31.27	Electrical - Contaminated	-	936	-	-	32	127	261	1,356	1,356	-	63	-	-	7,213	-
31.28	Electrical - Decontaminated	211	1,737	-	-	-	-	366	2,313	2,313	-	-	-	-	-	-
31.29	Emergency Diesel Generator	-	48	-	-	-	-	7	55	-	55	-	-	-	-	-
31.30	Emergency Diesel Generator - Insulated	-	5	-	-	-	-	1	6	-	6	-	-	-	-	-
31.31	Extraction Steam	-	42	-	-	-	-	6	48	-	48	-	-	-	-	-
31.32	Extraction Steam - Insulated	-	47	-	-	-	-	7	54	-	54	-	-	-	-	-
31.33	Feedwater - Insulated	-	64	-	-	-	-	10	73	-	73	-	-	-	-	-
31.34	Feedwater - Insulated - RCA	8	17	-	-	-	-	6	31	31	-	-	-	-	-	-
31.35	Fire Protection	-	27	-	-	-	-	4	31	-	31	-	-	-	-	-
31.36	Fire Protection - Insulated	-	3	-	-	-	-	0	3	-	3	-	-	-	-	-
31.37	Fire Protection - Insulated - RCA	1	2	-	-	-	-	1	3	3	-	-	-	-	-	-
31.38	Fire Protection - RCA	9	21	-	-	-	-	8	38	38	-	-	-	-	-	-

TABLE C-2
ST. LUCIE PLANT - UNIT 2
DECON DECOMMISSIONING COST ESTIMATE
(Thousands of 1998 Dollars)

ID	Activity Description	Decon	Remove	Pack	Ship	Burial	Other	Contingency	Total	NRC LicTerm	Site Restore	Burial site			10 CFR 61 GTCC Cu Ft
Number												A CF	B CF	C CF	pounds
Disposal of Plant Systems (continued)															
31.39	Fuel Pool	127	95	-	-	364	-	178	764	764	-	719	-	-	82,755
31.40	Fuel Pool - Insulated	85	66	-	-	128	-	91	370	370	-	234	-	-	29,062
31.41	HVAC	-	247	-	-	-	-	37	284	-	284	-	-	-	-
31.42	HVAC - Contaminated	-	1,445	-	-	468	794	597	3,304	3,304	-	922	-	-	106,417
31.43	Heater Drain & Vents - Insulated	-	112	-	-	-	-	17	128	-	128	-	-	-	-
31.44	Hydrogen Sampling	-	35	-	-	117	-	38	190	190	-	223	-	-	26,621
31.45	Integrated Leak Rate Testing	-	29	-	-	72	-	25	127	127	-	137	-	-	16,387
31.46	Main Steam - Insulated	-	102	-	-	-	-	15	117	-	117	-	-	-	-
31.47	Main Steam - Insulated - RCA	8	18	-	-	-	-	7	32	32	-	-	-	-	-
31.48	Misc Bulk Gas Supply	-	8	-	-	-	-	1	9	-	9	-	-	-	-
31.49	Misc Bulk Gas Supply - RCA	2	5	-	-	-	-	1	8	8	-	-	-	-	-
31.50	Miscellaneous	-	1	-	-	-	-	0	1	-	1	-	-	-	-
31.51	Miscellaneous - RCA	1	2	-	-	-	-	1	4	4	-	-	-	-	-
31.52	Post Accident Sampling	-	2	-	-	1	-	1	3	3	-	1	-	-	186
31.53	Post Accident Sampling - Insulated	-	17	-	-	7	-	6	30	30	-	12	-	-	1,672
31.54	Primary Water	-	98	-	-	56	66	48	268	268	-	140	-	-	12,690
31.55	Primary Water - Insulated	-	2	-	-	3	-	1	7	7	-	6	-	-	699
31.56	RCP Oil Collection	10	6	-	-	11	-	10	38	38	-	20	-	-	2,608
31.57	Radiation Monitoring	-	16	-	-	15	-	8	39	39	-	26	-	-	3,447
31.58	Reactor Coolant - Insulated	20	46	-	-	92	-	44	202	202	-	161	-	-	20,994
31.59	Refueling Equipment	-	82	-	-	87	0	42	211	211	-	172	-	-	19,681
31.60	SGBT Blowdown - Insulated	-	495	-	-	340	130	228	1,193	1,193	-	753	-	-	77,223
31.61	SGBT Blowdown - Ins - RCA	7	16	-	-	-	-	6	29	29	-	-	-	-	-
31.62	SGBT Blowdown - RCA	8	26	-	-	-	-	8	41	41	-	-	-	-	-
31.63	SGBT Miscellaneous - RCA	2	8	-	-	-	-	2	12	12	-	-	-	-	-
31.64	SGBT Waste Management	32	38	-	-	193	-	74	337	337	-	616	-	-	43,845
31.65	SGBT Waste Management - Insulated	48	51	-	-	80	-	57	236	236	-	152	-	-	18,169
31.66	Safety Injection	-	156	-	-	231	141	118	647	647	-	462	-	-	52,540
31.67	Safety Injection - Insulated	-	756	-	-	1,505	-	565	2,826	2,826	-	2,720	-	-	341,947
31.68	Sampling	-	5	-	-	-	-	1	6	-	6	-	-	-	-
31.69	Sampling - Insulated	-	7	-	-	-	-	1	8	-	8	-	-	-	-
31.70	Sampling - Insulated - RCA	5	15	-	-	-	-	5	24	24	-	-	-	-	-
31.71	Sampling - RCA	5	12	-	-	-	-	4	21	21	-	-	-	-	-
31.72	Secondary Side Wet Layup	-	7	-	-	-	-	1	8	-	8	-	-	-	-
31.73	Secondary Side Wet Layup - Ins	-	9	-	-	-	-	1	10	-	10	-	-	-	-
31.74	Secondary Side Wet Layup - Ins - RCA	2	5	-	-	-	-	2	9	9	-	-	-	-	-
31.75	Secondary Side Wet Layup - RCA	1	5	-	-	-	-	1	7	7	-	-	-	-	-
31.76	Service & Instrument Air	-	11	-	-	-	-	2	12	-	12	-	-	-	-
31.77	Service & Instrument Air - Ins	-	5	-	-	-	-	1	6	-	6	-	-	-	-
31.78	Service & Instrument Air - Ins - RCA	8	22	-	-	-	-	7	37	37	-	-	-	-	-
31.79	Service & Instrument Air - RCA	5	14	-	-	-	-	5	24	24	-	-	-	-	-
31.80	Sodium Hypochlorite	-	24	-	-	-	-	4	27	-	27	-	-	-	-
31.81	Spent Fuel	3	7	-	-	33	-	12	55	55	-	65	-	-	7,500
31.82	Spent Fuel - Ins	3	2	-	-	2	-	3	10	10	-	3	-	-	468
31.83	Steam Gen Blowdown Cooling	-	9	-	-	-	-	1	10	-	10	-	-	-	-
31.84	Steam Gen Blowdown Cooling - Ins - RCA	11	24	-	-	-	-	9	44	44	-	-	-	-	-
31.85	Steam Gen Blowdown Cooling - Insulated	-	1	-	-	-	-	0	1	-	1	-	-	-	-
31.86	Steam Gen Blowdown Cooling - RCA	15	31	-	-	-	-	12	58	58	-	-	-	-	-
31.87	Steam Generator Blowdown	-	15	-	-	35	-	13	64	64	-	60	-	-	8,052
31.88	Steam Generator Blowdown - Insulated	-	49	-	-	77	-	32	158	158	-	148	-	-	17,606
31.89	Turbine	-	1	-	-	-	-	0	1	-	1	-	-	-	-
31.90	Turbine Cooling Water	-	31	-	-	-	-	5	36	-	36	-	-	-	-
31.91	Turbine Cooling Water - Insulated	-	22	-	-	-	-	3	25	-	25	-	-	-	-
31.92	Turbine Lube Oil & Diesel Oil	-	32	-	-	-	-	5	37	-	37	-	-	-	-
31.93	Waste Management	770	522	-	-	1,804	-	966	4,061	4,061	-	5,181	-	-	409,911
31.94	Waste Management - Insulated	2,239	1,247	-	-	1,748	-	1,868	7,102	7,102	-	2,978	-	-	397,314
31 Totals		4,728	12,493	-	-	9,560	1,562	7,591	35,934	32,403	3,531	20,243	-	-	2,172,794
32	Erect scaffolding for systems removal	-	905	-	-	26	85	245	1,261	1,261	-	83	-	-	9,243

000162

TABLE C-2
ST. LUCIE PLANT - UNIT 2
DECON DECOMMISSIONING COST ESTIMATE
(Thousands of 1998 Dollars)

ID Number	Activity Description	Decon	Remove	Pack	Ship	Burial	Other	Contingncy	Total	NRC LicTerm	Site Restore	Burial site			10 CFR 61	
												A CF	B CF	C CF	pounds	GTCC Cu Ft
Decontamination of Site Buildings																
33.1	Reactor Building	665	375	54	22	3,430	155	1,316	6,016	6,016	-	7,301	-	-	821,464	-
33.2	East EP Pond	-	3	26	11	1,095	-	279	1,414	1,414	-	3,555	-	-	373,005	-
33.3	Fuel Handling Building	225	214	2	1	92	124	208	866	866	-	298	-	-	31,807	-
33.4	Primary Water Tank & Pump - Contaminated	1	4	2	1	119	-	31	158	158	-	240	-	-	27,384	-
33.5	Reactor Auxiliary Building	309	25	15	6	612	26	320	1,311	1,311	-	1,987	-	-	207,788	-
33.6	Steam Generator Blowdown Treatment	97	1	5	2	204	1	100	409	409	-	661	-	-	69,339	-
33	Totals	1,297	621	103	42	5,552	305	2,254	10,174	10,174	-	14,042	-	-	1,530,787	-
34	ORISE confirmatory survey	-	-	-	-	-	1,064	319	1,383	1,383	-	-	-	-	-	-
35	Terminate license	-	-	-	-	-	-	-	Note 1	-	-	-	-	-	-	-
Period 2 Additional Costs																
36	License Termination Survey	-	-	-	-	-	5,692	854	6,546	6,546	-	-	-	-	-	-
37	Mixed/Hazardous Waste	-	-	-	-	-	3,884	583	4,466	4,466	-	-	-	-	-	-
Subtotal Period 2 Activity Costs		6,812	19,723	5,411	2,690	49,168	12,778	32,132	128,713	124,900	3,813	71,545	2,708	408	8,598,556	655
Period 2 Undistributed Costs																
1	Oecon equipment	488	-	-	-	-	-	73	561	561	-	-	-	-	-	-
2	Decon supplies	613	-	-	-	-	-	153	767	767	-	-	-	-	-	-
3	DOC staff relocation expenses	-	837	-	-	-	-	126	963	963	-	-	-	-	-	-
4	Process liquid waste	456	-	240	356	2,652	-	968	4,672	4,672	-	-	4,358	-	602,714	-
5	Insurance	-	-	-	-	-	1,565	156	1,721	1,721	-	-	-	-	-	-
6	Property taxes	-	-	-	-	-	2,503	250	2,753	2,478	275	-	-	-	-	-
7	Health physics supplies	-	3,167	-	-	-	-	792	3,959	3,959	-	-	-	-	-	-
8	Heavy equipment rental	-	9,747	-	-	-	-	1,462	11,209	10,088	1,121	-	-	-	-	-
9	Small tool allowance	-	318	-	-	-	-	48	365	329	37	-	-	-	-	-
10	Pipe cutting equipment	-	749	-	-	-	-	112	862	862	-	-	-	-	-	-
11	Decon rig	974	-	-	-	-	-	146	1,120	1,120	-	-	-	-	-	-
12	Disposal of DAW generated	-	-	72	21	4,134	-	1,044	5,271	5,271	-	13,421	-	-	886,929	-
13	Decommissioning Equipment Disposition	-	-	-	-	83	-	277	62	422	-	270	-	-	30,000	-
14	Plant energy budget	-	-	-	-	-	3,077	462	3,539	3,185	354	-	-	-	-	-
15	NRC ISFSI Fees	-	-	-	-	-	899	90	989	989	-	-	-	-	-	-
16	NRC Fees	-	-	-	-	-	1,619	162	1,781	1,781	-	-	-	-	-	-
17	Emergency Planning Fees	-	-	-	-	-	321	32	353	353	-	-	-	-	-	-
18	Site Security Cost	-	-	-	-	-	7,013	1,052	8,065	8,065	-	-	-	-	-	-
19	Fixed Overhead	-	-	-	-	-	4,762	714	5,476	5,476	-	-	-	-	-	-
20	Radwaste Processing Skids	-	-	-	-	-	421	63	484	484	-	-	-	-	-	-
Subtotal Undistributed Costs Period 2		2,531	14,819	312	377	6,869	22,457	7,968	55,333	53,547	1,787	13,692	4,358	-	1,519,643	-
Staff Costs																
DOC Staff Cost		-	-	-	-	-	35,629	5,344	40,973	40,973	-	-	-	-	-	-
Utility Staff Cost		-	-	-	-	-	74,584	11,188	85,771	85,771	-	-	-	-	-	-
TOTAL PERIOD 2		9,343	34,541	5,723	3,066	56,037	145,448	56,633	310,791	305,191	5,600	85,236	7,066	408	10,118,199	655

TABLE C-2
ST. LUCIE PLANT - UNIT 2
DECON DECOMMISSIONING COST ESTIMATE
(Thousands of 1998 Dollars)

ID											NRC	Site	Burial site			10 CFR 61
Number	Activity Description	Decon	Remove	Pack	Ship	Burial	Other	Contingncy	Total	LicTerm	Restore	A CF	B CF	C CF	pounds	GTCC Cu Ft
PERIOD 3																
Demolition of Remaining Site Buildings																
38.1	Reactor Building	-	5,119	-	-	-	-	768	5,887	883	5,004	-	-	-	-	-
38.2	Fuel Handling Building	-	682	-	-	-	-	102	784	78	705	-	-	-	-	-
38.3	Intake Structure & CWS	-	5,018	-	-	-	-	753	5,771	-	5,771	-	-	-	-	-
38.4	Miscellaneous Structures	-	2,573	-	-	-	-	386	2,959	-	2,959	-	-	-	-	-
38.5	Primary Water Tank & Pump - Contaminated	-	2	-	-	-	-	0	2	-	2	-	-	-	-	-
38.6	Reactor Auxiliary Building	-	1,251	-	-	-	-	188	1,439	144	1,295	-	-	-	-	-
38.7	Steam Generator Blowdown Treatment	-	363	-	-	-	-	54	418	21	397	-	-	-	-	-
38.8	Turbine Building	-	825	-	-	-	-	124	948	-	948	-	-	-	-	-
38.9	Turbine Pedestal	-	440	-	-	-	-	66	506	-	506	-	-	-	-	-
38	Totals	-	16,273	-	-	-	-	2,441	18,714	1,126	17,587	-	-	-	-	-
Site Closeout Activities																
39	Grade & landscape site	-	81	-	-	-	-	12	93	-	93	-	-	-	-	-
40	Final report to NRC	-	-	-	-	-	67	10	77	77	-	-	-	-	-	-
Period 3 Additional Costs																
41	ISFSI License Termination	-	735	37	14	533	859	452	2,629	2,629	-	3,709	-	-	-	-
42	ISFSI Demolition and Site Restoration	-	159	-	-	-	87	53	299	299	-	-	-	-	-	-
Subtotal Period 3 Activity Costs		-	17,248	37	14	533	1,012	2,967	21,811	4,131	17,680	3,709	-	-	-	-
Period 3 Undistributed Costs																
1	Insurance	-	-	-	-	-	1,775	178	1,953	1,953	-	-	-	-	-	-
2	Property taxes	-	-	-	-	-	3,729	373	4,102	-	4,102	-	-	-	-	-
3	Heavy equipment rental	-	1,677	-	-	-	-	252	1,929	-	1,929	-	-	-	-	-
4	Small tool allowance	-	110	-	-	-	-	17	127	-	127	-	-	-	-	-
5	Plant energy budget	-	-	-	-	-	53	8	61	-	61	-	-	-	-	-
6	NRC ISFSI Fees	-	-	-	-	-	1,269	127	1,396	1,396	-	-	-	-	-	-
7	Emergency Planning Fees	-	-	-	-	-	453	45	498	498	-	-	-	-	-	-
8	Site Security Cost	-	-	-	-	-	2,262	339	2,601	-	2,601	-	-	-	-	-
Subtotal Undisributed Costs Period 3		-	1,787	-	-	-	9,541	1,338	12,666	3,847	8,819	-	-	-	-	-
Staff Costs																
DOC Staff Cost		-	-	-	-	-	4,762	714	5,476	-	5,476	-	-	-	-	-
Utility Staff Cost		-	-	-	-	-	7,386	1,108	8,494	7,645	849	-	-	-	-	-
TOTAL PERIOD 3		-	19,035	37	14	533	22,702	6,128	48,448	15,623	32,826	3,709	-	-	-	-

491000

TABLE C-2
ST. LUCIE PLANT - UNIT 2
DECON DECOMMISSIONING COST ESTIMATE
(Thousands of 1998 Dollars)

ID Number	Activity Description	Decon	Remove	Pack	Ship	Burial	Other	Contingency	Total	NRC LicTerm	Site Restore	Burial site			10 CFR 61	
												A CF	B CF	C CF	pounds	GTCC Cu Ft
TOTAL COST TO DECOMMISSION		10,532	55,622	6,219	3,392	61,995	239,778	75,612	453,151	413,580	39,571	93,862	12,352	408	11,165,502	655
Total cost to decommission with		20.03% contingency: \$ 453,151,198														
Total NRC license termination cost is		91.27%	or	\$ 413,579,710												
Non-nuclear demolition cost is		8.73%	or	\$ 39,571,488												
Total site radwaste volume buried						106,622	cubic feet									
Total site radwaste weight buried						11,165,502	pounds									
Total 10CFR61 greater than class C waste buried						655	cubic feet									
Total scrap metal released from site						21,126	tons									
Total craft labor requirements						1,430,088	person hours									

NOTES:

- 1) This activity is performed by the decommissioning staff following plant shutdown; the costs for this are included in this period's staff cost.
- 2) This activity, while performed after final plant shutdown, is considered part of operations and therefore no decommissioning costs are included for this activity.

000165

TABLE C-3
ST LUCIE PLANT - UNIT 1
SAFSTOR STATION DECOMMISSIONING COST ESTIMATE
(Thousands of 1998 Dollars)

ID Number	Activity Description	Decon	Remove	Pack	Ship	Burial	Other	Contingency	Total	NRC LicTerm	Site Restore.	Burial Site			10 CFR 61		
												A CF	B CF	C CF	pounds	GTCC	Cu Ft
PERIOD 1: Mothballing Activities																	
1	Prepare preliminary decommissioning cost	-	-	-	-		130	20	150	150	-	-	-	-		-	
2	Notification of Cessation of Operations								Note 1								
3	Remove fuel & source material								Note 2								
4	Notification of Permanent Defueling								Note 1								
5	Deactivate plant systems & process waste								Note 1								
6	Prepare and submit PSDAR	-	-	-	-		200	30	230	230	-		-	-		-	
7	Review plant dwgs & specs.	-	-	-	-		130	20	150	150	-		-	-		-	
8	Perform detailed rad survey								Note 1								
9	Estimate by-product inventory	-	-	-	-		100	15	115	115	-		-	-		-	
10	End product description	-	-	-	-		100	15	115	115	-		-	-		-	
11	Detailed by-product inventory	-	-	-	-		150	23	173	173	-		-	-		-	
12	Define major work sequence	-	-	-	-		100	15	115	115	-		-	-		-	
13	Perform SER and EA	-	-	-	-		310	47	357	357	-		-	-		-	
14	Perform Site-Specific Cost Study	-	-	-	-		500	75	575	575	-		-	-		-	
15	Prepare/submit License Termination Plan	-	-	-	-		410	61	471	471	-		-	-		-	
16	Receive NRC approval of termination plan								Note 1								
Activity Specifications																	
17.1	Prepare plant and facilities for SAFSTOR	-	-	-	-		492	74	566	566	-		-	-		-	
17.2	Plant systems	-	-	-	-		417	63	479	479	-		-	-		-	
17.3	Plant structures and buildings	-	-	-	-		312	47	359	359	-		-	-		-	
17.4	Waste management	-	-	-	-		200	30	230	230	-		-	-		-	
17.5	Facility and site dormancy	-	-	-	-		200	30	230	230	-		-	-		-	
17	Total	-	-	-	-		1,621	243	1,864	1,864	-		-	-		-	
Detailed Work Procedures																	
18.1	Plant systems	-	-	-	-		473	71	544	544	-		-	-		-	
18.2	Facility closeout & dormancy	-	-	-	-		120	18	138	138	-		-	-		-	
18	Total	-	-	-	-		593	89	682	682	-		-	-		-	
19	Procure vacuum drying system	-	-	-	-		10	2	12	12	-		-	-		-	
20	Drain/de-energize non-cont. systems	-	-	-	-		-	-	Note 1	-	-		-	-		-	
21	Drain & dry NSSS	-	-	-	-		-	-	Note 1	-	-		-	-		-	
22	Drain/de-energize contaminated systems	-	-	-	-		-	-	Note 1	-	-		-	-		-	
23	Decon/secure contaminated systems	-	-	-	-		-	-	Note 1	-	-		-	-		-	
Decontamination of Site Buildings																	
24.1	Reactor Building	576	-	-	-	-	-	288	865	865	-		-	-	-	-	
24.2	Fuel Handling Building	214	-	-	-	-	-	107	322	322	-		-	-	-	-	
24.3	Reactor Auxiliary	244	-	-	-	-	-	122	366	366	-		-	-	-	-	
24	Totals	1,035	-	-	-	-	-	517	1,552	1,552	-		-	-	-	-	
25	Prepare support equipment for storage	-	279	-	-	-	-	42	321	321	-		-	-		-	
26	Install containment pressure equal. lines	-	19	-	-	-	-	3	22	22	-		-	-		-	
27	Interim survey prior to dormancy	-	-	-	-	-	320	48	369	369	-		-	-		-	
28	Secure building accesses	-	-	-	-	-	-	-	Note 1	-	-		-	-		-	
29	Prepare & submit interim report	-	-	-	-	-	58	9	67	67	-		-	-		-	
Period 1 Additional Costs																	
30	Mixed/Hazardous Waste	-	-	-	-	-	3,884	583	4,466	4,466	-		-	-		-	
Subtotal Period 1 Activity Costs		1,035	298	-	-	-	8,616	1,854	11,803	11,803	-		-	-	-	-	

TABLE C-3
ST LUCIE PLANT - UNIT 1
SAFSTOR STATION DECOMMISSIONING COST ESTIMATE
(Thousands of 1998 Dollars)

ID	Activity Description	Decon	Remove	Pack	Ship	Burial	Other	Contingency	Total	NRC LicTerm	Site Restore.	Burial Site			10 CFR 61
Number												A CF	B CF	C CF	GTCC Cu Ft
Period 1 Undistributed Costs															
1	Decon equipment	488	-	-	-	-	-	73	561	561	-	-	-	-	-
2	Decon supplies	470	-	-	-	-	-	118	588	588	-	-	-	-	-
3	Process liquid waste	245	-	89	156	926	-	386	1,802	1,802	-	-	1,669	-	210,421
4	Insurance	-	-	-	-	-	2,098	210	2,307	2,307	-	-	-	-	-
5	Property taxes	-	-	-	-	-	591	59	650	650	-	-	-	-	-
6	Health physics supplies	-	287	-	-	-	-	72	359	359	-	-	-	-	-
7	Small tool allowance	-	15	-	-	-	-	2	17	17	-	-	-	-	-
8	Disposal of DAW generated	-	-	18	5	884	-	224	1,130	1,130	-	2,870	-	-	198,153
9	Plant energy budget	-	-	-	-	-	486	73	559	559	-	-	-	-	-
10	Fuel storage capital expenditures	-	-	-	-	-	17,888	2,683	20,571	20,571	-	-	-	-	-
11	NRC ISFSI Fees	-	-	-	-	-	212	21	234	234	-	-	-	-	-
12	NRC Fees	-	-	-	-	-	304	30	334	334	-	-	-	-	-
13	Emergency Planning Fees	-	-	-	-	-	76	8	83	83	-	-	-	-	-
14	Site Security Cost	-	-	-	-	-	1,000	150	1,150	1,150	-	-	-	-	-
15	Fixed Overhead	-	-	-	-	-	1,124	169	1,293	1,293	-	-	-	-	-
Subtotal Undistributed Costs Period 1		1,204	303	107	161	1,810	23,778	4,278	31,640	31,640	-	2,870	1,669	-	408,574
Staff Costs															
DOC Staff Cost		-	-	-	-	-	-	-	-	-	-	-	-	-	-
Utility Staff Cost		-	-	-	-	-	17,780	2,667	20,447	20,447	-	-	-	-	-
TOTAL COST TO SAFSTOR		2,238	600	107	161	1,810	50,174	8,799	63,890	63,890	-	2,870	1,669	-	408,574
Total cost to SAFSTOR with 15.97% contingency.		63,889,613													
Total site radwaste volume buried		4,540 cubic feet													
Total craft labor requirements		45,448 person hours													

TABLE C-3
ST LUCIE PLANT - UNIT 1
SAFSTOR STATION DECOMMISSIONING COST ESTIMATE
(Thousands of 1998 Dollars)

ID	Activity Description	Decon	Remove	Pack	Ship	Burial	Other	Contingency	Total	NRC LicTerm	Site Restore.	Burial Site			10 CFR 61	
Number												A CF	B CF	C CF	pounds	GTCC Cu Ft
PERIOD 2: SAFSTOR Dormancy Activities																
1	Quarterly inspection									Note 1						
2	Semi-annual environmental survey									Note 1						
3	Prepare reports									Note 1						
4	Health physics supplies	-	-	-	-		46	11	57	57	-		-	-		-
5	Insurance	-	-	-	-		118	12	130	130	-		-	-		-
6	Property taxes	-	-	-	-		394	39	433	433	-		-	-		-
7	Disposal of contaminated solid waste	-	-	1	0	29	-	7	38	38	-	102	-	-		-
8	Bituminous roof replacement	-	-	-	-		1	0	1	1	-		-	-		-
9	Maintenance supplies	-	-	-	-		99	25	123	123	-		-	-		-
10	Plant energy budget	-	-	-	-		78	12	90	90	-		-	-		-
11	NRC ISFSI Fees	-	-	-	-		61	6	67	67	-		-	-		-
12	NRC Fees	-	-	-	-		167	17	184	184	-		-	-		-
13	Emergency Planning Fees	-	-	-	-		22	2	24	24	-		-	-		-
14	Site Security Cost	-	-	-	-		288	43	331	331	-		-	-		-
15	Fixed Overhead	-	-	-	-		75	11	86	86	-		-	-		-
16	Site maintenance staff	-	-	-	-		1,525	229	1,754	1,754	-		-	-		-
PERIOD 2 ANNUAL MAINTENANCE TOTALS		-	-	1	0	29	2,873	415	3,319	3,319	-	102	-	-	-	-

Total cost SAFSTOR dormancy with 51,9792 years equals 172,496,930

Total site radwaste volume buried 5,297 cubic feet

891000

TABLE C-3
ST LUCIE PLANT - UNIT 1
SAFSTOR STATION DECOMMISSIONING COST ESTIMATE
(Thousands of 1998 Dollars)

ID	Activity Description	Decon	Remove	Pack	Ship	Burial	Other	Contingency	Total	NRC LicTerm	Site Restore.	Burial Site			10 CFR 61
Number												A CF	B CF	C CF	pounds GTCC Cu Ft
PERIOD 3															
1	Review plant dwgs & specs.	-	-	-	-		460	69	529	529	-	-	-	-	-
2	Perform detailed rad survey								Note 1						
3	End product description	-	-	-	-		100	15	115	115	-	-	-	-	-
4	Detailed by-product inventory	-	-	-	-		130	20	150	150	-	-	-	-	-
5	Define major work sequence	-	-	-	-		750	113	863	863	-	-	-	-	-
6	Perform SER and EA	-	-	-	-		310	47	357	357	-	-	-	-	-
7	Perform Site-Specific Cost Study	-	-	-	-		500	75	575	575	-	-	-	-	-
8	Prepare/submit License Termination Plan	-	-	-	-		410	61	471	471	-	-	-	-	-
9	Receive NRC approval of termination plan								Note 1						
Activity Specifications															
10.1	Re-activate plant & temporary facilities	-	-	-	-		737	111	848	763	85	-	-	-	-
10.2	Plant systems	-	-	-	-		417	63	479	431	48	-	-	-	-
10.3	Reactor internals	-	-	-	-		710	107	817	817	-	-	-	-	-
10.4	Reactor vessel	-	-	-	-		650	98	748	748	-	-	-	-	-
10.5	Biological shield	-	-	-	-		50	8	58	58	-	-	-	-	-
10.6	Steam generators	-	-	-	-		312	47	359	359	-	-	-	-	-
10.7	Reinforced concrete	-	-	-	-		160	24	184	92	92	-	-	-	-
10.8	Turbine & condenser	-	-	-	-		80	12	92	-	92	-	-	-	-
10.9	Plant structures & buildings	-	-	-	-		312	47	359	179	179	-	-	-	-
10.10	Waste management	-	-	-	-		460	69	529	529	-	-	-	-	-
10.11	Facility & site closeout	-	-	-	-		90	14	104	52	52	-	-	-	-
10	Total	-	-	-	-		3,978	597	4,574	4,026	548	-	-	-	-
Planning & Site Preparations															
11	Prepare dismantling sequence	-	-	-	-		240	36	276	276	-	-	-	-	-
12	Plant prep. & temp. svces	-	-	-	-		1,895	284	2,180	2,180	-	-	-	-	-
13	Design water clean-up system	-	-	-	-		140	21	161	161	-	-	-	-	-
14	Rigging/Conf. Cntrl Envlps/tooling/etc.	-	-	-	-		1,604	241	1,845	1,845	-	-	-	-	-
15	Procure casks/liners & containers	-	-	-	-		123	18	141	141	-	-	-	-	-
Detailed Work Procedures															
16.1	Plant systems	-	-	-	-		473	71	544	490	54	-	-	-	-
16.2	Reactor internals	-	-	-	-		250	38	288	288	-	-	-	-	-
16.3	Remaining buildings	-	-	-	-		135	20	155	39	116	-	-	-	-
16.4	CRD cooling assembly	-	-	-	-		100	15	115	115	-	-	-	-	-
16.5	CRD housings & ICI tubes	-	-	-	-		100	15	115	115	-	-	-	-	-
16.6	Incore instrumentation	-	-	-	-		100	15	115	115	-	-	-	-	-
16.7	Reactor vessel	-	-	-	-		363	54	417	417	-	-	-	-	-
16.8	Facility closeout	-	-	-	-		120	18	138	69	69	-	-	-	-
16.9	Missile shields	-	-	-	-		45	7	52	52	-	-	-	-	-
16.10	Biological shield	-	-	-	-		120	18	138	138	-	-	-	-	-
16.11	Steam generators	-	-	-	-		460	69	529	529	-	-	-	-	-
16.12	Reinforced concrete	-	-	-	-		100	15	115	58	58	-	-	-	-
16.13	Turbine & condensers	-	-	-	-		312	47	359	-	359	-	-	-	-
16.14	Auxiliary building	-	-	-	-		273	41	314	283	31	-	-	-	-
16.15	Reactor building	-	-	-	-		273	41	314	283	31	-	-	-	-
16	Total	-	-	-	-		3,224	484	3,708	2,989	719	-	-	-	-
17	Asbestos removal program	-	724	129	4	807	23	400	2,087	1,470	617	2,242	-	-	-

691000

TABLE C-3
ST LUCIE PLANT - UNIT 1
SAFSTOR STATION DECOMMISSIONING COST ESTIMATE
(Thousands of 1998 Dollars)

ID Number	Activity Description	Decon	Remove	Pack	Ship	Burial	Other	Contingency	Total	NRC LicTerm	Site Restore.	Burial Site			10 CFR 61	
												A CF	B CF	C CF	pounds	GTCC Cu Ft
Period 3 Additional Costs																
18	Site Characterization Survey	-	-	-	-	-	403	60	463	463	-	-	-	-	-	-
Subtotal Period 3 Activity Costs		-	724	129	4	807	14,291	2,540	18,495	16,611	1,884	2,242	-	-	-	-
Period 3 Undistributed Costs																
1	DOC staff relocation expenses	-	837	-	-	-	-	126	963	963	-	-	-	-	-	-
2	Insurance	-	-	-	-	-	285	28	313	313	-	-	-	-	-	-
3	Property taxes	-	-	-	-	-	593	59	653	653	-	-	-	-	-	-
4	Health physics supplies	-	264	-	-	-	-	66	330	330	-	-	-	-	-	-
5	Heavy equipment rental	-	444	-	-	-	-	67	510	510	-	-	-	-	-	-
6	Disposal of DAW generated	-	-	18	5	887	-	224	1,135	1,135	-	2,881	-	-	198,924	-
7	Plant energy budget	-	-	-	-	-	516	77	594	594	-	-	-	-	-	-
8	NRC Fees	-	-	-	-	-	305	30	335	335	-	-	-	-	-	-
9	Site Security Cost	-	-	-	-	-	715	107	822	822	-	-	-	-	-	-
10	Fixed Overhead	-	-	-	-	-	1,129	169	1,298	1,298	-	-	-	-	-	-
Subtotal Undistributed Costs Period 3		-	1,545	18	5	887	3,542	955	6,952	6,952	-	2,881	-	-	198,924	-
Staff Costs																
DOC Staff Cost		-	-	-	-	-	5,345	802	6,147	6,147	-	-	-	-	-	-
Utility Staff Cost		-	-	-	-	-	16,458	2,469	18,927	18,927	-	-	-	-	-	-
TOTAL PERIOD 3 COST		-	2,269	148	9	1,694	39,636	6,765	50,522	48,638	1,884	5,123	-	-	198,924	-

000170

TABLE C-3
ST LUCIE PLANT - UNIT 1
SAFSTOR STATION DECOMMISSIONING COST ESTIMATE
(Thousands of 1998 Dollars)

ID	Activity Description	Decon	Remove	Pack	Ship	Burial	Other	Contingency	Total	NRC LicTerm	Site Restore.	Burial Site			10 CFR 61 pounds	GTCC Cu Ft
Number												A CF	B CF	C CF		
PERIOD 4																
Nuclear Steam Supply System Removal																
19.1	Reactor Coolant Piping	30	45	4	5	153	-	66	302	302	-	371	-	-	34,669	-
19.2	Pressurizer Relief Tank	3	17	1	1	26	-	12	60	60	-	89	-	-	5,824	-
19.3	Reactor Coolant Pumps & Motors	72	39	28	20	2,730	-	734	3,622	3,622	-	5,776	-	-	620,400	-
19.4	Pressurizer	17	27	4	8	1,053	-	280	1,387	1,387	-	2,134	-	-	239,212	-
19.5	Steam Generators	98	613	2,045	1,956	4,568	-	1,842	11,124	11,124	-	19,034	-	-	2,524,482	-
19.6	CRDMs/CIs/Service Structure Removal	79	51	62	12	254	-	124	582	582	-	2,907	-	-	75,041	-
19.7	Reactor Vessel Internals	43	1,149	2,881	211	2,633	-	2,973	9,889	9,889	-	1,441	524	408	264,053	-
19.8	Vessel & Internals GTCC Disposal	-	-	-	-	13,290	-	6,645	19,935	19,935	-	-	-	-	-	650
19.9	Reactor Vessel	119	3,319	217	289	4,856	-	5,103	13,904	13,904	-	4,847	2,096	-	983,277	-
19	Totals	461	5,260	5,242	2,501	29,562	-	17,779	60,805	60,805	-	36,599	2,620	408	4,746,957	650
20	Remove spent fuel racks	238	26	-	-	106	201	182	754	754	-	346	-	-	38,385	-
Removal of Major Equipment																
21	Main Turbine/Generator	-	49	-	-	-	-	7	56	-	56	-	-	-	-	-
22	Main Condensers	-	199	-	-	-	-	30	229	-	229	-	-	-	-	-
Disposal of Plant Systems																
23.1	Air Evacuation	-	4	-	-	-	-	1	4	-	4	-	-	-	-	-
23.2	Air Evacuation - Insulated	-	15	-	-	-	-	2	17	-	17	-	-	-	-	-
23.3	Auxiliary Steam - Insulated	-	12	-	-	-	-	2	14	-	14	-	-	-	-	-
23.4	Chemical & Volume Control	-	57	-	-	288	-	86	431	431	-	912	-	-	65,546	-
23.5	Chemical & Volume Control - Insulated	-	331	-	-	515	-	212	1,059	1,059	-	894	-	-	117,281	-
23.6	Chemical Feed	-	1	-	-	-	-	0	2	-	2	-	-	-	-	-
23.7	Chemical Feed - Insulated	-	1	-	-	-	-	0	1	-	1	-	-	-	-	-
23.8	Circulating & Intake Cooling Water	-	125	-	-	-	-	19	144	-	144	-	-	-	-	-
23.9	Component Cooling	-	39	-	-	-	-	6	45	-	45	-	-	-	-	-
23.10	Component Cooling - RCA	-	101	-	-	-	-	15	116	116	-	-	-	-	-	-
23.11	Condensate	-	81	-	-	-	-	12	93	-	93	-	-	-	-	-
23.12	Condensate - Insulated	-	46	-	-	-	-	7	52	-	52	-	-	-	-	-
23.13	Condensate Polish Filter Demin	-	12	-	-	-	-	2	14	-	14	-	-	-	-	-
23.14	Condensate Polish Filter Demin - Ins	-	37	-	-	-	-	6	43	-	43	-	-	-	-	-
23.15	Condensate Recovery	-	2	-	-	-	-	0	2	-	2	-	-	-	-	-
23.16	Condensate Recovery - Insulated	-	0	-	-	-	-	0	0	-	0	-	-	-	-	-
23.17	Condensate Recovery - Insulated - RCA	-	0	-	-	-	-	0	0	0	-	-	-	-	-	-
23.18	Condensate Recovery - RCA	-	3	-	-	-	-	0	4	4	-	-	-	-	-	-
23.19	Condenser Tube Cleaning	-	17	-	-	-	-	3	20	-	20	-	-	-	-	-
23.20	Contnmt Spray & Refueling Water	-	245	-	-	2,483	-	682	3,411	3,411	-	6,404	-	-	564,410	-
23.21	Contnmt Spray & Refueling Water - Ins	-	142	-	-	649	-	198	988	988	-	1,259	-	-	147,467	-
23.22	Demineralized Makeup Water	-	8	-	-	-	-	1	9	-	9	-	-	-	-	-
23.23	Demineralized Makeup Water - RCA	-	4	-	-	-	-	1	5	5	-	-	-	-	-	-
23.24	Domestic/Makeup/Service Water	-	92	-	-	-	-	14	106	-	106	-	-	-	-	-
23.25	Domestic/Makeup/Service Water - RCA	-	31	-	-	-	-	5	36	36	-	-	-	-	-	-
23.26	Domestic/Makeup/Service Water-Ins	-	2	-	-	-	-	0	2	-	2	-	-	-	-	-
23.27	Domestic/Makeup/Service Water-Ins-RCA	-	3	-	-	-	-	1	4	4	-	-	-	-	-	-
23.28	Electrical - Clean	-	1,024	-	-	-	-	154	1,177	-	1,177	-	-	-	-	-
23.29	Electrical - Contaminated	-	408	-	-	18	72	117	615	615	-	36	-	-	4,061	-
23.30	Electrical - Decontaminated	-	773	-	-	-	-	116	888	888	-	-	-	-	-	-
23.31	Emergency Diesel Generator	-	38	-	-	-	-	6	43	-	43	-	-	-	-	-
23.32	Emergency Diesel Generator - Insulated	-	3	-	-	-	-	1	4	-	4	-	-	-	-	-
23.33	Extraction Steam	-	42	-	-	-	-	6	48	-	48	-	-	-	-	-
23.34	Extraction Steam - Insulated	-	42	-	-	-	-	6	48	-	48	-	-	-	-	-
23.35	Feedwater - Insulated	-	45	-	-	-	-	7	51	-	51	-	-	-	-	-
23.36	Feedwater - Insulated - RCA	-	10	-	-	-	-	1	11	11	-	-	-	-	-	-
23.37	Fire Protection	-	36	-	-	-	-	5	41	-	41	-	-	-	-	-
23.38	Fire Protection - Insulated	-	3	-	-	-	-	1	4	-	4	-	-	-	-	-
23.39	Fire Protection - Insulated - RCA	-	1	-	-	-	-	0	1	1	-	-	-	-	-	-
23.40	Fire Protection - RCA	-	7	-	-	-	-	1	8	8	-	-	-	-	-	-

TABLE C-3
ST LUCIE PLANT - UNIT 1
SAFSTOR STATION DECOMMISSIONING COST ESTIMATE
(Thousands of 1998 Dollars)

ID	Activity Description	Decon	Remove	Pack	Ship	Burial	Other	Contingency	Total	NRC LicTerm	Site Restore.	Burial Site			10 CFR 61 GTCC Cu Ft
Number												A CF	B CF	C CF	pounds
Disposal of Plant Systems (continued)															
23.41	Fuel Pool	-	55	-	-	231	-	72	358	358	-	465	-	-	52,522
23.42	Fuel Pool - Insulated	-	35	-	-	66	-	25	126	126	-	119	-	-	14,974
23.43	HVAC	-	61	-	-	-	-	9	70	-	70	-	-	-	-
23.44	HVAC - Contaminated	-	1,239	-	-	383	787	524	2,933	2,933	-	751	-	-	86,998
23.45	Heater Drain & Vent - Insulated	-	93	-	-	-	-	14	108	-	108	-	-	-	-
23.46	Hydrogen Sampling	-	25	-	-	108	-	33	167	167	-	209	-	-	24,624
23.47	Integrated Leak Rate Testing	-	22	-	-	60	-	20	102	102	-	111	-	-	13,585
23.48	Main Steam - Insulated	-	98	-	-	-	-	15	113	-	113	-	-	-	-
23.49	Main Steam - Insulated - RCA	-	14	-	-	-	-	2	17	17	-	-	-	-	-
23.50	Misc Bulk Gas	-	10	-	-	-	-	1	11	-	11	-	-	-	-
23.51	Misc Bulk Gas - RCA	-	5	-	-	-	-	1	5	5	-	-	-	-	-
23.52	Miscellaneous	-	5	-	-	-	-	1	6	-	6	-	-	-	-
23.53	Miscellaneous - RCA	-	3	-	-	-	-	1	4	4	-	-	-	-	-
23.54	Neutralization Basin Recirculation	-	9	-	-	-	-	1	10	-	10	-	-	-	-
23.55	Post Accident Sampling	-	8	-	-	33	-	10	51	51	-	64	-	-	7,400
23.56	Post Accident Sampling - Insulated	-	26	-	-	24	-	13	63	63	-	41	-	-	5,543
23.57	Primary Water	-	85	-	-	56	78	47	266	266	-	140	-	-	12,728
23.58	Primary Water - Insulated	-	2	-	-	3	-	1	6	6	-	6	-	-	689
23.59	RCP Oil Collection	-	1	-	-	1	0	0	2	2	-	2	-	-	175
23.60	Radiation Monitoring	-	13	-	-	13	-	7	33	33	-	22	-	-	3,004
23.61	Reactor Coolant - Insulated	-	41	-	-	94	-	34	169	169	-	163	-	-	21,388
23.62	Refueling Equipment	-	58	-	-	268	-	81	407	407	-	533	-	-	60,959
23.63	SGBTf Blowdown - Insulated	-	90	-	-	139	-	57	286	286	-	239	-	-	31,555
23.64	SGBTf HVAC	-	197	-	-	36	141	79	453	453	-	71	-	-	8,136
23.65	SGBTf Misc - RCA	-	1	-	-	-	-	0	1	1	-	-	-	-	-
23.66	SGBTf Waste Management	-	4	-	-	6	-	2	12	12	-	10	-	-	1,335
23.67	SGBTf Waste Management - Insulated	-	36	-	-	55	-	23	114	114	-	92	-	-	12,527
23.68	Safety Injection	-	112	-	-	1,443	-	389	1,943	1,943	-	3,247	-	-	327,912
23.69	Safety Injection - Insulated	-	405	-	-	985	-	347	1,737	1,737	-	1,786	-	-	223,859
23.70	Sampling	-	4	-	-	-	-	1	5	-	5	-	-	-	-
23.71	Sampling - Insulated	-	4	-	-	-	-	1	5	-	5	-	-	-	-
23.72	Sampling - Insulated - RCA	-	7	-	-	-	-	1	8	8	-	-	-	-	-
23.73	Sampling - RCA	-	7	-	-	-	-	1	8	8	-	-	-	-	-
23.74	Secondary Side Wet Layup	-	6	-	-	-	-	1	7	-	7	-	-	-	-
23.75	Secondary Side Wet Layup - Ins	-	7	-	-	-	-	1	9	-	9	-	-	-	-
23.76	Secondary Side Wet Layup - Ins - RCA	-	4	-	-	-	-	1	4	4	-	-	-	-	-
23.77	Secondary Side Wet Layup - RCA	-	4	-	-	-	-	1	4	4	-	-	-	-	-
23.78	Service & Instrument Air	-	13	-	-	-	-	2	16	-	16	-	-	-	-
23.79	Service & Instrument Air - Ins	-	7	-	-	-	-	1	8	-	8	-	-	-	-
23.80	Service & Instrument Air - Ins - RCA	-	24	-	-	-	-	4	28	28	-	-	-	-	-
23.81	Service & Instrument Air - RCA	-	17	-	-	-	-	3	20	20	-	-	-	-	-
23.82	Steam Gen Blowdown Cooling	-	8	-	-	-	-	1	9	-	9	-	-	-	-
23.83	Steam Gen Blowdown Cooling - Ins - RCA	-	15	-	-	-	-	2	17	17	-	-	-	-	-
23.84	Steam Gen Blowdown Cooling - Insulated	-	1	-	-	-	-	0	1	-	1	-	-	-	-
23.85	Steam Gen Blowdown Cooling - RCA	-	19	-	-	-	-	3	22	22	-	-	-	-	-
23.86	Steam Generator Blowdown	-	17	-	-	67	-	21	105	105	-	136	-	-	15,145
23.87	Steam Generator Blowdown - Insulated	-	46	-	-	81	-	32	159	159	-	148	-	-	18,323
23.88	Turbine	-	1	-	-	-	-	0	1	-	1	-	-	-	-
23.89	Turbine Cooling Water	-	28	-	-	-	-	4	33	-	33	-	-	-	-
23.90	Turbine Cooling Water - Insulated	-	18	-	-	-	-	3	20	-	20	-	-	-	-
23.91	Turbine Lube Oil & Diesel Oil	-	35	-	-	-	-	5	40	-	40	-	-	-	-
23.92	Waste Management	-	364	-	-	1,759	-	531	2,654	2,654	-	5,390	-	-	399,788
23.93	Waste Management - Insulated	-	643	-	-	1,016	-	415	2,073	2,073	-	1,751	-	-	230,863
23.94	Water Treatment	-	34	-	-	-	-	5	39	-	39	-	-	-	-
23.95	Water Treatment - Insulated	-	19	-	-	-	-	3	22	-	22	-	-	-	-
23 Totals		-	7,948	-	-	10,880	1,078	4,544	24,451	21,933	2,517	25,000	-	-	2,472,795
24	Erect scaffolding for systems removal	-	698	-	-	21	71	191	981	981	-	70	-	-	7,726

TABLE C-3
ST LUCIE PLANT - UNIT 1
SAFSTOR STATION DECOMMISSIONING COST ESTIMATE
(Thousands of 1998 Dollars)

ID Number	Activity Description	Decon	Remove	Pack	Ship	Burial	Other	Contingency	Total	NRC LicTerm	Site Restore.	Burial Site			10 CFR 61	
												A CF	B CF	C CF	pounds	GTCC Cu Ft
Decontamination of Site Buildings																
25.1	Reactor Building	588	331	54	22	3,430	155	1,266	5,846	5,846	-	7,301	-	-	821,464	-
25.2	Fuel Handling Building	198	189	2	1	92	124	188	794	794	-	298	-	-	31,807	-
25.3	Primary Water Tank Foundation - Contam	1	10	66	27	2,806	-	715	3,624	3,624	-	8,964	-	-	942,684	-
25.4	Reactor Auxiliary	274	22	15	6	612	26	301	1,255	1,255	-	1,987	-	-	207,788	-
25.5	Refueling Water Storage Tank - Contam	1	8	16	7	787	-	202	1,021	1,021	-	2,237	-	-	239,387	-
25	Totals	1,062	559	153	62	7,727	304	2,673	12,539	12,539	-	20,786	-	-	2,243,130	-
26	ORISE confirmatory survey	-	-	-	-	-	1,064	319	1,383	1,383	-	-	-	-	-	-
27	Terminate license	-	-	-	-	-	-	-	Note 1	-	-	-	-	-	-	-
Period 4 Additional Costs																
28	License Termination Survey	-	-	-	-	-	3,840	576	4,416	4,416	-	-	-	-	-	-
29	ISFSI License Termination	-	735	37	14	533	859	452	2,629	2,629	-	3,709	-	-	-	-
Subtotal Period 4 Activity Costs		1,761	15,475	5,431	2,577	48,829	7,416	26,753	108,242	105,440	2,802	86,508	2,620	408	9,508,993	650
Period 4 Undistributed Costs																
1	Decon equipment	488	-	-	-	-	-	73	561	561	-	-	-	-	-	-
2	Decon supplies	539	-	-	-	-	-	135	674	674	-	-	-	-	-	-
3	DOC staff relocation expenses	-	837	-	-	-	-	126	963	963	-	-	-	-	-	-
4	Process liquid waste	270	-	98	172	1,020	-	426	1,986	1,986	-	-	1,839	-	231,810	-
5	Insurance	-	-	-	-	-	754	75	829	829	-	-	-	-	-	-
6	Property taxes	-	-	-	-	-	1,975	197	2,172	1,955	217	-	-	-	-	-
7	Health physics supplies	-	2,015	-	-	-	-	504	2,518	2,518	-	-	-	-	-	-
8	Heavy equipment rental	-	7,773	-	-	-	-	1,166	8,939	8,045	894	-	-	-	-	-
9	Small tool allowance	-	181	-	-	-	-	27	208	187	21	-	-	-	-	-
10	Pipe cutting equipment	-	749	-	-	-	-	112	862	862	-	-	-	-	-	-
11	Disposal of DAW generated	-	-	61	16	2,955	-	747	3,778	3,778	-	9,593	-	-	662,272	-
12	Decommissioning Equipment Disposition	-	-	-	-	83	277	62	422	422	-	270	-	-	30,000	-
13	Plant energy budget	-	-	-	-	-	1,223	183	1,406	1,265	141	-	-	-	-	-
14	NRC Fees	-	-	-	-	-	1,148	115	1,262	1,262	-	-	-	-	-	-
15	Site Security Cost	-	-	-	-	-	3,675	551	4,226	4,226	-	-	-	-	-	-
16	Fixed Overhead	-	-	-	-	-	3,757	564	4,320	4,320	-	-	-	-	-	-
17	Radwaste Processing Skids	-	-	-	-	-	570	85	655	655	-	-	-	-	-	-
Subtotal Undistributed Costs Period 4		1,297	11,555	159	188	4,058	13,377	5,149	35,782	34,510	1,273	9,863	1,839	-	924,082	-
Staff Costs																
DOC Staff Cost		-	-	-	-	-	21,154	3,173	24,328	24,328	-	-	-	-	-	-
Utility Staff Cost		-	-	-	-	-	31,787	4,768	36,555	36,555	-	-	-	-	-	-
TOTAL PERIOD 4		3,058	27,030	5,590	2,765	52,887	73,734	39,843	204,907	200,833	4,075	96,372	4,459	408	10,433,075	650

000173

TABLE C-3
ST LUCIE PLANT - UNIT 1
SAFSTOR STATION DECOMMISSIONING COST ESTIMATE
(Thousands of 1998 Dollars)

ID	Activity Description	Decon	Remove	Pack	Ship	Burial	Other	Contingency	Total	NRC LicTerm	Site Restore.	Burial Site			10 CFR 61 GTCC Cu Ft
Number												A CF	B CF	C CF	pounds
PERIOD 5															
Demolition of Remaining Site Buildings															
30.1	Reactor Building	-	5,108	-	-	-	-	766	5,875	881	4,993	-	-	-	-
30.2	Fuel Handling Building	-	682	-	-	-	-	102	784	78	705	-	-	-	-
30.3	Intake & CWS	-	294	-	-	-	-	44	338	-	338	-	-	-	-
30.4	Miscellaneous Structures	-	798	-	-	-	-	120	918	-	918	-	-	-	-
30.5	Primary Water Tank Foundation - Contam	-	2	-	-	-	-	0	2	-	2	-	-	-	-
30.6	Reactor Auxiliary	-	1,251	-	-	-	-	188	1,439	144	1,295	-	-	-	-
30.7	Refueling Water Storage Tank - Contam	-	5	-	-	-	-	1	5	-	5	-	-	-	-
30.8	Turbine Building	-	834	-	-	-	-	125	959	-	959	-	-	-	-
30.9	Turbine Pedestal	-	440	-	-	-	-	66	506	-	506	-	-	-	-
30	Totals	-	9,414	-	-	-	-	1,412	10,826	1,103	9,722	-	-	-	-
Site Closeout Activities															
31	Grade & landscape site	-	81	-	-	-	-	12	93	-	93	-	-	-	-
32	Final report to NRC	-	-	-	-	-	156	23	179	179	-	-	-	-	-
Period 5 Additional Costs															
33	ISFSI Demolition and Site Restoration	-	159	-	-	-	87	53	299	299	-	-	-	-	-
Subtotal Period 5 Activity Costs															
		-	9,654	-	-	-	243	1,500	11,397	1,582	9,815	-	-	-	-
Period 5 Undistributed Costs															
1	Insurance	-	-	-	-	-	111	11	123	123	-	-	-	-	-
2	Property taxes	-	-	-	-	-	471	47	519	-	519	-	-	-	-
3	Heavy equipment rental	-	1,702	-	-	-	-	255	1,957	-	1,957	-	-	-	-
4	Small tool allowance	-	79	-	-	-	-	12	90	-	90	-	-	-	-
5	Plant energy budget	-	-	-	-	-	47	7	54	-	54	-	-	-	-
6	Site Security Cost	-	-	-	-	-	164	25	188	-	188	-	-	-	-
Subtotal Undistributed Costs Period 5															
		-	1,780	-	-	-	794	357	2,931	123	2,808	-	-	-	-
Staff Costs															
DOC Staff Cost		-	-	-	-	-	2,375	356	2,731	-	2,731	-	-	-	-
Utility Staff Cost		-	-	-	-	-	808	121	930	837	93	-	-	-	-
TOTAL PERIOD 5															
		-	11,434	-	-	-	4,220	2,335	17,989	2,541	15,448	-	-	-	-

471000
4

TABLE C-3
ST LUCIE PLANT - UNIT 1
SAFSTOR STATION DECOMMISSIONING COST ESTIMATE
(Thousands of 1998 Dollars)

ID Number	Activity Description	Decon	Remove	Pack	Ship	Burial	Other	Contingency	Total	NRC LicTerm	Site Restore.	Burial Site				10 CFR 61
												A CF	B CF	C CF	pounds	GTCC Cu Ft
TOTAL COST TO DECOMMISSION		5,297	41,333	5,878	2,943	57,922	317,127	79,303	509,804	488,399	21,406	109,662	6,128	408	11,040,572	650

Total cost to decommission with	18.42% contingency.	\$ 509,804,268
Total NRC license termination cost is	95.80% or	\$ 488,398,554
Non-nuclear demolition cost is	4.20% or	\$ 21,405,716
Total site radwaste volume buried		116,198 cubic feet
Total site radwaste weight buried		11,040,572 pounds
Total 10CFR61 greater than class C waste buried		650 cubic feet
Total scrap metal released from St. Lucie Unit 1 site		19,264 tons
Total craft labor requirements		930,617 person hours

NOTES:

- 1) This activity is performed by the decommissioning staff following plant shutdown; the costs for this are included in this period's staff cost.
- 2) This activity, while performed after final plant shutdown, is considered part of operations and therefore no decommissioning costs are included for this activity.

000175

TABLE C-4
ST LUCIE PLANT - UNIT 2
SAFSTOR STATION DECOMMISSIONING COST ESTIMATE
(Thousands of 1998 Dollars)

ID	Activity Description	Decon	Remove	Pack	Ship	Burial	Other	Contingency	Total	NRC LicTerm	Site Restore.	Burial Site			10 CFR 61
Number												A CF	B CF	C CF	pounds GTCC Cu Ft
PERIOD 1: Mothballing Activities															
1	Prepare preliminary decommissioning cost	-	-	-	-		56	8	64	64	-	-	-	-	-
2	Notification of Cessation of Operations								Note 1						
3	Remove fuel & source material								Note 2						
4	Notification of Permanent Defueling								Note 1						
5	Deactivate plant systems & process waste								Note 1						
6	Prepare and submit PSDAR	-	-	-	-		86	13	98	98	-	-	-	-	-
7	Review plant dwgs & specs	-	-	-	-		56	8	64	64	-	-	-	-	-
8	Perform detailed rad survey								Note 1						
9	Estimate by-product inventory	-	-	-	-		43	6	49	49	-	-	-	-	-
10	End product description	-	-	-	-		43	6	49	49	-	-	-	-	-
11	Detailed by-product inventory	-	-	-	-		64	10	74	74	-	-	-	-	-
12	Define major work sequence	-	-	-	-		43	6	49	49	-	-	-	-	-
13	Perform SER and EA	-	-	-	-		133	20	152	152	-	-	-	-	-
14	Perform Site-Specific Cost Study	-	-	-	-		214	32	246	246	-	-	-	-	-
15	Prepare/submit License Termination Plan	-	-	-	-		175	26	201	201	-	-	-	-	-
16	Receive NRC approval of termination plan								Note 1						
Activity Specifications															
17.1	Prepare plant and facilities for SAFSTOR	-	-	-	-		210	32	242	242	-	-	-	-	-
17.2	Plant systems	-	-	-	-		178	27	205	205	-	-	-	-	-
17.3	Plant structures and buildings	-	-	-	-		133	20	153	153	-	-	-	-	-
17.4	Waste management	-	-	-	-		86	13	98	98	-	-	-	-	-
17.5	Facility and site dormancy	-	-	-	-		86	13	98	98	-	-	-	-	-
17	Total	-	-	-	-		693	104	797	797	-	-	-	-	-
Detailed Work Procedures															
18.1	Plant systems	-	-	-	-		202	30	233	233	-	-	-	-	-
18.2	Facility closeout & dormancy	-	-	-	-		51	8	59	59	-	-	-	-	-
18	Total	-	-	-	-		254	38	292	292	-	-	-	-	-
19	Procure vacuum drying system	-	-	-	-		4	1	5	5	-	-	-	-	-
20	Drain/de-energize non-cont. systems	-	-	-	-		-	-	Note 1	-	-	-	-	-	-
21	Drain & dry NSSS	-	-	-	-		-	-	Note 1	-	-	-	-	-	-
22	Drain/de-energize contaminated systems	-	-	-	-		-	-	Note 1	-	-	-	-	-	-
23	Decon/secure contaminated systems	-	-	-	-		-	-	Note 1	-	-	-	-	-	-
Decontamination of Site Buildings															
24.1	Reactor Building	576	-	-	-		-	288	865	865	-	-	-	-	-
24.2	Fuel Handling Building	214	-	-	-		-	107	322	322	-	-	-	-	-
24.3	Reactor Auxiliary Building	244	-	-	-		-	122	366	366	-	-	-	-	-
24.4	Steam Generator Blowdown Treatment	75	-	-	-		-	38	113	113	-	-	-	-	-
24	Totals	1,110	-	-	-		-	555	1,665	1,665	-	-	-	-	-
25	Prepare support equipment for storage	-	279	-	-		-	42	321	321	-	-	-	-	-
26	Install containment pressure equal. lines	-	19	-	-		-	3	22	22	-	-	-	-	-
27	Interim survey prior to dormancy	-	-	-	-		320	48	369	369	-	-	-	-	-
28	Secure building accesses	-	-	-	-		-	-	Note 1	-	-	-	-	-	-
29	Prepare & submit interim report	-	-	-	-		25	4	29	29	-	-	-	-	-

000176

TABLE C-4
ST LUCIE PLANT - UNIT 2
SAFSTOR STATION DECOMMISSIONING COST ESTIMATE
(Thousands of 1998 Dollars)

ID	Activity Description	Decon	Remove	Pack	Ship	Burial	Other	Contingency	Total	NRC LicTerm	Site Restore.	Burial Site			10 CFR 61 pounds	GTCC Cu Ft
Number												A CF	B CF	C CF		
Period 1 Additional Costs																
30	Mixed/Hazardous Waste	-	-	-	-	-	3,884	583	4,466	4,466	-	-	-	-	-	-
Subtotal Period 1 Activity Costs		1,110	298	-	-	-	6,091	1,513	9,012	9,012	-	-	-	-	-	-
Period 1 Undistributed Costs																
1	Decon equipment	488	-	-	-	-	-	73	561	561	-	-	-	-	-	-
2	Decon supplies	518	-	-	-	-	-	130	648	648	-	-	-	-	-	-
3	Process liquid waste	267	-	97	170	1,009	-	421	1,964	1,964	-	-	1,819	-	229,226	-
4	Insurance	-	-	-	-	-	2,098	210	2,307	2,307	-	-	-	-	-	-
5	Property taxes	-	-	-	-	-	591	59	650	650	-	-	-	-	-	-
6	Health physics supplies	-	295	-	-	-	-	74	368	368	-	-	-	-	-	-
7	Small tool allowance	-	16	-	-	-	-	2	19	19	-	-	-	-	-	-
8	Disposal of DAW generated	-	-	17	4	824	-	208	1,054	1,054	-	2,677	-	-	184,795	-
9	Plant energy budget	-	-	-	-	-	503	75	578	578	-	-	-	-	-	-
10	Fuel storage capital expenditures	-	-	-	-	-	33,363	5,004	38,367	38,367	-	-	-	-	-	-
11	NRC ISFSI Fees	-	-	-	-	-	212	21	234	234	-	-	-	-	-	-
12	NRC Fees	-	-	-	-	-	304	30	334	334	-	-	-	-	-	-
13	Emergency Planning Fees	-	-	-	-	-	76	8	83	83	-	-	-	-	-	-
14	Site Security Cost	-	-	-	-	-	712	107	819	819	-	-	-	-	-	-
15	Fixed Overhead	-	-	-	-	-	1,124	169	1,293	1,293	-	-	-	-	-	-
Subtotal Undistributed Costs Period 1		1,273	311	114	174	1,833	38,982	6,592	49,279	49,279	-	2,677	1,819	-	414,021	-
Staff Costs																
DOC Staff Cost		-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
Utility Staff Cost		-	-	-	-	-	17,780	2,667	20,447	20,447	-	-	-	-	-	-
TOTAL COST TO SAFSTOR		2,384	608	114	174	1,833	62,853	10,772	78,738	78,738	-	2,677	1,819	-	414,021	-
Total cost to SAFSTOR with 15.85% contingency:		78,737,942														
Total site radwaste volume buried		4,495 cubic feet														
Total craft labor requirements		48,529 person hours														

000177

TABLE C-4
ST LUCIE PLANT - UNIT 2
SAFSTOR STATION DECOMMISSIONING COST ESTIMATE
(Thousands of 1998 Dollars)

ID	Activity Description	Decon	Remove	Pack	Ship	Burial	Other	Contingency	Total	NRC LicTerm	Site Restore.	Burial Site			10 CFR 61	
Number												A CF	B CF	C CF	pounds	GTCC Cu Ft
PERIOD 2: SAFSTOR Dormancy Activities																
1	Quarterly Inspection									Note 1						
2	Semi-annual environmental survey									Note 1						
3	Prepare reports									Note 1						
4	Health physics supplies	-	-	-	-		46	11	57	57	-	-	-	-	-	-
5	Insurance	-	-	-	-		106	11	116	116	-	-	-	-	-	-
6	Property taxes	-	-	-	-		394	39	433	433	-	-	-	-	-	-
7	Disposal of contaminated solid waste	-	-	1	0	29	-	7	38	38	-	102	-	-	-	-
8	Bituminous roof replacement	-	-	-	-		43	6	50	50	-	-	-	-	-	-
9	Maintenance supplies	-	-	-	-		99	25	123	123	-	-	-	-	-	-
10	Plant energy budget	-	-	-	-		78	12	90	90	-	-	-	-	-	-
11	NRC ISFSI Fees	-	-	-	-		47	5	51	51	-	-	-	-	-	-
12	NRC Fees	-	-	-	-		166	17	182	182	-	-	-	-	-	-
13	Emergency Planning Fees	-	-	-	-		17	2	18	18	-	-	-	-	-	-
14	Site Security Cost	-	-	-	-		76	11	87	87	-	-	-	-	-	-
15	Fixed Overhead	-	-	-	-		75	11	86	86	-	-	-	-	-	-
16	Site maintenance staff	-	-	-	-		700	105	805	805	-	-	-	-	-	-
PERIOD 2 ANNUAL MAINTENANCE TOTALS		-	-	1	0	29	1,845	262	2,138	2,138	-	102	-	-	-	-

Total cost SAFSTOR dormancy with 46.3367 years equals 99,061,846

Total site radwaste volume buried 4,722 cubic feet

000178

TABLE C-4
ST LUCIE PLANT - UNIT 2
SAFSTOR STATION DECOMMISSIONING COST ESTIMATE
(Thousands of 1998 Dollars)

ID	Activity Description	Decon	Remove	Pack	Ship	Burial	Other	Contingency	Total	NRC LicTerm	Site Restore.	Burial Site			10 CFR 61 GTCC Cu Ft
Number												A CF	B CF	C CF	pounds
PERIOD 3															
1	Review plant dwgs & specs.	-	-	-	-		197	30	226	226	-		-	-	-
2	Perform detailed rad survey								Note 1						
3	End product description	-	-	-	-		43	6	49	49	-		-	-	-
4	Detailed by-product inventory	-	-	-	-		56	8	64	64	-		-	-	-
5	Define major work sequence	-	-	-	-		321	48	369	369	-		-	-	-
6	Perform SER and EA	-	-	-	-		133	20	152	152	-		-	-	-
7	Perform Site-Specific Cost Study	-	-	-	-		214	32	246	246	-		-	-	-
8	Prepare/submit License Termination Plan	-	-	-	-		175	26	201	201	-		-	-	-
9	Receive NRC approval of termination plan								Note 1						
Activity Specifications															
10.1	Re-activate plant & temporary facilities	-	-	-	-		315	47	362	326	36		-	-	-
10.2	Plant systems	-	-	-	-		178	27	205	184	20		-	-	-
10.3	Reactor internals	-	-	-	-		304	46	349	349	-		-	-	-
10.4	Reactor vessel	-	-	-	-		278	42	320	320	-		-	-	-
10.5	Biological shield	-	-	-	-		21	3	25	25	-		-	-	-
10.6	Steam generators	-	-	-	-		133	20	153	153	-		-	-	-
10.7	Reinforced concrete	-	-	-	-		68	10	79	39	39		-	-	-
10.8	Turbine & condenser	-	-	-	-		34	5	39	-	39		-	-	-
10.9	Plant structures & buildings	-	-	-	-		133	20	153	77	77		-	-	-
10.10	Waste management	-	-	-	-		197	30	226	226	-		-	-	-
10.11	Facility & site closeout	-	-	-	-		38	6	44	22	22		-	-	-
10	Total	-	-	-	-		1,701	255	1,956	1,722	234		-	-	-
Planning & Site Preparations															
11	Prepare dismantling sequence	-	-	-	-		103	15	118	118	-		-	-	-
12	Plant prep. & temp. svces	-	-	-	-		1,895	284	2,180	2,180	-		-	-	-
13	Design water clean-up system	-	-	-	-		60	9	69	69	-		-	-	-
14	Rigging/Cont. Cntrl Envlps/tooling/etc.	-	-	-	-		1,604	241	1,845	1,845	-		-	-	-
15	Procure casks/liners & containers	-	-	-	-		53	8	60	60	-		-	-	-
Detailed Work Procedures															
16.1	Plant systems	-	-	-	-		202	30	233	209	23		-	-	-
16.2	Reactor internals	-	-	-	-		107	16	123	123	-		-	-	-
16.3	Remaining buildings	-	-	-	-		58	9	66	17	50		-	-	-
16.4	CRD cooling assembly	-	-	-	-		43	6	49	49	-		-	-	-
16.5	CRD housings & ICI tubes	-	-	-	-		43	6	49	49	-		-	-	-
16.6	Incore instrumentation	-	-	-	-		43	6	49	49	-		-	-	-
16.7	Reactor vessel	-	-	-	-		155	23	179	179	-		-	-	-
16.8	Facility closeout	-	-	-	-		51	8	59	30	30		-	-	-
16.9	Missile shields	-	-	-	-		19	3	22	22	-		-	-	-
16.10	Biological shield	-	-	-	-		51	8	59	59	-		-	-	-
16.11	Steam generators	-	-	-	-		197	30	226	226	-		-	-	-
16.12	Reinforced concrete	-	-	-	-		43	6	49	25	25		-	-	-
16.13	Turbine & condensers	-	-	-	-		133	20	153	-	153		-	-	-
16.14	Auxiliary building	-	-	-	-		117	18	134	121	13		-	-	-
16.15	Reactor building	-	-	-	-		117	18	134	121	13		-	-	-
16	Total	-	-	-	-		1,379	207	1,586	1,278	307		-	-	-
17	Asbestos removal program	-	724	129	4	807	23	400	2,087	1,470	617	2,242	-	-	-

000179

TABLE C-4
ST LUCIE PLANT - UNIT 2
SAFSTOR STATION DECOMMISSIONING COST ESTIMATE
(Thousands of 1998 Dollars)

ID											NRC	Site	Burial Site			10 CFR 61
Number	Activity Description	Decon	Remove	Pack	Ship	Burial	Other	Contingency	Total	LicTerm	Restore.	A CF	B CF	C CF	pounds	GTCC Cu Ft
Period 3 Additional Costs																
18	Site Characterization Survey	-	-	-	-		403	60	463	463	-		-	-		-
Subtotal Period 3 Activity Costs		-	724	129	4	807	8,358	1,650	11,672	10,514	1,158	2,242	-	-		-
Period 3 Undistributed Costs																
1	DOC staff relocation expenses	-	837	-	-		-	126	963	963	-		-	-		-
2	Insurance	-	-	-	-		283	28	311	311	-		-	-		-
3	Property taxes	-	-	-	-		590	59	649	649	-		-	-		-
4	Health physics supplies	-	263	-	-		-	66	329	329	-		-	-		-
5	Heavy equipment rental	-	441	-	-		-	66	507	507	-		-	-		-
6	Disposal of DAW generated	-	-	17	4	823	-	208	1,053	1,053	-	2,672	-	-	184,487	-
7	Plant energy budget	-	-	-	-		530	79	609	609	-		-	-		-
8	NRC Fees	-	-	-	-		303	30	333	333	-		-	-		-
9	Site Security Cost	-	-	-	-		424	64	487	487	-		-	-		-
10	Fixed Overhead	-	-	-	-		1,122	168	1,291	1,291	-		-	-		-
Subtotal Undistribnuted Costs Period 3		-	1,542	17	4	823	3,252	895	6,533	6,533	-	2,672	-	-	184,487	-
Staff Costs																
	DOC Staff Cost	-	-	-	-		3,506	526	4,032	4,032	-		-	-		-
	Utility Staff Cost	-	-	-	-		7,727	1,159	8,886	8,886	-		-	-		-
TOTAL PERIOD 3 COST		-	2,266	146	9	1,630	22,843	4,230	31,123	29,965	1,158	4,914	-	-	184,487	-

081000

TABLE C-4
ST LUCIE PLANT - UNIT 2
SAFSTOR STATION DECOMMISSIONING COST ESTIMATE
(Thousands of 1998 Dollars)

ID	Activity Description	Decon	Remove	Pack	Ship	Burial	Other	Contingency	Total	NRC LicTerm	Site Restore.	Burial Site			10 CFR 61 GTCC Cu Ft
Number												A CF	B CF	C CF	pounds
PERIOD 4															
Nuclear Steam Supply System Removal															
19.1	Reactor Coolant Piping	25	37	4	4	137	-	57	263	263	-	332	-	-	31,028
19.2	Pressurizer Relief Tank	3	17	1	1	26	-	12	60	60	-	89	-	-	5,824
19.3	Reactor Coolant Pumps & Motors	72	39	28	23	3,131	-	835	4,128	4,128	-	5,772	-	-	711,700
19.4	Pressurizer	17	27	4	8	1,059	-	281	1,396	1,396	-	2,127	-	-	240,755
19.5	Steam Generators	99	613	2,045	1,956	4,568	-	1,843	11,125	11,125	-	19,034	-	-	2,524,482
19.6	CRDMs/ICIs/Service Structure Removal	88	59	75	15	301	-	143	681	681	-	3,213	-	-	87,528
19.7	Reactor Vessel Internals	43	1,149	2,881	211	2,715	-	3,014	10,013	10,013	-	1,441	524	408	264,053
19.8	Vessel & Internals GTCC Disposal	-	-	-	-	13,290	-	6,645	19,935	19,935	-	-	-	-	655
19.9	Reactor Vessel	119	3,319	217	289	4,860	-	5,105	13,909	13,909	-	4,847	2,096	-	983,277
19	Totals	465	5,259	5,254	2,506	30,088	-	17,936	61,508	61,508	-	36,855	2,620	408	4,848,647
20	Remove spent fuel racks	221	24	-	-	99	186	169	700	700	-	321	-	-	35,640
Removal of Major Equipment															
21	Main Turbine/Generator	-	46	-	-	-	-	7	53	-	53	-	-	-	-
22	Main Condensers	-	199	-	-	-	-	30	229	-	229	-	-	-	-
Disposal of Plant Systems															
23.1	Air Evacuation	-	4	-	-	-	-	1	4	-	4	-	-	-	-
23.2	Air Evacuation - Insulated	-	16	-	-	-	-	2	19	-	19	-	-	-	-
23.3	Auxiliary Steam - Insulated	-	8	-	-	-	-	1	10	-	10	-	-	-	-
23.4	Chemical & Volume Control	-	64	-	-	301	-	91	457	457	-	937	-	-	68,497
23.5	Chemical & Volume Control - Insulated	-	484	-	-	750	-	308	1,542	1,542	-	1,294	-	-	170,414
23.6	Chemical Feed	-	2	-	-	-	-	0	2	-	2	-	-	-	-
23.7	Chemical Feed - Insulated	-	1	-	-	-	-	0	1	-	1	-	-	-	-
23.8	Circulating & Intake Cooling Water	-	138	-	-	-	-	21	158	-	158	-	-	-	-
23.9	Component Cooling	-	45	-	-	-	-	7	53	-	53	-	-	-	-
23.10	Component Cooling - RCA	-	125	-	-	-	-	19	143	143	-	-	-	-	-
23.11	Condensate	-	101	-	-	-	-	15	116	-	116	-	-	-	-
23.12	Condensate - Insulated	-	59	-	-	-	-	9	68	-	68	-	-	-	-
23.13	Condensate Recovery	-	2	-	-	-	-	0	3	-	3	-	-	-	-
23.14	Condensate Recovery - Insulated	-	0	-	-	-	-	0	0	-	0	-	-	-	-
23.15	Condensate Recovery - Insulated - RCA	-	0	-	-	-	-	0	0	0	-	-	-	-	-
23.16	Condensate Recovery - RCA	-	4	-	-	-	-	1	4	4	-	-	-	-	-
23.17	Condenser Tube Cleaning	-	19	-	-	-	-	3	22	-	22	-	-	-	-
23.18	Contnmt Spray & Refueling Water	-	250	-	-	318	304	187	1,059	1,059	-	697	-	-	72,173
23.19	Contnmt Spray & Refueling Water - Ins	-	151	-	-	689	-	210	1,050	1,050	-	1,342	-	-	156,703
23.20	Demineralized Makeup Water	-	3	-	-	-	-	0	4	-	4	-	-	-	-
23.21	Demineralized Makeup Water - RCA	-	2	-	-	-	-	0	2	2	-	-	-	-	-
23.22	Domestic/Makeup/Service Water	-	4	-	-	-	-	1	5	-	5	-	-	-	-
23.23	Domestic/Makeup/Service Water - RCA	-	7	-	-	-	-	1	9	9	-	-	-	-	-
23.24	Domestic/Makeup/Service Water-Ins	-	0	-	-	-	-	0	0	-	0	-	-	-	-
23.25	Domestic/Makeup/Service Water-Ins - RCA	-	1	-	-	-	-	0	1	1	-	-	-	-	-
23.26	Electrical - Clean	-	1,799	-	-	-	-	270	2,069	-	2,069	-	-	-	-
23.27	Electrical - Contaminated	-	835	-	-	32	127	236	1,230	1,230	-	63	-	-	7,213
23.28	Electrical - Decontaminated	-	1,508	-	-	-	-	226	1,735	1,735	-	-	-	-	-
23.29	Emergency Diesel Generator	-	48	-	-	-	-	7	55	-	55	-	-	-	-
23.30	Emergency Diesel Generator - Insulated	-	5	-	-	-	-	1	6	-	6	-	-	-	-
23.31	Extraction Steam	-	42	-	-	-	-	6	48	-	48	-	-	-	-
23.32	Extraction Steam - Insulated	-	47	-	-	-	-	7	54	-	54	-	-	-	-
23.33	Feedwater - Insulated	-	64	-	-	-	-	10	73	-	73	-	-	-	-
23.34	Feedwater - Insulated - RCA	-	15	-	-	-	-	2	17	17	-	-	-	-	-
23.35	Fire Protection	-	27	-	-	-	-	4	31	-	31	-	-	-	-
23.36	Fire Protection - Insulated	-	3	-	-	-	-	0	3	-	3	-	-	-	-
23.37	Fire Protection - Insulated - RCA	-	2	-	-	-	-	0	2	2	-	-	-	-	-
23.38	Fire Protection - RCA	-	17	-	-	-	-	3	20	20	-	-	-	-	-
23.39	Fuel Pool	-	84	-	-	364	-	112	561	561	-	719	-	-	82,755
23.40	Fuel Pool - Insulated	-	59	-	-	128	-	47	233	233	-	234	-	-	29,062

TABLE C-4
ST LUCIE PLANT - UNIT 2
SAFSTOR STATION DECOMMISSIONING COST ESTIMATE
(Thousands of 1998 Dollars)

ID	Activity Description	Decon	Remove	Pack	Ship	Burial	Other	Contingency	Total	NRC LicTerm	Site Restore.	Burial Site			10 CFR 61
Number												A CF	B CF	C CF	GTCC Cu Ft
Disposal of Plant Systems (continued)															
23.41	HVAC	-	247	-	-	-	-	37	284	-	284	-	-	-	-
23.42	HVAC - Contaminated	-	1,283	-	-	468	794	557	3,102	3,102	-	922	-	-	106,417
23.43	Heater Drain & Vents - Insulated	-	112	-	-	-	-	17	128	-	128	-	-	-	-
23.44	Hydrogen Sampling	-	31	-	-	117	-	37	185	185	-	223	-	-	26,621
23.45	Integrated Leak Rate Testing	-	26	-	-	72	-	25	123	123	-	137	-	-	16,387
23.46	Main Steam - Insulated	-	102	-	-	-	-	15	117	-	117	-	-	-	-
23.47	Main Steam - Insulated - RCA	-	15	-	-	-	-	2	18	18	-	-	-	-	-
23.48	Misc Bulk Gas Supply	-	8	-	-	-	-	1	9	-	9	-	-	-	-
23.49	Misc Bulk Gas Supply - RCA	-	4	-	-	-	-	1	5	5	-	-	-	-	-
23.50	Miscellaneous	-	1	-	-	-	-	0	1	-	1	-	-	-	-
23.51	Miscellaneous - RCA	-	2	-	-	-	-	0	2	2	-	-	-	-	-
23.52	Post Accident Sampling	-	2	-	-	1	-	1	3	3	-	1	-	-	186
23.53	Post Accident Sampling - Insulated	-	15	-	-	7	-	5	27	27	-	12	-	-	1,672
23.54	Primary Water	-	86	-	-	56	66	45	254	254	-	140	-	-	12,690
23.55	Primary Water - Insulated	-	2	-	-	3	-	1	6	6	-	6	-	-	699
23.56	RCP Oil Collection	-	6	-	-	11	-	4	21	21	-	20	-	-	2,608
23.57	Radiation Monitoring	-	14	-	-	15	-	7	37	37	-	26	-	-	3,447
23.58	Reactor Coolant - Insulated	-	40	-	-	92	-	33	165	165	-	161	-	-	20,994
23.59	Refueling Equipment	-	72	-	-	87	0	40	199	199	-	172	-	-	19,681
23.60	SGBT Blowdown - Insulated	-	437	-	-	340	130	214	1,121	1,121	-	753	-	-	77,223
23.61	SGBT Demin - Ins - RCA	-	14	-	-	-	-	2	16	16	-	-	-	-	-
23.62	SGBT Demin - RCA	-	22	-	-	-	-	3	25	25	-	-	-	-	-
23.63	SGBT Miscellaneous - RCA	-	7	-	-	-	-	1	8	8	-	-	-	-	-
23.64	SGBT Waste Management	-	34	-	-	193	-	57	283	283	-	616	-	-	43,845
23.65	SGBT Waste Management - Insulated	-	45	-	-	80	-	31	156	156	-	152	-	-	18,169
23.66	Safety Injection	-	139	-	-	231	141	114	625	625	-	462	-	-	52,540
23.67	Safety Injection - Insulated	-	675	-	-	1,505	-	545	2,724	2,724	-	2,720	-	-	341,947
23.68	Sampling	-	5	-	-	-	-	1	6	-	6	-	-	-	-
23.69	Sampling - Insulated	-	7	-	-	-	-	1	8	-	8	-	-	-	-
23.70	Sampling - Insulated - RCA	-	12	-	-	-	-	2	14	14	-	-	-	-	-
23.71	Sampling - RCA	-	10	-	-	-	-	2	12	12	-	-	-	-	-
23.72	Secondary Side Wet Layup	-	7	-	-	-	-	1	8	-	8	-	-	-	-
23.73	Secondary Side Wet Layup - Ins	-	9	-	-	-	-	1	10	-	10	-	-	-	-
23.74	Secondary Side Wet Layup - Ins - RCA	-	4	-	-	-	-	1	5	5	-	-	-	-	-
23.75	Secondary Side Wet Layup - RCA	-	4	-	-	-	-	1	4	4	-	-	-	-	-
23.76	Service & Instrument Air	-	11	-	-	-	-	2	12	-	12	-	-	-	-
23.77	Service & Instrument Air - Ins	-	5	-	-	-	-	1	6	-	6	-	-	-	-
23.78	Service & Instrument Air - Ins - RCA	-	18	-	-	-	-	3	21	21	-	-	-	-	-
23.79	Service & Instrument Air - RCA	-	12	-	-	-	-	2	14	14	-	-	-	-	-
23.80	Sodium Hypochlorite	-	24	-	-	-	-	4	27	-	27	-	-	-	-
23.81	Spent Fuel	-	6	-	-	33	-	10	49	49	-	65	-	-	7,500
23.82	Spent Fuel - Ins	-	1	-	-	2	-	1	4	4	-	3	-	-	468
23.83	Steam Gen Blowdown Cooling	-	9	-	-	-	-	1	10	-	10	-	-	-	-
23.84	Steam Gen Blowdown Cooling - Ins - RCA	-	21	-	-	-	-	3	24	24	-	-	-	-	-
23.85	Steam Gen Blowdown Cooling - Insulated	-	1	-	-	-	-	0	1	-	1	-	-	-	-
23.86	Steam Gen Blowdown Cooling - RCA	-	27	-	-	-	-	4	31	31	-	-	-	-	-
23.87	Steam Generator Blowdown	-	13	-	-	35	-	12	61	61	-	60	-	-	8,052
23.88	Steam Generator Blowdown - Insulated	-	43	-	-	77	-	30	151	151	-	148	-	-	17,606
23.89	Turbine	-	1	-	-	-	-	0	1	-	1	-	-	-	-
23.90	Turbine Cooling Water	-	31	-	-	-	-	5	36	-	36	-	-	-	-
23.91	Turbine Cooling Water - Insulated	-	22	-	-	-	-	3	25	-	25	-	-	-	-
23.92	Turbine Lube Oil & Diesel Oil	-	32	-	-	-	-	5	37	-	37	-	-	-	-
23.93	Waste Management	-	464	-	-	1,804	-	567	2,834	2,834	-	5,181	-	-	409,911
23.94	Waste Management - Insulated	-	1,115	-	-	1,748	-	716	3,579	3,579	-	2,978	-	-	397,314
23	Totals	-	11,399	-	-	9,560	1,562	4,982	27,503	23,972	3,531	20,243	-	-	2,172,794
24	Erect scaffolding for systems removal	-	810	-	-	26	85	222	1,143	1,143	-	83	-	-	9,243

000182

TABLE C-4
ST LUCIE PLANT - UNIT 2
SAFSTOR STATION DECOMMISSIONING COST ESTIMATE
(Thousands of 1998 Dollars)

ID Number	Activity Description	Decon	Remove	Pack	Ship	Burial	Other	Contingency	Total	NRC LicTerm	Site Restore.	Burial Site			10 CFR 61	
												A CF	B CF	C CF	pounds	GTCC Cu Ft
Decontamination of Site Buildings																
25.1	Reactor Building	588	331	54	22	3,430	155	1,266	5,846	5,846	-	7,301	-	-	821,464	-
25.2	East EP Pond	-	3	26	11	1,095	-	279	1,413	1,413	-	3,555	-	-	373,005	-
25.3	Fuel Handling Building	198	189	2	1	92	124	188	794	794	-	298	-	-	31,807	-
25.4	Pnmary Water Tank & Pump - Contaminate	1	3	2	1	119	-	31	157	157	-	240	-	-	27,384	-
25.5	Reactor Auxiliary Building	274	22	15	6	612	26	301	1,255	1,255	-	1,987	-	-	207,788	-
25.6	Steam Generator Blowdown Treatment	86	1	5	2	204	1	95	393	393	-	661	-	-	69,339	-
25 Totals		1,147	548	103	42	5,552	305	2,161	9,857	9,857	-	14,042	-	-	1,530,787	-
26	ORISE confirmatory survey	-	-	-	-	-	1,064	319	1,383	1,383	-	-	-	-	-	-
27	Terminate license	-	-	-	-	-	-	-	Note 1	-	-	-	-	-	-	-
Period 4 Additional Costs																
28	License Termination Survey	-	-	-	-	-	5,692	854	6,546	6,546	-	-	-	-	-	-
29	ISFSI License Termination	-	735	37	14	533	859	452	2,629	2,629	-	3,709	-	-	-	-
Subtotal Period 4 Activity Costs		1,833	19,021	5,394	2,562	45,857	9,753	27,130	111,551	107,738	3,813	75,253	2,620	408	8,597,111	655
Period 4 Undistributed Costs																
1	Decon equipment	488	-	-	-	-	-	73	561	561	-	-	-	-	-	-
2	Decon supplies	559	-	-	-	-	-	140	698	698	-	-	-	-	-	-
3	DOC staff relocation expenses	-	837	-	-	-	-	126	963	963	-	-	-	-	-	-
4	Process liquid waste	294	-	106	187	1,111	-	464	2,162	2,162	-	-	2,002	-	252,390	-
5	Insurance	-	-	-	-	-	635	63	698	698	-	-	-	-	-	-
6	Property taxes	-	-	-	-	-	1,405	141	1,546	1,391	155	-	-	-	-	-
7	Health physics supplies	-	2,280	-	-	-	-	570	2,850	2,850	-	-	-	-	-	-
8	Heavy equipment rental	-	5,531	-	-	-	-	830	6,361	5,725	636	-	-	-	-	-
9	Small tool allowance	-	229	-	-	-	-	34	264	237	26	-	-	-	-	-
10	Pipe cutting equipment	-	749	-	-	-	-	112	862	862	-	-	-	-	-	-
11	Disposal of DAW generated	-	-	40	10	1,961	-	496	2,507	2,507	-	6,366	-	-	439,503	-
12	Decommissioning Equipment Disposition	-	-	-	-	83	277	62	422	422	-	270	-	-	30,000	-
13	Plant energy budget	-	-	-	-	-	909	136	1,046	941	105	-	-	-	-	-
14	NRC Fees	-	-	-	-	-	909	91	1,000	1,000	-	-	-	-	-	-
15	Site Secunty Cost	-	-	-	-	-	3,426	514	3,940	3,940	-	-	-	-	-	-
16	Fixed Overhead	-	-	-	-	-	2,674	401	3,075	3,075	-	-	-	-	-	-
17	Radwaste Processing Skids	-	-	-	-	-	1,014	152	1,166	1,166	-	-	-	-	-	-
Subtotal Undistribnuted Costs Period 4		1,341	9,627	147	198	3,155	11,249	4,405	30,121	29,199	922	8,636	2,002	-	721,894	-
Staff Costs																
DOC Staff Cost		-	-	-	-	-	20,093	3,014	23,107	23,107	-	-	-	-	-	-
Utility Staff Cost		-	-	-	-	-	37,795	5,669	43,464	43,464	-	-	-	-	-	-
TOTAL PERIOD 4		3,174	28,648	5,541	2,760	49,011	78,890	40,219	208,242	203,508	4,734	81,890	4,622	408	9,319,005	655

000183

TABLE C-4
ST LUCIE PLANT - UNIT 2
SAFSTOR STATION DECOMMISSIONING COST ESTIMATE
(Thousands of 1998 Dollars)

ID	Activity Description	Decon	Remove	Pack	Ship	Burial	Other	Contingency	Total	NRC LicTerm	Site Restore.	Burial Site			10 CFR 61	
Number												A CF	B CF	C CF	pounds	GTCC Cu Ft
PERIOD 5																
Demolition of Remaining Site Buildings																
30.1	Reactor Building	-	5,119	-	-	-	-	768	5,887	883	5,004	-	-	-	-	-
30.2	Fuel Handling Building	-	682	-	-	-	-	102	784	78	705	-	-	-	-	-
30.3	Intake Structure & CWS	-	5,018	-	-	-	-	753	5,771	-	5,771	-	-	-	-	-
30.4	Miscellaneous Structures	-	2,573	-	-	-	-	386	2,959	-	2,959	-	-	-	-	-
30.5	Primary Water Tank & Pump - Contaminate	-	2	-	-	-	-	0	2	-	2	-	-	-	-	-
30.6	Reactor Auxiliary Building	-	1,251	-	-	-	-	188	1,439	144	1,295	-	-	-	-	-
30.7	Steam Generator Blowdown Treatment	-	363	-	-	-	-	54	418	21	397	-	-	-	-	-
30.8	Turbine Building	-	825	-	-	-	-	124	948	-	948	-	-	-	-	-
30.9	Turbine Pedestal	-	440	-	-	-	-	66	506	-	506	-	-	-	-	-
30	Totals	-	16,273	-	-	-	-	2,441	18,714	1,126	17,587	-	-	-	-	-
Site Closeout Activities																
31	Grade & landscape site	-	81	-	-	-	-	12	93	-	93	-	-	-	-	-
32	Final report to NRC	-	-	-	-	-	67	10	77	77	-	-	-	-	-	-
Period 5 Additional Costs																
33	ISFSI Demolition and Site Restoration	-	159	-	-	-	87	53	299	299	-	-	-	-	-	-
Subtotal Period 5 Activity Costs																
		-	16,513	-	-	-	154	2,516	19,183	1,502	17,680	-	-	-	-	-
Period 5 Undistributed Costs																
1	Insurance	-	-	-	-	-	111	11	123	123	-	-	-	-	-	-
2	Property taxes	-	-	-	-	-	471	47	519	-	519	-	-	-	-	-
3	Heavy equipment rental	-	1,702	-	-	-	-	255	1,957	-	1,957	-	-	-	-	-
4	Small tool allowance	-	110	-	-	-	-	17	127	-	127	-	-	-	-	-
5	Plant energy budget	-	-	-	-	-	53	8	61	-	61	-	-	-	-	-
6	Site Security Cost	-	-	-	-	-	393	59	452	-	452	-	-	-	-	-
Subtotal Undistributed Costs Period 5																
		-	1,812	-	-	-	1,029	397	3,238	123	3,116	-	-	-	-	-
Staff Costs																
	DOC Staff Cost	-	-	-	-	-	4,774	716	5,490	-	5,490	-	-	-	-	-
	Utility Staff Cost	-	-	-	-	-	2,878	432	3,310	2,979	331	-	-	-	-	-
TOTAL PERIOD 5																
		-	18,325	-	-	-	8,835	4,061	31,220	4,603	26,617	-	-	-	-	-

481000

TABLE C-4
ST LUCIE PLANT - UNIT 2
SAFSTOR STATION DECOMMISSIONING COST ESTIMATE
(Thousands of 1998 Dollars)

ID Number	Activity Description	Decon	Remove	Pack	Ship	Burial	Other	Contingency	Total	NRC LicTerm	Site Restore.	Burial Site			10 CFR 61	
												A CF	B CF	C CF	pounds	GTCC Cu Ft
	TOTAL COST TO DECOMMISSION	5,557	49,847	5,831	2,950	53,839	258,927	71,433	448,385	415,876	32,510	94,202	6,441	408	9,917,512	655
Total cost to decommission with		18.95% contingency.		\$		448,385,210										
Total NRC license termination cost is		92.75%	or	\$		415,875,612										
Non-nuclear demolition cost is		7.25%	or	\$		32,509,598										
Total site radwaste volume buried						101,051	cubic feet									
Total site radwaste weight buried						9,917,512	pounds									
Total 10CFR61 greater than class C waste buried						655	cubic feet									
Total scrap metal released from site						21,126	tons									
Total craft labor requirements						1,222,638	person hours									

NOTES:

- 1) This activity is performed by the decommissioning staff following plant shutdown; the costs for this are included in this period's staff cost.
- 2) This activity, while performed after final plant shutdown, is considered part of operations and therefore no decommissioning costs are included for this activity

000185

APPENDIX D

DECOMMISSIONING COSTS: DECON AND SAFSTOR ALTERNATIVES No On-Site ISFSI Fuel Storage

SUMMARY:

The results for the base case DECON and SAFSTOR alternatives, provided in Appendix C, assume that spent fuel will be stored in an on-site dry Independent Spent Fuel Storage Facility (ISFSI) to accommodate the anticipated DOE fuel acceptance schedule. The costs associated with designing, licensing, constructing, maintaining, and decommissioning an ISFSI are substantial. This appendix provides cost information based on a revised assumption (alternate scenarios) that the DOE will have removed all fuel from the plant within a 5 year, 2 month period from plant shutdown, thereby eliminating the requirement to maintain an on-site ISFSI.

The results of these alternate scenarios are summarized in Table D-1, "Estimated Impact of Spent Fuel Related Costs." Tables D-2 and D-3 provide cost results for the DECON alternative (no on-site ISFSI) for decommissioning St. Lucie Units 1 and 2, respectively. Tables D-4 and D-5 provide cost results for the SAFSTOR alternative (no on-site ISFSI) for decommissioning St. Lucie Units 1 and 2, respectively. In these scenarios it is assumed that the DOE will have accepted and removed all spent fuel no later than 5 years and 2 months after plant shutdown. This five-year acceptance period is based on nominal fuel assembly cool down requirements associated with transportation cask design limitations. Spent fuel assemblies are assumed to be stored during this 5-year period in the existing Fuel Handling Building's storage pool.

"Avoided" costs associated with the elimination of a requirement for on-site fuel storage include:

- ISFSI capital, including engineering, licensing, and construction costs
- Fuel storage cask costs
- Costs associated with personnel required to support ISFSI operation
- ISFSI license fees
- ISFSI decontamination costs
- ISFSI demolition costs

TABLE D-1

ST. LUCIE PLANT
ESTIMATED IMPACT OF SPENT FUEL RELATED COSTS
(Thousands of 1998 Dollars)

DECON	Unit 1	Unit 2
With Long-Term Dry Fuel Storage	428,917	453,151
Without Long-Term Dry Fuel Storage	<u>371,096</u>	<u>395,421</u>
Impact of Long-Term Dry Fuel Storage	57,821	57,730
Major Cost Components		
Capital Costs/Construction	20,571	38,367
ISFSI Operations	34,322	16,435
ISFSI Decommissioning	<u>2,928</u>	<u>2,928</u>
TOTAL	57,821	57,730

SAFSTOR	Unit 1	Unit 2
With Long Term Dry Fuel Storage	509,804	448,385
Without Long Term Dry Fuel Storage	<u>461,048</u>	<u>394,482</u>
Impact of Long Term Dry Fuel Storage	48,756	53,903
Major Cost Components		
Capital Costs/Construction	20,571	38,367
ISFSI Operations	25,257	12,608
ISFSI Decommissioning	<u>2,928</u>	<u>2,928</u>
TOTAL	48,756	53,903

TABLE D-2
ST LUCIE PLANT - UNIT 1
INTEGRATED STATION DECOMMISSIONING COST ESTIMATE
(Thousands of 1998 Dollars)

ID Number	Activity Description	Decon	Remove	Pack	Ship	Burial	Other	Contingency	Total	NRC LicTerm	Site Restore.	Burial Site			10 CFR 61 GTCC Cu Ft
												A CF	B CF	C CF	pounds
PERIOD 1: Mothballing Activities															
1	Prepare preliminary decommissioning cost	-	-	-	-		130	20	150	150	-	-	-	-	-
2	Notification of Cessation of Operations								Note 1						
3	Remove fuel & source material								Note 2						
4	Notification of Permanent Defueling								Note 1						
5	Deactivate plant systems & process waste								Note 1						
6	Prepare and submit PSDAR	-	-	-	-		200	30	230	230	-	-	-	-	-
7	Review plant dwgs & specs.	-	-	-	-		130	20	150	150	-	-	-	-	-
8	Perform detailed rad survey								Note 1						
9	Estimate by-product inventory	-	-	-	-		100	15	115	115	-	-	-	-	-
10	End product description	-	-	-	-		100	15	115	115	-	-	-	-	-
11	Detailed by-product inventory	-	-	-	-		150	23	173	173	-	-	-	-	-
12	Define major work sequence	-	-	-	-		100	15	115	115	-	-	-	-	-
13	Perform SER and EA	-	-	-	-		310	47	357	357	-	-	-	-	-
14	Perform Site-Specific Cost Study	-	-	-	-		500	75	575	575	-	-	-	-	-
15	Prepare/submit License Termination Plan	-	-	-	-		410	61	471	471	-	-	-	-	-
16	Receive NRC approval of termination plan								Note 1						
Activity Specifications															
17.1	Prepare plant and facilities for SAFSTOR	-	-	-	-		492	74	566	566	-	-	-	-	-
17.2	Decontamination Flush of NSSS	-	-	-	-		50	8	58	58	-	-	-	-	-
17.3	Plant systems	-	-	-	-		417	63	479	479	-	-	-	-	-
17.4	Plant structures and buildings	-	-	-	-		312	47	359	359	-	-	-	-	-
17.5	Waste management	-	-	-	-		200	30	230	230	-	-	-	-	-
17.6	Facility and site dormancy	-	-	-	-		200	30	230	230	-	-	-	-	-
17	Total	-	-	-	-		1,671	251	1,921	1,921	-	-	-	-	-
Detailed Work Procedures															
18.1	Decontamination Flush of NSSS	-	-	-	-		100	15	115	115	-	-	-	-	-
18.2	Plant systems	-	-	-	-		473	71	544	544	-	-	-	-	-
18.3	Facility closeout & dormancy	-	-	-	-		120	18	138	138	-	-	-	-	-
18	Total	-	-	-	-		693	104	797	797	-	-	-	-	-
19	Procure vacuum drying system	-	-	-	-		10	2	12	12	-	-	-	-	-
20	Drain/de-energize non-cont. systems	-	-	-	-		-	-	Note 1	-	-	-	-	-	-
21	Drain & dry NSSS	-	-	-	-		-	-	Note 1	-	-	-	-	-	-
22	Drain/de-energize contaminated systems	-	-	-	-		-	-	Note 1	-	-	-	-	-	-
23	Decon/secure contaminated systems	-	-	-	-		-	-	Note 1	-	-	-	-	-	-
24	Decon primary loop	604	-	-	-		-	302	906	906	-	-	-	-	-
Decontamination Flush of Contam. Sys															
25.1	Chemical & Volume Control	73	-	-	-		288	109	471	471	-	912	-	-	65,546
25.2	Chemical & Volume Control - Insulated	614	-	-	-		516	436	1,566	1,566	-	894	-	-	117,281
25.3	Fuel Pool	75	-	-	-		231	95	401	401	-	465	-	-	52,522
25.4	Fuel Pool - Insulated	50	-	-	-		66	42	157	157	-	119	-	-	14,974
25.5	RCP Oil Collection	0	-	-	-		1	0	1	1	-	2	-	-	175
25.6	Reactor Coolant - Insulated	20	-	-	-		94	33	147	147	-	163	-	-	21,388
25.7	SGBTf Waste Management	7	-	-	-		6	5	17	17	-	10	-	-	1,335
25.8	SGBTf Waste Management - Insulated	78	-	-	-		55	53	185	185	-	92	-	-	12,527
25.9	Waste Management	542	-	-	-		1,759	711	3,011	3,011	-	5,390	-	-	399,788
25.10	Waste Management - Insulated	1,221	-	-	-		1,016	864	3,101	3,101	-	1,751	-	-	230,863
25	Totals	2,679	-	-	-		4,032	0	2,348	9,059	-	9,798	-	-	916,398

TABLE D-2
ST LUCIE PLANT - UNIT 1
INTEGRATED STATION DECOMMISSIONING COST ESTIMATE
(Thousands of 1998 Dollars)

ID	Activity Description	Decon	Remove	Pack	Ship	Burial	Other	Contingency	Total	NRC LicTerm	Site Restore.	Burial Site			10 CFR 61 GTCC Cu Ft
Number												A CF	B CF	C CF	pounds
Decontamination of Site Buildings															
26.1	Reactor Building	576	-	-	-	-	-	288	865	865	-	-	-	-	-
26.2	Fuel Handling Building	214	-	-	-	-	-	107	322	322	-	-	-	-	-
26.3	Reactor Auxiliary	244	-	-	-	-	-	122	366	366	-	-	-	-	-
26	Totals	1,035	-	-	-	-	-	517	1,552	1,552	-	-	-	-	-
27	Prepare support equipment for storage	-	279	-	-	-	-	42	321	321	-	-	-	-	-
28	Install containment pressure equal lines	-	19	-	-	-	-	3	22	22	-	-	-	-	-
29	Interim survey prior to dormancy	-	-	-	-	-	320	48	369	369	-	-	-	-	-
30	Secure building accesses	-	-	-	-	-	-	-	Note 1	-	-	-	-	-	-
31	Prepare & submit interim report	-	-	-	-	-	58	9	67	67	-	-	-	-	-
Period 1 Additional Costs															
32	Mixed/Hazardous Waste	-	-	-	-	-	3,884	583	4,466	4,466	-	-	-	-	-
Subtotal Period 1 Activity Costs		4,318	298	-	-	4,032	8,766	4,527	21,941	21,941	-	9,798	-	-	916,398
Period 1 Undistributed Costs															
1	Decon equipment	488	-	-	-	-	-	73	561	561	-	-	-	-	-
2	Decon supplies	461	-	-	-	-	-	115	576	576	-	-	-	-	-
3	Process liquid waste	412	-	483	552	5,679	-	1,757	8,884	8,884	-	8,364	-	-	1,290,689
4	Insurance	-	-	-	-	-	1,400	140	1,540	1,540	-	-	-	-	-
5	Property taxes	-	-	-	-	-	394	39	434	434	-	-	-	-	-
6	Health physics supplies	-	476	-	-	-	-	119	594	594	-	-	-	-	-
7	Small tool allowance	-	52	-	-	-	-	8	60	60	-	-	-	-	-
8	Disposal of DAW generated	-	-	12	3	590	-	149	754	754	-	1,915	-	-	132,212
9	Plant energy budget	-	-	-	-	-	325	49	373	373	-	-	-	-	-
10	NRC Fees	-	-	-	-	-	203	20	223	223	-	-	-	-	-
11	Emergency Planning Fees	-	-	-	-	-	51	5	56	56	-	-	-	-	-
12	Site Security Cost	-	-	-	-	-	667	100	767	767	-	-	-	-	-
13	Fixed Overhead	-	-	-	-	-	750	112	862	862	-	-	-	-	-
Subtotal Undistributed Costs Period 1		1,361	528	495	555	6,269	3,788	2,687	15,683	15,683	-	1,915	8,364	-	1,422,901
Staff Costs															
DOC Staff Cost		-	-	-	-	-	-	-	-	-	-	-	-	-	-
Utility Staff Cost		-	-	-	-	-	11,859	1,779	13,637	13,637	-	-	-	-	-
TOTAL COST TO SAFSTOR		5,679	826	495	555	10,301	24,413	8,993	51,261	51,261	-	11,713	8,364	-	2,339,299
Total cost to SAFSTOR with 21.27% contingency		51,261,425													
Total site radwaste volume buried		20,077 cubic feet													
Total craft labor requirements		151,633 person hours													

TABLE D-2
ST LUCIE PLANT - UNIT 1
INTEGRATED STATION DECOMMISSIONING COST ESTIMATE
(Thousands of 1998 Dollars)

ID Number	Activity Description	Decon	Remove	Pack	Ship	Burial	Other	Contingency	Total	NRC LicTerm	Site Restore.	Burial Site			10 CFR 61	
												A CF	B CF	C CF	pounds	GTCC Cu Ft
PERIOD 2: SAFSTOR Dormancy Activities																
1	Quarterly inspection								Note 1							
2	Semi-annual environmental survey								Note 1							
3	Prepare reports								Note 1							
4	Health physics supplies	-	-	-	-		46	11	57	57	-		-	-		-
5	Insurance	-	-	-	-		271	27	298	298	-		-	-		-
6	Property taxes	-	-	-	-		394	39	433	433	-		-	-		-
7	Disposal of contaminated solid waste	-	-	1	0	29	-	7	38	38	-	102	-	-		-
8	Maintenance supplies	-	-	-	-		99	25	123	123	-		-	-		-
9	Plant energy budget	-	-	-	-		78	12	89	89	-		-	-		-
10	NRC Fees	-	-	-	-		175	17	192	192	-		-	-		-
11	Emergency Planning Fees	-	-	-	-		46	5	51	51	-		-	-		-
12	Site Security Cost	-	-	-	-		542	81	624	624	-		-	-		-
13	Fixed Overhead	-	-	-	-		749	112	862	862	-		-	-		-
14	Site maintenance staff	-	-	-	-		4,160	624	4,783	4,783	-		-	-		-
PERIOD 2 ANNUAL MAINTENANCE TOTALS		-	-	1	0	29	6,559	962	7,551	7,551	-	102	-	-	-	-

Total cost SAFSTOR dormancy with 4.555833 years equals 34,402,153

Total site radwaste volume buried 464 cubic feet

061000

TABLE D-2
ST LUCIE PLANT - UNIT 1
INTEGRATED STATION DECOMMISSIONING COST ESTIMATE
(Thousands of 1998 Dollars)

ID	Activity Description	Decon	Remove	Pack	Ship	Burial	Other	Contingency	Total	NRC LicTerm	Site Restore.	Burial Site			10 CFR 61
Number												A CF	B CF	C CF	pounds GTCC Cu Ft
PERIOD 3															
1	Review plant dwgs & specs.	-	-	-	-		460	69	529	529	-	-	-	-	-
2	Perform detailed rad survey								Note 1						
3	End product description	-	-	-	-		100	15	115	115	-	-	-	-	-
4	Detailed by-product inventory	-	-	-	-		130	20	150	150	-	-	-	-	-
5	Define major work sequence	-	-	-	-		750	113	863	863	-	-	-	-	-
6	Perform SER and EA	-	-	-	-		310	47	357	357	-	-	-	-	-
7	Perform Site-Specific Cost Study	-	-	-	-		500	75	575	575	-	-	-	-	-
8	Prepare/submit License Termination Plan	-	-	-	-		410	61	471	471	-	-	-	-	-
9	Receive NRC approval of termination plan								Note 1						
Activity Specifications															
10.1	Re-activate plant & temporary facilities	-	-	-	-		737	111	848	763	85	-	-	-	-
10.2	Plant systems	-	-	-	-		417	63	479	431	48	-	-	-	-
10.3	Reactor internals	-	-	-	-		710	107	817	817	-	-	-	-	-
10.4	Reactor vessel	-	-	-	-		650	98	748	748	-	-	-	-	-
10.5	Biological shield	-	-	-	-		50	8	58	58	-	-	-	-	-
10.6	Steam generators	-	-	-	-		312	47	359	359	-	-	-	-	-
10.7	Reinforced concrete	-	-	-	-		160	24	184	92	92	-	-	-	-
10.8	Turbine & condenser	-	-	-	-		80	12	92	-	92	-	-	-	-
10.9	Plant structures & buildings	-	-	-	-		312	47	359	179	179	-	-	-	-
10.10	Waste management	-	-	-	-		460	69	529	529	-	-	-	-	-
10.11	Facility & site closeout	-	-	-	-		90	14	104	52	52	-	-	-	-
10	Total	-	-	-	-		3,978	597	4,574	4,026	548	-	-	-	-
Planning & Site Preparations															
11	Prepare dismantling sequence	-	-	-	-		240	36	276	276	-	-	-	-	-
12	Plant prep & temp. svces	-	-	-	-		1,895	284	2,180	2,180	-	-	-	-	-
13	Design water clean-up system	-	-	-	-		140	21	161	161	-	-	-	-	-
14	Rigging/Cont. Cntrl Envlps/tooling/etc	-	-	-	-		1,604	241	1,845	1,845	-	-	-	-	-
15	Procure casks/liners & containers	-	-	-	-		123	18	141	141	-	-	-	-	-
Detailed Work Procedures															
16.1	Plant systems	-	-	-	-		473	71	544	490	54	-	-	-	-
16.2	Reactor internals	-	-	-	-		250	38	288	288	-	-	-	-	-
16.3	Remaining buildings	-	-	-	-		135	20	155	39	116	-	-	-	-
16.4	CRD cooling assembly	-	-	-	-		100	15	115	115	-	-	-	-	-
16.5	CRD housings & ICI tubes	-	-	-	-		100	15	115	115	-	-	-	-	-
16.6	Incore instrumentation	-	-	-	-		100	15	115	115	-	-	-	-	-
16.7	Reactor vessel	-	-	-	-		363	54	417	417	-	-	-	-	-
16.8	Facility closeout	-	-	-	-		120	18	138	69	69	-	-	-	-
16.9	Missile shields	-	-	-	-		45	7	52	52	-	-	-	-	-
16.10	Biological shield	-	-	-	-		120	18	138	138	-	-	-	-	-
16.11	Steam generators	-	-	-	-		460	69	529	529	-	-	-	-	-
16.12	Reinforced concrete	-	-	-	-		100	15	115	58	58	-	-	-	-
16.13	Turbine & condensers	-	-	-	-		312	47	359	-	359	-	-	-	-
16.14	Auxiliary building	-	-	-	-		273	41	314	283	31	-	-	-	-
16.15	Reactor building	-	-	-	-		273	41	314	283	31	-	-	-	-
16	Total	-	-	-	-		3,224	484	3,708	2,989	719	-	-	-	-
17	Asbestos removal program	-	724	129	4	807	23	400	2,087	1,470	617	2,242	-	-	-
Period 3 Additional Costs															
18	Site Characterization Survey	-	-	-	-	-	403	60	463	463	-	-	-	-	-
Subtotal Period 3 Activity Costs		-	724	129	4	807	14,291	2,540	18,495	16,611	1,884	2,242	-	-	-

TABLE D-2
ST LUCIE PLANT - UNIT 1
INTEGRATED STATION DECOMMISSIONING COST ESTIMATE
(Thousands of 1998 Dollars)

ID Number	Activity Description	Decon	Remove	Pack	Ship	Burial	Other	Contingency	Total	NRC LicTerm	Site Restore.	Burial Site			10 CFR 61	
												A CF	B CF	C CF	pounds	GTCC Cu Ft
Period 3 Undistributed Costs																
1	DOC staff relocation expenses	-	837	-	-	-	-	126	963	963	-	-	-	-	-	
2	Insurance	-	-	-	-	-	406	41	447	447	-	-	-	-	-	
3	Property taxes	-	-	-	-	-	590	59	649	649	-	-	-	-	-	
4	Health physics supplies	-	263	-	-	-	-	66	329	329	-	-	-	-	-	
5	Heavy equipment rental	-	441	-	-	-	-	66	507	507	-	-	-	-	-	
6	Disposal of DAW generated	-	-	18	5	883	-	223	1,129	1,129	-	2,865	-	-	197,823	
7	Plant energy budget	-	-	-	-	-	513	77	590	590	-	-	-	-	-	
8	NRC Fees	-	-	-	-	-	303	30	333	333	-	-	-	-	-	
9	Site Security Cost	-	-	-	-	-	711	107	817	817	-	-	-	-	-	
10	Fixed Overhead	-	-	-	-	-	1,122	168	1,291	1,291	-	-	-	-	-	
Subtotal Undistributed Costs Period 3		-	1,542	18	5	883	3,646	963	7,055	7,055	-	2,865	-	-	197,823	
Staff Costs																
DOC Staff Cost		-	-	-	-	-	5,323	799	6,122	6,122	-	-	-	-	-	
Utility Staff Cost		-	-	-	-	-	16,369	2,455	18,824	18,824	-	-	-	-	-	
TOTAL PERIOD 3 COST		-	2,266	148	9	1,689	39,628	6,756	50,496	48,612	1,884	5,107	-	-	197,823	

000192

TABLE D-2
ST LUCIE PLANT - UNIT 1
INTEGRATED STATION DECOMMISSIONING COST ESTIMATE
(Thousands of 1998 Dollars)

ID Number	Activity Description	Decon	Remove	Pack	Ship	Burial	Other	Contingency	Total	NRC LicTerm	Site Restore.	A CF	B CF	C CF	pounds	10 CFR 61 GTCC Cu Ft
PERIOD 4																
Nuclear Steam Supply System Removal																
19.1	Reactor Coolant Piping	32	48	4	5	153	-	67	308	308	-	371	-	-	34,669	-
19.2	Pressurizer Relief Tank	4	18	1	1	26	-	13	62	62	-	89	-	-	5,824	-
19.3	Reactor Coolant Pumps & Motors	77	41	28	20	2,730	-	737	3,632	3,632	-	5,776	-	-	620,400	-
19.4	Pressurizer	18	27	4	8	1,053	-	280	1,389	1,389	-	2,134	-	-	239,212	-
19.5	Steam Generators	104	613	2,045	1,956	4,568	-	1,846	11,133	11,133	-	19,034	-	-	2,524,482	-
19.6	CRDMs/CIs/Service Structure Removal	84	52	62	12	254	-	126	590	590	-	2,907	-	-	75,041	-
19.7	Reactor Vessel Internals	52	1,290	2,934	352	3,885	-	3,758	12,271	12,271	-	1,441	612	408	265,498	-
19.8	Vessel & Internals GTCC Disposal	-	-	-	-	13,290	-	6,645	19,935	19,935	-	-	-	-	-	650
19.9	Reactor Vessel	126	3,340	217	289	5,703	-	5,546	15,222	15,222	-	4,847	2,096	-	983,277	-
19	Totals	497	5,429	5,295	2,643	31,660	-	19,018	64,542	64,542	-	36,599	2,708	408	4,748,402	650
20	Remove spent fuel racks	251	26	-	-	106	201	189	774	774	-	346	-	-	38,385	-
Removal of Major Equipment																
21	Main Turbine/Generator	-	49	-	-	-	-	7	56	-	56	-	-	-	-	-
22	Main Condensers	-	199	-	-	-	-	30	229	-	229	-	-	-	-	-
Disposal of Plant Systems																
23.1	Air Evacuation	-	4	-	-	-	-	1	4	-	4	-	-	-	-	-
23.2	Air Evacuation - Insulated	-	15	-	-	-	-	2	17	-	17	-	-	-	-	-
23.3	Auxiliary Steam - Insulated	-	12	-	-	-	-	2	14	-	14	-	-	-	-	-
23.4	Chemical & Volume Control	69	60	-	-	288	-	122	539	539	-	912	-	-	65,546	-
23.5	Chemical & Volume Control - Insulated	578	349	-	-	516	-	505	1,948	1,948	-	894	-	-	117,281	-
23.6	Chemical Feed	-	1	-	-	-	-	0	2	-	2	-	-	-	-	-
23.7	Chemical Feed - Insulated	-	1	-	-	-	-	0	1	-	1	-	-	-	-	-
23.8	Circulating & Intake Cooling Water	-	125	-	-	-	-	19	144	-	144	-	-	-	-	-
23.9	Component Cooling	-	39	-	-	-	-	6	45	-	45	-	-	-	-	-
23.10	Component Cooling - RCA	47	110	-	-	-	-	40	196	196	-	-	-	-	-	-
23.11	Condensate	-	81	-	-	-	-	12	93	-	93	-	-	-	-	-
23.12	Condensate - Insulated	-	46	-	-	-	-	7	52	-	52	-	-	-	-	-
23.13	Condensate Polish Filter Demin	-	12	-	-	-	-	2	14	-	14	-	-	-	-	-
23.14	Condensate Polish Filter Demin - Ins	-	37	-	-	-	-	6	43	-	43	-	-	-	-	-
23.15	Condensate Recovery	-	2	-	-	-	-	0	2	-	2	-	-	-	-	-
23.16	Condensate Recovery - Insulated	-	0	-	-	-	-	0	0	-	0	-	-	-	-	-
23.17	Condensate Recovery - Insulated - RCA	0	0	-	-	-	-	0	0	0	-	-	-	-	-	-
23.18	Condensate Recovery - RCA	1	3	-	-	-	-	1	5	5	-	-	-	-	-	-
23.19	Condenser Tube Cleaning	-	17	-	-	-	-	3	20	-	20	-	-	-	-	-
23.20	Contnmnt Spray & Refueling Water	-	261	-	-	2,483	-	686	3,431	3,431	-	6,404	-	-	564,410	-
23.21	Contnmnt Spray & Refueling Water - Ins	-	150	-	-	649	-	200	999	999	-	1,259	-	-	147,467	-
23.22	Demineralized Makeup Water	-	8	-	-	-	-	1	9	-	9	-	-	-	-	-
23.23	Demineralized Makeup Water - RCA	2	4	-	-	-	-	1	7	7	-	-	-	-	-	-
23.24	Domestic/Makeup/Service Water	-	92	-	-	-	-	14	106	-	106	-	-	-	-	-
23.25	Domestic/Makeup/Service Water - RCA	15	34	-	-	-	-	13	61	61	-	-	-	-	-	-
23.26	Domestic/Makeup/Service Water-Ins	-	2	-	-	-	-	0	2	-	2	-	-	-	-	-
23.27	Domestic/Makeup/Service Water-Ins-RCA	2	4	-	-	-	-	1	7	7	-	-	-	-	-	-
23.28	Electrical - Clean	-	1,024	-	-	-	-	154	1,177	-	1,177	-	-	-	-	-
23.29	Electrical - Contaminated	-	436	-	-	18	72	124	649	649	-	36	-	-	4,061	-
23.30	Electrical - Decontaminated	112	831	-	-	-	-	181	1,124	1,124	-	-	-	-	-	-
23.31	Emergency Diesel Generator	-	38	-	-	-	-	6	43	-	43	-	-	-	-	-
23.32	Emergency Diesel Generator - Insulated	-	3	-	-	-	-	1	4	-	4	-	-	-	-	-
23.33	Extraction Steam	-	42	-	-	-	-	6	48	-	48	-	-	-	-	-
23.34	Extraction Steam - Insulated	-	42	-	-	-	-	6	48	-	48	-	-	-	-	-
23.35	Feedwater - Insulated	-	45	-	-	-	-	7	51	-	51	-	-	-	-	-
23.36	Feedwater - Insulated - RCA	5	11	-	-	-	-	4	20	20	-	-	-	-	-	-
23.37	Fire Protection	-	36	-	-	-	-	5	41	-	41	-	-	-	-	-
23.38	Fire Protection - Insulated	-	3	-	-	-	-	1	4	-	4	-	-	-	-	-
23.39	Fire Protection - Insulated - RCA	0	1	-	-	-	-	0	1	1	-	-	-	-	-	-
23.40	Fire Protection - RCA	3	8	-	-	-	-	3	14	14	-	-	-	-	-	-

TABLE D-2
ST LUCIE PLANT - UNIT 1
INTEGRATED STATION DECOMMISSIONING COST ESTIMATE
(Thousands of 1998 Dollars)

ID Number	Activity Description	Decon	Remove	Pack	Ship	Burial	Other	Contingency	Total	NRC LicTerm	Site Restore.	Burial Site			10 CFR 61	
												A CF	B CF	C CF	pounds	GTCC Cu Ft
Disposal of Plant Systems (continued)																
23.41	Fuel Pool	71	58	-	-	231	-	108	468	468	-	465	-	-	52,522	-
23.42	Fuel Pool - Insulated	47	37	-	-	66	-	49	199	199	-	119	-	-	14,974	-
23.43	HVAC	-	61	-	-	-	-	9	70	-	70	-	-	-	-	-
23.44	HVAC - Contaminated	-	1,317	-	-	383	787	543	3,030	3,030	-	751	-	-	86,998	-
23.45	Heater Drain & Vent - Insulated	-	93	-	-	-	-	14	108	-	108	-	-	-	-	-
23.46	Hydrogen Sampling	-	27	-	-	108	-	34	169	169	-	209	-	-	24,624	-
23.47	Integrated Leak Rate Testing	-	23	-	-	60	-	21	104	104	-	111	-	-	13,585	-
23.48	Main Steam - Insulated	-	98	-	-	-	-	15	113	-	113	-	-	-	-	-
23.49	Main Steam - Insulated - RCA	7	16	-	-	-	-	6	28	28	-	-	-	-	-	-
23.50	Misc Bulk Gas	-	10	-	-	-	-	1	11	-	11	-	-	-	-	-
23.51	Misc Bulk Gas - RCA	2	5	-	-	-	-	2	9	9	-	-	-	-	-	-
23.52	Miscellaneous	-	5	-	-	-	-	1	6	-	6	-	-	-	-	-
23.53	Miscellaneous - RCA	2	4	-	-	-	-	2	8	8	-	-	-	-	-	-
23.54	Neutralization Basin Recirculation	-	9	-	-	-	-	1	10	-	10	-	-	-	-	-
23.55	Post Accident Sampling	-	9	-	-	33	-	10	52	52	-	64	-	-	7,400	-
23.56	Post Accident Sampling - Insulated	-	27	-	-	24	-	13	65	65	-	41	-	-	5,543	-
23.57	Primary Water	-	90	-	-	56	78	48	273	273	-	140	-	-	12,728	-
23.58	Primary Water - Insulated	-	2	-	-	3	-	1	6	6	-	6	-	-	689	-
23.59	RCP Oil Collection	0	1	-	-	1	0	0	2	2	-	2	-	-	175	-
23.60	Radiation Monitoring	-	14	-	-	13	-	7	34	34	-	22	-	-	3,004	-
23.61	Reactor Coolant - Insulated	19	44	-	-	94	-	44	201	201	-	163	-	-	21,388	-
23.62	Refueling Equipment	-	61	-	-	268	-	82	412	412	-	533	-	-	60,959	-
23.63	SGBTf Blowdown - Insulated	-	95	-	-	139	-	58	292	292	-	239	-	-	31,555	-
23.64	SGBTf HVAC	-	209	-	-	36	141	82	468	468	-	71	-	-	8,136	-
23.65	SGBTf Misc - RCA	1	1	-	-	-	-	0	2	2	-	-	-	-	-	-
23.66	SGBTf Waste Management	6	4	-	-	6	-	6	22	22	-	10	-	-	1,335	-
23.67	SGBTf Waste Management - Insulated	73	38	-	-	55	-	60	226	226	-	92	-	-	12,527	-
23.68	Safety Injection	-	119	-	-	1,443	-	390	1,952	1,952	-	3,247	-	-	327,912	-
23.69	Safety Injection - Insulated	-	427	-	-	985	-	353	1,765	1,765	-	1,786	-	-	223,859	-
23.70	Sampling	-	4	-	-	-	-	1	5	-	5	-	-	-	-	-
23.71	Sampling - Insulated	-	4	-	-	-	-	1	5	-	5	-	-	-	-	-
23.72	Sampling - Insulated - RCA	3	8	-	-	-	-	3	13	13	-	-	-	-	-	-
23.73	Sampling - RCA	3	7	-	-	-	-	3	13	13	-	-	-	-	-	-
23.74	Secondary Side Wet Layup	-	6	-	-	-	-	1	7	-	7	-	-	-	-	-
23.75	Secondary Side Wet Layup - Ins	-	7	-	-	-	-	1	9	-	9	-	-	-	-	-
23.76	Secondary Side Wet Layup - Ins - RCA	1	4	-	-	-	-	1	7	7	-	-	-	-	-	-
23.77	Secondary Side Wet Layup - RCA	1	4	-	-	-	-	1	6	6	-	-	-	-	-	-
23.78	Service & Instrument Air	-	13	-	-	-	-	2	16	-	16	-	-	-	-	-
23.79	Service & Instrument Air - Ins	-	7	-	-	-	-	1	8	-	8	-	-	-	-	-
23.80	Service & Instrument Air - Ins - RCA	10	27	-	-	-	-	9	45	45	-	-	-	-	-	-
23.81	Service & Instrument Air - RCA	7	19	-	-	-	-	6	32	32	-	-	-	-	-	-
23.82	Steam Gen Blowdown Cooling	-	8	-	-	-	-	1	9	-	9	-	-	-	-	-
23.83	Steam Gen Blowdown Cooling - Ins - RCA	7	16	-	-	-	-	6	29	29	-	-	-	-	-	-
23.84	Steam Gen Blowdown Cooling - Insulated	-	1	-	-	-	-	0	1	-	1	-	-	-	-	-
23.85	Steam Gen Blowdown Cooling - RCA	10	21	-	-	-	-	8	39	39	-	-	-	-	-	-
23.86	Steam Generator Blowdown	-	19	-	-	67	-	21	106	106	-	136	-	-	15,145	-
23.87	Steam Generator Blowdown - Insulated	-	49	-	-	81	-	32	162	162	-	148	-	-	18,323	-
23.88	Turbine	-	1	-	-	-	-	0	1	-	1	-	-	-	-	-
23.89	Turbine Cooling Water	-	28	-	-	-	-	4	33	-	33	-	-	-	-	-
23.90	Turbine Cooling Water - Insulated	-	18	-	-	-	-	3	20	-	20	-	-	-	-	-
23.91	Turbine Lube Oil & Diesel Oil	-	35	-	-	-	-	5	40	-	40	-	-	-	-	-
23.92	Waste Management	507	387	-	-	1,759	-	790	3,443	3,443	-	5,390	-	-	399,788	-
23.93	Waste Management - Insulated	1,148	678	-	-	1,016	-	997	3,839	3,839	-	1,751	-	-	230,863	-
23.94	Water Treatment	-	34	-	-	-	-	5	39	-	39	-	-	-	-	-
23.95	Water Treatment - Insulated	-	19	-	-	-	-	3	22	-	22	-	-	-	-	-
23 Totals		2,758	8,317	-	-	10,880	1,078	6,007	29,040	26,523	2,517	25,000	-	-	2,472,795	-
24	Erect scaffolding for systems removal	-	735	-	-	21	71	200	1,027	1,027	-	70	-	-	7,726	-

TABLE D-2
ST LUCIE PLANT - UNIT 1
INTEGRATED STATION DECOMMISSIONING COST ESTIMATE
(Thousands of 1998 Dollars)

ID Number	Activity Description	Decon	Remove	Pack	Ship	Burial	Other	Contingency	Total	NRC LicTerm	Site Restore.	Burial Site			10 CFR 61
												A CF	B CF	C CF	GTCC Cu Ft
Decontamination of Site Buildings															
25.1	Reactor Building	623	352	54	22	3,430	155	1,289	5,924	5,924	-	7,301	-	-	821,464
25.2	Fuel Handling Building	210	200	2	1	92	124	197	827	827	-	298	-	-	31,807
25.3	Primary Water Tank Foundation - Contam	1	11	66	27	2,806	-	715	3,625	3,625	-	8,964	-	-	942,684
25.4	Reactor Auxiliary	290	23	15	6	612	26	310	1,281	1,281	-	1,987	-	-	207,788
25.5	Refueling Water Storage Tank - Contam	1	9	16	7	787	-	202	1,022	1,022	-	2,237	-	-	239,387
25	Totals	1,125	595	153	62	7,727	304	2,713	12,679	12,679	-	20,788	-	-	2,243,130
26	ORISE confirmatory survey	-	-	-	-	-	1,064	319	1,383	1,383	-	-	-	-	-
27	Terminate license	-	-	-	-	-	-	-	Note 1	-	-	-	-	-	-
Period 4 Additional Costs															
28	License Termination Survey	-	-	-	-	-	3,840	576	4,416	4,416	-	-	-	-	-
Subtotal Period 4 Activity Costs		4,632	15,349	5,448	2,705	50,395	6,557	29,060	114,146	111,344	2,802	82,800	2,708	408	9,510,438
Period 4 Undistributed Costs															
1	Decon equipment	488	-	-	-	-	-	73	561	561	-	-	-	-	-
2	Decon supplies	596	-	-	-	-	-	149	745	745	-	-	-	-	-
3	DOC staff relocation expenses	-	837	-	-	-	-	126	963	963	-	-	-	-	-
4	Process liquid waste	421	-	198	308	2,156	-	816	3,899	3,899	-	3,629	-	-	489,929
5	Insurance	-	-	-	-	-	1,044	104	1,148	1,148	-	-	-	-	-
6	Property taxes	-	-	-	-	-	3,110	311	3,421	3,079	342	-	-	-	-
7	Health physics supplies	-	2,633	-	-	-	-	658	3,291	3,291	-	-	-	-	-
8	Heavy equipment rental	-	12,242	-	-	-	-	1,836	14,078	12,671	1,408	-	-	-	-
9	Small tool allowance	-	228	-	-	-	-	34	263	236	26	-	-	-	-
10	Pipe cutting equipment	-	749	-	-	-	-	112	862	862	-	-	-	-	-
11	Disposal of DAW generated	-	-	96	26	4,989	-	1,261	6,371	6,371	-	16,197	-	-	1,097,481
12	Decommissioning Equipment Disposition	-	-	-	-	83	277	62	422	422	-	270	-	-	30,000
13	Plant energy budget	-	-	-	-	-	1,971	296	2,267	2,040	227	-	-	-	-
14	NRC Fees	-	-	-	-	-	1,674	167	1,842	1,842	-	-	-	-	-
15	Site Security Cost	-	-	-	-	-	4,453	668	5,121	5,121	-	-	-	-	-
16	Fixed Overhead	-	-	-	-	-	5,917	888	6,805	6,805	-	-	-	-	-
Subtotal Undistributed Costs Period 4		1,505	16,690	294	334	7,228	18,447	7,562	52,059	50,056	2,003	16,467	3,629	-	1,617,410
Staff Costs															
DOC Staff Cost		-	-	-	-	-	16,378	2,457	18,835	18,835	-	-	-	-	-
Utility Staff Cost		-	-	-	-	-	28,021	4,203	32,225	32,225	-	-	-	-	-
TOTAL PERIOD 4		6,137	32,039	5,742	3,039	57,623	69,404	43,281	217,264	212,459	4,805	99,267	6,337	408	11,127,848

000195

TABLE D-2
ST LUCIE PLANT - UNIT 1
INTEGRATED STATION DECOMMISSIONING COST ESTIMATE
(Thousands of 1998 Dollars)

ID	Activity Description	Decon	Remove	Pack	Ship	Burial	Other	Contingency	Total	NRC LicTerm	Site Restore.	Burial Site			10 CFR 61 GTCC Cu Ft
Number												A CF	B CF	C CF	pounds
PERIOD 5															
Demolition of Remaining Site Buildings															
29.1	Reactor Building	-	5,108	-	-	-	-	766	5,875	881	4,993	-	-	-	-
29.2	Fuel Handling Building	-	682	-	-	-	-	102	784	78	705	-	-	-	-
29.3	Intake & CWS	-	294	-	-	-	-	44	338	-	338	-	-	-	-
29.4	Miscellaneous Structures	-	798	-	-	-	-	120	918	-	918	-	-	-	-
29.5	Primary Water Tank Foundation - Contam	-	2	-	-	-	-	0	2	-	2	-	-	-	-
29.6	Reactor Auxiliary	-	1,251	-	-	-	-	188	1,439	144	1,295	-	-	-	-
29.7	Refueling Water Storage Tank - Contam	-	5	-	-	-	-	1	5	-	5	-	-	-	-
29.8	Turbine Building	-	834	-	-	-	-	125	959	-	959	-	-	-	-
29.9	Turbine Pedestal	-	440	-	-	-	-	66	506	-	506	-	-	-	-
29	Totals	-	9,414	-	-	-	-	1,412	10,826	1,103	9,722	-	-	-	-
Site Closeout Activities															
30	Grade & landscape site	-	81	-	-	-	-	12	93	-	93	-	-	-	-
31	Final report to NRC	-	-	-	-	-	156	23	179	179	-	-	-	-	-
Subtotal Period 5 Activity Costs															
		-	9,494	-	-	-	156	1,448	11,098	1,283	9,815	-	-	-	-
Period 5 Undistributed Costs															
1	Insurance	-	-	-	-	-	111	11	122	122	-	-	-	-	-
2	Property taxes	-	-	-	-	-	470	47	517	-	517	-	-	-	-
3	Heavy equipment rental	-	1,697	-	-	-	-	255	1,951	-	1,951	-	-	-	-
4	Small tool allowance	-	79	-	-	-	-	12	90	-	90	-	-	-	-
5	Plant energy budget	-	-	-	-	-	47	7	54	-	54	-	-	-	-
6	Site Security Cost	-	-	-	-	-	163	25	188	-	188	-	-	-	-
	Subtotal Undistributed Costs Period 5	-	1,776	-	-	-	791	356	2,923	122	2,801	-	-	-	-
Staff Costs															
	DOC Staff Cost	-	-	-	-	-	2,369	355	2,725	-	2,725	-	-	-	-
	Utility Staff Cost	-	-	-	-	-	806	121	927	835	93	-	-	-	-
TOTAL PERIOD 5															
		-	11,270	-	-	-	4,123	2,280	17,673	2,240	15,433	-	-	-	-

961000

TABLE D-2
ST LUCIE PLANT - UNIT 1
INTEGRATED STATION DECOMMISSIONING COST ESTIMATE
(Thousands of 1998 Dollars)

ID Number	Activity Description	Decon	Remove	Pack	Ship	Burial	Other	Contingency	Total	NRC LicTerm	Site Restore.	Burial Site			10 CFR 61	
												A CF	B CF	C CF	pounds	GTCC Cu Ft
TOTAL COST TO DECOMMISSION		11,815	46,400	6,388	3,803	69,748	167,452	65,690	371,096	348,975	22,122	116,552	14,701	408	13,664,970	650
Total cost to decommission with 21.51% contingency:		\$	371,096,283													
Total NRC license termination cost is 94.04%		or	\$	348,974,534												
Non-nuclear demolition cost is 5.96%		or	\$	22,121,755												
Total site radwaste volume buried				131,661	cubic feet											
Total site radwaste weight buried				13,664,970	pounds											
Total 10CFR61 greater than class C waste buried				650	cubic feet											
Total scrap metal released from site				19,264	tons											
Total craft labor requirements				1,147,700	person hours											

NOTES:

- 1) This activity is performed by the decommissioning staff following plant shutdown; the costs for this are included in this period's staff cost.
- 2) This activity, while performed after final plant shutdown, is considered part of operations and therefore no decommissioning costs are included for this activity.

000197

TABLE D-3
ST. LUCIE PLANT - UNIT 2
DECON DECOMMISSIONING COST ESTIMATE
(Thousands of 1998 Dollars)

ID Number	Activity Description	Decon	Remove	Pack	Ship	Burial	Other	Contingncy	Total	NRC LicTerm	Site Restore	Burial site			10 CFR 61	
												A CF	B CF	C CF	pounds	GTCC Cu Ft
PERIOD 1																
1	Prepare preliminary decommissioning cost	-	-	-	-		56	8	64	64	-	-	-	-	-	-
2	Notification of Cessation of Operations								Note 1							
3	Remove fuel & source material								Note 2							
4	Notification of Permanent Defueling								Note 1							
5	Deactivate plant systems & process waste								Note 1							
6	Prepare and submit PSDAR	-	-	-	-		86	13	98	98	-	-	-	-	-	-
7	Review plant dwgs & specs.	-	-	-	-		197	30	226	226	-	-	-	-	-	-
8	Perform detailed rad survey								Note 1							
9	Estimate by-product inventory	-	-	-	-		43	6	49	49	-	-	-	-	-	-
10	End product description	-	-	-	-		43	6	49	49	-	-	-	-	-	-
11	Detailed by-product inventory	-	-	-	-		56	8	64	64	-	-	-	-	-	-
12	Define major work sequence	-	-	-	-		321	48	369	369	-	-	-	-	-	-
13	Perform SER and EA	-	-	-	-		133	20	152	152	-	-	-	-	-	-
14	Perform Site-Specific Cost Study	-	-	-	-		214	32	246	246	-	-	-	-	-	-
15	Prepare/submit License Termination Plan	-	-	-	-		175	26	201	201	-	-	-	-	-	-
16	Receive NRC approval of termination plan								Note 1							
Activity Specifications																
17.1	Plant & temporary facilities	-	-	-	-		210	32	242	218	24	-	-	-	-	-
17.2	Plant systems	-	-	-	-		178	27	205	184	20	-	-	-	-	-
17.3	NSSS Decontamination Flush	-	-	-	-		21	3	25	25	-	-	-	-	-	-
17.4	Reactor internals	-	-	-	-		304	46	349	349	-	-	-	-	-	-
17.5	Reactor vessel	-	-	-	-		278	42	320	320	-	-	-	-	-	-
17.6	Biological shield	-	-	-	-		21	3	25	25	-	-	-	-	-	-
17.7	Steam generators	-	-	-	-		133	20	153	153	-	-	-	-	-	-
17.8	Reinforced concrete	-	-	-	-		68	10	79	39	39	-	-	-	-	-
17.9	Turbine & condenser	-	-	-	-		34	5	39	-	39	-	-	-	-	-
17.10	Plant structures & buildings	-	-	-	-		133	20	153	77	77	-	-	-	-	-
17.11	Waste management	-	-	-	-		197	30	226	226	-	-	-	-	-	-
17.12	Facility & site closeout	-	-	-	-		38	6	44	22	22	-	-	-	-	-
17	Total	-	-	-	-		1,617	243	1,860	1,638	222	-	-	-	-	-
Planning & Site Preparations																
18	Prepare dismantling sequence	-	-	-	-		103	15	118	118	-	-	-	-	-	-
19	Plant prep. & temp. svces	-	-	-	-		1,895	284	2,180	2,180	-	-	-	-	-	-
20	Design water clean-up system	-	-	-	-		60	9	69	69	-	-	-	-	-	-
21	Rigging/Cont. Cntrl Envlps/tooling/etc.	-	-	-	-		1,604	241	1,845	1,845	-	-	-	-	-	-
22	Procure casks/liners & containers	-	-	-	-		53	8	60	60	-	-	-	-	-	-
Detailed Work Procedures																
23.1	Plant systems	-	-	-	-		202	30	233	209	23	-	-	-	-	-
23.2	NSSS Decontamination Flush	-	-	-	-		43	6	49	49	-	-	-	-	-	-
23.3	Reactor internals	-	-	-	-		107	16	123	123	-	-	-	-	-	-
23.4	Remaining buildings	-	-	-	-		58	9	66	17	50	-	-	-	-	-
23.5	CRD cooling assembly	-	-	-	-		43	6	49	49	-	-	-	-	-	-
23.6	CRD housings & ICI tubes	-	-	-	-		43	6	49	49	-	-	-	-	-	-
23.7	Incore instrumentation	-	-	-	-		43	6	49	49	-	-	-	-	-	-
23.8	Reactor vessel	-	-	-	-		155	23	179	179	-	-	-	-	-	-
23.9	Facility closeout	-	-	-	-		51	8	59	30	30	-	-	-	-	-
23.10	Missile shields	-	-	-	-		19	3	22	22	-	-	-	-	-	-
23.11	Biological shield	-	-	-	-		51	8	59	59	-	-	-	-	-	-
23.12	Steam generators	-	-	-	-		197	30	226	226	-	-	-	-	-	-
23.13	Reinforced concrete	-	-	-	-		43	6	49	25	25	-	-	-	-	-
23.14	Turbine & condensers	-	-	-	-		133	20	153	-	153	-	-	-	-	-
23.15	Auxiliary building	-	-	-	-		117	18	134	121	13	-	-	-	-	-
23.16	Reactor building	-	-	-	-		117	18	134	121	13	-	-	-	-	-
23	Total	-	-	-	-		1,421	213	1,635	1,327	307	-	-	-	-	-

TABLE D-3
ST. LUCIE PLANT - UNIT 2
DECON DECOMMISSIONING COST ESTIMATE
(Thousands of 1998 Dollars)

ID Number	Activity Description	Decon	Remove	Pack	Ship	Burial	Other	Contingency	Total	NRC LicTerm	Site Restore	Burial site			10 CFR 61
												A CF	B CF	C CF	GTCC Cu Ft
24	Decon primary loop	573	-	-	-	-	-	287	860	860	-	-	-	-	-
25	Asbestos removal program	-	724	129	4	807	23	400	2,087	1,470	617	2,242	-	-	-
Period 1 Additional Costs															
26	Site Characterization Survey	-	-	-	-	-	605	91	695	695	-	-	-	-	-
Subtotal Period 1 Activity Costs		573	724	129	4	807	8,703	1,988	12,929	11,782	1,146	2,242	-	-	-
Period 1 Undistributed Costs															
1	Decon equipment	488	-	-	-	-	-	73	561	561	-	-	-	-	-
2	Decon supplies	29	-	-	-	-	-	7	37	37	-	-	-	-	-
3	DOC staff relocation expenses	-	837	-	-	-	-	126	963	963	-	-	-	-	-
4	Process liquid waste	99	-	313	303	3,795	-	1,075	5,586	5,586	-	5,286	-	-	862,611
5	Insurance	-	-	-	-	-	2,098	210	2,306	2,306	-	-	-	-	-
6	Property taxes	-	-	-	-	-	591	59	650	650	-	-	-	-	-
7	Health physics supplies	-	265	-	-	-	-	66	332	332	-	-	-	-	-
8	Heavy equipment rental	-	209	-	-	-	-	31	240	240	-	-	-	-	-
9	Small tool allowance	-	10	-	-	-	-	2	12	12	-	-	-	-	-
10	Disposal of DAW generated	-	-	17	4	824	-	208	1,054	1,054	-	2,675	-	-	184,692
11	Plant energy budget	-	-	-	-	-	523	78	601	601	-	-	-	-	-
12	NRC Fees	-	-	-	-	-	303	30	334	334	-	-	-	-	-
13	Emergency Planning Fees	-	-	-	-	-	76	8	83	83	-	-	-	-	-
14	Site Security Cost	-	-	-	-	-	712	107	818	818	-	-	-	-	-
15	Fixed Overhead	-	-	-	-	-	1,123	169	1,292	1,292	-	-	-	-	-
Subtotal Undistributed Costs Period 1		616	1,321	330	308	4,619	5,424	2,249	14,867	14,867	-	2,675	5,286	-	1,047,303
Staff Costs															
DOC Staff Cost		-	-	-	-	-	5,338	801	6,139	6,139	-	-	-	-	-
Utility Staff Cost		-	-	-	-	-	18,589	2,788	21,378	21,378	-	-	-	-	-
TOTAL PERIOD 1 COST		1,189	2,045	459	312	5,426	38,054	7,826	55,312	54,165	1,146	4,917	5,286	-	1,047,303

TABLE D-3
ST. LUCIE PLANT - UNIT 2
DECON DECOMMISSIONING COST ESTIMATE
(Thousands of 1998 Dollars)

ID	Activity Description	Decon	Remove	Pack	Ship	Burial	Other	Contingency	Total	NRC LicTerm	Site Restore	Burial site			10 CFR 61 GTCC Cu Ft
Number												A CF	B CF	C CF	pounds
PERIOD 2															
Nuclear Steam Supply System Removal															
27.1	Reactor Coolant Piping	28	41	4	4	137	-	60	274	274	-	332	-	-	31,028
27.2	Pressurizer Relief Tank	4	19	1	1	26	-	13	63	63	-	89	-	-	5,824
27.3	Reactor Coolant Pumps & Motors	82	44	28	23	3,131	-	841	4,149	4,149	-	5,772	-	-	711,700
27.4	Pressurizer	19	27	4	8	1,059	-	283	1,399	1,399	-	2,127	-	-	240,755
27.5	Steam Generators	112	613	2,045	1,956	4,568	-	1,850	11,145	11,145	-	19,034	-	-	2,524,482
27.6	CRDMs/ICIs/Service Structure Removal	100	60	75	15	301	-	150	700	700	-	3,213	-	-	87,528
27.7	Reactor Vessel Internals	56	1,290	2,934	352	4,086	-	3,860	12,579	12,579	-	1,441	612	408	265,498
27.8	Vessel & Internals GTCC Disposal	-	-	-	-	13,290	-	6,645	19,935	19,935	-	-	-	-	655
27.9	Reactor Vessel	135	3,340	217	289	7,332	-	6,366	17,680	17,680	-	4,847	2,096	-	983,277
27 Totals		537	5,434	5,308	2,648	33,931	-	20,067	67,925	67,925	-	36,855	2,708	408	4,850,092
28	Remove spent fuel racks	249	24	-	-	99	186	183	742	742	-	321	-	-	35,640
Removal of Major Equipment															
29	Main Turbine/Generator	-	46	-	-	-	-	7	53	-	53	-	-	-	-
30	Main Condensers	-	199	-	-	-	-	38	229	-	229	-	-	-	-
Disposal of Plant Systems															
31.1	Air Evacuation	-	4	-	-	-	-	1	4	-	4	-	-	-	-
31.2	Air Evacuation - Insulated	-	16	-	-	-	-	2	19	-	19	-	-	-	-
31.3	Auxiliary Steam - Insulated	-	8	-	-	-	-	1	10	-	10	-	-	-	-
31.4	Chemical & Volume Control	91	72	-	-	301	-	139	603	603	-	937	-	-	68,497
31.5	Chemical & Volume Control - Insulated	923	542	-	-	750	-	785	3,000	3,000	-	1,294	-	-	170,414
31.6	Chemical Feed	-	2	-	-	-	-	0	2	-	2	-	-	-	-
31.7	Chemical Feed - Insulated	-	1	-	-	-	-	0	1	-	1	-	-	-	-
31.8	Circulating & Intake Cooling Water	-	138	-	-	-	-	21	158	-	158	-	-	-	-
31.9	Component Cooling	-	46	-	-	-	-	7	53	-	53	-	-	-	-
31.10	Component Cooling - RCA	64	147	-	-	-	-	54	266	266	-	-	-	-	-
31.11	Condensate	-	101	-	-	-	-	15	116	-	116	-	-	-	-
31.12	Condensate - Insulated	-	59	-	-	-	-	9	68	-	68	-	-	-	-
31.13	Condensate Recovery	-	2	-	-	-	-	0	3	-	3	-	-	-	-
31.14	Condensate Recovery - Insulated	-	0	-	-	-	-	0	0	-	0	-	-	-	-
31.15	Condensate Recovery - Insulated - RCA	0	0	-	-	-	-	0	1	1	-	-	-	-	-
31.16	Condensate Recovery - RCA	1	4	-	-	-	-	1	6	6	-	-	-	-	-
31.17	Condenser Tube Cleaning	-	19	-	-	-	-	3	22	-	22	-	-	-	-
31.18	Contaminant Spray & Refueling Water	-	283	-	-	318	304	196	1,100	1,100	-	697	-	-	72,173
31.19	Contaminant Spray & Refueling Water - Ins	-	170	-	-	689	-	215	1,074	1,074	-	1,342	-	-	156,703
31.20	Demineralized Makeup Water	-	3	-	-	-	-	0	4	-	4	-	-	-	-
31.21	Demineralized Makeup Water - RCA	1	2	-	-	-	-	1	4	4	-	-	-	-	-
31.22	Domestic/Makeup/Service Water	-	4	-	-	-	-	1	5	-	5	-	-	-	-
31.23	Domestic/Makeup/Service Water - RCA	4	9	-	-	-	-	3	16	16	-	-	-	-	-
31.24	Domestic/Makeup/Service Water-Ins	-	0	-	-	-	-	0	0	-	0	-	-	-	-
31.25	Domestic/Makeup/Service Water-Ins - RCA	0	1	-	-	-	-	0	1	1	-	-	-	-	-
31.26	Electrical - Clean	-	1,799	-	-	-	-	270	2,069	-	2,069	-	-	-	-
31.27	Electrical - Contaminated	-	936	-	-	32	127	261	1,356	1,356	-	63	-	-	7,213
31.28	Electrical - Decontaminated	211	1,737	-	-	-	-	366	2,313	2,313	-	-	-	-	-
31.29	Emergency Diesel Generator	-	48	-	-	-	-	7	55	-	55	-	-	-	-
31.30	Emergency Diesel Generator - Insulated	-	5	-	-	-	-	1	6	-	6	-	-	-	-
31.31	Extraction Steam	-	42	-	-	-	-	6	48	-	48	-	-	-	-
31.32	Extraction Steam - Insulated	-	47	-	-	-	-	7	54	-	54	-	-	-	-
31.33	Feedwater - Insulated	-	64	-	-	-	-	10	73	-	73	-	-	-	-
31.34	Feedwater - Insulated - RCA	8	17	-	-	-	-	6	31	31	-	-	-	-	-
31.35	Fire Protection	-	27	-	-	-	-	4	31	-	31	-	-	-	-
31.36	Fire Protection - Insulated	-	3	-	-	-	-	0	3	-	3	-	-	-	-
31.37	Fire Protection - Insulated - RCA	1	2	-	-	-	-	1	3	3	-	-	-	-	-
31.38	Fire Protection - RCA	9	21	-	-	-	-	8	38	38	-	-	-	-	-
31.39	Fuel Pool	127	95	-	-	364	-	178	764	764	-	719	-	-	82,755

TABLE D-3
ST. LUCIE PLANT - UNIT 2
DECON DECOMMISSIONING COST ESTIMATE
(Thousands of 1998 Dollars)

ID Number	Activity Description	Decon	Remove	Pack	Ship	Burial	Other	Contingency	Total	NRC LicTerm	Site Restore	Burial site			10 CFR 61
												A CF	B CF	C CF	GTCC Cu Ft
Disposal of Plant Systems (continued)															
31.40	Fuel Pool - Insulated	85	66	-	-	128	-	91	370	370	-	234	-	-	29,062
31.41	HVAC	-	247	-	-	-	-	37	284	-	284	-	-	-	-
31.42	HVAC - Contaminated	-	1,445	-	-	468	794	597	3,304	3,304	-	922	-	-	106,417
31.43	Heater Drain & Vents - Insulated	-	112	-	-	-	-	17	128	-	128	-	-	-	-
31.44	Hydrogen Sampling	-	35	-	-	117	-	38	190	190	-	223	-	-	26,621
31.45	Integrated Leak Rate Testing	-	29	-	-	72	-	25	127	127	-	137	-	-	16,387
31.46	Main Steam - Insulated	-	102	-	-	-	-	15	117	-	117	-	-	-	-
31.47	Main Steam - Insulated - RCA	8	18	-	-	-	-	7	32	32	-	-	-	-	-
31.48	Misc Bulk Gas Supply	-	8	-	-	-	-	1	9	-	9	-	-	-	-
31.49	Misc Bulk Gas Supply - RCA	2	5	-	-	-	-	1	8	8	-	-	-	-	-
31.50	Miscellaneous	-	1	-	-	-	-	0	1	-	1	-	-	-	-
31.51	Miscellaneous - RCA	1	2	-	-	-	-	1	4	4	-	-	-	-	-
31.52	Post Accident Sampling	-	2	-	-	1	-	1	3	3	-	1	-	-	186
31.53	Post Accident Sampling - Insulated	-	17	-	-	7	-	6	30	30	-	12	-	-	1,672
31.54	Primary Water	-	98	-	-	56	66	48	268	268	-	140	-	-	12,690
31.55	Primary Water - Insulated	-	2	-	-	3	-	1	7	7	-	6	-	-	699
31.56	RCP Oil Collection	10	6	-	-	11	-	10	38	38	-	20	-	-	2,608
31.57	Radiation Monitoring	-	16	-	-	15	-	8	39	39	-	26	-	-	3,447
31.58	Reactor Coolant - Insulated	20	46	-	-	92	-	44	202	202	-	161	-	-	20,994
31.59	Refueling Equipment	-	82	-	-	87	0	42	211	211	-	172	-	-	19,681
31.60	SGBTf Blowdown - Insulated	-	495	-	-	340	130	228	1,193	1,193	-	753	-	-	77,223
31.61	SGBTf Demin - Ins - RCA	7	16	-	-	-	-	6	29	29	-	-	-	-	-
31.62	SGBTf Demin - RCA	8	26	-	-	-	-	8	41	41	-	-	-	-	-
31.63	SGBTf Miscellaneous - RCA	2	8	-	-	-	-	2	12	12	-	-	-	-	-
31.64	SGBTf Waste Management	32	38	-	-	193	-	74	337	337	-	616	-	-	43,845
31.65	SGBTf Waste Management - Insulated	48	51	-	-	80	-	57	236	236	-	152	-	-	18,169
31.66	Safety Injection	-	156	-	-	231	141	118	647	647	-	462	-	-	52,540
31.67	Safety Injection - Insulated	-	756	-	-	1,505	-	565	2,826	2,826	-	2,720	-	-	341,947
31.68	Sampling	-	5	-	-	-	-	1	6	-	6	-	-	-	-
31.69	Sampling - Insulated	-	7	-	-	-	-	1	8	-	8	-	-	-	-
31.70	Sampling - Insulated - RCA	5	15	-	-	-	-	5	24	24	-	-	-	-	-
31.71	Sampling - RCA	5	12	-	-	-	-	4	21	21	-	-	-	-	-
31.72	Secondary Side Wet Layup	-	7	-	-	-	-	1	8	-	8	-	-	-	-
31.73	Secondary Side Wet Layup - Ins	-	9	-	-	-	-	1	10	-	10	-	-	-	-
31.74	Secondary Side Wet Layup - Ins - RCA	2	5	-	-	-	-	2	9	9	-	-	-	-	-
31.75	Secondary Side Wet Layup - RCA	1	5	-	-	-	-	1	7	7	-	-	-	-	-
31.76	Service & Instrument Air	-	11	-	-	-	-	2	12	-	12	-	-	-	-
31.77	Service & Instrument Air - Ins	-	5	-	-	-	-	1	6	-	6	-	-	-	-
31.78	Service & Instrument Air - Ins - RCA	8	22	-	-	-	-	7	37	37	-	-	-	-	-
31.79	Service & Instrument Air - RCA	5	14	-	-	-	-	5	24	24	-	-	-	-	-
31.80	Sodium Hypochlorite	-	24	-	-	-	-	4	27	-	27	-	-	-	-
31.81	Spent Fuel	3	7	-	-	33	-	12	55	55	-	65	-	-	7,500
31.82	Spent Fuel - Ins	3	2	-	-	2	-	3	10	10	-	3	-	-	468
31.83	Steam Gen Blowdown Cooling	-	9	-	-	-	-	1	10	-	10	-	-	-	-
31.84	Steam Gen Blowdown Cooling - Ins - RCA	11	24	-	-	-	-	9	44	44	-	-	-	-	-
31.85	Steam Gen Blowdown Cooling - Insulated	-	1	-	-	-	-	0	1	-	1	-	-	-	-
31.86	Steam Gen Blowdown Cooling - RCA	15	31	-	-	-	-	12	58	58	-	-	-	-	-
31.87	Steam Generator Blowdown	-	15	-	-	35	-	13	64	64	-	60	-	-	8,052
31.88	Steam Generator Blowdown - Insulated	-	49	-	-	77	-	32	158	158	-	148	-	-	17,606
31.89	Turbine	-	1	-	-	-	-	0	1	-	1	-	-	-	-
31.90	Turbine Cooling Water	-	31	-	-	-	-	5	36	-	36	-	-	-	-
31.91	Turbine Cooling Water - Insulated	-	22	-	-	-	-	3	25	-	25	-	-	-	-
31.92	Turbine Lube Oil & Diesel Oil	-	32	-	-	-	-	5	37	-	37	-	-	-	-
31.93	Waste Management	770	522	-	-	1,804	-	966	4,061	4,061	-	5,181	-	-	409,911
31.94	Waste Management - Insulated	2,239	1,247	-	-	1,748	-	1,868	7,102	7,102	-	2,978	-	-	397,314
31 Totals		4,728	12,493	-	-	9,560	1,562	7,591	35,934	32,403	3,531	20,243	-	-	2,172,794
32	Erect scaffolding for systems removal	-	905	-	-	26	85	245	1,261	1,261	-	83	-	-	9,243

TABLE D-3
ST. LUCIE PLANT - UNIT 2
DECON DECOMMISSIONING COST ESTIMATE
(Thousands of 1998 Dollars)

ID Number	Activity Description	Decon	Remove	Pack	Ship	Burial	Other	Contingency	Total	NRC LicTerm	Site Restore	Burial site			pounds	10 CFR 61 GTCC Cu Ft
												A CF	B CF	C CF		
Decontamination of Site Buildings																
33.1	Reactor Building	665	375	54	22	3,430	155	1,316	6,016	6,016	-	7,301	-	-	821,464	-
33.2	East EP Pond	-	3	26	11	1,095	-	279	1,414	1,414	-	3,555	-	-	373,005	-
33.3	Fuel Handling Building	225	214	2	1	92	124	208	866	866	-	298	-	-	31,807	-
33.4	Primary Water Tank & Pump - Contaminate	1	4	2	1	119	-	31	158	158	-	240	-	-	27,384	-
33.5	Reactor Auxiliary Building	309	25	15	6	612	26	320	1,311	1,311	-	1,987	-	-	207,788	-
33.6	Steam Generator Blowdown Treatment	97	1	5	2	204	1	100	409	409	-	661	-	-	69,339	-
33	Totals	1,297	621	103	42	5,552	305	2,254	10,174	10,174	-	14,042	-	-	1,530,787	-
34	ORISE confirmatory survey	-	-	-	-	-	1,064	319	1,383	1,383	-	-	-	-	-	-
35	Terminate license	-	-	-	-	-	-	-	Note 1	-	-	-	-	-	-	-
Period 2 Additional Costs																
36	License Termination Survey	-	-	-	-	-	5,692	854	6,546	6,546	-	-	-	-	-	-
37	Mixed/Hazardous Waste	-	-	-	-	-	3,884	583	4,466	4,466	-	-	-	-	-	-
Subtotal Period 2 Activity Costs		6,812	19,723	5,411	2,690	49,168	12,778	32,132	128,713	124,900	3,813	71,545	2,708	408	8,598,556	655
Period 2 Undistributed Costs																
1	Decon equipment	488	-	-	-	-	-	73	561	561	-	-	-	-	-	-
2	Decon supplies	613	-	-	-	-	-	153	767	767	-	-	-	-	-	-
3	DOC staff relocation expenses	-	837	-	-	-	-	126	963	963	-	-	-	-	-	-
4	Process liquid waste	456	-	240	356	2,652	-	968	4,672	4,672	-	4,358	-	-	602,714	-
5	Insurance	-	-	-	-	-	1,376	138	1,514	1,514	-	-	-	-	-	-
6	Property taxes	-	-	-	-	-	2,503	250	2,753	2,478	275	-	-	-	-	-
7	Health physics supplies	-	3,167	-	-	-	-	792	3,959	3,959	-	-	-	-	-	-
8	Heavy equipment rental	-	9,747	-	-	-	-	1,462	11,209	10,088	1,121	-	-	-	-	-
9	Small tool allowance	-	318	-	-	-	-	48	365	329	37	-	-	-	-	-
10	Pipe cutting equipment	-	749	-	-	-	-	112	862	862	-	-	-	-	-	-
11	Decon rig	974	-	-	-	-	-	146	1,120	1,120	-	-	-	-	-	-
12	Disposal of DAW generated	-	-	72	21	4,134	-	1,044	5,271	5,271	-	13,421	-	-	886,929	-
13	Decommissioning Equipment Disposition	-	-	-	-	83	277	62	422	422	-	270	-	-	30,000	-
14	Plant energy budget	-	-	-	-	-	3,077	462	3,539	3,185	354	-	-	-	-	-
15	NRC Fees	-	-	-	-	-	1,619	162	1,781	1,781	-	-	-	-	-	-
16	Emergency Planning Fees	-	-	-	-	-	189	19	208	208	-	-	-	-	-	-
17	Site Security Cost	-	-	-	-	-	7,013	1,052	8,065	8,065	-	-	-	-	-	-
18	Fixed Overhead	-	-	-	-	-	4,762	714	5,476	5,476	-	-	-	-	-	-
19	Radwaste Processing Skids	-	-	-	-	-	421	63	484	484	-	-	-	-	-	-
Subtotal Undistributed Costs Period 2		2,531	14,819	312	377	6,869	21,238	7,846	53,992	52,205	1,787	13,692	4,358	-	1,519,643	-
Staff Costs																
DOC Staff Cost		-	-	-	-	-	35,629	5,344	40,973	40,973	-	-	-	-	-	-
Utility Staff Cost		-	-	-	-	-	74,584	11,188	85,771	85,771	-	-	-	-	-	-
TOTAL PERIOD 2		9,343	34,541	5,723	3,066	56,037	144,229	56,511	309,450	303,850	5,600	85,236	7,066	408	10,118,199	655

TABLE D-3
ST. LUCIE PLANT - UNIT 2
DECON DECOMMISSIONING COST ESTIMATE
(Thousands of 1998 Dollars)

ID Number	Activity Description	Decon	Remove	Pack	Ship	Burial	Other	Contingency	Total	NRC LicTerm	Site Restore	Burial site			10 CFR 61 GTCC Cu Ft
												A CF	B CF	C CF	pounds
PERIOD 3															
Demolition of Remaining Site Buildings															
38.1	Reactor Building	-	5,119	-	-	-	-	768	5,887	683	5,004	-	-	-	-
38.2	Fuel Handling Building	-	682	-	-	-	-	102	784	78	705	-	-	-	-
38.3	Intake Structure & CWS	-	5,018	-	-	-	-	753	5,771	-	5,771	-	-	-	-
38.4	Miscellaneous Structures	-	2,573	-	-	-	-	386	2,959	-	2,959	-	-	-	-
38.5	Primary Water Tank & Pump - Contaminated	-	2	-	-	-	-	0	2	-	2	-	-	-	-
38.6	Reactor Auxiliary Building	-	1,251	-	-	-	-	188	1,439	144	1,295	-	-	-	-
38.7	Steam Generator Blowdown Treatment	-	363	-	-	-	-	54	418	21	397	-	-	-	-
38.8	Turbine Building	-	825	-	-	-	-	124	948	-	948	-	-	-	-
38.9	Turbine Pedestal	-	440	-	-	-	-	66	506	-	506	-	-	-	-
38	Totals	-	16,273	-	-	-	-	2,441	18,714	1,126	17,587	-	-	-	-
Site Closeout Activities															
39	Grade & landscape site	-	81	-	-	-	-	12	93	-	93	-	-	-	-
40	Final report to NRC	-	-	-	-	-	67	10	77	77	-	-	-	-	-
Subtotal Period 3 Activity Costs															
		-	16,354	-	-	-	67	2,463	18,883	1,203	17,680	-	-	-	-
Period 3 Undistributed Costs															
1	Insurance	-	-	-	-	-	111	11	122	122	-	-	-	-	-
2	Property taxes	-	-	-	-	-	470	47	517	-	517	-	-	-	-
3	Heavy equipment rental	-	1,677	-	-	-	-	252	1,929	-	1,929	-	-	-	-
4	Small tool allowance	-	110	-	-	-	-	17	127	-	127	-	-	-	-
5	Plant energy budget	-	-	-	-	-	53	8	61	-	61	-	-	-	-
6	Site Security Cost	-	-	-	-	-	392	59	451	-	451	-	-	-	-
Subtotal Undistributed Costs Period 3															
		-	1,787	-	-	-	1,027	393	3,207	122	3,085	-	-	-	-
Staff Costs															
	DOC Staff Cost	-	-	-	-	-	4,762	714	5,476	-	5,476	-	-	-	-
	Utility Staff Cost	-	-	-	-	-	2,689	403	3,093	2,783	309	-	-	-	-
TOTAL PERIOD 3															
		-	18,141	-	-	-	8,545	3,974	30,660	4,109	26,551	-	-	-	-

000203

TABLE D-3
ST. LUCIE PLANT - UNIT 2
DECON DECOMMISSIONING COST ESTIMATE
(Thousands of 1998 Dollars)

ID Number	Activity Description	Decon	Remove	Pack	Ship	Burial	Other	Contingncy	Total	NRC LicTerm	Site Restore	Burial site			10 CFR 61 GTCC Cu Ft	
												A CF	B CF	C CF	pounds	
TOTAL COST TO DECOMMISSION		10,532	54,727	6,182	3,378	61,463	190,827	68,311	395,421	362,124	33,297	90,153	12,352	408	11,165,502	655

Total cost to decommission with	20.88% contingency.	\$	395,420,995
Total NRC license termination cost is	91.58%	or	\$ 362,124,238
Non-nuclear demolition cost is	8.42%	or	\$ 33,296,756
Total site radwaste volume buried		102,913	cubic feet
Total site radwaste weight buried		11,165,502	pounds
Total 10CFR61 greater than class C waste buried		655	cubic feet
Total scrap metal released from site		21,126	tons
Total craft labor requirements		1,405,652	person hours

NOTES:

- 1) This activity is performed by the decommissioning staff following plant shutdown, the costs for this are included in this period's st
- 2) This activity, while performed after final plant shutdown, is considered part of operations and therefore no decommissioning cost

000204

TABLE D-4
ST LUCIE PLANT - UNIT 1
SAFSTOR STATION DECOMMISSIONING COST ESTIMATE
(Thousands of 1998 Dollars)

ID	Activity Description	Decon	Remove	Pack	Ship	Burial	Other	Contingency	Total	NRC LicTerm	Site Restore.	Burial Site			
Number												A CF	B CF	C CF	pounds
PERIOD 1: Mothballing Activities															
1	Prepare preliminary decommissioning cost	-	-	-	-		130	20	150	150	-	-	-	-	
2	Notification of Cessation of Operations								Note 1						
3	Remove fuel & source material								Note 2						
4	Notification of Permanent Defueling								Note 1						
5	Deactivate plant systems & process waste								Note 1						
6	Prepare and submit PSDAR	-	-	-	-		200	30	230	230	-		-	-	
7	Review plant dwgs & specs.	-	-	-	-		130	20	150	150	-		-	-	
8	Perform detailed rad survey								Note 1						
9	Estimate by-product inventory	-	-	-	-		100	15	115	115	-		-	-	
10	End product description	-	-	-	-		100	15	115	115	-		-	-	
11	Detailed by-product inventory	-	-	-	-		150	23	173	173	-		-	-	
12	Define major work sequence	-	-	-	-		100	15	115	115	-		-	-	
13	Perform SER and EA	-	-	-	-		310	47	357	357	-		-	-	
14	Perform Site-Specific Cost Study	-	-	-	-		500	75	575	575	-		-	-	
15	Prepare/submit License Termination Plan	-	-	-	-		410	61	471	471	-		-	-	
16	Receive NRC approval of termination plan								Note 1						
Activity Specifications															
17.1	Prepare plant and facilities for SAFSTOR	-	-	-	-		492	74	566	566	-		-	-	
17.2	Plant systems	-	-	-	-		417	63	479	479	-		-	-	
17.3	Plant structures and buildings	-	-	-	-		312	47	359	359	-		-	-	
17.4	Waste management	-	-	-	-		200	30	230	230	-		-	-	
17.5	Facility and site dormancy	-	-	-	-		200	30	230	230	-		-	-	
17	Total	-	-	-	-		1,621	243	1,864	1,864	-		-	-	
Detailed Work Procedures															
18.1	Plant systems	-	-	-	-		473	71	544	544	-		-	-	
18.2	Facility closeout & dormancy	-	-	-	-		120	18	138	138	-		-	-	
18	Total	-	-	-	-		593	89	682	682	-		-	-	
19	Procure vacuum drying system	-	-	-	-		10	2	12	12	-		-	-	
20	Drain/de-energize non-cont. systems	-	-	-	-		-	-	Note 1	-	-		-	-	
21	Drain & dry NSSS	-	-	-	-		-	-	Note 1	-	-		-	-	
22	Drain/de-energize contaminated systems	-	-	-	-		-	-	Note 1	-	-		-	-	
23	Decon/secure contaminated systems	-	-	-	-		-	-	Note 1	-	-		-	-	
Decontamination of Site Buildings															
24.1	Reactor Building	576	-	-	-		-	288	865	865	-		-	-	-
24.2	Fuel Handling Building	214	-	-	-		-	107	322	322	-		-	-	-
24.3	Reactor Auxiliary	244	-	-	-		-	122	366	366	-		-	-	-
24	Totals	1,035	-	-	-		-	517	1,552	1,552	-		-	-	
25	Prepare support equipment for storage	-	279	-	-		-	42	321	321	-		-	-	
26	Install containment pressure equal. lines	-	19	-	-		-	3	22	22	-		-	-	
27	Interim survey prior to dormancy	-	-	-	-		320	48	369	369	-		-	-	
28	Secure building accesses	-	-	-	-		-	-	Note 1	-	-		-	-	
29	Prepare & submit interim report	-	-	-	-		58	9	67	67	-		-	-	
Period 1 Additional Costs															
30	Mixed/Hazardous Waste	-	-	-	-		3,884	583	4,466	4,466	-		-	-	
Subtotal Period 1 Activity Costs		1,035	298	-	-	-	8,616	1,854	11,803	11,803	-	-	-	-	

TABLE D-4
ST LUCIE PLANT - UNIT 1
SAFSTOR STATION DECOMMISSIONING COST ESTIMATE
(Thousands of 1998 Dollars)

ID Number	Activity Description	Decon	Remove	Pack	Ship	Burial	Other	Contingency	Total	NRC LicTerm	Site Restore.	Burial Site			
												A CF	B CF	C CF	pounds
Period 1 Undistributed Costs															
1	Decon equipment	488	-	-	-	-	-	73	561	561	-	-	-	-	
2	Decon supplies	470	-	-	-	-	-	118	588	588	-	-	-	-	
3	Process liquid waste	245	-	89	156	926	-	386	1,802	1,802	-	-	1,669	-	210,421
4	Insurance	-	-	-	-	-	2,098	210	2,307	2,307	-	-	-	-	
5	Property taxes	-	-	-	-	-	591	59	650	650	-	-	-	-	
6	Health physics supplies	-	287	-	-	-	-	72	359	359	-	-	-	-	
7	Small tool allowance	-	15	-	-	-	-	2	17	17	-	-	-	-	
8	Disposal of DAW generated	-	-	18	5	884	-	224	1,130	1,130	-	2,870	-	-	198,153
9	Plant energy budget	-	-	-	-	-	486	73	559	559	-	-	-	-	
10	NRC Fees	-	-	-	-	-	304	30	334	334	-	-	-	-	
11	Emergency Planning Fees	-	-	-	-	-	76	8	83	83	-	-	-	-	
12	Site Security Cost	-	-	-	-	-	1,000	150	1,150	1,150	-	-	-	-	
13	Fixed Overhead	-	-	-	-	-	1,124	169	1,293	1,293	-	-	-	-	
Subtotal Undistributed Costs Period 1		1,204	303	107	161	1,810	5,679	1,573	10,836	10,836	-	2,870	1,669	-	408,574
Staff Costs															
DOC Staff Cost		-	-	-	-	-	-	-	-	-	-	-	-	-	
Utility Staff Cost		-	-	-	-	-	17,780	2,667	20,447	20,447	-	-	-	-	
TOTAL COST TO SAFSTOR		2,238	600	107	161	1,810	32,075	6,095	43,085	43,085	-	2,870	1,669	-	408,574
Total cost to SAFSTOR with 16.48% contingency:		43,085,448													
Total site radwaste volume buried		4,540 cubic feet													
Total craft labor requirements		45,448 person hours													

TABLE D-4
ST LUCIE PLANT - UNIT 1
SAFSTOR STATION DECOMMISSIONING COST ESTIMATE
(Thousands of 1998 Dollars)

ID	Activity Description	Decon	Remove	Pack	Ship	Burial	Other	Contingency	Total	NRC LicTerm	Site Restore.	Burial Site			
Number												A CF	B CF	C CF	pounds
PERIOD 2: SAFSTOR Dormancy Activities															
1	Quarterly Inspection									Note 1					
2	Semi-annual environmental survey									Note 1					
3	Prepare reports									Note 1					
4	Health physics supplies	-	-	-	-		46	11	57	57	-		-	-	
5	Insurance	-	-	-	-		70	7	77	77	-		-	-	
6	Property taxes	-	-	-	-		394	39	433	433	-		-	-	
7	Disposal of contaminated solid waste	-	-	1	0	29	-	7	38	38	-	102	-	-	
8	Biluminous roof replacement	-	-	-	-		1	0	1	1	-		-	-	
9	Maintenance supplies	-	-	-	-		99	25	123	123	-		-	-	
10	Plant energy budget	-	-	-	-		78	12	90	90	-		-	-	
11	NRC Fees	-	-	-	-		162	16	178	178	-		-	-	
12	Emergency Planning Fees	-	-	-	-		4	0	4	4	-		-	-	
13	Site Security Cost	-	-	-	-		219	33	252	252	-		-	-	
14	Fixed Overhead	-	-	-	-		75	11	86	86	-		-	-	
15	Site maintenance staff	-	-	-	-		1,304	196	1,500	1,500	-		-	-	
PERIOD 2 ANNUAL MAINTENANCE TOTALS		-	-	1	0	29	2,450	358	2,839	2,839	-	102	-	-	-
Total cost SAFSTOR dormancy with		51.9792	years equals	147,546,676											
Total site radwaste volume buried				5,297	cubic feet										

000207

TABLE D-4
ST LUCIE PLANT - UNIT 1
SAFSTOR STATION DECOMMISSIONING COST ESTIMATE
(Thousands of 1998 Dollars)

ID	Activity Description	Decon	Remove	Pack	Ship	Burial	Other	Contingency	Total	NRC LicTerm	Site Restore.	Burial Site			
Number												A CF	B CF	C CF	pounds
PERIOD 3															
1	Review plant dwgs & specs.	-	-	-	-		460	69	529	529	-	-	-	-	-
2	Perform detailed rad survey	-	-	-	-				Note 1		-	-	-	-	-
3	End product description	-	-	-	-		100	15	115	115	-	-	-	-	-
4	Detailed by-product inventory	-	-	-	-		130	20	150	150	-	-	-	-	-
5	Define major work sequence	-	-	-	-		750	113	863	863	-	-	-	-	-
6	Perform SER and EA	-	-	-	-		310	47	357	357	-	-	-	-	-
7	Perform Site-Specific Cost Study	-	-	-	-		500	75	575	575	-	-	-	-	-
8	Prepare/submit License Termination Plan	-	-	-	-		410	61	471	471	-	-	-	-	-
9	Receive NRC approval of termination plan	-	-	-	-				Note 1		-	-	-	-	-
Activity Specifications															
10.1	Re-activate plant & temporary facilities	-	-	-	-		737	111	848	763	85	-	-	-	-
10.2	Plant systems	-	-	-	-		417	63	479	431	48	-	-	-	-
10.3	Reactor internals	-	-	-	-		710	107	817	817	-	-	-	-	-
10.4	Reactor vessel	-	-	-	-		650	98	748	748	-	-	-	-	-
10.5	Biological shield	-	-	-	-		50	8	58	58	-	-	-	-	-
10.6	Steam generators	-	-	-	-		312	47	359	359	-	-	-	-	-
10.7	Reinforced concrete	-	-	-	-		160	24	184	92	92	-	-	-	-
10.8	Turbine & condenser	-	-	-	-		80	12	92	-	92	-	-	-	-
10.9	Plant structures & buildings	-	-	-	-		312	47	359	179	179	-	-	-	-
10.10	Waste management	-	-	-	-		460	69	529	529	-	-	-	-	-
10.11	Facility & site closeout	-	-	-	-		90	14	104	52	52	-	-	-	-
10	Total	-	-	-	-		3,978	597	4,574	4,026	548	-	-	-	-
Planning & Site Preparations															
11	Prepare dismantling sequence	-	-	-	-		240	36	276	276	-	-	-	-	-
12	Plant prep. & temp. svces	-	-	-	-		1,895	284	2,180	2,180	-	-	-	-	-
13	Design water clean-up system	-	-	-	-		140	21	161	161	-	-	-	-	-
14	Rigging/Cont. Cntrl Envirps/tooling/etc.	-	-	-	-		1,604	241	1,845	1,845	-	-	-	-	-
15	Procure casks/liners & containers	-	-	-	-		123	18	141	141	-	-	-	-	-
Detailed Work Procedures															
16.1	Plant systems	-	-	-	-		473	71	544	490	54	-	-	-	-
16.2	Reactor internals	-	-	-	-		250	38	288	288	-	-	-	-	-
16.3	Remaining buildings	-	-	-	-		135	20	155	39	116	-	-	-	-
16.4	CRD cooling assembly	-	-	-	-		100	15	115	115	-	-	-	-	-
16.5	CRD housings & ICI tubes	-	-	-	-		100	15	115	115	-	-	-	-	-
16.6	Incore instrumentation	-	-	-	-		100	15	115	115	-	-	-	-	-
16.7	Reactor vessel	-	-	-	-		383	54	417	417	-	-	-	-	-
16.8	Facility closeout	-	-	-	-		120	18	138	69	69	-	-	-	-
16.9	Missile shields	-	-	-	-		45	7	52	52	-	-	-	-	-
16.10	Biological shield	-	-	-	-		120	18	138	138	-	-	-	-	-
16.11	Steam generators	-	-	-	-		460	69	529	529	-	-	-	-	-
16.12	Reinforced concrete	-	-	-	-		100	15	115	58	58	-	-	-	-
16.13	Turbine & condensers	-	-	-	-		312	47	359	-	359	-	-	-	-
16.14	Auxiliary building	-	-	-	-		273	41	314	283	31	-	-	-	-
16.15	Reactor building	-	-	-	-		273	41	314	283	31	-	-	-	-
16	Total	-	-	-	-		3,224	484	3,708	2,989	719	-	-	-	-
17	Asbestos removal program	-	724	129	4	807	23	400	2,087	1,470	617	2,242	-	-	-

000208

TABLE D-4
ST LUCIE PLANT - UNIT 1
SAFSTOR STATION DECOMMISSIONING COST ESTIMATE
(Thousands of 1998 Dollars)

ID Number	Activity Description	Decon	Remove	Pack	Ship	Burial	Other	Contingency	Total	NRC LicTerm	Site Restore.	Burial Site				
												A CF	B CF	C CF	pounds	
Period 3 Additional Costs																
18	Site Characterization Survey	-	-	-	-	-	403	60	463	463	-	-	-	-	-	
Subtotal Period 3 Activity Costs		-	724	129	4	807	14,291	2,540	18,495	16,611	1,884	2,242	-	-	-	
Period 3 Undistributed Costs																
1	DOC staff relocation expenses	-	837	-	-	-	-	126	963	963	-	-	-	-	-	
2	Insurance	-	-	-	-	-	285	28	313	313	-	-	-	-	-	
3	Property taxes	-	-	-	-	-	593	59	653	653	-	-	-	-	-	
4	Health physics supplies	-	264	-	-	-	-	66	330	330	-	-	-	-	-	
5	Heavy equipment rental	-	444	-	-	-	-	67	510	510	-	-	-	-	-	
6	Disposal of DAW generated	-	-	18	5	887	-	224	1,135	1,135	-	2,881	-	-	198,924	
7	Plant energy budget	-	-	-	-	-	516	77	594	594	-	-	-	-	-	
8	NRC Fees	-	-	-	-	-	305	30	335	335	-	-	-	-	-	
9	Site Security Cost	-	-	-	-	-	715	107	822	822	-	-	-	-	-	
10	Fixed Overhead	-	-	-	-	-	1,129	169	1,298	1,298	-	-	-	-	-	
Subtotal Undistributed Costs Period 3		-	1,545	18	5	887	3,542	955	6,952	6,952	-	2,881	-	-	198,924	
Staff Costs																
DOC Staff Cost		-	-	-	-	-	5,345	802	6,147	6,147	-	-	-	-	-	
Utility Staff Cost		-	-	-	-	-	16,458	2,469	18,927	18,927	-	-	-	-	-	
TOTAL PERIOD 3 COST		-	2,269	148	9	1,694	39,636	6,765	50,522	48,638	1,884	5,123	-	-	198,924	

000209

TABLE D-4
ST LUCIE PLANT - UNIT 1
SAFSTOR STATION DECOMMISSIONING COST ESTIMATE
(Thousands of 1998 Dollars)

ID	Activity Description	Decon	Remove	Pack	Ship	Burial	Other	Contingency	Total	NRC LicTerm	Site Restore.	Burial Site			pounds
Number												A CF	B CF	C CF	
PERIOD 4															
Nuclear Steam Supply System Removal															
19.1	Reactor Coolant Piping	30	45	4	5	153	-	66	302	302	-	371	-	-	34,669
19.2	Pressurizer Relief Tank	3	17	1	1	26	-	12	60	60	-	89	-	-	5,824
19.3	Reactor Coolant Pumps & Motors	72	39	28	20	2,730	-	734	3,622	3,622	-	5,776	-	-	620,400
19.4	Pressurizer	17	27	4	8	1,053	-	280	1,387	1,387	-	2,134	-	-	239,212
19.5	Steam Generators	98	613	2,045	1,956	4,568	-	1,842	11,124	11,124	-	19,034	-	-	2,524,482
19.6	CRDMs/ICIs/Service Structure Removal	79	51	62	12	254	-	124	582	582	-	2,907	-	-	75,041
19.7	Reactor Vessel Internals	43	1,149	2,881	211	2,633	-	2,973	9,889	9,889	-	1,441	524	408	264,053
19.8	Vessel & Internals GTCC Disposal	-	-	-	-	13,290	-	6,645	19,935	19,935	-	-	-	-	-
19.9	Reactor Vessel	119	3,319	217	289	4,856	-	5,103	13,904	13,904	-	4,847	2,096	-	983,277
19	Totals	461	5,260	5,242	2,501	29,562	-	17,779	60,805	60,805	-	38,599	2,620	408	4,746,957
20	Remove spent fuel racks	238	26	-	-	106	201	182	754	754	-	346	-	-	38,385
Removal of Major Equipment															
21	Main Turbine/Generator	-	49	-	-	-	-	7	56	-	56	-	-	-	-
22	Main Condensers	-	199	-	-	-	-	30	229	-	229	-	-	-	-
Disposal of Plant Systems															
23.1	Air Evacuation	-	4	-	-	-	-	1	4	-	4	-	-	-	-
23.2	Air Evacuation - Insulated	-	15	-	-	-	-	2	17	-	17	-	-	-	-
23.3	Auxiliary Steam - Insulated	-	12	-	-	-	-	2	14	-	14	-	-	-	-
23.4	Chemical & Volume Control	-	57	-	-	288	-	86	431	431	-	912	-	-	65,546
23.5	Chemical & Volume Control - Insulated	-	331	-	-	516	-	212	1,059	1,059	-	894	-	-	117,281
23.6	Chemical Feed	-	1	-	-	-	-	0	2	-	2	-	-	-	-
23.7	Chemical Feed - Insulated	-	1	-	-	-	-	0	1	-	1	-	-	-	-
23.8	Circulating & Intake Cooling Water	-	125	-	-	-	-	19	144	-	144	-	-	-	-
23.9	Component Cooling	-	39	-	-	-	-	6	45	-	45	-	-	-	-
23.10	Component Cooling - RCA	-	101	-	-	-	-	15	116	116	-	-	-	-	-
23.11	Condensate	-	81	-	-	-	-	12	93	-	93	-	-	-	-
23.12	Condensate - Insulated	-	46	-	-	-	-	7	52	-	52	-	-	-	-
23.13	Condensate Polish Filter Demin	-	12	-	-	-	-	2	14	-	14	-	-	-	-
23.14	Condensate Polish Filter Demin - Ins	-	37	-	-	-	-	8	43	-	43	-	-	-	-
23.15	Condensate Recovery	-	2	-	-	-	-	0	2	-	2	-	-	-	-
23.16	Condensate Recovery - Insulated	-	0	-	-	-	-	0	0	-	0	-	-	-	-
23.17	Condensate Recovery - Insulated - RCA	-	0	-	-	-	-	0	0	0	-	-	-	-	-
23.18	Condensate Recovery - RCA	-	3	-	-	-	-	0	4	4	-	-	-	-	-
23.19	Condenser Tube Cleaning	-	17	-	-	-	-	3	20	-	20	-	-	-	-
23.20	Contnmnt Spray & Refueling Water	-	245	-	-	2,483	-	682	3,411	3,411	-	6,404	-	-	564,410
23.21	Contnmnt Spray & Refueling Water - Ins	-	142	-	-	649	-	198	988	988	-	1,259	-	-	147,467
23.22	Demineralized Makeup Water	-	8	-	-	-	-	1	9	-	9	-	-	-	-
23.23	Demineralized Makeup Water - RCA	-	4	-	-	-	-	1	5	5	-	-	-	-	-
23.24	Domestic/Makeup/Service Water	-	92	-	-	-	-	14	106	-	106	-	-	-	-
23.25	Domestic/Makeup/Service Water - RCA	-	31	-	-	-	-	5	36	36	-	-	-	-	-
23.26	Domestic/Makeup/Service Water-Ins	-	2	-	-	-	-	0	2	-	2	-	-	-	-
23.27	Domestic/Makeup/Service Water-Ins-RCA	-	3	-	-	-	-	1	4	4	-	-	-	-	-
23.28	Electrical - Clean	-	1,024	-	-	-	-	154	1,177	-	1,177	-	-	-	-
23.29	Electrical - Contaminated	-	408	-	-	18	72	117	615	615	-	36	-	-	4,061
23.30	Electrical - Decontaminated	-	773	-	-	-	-	116	888	888	-	-	-	-	-
23.31	Emergency Diesel Generator	-	38	-	-	-	-	6	43	-	43	-	-	-	-
23.32	Emergency Diesel Generator - Insulated	-	3	-	-	-	-	1	4	-	4	-	-	-	-
23.33	Extraction Steam	-	42	-	-	-	-	6	48	-	48	-	-	-	-
23.34	Extraction Steam - Insulated	-	42	-	-	-	-	6	48	-	48	-	-	-	-
23.35	Feedwater - Insulated	-	45	-	-	-	-	7	51	-	51	-	-	-	-
23.36	Feedwater - Insulated - RCA	-	10	-	-	-	-	1	11	11	-	-	-	-	-
23.37	Fire Protection	-	36	-	-	-	-	5	41	-	41	-	-	-	-
23.38	Fire Protection - Insulated	-	3	-	-	-	-	1	4	-	4	-	-	-	-
23.39	Fire Protection - Insulated - RCA	-	1	-	-	-	-	0	1	1	-	-	-	-	-
23.40	Fire Protection - RCA	-	7	-	-	-	-	1	8	8	-	-	-	-	-

TABLE D-4
ST LUCIE PLANT - UNIT 1
SAFSTOR STATION DECOMMISSIONING COST ESTIMATE
(Thousands of 1998 Dollars)

ID Number	Activity Description	Decon	Remove	Pack	Ship	Burial	Other	Contingency	Total	NRC LicTerm	Site Restore.	Burial Site			
												A CF	B CF	C CF	pounds
Disposal of Plant Systems (continued)															
23.41	Fuel Pool	-	55	-	-	231	-	72	358	358	-	465	-	-	52,522
23.42	Fuel Pool - Insulated	-	35	-	-	66	-	25	126	126	-	119	-	-	14,974
23.43	HVAC	-	61	-	-	-	-	9	70	-	70	-	-	-	-
23.44	HVAC - Contaminated	-	1,239	-	-	383	787	524	2,933	2,933	-	751	-	-	86,998
23.45	Heater Drain & Vent - Insulated	-	93	-	-	-	-	14	108	-	108	-	-	-	-
23.46	Hydrogen Sampling	-	25	-	-	108	-	33	187	167	-	209	-	-	24,624
23.47	Integrated Leak Rate Testing	-	22	-	-	60	-	20	102	102	-	111	-	-	13,585
23.48	Main Steam - Insulated	-	98	-	-	-	-	15	113	-	113	-	-	-	-
23.49	Main Steam - Insulated - RCA	-	14	-	-	-	-	2	17	17	-	-	-	-	-
23.50	Misc Bulk Gas	-	10	-	-	-	-	1	11	-	11	-	-	-	-
23.51	Misc Bulk Gas - RCA	-	5	-	-	-	-	1	5	5	-	-	-	-	-
23.52	Miscellaneous	-	5	-	-	-	-	1	6	-	6	-	-	-	-
23.53	Miscellaneous - RCA	-	3	-	-	-	-	1	4	4	-	-	-	-	-
23.54	Neutralization Basin Recirculation	-	9	-	-	-	-	1	10	-	10	-	-	-	-
23.55	Post Accident Sampling	-	8	-	-	33	-	10	51	51	-	64	-	-	7,400
23.56	Post Accident Sampling - Insulated	-	26	-	-	24	-	13	63	63	-	41	-	-	5,543
23.57	Primary Water	-	85	-	-	56	78	47	266	266	-	140	-	-	12,728
23.58	Primary Water - Insulated	-	2	-	-	3	-	1	6	6	-	6	-	-	689
23.59	RCP Oil Collection	-	1	-	-	1	0	0	2	2	-	2	-	-	175
23.60	Radiation Monitoring	-	13	-	-	13	-	7	33	33	-	22	-	-	3,004
23.61	Reactor Coolant - Insulated	-	41	-	-	94	-	34	169	169	-	163	-	-	21,388
23.62	Refueling Equipment	-	58	-	-	268	-	81	407	407	-	533	-	-	60,959
23.63	SGBTf Blowdown - Insulated	-	90	-	-	139	-	57	286	286	-	239	-	-	31,555
23.64	SGBTf HVAC	-	197	-	-	36	141	79	453	453	-	71	-	-	8,136
23.65	SGBTf Misc - RCA	-	1	-	-	-	-	0	1	1	-	-	-	-	-
23.66	SGBTf Waste Management	-	4	-	-	6	-	2	12	12	-	10	-	-	1,335
23.67	SGBTf Waste Management - Insulated	-	36	-	-	55	-	23	114	114	-	92	-	-	12,527
23.68	Safety Injection	-	112	-	-	1,443	-	389	1,943	1,943	-	3,247	-	-	327,912
23.69	Safety Injection - Insulated	-	405	-	-	985	-	347	1,737	1,737	-	1,786	-	-	223,859
23.70	Sampling	-	4	-	-	-	-	1	5	-	5	-	-	-	-
23.71	Sampling - Insulated	-	4	-	-	-	-	1	5	-	5	-	-	-	-
23.72	Sampling - Insulated - RCA	-	7	-	-	-	-	1	8	8	-	-	-	-	-
23.73	Sampling - RCA	-	7	-	-	-	-	1	8	8	-	-	-	-	-
23.74	Secondary Side Wet Layup	-	6	-	-	-	-	1	7	-	7	-	-	-	-
23.75	Secondary Side Wet Layup - Ins	-	7	-	-	-	-	1	9	-	9	-	-	-	-
23.76	Secondary Side Wet Layup - Ins - RCA	-	4	-	-	-	-	1	4	4	-	-	-	-	-
23.77	Secondary Side Wet Layup - RCA	-	4	-	-	-	-	1	4	4	-	-	-	-	-
23.78	Service & Instrument Air	-	13	-	-	-	-	2	16	-	16	-	-	-	-
23.79	Service & Instrument Air - Ins	-	7	-	-	-	-	1	8	-	8	-	-	-	-
23.80	Service & Instrument Air - Ins - RCA	-	24	-	-	-	-	4	28	28	-	-	-	-	-
23.81	Service & Instrument Air - RCA	-	17	-	-	-	-	3	20	20	-	-	-	-	-
23.82	Steam Gen Blowdown Cooling	-	8	-	-	-	-	1	9	-	9	-	-	-	-
23.83	Steam Gen Blowdown Cooling - Ins - RCA	-	15	-	-	-	-	2	17	17	-	-	-	-	-
23.84	Steam Gen Blowdown Cooling - Insulated	-	1	-	-	-	-	0	1	-	1	-	-	-	-
23.85	Steam Gen Blowdown Cooling - RCA	-	19	-	-	-	-	3	22	22	-	-	-	-	-
23.86	Steam Generator Blowdown	-	17	-	-	67	-	21	105	105	-	136	-	-	15,145
23.87	Steam Generator Blowdown - Insulated	-	46	-	-	81	-	32	159	159	-	148	-	-	18,323
23.88	Turbine	-	1	-	-	-	-	0	1	-	1	-	-	-	-
23.89	Turbine Cooling Water	-	28	-	-	-	-	4	33	-	33	-	-	-	-
23.90	Turbine Cooling Water - Insulated	-	18	-	-	-	-	3	20	-	20	-	-	-	-
23.91	Turbine Lube Oil & Diesel Oil	-	35	-	-	-	-	5	40	-	40	-	-	-	-
23.92	Waste Management	-	364	-	-	1,759	-	531	2,654	2,654	-	5,390	-	-	399,788
23.93	Waste Management - Insulated	-	643	-	-	1,016	-	415	2,073	2,073	-	1,751	-	-	230,863
23.94	Water Treatment	-	34	-	-	-	-	5	39	-	39	-	-	-	-
23.95	Water Treatment - Insulated	-	19	-	-	-	-	3	22	-	22	-	-	-	-
23	Totals	-	7,948	-	-	10,880	1,078	4,544	24,451	21,933	2,517	25,000	-	-	2,472,795
24	Erect scaffolding for systems removal	-	698	-	-	21	71	191	981	981	-	70	-	-	7,726

TABLE D-4
ST LUCIE PLANT - UNIT 1
SAFSTOR STATION DECOMMISSIONING COST ESTIMATE
(Thousands of 1998 Dollars)

ID Number	Activity Description	Decon	Remove	Pack	Ship	Burial	Other	Contingency	Total	NRC LicTerm	Site Restore.	Burial Site			pounds
												A CF	B CF	C CF	
Decontamination of Site Buildings															
25.1	Reactor Building	588	331	54	22	3,430	155	1,266	5,846	5,846	-	7,301	-	-	821,464
25.2	Fuel Handling Building	198	189	2	1	92	124	188	794	794	-	298	-	-	31,807
25.3	Primary Water Tank Foundation - Contam	1	10	66	27	2,806	-	715	3,624	3,624	-	8,964	-	-	942,684
25.4	Reactor Auxiliary	274	22	15	6	612	26	301	1,255	1,255	-	1,987	-	-	207,788
25.5	Refueling Water Storage Tank - Contam	1	8	16	7	787	-	202	1,021	1,021	-	2,237	-	-	239,387
25	Totals	1,062	559	153	62	7,727	304	2,673	12,539	12,539	-	20,786	-	-	2,243,130
26	ORISE confirmatory survey	-	-	-	-	-	1,064	319	1,383	1,383	-	-	-	-	-
27	Terminate license	-	-	-	-	-	-	-	Note 1	-	-	-	-	-	-
Period 4 Additional Costs															
28	License Termination Survey	-	-	-	-	-	3,840	576	4,416	4,416	-	-	-	-	-
Subtotal Period 4 Activity Costs		1,761	14,740	5,395	2,563	48,296	6,557	26,301	105,614	102,812	2,802	82,800	2,620	408	9,508,993
Period 4 Undistributed Costs															
1	Decon equipment	488	-	-	-	-	-	73	561	561	-	-	-	-	-
2	Decon supplies	539	-	-	-	-	-	135	674	674	-	-	-	-	-
3	DOC staff relocation expenses	-	837	-	-	-	-	126	963	963	-	-	-	-	-
4	Process liquid waste	269	-	97	171	1,015	-	424	1,975	1,975	-	-	1,829	-	230,591
5	Insurance	-	-	-	-	-	754	75	829	829	-	-	-	-	-
6	Property taxes	-	-	-	-	-	1,975	197	2,172	1,955	217	-	-	-	-
7	Health physics supplies	-	1,964	-	-	-	-	491	2,455	2,455	-	-	-	-	-
8	Heavy equipment rental	-	7,773	-	-	-	-	1,168	8,939	8,045	894	-	-	-	-
9	Small tool allowance	-	181	-	-	-	-	27	208	187	21	-	-	-	-
10	Pipe cutting equipment	-	749	-	-	-	-	112	862	862	-	-	-	-	-
11	Disposal of DAW generated	-	-	61	16	2,955	-	747	3,778	3,778	-	9,593	-	-	662,272
12	Decommissioning Equipment Disposition	-	-	-	-	83	277	62	422	422	-	270	-	-	30,000
13	Plant energy budget	-	-	-	-	-	1,223	183	1,406	1,265	141	-	-	-	-
14	NRC Fees	-	-	-	-	-	1,148	115	1,262	1,262	-	-	-	-	-
15	Site Security Cost	-	-	-	-	-	3,675	551	4,226	4,226	-	-	-	-	-
16	Fixed Overhead	-	-	-	-	-	3,757	564	4,320	4,320	-	-	-	-	-
17	Radwaste Processing Skids	-	-	-	-	-	570	85	655	655	-	-	-	-	-
Subtotal Undistributed Costs Period 4		1,296	11,504	158	187	4,052	13,377	5,134	35,708	34,436	1,273	9,863	1,829	-	922,863
Staff Costs															
DOC Staff Cost		-	-	-	-	-	21,154	3,173	24,328	24,328	-	-	-	-	-
Utility Staff Cost		-	-	-	-	-	31,787	4,768	36,555	36,555	-	-	-	-	-
TOTAL PERIOD 4		3,057	26,243	5,553	2,750	52,349	72,876	39,376	202,204	198,129	4,075	92,663	4,449	408	10,431,856

TABLE D-4
ST LUCIE PLANT - UNIT 1
SAFSTOR STATION DECOMMISSIONING COST ESTIMATE
(Thousands of 1998 Dollars)

ID	Activity Description	Decon	Remove	Pack	Ship	Burial	Other	Contingency	Total	NRC LicTerm	Site Restore.	Burial Site			
Number												A CF	B CF	C CF	pounds
PERIOD 5															
Demolition of Remaining Site Buildings															
29.1	Reactor Building	-	5,108	-	-	-	-	766	5,875	881	4,993	-	-	-	-
29.2	Fuel Handling Building	-	682	-	-	-	-	102	784	78	705	-	-	-	-
29.3	Intake & CWS	-	294	-	-	-	-	44	338	-	338	-	-	-	-
29.4	Miscellaneous Structures	-	798	-	-	-	-	120	918	-	918	-	-	-	-
29.5	Primary Water Tank Foundation - Contam	-	2	-	-	-	-	0	2	-	2	-	-	-	-
29.5	Reactor Auxiliary	-	1,251	-	-	-	-	188	1,439	144	1,295	-	-	-	-
29.7	Refueling Water Storage Tank - Contam	-	5	-	-	-	-	1	5	-	5	-	-	-	-
29.8	Turbine Building	-	834	-	-	-	-	125	959	-	959	-	-	-	-
29.9	Turbine Pedestal	-	440	-	-	-	-	66	506	-	506	-	-	-	-
29	Totals	-	9,414	-	-	-	-	1,412	10,826	1,103	9,722	-	-	-	-
Site Closeout Activities															
30	Grade & landscape site	-	81	-	-	-	-	12	93	-	93	-	-	-	-
31	Final report to NRC	-	-	-	-	-	156	23	179	179	-	-	-	-	-
Subtotal Period 5 Activity Costs		-	9,494	-	-	-	156	1,448	11,098	1,283	9,815	-	-	-	-
Period 5 Undistributed Costs															
1	Insurance	-	-	-	-	-	111	11	123	123	-	-	-	-	-
2	Property taxes	-	-	-	-	-	471	47	519	-	519	-	-	-	-
3	Heavy equipment rental	-	1,702	-	-	-	-	255	1,957	-	1,957	-	-	-	-
4	Small tool allowance	-	79	-	-	-	-	12	90	-	90	-	-	-	-
5	Plant energy budget	-	-	-	-	-	47	7	54	-	54	-	-	-	-
6	Site Security Cost	-	-	-	-	-	164	25	188	-	188	-	-	-	-
Subtotal Undistribtned Costs Period 5		-	1,780	-	-	-	794	357	2,931	123	2,808	-	-	-	-
Staff Costs															
DOC Staff Cost		-	-	-	-	-	2,375	356	2,731	-	2,731	-	-	-	-
Utility Staff Cost		-	-	-	-	-	808	121	930	837	93	-	-	-	-
TOTAL PERIOD 5		-	11,275	-	-	-	4,133	2,282	17,690	2,242	15,448	-	-	-	-

000213

TABLE D-4
ST LUCIE PLANT - UNIT 1
SAFSTOR STATION DECOMMISSIONING COST ESTIMATE
(Thousands of 1998 Dollars)

ID Number	Activity Description	Decon	Remove	Pack	Ship	Burial	Other	Contingency	Total	NRC LicTerm	Site Restore.	Burial Site			pounds
												A CF	B CF	C CF	
	TOTAL COST TO DECOMMISSION	5,295	40,387	5,841	2,928	57,384	275,085	73,127	461,048	439,642	21,406	105,953	6,119	408	11,039,353
	Total cost to decommission with 18.85% contingency					\$ 461,047,742									
	Total NRC license termination cost is 95.36%		or			\$ 439,642,028									
	Non-nuclear demolition cost is 4.64%		or			\$ 21,405,716									
	Total site radwaste volume buried					112,480 cubic feet									
	Total site radwaste weight buried					11,039,353 pounds									
	Total 10CFR61 greater than class C waste buried					650 cubic feet									
	Total scrap metal released from St. Lucie Unit 1 site					19,264 tons									
	Total craft labor requirements					906,179 person hours									

NOTES:

- 1) This activity is performed by the decommissioning staff following plant shutdown; the costs for this are included in this period's staff cost.
- 2) This activity, while performed after final plant shutdown, is considered part of operations and therefore no decommissioning costs are included for this activity.

TABLE D-5
ST LUCIE PLANT - UNIT 2
SAFSTOR STATION DECOMMISSIONING COST ESTIMATE
(Thousands of 1998 Dollars)

ID Number	Activity Description	Decon	Remove	Pack	Ship	Burial	Other	Contingency	Total	NRC LicTerm	Site Restore.	Burial Site			10 CFR 61
												A CF	B CF	C CF	pounds GTCC Cu Ft
PERIOD 1: Mothballing Activities															
1	Prepare preliminary decommissioning cost	-	-	-	-		56	8	64	64	-	-	-	-	-
2	Notification of Cessation of Operations								Note 1						
3	Remove fuel & source material								Note 2						
4	Notification of Permanent Defueling								Note 1						
5	Deactivate plant systems & process waste								Note 1						
6	Prepare and submit PSDAR	-	-	-	-		86	13	98	98	-	-	-	-	-
7	Review plant dwgs & specs	-	-	-	-		56	8	64	64	-	-	-	-	-
8	Perform detailed rad survey								Note 1						
9	Estimate by-product inventory	-	-	-	-		43	6	49	49	-	-	-	-	-
10	End product description	-	-	-	-		43	6	49	49	-	-	-	-	-
11	Detailed by-product inventory	-	-	-	-		64	10	74	74	-	-	-	-	-
12	Define major work sequence	-	-	-	-		43	6	49	49	-	-	-	-	-
13	Perform SER and EA	-	-	-	-		133	20	152	152	-	-	-	-	-
14	Perform Site-Specific Cost Study	-	-	-	-		214	32	246	246	-	-	-	-	-
15	Prepare/submit License Termination Plan	-	-	-	-		175	26	201	201	-	-	-	-	-
16	Receive NRC approval of termination plan								Note 1						
Activity Specifications															
17.1	Prepare plant and facilities for SAFSTOR	-	-	-	-		210	32	242	242	-	-	-	-	-
17.2	Plant systems	-	-	-	-		178	27	205	205	-	-	-	-	-
17.3	Plant structures and buildings	-	-	-	-		133	20	153	153	-	-	-	-	-
17.4	Waste management	-	-	-	-		86	13	98	98	-	-	-	-	-
17.5	Facility and site dormancy	-	-	-	-		86	13	98	98	-	-	-	-	-
17	Total	-	-	-	-		693	104	797	797	-	-	-	-	-
Detailed Work Procedures															
18.1	Plant systems	-	-	-	-		202	30	233	233	-	-	-	-	-
18.2	Facility closeout & dormancy	-	-	-	-		51	8	59	59	-	-	-	-	-
18	Total	-	-	-	-		254	38	292	292	-	-	-	-	-
19	Procure vacuum drying system	-	-	-	-		4	1	5	5	-	-	-	-	-
20	Drain/de-energize non-cont systems	-	-	-	-		-	-	Note 1	-	-	-	-	-	-
21	Drain & dry NSSS	-	-	-	-		-	-	Note 1	-	-	-	-	-	-
22	Drain/de-energize contaminated systems	-	-	-	-		-	-	Note 1	-	-	-	-	-	-
23	Decon/secure contaminated systems	-	-	-	-		-	-	Note 1	-	-	-	-	-	-
Decontamination of Site Buildings															
24.1	Reactor Building	576	-	-	-		-	288	865	865	-	-	-	-	-
24.2	Fuel Handling Building	214	-	-	-		-	107	322	322	-	-	-	-	-
24.3	Reactor Auxiliary Building	244	-	-	-		-	122	366	366	-	-	-	-	-
24.4	Steam Generator Blowdown Treatment	75	-	-	-		-	38	113	113	-	-	-	-	-
24	Totals	1,110	-	-	-		-	555	1,665	1,665	-	-	-	-	-
25	Prepare support equipment for storage	-	279	-	-		-	42	321	321	-	-	-	-	-
26	Install containment pressure equal lines	-	19	-	-		-	3	22	22	-	-	-	-	-
27	Interim survey prior to dormancy	-	-	-	-		320	48	369	369	-	-	-	-	-
28	Secure building accesses	-	-	-	-		-	-	Note 1	-	-	-	-	-	-
29	Prepare & submit interim report	-	-	-	-		25	4	29	29	-	-	-	-	-

TABLE D-5
ST LUCIE PLANT - UNIT 2
SAFSTOR STATION DECOMMISSIONING COST ESTIMATE
(Thousands of 1998 Dollars)

ID Number	Activity Description	Decon	Remove	Pack	Ship	Burial	Other	Contingency	Total	NRC LicTerm	Site Restore.	Burial Site			10 CFR 61	
												A CF	B CF	C CF	pounds	GTCC Cu Ft
Period 1 Additional Costs																
30	Mixed/Hazardous Waste	-	-	-	-		3,884	583	4,466	4,466	-		-	-		-
Subtotal Period 1 Activity Costs		1,110	298	-	-	-	6,091	1,513	9,012	9,012	-	-	-	-	-	-
Period 1 Undistributed Costs																
1	Decon equipment	488	-	-	-		-	73	561	561	-		-	-		-
2	Decon supplies	518	-	-	-		-	130	648	648	-		-	-		-
3	Process liquid waste	267	-	97	170	1,009		421	1,964	1,964	-	-	1,819	-	229,226	-
4	Insurance	-	-	-	-		2,098	210	2,307	2,307	-		-	-		-
5	Property taxes	-	-	-	-		591	59	650	650	-		-	-		-
6	Health physics supplies	-	295	-	-		-	74	368	368	-		-	-		-
7	Small tool allowance	-	16	-	-		-	2	19	19	-		-	-		-
8	Disposal of DAW generated	-	-	17	4	824		208	1,054	1,054	-	2,677	-	-	184,795	-
9	Plant energy budget	-	-	-	-		503	75	578	578	-		-	-		-
10	NRC Fees	-	-	-	-		304	30	334	334	-		-	-		-
11	Emergency Planning Fees	-	-	-	-		76	8	83	83	-		-	-		-
12	Site Security Cost	-	-	-	-		712	107	819	819	-		-	-		-
13	Fixed Overhead	-	-	-	-		1,124	169	1,293	1,293	-		-	-		-
Subtotal Undistributed Costs Period 1		1,273	311	114	174	1,833	5,408	1,566	10,679	10,679	-	2,677	1,819	-	414,021	-
Staff Costs																
DOC Staff Cost		-	-	-	-		-	-	-	-	-		-	-		-
Utility Staff Cost		-	-	-	-		17,780	2,667	20,447	20,447	-		-	-		-
TOTAL COST TO SAFSTOR		2,384	608	114	174	1,833	29,278	5,746	40,138	40,138	-	2,677	1,819	-	414,021	-
Total cost to SAFSTOR with 16.71% contingency.		40,137,527														
Total site radwaste volume buried		4,495 cubic feet														
Total craft labor requirements		48,529 person hours														

TABLE D-5
ST LUCIE PLANT - UNIT 2
SAFSTOR STATION DECOMMISSIONING COST ESTIMATE
(Thousands of 1998 Dollars)

ID Number	Activity Description	Decon	Remove	Pack	Ship	Burial	Other	Contingency	Total	NRC LicTerm	Site Restore.	Burial Site			10 CFR 61
												A CF	B CF	C CF	GTCC Cu Ft
PERIOD 2: SAFSTOR Dormancy Activities															
1	Quarterly inspection									Note 1					
2	Semi-annual environmental survey									Note 1					
3	Prepare reports									Note 1					
4	Health physics supplies	-	-	-	-		46	11	57	57	-	-	-	-	-
5	Insurance	-	-	-	-		72	7	79	79	-	-	-	-	-
6	Property taxes	-	-	-	-		394	39	433	433	-	-	-	-	-
7	Disposal of contaminated solid waste	-	-	1	0	29	-	7	38	38	-	102	-	-	-
8	Bituminous roof replacement	-	-	-	-		43	6	50	50	-	-	-	-	-
9	Maintenance supplies	-	-	-	-		99	25	123	123	-	-	-	-	-
10	Plant energy budget	-	-	-	-		78	12	90	90	-	-	-	-	-
11	NRC Fees	-	-	-	-		162	16	178	178	-	-	-	-	-
12	Emergency Planning Fees	-	-	-	-		4	0	4	4	-	-	-	-	-
13	Site Security Cost	-	-	-	-		76	11	87	87	-	-	-	-	-
14	Fixed Overhead	-	-	-	-		75	11	86	86	-	-	-	-	-
15	Site maintenance staff	-	-	-	-		562	84	646	646	-	-	-	-	-
PERIOD 2 ANNUAL MAINTENANCE TOTALS		-	-	1	0	29	1,610	232	1,872	1,872	-	102	-	-	-

Total cost SAFSTOR dormancy with 46.3367 years equals 86,761,653

Total site radwaste volume buried 4,722 cubic feet

TABLE D-5
ST LUCIE PLANT - UNIT 2
SAFSTOR STATION DECOMMISSIONING COST ESTIMATE
(Thousands of 1998 Dollars)

ID Number	Activity Description	Decon	Remove	Pack	Ship	Burial	Other	Contingency	Total	NRC LicTerm	Site Restore.	Burial Site			10 CFR 61
												A CF	B CF	C CF	GTCC Cu Ft
PERIOD 3															
1	Review plant dwgs & specs.	-	-	-	-		197	30	226	226	-	-	-	-	-
2	Perform detailed rad survey								Note 1						
3	End product description	-	-	-	-		43	6	49	49	-	-	-	-	-
4	Detailed by-product inventory	-	-	-	-		56	8	64	64	-	-	-	-	-
5	Define major work sequence	-	-	-	-		321	48	369	369	-	-	-	-	-
6	Perform SER and EA	-	-	-	-		133	20	152	152	-	-	-	-	-
7	Perform Site-Specific Cost Study	-	-	-	-		214	32	246	246	-	-	-	-	-
8	Prepare/submit License Termination Plan	-	-	-	-		175	26	201	201	-	-	-	-	-
9	Receive NRC approval of termination plan								Note 1						
Activity Specifications															
10.1	Re-activate plant & temporary facilities	-	-	-	-		315	47	362	326	36	-	-	-	-
10.2	Plant systems	-	-	-	-		178	27	205	184	20	-	-	-	-
10.3	Reactor internals	-	-	-	-		304	46	349	349	-	-	-	-	-
10.4	Reactor vessel	-	-	-	-		278	42	320	320	-	-	-	-	-
10.5	Biological shield	-	-	-	-		21	3	25	25	-	-	-	-	-
10.6	Steam generators	-	-	-	-		133	20	153	153	-	-	-	-	-
10.7	Reinforced concrete	-	-	-	-		68	10	79	39	39	-	-	-	-
10.8	Turbine & condenser	-	-	-	-		34	5	39	-	39	-	-	-	-
10.9	Plant structures & buildings	-	-	-	-		133	20	153	77	77	-	-	-	-
10.10	Waste management	-	-	-	-		197	30	226	226	-	-	-	-	-
10.11	Facility & site closeout	-	-	-	-		38	6	44	22	22	-	-	-	-
10	Total	-	-	-	-		1,701	255	1,956	1,722	234	-	-	-	-
Planning & Site Preparations															
11	Prepare dismantling sequence	-	-	-	-		103	15	118	118	-	-	-	-	-
12	Plant prep. & temp. svces	-	-	-	-		1,895	284	2,180	2,180	-	-	-	-	-
13	Design water clean-up system	-	-	-	-		60	9	69	69	-	-	-	-	-
14	Rigging/Cont. Cntrl Envlps/tooling/etc.	-	-	-	-		1,604	241	1,845	1,845	-	-	-	-	-
15	Procure casks/liners & containers	-	-	-	-		53	8	60	60	-	-	-	-	-
Detailed Work Procedures															
16.1	Plant systems	-	-	-	-		202	30	233	209	23	-	-	-	-
16.2	Reactor internals	-	-	-	-		107	16	123	123	-	-	-	-	-
16.3	Remaining buildings	-	-	-	-		58	9	66	17	50	-	-	-	-
16.4	CRD cooling assembly	-	-	-	-		43	6	49	49	-	-	-	-	-
16.5	CRD housings & ICI tubes	-	-	-	-		43	6	49	49	-	-	-	-	-
16.6	Incore instrumentation	-	-	-	-		43	6	49	49	-	-	-	-	-
16.7	Reactor vessel	-	-	-	-		155	23	179	179	-	-	-	-	-
16.8	Facility closeout	-	-	-	-		51	8	59	30	30	-	-	-	-
16.9	Missile shields	-	-	-	-		19	3	22	22	-	-	-	-	-
16.10	Biological shield	-	-	-	-		51	8	59	59	-	-	-	-	-
16.11	Steam generators	-	-	-	-		197	30	226	226	-	-	-	-	-
16.12	Reinforced concrete	-	-	-	-		43	6	49	25	25	-	-	-	-
16.13	Turbine & condensers	-	-	-	-		133	20	153	-	153	-	-	-	-
16.14	Auxiliary building	-	-	-	-		117	18	134	121	13	-	-	-	-
16.15	Reactor building	-	-	-	-		117	18	134	121	13	-	-	-	-
16	Total	-	-	-	-		1,379	207	1,586	1,278	307	-	-	-	-
17	Asbestos removal program	-	724	129	4	807	23	400	2,087	1,470	617	2,242	-	-	-

TABLE D-5
ST LUCIE PLANT - UNIT 2
SAFSTOR STATION DECOMMISSIONING COST ESTIMATE
(Thousands of 1998 Dollars)

1D Number	Activity Description	Decon	Remove	Pack	Ship	Burial	Other	Contingency	Total	NRC LicTerm	Site Restore.	Burial Site			10 CFR 61 pounds	10 CFR 61 GTCC Cu Ft
												A CF	B CF	C CF		
Period 3 Additional Costs																
18	Site Characterization Survey	-	-	-	-		403	60	463	463	-	-	-	-	-	-
Subtotal Period 3 Activity Costs		-	724	129	4	807	8,358	1,650	11,672	10,514	1,158	2,242	-	-	-	-
Period 3 Undistributed Costs																
1	DOC staff relocation expenses	-	837	-	-		-	126	963	963	-	-	-	-	-	-
2	Insurance	-	-	-	-		283	28	311	311	-	-	-	-	-	-
3	Property taxes	-	-	-	-		590	59	649	649	-	-	-	-	-	-
4	Health physics supplies	-	263	-	-		-	66	329	329	-	-	-	-	-	-
5	Heavy equipment rental	-	441	-	-		-	66	507	507	-	-	-	-	-	-
6	Disposal of DAW generated	-	-	17	4	823	-	208	1,053	1,053	-	2,672	-	-	184,487	-
7	Plant energy budget	-	-	-	-		530	79	609	609	-	-	-	-	-	-
8	NRC Fees	-	-	-	-		303	30	333	333	-	-	-	-	-	-
9	Site Security Cost	-	-	-	-		424	64	487	487	-	-	-	-	-	-
10	Fixed Overhead	-	-	-	-		1,122	168	1,291	1,291	-	-	-	-	-	-
Subtotal Undistributed Costs Period 3		-	1,542	17	4	823	3,252	895	6,533	6,533	-	2,672	-	-	184,487	-
Staff Costs																
DOC Staff Cost		-	-	-	-		3,506	526	4,032	4,032	-	-	-	-	-	-
Utility Staff Cost		-	-	-	-		7,727	1,159	8,886	8,886	-	-	-	-	-	-
TOTAL PERIOD 3 COST		-	2,266	146	9	1,630	22,843	4,230	31,123	29,965	1,158	4,914	-	-	184,487	-

000219

TABLE D-5
ST LUCIE PLANT - UNIT 2
SAFSTOR STATION DECOMMISSIONING COST ESTIMATE
(Thousands of 1998 Dollars)

ID	Activity Description	Decon	Remove	Pack	Ship	Burial	Other	Contingency	Total	NRC LicTerm	Site Restore	Burial Site			10 CFR 61
Number												A CF	B CF	C CF	GTCC Cu Ft
PERIOD 4															
Nuclear Steam Supply System Removal															
19.1	Reactor Coolant Piping	25	37	4	4	137	-	57	263	263	-	332	-	-	31,028
19.2	Pressurizer Relief Tank	3	17	1	1	26	-	12	60	60	-	89	-	-	5,824
19.3	Reactor Coolant Pumps & Motors	72	39	28	23	3,131	-	835	4,128	4,128	-	5,772	-	-	711,700
19.4	Pressurizer	17	27	4	8	1,059	-	281	1,396	1,396	-	2,127	-	-	240,755
19.5	Steam Generators	99	613	2,045	1,956	4,568	-	1,843	11,125	11,125	-	19,034	-	-	2,524,482
19.6	CRDMs/ICIs/Service Structure Removal	88	59	75	15	301	-	143	681	681	-	3,213	-	-	87,528
19.7	Reactor Vessel Internals	43	1,149	2,881	211	2,715	-	3,014	10,013	10,013	-	1,441	524	408	264,053
19.8	Vessel & Internals GTCC Disposal	-	-	-	-	13,290	-	6,645	19,935	19,935	-	-	-	-	655
19.9	Reactor Vessel	119	3,319	217	289	4,860	-	5,105	13,909	13,909	-	4,847	2,096	-	983,277
19	Totals	465	5,259	5,254	2,506	30,088	-	17,936	61,508	61,508	-	36,855	2,620	408	4,848,647
20	Remove spent fuel racks	221	24	-	-	99	186	169	700	700	-	321	-	-	35,640
Removal of Major Equipment															
21	Main Turbine/Generator	-	46	-	-	-	-	7	53	-	53	-	-	-	-
22	Main Condensers	-	199	-	-	-	-	30	229	-	229	-	-	-	-
Disposal of Plant Systems															
23.1	Air Evacuation	-	4	-	-	-	-	1	4	-	4	-	-	-	-
23.2	Air Evacuation - Insulated	-	16	-	-	-	-	2	19	-	19	-	-	-	-
23.3	Auxiliary Steam - Insulated	-	8	-	-	-	-	1	10	-	10	-	-	-	-
23.4	Chemical & Volume Control	-	64	-	-	301	-	91	457	457	-	937	-	-	68,497
23.5	Chemical & Volume Control - Insulated	-	484	-	-	750	-	308	1,542	1,542	-	1,294	-	-	170,414
23.6	Chemical Feed	-	2	-	-	-	-	0	2	-	2	-	-	-	-
23.7	Chemical Feed - Insulated	-	1	-	-	-	-	0	1	-	1	-	-	-	-
23.8	Circulating & Intake Cooling Water	-	138	-	-	-	-	21	158	-	158	-	-	-	-
23.9	Component Cooling	-	46	-	-	-	-	7	53	-	53	-	-	-	-
23.10	Component Cooling - RCA	-	125	-	-	-	-	19	143	143	-	-	-	-	-
23.11	Condensate	-	101	-	-	-	-	15	116	-	116	-	-	-	-
23.12	Condensate - Insulated	-	59	-	-	-	-	9	68	-	68	-	-	-	-
23.13	Condensate Recovery	-	2	-	-	-	-	0	3	-	3	-	-	-	-
23.14	Condensate Recovery - Insulated	-	0	-	-	-	-	0	0	-	0	-	-	-	-
23.15	Condensate Recovery - Insulated - RCA	-	0	-	-	-	-	0	0	-	0	-	-	-	-
23.16	Condensate Recovery - RCA	-	4	-	-	-	-	1	4	-	4	-	-	-	-
23.17	Condenser Tube Cleaning	-	19	-	-	-	-	3	22	-	22	-	-	-	-
23.18	Contnmnt Spray & Refueling Water	-	250	-	-	318	304	187	1,059	1,059	-	697	-	-	72,173
23.19	Contnmnt Spray & Refueling Water - Ins	-	151	-	-	689	-	210	1,050	1,050	-	1,342	-	-	156,703
23.20	Demineralized Makeup Water	-	3	-	-	-	-	0	4	-	4	-	-	-	-
23.21	Demineralized Makeup Water - RCA	-	2	-	-	-	-	0	2	-	2	-	-	-	-
23.22	Domestic/Makeup/Service Water	-	4	-	-	-	-	1	5	-	5	-	-	-	-
23.23	Domestic/Makeup/Service Water - RCA	-	7	-	-	-	-	1	9	-	9	-	-	-	-
23.24	Domestic/Makeup/Service Water-Ins	-	0	-	-	-	-	0	0	-	0	-	-	-	-
23.25	Domestic/Makeup/Service Water-Ins - RCA	-	1	-	-	-	-	0	1	-	1	-	-	-	-
23.26	Electrical - Clean	-	1,799	-	-	-	-	270	2,069	-	2,069	-	-	-	-
23.27	Electrical - Contaminated	-	835	-	-	32	127	236	1,230	1,230	-	63	-	-	7,213
23.28	Electrical - Decontaminated	-	1,508	-	-	-	-	226	1,735	1,735	-	-	-	-	-
23.29	Emergency Diesel Generator	-	48	-	-	-	-	7	55	-	55	-	-	-	-
23.30	Emergency Diesel Generator - Insulated	-	5	-	-	-	-	1	6	-	6	-	-	-	-
23.31	Extraction Steam	-	42	-	-	-	-	6	48	-	48	-	-	-	-
23.32	Extraction Steam - Insulated	-	47	-	-	-	-	7	54	-	54	-	-	-	-
23.33	Feedwater - Insulated	-	64	-	-	-	-	10	73	-	73	-	-	-	-
23.34	Feedwater - Insulated - RCA	-	15	-	-	-	-	2	17	-	17	-	-	-	-
23.35	Fire Protection	-	27	-	-	-	-	4	31	-	31	-	-	-	-
23.36	Fire Protection - Insulated	-	3	-	-	-	-	0	3	-	3	-	-	-	-
23.37	Fire Protection - Insulated - RCA	-	2	-	-	-	-	0	2	-	2	-	-	-	-
23.38	Fire Protection - RCA	-	17	-	-	-	-	3	20	-	20	-	-	-	-
23.39	Fuel Pool	-	84	-	-	364	-	112	561	561	-	719	-	-	82,755
23.40	Fuel Pool - Insulated	-	59	-	-	128	-	47	233	233	-	234	-	-	29,062

TABLE D-5
ST LUCIE PLANT - UNIT 2
SAFSTOR STATION DECOMMISSIONING COST ESTIMATE
(Thousands of 1998 Dollars)

ID											NRC	Site	Burial Site			10 CFR 61	
Number	Activity Description	Decon	Remove	Pack	Ship	Burial	Other	Contingency	Total	LicTerm	Restore.	A CF	B CF	C CF	pounds	GTCC	Cu Ft
Disposal of Plant Systems (continued)																	
23.41	HVAC	-	247	-	-	-	-	37	284	-	284	-	-	-	-	-	-
23.42	HVAC - Contaminated	-	1,283	-	-	468	794	557	3,102	3,102	-	922	-	-	106,417	-	-
23.43	Heater Drain & Vents - Insulated	-	112	-	-	-	-	17	128	-	128	-	-	-	-	-	-
23.44	Hydrogen Sampling	-	31	-	-	117	-	37	185	185	-	223	-	-	26,621	-	-
23.45	Integrated Leak Rate Testing	-	26	-	-	72	-	25	123	123	-	137	-	-	16,387	-	-
23.46	Main Steam - Insulated	-	102	-	-	-	-	15	117	-	117	-	-	-	-	-	-
23.47	Main Steam - Insulated - RCA	-	15	-	-	-	-	2	18	18	-	-	-	-	-	-	-
23.48	Misc Bulk Gas Supply	-	8	-	-	-	-	1	9	-	9	-	-	-	-	-	-
23.49	Misc Bulk Gas Supply - RCA	-	4	-	-	-	-	1	5	5	-	-	-	-	-	-	-
23.50	Miscellaneous	-	1	-	-	-	-	0	1	-	1	-	-	-	-	-	-
23.51	Miscellaneous - RCA	-	2	-	-	-	-	0	2	-	2	-	-	-	-	-	-
23.52	Post Accident Sampling	-	2	-	-	1	-	1	3	3	-	1	-	-	186	-	-
23.53	Post Accident Sampling - Insulated	-	15	-	-	7	-	5	27	27	-	12	-	-	1,672	-	-
23.54	Primary Water	-	86	-	-	56	66	45	254	254	-	140	-	-	12,690	-	-
23.55	Primary Water - Insulated	-	2	-	-	3	-	1	6	6	-	6	-	-	699	-	-
23.56	RCP Oil Collection	-	6	-	-	11	-	4	21	21	-	20	-	-	2,608	-	-
23.57	Radiation Monitoring	-	14	-	-	15	-	7	37	37	-	26	-	-	3,447	-	-
23.58	Reactor Coolant - Insulated	-	40	-	-	92	-	33	165	165	-	161	-	-	20,994	-	-
23.59	Refueling Equipment	-	72	-	-	87	0	40	199	199	-	172	-	-	19,681	-	-
23.60	SGBTf Blowdown - Insulated	-	437	-	-	340	130	214	1,121	1,121	-	753	-	-	77,223	-	-
23.61	SGBTf Demin - Ins - RCA	-	14	-	-	-	-	2	16	16	-	-	-	-	-	-	-
23.62	SGBTf Demin - RCA	-	22	-	-	-	-	3	25	25	-	-	-	-	-	-	-
23.63	SGBTf Miscellaneous - RCA	-	7	-	-	-	-	1	8	8	-	-	-	-	-	-	-
23.64	SGBTf Waste Management	-	34	-	-	193	-	57	283	283	-	616	-	-	43,845	-	-
23.65	SGBTf Waste Management - Insulated	-	45	-	-	80	-	31	156	156	-	152	-	-	18,169	-	-
23.66	Safety Injection	-	139	-	-	231	141	114	625	625	-	462	-	-	52,540	-	-
23.67	Safety Injection - Insulated	-	675	-	-	1,505	-	545	2,724	2,724	-	2,720	-	-	341,947	-	-
23.68	Sampling	-	5	-	-	-	-	1	6	-	6	-	-	-	-	-	-
23.69	Sampling - Insulated	-	7	-	-	-	-	1	8	-	8	-	-	-	-	-	-
23.70	Sampling - Insulated - RCA	-	12	-	-	-	-	2	14	14	-	-	-	-	-	-	-
23.71	Sampling - RCA	-	10	-	-	-	-	2	12	12	-	-	-	-	-	-	-
23.72	Secondary Side Wet Layup	-	7	-	-	-	-	1	8	-	8	-	-	-	-	-	-
23.73	Secondary Side Wet Layup - Ins	-	9	-	-	-	-	1	10	-	10	-	-	-	-	-	-
23.74	Secondary Side Wet Layup - Ins - RCA	-	4	-	-	-	-	1	5	5	-	-	-	-	-	-	-
23.75	Secondary Side Wet Layup - RCA	-	4	-	-	-	-	1	4	4	-	-	-	-	-	-	-
23.76	Service & Instrument Air	-	11	-	-	-	-	2	12	-	12	-	-	-	-	-	-
23.77	Service & Instrument Air - Ins	-	5	-	-	-	-	1	6	-	6	-	-	-	-	-	-
23.78	Service & Instrument Air - Ins - RCA	-	18	-	-	-	-	3	21	21	-	-	-	-	-	-	-
23.79	Service & Instrument Air - RCA	-	12	-	-	-	-	2	14	14	-	-	-	-	-	-	-
23.80	Sodium Hypochlorite	-	24	-	-	-	-	4	27	-	27	-	-	-	-	-	-
23.81	Spent Fuel	-	6	-	-	33	-	10	49	49	-	65	-	-	7,500	-	-
23.82	Spent Fuel - Ins	-	1	-	-	2	-	1	4	4	-	3	-	-	468	-	-
23.83	Steam Gen Blowdown Cooling	-	9	-	-	-	-	1	10	-	10	-	-	-	-	-	-
23.84	Steam Gen Blowdown Cooling - Ins - RCA	-	21	-	-	-	-	3	24	24	-	-	-	-	-	-	-
23.85	Steam Gen Blowdown Cooling - Insulated	-	1	-	-	-	-	0	1	-	1	-	-	-	-	-	-
23.86	Steam Gen Blowdown Cooling - RCA	-	27	-	-	-	-	4	31	31	-	-	-	-	-	-	-
23.87	Steam Generator Blowdown	-	13	-	-	35	-	12	61	61	-	60	-	-	8,052	-	-
23.88	Steam Generator Blowdown - Insulated	-	43	-	-	77	-	30	151	151	-	148	-	-	17,606	-	-
23.89	Turbine	-	1	-	-	-	-	0	1	-	1	-	-	-	-	-	-
23.90	Turbine Cooling Water	-	31	-	-	-	-	5	36	-	36	-	-	-	-	-	-
23.91	Turbine Cooling Water - Insulated	-	22	-	-	-	-	3	25	-	25	-	-	-	-	-	-
23.92	Turbine Lube Oil & Diesel Oil	-	32	-	-	-	-	5	37	-	37	-	-	-	-	-	-
23.93	Waste Management	-	464	-	-	1,804	-	567	2,834	2,834	-	5,181	-	-	409,911	-	-
23.94	Waste Management - Insulated	-	1,115	-	-	1,748	-	716	3,579	3,579	-	2,978	-	-	397,314	-	-
23	Totals	-	11,399	-	-	9,560	1,562	4,982	27,503	23,972	3,531	20,243	-	-	2,172,794	-	-
24	Erect scaffolding for systems removal	-	810	-	-	26	85	222	1,143	1,143	-	83	-	-	9,243	-	-

TABLE D-5
ST LUCIE PLANT - UNIT 2
SAFSTOR STATION DECOMMISSIONING COST ESTIMATE
(Thousands of 1998 Dollars)

ID											NRC	Site	Burial Site			10 CFR 61
Number	Activity Description	Decon	Remove	Pack	Ship	Burial	Other	Contingency	Total	LicTerm	Restore.	A CF	B CF	C CF	pounds	GTCC Cu Ft
Decontamination of Site Buildings																
25.1	Reactor Building	588	331	54	22	3,430	155	1,266	5,846	5,846	-	7,301	-	-	821,464	-
25.2	East EP Pond	-	3	26	11	1,095	-	279	1,413	1,413	-	3,555	-	-	373,005	-
25.3	Fuel Handling Building	198	189	2	1	92	124	188	794	794	-	298	-	-	31,807	-
25.4	Primary Water Tank & Pump - Contaminate	1	3	2	1	119	-	31	157	157	-	240	-	-	27,384	-
25.5	Reactor Auxiliary Building	274	22	15	6	612	26	301	1,255	1,255	-	1,987	-	-	207,788	-
25.6	Steam Generator Blowdown Treatment	86	1	5	2	204	1	95	393	393	-	661	-	-	69,339	-
25 Totals		1,147	548	103	42	5,552	305	2,161	9,857	9,857	-	14,042	-	-	1,530,787	-
26	ORISE confirmatory survey	-	-	-	-		1,064	319	1,383	1,383	-		-	-		-
27	Terminate license								Note 1							
Period 4 Additional Costs																
28	License Termination Survey	-	-	-	-		5,692	854	6,546	6,546	-		-	-		-
Subtotal Period 4 Activity Costs		1,833	18,286	5,358	2,548	45,324	8,895	26,679	108,922	105,109	3,813	71,545	2,620	408	8,597,111	655
Period 4 Undistributed Costs																
1	Decon equipment	488	-	-	-		-	73	561	561	-		-	-		-
2	Decon supplies	559	-	-	-		-	140	698	698	-		-	-		-
3	DOC staff relocation expenses	-	837	-	-		-	126	963	963	-		-	-		-
4	Process liquid waste	293	-	106	186	1,105	-	461	2,152	2,152	-	-	1,993	-	251,172	-
5	Insurance	-	-	-	-		635	63	698	698	-		-	-		-
6	Property taxes	-	-	-	-		1,405	141	1,546	1,391	155		-	-		-
7	Health physics supplies	-	2,229	-	-		-	557	2,786	2,786	-		-	-		-
8	Heavy equipment rental	-	5,531	-	-		-	830	6,361	5,725	636		-	-		-
9	Small tool allowance	-	229	-	-		-	34	264	237	26		-	-		-
10	Pipe cutting equipment	-	749	-	-		-	112	862	862	-		-	-		-
11	Disposal of DAW generated	-	-	40	10	1,961	-	496	2,507	2,507	-	6,366	-	-	439,503	-
12	Decommissioning Equipment Disposition	-	-	-	-	83	277	62	422	422	-	270	-	-	30,000	-
13	Plant energy budget	-	-	-	-		909	136	1,046	941	105		-	-		-
14	NRC Fees	-	-	-	-		909	91	1,000	1,000	-		-	-		-
15	Site Security Cost	-	-	-	-		3,426	514	3,940	3,940	-		-	-		-
16	Fixed Overhead	-	-	-	-		2,674	401	3,075	3,075	-		-	-		-
17	Radwaste Processing Skids	-	-	-	-		1,014	152	1,166	1,166	-		-	-		-
Subtotal Undistributed Costs Period 4		1,339	9,576	146	197	3,149	11,249	4,390	30,047	29,125	922	6,636	1,993	-	720,675	-
Staff Costs																
DOC Staff Cost		-	-	-	-		20,093	3,014	23,107	23,107	-		-	-		-
Utility Staff Cost		-	-	-	-		37,795	5,669	43,464	43,464	-		-	-		-
TOTAL PERIOD 4		3,172	27,862	5,504	2,745	48,473	78,031	39,752	205,539	200,804	4,734	78,181	4,613	408	9,317,786	655

TABLE D-5
ST LUCIE PLANT - UNIT 2
SAFSTOR STATION DECOMMISSIONING COST ESTIMATE
(Thousands of 1998 Dollars)

ID Number	Activity Description	Decon	Remove	Pack	Ship	Burial	Other	Contingency	Total	NRC LicTerm	Site Restore.	Burial Site			10 CFR 61	
												A CF	B CF	C CF	pounds	GTCC Cu Ft
PERIOD 5																
Demolition of Remaining Site Buildings																
29.1	Reactor Building	-	5,119	-	-	-	-	768	5,887	883	5,004	-	-	-	-	
29.2	Fuel Handling Building	-	682	-	-	-	-	102	784	78	705	-	-	-	-	
29.3	Intake Structure & CWS	-	5,018	-	-	-	-	753	5,771	-	5,771	-	-	-	-	
29.4	Miscellaneous Structures	-	2,573	-	-	-	-	396	2,959	-	2,959	-	-	-	-	
29.5	Primary Water Tank & Pump - Contaminate	-	2	-	-	-	-	0	2	-	2	-	-	-	-	
29.6	Reactor Auxiliary Building	-	1,251	-	-	-	-	188	1,439	144	1,295	-	-	-	-	
29.7	Steam Generator Blowdown Treatment	-	363	-	-	-	-	54	418	21	397	-	-	-	-	
29.8	Turbine Building	-	825	-	-	-	-	124	948	-	948	-	-	-	-	
29.9	Turbine Pedestal	-	440	-	-	-	-	66	506	-	506	-	-	-	-	
29	Totals	-	16,273	-	-	-	-	2,441	18,714	1,126	17,587	-	-	-	-	
Site Closeout Activities																
30	Grade & landscape site	-	81	-	-	-	-	12	93	-	93	-	-	-	-	
31	Final report to NRC	-	-	-	-	-	67	10	77	77	-	-	-	-	-	
Subtotal Period 5 Activity Costs		-	16,354	-	-	-	67	2,463	18,883	1,203	17,680	-	-	-	-	
Period 5 Undistributed Costs																
1	Insurance	-	-	-	-	-	111	11	123	123	-	-	-	-	-	
2	Property taxes	-	-	-	-	-	471	47	519	-	519	-	-	-	-	
3	Heavy equipment rental	-	1,702	-	-	-	-	255	1,957	-	1,957	-	-	-	-	
4	Small tool allowance	-	110	-	-	-	-	17	127	-	127	-	-	-	-	
5	Plant energy budget	-	-	-	-	-	53	8	61	-	61	-	-	-	-	
6	Site Security Cost	-	-	-	-	-	393	59	452	-	452	-	-	-	-	
Subtotal Undistributed Costs Period 5		-	1,812	-	-	-	1,029	397	3,238	123	3,116	-	-	-	-	
Staff Costs																
DOC Staff Cost		-	-	-	-	-	4,774	716	5,490	-	5,490	-	-	-	-	
Utility Staff Cost		-	-	-	-	-	2,878	432	3,310	2,979	331	-	-	-	-	
TOTAL PERIOD 5		-	18,165	-	-	-	8,748	4,008	30,921	4,304	26,617	-	-	-	-	

000223

TABLE D-5
ST LUCIE PLANT - UNIT 2
SAFSTOR STATION DECOMMISSIONING COST ESTIMATE
(Thousands of 1998 Dollars)

ID Number	Activity Description	Decon	Remove	Pack	Ship	Burial	Other	Contingency	Total	NRC LicTerm	Site Restore.	Burial Site				10 CFR 61
												A CF	B CF	C CF	pounds	GTCC Cu Ft
TOTAL COST TO DECOMMISSION		5,556	48,901	5,794	2,936	53,301	213,515	64,480	394,482	361,973	32,510	90,493	6,431	408	9,916,294	855

Total cost to decommission with	19.54% contingency:	\$ 394,482,295
Total NRC license termination cost is	91.76% or	\$ 361,972,697
Non-nuclear demolition cost is	8.24% or	\$ 32,509,598
Total site radwaste volume buried		97,333 cubic feet
Total site radwaste weight buried		9,916,294 pounds
Total 10CFR61 greater than class C waste buried		655 cubic feet
Total scrap metal released from St. Lucie Unit 1 site		21,126 tons
Total craft labor requirements		1,198,200 person hours

NOTES:

- 1) This activity is performed by the decommissioning staff following plant shutdown; the costs for this are included in this period's staff cost.
- 2) This activity, while performed after final plant shutdown, is considered part of operations and therefore no decommissioning costs are included for this activity.

000224