FILED 4/8/2024
DOCUMENT NO. 01650-2024
FPSC - COMMISSION CLERK

FLORIDA PUBLIC SERVICE COMMISSION

EXHIBIT INDEX

FOR THE HEARING DATED 03/26/2024 IN DOCKET 20240001

1.	Comprehensive Exhibit List	3
2.	Excerpt from FPL's Procedure 0-PME-049.0 Reactor Trip and Trip Bypass Breaker Inspection Maintenance.	8
3.	Resume of Richard A. Polich.	10
4.	Richard Polich Regulatory Testimony List.	15
5.	Testimony of Richard Polich in docket 20220001-EI and Notice of Withdrawal of Portions of Testimony.	17
6.	Review of Nuclear Operations Florida Power & Light Company.	444
8.	Review of Florida Power & Light Company Nuclear Operations January 2024.	549
9.	Summary of outages.	549
10.	As filed in Docket No. 20220001-EI, FPL's Response to Staff's Second Set of Interrogatories Nos. 4 and 9 (Including Attachments)	552
11.	As filed in Docket No. 20220001-EI, FPL's Response to Staff's Third Set of Interrogatories Nos. 11, 12, 13, 14, 15, and 16	564

12.	As filed in Docket No. 20220001-EI, FPL's Response to Staff's Fourth Set of Interrogatories No. 30	580
13.	As filed in Docket No. 20220001-EI, FPL's Response to Staff's Fifth Set of Interrogatories Nos. 31, 33, and 34	586
14.	As filed in Docket No. 20220001-EI, FPL's Response to OPC's First Set of Interrogatories Nos. 1, 2, 3, 4, 5, 6, 7, 7 Supplemental, 8, 9, 10, and 11	602
15.	As filed in Docket No. 20220001-EI, FPL's Response to OPC's Second Set of Interrogatories No. 14	617
16.	As filed in Docket No. 20220001-EI, FPL's Response to OPC's Third Set of Interrogatories Nos. 36, 41, 42, 43, 44, 45, 46, 47, 48, 49, and 50	620
17.	As filed in Docket No. 20220001-EI, FPL's Response to OPC's First Request for Production of Documents Nos. 3, 8, 9, 13, 14, 15, 16, 18, 19, and 19 Supplemental (Including Attachments)	635
18.	As filed in Docket No. 20220001-EI, FPL's Response to OPC's Third Request for Production of Documents Nos. 30, 31, 32, 33, 34, 35, 36, 37, and 38 (Including Attachments)	648
19.	As filed in Docket No. 20230001-EI, FPL's Response to OPC's First Set of Interrogatories Nos. 8 and 9	673
20.	As filed in Docket No. 20230001-EI, FPL's Response to Staff's Sixth Set of Interrogatories Nos. 14, 15, 16, 17, 18, 19, 20, 21, 22, 23, 23 supplemental, 24, and 25 (Including Attachments)	679
21.	As filed in Docket No. 20230001-EI, FPL witness, Edward Anderson's prefiled exhibit EJA-1 – Schedule E1-B	722
22.	As filed in Docket No. 20240001-EI, FPL's Response to Staff's Second Set of Interrogatories, No. 9 (Including Attachments)	726

FPSC EXH No. 1
03/20/2024

ADMITTED

Docket No. 20240001-EI
Comprehensive Exhibit List for Entry into Hearing Record
(March 26-27, 2024)

EXH #	Witness	I.D. # As Filed	Exhibit Description	Issue Nos.	Entered
STAFF					
1		Exhibit List	Comprehensive Exhibit List		
FLORIDA POWER & LIGHT COMPANY – DIRECT					
2	Daniel DeBoer	DD-1	Excerpt from FPL's Procedure 0-PME-049.0 Reactor Trip and Trip Bypass Breaker Inspection Maintenance.	1	
OFFICE OF PUBLIC COUNSEL - DIRECT					
3	Richard A. Polich	RAP-1	Resume of Richard A. Polich.	1 and 2	
4	Richard A. Polich	RAP-2	Richard Polich Regulatory Testimony List.	1 and 2	
5	Richard A. Polich	RAP-3	Testimony of Richard Polich in docket 20220001-EI and Notice of Withdrawal of Portions of Testimony.	1 and 2	
6	Richard A. Polich	RAP-4	Review of Nuclear Operations Florida Power & Light Company.	1 and 2	
7	Richard A. Polich	RAP-5	Turkey Point Units 3 and 4 Special Inspection Report.	1 and 2	
STAFF - DIRECT					
8	Carl Vinson	CV-1	Review of Florida Power & Light Company Nuclear Operations January 2024.	1 and 2	

FPSC EXH No. 1
03/20/2024

ADMITTED

Docket No. 20240001-EI
Comprehensive Exhibit List for Entry into Hearing Record
(March 26-27, 2024)

EXH #	Witness	I.D. # As Filed	Exhibit Description	Issue Nos.	Entered
9	Tom Ballinger	TEB-1	Summary of outages.	1 and 2	
STAFF HEARING EXHIBITS					
10	Stipulated, Nos. 4, and 9b DeBoer, No. 9a	Staff Exhibit 10	As filed in Docket No. 20220001-EI, FPL's Response to Staff's Second Set of Interrogatories Nos. 4 and 9 (Including Attachments)	1 and 2	
11	FPL Witness DeBoer, Nos. 11-14, and 16. Stipulated, No. 15	Staff Exhibit 11	As filed in Docket No. 20220001-EI, FPL's Response to Staff's Third Set of Interrogatories Nos. 11, 12, 13, 14, 15, and 16	1 and 2	
12	Stipulated, No. 30	Staff Exhibit 12	As filed in Docket No. 20220001-EI, FPL's Response to Staff's Fourth Set of Interrogatories No. 30	1 and 2	
13	FPL Witness DeBoer, Nos. 31, 33, and 34	Staff Exhibit 13	As filed in Docket No. 20220001-EI, FPL's Response to Staff's Fifth Set of Interrogatories Nos. 31, 33, and 34	1 and 2	
14	FPL Witness DeBoer, No. 7 Supplemental	Staff Exhibit 14	As filed in Docket No. 20220001-EI, FPL's Response to OPC's First Set of Interrogatories Nos. 1, 2, 3, 4, 5, 6, 7, 7 Supplemental, 8, 9, 10, and 11	1 and 2	

Docket No. 20240001-EI
Comprehensive Exhibit List for Entry into Hearing Record
(March 26-27, 2024)

EXH #	Witness	I.D. # As Filed	Exhibit Description	Issue Nos.	Entered
15	FPL Witness DeBoer, No. 14	Staff Exhibit 15	As filed in Docket No. 20220001-EI, FPL's Response to OPC's Second Set of Interrogatories No. 14	1 and 2	
16	FPL Witness DeBoer, Nos. 36, 41, 42, 43, 44, 45, 46, 47, 48, 49, and 50	Staff Exhibit 16	As filed in Docket No. 20220001-EI, FPL's Response to OPC's Third Set of Interrogatories Nos. 36, 41, 42, 43, 44, 45, 46, 47, 48, 49, and 50	1 and 2	
17		Staff Exhibit 17	As filed in Docket No. 20220001-EI, FPL's Response to OPC's First Request for Production of Documents Nos. 3, 8, 9, 13, 14, 15, 16, 18, 19, and 19 Supplemental (Including Attachments)	1 and 2	
18		Staff Exhibit 18	As filed in Docket No. 20220001-EI, FPL's Response to OPC's Third Request for Production of Documents Nos. 30, 31, 32, 33, 34, 35, 36, 37, and 38 (Including Attachments)	1 and 2	
19	FPL Witness DeBoer, Nos. 8 and 9	Staff Exhibit 19	As filed in Docket No. 20230001-EI, FPL's Response to OPC's First Set of Interrogatories Nos. 8 and 9	1 and 2	

FPSC EXH No. 1
03/20/2024

ADMITTED

Docket No. 20240001-EI
Comprehensive Exhibit List for Entry into Hearing Record
(March 26-27, 2024)

EXH #	Witness	I.D. # As Filed	Exhibit Description	Issue Nos.	Entered
20	Stipulated, Nos. 14-21, and 25 DeBoer, Nos. 22, 24, and co-sponsored 14-21, and 25	Staff Exhibit 20	As filed in Docket No. 20230001-EI, FPL's Response to Staff's Sixth Set of Interrogatories Nos. 14, 15, 16, 17, 18, 19, 20, 21, 22, 23, 23 supplemental, 24, and 25 (Including Attachments)	1 and 2	
21	Stipulated	Staff Exhibit 21	As filed in Docket No. 20230001-EI, FPL witness, Edward Anderson's prefiled exhibit EJA-1 – Schedule E1-B	1 and 2	
22	Stipulated	Staff Exhibit 22	As filed in Docket No. 20240001-EI, FPL's Response to Staff's Second Set of Interrogatories, No. 9 (Including Attachments)	1 and 2	

FPSC EXH No. 1
03/20/2024

ADMITTED

HEARING EXHIBITS

Exhibit Number	Witness	Party	Description	Moved In/Due Date of Late Filed

REVISION NO.:	PROCEDURE TITLE:	PAGE:
9	REACTOR TRIP AND TRIP BYPASS BREAKER INSPECTION AND MAINTENANCE	78 of 157
PROCEDURE NO.: 0-PME-049.01	TURKEY POINT PLANT	**INITIAL**

4.25 Cubicle Inspection (continued)

7. **INSPECT** switchgear cubicle for the following:

A. **INSPECT** control wiring for integrity of insulation and tightness of connections.

B. IF any control wiring is found loose, THEN **TIGHTEN** connections and **RECORD** any abnormal findings in Section 5.2, Step 1.

C. **VERIFY** left and right interior rail assemblies are **NOT** distorted.

D. **VERIFY** edges of rail assembly where breaker wheels roll are **NOT** mushroomed, rounded off, or bent inward or outward.

E. **REPLACE** rails, if necessary.

F. **VERIFY** breaker element levering pins welded on each rail are intact and undistorted.

G. **VERIFY** breaker release latch **NOT** bent and touches bottom of cell rail.

H. **PRESS** release latch by hand to its limit and **VERIFY** release latch springs back when released.

I. Cell positioning stop bracket **NOT** distorted.

J. Switchgear that the secondary contact assembly phenolic material **NOT** cracked.

K. Switchgear secondary contact assembly conductive surface **NOT** abnormally or unevenly worn.

L. Ground contact **NOT** corroded, **NOT** loose, and surface **NOT** abnormally or unevenly worn.

M. **REMOVE** cell switch covers.

N. **VERIFY** cell switch contacts are clean.

O. IF cell switch contacts require cleaning or lubrication, THEN:

(1) **CLEAN** with a cloth and isopropyl alcohol.

(2) **APPLY** grease (G77).

4.25 Cubicle Inspection (continued)

7. (continued)

P. **PRESS** spring-loaded plunger several times and **VERIFY** smooth and unbinding operation of switch.

Q. With spring-loaded plunger pressed, **VERIFY** correct contact configuration and contact resistance using a ohmmeter.

Functional Criteria: 1 ohm or less

R. With spring-loaded plunger released, **VERIFY** correct contact configuration and contact resistance using a ohmmeter.

Functional Criteria: 1 ohm or less

S. **INSTALL** cell switch covers.

FPSC EXH No. 3
03/18/2024
ADMITTED

GDS Associates, Inc
ENGINEERS & CONSULTANTS

Richard A. Polich, P.E.

C3-10

Managing Director – Power Supply Services

EDUCATION

Master of Business Administration, University of Michigan, 1990
Bachelor of Science, Mechanical Engineering, University of Michigan, 1979
Bachelor of Science, Nuclear Engineering, University of Michigan, 1979

ENGINEERING REGISTRATION

Professional Engineer in the State of Michigan

PROFESSIONAL MEMBERSHIP

National Society of Professional Engineers
American Nuclear Society
American Society of Mechanical Engineers

PROFESSIONAL EXPERIENCE

Mr. Polich has more than 40 years' experience as an energy industry engineer, manager, and leader, combining his business and technical expertise in the management of governmental, industrial, and utility projects. He has worked extensively in nuclear, coal, IGCC, natural gas, green/renewable generation. Mr. Polich has developed generation projects in wind, solar, and biomass in Australia, Canada, Caribbean, South America and United States. His generation experience includes engineering of systems and providing engineering support of plant operations. Notable projects include the Midland Nuclear Project and its conversion to natural gas combined cycle, start-up testing support for Consumers' coal-fired Campbell 3, Palisades nuclear steam generator replacement support, Covert Generating Station feasibility evaluation, and a Lake Erie offshore wind project. He also has extensive experience in utility rates and regulation, having managed Consumers Energy's rates group for several years. In that function his responsibilities included load and revenue forecasting, overseeing the design of gas and electric rates, and testifying in regulatory proceedings. Mr. Polich has testified in over thirty regulatory and legislative proceedings.

Mr. Polich has been involved in the nuclear industry since 1978. While at GDS, Mr. Polich has provided Utah Associated Municipal Power System project cost analysis for a small modular nuclear power project. Last year, he provided advisory services to the Vermont Public Utility Commission on the ownership transfer, nuclear decommissioning trust fund adequacy and decommissioning methodology of Vermont Yankee. Mr. Polich has supported GDS oversight efforts of the construction of the Vogtle Nuclear Plant units 3 & 4 for the Georgia Public Service Commission. He has also provided decommissioning assessment analysis on St. Lucie Nuclear, and Grand Gulf Nuclear projects. Mr. Polich was part of the design engineering team for the Erie Nuclear Plant by the design engineering firm, Gilbert Commonwealth. Key responsibilities were the design of systems and component specifications associated with the nuclear steam supply systems (NSSS) and steam turbine thermal cycle. Worked directly with Babcock and Wilcox on NSSS design and ancillary system specifications. Mr. Polich was also senior engineer on the Midland Nuclear project, responsible for oversight of Bechtel design engineering and interfacing with NSSS vendor Babcock & Wilcox on ancillary systems. His responsibilities also included negotiation with the Nuclear Regulatory Commission on new regulation requirements. Mr. Polich's role evolved into onsite engineering during construction of the Midland Nuclear Plant and as a project trouble shooter at the Palisades Nuclear Plant.

C3-8

FPSC EXH No. 3
03/18/2024
ADMITTED

SPECIFIC PROJECT EXPERIENCE

NUCLEAR PROJECT EXPERIENCE

Utah Association of Municipal Utilities – Provided assessment of project costs and economics during contract negotiation phase of project. Included review of Small Modular Reactor design concepts, identification of critical issues, project schedule, risk analysis and estimated cost provided by NuScale and EPC contractors. Provided technical support for UAMPS team on as needed basis.

Vermont Yankee – Provided the Vermont Public Utility Commission advisory services on the asset transfer of Vermont Yankee from Entergy Nuclear Operations, Inc. to NorthStar Group Holdings, LLC. This effort has included assessment of financial strength of new company, adequacy of Nuclear Decommissioning Trust Fund to fund decommissioning efforts, evaluation of decommissioning methodology and State of Vermont Risk.

Vogtle Nuclear Plant Units 3 & 4 – Provided advisory services to the team performing the oversight of the construction of the Vogel Plant Units 3 & 4 as part of GDS project oversight responsibilities for the Georgia Public Service Commission.

St. Lucie Nuclear Plant – Provided a risk assessment, decommissioning funding study and ownership evaluation for City of Vero Beach. This included review of project maintenance history, steam generator replacement project, analysis of decommissioning needs and funding and assessing current value of Vero Beach's ownership share.

Grand Gulf Nuclear Project – Assessed the adequacy of decommissioning funding and funding level for the grand Gulf Nuclear plant for Cooperative Energy. Project purpose was to assess changes in decommissioning funding rates and to determine if sufficient funds would be available for plant decommissioning.

Consumers Energy Midland Nuclear Plant – Responsible for overseeing EPC contractor design and construction of primary and secondary nuclear systems. Included review of systems for compliance with Nuclear Regulatory Commission regulations. Key projects included:

- Leading team to analyze plant and determine best methods for compliance with new CFR Appendix R Fire Protection rules
- Design of primary cooling system pump oil collection and disposal systems
- Oversight of redesign of component cooling water systems
- Analysis of diesel generator capability to meet emergency shutdown power requirements
- Primary interface with Dow Chemical for steam supply contract

Ohio Edison Company Erie Nuclear Project – Design engineer responsible for the design, equipment specifications, bid evaluations and regulatory licensing for nuclear steam supply system and ancillary systems. Key projects included:

- Project Thermal Analysis
- Development of NSS valve specifications
- Major equipment bid Proposal Evaluation and recommendations
- Interface with Babcock & Wilcox on NSSS Design

RATES & REGULATORY

GDS Associates, Inc. – Managing Director

North Dakota Public Service Commission Staff – Case No. PU-16-666 MDU General Rate Case

Provided testimony on behalf of the North Dakota Public Service Commission Staff regarding return on equity, cost of capital, revenue requirement, and generation resource costs. C3-9

FPSC EXH No. 3
03/18/2024
ADMITTED

North Dakota Public Service Commission Staff – Case No. PU-15-96 NSP Determination of Prudence

Provided testimony on behalf of the North Dakota Public Service Commission Staff regarding analysis and recommendation concerning Northern States Power's ("NSP") need for additional generation resources.

Consumers Energy - Supervisor of Pricing and Forecasting

Managed the group responsible for setting and obtaining regulatory approval for the company's electric and gas rates. Developed new approaches to electric and natural gas competitive pricing, redesigned electric rates to simplify rates and eliminate losses, and defined new strategies for customer energy pricing. Negotiated new electric supply contracts with key industrial electric customers resulting in over $800M in annual revenue. Testified in multiple regulatory proceedings.

EOS Energy Options & Solutions – Consulting Company

Provided testimony for multiple clients in both Detroit Edison and Consumers Energy in over 30 regulatory proceedings. Testimony topics included rates, public policy and deregulation. Also testified in several legislative proceedings in both Michigan and Ohio, addressing energy policy. Provided expert witness testimony in Massachusetts regarding wind energy projects.

NATURAL GAS COMBINED CYCLE EXPERIENCE

Consumers Energy – 1,560 MW Midland Cogeneration Venture
Member of a small team selected to investigate the feasibility of converting the mothballed Midland Nuclear Plant into a fossil fueled power plant. Established new plant configuration that repowered the existing nuclear steam turbine with natural gas fired combustion turbines and heat recovery steam generators. Developed the new thermal cycle and heat rate, determined how to supply steam to Dow chemical for cogeneration, developed models for projecting plant performance, and defined which portions of the nuclear plant were useful in the new combined cycle plant and forecasted project economics.

Nordic Energy – Vice President

Project Manager for the development of two 1,150 MW IGCC projects proposed to Georgia Power and Xcel Energy in response to RFPs. Responsibilities included establishing thermal cycles, equipment selection, site selection, supervising engineering, developing project proforma and proposals.

Project Manager for 230 MW power barge to be located on the Columbia River near Portland, Oregon. Lead the project development team responsible for securing equipment, designing the power plant, design of barges, assessing site feasibility, developing project economics and interconnection applications.

RENEWABLE ENERGY EXPERIENCE

Matinee Energy – Utility Scale Solar Developer

Engineering design and project development consultant for utility scale solar photovoltaic projects. Development activities include site selection, equipment specifications, financial analysis, and preparation of proposals. Also responsible for engineering and securing electrical interconnection.

Windlab Developments USA – Wind Power Developer

Responsible for greenfield development of the US platform for wind energy projects east of the Mississippi. Developed the company's engineering protocol for wind project design and construction, responsible for managing engineering design and construction of projects, and established six wind power projects (750 MW). Responsible for negation of Power Purchase Agreements, electrical interconnection studies, interface with Midwest ISO and submitting Generation Interconnection Application.

FPSC EXH No. 3
03/18/2024
ADMITTED

TradeWind Energy - Wind Power Project Developer

Project developer for 800 MW of wind power projects in Michigan and Indiana. Introduced new project management methods to the development process which resulted in savings of over $200,000 annually on each project.

Third Planet Windpower – Wind Power Project Developer

Engineering and project management consultant to support the startup of new wind power company. Established engineering standards used for selection of wind project equipment and project construction, analysis tools for evaluating projecting wind project power production, and performed project economic modeling.

Noble Environmental Power – Wind Power Project Developer

Electric transmission system consultant on the development of several wind power projects. Supported Noble's decisions on transmission gird interconnect and negotiate interconnection agreements.

ENERGY EFFICIENCY EXPERIENCE

Arkansas Energy Office – Weatherization Assistance Program Evaluation

Evaluated the performance and operations of Arkansas's Weatherization Assistance Program. This included review of program effectiveness, program operations, energy efficiencies attained, adequacy of energy efficiency measures and subcontractor performance.

CLEAResult – Arkansas Energy Efficiency Programs

Energy efficiency operations and program support for 400% increase in Arkansas' energy efficiency programs. Developed processes for data collection, field staff deployment and job assignments.

ECONOMIC IMPACT ASSESSMENT

Michigan Department of Environmental Quality - Economic Impacts of a Renewable Portfolio Standard and Energy Efficiency Program for Michigan

Project Manager for this report which focused on the economic impact of renewable portfolio standard and energy efficiency programs on the State of Michigan. The evaluation used in this report encompassed using integrated resource planning models, econometric modeling, and electric pricing models for the entire State of Michigan.

West Michigan Business Alliance - Alternative and Renewable Energy Cluster Analysis

Prepared the report providing a road map for Western Michigan businesses to establish new business in the renewable energy industry.

POWER PROJECT EXPERIENCE:

Detroit Edison St Clair Power Station – Performed coal combustion analysis associated with conversion Powder River Basin coal. Work included pulverizer mill performance testing, boiler combustion analysis on new coal, and unit performance analysis.

Consumers Energy Campbell 3 - Supported start-up efforts of this 800 MW pulverized coal power plant. Part of team that performed analysis of boiler data and determined the cause of superheater failure. Also part of team to analyze performance test data for warranty evaluation.

Consumers Energy Weadock Plant – Design oversight and specified various plant upgrades during major maintenance outage. Included replacement of high-pressure superheater, design of new steam supply pipes, valve specifications and supported plant restart.

FPSC EXH No. 3
03/18/2024
ADMITTED

PAPERS & PUBLICATIONS

Engineering and Economic Evaluation of Offshore Wind Plant Performance and Cost Data, 2011, Produced for the Electric Power Research Institute, KEMA, Inc.

FERC's 15% Fast Track Screening Criterion, 2012, Paper reviewing the FERC 15% screening criteria for electrical interconnection, KEMA, Inc.

Island of Saint Maarten Sustainable Energy Study, 2012, Produced for the Cabinet of Ministry VROMI, KEMA Inc.

A Study of Economic Impacts from the Implementation of a Renewable Portfolio Standard and an Energy Efficiency Program in Michigan, 2007, Produced for the Michigan Department of Environmental Quality

Alternative and Renewable Energy Cluster Analysis, 2007, Produced for the West Michigan Strategic Alliance and The Right Place

COURSES & SEMINARS

Association of Energy Engineers – Certified Energy Manager
Green Building Council – Associated LEED Certification Training
CLEAResult Leadership Academy

COMMUNITY SERVICE AND ACTIVITIES

Bicycling, hiking and cross-country skiing
Instrument-Rated Private Pilot
Habitat for Humanity
Scoutmaster
Soccer coach and referee
Volunteer work for disaster relief and building homes in Mexico

FPSC EXH No. 4
03/18/2024
ADMITTED

PREVIOUS TESTIMONY OF RICHARD A. POLICH

JURISDICTION	CASE	ON BEHALF	TITLE
Minnesota	5-2500-38476	Minnesota Dept of Commerce	Matter of Sherco Unit 3 Energy Replacement Costs.
FERC	ER21-2186-001	Joint Customers	Fern Solar, LLC
International Court of Arbitration of The International Chamber of Commerce		Olin Corporation	Dow Chemical Company vs. Blue Cube Operations LLC & Olin Corporation
FERC	ER21-2364-001	Joint Customers	Albemarle Beach Solar, LLC
FERC	ER20-2576-001	Joint Customers	Holloman Lessee, LLC
FERC	ER21-2091-001	Joint Customers	Mechanicsville Solar
Michigan	U-21090	Biomass Plants	Request for Approval of Consumers Energy Integrated Resource Plan
Minnesota	G-002/CI-21-610	Minnesota Dept of Commerce	Investigation into the cause of outages at Xcel Energy's gas peaking facilities.
FERC	ER21-864	Glidepath	Revenue Requirement for Reactive Power Production Capability of Meyersdale Storage, LLC.
Florida	20220001-E1	Citizens of the Public Council	Florida Power Fuel and {Purchase Power Cost Recovery
Minnesota	E999/AA-20-171	Minnesota Dept of Commerce	Investigation into the cause of outages at Minnesota Power's Clay Boswell coal plant and impact on replacement power costs.
Florida	2019140-EI	Citizens of the Public Council	Crystal River 3 Accelerated Decommissioning
Florida	2019001-EI	Citizens of the Public Council	Fuel Adjustment Clause – Bartow Steam Turbine Failure Power Supply Cost Recovery Disallowance
FERC	ER17-1821-002	Joint Customers	Revenue Requirement for Reactive Power Production Capability of the Panda Stonewall Generating Facility
North Carolina	E-2 Sub1142	Duke Energy Progress	Duke Energy Progress General Rate Case
Indiana	38707 FAC111-S1	Nucor Steel	Duke Energy Indiana, LLC for Fuel Cost Adjustment Clause
North Dakota	PU-16-166	ND PSC Staff	Montana-Dakota Utilities 2016 Electric Rate Increase Application
Hawaii	2015-0022	Sun Edison	Regarding the Hawaiian Electric Company, Inc. and NextEra Merger
North Dakota	PU-15-96	ND PSC Staff	Northern States Power Determination of Prudence
Michigan	U-10143	Consumers Energy	Consumers Energy Approval of an Experimental Retail Wheeling Case
Michigan	U-10335	Consumers Energy	General Rate Case
Michigan	U-10625	Consumers Energy	Proposal for Market-Based Rates Under Rate-K
Michigan	U-10685	Consumers Energy	1996 General Rate Case
Michigan	U-11915	Energy Michigan	Supplier Licensing
Michigan	U-11955	Energy Michigan	Consumers Energy Stranded & Implementation Cost Recovery
Michigan	U-11956	Energy Michigan	Detroit Edison Stranded & Implementation Cost Recovery
Michigan	U-12478	Energy Michigan	Detroit Edison Asset Securitization Case

FPSC EXH No. 4
03/18/2024
ADMITTED

PREVIOUS TESTIMONY OF RICHARD A. POLICH

JURISDICTION	CASE	ON BEHALF	TITLE
Michigan	U-12488	Energy Michigan	Consumers Energy Retail Open Access Tariff
Michigan	U-12489	Energy Michigan	Detroit Edison Retail Open Access Tariffs
Michigan	U-12505	Energy Michigan	Consumers Energy Asset Securitization Cases
Michigan	U-12639	Energy Michigan	Stranded Cost Methodology Case
Michigan	U-13380	Energy Michigan	Consumers Energy 2000, 2001 & 2002 Stranded Cost Case
Michigan	U-13350	Energy Michigan	Detroit Edison 2000 & 2001 Stranded Cost Case
Michigan	U-13715	Energy Michigan	Consumers Energy Securitization of Qualified Costs
Michigan	U-13720	Energy Michigan	Consumers Energy 2002 Stranded Costs
Michigan	U-13808	Energy Michigan	Detroit Edison General Rate Case
Michigan	U-13808-R	Energy Michigan	Detroit Edison 2004 Stranded Cost &
Michigan	U-14474	Energy Michigan	Detroit Edison 2004 PSCR Reconciliation Case
Michigan	U-13933	Energy Michigan	Detroit Edison Low-Income Energy Assistance Credit for Residential Electric Customers
Michigan	U-13917-R	Energy Michigan	Consumers Energy 2004 PSCR Reconciliation Case
Michigan	U-13989	Energy Michigan	Consumers Energy Request for Special Contract Approval
Michigan	U-14098	Energy Michigan	Consumers Energy 2003 Stranded Costs
Michigan	U-14148	Energy Michigan	Consumers Energy MCL 460.10d(4) Case
Michigan	U-14347	Energy Michigan	Consumers Energy General Rate Case
Michigan	U-14274-R	Energy Michigan	Consumers Energy 2005 PSCR Reconciliation Case
Michigan	U-14275-R	Energy Michigan	Detroit Edison Company 2005 PSCR Reconciliation Case
Michigan	U-14399	Energy Michigan	Detroit Edison Company Application for Unbundling of Rate
Michigan	U-14992	Energy Michigan	Power Purchase Agreement and Other Relief in Connection with the sale of the Palisades Nuclear Power Plant and Other Assets

FPSC EXH No. 5
03/18/2024

ADMITTED

C3-117

FILED 9/14/2022
DOCUMENT NO. 06564-2022
FPSC - COMMISSION CLERK

STATE OF FLORIDA
OFFICE OF PUBLIC COUNSEL

C/O THE FLORIDA LEGISLATURE
111 WEST MADISON ST.
ROOM 812
TALLAHASSEE, FLORIDA 32399-1400
850-488-9330

EMAIL: OPC_WEBSITE@LEG.STATE.FL.US
WWW.FLORIDAOPC.GOV

WILTON SIMPSON
President of the Senate

CHRIS SPROWLS
Speaker of the House of Representatives

September 14, 2022

Adam J. Teitzman, Commission Clerk
Florida Public Service Commission
2540 Shumard Oak Boulevard
Tallahassee, Florida 32399-0850

Re: Docket No. 20220001-EI

Dear Mr. Teitzman,

Please find enclosed for filing in the above referenced docket the Direct Testimony and Exhibits of Richard Polich, P.E. This filing is being made via the Florida Public Service Commission's Web Based Electronic Filing portal.

If you have any questions or concerns; please do not hesitate to contact me. Thank you for your assistance in this matter.

Sincerely,

Richard Gentry
Public Counsel

/s/ Stephanie A. Morse
Stephanie A. Morse
Associate Public Counsel
Florida Bar No. 0068713

C3-15

FPSC EXH No. 5
03/18/2024

ADMITTED

C3-118

CERTIFICATE OF SERVICE
DOCKET NO. 20220001-EI

I HEREBY CERTIFY that a true and correct copy of the foregoing has been furnished by electronic mail on this 14th day of September 2022, to the following:

J. Wahlen/M. Means/V. Ponder
Ausley Law Firm
P.O. Box 391
Tallahassee FL 32302
jwahlen@ausley.com
mmeans@ausley.com
vponder@ausley.com

Dianne M. Triplett
Duke Energy
299 First Avenue North
St. Petersburg FL 33701
Dianne.triplett@duke-energy.com

Suzanne Brownless/Ryan Sandy
Florida Public Service Commission
Office of the General Counsel
2540 Shumard Oak Boulevard
Tallahassee, Florida 32399-0850
sbrownle@psc.state.fl.us
rsandy@psc.state.fl.us

Matthew R. Bernier/Robert L. Pickels/Stephanie A. Cuello
Duke Energy
106 E. College Avenue, Suite 800
Tallahassee FL 32301
FLRegulatoryLegal@duke-energy.com
matthew.bernier@duke-energy.com
robert.pickels@duke-energy.com
stephanie.cuello@duke-energy.com

Jon C. Moyle, Jr.
Florida Industrial Power Users Group
c/o Moyle Law Firm
118 North Gadsden Street
Tallahassee FL 32301
jmoyle@moylelaw.com
mqualls@moylelaw.com

Maria Jose Moncada/David Lee
Florida Power & Light Company
700 Universe Boulevard
Juno Beach FL 33408-0420
david.lee@fpl.com
maria.moncada@fpl.com

Kenneth A. Hoffman
Florida Power & Light Company
134 W. Jefferson Street
Tallahassee FL 32301-1859
ken.hoffman@fpl.com

Mr. Mike Cassel
Florida Public Utilities Company
208 Wildlight Ave.
Yulee FL 32097
mcassel@fpuc.com

FPSC EXH No. 5
03/18/2024

ADMITTED

C3-119

Michelle D. Napier
Florida Public Utilities Company
1635 Meathe Drive
West Palm Beach FL 33411
mnapier@fpuc.com

Beth Keating
Gunster Law Firm
215 South Monroe St., Suite 601
Tallahassee FL 32301
bkeating@gunster.com

Corey Allain
Nucor Steel Florida, Inc.
22 Nucor Drive
Frostproof FL 33843
corey.allain@nucor.com

James W. Brew/Laura Wynn Baker
PCS Phosphate - White Springs
c/o Stone Law Firm
1025 Thomas Jefferson St., NW, 8th Floor, W. Tower
Washington DC 20007
jbrew@smxblaw.com
lwb@smxblaw.com

Ms. Paula K. Brown
Tampa Electric Company
Regulatory Affairs
P. O. Box 111
Tampa FL 33601-0111
regdept@tecoenergy.com

Peter J. Mattheis/Michael K. Lavanga/Joseph R. Briscar
Stone Law Firm
1025 Thomas Jefferson St., NW, Ste. 800 W.
Washington DC 20007
jrb@smxblaw.com
pjm@smxblaw.com
mkl@smxblaw.com

Robert Scheffel Wright/John T. LaVia III
Florida Retail Federation
1300 Thomaswood Drive
Tallahassee FL 32308
schef@gbwlegal.com
jlavia@gbwlegal.com

/s/Stephanie A. Morse
Stephanie A. Morse
Associate Public Counsel
Morse.Stephanie@leg.state.fl.us

FPSC EXH No. 5
03/18/2024
ADMITTED

BEFORE THE FLORIDA PUBLIC SERVICE COMMISSION

In re: Fuel and purchased power cost recovery clause with generating performance incentive factor.	DOCKET NO. 20220001-EI FILED: September 14, 2022

DIRECT TESTIMONY

OF

RICHARD A. POLICH, P.E. (STATE OF MICHIGAN)

ON BEHALF OF THE CITIZENS OF THE PUBLIC COUNSEL

Richard Gentry
Public Counsel

Charles Rehwinkel
Deputy Public Counsel
Florida Bar No. 527599
Rehwinkel.Charles@leg.state.fl.us

Stephanie Morse
Associate Public Counsel
Florida Bar No. 0068713
Morse.Stephanie@leg.state.fl.us

Office of Public Counsel
c/o The Florida Legislature
111 West Madison Street, Room 812
(850) 488-9330

Attorneys for the Citizens
of the State of Florida

FPSC EXH No. 5
03/18/2024
ADMITTED

C3-121

TABLE OF CONTENTS

I. INTRODUCTION 1

II. TESTIMONY SUMMARY 7

III. DESCRIPTION OF FPL NUCLEAR POWER PLANTS 10

IV. ST. LUCIE OPERATING HISTORY FOR 2019, 2020 AND 2021 13

V. TURKEY POINT OPERATING HISTORY FOR 2019, 2020 AND 2021 15

VI. ST. LUCIE AND TURKEY POINT PERSONNEL REDUCTIONS 17

VII. NRC INVESTIGATIONS 19

VIII ASSESSMENT OF ST. LUCIE AND TURKEY POINT OPERATIONS 31

IX ASSESSMENT OF OUTAGES AND DERATES IMPACT ON REPLACEMENT POWER COSTS 35

EXHIBITS

RESUME OF RICHARD A. POLICH, P.E. RAP-1

LIST OF RICHARD A. POLICH TESTIMONY RAP-2

COMPOSITE - FPL'S AUGUST 3, 2022 OBJECTIONS TO OPC'S DISCOVERY; FPL'S RESPONSES AND OBJECTIONS TO INT. 16 AND POD 20; AND EXCERPT OF FPL'S APRIL 1, 2022 PETITION RAP-3

SEPTEMBER 12, 2019 NRC NOTICE OF VIOLATION RAP-4

APRIL 6, 2021 NRC NOTICE OF VIOLATION RAP-5

SEPTEMBER 30, 2021 NRC SUPPLEMENTAL INSPECTION REPORT RAP-6

FPL'S RESPONSE TO OPC INTERROGATORY NOS. 37 - 40 RAP-7

APRIL 15, 2019 NRC INSPECTION REPORT RAP-8

FEBRUARY 11, 2021 NRC INSPECTION REPORT RAP-9

C3-19

FPSC EXH No. 5
03/18/2024
ADMITTED

C3-122

PERFORMANCE DATA FOR 2010-2021 RAP-10

TURKEY POINT UNIT 4 ROOT CAUSE EVALUATION RE:
GENERATOR LOCKOUT FROM LOSS OF EXCITER RAP-11

FPL'S RESPONSE TO STAFF'S INTERROGATORY NO. 4 RAP-12

TURKEY POINT UNIT 4 ROOT CAUSE EVALUATION RE. REACTOR
TRIP DURING RESTORATION FROM RPS TESTING RAP-13

C3-20

FPSC EXH No. 5
03/18/2024

ADMITTED

C3-123

I. INTRODUCTION

Q. PLEASE STATE YOUR NAME, TITLE AND BUSINESS ADDRESS.

A. My name is Richard A. Polich. I am a Managing Director at GDS Associates, Inc. ("GDS"). My business address is 1850 Parkway Place, Suite 800, Marietta, Georgia, 30067.

Q. WHAT ARE YOUR DUTIES AND RESPONSIBILITIES AT GDS ASSOCIATES?

A. My primary duties are within GDS's Power Supply Planning Department. While employed by GDS, I have provided consulting services for areas such as:

- Generation Asset Management,
- Engineering analysis of generation projects,
- Engineering evaluation of waste to energy projects,
- Energy management consulting services,
- Nuclear decommissioning cost evaluation,
- Modular nuclear project cost evaluation,
- Renewable energy project cost assessment and economic evaluation,
- Testimony on rate of return, cost of service, regulatory disallowances, determination of prudence, revenue requirements and plant in service, and
- Review of generation project design and construction.

Q. MR. POLICH, PLEASE SUMMARIZE YOUR FORMAL EDUCATION.

A. I graduated from the University of Michigan - Ann Arbor in August 1979 with a Bachelor of Science Engineering Degree in Nuclear Engineering and a Bachelor of Science Engineering Degree in Mechanical Engineering.

C3-21

FPSC EXH No. 5
03/18/2024

ADMITTED

C3-124

Q. PLEASE BRIEFLY DESCRIBE YOUR PROFESSIONAL EXPERIENCE.

I have over 40 years of work experience in the energy sector, performing duties and services for a myriad of companies and organizations, and representing the interests of private and public constituencies throughout the country.

In May 1978, I joined Commonwealth Associates, Inc., located in Jackson, Michigan, as a Graduate Engineer and worked on several plant modification and new plant construction projects.

In May 1979, I joined Consumers Power Inc., (now called Consumers Energy), located in Jackson, Michigan, as an Associate Engineer in the Plant Engineering Services Department.

In April 1980, I transferred to the Midland Nuclear Project and progressed through various job classifications to Senior Engineer. I was also part of a small team that evaluated the potential to repower the nuclear steam turbine with combustion turbines. One of my responsibilities was to provide the initial thermal design for the combined cycle project, utilizing one of the two existing nuclear steam turbines while still providing process steam for Dow Chemical Company. This project is now known as the Midland Cogeneration Venture, a 12-combustion turbine and steam turbine project capable of providing 1,633 MW of capacity.

In July 1987, I transferred to the Market Services Department as a Senior Engineer and reached the level of Senior Market Representative. While in this department, I analyzed the economic and engineering feasibility of customer cogeneration projects.

In July 1992, I transferred to the Rates and Regulatory Affairs Department of Consumers Energy as a Principal Rate Analyst. In that capacity, I performed studies

FPSC EXH No. 5
03/18/2024

ADMITTED

relating to all facets of development and design of Consumers Energy's gas, retail, electric and electric wholesale rates. During this period, I was heavily involved in the development of Consumers Energy's Direct Access program and in the development of Consumers Energy's Retail Open Access program. I also participated in the development of Consumers Energy's revenue forecast.

In March 1998, I joined Nordic Energy, LLC ("Nordic"), located in Ann Arbor, Michigan, as Vice President in charge of marketing and sales. My responsibilities included all aspects of obtaining new customers and enabling Nordic to supply electricity to those customers. In May 2000, my responsibilities shifted to Operations and Regulatory Affairs and my responsibilities included management of supply purchases, transmission services, and development of new power projects. My Regulatory Affairs responsibilities also included overseeing regulatory and legislative issues for the company.

In March 2003, I formed Energy Options & Solutions, based in Ann Arbor, Michigan, as a consulting concern focusing on providing engineering services and regulatory support. Through my work with Energy Options & Solutions, I gained extensive experience consulting in the areas of project development and economic analysis with renewable energy companies across the country, including: Noble Environmental Power located in Centerbrook, Connecticut; Third Planet Windpower, LLC located in Palm Beach Gardens, Florida; TradeWind Energy, LLC located in Lenexa, Kansas; Windlab Developments USA located in Canberra, Australian Capital Territory, Australia; and Matinee Energy Inc. located in Tucson, Arizona, among others.

Other examples of my consulting work include evaluation of the Arkansas Weatherization Assistance Program for the Arkansas Energy Office and providing the

FPSC EXH No. 5
03/18/2024
ADMITTED

West Michigan Business Alliance with an evaluation of the business opportunities for Western Michigan businesses in the renewable energy business sector.

In 2007, I served as primary author of a report on the economic impacts of renewable portfolio standards and energy efficiency programs for the Department of Environmental Quality – State of Michigan.

In 2011, I joined KEMA, Inc. ("KEMA") located in Burlington, Massachusetts, as a Service Line Leader responsible for developing its renewable energy consulting business. While at KEMA, I performed multiple renewable energy studies for the Electric Power Research Institute, including a renewable energy options study for the country of Sint Maarten (a constituent country of the Kingdom of the Netherlands). I also assisted Lake Erie Energy Development Corporation in its successful application to the U.S. Department of Energy for a multi-million dollar grant to develop an offshore wind project in Lake Erie.

In 2013, I joined CLEAResult, located in Little Rock, Arkansas, as Director of Operations. My primary responsibility involved supporting program operations in assisting the company's Arkansas unit to successfully meet a 400% increase in energy efficiency program goals that it managed for Entergy. I was also responsible for managing the CLEAResult's natural gas energy efficiency programs in the State of Oklahoma.

In 2015, I joined the Georgia office of GDS Associates, Inc., a consulting group focusing on utility engineering and consulting services, as Managing Director.

I have been a registered Professional Engineer since 1983 and I am licensed in the State of Michigan.

My resume is included as Exhibit No. ___(RAP-1).

FPSC EXH No. 5
03/18/2024
ADMITTED

Q. HAVE YOU TESTIFIED IN OTHER REGULATORY PROCEEDINGS?

A. Yes, Exhibit No. ___(RAP-2) contains a list of regulatory proceedings in which I have provided testimony.

Q. WHAT IS THE NATURE OF YOUR BUSINESS?

A. GDS is an engineering and consulting firm with offices in Marietta, Georgia; Austin, Texas; Auburn, Alabama; Orlando, Florida; Manchester, New Hampshire; Kirkland, Washington; Portland, Oregon; and Madison, Wisconsin. GDS has over 170 employees with backgrounds in engineering, accounting, management, economics, finance, and statistics. GDS provides rate and regulatory consulting services in the electric, natural gas, water, and telephone utility industries. GDS also provides a variety of other services in the electric utility industry including power supply planning, generation support services, financial analysis, load forecasting, and statistical services. Our clients are primarily publicly owned utilities, municipalities, customers of privately owned utilities, groups or associations of customers, and government agencies.

Q. WHOM DO YOU REPRESENT IN THIS PROCEEDING?

A. I am representing the Florida Office of Public Counsel ("OPC").

Q. WHAT WAS YOUR ASSIGNMENT IN THIS PROCEEDING?

A. I was asked by the OPC to conduct a review of, and to evaluate Florida Power & Light Company's ("FPL") operation of the St Lucie Nuclear Plant ("St Lucie") and Turkey Point Nuclear Power Plant ("Turkey Point) for the period of 2019 through 2021 and beyond, to evaluate other factors that might be impacting the cost of fuel in the ongoing fuel cost recovery clause dockets. The review and evaluation included assessment of the plant operations which led to several outages and derates (or reductions in the plant's operating

FPSC EXH No. 5
03/18/2024
ADMITTED

capacity while it remains in operation). My testimony also includes an assessment of replacement power costs impacts for 2019, 2020 and 2021 in which the units at St Lucie and Turkey Point were not available to provide full capacity, and the cost of the replacement power that FPL is seeking to recover from its ratepayers in this proceeding. I was also asked to review the FPL nuclear operations to determine if there were any circumstances and factors that impact the current estimated and projected fuel costs and ongoing fuel costs that are at issue in the current docket.

Q. DID OTHER GDS PERSONNEL ASSIST YOU IN THE ANALYSIS AND DEVELOPMENT OF YOUR TESTIMONY IN THIS MATTER?

A. Yes, Megan Morello assisted me with review of documents. Megan Morello is employed by GDS as a Project Manager in the Power Supply department. She has a bachelor's degree in mechanical engineering from Georgia Institute of Technology and is a Registered Professional Engineer in Georgia.

Q. ARE YOU SPONSORING ANY EXHIBITS?

A. Yes, I am sponsoring the following exhibits:

1. Exhibit No. ___(RAP-1) Resume of Richard A. Polich, P.E.
2. Exhibit No. ___(RAP-2) List of Richard A. Polich Testimony
3. Exhibit No. ___(RAP-3) Composite - FPL's August 3, 2022 Objections to OPC's Discovery; FPL's Responses And Objections to INT. 16 and POD 20; and Excerpt of FPL's April 1, 2022 Petition
4. Exhibit No. ___(RAP-4) September 12, 2019 NRC Notice Of Violation
5. Exhibit No. ___(RAP-5) April 6 2021 NRC Notice of Violation
6. Exhibit No. ___(RAP-6) September 30, 2021 NRC Supplemental Inspection Report
7. Exhibit No. ___(RAP-7) FPL's Response to OPC Interrogatory Nos. 37 – 40

FPSC EXH No. 5
03/18/2024

ADMITTED

C3-129

8. Exhibit No. ___(RAP-8) April 15, 2019 NRC Inspection Report

9. Exhibit No. ___(RAP-9) February 11, 2021 NRC Inspection Report

10. Exhibit No. ___(RAP-10) Performance Data For 2010-2021

11. Exhibit No. ___(RAP-11) Turkey Point Unit 4 Root Cause Evaluation Re: Generator Lockout from Loss of Exciter

12. Exhibit No. ___(RAP-12) FPL's Response To Staff's Interrogatory No. 4

13. Exhibit No. ___(RAP-13) Turkey Point Unit 4 Root Cause Evaluation Re. Reactor Trip During Restoration From Rps Testing

II. TESTIMONY SUMMARY

Q. PLEASE SUMMARIZE YOUR TESTIMONY.

A. I have identified concerns with the staffing, culture and operations at the four nuclear units of FPL that need to be investigated by the Florida Public Service Commission ("Commission") as these issues affect past, current and future fuel costs paid by FPL customers. Market forces over the last decade have placed significant cost reduction pressure on regulated and merchant nuclear plant owners alike because of the need to be competitive with combined cycle power generation using cheap natural gas fuel. Although this phenomenon has abated somewhat in the last two years with the recent large price increases in the natural gas market, the impact on nuclear plant operations is already in place. Nuclear power generation is a valuable carbon-free power generation resource that is critical to achieving carbon emission reduction goals for many utilities. It is critical that utilities operating nuclear power facilities maintain sufficient operational resources to safely and properly operate these facilities.

Review of operations at FPL's St Lucie and Turkey Point facilities over the last three years indicates that there has been an increased frequency of outage and derate hours

FPSC EXH No. 5
03/18/2024
ADMITTED

that have resulted in avoidable (and potentially avoidable) replacement power costs. Since 2017 FPL has reduced budgeted personnel headcount at St. Lucie by 24.7% and Turkey Point by 25.2%. Actual head count at the plant sites has been reduced by 28.0% at St. Lucie and 22.3% at Turkey Point.

Reductions in personnel alone are not necessarily a red flag in the assessment of nuclear plant operations. However, there have been a series of instances at St. Lucie and Turkey Point over recent years which are indicative of potential problems and which call into question whether force reductions during times of frozen base rates are in the best interests of customers who pay for replacement power in the event of outages.

The events that I believe have a bearing on the outages in this case have occurred of the past 5 years and indicate a set of circumstances that may be continuing to impact FPL's operations and ongoing fuel costs when viewed in connection with the workforce trends. Several events will be discussed. In one instance, for example, the United States Nuclear Regulatory Commission ("NRC") determined that FPL's Regional Vice President (VP) – Operations, deliberately caused a contract employee's assignment to be cancelled the week of March 13, 2017 because the employee raised a nuclear safety concern via the submission of a condition report. The NRC determined that the deliberate actions of the now former FPL Regional VP - Operations caused FPL to be in violation of 10 C.F.R. § 50.7, which is significant because of the potential that individuals might not raise safety issues for fear of retaliation; the NRC also assessed a civil penalty of $232,000 for a Severity Level II violation.

In another instance, at Turkey Point, three FPL employees (mechanics) falsified information on work orders in January 2019 (see Exhibit No. ___(RAP-4)). In July 2019,

FPSC EXH No. 5
03/18/2024

ADMITTED

C3-131

two FPL Instrumentation and Control (I&C) technicians at Turkey Point deliberately provided incomplete or inaccurate information in maintenance records and the FPL I&C technicians, an FPL I&C Supervisor, and the FPL I&C Department Head deliberately failed to immediately notify the main control room of a mispositioned plant component, as required by plant procedures. The NRC investigation into these three apparent violations resulted in a Notice of Violation and a proposed civil penalty of $150,000 (see Exhibit No. ___(RAP-5)).

The NRC also determined that in the first quarter of 2021, review of Turkey Point performance indicated that unplanned reactor scrams[1] exceed the Unplanned Scrams per 7000 Critical Hours performance indicator, resulting in a performance rating downgrade from green to white (see Exhibit No. ___(RAP-4)).

These events, coupled with decreased headcount and increased outage and derate hours, are a potential indication of a deficient nuclear operations culture at St. Lucie and Turkey Point facilities. FPL's overall effort at reducing operational costs through personnel reductions has the potential to cause stress to be placed on personnel to do more with less. In turn, mistakes can result and lead to avoidable outages and increased, imprudent fuel costs for customers. My review of the cause of plant outages indicates that lower head count may be contributing to lower plant performance. I recommend the Commission disallow fuel cost recovery associated with several derates and outages, in the amount of at least $2, 660,713.

In my testimony I have also taken a more holistic look at the circumstances that may be impacting the ongoing costs of fuel needed to replace the output of the four FPL

[1] As defined and described in Section VII of my testimony.

C3-29

FPSC EXH No. 5
03/18/2024
ADMITTED

nuclear units when they are unavailable. This effort indicates that FPL customers may be paying excessive costs of replacement power in 2022 and 2023. This wider view of FPL's nuclear operations involved an evaluation of factors and operational conditions as mentioned above and discussed below that may be having an ongoing impact on the replacement power costs of FPL that are at issue in the current docket and in the ongoing recovery of fuel costs to be recovered in the future. Because of the continuum of past, current, and future fuels costs, I am recommending that the Commission establish a "spin-off" docket for the purpose of investigating and fully evaluating FPL's nuclear operations as it is impacting fuel costs in general, in addition to making certain disallowances for imprudence on FPL's part in operating their nuclear units. This spin-off docket should review FPL's nuclear operations and at least consider whether they are negatively impacting customers' fuel rates.

III. DESCRIPTION OF FPL NUCLEAR POWER PLANTS

Q. PLEASE PROVIDE A GENERAL DESCRIPTION OF THE PLANT ST. LUCIE NUCLEAR GENERATING STATION.

A. Plant St. Lucie Nuclear Plant ("St. Lucie") has two separate pressurized water reactor ("PWR") nuclear units, capable of a net electrical output of about 981 MW for Unit 1 and 987 MW for Unit 2[2]. The nuclear steam supply system was designed by Combustion Engineering and provide steam to Westinghouse steam turbine-generators. Unit 1 entered commercial operation in December 1976 and Unit 2 entered commercial operation in

[2] This capacity is based on FPL capacity contained in FPL GPIF reports.

FPSC EXH No. 5
03/18/2024
ADMITTED

August 1983. The current Nuclear Operating License for Unit 1 expires in March 2036 and Unit 2's license expires in April 2043.

Q. PLEASE PROVIDE A GENERAL DESCRIPTION OF THE TURKEY POINT NUCLEAR UNITS.

A. Turkey Point has two separate PWR nuclear units, capable of a net electrical output of at least 837 MW for Unit 3 and 821 MW for Unit 4.[3] The nuclear steam supply system was designed by Westinghouse and provides steam to Westinghouse steam turbine-generators. Unit 3 entered commercial operation in December 1972 and Unit 4 entered commercial operation in September 1973. The NRC had initially approved Turkey Point's Nuclear Operating License extension in 2019, but on February 24, 2022 the NRC reversed the extension for further environmental impact review. The current Nuclear Operating Licenses expire in 2032 for Unit 3 and 2033 for Unit 4.

Q. WHAT PLANT OPERATING FACTORS ARE AN INDICATION OF A PLANTS RELIABILITY PERFORMANCE?

A. There are five factors contained in the GPIF reports that FPL files with the Commission that contains indicators of overall plan reliability performance:

1. Equivalent Availability Factor (EAF): The fraction of a given operating period in which a generating unit is available without any outages or equipment deratings.

$$EAF = \frac{Period\ Hours - Sum\ of\ (FOH, PFOH.POH, PPOH)}{Period\ Hours}$$

2. Forced Outage Hours (FOH): Hours in which a plant is in a forced outage.
3. Partial Forced Outage Hours (PFOH): Calculation of equivalent forced outage hours when a plant is forced to derate.

[3] *Ibid.*

FPSC EXH No. 5
03/18/2024
ADMITTED

$$PFOH = \frac{Forced\ Derate\ Hours\ \times Derate\ MW}{Maximum\ MW\ Capacity}$$

4. Effective Forced Outage Rate: Percent of yearly hours plant is in forced outage or forced derate.

5. Planned Outage Hours (POH): This is the number of hours a plant is in a planned outage. Planned outages are usually scheduled well in advance of the outage.

6. Partial Planned Outage Hours (PPOH): Calculation of equivalent planned outage hours when a plant is in a planned derate.

$$PFOH = \frac{Planned\ Derate\ Hours\ \times Derate\ MW}{Maximum\ MW\ Capacity}$$

7. Capacity Factor (CF): The ratio, for the period of time considered, of (a) the electrical energy produced by a generating unit to (b) the electrical energy that could have been produced at continuous full power operation during the same period.

The Generation Performance Incentive Factor ("GPIF") report that FPL files monthly and annually with the Commission combines FOH and PFOH into a single reported metric, as it does for the POH and PPOH. EAF should be calculated using the sum of FOH, PFOH, POH, and PFOH hours.

FPSC EXH No. 5
03/18/2024

ADMITTED

C3-135

Q. PLEASE DESCRIBE THE BASIS FOR COLOR CODING OF THE PERFORMANCE FACTORS IN Tables 1-5 and Exhibit 10.

A. I color coded the plant performance factor to illustrate periods of concern as follows:

EAF Performance Factor	
>95%	
90% - 95%	
85% - 90%	
80% - 85%	
<80%	

EFOR Performance Factor	
<3.0%	
3.0% 5.0%	
>5.0%	

IV. ST. LUCIE OPERATING HISTORY FOR 2019, 2020 AND 2021

Q. HAVE YOU REVIEWED THE OPERATING HISTORY FOR ST. LUCIE, AS IT RELATES TO THE FIVE GPIF PERFORMANCE FACTORS?

A. Yes, I have reviewed the GPIF reports produced by FPL since 2010 relating to St. Lucie.

Q. PLEASE DESCRIBE THE OPERATING HISTORY OF THE ST. LUCIE UNIT 1 OVER THE 2017 – 2021 PERIOD.

A. Table 1 presents the GPIF Report five performance factors for St. Lucie Unit 1 for the period of 2017 – 2021. The data in the table indicates St. Lucie Unit 1's 2019 plant performance was poor, and below average in 2021. The poor performance in 2019 was due to a generator ground fault in April 2019 which resulted in 1,360 forced outage hours and a reactor coolant pump ground fault in September 2019 which resulted in 351 forced outage

LINE	St. Lucie 1	2017	2018	2019	2020	2021
1	EAF	97.4%	90.8%	70.1%	99.8%	88.6%
2	FOH + PFOH	246.7	74.5	1,810.1	12.8	153.7
3	EFOR %	2.8%	0.9%	20.7%	0.1%	1.8%
4	POH + PPOH	8.6	809.4	888.2	6.3	840.8
5	Capacity Factor	99.1%	92.2%	71.3%	101.3%	89.8%

Table 1 - St. Lucie Unit 1 Performance Factors

FPSC EXH No. 5
03/18/2024

ADMITTED

hours. The below average performance in 2021 was due to a spring refueling outage which lasted 816 hours, 93.5 hours more than originally planned.

Q. HOW DOES ST. LUCIE UNIT 2'S PERFORMANCE COMPARE TO THAT OF UNIT 1 OVER THE 2017 – 2021 PERIOD?

A. Table 2 presents the GPIF report five performance factors for St Lucie Unit 2 on the same basis for the period of 2017 - 2019. St Lucie Unit 2 had below average performance in

LINE	St. Lucie 2	2017	2018	2019	2020	2021
1	EAF	89.7%	87.8%	100.0%	91.1%	89.5%
2	FOH + PFOH	110.2	252.2	-	60.0	90.6
3	EFOR %	1.3%	2.9%	0.0%	0.7%	1.0%
4	POH + PPOH	884.5	873.5	0.7	721.3	827.2
5	Capacity Factor	91.7%	88.6%	102.7%	93.2%	91.5%

Table 2 - St Lucie Unit 2 Performance Factors

2017 due to planned maintenance and a turbine control system fault. The below average performance in 2018 was due to an extended planned refueling maintenance outage which totaled about 930 hours between the planned and forced portions of the outage and a forced outage due to a 6.9 kV bus fault which lasted approximately 140 hours. The below average performance in 2021 was due to an 830 hour refueling maintenance outage that was extended at derated load for 46.1 hours more than originally planned. As compared to Unit 1, Unit 2's overall performance was better than Unit 1's for that same period.

FPSC EXH No. 5
03/18/2024

ADMITTED

C3-137

V. TURKEY POINT OPERATING HISTORY FOR 2019, 2020 AND 2021

Q. HAVE YOU REVIEWED THE OPERATING HISTORY FOR TURKEY POINT'S NUCLEAR UNITS, AS IT RELATES TO THE FIVE GPIF PERFORMANCE FACTORS?

A. Yes, I have reviewed the GPIF reports produced by FPL since 2010 related to the nuclear units at Turkey Point.

Q. PLEASE DESCRIBE THE OPERATING HISTORY OF THE TURKEY POINT UNIT 3 OVER THE 2017 – 2021 PERIOD.

A. Table 3 presents the GPIF report five performance factors for Turkey Point Unit 3 for the period of 2017 - 2019. Turkey Point Unit 3's performance factors were below average in

LINE	Turkey Point 3	2017	2018	2019	2020	2021
1	EAF	85.2%	88.6%	99.1%	85.3%	84.0%
2	FOH + PFOH	407.6	1.6	84.5	535.2	658.3
3	EFOR %	4.7%	0.0%	1.0%	6.1%	7.5%
4	POH + PPOH	906.2	1,001.0	-	681.8	743.9
5	Capacity Factor	86.9%	90.6%	102.8%	89.3%	86.3%

Table 3 -- Turkey Point Unit 3 Performance Factors

2017 and 2018 based on EAF, and poor in 2020 and 2021 due to the high forced outage rate. In 2017, Turkey Point had three forced outages near or over 100 hours (totaling almost 400 hours), two of which were caused by reactor coolant pump problems and one was associated with a 4 kV buss failure. In 2018, a longer than normal refueling outage of 949 hours caused the lower EAF. In 2020, the Unit experienced three forced outages and eight (8) significant separate plant derates which caused an excessive forced outage rate and 535.2 equivalent forced outage hours. In 2021, Turkey Point Unit 3 had two forced outages, including the over 300-plus hour refueling outage extension, that was 328.4 hours beyond

C3-35

FPSC EXH No. 5
03/18/2024

ADMITTED

C3-138

the planned outage duration and six (6) plant derates, which caused an excessive forced outage rate.

Q. HOW DOES TURKEY POINT UNIT 4'S PERFORMANCE COMPARE TO THAT OF UNIT 3 OVER THE 2017 – 2021 PERIOD, AS IT RELATES TO THE FIVE GPIF PERFORMANCE FACTORS?

A. Table 4 presents the GPIF five performance factors for St Lucie Unit 2 on the same basis for the period of 2017 - 2019. Turkey Point Unit 4's performance factors were below

LINE	Turkey Point 4	2017	2018	2019	2020	2021
1	EAF	89.5%	99.6%	90.6%	83.0%	99.5%
2	FOH + PFOH	213.4	3.1	10.0	494.2	49.2
3	EFOR %	2.4%	0.0%	0.1%	5.6%	0.6%
4	POH + PPOH	705.7	28.1	815.5	1,001.2	-
5	Capacity Factor	91.2%	101.4%	91.9%	84.3%	102.7%

Table 4 - Turkey Point Unit 4 Performance Factors

average in 2017 and poor in 2020. In 2017, a 141-hour forced outage due to flow control valve failure, a planned maintenance outage and several derates contributed to the low EAF. In 2020, a 365 equivalent hour forced outage due the exciter failure, a 130 hour forced outage due to extension of a maintenance outage, and four plant derates contributed to below average EAF and an excessive outage rate.

Q. YOU HAVE MENTIONED HEAD COUNT REDUCTIONS AT THE ST. LUCIE AND TURKEY POINT NUCLEAR PLANT SITES. CAN YOU GIVE A BRIEF EXPLANATION WHY YOU ARE PROVIDING TESTIMONY ON THIS ASPECT OF THE FPL OPERATIONS?

A. Yes. As I was evaluating the outages and reviewing the documentation provided by FPL (and available from the NRC), I became concerned that industry cost trends, market forces and other corporate culture issues could be driving the company to cut costs in its nuclear

FPSC EXH No. 5
03/18/2024
ADMITTED

operations in a way that could impact customer fuel rates. For this reason, I sought to understand whether staffing levels had changed, and I asked the OPC to serve discovery in this area.

VI. ST. LUCIE AND TURKEY POINT PERSONNEL REDUCTIONS

Q. WHAT HAVE YOU LEARNED ABOUT CHANGES FPL HAS MADE IN PERSONNEL HEAD COUNT SINCE 2017 AT ST. LUCIE?

A. In January 2017, the St. Lucie station's (encompassing Units 1 & 2) actual head count for that month was 636, and its budgeted head count was 649. Based on data provided by FPL in response to OPC's Interrogatory Nos. 39 and 40, Attachment 1 (Exhibit No. ___(RAP 7)), St. Lucie's head count had fallen to 458 by the end of 2021 and the budgeted head count had fallen to 489. This represents a 28.9% reduction in actual head count and a 24.7% reduction in budgeted head count. St. Lucie has experienced a reduction of 178 people




Figure 1- St. Lucie Head Count

FPSC EXH No. 5
03/18/2024

ADMITTED

C3-140

since 2017 and FPL has dropped the budgeted headcount by 160 people. Considering this is a two-unit plant, there are currently only an average of 229 people per unit on site or available to the unit. Figure 1 presents a graph of the monthly changes in St. Lucie' actual and budgeted headcount since 2017.

Q. WHAT HAVE YOU LEARNED ABOUT CHANGES FPL HAS MADE IN PERSONNEL HEAD COUNT SINCE 2017 AT TURKEY POINT?

A. In January 2017, the Turkey Point nuclear plant (encompassing both Units (3 &4), actual head count for that month was 613, and its budgeted head count was 644. Based on data provided by FPL in response to OPC's Interrogatory Nos. 37 and 38, Attachment 1 (Exhibit No. ___(RAP 7)), Turkey Point's head count had fallen to 476 by the end of 2021 and the budgeted head count had fallen to 485. This represents a 22.3% reduction in actual head count and a




Figure 2- Turkey Point Head Count

25.2% reduction in budgeted head count. Turkey Point has experienced a reduction of 137 people since January 2017 and FPL has dropped the budgeted headcount by 163 people.

FPSC EXH No. 5
03/18/2024
ADMITTED

Considering this is a two-unit plant, there are currently only an average of 238 people per unit on site or available to the unit. Figure 2 presents a graph of the monthly changes in Turkey Point's actual and budgeted headcount since 2017.

VII. NRC INVESTIGATIONS

Q. YOU HAVE MENTIONED INSTANCES OF NRC INVESTIGATIONS AND CIVIL PENALTIES RELATED TO THE FPL OPERATIONS AT ST. LUCIE AND TURKEY POINT. CAN YOU BRIEFLY EXPLAIN WHY YOU HAVE PROVIDED TESTIMONY ON THIS ASPECT OF FPL'S NUCLEAR OPERATIONS?

A. Yes. As a part of my inquiry in this case, I looked at the evidence of outages over recent years and also evaluated staffing levels as indicated above. I believe that, in addition to these aspects of the operations, an important indicator of the prudence of the operations of the organization is how the company is viewed by the safety regulator who has special insight into the operations based on its access to the nuclear plants and its role in protecting the safety of Americans, its presence on-site, and its access to all aspects of FPL's nuclear operations. For this reason, I reviewed the recent history of NRC inspections and violation findings at the four plant sites. I present a summary of this review below as it bears on the recent past, the present and the future of fuel costs borne by FPL customers.

FPSC EXH No. 5
03/18/2024

ADMITTED

C3-142

Q. PLEASE DESCRIBE THE MARCH 13, 2017 INCIDENT THAT LED TO THE NRC ISSUING THE SEPTEMBER 12, 2019 NOTICE OF VIOLATION AND IMPOSITION OF A $232,000 CIVIL PENALTY (EXHIBIT NO. ___(RAP-4)).

A. On March 13, 2017, an employee of FPL contractor Framatome (formerly known as AREVA) submitted a condition report to FPL management, documenting concerns with the requirement for Framatome personnel to wear multiple dosimeters while performing refueling work. Framatome was a contractor to FPL for refueling work at both the St. Lucie and Turkey Point. The contract employee was a lead supervisor for Framatome's refueling team at St. Lucie, and had been pre-scheduled by Framatome and FPL to transfer to Turkey Point for the same role. On March 16, 2017, the contract employee's re-assignment to Turkey Point was canceled due to actions by FPL's Regional Vice President (VP) – Operations. The NRC determined that the cancellation of the contract employee's work assignment for raising a nuclear safety concern via the submission of a condition report was a violation of 10 C.F.R. § 50.7 (See Exhibit No. ___ (RAP-4), page 2, first paragraph).

The U.S. Nuclear Regulatory Commission (NRC) Office of Investigations (OI) documented that FPL's Regional VP - Operations sent an e-mail to the Framatome VP of Outage Services on March 14, 2017, and in subsequent discussions, requested cancelation of the employee's Turkey Point assignment. The NRC investigation found the FPL Regional Vice President - Operations deliberately discriminated against a Framatome contract employee for engaging in a protected activity in March of 2017. In addition, evidence was found that a former FPL Corporate Support Vice President, whose previous position was FPL Regional VP-Operations (discussed above), deliberately provided

C3-40

FPSC EXH No. 5
03/18/2024
ADMITTED

incomplete and inaccurate information to FPL that was subsequently submitted by FPL to the NRC.

The NRC determined this was a Severity Level II violation of 10 C.F.R. §.50.7 and imposed the $232,000 civil penalty on FPL. As a result of this instance, FPL agreed to perform the following corrective actions:

1. Establish an Employee Concerns Program (ECP) investigation and Safety Conscious Work Environment ("SCWE") surveys in St. Lucie and Turkey Point radiation protection departments, and training of senior nuclear managers.
2. Conduct a nuclear fleet-wide communication that reinforced the SCWE policy.
3. Conduct personnel training, ECP third-party audits, and create a personnel action review board to review certain employment actions involving contractor personnel brought to FPL's attention.

Q. ARE YOU AWARE OF THE TURKEY POINT UNIT 3 OUTAGES THAT OCCURRED IN AUGUST 2020 FOR WHICH FPL IS NOT SEEKING COST RECOVERY?

A. Yes. I am aware of this situation, but FPL has blocked me from reviewing their records containing details of these events and from understanding the basis for their decision to exclude the replacement power costs from recovery in the Fuel Clause docket.[4] I have included in my testimony information related to these events from the publicly available

[4] See, FPL's April 2, 2022 *Petition for Approval of Fuel Cost Recovery and Capacity Cost Recovery Net Final True-Ups for the Period Ending December 2021 and 2021 Asset Optimization Incentive Mechanism Results*, Docket No. 2022001-EI.

FPSC EXH No. 5
03/18/2024

ADMITTED

files of the NRC, but I have not been able to determine the reasons why FPL is not asking the Commission to include these costs for recovery. I would note that the Company included a brief description of certain of the events in the September 3, 2020 testimony of Robert Coffey, Vice President, Nuclear in the FPL Nuclear Business Unit in Docket 20200001-EI. In conjunction with his testimony supporting the recovery of all 2020 fuel costs, Mr. Coffey testified at TR 409 this way:

> In March 2020, St. Lucie Unit 2 experienced a delay in return to service following the refueling outage associated with the planned replacement of a 6900 volt electrical switchgear required for plant operation; in July 2020, Turkey Point Unit 4 shut down due to a main generator lock out from a loss of exciter and in August 2020, Turkey Point Unit 3 shut down in response to rising steam generator levels. ***FPL's response to each unplanned outage was appropriate and efficient, and the units were returned to service safely.***

(Emphasis added.) In the 2020 Fuel Clause hearing, FPL lumped several outages together in this testimony and described to the Commission under oath that their response to the outages were appropriate and efficient. After FPL tried to block OPC counsel from inquiring about the outages (TR 506, lines 12-15), the Commission allowed some very limited explanation of related matters. TR 507-520; 526-527. These outage prudence determinations were deferred from the 2021 fuel cycle hearings into this current round. The exciter-related outage described above is contested in this case, while FPL has indicated that it wants to refund the replacement power costs it was allowed to collect while avoiding oversight of the reasons for the proposed refund.

FPSC EXH No. 5
03/18/2024

ADMITTED

Q. IF FPL IS NOT SEEKING RECOVERY OF REPLACEMENT POWER COSTS, THEN WHY DO YOU NEED TO SEE THE INFORMATION?

A. The customers and the Commission should have an understanding about FPL's decision-making with regard to what fuel costs they submit for recovery as being prudent. One would assume that, given its duty to its shareholders, FPL has an obligation to recover in the ratemaking process all costs that are reasonably and prudently incurred. FPL originally took steps to recover these costs in 2020 and now appears to be trying to evade regulatory oversight by refunding the money. The company refuses to state why it no longer seeks recovery for these replacement power costs; whether because they were incurred due to some imprudent action or decision-making by the company or because the company received cost reimbursement from a vendor or an insurance company (Exhibit No. ___(RAP-3)). The customers and the Commission should be allowed to inquire as to the circumstances of any imprudence in FPL's actions or decision-making for any one of several reasons. If actions occurred associated with these events are indicative of a pattern of activity within the FPL nuclear organization that is related to staffing levels or to the corporate culture that has been at issue in recent NRC violation notices, those facts are also relevant to this case. Likewise, if the actions related to these events are similar to other events at issue and discussed in my testimony, then it begs the question as to why the related replacement costs for any one event are to not be recovered while all other replacement power costs related to the outages I have discussed continue to be sought in the Fuel Clause. Said a different way, what if the facts that prompted FPL ***not*** to seek recovery are the same or similar to factual scenarios under which FPL is seeking recovery for other incidents? Additionally, if there is third party cost reimbursement, the customers

FPSC EXH No. 5
03/18/2024
ADMITTED

and Commission are entitled to know the circumstances so that the parties can understand whether FPL is properly and prudently pursuing recovery from third parties in all instances where vendors or an insurance company may be obligated to compensate FPL; and if not, why not?

Q. WHAT DO YOU RECOMMEND WITH REGARD TO THESE EVENTS?

A. Given that I have not seen the information, I reserve the right to provide supplemental testimony that addresses any relevant issues related to these events. Furthermore, to the extent that discovery of information related to these events has a bearing on any aspect of my testimony – including any contrasts with contested claims of prudent replacement power cost – the Commission should allow the record to be reopened in a future proceeding, including but not limited to any spin-off investigation docket.

Q. PLEASE DESCRIBE THE INCIDENTS THAT LED TO THE NRC ISSUING THE APRIL 6, 2021 NOTICE OF VIOLATION AND IMPOSITION OF A $150,000 CIVIL PENALTY (EXHIBIT NO. ___(RAP-5)).

A. On April 6, 2021 the NRC issued a Notice of Violation and Civil Penalty related to three instances where FPL employees at Turkey Point falsified information, and/or provided inaccurate or incomplete information in maintenance records. The first incident occurred on July 10, 2019 when FPL mechanics falsified maintenance records on a work order, falsely stating maintenance activities associated with a *safety-related* check valve had been completed. They also recorded inaccurate information on the status of tools that were required (but not used) for conducting the maintenance work (that was not actually performed). The FPL employees also recorded inaccurate measurements using falsified values, copied from a prior actual performance of the work.

FPSC EXH No. 5
03/18/2024
ADMITTED

A second and third incident occurred on November 10, 2021, in which FPL I&C technicians, an FPL I&C Supervisor, and the FPL I&C Department Head deliberately failed to immediately notify the main control room of a mispositioned plant component, as required by plant procedures. These two incidents involved failure to comply with plant procedures to notify the control room of a mispositioned component and failure to maintain accurate and complete maintenance records. The NRC determined that all three incidents involved deliberate misconduct by FPL employees, which was a Severity Level III violation and assessed a $150,000 civil penalty on FPL.

Q. PLEASE DESCRIBE THE REASONS FOR THE NRC TO DOWNGRADE TURKEY POINT UNIT 3's PERFORMANCE INDICATOR FROM GREEN TO WHITE IN MAY 2021 (SEE EXHIBIT NO.___(RAP-6)).

A. As part of the NRC's Reactor Oversight Process, the agency monitors the number of unplanned scrams per 7,000 hours of operation. An unplanned scram is an emergency shutdown of the nuclear reactor by rapid insertion of the control rods that will initiate termination of the fission process in the reactor. It is also known as a reactor trip. An unplanned reactor scram puts the reactor safety systems under additional stress because of the rapid change in plant stability and the various systems that need to respond to plant transients. The NRC uses the categories shown in Table 5 to define plant performance level associated with the unplanned scrams per 7,000 hours:

Performance Indicator	Unplanned Scrams per 7,000 Hours
Green	≤ 3 Scrams
White	4-6 Scrams
Yellow	7-25 Scrams
Red	>25 Scrams

Table 5 - NRC Unplanned Scrams Performance Indicators

FPSC EXH No. 5
03/18/2024
ADMITTED

The NRC downgraded Turkey point Unit 3's Unplanned scrams in a 7,000 Critical Hours performance indicator to white due to four unplanned scrams between August 2020 and March 2021.

Q. WHAT IS THE SIGNIFICANCE OF THIS DOWNGRADE?

A. The NRC uses the measurement of the number of Unplanned Scrams in a 7,000 Critical Hours performance indicator to flag nuclear plants which may be having operational problems. An unplanned reactor scram results in very rapid changes in the nuclear plant operating conditions and forces the plant nuclear safety systems to respond to those operating condition changes in a short period. In addition to the extra cost of replacement power during the outage triggered by the event, the more frequently a nuclear plant unplanned scram occurs, the higher the potential for a safety component or system to fail, causing additional problems, including exposing customers to higher fuel costs in the future. An example of problems that can occur during an unplanned scram occurred at the Browns Ferry Nuclear plant in 1980 when 40% of the control rods failed to fully insert into the reactor core. In that situation, two additional scrams were required to fully insert the control rods.[5]

Q. PLEASE DESCRIBE THE FIRST OF THE FOUR UNPLANNED REACTOR SCRAM EVENTS THAT OCCURRED BETWEEN AUGUST 2020 AND MARCH 2021.

A. The first event occurred on August 17, 2020, and was a manual trip by plant operators due to rising steam generator levels that were approaching the automatic turbine trip setpoint. The cause was an inadvertent opening of a low-pressure heater bypass valve in response to

[5] AEOD/C001, "Report on the Browns Ferry 3 Partial Failure to Scram Event on June 28, 1980," Office for Analysis and Evaluation of Operational Data, U.S. Nuclear Regulatory Commission, July 30, 1980. [8008140575]

FPSC EXH No. 5
03/18/2024
ADMITTED

low-pressure at the suction of the steam generator feedwater pump (SGFP). Investigation by FPL found a design modification in 2012 had not included this scenario in the turbine control system design analysis. Because I have been blocked from accessing and independently reviewing the FPL internal documents related to this event, I am unable to determine the nature of any human element (FPL employee or contractor) related to the prudence of this event as it relates to or affects the recovery of fuel costs.

Q. PLEASE DESCRIBE THE SECOND OF THE FOUR UNPLANNED REACTOR SCRAM EVENTS THAT OCCURRED BETWEEN AUGUST 2020 AND MARCH 2021.

A. The second event occurred on August 19, 2020 (two days after the first event), and was an automatic trip by the plant plant's reactor protection system during startup, caused by high neutron flux condition in the reactor. According to the NRC, *FPL's own root cause evaluation determined this was operator error committed by an FPL employee.* The FPL unit supervisor and FPL reactor plant operators were determined to have had knowledge gaps in conducting reactor startup operations. As a result of the discovery of knowledge gaps among its employees, FPL had to make procedural and training material changes for plant operators and supervisors. Because I have been blocked from accessing and independently reviewing the FPL internal documents related to this event, I am unable to fully formulate an opinion about this event as it relates to the prudence of FPL's culture, workforce staffing or other aspects of prudence as it relates to or affects the recovery of fuel costs.

FPSC EXH No. 5
03/18/2024

ADMITTED

C3-150

Q. PLEASE DESCRIBE THE THIRD OF THE FOUR UNPLANNED REACTOR SCRAM EVENTS THAT OCCURRED BETWEEN AUGUST 2020 AND MARCH 2021.

A. The third event that occurred on August 20, 2020, the day after the second event occurred, was caused by improper valve alignment of the pump suction flow control valve and failure to place the recirculation to condenser control valves in automatic. According to the NRC, *FPL's own root cause evaluation determined this was operator error committed by an FPL employee.* FPL operators had not properly moved the master controller for the Turkey Point Unit 3 SGFP recirculation valve(s) to the appropriate position for the plant conditions. FPL operators attempted to adjust these recirculation valves after discovering the error, causing low suction pressure on the SGFP. The RCA investigation determined that the FPL operators had failed to properly review valve alignment and status of all components following an unplanned reactor scram. As a result of the discovery of the FPL employee errors, FPL had to implement procedural and training changes to prevent this event from recurring. Because I have been blocked from accessing and independently reviewing the FPL internal documents related to this event, I am unable to fully formulate and opinion about this event as it relates to the prudence of FPL's culture, workforce staffing or other aspects of prudence as it relates to or affects the recovery of fuel costs.

Q. PLEASE DESCRIBE THE FOURTH OF THE FOUR UNPLANNED REACTOR SCRAM EVENTS THAT OCCURRED BETWEEN AUGUST 2020 AND MARCH 2021.

A. The fourth event occurred on March 1, 2021, following testing of the Reactor Protection System. The restoration included reactor operators closing the reactor trip breaker and

C3-48

FPSC EXH No. 5
03/18/2024
ADMITTED

opening the bypass breaker. Apparently, the reactor breaker was actually opened but the switch indicated it was closed. This event is described in FPL Witness Dean Curtland's testimony, starting on page 8, line 10. FPL found graphite grease had hardened and may have prevented the switch from properly indicating the proper position of the reactor trip breaker.

Q. PLEASE DESCRIBE THE NRC'S FINDINGS FROM THE MARCH 1, 2019 PROBLEM IDENTIFICATION AND RESOLUTION INSPECTION AT TURKEY POINT UNITS 3 AND 4 (Exhibit No. ___(RAP-8)).

A. The NRC identified two findings associated with safety related valve testing in which FPL plant personnel were not performing testing in accordance with proper procedure and had not complied with American Society of Mechanical Engineers (ASME)" Operation and Maintenance of Nuclear Power Plants" (OM) Code[6] and FPL's in-service test (IST) program.[7] The first NRC finding involved surveillance testing in which safety-related check valves were preconditioned by FPL plant personnel following the valves failing the initial test and prior to the retest. The plant's IST 0-ADM 502 Section 5.1.1, item 11, states in part: "Preconditioning pumps and valves in the IST program shall be avoided. Preconditioning is the alteration, manipulation, or adjustment of the physical condition of an SSC before In-Service Testing for the expressed purpose of returning acceptable test results and masking action As Found conditions." The purpose of in-service testing of safety valves is to determine how the valves would perform during normal operation.

[6] ASME OM Code, *"Operation and Maintenance of Nuclear Power Plants,"2020.* Establishes the requirements for preservice and in-service testing and examination of certain components to assess their operational readiness in light-water reactor power plants.
[7] FPL IST Program, 0-ADM-502.

FPSC EXH No. 5
03/18/2024
ADMITTED

Preconditioning should not be done prior to the first performance test or immediately repeated retests.

The preconditioning that was prohibited in this case involved a procedure in which plant personnel would manipulate the valve in some manner to prepare it for the test procedure that could have the effect – whether intended or not – of "helping" the valve pass the test. In the October 14, 2018 incident, two check valves failed their leak test. The plant personnel preconditioned the valve for the follow-up test by applying additional force by rapping the valve with a brass hammer. This application of force invalidated the test because the valve was no longer in "as found condition or normal operating condition." The operators should have retested the valve without preconditioning and if the valve still did not pass the leak rate test, they should have identified the problem in the testing report and identified the need for further action to inspect, perform maintenance, and/or repair the valve. This preconditioning by FPL employee(s) was a violation of ASME ON Code and FPL IST procedure.

The second NRC finding was that the FPL plant personnel failed to declare the check valves "inoperable" after failure of the IST tests. The NRC also found FPL plant personnel had, dating back to 2010, been involved in other instances of these procedures violations and of notifications not being followed.

Q. PLEASE DESCRIBE THE NRC'S FINDINGS FROM THE FEBRUARY 11, 2021 INTEGRATED INSPECTION REPORT AT TURKEY POINT UNITS 3 AND 4 (Exhibit No. ___(RAP-9)).

A. The NRC identified an incident on September 26, 2020 in which FPL personnel failed to follow FPL procedure MA-AA-100-1002, "*Scaffold Installation,*

FPSC EXH No. 5
03/18/2024
ADMITTED

Modification, and Removal Requests," by erecting scaffolding that could interfere with operation of plant components. During the testing of a motor operated valve for the containment sump isolation valve, the valve steam position indicator impacted the scaffolding, causing damage to the valve and making the valve inoperable. This made the residual heat removal system (RHR) inoperable and caused Unit 4 control room operators to enter a 72-hour shutdown action statement (notice of potential shutdown) because the RHR is a safety-related system used for removing heat from containment in the event of an accident and because the RHR valve is a pressure boundary valve for containment. Upon investigation, FPL found that maintenance personnel had not properly walked down the location of scaffolding to verify that the scaffolding, upon completion of assembly, would not interfere with equipment operation. In addition, the scaffolding installation team had not discussed with operations personnel the potential for interaction of the scaffolding with plant equipment.

VIII ASSESSMENT OF ST. LUCIE AND TURKEY POINT OPERATIONS

Q. WHAT ARE YOUR CONCERNS WITH THE INFORMATION YOU HAVE THUS FAR PRESENTED IN YOUR TESTIMONY?

A. Review of the various plant performance parameters, headcount history, NRC findings, and outages present areas of concern regarding FPL's plant operations. The St. Lucie units have been in operation for over 39 years and Turkey Point units have been in operation for over 49 years. The sequence of reactor unplanned scrams in August of 2020 appears to be an indication of deficient training, inadequate staffing, and potential lack of experience

FPSC EXH No. 5
03/18/2024
ADMITTED

among plant personnel. The past evidence of falsification of maintenance records and of FPL managers taking punitive actions against a contractor, although assumedly addressed, raise concerns that they could be indicators of potential cultural issues emanating from cost pressures in a way that can impact plant operations and performance. Any one of these items in isolation may not necessarily constitute an indication of bigger issues. However, when aggregated and evaluated against the backdrop of a significant reduction in headcount at both plants, as well as recent NRC findings, agreed-violations and a downgrade from "green" to "white" for a period of time, these factors may point toward employees' workload increases resulting in lower performance and more errors. Reduction in plant headcount of more than 20% without corresponding reduction in workload, raises concerns with how the work is being accomplished.

FPSC EXH No. 5
03/18/2024

ADMITTED

C3-155

Q. WHAT EVIDENCE CAN YOU PROVIDE TO SUPPORT YOUR CONCERNS?

A. In addition to the NRC reports cited earlier, review of St. Lucie and Turkey Point GPIF reports contains some indication that in recent years, plant performance has degraded. Exhibit No. ___(RAP-10), provides the five performance indicators discussed earlier, for St. Lucie and Turkey Point for the 11-year period of 2010 – 2021. The data shows that between 2010 and 2016, overall on average plant EAF and EFOR indicated some improvement. Figure 3 provides a graph of the average EAF and EFOR for all four of FPL's nuclear units. The data shows that starting in 2016, average EAF and EFOR




Figure 3 - Average Nuclear Plant EAF and EFOR

improved significantly, peaking in 2018. Since 2018, average EAF and EFOR have declined. This degradation generally corresponds with FPL's headcount reduction shown in Figures 1 and 2, assuming some lagging effect as the reductions were implemented. The data in Exhibit No. ___(RAP-10) shows that Turkey Point Unit 3 EAF and EFOR for 2020

C3-53

FPSC EXH No. 5
03/18/2024
ADMITTED

and 2021 were the worst since about 2014, which again generally corresponds with FPL's headcount reduction.

Q. WHAT COULD BE THE IMPACT ON PLANT OPERATIONS PERSONNEL BEING REQUIRED TO PERFORM THEIR TASKS WITH LESS OVERALL STAFFING RESOURCES?

A. A situation of overworked personnel in a nuclear plant environment has the potential to contribute to more frequent plant forced outages, derates, and extension of maintenance outages due to personnel errors, failure to notice equipment problems, lack of observance in performing tasks, insufficient time to assess plant operations and tasks, insufficient planning, inopportune unavailability of staff to perform critical tasks and other issues. Increased outages and derates have the potential to create large scale forced outage durations, multiple smaller forced outage durations or a combination of both types of outages. These circumstances can result in noticeable and readily identifiable instances of higher replacement power costs or smaller and less noticeable or material replacement power costs that can nevertheless have a cumulative effect on the fuel costs borne by customers. All of these can impact the fuel costs that customers incur in the rates to be set in this hearing.

Q. WHAT RECOMMENDATION DO YOU HAVE FOR THE COMMISSION TO ADDRESS THIS ISSUE?

A. First, an investigation and independent assessment of FPL nuclear operations may be a valuable option if FPL has not had an independent assessment recently. I recommend that the Commission initiate such an investigation. An independent evaluation can assess personnel performance and determine if personnel cuts have resulted in workforce

FPSC EXH No. 5
03/18/2024
ADMITTED

performance degradation due to stresses and overwork. Performing an independent assessment can provide valuable insight into operations and personnel tweaks that could help avoid future problems. I have been involved in similar assessments which resulted in identifying important changes which improved moral, performance, and personnel integrity, and, ultimately, safety.

A second recommendation is for the Commission to establish a spin-off proceeding to perform an in-depth evaluation of the FPL headcount reductions' impact on nuclear operations and ratepayer-borne fuel cost impacts since 2016 and into the future.

IX ASSESSMENT OF OUTAGES AND DERATES IMPACT ON REPLACEMENT POWER COSTS

Q. PLEASE DESCRIBE THE EVENTS OF JULY 5, 2020 AT TURKEY POINT UNIT 4 THAT LED TO THE AUTOMATIC SHUTDOWN DUE TO MAIN GENERATOR LOCKOUT AND TURBINE TRIP.

A. During heavy thunderstorm, several alarms occurred involving the generator and exciter monitoring systems. The generator reactive load was observed to be oscillating between 115 MVAR and 200 MVAR, and the exciter field voltage was also found to be oscillating. The reactor then tripped due to a main generator lockout. The Main Generator Lockout was caused by the actuation of the Voltage Regulator Lockout relay due to loss of the Voltage Regulator Power Supplies #1 & #2 (and thus loss of excitation). FPL then initiated a failure investigation process and developed actions to identify, inspect and test any component that could have been affected by the failure of the PMG stator. The investigation team

FPSC EXH No. 5
03/18/2024
ADMITTED

determined the unit trip was caused by failure of the generator exciter permanent magnet generator (PMG).

Q. PLEASE DESCRIBE A GENERATOR EXCITER, ITS FUNCTION IN POWER PRODUCTION, AND THE PURPOSE OF THE PMG.

A. The generator exciter creates a DC current by rotating the PMG inside of exciter windings (wire coil). This DC current is fed to the rotor of the synchronous generator to create a magnetic field which is rotated inside the generaor to create electricity. The exciter is connected to the generator shaft. The exciter PMG is what initiates the process of energizing the generator for production of electricity. Without the exciter, the generator is a rotating mass and cannot produce power because there is no magnetic field.

Q. DID FPL CONDUCT A ROOT CAUSE EVALUATION (RCE) FOR THIS EVENT?




Figure 4 - Generator Exciter Configuration

A. Yes. Exhibit No. ___ (RAP-11) is a copy of the Turkey Point Nuclear Unit 4 Reactor Trip Due to Gen Lockout from Loss of Exciter Root Cause Evaluation (RCE).

FPSC EXH No. 5
03/18/2024

ADMITTED

C3-159

Q. WHAT DID FPL's INVESTIGATION TEAM DETERMINE TO BE THE CAUSE OF THE EXCITER FAILURE?

A. Upon disassembly of the exciter, the investigation revealed water intrusion and found that the PMG was damaged. The root cause team found the failure of the PMG was likely due to a culmination of age-related breakdown of the PMG stator winding insulation, along with water intrusion due to inadequate sealing of the Exciter housing. The RCE claims the overall root casue to be weakness in the Exciter PM program resulted from a failure to fully assess risk of PMG stator winding age, thus making it more susceptible to failure when exposed to water/moisture. Contibuting factors to the failure were found by FPL to inlcude:

1. SCC #1) Weakness in Exciter PM Program based on existing Original Equipment Manufacturer ("OEM") and Industry recommendations which were CONDITION BASED, and did not require TIME-BASED PMG stator rewind, thereby increasing susceptibility to failure from other stressors.
2. SCC #2) OEM procedure 3.2.2.1 did not include site specific weather sealing requirements based on OEM specifications.

Q. WHAT WAS DETERMINED TO BE THE CAUSE OF THE WATER INTRUSION INTO THE EXCITER?

A. The first occurrence of water intrusion into the Exciter occurred in 2001 which led to a ground fault in the exciter. This event resulted in FPL installing additional weather seals on the exciter. While FPL did modify the Maintenance Support Package for the exciter to incorporate the new seals and inspection, it failed to incorporate the seals requirement into the OEM procedures. During event investigation, it was found that water had accumulated

C3-57

FPSC EXH No. 5
03/18/2024
ADMITTED

inside the PMG and pedestal bolt holes. The following degradation of seals were also discovered:

1. The partition seal between the AC Exciter compartment and PMG compartment.
2. Housing floor gaskets which were found dislodged in sections around the perimeter of the PMG compartment.
3. The site-specific vertical foam weather seal designed under MSP 02-055 and required in site procedure 0-GMM-090.1 was not installed.

As a result, the investigation team determined the most probable path of water ingress was through the missing vertical foam seal and the degraded and dislodged floor gaskets. ***The RCE concluded that the failure of the PMG stator was due to insulation degradation coupled with additional stressors; water intrusion being the likely cause.***

Q. DID ANY FPL ACTIVITIES CONTRIBUTE TO THE EXCITER FAILURE OR COULD THE EXCITER PROBLEM BEEN FOUND PRIOR TO FAILURE?

A. Yes. FPL was aware of the potential for water intrusion into the Exciter based on the 2001 event. FPL personnel had not properly installed seals which contributed to water intrusion. In addition, FPL failed to inspect the seals during periodic exciter inspections to ensure they performed their intended function to keep water out. The Turkey Point steam turbines, generators and exciters are located outdoors and exposed to the ambient weather conditions. Prudent utility maintenance requires that seals required to maintain equipment and prevent water intrusion need to be inspected on a regular basis. FPL did not adhere to this standard.

FPSC EXH No. 5
03/18/2024

ADMITTED

C3-161

Q. WHAT WAS THE AMOUNT OF REPLACEMENT POWER COSTS FOR THE OUTAGE?

A. According FPL response to Staff Interrogatory No. 4 (Exhibit No. ___(RAP-12)), the replacement power cost for the outage from the July 2020 of Turkey Point Unit No. 4 was $1,453,970.[8] I am accepting these calculations for the purposes of my testimony at this time even though I do not agree they are necessarily calculated correctly. At this point, it is my opinion that the calculation of the replacement power costs related to specific outages caused by imprudent action or decision-making of FPL should be based on the incremental or "but for" costs of generation, fuel or purchases. FPL should be required to calculate replacement power costs on this basis and the refunds or credits to customers should be ordered by the Commission accordingly.

Q. WHAT IS YOUR RECOMMENDATION ON FPL RECOVERY OF THOSE REPLACEMENT POWER COSTS?

A. It is my recommendation that the Commission disallow recovery of the $1,453,970 in replacement power costs associated with the outage caused by the exciter failure because the event was preventable.

Q. PLEASE DESCRIBE THE EVENTS OF MARCH 1, 2021 AT TURKEY POINT UNIT 3 WHICH RESULTED IN AN UNPLANNED AUTOMATIC REACTOR TRIP.

A. Turkey Point Unit 3 experienced an unplanned scram of the reactor due to during restoration from Reactor Protection System Testing. The reactor safely shutdown and there was not any damage to equipment.

[8] FPL used average values versus actual hourly incremental in computing the replacement power costs. I reserve the right to adjust these figures if deemed necessary, based on new, corrected information.

FPSC EXH No. 5
03/18/2024

ADMITTED

C3-162

Q. DID FPL CONDUCT A ROOT CAUSE INVESTIGATION FOR THIS EVENT?

A. Yes, Exhibit No. ___ (RAP-13) is a copy of the Turkey Point Nuclear Unit 3 Trip During Restoration from RPS Testing RCE.

Q. WHAT WAS DETERMINED TO BE THE CAUSE OF THIS SCRAM?

A. The reactor trip was caused by improper operation of the reactor trip breaker ("RTB"). The cause of the RTB to malfunction was not directly determined but multiple contributing causes were found. One of the main culprits was hardened grease on the cell switches. The breaker was a Westinghouse breaker and Westinghouse performed an extensive investigation to determine the cause of the problem. In their investigation, Westinghouse found that FPL had not properly maintained the cell switches in the breaker and that the hardened lubrication could cause the stationary contacts to become dislodged. The Maintenance Program Manual ("MPM") for Westinghouse Safety Related Type DB Circuit Breakers and Associated Switchgear, Revision 1, July 2011 defines that the DB cell switch as a Category B item and the interval for conducting the procedure provided should not exceed 5 Years. In addition, Westinghouse MPM recommended a service life of 100 cycles for cell switches, which was not included in FPL preventative maintenance and only requires inspection every 18 months. FPL incorrectly planned or conducted maintenance of the switch on a conditional or "as found" basis instead of the method required or prescribed by Westinghouse. ***The RCE determined the root cause was cleaning and lubricating cell switch contacts is conditional based, rather than prescriptive.***

C3-60

FPSC EXH No. 5
03/18/2024

ADMITTED

Q. DID ANY FPL ACTIVITIES CONTRIBUTE TO THE RTB FAILURE OR COULD THE RTB PROBLEM HAVE BEEN FOUND PRIOR TO FAILURE?

A. Yes, FPL failed to follow the Westinghouse prescribed MPM which resulted in a lack of proper cleaning of the cell switch and relies on skill of the craft and judgement of the journeyman performing the inspection.

Q. WHAT WAS THE AMOUNT OF REPLACEMENT POWER COSTS FOR THE OUTAGE?

A. According FPL response to Staff Interrogatory No.4 (Exhibit No. ___(RAP-12)), the replacement power cost for the outage from the March 2021 outage of Turkey Point Unit No. 3 was $1,206,743.[9] I am accepting these calculations for the purposes of my testimony at this time even though I do not agree they are necessarily calculated correctly. At this point, it is my opinion that the calculation of the replacement power costs related to specific outages caused by imprudent action or decision-making of FPL should be based on the incremental or "but for" costs of generation, fuel or purchases. FPL should be required to calculate replacement power costs on this basis and the refunds or credits to customers should be ordered by the Commission accordingly.

Q. WHAT IS YOUR RECOMMENDATION ON FPL RECOVERY OF THOSE REPLACEMENT POWER COSTS?

A. It is my recommendation that the Commission disallow recovery of the $1,206,743 in replacement power costs associated with the outage caused by the RTB failure because the event was preventable.

[9] FPL used average values versus actual hourly incremental in computing the replacement power costs. I reserve the right to adjust these figures if deemed necessary, based on new, corrected information.

FPSC EXH No. 5
03/18/2024

ADMITTED

C3-164

Q. DOES THAT FACT THAT YOU ARE NOT RECOMENDING DISALLOWANCES OR MAKING A RECOMMENDATION ON ALL OF THE FORCED OUTAGES OR DERATES DURING THE PERIOD OF 2019 - 2021 INDICATE THAT YOU HAVE DETERMINED THAT FPL WAS PRUDENT IN ALL ASPECTS OF THOSE EVENTS AND THE NEED FOR AND AMOUNT OF REPLACEMENT POWER ASSOCIATED WITH THEM?

A. No. Although I have made an effort to review all of the available material related all outage events, it was not possible for me to discern in every event whether I had all information or that FPL had met its burden to demonstrate that it was reasonable and prudent in all of its actions. My silence on any particular outage does not mean that I have formed an opinion that customers should pay the associated replacement power costs related to those outages. **As I have testified above, however, I do believe that the Commission should open a spin-off investigation and review patterns of events that may be inducing customers to pay more in replacement power costs in the fuel factor.**

Q. DOES THAT CONCLUDE YOUR TESTIMONY?

A. Yes, it does.

C3-62

FPSC EXH No. 5
03/18/2024
ADMITTED

C3-165

GDS Associates, Inc
ENGINEERS & CONSULTANTS

Richard A. Polich, P.E.
Managing Director – Power Supply Services

EDUCATION

Master of Business Administration, University of Michigan, 1990
Bachelor of Science, Mechanical Engineering, University of Michigan, 1979
Bachelor of Science, Nuclear Engineering, University of Michigan, 1979

ENGINEERING REGISTRATION

Professional Engineer in the State of Michigan

PROFESSIONAL MEMBERSHIP

National Society of Professional Engineers
American Nuclear Society
American Society of Mechanical Engineers

PROFESSIONAL EXPERIENCE

Mr. Polich has more than 40 years' experience as an energy industry engineer, manager, and leader, combining his business and technical expertise in the management of governmental, industrial and utility projects. He has worked extensively in nuclear, coal, IGCC, natural gas, green/renewable generation. Mr. Polich has developed generation projects in wind, solar, and biomass in Australia, Canada, Caribbean, South American and United States. His generation experience includes engineering of systems and providing engineering support of plant operations. Notable projects include the Midland Nuclear Project and its conversion to natural gas combined cycle, start-up testing support for Consumers' coal-fired Campbell 3, Palisades nuclear steam generator replacement support, Covert Generating Station feasibility evaluation, and a Lake Erie offshore wind project. He also has extensive experience in utility rates and regulation, having managed Consumers Energy's rates group for a number of years. In that function his responsibilities included load and revenue forecasting, overseeing the design of gas and electric rates and testifying in regulatory proceedings. Mr. Polich has testified in over thirty regulatory and legislative proceedings.

Mr. Polich has been involved in the nuclear industry since 1978. While at GDS, Mr. Polich has provided Utah Associated Municipal Power System project cost analysis for a small modular nuclear power project. Last year, he provided advisory services to the Vermont Public Utility Commission on the ownership transfer, nuclear decommissioning trust fund adequacy and decommissioning methodology of Vermont Yankee. Mr. Polich has supported GDS oversight efforts of the construction of the Vogel Nuclear Plant units 2&3 for the Georgia Public Service Commission. He has also provided decommissioning assessment analysis on St. Lucie Nuclear, and Grand Gulf Nuclear projects. Mr. Polich was part of the design engineering team for the Erie Nuclear Plant by the design engineering firm, Gilbert Commonwealth. Key responsibilities were the design of systems and component specifications associated with the nuclear steam supply systems (NSSS) and steam turbine thermal cycle. Worked directly with Babcock and Wilcox on NSSS design and ancillary system specifications. Mr. Polich was also senior engineer on the Midland Nuclear project, responsible for oversight of Bechtel design engineering and interfacing with NSSS vendor Babcock & Wilcox on ancillary systems. His responsibilities also included negotiation with the Nuclear Regulatory Commission on new regulation requirements. Mr. Polich's role evolved into onsite engineering during construction of the Midland Nuclear Plant and as a project trouble shooter at the Palisades Nuclear Plant.

FPSC EXH No. 5
03/18/2024
ADMITTED

GDS Associates, Inc
ENGINEERS & CONSULTANTS

Richard A. Polich, P.E.
Managing Director – Power Supply Services

SPECIFIC PROJECT EXPERIENCE

NUCLEAR PROJECT EXPERIENCE

Utah Association of Municipal Utilities – Provided assessment of project costs and economics during contract negotiation phase of project. Included review of Small Modular Reactor design concepts, identification of critical issues, project schedule, risk analysis and estimated cost provided by NuScale and EPC contractors. Provide technical support for UAMPS team on as needed basis.

Vermont Yankee – Provided the Vermont Public Utility Commission advisory services on the asset transfer of Vermont Yankee from Entergy Nuclear Operations, Inc. to NorthStar Group Holdings, LLC. This effort has included assessment of financial strength of new company, adequacy of Nuclear Decommissioning Trust Fund to fund decommissioning efforts, evaluation of decommissioning methodology and State of Vermont Risk.

Vogel Nuclear Plant Units 3 & 4 – Mr. Polich has provided advisory services to the team performing the oversight of the construction of the Vogel Plant Units 3 & 4 as part of GDS project oversight responsibilities for the Georgia Public Service Commission.

St. Lucie Nuclear Plant – Provided a risk assessment, decommissioning funding study and ownership evaluation for City of Vero Beach. This included review of project maintenance history, steam generator replacement project, analysis of decommissioning needs and funding and assessing current value of Vero Beach's ownership share.

Grand Gulf Nuclear Project – Assessed the adequacy of decommissioning funding and funding level for the grand Gulf Nuclear plant for Cooperative Energy. Project purpose was to assess changes in decommissioning funding rates and to determine if sufficient funds would be available for plant decommissioning.

Consumers Energy Midland Nuclear Plant – Responsible for overseeing EPC contractor design and construction of primary and secondary nuclear systems. Included review of systems for compliance with Nuclear Regulatory Commission regulations. Key projects included:

- Leading team to analyze plant and determine best methods for compliance with new CFR Appendix R Fire Protection rules
- Design of primary cooling system pump oil collection and disposal systems.
- Oversight of redesign of component cooling water systems.
- Analysis of diesel generator capability to meet emergency shutdown power requirements.
- Primary interface with Dow Chemical for steam supply contract.

Ohio Edison Company Erie Nuclear Project – Design engineer responsible for the design, equipment specifications, bid evaluations and regulatory licensing for nuclear steam supply system and ancillary systems. Key projects included:

- Project Thermal Analysis
- Development of NSS valve specifications
- Major equipment bid Proposal Evaluation and recommendations

Interface with Babcock & Wilcox on NSSS Design

RATES & REGULATORY

GDS associates, Inc. – Managing Director

North Dakota Public Service Commission Staff – Case No. PU-16-666 MDU Generatl Rate Case

Provided testimony on behalf of the North Dakota Public Service Commission Staff regarding return on equity, cost of capital, revenue requirement, and generation resource costs.

FPSC EXH No. 5
03/18/2024
ADMITTED

North Dakota Public Service Commission Staff – Case No. PU-15-96 NSP Determination of Prudence

Provided testimony on behalf of the North Dakota Public Service Commission Staff regarding analysis and recommendation concerning Northern States Power's ("NSP") need for additional generation resources.

Consumers Energy - Supervisor of Pricing and Forecasting

Managed the group responsible for setting and obtaining regulatory approval for the company's electric and gas rates. Developed new approaches to electric and natural gas competitive pricing, redesigned electric rates to simplify rates and eliminate losses and defined new strategies for customer energy pricing. Negotiated new electric supply contracts with key industrial electric customers resulting in over $800M in annual revenue. Testified in multiple regulatory proceedings.

EOS Energy Options & Solutions – Consulting Company

Provided testimony for multiple clients in both Detroit Edison and Consumers Energy in over 30 regulatory proceedings. Testimony topics included rates, public policy and deregulation. Also testified in several legislative proceedings in both Michigan and Ohio, addressing energy policy. Provided expert witness testimony in Massachusetts regarding wind energy projects.

NATURAL GAS COMBINED CYCLE EXPERIENCE

Consumers Energy – 1,560 MW Midland Cogeneration Venture
Member of a small team selected to investigate the feasibility of converting the mothballed Midland Nuclear Plant into a fossil fueled power plant. Established new plant configuration that repowered the existing nuclear steam turbine with natural gas fired combustion turbines and heat recovery steam generators. Developed the new thermal cycle and heat rate, determined how to supply steam to Dow chemical for cogeneration, developed models for projecting plant performance, defined which portions of the nuclear plant were useful in the new combined cycle plant and forecasted project economics.

Nordic Energy – Vice President

Project Manager for the development of two 1,150 MW IGCC projects proposed to Georgia Power and Xcel Energy in response to RFPs. Responsibilities included establishing thermal cycles, equipment selection, site selection, supervising engineering, developing project proforma and proposals.

Project Manager for 230 MW power barge to be located on the Columbia River near Portland Oregon. Lead the project development team responsible for securing equipment, designing the power plant, design of barges, assessing site feasibility, developing project economics and interconnection applications.

RENEWABLE ENERGY EXPERIENCE

Matinee Energy – Utility Scale Solar Developer

Engineering design and project development consultant for utility scale solar photovoltaic projects. Development activities include site selection, equipment specifications, financial analysis and preparation of proposals. Also responsible for engineering and securing electrical interconnection.

Windlab Developments USA – Wind Power Developer

Responsible for greenfield development of the US platform for wind energy projects east of the Mississippi. Developed the company's engineering protocol for wind project design and construction, responsible for managing engineering design and construction of projects, and established six wind power projects (750 MW). Responsible for negation of Power Purchase Agreements, electrical interconnection studies, interface with Midwest ISO and submitting Generation Interconnection Application.

TradeWind Energy - Wind Power Project Developer

Project developer for 800 MW of wind power projects in Michigan and Indiana. Introduced new project

FPSC EXH No. 5
03/18/2024
ADMITTED

management methods to the development process which resulted in savings of over $200,000 annually on each project.

Third Planet Windpower – Wind Power Project Developer

Engineering and project management consultant to support the startup of new wind power company. Established engineering standards used for selection of wind project equipment and project construction, analysis tools for evaluating projecting wind project power production, and performed project economic modeling.

Noble Environmental Power – Wind Power Project Developer

Electric transmission system consultant on the development of several wind power projects. Supported Noble's decisions on transmission gird interconnect and negotiate interconnection agreements.

ENERGY EFFICIENCY EXPERIENCE

Arkansas Energy Office – Weatherization Assistance Program Evaluation

Evaluated the performance and operations of Arkansas's Weatherization Assistance Program. This included review of program effectiveness, program operations, energy efficiencies attained, adequacy of energy efficiency measures and subcontractor performance.

CLEAResult – Arkansas Energy Efficiency Programs

Energy efficiency operations and program support for 400% increase in Arkansas energy efficiency programs. Developed processes for data collection, field staff deployment and job assignments.

ECONOMIC IMPACT ASSESSMENT

Michigan Department of Environmental Quality - Economic Impacts of a Renewable Portfolio Standard and Energy Efficiency Program for Michigan

Project Manager for this report which focused on the economic impact of renewable portfolio standard and energy efficiency programs on the State of Michigan. The evaluation sued in this report encompassed using integrated resource planning models, econometric modeling and electric pricing models for the entire State of Michigan.

West Michigan Business Alliance - Alternative and Renewable Energy Cluster Analysis

Prepared the report provided a road map for Western Michigan businesses to establish new business in the renewable energy industry.

POWER PROJECT EXPERIENCE:

Detroit Edison St Clair Power Station – Performed coal combustion analysis associated with conversion Powder River Basin coal. Work included pulverizer mill performance testing, boiler combustion analysis on new coal, and unit performance analysis.

Consumers Energy Campbell 3 - Supported start-up efforts of this 800 MW pulverized coal power plant. Part of team that performed analysis of boiler data and determined the cause of superheater failure. Also part of team to analyze performance test data for warranty evaluation.

Consumers Energy Weadock Plant – Design oversight and specified various plant upgrades during major maintenance outage. Included replacement of high-pressure superheater, design of new steam supply pipes, valve specifications and supported plant restart.

FPSC EXH No. 5
03/18/2024
ADMITTED

PAPERS & PUBLICATIONS

Engineering and Economic Evaluation of Offshore Wind Plant Performance and Cost Data, 2011, Produced for the Electric Power Research Institute, KEMA, Inc.

FERC's 15% Fast Track Screening Criterion, 2012, Paper reviewing the FERC 15% screening criteria for electrical interconnection, KEMA, Inc.

Island of Saint Maarten Sustainable Energy Study, 2012, Produced for the Cabinet of Ministry VROMI, KEMA Inc.

A Study of Economic Impacts from the Implementation of a Renewable Portfolio Standard and an Energy Efficiency Program in Michigan, 2007, Produced for the Michigan Department of Environmental Quality

Alternative and Renewable Energy Cluster Analysis, 2007, Produced for the West Michigan Strategic Alliance and The Right Place

COURSES & SEMINARS

Association of Energy Engineers – Certified Energy Manager
Green Building Council – Associated LEED Certification Training
CLEAResult Leadership Academy

COMMUNITY SERVICE AND ACTIVITIES

Bicycling, hiking and cross-country skiing
Instrument-Rated Private Pilot
Habitat for Humanity
Scoutmaster
Soccer coach and referee
Volunteer work for disaster relief and building homes in Mexico

FPSC EXH No. 5
03/18/2024
ADMITTED

C3-170

PREVIOUS TESTIMONY OF RICHARD A. POLICH

COMMISSION	CASE	ON BEHALF	TITLE
FERC	ER21-2186-001	Joint Customers	Fern Solar, LLC
FERC	ER21-2364-001	Joint Customers	Albemarle Beach Solar, LLC
FERC	ER20-2576-001	Joint Customers	Holloman Lessee, LLC
FERC	ER21-2091-001	Joint Customers	Mechanicsville Solar
Michigan	U-21090	Biomass Plants	Request for Approval of Consumers Energy Integrated Resource Plan
Minnesota	G-002/CI-21-610	Minnesota Dept of Commerce	Investigation into the cause of outages at Xcel Energy's gas peaking facilities.
FERC	ER21-864	Glidepath	Revenue Requirement for Reactive Power Production Capability of Meyersdale Storage, LLC.
Minnesota	E999/AA-20-171	Minnesota Dept of Commerce	Investigation into the cause of outages at Minnesota Power's Clay Boswell coal plant and impact on replacement power costs.
Florida	2019140-EI	Florida Office of Public Council	Crystal River 3 Accelerated Decommissioning
Florida	2019001-EI	Florida Office of Public Council	Fuel Adjustment Clause – Bartow Steam Turbine Failure Power Supply Cost Recovery Disallowance
FERC	ER17-1821-002	Joint Customers	Revenue Requirement for Reactive Power Production Capability of the Panda Stonewall Generating Facility
North Carolina	E-2 Sub1142	Duke Energy Progress	Duke Energy Progress General Rate Case
Indiana	38707 FAC111-S1	Nucor Steel	Duke Energy Indiana, LLC for Fuel Cost Adjustment Clause
North Dakota	PU-16-166	ND PSC Staff	Montana-Dakota Utilities 2016 Electric Rate Increase Application
Hawaii	2015-0022	Sun Edison	Regarding the Hawaiian Electric Company, Inc. and NextEra Merger
North Dakota	PU-15-96	ND PSC Staff	Northern States Power Determination of Prudence
Michigan	U-10143	Consumers Energy	Consumers Energy Approval of an Experimental Retail Wheeling Case
Michigan	U-10335	Consumers Energy	General Rate Case
Michigan	U-10625	Consumers Energy	Proposal for Market-Based Rates Under Rate-K
Michigan	U-10685	Consumers Energy	1996 General Rate Case
Michigan	U-11915	Energy Michigan	Supplier Licensing
Michigan	U-11955	Energy Michigan	Consumers Energy Stranded & Implementation Cost Recovery
Michigan	U-11956	Energy Michigan	Detroit Edison Stranded & Implementation Cost Recovery
Michigan	U-12478	Energy Michigan	Detroit Edison Asset Securitization Case
Michigan	U-12488	Energy Michigan	Consumers Energy Retail Open Access Tariff
Michigan	U-12489	Energy Michigan	Detroit Edison Retail Open Access Tariffs
Michigan	U-12505	Energy Michigan	Consumers Energy Asset Securitization Cases
Michigan	U-12639	Energy Michigan	Stranded Cost Methodology Case
Michigan	U-13380	Energy Michigan	Consumers Energy 2000, 2001 & 2002 Stranded Cost Case
Michigan	U-13350	Energy Michigan	Detroit Edison 2000 & 2001 Stranded Cost Case

C3-68

FPSC EXH No. 5
03/18/2024

ADMITTED

C3-171

Docket No. 20220001-EI
List of Richard A. Polich Testimony
Exhibit RAP-2, Page 2 of 2

PREVIOUS TESTIMONY OF RICHARD A. POLICH

COMMISSION	CASE	ON BEHALF	TITLE
Michigan	U-13715	Energy Michigan	Consumers Energy Securitization of Qualified Costs
Michigan	U-13720	Energy Michigan	Consumers Energy 2002 Stranded Costs
Michigan	U-13808	Energy Michigan	Detroit Edison General Rate Case
Michigan	U-13808-R	Energy Michigan	Detroit Edison 2004 Stranded Cost &
Michigan	U-14474	Energy Michigan	Detroit Edison 2004 PSCR Reconciliation Case
Michigan	U-13933	Energy Michigan	Detroit Edison Low-Income Energy Assistance Credit for Residential Electric Customers
Michigan	U-13917-R	Energy Michigan	Consumers Energy 2004 PSCR Reconciliation Case
Michigan	U-13989	Energy Michigan	Consumers Energy Request for Special Contract Approval
Michigan	U-14098	Energy Michigan	Consumers Energy 2003 Stranded Costs
Michigan	U-14148	Energy Michigan	Consumers Energy MCL 460.10d(4) Case
Michigan	U-14347	Energy Michigan	Consumers Energy General Rate Case
Michigan	U-14274-R	Energy Michigan	Consumers Energy 2005 PSCR Reconciliation Case
Michigan	U-14275-R	Energy Michigan	Detroit Edison Company 2005 PSCR Reconciliation Case
Michigan	U-14399	Energy Michigan	Detroit Edison Company Application for Unbundling of Rate
Michigan	U-14992	Energy Michigan	Power Purchase Agreement and for Other Relief in Connection with the sale of the Palisades Nuclear Power Plant and Other Assets

FPSC EXH No. 5
03/18/2024

ADMITTED

BEFORE THE FLORIDA PUBLIC SERVICE COMMISSION

In re: Fuel and purchased power cost recovery clause with generating performance incentive factor.	Docket No.: 20220001-EI Filed: August 3, 2022

FLORIDA POWER & LIGHT COMPANY'S OBJECTIONS TO THE OFFICE OF PUBLIC COUNSEL'S SECOND SET OF INTERROGATORIES (Nos. 14-35) AND SECOND REQUEST FOR PRODUCTION OF DOCUMENTS (Nos. 20-25)

Florida Power & Light Company ("FPL"), pursuant to Rules 1.340 and 1.350, Florida Rules of Civil Procedure and Rule 28-106.206, Florida Administrative Code, submits the following objections to the Office of Public Counsel's ("OPC") Second Set of Interrogatories (Nos. 14-35) and Second Request for Production of Documents (Nos. 20-25).

I. General Objections

FPL objects to each and every request for information or documents that call for information protected by the attorney-client privilege, the work product doctrine, the accountant-client privilege, the trade secret privilege, or any other applicable privilege or protection afforded by law, whether such privilege or protection appears at the time response is first made or is later determined to be applicable for any reason. FPL in no way intends to waive such privilege or protection. The nature of the privileged or protected document(s), if any, will be described in a privilege log prepared by FPL.

In certain circumstances, FPL may determine, upon investigation and analysis, that information or documents responsive to certain discovery requests to which objections are not otherwise asserted is confidential and proprietary and should be produced only with provisions in place to protect the confidentiality of the information. By agreeing to provide such information or documents in response to such request, FPL is not waiving its right to insist upon appropriate protection of confidentiality by means of a protective order, a request for confidential classification, a Notice of Intent, and any other process as provided for by Florida Statutes and

FPSC EXH No. 5
03/18/2024
ADMITTED

Commission Rules, or other action to protect the confidential information or documents requested. FPL asserts its right to require such protection of any and all information and documents that may qualify for protection under the Florida Rules of Civil Procedure, Florida Statutes, and other applicable statutes, rules and legal principles.

FPL objects to each request to the extent that it seeks information that is duplicative, not relevant to the subject matter of this docket, and is not reasonably calculated to lead to the discovery of admissible evidence.

FPL objects to each and every discovery request to the extent it is vague, ambiguous, overly broad, imprecise, or utilizes terms that are subject to multiple interpretations but are not properly defined or explained for purposes of such discovery requests. Any responses provided by FPL will be provided subject to, and without waiver of, the foregoing objection.

FPL also objects to each and every discovery request to the extent it calls for FPL to prepare information in a particular format or perform calculations or analyses not previously prepared or performed as unduly burdensome and as purporting to expand FPL's obligations under applicable law.

FPL objects to providing information to the extent that such information is already in the public record before the Florida Public Service Commission or other public agency and available to OPC through normal procedures or is readily accessible through legal search engines.

FPL objects to each and every discovery request that calls for the production of documents and/or disclosure of information from NextEra Energy, Inc. and any subsidiaries and/or affiliates of NextEra Energy, Inc. that do not deal with transactions or cost allocations between FPL and either NextEra Energy, Inc. or any subsidiaries and/or affiliates. Such documents and/or information do not affect FPL's rates or cost of service to FPL's customers. Therefore, those documents and/or information are irrelevant, immaterial, and not reasonably

FPSC EXH No. 5
03/18/2024
ADMITTED

calculated to lead to the discovery of admissible evidence. Furthermore, FPL is the party appearing before the Florida Public Service Commission in this docket. To require any non-regulated entities to participate in irrelevant discovery is by its very nature unduly burdensome and overbroad. Subject to, and without waiving any other objections, FPL will respond to the extent the discovery pertains to FPL and FPL's rates or cost of service charged to FPL's customers. To the extent any responsive documents contain irrelevant parent and/or affiliate information as well as information related to FPL and FPL's rates or cost of service charged to its customers, FPL may redact the irrelevant parent and affiliate information from the responsive document(s).

Where any discovery request calls for production of documents, FPL objects to any production location other than the location established by FPL, at FPL's Tallahassee Office located at 134 W. Jefferson Street, Tallahassee, Florida, unless otherwise agreed by the parties.

FPL objects to each and every discovery request and any instructions that purport to expand FPL's obligations under applicable law.

In addition, FPL reserves its right to count discovery requests and their sub-parts, as permitted under the applicable rules of procedure and the Order Establishing Procedure that will presumably be issued following the filing of the Petition in this docket, in determining whether it is obligated to respond to additional discovery requests served by any party.

FPL expressly reserves and does not waive any and all objections it may have to the admissibility, authenticity or relevancy of the information provided in its responses.

FPSC EXH No. 5
03/18/2024
ADMITTED

II. Specific Objections

A. Interrogatories

Interrogatory No. 16: FPL objects to OPC's Interrogatory No. 16 on the ground that it is overbroad and not reasonably calculated to lead to the discovery of admissible evidence. Interrogatory No. 16 requests information regarding "every outage" occurring since January 1, 2020. This issues in this docket concern cost recovery through the Fuel (and Purchased Power) Cost Recovery ("FCR") Clause. Outages for which FPL does not seek cost recovery through the FCR Clause are outside the scope of this docket. Subject to this objection, FPL will respond with relevant information within the scope of this docket.

B. Requests for Production

Request for Production No. 20. OPC's Request for Production No. 20 seeks documents identified in Interrogatory No. 16. Accordingly, FPL incorporates herein its objection to Interrogatory No. 16.

Respectfully submitted this 3rd day of August 2022.

Respectfully submitted,

By: *s/ Maria Jose Moncada*

Maria Jose Moncada
Managing Attorney
maria.moncada@fpl.com
Fla. Bar No. 0773301
David M. Lee
Senior Attorney
david.lee@fpl.com
Fla. Bar No. 103152
Florida Power & Light Company
700 Universe Boulevard
Juno Beach, Florida 33408-0420
Telephone: (561) 304-5795
Facsimile: (561) 691-7135

FPSC EXH No. 5
03/18/2024

ADMITTED

CERTIFICATE OF SERVICE
Docket 20220001-EI

I HEREBY CERTIFY that a true and correct copy of the foregoing has been furnished by electronic delivery on this 3rd day of August 2022 to the following:

Suzanne Brownless
Ryan Sandy
Division of Legal Services
Florida Public Service Commission
2540 Shumard Oak Blvd.
Tallahassee, Florida 32399-0850
sbrownle@psc.state.fl.us
rsandy@psc.state.fl.us

Paula K. Brown, Manager
Tampa Electric Company
Regulatory Coordinator
Post Office Box 111
Tampa, Florida 33601-0111
regdept@tecoenergy.com

J. Jeffrey Wahlen
Malcolm N. Means
Virginia Ponder
Ausley & McMullen
P.O. Box 391
Tallahassee, Florida 32302
jwahlen@ausley.com
mmeans@ausley.com
vponder@ausley.com
Attorneys for Tampa Electric Company

Michelle D. Napier
Director, Regulatory Affairs Distribution
Florida Public Utilities Company
1635 Meathe Drive
West Palm Beach, FL33411
mnapier@fpuc.com

Mike Cassel
Vice President/Government and
Regulatory Affairs
Florida Public Utilities Company
208 Wildlight Ave.
Yulee, Florida 32097
mcassel@fpuc.com

Richard Gentry
Patricia A. Christensen
Charles J. Rehwinkel
Stephanie Morse
Mary Wessling
Office of Public Counsel
c/o The Florida Legislature
111 West Madison St., Room 812
Tallahassee, FL 32399-1400
gentry.richard@leg.state.fl.us
christensen.patty@leg.state.fl.us
rehwinkel.charles@leg.state.fl.us
morse.stephanie@leg.state.fl.us
wessling.mary@leg.state.fl.us

Robert L. Pickels
Duke Energy Florida
106 East College Avenue, Suite 800
Tallahassee, Florida 32301
robert.pickels@duke-energy.com
FLRegulatoryLegal@duke-energy.com

Dianne M. Triplett
299 First Avenue North
St. Petersburg, Florida 33701
dianne.triplett@duke-energy.com

Matthew R. Bernier
Stephanie A. Cuello
Duke Energy Florida
106 East College Avenue, Suite 800
Tallahassee, Florida 32301
robert.pickels@duke-energy.com
matthew.bernier@duke-energy.com
stephanie.cuello@duke-energy.com
FLRegulatoryLegal@duke-energy.com
Attorneys for Duke Energy Florida

FPSC EXH No. 5
03/18/2024

ADMITTED

C3-177

Beth Keating
Gunster Law Firm
215 South Monroe St., Suite 601
Tallahassee, Florida 32301-1804
bkeating@gunster.com
Attorneys for Florida Public Utilities Company

Jon C. Moyle, Jr.
Moyle Law Firm, P.A.
118 North Gadsden Street
Tallahassee, FL 32301
jmoyle@moylelaw.com
mqualls@moylelaw.com
Attorneys for Florida Industrial Power Users Group

Peter J. Mattheis
Michael K. Lavanga
Joseph R. Briscar
Stone Mattheis Xenopoulos & Brew, PC
1025 Thomas Jefferson Street, NW
Eighth Floor, West Tower
Washington, DC 20007-5201
pjm@smxblaw.com
mkl@smxblaw.com
jrb@smxblaw.com
Attorneys for Nucor Steel Florida, Inc.

James W. Brew
Laura Wynn Baker
Stone Mattheis Xenopoulos & Brew, P.C.
1025 Thomas Jefferson Street, NW
Eighth Floor, West Tower
Washington, DC 20007
jbrew@smxblaw.com
lwb@smxblaw.com
Attorneys for PCS Phosphate-White Springs

Robert Scheffel Wright
John T. LaVia, III
Gardner, Bist, Bowden, Dee
LaVia, Wright, Perry & Harper, P.A.
1300 Thomaswood Drive
Tallahassee, FL 32308
schef@gbwlegal.com
jlavia@gbwlegal.com
Attorneys for The Florida Retail Federation

By: *s/ Maria Jose Moncada*
Maria Jose Moncada
Florida Bar No. 073301

FPSC EXH No. 5
03/18/2024

ADMITTED

C3-178

Florida Power & Light Company
Docket No. 20220001-EI
OPC's 2nd Set of Interrogatories
Interrogatory No. 16
Page 1 of 1

QUESTION:
Gain/Loss Form. Please identify each outage occurring since January 1, 2020 (including any that were on going in which a Gain/Loss Form substantially similar to the document beginning at Bates No. FCR22-002142 was utilized) and identify the documents containing the Gain/Loss form utilized for each outage.

RESPONSE:
See FPL's Objections filed August 3, 2022. Subject to those objections:
Turkey Point Unit 3 Cycle 31 Refueling Outage – Gain loss Walk T3R31
Turkey Point Unit 3 Cycle 32 Refueling Outage – Gain loss Walk T3R32
Turkey Point Unit 4 Cycle 31 Refueling Outage – Gain loss Walk T4R31
Turkey Point Unit 4 Cycle 32 Refueling Outage – Gain loss Walk T4R32
Turkey Point Unit 4 Cycle 33 Refueling Outage – Gain loss Walk T4R33
Turkey Point Unit 4 – PTN Volt Reg forced outage
St. Lucie Unit1 Cycle 30 Refueling Outage – PSL Gain loss Walk L1R30
St. Lucie Unit 2 Cycle 25 Refueling Outage – PSL Gain loss Walk L2R25
St. Lucie Unit 2 Cycle 26 Refueling Outage – PSL Gain loss Walk L2R26
St. Lucie Unit 2 - CEA 2022 unplanned outage

FPSC EXH No. 5
03/18/2024

ADMITTED

C3-179

Florida Power & Light Company
Docket No. 20220001-EI
OPC's Second Request for Production of Documents
Request No. 20
Page 1 of 1

QUESTION:
Gain/Loss Form. Please produce each document identified in Interrogatory No. 16.

RESPONSE:
See FPL's Objections filed August 3, 2022. Subject to those objections, documents responsive to this request are provided as Bates FCR-22-002433 – FCR-22-003132.

FPSC EXH No. 5
03/18/2024

ADMITTED

C3-189

BEFORE THE FLORIDA PUBLIC SERVICE COMMISSION

In re: Fuel and Purchased Power Cost Recovery Clause with Generating Performance Incentive Factor	Docket No: 20220001-EI Filed: April 1, 2022

PETITION FOR APPROVAL OF FUEL COST RECOVERY AND CAPACITY COST RECOVERY NET FINAL TRUE-UPS FOR THE PERIOD ENDING DECEMBER 2021 AND 2021 ASSET OPTIMIZATION INCENTIVE MECHANISM RESULTS

Florida Power & Light Company ("FPL") hereby petitions this Commission for approval of (1) pre-consolidated FPL's Fuel and Purchased Power Cost Recovery ("FCR") final net true-up under-recovery of $11,681,957 for the period ending December 2021, (2) pre-consolidated FPL's Capacity Cost Recovery ("CCR") final net true-up over-recovery of $3,634,686 for the period ending December 2021, (3) pre-consolidated Gulf Power Company's ("Gulf") FCR final net true-up over-recovery of $21,938,913 for the period ending December 2021, (4) Gulf's CCR final net true-up under-recovery of $3,937,996 for the period ending December 2021, and (5) retention and recovery of $13,855,504 of the $63,092,506 total 2021 Asset Optimization Program gains, representing 60% of the gains above $40 million threshold established in Order Nos. PSC-13-0023-S-EI and PSC-16-0560-AS-EI. The FPL and Gulf FCR final true-ups result in a combined over-recovery of $10,256,956, and CCR final true-ups result in a combined under-recovery of $303,310. FPL incorporates the prepared testimony and exhibits of FPL witnesses Renae B. Deaton, Gerard J. Yupp and Dean Curtland.

1. Although Gulf was legally merged with and into FPL effective January 1, 2021, Gulf and FPL remained separate ratemaking entities and, as such, each filed its 2021 FCR and CCR costs and factors separately in Docket No. 20210001. Therefore, FPL is providing and seeking approval of final true-ups of the 2021 FCR and CCR costs for both pre-consolidated FPL

C3-78

FPSC EXH No. 5
03/18/2024
ADMITTED

C3-181

and pre-consolidated Gulf. The combined 2021 net final true-ups will be included in the calculation of FPL's 2023 FCR and CCR factors, which will be filed later this year.[1]

2. The calculations and supporting documentation for FPL's and Gulf's FCR and CCR final net true-up amounts for the period ending December 2021 are contained in the prepared testimony and exhibits of witness Deaton.

3. By Order No. 2021-0460-PCO-EI dated December 15, 2021, the Commission approved FPL's 2022 mid-course correction petition, which included revised 2021 actual/estimated true-ups for FPL and Gulf. FPL's revised 2021 FCR actual/estimated true-up was an under-recovery of $585,866,364. FPL's actual final true-up, including interest, for the period January 2021 through December 2021 is an under-recovery of $597,548,321. The $597,548,321 actual under-recovery, less the revised actual/estimated under-recovery of $585,866,364, results in an FCR final net true-up under-recovery of $11,681,957 for FPL.[2]

4. Gulf's revised 2021 FCR actual/estimated true-up approved on December 15, 2021 was an under-recovery of $103,719,775. Gulf's actual final true-up, including interest, for the period January 2021 through December 2021 is an under-recovery of $81,780,862. The $81,780,862 actual under-recovery, less Gulf's revised actual/estimated under-recovery of $103,719,775 results in a FCR final net true-up over-recovery of $21,938,913 for Gulf.

[1] Effective January 1, 2022, the rates and tariffs of Gulf and FPL were consolidated and unified, all former Gulf customers became FPL customers, and Gulf ceased to exist as a separate ratemaking entity. *See* Order Nos. PSC-2021-0446-S-EI and PSC-2021-04464A-S-EI issued in Docket No. 20210015. Accordingly, the FCR and CCR factors for FPL and Gulf were consolidated effective January 1, 2022. *See* Order Nos. PSC-2021-0460-PCO-EI and PSC-2021-0442-FOF-EI issued in Docket No. 20210001.

[2] FPL will not pursue recovery of the replacement power costs associated with outages at the Turkey Point Nuclear Unit 3 in August of 2020, which were a subject of Issue 2K in Order No. PSC-2021-0403-PHO-EI, and will refund with interest any associated costs collected from customers when its fuel factor is next reset.

C3-79

FPSC EXH No. 5
03/18/2024

ADMITTED

C3-182

UNITED STATES
NUCLEAR REGULATORY COMMISSION
WASHINGTON, D.C. 20555-0001

September 12, 2019

EA-18-066
EA-19-045

Mr. Mano Nazar, President
and Chief Nuclear Officer
Nuclear Division
Florida Power & Light Company
Mail Stop: EX/JB
700 Universe Blvd.
Juno Beach, FL 33408

SUBJECT: ST. LUCIE PLANT – NOTICE OF VIOLATION AND PROPOSED IMPOSITION OF CIVIL PENALTY - $232,000 (NRC INVESTIGATION REPORT NUMBERS 2-2017-024 AND 2-2019-009)

Dear Mr. Nazar:

This letter refers to two investigations conducted by the U.S. Nuclear Regulatory Commission (NRC) Office of Investigations (OI) related to Florida Power and Light's (FPL) St. Lucie Nuclear Plant. The purposes of the investigations were to determine whether a contract employee at St. Lucie Nuclear Plant was the subject of employment discrimination in violation of Title 10 of the *Code of Federal Regulations* (10 CFR) 50.7, "Employee protection" (OI Report No. 2-2017-024); and to determine whether a FPL senior licensee executive, or potentially others, deliberately provided the NRC with incomplete and inaccurate information in violation of 10 CFR 50.9, "Completeness and accuracy of information" (OI Report No. 2-2019-009).

For OI investigation 2-2017-024 (dated May 21, 2018), NRC determined that the FPL Regional Vice President (VP) – Operations, deliberately caused a contract employee's assignment to be cancelled the week of March 13, 2017. The cancellation occurred, in part, because the contract employee entered a concern into St. Lucie's corrective action program on March 13, 2017. In summary, a Framatome (formerly known as Areva) part-time employee asserted that his work re-assignment was cancelled in March 2017, after submitting a condition report at FPL's St. Lucie nuclear plant. The contract employee, as the lead supervisor for Framatome's refueling team at St. Lucie, had been pre-scheduled by Framatome and FPL to transfer to Turkey Point nuclear plant for the same role. On March 13, 2017, the contract employee submitted a condition report that documented concerns with the St. Lucie's requirement for Framatome personnel to wear multiple dosimeters while performing refueling work. On March 16, 2017, the contract employee's re-assignment to Turkey Point was cancelled.

The NRC determined that the contract employee's work assignment was cancelled, at least in part, for raising a nuclear safety concern via the submission of a condition report. The cancellation of the contract employee's work assignment is a violation of 10 CFR 50.7.

C3-180

FPSC EXH No. 5
03/18/2024
ADMITTED
M. Nazar

Additionally, the NRC determined that the deliberate actions of the former FPL Regional VP - Operations caused FPL to be in violation of 10 CFR 50.7. Our determinations were based on information developed during the investigation and information that you provided during the predecisional enforcement conference (PEC) process.

OI's investigation documented that FPL's Regional VP - Operations sent an e-mail to the Framatome VP of Outage Services on March 14, 2017. The body of the FPL VP's e-mail included the text of the condition report that was submitted by the contract employee on March 13, 2017, and a related question regarding the condition report. The evidence documented that both VPs acknowledged the sending, and the receipt, of the March 14th e-mail. Additionally, the evidence indicated that the FP&L Regional VP initiated a subsequent phone discussion on March 14th with the Framatome VP of Outage Services which included discussing the contract employee's reassignment to Turkey Point. OI's evidence documented that on March 14th the Framatome VP (Outage Services), contacted the Framatome Manager, PWR/Reactor Services and directed him to inform the contract employee that his re-assignment was cancelled. On March 16th, the Framatome Manager (PWR/Reactor Services), informed the employee that his re-assignment to Turkey Point was cancelled. The temporal proximity of the concerned individual's (CI) submission of the condition report and the initiation of the adverse action by an FPL executive and the subsequent implementation of the adverse action within a few days by Framatome management was deemed a discriminatory act. The NRC determined that neither FPL or Framatome presented sufficient evidence to support their assertions that the adverse employment action was justified for business reasons.

During the PECs, FPL and Framatome denied that a violation of 10 CFR 50.7 occurred. Generally, FPL and Framatome asserted that (1) the protected activity was not a contributing factor to any adverse personnel action and that the NRC's only basis was "temporal proximity," (2) that Framatome's reassignment of the contractor was justified by legitimate safety (business) reasons; (3) and that the contractor did not suffer an adverse personnel action, but instead was reassigned. The NRC's determination that a violation occurred was based on factors such as: the CI's subordinates, coworkers, and superiors, both at Framatome and FPL, almost universally spoke very highly of him; neither FPL or Framatome produced sufficient evidence to indicate that the performance of the CI, or the performance of his reactor services team, was a significant concern during the refueling outage; and, the staff noted that the former FPL Regional VP – Operation's testimony differed significantly from the testimony of other witnesses and included inconsistencies that undercut his credibility and specifically discredited his assertions that the CI's removal from the Turkey Point outage was unrelated to his protected activities. The NRC determined that FPL's and Framatome's assertion that the contractor's reassignment was justified by legitimate safety (business) reasons was not reasonable because of evidence which indicated that the 2017 spring refueling outage was the shortest outage for St. Lucie in many years and that the reactor services portion of the outage, managed by the contract employee, incurred only minimal scheduling delays. Lastly, the NRC determined that the contractor did suffer an adverse action when he was removed from the Turkey Point outage. When the contractor was directed not to go to Turkey Point, it was not clear if Framatome would provide an alternative work assignment. The individual is a part-time Framatome employee and is only paid when he works. A reasonable person would view the cancellation of the workers pre-scheduled transfer as a materially adverse action and one that could potentially chill others who raise nuclear safety concerns.

The NRC considers violations of 10 CFR 50.7 significant because of the potential that individuals might not raise safety issues for fear of retaliation. Based on the deliberate action

FPSC EXH No. 5
03/18/2024

ADMITTED

C3-84

and the level of manager involved in the adverse action, this violation has been categorized in accordance with the "NRC Enforcement Policy," at Severity Level II. See NRC Enforcement Policy, Violation Example 6.10.b.1.

In accordance with the NRC Enforcement Policy, a base civil penalty in the amount of $232,000 is considered for the Severity Level II violation of 10 CFR 50.7, "Employee Protection." The NRC considered both the Identification and Corrective Action factors with respect to this willful violation in accordance with the civil penalty assessment process in Section 2.3.4 of the NRC Enforcement Policy. Credit for Identification is not appropriate, since the violation was identified by the NRC via the Agency's allegation program. The NRC determined *Corrective Action* credit was warranted due to corrective actions initiated by FPL. Completed corrective actions include an Employee Concerns Program (ECP) investigation, safety conscious work environment (SCWE) surveys in St. Lucie and Turkey Point radiation protection departments, and training of senior nuclear managers. Planned corrective actions include items such as a fleet-wide communication that reinforces the SCWE policy, ECP personnel training, ECP third-party audits, and the creation of a personnel action review board process to review certain employment actions involving contractor personnel brought to FPL's attention. Therefore, to emphasize the importance of prompt identification and correction of violations, the NRC has determined, as provided for in Section 2.3.4 of the NRC Enforcement Policy, to issue the enclosed Notice of Violation (Notice) and Proposed Imposition of Civil Penalty of $232,000, which is the base civil penalty amount for the Severity Level II violation.

If you disagree with this enforcement sanction, you may deny the violation, as described in the enclosed Notice, or you may request alternative dispute resolution (ADR) with the NRC in an attempt to resolve this issue. ADR is a general term encompassing various techniques for resolving conflicts using a neutral third party. The technique that the NRC has decided to employ is mediation. Mediation is a voluntary, informal process in which a trained neutral (the "mediator") works with parties to help them reach resolution. If the parties agree to use ADR, they select a mutually agreeable neutral mediator who has no stake in the outcome and no power to make decisions. Mediation gives parties an opportunity to discuss issues, clear up misunderstandings, be creative, find areas of agreement, and reach a final resolution of the issues. Additional information concerning the NRC's ADR program can be found at http://www.nrc.gov/about-nrc/regulatory/enforcement/adr.html.

The Institute on Conflict Resolution (ICR) at Cornell University has agreed to facilitate the NRC's program as a neutral third party. If you are interested in pursuing this issue through the ADR program, please contact: (1) the ICR at (877) 733-9415; and (2) David Jones at (301) 287-9525 within 10 days of the date of this letter. You may also contact both ICR and Mr. Jones for additional information. If you decide to participate in ADR, your submitted signed agreement to mediate using the NRC ADR program will stay the 30-day time period for payment of the civil penalty until the ADR process is completed.

You are required to respond to this letter and should follow the instructions specified in the enclosed Notice when preparing your response. If you have additional information that you believe the NRC should consider, you may provide it in your response to the Notice. The NRC will use your response, in part, to determine whether further enforcement action is necessary to ensure compliance with regulatory requirements.

C3-82

FPSC EXH No. 5
03/18/2024

ADMITTED

C3-185

Docket No. 20220001-EI
September 12, 2019 NRC Notice of Violation
Exhibit RAP-4, Page 4 of 9

In accordance with 10 CFR 2.390 of the NRC's "Rules of Practice," a copy of this letter, its enclosures, and your response, if you choose to provide one, will be made available electronically for public inspection in the NRC Public Document Room and from ADAMS, accessible from the NRC Web site at http://www.nrc.gov/reading-rm/adams.html. The NRC will also make available, within ADAMS, the letter describing the apparent violation, dated October 19, 2018, and the NRC presentation from the PEC held on February 4, 2019. To the extent possible, your response, if provided, should not include any personal privacy or proprietary information so that it can be made available to the public without redaction. The NRC also includes significant enforcement actions on its Web site at http://www.nrc.gov/reading rm/doc collections/enforcement/actions/.

Concerning OI Report No. 2-2019-009 (dated April 23, 2019), the NRC determined that a former FPL Corporate Support Vice President, whose previous position was FPL Regional VP-Operations (discussed above), deliberately provided incomplete and inaccurate information to FPL that was subsequently submitted by FPL to the NRC. Had the inaccurate information not been detected it would have adversely impacted NRC's deliberations for OI investigation 2-2017-024. In a letter dated December 10, 2018, Agencywide Documents Access and Management System (ADAMS) Accession No. ML18346A182, FPL submitted to the NRC a photocopied journal that had been maintained by the then FPL Regional Vice President (VP) - Operations. The letter stated that the journal contained material that was highly relevant to the facts in OI investigation 2-2017-024. Subsequently, in a letter dated January 17, 2019 (ADAMS No. ML#19024A085), FPL stated that they had developed cause to question the authenticity of the outage journal. The evidence developed during OI's investigation (2-2019-009) revealed that the FPL Regional VP - Operations deliberately submitted a journal to FPL which contained incomplete and inaccurate information. Had the inaccurate information not been detected it would have adversely impacted NRC's deliberations for the St. Lucie discrimination case (OI investigation 2-2017-024).

Section 2.3.11, "Inaccurate and Incomplete Information," of the Enforcement Policy, states that "*Generally, if the matter was promptly identified and corrected by the licensee or applicant before the NRC relies on the information, or before the NRC raises a question about the information, no enforcement action will be taken for the initial inaccurate or incomplete information.*" Therefore, the NRC determined that pursuant to Section 2.3.11 of the Enforcement Policy, no further action should be taken with respect to FPL for OI Report 2-2019-009) because FPL (1) proactively identified the concern and promptly informed the NRC, (2) withdrew the journal prior to it adversely impacting the NRC's enforcement proceedings for the discrimination case (OI Report 2-2017-024), (3) conducted a detailed investigation which included the hiring of a forensics analyst, and (4) took appropriate personnel actions. For NRC enforcement actions involving the FPL VP, see (ADAMS No. ML19234A334).

C3-83

FPSC EXH No. 5
03/18/2024

ADMITTED

C3-186

If you have any questions concerning either of these matters, please contact David Jones of my staff at (301) 287-9525.

Sincerely,

/RA/

George A. Wilson, Director
Office of Enforcement

Docket No. 50-335 and 50-389
License No. DPR-67 and NPF-16

Enclosures:
1. Notice of Violation and Proposed Imposition of Civil Penalty
2. NUREG/BR-0254 Payment Methods
3. NUREG/BR-0317 Rev. 2, Enforcement Alternative Dispute Resolution Program

C3-84

FPSC EXH No. 5
03/18/2024

ADMITTED

C3-187

M. Nazar 6

SUBJECT: ST. LUCIE PLANT – NOTICE OF VIOLATION AND PROPOSED IMPOSITION OF CIVIL PENALTY - $232,000 (NRC INVESTIGATION REPORT NUMBERS 2-2017-024 AND 2-2019-009)
DATE: September 12, 2019

DISTRIBUTION: WITHOUT ENCLOSURES

P. Moulding, OGC	S. Kirkwood, OGC	M. Kowal, RII
S. Sparks, RII	B. Hughes, NRR	D. Aird, NRR
D. Willis, OE	OE R/F	

Publicly Available
ADAMS Accession No.: ML19234A332

OFFICE	OE/EB	OE/CRB	OGC	OE/D
NAME	DJones	DSolorio	SKirkwood	GWilson
DATE	8/30/19	9/9/19	8/22/19	9/12/19

OFFICIAL RECORD COPY

C3-85

FPSC EXH No. 5
03/18/2024

ADMITTED

C3-188

NOTICE OF VIOLATION
AND
PROPOSED IMPOSITION OF CIVIL PENALTY

St. Lucie Plant
Juno Beach, FL

Docket No. 050-335/389
License No. DPR-67/NPF-16
EA-18-066

During an NRC investigation completed on May 21, 2018, a violation of an NRC requirement was identified. In accordance with the NRC Enforcement Policy, the NRC proposes to impose a civil penalty pursuant to Section 234 of the Atomic Energy Act of 1954, as amended (Act), 42 U.S.C. 2282, and 10 CFR 2.205. The particular violation and associated civil penalty is set forth below:

A. 10 CFR 50.7(a), states, in part, that “Discrimination by a Commission licensee, an applicant for a Commission license, or a contractor or subcontractor of a Commission licensee or applicant against an employee for engaging in certain protected activities is prohibited. Discrimination includes discharge and other actions that relate to compensation, terms, conditions, or privileges of employment.” The protected activities are established in section 211 of the Energy Reorganization Act of 1974, as amended, and in general are related to the administration or enforcement of a requirement imposed under the Atomic Energy Act or the Energy Reorganization Act.

10 CFR 50.7(a)(1)(i), states, in part, that the protected activities include but are not limited to providing the Commission or his or her employer information about alleged violations of either of the statutes named in paragraph (a) introductory text of this section or possible violations of requirements imposed under either of those statutes.

A Florida Power and Light Regional Vice President - Operations deliberately discriminated against a Framatome (formerly known as Areva) contract employee for engaging in a protected activity in March of 2017. Specifically, a contract employee who raised safety concerns during the St. Lucie refueling outage had a work assignment to Turkey Point Nuclear Plant cancelled shortly after submitting a condition report. The actions of FPL management were, in part, based on the contractor’s engagement in a protected activity.

This is a Severity Level II violation (Enforcement Policy Sections 2.2.1.d, 6.10).
Civil Penalty - $232,000.

Pursuant to the provisions of 10 CFR 2.201, Florida Power & Light is hereby required to submit a written statement or explanation to the Director, Office of Enforcement, U.S. Nuclear Regulatory Commission, with a copy to the Document Control Desk, Washington, DC 20555-0001, within 30 days of the date of this Notice of Violation and Proposed Imposition of Civil Penalty. This reply should be clearly marked as a "Reply to a Notice of Violation (EA-18-066)” and should include for the violation: (1) the reason for the violation, or, if contested, the basis for disputing the violation or severity level; (2) the corrective steps that have been taken and the results achieved; (3) the corrective steps that will be taken to avoid further violations; (4) your plan and schedule for completing short and long term corrective actions and (5) the date when full compliance will be achieved.

C3-86

FPSC EXH No. 5
03/18/2024

ADMITTED

C3-189

Your response may reference or include previous docketed correspondence, if the correspondence adequately addresses the required response. If an adequate reply is not received within the time specified in this Notice, the NRC may issue an order or a Demand for Information requiring you to explain why your license should not be modified, suspended, or revoked or why the NRC should not take other action as may be proper. Consideration may be given to extending the response time for good cause shown.

Florida Power & Light may pay the civil penalty in accordance with NUREG/BR-0254 and by submitting to the Director, Office of Enforcement, U.S. Nuclear Regulatory Commission, a statement indicating when and by what method payment was made, or may protest imposition of the civil penalty in whole or in part, by a written answer within 30 days of the date of this Notice addressed to the Director, Office of Enforcement, U.S. Nuclear Regulatory Commission. Should the Licensee fail to answer within 30 days of the date of this Notice, the NRC will issue an order imposing the civil penalty. Should the Licensee elect to file an answer in accordance with 10 CFR 2.205 protesting the civil penalty, in whole or in part, such answer should be clearly marked as an "Answer to a Notice of Violation (EA-18-066)" and may: (1) deny the violation listed in this Notice, in whole or in part; (2) demonstrate extenuating circumstances; (3) show error in this Notice; or (4) show other reasons why the penalty should not be imposed. In addition to protesting the civil penalty in whole or in part, such answer may request remission or mitigation of the penalty.

In requesting mitigation of the proposed penalty, the response should address the factors addressed in Section 2.3.4 of the Enforcement Policy. Any written answer addressing these factors pursuant to 10 CFR 2.205 should be set forth separately from the statement or explanation provided pursuant to 10 CFR 2.201, but may incorporate parts of the 10 CFR 2.201 reply by specific reference (e.g., citing page and paragraph numbers) to avoid repetition. The attention of the Licensee is directed to the other provisions of 10 CFR 2.205 regarding the procedure for imposing (a) civil penalty.

Upon failure to pay any civil penalty which subsequently has been determined in accordance with the applicable provisions of 10 CFR 2.205 to be due, this matter may be referred to the Attorney General, and the penalty, unless compromised, remitted, or mitigated, may be collected by civil action pursuant to Section 234c of the Act, 42 U.S.C. 2282c.

The responses noted above, i.e., Reply to Notice of Violation, Statement as to payment of civil penalty(ies), and Answer to a Notice of Violation, should be addressed to: Director, Office of Enforcement, U.S. Nuclear Regulatory Commission, One White Flint North, 11555 Rockville, MD 20852-2738, with a copy to the Regional Administrator, U.S., Nuclear Regulatory Commission, Region II, 245 Peachtree Center Ave. N.E., Suite 1200, Atlanta, GA 30303, and the U.S. Nuclear Regulatory Commission, ATTN: Document Control Desk, Washington, DC 20555-0001, and a copy to the NRC Resident Inspector at the facility that is the subject of this Notice."

Your response will be made available electronically for public inspection in the NRC Public Document Room or in the NRC's Agencywide Documents Access and Management System (ADAMS), accessible from the NRC Web site at http://www.nrc.gov/reading-rm/adams.html. To the extent possible, your response should not include any personal privacy or proprietary information. If personal privacy or proprietary information is necessary to provide an acceptable

C3-87

FPSC EXH No. 5
03/18/2024

ADMITTED

C3-190

response, then please provide a bracketed copy of your response that identifies the information that should be protected and a redacted copy of your response that deletes such information. If you request that such material is withheld from public disclosure, you must specifically identify the portions of your response that you seek to have withheld and provide in detail the bases for your claim (e.g., explain why the disclosure of information will create an unwarranted invasion of personal privacy or provide the information required by 10 CFR 2.390(b) to support a request for withholding confidential commercial or financial information). If safeguards information is necessary to provide an acceptable response, please provide the level of protection described in 10 CFR 73.21.

In accordance with 10 CFR 19.11, you may be required to post this Notice within two working days of receipt.

Dated this 12th day of September, 2019

C3-88

FPSC EXH No. 5
03/18/2024

ADMITTED

C3-181

UNITED STATES
NUCLEAR REGULATORY COMMISSION
REGION II
245 PEACHTREE CENTER AVENUE N.E., SUITE 1200
ATLANTA, GEORGIA 30303-1200

April 6, 2021

EA-20-043
EA-20-150

Mr. Don Moul, Executive Vice President
Nuclear Division and Chief Nuclear Officer
Florida Power & Light Company
Mail Stop: EX/JB
700 Universe Blvd.
Juno Beach, FL 33408

SUBJECT: TURKEY POINT NUCLEAR GENERATING STATION - NOTICE OF VIOLATION AND PROPOSED IMPOSITION OF CIVIL PENALTY – $150,000, NRC INSPECTION REPORT NOS. 05000250/2021090 AND 05000251/2021090; INVESTIGATION REPORT NOS. 2-2019-011 AND 2-2019-025; EXERCISE OF ENFORCEMENT DISCRETION

Dear Mr. Moul:

This letter is in reference to three apparent violations (AVs) identified as a result of two separate investigations completed by the Nuclear Regulatory Commission's (NRC) Office of Investigations (OI) concerning activities at Florida Power and Light Company's (FPL) Turkey Point Nuclear Generating Station (Turkey Point).

The first AV was related to an OI investigation completed on March 10, 2020. The investigation was conducted to determine if three mechanics at Turkey Point Unit 3 deliberately falsified information in a work order package associated with the January 23, 2019, inspection and maintenance of a safety-related check valve. The details of the AV and investigation are documented in NRC Inspection Report 05000250/2020011 and 05000251/2020011, issued on July 23, 2020 (Agencywide Documents Access and Management System (ADAMS) Accession No. ML20205L316). The AV involved the recording of inaccurate/incomplete information associated with maintenance and inspection of a safety-related auxiliary feedwater check valve, contrary to the requirements of 10 CFR 50.9(a), "Completeness and Accuracy of Information."

On March 3, 2021, a pre-decisional enforcement conference (PEC) was conducted via teleconference at FPL's request, with members of your staff to discuss the AV. The conference was closed to public observation because the subject matter was related to an OI report, the details of which have not been publicly released. At the conference, FPL accepted the violation as described in the inspection report including the willful aspects, provided its assessment of the significance of the violation, discussed the root and contributing causes, provided additional circumstances regarding identification of the violation, and discussed several corrective actions taken in response to the incident.

C3-89

FPSC EXH No. 5
03/18/2024
ADMITTED
D. Moul

OS-192

The second and third AVs were related to an OI investigation completed on November 10, 2020. The investigation was conducted to determine whether two instrumentation and control (I&C) technicians at Turkey Point deliberately provided incomplete or inaccurate information in maintenance records, and whether the I&C technicians, an I&C Supervisor, and the I&C Department Head deliberately failed to immediately notify the main control room of a mispositioned plant component, as required by plant procedures. The mispositioned plant component incident occurred on July 10, 2019, when I&C technicians mistakenly began maintenance on a pressure switch associated with the Unit 3C charging pump instead of the 4C charging pump. The details of the second and third AV and the OI investigation are documented in NRC Inspection Report 05000250/2021011 and 05000251/2021011, issued on February 4, 2021 (ADAMS Accession No. ML21036A158). The two AVs involved: (1) the failure to comply with plant procedure OP-AA-100-1002, "Plant Status Control Management," as required by 10 CFR Part 50, Appendix B, Criterion V, "Instructions, Procedures, and Drawings," when the I&C Supervisor and Department Head failed to notify the main control room of a mispositioned plant component; and (2) the failure of two I&C technicians to maintain a complete and accurate record of maintenance performed on the 4C charging pump, contrary to the requirements of 10 CFR 50.9(a), "Completeness and Accuracy of Information."

In response to the second and third AVs, FPL provided a written response by letter dated March 5, 2021. FPL agreed that both violations occurred as documented in the inspection report and agreed with the willful aspects. FPL provided additional details regarding the seriousness of the incident, its assessment of the significance, root causes, circumstances regarding identification of the violation and corrective actions. FPL's letter also suggested that the NRC exercise its discretion to reduce the severity level and civil penalty, if any, to acknowledge FPL's initial identification of the issues and its corrective actions stemming from the previous event of January 23, 2019. FPL noted that these corrective actions helped to identify the events associated with the second OI report and pointed out the very low safety significance of those events and FPL's prompt and comprehensive additional corrective actions.

Based on the information developed during the investigations, the information that FPL provided during the PEC, and the information provided by FPL in its written response of March 5, 2021, the NRC has determined that three violations of NRC requirements occurred. The violations are cited in the enclosed Notice of Violation and Proposed Imposition of Civil Penalty (Notice) and the circumstances surrounding these violations are described in detail in the above referenced inspection reports.

The first violation documented in the Notice occurred on January 23, 2019, when mechanics assigned to work on auxiliary feedwater check valve AFWU-3-017 recorded inaccurate information in work order 40542353. The NRC concluded that the actions of FPL staff were deliberate and caused FPL to be in violation of 10 CFR 50.9(a), "Completeness and Accuracy of Information."

The second and third violations documented in the Notice occurred on July 10, 2019, after I&C technicians mistakenly began maintenance on the wrong charging pump. Upon being notified by the I&C technicians, the I&C Supervisor and the I&C Department Head deliberately failed to immediately notify the Operations Shift Manager that I&C technicians assigned to work on the 4C charging pump inadvertently manipulated a pressure switch on the 3C charging pump. These actions were in violation of 10 CFR 50, Appendix B, Criterion V, "Instructions, Procedures, and Drawings," and FPL plant procedure OP-AA-100-1002, "Plant Status Control Management." The third violation involved two FPL I&C employees who deliberately maintained information recorded in the PS-4-201C Work Order Task Description (WOTD) and

OS-190

FPSC EXH No. 5
03/18/2024
ADMITTED
D. Moul

C3-193

Breaker/Switch/Valve Manipulation Form (Form 747) associated with Work Order (WO) Package 40632818-01 that was not complete and accurate in all material respects, as required by 10 CFR 50.9(a), "Completeness and Accuracy of Information." Specifically, information recorded on both documents was inaccurate because it reflected work performed on the Unit 4C charging pump pressure switch (PS-4-201C), when in fact no work was performed on PS-4-201C.

The violations did not cause any actual consequences to the plant. Regarding the violation occurring on January 23, 2019, FPL confirmed that the safety related auxiliary feedwater check valve was not degraded, had not negatively impacted plant operation, and FPL promptly completed the WO after the incident without any impact to the plant. Regarding the two violations occurring on July 10, 2019, FPL's Unit 3 licensed main control room operators responded promptly and in accordance with plant procedures to the charging pump trip by placing another charging pump in service. The two violations did not result in a plant transient and caused only minimal impact to plant operation.

However, the potential consequences of the three violations, when viewed individually and together, are significant and concerning to the NRC. All three violations involved deliberate misconduct on the part of multiple individuals. One violation (Violation No. 2 of the Notice) was directly attributable to individuals in a supervisory and/or management role. As discussed in the NRC Enforcement Policy, willful violations are of particular concern because the NRC's regulatory program is based on licensees and their contractors, employees, and agents acting with integrity and communicating with candor. In light of the above and because the violations are interrelated to a common cause involving integrity issues among multiple FPL staff and inadequate management oversight, these violations have been categorized as a Severity Level III problem in accordance with the NRC Enforcement Policy.

In accordance with the Enforcement Policy, a base civil penalty in the amount of $150,000 is considered for a Severity Level III violation or problem. Because the violations were willful, the NRC considered whether credit was warranted for *Identification* and *Corrective Action* in accordance with the civil penalty assessment process in Section 2.3.4 of the Enforcement Policy.

At the PEC of March 3, 2021, FPL highlighted that the violation of January 23, 2019, associated with inaccurate information in work order 40542353 would have remained undetected but for FPL's efforts to thoroughly investigate the issue to ensure that all work steps were completed in all respects. FPL also noted that its investigation expanded well beyond the original concern brought forth by NRC, resulting in FPL's identification of the falsified maintenance record. In reviewing the information presented by FPL at the PEC, and related investigation and inspection information, the NRC agrees with FPL that credit should be granted for the civil penalty assessment factor of *Identification*. Regarding the two violations associated with the second OI report, identification credit is warranted to reflect FPL's efforts to identify both violations occurring on July 10, 2019, within hours of the occurrence of the incident. Based on the above, the NRC concluded that credit is warranted for the civil penalty assessment factor of *Identification* for the Severity Level III problem documented in the Notice.

Regarding the civil penalty assessment factor of *Corrective Action*, at the PEC of March 3, 2021, FPL identified a number of site-specific corrective actions taken in response to Violation No. 1 of the Notice, including but not limited to: (1) FPL performed an immediate investigation into the incident; (2) FPL reviewed safety-related work completed by the Turkey Point Maintenance department for the three months prior to the January 2019 incident, and reviewed

C3-91

FPSC EXH No. 5
03/18/2024
ADMITTED
D. Moul

safety-related work completed by the three mechanics involved; (3) Turkey Point managers held department meetings with all employees in 2019, including contractors, to address the importance of integrity and trust; (4) FPL completed training with all Turkey Point employees covering 10 CFR 50.5 and 10 CFR 50.9 and the consequences of violating those requirements in 2019; (5) Turkey Point leadership completed a case study on the incident of January 23, 2019; and (6) FPL denied site access and issued disciplinary actions for the individuals involved. The NRC concluded that these actions reflect an appropriate, graduated approach to address causes known by FPL to exist at that time, and were commensurate with the significance of the January 23, 2019, incident. As such, credit is warranted for the civil penalty assessment factor of *Corrective Action* for this violation.

In response to the incident of July 10, 2019, and as documented in its written response of March 5, 2021, FPL conducted several layers of inquiry upon becoming aware of the incident, including but not limited to: (1) denying the individuals' unescorted site access, terminating their employment, and immediately having the former Site Vice President share the incident in small sessions with station personnel; (2) performing a Common Cause Evaluation (CCE) of the incident, including an assessment of the extent of condition by reviewing randomly selected work activities for Turkey Point's Security, Radiation Protection, Operations, and Chemistry departments; (3) updating fleet procedure AD-AA-103, "Nuclear Safety Culture Program," to include the Security and Emergency Preparedness Departments which is in addition to the already performed semi-annual verifications of randomly selected work activities across the NextEra fleet for the Maintenance , Operations, Radiation Protection and Chemistry Departments; (4) revising the Turkey Point Department Plan of the Day agendas to include integrity discussions; (5) developing and implementing leadership training for all supervisors, managers, General Maintenance Leaders and Nuclear Watch Engineers on identification of potential integrity events and the actions to take in response to potential integrity events; (6) issuing a fleet-wide communication from the Chief Nuclear Officer (CNO) regarding expectations for accurately performing and documenting work activities, focusing on the message, "Your Signature Is Your Word," followed by a series of communications from the CNO focused on Nuclear Safety Culture (NSC) topics, including the importance of integrity and the meaning of signatures on signed documents; (7) implementing an annual training requirement for all nuclear fleet employees regarding the "Value of Your Signature," which includes the importance of providing complete and accurate information to the NRC (10 CFR 50.9), deliberate misconduct (10 CFR 50.5), the potential consequences for violations of 10 CFR 50.5 and 10 CFR 50.9, the need to report errors to the control room and/or management, what it means to sign a quality record, and understanding electronic signatures; (8) revising the nuclear fleet's corrective action program condition report screening procedure, PI-AA-104-1000, to require causal analysis for substantiated NSC events; and (9) revising the NSC program procedure, AD-AA-103, to require the NSC Monitoring Panel to review of internal evaluations of substantiated integrity events and all NRC violations related to NSC. Based on the above, the NRC concluded that credit is warranted for the civil penalty assessment factor of *Corrective Action* for Violations No. 2 and 3 of the Notice, and for the Severity Level III problem.

The NRC normally would not propose a civil penalty for this Severity Level III problem, because credit is warranted for the civil penalty assessment factors of *Identification* and *Corrective Action*. However, the circumstances of the three violations are very concerning to the NRC for several reasons. In this case, a total of seven FPL employees engaged in deliberate misconduct involving two separate incidents, within approximately a six-month time period, which is indicative of a much wider NSC concern. As also mentioned above, willful violations are of particular concern because the NRC's regulatory program is based on licensees and their contractors, employees, and agents acting with integrity and communicating with candor. The

C3-194
C3-192

FPSC EXH No. 5
03/18/2024

ADMITTED

C3-95

NRC also notes that FPL's supervisory oversight was not sufficient to instill an appropriate NSC at that time, and in fact supervisors also engaged in deliberate misconduct in the second and third violations. Finally, the NRC considers the deliberate behavior of an I&C supervisor and an I&C Department Head, who initially attempted to hide the incident and influenced others within the I&C department to participate in the concealment of the maintenance error of July 10, 2019, to be particularly concerning.

Consistent with Enforcement Policy Section 3.6, Use of Discretion in Determining the Amount of a Civil Penalty, the NRC has the flexibility to exercise enforcement discretion to propose a base civil penalty where application of the civil penalty assessment factors would otherwise result in zero penalty. In this case, the circumstances of the three violations reflect particularly poor licensee performance in multiple areas, including but not limited to the lack of integrity of multiple FPL employees, the absence of effective management oversight and appropriate work controls within the Maintenance department, the deliberate concealment of the violation by two FPL supervisors/managers, and a less than adequate NSC at that time. Additionally, one of the violations that occurred on July 19, 2019 (i.e., the 10 CFR 50.9 violation), is a repeat of the same type of violation that occurred on January 23, 2019, when multiple FPL employees also deliberately falsified plant records, and all three violations are related to a common root cause. As such, the NRC has concluded that the exercise of enforcement discretion is warranted to propose a base civil penalty in the amount of $150,000.

Therefore, I have been authorized, after consultation with the Director, Office of Enforcement, to issue the enclosed Notice of Violation and Proposed Imposition of Civil Penalty (Notice) in the base amount of $150,000 for the SL III problem.

If you disagree with this enforcement sanction, you may deny the violation, as described in the Notice, or you may request alternative dispute resolution (ADR) with the NRC in an attempt to resolve this issue. ADR is a general term encompassing various techniques for resolving conflicts using a neutral third party. The technique that the NRC has decided to employ is mediation. Mediation is a voluntary, informal process in which a trained neutral (the "mediator") works with parties to help them reach resolution. If the parties agree to use ADR, they select a mutually agreeable neutral mediator who has no stake in the outcome and no power to make decisions. Mediation gives parties an opportunity to discuss issues, clear up misunderstandings, be creative, find areas of agreement, and reach a final resolution of the issues. Additional information concerning the NRC's ADR program can be found at http://www.nrc.gov/about-nrc/regulatory/enforcement/adr.html.

The Institute on Conflict Resolution (ICR) at Cornell University has agreed to facilitate the NRC's program as a neutral third party. If you are interested in pursuing this issue through the ADR program, please contact: (1) the ICR at (877) 733-9415; and (2) Mr. David Dumbacher at (404) 997-4628 within 10 days of the date of this letter. You may also contact both ICR and Mr. Dumbacher for additional information. Your submitted signed agreement to mediate using the NRC ADR program will stay the 30-day time period for payment of the civil penalty and the required written response, as identified in the enclosed notice, until the ADR process is completed.

The NRC has concluded that information regarding (1) the reason for the violations; (2) the corrective steps that have been taken and the results achieved; (3) the corrective steps that will be taken; and (4) the date when full compliance was achieved was adequately addressed at the

C3-93

FPSC EXH No. 5
03/18/2024

ADMITTED

C3-196

pre-decisional enforcement conference and in FPL's letter of March 5, 2021. Therefore, you are not required to respond to this letter unless the description therein does not accurately reflect your corrective actions or your position. In that case, or if you choose to provide additional information, you should follow the instructions specified in the enclosed Notice.

For administrative purposes, this letter is issued as NRC IR 05000250/2021090 and 05000251/2021090. AV 05000250/2020011-01 has been re-designated as Notice of Violation (NOV) 05000250/2020011-01. AV 05000250,05000251/2021011-01 has been re-designated as NOV 05000250,05000251/2021011-01. AV 05000250,05000251/2021011-02 has been re-designated as NOV 05000250,05000251/2021011-02.

In accordance with 10 CFR 2.390 of the NRC's "Agency Rules of Practice and Procedure," a copy of this letter, its enclosures, and your response, if you choose to provide one, will be made available electronically for public inspection in the NRC Public Document Room and from the NRC's Agencywide Documents Access and Management System (ADAMS), accessible from the NRC Web site at http://www.nrc.gov/reading-rm/adams.html. To the extent possible, your response should not include any personal privacy, proprietary, or safeguards information so that it can be made available to the Public without redaction. The NRC also includes significant enforcement actions on its Web site at http://www.nrc.gov/reading rm/doc collections/enforcement/actions/.

If you have any questions concerning this matter, please contact Mr. David Dumbacher of my staff at (404) 997-4628.

Sincerely,

/RA/

Laura A. Dudes
Regional Administrator

Docket Nos.: 05000250, 05000251
License Nos.: DPR-31, DPR-41

Enclosures:
1. Notice of Violation and Proposed Imposition of Civil Penalty
2. NUREG/BR-0254 Payment Methods

cc: Distribution via ListServ

C3-94

FPSC EXH No. 5
03/18/2024

ADMITTED

C3-197

D. Moul 5

SUBJECT: TURKEY POINT NUCLEAR GENERATING STATION - NOTICE OF VIOLATION AND PROPOSED IMPOSITION OF CIVIL PENALTY – $150,000, NRC INSPECTION REPORT NOS. 05000250/2021090 AND 05000251/2021090; INVESTIGATION REPORT NOS. 2-2019-011 AND 2-2019-025; EXERCISE OF ENFORCEMENT DISCRETION Dated April 6, 2021

DISTRIBUTION:

M. Doane, OEDO
Region II Regional Coordinator, OEDO
A. Veil, NRR
P. Moulding, OGC
M. Lemoncelli, OGC
D. Roberts, OEDO
R. Laufer, SECY
D. Decker, OCA
A. Moreno, OCA
All Regions Enforcement Coordinators
H. Harrington, OPA
T. Higgs, HQ:OI
A. Echavarria, HQ:OI
R. Feitel, OIG
B. Hughes, NRR
M. Simon, OGC
A. Vegel, OE
P. Snyder, OE
D. Jones, OE
L. Dudes, RII
J. Munday, RII
M. Miller, RII
M. Franke, RII
B. Venkataraman, RII
D. Dumbacher, RII
D. Orr, RII
R. Hannah, RII
D. Gasperson, RII
J. Pelchat, RII
S. Sparks, RII
S. Price, RII
M. Kowal, RII
L. Gibson, RII
S. Luina, RII OI
OEMAIL Resource
RidsNrrDirs Enforcement Resource
PUBLIC

ADAMS Accession No. ML21096A096

OFFICE	RII/DRP	RII/DRP	RII/DRP	RII/EICS	RII/ORA	OE
NAME	B.Venkataraman	T.Inverso	M.Miller	M.Kowal	S.Price	J. Peralta
DATE	3/24/2021	3/23/2021	3/23/2021	3/23/2021	3/25/2021	3/31/2021
OFFICE	OGC	NRR	RII/ORA			
NAME	M. Simon	R. Felts	L. Dudes			
DATE	3/31/2021	3/29/2021	4/6/2021			

OFFICIAL RECORD COPY

C3-95

FPSC EXH No. 5
03/18/2024

ADMITTED

C3-198

NOTICE OF VIOLATION
AND
PROPOSED IMPOSITION OF CIVIL PENALTY

Florida Power and Light Company
Turkey Point Nuclear Generating Station
Units 3 and 4

Docket Nos.: 50-250, 50-251
License Nos.: DPR-31, DRP-41
EA-20-043, EA-20-150

During an NRC investigation completed on March 10, 2020, and an NRC investigation completed on November 10, 2020, violations of NRC requirements were identified. In accordance with the NRC Enforcement Policy, the NRC proposes to impose a civil penalty of $150,000 pursuant to Section 234 of the Atomic Energy Act of 1954, as amended (Act), 42 U.S.C. 2282, and 10 CFR 2.205. The particular violations and associated civil penalty are set forth below:

1. 10 CFR 50.9(a), "Complete and Accuracy of Information" states, in part, that information required by the Commission's regulations, orders, or license conditions to be maintained by the licensee shall be complete and accurate in all material respects.

   Contrary to the above, on January 23, 2019, the licensee maintained information recorded in steps 4.6 and 4.11 of Work Order (WO) 40542353 that was not complete and accurate in all material respects. Specifically, step 4.6 of the WO was marked complete, yet the work was not performed using the Check Valve Data Sheet (CVDS). Additionally, for step 4.11, inaccurate information was recorded regarding the tools used in the Journeyman Work Report and inaccurate measurement values were recorded in the CVDS. Documents associated with WO 40542353 are records that the licensee is required to maintain pursuant to 10 CFR Part 50, Appendix B, Criterion XVII, "Quality Assurance Records." Records of inspections of safety-related equipment are material to the NRC because they indicate whether the licensee is performing quality-related and safety-related activities in accordance with its operating procedures and NRC regulations.

2. 10 CFR Part 50 Appendix B, Criterion V, "Instructions, Procedures, and Drawings" states that activities affecting quality shall be prescribed by documented instructions, procedures, or drawings, of a type appropriate to the circumstances and shall be accomplished in accordance with these instructions, procedures, or drawings.

   Procedure OP-AA-100-1002, "Plant Status Control Management" (an FPL implemented safety-related procedure), Step 3.6.7, states, in part, that site personnel are to immediately notify the Operations Shift Manager of any inadvertent bumping or mispositioning of plant components.

   Contrary to the above, on July 10, 2019, the reporting of a mispositioned plant component, an activity affecting quality, was not accomplished in accordance with procedure OP-AA-100-1002. Specifically, site personnel failed to immediately notify the Operations Shift Manager that Instrumentation and Controls (I&C) technicians assigned to work on the 4C charging pump inadvertently manipulated a pressure switch on the Unit 3C charging pump. The I&C technicians, I&C Supervisor and I&C Department Head had several opportunities to report the human performance error to the control room and failed to do so.

FPSC EXH No. 5
03/18/2024
ADMITTED

C3-199

3. 10 CFR 50.9(a), “Complete and Accuracy of Information” states, in part, that information required by the Commission’s regulations, orders, or license conditions to be maintained by the licensee shall be complete and accurate in all material respects.

   Contrary to the above, on July 10, 2019, the licensee maintained information recorded in the in the Pressure Switch (PS) PS-4-201C Work Order Task Description (WOTD) and Breaker/Switch/Valve Manipulation Form (Form 747) associated with WO Package 40632818-01 that was not complete and accurate in all material respects. Specifically, information recorded on both documents was inaccurate because it reflected work performed on the Unit 4C charging pump pressure switch (PS-4-201C), when in fact no work was performed on PS-4-201C. Additionally, the WO contained no documentation or notes explaining that the steps were completed on the wrong component. Documents associated with WO Package 40632818-01 for the safety-related Unit 4C charging pump are records that the licensee is required to maintain pursuant to 10 CFR Part 50, Appendix B, Criterion XVII, “Quality Assurance Records.” Records of maintenance of safety-related equipment are material to the NRC because they indicate whether the licensee is performing quality-related and safety-related activities in accordance with its operating procedures and NRC regulations.

This is a Severity Level III problem (Enforcement Policy Sections 2.2.1.d, 6.1, 6.9).
Civil Penalty - $150,000.

The NRC has concluded that information regarding the reason for the violations, the corrective actions taken and planned to correct the violations and prevent recurrence and the date when full compliance was achieved was adequately addressed at the March 3, 2021, predecisional enforcement conference and in FPL’s written response dated March 5, 2021. However, if the description therein does not accurately reflect your position or your corrective actions, you are required to submit a written statement or explanation pursuant to 10 CFR 2.201 within 30 days of the date of the letter transmitting this Notice of Violation. In that case, or if you choose to respond, clearly mark your response as a ‘Reply to a Notice of Violation – EA-20-043, EA-20-150’, and send it to the Director, Office of Enforcement, U.S. Nuclear Regulatory Commission, One White Flint North, 11555 Rockville, MD 20852-2738, with a copy to the Regional Administrator, U.S., Nuclear Regulatory Commission, Region II, 245 Peachtree Center Avenue, N. E., Suite 1200, Atlanta, GA, 30303, and the NRC Resident Inspector at the facility that is the subject of this Notice, and the Document Control Desk, Washington, DC 20555-0001.

FPL may pay the civil penalty proposed above in accordance with NUREG/BR-0254 and by submitting to the Director, Office of Enforcement, U.S. Nuclear Regulatory Commission, a statement indicating when and by what method payment was made, or may protest imposition of the civil penalty in whole or in part, by a written answer addressed to the Director, Office of Enforcement, U.S. Nuclear Regulatory Commission, within 30 days of the date of this Notice. Should FPL fail to answer within 30 days of the date of this Notice, the NRC will issue an order imposing the civil penalty. Should FPL elect to file an answer in accordance with 10 CFR 2.205 protesting the civil penalty, in whole or in part, such answer should be clearly marked as an "Answer to a Notice of Violation" and may: (1) deny the violations listed in this Notice, in whole or in part; (2) demonstrate extenuating circumstances; (3) show error in this Notice; or (4) show other reasons why the penalty should not be imposed. In addition to protesting the civil penalty in whole or in part, such answer may request remission or mitigation of the penalty.

In requesting mitigation of the proposed penalty, the response should address the factors discussed in Section 2.3.4 of the Enforcement Policy. Any written answer addressing these

C3-97

FPSC EXH No. 5
03/18/2024
ADMITTED

factors pursuant to 10 CFR 2.205 should be set forth separately from the statement or explanation provided pursuant to 10 CFR 2.201, but may incorporate parts of the 10 CFR 2.201 reply by specific reference (e.g., citing page and paragraph numbers) to avoid repetition. The attention of FPL is directed to the other provisions of 10 CFR 2.205 regarding the procedure for imposing a civil penalty.

Upon failure to pay any civil penalty which subsequently has been determined in accordance with the applicable provisions of 10 CFR 2.205 to be due, this matter may be referred to the Attorney General, and the penalty, unless compromised, remitted, or mitigated, may be collected by civil action pursuant to Section 234c of the Act, 42 U.S.C. 2282c.

The responses noted above, i.e., Reply to Notice of Violation, Statement as to Payment of Civil Penalty, and Answer to a Notice of Violation, should be addressed to: Anton Vegel, Director, Office of Enforcement, U.S. Nuclear Regulatory Commission, One White Flint North, 11555 Rockville Pike, Rockville, MD 20852-2738, with a copy to the Regional Administrator, U.S. Nuclear Regulatory Commission, Region II, 245 Peachtree Center Avenue, N. E., Suite 1200, Atlanta, GA, 30303, and the NRC Resident Inspector at the facility that is subject to this Notice, and the Document Control Center, Washington, DC 20555-0001.

If you choose to respond, your response will be made available electronically for public inspection in the NRC Public Document Room or in the NRC's Agencywide Documents Access and Management System (ADAMS), accessible from the NRC Web site at http://www.nrc.gov/reading-rm/adams.html. To the extent possible, your response should not include any personal privacy or proprietary information so that it can be made available to the public without redaction. If personal privacy or proprietary information is necessary to provide an acceptable response, then please provide a bracketed copy of your response that identifies the information that should be protected and a redacted copy of your response that deletes such information. If you request that such material is withheld from public disclosure, you must specifically identify the portions of your response that you seek to have withheld and provide in detail the bases for your claim (e.g., explain why the disclosure of information will create an unwarranted invasion of personal privacy or provide the information required by 10 CFR 2.390(b) to support a request for withholding confidential commercial or financial information). If safeguards information is necessary to provide an acceptable response, please provide the level of protection described in 10 CFR 73.21.

In accordance with 10 CFR 19.11, you may be required to post this Notice within two working days of receipt.

Dated this 6th day of April 2021.

C3-201

FPSC EXH No. 5
03/18/2024
ADMITTED

UNITED STATES
NUCLEAR REGULATORY COMMISSION
REGION II
245 PEACHTREE CENTER AVENUE N.E., SUITE 1200
ATLANTA, GEORGIA 30303-1200

May 7, 2021

Mr. Don Moul
Executive Vice President, Nuclear Division and Chief Nuclear Officer
Florida Power & Light Company
Mail Stop: EX/JB
700 Universe Blvd.
Juno Beach, FL 33408

SUBJECT: TURKEY POINT UNITS 3 & 4 – INTEGRATED INSPECTION REPORT 05000250/2021001 AND 05000251/2021001 AND ASSESSMENT FOLLOW-UP LETTER

Dear Mr. Moul:

On March 31, 2021, the U.S. Nuclear Regulatory Commission (NRC) completed an inspection at Turkey Point Units 3 & 4 and discussed the results of this inspection with Mr. Michael Pearce and other members of your staff. The results of this inspection are documented in the enclosed report.

One finding of very low safety significance (Green) is documented in this report. This finding involved a violation of NRC requirements. One Severity Level IV violation without an associated finding is documented in this report. We are treating these violations as non-cited violations (NCVs) consistent with Section 2.3.2 of the Enforcement Policy.

If you contest the violations or the significance or severity of the violations documented in this inspection report, you should provide a response within 30 days of the date of this inspection report, with the basis for your denial, to the U.S. Nuclear Regulatory Commission, ATTN: Document Control Desk, Washington, DC 20555-0001; with copies to the Regional Administrator, Region II; the Director, Office of Enforcement; and the NRC Resident Inspector at Turkey Point Units 3 & 4 .

If you disagree with a cross-cutting aspect assignment in this report, you should provide a response within 30 days of the date of this inspection report, with the basis for your disagreement, to the U.S. Nuclear Regulatory Commission, ATTN: Document Control Desk, Washington, DC 20555-0001; with copies to the Regional Administrator, Region II; and the NRC Resident Inspector at Turkey Point Units 3 & 4 .

As a result of its quarterly review of plant performance, which was completed on March 31, 2021, the NRC updated its assessment of Turkey Point Nuclear Plant Unit 3. The NRC's evaluation consisted of a review of performance indicators and inspection results. This letter informs you of the NRC's assessment of your facility. This letter supplements, but does not supersede, the annual assessment letter issued on March 3, 2021.

C3-99

FPSC EXH No. 5
03/18/2024
D. Moul
ADMITTED

The NRC's review of Turkey Point Nuclear Plant Unit 3 identified that the Unplanned Scrams per 7000 Critical Hours performance indicator has crossed the green-to-white threshold. This was due to four unplanned scams that occurred on August 17, 2020, August 19, 2020, August 20, 2020, and March 1, 2021. The NRC will be in contact to discuss specific planning and scheduling activities regarding this performance indicator and the anticipated 95001 inspection.

This letter, its enclosure, and your response (if any) will be made available for public inspection and copying at http://www.nrc.gov/reading-rm/adams.html and at the NRC Public Document Room in accordance with Title 10 of the *Code of Federal Regulations* 2.390, "Public Inspections, Exemptions, Requests for Withholding."

Please contact Mr. David Dumbacher at 404-997-4628 with any questions you have regarding this letter.

Sincerely,

/RA/

Mark S. Miller, Director,
Division of Reactor Projects

Docket Nos. 05000250 and 05000251
License Nos. DPR-31 and DPR-41

Enclosure:
As stated

cc w/ encl: Distribution via LISTSERV®

FPSC EXH No. 5
03/18/2024
D. Moul
ADMITTED

SUBJECT: TURKEY POINT UNITS 3 & 4 – INTEGRATED INSPECTION REPORT 05000250/2021001 AND 05000251/2021001 AND ASSESSMENT FOLLOW-UP LETTER dated May 7, 2021

DISTRIBUTION:
M. Kowal, RII
S. Price, RII
L. Gibson, RII
RidsNrrPMTurkeyPoint Resource
RidsNrrDro Resource
PUBLIC

ADAMS ACCESSION NUMBER: **ML21127A186**

X SUNSI Review		X Non-Sensitive ☐ Sensitive		X Publicly Available ☐ Non-Publicly Available	
OFFICE	RII/DRP	RII/DRP	RII/DRP	RII/DRP	RII/DRP
NAME	R. Reyes	D. Orr	D. Dumbacher	J. Hamman	M. Miller
DATE	05/05/2021	05/05/2021	05/05/2021	05/05/2021	05/07/2021

OFFICIAL RECORD COPY

FPSC EXH No. 5
03/18/2024

ADMITTED

C3-204

U.S. NUCLEAR REGULATORY COMMISSION
Inspection Report

Docket Numbers:	05000250 and 05000251
License Numbers:	DPR-31 and DPR-41
Report Numbers:	05000250/2021001 and 05000251/2021001
Enterprise Identifier:	I-2021-001-0081
Licensee:	Florida Power & Light Company
Facility:	Turkey Point Units 3 & 4
Location:	Homestead, FL 33035
Inspection Dates:	January 01, 2021 to March 31, 2021
Inspectors:	C. Fontana, Emergency Preparedness Inspector D. Orr, Senior Resident Inspector R. Reyes, Resident Inspector S. Sanchez, Senior Emergency Preparedness Inspector J. Walker, Emergency Response Inspector
Approved By:	David E. Dumbacher, Chief Reactor Projects Branch 3 Division of Reactor Projects

C3-102

FPSC EXH No. 5
03/18/2024

ADMITTED

C3-205

SUMMARY

The U.S. Nuclear Regulatory Commission (NRC) continued monitoring the licensee's performance by conducting an integrated inspection at Turkey Point Units 3 & 4 , in accordance with the Reactor Oversight Process. The Reactor Oversight Process is the NRC's program for overseeing the safe operation of commercial nuclear power reactors. Refer to https://www.nrc.gov/reactors/operating/oversight.html for more information.

List of Findings and Violations

Failure to Maintain the Effectiveness of the Emergency Plan			
Cornerstone	Severity	Cross-Cutting Aspect	Report Section
Not Applicable	Severity Level IV NCV 05000250,05000251/2021001-01 Open	Not Applicable	71114.04
The inspectors identified a Severity Level IV (SL-IV) non-cited violation (NCV) of Title 10 of the Code of Federal Regulations (CFR), Part 50.54(q)(2), for failure to maintain the effectiveness of the Turkey Point Nuclear Station (TPN) Emergency Plan (E-Plan). Specifically, the licensee had not revised the E-Plan for a change to the number of Alert and Notification System (ANS) sirens.			

Failure to Correctly Verify the Component as Instructed in Work Order			
Cornerstone	Significance	Cross-Cutting Aspect	Report Section
Mitigating Systems	Green NCV 05000250,05000251/2021001-02 Open/Closed	[H.12] - Avoid Complacency	71152
A self-revealed Green Non-Cited Violation (NCV) of 10 CFR, Part 50, Appendix B, Criterion V, "Instructions, Procedures, and Drawings," was identified for the failure to correctly verify a component specified in a work order (WO). Specifically, instrument and control (I&C) technicians did not follow the proper verification steps in WO 40632818 and incorrectly conducted work on the 3C charging pump.			

Additional Tracking Items

Type	Issue Number	Title	Report Section	Status
URI	05000250/2021001-03	Unit 3 Automatic Reactor Trip due to Reactor Trip Breaker Cell Switch Malfunction	71153	Open
URI	05000250/2021001-04	Inadvertent Opening of 3A Steam Generator Feedwater Pump Recirculation Valves Causes a Rapid Decrease in Unit 3 Steam Generator Water Levels	71153	Open
LER	05000250/2020-002-00	LER 2020-002-00 for Turkey Point Unit 3 Manual Reactor Trip in Response to High	71153	Closed

C3-103

FPSC EXH No. 5
03/18/2024

ADMITTED

C3-206

		Steam Generator Level following Inadvertent Opening of Feedwater Heater Bypass Valve		
LER	05000250/2020-002-01	LER 2020-002-01 for Turkey Point, Unit 3, Manual Reactor Trip in Response to High Steam Generator Level following Inadvertent Opening of Feedwater Heater Bypass Valve (Rev 1)	71153	Closed
LER	05000250/2020-005-00	LER 2020-005-00 for Turkey Point Unit 3, Technical Specification Action Not Taken for Unrecognized Inoperable Source Range Channel	71153	Closed
LER	05000250/2020-005-01	LER 2020-005-01 for Turkey Point, Unit 3, Technical Specification Action Not Taken for Unrecognized Inoperable Source Range Channel (Rev 1)	71153	Closed

C3-104

FPSC EXH No. 5
03/18/2024

ADMITTED

C3-207

PLANT STATUS

Unit 3 began the inspection period at 55% of rated thermal power to facilitate main condenser water box tube repairs. Unit 3 was returned to rated thermal power on January 3, but was down-powered to 52% on February 2, due to high sodium concentrations recurring in all three steam generators. Unit 3 was returned to rated thermal power on February 9, after the licensee completed additional main condenser tube inspections and plugging to eliminate the source of sodium contamination in the condensate system. On March 1, Unit 3 experienced an automatic reactor trip at the conclusion of a routine test of the reactor protection system (RPS). The licensee determined a malfunction of the B-train reactor trip breaker cubicle cell switch during the RPS test restoration caused the reactor trip. The cell switch was replaced and Unit 3 returned to rated thermal power on March 5. On March 24, Unit 3 was down-powered to 85% when the 3A steam generator feedwater pump recirculation valves to the main condenser failed open in response to feedwater flow instruments being isolated to repair a steam leak. Unit 3 was returned to rated thermal power on March 25, and remained at, or near, rated thermal power for the remainder of the inspection period.

Unit 4 began the inspection period at rated thermal power. Unit 4 was down-powered to 82% on March 16, and to 72% on March 17, to replace the 4A condensate pump motor. Unit 4 was returned to rated thermal power on March 24, and remained at or near rated thermal power for the remainder of the inspection period.

INSPECTION SCOPES

Inspections were conducted using the appropriate portions of the inspection procedures (IPs) in effect at the beginning of the inspection unless otherwise noted. Currently approved IPs with their attached revision histories are located on the public website at http://www.nrc.gov/reading-rm/doc-collections/insp-manual/inspection-procedure/index.html. Samples were declared complete when the IP requirements most appropriate to the inspection activity were met consistent with Inspection Manual Chapter (IMC) 2515, “Light-Water Reactor Inspection Program - Operations Phase.” The inspectors performed plant status activities described in IMC 2515, Appendix D, “Plant Status,” and conducted routine reviews using IP 71152, “Problem Identification and Resolution.” The inspectors reviewed selected procedures and records, observed activities, and interviewed personnel to assess licensee performance and compliance with Commission rules and regulations, license conditions, site procedures, and standards.

Starting on March 20, 2020, in response to the National Emergency declared by the President of the United States on the public health risks of the Coronavirus Disease 2019 (COVID-19), resident inspectors were directed to begin telework and to remotely access licensee information using available technology. During this time, the resident inspectors performed periodic site visits each week; conducted plant status activities as described in IMC 2515, Appendix D, “Plant Status”; observed risk-significant activities; and completed on-site portions of IPs. In addition, resident and regional baseline inspections were evaluated to determine if all or portions of the objectives and requirements stated in the IP could be performed remotely. If the inspections could be performed remotely, they were conducted per the applicable IP. In some cases, portions of an IP were completed remotely and on-site. The inspections documented below met the objectives and requirements for completion of the IP.

C3-105

FPSC EXH No. 5
03/18/2024

ADMITTED

C3-208

REACTOR SAFETY

71111.04 - Equipment Alignment

Partial Walkdown Sample (IP Section 03.01) (4 Samples)

The inspectors evaluated system configurations during partial walkdowns of the following systems/trains:

(1) 3B emergency diesel generator (EDG), and the 3A and 3B fuel oil transfer system alignment after fuel oil transfer operations and returning the 3B EDG back to an operable condition on January 11, 2021
(2) Unit 3 and Unit 4 auxiliary feedwater (AFW) systems, after testing train 1 and restoring systems back to an operable status with the A AFW pump aligned to train 1 and the B and C AFW pumps aligned to train 2 on January 19, 2021
(3) Unit 3 residual heat removal (RHR) system after 3-759A, 3A RHR heat exchanger outlet manual isolation valve, was cycled for 3-OSP-050.11, RHR/SI Manual Valve Operability Test, on February 16, 2021
(4) 3B intake cooling water (ICW) and component cooling water (CCW) headers while the 3A ICW and CCW headers were out of service for maintenance on February 25, 2021

71111.05 - Fire Protection

Fire Area Walkdown and Inspection Sample (IP Section 03.01) (7 Samples)

The inspectors evaluated the implementation of the fire protection program by conducting a walkdown and performing a review to verify program compliance, equipment functionality, material condition, and operational readiness of the following fire areas:

(1) Unit 3 and Unit 4 EDG buildings, (fire zones (FZs) 072, 073, 133 and 138) on January 05, 2021
(2) 3B, 4A and 4B RHR pump rooms (FZs 013, 015 and 016) on January 11, 2021
(3) Unit 3 and Unit 4 refueling water storage tank areas (FZ 123) on January 19, 2021
(4) 3A RHR pump room, Unit 3 10’ access to RHR pits and RHR heat exchanger pit (FZs 011, 012, and 013) on January 26 and February 16, 2021
(5) Safety-related 3A, 3B, 4A, and 4B 125Vdc station batteries (FZs 103,110, 109,102); D-52 safety-related spare station battery (FZ 025A); Unit 3 and Unit 4 cable spreading room (FZ 098); and, the Unit 3 and Unit 4 reactor protection system motor generator set rooms (FZs 104 and 101) on February 04, 2021
(6) Unit 3 and Unit 4 high head safety injection pump rooms, (FZs 052 and 053) on February 25, 2021
(7) Unit 3 and Unit 4 charging pump (FZs 045 and 055) and containment spray pump rooms (FZs 031 and 038) on March 01, 2021

Fire Brigade Drill Performance Sample (IP Section 03.02) (1 Sample)

(1) The inspectors evaluated the onsite fire brigade training and performance during an announced fire drill in the Unit 4 hydrogen seal oil system area, FZ 081, on March 01, 2021

C3-106

FPSC EXH No. 5
03/18/2024
ADMITTED

C3-209

71111.06 - Flood Protection Measures

Cable Degradation (IP Section 03.02) (1 Sample)

The inspectors evaluated cable submergence protection in:

(1) Manholes 303, 304, 405, and 423 while the licensee implemented engineering change 294356, flood protection improvements, on February 02, 2021

71111.07A - Heat Sink Performance

Annual Review (IP Section 03.01) (1 Sample)

The inspectors evaluated readiness and performance of:

(1) The Unit 4 CCW heat exchangers on February 1, 2021, and the Unit 3 CCW heat exchangers on February 19, 2021

71111.11Q - Licensed Operator Requalification Program and Licensed Operator Performance

Licensed Operator Performance in the Actual Plant/Main Control Room (IP Section 03.01) (1 Sample)

(1) The inspectors observed and evaluated licensed operator performance in the Control Room during:
- 3-GOP-100, Fast Load Reduction, and 3-ONOP-071.1, Secondary Chemistry Deviation from Limits, for a sodium intrusion originating in the 3AS main condenser hotwell on February 2, 2021
- 3-EOP-E-0, Reactor Trip or Safety Injection, 3-EOP-ES-0.1, Reactor Trip Response, and 3-GOP-103 Power Operation to Hot Standby, for an automatic reactor trip on March 1, 2021
- A reactor startup using 3-GOP-301, Hot Standby to Power Operation, on March 4, 2021
- Main control room turnover and Unit 4 down power to 83% for the 4A condensate pump motor replacement using 4-GOP-103, Power Operation to Hot Standby, on March 16, 2021

Licensed Operator Requalification Training/Examinations (IP Section 03.02) (1 Sample)

(1) The inspectors observed and evaluated a requalification training simulator scenario administered to an operating crew on February 15, 2021

71111.12 - Maintenance Effectiveness

Maintenance Effectiveness (IP Section 03.01) (1 Sample)

The inspectors evaluated the effectiveness of maintenance to ensure the following structures, systems, and components (SSCs) remain capable of performing their intended function:

C3-107

FPSC EXH No. 5
03/18/2024
ADMITTED

C3-210

(1) Action Request (AR) 2379162, Main Condenser Maintenance Rule (a)(1) Evaluation on March 30, 2021

Quality Control (IP Section 03.02) (1 Sample)

The inspectors evaluated the effectiveness of maintenance and quality control activities to ensure the following SSC remained capable of performing its intended function:

(1) WO 40713743-08, install watertight seals at manhole 301, observed appropriate level of qualification of materials in use, and at the jobsite, to effect flood protection improvements on March 25, 2021

71111.13 - Maintenance Risk Assessments and Emergent Work Control

Risk Assessment and Management Sample (IP Section 03.01) (7 Samples)

The inspectors evaluated the accuracy and completeness of risk assessments for the following planned and emergent work activities to ensure configuration changes and appropriate work controls were addressed:

(1) Unit 3 and Unit 4 on-line risk monitor (OLRM) with 3A ICW pump, 4CM motor-driven instrument air compressor, 4S231A 4A EDG control panel room air conditioner, and MOV-4-1403, AFW turbine steam supply from the A steam generator, out of service (OOS) on January 5, 2021
(2) Unit 3 and Unit 4 OLRM with 4B emergency containment cooler, 3B CCW heat exchanger, and PCV-4-456, pressurizer power operated relief valve OOS on January 21, 2021
(3) Unit 3 and Unit 4 OLRM with Unit 3 train 2 AFW feedwater flow control valves, 4C CCW heat exchanger, 4A EDG control panel room air conditioner unit 4S231A, and PCV-4-456, pressurizer power operated relief valve, OOS on January 27, 2021
(4) Unit 3 and Unit 4 OLRM with 3CM, motor-driven instrument air compressor, E233 water chiller unit for electrical equipment room AHU-78, and PCV-4-456, pressurizer power operated relief valve OOS on February 19, 2021
(5) Unit 3 and Unit 4 OLRM during the 3B CCW pump motor high risk heavy load lift over safety-related systems on February 18, 2021
(6) Unit 3 and Unit 4 OLRM with 3A ICW and CCW headers, 3C motor-driven instrument air compressor, E233 water chiller unit for electrical equipment room AHU-78, 4A charging pump, and PCV-4-456, pressurizer power operated relief valve OOS on February 26, 2021
(7) Unit 3 and Unit 4 OLRM with 3B ICW pump, 4B charging pump, Unit 4 train 1 AFW flow control valves, E233 water chiller unit for electrical equipment room AHU-V78, and PCV-4-456, pressurizer power operated relief valve OOS on March 10, 2021

71111.15 - Operability Determinations and Functionality Assessments

Operability Determination or Functionality Assessment (IP Section 03.01) (6 Samples)

The inspectors evaluated the licensee's justifications and actions associated with the following operability determinations and functionality assessments:

C3-108

FPSC EXH No. 5
03/18/2024

ADMITTED

C3-211

(1) AR 2380722, 2327425, and 1864215 Steam Leak from Upstream Side of Check Valve 3-10-398 During AFW Pump Testing on January 14, 2021
(2) AR 2377269, 3B ICW Pump Low Discharge Flow Rate on February 03, 2021
(3) AR 2382650, Unit 3 TC-432C1, Overtemperature Trip, and TC-432C2, Overtemperature Rod Stop, Setpoint and Reset Minimum Unsatisfactory on February 12, 2021
(4) AR 2382952, 3A CCW Pump Inboard Bearing Water Shield Found Backwards on February 18, 2021
(5) AR 2380012, Turkey Point Cooling Canal Silt Deposits on February 19, 2021
(6) AR 2386577, 3B ICW Pump Sole Plate Inspection Identified Degradation on March 24, 2021

71111.18 - Plant Modifications

Temporary Modifications and/or Permanent Modifications (IP Section 03.01 and/or 03.02) (1 Sample)

(1) Engineering Change 295954, Install Permanent Unit 3 Reactor Trip and Bypass Breakers Contacts Test Points to Support RPS Testing, reviewed on March 4, 2021

71111.19 - Post-Maintenance Testing

Post-Maintenance Test Sample (IP Section 03.01) (6 Samples)

The inspectors evaluated the following post-maintenance test activities to verify system operability and functionality:

(1) Work Order (WO) 40673626, 40806 Reverse Starter Maintenance for AFW Pump Steam Supply from 4B Steam Generator, MOV-4-1404, post-maintenance test (PMT) performed within WO standard and reviewed on February 04, 2021
(2) WO 40746281, Replace PCV-4-1705, Nitrogen (N2) Backup Pressure Control Valve to Train 2 Unit 4 AFW Flow Control Valve, PMT performed using section 4.3 of 4-OSP-075.7, Auxiliary Feedwater Train 2 Backup Nitrogen Test and reviewed on March 15, 2021
(3) WO 40755945, 3B ICW Pump Replacement, PMT performed using 3-OSP-019.1, Intake Cooling Water Inservice Test and reviewed on March 16, 2021
(4) WO 40679187, MOV-3-1405, AFW Pump Steam Supply from 3C Steam Generator, Stem Lubrication and Actuator Gearbox Grease Inspection, PMT performed within WO standard and reviewed on March 22, 2021
(5) WO 40698263, Replace PT-4-484, 4B Main Steam Line Pressure Transmitter, PMT performed using 4-SMI-072.01, P-4-468, P-4-474, P-4-484 and P-4-494 Steam Pressures Channel Calibration, Protection Channel II and reviewed on March 22, 2021
(6) WOs 40766915 and 40686024, Unit 3 B Reactor Trip Breaker and Cell Switch Replacements, PMT performed using 3-SMI-049.01B, Train B Reactor Protection System Logic Test and reviewed on March 24, 2021

71111.22 - Surveillance Testing

The inspectors evaluated the following surveillance tests:

C3-109

FPSC EXH No. 5
03/18/2024

ADMITTED

C3-212

Surveillance Tests (other) (IP Section 03.01) (3 Samples)

(1) 3-OSP-023.1, Diesel Generator Operability Test (3A EDG Normal Start Test) on January 15, 2021
(2) 4-OSP-075.2, Auxiliary Feedwater Train 2 Operability Verification and 4-OSP-075.9, C AFW Overspeed Test on January 20, 2021
(3) 4-OSP-068.2, Containment Spray Gas Accumulation Management Program; 0-OSP-202.3, Safety Injection Pump and Piping Venting; and, 4-OSP-202.2, RHR Pump and Piping Venting on January 22, 2021

Inservice Testing (IP Section 03.01) (2 Samples)

(1) 3-OSP-019.1, Intake Cooling Water Inservice Test (Sections 7.2 ICW Pump 3B and Discharge Check Valve Test) quarterly tests that were performed on June 04, 2020, August 08, 2020, and December 03, 2020. Review completed on February 02, 2021.
(2) 3-OSP-068.5B, 3B Containment Spray Pump Inservice Test on February 04, 2021

71114.01 - Exercise Evaluation

Inspection Review (IP Section 02.01-02.11) (1 Sample)

(1) The inspectors evaluated the biennial emergency plan exercise during the week of February 8, 2021. The simulated scenario began with an explosion and fire that caused damage to the 3B intake cooling water pump motor. This met the conditions for declaring an Alert. Subsequently, a reactor coolant system (RCS) leak slowly increased until charging pumps were unable to maintain RCS inventory, thus meeting the conditions for manually shutting down the reactor & initiating safety injection. With four control rods stuck out of the reactor core and radiation monitors increasing (indicative of fuel clad damage), the conditions for declaring a Site Area Emergency were met. When a containment purge exhaust valve seal deteriorated and began to leak by, conditions for a General Emergency were met, and the Offsite Response Organizations were able to demonstrate their ability to implement emergency actions.

71114.04 - Emergency Action Level and Emergency Plan Changes

Inspection Review (IP Section 02.01-02.03) (1 Sample)

(1) The inspectors reviewed and evaluated Emergency Action Level, Emergency Plan, and Emergency Plan Implementing Procedure changes during the week of February 8, 2021. This evaluation does not constitute NRC approval.

71114.06 - Drill Evaluation

Drill/Training Evolution Observation (IP Section 03.02) (1 Sample)

The inspectors evaluated:

C3-110

FPSC EXH No. 5
03/18/2024
ADMITTED

(1) Emergency classification and notification to local counties and Florida State during licensed operator continuing training in the control room simulator on February 15, 2021

71114.08 - Exercise Evaluation Scenario Review

Inspection Review (IP Section 02.01 - 02.04) (1 Sample)

(1) The inspectors reviewed and evaluated in-office, the proposed scenario for the biennial emergency plan exercise at least 30 days prior to the day of the exercise.

OTHER ACTIVITIES – BASELINE

71151 - Performance Indicator Verification

The inspectors verified licensee performance indicators submittals listed below:

EP01: Drill/Exercise Performance (IP Section 03.12) (1 Sample)

(1) Unit 3 January 1, 2020, through December 31, 2020
Unit 4 January 1, 2020, through December 31, 2020

IE01: Unplanned Scrams per 7000 Critical Hours Sample (IP Section 03.01) (2 Samples)

(1) Unit 3 January 1, 2020 through December 31, 2020
(2) Unit 4 January 1, 2020 through December 31, 2020

EP02: ERO Drill Participation (IP Section 03.13) (1 Sample)

(1) Unit 3 January 1, 2020, through December 31, 2020
Unit 4 January 1, 2020, through December 31, 2020

IE03: Unplanned Power Changes per 7000 Critical Hours Sample (IP Section 03.02) (2 Samples)

(1) Unit 3 January 1, 2020 through December 31, 2020
(2) Unit 4 January 1, 2020 through December 31, 2020

EP03: Alert & Notification System Reliability (IP Section 03.14) (1 Sample)

(1) Unit 3 January 1, 2020, through December 31, 2020
Unit 4 January 1, 2020, through December 31, 2020

IE04: Unplanned Scrams with Complications Sample (IP Section 03.03) (2 Samples)

(1) Unit 3 January 1, 2020 through December 31, 2020
(2) Unit 4 January 1, 2020 through December 31, 2020

71153 - Follow-up of Events and Notices of Enforcement Discretion

Event Follow-up (IP Section 03.01) (2 Samples)

FPSC EXH No. 5
03/18/2024
ADMITTED

(1) The inspectors responded to the main control room and evaluated a Unit 3 automatic reactor trip from an automatic turbine trip that occurred during restoration from a routine test of the reactor protection system on March 1, 2021.
(2) The inspectors evaluated a Unit 3 manual turbine runback to 85% in response to unexpected and rapid steam generator water level decrease in all three steam generators which was caused by a rapid reduction in steam generator feedwater flow due to the unanticipated opening of the 3A steam generator feedwater pump recirculation to condenser flow control valves, CV-3-1415 and CV-3-1416, on March 24, 2021. CV-3-1415 and CV-3-1416, which were earlier placed in manual operation to facilitate isolating feedwater flow instruments FT-3-1416A/B/and C, transferred to automatic control and fully opened when FT-3-1416A/B/and C indicated zero feedwater flow.

Event Report (IP Section 03.02) (2 Samples)

The inspectors evaluated the following licensee event reports (LERs):

(1) LER 05000250/2020-002-00 and -01, Manual Reactor Trip in Response to High Steam Generator Level following Inadvertent Opening of Feedwater Heater Bypass Valve, (ADAMS Accession Nos. ML20267A235 and ML21064A212). The inspection conclusions associated with Revision 00 and 01 of this LER are documented in Inspection Report 05000250/2020050 and 05000251/2020050 (ADAMS Accession No. ML20344A126).
(2) LER 05000250/2020-005-00 and -01, Technical Specification Action Not Taken for Unrecognized Inoperable Source Range Channel, (ADAMS Accession Nos. ML20289A294 and ML21064A218). The inspection conclusions associated with Revision 00 and 01 of this LER are documented in Inspection Report 05000250/2020050 and 05000251/2020050 (ADAMS Accession No. ML20344A126).

INSPECTION RESULTS

Failure to Maintain the Effectiveness of the Emergency Plan			
Cornerstone	Severity	Cross-Cutting Aspect	Report Section
Not Applicable	Severity Level IV NCV 05000250,05000251/2021001-01 Open/Closed	Not Applicable	71114.04
The inspectors identified a Severity Level IV (SL-IV) non-cited violation (NCV) of Title 10 of the Code of Federal Regulations (CFR), Part 50.54(q)(2), for failure to maintain the effectiveness of the Turkey Point Nuclear Station Emergency Plan (E-Plan). Specifically, the licensee had not revised the E-Plan for a change to the number of Alert and Notification System (ANS) sirens.			
Description: While performing a detailed review of a corrective action program document (AR 02344404) generated from the last emergency preparedness inspection, the inspectors identified that the licensee had not updated their E-Plan to correctly reflect the number of ANS sirens in-place at TPN. The inspectors determined that Section 5.2.8 of the E-Plan states the ANS network consists of 45 pole mounted sirens and two indoor sirens. After reviewing siren performance indicator data, the inspectors noted that there are a total of 48			

FPSC EXH No. 5
03/18/2024

ADMITTED

C3-215

sirens. The inspectors also determined that an additional pole mounted siren (siren 50) was added in December 2015, but the licensee failed to update the E-Plan ANS network description to reflect the most current information. From December 2015 to present, there were several opportunities for the licensee to identify and revise the E-Plan with the updated ANS information. Although maintenance and testing of the sirens continued, and proper functionality of the ANS was maintained, the inspectors determined that this issue was a violation for failure to maintain the effectiveness of the TPN E-Plan.

Corrective Actions: The licensee entered the issue into the corrective action program on February 11, 2020.

Corrective Action References: AR 02384000

Performance Assessment: The licensee's failure to maintain the effectiveness of the TPN E-Plan was determined to impede the NRCs ability to perform its regulatory function and is dispositioned using the Traditional Enforcement process.

Enforcement: This finding is a violation of NRC requirements, and because it has the potential for impacting the NRC's ability to perform its regulatory function, traditional enforcement is applicable in accordance with Inspection Manual Chapter 0611 and 0612, Appendix B, Figure 2. This finding is determined to be a SL-IV violation in accordance with Section 6.6.d.1 of the Enforcement Policy because it involves the licensee's ability to meet or implement a regulatory requirement not related to assessment or notification such that the effectiveness of the emergency plan is reduced.

Violation: Title 10 of the CFRs, Part 50.54(q)(2) states, in part, that a licensee shall follow and maintain the effectiveness of an E-Plan that meets the requirements in Appendix E to this part. Contrary to the above, the licensee failed to maintain the E-Plan, which is a higher tier document that must be maintained up-to-date and accurate at all times. Specifically, from December 2015 until February 2021, the TPN E-Plan had not been revised after a change was made to the number of ANS sirens.

Enforcement Action: This violation is being treated as a non-cited violation, consistent with Section 2.3.2 of the Enforcement Policy.

Failure to Correctly Verify the Component as Instructed in Work Order			
Cornerstone	Significance	Cross-Cutting Aspect	Report Section
Mitigating Systems	Green NCV 05000250,05000251/2021001-02 Open/Closed	[H.12] - Avoid Complacency	71152

A self-revealed Green Non-Cited Violation (NCV) of 10 CFR, Part 50, Appendix B, Criterion V, "Instructions, Procedures, and Drawings," was identified for the failure to correctly verify a component specified in a work order (WO). Specifically, Instrument and Control (I&C) technicians did not follow the proper verification steps in WO 40632818 and incorrectly conducted work on the 3C charging pump.

Description: On July 10, 2019, Unit 4 plant conditions were established to facilitate maintenance on the 4C charging pump. I&C technicians were authorized to complete WO 40632818 and calibrate pressure switch PS-4-201C, which provides a low oil pressure trip signal to the 4C charging pump. The I&C technicians did not follow the proper verification

C3-113

FPSC EXH No. 5
03/18/2024

ADMITTED

C3-216

steps and incorrectly conducted work on the 3C charging pump. The Unit 3 chemical volume and control system was in a normal alignment with only the 3C charging pump, operating to maintain programmed reactor coolant system (RCS) pressurizer level and reactor coolant pump (RCP) seal injection.

The I&C technicians conducted a pre-job brief prior to performing the work order and discussed the work that was intended to be completed on the Unit 4C charging pump. The I&C technicians proceeded to the work area with the correct WO that described the work to be performed on Unit 4. However, the I&C technicians informed radiation protection (RP) of their intention to perform work on Unit 3. Despite being advised by RP that the charging pump maintenance outage was being performed on Unit 4, the I&C technicians still proceeded to the 3C charging pump.

Step 4.1 of WO 40632818 is listed as a critical step and instructs the performer to verify the intended component before starting the work. However, the I&C technicians did not recognize the appropriate Unit color identifiers, or the absence of a clearance boundary, did not properly match component identification numbers with the number listed in the WO, and did not recognize that the 3C charging pump was running. As a result, the I&C technicians manipulated an isolation valve for pressure switch PS-3-201C and loosened the test cap causing oil to flow out on the 3C charging pump. This result caused the I&C technicians to review the WO and to recognize that they were working on Unit 3 and not Unit 4.

The 3C charging pump trip on low oil pressure at about 10:09 a.m. was a silent trip. There are no local or control room alarms or annunciators associated with the low oil pressure condition. The reactor operator attempted to restart the 3C charging pump within twenty seconds, but it tripped again on low oil pressure because PS-3-201C was still vented. Within a minute, the reactor operator started the 3B charging pump restoring RCS makeup and RCP seal injection. An equipment operator reported to the Unit 3 charging pump room and it was recorded that the 3C charging pump did not appear to have anything obviously wrong with it. The I&C technicians had already left the area prior to the arrival of the equipment operator.

At 11:08 a.m., control room operators initiated an action request, AR 2320506, to investigate and correct, the anomalous 3C charging pump trip. At about 11:30 a.m., the I&C department head informed the maintenance director and site director that the 3C charging pump trip was the result of a human performance error. At 2:08 p.m., the control room operators returned the 3C charging pump to an operable condition.

Corrective Actions: FPL promptly initiated a human performance incident investigation and AR 2320534.

Corrective Action References: AR 2320534 and AR 2320506

Performance Assessment:

Performance Deficiency: The I&C technicians' failure to verify the correct component to be worked on before starting work, as instructed in Step 4.1 of WO 40632818, was a performance deficiency.

Screening: The inspectors determined the performance deficiency was more than minor because it was associated with the Human Performance attribute of the Mitigating Systems cornerstone and adversely affected the cornerstone objective to ensure the availability, reliability, and capability of systems that respond to initiating events to prevent undesirable

C3-114

FPSC EXH No. 5
03/18/2024

ADMITTED

C3-217

consequences. Specifically, I&C technicians failed to use the appropriate human performance tools to prevent working on the wrong component. The human performance error caused an unplanned unavailability of the Unit 3C charging pump.

Significance: The inspectors assessed the significance of the finding using Appendix A, "The Significance Determination Process (SDP) for Findings At-Power." The inspectors screened this finding using IMC 0609, Attachment 4, "Initial Characterization of Findings," for Mitigating Systems, and IMC 0609, Appendix A, "The Significance Determination Process (SDP) for Findings At-Power," and determined the finding to be of very low safety significance (Green) because the finding did not represent a loss of the PRA function of one or more non-TS trains of equipment designated as risk-significant in accordance with the licensee's maintenance rule program for greater than 3 days.

Cross-Cutting Aspect: H.12 - Avoid Complacency: Individuals recognize and plan for the possibility of mistakes, latent issues, and inherent risk, even while expecting successful outcomes. Individuals implement appropriate error reduction tools. The inspectors reviewed this performance deficiency for cross-cutting aspects as required by IMC 0310, "Aspects Within the Cross-Cutting Areas." The I&C technicians did not implement the appropriate error reduction tools, despite multiple barriers and opportunities to prevent work on the wrong component.

Enforcement:

Violation: 10 CFR 50 Appendix B, Criterion V, states that activities affecting quality shall be prescribed by documented instructions, procedures, or drawings, of a type appropriate to the circumstances and shall be accomplished in accordance with these instructions, procedures, or drawings.

The maintenance being performed on the safety-related charging pump was being directed by WO 40632818. Step 4.1 of WO 40632818 instructed the worker to "Verify the component to be worked has been properly identified: PS-4-201C; Charging Pump 4P201C Interlock Control Pressure Switch in Charging Pump Room."

Contrary to the above, on July 10, 2019, the licensee failed to accomplish Step 4.1 of WO 40632818, when the correct component was not properly identified. The I&C technicians failed to verify work was being accomplished on pressure switch PS-4-201C, causing a trip of the 3C charging pump when work was performed on pressure switch PS-3-201C.

Enforcement Action: This violation is being treated as a non-cited violation, consistent with Section 2.3.2 of the Enforcement Policy.

Unresolved Item (Open)	Unit 3 Automatic Reactor Trip due to Reactor Trip Breaker Cell Switch Malfunction URI 05000250/2021001-03	71153

Description: On March 1, 2021, at 1108 hours, Unit 3 experienced an unplanned reactor trip from 100% power. Restoration from a routine test of the reactor protection system (RPS) was in progress when the reactor trip occurred. All equipment required for the immediate reactor trip response functioned normally. The licensee determined a malfunction of the B-train reactor trip breaker cubicle cell switch during the RPS test restoration caused the reactor trip. An unresolved item (URI) is opened for additional review to determine if the cubicle cell switch malfunction and subsequent reactor trip was reasonably foreseeable and preventable

C3-115

FPSC EXH No. 5
03/18/2024

ADMITTED

C3-218

and to also determine if appropriate regulatory requirements or self-imposed standards were followed for maintenance of the reactor trip breakers and associated cell switches (i.e. to determine if a performance deficiency exists).

Planned Closure Actions: The NRC inspectors intend to review the licensee and vendor failure analysis of the B-train reactor trip breaker and associated cell switches. Additionally, the NRC inspectors intend to review the licensee's root cause analysis and other associated investigation documents and interview plant personnel.

Licensee Actions: Prior to reactor startup, the licensee replaced the B-train reactor trip breaker and cubicle cell switches. The A-train reactor trip breaker and A and B-train bypass breaker cubicles and cell switches were inspected, cleaned, and tested for proper operation. A modification to detect for a standing trip signal from cell switch contacts was installed in the Unit 3 reactor trip and bypass breakers. A similar modification to detect for a standing trip signal is intended for the Unit 4 breakers during the next Unit 4 refueling outage. The licensee contracted with the reactor trip breaker vendor to perform a failure analysis of the previously installed B-train reactor trip breaker and associated cubicle cell switches.

Corrective Action References: AR 2385529

Unresolved Item (Open)	Inadvertent Opening of 3A Steam Generator Feedwater Pump Recirculation Valves Causes a Rapid Decrease in Unit 3 Steam Generator Water Levels URI 05000250/2021001-04	71153

Description: On March 24, 2021, main control room operators performed a manual turbine runback on Unit 3 from 100% power to 85% in response to a rapid decrease in steam generator water levels. The unexpected and rapid water level decrease was caused by an equally unexpected and rapid reduction in steam generator feedwater flow due to the unanticipated opening of the 3A steam generator feedwater pump recirculation to condenser flow control valves, CV-3-1415 and CV-3-1416. CV-3-1415 and CV-3-1416 were placed in manual operation to facilitate isolating flow instruments, FT-3-1416A/B/and C. Plant operators recently identified a steam leak at a common process connection to all three flow transmitters. Plant engineers and operators assumed CV-3-1415 and CV-3-1416 would remain in manual operation but the distributed control system (DCS) logic by design overrode and fully opened CV-3-1415 and CV-3-1416. A URI is opened for additional review to determine if the DCS override function for CV-3-1415 and CV-3-1416 was reasonably foreseeable and the transient preventable, and to also determine if appropriate regulatory requirements or self-imposed standards were followed for isolating FT-3-1416A/B/and C (i.e. to determine if a performance deficiency exists).

Planned Closure Actions: The NRC inspectors intend to review the licensee human performance learning opportunity reviews and interview plant personnel. The inspectors also intend to review the DCS logic diagrams to understand the plant information available to engineers involved in the decision to isolate FT-3-1416A/B/and C.

Licensee Actions: The licensee completed a human performance investigation to understand the learning opportunities with those involved and the quality of the reviews that occurred prior to the isolating FT-3-1416A/B/and C. The licensee also completed an extent of condition review for other DCS controllers that can be overridden by process control logic to

C3-116

FPSC EXH No. 5
03/18/2024

ADMITTED

C3-219

automatic control from manual control and verified the logic was appropriate and operating procedures were adequate.

Corrective Action References: AR 2387840

EXIT MEETINGS AND DEBRIEFS

The inspectors verified no proprietary information was retained or documented in this report.

- On February 12, 2021, the inspectors presented the Emergency Preparedness Exercise Inspection results to Michael Pearce, Site Vice President and other members of the licensee staff.
- On April 13, 2021, the inspectors presented the Resident Inspector Quarterly Exit inspection results to Michael Pearce, Site Vice President and other members of the licensee staff.
- On April 22, 2021, the inspectors presented the Resident Inspector Quarterly Re-exit to Include Finding Related to 2019 Charging Pump Trip Issue inspection results to Michael Pearce, Site Vice President.

C3-117

FPSC EXH No. 5
03/18/2024

ADMITTED

DOCUMENTS REVIEWED

Inspection Procedure	Type	Designation	Description or Title	Revision or Date
71114.04	Corrective Action Documents	AR 02344324,	NRC EP inspection identified potential violation	
	Corrective Action Documents Resulting from Inspection	AR 02384000	NRC identified potential SL-IV NCV	
	Procedures		Turkey Point Radiological Emergency Plan	66
		EP-AA-100-1007	Evaluation of Changes to the Emergency Plan, Supporting Documents, & Equipment (10 CFR 50.54(q))	Rev. 9

FPSC EXH No. 5
03/18/2024

ADMITTED

C3-221

Florida Power & Light Company
Docket No. 20220001-EI
OPC's Third Set of Interrogatories
Interrogatory No. 37
Page 1 of 1

QUESTION:
Please provide the following staffing information for Turkey Point Unit 3:

a. **Provide the authorized number of staff included in the annual plant budget for the last five years.**

b. **Staffing levels on a monthly basis for the last five years.**

c. **Identify the personnel changes in each month over the last five years by staff assignment and reason for individual leaving a position.**

RESPONSE:
See FPL's Objections filed on August 8, 2022. Subject to those objections, see Attachment 1 to this Interrogatory for answers to subparts (a) and (b). FPL does not budget staff by unit, information provided is by site. FPL assumes the last five years to be 2017-2021.

FPSC EXH No. 5
03/18/2024

ADMITTED

C3-222

Florida Power & Light Company
Docket No. 20220001-EI
OPC's Third Set of Interrogatories
Interrogatory No. 38
Page 1 of 1

QUESTION:
Please provide the following staffing information for Turkey Point Unit 4:

a. **Provide the authorized number of staff included in the annual plant budget for the last five years.**

b. **Staffing levels on a monthly basis for the last five years.**

c. **Identify the personnel changes in each month over the last five years by staff assignment and reason for individual leaving a position.**

RESPONSE:
See FPL's Objections filed on August 8, 2022. Subject to those objections, see FPL's response to OPC's Third Set of Interrogatories No. 37, including Attachment 1, for answers to subparts (a) and (b).

FPSC EXH No. 5
03/18/2024

ADMITTED

C3-223

Florida Power & Light Company
Docket No. 20220001-EI
OPC's Third Set of Interrogatories
Interrogatory No. 39
Page 1 of 1

QUESTION:
Please provide the following staffing information for St Lucie Unit 1:

a. **Provide the authorized number of staff included in the annual plant budget for the last five years.**

b. **Staffing levels on a monthly basis for the last five years.**

c. **Identify the personnel changes in each month over the last five years by staff assignment and reason for individual leaving a position.**

RESPONSE:
See FPL's Objections filed on August 8, 2022. Subject to those objections, see FPL's response to OPC's Third Set of Interrogatories No. 37, including Attachment 1, for answers to subparts (a) and (b).
.

FPSC EXH No. 5
03/18/2024

ADMITTED

C3-224

Florida Power & Light Company
Docket No. 20220001-EI
OPC's Third Set of Interrogatories
Interrogatory No. 40
Page 1 of 1

QUESTION:
Please provide the following staffing information for St. Lucie Unit 2:

a. **Provide the authorized number of staff included in the annual plant budget for the last five years.**

b. **Staffing levels on a monthly basis for the last five years.**

c. **Identify the personnel changes in each month over the last five years by staff assignment and reason for individual leaving a position**

RESPONSE:
See FPL's Objections filed on August 8, 2022. Subject to those objections, see FPL's response to OPC's Third Set of Interrogatories No. 37, including Attachment 1, for answers to subparts (a) and (b).

FPSC EXH No. 5
03/18/2024

ADMITTED

C3-225

Docket No. 20220001-EI
FPL's Response to OPC's Interrogatory Nos. 37-40
Exhibit RAP-7, Page 5 of 7

Florida Power & Light Company
Docket No. 20220001-EI
OPC's Third Set of Interrogatories
Interrogatory No. 37
Attachment 1 of 1
Page 1 of 3

	*Time	Headcount Actual (A)	Headcount 2017 Approved Budget (B)	Headcount 2018 Approved Budget (C)	Headcount 2019 Approved Budget (D)
St. Lucie	Jan 2017	636.0	649.0		
	Feb 2017	696.0	649.0		
	Mar 2017	692.0	649.0		
	Apr 2017	639.0	649.0		
	May 2017	633.0	654.0		
	Jun 2017	617.0	654.0		
	Jul 2017	620.0	654.0		
	Aug 2017	618.0	649.0		
	Sep 2017	609.0	649.0		
	Oct 2017	606.0	649.0		
	Nov 2017	603.0	649.0		
	Dec 2017	588.0	649.0		
	Jan 2018	593.0		594.0	
	Feb 2018	609.0		594.0	
	Mar 2018	662.0		593.0	
	Apr 2018	598.0		593.0	
	May 2018	587.0		596.0	
	Jun 2018	581.0		596.0	
	Jul 2018	576.0		590.0	
	Aug 2018	640.0		590.0	
	Sep 2018	610.0		587.0	
	Oct 2018	569.0		587.0	
	Nov 2018	565.0		587.0	
	Dec 2018	526.0		587.0	
	Jan 2019	525.0			511.0
	Feb 2019	518.0			511.0
	Mar 2019	513.0			506.0
	Apr 2019	510.0			506.0
	May 2019	510.0			506.0
	Jun 2019	509.0			506.0
	Jul 2019	507.0			506.0
	Aug 2019	500.0			506.0
	Sep 2019	519.0			506.0
	Oct 2019	577.0			506.0
	Nov 2019	506.0			506.0
	Dec 2019	503.0			506.0

C3-123

FPSC EXH No. 5
03/18/2024

ADMITTED

C3-226

Docket No. 20220001-EI
FPL's Response to OPC's Interrogatory Nos. 37-40
Exhibit RAP-7, Page 6 of 7

Florida Power & Light Company
Docket No. 20220001-EI
OPC's Third Set of Interrogatories
Interrogatory No. 37
Attachment 1 of 1
Page 2 of 3

	*Time	Headcount Actual (A)	Headcount 2017 Approved Budget (B)	Headcount 2018 Approved Budget (C)	Headcount 2019 Approved Budget (D)
Turkey Point	Jan 2017	613.0	648.0		
	Feb 2017	601.0	652.0		
	Mar 2017	640.0	656.0		
	Apr 2017	614.0	655.0		
	May 2017	612.0	655.0		
	Jun 2017	603.0	656.0		
	Jul 2017	602.0	653.0		
	Aug 2017	588.0	652.0		
	Sep 2017	620.0	647.0		
	Oct 2017	627.0	649.0		
	Nov 2017	581.0	648.0		
	Dec 2017	575.0	648.0		
	Jan 2018	571.0		602.0	
	Feb 2018	569.0		602.0	
	Mar 2018	568.0		609.0	
	Apr 2018	574.0		609.0	
	May 2018	574.0		609.0	
	Jun 2018	584.0		616.0	
	Jul 2018	578.0		616.0	
	Aug 2018	570.0		587.0	
	Sep 2018	622.0		582.0	
	Oct 2018	612.0		583.0	
	Nov 2018	573.0		583.0	
	Dec 2018	544.0		570.0	
	Jan 2019	540.0			533.0
	Feb 2019	535.0			531.0
	Mar 2019	590.0			531.0
	Apr 2019	522.0			531.0
	May 2019	508.0			531.0
	Jun 2019	502.0			531.0
	Jul 2019	500.0			536.0
	Aug 2019	493.0			536.0
	Sep 2019	498.0			531.0
	Oct 2019	498.0			531.0
	Nov 2019	496.0			531.0
	Dec 2019	493.0			530.0

C3-124

FPSC EXH No. 5
03/18/2024

ADMITTED

C3-227

Florida Power & Light Company
Docket No. 20220001-EI
OPC's Third Set of Interrogatories
Interrogatory No. 37
Attachment 1 of 1
Page 3 of 3

	*Time	Headcount Actual (A)	Headcount 2020 Approved Budget (B)	Headcount 2021 Approved Budget (C)
St. Lucie	Jan 2020	512.0	513.0	
	Feb 2020	588.0	513.0	
	Mar 2020	507.0	500.0	
	Apr 2020	496.0	500.0	
	May 2020	498.0	500.0	
	Jun 2020	501.0	500.0	
	Jul 2020	499.0	500.0	
	Aug 2020	497.0	500.0	
	Sep 2020	496.0	500.0	
	Oct 2020	496.0	500.0	
	Nov 2020	495.0	500.0	
	Dec 2020	493.0	500.0	
	Jan 2021	490.0		500.0
	Feb 2021	488.0		500.0
	Mar 2021	512.0		500.0
	Apr 2021	570.0		497.0
	May 2021	484.0		492.0
	Jun 2021	480.0		492.0
	Jul 2021	474.0		489.0
	Aug 2021	552.0		489.0
	Sep 2021	530.0		489.0
	Oct 2021	475.0		489.0
	Nov 2021	469.0		489.0
	Dec 2021	458.0		489.0
Turkey Point	Jan 2020	483.0	509.0	
	Feb 2020	493.0	509.0	
	Mar 2020	563.0	508.0	
	Apr 2020	510.0	508.0	
	May 2020	482.0	497.0	
	Jun 2020	490.0	497.0	
	Jul 2020	490.0	502.0	
	Aug 2020	489.0	502.0	
	Sep 2020	561.0	497.0	
	Oct 2020	591.0	497.0	
	Nov 2020	507.0	497.0	
	Dec 2020	503.0	495.0	
	Jan 2021	500.0		485.0
	Feb 2021	501.0		485.0
	Mar 2021	501.0		485.0
	Apr 2021	499.0		485.0
	May 2021	506.0		485.0
	Jun 2021	507.0		485.0
	Jul 2021	509.0		488.0
	Aug 2021	514.0		488.0
	Sep 2021	548.0		485.0
	Oct 2021	583.0		485.0
	Nov 2021	498.0		485.0
	Dec 2021	476.0		485.0

C3-125

FPSC EXH No. 5
03/18/2024
ADMITTED

UNITED STATES
NUCLEAR REGULATORY COMMISSION
REGION II
245 PEACHTREE CENTER AVENUE N.E., SUITE 1200
ATLANTA, GEORGIA 30303-1200

April 15, 2019

Mr. Mano Nazar
President and Chief Nuclear Officer
Nuclear Division
Florida Power & Light Co.
Mail Stop: EX/JB
700 Universe Blvd.
Juno Beach, FL 33408

SUBJECT: TURKEY POINT NUCLEAR GENERATING STATION – NUCLEAR REGULATORY COMMISSION PROBLEM IDENTIFICATION AND RESOLUTION INSPECTION REPORT 05000250/2019010 AND 05000251/2019010

Dear Mr. Nazar:

On March 1, 2019, the U.S. Nuclear Regulatory Commission (NRC) completed a problem identification and resolution inspection at your Turkey Point Units 3, 4 and discussed the results of this inspection with Mr. Robert Coffey, Southern Regional Vice President, and other members of your staff. The results of this inspection are documented in the enclosed report.

The NRC inspection team reviewed the station's corrective action program and the station's implementation of the program to evaluate its effectiveness in identifying, prioritizing, evaluating, and correcting problems, and to confirm that the station was complying with NRC regulations and licensee standards for corrective action programs. Based on the samples reviewed, the team determined that your staff's performance in each of these areas adequately supported nuclear safety.

The team also evaluated the station's processes for use of industry and NRC operating experience information and the effectiveness of the station's audits and self-assessments. Based on the samples reviewed, the team determined that your staff's performance in each of these areas adequately supported nuclear safety.

Finally, the team reviewed the station's programs to establish and maintain a safety-conscious work environment, and interviewed station personnel to evaluate the effectiveness of these programs. Based on the team's observations and the results of these interviews the team found no evidence of challenges to your organization's safety-conscious work environment. Your employees appeared willing to raise nuclear safety concerns through at least one of the several means available.

NRC inspectors documented three findings of very low safety significance (Green) in this report. These findings involved violations of NRC requirements.

If you contest the violations or significance or severity of the violations documented in this inspection report, you should provide a response within 30 days of the date of this inspection report, with the basis for your denial, to the U.S. Nuclear Regulatory Commission, ATTN:

C3-126

FPSC EXH No. 5
03/18/2024
M. Nazar
ADMITTED

Document Control Desk, Washington, DC 20555-0001; with copies to the Regional Administrator, Region II; the Director, Office of Enforcement; and the NRC resident inspector at Turkey Point.

If you disagree with a cross-cutting aspect assignment in this report, you should provide a response within 30 days of the date of this inspection report, with the basis for your disagreement, to the U.S. Nuclear Regulatory Commission, ATTN: Document Control Desk, Washington, DC 20555-0001; with copies to the Regional Administrator, Region II; and the NRC resident inspector at Turkey Point.

This letter, its enclosure, and your response (if any) will be made available for public inspection and copying at http://www.nrc.gov/reading-rm/adams.html and at the NRC Public Document Room in accordance with 10 CFR 2.390, "Public Inspections, Exemptions, Requests for Withholding."

Sincerely,

/RA/

Randall A. Musser, Chief
Reactor Projects Branch 3
Division of Reactor Projects

Docket Nos.: 50-250, 50-251
License Nos.: DPR-31, DPR-41

Enclosure:
Inspection Report 05000250/2019010 and 05000251/2019010

cc Distribution via ListServ

C3-230

FPSC EXH No. 5
03/18/2024
M. Nazar
ADMITTED

SUBJECT: TURKEY POINT NUCLEAR GENERATING STATION – NUCLEAR REGULATORY COMMISSION PROBLEM IDENTIFICATION AND RESOLUTION INSPECTION REPORT 05000250/2019010 AND 05000251/2019010 April 15, 2019

DISTRIBUTION:
S. Price, RII
M. Kowal, RII
K. Sloan, RII
OE Mail
RIDSNRRDIRS
PUBLIC
RidsNrrPMTurkeyPoint Resource

ADAMS ACCESSION NUMBER: ML19105B281

OFFICE	RII/DRP	RII/DRP	RII/DRS	RII/DRP	RII/DRP	RII/DRP	RII/DRP
NAME	WDeschaine	DDumbacher	JDymek	RReyes	AWilson	RTaylor	RMusser
DATE	4/12/2019	4/12/2019	4/11/2019	4/12/2019	4/11/2019	4/12/2019	

OFFICIAL RECORD COPY

C3-128

FPSC EXH No. 5
03/18/2024

ADMITTED

C3-231

U.S. NUCLEAR REGULATORY COMMISSION

REGION II

Docket Number(s):	05000250 and 05000251
License Number(s):	DPR-31 and DPR-41
Report Number(s):	05000250/2019010 and 05000251/2019010
Enterprise Identifier:	I-2019-010-0018
Licensee:	Florida Power & Light Company (FPL)
Facility:	Turkey Point Nuclear Generating Station, Units 3 and 4
Location:	9760 SW 344th Street Homestead, FL 33035
Inspection Dates:	February 11, 2019 through March 1, 2019
Inspectors:	Wesley Deschaine, Project Engineer (Team Leader) John Dymek, Reactor Inspector Dave Dumbacher, Senior Operations Engineer Roger Reyes, Resident Inspector
Approved By:	Randall A. Musser, Chief Reactor Projects Branch 3 Division of Reactor Projects

C3-129

FPSC EXH No. 5
03/18/2024

ADMITTED

C3-232

SUMMARY

The U.S. Nuclear Regulatory Commission (NRC) continued monitoring the licensee's performance by conducting a problem identification and resolution inspection at Turkey Point Units 3 and 4 in accordance with the Reactor Oversight Process. The Reactor Oversight Process is the NRC's program for overseeing the safe operation of commercial nuclear power reactors. Refer to https://www.nrc.gov/reactors/operating/oversight.html for more information. Findings and violations being considered in the NRC's assessment are summarized in the table below.

List of Findings and Violations

Preconditioning of safety-related check valves prior to retesting			
Cornerstone	Significance	Cross-cutting Aspect	Report Section
Mitigating Systems	Green NCV 05000250/2019010-02 Open/Closed	[H.9] - Training	71152B
The NRC identified a green, non-cited violation (NCV) of 10 CFR 50, Appendix B, Criterion V, in that the licensee failed to comply with procedure 0-ADM-502, In-Service Testing Program, when preconditioning of safety related check valves was conducted prior to retesting.			

Failure to comply with the ASME OM code during safety-related check valve testing			
Cornerstone	Significance	Cross-cutting Aspect	Report Section
Mitigating Systems	Green NCV 05000250/2019010-03 Open/Closed	[P.1] - Identification	71152B
The NRC identified a green, NCV of 10 CFR 50.55a(f)(4), when the licensee failed to declare safety-related valves inoperable and failed to take corrective action after a failed in-service test (IST) as required by the ASME OM code.			

Inadequate Maintenance Procedures to Ensure Flood Protection for the 4A and 4B RHR trains			
Cornerstone	Significance	Cross-cutting Aspect	Report Section
Mitigating Systems	Green NCV 05000251/2019010-01 Open/Closed	[H.11] - Challenge the Unknown	71152B
The NRC identified a green, NCV of Technical Specification 6.8.1, for the licensee's failure to establish, implement and maintain written procedures to prevent foreign material from potentially degrading the residual heat removal (RHR) pump room sump pumps.			

Additional Tracking Items

None

C3-130

FPSC EXH No. 5
03/18/2024

ADMITTED

C3-238

INSPECTION SCOPES

Inspections were conducted using the appropriate portions of the inspection procedures (IPs) in effect at the beginning of the inspection unless otherwise noted. Currently approved IPs with their attached revision histories are located on the public website at http://www.nrc.gov/reading-rm/doc-collections/insp-manual/inspection-procedure/index.html. Samples were declared complete when the IP requirements most appropriate to the inspection activity were met consistent with Inspection Manual Chapter (IMC) 2515, "Light-Water Reactor Inspection Program - Operations Phase." The inspectors reviewed selected procedures and records, observed activities, and interviewed personnel to assess licensee performance and compliance with Commission rules and regulations, license conditions, site procedures, and standards.

OTHER ACTIVITIES – BASELINE

71152B - Problem Identification and Resolution

02.04 Biennial Team Inspection (1 Sample)

The inspectors performed a biennial assessment of the licensee's corrective action program, use of operating experience, self-assessments and audits, and safety conscious work environment.

- Corrective Action Program Effectiveness – The inspectors assessed the corrective action program's effectiveness in identifying, prioritizing, evaluating, and correcting problems.

- Operating Experience, Self-Assessments and Audits – The inspectors assessed the effectiveness of the station's processes for use of operating experience, audits and self-assessments.

- Safety Conscious Work Environment – The inspectors assessed the effectiveness of the station's programs to establish and maintain a safety-conscious work environment.

INSPECTION RESULTS

Assessment	71152B
Corrective Action Program Effectiveness Based on the samples reviewed, the team determined that the licensee's corrective action program (CAP) complied with regulatory requirements and self-imposed standards. The licensee's implementation of the CAP adequately supported nuclear safety. Effectiveness of Problem Identification: The inspectors determined that the licensee was effective in identifying problems and entering them into the CAP and there was a low threshold for entering issues into the CAP. This conclusion was based on a review of the requirements for initiating Action Requests (ARs) as described in licensee procedure PI-AA-	

C3-131

FPSC EXH No. 5
03/18/2024

ADMITTED

C3-234

104-1000, “Condition Reporting,” and management’s expectation that employees were encouraged to initiate ARs for any reason. Additionally, site management was actively involved in the CAP and focused appropriate attention on significant plant issues. Based on reviews and walkdowns of accessible portions of selected systems, the inspectors determined that deficiencies were being identified and placed in the CAP.

Effectiveness of Prioritization and Evaluation of Issues: Based on the review of ARs sampled by the inspection team during the onsite period, the inspectors concluded that problems were generally prioritized and evaluated in accordance with the AR significance determination guidance in procedure PI-AA-104-1000. The inspectors determined that in general, adequate consideration was given to system or component operability and associated plant risk. The inspectors determined that plant personnel had conducted root cause and apparent cause analyses in compliance with the licensee’s CAP procedures and cause determinations were appropriate, and considered the significance of the issues being evaluated. A variety of formal causal-analysis techniques were used to evaluate ARs depending on the type and complexity of the issue consistent with the applicable cause evaluation procedures.

Effectiveness of Corrective Actions: Based on a review of corrective action documents, interviews with licensee staff, and verification of completed corrective actions, the inspectors determined that overall, corrective actions were timely, commensurate with the safety significance of the issues, and effective, in that conditions adverse to quality were corrected. For significant conditions adverse to quality, the corrective actions directly addressed the cause and effectively prevented recurrence. The team reviewed performance indicators, ARs, and effectiveness reviews, as applicable, to verify that the significant conditions adverse to quality had not recurred. Effectiveness reviews for corrective actions to prevent recurrence (CAPRs) were sufficient to ensure corrective actions were properly implemented and were effective.

Assessment	71152B

Use of Operating Experience, Self-Assessments and Audits

The inspectors examined the licensee's program for obtaining and using industry operating experience. This included review of procedure PI-AA-102-1002, "Internal Operating Experience", selected corrective program action requests, and the licensee’s operating experience (OE) database to assess the effectiveness of how external and internal OE data was handled at the plant. Additionally, the inspectors selected OE documents such as NRC generic communications, licensee event reports, vendor notifications, and plant internal OE items which had been issued since January 2016 to verify whether the licensee had appropriately evaluated each notification for applicability to the Turkey Point Nuclear plant, and whether issues identified through these reviews were entered into the CAP.

The team determined that station’s processes for the use of industry and NRC operating experience information and for the performance of audits and self-assessments were effective and complied with all regulatory requirements and licensee standards. The implementation of these programs adequately supported nuclear safety. The team concluded that operating experience was adequately evaluated for applicability and that appropriate actions were implemented to address lessons learned as needed. The inspectors determined that the licensee was effective at performing self-assessments and audits to identify issues at

C3-132

FPSC EXH No. 5
03/18/2024

ADMITTED

C3-235

a low level, properly evaluated those issues, and resolved them commensurate with their safety significance.

Assessment	71152B

Safety Conscious Work Environment

Based on a sample size of approximately 20 people interviewed from a cross-section of plant employees, the team found no evidence of challenges to a safety-conscious work environment. Employees interviewed appeared willing to raise nuclear safety concerns through at least one of the several means available.

Preconditioning of safety-related check valves prior to retesting			
Cornerstone	Significance	Cross-cutting Aspect	Report Section
Mitigating Systems	Green NCV 05000250/2019010-02 Open/Closed	[H.9] - Training	71152B

The NRC identified a green, NCV of 10 CFR 50, Appendix B, Criterion V, in that the licensee failed to comply with procedure 0-ADM-502, In-Service Testing Program, when preconditioning of safety related check valves was conducted prior to retesting.

Description:

The inspectors reviewed ARs associated with the most recent surveillance testing on Unit 3 chemical and volume control system (CVCS) valves 312A, 312B and 312C. These 3-inch check valves are classified as safety-related Class 1 and provide a reactor coolant pressure boundary function. The valves are tested per the ASME OM code and the licensee's in-service test (IST) program as described in 0-ADM-502, In-Service Testing Program every 36 months during refueling outages. On October 12, 2018, valve 312C failed its IST with a leak rate of 220,000 standard cubic centimeters per minute (sccm). AR 2285407 described the acceptance criteria as no greater than 17,600 sccm. The licensee exited the test procedure, decided to back flush and seat the check valve and then performed a satisfactory IST retest. On October 14, 2018, valves 312A and 312B, failed their IST. Both valves had back flow leakage greater than the 12 gallons per minute (GPM) acceptance criteria. The licensee exited the test procedure and mechanically agitated the valve bodies with a brass hammer. A subsequent retest was satisfactory on both valves. The final disposition in associated AR 2285745 concluded that it was acceptable to apply additional forces to the valves to get them to re-seat. The inspectors noted that mechanically agitating valves 312A and 312B, and back flushing 312C were used to influence the performance of the "follow-up" test due to the unacceptable results of the IST "initial" tests. The licensee's IST program document 0-ADM-502, Section 5.1.1, item 11, states in part: "Preconditioning pumps and valves in the IST program shall be avoided. Preconditioning is the alteration, manipulation, or adjustment of the physical condition of an SSC before In-Service Testing for the expressed purpose of returning acceptable test results and masking action As Found conditions." The inspectors determined that during the Unit 3 refueling outage (PT3-30) valves 312A, 312B, and 312C were

C3-133

FPSC EXH No. 5
03/18/2024

ADMITTED

C3-236

preconditioned prior to “follow-up” tests.

The inspector’s review of the two previous ISTs on valves 312A and 312B identified additional examples of preconditioning. On October 16, 2010, valve 312A failed an initial IST. At that time the plan of record IST was a radiograph to verify the check was seated. AR 0587621 stated that “the use of mechanical agitation to ensure the disc was loose and not stuck in place is acceptable for this evolution.” The valve was mechanically agitated (hit with a brass hammer) and a new test method using a backflow leakage test criteria was performed to satisfy the IST. The retest obtained satisfactory IST results. The inspectors concluded this was an example of preconditioning. AR 2075864 described that on September 23, 2015, just before the 2015 Unit 3 refueling outage (PT3-28), the licensee identified that in dispositioning the 2010 issue they did not comply with the ASME OM code after the initial failure of 312A. The AR also discussed potential preconditioning, however no follow-up actions regarding preconditioning were taken. On October 7, 2015 a prompt operability determination was completed and valve 312A was determined to be operable but non-conforming. On October 31, 2015, during PT3-28 valves 312A and 312B failed the backflow IST. The test procedure was then revised to include an Air Operated Double Diaphragm (AODD) pump installed on the upstream side of the valve in an attempt to seat the check prior to re-performing the backflow tests. The inspectors concluded that the AODD pump preconditioned the valves. On November 1, 2015, valve 312B passed but valve 312A failed the retest. Radiography on November 1, 2015, confirmed that 312A was not fully seated. The radiograph performed on November 1, 2015, was similar to the October 16, 2010, radiograph results. Valve 312A disassembly revealed internal valve component critical clearances being exceeded due to vibration/oscillation induced wear of the disk post, disc arm post hole and hinge pin hole/bushings, and hinge pin. The sum total of the increased clearances allowed the outer diameter edge of the upper disc seat surface to lodge below the inner diameter edge of the upper body seat surface. In all the inspectors identified six examples of preconditioning which is prohibited by licensee’s IST program document.

Corrective Actions:

The licensee acknowledged the unacceptable preconditioning issues and entered them into the CAP. As corrective actions the licensee is planning to address acceptable and unacceptable preconditioning by implementing revisions to Operations, Maintenance, and Work Order Planning procedures and training for the Operations, Maintenance and Engineering departments.

Corrective Action References: ARs 2300895, 2303966, 2301832

Performance Assessment:

Performance Deficiency: Preconditioning safety-related valves 3-312A, 3-312B and 3-312C, after the initial IST failures and prior to the IST retest to obtain satisfactory test results, was a performance deficiency that was within the licensee’s ability to foresee, correct, and prevent.

Screening: The inspectors determined the performance deficiency was more than minor because if left uncorrected, it would have the potential to lead to a more significant safety concern. Specifically, preconditioning the check valves could mask conditions indicative of degradation occurring in each valve. These conditions, if left uncorrected, could result in the failure of the valve to perform its safety function during plant operation.

C3-134

FPSC EXH No. 5
03/18/2024

ADMITTED

C3-237

Significance: The inspectors assessed the significance of the finding using IMC 0609 Appendix A, "Significance Determination of Reactor Inspection Findings for At - Power Situations". Using IMC 0609, Appendix A, Exhibit 2, the inspectors determined the issue was of very low safety significance (Green) because it did not represent a loss of system or train function. The licensee conducted a past operability review and determined that each valve was currently operable but non-conforming.

Cross-cutting Aspect: H.9 - Training: The organization provides training and ensures knowledge transfer to maintain a knowledgeable, technically competent workforce and instill nuclear safety values. Specifically, the licensee did not provide adequate training to ensure a knowledgeable organization on the subject of preconditioning.

Enforcement:

Violation: 10 CFR Part 50, Appendix B, Criterion V, requires in part, that activities affecting quality shall be prescribed by documented instructions, procedures, or drawings, of a type appropriate to the circumstances and shall be accomplished in accordance with these instructions, procedures, or drawings.

IST program requirements and restrictions applicable to safety-related check valves 3-312A, 312B and 312C are provided in procedure 0-ADM-502, In-Service Testing Program. 0-ADM-502, Step 5.1.1, item 11, states that preconditioning pumps and valves in the IST program shall be avoided. Preconditioning is the alteration, variation, manipulation, or adjustment of the physical condition of a system, structure, or component (SSC), before in-service testing for the expressed purpose of returning acceptable test results and masking actual As Found conditions.

Contrary to the above, six examples of preconditioning were identified on the CVCS:

- On October 16, 2010, after the initial IST failure and prior to the IST retest, check valve 312A was preconditioned by mechanical agitation (hit with a brass hammer) to seat the check.
- On October 31, 2015, after the initial IST failures and prior to the IST retest, check valves 312A and 312B were preconditioned by installing a sandpiper pump to seat the check on each.
- On October 12, 2018, after the initial IST failure and prior to the IST retest check valve 312C was preconditioned by back flushing the valve to seat the check
- On October 14, 2018 after initial IST failures and prior to the IST retests, check valves 312A and 312B were preconditioned by mechanical agitation (hit with a brass hammer) to seat the check.

Enforcement Action: This violation is being treated as a Non-Cited Violation, consistent with Section 2.3.2 of the Enforcement Policy.

Failure to comply with the ASME OM code during safety-related check valve testing			
Cornerstone	Significance	Cross-cutting Aspect	Report Section

C3-135

FPSC EXH No. 5
03/18/2024

ADMITTED

C3-238

Mitigating Systems	Green NCV 05000250/2019010-03 Open/Closed	[P.1] - Identification	71152B

The NRC identified a green, Non-cited Violation (NCV) of 10 CFR 50.55a(f)(4), when the licensee failed to declare safety-related valves inoperable and failed to take corrective action after a failed IST as required by the ASME OM code.

Description:
The inspectors reviewed ARs associated with the most recent surveillance testing on Unit 3 CVCS valves 312A, 312B and 312C. These 3-inch check valves are classified as safety-related Class 1 and provide a reactor coolant pressure boundary function. The valves are tested per the ASME OM code and the licensee's IST program as described in 0-ADM-502, In-Service Testing Program every 36 months during refueling outages.

On October 12, 2018, valve 312C failed its IST with a leak rate of 220,000 standard cubic centimeters per minute (sccm). AR 2285407 described the acceptance criteria as no greater than 17,600 sccm. The licensee exited the test procedure, decided to back flush and seat the check valve and then performed a satisfactory IST retest.

On October 14, 2018, valves 312A and 312B, failed their IST. Both valves had back flow leakage significantly greater than the 12 gallons per minute (GPM) acceptance criteria. The licensee exited the test procedure and decided to mechanically agitate the valve bodies with a brass hammer. A subsequent retest was satisfactorily on both valves.

The inspectors determined that after the initial test failures for all three valves the licensee did not comply with the ASME OM code requiring the valves to be declared inoperable and for corrective actions to be implemented prior to retest.

The inspector's review of the two previous ISTs on valves 312A and 312B identified additional examples of non-compliance with the ASME OM code.

AR 0587621 described that on October 16, 2010, valve 312A failed an initial IST. The valve was mechanically agitated (hit with a brass hammer) and a new test method using a backflow leakage test criterion was performed to satisfy the IST. The retest obtained satisfactory IST results.

On October 31, 2015, during PT3-28 valves 312A and 312B failed the initial backflow IST. The test procedure was then revised to include an AODD pump installed on the upstream side of the valve in an attempt to seat the check prior to re-performing the backflow tests. The valves were not declared inoperable prior to this re-test. On November 1, 2015, valve 312B passed but valve 312A failed the retest. Radiography on November 1, 2015, confirmed that 312A was not fully seated. The radiograph performed on November 1, 2015, was similar to the October 16, 2010, radiograph results. Valve 312A disassembly revealed internal valve component critical clearances being exceeded due to vibration/oscillation induced wear of the disk post, disc arm post hole and hinge pin hole/bushings, and hinge pin. The sum total of the increased clearances allowed the outer diameter edge of the upper disc seat surface to lodge below the inner diameter edge of the upper body seat surface. A past operability review was completed on 312A for the period of concern from October 16, 2010 to November 7, 2015 and concluded that the valve was operable but degraded.

C3-136

FPSC EXH No. 5
03/18/2024

ADMITTED

C3-239

The inspectors determined that after the initial test failures for 312A in 2010, and 312A and 312B in 2015 the licensee did not comply with the ASME OM code requiring the valves to be declared inoperable and for corrective actions to be implemented prior to retest.

Corrective Actions:
The licensee acknowledged that they failed to follow the ASME OM code requiring IST valves that fail their initial IST to be declared inoperable and for corrective actions to be implemented prior to retest and entered them into the CAP.

Corrective Action References: ARs 2300895, 2303963

Performance Assessment:

Performance Deficiency: The licensee's repeated failures to declare safety-related valves 312A, 312B and 312C inoperable after a failed IST and failure to complete corrective actions prior to retest, as required by the ASME OM code, was a performance deficiency.

Screening: The inspectors determined the performance deficiency was more than minor because if left uncorrected, it would have the potential to lead to a more significant safety concern. Specifically, failing to declare safety-related valves inoperable after a failed IST and completing corrective actions prior to retest, as required by the ASME OM code could mask conditions indicative of degradation occurring in each valve. These conditions, if left uncorrected, could result in the failure of the valve to perform its safety function during plant operation.

Significance: The inspectors assessed the significance of the finding using IMC 0609 Appendix A, "Significance Determination of Reactor Inspection Findings for At - Power Situations". Using IMC 0609, Appendix A, Exhibit 2, the inspectors determined the issue was of very low safety significance (Green) because it did not represent a loss of system or train function. The licensee conducted a past operability review and determined that each valve was currently operable but non-conforming because the safety related function of the valve to open and provide a boration flow path to the RCS was maintained.

Cross-cutting Aspect: P.1 - Identification: The organization implements a corrective action program with a low threshold for identifying issues. Individuals identify issues completely, accurately, and in a timely manner in accordance with the program. The finding was determined to be reflective of present licensee performance from the period of October 2010 through October 2018, in that the license failed to identify issues completely, accurately, and in a timely manner in accordance with the IST program requirements. Specifically, multiple ARs were entered into the CAP after each failed IST but the licensee repeatedly failed to identify additional compliance requirements with the ASME OM code after each test failure.

Enforcement:

Violation: 10 CFR 50.55a(f)(4) requires, in part, that throughout the service life of a boiling or pressurized water-cooled nuclear power facility, pumps and valves that were classified as ASME Code Class1, Class 2 and Class 3 must meet the in-service test requirements set forth in the ASME OM Code. The ASME OM Code of record for Turkey Point Unit 3 was 2004 Edition through the 2006 Addenda. Subsection ISTC-5224, Corrective Action, described the required actions to be taken as a result of a test failure and states in part "If a check valve fails to exhibit the required change of obturator position, it shall be declared inoperable. A

C3-137

FPSC EXH No. 5
03/18/2024

ADMITTED

retest showing acceptable performance shall be run following any required corrective action before the valve is returned to service."

Contrary to the above, six examples of non-compliance with the ASME OM code subsection ISTC-5224 were identified on the CVCS system where after initial failure of the IST the licensee did not declare the valves inoperable and did not take corrective actions as required by the code. The specific dates were:

- On October 16, 2010 after the IST failure of valve 312A.
- On October 31, 2015, after the IST failures of valves 312A and 312B.
- On October 12, 2018, after the LLRT failure of valve 312C.
- On October 14, 2018, after the IST failures of valves 312A and 312B.

Enforcement Action: This violation is being treated as a Non-Cited Violation, consistent with Section 2.3.2 of the Enforcement Policy.

Inadequate Maintenance Procedures to Ensure Flood Protection for the 4A and 4B RHR trains			
Cornerstone	Significance	Cross-cutting Aspect	Report Section
Mitigating Systems	Green NCV 05000251/2019010-01 Open/Closed	[H.11] - Challenge the Unknown	71152B
The NRC identified a green, NCV of Technical Specification 6.8.1, for the licensee's failure to establish, implement and maintain written procedures to prevent foreign material from potentially degrading the RHR pump room sump pumps.			

Description:

Previously in 2016, the NRC had issued NCV 05000251/2016003-01, Failure to provide adequate flood protection, for the 4A RHR train due to debris that could potentially degrade the room's sump pumps. On February 15, 2019, NRC inspectors discovered debris in both the Unit 4 RHR pump rooms. Insulation material in open, unsecured, clear plastic bags was staged on the floor of both pump rooms near the sumps per Work Order 40570457. The licensee performed an immediate operability evaluation as part of AR 02302239 which concluded the RHR pumps remained operable because the sump pumps have an alarm and that the open bags containing the insulation material would have been prevented or slowed from migrating to the sump pumps. The NRC inspectors reviewed the AR 02302239 and concluded that any degradation caused by the loose insulation or the bags would occur slowly enough that the alarm function would allow operator action to preserve the safety function of the RHR pumps in the rooms. Also the likelihood of a flood initiating in both rooms simultaneously was very low, thus it was not deemed credible to have a total loss of the RHR function. Turkey Point documented design and licensing basis requirements in RHR DBD 5610-050-DB-001 and Licensing commitment N0056 credited measures to mitigate flooding in the RHR pump rooms. The flood protection device referred to was the two sump pumps in each room.

FPSC EXH No. 5
03/18/2024

ADMITTED

C3-241

Corrective Actions: The licensee took immediate corrective actions to secure the bagged insulation in the 4A and 4B RHR pump rooms and initiated a past-operability review.

Corrective Action Reference: AR 02302239

Performance Assessment:

Performance Deficiency: The failure to have adequate maintenance procedures to control foreign material from potentially affecting the performance of the RHR pump rooms' flood mitigating equipment is a performance deficiency.

Screening: The inspectors determined the performance deficiency was more than minor because if left uncorrected, it would have the potential to lead to a more significant safety concern. Specifically, the licensee's failure to maintain written procedures or documented instructions required by Regulatory Guide 1.33 that address maintenance activities in the RHR pump rooms led to an unnecessary potential flood mitigation challenge to both the 4A and 4B RHR pumps.

Significance: The inspectors assessed the significance of the finding using IMC 0609 Appendix A, "Significance Determination of Reactor Inspection Findings for At - Power Situations". Using IMC 0609, Appendix A, Exhibit 4, the inspectors determined the issue was of very low safety significance (Green) because the finding was related to RHR pumps and did not result in an associated total loss of any safety function.

Cross-cutting Aspect: H.11 - Challenge the Unknown: Individuals stop when faced with uncertain conditions. Risks are evaluated and managed before proceeding. This finding was assigned a cross-cutting aspect in the human performance area because the licensee staff failed to stop when the WO required the insulation to be removed but it didn't direct were to store the material and risks, such as flooding, were not evaluated and managed before proceeding.

Enforcement:

Violation: Technical Specification 6.8.1 requires written procedures specified by the Quality Assurance Topical Report (QATR) to be established, implemented, and maintained. The QATR requires procedures for maintenance listed in section 9a of Appendix A of NRC Regulatory Guide 1.33, Quality Assurance Program Requirements, Revision 2, dated February 1978. Regulatory Guide 1.33 requires, in part, that maintenance activities that can affect the performance of safety-related equipment be performed in accordance with written procedures, documented instructions, or drawings appropriate to the circumstances. Contrary to the above, from February 15, 2019 to present, the licensee did not have guidance that was established, implemented, and maintained to preclude maintenance activities from introducing materials that could affect the function of the Unit 4A and 4B RHR pumps in a flooding event. Specifically work order 40570457 titled "Remove insulation in 4A RHR pump room" did not reference a governing procedure or provide specific instructions to ensure that removed insulation was properly stored so that it would not clog the sump pumps used to mitigate flooding concerns. The licensee took immediate corrective actions to secure the bagged insulation in the 4A and 4B RHR pump rooms and initiated a past-operability review.

C3-139

FPSC EXH No. 5
03/18/2024

ADMITTED

C3-242

Enforcement Action: This violation is being treated as a Non-Cited Violation, consistent with Section 2.3.2 of the Enforcement Policy.

EXIT MEETINGS AND DEBRIEFS

The inspectors verified no proprietary information was retained or documented in this report.

- On March 1, 2019, the inspector presented the inspection results to Mr. Robert Coffey, Regional Vice President – Southern Region and other members of the licensee staff.

LIST OF DOCUMENTS REVIEWED

Procedures
0-ADM-225 Online Risk Assessments
0-ADM-532, ASME Section XI Repair / Replacement Program, Revision 1
3-NOP-040.02, Refueling Core Shuffle, Revision 21
3-NOP-040.03, Fuel Handling and Insert Shuffle in the Spent Fuel Pit, Revision 18
3-OSP-055.1, Emergency Containment Cooler Operability Test
AD-AA-103, Nuclear Safety Culture Program
EN-AA-203-1001, Operability Determinations / Functionality Assessments, Revision 32
MA-AA-100-1008, Station Housekeeping and Material Control, Revision 13 dated 09/08/2016
MA-AA-100-1008, Station Housekeeping and Material Control, Revision 20 dated 02/08/2019
MA-AA-100-1022, Insulation Removal, Installation for Maintenance Activities
OP-AA-108-1000, Operator Challenges Program Management
OP-AA-108-1000-F01, Revision 2, Operator Challenge Assessment Sheet
PI-AA-100-1005, Root Cause Analysis
PI-AA-100-1005-F04, Effectiveness Review Form
PI-AA-102, Operating Experience Program, Revision 16
PI-AA-102-1001, Operating Experience Program Screening and Responding to Incoming Operating Experience
PI-AA-102-1002, Internal Operating Experience, Revision 10
PI-AA-104-1000, Condition Reporting
AD-AA-103, Nuclear Safety Culture Program, Revision 12
ER-AA-100-2002-10000, Maintenance Rule Activity Guidance, Revision 2
ER-AA-100-2002, Maintenance Rule Program Administration, Revision 7
ER-AA-101, Equipment Reliability, Revision 9
ER-AA-201-2001, System and Program Health Reporting, Revision 14
ER-AA-201-2002, System Performance Monitoring, Revision 6
ER-AA-201, Detection Process for Equipment Performance, Revision 5
NA-AA-200-1000, Employee Concerns Program, Revision 2
PI-AA-01, Corrective Action Program and Condition Reporting, Revision 4
PI-AA-02, Self-Assessment, Revision 0
PI-AA-03, Operating Experience, Revision 1
PI-AA-04, Human Performance, Revision 0
PI-AA-05, Change Management, Revision 2
PI-AA-100, Condition Assessment and Response, Revision 11
PI-AA-100-105, Condition Assessment and Response, Revision 18
PI-AA-100-106, Common Cause Evaluation, Revision 16

C3-140

FPSC EXH No. 5
03/18/2024

ADMITTED

C3-248

PI-AA-100-107, Issue Investigation, Revision 21
PI-AA-100-108, Condition Evaluation, Revision 09
PI-AA-101, Assessment and Improvement Program, Revision 26
PI-AA-104-1000, Condition Reporting, Revision 20
PI-AA-203, Action Tracking Management, Revision 12

0-ADM-016.4, Fire Watch Program, Revision 11A
0-NCAP-027, Calibration and Operation of the Benchtop pH/Conductivity/TDS Meter, Revision 1
OGMP-102.21, Installation and Maintenance of Thermo-lag Fire Barrier Systems, Revision 2
EN-AA-213-1000-F01, Engineering Product Risk and Consequences Assessment, Revision 4
MM-AA-100, Conduct of Maintenance, Revision 8
MM-AA-100-1008, Housekeeping and Material Control, Revision 19
MM-AA-101-1000, Foreign Material Exclusion, Revision 22
0-ADM-502, In-service Testing (IST) Program
0-ADM-531, Containment Leakage Rate Testing Program
0-ADM-539, In-service Testing – Condition Monitoring of Check Valves
3-OSP-047.1D, Charging Line Isolation and Check Valve Test
3-OSP-047.2, 3-312A and 3-312B In-service Test
3-OSP-051.5, Local Leak Rate Tests
4-OSP-051.5, Local Leak Rate Tests
ER-AA-100-2002, Maintenance Rule Program Administration
ER-AA-113-1000, In-service Testing Procedure
MA-AA-203-1000, Maintenance Testing
MA-AA-203-1001, Work Order Planning
TP-15-006, 3-312A and 3-312B Closure Test

ARs Reviewed

2146943, 2180657, 2220785, 2235484, 2239149, 2241062, 2246906, 2248895, 2262955, 2264188, 2301504, 2302239, 2216800, 2155629, 2123851, 2129632, 2155318, 2239149, 2042744, 2056905, 2147487, 2155881, 2170347, 2181184, 2181350, 2187711, 2188672, 2192198, 2194260, 2194720, 2206181, 2212152, 2214729, 2222270, 2224143, 2224218, 2249535, 2261216, 2261941, 2264782, 0587621, 1728305, 2075864, 2087510, 2088888, 2095982, 2152029, 2155621, 2180643, 2180974, 2187392, 2212379, 2212385, 2213443, 2218834, 2220993, 2283013, 2285407, 2285537, 2285745, 2287548, 2287883, 2288068, 2228814, 2285407, 2285745, 2296174, 2300895

Assessments:
SSC Preconditioning Issues in the NextEra Energy Fleet 2301832
EP Readiness for January 2018 NRC Program Inspection 2239789
PTN 4A Intake Cooling Water Pump CMM 2255778
Pre-NRC 71111.11 Licensed Operator Continuing Training 2191963
PT4-30 Rad Worker Practices 2231158
Risk Management 2291826
Boric Acid Corrosion Control 2218853
PTN Outage S/D Risk Strategy 2195583
Professionalism at PTN 2207311
PTN Review of Maintenance Five Focus Areas 2240755
PTN On-line Work Management 2235702
PT3-29 Foreign Material Exclusion Control 2195558
PT3-29 Plant Readiness for Operations 2202133

C3-141

FPSC EXH No. 5
03/18/2024

ADMITTED

C3-244

PTN-Operational Decision Making 2211949

Other Documents
Quality Assurance Topical Report, (FPL-1), Revision 21
Turkey Point Unit 3 – Key PRA Results, Revision 11
OWA, Burdens, CRD, Compensatory Actions, NSO Top Ten challenge and Temp modifications lists, current 2/11/19
Drawing 5614-M-3064, Safety Injection Accumulator System inside Containment
TR-AA-230-1000 Training Analysis Worksheet for ASME Section XI potential knowledge gaps
RHR DBD 5610-050-DB-001, Revision 11 dated 11/30/2007
Licensing commitment N0056, dated September 4, 1979
AT-01.01 AR Report (All Security Related AR's 1/1/2017 to 12/31/2018)
Control Room Report-Fire Protection Impairment List, 2/19/2019
Mentoring Guide Fire Protection Program Owner, Revision 2
Root Cause Evaluation for AR 2192198 High Energy Arc Fault Event of 3/18/2017
Notifier Fire Detection System Manual VTM V001049
Work Package 40559449, Unit 4 SG Main Feed-water Flow Control Valve Trouble Shooting
CN-2.29 Specification for Electrical Conduit and Cable Tray Supports PTN Unit 3 & 4, Revision 2
Licensee Event Report (LER) 2017-001-00, Phase to Ground Flashover from Thermo-Lag

Work orders
40570457, 40538300, 40538199, 40550272, 40407132, 40546401, 40578200, 406244

C3-142

C3-245

FPSC EXH No. 5
03/18/2024

ADMITTED

UNITED STATES
NUCLEAR REGULATORY COMMISSION
REGION II
245 PEACHTREE CENTER AVENUE N.E., SUITE 1200
ATLANTA, GEORGIA 30303-1200

February 11, 2021

Mr. Don Moul
Executive Vice President, Nuclear Division and Chief Nuclear Officer
Florida Power & Light Company
Mail Stop: EX/JB
700 Universe Blvd
Juno Beach , FL 33408

SUBJECT: TURKEY POINT UNITS 3 & 4 – INTEGRATED INSPECTION REPORT 05000250/2020004 AND 05000251/2020004 AND INDEPENDENT SPENT FUEL STORAGE INSTALLATION INSPECTION (ISFSI) 07200062/2020002

Dear Mr. Moul:

On December 31, 2020, the U.S. Nuclear Regulatory Commission (NRC) completed an inspection at Turkey Point Units 3 & 4. On January 14, 2021, the NRC inspectors discussed the results of this inspection with Mr. Michael Pearce, Site Vice President, and other members of your staff. The results of this inspection are documented in the enclosed report.

One finding of very low safety significance (Green) is documented in this report. This finding involved a violation of NRC requirements. We are treating this violation as a non-cited violation (NCV) consistent with Section 2.3.2 of the Enforcement Policy.

If you contest the violation or the significance or severity of the violation documented in this inspection report, you should provide a response within 30 days of the date of this inspection report, with the basis for your denial, to the U.S. Nuclear Regulatory Commission, ATTN: Document Control Desk, Washington, DC 20555-0001; with copies to the Regional Administrator, Region II; the Director, Office of Enforcement; and the NRC Resident Inspector at Turkey Point Units 3 & 4.

If you disagree with a cross-cutting aspect assignment in this report, you should provide a response within 30 days of the date of this inspection report, with the basis for your disagreement, to the U.S. Nuclear Regulatory Commission, ATTN: Document Control Desk, Washington, DC 20555-0001; with copies to the Regional Administrator, Region II; and the NRC Resident Inspector at Turkey Point Units 3 & 4.

C3-143

FPSC EXH No. 5
03/18/2024
D. Moul
ADMITTED

This letter, its enclosure, and your response (if any) will be made available for public inspection and copying at http://www.nrc.gov/reading-rm/adams.html and at the NRC Public Document Room in accordance with Title 10 of the *Code of Federal Regulations* 2.390, "Public Inspections, Exemptions, Requests for Withholding."

Sincerely,

/RA/

Booma Venkataraman, Acting Chief
Reactor Projects Branch 3
Division of Reactor Projects

Docket Nos. 05000250, 05000251 and 07200062
License Nos. DPR-31 and DPR-41

Enclosure:
As stated

cc w/ encl: Distribution via LISTSERV®

FPSC EXH No. 5
03/18/2024
D. Moul
ADMITTED

SUBJECT: TURKEY POINT UNITS 3 & 4 – INTEGRATED INSPECTION REPORT 05000250/2020004 AND 05000251/2020004 dated February 11, 2021

DISTRIBUTION:
M. Kowal
S. Price
L. Gibson
RidsNrrPMTurkeyPoint Resource
Public
RidsNrrDro Resource

ADAMS ACCESSION NUMBER: ML21042A078

X SUNSI Review		X Non-Sensitive ☐ Sensitive		X Publicly Available ☐ Non-Publicly Available	
OFFICE	Rii/DRP	RII/DRP	RII/DRP	RII/DRP	
NAME	R. Reyes	D. Orr	J. Hamman	B. Venkataraman	
DATE	02/10/2021	02/10/2021	02/10/2021	02/11/2021	

OFFICIAL RECORD COPY

FPSC EXH No. 5
03/18/2024

ADMITTED

C3-248

U.S. NUCLEAR REGULATORY COMMISSION
Inspection Report

Docket Numbers:	05000250, 05000251 and 07200062
License Numbers:	DPR-31 and DPR-41
Report Numbers:	05000250/2020004, 05000251/2020004, and 07200062/2020002
Enterprise Identifier:	I-2020-004-0039 and I-2020-002-007
Licensee:	Florida Power & Light Company
Facility:	Turkey Point Units 3 & 4
Location:	Homestead, FL 33035
Inspection Dates:	October 01, 2020 to December 31, 2020
Inspectors:	P. Cooper, Senior Reactor Inspector C. Dykes, Senior Health Physicist M. Magyar, Reactor Inspector D. Orr, Senior Resident Inspector R. Reyes, Resident Inspector J. Rivera, Health Physicist
Approved By:	Booma Venkataraman, Acting Chief Reactor Projects Branch 3 Division of Reactor Projects

C3-146

FPSC EXH No. 5
03/18/2024

ADMITTED

C3-249

SUMMARY

The U.S. Nuclear Regulatory Commission (NRC) continued monitoring the licensee's performance by conducting an integrated inspection at Turkey Point Units 3 & 4, in accordance with the Reactor Oversight Process. The Reactor Oversight Process is the NRC's program for overseeing the safe operation of commercial nuclear power reactors. Refer to https://www.nrc.gov/reactors/operating/oversight.html for more information.

List of Findings and Violations

Inadequate procedural compliances during erecting of scaffold caused damage to safety-related motor operated valve during operation			
Cornerstone	Significance	Cross-Cutting Aspect	Report Section
Mitigating Systems	Green NCV 05000251/2020004-01 Open/Closed	[H.8] - Procedure Adherence	71111.15
A self-revealed, Green finding and associated, non-cited violation (NCV) of Technical Specification 6.8.1 was identified when the licensee failed to follow procedure MA-AA-100-1002, Scaffold Installation, Modification, and Removal Requests, when the licensee erected a scaffold that interfered with operation of plant equipment. During testing of motor-operated valve, MOV-4-861B, containment south recirculation sump isolation valve, the valve stem local position indicator impacted a scaffold in the B residual heat removal (RHR) pump room and caused damage to the position indicator requiring MOV-4-861B to be taken out of service for corrective maintenance.			

Additional Tracking Items

Type	Issue Number	Title	Report Section	Status
LER	05000250/2020-004-00	LER 2020-004-00 for Turkey Point Unit 3 re Manual Reactor Trip in Response to Automatic Trip of the 3B Steam Generator Feedwater Pump	71153	Closed
LER	05000250/2020-003-00	LER 2020-003-00 for Turkey Point, Unit 3, Automatic Reactor Trip due to High Source Range Flux during Reactor Startup	71153	Closed

C3-147

C3-250

FPSC EXH No. 5
03/18/2024

ADMITTED

PLANT STATUS

Unit 3 began the inspection period at near rated thermal power. Unit 3 experienced an automatic turbine runback to 83% power on November 7, 2020, in response to several feedwater system control valves failing and causing the heater drain pumps to trip. Unit 3 was down-powered to 25% on November 21, 2020, to facilitate repairs to the Distributed Control System which was the cause for several feedwater system control valves failing on November 7, 2020. Unit 3 was returned to rated thermal power on November 23, 2020. Unit 3 was down-powered to 42% rated thermal power on December 2, 2020, to facilitate an emergent repair to a protective relay associated with the 3C transformer. The 3C transformer supplies electrical power to the 3C condensate and 3B steam generator feedwater pumps. Unit 3 was returned to rated thermal power on December 5, 2020. Unit 3 was down-powered to 50% power on December 16, 2020, when operators entered an off-normal procedure for high sodium concentrations in all three steam generators. Unit 3 power was increased to 55% on December 24 and remained at that power level for the remainder of the inspection period to facilitate main condenser tube inspections and plugging to eliminate the source of sodium contamination in the condensate system.

Unit 4 began the inspection period in end-of-cycle coastdown at 95% rated thermal power and was shutdown on October 3, 2020, to begin refueling outage T4R32. Unit 4 was restarted on November 14, 2020, and returned to rated thermal power on November 22, 2020, and remained at or near rated thermal power for the remainder of the inspection period.

INSPECTION SCOPES

Inspections were conducted using the appropriate portions of the inspection procedures (IPs) in effect at the beginning of the inspection unless otherwise noted. Currently approved IPs with their attached revision histories are located on the public website at http://www.nrc.gov/reading-rm/doc-collections/insp-manual/inspection-procedure/index.html. Samples were declared complete when the IP requirements most appropriate to the inspection activity were met consistent with Inspection Manual Chapter (IMC) 2515, “Light-Water Reactor Inspection Program - Operations Phase.” The inspectors performed plant status activities described in IMC 2515, Appendix D, “Plant Status,” and conducted routine reviews using IP 71152, “Problem Identification and Resolution.” The inspectors reviewed selected procedures and records, observed activities, and interviewed personnel to assess licensee performance and compliance with Commission rules and regulations, license conditions, site procedures, and standards.

Starting on March 20, 2020, in response to the National Emergency declared by the President of the United States on the public health risks of the Coronavirus Disease 2019 (COVID-19), resident inspectors were directed to begin telework and to remotely access licensee information using available technology. During this time, the resident inspectors performed periodic site visits each week; conducted plant status activities as described in IMC 2515, Appendix D, “Plant Status”; observed risk-significant activities; and completed on-site portions of IPs. In addition, resident and regional baseline inspections were evaluated to determine if all or portions of the objectives and requirements stated in the IP could be performed remotely. If the inspections could be performed remotely, they were conducted per the applicable IP. In some cases, portions of an IP were completed remotely and on-site. The inspections documented below met the objectives and requirements for completion of the IP.

REACTOR SAFETY

C3-148

FPSC EXH No. 5
03/18/2024
ADMITTED

71111.04 - Equipment Alignment

Partial Walkdown Sample (IP Section 03.01) (1 Sample)

The inspectors evaluated system configurations during partial walkdowns of the following systems/trains:

(1) 3A, 3B, and 4B high head safety injection pumps; Unit 3 refueling water storage tank; and, the 3A, 3B, and 4B safety-related 4 kilo-Volt (kV) switchgears while the 4A safety-related 4kV switchgear was out of service (OOS) on October 15, 2020

Complete Walkdown Sample (IP Section 03.02) (1 Sample)

(1) Unit 3 and Unit 4 Auxiliary Feedwater Systems on November 4, 2020

71111.05 - Fire Protection

Fire Area Walkdown and Inspection Sample (IP Section 03.01) (1 Sample)

The inspectors evaluated the implementation of the fire protection program by conducting a walkdown and performing a review to verify program compliance, equipment functionality, material condition, and operational readiness of the following fire areas:

(1) Unit 3A, 3B, 4A and 4B Safety-related 4Kv Switchgears, Fire zones 71, 70, 68 and 67 respectively. Unit 3A, 3B, 3C, 3D, 4A, 4B, 4C, and 4D safety-related 480-Volt Load Centers, Fire zones 095, 096, 093 and 094 respectively, on November 9, 2020

71111.08P - Inservice Inspection Activities (PWR)

PWR Inservice Inspection Activities Sample (IP Section 03.01) (1 Sample)

(1) The inspectors verified that the reactor coolant system boundary, steam generator tubes, reactor vessel internals, risk-significant piping system boundaries, and containment boundary are appropriately monitored for degradation and that repairs and replacements were appropriately fabricated, examined and accepted by reviewing the following activities from October 12 - 16, 2019:

03.01.a - Nondestructive Examination and Welding Activities.

- Ultrasonic Testing (UT)
  - 12"-RC-1401-9, Pressurizer safe end to nozzle weld, ASME Class 1, Report # 5.39-001
  - 3"-CH-1401-37, Elbow to Branch Connection, AUG/MRP-146, ASME Class 1, WO#40679281
- Liquid Penetrant (PT)
  - 4-312A, Replacement of Charging to Reactor Coolant Loop "A" Check Valve, ASME Class 1, WO#40656497
  - 12"-RC-1401-9, Pressurizer safe end to nozzle weld, AUG/LR, ASME Class 1 , WO#40678614
- Radiographic Inspection Technique (RT)
  - 4-312A, Replacement of Charging to Reactor Coolant Loop "A" Check Valve, ASME Class 1, WO#40656497

FPSC EXH No. 5
03/18/2024
ADMITTED

C3-252

03.01.c – Pressurized-Water Reactor Boric Acid Corrosion Control Activities.

- 4-298J, RCP C Seal Water Injection Isolation Valve, AR02370233
- CV-4-310A, Charging to RC loop A Control Valve, AR02370232

71111.11A - Licensed Operator Requalification Program and Licensed Operator Performance

Requalification Examination Results (IP Section 03.03) (1 Sample)

The licensee completed the annual requalification operating examinations required to be administered to all licensed operators in accordance with Title 10 of the *Code of Federal Regulations* 55.59(a)(2), "Requalification Requirements," of the NRC's "Operator's Licenses." During the week of December 28, 2020, the inspector performed an in-office review of the overall pass/fail results of the individual operating examinations, the crew simulator operating examinations, and the biennial written examinations in accordance with Inspection Procedure (IP) 71111.11, "Licensed Operator Requalification Program." These results were compared to the thresholds established in Section 3.02, "Requalification Examination Results," of IP 71111.11.

(1) The inspectors reviewed and evaluated the licensed operator examination failure rates for the requalification annual operating exam administered on December 2, 2020.

71111.11Q - Licensed Operator Requalification Program and Licensed Operator Performance

Licensed Operator Performance in the Actual Plant/Main Control Room (IP Section 03.01) (1 Sample)

(1) The inspectors observed and evaluated licensed operator performance in the control room during:

- 4-GOP-305, Hot Standby to Cold Shutdown; 4-ONOP-046.4, Malfunction of Boron Concentration Control System; and, 4-OSP-059.6, Source Range High Flux at Shutdown Setpoint Calibration on October 3, 2020
- 4-NOP-041.07, Draining the Reactor Coolant System on October 6 - 7, 2020
- Through wall leak on the Unit 4 emergency boration line and Technical Specification 3.0.3 entry and exit on December 14, 2020

Licensed Operator Requalification Training/Examinations (IP Section 03.02) (1 Sample)

(1) The inspectors observed and evaluated an operating crew's response to a requalification training simulator scenario in the control room simulator on November 19, 2020.

71111.12 - Maintenance Effectiveness

Maintenance Effectiveness (IP Section 03.01) (1 Sample)

C3-150

FPSC EXH No. 5
03/18/2024
ADMITTED

C3-253

The inspectors evaluated the effectiveness of maintenance to ensure the following structures, systems, and components (SSCs) remain capable of performing their intended function:

(1) AR 2092653, Unit 3 startup transformer lockout (event date on November 18, 2015) and a(1) action plan on December 22, 2020

Quality Control (IP Section 03.02) (1 Sample)

The inspectors evaluated the effectiveness of maintenance and quality control activities to ensure several safety-related SSCs remained capable of performing their intended function by reviewing multiple work orders and ensuring quality control verifications were properly specified in accordance with the Quality Assurance Program and implemented in:

(1) Work orders 40569949, 40631128, 40669279, 40631121, 40657784, 40670685, 40735938, 40656497, 40669087, 40633489, 40669176, 40668808, 40668806, 40668859, 40744785, 40668907, and 40668875 on December 8, 2020 and December 9, 2020

71111.13 - Maintenance Risk Assessments and Emergent Work Control

Risk Assessment and Management Sample (IP Section 03.01) (1 Sample)

The inspectors evaluated the accuracy and completeness of risk assessments for the following planned and emergent work activities to ensure configuration changes and appropriate work controls were addressed:

(1) Unit 3 online and Unit 4 shutdown risk assessment while the 4A safety-related 4kV switchgear and associated loads were OOS on October 13 and 16, 2020

71111.15 - Operability Determinations and Functionality Assessments

Operability Determination or Functionality Assessment (IP Section 03.01) (5 Samples)

The inspectors evaluated the licensee's justifications and actions associated with the following operability determinations and functionality assessments:

(1) Action Requests (ARs) 2372250 and 2372386, 4A sequencer relays model RXMB1 found with cracks on case on October 21, 2020
(2) AR 2370173, Source range nuclear instrument, N-4-31, OOS for drifting indication on October 26, 2020
(3) AR 2374494, Auxiliary building concrete discovered unexpected level of degradation on November 16, 2020
(4) AR 2374542, Charging to reactor coolant loop A check valve, 4-312A, failed post-maintenance back leakage acceptance criteria on November 23, 2020
(5) AR 2369425, Containment south recirculation sump isolation valve, 4-861B MOV, did not travel open on October 1, 2020

71111.18 - Plant Modifications

C3-151

FPSC EXH No. 5
03/18/2024

ADMITTED

C3-254

Temporary Modifications and/or Permanent Modifications (IP Section 03.01 and/or 03.02) (1 Sample)

The inspectors evaluated the following temporary or permanent modifications:

(1) Engineering change (EC) 295393, Replacement of charging to reactor coolant loop A check valve, 4-312A, on October 29, 2020

71111.19 - Post-Maintenance Testing

Post-Maintenance Test Sample (IP Section 03.01) (6 Samples)

The inspectors evaluated the following post-maintenance test activities to verify system operability and functionality:

(1) Work order (WO) 40631121-27, 4A Containment Spray Pump 480 V Breaker Replacement and Modification to MasterPac Style. Post-maintenance test (PMT) performed within work order task and reviewed on October 16, 2020.
(2) WO 40669087, Letdown Relief Valve, RV-4-203, Replacement and WO 40746020, Letdown Flow Control Valve, CV-4-200C, Overhaul. PMT performed using 4-OSP-051.5, Local Leak Rate Test (Section 7.14 Containment Penetration 14, Letdown) and reviewed on October 30, 2020.
(3) WO 40400199, Positioner Replacement for FCV-4-489, 4B Feedwater Bypass Flow Control Valve per EC 293060. PMT performed using 4-OSP-074.5, FW Control Valve and Bypass Valve Inservice Test and reviewed on November 11, 2020
(4) WO 40656497, Charging to Reactor Coolant Loop A Check Valve, 4-312A, Replacement. PMT performed using 4-OSP-047.1D, Charging Line Isolation and Check Valve Test and reviewed on November 20, 2020.
(5) WO 40747435, 4B Reactor Coolant Pump Power Cable Electrical Penetration Repair. PMT performed using 4-OSP-051.5, Local Leak Rate Test (Section 7.48 4kV RCP Electrical Penetration) and reviewed on November 23, 2020.
(6) WO 40744940, 4B Main Steam Line Dump to Atmosphere Control Valve, CV-4-1607, Overhaul. PMT performed using 4-OSP-206.1, Inservice Valve Testing - Cold Shutdown (Section 7.1 Main Steam Valve Test) and reviewed on November 23, 2020.

71111.20 - Refueling and Other Outage Activities

Refueling/Other Outage Sample (IP Section 03.01) (1 Sample)

(1) The inspectors evaluated Unit 4 refueling outage PT4-32 activities from October 3 to November 17, 2020

71111.22 - Surveillance Testing

The inspectors evaluated the following surveillance tests:

Surveillance Tests (other) (IP Section 03.01) (2 Samples)

C3-152

FPSC EXH No. 5
03/18/2024
ADMITTED

C3-255

(1) 4-OSP-072.6, Main Steam Safety Valve Set Point Surveillance Using Team Trevitest Mark VIII Equipment (for relief valves RV-4-1400, 1403, 1407 and 1412) on October 16, 2020
(2) 4-OSP-203.1, Train A Engineered Safeguards Integrated Test on November 17, 2020

Containment Isolation Valve Testing (IP Section 03.01) (1 Sample)

(1) 4-OSP-051.5, Local Leak Rate Tests, section 7.14, Containment Penetration 14 - Letdown, on October 13, 2020

71114.06 - Drill Evaluation

Select Emergency Preparedness Drills and/or Training for Observation (IP Section 03.01) (1 Sample)

(1) The inspectors evaluated virtual table-top scenarios for the technical support center and emergency operations facility responders on December 16 and 17, 2020

RADIATION SAFETY

71124.01 - Radiological Hazard Assessment and Exposure Controls

Radiological Hazard Assessment (IP Section 03.01) (1 Sample)

(1) The inspectors evaluated how the licensee identifies the magnitude and extent of radiation levels and the concentrations and quantities of radioactive materials and how the licensee assesses radiological hazards.

Instructions to Workers (IP Section 03.02) (1 Sample)

(1) The inspectors evaluated radiological protection-related instructions to plant workers.

Contamination and Radioactive Material Control (IP Section 03.03) (2 Samples)

The inspectors evaluated licensee processes for monitoring and controlling contamination and radioactive material.

(1) Observed licensee perform surveys of potentially contaminated material leaving Unit 4 Containment and the Radiological Control Area (RCA).
(2) Observed workers exiting Unit 4 Containment and the RCA during Unit 4 refueling outage.

Radiological Hazards Control and Work Coverage (IP Section 03.04) (3 Samples)

The inspectors evaluated in-plant radiological conditions during facility walkdowns and observation of radiological work activities.

(1) RWP 20-4100 Task 15 Unit 4 Reactor Head Lift, Rev 00
(2) RWP 20-4014 Job Specific, Unit 4 Reactor Sump Entry, Rev 00
(3) RWP 20-4100 Task 1, Unit 4 Upper Internals Lift, Rev 00

C3-153

FPSC EXH No. 5
03/18/2024

ADMITTED

C3-256

High Radiation Area and Very High Radiation Area Controls (IP Section 03.05) (3 Samples)

During facility walkdowns, the inspectors reviewed several postings and physical controls for High Radiation Areas (HRAs), Locked High Radiation Areas (LHRAs), and Very High Radiation Areas (VHRAs) located in the following areas:

(1) Unit 4 Auxiliary Building
(2) Unit 4 Containment
(3) Unit 4 Radwaste Building

Radiation Worker Performance and Radiation Protection Technician Proficiency (IP Section 03.06) (1 Sample)

(1) The inspectors evaluated radiation worker and radiation protection technician performance as it pertains to radiation protection requirements.

71124.08 - Radioactive Solid Waste Processing & Radioactive Material Handling, Storage, & Transportation

Radioactive Material Storage (IP Section 03.01) (1 Sample)

(1) Inspectors evaluated the licensee's performance in controlling, labelling and securing radioactive materials.

Radioactive Waste System Walkdown (IP Section 03.02 (1 Sample)

(1) Inspectors walked down accessible portions of the solid radioactive waste systems and evaluated system configuration and functionality.

Waste Characterization and Classification (IP Section 03.03) (2 Samples)

The inspectors evaluated the licensee's characterization and classification of radioactive waste.

(1) 10 CFR 61 Analysis 2018 DAW
(2) 10 CFR 61 Analysis 2018 RAM

Shipment Preparation (IP Section 03.04) (1 Sample)

(1) The inspectors observed shipment no. PTN-M-20-057 containing LSA-II used laundry, for review against requirements.

Shipping Records (IP Section 03.05) (4 Samples)

(1) W-18-014, UN3321, Radioactive Material, Low specific activity (LSA-II), 7, Depleted Resin in HIC, 10/24/2018
(2) W-18-011, UN3221, Radioactive Material, Low specific activity (LSA-II), 7, DAW, 10/04/2018
(3) W-19-006, UN3221, Radioactive Material, Low specific activity (LSA-II), 7 fissile excepted, DAW, 06/14/2019

C3-154

FPSC EXH No. 5
03/18/2024
ADMITTED

C3-257

(4) W-20-003, UN3221, Radioactive Material, Low specific activity (LSA-II), 7, fissile excepted, 2018 DAW, 03/17/2020

OTHER ACTIVITIES – BASELINE

71151 - Performance Indicator Verification

The inspectors verified licensee performance indicators submittals listed below:

MS06: Emergency AC Power Systems (IP Section 02.05) (2 Samples)

(1) Unit 3 October 2019 through September 2020
(2) Unit 4 October 2019 through September 2020

MS07: High Pressure Injection Systems (IP Section 02.06) (2 Samples)

(1) Unit 3 October 2019 through September 2020
(2) Unit 4 October 2019 through September 2020

MS08: Heat Removal Systems (IP Section 02.07) (2 Samples)

(1) Unit 3 October 2019 through September 2020
(2) Unit 4 October 2019 through September 2020

MS09: Residual Heat Removal Systems (IP Section 02.08) (2 Samples)

(1) Unit 3 October 2019 through September 2020
(2) Unit 4 October 2019 through September 2020

MS10: Cooling Water Support Systems (IP Section 02.09) (2 Samples)

(1) Unit 3 October 2019 through September 2020
(2) Unit 4 October 2019 through September 2020

OR01: Occupational Exposure Control Effectiveness Sample (IP Section 02.15) (1 Sample)

(1) May 1, 2019 to September 30, 2020

71152 - Problem Identification and Resolution

Semiannual Trend Review (IP Section 02.02) (1 Sample)

(1) The inspectors reviewed the licensee's corrective action program for potential adverse trends in local leak rate testing failures during the recent Unit 4 refuel outage, PT4-32, that might be indicative of a more significant safety issue. This issue was documented in AR 2372183, System 051, (Containment Isolation), Exceeded Monitoring Criteria, and was evaluated by the licensee using common cause analysis methods. The inspectors review concluded there was no adverse trend.

Annual Follow-up of Selected Issues (IP Section 02.03) (2 Samples)

C3-155

FPSC EXH No. 5
03/18/2024
ADMITTED

C3-258

The inspectors reviewed the licensee's implementation of its corrective action program related to the following issues:

(1) AR 2366359, apply multiplication factor trends to nuclear instrument detector monitoring. This issue was selected for follow-up to verify the licensee's corrective actions were appropriate to address a failure to develop and establish a preventive maintenance schedule to perform source range nuclear instrument detector baseline and trending tests as described in Turkey Points Units 3 and 4 - Special Inspection Report 05000250/2020050 and 05000251/2020050 dated December 9, 2020 (ADAMS Accession No. ML20344A126).

(2) NCV 05000250/251-2019-001-02, Failure to Perform Structures Monitoring Program Inspections IAW License Renewal Commitments, and ARs 2305563, 2306492, and 2304913. The NCV was described in Turkey Point Nuclear Generating Station Inspection Report 05000250/2019001 and 05000251/2019001 dated May 14, 2019 (ADAMS Accession No. ML19134A371). This issue was selected for follow-up to verify the licensee's corrective actions were appropriate to address the performance deficiency and failure to inspect several safety-related structures in accordance with license renewal commitments.

71153 - Followup of Events and Notices of Enforcement Discretion

Event Report (IP Section 03.02) (2 Samples)

The inspectors evaluated the following licensee event reports (LERs):

(1) LER 05000250/2020-003-00, Automatic Reactor Trip due to Source Range High Flux During Reactor Startup, (ADAMS Accession No. ML20274A206). The inspection conclusions associated with this LER are documented in Inspection Report 05000250/2020050 and 05000251/2020050 (ADAMS Accession No. ML20344A126).

(2) LER 05000250/2020-004-00, Manual Reactor Trip in Response to Automatic Trip of the 3B Steam Generator Feedwater Pump, (ADAMS Accession No. ML20281A330). The inspection conclusions associated with this LER are documented in Inspection Report 05000250/2020050 and 05000251/2020050 (ADAMS Accession No. ML20344A126).

OTHER ACTIVITIES – TEMPORARY INSTRUCTIONS, INFREQUENT AND ABNORMAL

60855.1 - Operation of an Independent Spent Fuel Storage Installation at Operating Plants

Operation of an Independent Spent Fuel Storage Installation at Operating Plants (1 Sample)

(1) The inspectors evaluated the licensee's activities related to long-term operation and monitoring of their independent spent fuel storage installation on December 22, 2020

INSPECTION RESULTS

Inadequate procedural compliances during erecting of scaffold caused damage to safety-related motor operated valve during operation			
Cornerstone	Significance	Cross-Cutting Aspect	Report Section

C3-156

FPSC EXH No. 5
03/18/2024

ADMITTED

C3-259

Mitigating Systems	Green NCV 05000251/2020004-01 Open/Closed	[H.8] - Procedure Adherence	71111.15

A self-revealed, Green finding and associated, non-cited violation (NCV) of Technical Specification 6.8.1 was identified when the licensee failed to follow procedure MA-AA-100-1002, Scaffold Installation, Modification, and Removal Requests, when the licensee erected a scaffold that interfered with operation of plant equipment. During testing of motor-operated valve, MOV-4-861B, containment south recirculation sump isolation valve, the valve stem local position indicator impacted a scaffold in the B residual heat removal (RHR) pump room and caused damage to the position indicator requiring MOV-4-861B to be taken out of service for corrective maintenance.

Description: On September 26, 2020, at 0412 hours, normally closed MOV-4-861B failed its surveillance test to stroke full open. Control room operators declared MOV-4-861B inoperable and Unit 4 entered a 72-hour shutdown action statement for an inoperable RHR suction flow path from the south containment sump. MOV-4-861B is a containment south recirculation sump suction isolation valve for the RHR system located in the B RHR pump room. The safety-related functions of MOV-4-861B are to: 1) open during the loss of coolant accident (LOCA) recirculation phase to allow the RHR pumps to take suction from the containment south recirculation sump; 2) remain closed during the LOCA injection phase to provide containment isolation and isolate the RHR pumps from the containment south recirculation sump; and 3) as a normally closed RHR system boundary valve, it passively maintains the RHR system pressure boundary integrity.

After MOV-4-861B failed to fully open, plant operators identified that the local stem position indicator impacted a scaffold beam. The local position indicator is a metal rod welded on the end of the valve stem. The valve stem is in a protective shroud and the metal rod travels outside the protective shroud to provide local indication. The as-found valve condition identified the metal rod, used for position indication, was bent as a result of interference with a recently erected scaffold. During the open stroke the metal rod contacted the scaffold, causing the rod to bend which then prevented the valve from fully opening. A torque switch actuating in the open direction stopped MOV-4-861B. The licensee completed a past operability review (POR) and determined the valve stem traveled 86 percent open prior to the actuator tripping on the high torque setting. The POR concluded that MOV-4-861B was sufficiently open to perform its safety-related function of opening and supplying adequate flow during the LOCA recirculation phase. A component load path review was additionally completed by the licensee for the stem nut, valve stem and motor actuator. The licensee determined the MOV components were not overstressed due to the motor actuator tripping on the torque setting thus preventing excessive forces on the actuator and valve components. To retest and fully close MOV-4-861B, interim corrective actions were completed and included cutting off the bent portion of the metal rod from the valve stem. On September 26, 2020 at 1706 hours, the post-maintenance tests were satisfactorily completed and MOV-4-861B was returned to service.

The procedure for installation of scaffolding, including areas near safety-related systems, structures and components (SSC), is MA-AA-100-1002, Scaffold Installation, Modification and Removal Requests. Attachment 2 of the procedure, Scaffolding Pre-erection Walkdown and Evaluation, requires performing a scaffold pre-erection walkdown and addressing seventeen questions for the scaffold being built. The licensee found that maintenance personnel had not adequately complied with specific portions of the scaffolding procedure, in that there was no scaffold walkdown and questions 1 and 4 were not adequately completed. Specifically,

C3-157

FPSC EXH No. 5
03/18/2024

ADMITTED

C3-260

Question 1, “Are special requirements for scaffolding construction necessary to reduce the potential adverse impact on adjacent Critical Plant Equipment?” was not correctly answered. Seven items are required to be evaluated under this question. Item 3 specifies “Physical interference with active components such as pumps, motors, and valves, dampers, etc.” The inspectors determined this item was not completed. The scaffold erector did not discuss the potential for interaction with plant equipment with operations personnel and a scaffold pre-erection walkdown with operations personnel was not performed. Question 4 of Attachment 2 states “Will scaffold construction be in proximity to valves or exposed rotating equipment?” Four items are required to be evaluated under this question. Item 2 specifies “Scaffold or scaffold components which could impede the stem travel of air or motor operated valves.” The inspectors determined that this step was performed incorrectly. The scaffold erection lead assumed that the scaffold was erected with sufficient clearance such that the local position indicator rod would not impact the scaffold if the valve opened. Maintenance personnel failed to validate this assumption and did not request that operations personnel perform a walkdown.

Corrective Actions: The licensee promptly removed the bent portion of the local position indicator rod and retested MOV-4-861B. Engineers evaluated the condition and determined that the MOV components were not overstressed. The licensee plans to require refresher training for all scaffold builders who approve final installations.

Corrective Action References: Action Request 2369425

Performance Assessment:

Performance Deficiency: The failure to adequately comply with procedural instructions and erect a scaffold located near MOV-4-861B that did not interfere with its operation and ability to fully open is a performance deficiency.

Screening: The inspectors determined the performance deficiency was more than minor because it was associated with the Equipment Performance attribute of the Mitigating Systems cornerstone and adversely affected the cornerstone objective to ensure the availability, reliability, and capability of systems that respond to initiating events to prevent undesirable consequences. The inspectors determined the performance deficiency was more than minor because it was associated with the Equipment Performance attribute of the Mitigating Systems cornerstone objective to ensure the availability, reliability and capability of systems that respond to initiating events to prevent undesirable consequences (i.e., core damage). Specifically, the inadequately erected scaffold resulted in damage to MOV-4-861B during surveillance testing, requiring the RHR suction flow path from the containment south recirculation sump to be taken out of service to repair and test the MOV-4-861B.

Significance: The inspectors assessed the significance of the finding using Appendix A, “The Significance Determination Process (SDP) for Findings At-Power.” The inspectors screened this finding as very low safety significance (Green) using Exhibit 2, Mitigating Systems Screening Questions and answered No to question A.6, Does the degraded condition represent a loss of the PRA function of one or more non-TS trains of equipment designated as risk-significant in accordance with the licensee’s maintenance rule program for greater than 3 days. Specifically, with the stem position at 86 percent full open, MOV-4-861B was determined to be operable and capable of performing its specified safety function.

Cross-Cutting Aspect: H.8 - Procedure Adherence: Individuals follow processes, procedures, and work instructions. The inspectors reviewed this performance deficiency for cross-cutting

C3-158

FPSC EXH No. 5
03/18/2024

ADMITTED

C3-261

aspects as required by IMC 0310, “Aspects Within the Cross-Cutting Areas,” and concluded that maintenance personnel failed to follow procedure instructions and erected a scaffold that interfered with the operation of MOV-4-861B.

Enforcement:

Violation: Technical Specification 6.8.1 requires written procedures specified by the Quality Assurance Topical Report (QATR) to be established, implemented, and maintained. The QATR requires procedures for maintenance listed in Section 9.a., Procedures for Performing Maintenance, of Appendix A of NRC Regulatory Guide 1.33, Quality Assurance Program Requirements, Revision 2, dated February 1978. Section 9.a. requires, in part, that maintenance activities that can affect the performance of safety-related equipment be performed in accordance with written procedures, documented instructions, or drawings appropriate to the circumstances. Procedure MA-AA-100-1002, Scaffold Installation, Modification, and Removal Requests, Rev. 12, specifies the procedural process to be used to build temporary scaffolding in areas that can affect the performance of safety-related systems, structures and components, and provides the requirements for control of scaffolds erected. Attachment 2, Scaffold Pre-Erection Walkdown and Evaluation, requires a walkdown of all scaffolding and evaluation of seventeen questions to be completed on the scaffold being built. Question 1 includes a requirement to evaluate for potential physical interferences with active components such as pumps, motors, valves and dampers. Question 4 includes a requirement to evaluate for potential scaffold components which could impede the stem travel of air or motor operated valves. Contrary to the above, in the construction and approval of the scaffold erected and located adjacent to MOV-4-861, from August 31, 2020, to September 26, 2020, a scaffold walkdown was not completed and Question 1 and Question 4 of Attachment 2 were not evaluated for valve stem interference during MOV operation.

Enforcement Action: This violation is being treated as an non-cited violation, consistent with Section 2.3.2 of the Enforcement Policy.

EXIT MEETINGS AND DEBRIEFS

The inspectors verified no proprietary information was retained or documented in this report.

- On January 14, 2021, the inspectors presented the integrated inspection results to Mr. Michael Pearce, Site Vice President, and other members of the licensee staff.
- On October 14, 2020, the inspectors presented the RP inspection exit meeting inspection results to Michael Pearce, Site Vice President and other members of the licensee staff.
- On October 15, 2020, the inspectors presented the Inservice Inspection Exit inspection results to Michael Pearce, Site Vice President and other members of the licensee staff.

C3-159

FPSC EXH No. 5
03/18/2024

ADMITTED

C3-202

DOCUMENTS REVIEWED

Inspection Procedure	Type	Designation	Description or Title	Revision or Date
71124.01	Radiation Surveys	PTN-M-20200922-10	ISFSI Semi Annual	09/22/2020

C3-160

FPSC EXH No. 5
03/18/2024

ADMITTED

C3-262

Florida Power & Light

ST. LUCIE AND TURKEY POINT GPIF DATA

PERFORMANCE DATA FOR 2010-2021

LINE	St. Lucie 1	2010	2011	2012	2013	2014	2015	2016	2017	2018	2019	2020	2021
1	EAF	72.6%	84.0%	59.5%	80.2%	99.9%	89.9%	79.4%	97.4%	90.8%	70.1%	99.8%	88.6%
2	FOH + PFOH	1,810.7	895.5	216.5	593.0	25.5	102.2	834.9	246.7	74.5	1,810.1	12.8	153.7
3	EFOR %	20.7%	10.2%	2.5%	6.8%	0.3%	1.2%	9.5%	2.8%	0.9%	20.7%	0.1%	1.8%
4	POH + PPOH	1,806.6	2,046.8	4,149.3	1,073.9	22.9	933.7	1,199.0	8.6	809.4	888.2	6.3	840.8
5	Capacity Factor	72.1%	85.0%	57.3%	81.1%	101.5%	91.2%	80.5%	99.1%	92.2%	71.3%	101.3%	89.8%
LINE	St. Lucie 2	2010	2011	2012	2013	2014	2015	2016	2017	2018	2019	2020	2021
6	EAF	97.5%	63.1%	67.1%	97.7%	80.7%	82.2%	97.8%	89.7%	87.8%	100.0%	91.1%	89.5%
7	FOH + PFOH	428.2	882.5	325.9	287.9	374.5	456.4	-	110.2	252.2	-	60.0	90.6
8	EFOR %	4.9%	10.1%	3.7%	3.3%	4.3%	5.2%	0.0%	1.3%	2.9%	0.0%	0.7%	1.0%
9	POH + PPOH	21.0	2,610.4	2,913.8	30.0	1,321.4	1,339.5	232.5	884.5	873.5	0.7	721.3	827.2
10	Capacity Factor	99.9%	66.6%	67.6%	99.6%	82.3%	83.9%	100.1%	91.7%	88.6%	102.7%	93.2%	91.5%
LINE	Turkey Point 3	2010	2011	2012	2013	2014	2015	2016	2017	2018	2019	2020	2021
11	EAF	85.8%	93.4%	36.4%	87.7%	84.0%	84.5%	98.7%	85.2%	88.6%	99.1%	85.3%	84.0%
12	FOH + PFOH	356.9	234.0	34.9	1,814.3	792.7	74.2	195.5	407.6	1.6	84.5	535.2	658.3
13	EFOR %	4.1%	2.7%	0.4%	20.7%	9.0%	0.8%	2.2%	4.7%	0.0%	1.0%	6.1%	7.5%
14	POH + PPOH	1,088.2	-	6,167.1	101.2	1,235.7	1,517.7	-	906.2	1,001.0	-	681.8	743.9
15	Capacity Factor	85.4%	96.0%	40.8%	88.0%	74.6%	84.6%	100.7%	86.9%	90.6%	102.8%	89.3%	86.3%
LINE	Turkey Point 4	2010	2011	2012	2013	2014	2015	2016	2017	2018	2019	2020	2021
16	EAF	95.0%	81.5%	84.0%	65.1%	86.7%	98.1%	89.8%	89.5%	99.6%	90.6%	83.0%	99.5%
17	FOH + PFOH	442.6	261.9	-	293.8	469.0	126.5	143.2	213.4	3.1	10.0	494.2	49.2
18	EFOR %	5.1%	3.0%	0.0%	3.4%	5.4%	1.4%	1.6%	2.4%	0.0%	0.1%	5.6%	0.6%
19	POH + PPOH	137.5	1,441.2	1,440.4	3,331.0	1,288.0	162.6	953.2	705.7	28.1	815.5	1,001.2	
20	Capacity Factor	94.9%	84.0%	86.0%	65.1%	85.7%	98.0%	91.1%	91.2%	101.4%	91.9%	84.3%	102.7%

C3-161

FPSC EXH No. 5
03/18/2024
NEXTera ENERGY
ADMITTED

C3-264

TURKEY POINT NUCLEAR

UNIT 4 REACTOR TRIP DUE TO GEN LOCKOUT FROM LOSS OF EXCITER

EVENT DATE: 7/05/2020

AR NUMBER: 02361794

Root Cause Team	Name	Dept/Group
Management Sponsor	Dianne Strand	Engineering
Team Leader	Mike Coen	Operations
RC Evaluator	Charles Zyne	Engineering
Team Member	Randall Kerkes	Site/PGD Engineering
Team Member	Doug Vogt	Turbine PGD
Team Member	Orlando Carol	System Engineering
Team Member	Clyde Meredith	Maintenance
Team Member	Brian Bakke	Training
Team Member	Clea Duffy	Perf. Improvement

Root Cause Evaluator: _____ **Date:** _____
Print/Sign

Management Sponsor: _____ **Date:** _____
Print/Sign

MRC Chair: _____ **Date:** _____
Print/Sign

Electronic Signature may be obtained by assigning actions in NAMS.
Refer to PI-AA-104-1000 for details.

C3-162
FCR-22-000453

FPSC EXH No. 5
03/18/2024
NEXTera ENERGY
ADMITTED

Table of Contents

- Executive Summary 3
- Event Description – Narrative 7
- Problem Statement 7
- Analysis (FIP S/R, Timeline, RC S/R, Barrier Analysis, Why Staircase) 7
- Causal Factor Categorization 14
- Evaluation Attributes 15
  - Previous Occurrences
  - Extent of Condition
  - Extent of Cause
  - Nuclear Safety Culture Evaluation
  - Risk / Consequence
- Operating Experience 30
- Lessons Learned 35
- Proof Statement 35
- Corrective Actions 37
- Deferral Justification 40
- Effectiveness Review Plan 40
- Attachments 41

1. Root Cause Charter 42
2. Photos 43
3. Exciter Ground Detection System 55
4. Exciter PM Description and Status 64
5. FIP Team Support/Refute Matrix 67
6. Root Cause Support/Refute Matrix 92
7. Barrier Analysis 137
8. Timeline 147
9. Potential Paths of Water Ingress 154

FPSC EXH No. 5
03/18/2024
NEXTera ENERGY
ADMITTED

1. Executive Summary

On July 5th, 2020 at approximately 1844, during a heavy thunderstorm, the Control Room received an annunciator showing a Unit 4 “Generator Field Brush Failure/Ground”.

A Turbine Operator was dispatched to attempt to clear the alarm. The alarm momentarily cleared, then immediately re-alarmed. Two additional alarms then came in indicating “Generator Voltage Regulator Loss of Backup” and “Generator Voltage Regulator Transfer to Manual”. The first of these two alarms cleared as soon as it was acknowledged, however, the initial alarm for the “Generator Field Brush Failure/Ground” and the “Generator Voltage Regulator Transfer to Manual” alarms remained locked-in. Operations noted one additional alarm at the local Voltage Regulator panel, showing a “Loss of Field Current Transducer (XDCR) #1” which then caused the Voltage Regulator to swap from Automatic AC regulator to Manual DC regulator.

As the event progressed, the annunciators indicating “Generator Voltage Regulator Loss of Backup” and “Generator Voltage Regulator Trouble” were received multiple times during the event. Operations also observed reactive load on the Unit 4 Main Generator increase from 115 MVAR to 200 MVAR during a 5-minute period and that the Exciter field volts were oscillating. The Unit 4 Reactor then tripped due to a Main Generator (4K2) Lockout followed by a Turbine Trip at approximately 2107. The Main Generator Lockout was caused by the actuation of the Voltage Regulator Lockout relay due to loss of the Voltage Regulator Power Supplies #1 & #2 (and thus loss of excitation).

In response to the event, the Outage Control Center (OCC) was manned and a Failure Investigation Process (FIP) Team was assembled to perform the initial investigation and to identify the cause which led to the alarms and subsequent unit trip. The FIP Team determined that the unit trip was initiated by a failure of the Exciter Permanent Magnet Generator (PMG) stator. The investigation focused on many potential contributors including age, vibration, water intrusion, foreign material, assembly error and other potential contributors.

The FIP Team developed actions to identify, inspect and test any component that could have been affected by the failure of the PMG stator.

After disassembly and further inspections of the failed equipment the station replaced the failed PMG stator and the Exciter rotor. The rotating assembly was replaced due to collateral magnet damage in the PMG Pole Support caused by stator failure debris and thermally induced cracking. Inspections also revealed water inside both the PMG and Exciter housing compartments. Exciter housing door seals, partition seals, and floor seals were found in degraded conditions and were subsequently replaced. Rubber gaskets at the base of the Exciter housing did not meet site specific requirements and were found dislodged and drawn into the PMG compartment. Additionally, site specific vertical weather seals were missing. Further reviews revealed site procedure 0-GMM-090.1 ‘Exciter Removal, Inspection and Installation’ includes the site-specific gasket and vertical weather seal, however, OEM procedure 3.2.2.1 which installs the Exciter housing does not. The specific source of water intrusion inside the PMG compartment cannot be determined, however, water was most likely drawn into the PMG compartment through the missing vertical weather seal and dislodged rubber gaskets (ref. Attachment 9 for potential paths of water ingress).

FPSC EXH No. 5
03/18/2024
NEXTera ENERGY
ADMITTED

Extensive testing was completed on the voltage regulator, cabling, and all major components within the Exciter that were potentially affected by the failed PMG stator. Areas where water intrusion was noted were also addressed and corrected (seals that were found degraded and dislodged were replaced).

The failed Unit 4 PMG stator had been in service since 1986 (34 years in service) without rewind. A review of EPRI report 'Tools to Optimize Maintenance of Generator Excitation System, Voltage Regulator and Field Ground Detection' dated 2002, discusses the detrimental impacts of aging on the reliability of winding insulation for Generator and Exciter components. Similar EPRI report 'Plant Support Engineering: Main Generator End-of-Life and Planning Considerations' dated 2007 states the life expectancy of winding insulation to be between 10-30 years. Although these reports identify aging as a failure mechanism, they do not explicitly recommend rewinds as a corrective action. Preventive Maintenance (PM) activities recommended and performed by the OEM also lacked rewind activities.

Furthermore, the EPRI reports note that aging of winding insulation alone does not likely cause equipment failures. The presence of one or more additional stressors such as temperature, vibration, and water, is required for a failure to occur. This conclusion was validated through review of industry operating experience (OE). No examples of failures of winding insulation attributed to age alone were identified. With regards to the failed Unit 4 PMG stator winding, water is the additional stressor which lead to a fault.

Maintenance work on the Exciter, including weather sealing, was performed by the OEM in accordance with OEM procedures. However, as evidence showed, not all weather sealing was installed by the OEM during the last housing installation. FPL verification of work performed by the OEM focuses on review of documentation that evidences that the work performed is in accordance with OEM procedures. Communication of site-specific OE to the OEM (and to the industry) happened at the time of discovery of initial water intrusion in the 2002 timeframe. FPL review of OEM procedures typically focuses on performing high level review of work scope and screens for nuclear safety requirements in accordance with FPL procedures. Furthermore, FPL relies on the OEM due to their vast industry and site-specific experience regarding Exciter related work. Accordingly, the FPL review of OEM procedure to remove, inspect and install the Exciter housing did not identify the absence of the site-specific sealing requirements.

In summary, failure of the Unit 4 PMG stator occurred due to an aged winding in combination with water intrusion. Neither an aged winding nor water intrusion occurring by themselves would have resulted in failure of the stator. FPL incorporates OEM and industry OE (including site specific OE) into our maintenance program. However, there was no requirement by the OEM or industry documents to perform a rewind on a specified frequency. The Exciter housing vertical weather seals were missing, and gaskets were dislodged. These water intrusion components were not installed in accordance with site procedure guidance. 0-GMM-090.1 'Exciter Removal, Inspection and Installation' contains the site-specific gasket and vertical weather seal guidance, however, OEM procedure 3.2.2.1 which installs the Exciter housing does not.

The root cause investigation was initiated to determine the cause and contributing causes.

FPSC EXH No. 5
03/18/2024
NEXTera ENERGY
ADMITTED

C3-268

Problem Statement: On July 5th, 2020 at approximately 2107, during a heavy rainstorm Unit 4 tripped automatically from 100% power due to a Generator Lockout.

The Root Cause Team identified the following Significant Contributing Causes (SCC) to the event:

Significant Contributing Causes:

SCC #1) Weakness in Exciter PM Program based on existing OEM and Industry recommendations which were CONDITION BASED, and did not require TIME-BASED PMG stator rewind, thereby increasing susceptibility to failure from other stressors.

SCC #2) OEM procedure 3.2.2.1 did not include site specific weather sealing requirements based on OE.

Root Cause:

A weakness in the Exciter PM program resulted from a failure to fully assess risk of PMG stator winding age making it more susceptible to failure when exposed to water/moisture.

The Corrective Action(s) to Prevent Recurrence (CAPR) for the Root Cause is:

The root cause of the event is composed of two significant contributors, which individually will not result in a PMG stator winding fault, however, when combined caused the event. As such, two Corrective Actions to Prevent Recurrence were identified:

- Initiate a TIME-BASED PMG stator rewind PM
- Revise Siemens procedure 3.2.2.1, *Exciter Enclosure Removal and Reinstallation,* to require site specific weather seals for Exciter housing.

Contributing Cause

CC#1: Instructions in PTN procedure 0-GMM-090.1, "Exciter Removal, Inspection and Installation," in providing discretionary guidance in lieu of a mandated requirement on Exciter housing application of site specific weather seals for prevention of water intrusion.

The Corrective actions to address the contributors, extent of condition, and enhancements are:

- Issue PCR against 0-GMM-090.1, *"Exciter Removal, Inspection and Installation"* to eliminate discretionary wording regarding application of weather seals
- Action for each site to scope replacement of Exciter components (PMG Stator, AC Exciter Field, and AC Exciter Armature) with rewound spares into the following outages:
  - SL1-30 Spring 2021
  - PTN3-32 Fall 2021
  - PTN4-33 Spring 2022
  - SL2-27 Spring 2023

C3-166

FPSC EXH No. 5
03/18/2024
NEXTera ENERGY
ADMITTED

- Issue PCR against 0-GME-090.02, “Generator Voltage Regulator & Excitation Switchgear - Inspection and Maintenance” to require clarification that if the procedure is being performed as part of a routine PM activity, the Voltage Regulator Roof shall be coated for water intrusion, all existing door gaskets and seals replaced, and supplementary seals be reapplied.
- System Engineering to review Large/Small motors and large Transformer single point vulnerabilities (SPVs), and associated PM philosophy / Life Cycle Management Plans (LCMPs) for adequate continued reliability and assess whether an age-based Exciter rewind activity is required.
- System Engineer for Emergency Diesel Generators to review existing PM program and assess whether an age-based Exciter rewind activity is required.
- Create LTAM to install a ground detection system to detect grounds on the Exciter and PGM windings and downstream circuits.
- Create LTAM to install leak detection system to identify online water intrusion inside the Exciter housing.

FPSC EXH No. 5
03/18/2024
NEXTera ENERGY
ADMITTED

2. Root Cause Report

2.1 Event Description

On July 5th, 2020 at approximately 1844, during a heavy thunderstorm, the Control Room received Annunciator AN-E-8/3 (GEN CONTACT FIELD BRUSH CONTACT FAIL/GROUND) on Unit 4. At approximately 1900, the Turbine Operator depressed the RESET pushbutton above the generator field breaker IAW Procedure 4-ARP-097.CR.E. Annunciator AN-E-8/3 momentarily reset then re-alarmed. Annunciators AN-E-9/3 (GEN VOLT REG LOSS OF BACKUP) and AN-E-7/6 (GEN VOLT REG TRANSFER TO MANUAL) subsequently alarmed. Annunciator AN-E-9/3 cleared as soon as it was acknowledged. However, Annunciators AN-E-8/3 and AN-E-7/6 remained locked-in. At this time, the Voltage Regulator (VR) swapped from Automatic AC regulator to Manual DC regulator.

At approximately 2045, Operations noted one alarm on the local VR panel, “Loss of XDCR No. 1”. Shortly thereafter, at approximately 2050, Annunciators, AN-E-9/3 (GEN VOLT REG LOSS OF BACKUP) and AN-E-8/6 (GEN VOLT REG TROUBLE) were received multiple times. Operations also observed reactive load on the Unit 4 Main Generator increase from 115 MVAR to 200 MVAR during a 5-minute period. At approximately 2100, Operations reported that the Exciter field volts were oscillating. Then, at 2107 the Unit 4 Reactor tripped due to a Main Generator (4K2) Lockout followed by a Turbine Trip. The Main Generator Lockout was caused by the actuation of the VR Lockout relay due to loss of VR Power Supplies #1 & #2. After the trip, the following Generator Exciter Switchgear control cabinet alarms remained locked in: Power Supply #1, Power Supply #2, Firing Circuit #2, and Loss of XDCR #1.

2.2 Problem Statement

On July 5th, 2020 at approximately 2107, during a heavy rainstorm Unit 4 Tripped Automatically from 100% power due to a Generator Lockout.
Object: Unit 4 Exciter PMG
Defect: Failure of PMG Stator winding insulation leading to an electrical fault.
Consequence: Reactor and Turbine Trip

3. Analysis

A. Analysis Methodology

The Root Cause Team used the investigative information and the Direct Cause provided by the FIP Team to determine the Root Cause and the Contributing Causes that led to this event. The Root Cause Team verified the FIP Team’s findings and proceeded to gain a deeper understanding of the event and the Root Cause.

The Root Cause Team used the following assessment tools in the evaluation:

- Timeline was developed and reviewed-refer to TIMELINE attachment

FPSC EXH No. 5
03/18/2024
NEXTera ENERGY
ADMITTED

- Interviews were conducted to gain additional information on Programmatic/Organizational (O&P) barriers being used prior to the event and to gain additional insight beyond the FIP Team findings
- Reviewed all evidence gathered by the FIP Team and then the Root Cause Team verified assumptions and conclusions as appropriate

Causal Analysis was performed by using:

- FIP Team Support/Refute Matrix - Used by the FIP team to organize their investigation and document their findings that support the conclusion of the Direct Cause. The Root Cause Team development of a ROOT CAUSE Support/Refute Matrix.
- Barrier Analysis - Gathered and organized the Root Cause Team's investigative data and determined which organizational and programmatic (O&P) barriers failed or were missing to prevent the final consequential event.
- Performed analysis of the O&P factors and drivers.
- Why Analysis charting - Used to organize the Root Cause Team's conclusions and to verify and document the linkage between event and cause.

The Root Cause Team used the above-mentioned information gathering and analysis techniques to arrive at the following causes.

Unit 4 Exciter PMG Failure - (Direct Cause)

A FIP Team was formed immediately after Unit 4 Tripped Automatically from 100% power due to a Generator Lockout. The FIP Team was comprised of experienced Engineers from PTN, senior level Engineers from NextEra fleet along with Operations and Maintenance personnel. The purpose of the FIP Team was to determine via a Support/Refute matrix all possible causes of the event and to systematically collect evidence to either support or refute each cause until the most likely cause is determined. From the Support/Refute matrix it was determined that the Direct Cause was the failure of the PMG. The Root Cause Team concurred with the FIP Team conclusion of the Direct Cause.

Initially, this evaluation concluded that the most likely cause of the PMG stator failure was the presence of an external stressor (e.g. water, foreign material, vibrations, lightning, etc.) on an aged PMG stator winding with reduced margins that led to a fault internal to the PMG, resulted in power loss to the voltage regulator, and caused the subsequent unit trip. Further analysis by the Root Cause Team determined that the failure of the PMG was likely due to a culmination of age-related breakdown of the PMG stator winding insulation along with water intrusion due to inadequate sealing of the Exciter housing. Other stressors evaluated including vibration, lightning strikes, and an identified loose shim stock were discounted/refuted as a potential contributor to the event.

<u>Discussion on Age Related Degradation and Impact of Moisture on Winding Insulation:</u>
A review of EPRI document titled 'Tools to Optimize Maintenance of Generator Excitation System, Voltage Regulator and Field Ground Detection' dated 2002, as well as review of industry OE, revealed that component age in and of itself usually does not lead to failure of winding insulation. However, it does make the insulation more susceptible to other failure

FPSC EXH No. 5
03/18/2024
NEXTera ENERGY
ADMITTED

factors. As the insulation ages, chemical changes occur in the insulation. Varnish, employed in older systems to bind insulation together, becomes dry and brittle. Other binding materials also may weaken. It is usually the binding material, the varnish or epoxy, that degrades with age; not the actual insulation material. Factors such as temperature and vibration tend to prematurely age insulation.

Moisture reduces the resistance of the insulation. Moisture, creating a conductive film on windings, allows tracking of current, leading to insulation degradation. Furthermore, a ground path can develop from tiny cracks in the insulation through moisture. As dust and other particles can attract moisture, moisture too can cause particles to adhere to surfaces. During operation, the
warm winding will typically evaporate out the moisture; thereby moisture tends to be more of a problem during start-up. However, moisture that has been absorbed into the insulation will take a significant amount of time to be driven out of the insulation. Furthermore, an excessive amount of moisture can create grounds during operation. For example, a water leak can thoroughly wet a section of the winding, weakening the insulation, and develop a fault.

Discussion on Exciter housing weather seals:
In 2001 the Unit 3 Exciter housing experienced water intrusion which led to a ground on the Main Generator Exciter (CR 01-1813) but did not lead to a Main Turbine / Generator trip that caused an automatic Reactor trip. As a result of that event, Maintenance Support Package MSP 02-055 was issued which required a vertical foam weather seal to be installed between the Exciter housing vertical lip and the Turbine Deck curb. This weather seal was incorporated into PTN procedure 0-GMM-090.1 *"Exciter Removal, Inspection and Installation"* to be installed on both Units' Exciter housing. However, OEM procedures were not revised accordingly. Additionally, in 2008 the PTN subject matter expert for the Generator/Exciter equipment developed a weather sealing detail for the Exciter housing that replaced the standard ¼" thick inner rubber gasket with a ½" thick foam gasket to ensure proper compression between the housing and Turbine Deck curb. This site-specific seal was developed due to previous water intrusion events that demonstrated the standard ¼" thick inner rubber gasket did not provide a sufficient seal between the Exciter housing and Turbine Deck curb. The inner foam gasket was incorporated into procedure 0-GMM-090.1 *"Exciter Removal, Inspection and Installation"* but was not included in OEM procedures. Further, 0-GMM-090.1 was revised to require installation of the ½" inner foam gasket but did not require vertical foam weather seals (discretionary) each time the Exciter housing is removed and reinstalled.

Discussion on Potential Water Ingress into PMG compartment
During troubleshooting and investigation following the event, water was found inside the PMG compartment accumulated inside the PMG and pedestal bolt holes. The Exciter housing is designed to be sealed from the outside environment and prevent water intrusion inside these compartments, However, during Exciter housing disassembly the housing door seals were found with normal wear and degradation. The partition seal between the AC Exciter compartment (positive pressure area) and PMG compartment (negative pressure area) was also found degraded. Of particular concern was the housing floor gaskets which were found dislodged in sections around the perimeter of the PMG compartment. These floor gaskets did not meet the site-specific design which uses an inner ½" thick foam seal. Instead,

FPSC EXH No. 5
03/18/2024
NEXTera ENERGY
ADMITTED

the standard ¼" thick rubber inner gasket was applied. Additionally, the site-specific vertical foam weather seal designed under MSP 02-055 and required in site procedure 0-GMM-090.1 was not installed. Although the source of water intrusion into the PMG compartment could not be ultimately determined following the event, the most probable path of water ingress was through the missing vertical foam seal and degraded and dislodged floor gaskets. Attachment 9 provides a visual aid showing the potential paths of water ingress into the PMG compartment.

Reference Support Refute Matrix attachments for additional details.

Conclusion: The analysis tools concluded that the failure of the PMG stator was due to insulation degradation coupled with additional stressors; water intrusion being the likely cause. The PM strategy historically used on this component was to perform periodic testing and inspection, but only rewind if required (CONDITION-BASED PM, test and maintain strategy versus a TIME-BASED rewind frequency). The analysis tools also confirm that additional stressors (water) had been introduced in the past with limited consequences. During this event when water was introduced to this aging component, it caused winding shorts leading to stator failure.

Barrier Analysis Chart

Refer to Attachment Barrier Analysis Chart

Weak barriers were identified involving project oversight that are derived from OEM control of work packages and use of OEM procedures. The use of OEM proprietary work packages makes oversight difficult and can limit historical knowledge and OE available to site personnel. The seal inspection and suitability, and the decision whether to reseal the Exciter housing, are provided by contract personnel without requiring specific site concurrence.

(Additional Weak Barriers were:)

1) PTN procedures on Exciter housing sealing process were found to be a weak barrier. The PTN procedure 0-GMM-090.1 '*Exciter Remove, Inspection and Installation'* had been updated to add the use of site specific inner foam gasket and site specific vertical foam weather seal to mitigate water intrusion based on previous site OE. As replacement of the vertical foam weather seal was a discretionary step in the PTN procedure, this barrier would have also been weak even had this step been incorporated into the OEM procedure. No barrier was found to address equipment degradation due to age. A PM to rewind the PMG stator had been created in 2019 but not yet implemented. There was no possible judicious approach available to implement the new PM prior to this failure. It was also determined that there is no method available to trend ambient operating condition of the PMG inside the Exciter housing to determine the level of potential stressors (e.g. humidity) that would have a cumulative and adverse effect on an aging PMG.

FPSC EXH No. 5
03/18/2024
NEXTera ENERGY
ADMITTED

Why Staircase Analyses

With a combination of factors leading to the failure of the PMG, two Why Staircases were used to address the individual factors.

Defect 1: Unit 4 Failure of Turbine Exciter PMG insulation

Q: Why did the turbine exciter function fail?
A: The turbine exciter function failed because the PMG stator winding insulation failed leading to shorting of the stator windings. **Direct Cause (Equipment)**

Q: Why did the PMG stator winding insulation fail?
A: PMG stator windings insulation failed as it was in operation for over 30 years without rewind.

Q: Why was the PMG stator winding insulation in operation for this extended period without a rewind activity?
A: There was no specific plan to perform a rewind activity, either one-time or through an interval period process.

Q: Why was there no specific plan to perform this one-time or interval rewind on a time-based or condition-based component?
A: Site PM philosophy (CONDITION BASED) historically relied on routine test and inspection results to validate fitness for continued service. A PM for rewind was created late in component life but was not implemented prior to failure. This new PM was considered an enhancement to the existing PM strategy.

Q: Why was the rewind PM not implemented prior to failure?
A: The Rewind PM was planned to align with next major inspection (outage) and was not considered an immediate need to address equipment reliability.

Q: Why was the Rewind PM not considered an immediate need to address equipment reliability.
A: The preventive maintenance (PM) program was based on existing Exciter OEM and Industry recommendations that do not require periodic rewind of the PMG stator.

Weakness in Exciter PM Program based on existing OEM and Industry recommendations which were CONDITION BASED, and did not require TIME-BASED PMG stator rewind, thereby increasing susceptibility to failure from other stressors.

Significant Contributing Cause #1 (Weakness in Exciter PM Program)

FPSC EXH No. 5
03/18/2024
NEXTera ENERGY
ADMITTED

Defect 2: Unit 4 Failure of Turbine Exciter Function due to water intrusion

Q: Why did the Turbine Exciter function fail?
A: Because PMG stator windings shorted. **Direct Cause (Equipment)**

Q: Why did the PMG stator windings short?
A: The PMG stator windings shorted as there was substantive evidence that water intrusion occurred at the PMG compartment during a heavy rainstorm.

Q: Why did water intrusion occur at the PMG compartment?
A: Exciter housing weather seals were ineffective.

Q: Why were Exciter housing weather seals ineffective?
A: Exciter housing weather seals were not installed per site specific requirements.

- Inner gasket was ¼" thick rubber vs site required ½" foam
- Vertical foam weather seal was not installed (discretionary)

Q: Why were Exciter housing weather seals not installed per site specific requirements?
A: Exciter housing was reassembled by OEM using their procedure 3.2.2.1 that did not address site specific weather sealing requirements.

Q: Why did the OEM procedure 3.2.2.1 not require site specific seal requirements?
A: Site specific weather sealing steps, including those based on OE, were not incorporated as required steps into OEM procedure 3.2.2.1 – Latent Error.

Significant Contributing Cause #2 - OEM procedure 3.2.2.1 did not include site specific weather sealing requirements based on OE. **– Latent Error.**

Conclusions:

The two independent Why Staircase conclusions were reached utilizing other investigative tools including internal and external OE, interviews, Ops logs, field inspections, FIP Team reports, etc. The results of the Why Staircase Analyses have substantiated the other analysis tools' conclusions. It is important to note that from the timeline it is evident that the Exciter housing has had water intrusion at times in the past. These past water intrusion events resulted in generator ground indications only; as such, it must be concluded that this

FPSC EXH No. 5
03/18/2024
NEXTera ENERGY
ADMITTED

water intrusion event has a different characteristic, and that characteristic is attributed to age related degradation of the insulation. While the stator winding most likely would not have failed due to this age-related degradation alone, the addition of water as a stressor resulted in failure. Therefore, the conclusions of the Why Staircases have identified two strong contributing causes which, when combined, result in one Root Cause; **A weakness in Exciter PM program resulted from the failure to fully assess the risk of PMG stator winding age making it susceptible to failure when exposed to water/moisture.**

FPSC EXH No. 5
03/18/2024
NEXTera ENERGY
ADMITTED

4. Causal Factor Categorization Analysis

Causal Factor Characterization (Each causal factor identified is listed and classified in the appropriate People, Programmatic, Organizational and Equipment categories.)		
Cause Type	**Cause Statement**	**Category**
Root Cause	A weakness in Exciter PM program resulted from a failure to fully assess risk of PMG stator winding age making it more susceptible to failure when exposed to water/moisture.	Programmatic
Significant Contributing Cause (SCC1)	Weakness in Exciter PM Program based on existing OEM and Industry recommendations which were CONDITION BASED, and did not require TIME-BASED PMG stator rewind, thereby increasing susceptibility to failure from other stressors.	Programmatic
Significant Contributing Cause (SCC2)	OEM procedure 3.2.2.1 did not include site specific weather sealing requirements based on OE. – latent error.	Organizational
Contributing Cause (CC1)	Instructions in PTN procedure 0-GMM-090.1, “Exciter Removal, Inspection and Installation,” in providing discretionary guidance in lieu of a mandated requirement on Exciter housing application of site specific weather seals for prevention of water intrusion.	Organizational
None		People
None		Equipment

FPSC EXH No. 5
03/18/2024
NEXTera ENERGY
ADMITTED

5. Evaluation Attributes

A. PTN Previous Occurrences

Per PI-AA-204-1000, "Condition Reporting", Section 2.2, Step 43, a *Repeat Event* is defined as: Two or more independent occurrences of the same or similar event resulting from the same fundamental problem from the same fundamental cause for which previous root or apparent cause analysis has occurred and corrective action failed. Similar means common or comparable characteristics, which may include one or more of the following: plant conditions, organizations, processes, programs or procedures. Identification of a repeat event is a judgment call and should take into consideration the specifics of the condition. The length of time for repeat event identification should be significance based, typically including events occurring within at least a three-year period for programmatic issues, four years for training issues, and at least a five-year period for equipment issues, but dependent on the opportunity for recurrence and the risk significance of the event. Significant events may warrant a life of the plant review (examples – critical component failures, plant trip, significant injury, etc.). Since the event is an organizational control issue affecting a programmatic issue and significance resulting in a plant trip, an extensive historical review was conducted was performed in NAMS for the PTN site concentrating on the following keywords in the description and subject of ARs: "Exciter Winding Program", "Exciter Water Moisture" and "Exciter Water Intrusion". No similar events under a previous root or apparent cause evaluation was found, therefore, this RCE is not considered a Repeat Event.

This review, however, did determine that there were instances where compliance to FPL standards was not met regarding prevention of water intrusion inside the Exciter housing. This will be reviewed in the Extent of Condition/Cause with associated actions.

1) 9/29/2001PTN U3 Water Intrusion caused a forced power reduction due to severe weather and continuous heavy rains. A large pressure differential was created in the Exciter housing by the oversized blower, drawing water into the housing and blowing water on to exciter electrical components throughout the housing. This was caused by a failure of gaskets and removal of pipe plugs which produced a leak path from the external environmental conditions to the internal Exciter components.

2) 6/17/2002-7/10/2002 During this time frame another water intrusion event occurred on the U3 Exciter housing, which prompted engineering to issue an MSP 02-055 to provide direction on sealing the Exciter housing. The work order was

FPSC EXH No. 5
03/18/2024
NEXTera ENERGY
ADMITTED

awaiting engineering on 6/18/2002. On 7/10/2002 the work order was again taken to approved status, but no repairs to the gasket area was performed.

3) 12/8/2004 Manual reactor scram on U3 had to be initiated due to water leak inside the Exciter housing. The cause was due to improper gasket material and improper assembly of Exciter cooler by an outside vendor resulting in a (~`90 gpm) leak on the Turbine Plant Cooling Water (TPCW) piping inside the housing. While this 2004 event is not due to inclement weather it is important to note that water intrusion, an unacceptable condition, does not appear to be enough to cause shorting of the windings of the equipment when insulation is in good condition. In the subject 7/5/2020 event, the cumulative impact of aged insulation and water intrusion inside the PMG compartment resulted in the stator winding fault.

B. PTN Extent of Condition

Same Object – Same Defect:

Object: Unit 4 Exciter PMG Stator.
Defect: Failure of PMG Stator winding insulation leading to an electrical fault.

Same object and same defect apply to the Unit 3 Exciter PMG Stator windings which was installed in 1972. The Unit 3 PMG Stator is just as susceptible to the same failure mechanism given the age of the stator and potential for water intrusion to occur inside of the Unit 3 Exciter housing.

- *Rewind PMG Stator for PTN and PSL.*
- *Immediate temporary seal for PTN.*
- *Immediate investigation for PSL Exciter Housing sealing integrity*
- *Seal Exciter Housing for PTN*
- *Seal Exciter Housing for PSL (if needed)*

FPSC EXH No. 5
03/18/2024
NEXTera ENERGY
ADMITTED

Same Object – Similar Defect:

Object: Unit 4 Exciter PMG Stator.
Defect: Failure of PMG Stator field cables to the Voltage Regulator housing, or jumper cables internal to the Exciter housing.

Same object and Similar Defect apply to the Unit 3 and Unit 4 Exciter PMG Stator field cables and jumper cables. These components may fault and cause a similar event to the failure of the PMG stator winding. However, there was no evidence of failure of these components during investigations. Field cables and jumper cables were tested satisfactory under FAR #5. No actions necessary.

Similar Object – Similar Defect:

Object: Unit 3 and 4 Exciter Rotor and A/C Stator.
Defect: Failure of Exciter Rotor or A/C Stator windings leading to an electrical fault.

Similar Object and Similar defect apply to the Exciter Rotor and Stator for Units 3 and 4. They are of similar construction to the PMG stator (i.e. insulating windings wrapped around an iron core). PM's for these components may not be adequate to ensure continued reliability.

- *Rewind Exciter Rotor and Exciter Stator for PTN*
- *Rewinds Exciter Rotor and Exciter Stator for PSL*

Similar Object – Similar Defect:

Object: Unit 3 and 4 Voltage Regulator – field breaker and Power Drawer.
Defect: Failure of Power Drawer or field breaker in voltage regulator leading to an electrical fault.

Similar Object and Similar defect apply to the voltage regulator field breaker and power drawer for Units 3 and 4. These components are directly connected to PMG with no ground fault monitoring. Small amount of water intrusion in Voltage Regulator housing observed by operator prior to event. These components may fault and cause a similar event to the failure of the PMG stator winding. However, there was no evidence of failure of these components during investigations. Voltage Regulator has been tested under FAR # 3. Voltage Regulator housing inspected and repaired for water leak under FAR#10. No actions necessary.

FPSC EXH No. 5
03/18/2024
NEXTera ENERGY
ADMITTED

Summary: The Extent of Condition applies to the Exciter PMG Stator, Stator field and jumper cables, and the Exciter Stator and Rotor for both Units. They may be susceptible to a similar failure experienced by the Unit 4 PMG stator windings. With regards to the PMG stator field and jumper cables, no degradation was identified during investigations. The Exciter Rotor and A/C Stator are vulnerable to a similar failure given their similarities in construction to the PMG stator and the fact that they are installed outdoors covered by the Exciter housing. Corrective actions and interim actions in this report will address the extent of condition.

C. Extent of Cause

The RCE has determined two Significant Contributing Causes SCCs of the event where individually, neither will cause the event, but when combined would lead to our event. Therefore, the Extent of Cause will evaluate each SCC individually along with both causes collectively occurring.

SIGNIFICANT CONTRIBUTING CAUSE 1 – Weakness in Exciter PM Program based on existing OEM and Industry recommendations which were CONDITION BASED, and did not require TIME-BASED PMG stator rewind, thereby increasing susceptibility to failure from other stressors.

SIGNIFICANT CONTRIBUTING CAUSE 2 – OEM procedure 3.2.2.1 did not include site specific weather sealing requirements based on OE – Latent Error.

Same Object – Same Cause SCC#1:
Object: Unit 4 Exciter PMG Stator.

Cause: PM Program did not require time-based PMG Stator Rewind

Same object and same defect apply to the Unit 3 Exciter PMG Stator with no PM Program for Interval Rewind of the PMG Stator.

- *Initiate new PM for PMG Stator rewind (**CAPR#1**)*

FPSC EXH No. 5
03/18/2024
NEXTera ENERGY
ADMITTED

Same Object – Similar Cause SCC#1:

Object: Unit 4 Exciter PMG Stator.
Cause: Lack of other age-related PMs regarding other PMG Stator Failure mechanisms.

The same object with similar cause applies to both the PTN Unit 3 and 4 Generator PMG Stators with a lack of age-related PMs to ensure reliable service. New rewind PM (CAPR#1) will address all probable age related failure mechanisms of the PMG Stator. No additional actions necessary.

Similar Object – Similar Cause SCC#1:

Object: Single Point Vulnerable (SVP) Wound equipment (U3/U4 Generator Exciter Rotor and A/C Stator, motors, transformers, etc.)
Cause: PM Program did not include age related PMs.

The SPV wound equipment are of similar construction to the PMG stator (i.e. insulated windings). PMs for these components may not be adequate to ensure continued reliability.

- *System Engineering to review Large/Small motors, and large Transformer SPVs and associated PM philosophy / Life Cycle Management Plans (LCMPs) for adequate continued reliability. (**CA#4**)*

Similar Object – Similar Cause SCC#1:

Object: Units 3 & 4 Emergency Diesel Generator (EDG) Exciters
Cause: Lack of age-related PMs regarding Exciter System mechanisms.

The electrical aspects of the PM program established for the Emergency Diesel Generators are performed in accordance with procedure ¾-PME-023.2, "Emergency Diesel Generator Electrical Maintenance". Currently, the PM program includes several electrical checks of the Exciter system but does not include an age-based Exciter rewind activity. It is important to note that LTAM PTN-11-0033 to replace both the Unit 3 and 4 EDG Voltage Regulator systems (i.e. exciter components) is currently scheduled for 2021. The project is anticipated to be implemented during PT3-33/34 for the Unit 3 A and B EDGs, and PT4-33/34 for Unit 4 A and B EDGs.

FPSC EXH No. 5
03/18/2024
NEXTera ENERGY
ADMITTED

C3-283

- *System Engineer for Emergency Diesel Generators to review existing PM program and assess whether an age-based Exciter rewind activity is required. **(CA#5)***

Summary (SCC#1): The Extent of Cause applies to the PMG Stator for both Units and their associated PM strategies. It also applies to the Exciter Rotor and Stator for each Unit given their similarities in construction. Additionally, SPV wound equipment (Steam Generator Feed Pump Motors, Reactor Coolant Pump Motors, Main and Auxiliary Transformers) apply to the extent of cause, as well as the EDG Exciters. Actions have been created to address the Extent of Cause with this significant contributor.

C3-181

FPSC EXH No. 5
03/18/2024
NEXTera ENERGY
ADMITTED

SIGNIFICANT CONTRIBUTING CAUSE 2 – OEM procedure 3.2.2.1 did not include site specific weather sealing requirements based on OE – latent error.

Same Object – Same Cause SCC#2:

Object: PTN and PSL Exciter PMG Stator.
Cause: OEM procedure 3.2.2.1 which reinstalls the Exciter Housing does not include site specific seals.

Same object and same cause apply to PTN and PSL Exciter PMG Stators, and their enclosures given OEM procedure 3.2.2.1 applies to both units.

- *Revise Siemens procedure 3.2.2.1 Exciter Enclosure Removal and Reinstallation to require site specific weather seals for Exciter Housing (**CAPR#2**)*
- *Review Siemens procedure for PSL Exciter Enclosure Removal and Reinstallation and revise as required. (**CA#3**)*

Same Object – Similar Cause SCC#2:

Object: PTN and PSL Exciter PMG Stator.
Cause: OEM procedures did not incorporate site OE.

- *Review PTN OEM procedures for Exciter equipment to ensure all relevant site OE is incorporated (**CA#4**).*
- *Review PSL OEM procedures for Exciter equipment to ensure all relevant site OE is incorporated (**CA#5**).*

Similar Object – Similar Cause SCC#2:

Object: SPV Wound equipment (U3/U4 Generator Exciter Rotor and A/C Stator, motors, transformers, etc.)
Cause: OEM procedures did not incorporate site OE.

- *Review SPV Wound equipment OEM procedures to ensure all relevant site OE is incorporated. (**CA#6**)*

C3-285

FPSC EXH No. 5
03/18/2024
NEXTera ENERGY
ADMITTED

Similar Object – Similar Cause SCC#2:

Object: Units 3 and 4 Emergency Diesel Generator Exciters
Cause: OEM procedures did not incorporate site OE.

- *EDG Equipment Vendor procedures may not have all relevant site OE incorporated (**CA#7**).*

Summary (SCC#2): The Extent of Cause for Significant Contributing Cause 2 applies to OEM procedure 3.2.2.1 and the lack of incorporation of site OE regarding site specific weather seals. It also applies to other vendor procedures for similar equipment which may not have all applicable site OE incorporated. Actions have been created to address the Extent of Cause for this Significant Contributor.

Extent of Cause Assessment w/Two Causes from SCC#1 and SCC#2

As this RCE has revealed two distinctive significant contributors caused the event, the following Extent of Cause assessment and subsequent actions provides credible substance in potentially preventing a similar event from occurring. **The Extent of Cause for Similar Object (Single Point Vulnerable Wound Equipment) – Similar Defect (Two Known Defects)** revealed potential concerns where opportunities in corrective measures are provided herein.

As stated in PI-AA-100-1005, “Root Cause Analysis” procedure, “There must be an element of judgment applied when determining the extent of condition/cause. The assessment must be of sufficient depth to mitigate a repeat event, but not so broad as to create corrective actions directed towards low probability events. This judgment shall be based on a review of the risk and consequences of reducing the extent of condition/cause from the broad-based evaluation. A Similar Object and Similar Defect assessment provides the greatest value in viable corrective actions, which is basis for the below assessment.

Similar Object – Similar Cause

C3-183
FCR-22-000474

FPSC EXH No. 5
03/18/2024
NEXTera ENERGY
ADMITTED

C3-286

Insulation aging is the aggregate effect of stresses imposed on an insulation system. As example, the stator winding insulation system provides a barrier between the copper conductors and ground. Stressors gradually degrade the insulation over time increasing failure potential. Stressors consist of electrical, environmental, mechanical, and thermal.

Object: Stator/Rotor Windings on Critical Single Point Vulnerable (SPV) Wound Equipment

Cause#1: Lack of a PM program on critical motor subcomponents (new or aged)

Cause#2: Lack of site OE incorporated into OEM procedures.

a. Electrical: Connections, dielectric aging, tracking, corona, transients
b. Environmental: Moisture, chemical, abrasion, ventilation
c. Mechanical: vibration (coil movement), rotor impact, foreign material
d. Thermal: ambient temperature, lack of ventilation, load, cycling

These stressors apply generically to all rotating electrical apparatus. While some of these stressors are present as a part of normal operation, others are external influences that accelerate degradation and reduce insulation life. In the case of the PTN4 PMG Stator failure, normal aging coupled with moisture intrusion over time led to an online failure.

Extent of cause applies to motors, large transformers, and generators operating in a similar environment, with age being a factor in failure potential. As a result, actions as part of this RCE have been initiated to evaluate the existing PM program for Critical / SPV motors, large transformers, and EDGs, and initiate PMCs in EStrategy for any gaps identified in respect to life cycle management rewinds.

C3-184

FPSC EXH No. 5
03/18/2024
NEXTera ENERGY
ADMITTED

D. Safety Culture Evaluation

During the Safety Culture Impact Review minor issues were found, none indicating a weakness in the stations Safety Conscious Work Environment. Missing Barriers were identified but all pertained to a weak or broken barrier and were organizational or programmatic in nature, not personnel issues.

The Nuclear Safety Culture Evaluation Form was filled out based on information obtained through the FIP, reviews of Operator, OCC and FIP Team logs, research, interviews and the RCE process. Furthermore, feedback from the Employees Concerns Program did not identify any concerns that were brought up dealing specifically with the PMG Exciter failure, the FIP process, the RCE, or interviews conducted during the investigation. The PTN team has and continues to consistently display a strong Safety Conscious Work Environment.

INTRODUCTION

The safety culture evaluation is performed for each CAQ RCE. The nuclear safety culture evaluation is also performed for issue investigations when addressing an NRC finding. When addressing an NRC finding or violation, the investigation should determine the cause of the condition leading to the finding/violation, and Cross-Cutting aspect if applicable.

The purpose of a nuclear safety culture evaluation is to determine if the organization has a healthy bias towards nuclear plant safety and demonstrates their commitment to nuclear safety culture as an overriding priority across the Reactor Oversight Program cornerstones of safety. The intent of the evaluation is to ensure the analysis assesses the root cause(s) to the Nuclear Safety Cross-Cutting Aspects and the corresponding corrective actions are aligned to mitigate repetitive events.

This Safety Culture Evaluation is part of the Regulatory Margin Corrective Action Strategy defined in LI-AA-200. The focus of this program is to initiate action prior to an NRC performance threshold being crossed.

Each identified cause is categorized against the most relevant aspects in the categories of Human Performance (H), Problem Identification & Resolution (P) and Safety Conscious Work Environment (S).

Note
Per NRC Inspection Manual Chapter 0310, the supplemental cross-cutting aspects (X) are to be considered only when performing or reviewing safety culture assessments during the conduct of the supplemental inspections (95001, 95002 and 95003).

FPSC EXH No. 5
03/18/2024
NEXTera ENERGY
ADMITTED

The following definitions are provided as an aide to understanding and performing the safety culture evaluation.

Nuclear Safety Culture: The core values and behaviors resulting from a collective commitment by leaders and individuals to emphasize safety over competing goals to ensure protection of people and the environment.

Cross-Cutting Area: Fundamental performance characteristics that extend across all the Reactor Oversight Program cornerstones of safety. These areas are human performance (HU), problem identification and resolution (PI&R), and safety conscious work environment (SCWE).

Cross-Cutting Aspect: A performance characteristic that is the most significant contributor to a performance deficiency.

FPSC EXH No. 5
03/18/2024
NEXTera ENERGY
ADMITTED

Nuclear Safety Culture Evaluation Table

06.01 Human Performance (H)

#	Criteria	Comment
H.1	**Resources:** Leaders ensure that personnel, equipment, procedures, and other resources are available and adequate to support nuclear safety (LA.1).	***Significant Contributing Cause / CAPR #2)*** OEM procedure 3.2.2.1 did not include site specific weather sealing requirements based on OE– Latent Error.
H.2	**Field Presence:** Leaders are commonly seen in the work areas of the plant observing, coaching, and reinforcing standards and expectations. Deviations from standards and expectations are corrected promptly. Senior managers ensure supervisory and management oversight of work activities, including contractors and supplemental personnel (LA.2).	Not Applicable
H.3	**Change Management:** Leaders use a systematic process for evaluating and implementing change so that nuclear safety remains the overriding priority (LA.5).	Not Applicable
H.4	**Teamwork:** Individuals and work groups communicate and coordinate their activities within and across organizational boundaries to ensure nuclear safety is maintained (PA.3).	Not Applicable
H.5	**Work Management:** The organization implements a process of planning, controlling, and executing work activities such that nuclear safety is the overriding priority. The work process includes the identification and management of risk commensurate to the work and the need for coordination with different groups or job activities (WP.1).	***Significant Contributing Cause / CAPR #2)*** OEM procedure 3.2.2.1 did not include site specific weather sealing requirements based on OE – Latent Error.
H.6	**Design Margins:** The organization operates and maintains equipment within design margins. Margins are carefully guarded and changed only through a systematic and rigorous process. Special attention is placed on maintaining fission product barriers, defense-in-depth, and safety related equipment (WP.2).	Not Applicable
H.7	**Documentation:** The organization creates and maintains complete, accurate and, up-to-date documentation (WP.3).	Not Applicable
H.8	**Procedure Adherence:** Individuals follow processes, procedures, and work instructions (WP.4).	Not Applicable
H.9	**Training:** The organization provides training and ensures knowledge transfer to maintain a knowledgeable, technically	Not Applicable

FPSC EXH No. 5
03/18/2024
NEXTera ENERGY
ADMITTED

	competent workforce and instill nuclear safety values (CL.4).	
H.10	**Bases for Decisions:** Leaders ensure that the bases for operational and organizational decisions are communicated in a timely manner (CO.2).	Not Applicable
H.11	**Challenge the Unknown:** Individuals stop when faced with uncertain conditions. Risks are evaluated and managed before proceeding (QA.2).	Not Applicable
H.12	**Avoid Complacency:** Individuals recognize and plan for the possibility of mistakes, latent issues, and inherent risk, even while expecting successful outcomes. Individuals implement appropriate error reduction tools (QA.4).	Not Applicable
H.13	**Consistent Process:** Individuals use a consistent, systematic approach to make decisions. Risk insights are incorporated as appropriate (DM.1).	Not Applicable
H.14	**Conservative Bias:** Individuals use decision making practices that emphasize prudent choices over those that are simply allowable. A proposed action is determined to be safe in order to proceed, rather than unsafe in order to stop (DM.2).	Not Applicable

06.02 Problem Identification and Resolution (P)

#	Criteria	Comment
P.1	**Identification:** The organization implements a corrective action program with a low threshold for identifying issues. Individuals identify issues completely, accurately, and in a timely manner in accordance with the program (PI.1).	Not Applicable
P.2	**Evaluation:** The organization thoroughly evaluates issues to ensure that resolutions address causes and extent of conditions commensurate with their safety significance (PI.2).	Not Applicable
P.3	**Resolution:** The organization takes effective corrective actions to address issues in a timely manner commensurate with their safety significance (PI.3).	Not Applicable
P.4	**Trending:** The organization periodically analyzes information from the corrective action program and other assessments in the aggregate to identify programmatic and common cause issues (PI.4).	***(Significant Contrib Cause / CAPR #1)*** Weakness in Exciter Program based on ex OEM and Industry recommendations wh were CONDITION BASED, and did not TIME-BASED PMC rewind, thereby incre susceptibility to failu other stressors. (AR 00406541)

FPSC EXH No. 5
03/18/2024
NEXTera ENERGY
ADMITTED

C3-291

		2010-10671- INPO A (ER.2-1) – Critical Components are Fail
P.5	**Operating Experience:** The organization systematically and effectively collects, evaluates, and implements relevant internal and external operating experience in a timely manner (CL.1).	***Significant Contribu Cause / CAPR #2)*** OEM procedure 3.2. not include site spec weather sealing requirements based Latent Error.
P.6	**Self-Assessment:** The organization routinely conducts self-critical and objective assessments of its programs and practices (CL.2).	Not Applicable

06.03 Safety Conscious Work Environment (S)

#	Criteria	Comment
S.1	**SCWE Policy:** The organization effectively implements a policy that supports individuals' rights and responsibilities to raise safety concerns, and does not tolerate harassment, intimidation, retaliation, or discrimination for doing so (RC.1).	Not Applicable
S.2	**Alternate Process for Raising Concerns**: The organization effectively implements a process for raising and resolving concerns that is independent of line management influence. Safety issues may be raised in confidence and are resolved in a timely and effective manner (RC.2).	Not Applicable
S.3	**Free Flow of Information:** Individuals communicate openly and candidly, both up, down, and across the organization and with oversight, audit, and regulatory organizations (CO.3).	Not Applicable

06.04 Supplemental Cross-Cutting Aspects (X)

#	Criteria	Comment
X.1	**Incentives, Sanctions, and Rewards:** Leaders ensure incentives, sanctions, and rewards are aligned with nuclear safety policies and reinforce behaviors and outcomes that reflect safety as the overriding priority (LA.3).	Not Applicable
X.2	**Strategic Commitment to Safety:** Leaders ensure plant priorities are aligned to reflect nuclear safety as the overriding priority (LA.4).	Not Applicable
X.3	**Roles, Responsibilities, and Authorities**: Leaders clearly define roles, responsibilities, and authorities to ensure nuclear safety	Not Applicable

C3-189
FCR-22-000480

FPSC EXH No. 5
03/18/2024
NEXTera ENERGY
ADMITTED

C3-292

	(LA.6).	
X.4	**Constant Examination:** Leaders ensure that nuclear safety is constantly scrutinized through a variety of monitoring techniques, including assessments of nuclear safety culture (LA.7).	Not Applicable
X.5	**Leader Behaviors:** Leaders exhibit behaviors that set the standard for safety (LA.8).	Not Applicable
X.6	**Standards:** Individuals understand the importance of adherence to nuclear standards. All levels of the organization exercise accountability for shortfalls in meeting standards (PA.1).	Not Applicable
X.7	**Job Ownership:** Individuals understand and demonstrate personal responsibility for the behaviors and work practices that support nuclear safety (PA.2).	Not Applicable
X.8	**Benchmarking:** The organization learns from other organizations to continuously improve knowledge, skills, and safety performance (CL.3).	Not Applicable
X.9	**Work Process Communications:** Individuals incorporate safety communications in work activities (CO.1).	Not Applicable
X.10	**Expectations:** Leaders frequently communicate and reinforce the expectation that nuclear safety is the organization's overriding priority (CO.4).	Not Applicable
X.11	**Challenge Assumptions:** Individuals challenge assumptions and offer opposing views when they think something is not correct (QA.3).	Not Applicable
X.12	**Accountability for Decisions:** Single-point accountability is maintained for nuclear safety decisions (DM.3).	Not Applicable

5.E Risk/Consequence

Personnel safety
There were no risks to Personnel Safety

Environmental safety
There were no risks to Environmental Safety

Actual nuclear safety significance
This event resulted in an automatic Reactor trip due to Turbine Trip / Generator Lockout. Reactor power was at 100% at the time of the trip. There was no challenge to the integrity of the primary or secondary plant. The plant response during this event is bounded by an event assuming a loss of load analyzed in Turkey Point's Updated Final Safety Analysis Report. This event is not a safety significant event and had no adverse effect on the health and safety of the public.

FPSC EXH No. 5
03/18/2024
NEXTera ENERGY
ADMITTED

Note: This trip negatively impacted the NRC performance indicator for "Unplanned Scrams per 7000 critical hours." There is adequate margin to white for the NRC PI, and no additional actions are required for this indicator.

6. Operating Experience

An OE search was conducted on the INPO industry websites, IRIS Experience report and the NextEra Energy fleet Corrective Action Program (CAP) to determine if prior OE was available related to Turbine Exciter PMG failures and/or Turbine trip from a Main Generator lockout or other potentially related issues. The first focus was on HB Robinson due to it being most like PTN regarding its Turbine Generator then the review was expanded to the entire industry and then to PTN.

HB Robinson OE Review:

Robinson U2 - (2/27/1985) – IRIS # 276795

HB Robinson U2 experienced a Turbine trip due to failed Min Transformer lightning arrestor on “C” Transformer causing a generator-to-Main Transformer differential Generator lockout giving a Turbine trip.

Robinson U2 - (5/2/1988) IRIS Report #286116

HB Robinson U2 experienced a Turbine trip with reactor power greater than 10 percent Turbine Governor valve position limiter failed to zero position which signals the four governor valves to shut. The Turbine tripped from a Main Generator lockout which resulted in a reactor trip. The Generator lockout occurred due to a reverse power condition caused by closure of the Turbine Governor valves.

Robinson U2 - (11/17/2006) – IRIS # 223907

HB Robinson U2 experienced a Main Generator voltage regulator alarm. The cause for the Main Generator voltage regulator alarm was due to an apparent faulty Overexcitation Protection module but that no failure of the voltage regulator had occurred and even with the alarm locked in none of the voltage regulator’s capacity was lost.

Robinson U2 - (8/11/2019) – IRIS # 461198

HB Robinson U2 experienced a Plant trip and subsequent outage due to Main Generator exciter failure

On 8/11/2019 at 08:41, an automatic plant trip occurred on Main Generator Lockout. The first out annunciator received was a Turbine trip. At the same time the control board indicator for the exciter field breaker amps began to fail with excessive voltage to ground resulting in the meter smoking and emitting some arcing. This was followed by the loss of field (40) relay actuating, causing a Main Generator Lockout and exciter field breaker trip, resulting in a turbine trip and subsequent reactor trip. Alarms APP-009-A1 (loss of generator excitation), APP-009-A2 (generator excitation low/trip), APP-009-B1 (regulator field forcing), and APP-009-D1 (exciter power loss/trip or generator field

FPSC EXH No. 5
03/18/2024
NEXTera ENERGY
ADMITTED

ground detection) were received. Upon investigation, strong acrid odor was noted on the turbine deck. The exciter was found with significant damage including metal slag on the floor of the exciter house.

It was later determined that an arc fault had occurred inside the exciter armature (rotor) causing substantial damage to the rotating and stationary windings of the exciter as well as the inboard diode wheels. Due to excessive damage to the rotating components of the exciter, the exact cause could not be determined. The cause was most likely a latent failure of the exciter armature due to either coil or core failure, although as stated the precise cause was indeterminate.

Robinson Corrective Action Summary:

- Replace the exciter with a refurbished exciter.
- Test all related circuits (voltage regulator, main generator field and stator) to ensure fault did not damage them.
- Replace the control board meter and removed the unintended ground path(s) and Megger cables to ensure no additional low resistance paths existed. Fuses to its circuit to help prevent excessive overcurrent were added.

Review of Industry OE:
Braidwood U2 (Exelon) - (11/30/1993) IRIS # 141879
Braidwood U2 found age related degraded component

Nomex components (winding components) located under the phase leads were found to have migrated from their original position. **The apparent cause was the exciter retaining band lost its tension preload due to age related degradation.** Migrating components under the banding is a known occurrence that could possibly occur within "advanced age" exciters. However, Siemens never notified Exelon of this migration possibility before their A2R18 outage. After the condition was noticed during A2R18, Exelon decided that the exciter needed replacement instead of returning to operation.

Waterford 3 (Entergy)
Waterford U3 experienced a Main Generator trip due to a loss of excitation.

An automatic main generator/turbine trip occurred due to the main generator losing excitation. Upon inspection, two outboard diodes were found to have arced and shorted within the rotating rectifier circuit. Excessive dirt and other debris were built up in the interior of the rotating rectifier. The debris formed an electrical path between diodes and subsequently caused the arcing. **The main causal factors were an unclear preventative maintenance scope and not completing work order steps without justification.**

Indian Point Unit 2 (Entergy)
Indian Point U2 experienced a Min Generator trip due to a loss of excitation.

Alarms for "Exciter Cubicle Trouble" were received by the Control Room but before operators could investigate, the main generator tripped due to loss of excitation. A diode stack had failed, and **the root cause was that the power diode test method proved**

FPSC EXH No. 5
03/18/2024
NEXTera ENERGY
ADMITTED

unable to detect component degradation. A corrective action implemented a preventative maintenance strategy to guarantee proper monitoring and testing of the power diodes.

Hope Creek U1 (11/30/1993) IRIS # 141879
Hope Creek forced normal Rx shutdown due to failure of Main Generator Exciter

Operator on normal rounds reported arcing on the Main Generator /Alterex inboard excite #2 brush. These brushes cam be changed out on-line and that was attempted but during that process the other two brushes (brush 1 and 3) began arcing at which time it was decided to take the unit off-line for repairs. The cause was degraded brush to collector ring contact causing overheating and deterioration of the collector ring surface. **This was an age-related component failure.**

INPO'S Encyclopedia of OE:

SER 60-82
An electrical fault within the main generator exciter was accompanied by arcing. This led to a reactor trip, extensive exciter damage (needing three weeks of repair), and an indefinite cause. It is suspected that either loose bolting between exciter bus bars and brush support or a failed connection located at the 90-degree bend of a bus bar led to the arcing. In response to this issue, Westinghouse disseminated a letter to turbo generator owners reminding them that they should verify the tightness of exciter connections and check the exciter bus bars bolt torque before each plant startup.

O&MR 256-85
A loss of main generator excitation caused a turbine generator trip resulting in a subsequent reactor trip. The cause of exciter failure was a brush failure. The brush became lodged between its guide and spring arm and thus caused arcing. The brush had excessive wear and the incident could have been prevented had the brush inspection criteria been more stringent. The resultant solution was increasing brush inspection to every 14 days, adding brush replacement criteria to the inspection, and presenting preventative maintenance training to the electrical maintenance personnel.

Utility Generator Predictive Maintenance conference (12/3/1998):

Under the section in the report regarding Moisture, the following was stated:

The presence of contaminated water, condensation, or any type of moisture can also cause failure of diode wheel components. Electrical "tracking", as described earlier, can occur with moisture in the same way as it does with dirt or fly ash. Moisture can also lower the insulation resistance of the diode wheel components and the windings.

Outdoor generating units in high humidity areas are prone to having moisture form in the exciter house through condensation on the cooling coils. Condensation was so much of a problem at Florida Power & Lights (FPL) Martin, Manatee and Sanford stations that the cooling water would often be shut off when the units cycled off at night.

Moisture can also be a problem on outdoor units, if the seal between the exciter house and the sole plate is not adequate. One of the units in southern Florida (PTN's Unit 3)

FPSC EXH No. 5
03/18/2024
NEXTera ENERGY
ADMITTED

was found to be drawing water off the turbine deck and into the exciter house in the area of the PMG. The problem was found when the rotor ground detector indicated a problem. The unit was shut down and the exciter house was swabbed and then vacuumed. The base was temporarily sealed with a bead of RTV. A more permanent fix was enacted during the next refueling outage. Better seals and their correct installation solve the problem.

Of course, cooler leaks, inside the Exciter housing, can also be a source of moisture. Cooler leaks should be repaired immediately.

Both issues mentioned in this section of the "Utility Generator Predictive Maintenance conference report" (internal and external water intrusion) have reoccurred at PTN subsequent to this report dated 12/3/1998. These issues and are documented OE contained in the IRIS Experience Report and are listed below.

Turkey Point specific OE Review:

Turkey Point U3 - (IRIS # 194413) / Date: 9/29/2001
Turkey Point U3 experienced a Forced power reduction due to failure of gasket / seal / o-ring(s) in the Main Turbine Generator.

On 9/29/2001 at 10:30 AM Turkey Point U3 received a Main Generator ground indication in the Control room. Following efforts to clear the ground the station decided to take the unit off-line. The unit went into a forced power reduction due to **water intrusion into the U3 Exciter housing**. **During the event it was noted that the station had been under a severe weather condition with continuous rainfall**. The cause of the water intrusion was ineffective sealing of the exciter bolt channels. With a large pressure differential created in the Exciter housing by the oversized blower it contributed to the volume of water that was drawn into the housing. The investigation also stated that the removal of pipe plugs for an upcoming outage combined with the heavy rains in the area were the contributing causes which led to the event. Extent of condition inspections were conducted to ensure PTN U4 did not have existing leak paths or other relative areas of concern. U4 Exciter housing was found to be sealed properly and dry.

Turkey Point U3 - (IRIS # 213642) / Date: 12/28/2004
Turkey Point U3 experienced a manual scram due to failure of housing assembly in Main Generator Exciter.

On December 28, 2004 at 22:46 hours a manual Reactor trip was initiated due to a large (~90gpm) turbine plant cooling **water leak within the Unit 3 Main Generator Exciter housing.** The discovery of the leak resulted in a fast load reduction from 100% power operation to 70% power at 2235 hours. Once the Operating crew determined the potential impact from the turbine plant cooling water leak, in the Exciter housing and that the leak was non-isolatable, the reactor was manually tripped at 2246 hours.

OE SUMMARY:

Whereas Robinson has experienced numerous issues with their U2 Turbine Generator resulting in Turbine lockouts, Turbine trips and Reactor trips, their 2017 event, where an

FPSC EXH No. 5
03/18/2024
NEXTera ENERGY
ADMITTED

arc-fault occurred in the exciter components and the evidence (debris, smell, visual damage) found during the investigation process, is very similar in nature to what occurred and was subsequently found at PTN during the July 2020 - U4 Turbine Exciter event. A search of OE across the industry show stations experiencing Turbine Exciter issues, most attributed with age related degradation and/or preventive maintenance and monitoring practices. While relatively little to no OE was found directly related to the PMG portion of the Exciter system, the failures noted were primarily due to stator-rotor contact due to bearing failures. There was one paper written by EPRI in Dec 1998 that referenced several FPL plants that were experiencing condensation problems in the Exciter house and even one that speaks of a South Florida plant (PTN Unit 3) where the fan created such a pressure difference that coupled with poor housing base gaskets resulted in water being drawn off the turbine deck into the PMG compartment.

Except for the Robinson event and the events referred to in the EPRI Report mentioned above no other similar issues as what occurred at PTN could be found for comparison.

A review of external and internal OE for PTN identified two issues both related to water intrusion. From the dates shown on the documents it shows that these issues have reoccurred at various times. One issue was water intrusion (leaking gaskets) from an internal source and the other was water intrusion from an external source. The discussion in the OE regarding the external water intrusion highlights three factors. First being the environmental conditions at the time (heavy rains), which can have an adverse effect on outdoor Turbine structures such as what we have here at PTN. Secondly the inadequate sealing of the bolt channels and removal of pipe plugs allowing a leak path into the housing to exist. Third the dynamics and ability of the fan inside the Exciter housing when at full power, that can draw up migrating water and disperse it throughout the housing, potentially affecting the electrical components contained therein and resulting in faults to the electrical components.

While very little OE exists relating directly to the PMG, there is industry wide experience with cable aging effects. Some insulation types such as XLPE is expected to last 60-70 years; however, most insulation materials used is expected to have a shorter life expectancy under normal conditions (20-30 years). When insulation is exposed to more extreme conditions the life expectancy is expected to be less. Once the insulation is compromised, water or contamination can lead to shorts which in turn lead to further failure.

The overall assessment of OE leads to two potential contributing causes for failure. One being age related degradation of Turbine Exciter components and second being water intrusion and saturation of exciter electrical components. It is important to note that the review of internal and external OE did not reveal any failures that were solely attributed to aging of a PMG or Exciter stator/rotor winding. Additionally, vendor and industry documentation for Exciter maintenance does not require Exciter/PMG rewind activities. EPRI documents titled ‘Tools to Optimize Maintenance of Generator Excitation System, Voltage Regulator and Field Ground Detection’ dated 2002, and ‘Plant Support Engineering: Main Generator End-of-Life and Planning Considerations’ dated 2007, make no mention of a requirement for Exciter/PMG winding rewinds. Overhaul activities are recommended which include thorough cleaning, inspection, and testing of these components.

FPSC EXH No. 5
03/18/2024
NEXTera ENERGY
ADMITTED

EPRI and other industry reports recommend condition-based PM philosophy (test and maintain) for brushless exciters are referenced from 1998 to 2002. At that time brushless exciter with PMG design were 15 years old and age-related risk did not contribute in any failure analysis. The industry had not experienced winding failures due to age at that time.

INPO IER Level 2-11-2 "2009 – 2010 Scram Analysis" vs. PTN Response vs. LCM

A review of the PTN response to INPO IER L2-11-2 in respect to Life Cycle Management found the conclusion failed to recognize weakness in the PM program. The Rotating Exciter and Voltage Regulator interim conclusion states:

"No replacement or LCMPs are needed for this component type at this time. However, this conclusion should be revisited after the EPU mods."

The most recent LCM review in 2014 following EPU provided no update to that previous conclusion. Some of the issues specifically outlined in the IER that are directly applicable to the current RCE are as follows:

- Over reliance on skill of craft.
- Discretionary use of blanket statements allowing individual decisions on work steps.
- Ensure planners have requisite knowledge & skill.

An action will be created to provide an update to the IER and to update the Life Cycle Management Plan.

7. Lessons Learned

Vendor recommendations and current industry practices alone with regards to equipment maintenance may not be sufficient to support equipment reliability. The PM philosophy at PTN developed for maintaining the Exciter and Generator components relied upon the recommendations of the OEM and the Industry (CONDITION-BASED) and are considered robust. However, they lacked a requirement to perform a TIME-BASED rewind of the Exciter components. This lack of a rewind requirement allowed the equipment to age which increased susceptibility to failure from other external stressors. Single Point Vulnerability SPV components which are similar in design (i.e. insulating windings around an iron core, e.g. motors and transformers) should be reviewed for appropriate Life Cycle Management (LCM) activities which specifically address age.

8. Proof Statement

(Problem Statement)
On July 5th, 2020 at approximately 2107, during a heavy rainstorm, Unit 4 Tripped Automatically from 100% power due to a Generator Lockout. Object: Unit 4 Exciter PMG.

FPSC EXH No. 5
03/18/2024
NEXTera ENERGY
ADMITTED

C3-299

Defect: Winding Failure. Consequence: Loss of Generator Field Excitation and subsequent tripping of the Reactor and Turbine.
Is caused by
(Root Cause)
A weakness in Exciter PM program resulted from a failure to fully assess risk of PMG stator winding age making it more susceptible to failure when exposed to water/moisture.

And is corrected by
(CAPR) This event will be prevented from re-occurrence by:

- Initiate a TIME-BASED PMG stator rewind PM

Revise OEM procedure 3.2.2.1 to include installation of site-specific weather seals during Exciter housing installation.

C3-197

FPSC EXH No. 5
03/18/2024
ADMITTED

9. Corrective Actions

Area	Category	Corrective Action/Assignment	Responsible	Assignment Type	Due Date
Direct Cause (s)					
Direct Cause PMG Failure	Equipment	• Replace failed PMG Stator and damaged Exciter Rotor. **COMPLETE** • Apply temporary sealant on Unit 4 Exciter Housing**. COMPLETE**			
Root Cause (s)					
Root Cause A weakness in the Exciter PM program resulted from a failure to fully assess risk of PMG stator winding age making it more susceptible to failure when exposed to water/moisture	Programmatic	Addressed by **CAPR #1** and **CAPR #2** below			
Significant Contributing Cause (s)					
Significant Contributing Cause #1 Weakness in Exciter PM Program based on existing OEM and Industry recommendations which were CONDITION BASED, and did not require TIME-BASED PMG stator rewind, thereby increasing susceptibility to failure from other stressors.	Programmatic	**CAPR #1**: Initiate a TIME-BASED PMG stator rewind PM for Unit 4	PGD Tech. Services	CAPR Assignment 21	11/19/2020
Significant Contributing Cause #2 OEM procedure 3.2.2.1 did not include site specific weather sealing requirements based on OE – latent error.	Organizational	**CAPR #2**: Revise Siemens procedure 3.2.2.1 *Exciter Enclosure Removal and Reinstallation* to require site specific weather seals for Exciter Housing	PTN Nuc. Construction	CAPR Assignment 22	Complete
Contributing Cause (s)					
CC #1: Instructions in PTN procedure 0-GMM-090.1, "Exciter Removal, Inspection and Installation," in providing discretionary guidance in lieu of a mandated requirement on Exciter housing application of site specific weather seals for prevention of water intrusion.	Organizational	**CA #1:** Revise site procedure 0-GMM-090.1 to require base seal with each assembly.	PTN Nuc. Construction	CA Assignment 23	Complete
Extent of Condition Action					

Area	Category	Corrective Action/Assignment	Responsible	Assignment Type	Due Date
New Exciter Rewind PMs for PTN and PSL scheduled beyond service life of components.	Programmatic	**LTCA #1-4:** Scope replacement of PMG Stator, AC Exciter Field, and AC Exciter Armature with rewound spares during the following outages: ▪ **LTCA #1**: SL1-30 Spring 2021 (Assignments 24 & 41) ▪ **LTCA #2:** PTN3-32 Fall 2021 (Assignments 25 & 42) ▪ **LTCA #3**: PTN4-33 Spring 2022 (Assignments 26 & 43) ▪ **LTCA #4**: SL2-27 Spring 2023 (Assignments 27 & 44)	PGD Tech. Services	LTCA	8/31/2021
Units 3 & 4 Exciter Housing requires immediate sealing	Equipment	Apply temporary sealant on both Units 3 & 4 Exciter Housing**. COMPLETE.**	N/A	N/A	N/A
Unit 3 Exciter Housing lacks site specific seals.	Equipment	**LTCA #5**: Seal Unit 3 Exciter Housing IAW 0-GMM-90.1 or Siemens procedure 3.2.2.1 during next refueling outage.	PTN Nuc. Construction	LTCA Assignment 45	2/26/2021
Unit 4 Exciter Housing lacks site specific seals.	Equipment	**LTCA #6:** Seal Unit 4 Exciter Housing IAW 0-GMM-90.1 or Siemens procedure 3.2.2.1 during next refueling outage.	PTN Nuc. Construction	LTCA Assignment 46	8/31/2021
PSL Exciter Housing may lack site specific seals.	Equipment	**LTCA #7**: Assess if site specific sealing is required for PSL Units 1 and 2 Exciter Housing and address as necessary.	PGD Tech. Services	LTCA Assignment 47	2/26/2021
Extent of Cause Actions					
PSL vendor procedure for Exciter Housing Removal and Reinstallation may lack site specific seals.	Programmatic	**CA#2**: Review Siemens procedure for PSL Exciter Enclosure Removal and Reinstallation and revise as required.	PSL Project Mgr.	CA Assignment 28	12/18/2020
PTN Vendor procedures related to Exciter compartments may not have all relevant site OE incorporated.	Programmatic	**CA#3:** Review PTN vendor procedures for Exciter equipment to ensure all relevant site OE is incorporated.	PTN Nuc. Construction	CA Assignment 29	12/18/2020
PSL Vendor procedures related to Exciter compartments may not have all relevant site OE incorporated.	Programmatic	**CA#4:** Review PSL vendor procedures for Exciter equipment to ensure all relevant site OE is incorporated.	PSL Project Mgr.	CA Assignment 30	12/18/2020
SPV Wound Equipment Vendor procedures may not have all relevant site OE incorporated.	Programmatic	**CA#5**: Review SPV Wound equipment vendor procedures to ensure all relevant site OE is incorporated	PTN System Engr.	CA Assignment 31	12/18/2020
EDG Equipment Vendor procedures may not have all relevant site OE incorporated.	Programmatic	**CA#6**: Review PTN EDG Equipment Vendor procedures to ensure all relevant site OE incorporated	PTN System Engr.	CA Assignment 32	12/18/2020

Area	Category	Corrective Action/Assignment	Responsible	Assignment Type	Due Date
Single Point Vulnerable (SPV) equipment (SGFPs, RCPs, large Transformers) may not have adequate PMs to address aging of insulation. The PMs for these components may not be adequate to ensure continued reliability.	Programmatic	**CA #7:** System Engineering to review Large/Small motors, and large Transformer SPVs and associated PM philosophy / Life Cycle Management Plans (LCMPs) for adequate age-related tasks. As part of this review, identify and evaluate time-based rewind PM coincident with probable stressors at location and provide remedial sub-actions. Sub-actions to include the activation of a rewind PM and practical remedies to eliminate or reduce the effects of external stressors such as: • Electrical: Connections, dielectric aging, tracking, corona, transients • Environmental: Moisture, chemical, abrasion, ventilation • Mechanical: vibration (coil movement), rotor impact, foreign material • Thermal: ambient temperature, lack of ventilation, load, cycling	PTN System Engr. Supv.	CA Assignment 33	11/19/2020
Exciter Systems for Emergency Diesel Generators (EDGs) may not have adequate PMs to perform age related rewind activities.	Programmatic	**CA #8:** System Engineer for Emergency Diesel Generators to review existing PM program and assess whether an age-based Exciter rewind activity is required.	PTN System Engr.	CA Assignment 34	11/19/2020
Current weather seal applied to both Unit 3 and 4 Exciter Housing is a temporary measure. Need a Bridging strategy to ensure temporary seals remain intact until site specific foam gasket and vertical foam seal are installed.	Programmatic	**CA #9:** Site staff to perform monthly inspection of Unit 3 and 4 Exciter Housing temporary weather seals. Due date associates with establishing an inspection program.	PTN Nuc. Construction	CA Assignment 35	11/19/2020
PM 50551-42 includes task to performs Exciter Housing Door Seal and Hardware inspection every 36M. Seal replacements are discretionary.	Programmatic	**CA #10:** Revise PM 50551-42 to require replacement of all Exciter housing door seals. Consider creating a new standalone 18M PM task for door seal replacements.	PGD Tech. Services	PMCA Assignment 36	2/26/2021
Other (Enhancements)					
Lack of Ground Detection System on PMG Stator Windings	Equipment	**A #1:** Create LTAM to install a ground detection system to detect grounds on the PMG stator windings and downstream circuits. Consider also Exciter stator monitoring.	PGD Engr.	MA Assignment 37	2/26/2021
Inability to monitor exciter interior online for water intrusion.	Equipment	**A #2:** Create LTAM to install leak detection system to identify online water intrusion inside Exciter housing.	PGD Engr.	MA Assignment 38	2/26/2021
0-GME-090.02 for Voltage Regulator Switchgear Maintenance relies on discretionary repairs to mitigate water intrusion into the Voltage Regulator housing.	Programmatic	**A #3:** PCR against 0-GME-090.02 to require clarification that if the procedure is being performed as part of a routine PM activity, the Voltage Regulator Roof shall be coated for water intrusion, all existing door gaskets and seals replaced, and supplementary seals be reapplied.	PTN System Engr.	PCRA Assignment 39	11/19/2020

FPSC EXH No. 5
03/18/2024
NEXTera ENERGY
ADMITTED

10. **Deferral Justification**

All associated actions including the CAPR are justifiably provided with a completion due date commensurate with ensuring the least probable risk for equipment failure. The applied dates on the contributor's respective actions will not impact or affect any/all safety systems presently operating. The FIP activities that followed the event date provided immediate interim actions as applicable per the program requirements. Any/all equipment actions or assignments identified from the FIP and RCE conclusions will be performed during subsequent refueling outages. Both PSL and PTN will be provided with interim corrective actions to ensure sufficient temporary sealant is applied at the susceptible locations around the Exciter housing. There are no FIP actions impacted as a result of the actions and associated dates applied. O&P weaknesses have been identified and associated actions are being assigned. These identified O&P weaknesses are not considered to require immediate attention. Appropriate assignment due dates will be applied to ensure appropriate oversight to same-same, same-similar and similar-similar equipment during subsequent refueling cycles and identified equipment respective PMs.

11. **Effectiveness Review Plan**

The following attributes are required when performing the effectiveness review.

a. Methodology

Perform assessment to document the following:

1. Review of all CAPR actions and CA actions taken and dates completed from this CR.
2. Search for similar condition reports.
3. Search for any condition reports that may have resulted from the corrective actions from this root cause.

b. Attributes

1. Verify that the actions have been implemented as written.
2. Verify that no similar issues have been reported since the corrective actions were implemented.
3. Verify that no new unwanted/unexpected conditions have occurred due to the corrective actions implemented for this event.
4. Verify that the O&P changes are comprehensive enough to ensure that designers, planners and implementers are adequately informed to minimize water intrusion events for same/similar objects.

FPSC EXH No. 5
03/18/2024
ADMITTED

C3-304

c. Success Criteria

1. All the actions have been implemented as prescribed in the root cause report.
2. No Turbine Exciter equipment failures/trips or perturbations due to water intrusion or condensate buildup within the housing since the Extent of Condition and Cause actions and other field related corrective actions having been implemented.
3. No new unwanted/unexpected conditions have occurred due to the corrective actions implemented for this event.

d. Timeframe – Complete the effectiveness review within 18 months of the completion date of the final CAPR.

12. **Attachments**

- Attachment 1 - Root Cause Charter
- Attachment 2 - Photographs
- Attachment 3 - Exciter Ground Detection System
- Attachment 4 – Exciter PM Description and Status
- Attachment 5 – FIP Team Support/Refute Matrix
- Attachment 6 – Root Cause Support/Refute Matrix
- Attachment 7 - Barrier Analysis
- Attachment 8 – Timeline
- Attachment 9 – Potential Paths of Water Ingress

C3-202
FCR-22-000493

FPSC EXH No. 5
03/18/2024
NEXTera ENERGY
ADMITTED

Attachment 1: Root Cause Charter

ROOT CAUSE CHARTER

Facility/CR Number:
Turkey Point Nuclear / AR 02361794

Manager Sponsor:
Dianne Strand, Engineering Director

Brief Event Description:
The Unit 4 Reactor tripped due to a Main Generator (4K2) Lockout followed by a Turbine Trip. The Main Generator Lockout was caused by actuation of the Voltage Regulator (VR) Lockout relay due to loss of VR Power Supplies #1 & #2.

Detailed Event Description:
On July 5th, 2020 at approximately 1844, during a heavy thunderstorm, the Control Room received Annunciator AN-E-8/3 (GEN CONTACT FIELD BRUSH CONTACT FAIL/GROUND) on Unit 4. At approximately 1900, the Turbine Operator depressed the RESET pushbutton above the generator field breaker IAW Procedure 4-ARP-097.CR.E. Annunciator AN-E-8/3 momentarily reset then re-alarmed. Annunciators AN-E-9/3 (GEN VOLT REG LOSS OF BACKUP) and AN-E-7/6 (GEN VOLT REG TRANSFER TO MANUAL) subsequently alarmed. Annunciator AN-E-9/3 cleared as soon as it was acknowledged. However, Annunciators AN-E-8/3 and AN-E-7/6 remained locked-in. At this time the VR swapped from Automatic AC regulator to Manual DC regulator.

At approximately 2045, Operations noted one alarm on the local VR panel, “Loss of XDCR No. 1”. Shortly thereafter, at approximately 2050, Annunciators, AN-E-9/3 (GEN VOLT REG LOSS OF BACKUP) & AN-E-8/6 (GEN VOLT REG TROUBLE) were received multiple times. Operations also observed reactive load on the Unit 4 Main Generator increase from 115 MVAR to 200 MVAR during a 5-minute period.

At approximately 2100, Operations reported that the Exciter field volts were oscillating. Then, at 2107 the Unit 4 Reactor tripped due to a Main Generator (4K2) Lockout followed by a Turbine Trip. The Main Generator Lockout was caused by the actuation of the VR Lockout relay due to loss of VR Power Supplies #1 & #2. After the trip, the following Generator Exciter Switchgear control cabinet alarms remained locked in: Power Supply #1, Power Supply #2, Firing Circuit #2, and Loss of XDCR #1.

Problem Statement:
The Unit 4 Reactor tripped due to a Main Generator (4K2) Lockout followed by a Turbine Trip. The Main Generator Lockout was caused by actuation of the Voltage Regulator (VR) Lockout relay due to loss of VR Power Supplies #1 & #2.

FPSC EXH No. 5
03/18/2024
NEXTera ENERGY
ADMITTED

Attachment 2: Photographs



Fig. 1 U4 Exciter Housing

FPSC EXH No. 5
03/18/2024
NEXTera ENERGY
ADMITTED




Fig. 2 U4 Exciter with PMG Stator Installed

FPSC EXH No. 5
03/18/2024
NEXTera ENERGY
ADMITTED




Fig. 3 U4 Exciter with Housing and PMG Stator Removed

FPSC EXH No. 5
03/18/2024
NEXTera ENERGY
ADMITTED




Fig 4 Exciter Rotating Element Removed

FPSC EXH No. 5
03/18/2024
NEXTera ENERGY
ADMITTED



Fig. 5 U4 PMG Stator Removed

FPSC EXH No. 5
03/18/2024
NEXTera ENERGY
ADMITTED

C3-311



Fig. 6 PMG Stator Core – Coil Melt in Slots

FPSC EXH No. 5
03/18/2024
NEXTera ENERGY
ADMITTED



Fig. 7 PMG Stator Coil Connection Ring Failures

FPSC EXH No. 5
03/18/2024
NEXTera ENERGY
ADMITTED



Fig. 8 PMG Pole Support w/ Magnets



Fig. 9 PMG Magnet Rub

FPSC EXH No. 5
03/18/2024
NEXTera ENERGY
ADMITTED



Fig. 10 PMG Magnet Cracking

FPSC EXH No. 5
03/18/2024
NEXTera ENERGY
ADMITTED

C3-315



Fig. 11 Foreign Material (Shims) Found in AC Exciter Section

FPSC EXH No. 5
03/18/2024
NEXTera ENERGY
ADMITTED



Fig. 12 Liberated Shim Stock Found in AC Exciter Section



Fig. 13 Exciter Base to Housing Seal / Gasket Arrangement

FPSC EXH No. 5
03/18/2024
NEXTera ENERGY
ADMITTED


Attachment 3: Generator and Exciter Ground Detection System Discussion

The Turkey Point Units 3 and 4 brushless excitation systems are ungrounded. The Generator Field Ground Detection System monitors ground for Generator Rotor, Exciter Rotor (exciter armature), and Rectifier Diode Wheels. The exciter is equipped with a set of auxiliary slip rings that permit intermittent ground checks through the operation of a set of solenoid actuated brushes (two brushes for each slip ring for redundancy) and an external monitoring circuit. One slip ring is connected to the midpoint of the star-connected exciter armature and the other is connected to the shaft (ground). The automated Ground Detector Panel is located inside the Excitation Switchgear right cubicle above Field Breaker panel. It consists of the circuitry which applies a DC voltage across the two slip rings and measures the resultant current flow.





FPSC EXH No. 5
03/18/2024
NEXTera ENERGY
ADMITTED



The ground detector panel provides an automatic ground check on the Generator rotor and exciter rotor once every 24-hours. Three push buttons switch are located on ground detector module for TEST- RESET – SIMULATE function with status indication lights. Operation of the test switch allows a ground check to be performed manually at any time.

During the period of time that the ground detector panel is not performing a ground check, brushes are disconnected from the machine slip rings and ground sensing is inactive. Brushes only contact the slip rings for one minute every 24 hours during an automated test cycle. If a ground is detected during the one min test cycle, then an alarm will latch in until manually reset from the ground detection panel.

Event cause and analysis:

Control Room received Annunciator AN-E-8/3 (GEN CONTACT FIELD BRUSH CONTACT FAIL/GROUND) on Unit 4 at 1844 with heavy rainstorm. This is the first alarm received from voltage regulator prior to trip event. At approximately 1900, the Turbine Operator depressed the RESET pushbutton above the generator field breaker IAW Procedure 4-ARP-097.CR.E. Annunciator AN-E-8/3 momentarily reset then re-alarmed.

Automated ground detection cycle is only 1 minute, and brushes should have been pull back after 1-minute cycle assuming no mechanical locking or solenoid miss operation. Brushes no longer connected to slip ring after 1 minute from receiving alarm.

C3-320

FPSC EXH No. 5
03/18/2024
ADMITTED

Alarm stay locked in after manual reset which means there was still ground current path between brushes or Exciter housing cable terminals. This is likely from excessive moisture around brush area which result in small amount of ground current to flow between brushes and alarm stay locked in assuming ground detection panel is healthy and working properly.
FAR # 7 confirmed no issue on Ground Detector sensing panel. Ground brushes solenoid actuation system PM performed, and no issue found in solenoid actuation arrangement.
Cause Analysis: Moisture contributes to keep ground alarm stay locked in during heavy rain.


C3-218
FCR-22-000509

FPSC EXH No. 5
03/18/2024
ADMITTED

C3-321

Barrier Analysis and Alternatives – PMG Winding Failure:


Simplified diagram of Turkey Point Units 3and 4 WTA-300 voltage regulator with brushless exciter and main generator:



- Turkey Point units 3 and 4 have Generator field ground monitoring system and do not have exciter field ground monitoring. Generator field ground system monitors ground on Generator rotor, rectifier diode wheel and exciter rotor (armature). Exciter field ground monitors continuous ground on exciter stator (field), Voltage Regulator, cables and PMG stator.
- Point Beach WTA-300B installed in 2000 have exciter field ground monitoring addition to the generator field ground monitor system. PB voltage regulator drawing no: 97-MK365SAA. 64B is Generator field ground detector and 64F is exciter field ground detector.

C3-219
FCR-22-000510

FPSC EXH No. 5
03/18/2024
ADMITTED



Simplified Drawing of AVR, PMG, and AC Exciter Circuits

- Exciter Field Ground identify small ground which can accelerate over time if undetected and result in catastrophic event like PMG winding fail or exciter stator winding fail. Field Ground provides early detection of degradation of winding insulation in some fault scenario however Exciter Field Ground will not help to identify catastrophic fault on PMG or exciter field winding which do not give enough time for operator action for troubleshoot and analysis.
- Exciter field ground module connects to exciter field terminal of voltage regulator output with ground and provides continuous ground monitoring.

Proposed addition/modification of exciter field ground detector in Turkey Point WTA-300 voltage regulator:

- Exciter field ground module 64F installed at Point Beach is obsolete and Basler (OEM of voltage regulator) no longer manufacture that style module.
- Two vendor options suitable to add in Turkey Point WTA-300 voltage regulator for continuous monitoring of ground on Exciter field winding, voltage regulator power drawer, field breaker and PMG stator winding. Bender module ISO-685-D and Basler relay BE1-64F.
- Digital ground monitor module / relay has two levels of adjustable alarm setting for ground resistance. First level of ground used for alarm. Second level of ground can be used for operator action to initiates control shutdown.

FPSC EXH No. 5
03/18/2024
NEXTera ENERGY
ADMITTED


- Bender module ISO-685D has digital display of ground resistance with two level alarm settings. Bender module also have analog output to use for plant DCS / PI to give ground resistance trend. Bander module ISO-685 is installed in couple of FPL fossil units and going to be installed on all Toshiba steam units.
- Basler (voltage regulator OEM) has BE1-64F ground relay with two adjustable alarm setting. Basler relay do not have digital indication and analog output for ground resistance measurement.
- Power supply for exciter field ground is 120Vac which can be connected to existing generator field ground detector power supply. Alarm contact can be parallel to Generator field ground annunciator. Trip level alarm can be group in to “Voltage Regulator Trouble” for immediate operator action – control shutdown.




Bender ISO 685-D ground detector module

Bender module exciter field connection, power supply and alarm contacts diagram:

FPSC EXH No. 5
03/18/2024
NEXTera ENERGY
ADMITTED



Exciter Field Ground Detector Module



Basler field ground fault relay BE1-64F

FPSC EXH No. 5
03/18/2024
ADMITTED




Figure 1 - BE1-64F Connection Diagram for a Typical Application

Basler BE1-64F connection diagram

FPSC EXH No. 5
03/18/2024
NEXTera ENERGY
ADMITTED

Attachment 4: Exciter PM Description and Status

There are five Westinghouse Frame A201C Exciters shared between PTN and PSL. Four are permanently installed (two at each site) with one spare shared between the sites. However, the spare Exciter base is not interchangeable and as a result only the individual parts (PMG, rotating element, AC Exciter Stator) are considered viable spares. The Brushless Exciters have never been fully refurbished. Maintenance strategy currently consists of the following:

i. Minor Inspection - Each Exciter is inspected and tested in place every 18 months (each refueling outage)
   a. PMG Stator
      i. Insulation resistance
      ii. Resistance measurement
      iii. Visual inspection
   b. AC Exciter Field
      i. Insulation resistance
      ii. Pole balance and impedance calculation of Field Winding
      iii. Resistance measurement
   c. AC Exciter Armature (including Diode Wheels)
      i. Diode Fuse resistance measurements
      ii. Pole balance and impedance calculation of Field Winding
      iii. Insulation resistance
      iv. Resistance measurement
      v. Visual inspection

ii. Major Inspection – At 7.5 years (5 refueling outages) each Exciter is disassembled. Inspections and tests are as with the Minor inspection with the following additions:
   a. PMG Stator
      i. Stator removed from base, inspected
   b. AC Exciter Stator
      i. Disassembled (horizontally split for rotor removal) and inspected
   c. AC Exciter Armature (including Diode Wheels and PMG Pole Support)
      i. Insulation resistance with rotor install -Diode Wheels to Shaft
      ii. Insulation resistance with rotor install - Diode Wheel to Diode Wheel

FPSC EXH No. 5
03/18/2024
ADMITTED

iii. Replacement of complete rotating element with an overhauled spare

iii. Each rotating element (including the spare) is fully refurbished at 7.5 years (Siemens Shop Overhaul). Work occurs between outages.
   a. PMG Magnets requalified or replaced
   b. AC Armature cleaned, inspected, tested
   c. Diode wheels disassembled and overhauled
      i. Fuses
      ii. Heat sinks with diodes installed
      iii. Supports and insulation
      iv. Forward resistance and reverse leakage current check of diodes
      v. Fuse resistance checks
      vi. Charge capacitors, capacitance check
      vii. Replace heat sink insulation
      viii. Test heat sink hardness
   d. NDE
   e. High speed balance

iv. FPL Exciter rewind status
   a. Rotating Elements: Two of the five rotating elements (AC Armatures) have been rewound for cause
      i. Spare: Rewound in 2010. Removed from PTN4 after 2020 PMG failure and currently at Siemens for refurbishment
      ii. PSL1: Not Rewound (~40 years old)
      iii. PSL2: Rewound 2015
      iv. PTN3: Not Rewound (~40 years old)
      v. PTN4: Not Rewound (~40 years old)
   b. Stationary Components: There is no record available of rewind of any of the stationary components (PMG Stator or AC Exciter Stator). However, PTN and PSL exciters and PMGs are current for minor and major maintenance.
   c. Status of PTN4 Exciter prior to 2020 PMG failure:
      i. Major overhaul Spring 2019

FPSC EXH No. 5
03/18/2024
NEXTera ENERGY
ADMITTED

1. Major inspection performed on PMG and AC field
2. Spare rotating element was installed; rotating element was rewound in 2010 and overhauled in 2018 prior to installation

v. The proposed schedule for implementation of the rewind schedule for PMG Stator, AC Exciter Field, and AC Exciter Armature is as follows
   a. SL1-30 April 2021
   b. PTN3-32 Fall 2021
   c. PTN4-33 Spring 2022
   d. SL2-27 Spring 2023

FPSC EXH No. 5
03/18/2024
NEXTera ENERGY
ADMITTED

Attachment 5: FIP TEAM SUPPORT / REFUTE MATRIX

FIP TEAM SUPPORT / REFUTE MATRIX					
Support/Refute Matrix – AR 02361794, Generator Exciter Switchgear Control Cabinet Alarms					
Failure Modes/Cause	**Discussion**	**Supporting Evidence**	**Refuting Evidence**	**Actions**	**Status**
Equipment: Generator Exciter					
1. Generator Ground	A single generator ground alone will not cause a trip given the system is ungrounded. A ground would actuate the 64 and 64X relays which provide interlocks to the ground brush solenoids and cause annunciator E-8/3 to come in.		This does not result in a Generator lockout / Turbine trip. However, the ground detection system is still indicating a ground while not connected to the Rotor. A SAT megger was performed on the Rotor Shaft (106 MΩs) via FAR 5 per WO 40731687-17.	Visually and electrically check the Exciter, Diode Wheel, Slip Rings and Ground Brushes. **FAR 5 performed a megger of the rotor shaft with SAT results (106MOhms)** **FAR 7 was issued to troubleshoot the ground detection circuit. Wires GD4 and GD5 were replaced due to bad insulation. PMT is pending.**	**Refuted**

C3-331

FPSC EXH No. 5
03/18/2024
NEXTera ENERGY
ADMITTED

FIP TEAM SUPPORT / REFUTE MATRIX

Support/Refute Matrix – AR 02361794, Generator Exciter Switchgear Control Cabinet Alarms

Failure Modes/Cause	Discussion	Supporting Evidence	Refuting Evidence	Actions	Status
2. Field Brushes not making good contact with aux slip rings	Does not cause a trip but caused an annunciator to come in (E-8/3).		This does not result in a Generator lockout / Turbine trip.	Perform a visual inspection & continuity check. Perform a TEST from VR Panel and confirm no brush contact fail alarm. **FAR 7 was issued to troubleshoot the ground detection circuit. Wires GD4 and GD5 were replaced due to bad insulation. PMT is pending.**	**Refuted**
3. Ground Detection Instrument Failure	Does not cause a trip but caused an annunciator to come in (E-8/3).		This does not result in a Generator lockout / Turbine trip.	Perform TEST from VR Panel and confirm “no brush contact fail alarm”. Check Ground detector panel lights working with TEST. **FAR 7 was issued to**	**Refuted**

FPSC EXH No. 5
03/18/2024
NEXTera ENERGY
ADMITTED

FIP TEAM SUPPORT / REFUTE MATRIX

Support/Refute Matrix – AR 02361794, Generator Exciter Switchgear Control Cabinet Alarms

Failure Modes/Cause	Discussion	Supporting Evidence	Refuting Evidence	Actions	Status
				troubleshoot the ground detection circuit. Wires GD4 and GD5 were replaced due to bad insulation. PMT is pending.	
4. Over Excitation	An over excitation condition will cause a generator lockout.		Refuted by lack of receipt of Annunciator E-8/2 Generator Field Forcing/Volt Regulating Limit alarm. Voltage Regulator has Over Excitation Protection modules that would prevent the type of damage that was observed. Additionally, FAR 3 performed 0-GME-090.01 section 4.17 which confirmed the Forcing Alarm Module setpoints were set correctly. This module drives the E-8/2 annunciator.	None	**Refuted**

C3-333

FPSC EXH No. 5
03/18/2024
NEXTera ENERGY
ADMITTED

FIP TEAM SUPPORT / REFUTE MATRIX

Support/Refute Matrix – AR 02361794, Generator Exciter Switchgear Control Cabinet Alarms

Failure Modes/Cause	Discussion	Supporting Evidence	Refuting Evidence	Actions	Status
5. Generator Voltage Imbalance	Does not cause a trip but caused an annunciator to come in (E-7/6).		Refuted by lack of receipt of Annunciator E-8/5. The 260/A voltage balance relay which drives the E-8/5 annunciator monitors the generator output voltage, not the PMG and Exciter voltage. Damage was isolated to PMG/Exciter equipment.	None	**Refuted**
6. Loss of sensing module	Does not cause a trip but caused an annunciator to come in (E-7/6).		This does not result in a Generator lockout / Turbine trip. It would explain the transfer of the voltage regulator from AC to DC control. The PMG provides the source voltage which the failing of would result in the loss of sensing.	Perform Procedure 0-GME-090.01 Section 4.6. Check Regulator PT secondary fuses. Check metering PT secondary fuses. **FAR 3 tested the Loss of Sensing Module with SAT results.**	**Refuted**

C3-231
FCR-22-000522

FPSC EXH No. 5
03/18/2024
NEXTera ENERGY
ADMITTED

FIP TEAM SUPPORT / REFUTE MATRIX

Support/Refute Matrix – AR 02361794, Generator Exciter Switchgear Control Cabinet Alarms

Failure Modes/Cause	Discussion	Supporting Evidence	Refuting Evidence	Actions	Status
7. Loss of transducer/s	Does not cause a trip but caused an annunciator to come in (E-7/6).		This does not result in a Generator lockout / Turbine trip. It would explain the transfer of the voltage regulator from AC to DC control. The PMG provides the source voltage which the failing of would result in the loss of XDCRs.	Perform Procedure 0-GME-090.01 Section 4.9. **FAR 3 tested the Loss of Transducer Module with SAT results.**	**Refuted**
8. Fan Failure	Does not cause a trip but caused an annunciator to come in (E-9/3).		This does not result in a Generator lockout / Turbine trip. Temperature was reported to be 68 degrees which would not challenge equipment threshold of 100 degrees F.	None	**Refuted**
9. Enclosure Over Temperature	High temperatures in the VR Enclosure can cause component malfunctions and subsequent generator trip. Annunciator E-9/3 did come in and can be triggered by enclosure		Refuted by Operations investigation. Temperature was reported to be 68 degrees F. Alarm trip point is 100F or greater.	None	**Refuted**

C3-335

FPSC EXH No. 5
03/18/2024
NEXTera ENERGY
ADMITTED

FIP TEAM SUPPORT / REFUTE MATRIX

Support/Refute Matrix – AR 02361794, Generator Exciter Switchgear Control Cabinet Alarms

Failure Modes/Cause	Discussion	Supporting Evidence	Refuting Evidence	Actions	Status
	overtemperature.				
10. Power Amp Blown Fuses	Does not cause a trip but caused an annunciator to come in (E-9/3).		Fuses checked SAT per WO 40731687-01	Check fuse continuity.	**Refuted**
11. Loss of pulse to firing circuits	Does not cause a trip but caused an annunciator to come in (E-9/3).		This does not result in a Generator lockout / Turbine trip.	Perform Procedure 0-GME-090.01 Section 4.10. **FAR 3 tested the Firing Circuit Modules [LRBB] and [LREE] with SAT results.**	**Refuted**

C3-233
FCR-22-000524

FPSC EXH No. 5
03/18/2024
NEXTera ENERGY
ADMITTED

FIP TEAM SUPPORT / REFUTE MATRIX

Support/Refute Matrix – AR 02361794, Generator Exciter Switchgear Control Cabinet Alarms

Failure Modes/Cause	Discussion	Supporting Evidence	Refuting Evidence	Actions	Status
12. Exciter Field Breaker ground fault	A ground fault on Exciter Field Breaker may have caused the sustained high current on T-30 phase. (TAW report concludes cause of failure was fault external to PMG)		Refuted by lack of receipt of Annunciator E-8/5. Breaker was inspected SAT under FAR #3. No signs of damage or overheating.	Rack out and visually inspect field breaker. Perform procedure 0-GME-090.01 Section 4.3 **FAR 3 tested the Generator Field Breaker FB-4 with SAT results.**	**Refuted**
13. Failure of PS1 and PS2	Failure of both power supplies would result in voltage regulator lockout, generator lockout and turbine trip. Causes annunciator to come in (E-9/3).		Power supplies where functionally tested SAT during performance of FAR 3. Visual inspections of the supplies did not reveal any damage. Fuses are intact.	Procedure 0-GME-090.01 Section 4.5 **FAR 3 tested the both 24VDC Power Supplies with SAT results.**	**Refuted**

FPSC EXH No. 5
03/18/2024
NEXTera ENERGY
ADMITTED

FIP TEAM SUPPORT / REFUTE MATRIX

Support/Refute Matrix – AR 02361794, Generator Exciter Switchgear Control Cabinet Alarms

Failure Modes/Cause	Discussion	Supporting Evidence	Refuting Evidence	Actions	Status
14. Failure of PS1 and PS2 fuses	Failure of both power supply fuses would result in voltage regulator lockout. Causes annunciator to come in (E-9/3).		Fuses checked SAT per WO 40731687-01	Check Fuse Continuity	**Refuted**
15. Failure of PS1 and PS2 transformers	Failure of both power supply transformers would result in voltage regulator lockout. Causes annunciator to come in (E-9/3).		Power supplies where functionally tested SAT. Output voltages were as expected.	Procedure 0-GME-090.01 Section 4.5 **FAR 3 tested the both 24VDC Power Supplies with SAT results.**	**Refuted**
16. PMG Failure (loss of voltage to PS1 and PS2)	Failure of PMG would result in loss of voltage to PS1/PS2 and subsequent regulator lockout	Evidence of arc flash event and pressure wave in PMG stator. Melted copper beads and dislodged enclosure gasket were found in vicinity of PMG. Acrid smell at north end of generator. Electrical checks (DLRO and megger readings) per WOs		PMG Visual Inspection. PMG Electrical Checks. **FAR 5 performed electrical testing of the PMG. Megger results of the PMG were 10KOhms.**	**Direct Cause**

FPSC EXH No. 5
03/18/2024
NEXTera ENERGY
ADMITTED

C3-338

FIP TEAM SUPPORT / REFUTE MATRIX

Support/Refute Matrix – AR 02361794, Generator Exciter Switchgear Control Cabinet Alarms

Failure Modes/Cause	Discussion	Supporting Evidence	Refuting Evidence	Actions	Status
		40731687-04 & 40731687-17 were UNSAT as well. Removal of the PMG stator revealed severe winding and core damage. There is also indication of isolated rubbing damage between the magnet and stator which looks like interference with the debris.		**Note that this is default value for the instrument and no voltage was developed with the test indicating a hard ground within the PMG.**	
17. Grid Disturbance	Transient in the grid may have caused regulator lockout.		A review by Operations of the PI data as well as a discussion / review by Transmission (Mike Powers) has determined that there was no grid disturbance during the time of the event.	Review PI data Discuss with Mike Powers	**Refuted**

C3-236
FCR-22-000527

FPSC EXH No. 5
03/18/2024
NEXTera ENERGY
ADMITTED

FIP TEAM SUPPORT / REFUTE MATRIX

Support/Refute Matrix – AR 02361794, Generator Exciter Switchgear Control Cabinet Alarms

Failure Modes/Cause	Discussion	Supporting Evidence	Refuting Evidence	Actions	Status
18. Roof leak causing water intrusion inside voltage regulator housing	Water intrusion into housing / voltage regulator cabinets may have caused lockout. (TAW report concludes cause of failure was fault external to PMG)		Per inspection performed via WO 40731687-01, there was no evidence of water intrusion within any circuits or equipment. There was some superficial water around edges of the room and some small drips.	Visual Inspection **FAR 10 repaired/reapplied protective coating on regulator housing.** **FAR 3 test the Voltage Regulator system with SAT results. No components were found in a failed state.**	**Refuted**
19. PMG Stator Coil to Magnet air gap failure	Loss of PMG air gap would result in a hard rub and severe stator core damage and fault of the PMG stator windings.	Visual inspection of the PMG following removal of the stator revealed some rubbing on the surface of the magnets and stator windings. The rubbing is not in large areas or appear to be indicative of contact between the two, but more likely the rubbing of debris within the PMG following the	Visual inspection of the disassembled PMG found indications of rubbing. The core rubbing indications appear to be secondary collateral damage; a result of copper and core material slag being dragged through the air gap following the event. No significant smearing of stator core laminations was discovered	Visual Inspection **Air gap was validated SAT via FAR 5 per WO 40731687-17.**	**Refuted**

FPSC EXH No. 5
03/18/2024
NEXTera ENERGY
ADMITTED

FIP TEAM SUPPORT / REFUTE MATRIX

Support/Refute Matrix – AR 02361794, Generator Exciter Switchgear Control Cabinet Alarms

Failure Modes/Cause	Discussion	Supporting Evidence	Refuting Evidence	Actions	Status
		failure. The Unit 4 turbine/generator has had a history of vibration issues which could contribute to loss of the air gap	which would be expected with a hard rub due to loss of air gap. Discrete stator slots remained visible following the event. The sinusoidal shaft was found aligned with air gap between the shaft and spider indicating correct alignment.		
20. Winding Insulation Breakdown / Failure	Breakdown of insulation can lead to turn to turn, phase to phase, or phase to ground fault (and subsequent lockout due to loss of PMG voltage to AVR power supply). Besides accelerated ageing, temperature also affects the insulation in other ways. As the winding heats up or cools	Electrical checks (DLRO and megger readings) per WOs 40731687-04 & 40731687-17 were UNSAT. Stator windings manufactured in 1986. Discussions with TAW reinforced the potential of an age-related failure of the stator windings (like thermal degradation). Removal of the stationary coil revealed severe damage to the windings.	No OEM documents specifying rewind interval.	Visual Inspection of winding. Evaluation of winding characteristics following the failure (burn pattern in windings, core, and connections) DLRO and Megger of windings. Discussed winding failure with TAW for concurrence of	**Potential Cause #1**

FIP TEAM SUPPORT / REFUTE MATRIX

Support/Refute Matrix – AR 02361794, Generator Exciter Switchgear Control Cabinet Alarms

Failure Modes/Cause	Discussion	Supporting Evidence	Refuting Evidence	Actions	Status
	down, the copper winding expands and contracts more than the iron core in which it is mounted. The expansion and contraction put mechanical stress on the insulation. Cyclic stress can cause separation of the insulation that develops into permanent cracks and voids Turn to turn shorts in a single phase would cause heating in the affected core slots, eventually degrading to a phase to ground fault. A second fault would create a return path, allowing high fault current flow between fault	There are areas showing phase to phase breakdown and failed insulation. Assessment of failed windings revealed indication of a phase to ground failure based on burn pattern around the circumference of the stator core (discrete coil failure locations). TAW found evidence of multiple connection failures in the T30 phase which would support a sudden short circuit event in the PMG due to multiple internal grounds.		potential failure mode. Send failed PMG stator our for additional analysis and forensics testing.	

FPSC EXH No. 5
03/18/2024
NEXTera ENERGY
ADMITTED

FIP TEAM SUPPORT / REFUTE MATRIX

Support/Refute Matrix – AR 02361794, Generator Exciter Switchgear Control Cabinet Alarms

Failure Modes/Cause	Discussion	Supporting Evidence	Refuting Evidence	Actions	Status
	locations.				
21. Foreign Material	FM may have caused equipment damage or electrical fault. Debris entering the PMG during operation could cause impact damage to stator insulation resulting in the same failure modes described in item 20. Particles such as dirt, dust, soot, etc., create problems in several ways. One way is that small particles can abrade the insulation. Particles that get	Visual inspection of the PMG following disassembly identified heavy copper deposition throughout due to arcing and extensive core damage. Some Shim stock and other material was found loose within the exciter housing and PMG area.	No Foreign Material was identified in the failure debris during initial inspections of the failed PMG stator.	Further inspection with forensic disassembly of the stator windings to look for evidence FM.	**Potential Cause #2**

FPSC EXH No. 5
03/18/2024
NEXTera ENERGY
ADMITTED

FIP TEAM SUPPORT / REFUTE MATRIX

Support/Refute Matrix – AR 02361794, Generator Exciter Switchgear Control Cabinet Alarms

Failure Modes/Cause	Discussion	Supporting Evidence	Refuting Evidence	Actions	Status
	between the winding and the core or supports, act like sandpaper grit wearing away more insulation through vibration. Another mode is that the particles attract moisture and form a conductive path.				
22. Voltage Regulator Field Cable ground fault	A ground fault on the voltage regulator field cables may have cause the sustained high current on T-30 phase. (TAW report concludes cause of failure was fault external to PMG)		Megger of field cable from voltage regulator to PMG, with cable isolated from PMG, resulted in SAT readings (in the G Ohm range). This check was performed via FAR #5 per WO 40731687-17.	CHAR and Megger field cables once isolated from the PMG Stator Coil	**Open**
23. Water Intrusion inside PMG compartment	Moisture within the PMG can compromise insulation withstand leading to failure. An excessive amount of moisture can create	Water was located within the PMG and AC exciter compartments following the event. Volume was indeterminate but PMG and pedestal bolt holes in the frame contained	No direct evidence of water within the PMG itself was found with disassembly. However excessive heating that occurred with the winding failure would have removed any forensic	Perform Visual inspection on PMG once it has been removed. **FAR 9 was issued to inspect/repair the**	**Potential Contributing Cause #1**

FPSC EXH No. 5
03/18/2024
NEXTera ENERGY
ADMITTED

FIP TEAM SUPPORT / REFUTE MATRIX

Support/Refute Matrix – AR 02361794, Generator Exciter Switchgear Control Cabinet Alarms

Failure Modes/Cause	Discussion	Supporting Evidence	Refuting Evidence	Actions	Status
	grounds during operation. For example, a water leak can thoroughly wet a section of the winding, weakening the insulation, and developing a fault.	standing water confirming some amount of intrusion. The PMG compartment is a highly turbulent environment due to forced air cooling airflow from the pole support fan. This could allow distribution of moisture over the PMG during operation in heavy rain events contributing to degradation of insulation quality.	evidence.	**seals associated with the Exciter housing.** **FAR 10 was issued to inspect/repair the VR Housing.** **FAR 16 includes steps to inspect/repair conduit seals as necessary.**	
24. PMG Internal Component Failure (Other than Winding)	Failure of PMG would result in loss of voltage to PS1/PS2 and subsequently cause a voltage regulator lockout PMG is a simple design, with limited components. Component failures	The inspection of the removed stator does show core damage along with insulation damage.	Internals of the PMG include only a stator core. Based on disassembled inspection, core loss appears to be collateral damage due to winding failure in the core slots. Damage appears limited to the slot areas with no significant evidence of	Perform forensics on PMG once it has been removed.	**Refuted**

FPSC EXH No. 5
03/18/2024
NEXTera ENERGY
ADMITTED

FIP TEAM SUPPORT / REFUTE MATRIX

Support/Refute Matrix – AR 02361794, Generator Exciter Switchgear Control Cabinet Alarms

Failure Modes/Cause	Discussion	Supporting Evidence	Refuting Evidence	Actions	Status
	would originate in the stator, stator core, or rotating pole support (magnets). Abrasion of the insulating material results from mechanical wear either from a moving object in contact with the insulation, or from the insulation itself moving against an object. As mentioned, thermal expansion and contraction of the winding causes portions of the winding to move; thus creating the possibility of the insulation wearing against the core and winding supports. Small localized damage		lamination fusing or heating in visible portions of the back iron. The failure characteristics indicate a short circuit / high current event rather than localized hotspots in the core.		

FPSC EXH No. 5
03/18/2024
NEXTera ENERGY
ADMITTED

FIP TEAM SUPPORT / REFUTE MATRIX

Support/Refute Matrix – AR 02361794, Generator Exciter Switchgear Control Cabinet Alarms

Failure Modes/Cause	Discussion	Supporting Evidence	Refuting Evidence	Actions	Status
	to the insulation allows interturn or ground leakage current to flow. The leakage current further heats the damaged insulation, causing more damage; thus, causing more leakage current, more heat, and eventually failure.				
25. Lightning Strike	Lightning Strike can cause damage to electrical equipment and subsequently cause a voltage regulator lockout (TAW report concludes cause of failure was fault external to PMG)	Through discussion with a former electrical SME at the station it was identified that there have been multiple motor failures in the past which were likely caused by indirect lightning strikes. All electrical equipment is tied together with different levels of resistance through a station ground, and equipment transients have been seen on	No evidence of lighting strike. It is unlikely that a lightning strike would only affect the PMG and no other more susceptible equipment Inspection did not reveal any lighting strike damage at or near the exciter housing or the voltage regulator housing. No similar damage or evidence of degradation	Perform visual inspection on PMG once it has been removed.	**Refuted**

FPSC EXH No. 5
03/18/2024
NEXTera ENERGY
ADMITTED

FIP TEAM SUPPORT / REFUTE MATRIX

Support/Refute Matrix – AR 02361794, Generator Exciter Switchgear Control Cabinet Alarms

Failure Modes/Cause	Discussion	Supporting Evidence	Refuting Evidence	Actions	Status
		equipment due to lightning events.	identified in the AC exciter stator which would result with a high voltage discharge through the stationary exciter assembly The U4 Exciter PMG stator is an ungrounded wye connected design. As such there is no direct path through the grounding grid to the stator neutral that would facilitate a lightning related failure.		
26. Overcurrent from Voltage Regulator	Over-excitation, excessive field current could damage the PMG field windings and potentially breakdown the insulation leading to a flashover event within the component. (TAW report concludes cause of failure was fault external to PMG)		No indication of breaker overcurrent trip. Assumes back feed from AVR power supply to PMG. Design is PMG powers the AVR PS AVR functionally tested SAT. No fuses blown in power supply circuit that would indicate excessive current	FAR 3 was issued to functionally check the Power Drawer and Field Breaker.	**Refuted**

FPSC EXH No. 5
03/18/2024
NEXTera ENERGY
ADMITTED

FIP TEAM SUPPORT / REFUTE MATRIX

Support/Refute Matrix – AR 02361794, Generator Exciter Switchgear Control Cabinet Alarms

Failure Modes/Cause	Discussion	Supporting Evidence	Refuting Evidence	Actions	Status
27. PMG Stator Core Failure	Core lamination insulation degradation will result in inter-laminar shorts in the core. This produces hot spots in the core iron which degrade the insulation of windings installed in the core slots leading to insulation failure over time and a stator failure. Induced current, if not minimized, will generate heat in the iron, weakening the core and damaging the windings. Damage to the lamination insulation permits excessive current that can overheat both the laminations and windings.	Visual inspection of PMG stator windings found heavy copper and core iron deposition throughout due to arcing and extensive core damage. Inspection of failure debris identified a significant number of individual core lamination tooth tops liberated from the core assembly. These lamination teeth showed no evidence of mechanical damage on the tooth surface due to an interference rub. All of these teeth showed evidence of melting approximately ¼" down their length which would be below the stator wedge. This indicates that heating occurred down in the core slot rather than	Based on disassembled inspection, core loss appears to be collateral damage due to winding failure in the core slots. Damage appears limited to the slot areas with no significant evidence of lamination fusing or heating in visible portions of the back iron. The failure characteristics indicate a short circuit / high current event rather than localized hotspots in the core.	Perform visual inspection during disassembly.	**Refuted**

FPSC EXH No. 5
03/18/2024
NEXTera ENERGY
ADMITTED

FIP TEAM SUPPORT / REFUTE MATRIX

Support/Refute Matrix – AR 02361794, Generator Exciter Switchgear Control Cabinet Alarms

Failure Modes/Cause	Discussion	Supporting Evidence	Refuting Evidence	Actions	Status
		the surface as a result of localized core lamination heating.			
28. Vibration	The vibrations of the unit 4 generator have been elevated and a concern since startup from the previous outage. Several forces act on the winding conductors. These include vibration from the exciter and generator, and the magnetic force. In rotating exciters and transformers, the magnetic force on the AC winding is at twice	Following the Unit 4 Exciter Rotor replacement during PT4-31, elevated vibrations have been recorded on bearing #9. The highest vibration measured following rotor replacement was 8.31mils during initial startup. Vibrations settled to 5-7mils during base load operation and have remained in this range until the Generator Lockout event on 7/5/2020.		1. Review of vibration profile from the last outage. Along with as left testing & measurements 2. Review of event profile to identify magnitude and timing of the vibration changes as the related to the event. During Startup, Operations monitors vibrations of the Generator	**Potential Contributing Cause #2**

FPSC EXH No. 5
03/18/2024
NEXTera ENERGY
ADMITTED

FIP TEAM SUPPORT / REFUTE MATRIX

Support/Refute Matrix – AR 02361794, Generator Exciter Switchgear Control Cabinet Alarms

Failure Modes/Cause	Discussion	Supporting Evidence	Refuting Evidence	Actions	Status
	the synchronous speed. Any looseness in the wedges or winding supports will allow the winding to vibrate at the location of the looseness. This vibration not only creates cyclic stresses in the insulation, but also can allow rubbing and abrasion of the insulation against the core iron or the support.			using System1. Additionally, Siemens will have vibration Engineer monitoring the Generator vibrations remotely.	
29. Assembly Error/Damage	Mechanical impact on the laminations is the most frequent cause of damage. Work performed on exciters and motors, particularly during removal and installation of the rotor, can score or crush the ends of the	There was considerable difficulty in disassembling the exciter coupling. Several bolts could not be removed and had to be cut to enable exciter removal. It is plausible that some galling of these bolts occurred during the 14-month operating cycle due to the as-left	TAW inspection and report did not find any indication of winding damage due to direct contact between the magnets and the stator. The report identifies a potential cause involving short circuit currents damaging the stator windings and the physical damage between the magnets and stator	TAW Inspection	**Refuted**

FPSC EXH No. 5
03/18/2024
NEXTera ENERGY
ADMITTED

FIP TEAM SUPPORT / REFUTE MATRIX

Support/Refute Matrix – AR 02361794, Generator Exciter Switchgear Control Cabinet Alarms

Failure Modes/Cause	Discussion	Supporting Evidence	Refuting Evidence	Actions	Status
	laminations together if not carefully done. Abrasive particles and other foreign material striking the ends of the laminations can wear off the insulating film and form a conductive path across laminations.	alignment. Mechanical impact on winding during assembly can damage	coming from debris drag following the failure.		
30. PMG Stator Winding jumper cable ground fault	A ground fault on PMG Stator Winding jumper cables may have cause the sustained high current on T-30 phase. (TAW report concludes cause of failure was fault external to PMG)	Oxidation on stator windings would have degraded the insulation and air gap needed to maintain the integrity of the PMG circuit. The generator lockout which opens the field circuit breaker would have challenged the insulation which was possibly wetted due to the storm at the time of the event.	Megger of field cable (including jumper cable) from voltage regulator to PMG, with cable isolated from PMG Stator Windings, resulted in SAT readings (in the G Ohm range). This check was performed via FAR #5 per WO 40731687-17.	Megger jumper cables once isolated from the PMG Stator Coil and field cable.	**Open**

FPSC EXH No. 5
03/18/2024
NEXTera ENERGY
ADMITTED

FIP TEAM SUPPORT / REFUTE MATRIX

Support/Refute Matrix – AR 02361794, Generator Exciter Switchgear Control Cabinet Alarms

Failure Modes/Cause	Discussion	Supporting Evidence	Refuting Evidence	Actions	Status
31. Voltage Regulator local voltmeter ground fault	A ground fault on the voltage regulator voltmeter may have caused the sustained high current on T-30 phase. The voltmeter is connected to T-10 and T-30 phases (TAW report concludes cause of failure was fault external to PMG)		Voltmeter is protected by 6A fuses. It is expected that the fuses would blow on a fault condition. If fault was below 6A, it would not have resulted in the damage observed on the PMG winding connections.	Inspect local voltmeter and voltmeter fuses	**Refuted**
32. Governor Control Panel potential transformer ground fault.	A ground fault on the Governor Control Panel PTs may have caused the sustained high current on T-30 phase. The PTs are connected to all three phases. (TAW report concludes cause of failure was fault external to PMG)		PTs are protected by 6A fuses. It is expected that the fuses would blow on a fault condition. If fault was below 6A, it would not have resulted in the damage observed on the PMG winding connections.	Inspect Governor Control Panel PTs and PT fuses.	**Refuted**

FPSC EXH No. 5
03/18/2024
NEXTera ENERGY
ADMITTED

FIP TEAM SUPPORT / REFUTE MATRIX

Support/Refute Matrix – AR 02361794, Generator Exciter Switchgear Control Cabinet Alarms

Failure Modes/Cause	Discussion	Supporting Evidence	Refuting Evidence	Actions	Status
33. Ground Fault on 24VDC Power Supply Transformers	A ground fault on the 24VDC Power Supply Transformers may have caused the sustained high current on T-30 phase. (TAW report concludes cause of failure was fault external to PMG)		Power Supply Transformers are protected by 6A fuses. Fuses were found intact. FAR #3 tested the both 24VDC Power Supplies with SAT results with no work done on the transformers.	Visual inspection of transformers and fuses. Procedure 0-GME-090.01 Section 4.5.	**Refuted**
34. Ground Fault on Power Amplifier drawers	A ground fault on the 24VDC Power Supply Transformers may have caused the sustained high current on T-30 phase. (TAW report concludes cause of failure was fault external to PMG)		Power Amplifiers are protected by voltraps and 800A fuses. A sustained overcurrent condition from a ground fault will damage voltraps and blow fuses. Voltraps were powered up during testing under FAR #3 and no issues were identified. 800A fuses were intact. Additionally, power drawers were tested SAT under FAR #3.	Visual inspection of voltraps and 800A fuses	**Refuted**

FPSC EXH No. 5
03/18/2024
NEXTera ENERGY
ADMITTED

C3-354

FIP TEAM SUPPORT / REFUTE MATRIX

Support/Refute Matrix – AR 02361794, Generator Exciter Switchgear Control Cabinet Alarms

Failure Modes/Cause	Discussion	Supporting Evidence	Refuting Evidence	Actions	Status
35. Ground fault on PMG Stator windings to PMG housing	Ground fault on PMG Stator windings can cause sustained overcurrent condition. (TAW report concludes cause of failure was fault external to PMG)	Oxidation on stator windings would have degraded the insulation and air gap needed to maintain the integrity of the PMG circuit. That level of oxidation looks to have been caused by overheating due to a single-phase ground on the PMG, AVR Power Drawer, Field Circuit Breaker, exciter stator, and interconnecting wires. There isn't a monitoring system at PTN that would give indication of this happening.	No signs of arcing or overheating was found on the Exciter housing that would be indicative of a high current ground.	Inspect PMG housing for signs of arcing or overheating. Perform megger testing of PMG Stator Windings. Perform forensics of PMG.	**Refuted**

C3-252
FCR-22-000543

FPSC EXH No. 5
03/18/2024
NEXTera ENERGY
ADMITTED

Attachment 6: ROOT CAUSE TEAM'S SUPPORT / REFUTE MATRIX

RCE TEAM SUPPORT / REFUTE MATRIX					
PROBLEM STATEMENT:	On July 5th, 2020 at approximately 2107, during a heavy rainstorm Unit 4 Tripped Automatically from 100% power due to a Generator Lockout.				
Failure Modes/Cause	**Discussion**	**Supporting Evidence**	**Refuting Evidence**	**Actions**	**Status**
EQUIPMENT					
1. Generator Ground	A single generator ground alone will not cause a trip given the system is ungrounded. A ground would actuate the 64 and 64X relays which provide interlocks to the ground brush solenoids and cause annunciator E-8/3 to come in.		This does not result in a Generator lockout / Turbine trip. However, the ground detection system is still indicating a ground while not connected to the Rotor. A SAT megger was performed on the Rotor Shaft (106 MΩs) via FAR 5 per WO 40731687-17.	Visually and electrically check the Exciter, Diode Wheel, Slip Rings and Ground Brushes. **FAR 5 performed a megger of the rotor shaft with SAT results (106MOhms)** **FAR 7 was issued to troubleshoot the ground detection circuit. Wires GD4 and GD5 were replaced due to bad insulation. PMT is pending.**	**Refuted**

FPSC EXH No. 5
03/18/2024
NEXTera ENERGY
ADMITTED

RCE TEAM SUPPORT / REFUTE MATRIX					
PROBLEM STATEMENT:	On July 5th, 2020 at approximately 2107, during a heavy rainstorm Unit 4 Tripped Automatically from 100% power due to a Generator Lockout.				
Failure Modes/Cause	**Discussion**	**Supporting Evidence**	**Refuting Evidence**	**Actions**	**Status**
2. Ground Detection System Field Brushes not making good contact with aux slip rings	Does not cause a trip but caused an annunciator to come in (E-8/3).		This does not result in a Generator lockout / Turbine trip.	Perform a visual inspection & continuity check. Perform a TEST from VR Panel and confirm no brush contact fail alarm. **FAR 7 was issued to troubleshoot the ground detection circuit. Wires GD4 and GD5 were replaced due to bad insulation. PMT is pending.**	**Refuted**
3. Ground Detection Instrument Failure	Does not cause a trip but caused an annunciator to come in (E-8/3).		This does not result in a Generator lockout / Turbine trip.	Perform TEST from VR Panel and confirm “no brush contact fail alarm”. Check Ground detector panel lights working with	**Refuted**

FPSC EXH No. 5
03/18/2024
NEXTera ENERGY
ADMITTED

RCE TEAM SUPPORT / REFUTE MATRIX					
PROBLEM STATEMENT:	On July 5th, 2020 at approximately 2107, during a heavy rainstorm Unit 4 Tripped Automatically from 100% power due to a Generator Lockout.				
Failure Modes/Cause	**Discussion**	**Supporting Evidence**	**Refuting Evidence**	**Actions**	**Status**
				TEST. **FAR 7 was issued to troubleshoot the ground detection circuit. Wires GD4 and GD5 were replaced due to bad insulation. PMT is pending.**	
4. Over Excitation	An over excitation condition will cause a generator lockout.		Refuted by lack of receipt of Annunciator E-8/2 Generator Field Forcing/Volt Regulating Limit alarm. Voltage Regulator has Over Excitation Protection modules that would prevent the type of damage that was observed. Additionally, FAR 3 performed 0-GME-090.01 section 4.17 which confirmed the Forcing Alarm Module setpoints were set correctly. This module	None	**Refuted**

FPSC EXH No. 5
03/18/2024
NEXTera ENERGY
ADMITTED

RCE TEAM SUPPORT / REFUTE MATRIX					
PROBLEM STATEMENT:	On July 5th, 2020 at approximately 2107, during a heavy rainstorm Unit 4 Tripped Automatically from 100% power due to a Generator Lockout.				
Failure Modes/Cause	**Discussion**	**Supporting Evidence**	**Refuting Evidence**	**Actions**	**Status**
			drives the E-8/2 annunciator.		
5. Generator Voltage Imbalance	Does not cause a trip but caused an annunciator to come in (E-7/6).		Refuted by lack of receipt of Annunciator E-8/5. The 260/A voltage balance relay which drives the E-8/5 annunciator monitors the generator output voltage, not the PMG and Exciter voltage. Damage was isolated to PMG/Exciter equipment.	None	**Refuted**

FPSC EXH No. 5
03/18/2024
NEXTera ENERGY
ADMITTED

RCE TEAM SUPPORT / REFUTE MATRIX					
PROBLEM STATEMENT:	On July 5th, 2020 at approximately 2107, during a heavy rainstorm Unit 4 Tripped Automatically from 100% power due to a Generator Lockout.				
Failure Modes/Cause	**Discussion**	**Supporting Evidence**	**Refuting Evidence**	**Actions**	**Status**
6. Loss of Voltage Regulator Sensing Module	Does not cause a trip but caused an annunciator to come in (E-7/6).		This does not result in a Generator lockout / Turbine trip. It would explain the transfer of the voltage regulator from AC to DC control. The PMG provides the source voltage which the failing of would result in the loss of sensing.	Perform Procedure 0-GME-090.01 Section 4.6. Check Regulator PT secondary fuses. Check metering PT secondary fuses. **FAR 3 tested the Loss of Sensing Module with SAT results.**	**Refuted**
7. Loss of Voltage Regulator Transducer/s	Does not cause a trip but caused an annunciator to come in (E-7/6).		This does not result in a Generator lockout / Turbine trip. It would explain the transfer of the voltage regulator from AC to DC control. The PMG provides the source voltage which the failing of would result in the loss of XDCRs.	Perform Procedure 0-GME-090.01 Section 4.9. **FAR 3 tested the Loss of Transducer Module with SAT results.**	**Refuted**

FPSC EXH No. 5
03/18/2024
NEXTera ENERGY
ADMITTED

RCE TEAM SUPPORT / REFUTE MATRIX					
PROBLEM STATEMENT:	On July 5th, 2020 at approximately 2107, during a heavy rainstorm Unit 4 Tripped Automatically from 100% power due to a Generator Lockout.				
Failure Modes/Cause	**Discussion**	**Supporting Evidence**	**Refuting Evidence**	**Actions**	**Status**
8. Voltage Regulator Enclosure Fan Failure	Does not cause a trip but caused an annunciator to come in (E-9/3).		This does not result in a Generator lockout / Turbine trip. Temperature was reported to be 68 degrees which would not challenge equipment threshold of 100 degrees F.	None	**Refuted**
9. Voltage Regulator Enclosure Over Temperature	High temperatures in the VR Enclosure can cause component malfunctions and subsequent generator trip. Annunciator E-9/3 did come in and can be triggered by enclosure overtemperature.		Refuted by Operations investigation. Temperature was reported to be 68 degrees F. Alarm trip point is 100F or greater.	None	**Refuted**

C3-301

FPSC EXH No. 5
03/18/2024
NEXTera ENERGY
ADMITTED

RCE TEAM SUPPORT / REFUTE MATRIX					
PROBLEM STATEMENT:	On July 5th, 2020 at approximately 2107, during a heavy rainstorm Unit 4 Tripped Automatically from 100% power due to a Generator Lockout.				
Failure Modes/Cause	**Discussion**	**Supporting Evidence**	**Refuting Evidence**	**Actions**	**Status**
10. Voltage Regulator Power Amp Blown Fuses	Does not cause a trip but caused an annunciator to come in (E-9/3).		Fuses checked SAT per WO 40731687-01	Check fuse continuity.	**Refuted**
11. Loss of Voltage Regulator pulse to firing circuits	Does not cause a trip but caused an annunciator to come in (E-9/3).		This does not result in a Generator lockout / Turbine trip.	Perform Procedure 0-GME-090.01 Section 4.10. **FAR 3 tested the Firing Circuit Modules [LRBB] and [LREE] with SAT results.**	**Refuted**

C3-259
FCR-22-000550

FPSC EXH No. 5
03/18/2024
NEXTera ENERGY
ADMITTED

RCE TEAM SUPPORT / REFUTE MATRIX					
PROBLEM STATEMENT:	On July 5th, 2020 at approximately 2107, during a heavy rainstorm Unit 4 Tripped Automatically from 100% power due to a Generator Lockout.				
Failure Modes/Cause	**Discussion**	**Supporting Evidence**	**Refuting Evidence**	**Actions**	**Status**
12. Exciter Field Breaker ground fault	A ground fault on Exciter Field Breaker may have caused the sustained high current on T-30 phase. (TAW report concludes cause of failure was fault external to PMG)		Refuted by lack of receipt of Annunciator E-8/5. Breaker was inspected SAT under FAR #3. No signs of damage or overheating.	Rack out and visually inspect field breaker. Perform procedure 0-GME-090.01 Section 4.3 **FAR 3 tested the Generator Field Breaker FB-4 with SAT results.**	**Refuted**
13. Failure of power supplies PS1 and PS2	Failure of both power supplies would result in voltage regulator lockout, generator lockout and turbine trip. Causes annunciator to come in (E-9/3).		Power supplies where functionally tested SAT during performance of FAR 3. Visual inspections of the supplies did not reveal any damage. Fuses are intact.	Procedure 0-GME-090.01 Section 4.5 **FAR 3 tested the both 24VDC Power Supplies with SAT results.**	**Refuted**

FPSC EXH No. 5
03/18/2024
NEXTera ENERGY
ADMITTED

RCE TEAM SUPPORT / REFUTE MATRIX					
PROBLEM STATEMENT:	On July 5th, 2020 at approximately 2107, during a heavy rainstorm Unit 4 Tripped Automatically from 100% power due to a Generator Lockout.				
Failure Modes/Cause	**Discussion**	**Supporting Evidence**	**Refuting Evidence**	**Actions**	**Status**
14. Failure of power supply PS1 and PS2 fuses	Failure of both power supply fuses would result in voltage regulator lockout. Causes annunciator to come in (E-9/3).		Fuses checked SAT per WO 40731687-01	Check Fuse Continuity	**Refuted**
15. Failure of power supply PS1 and PS2 transformers	Failure of both power supply transformers would result in voltage regulator lockout. Causes annunciator to come in (E-9/3).		Power supplies where functionally tested SAT. Output voltages were as expected.	Procedure 0-GME-090.01 Section 4.5 **FAR 3 tested the both 24VDC Power Supplies with SAT results.**	**Refuted**
16. PMG Failure (loss of voltage to PS1 and PS2)	Failure of PMG would result in loss of voltage to PS1/PS2 and subsequent regulator lockout	Evidence of arc flash event and pressure wave in PMG stator. Melted copper beads and dislodged enclosure gasket were found in vicinity of PMG. Acrid smell at north end of generator. Electrical		PMG Visual Inspection. PMG Electrical Checks. **FAR 5 performed electrical testing of the PMG. Megger**	**Direct Cause**

FPSC EXH No. 5
03/18/2024
NEXTera ENERGY
ADMITTED

RCE TEAM SUPPORT / REFUTE MATRIX					
PROBLEM STATEMENT:	On July 5th, 2020 at approximately 2107, during a heavy rainstorm Unit 4 Tripped Automatically from 100% power due to a Generator Lockout.				
Failure Modes/Cause	**Discussion**	**Supporting Evidence**	**Refuting Evidence**	**Actions**	**Status**
		checks (DLRO and megger readings) per WOs 40731687-04 & 40731687-17 were UNSAT as well. Removal of the PMG stator revealed severe winding and core damage. There is also indication of isolated rubbing damage between the magnet and stator which looks like interference with the debris.		**results of the PMG were 10KOhms. Note that this is default value for the instrument and no voltage was developed with the test indicating a hard ground within the PMG.**	
17. Grid Disturbance	Transient in the grid may have caused regulator lockout.		A review by Operations of the PI data as well as a discussion / review by Transmission (Mike Powers) has determined that there was no grid disturbance during the time of the event.	Review PI data Discuss with Mike Powers	**Refuted**

FPSC EXH No. 5
03/18/2024
NEXTera ENERGY
ADMITTED

RCE TEAM SUPPORT / REFUTE MATRIX					
PROBLEM STATEMENT:	On July 5th, 2020 at approximately 2107, during a heavy rainstorm Unit 4 Tripped Automatically from 100% power due to a Generator Lockout.				
Failure Modes/Cause	**Discussion**	**Supporting Evidence**	**Refuting Evidence**	**Actions**	**Status**
18. Roof leak causing water intrusion inside Voltage Regulator housing	Water intrusion into housing / voltage regulator cabinets may have caused lockout. (TAW report concludes cause of failure was fault external to PMG)		Per inspection performed via WO 40731687-01, there was no evidence of water intrusion within any circuits or equipment. There was some superficial water around edges of the room and some small drips.	Visual Inspection **FAR 10 repaired/reapplied protective coating on regulator housing.** **FAR 3 test the Voltage Regulator system with SAT results. No components were found in a failed state.**	**Refuted**
19. PMG Stator Coil to Magnet air gap failure	Loss of PMG air gap would result in a hard rub and severe stator core damage and fault of the PMG stator windings.	Visual inspection of the PMG following removal of the stator revealed some rubbing on the surface of the magnets and stator windings. The rubbing is not in large areas or appear to be indicative of contact between the two, but more likely the	Visual inspection of the disassembled PMG found indications of rubbing. The core rubbing indications appear to be secondary collateral damage; a result of copper and core material slag being dragged through the air gap following the event. No significant	Visual Inspection **Air gap was validated SAT via FAR 5 per WO 40731687-17.**	**Refuted**

FPSC EXH No. 5
03/18/2024
NEXTera ENERGY
ADMITTED

RCE TEAM SUPPORT / REFUTE MATRIX					
PROBLEM STATEMENT:	On July 5th, 2020 at approximately 2107, during a heavy rainstorm Unit 4 Tripped Automatically from 100% power due to a Generator Lockout.				
Failure Modes/Cause	**Discussion**	**Supporting Evidence**	**Refuting Evidence**	**Actions**	**Status**
		rubbing of debris within the PMG following the failure. The Unit 4 turbine/generator has had a history of vibration issues which could contribute to loss of the air gap	smearing of stator core laminations was discovered which would be expected with a hard rub due to loss of air gap. Discrete stator slots remained visible following the event. The sinusoidal shaft was found aligned with air gap between the shaft and spider indicating correct alignment.		
20. Winding Insulation Breakdown / Failure	Breakdown of insulation can lead to turn to turn, phase to phase, or phase to ground fault (and subsequent lockout due to loss of PMG voltage to AVR power supply). Besides accelerated ageing, temperature also affects the	Electrical checks (DLRO and megger readings) per WOs 40731687-04 & 40731687-17 were UNSAT. Stator windings manufactured in 1986. Discussions with TAW reinforced the potential of an age-related failure of the stator windings (like	No OEM documents specifying rewind interval.	Visual Inspection of winding. Evaluation of winding characteristics following the failure (burn pattern in windings, core, and connections) DLRO and Megger of windings.	**Significant Contributing Cause #1**

FPSC EXH No. 5
03/18/2024
NEXTera ENERGY
ADMITTED

RCE TEAM SUPPORT / REFUTE MATRIX					
PROBLEM STATEMENT:	On July 5th, 2020 at approximately 2107, during a heavy rainstorm Unit 4 Tripped Automatically from 100% power due to a Generator Lockout.				
Failure Modes/Cause	**Discussion**	**Supporting Evidence**	**Refuting Evidence**	**Actions**	**Status**
	insulation in other ways. As the winding heats up or cools down, the copper winding expands and contracts more than the iron core in which it is mounted. The expansion and contraction put mechanical stress on the insulation. Cyclic stress can cause separation of the insulation that develops into permanent cracks and voids Turn to turn shorts in a single phase would cause heating in the affected core slots, eventually degrading to a phase to ground fault. A second fault	thermal degradation). Removal of the stationary coil revealed severe damage to the windings. There are areas showing phase to phase breakdown and failed insulation. Assessment of failed windings revealed indication of a phase to ground failure based on burn pattern around the circumference of the stator core (discrete coil failure locations). TAW found evidence of multiple connection failures in the T30 phase which would support a sudden short circuit event in the PMG due to multiple internal grounds. EPRI Report discusses age		Discussed winding failure with TAW for concurrence of potential failure mode. Review any additional findings from Siemens during rewind activity.	

FPSC EXH No. 5
03/18/2024
NEXTera ENERGY
ADMITTED

RCE TEAM SUPPORT / REFUTE MATRIX					
PROBLEM STATEMENT:	On July 5th, 2020 at approximately 2107, during a heavy rainstorm Unit 4 Tripped Automatically from 100% power due to a Generator Lockout.				
Failure Modes/Cause	**Discussion**	**Supporting Evidence**	**Refuting Evidence**	**Actions**	**Status**
	would create a return path, allowing high fault current flow between fault locations.	as one of several factors that contribute to winding insulation degradation. Although age alone does not lead to failure, it does make the insulation more susceptible to other failure factors.			
21. Foreign Material	FM may have caused equipment damage or electrical fault. Debris entering the PMG during operation could cause impact damage to stator insulation resulting in the same failure modes described in item 20. Particles such as dirt, dust, soot, etc., create problems in several ways. One way is that	Visual inspection of the PMG following disassembly identified heavy copper deposition throughout due to arcing and extensive core damage. Some Shim stock and other material was found loose within the exciter housing.	No externally originating Foreign Material (FM) was identified in the failure debris within the PMG pole support or the PMG stator following disassembly with either the FPL inspection on site, or the disassembled inspection at TAW. The disassembled inspection specifically looked for any debris other than native materials. Debris was limited to copper and iron slag from the PMG stator failure, along with some	Further inspection with forensic disassembly of the stator windings to look for evidence FM.	**Refuted**

FPSC EXH No. 5
03/18/2024
NEXTera ENERGY
ADMITTED

RCE TEAM SUPPORT / REFUTE MATRIX					
PROBLEM STATEMENT:	On July 5th, 2020 at approximately 2107, during a heavy rainstorm Unit 4 Tripped Automatically from 100% power due to a Generator Lockout.				
Failure Modes/Cause	**Discussion**	**Supporting Evidence**	**Refuting Evidence**	**Actions**	**Status**
	small particles can abrade the insulation. Particles that get between the winding and the core or supports, act like sandpaper grit wearing away more insulation through vibration. Another mode is that the particles attract moisture and form a conductive path.		smaller pieces of burned fabric / strand like material, later determined to be stator coil insulation remnants. Several stator core lamination tooth tops were also mixed in the debris. These lamination teeth illustrated melting approx. 3/8" down their length with the tooth tips fully intact. This indicated heating in the core slot rather than liberation by hard surface contact due to a rub or FME in the stator to magnet air gap. Loose shim-stock had been found within the AC Exciter portion of the exciter housing, but none within the PMG section of the housing which is intended to be isolated by design. Following the failure event,		

FPSC EXH No. 5
03/18/2024
NEXTera ENERGY
ADMITTED

RCE TEAM SUPPORT / REFUTE MATRIX					
PROBLEM STATEMENT:	On July 5th, 2020 at approximately 2107, during a heavy rainstorm Unit 4 Tripped Automatically from 100% power due to a Generator Lockout.				
Failure Modes/Cause	**Discussion**	**Supporting Evidence**	**Refuting Evidence**	**Actions**	**Status**
			a small portion of the rubber seal between the two compartments was found compromised (~8-inch length sucked inward toward the PMG compartment) leaving a potential path for FM ingress from one compartment to another. While this gap left potential for FM ingress, based on the size of the access path, location and type of FM (shim stock) found in the AC Exciter compartment, and lack of findings in the PMG or PMG compartment, the likelihood of FM as an initiator to the failure event is deemed low and has been refuted. It should also be noted that there was no evidence of an arc flash event (i.e. burn marks,		

FPSC EXH No. 5
03/18/2024
NEXTera ENERGY
ADMITTED

RCE TEAM SUPPORT / REFUTE MATRIX					
PROBLEM STATEMENT:	On July 5th, 2020 at approximately 2107, during a heavy rainstorm Unit 4 Tripped Automatically from 100% power due to a Generator Lockout.				
Failure Modes/Cause	**Discussion**	**Supporting Evidence**	**Refuting Evidence**	**Actions**	**Status**
			melted metal) on the loose shim stock that was recovered, further refuting the shim as a likely initiator to the event.		
22. Voltage Regulator Field Cable ground fault	A ground fault on the voltage regulator field cables may have cause the sustained high current on T-30 phase. (TAW report concludes cause of failure was fault external to PMG)		Megger of field cable from voltage regulator to PMG, with cable isolated from PMG, resulted in SAT readings (in the G Ohm range) which refutes an external fault event postulated by TAW. This check was performed via FAR #5 per WO 40731687-17.	CHAR and Megger field cables were performed SAT.	**Refuted**

FPSC EXH No. 5
03/18/2024
NEXTera ENERGY
ADMITTED

RCE TEAM SUPPORT / REFUTE MATRIX					
PROBLEM STATEMENT:	On July 5th, 2020 at approximately 2107, during a heavy rainstorm Unit 4 Tripped Automatically from 100% power due to a Generator Lockout.				
Failure Modes/Cause	**Discussion**	**Supporting Evidence**	**Refuting Evidence**	**Actions**	**Status**
23. Water Intrusion inside PMG compartment	Moisture within the PMG can compromise insulation withstand leading to failure. An excessive amount of moisture can create grounds during operation. For example, a water leak can thoroughly wet a section of the winding, weakening the insulation, and developing a fault. The Exciter Housing is designed to be sealed from outside ambient air. Fresh air is not circulated through the housing. Therefore, the concern with water intrusion is focused on external (rain) or internal	Water was located within the PMG and AC exciter compartments following the event. Volume was indeterminate but PMG and pedestal bolt holes in the frame contained standing water confirming some amount of intrusion. The PMG compartment is a highly turbulent environment due to forced air cooling airflow from the pole support fan. This could allow distribution of moisture over the PMG during operation in heavy rain events contributing to degradation of insulation quality. Also, of importance is the fact that the event occurred during a heavy downpour. During disassembly of the	No direct evidence of water within the PMG itself was found during disassembly. However excessive heating that occurred with the winding failure would have removed any forensic evidence.	Perform Visual inspection on PMG once it has been removed. **FAR 9 was issued to inspect/repair the seals associated with the Exciter housing.** **FAR 10 was issued to inspect/repair the VR Housing.** **FAR 16 includes steps to inspect/repair conduit seals as necessary.**	**Significant Contributing Cause #2**

FPSC EXH No. 5
03/18/2024
NEXTera ENERGY
ADMITTED

RCE TEAM SUPPORT / REFUTE MATRIX					
PROBLEM STATEMENT:	On July 5th, 2020 at approximately 2107, during a heavy rainstorm Unit 4 Tripped Automatically from 100% power due to a Generator Lockout.				
Failure Modes/Cause	**Discussion**	**Supporting Evidence**	**Refuting Evidence**	**Actions**	**Status**
	(condensation) undesired moisture.	Exciter housing under WO 40731687-08, the housing door seals, partition seals, and floor gaskets all appeared degraded and were subsequently replaced. The floor seals were found dislodged and sucked inward around the perimeter of the PMG compartment. Also, vertical weather seals described in 0-GMM-090.1 and MSP 02-055 were missing. The specific source of water intrusion inside the PMG and Exciter compartments is not known, however, water most likely entered these compartments through the dislodged floor gaskets and missing vertical weather seal. (Ref. Attachment 9)			

FPSC EXH No. 5
03/18/2024
NEXTera ENERGY
ADMITTED

RCE TEAM SUPPORT / REFUTE MATRIX					
PROBLEM STATEMENT:	On July 5th, 2020 at approximately 2107, during a heavy rainstorm Unit 4 Tripped Automatically from 100% power due to a Generator Lockout.				
Failure Modes/Cause	**Discussion**	**Supporting Evidence**	**Refuting Evidence**	**Actions**	**Status**
24. PMG Internal Component Failure (Other than Winding)	Failure of PMG would result in loss of voltage to PS1/PS2 and subsequently cause a voltage regulator lockout PMG is a simple design, with limited components. Component failures would originate in the stator, stator core, or rotating pole support (magnets). Abrasion of the insulating material results from mechanical wear either from a moving object in contact with the insulation, or from the insulation itself moving against an object. As mentioned,	The inspection of the removed stator does show core damage along with insulation damage.	Internals of the PMG include only a stator core. Based on disassembled inspection, core loss appears to be collateral damage due to winding failure in the core slots. Damage appears limited to the slot areas with no significant evidence of lamination fusing or heating in visible portions of the back iron. The failure characteristics indicate a short circuit / high current event rather than localized hotspots in the core.	Complete pending any discovery from Siemens during rewind.	**Refuted**

FPSC EXH No. 5
03/18/2024
NEXTera ENERGY
ADMITTED

RCE TEAM SUPPORT / REFUTE MATRIX					
PROBLEM STATEMENT:	On July 5th, 2020 at approximately 2107, during a heavy rainstorm Unit 4 Tripped Automatically from 100% power due to a Generator Lockout.				
Failure Modes/Cause	**Discussion**	**Supporting Evidence**	**Refuting Evidence**	**Actions**	**Status**
	thermal expansion and contraction of the winding causes portions of the winding to move; thus creating the possibility of the insulation wearing against the core and winding supports. Small localized damage to the insulation allows interturn or ground leakage current to flow. The leakage current further heats the damaged insulation, causing more damage; thus, causing more leakage current, more heat, and eventually failure.				

FPSC EXH No. 5
03/18/2024
NEXTera ENERGY
ADMITTED

RCE TEAM SUPPORT / REFUTE MATRIX					
PROBLEM STATEMENT:	On July 5th, 2020 at approximately 2107, during a heavy rainstorm Unit 4 Tripped Automatically from 100% power due to a Generator Lockout.				
Failure Modes/Cause	**Discussion**	**Supporting Evidence**	**Refuting Evidence**	**Actions**	**Status**
25. Lightning Strike	Lightning Strike can cause damage to electrical equipment and subsequently cause a voltage regulator lockout (TAW report concludes cause of failure was fault external to PMG)	Through discussion with a former electrical SME at the station it was identified that there have been multiple motor failures in the past which were likely caused by indirect lightning strikes. All electrical equipment is tied together with different levels of resistance through a station ground, and equipment transients have been seen on equipment due to lightning events.	No evidence of lighting strike. It is unlikely that a lightning strike would only affect the PMG and no other more susceptible equipment Inspection did not reveal any lighting strike damage at or near the exciter housing or the voltage regulator housing. No similar damage or evidence of degradation identified in the AC exciter stator which would result with a high voltage discharge through the stationary exciter assembly The U4 Exciter PMG stator is an ungrounded wye connected design. As such there is no direct path through the grounding grid	Perform visual inspection on PMG once it has been removed. Complete.	**Refuted**

FPSC EXH No. 5
03/18/2024
NEXTera ENERGY
ADMITTED

RCE TEAM SUPPORT / REFUTE MATRIX					
PROBLEM STATEMENT:	On July 5th, 2020 at approximately 2107, during a heavy rainstorm Unit 4 Tripped Automatically from 100% power due to a Generator Lockout.				
Failure Modes/Cause	**Discussion**	**Supporting Evidence**	**Refuting Evidence**	**Actions**	**Status**
			to the stator neutral that would facilitate a lightning related failure.		
26. Overcurrent from Voltage Regulator	Over-excitation, excessive field current could damage the PMG field windings and potentially breakdown the insulation leading to a flashover event within the component. (TAW report concludes cause of failure was fault external to PMG)		No indication of breaker overcurrent trip. Assumes back feed from AVR power supply to PMG. Design is PMG powers the AVR PS AVR functionally tested SAT. No fuses blown in power supply circuit that would indicate excessive current	FAR 3 was issued to functionally check the Power Drawer and Field Breaker.	**Refuted**

FPSC EXH No. 5
03/18/2024
NEXTera ENERGY
ADMITTED

RCE TEAM SUPPORT / REFUTE MATRIX					
PROBLEM STATEMENT:	On July 5th, 2020 at approximately 2107, during a heavy rainstorm Unit 4 Tripped Automatically from 100% power due to a Generator Lockout.				
Failure Modes/Cause	**Discussion**	**Supporting Evidence**	**Refuting Evidence**	**Actions**	**Status**
27. PMG Stator Core Failure	Core lamination insulation degradation will result in inter-laminar shorts in the core. This produces hot spots in the core iron which degrade the insulation of windings installed in the core slots leading to insulation failure over time and a stator failure. Induced current, if not minimized, will generate heat in the iron, weakening the core and damaging the windings. Damage to the lamination insulation permits excessive current that can overheat both the laminations and	Visual inspection of PMG stator windings found heavy copper and core iron deposition throughout due to arcing and extensive core damage. Inspection of failure debris identified a significant number of individual core lamination tooth tops liberated from the core assembly. These lamination teeth showed no evidence of mechanical damage on the tooth surface due to an interference rub. All of these teeth showed evidence of melting approximately ¼" down their length which would be below the stator wedge. This indicates that heating occurred down in	Based on disassembled inspection, core loss appears to be collateral damage due to winding failure in the core slots. Damage appears limited to the slot areas with no significant evidence of lamination fusing or heating in visible portions of the back iron. The failure characteristics indicate a short circuit / high current event rather than localized hotspots in the core.	Perform visual inspection during disassembly.	**Refuted**

FPSC EXH No. 5
03/18/2024
NEXTera ENERGY
ADMITTED

RCE TEAM SUPPORT / REFUTE MATRIX					
PROBLEM STATEMENT:	On July 5th, 2020 at approximately 2107, during a heavy rainstorm Unit 4 Tripped Automatically from 100% power due to a Generator Lockout.				
Failure Modes/Cause	**Discussion**	**Supporting Evidence**	**Refuting Evidence**	**Actions**	**Status**
	windings.	the core slot rather than the surface as a result of localized core lamination heating.			
28. Vibration	The vibrations of the unit 4 generator have been elevated and a concern since startup from the previous outage. Several forces act on the winding conductors. These include vibration from the exciter and generator, and the magnetic force. In rotating exciters and transformers, the magnetic force on the	Following the Unit 4 Exciter Rotor replacement during PT4-31, elevated vibrations have been recorded on bearing #9. The highest vibration measured following rotor replacement was 8.31mils during initial startup. Vibrations settled to 5-7mils during base load operation and have remained in this range until the Generator Lockout event on 7/5/2020.	This failure mode is conditioned on operating time and severity of the elevated vibration condition such that the material would be over stressed and driven to failure. As the mechanism noted is also age related, it is not a contributor to the failure. The recently noted response of the machine, is at a level requiring investigation and	1. Review of vibration profile from the last outage. Along with as left testing & measurements 2. Review of event profile to identify magnitude and timing of the vibration changes as the related to the event. During Startup, Operations monitors vibrations	**Refuted**

FPSC EXH No. 5
03/18/2024
NEXTera ENERGY
ADMITTED

RCE TEAM SUPPORT / REFUTE MATRIX					
PROBLEM STATEMENT:	On July 5th, 2020 at approximately 2107, during a heavy rainstorm Unit 4 Tripped Automatically from 100% power due to a Generator Lockout.				
Failure Modes/Cause	**Discussion**	**Supporting Evidence**	**Refuting Evidence**	**Actions**	**Status**
	AC winding is at twice the synchronous speed. Any looseness in the wedges or winding supports will allow the winding to vibrate at the location of the looseness. This vibration not only creates cyclic stresses in the insulation, but also can allow rubbing and abrasion of the insulation against the core iron or the support.		correction at the next opportunity for continued operation, it is not of the level requiring removal from service and is within the scope of design tolerance of the machine. This condition is one that has been developing as the machine ages. The vibration levels over the life of the equipment noted have not historically been abnormal and have been well below the threshold of concern. If operation were to continue with the present condition uncorrected, it may be a contributor to an equipment failure at a later date.	of the Generator using System1. Additionally, Siemens will have vibration Engineer monitoring the Generator vibrations remotely.	

FPSC EXH No. 5
03/18/2024
NEXTera ENERGY
ADMITTED

C3-381

RCE TEAM SUPPORT / REFUTE MATRIX					
PROBLEM STATEMENT:	On July 5th, 2020 at approximately 2107, during a heavy rainstorm Unit 4 Tripped Automatically from 100% power due to a Generator Lockout.				
Failure Modes/Cause	**Discussion**	**Supporting Evidence**	**Refuting Evidence**	**Actions**	**Status**
29. Assembly Error/Damage	Mechanical impact on the laminations is the most frequent cause of damage. Work performed on exciters and motors, particularly during removal and installation of the rotor, can score or crush the ends of the laminations together if not carefully done. Abrasive particles and other foreign material striking the ends of the laminations can wear off the insulating film and form a conductive path across laminations.	There was considerable difficulty in disassembling the exciter coupling. Several bolts could not be removed and had to be cut to enable exciter removal. It is plausible that some galling of these bolts occurred during the 14-month operating cycle due to the as-left alignment. Mechanical impact on winding during assembly can damage	TAW inspection and report did not find any indication of winding damage due to direct contact between the magnets and the stator. The report identifies a potential cause involving short circuit currents damaging the stator windings and the physical damage between the magnets and stator coming from debris drag following the failure. Any evidence of assembly damage may have been lost during the fault event.	TAW Inspection	**Refuted**

FPSC EXH No. 5
03/18/2024
NEXTera ENERGY
ADMITTED

RCE TEAM SUPPORT / REFUTE MATRIX					
PROBLEM STATEMENT:	On July 5th, 2020 at approximately 2107, during a heavy rainstorm Unit 4 Tripped Automatically from 100% power due to a Generator Lockout.				
Failure Modes/Cause	**Discussion**	**Supporting Evidence**	**Refuting Evidence**	**Actions**	**Status**
30. PMG Stator Winding jumper cable ground fault	A ground fault on PMG Stator Winding jumper cables may have cause the sustained high current on T-30 phase. (TAW report concludes cause of failure was fault external to PMG)	Oxidation on stator windings would have degraded the insulation and air gap needed to maintain the integrity of the PMG circuit. The generator lockout which opens the field circuit breaker would have challenged the insulation which was possibly wetted due to the storm at the time of the event.	Megger of field cable (including jumper cable) from voltage regulator to PMG, with cable isolated from PMG Stator Windings, resulted in SAT readings (in the G Ohm range). This check was performed via FAR #5 per WO 40731687-17.	Megger jumper cables once isolated from the PMG Stator Coil and field cable. Complete.	**Refuted**
31. Voltage Regulator local voltmeter ground fault	A ground fault on the voltage regulator voltmeter may have caused the sustained high current on T-30 phase. The voltmeter is connected to T-10 and T-30 phases (TAW report concludes cause of failure was fault		Voltmeter is protected by 6A fuses. It is expected that the fuses would blow on a fault condition. If fault was below 6A, it would not have resulted in the damage observed on the PMG winding connections. Local voltmeter functioned satisfactory following startup.	Inspect local voltmeter and voltmeter fuses Needs cleanup	**Refuted**

FPSC EXH No. 5
03/18/2024
NEXTera ENERGY
ADMITTED

RCE TEAM SUPPORT / REFUTE MATRIX					
PROBLEM STATEMENT:	On July 5th, 2020 at approximately 2107, during a heavy rainstorm Unit 4 Tripped Automatically from 100% power due to a Generator Lockout.				
Failure Modes/Cause	**Discussion**	**Supporting Evidence**	**Refuting Evidence**	**Actions**	**Status**
	external to PMG)				
32. Governor Control Panel potential transformer ground fault.	A ground fault on the Governor Control Panel PTs may have caused the sustained high current on T-30 phase. The PTs are connected to all three phases. (TAW report concludes cause of failure was fault external to PMG)		PTs are protected by 6A fuses. It is expected that the fuses would blow on a fault condition. If fault was below 6A, it would not have resulted in the damage observed on the PMG winding connections. PTs and PT fuses tested satisfactory during FAR #3.	Inspect Governor Control Panel PTs and PT fuses. Needs cleanup	**Refuted**

FPSC EXH No. 5
03/18/2024
NEXTera ENERGY
ADMITTED

RCE TEAM SUPPORT / REFUTE MATRIX					
PROBLEM STATEMENT:	On July 5th, 2020 at approximately 2107, during a heavy rainstorm Unit 4 Tripped Automatically from 100% power due to a Generator Lockout.				
Failure Modes/Cause	**Discussion**	**Supporting Evidence**	**Refuting Evidence**	**Actions**	**Status**
33. Ground Fault on Voltage Regulator 24VDC Power Supply Transformers	A ground fault on the 24VDC Power Supply Transformers may have caused the sustained high current on T-30 phase. (TAW report concludes cause of failure was fault external to PMG)		Power Supply Transformers are protected by 6A fuses. Fuses were found intact. FAR #3 tested the both 24VDC Power Supplies with SAT results with no work done on the transformers.	Visual inspection of transformers and fuses. Procedure 0-GME-090.01 Section 4.5.	**Refuted**
34. Ground Fault on Voltage Regulator Power Amplifier drawers Clarify they are VR components.	A ground fault on the 24VDC Power Supply Transformers may have caused the sustained high current on T-30 phase. (TAW report concludes cause of failure was fault external to PMG)		Power Amplifiers are protected by voltraps and 800A fuses. A sustained overcurrent condition from a ground fault will damage voltraps and blow fuses. Voltraps were powered up during testing under FAR #3 and no issues were identified. 800A fuses were intact. Additionally, power drawers were tested SAT under FAR #3.	Visual inspection of voltraps and 800A fuses. Complete.	**Refuted**

FPSC EXH No. 5
03/18/2024
NEXTera ENERGY
ADMITTED

RCE TEAM SUPPORT / REFUTE MATRIX					
PROBLEM STATEMENT:	On July 5th, 2020 at approximately 2107, during a heavy rainstorm Unit 4 Tripped Automatically from 100% power due to a Generator Lockout.				
Failure Modes/Cause	**Discussion**	**Supporting Evidence**	**Refuting Evidence**	**Actions**	**Status**
35. Ground fault on PMG Stator windings to PMG housing	Ground fault on PMG Stator windings can cause sustained overcurrent condition. (TAW report concludes cause of failure was fault external to PMG)	Oxidation on stator windings would have degraded the insulation and air gap needed to maintain the integrity of the PMG circuit. That level of oxidation looks to have been caused by overheating due to a single-phase ground on the PMG, AVR Power Drawer, Field Circuit Breaker, exciter stator, and interconnecting wires. There isn't a monitoring system at PTN that would give indication of this happening.	No signs of arcing or overheating was found on the Exciter housing that would be indicative of a high current ground.	Inspect PMG housing for signs of arcing or overheating. Perform megger testing of PMG Stator Windings. Perform forensics of PMG. These were completed SAT.	**Refuted**
PROGRAMMATIC/ORGANIZATIONAL					
36. Timely Exciter Winding PM Implementation Inadequate PM Strategy	Level 1 Assessment AR 2327198 for Fleet Exciter PM/Spare is issued in response to the H.B. Robinson	On 12/4/2019, assignment 07 of the L1A initiates PMC-19-006814 to create new PMs to rewind both stationary and rotating		Pull up due date of new Unit 4 PM to perform at the next refueling outage	**Significant Contributing Cause #1**

FPSC EXH No. 5
03/18/2024
NEXTera ENERGY
ADMITTED

RCE TEAM SUPPORT / REFUTE MATRIX					
PROBLEM STATEMENT:	On July 5th, 2020 at approximately 2107, during a heavy rainstorm Unit 4 Tripped Automatically from 100% power due to a Generator Lockout.				
Failure Modes/Cause	**Discussion**	**Supporting Evidence**	**Refuting Evidence**	**Actions**	**Status**
	event. Assessment recommends rewinding of Exciter rotating and stationary windings based on age of components. 5R Exciter overhaul PMs are recommended to include component rewind.	windings. PMC is approved on 2/3/2020. New 15R PMs 45986-58 (3K2) and 50551-60 (4K2) are activated for the rewind activity. These new PMs are given a due date of PT3-32 and PT4-36. These due dates lack pace considering the age of the Exciter windings have already exceeded the industry recommended service life of 30 years.		PT4-32.	
37. PM for Exciter Housing Door Seal inspections is reactionary vs preventive with regards to weather seals	36M Exciter Inspection PM 50551-42 performs an Exciter housing door seals and hardware inspection task. Additionally, as part of their inspections Siemens also inspects for Exciter housing seals and performs	During investigations following the Unit trip, water was observed inside the Exciter Housing. Exciter Door seal and hardware inspection task, as well as Siemens Exciter Testing reports, do not include explicit instructions to replace all weather seals of Exciter		Revise PM 50551-42 to require replacement of all Exciter housing door seals. Consider creating a new standalone 18M PM task for door seal replacements.	**Potential Contributor**

FPSC EXH No. 5
03/18/2024
NEXTera ENERGY
ADMITTED

RCE TEAM SUPPORT / REFUTE MATRIX					
PROBLEM STATEMENT:	On July 5th, 2020 at approximately 2107, during a heavy rainstorm Unit 4 Tripped Automatically from 100% power due to a Generator Lockout.				
Failure Modes/Cause	**Discussion**	**Supporting Evidence**	**Refuting Evidence**	**Actions**	**Status**
	replacements only when degradation is found.	housing regardless of condition. This can allow degradation within the 36M frequency that can allow water intrusion during heavy rain.			
38. Lack of Ground Detection System on PMG Stator Windings	The current ground detection system on the Unit 4 Generator and Exciter components does not include PMG Stator Winding ground detection. This system may have notified Operations of a potential issue and allowed for a response before failure.	PMG Stator windings do not have a ground detection system installed. If one were installed, a ground condition can result in Control Room alarm and Operator actions to find the source and eliminate.	Although a ground detection system on the PMG stator can alert the Control Room of a single ground condition and provide time for troubleshooting, it would not have allowed enough time to respond to the multiple ground fault event that occurred over a short duration (approximately 166 minutes between initial ground alarm and subsequent failure).	None	**Refuted**
39. Limitations of Vibration Monitoring equipment.	The current Vibration Monitoring equipment provides relative vibration vs absolute.	Current Vibration is monitored with proximitors (relative vibration transducers)	This failure mode is conditioned on operating time and severity of the elevated vibration condition	Survey perform ODS testing of the existing generator & exciter structure	**Refuted**

FPSC EXH No. 5
03/18/2024
NEXTera ENERGY
ADMITTED

C3-388

RCE TEAM SUPPORT / REFUTE MATRIX					
PROBLEM STATEMENT:	On July 5th, 2020 at approximately 2107, during a heavy rainstorm Unit 4 Tripped Automatically from 100% power due to a Generator Lockout.				
Failure Modes/Cause	**Discussion**	**Supporting Evidence**	**Refuting Evidence**	**Actions**	**Status**
	This may mask an undesirable vibration condition	measuring the vibration response difference of its mounting position (casing or bearing structure) and the target (rotating element or shaft). In its use the assumption is the structure is stiff and provides minimal input to the vibration signal. If the structure is weak and has a significant amount of vibration the value provided may not be a true value. The actual level of casing response is unknown as it is not measured, and the actual shaft vibration is not known because it is masked by the input of the structural vibration. Shims located under the exciter skid were found	such that the material would be over stressed and driven to failure. As the mechanism noted is also age related, it is not a contributor to the failure. The recently noted response of the machine, is at a level requiring investigation and correction at the next opportunity for continued operation, it is not of the level requiring removal from service and is within the scope of design tolerance of the machine. This condition is one that has been developing as the machine ages. The vibration levels over the life of the equipment noted have not	and absolute shaft vibration. Inspect generator foundation bolting for proper clearance.	

C3-286
FCR-22-000577

FPSC EXH No. 5
03/18/2024
NEXTera ENERGY
ADMITTED

RCE TEAM SUPPORT / REFUTE MATRIX					
PROBLEM STATEMENT:	On July 5th, 2020 at approximately 2107, during a heavy rainstorm Unit 4 Tripped Automatically from 100% power due to a Generator Lockout.				
Failure Modes/Cause	**Discussion**	**Supporting Evidence**	**Refuting Evidence**	**Actions**	**Status**
		displaced/missing. For a shim to migrate out of its location requires differential movement between the contacting structures, in this case exciter base plate and skid. The level of vibration response on the exciter appears somewhat excessive for a vibration issue on the generator. Unit #3 Vibration response investigation (AR-02293836 & subsequent Siemens/FPL Vibration RCA Team Report) indicated potential age-related issues affecting structural response of the machine that needed investigation. These same issues, due to similarities	historically been abnormal and have been well below the threshold of concern. If operation were to continue with the present condition uncorrected, it may be a contributor to an equipment failure at a later date.		

FPSC EXH No. 5
03/18/2024
NEXTera ENERGY
ADMITTED

RCE TEAM SUPPORT / REFUTE MATRIX					
PROBLEM STATEMENT:	On July 5th, 2020 at approximately 2107, during a heavy rainstorm Unit 4 Tripped Automatically from 100% power due to a Generator Lockout.				
Failure Modes/Cause	**Discussion**	**Supporting Evidence**	**Refuting Evidence**	**Actions**	**Status**
		in design, age and environment may be evident on Unit #4.			
40. Weakness in Annunciator Response Procedures	ARP's may not provide sufficient guidance to Operators following ground alarms on the Unit 4 Generator Exciter to prevent failure from occurring.	Alarm response procedure guidance for E8/4 Generator Ground is to validate alarm (by reset and going to test) and to check for TPCW leaks. Actions for valid alarms are notify Electrical and consider shutting down unit. Generically, the E panel alarm guidance is to notify Electrical and Transmission System Operator, or System Dispatch. Off normal procedure ONOP-090, Abnormal Generator MW/MVAR Oscillation, contains	System design is ungrounded. Operation may continue with one ground. A second ground would cause a short and result in transient / trip. Alarm response and Off-normal procedure philosophy is to validate alarm prior to taking action. This validation typically includes Electrical and Engineering support. Management notifications would be performed prior to a removing unit from service. There were approximately two hours between alarm and unit trip. This is not a	None.	**Refuted –**

FPSC EXH No. 5
03/18/2024
NEXTera ENERGY
ADMITTED

RCE TEAM SUPPORT / REFUTE MATRIX					
PROBLEM STATEMENT:	On July 5th, 2020 at approximately 2107, during a heavy rainstorm Unit 4 Tripped Automatically from 100% power due to a Generator Lockout.				
Failure Modes/Cause	**Discussion**	**Supporting Evidence**	**Refuting Evidence**	**Actions**	**Status**
		guidance to notify groups (Electrical, System Dispatch, System Protection, System Engineer/Component Specialist) and response by manipulating voltage regulators and power system stabilizer. Guidance does not provide hard criteria to remove unit from service.	reasonable amount of time to allow for offsite personnel to validate alarm and for management notifications to occur. In addition, removing unit from service for a valid ground does not eliminate the ground and would likely result in exciter/PMG repair/replacement.		
41. Corrective Actions Lack Priority	Corrective Actions to repair exciter door seals, address bearing #9 vibrations, and LTAM PTN-18-002 To replace voltage regulators are not addressed in a timely manner.	As an example: Multiple water intrusion events associated with the exciter housing along with past extent of cause events failed to provide sufficient remedies in prevention space regarding water ingress to a sensitive environment.		Investigate past WO designated priorities and extensions on water ingress issues.	**Potential Contributor**

FPSC EXH No. 5
03/18/2024
NEXTera ENERGY
ADMITTED

RCE TEAM SUPPORT / REFUTE MATRIX					
PROBLEM STATEMENT:	On July 5th, 2020 at approximately 2107, during a heavy rainstorm Unit 4 Tripped Automatically from 100% power due to a Generator Lockout.				
Failure Modes/Cause	**Discussion**	**Supporting Evidence**	**Refuting Evidence**	**Actions**	**Status**
42. The current organizational structure at the site level, has not ensured assigned oversite has received the knowledge, training or expertise to monitor, track and develop actions to address cumulative stressors that can affect the Turbine Generator	A lack of knowledge of the Turbine / Generator/ Exciter systems may have prevented personnel from fully understanding the collateral impacts of system stressors	PMG Stator failure occurred in a rainstorm and some signs of water intrusion were noted in the PMG portion of the Exciter House following the failure. The U4 Turbine Generator experienced elevated vibration during the previous operating cycle The U4 PMG Stator has been in service for approximately 34 years without a rewind. Maintenance philosophy was to inspect, test, and maintain	There is no evidence that the failure of the PMG stator winding was due to or affected by ineffective oversight or lack of technical assessment of aggregate stressors. Three potential stressors have been noted as potential contributors to the failure. Vibration: While vibration levels at the #9 bearing adjacent to the PMG were elevated during the prior operating cycle, they remained well within OEM specified limits. Vertical displacement values reached a short-term peak of ~7 mils with a max allowable peak of 14 mils. Vibration levels at the stationary PMG stator housing are not a monitored parameter, however		**Refuted**

FPSC EXH No. 5
03/18/2024
NEXTera ENERGY
ADMITTED

RCE TEAM SUPPORT / REFUTE MATRIX					
PROBLEM STATEMENT:	On July 5th, 2020 at approximately 2107, during a heavy rainstorm Unit 4 Tripped Automatically from 100% power due to a Generator Lockout.				
Failure Modes/Cause	**Discussion**	**Supporting Evidence**	**Refuting Evidence**	**Actions**	**Status**
			periodic walkdowns of the Exciter housing over the operating cycle did not identify any significant physical vibration of note at the PMG housing compartment or surrounding deck. While vibration is known to be a long-term mechanical stressor to motor / generator winding insulation (cyclic stress), the recorded levels do not support this as a significant degradation mechanism to U4 PMG life that would require specialized actions to mitigate. Moisture: The U4 Exciter housing was last removed during the Spring 2019 outage. Exciter base seals were inspected for serviceability prior to re-		

FPSC EXH No. 5
03/18/2024
NEXTera ENERGY
ADMITTED

RCE TEAM SUPPORT / REFUTE MATRIX					
PROBLEM STATEMENT:	On July 5th, 2020 at approximately 2107, during a heavy rainstorm Unit 4 Tripped Automatically from 100% power due to a Generator Lockout.				
Failure Modes/Cause	**Discussion**	**Supporting Evidence**	**Refuting Evidence**	**Actions**	**Status**
			installation. There was no known indication of a leak in the PMG compartment when the unit was returned to service. During operation these base seals cannot be inspected, leaving potential for unnoted migration during an operating cycle. Following the U4 PMG failure, some migration of base seals at the corners of the PMG section of the exciter house was noted. This migration would allow moisture ingress along the floor as the PMG section of the housing operates at a high negative pressure. While moisture is a known stressor to electrical insulation, the inability to monitor for ingress online prevents a condition assessment by site or fleet		

FPSC EXH No. 5
03/18/2024
NEXTera ENERGY
ADMITTED

RCE TEAM SUPPORT / REFUTE MATRIX					
PROBLEM STATEMENT:	On July 5th, 2020 at approximately 2107, during a heavy rainstorm Unit 4 Tripped Automatically from 100% power due to a Generator Lockout.				
Failure Modes/Cause	**Discussion**	**Supporting Evidence**	**Refuting Evidence**	**Actions**	**Status**
			personnel other than with outage inspections. Age: Aging is a known degradation mechanism. To address this, the site has historically adhered a maintenance strategy of routine inspections and electrical testing at 18-month intervals, with disassembled inspections at 7.5 years. Siemens / Westinghouse does not specify rewind intervals for Permanent Magnet Generators. According to OEM Generator Engineering, PMG stator rewind has only been done for cause, failing an electrical test, or reaching a condition that was deemed unacceptable for continued operation. Note that all inspection reports for 18		

FPSC EXH No. 5
03/18/2024
NEXTera ENERGY
ADMITTED

RCE TEAM SUPPORT / REFUTE MATRIX					
PROBLEM STATEMENT:	On July 5th, 2020 at approximately 2107, during a heavy rainstorm Unit 4 Tripped Automatically from 100% power due to a Generator Lockout.				
Failure Modes/Cause	**Discussion**	**Supporting Evidence**	**Refuting Evidence**	**Actions**	**Status**
			months and 7.5-year inspections found no degradation and were dispositioned as SAT by both OEM and site personnel for return to service. Based on test and inspection performed approximately 15 months prior to the failure, no condition concern had been noted and left unaddressed. Without positive confirmation of the presence of cumulative stressors prior to the PMG failure and a failure to appropriately assess or mitigate, a postulated lack of technical rigor or oversight is unsupported.		
43. Insufficient vibration analysis performed on Unit 4 #9 bearing	Ongoing communication through the operating	The Fleet Team was requested to monitor the start up from this forced	This failure mode is conditioned on operating time and severity of the	None.	**Refuted**

FPSC EXH No. 5
03/18/2024
NEXTera ENERGY
ADMITTED

RCE TEAM SUPPORT / REFUTE MATRIX					
PROBLEM STATEMENT:	On July 5th, 2020 at approximately 2107, during a heavy rainstorm Unit 4 Tripped Automatically from 100% power due to a Generator Lockout.				
Failure Modes/Cause	**Discussion**	**Supporting Evidence**	**Refuting Evidence**	**Actions**	**Status**
vibration response	period with site personnel indicated that the exciter had an imbalance issue. The Fleet Team was requested to provide input through the period on specific vibration anomalies on the specific responses. The responses were noted to be driven by the generator response and imbalance was called out not to be the issue.	outage. During the event high vibration was evident on the exciter. Analysis of the response indicated the presence of an H2 Seal Rub initiating around 1700 RPM, the exciter was noted to respond to the change in phase angle of the balance vector which occurs because of a rub on the rotating assembly. While the exact cause of correction is known, the rub condition appears to have been reduced or dissipated at this time. Based on the above and the communication that this response was similar to the 4-31 start up, this was also reviewed. Reviewing the data indicated a similar condition on start up	elevated vibration condition such that the material would be over stressed and driven to failure. As the mechanism noted is also age related, it is not a contributor to the failure. The recently noted response of the machine, is at a level requiring investigation and correction at the next opportunity for continued operation, it is not of the level requiring removal from service and is within the scope of design tolerance of the machine. This condition is one that has been developing as the machine ages. The vibration levels over the life of the		

FPSC EXH No. 5
03/18/2024
NEXTera ENERGY
ADMITTED

RCE TEAM SUPPORT / REFUTE MATRIX					
PROBLEM STATEMENT:	On July 5th, 2020 at approximately 2107, during a heavy rainstorm Unit 4 Tripped Automatically from 100% power due to a Generator Lockout.				
Failure Modes/Cause	**Discussion**	**Supporting Evidence**	**Refuting Evidence**	**Actions**	**Status**
		where the seal rub was initiated during roll up, the effect continued through the subsequent run. (The rub was sustained during the subsequent run period.) Review of previous startups also indicated a similar condition on startups to varying degrees.	equipment noted have not historically been abnormal and have been well below the threshold of concern. If operation were to continue with the present condition uncorrected, it may be a contributor to an equipment failure at a later date.		
44. Nuclear Structure inhibits timely resolution of system issues.	The lack of site expertise for subject single point vulnerable host component lends itself to concerns on creating and defending work order priorities, both short term and long term scheduled issues. Representing concerns	Based on search findings to date within this RCE, substantive evidence has shown numerous water intrusion events on the exciter housing. Additionally, discerning the probable root cause being the age of the failed PMG stator windings combined with additional		Re-visit the Change Management Plan on resource allocations regarding nuclear systems personnel, work controls, and outage planners.	**Potential Contributor**

FPSC EXH No. 5
03/18/2024
NEXTera ENERGY
ADMITTED

RCE TEAM SUPPORT / REFUTE MATRIX					
PROBLEM STATEMENT:	On July 5th, 2020 at approximately 2107, during a heavy rainstorm Unit 4 Tripped Automatically from 100% power due to a Generator Lockout.				
Failure Modes/Cause	**Discussion**	**Supporting Evidence**	**Refuting Evidence**	**Actions**	**Status**
	and priorities within Plant Health Sub-Committees is critical in allocating the necessary resources to ensure the SSCs are maintained properly and within the ER standards afforded for the critical equipment.	stressors including water intrusion into the housing, favors the nuclear structure in having dedicated expertise in the site owned and managed turbine, generator and exciter model, a model that is not to be treated as a generic model to all nuclear/fossil fleet owners.			

Attachment 7: Barrier Analysis chart

FPSC EXH No. 5
03/18/2024
NEXTera ENERGY
ADMITTED

RCE AR 2361794: Unit 4 Exciter Failure

Root Cause: A weak PM program philosophy had resulted from a failure to fully assess risk of equipment age making the PMG stator more susceptible to failure when exposed to water/moisture.

Barriers to Prevent Condition	Discussion of Evidence/Facts	Conclusion: 1. Barrier Missing 2. Weak Barrier 3. Barrier Failed 4. No Failed Barrier 5. Barrier not used	Why was the barrier missing, weak, failed, or not used?
Work Management process change	Removal of Site Turbine / Generator/ Exciter representative via the CMP allowed for reduced focus/timeliness of required actions and commitments to maintain the subject single point vulnerable equipment to the degree needed for optimal availability.	4. No Failed Barrier	There was no explicit requirement from either the vendor or industry OE to perform an Exciter rewind. Proper focus and timeliness from either a site representative (prior organization) or fleet turbine/generator team (current organization) would still not have resulted in a rewind PM.

FPSC EXH No. 5
03/18/2024
NEXTera ENERGY
ADMITTED

C3-401

RCE AR 2361794: Unit 4 Exciter Failure

Root Cause: A weak PM program philosophy had resulted from a failure to fully assess risk of equipment age making the PMG stator more susceptible to failure when exposed to water/moisture.

Barriers to Prevent Condition	Discussion of Evidence/Facts	Conclusion: 1. Barrier Missing 2. Weak Barrier 3. Barrier Failed 4. No Failed Barrier 5. Barrier not used	Why was the barrier missing, weak, failed, or not used?
Conduct of Engineering (EN-AA-104)	**A review of EN-AA-104 (Conduct of Engineering) has identified that the responsibility and ownership of Turbine components was shifted to the EOOS engineering group in 2015, an off-site group. There is no specific individual within the PTN system engineering group that is assigned as the Turbine system Engineer, they are now identified as a support group for EOOS. The failed components have not been replaced per vendor / mfg.'s recommendations and are currently experiencing age related failures.**	**4. No Failed Barrier**	**There was no explicit requirement from either the vendor or industry OE to perform an Exciter rewind. Had component ownership remained with a site representative (prior organization) it would still not have resulted in a rewind PM.**

C3-299

FPSC EXH No. 5
03/18/2024
NEXTera ENERGY
ADMITTED

RCE AR 2361794: Unit 4 Exciter Failure

Root Cause: A weak PM program philosophy had resulted from a failure to fully assess risk of equipment age making the PMG stator more susceptible to failure when exposed to water/moisture.

Barriers to Prevent Condition	Discussion of Evidence/Facts	Conclusion: 1. Barrier Missing 2. Weak Barrier 3. Barrier Failed 4. No Failed Barrier 5. Barrier not used	Why was the barrier missing, weak, failed, or not used?
Project Oversight	**OEM procedures provide the technical instruction and criteria for performance of exciter maintenance. These procedures are proprietary but subject to customer review and approval prior to execution.** **A potential gap exists in that the scope of work performed by the OEM is not all inclusive. Multiple entities are involved with varying scope of responsibilities leaving potential for missed scope upon conclusion of Exciter maintenance projects. Examples: OEM performs mechanical work and electrical testing, site or contractor performs electrical de-terminations / re-terminations, site or contractor performs coatings.**	**3. Barrier Failed**	**Aggregate Exciter Maintenance project scope may not have the appropriate level of review to ensure continuity between work groups.**

FPSC EXH No. 5
03/18/2024
NEXTera ENERGY
ADMITTED

RCE AR 2361794: Unit 4 Exciter Failure

Root Cause: A weak PM program philosophy had resulted from a failure to fully assess risk of equipment age making the PMG stator more susceptible to failure when exposed to water/moisture.

Barriers to Prevent Condition	Discussion of Evidence/Facts	Conclusion: 1. Barrier Missing 2. Weak Barrier 3. Barrier Failed 4. No Failed Barrier 5. Barrier not used	Why was the barrier missing, weak, failed, or not used?
Siemens Work Process	**1. Standard for measuring and determining health and suitability of continued operability of seals.** **2. Is work process inclusive of circle slash steps to ensure all steps are completed and every seal inspected and measured for suitability.** **3. Is work reviewed by others?** **4. Is there accountability in Siemens following their procedures? How does the equipment go through several 2 cycle cycles of OK/replace then go through several cycles in a row with seals being acceptable?** **5. Are Siemens procedures required to**	**3. Barrier Failed**	**1) FPL has historically used Siemens to evaluate and recommend life expectancy of Turbine components and the frequency at which they are inspected, refurbished or replaced. This has been a weakness in the past in FPL's organizational ownership of our Turbine generators.** **2) Siemens work management process is commensurate to the FPL process utilizing step by step instruction and place-keeping methods such as "circling and slashing" each step. Retention and review of Siemens documentation can be reviewed by FPL oversight during task performance but becomes vague after the fact due to their work documents being proprietary in nature and not included in the shell work orders GFPL provides them.** **3) Siemens work documents are reviewed and approved by the FPL Turbine supervisor before being included in their field packages. Siemens work steps also include the level of oversight needed to verify and validate critical steps.** **4) Yes, Siemens requires verbatim compliance to their**

FPSC EXH No. 5
03/18/2024
NEXTera ENERGY
ADMITTED

C3-404

RCE AR 2361794: Unit 4 Exciter Failure

Root Cause: A weak PM program philosophy had resulted from a failure to fully assess risk of equipment age making the PMG stator more susceptible to failure when exposed to water/moisture.

Barriers to Prevent Condition	Discussion of Evidence/Facts	Conclusion: 1. Barrier Missing 2. Weak Barrier 3. Barrier Failed 4. No Failed Barrier 5. Barrier not used	Why was the barrier missing, weak, failed, or not used?
	be reviewed and approved by FPL? What is done if there is ever a revised procedure? Are the procedures up to date with learned information? 6. Do existing procedures provide enough information to allow for revision for improvement?		work orders. Station personnel currently lacks the knowledge or expertise for challenging the frequency and technical justification for some of their decisions. 5) Yes, Siemens work documents are reviewed by the FPL Turbine supervisor. Procedure revisions are not reviewed and/or checked to ensure latest technical learnings have been incorporated into their procedures. FPL has an over-reliance on the vendor for their technical knowledge of the Turbine and associated components. 6) Existing Siemens procedures need to be reviewed by the most technically knowledgeable individual within the FPL EOOS organization to ensure all industry knowledge and improvement opportunities have been captured and incorporated into their procedures.
Station Procedures	Site Exciter Maintenance procedures provide the technical instruction and criteria for performance of exciter	2. Weak Barrier	Significance of site OE underestimated during the procedure revision process allowing critical activities to be dispositioned as discretionary.

C3-302

FPSC EXH No. 5
03/18/2024
NEXTera ENERGY
ADMITTED

RCE AR 2361794: Unit 4 Exciter Failure

Root Cause: A weak PM program philosophy had resulted from a failure to fully assess risk of equipment age making the PMG stator more susceptible to failure when exposed to water/moisture.

Barriers to Prevent Condition	Discussion of Evidence/Facts	Conclusion: 1. Barrier Missing 2. Weak Barrier 3. Barrier Failed 4. No Failed Barrier 5. Barrier not used	Why was the barrier missing, weak, failed, or not used?
	maintenance. It has been identified that previous procedure updates may not have sufficiently captured site OE when outlining specific work steps. **In addition, site procedures are not used by all entities performing aggregate work scope leaving potential for non-performance of site-specific maintenance requirements.** **1. Standard for measuring and determining acceptability of previous**		**Vendors allowed to work to their own procedures rather than site procedures. Pertinent site-specific OE may not be incorporated into their work plans.** **The current work management process has FPL develop a "Shell" work order task for all Siemens tasks for them to use. Siemens then expands the description of the work order task by inserting the Siemens work standard (example). Perform work per Siemens 3.2.2.6 work standard.) The Siemens specific work document (Siemens 3.2.2.6) is then reviewed by an FPL Supervisor to ensure critical steps and appropriate hold points and/or adequate inspection & verification signoffs are included. If the document does not meet the FPL standards, then the document is rejected, and Siemens revises the work documents to include the revisions requested by FPL oversight.** **Because Siemens does not attach the actual work document to the work task in EWP during the package closure process, it is difficult to go back and verify or**

FPSC EXH No. 5
03/18/2024
NEXTera ENERGY
ADMITTED

RCE AR 2361794: Unit 4 Exciter Failure

Root Cause: A weak PM program philosophy had resulted from a failure to fully assess risk of equipment age making the PMG stator more susceptible to failure when exposed to water/moisture.

Barriers to Prevent Condition	Discussion of Evidence/Facts	Conclusion: 1. Barrier Missing 2. Weak Barrier 3. Barrier Failed 4. No Failed Barrier 5. Barrier not used	Why was the barrier missing, weak, failed, or not used?
	results **2. Is work process inclusive of circle slash steps to ensure all steps are completed with information regarding what results are appropriate.** **3. Is work reviewed by others?** **4. Is there accountability to follow procedure?** **5. Are procedures required to be reviewed and approved? What is done if there is ever a revised procedure? Are the procedures up to date with learned information?** **6. Do existing procedures provide enough information to allow for revision**		**validate specific details of the work that was done. Siemens does download the Journeymen's work report into EWP which are most times very detailed.**

FPSC EXH No. 5
03/18/2024
NEXTera ENERGY
ADMITTED

RCE AR 2361794: Unit 4 Exciter Failure

Root Cause: A weak PM program philosophy had resulted from a failure to fully assess risk of equipment age making the PMG stator more susceptible to failure when exposed to water/moisture.

Barriers to Prevent Condition	Discussion of Evidence/Facts	Conclusion: 1. Barrier Missing 2. Weak Barrier 3. Barrier Failed 4. No Failed Barrier 5. Barrier not used	Why was the barrier missing, weak, failed, or not used?
	for improvement? **7. Is there an accountability supply information on the WO.**		
Seal EC process	**1. What was the initial request vs. final product.** **2. Is there an issue real or perceived hindering voluntary submission vs. required submission of a process or providing recommendations vs. requirements?** **3. Was the issue fully understood or supplied to the EC performer.** **4. Was the requester part of the approval process?**	**2. Weak Barrier**	**EC 241744 (MSP 02-055) issuance with the recommended change to the 0-GMM-090.1 '*Exciter Removal, Inspection and Installation*', the only site procedure associated with the exciter overhaul that provided instructions to remove and install the housing, should have mandated that new sealant shall always be applied the housing is removed. There should not be any discretionary decision from craft or planners whether sealant should be applied. Additionally, Sealant degrades with time, and will degrade at an accelerated rate with conditions at PTN. This provides greater basis for a mandated sealant application during standard housing removal intervals and for-cause removals.**

FPSC EXH No. 5
03/18/2024
NEXTera ENERGY
ADMITTED

RCE AR 2361794: Unit 4 Exciter Failure

Root Cause: A weak PM program philosophy had resulted from a failure to fully assess risk of equipment age making the PMG stator more susceptible to failure when exposed to water/moisture.

Barriers to Prevent Condition	Discussion of Evidence/Facts	Conclusion: 1. Barrier Missing 2. Weak Barrier 3. Barrier Failed 4. No Failed Barrier 5. Barrier not used	Why was the barrier missing, weak, failed, or not used?
PM to rewind exciter & PMG based on age	EPRI and other industry documents provide a 10 to 30 year service life for Exciter and PMG windings. They do not explicitly require rewind activities. Winding gets prematurely aged and becomes more susceptible to other failure factors such as vibration, humidity, temperature and water intrusion. As the insulation ages, chemical changes make insulation dry, and brittle. Varnish and epoxy used for binding gets weakened with age.	2. Weak Barrier	No PM for exciter and PMG rewind prior to 2019. Siemens as OEM does not recommend rewind of exciter and PMG based on age. Funding has not been set aside for replacement of critical components, such as TG exciter components, that are currently at or past normal life-expectancy. Funding allocation requires LTAM approval and success hinges on competition with all other plant funding priorities.
No trend indication for humidity in exciter and PMG housing	Not presently able to obtain condition inside doghouse for humidity and water considering history and outdoor unit with South Florida harsh environment.	1. Barrier Missing	Westinghouse brushless exciter design does not include trend monitoring of humidity. Voltage regulator housing has humidity meter for operator log measurement.

FPSC EXH No. 5
03/18/2024
NEXTera ENERGY
ADMITTED

RCE AR 2361794: Unit 4 Exciter Failure

Root Cause: A weak PM program philosophy had resulted from a failure to fully assess risk of equipment age making the PMG stator more susceptible to failure when exposed to water/moisture.

Barriers to Prevent Condition	Discussion of Evidence/Facts	Conclusion: 1. Barrier Missing 2. Weak Barrier 3. Barrier Failed 4. No Failed Barrier 5. Barrier not used	Why was the barrier missing, weak, failed, or not used?
No exciter field and PMG ground alarm	Ground monitoring provides early indication for failures of winding if due to slow ground fault. However, ground monitoring will not help to prevent catastrophic failures. No awareness of the potential initial ground on PMG winding in days, week or month prior to trip event. Second ground results are likely the catastrophic event.	1. Barrier Missing	WTA-300 voltage regulator at PTN do not have exciter field ground monitoring installed. Only Generator field ground monitoring system at Turkey Point. Latter version of WTA-300B at Point Beach has two modules in design. One for Generator field ground and second for exciter field ground which includes PMG stator winding.
Sealing of exciter housing with exciter base to prevent water in negative pressure PMG area, especially during heavy rain condition.	Lack of direction in 0-GMM-090.01 '*Exciter Removal, Inspection and Installation*'. Siemens procedure v/s plant procedure for doghouse sealing. Sealing history. Sealing material and process etc.	2. Weak Barrier	As proven via the inspection of Unit 3 exciter housing during this root cause investigation, the sealant was not applied at the suspect interface location.

FPSC EXH No. 5
03/18/2024
NEXTera ENERGY
ADMITTED

Attachment 8: Timeline

DATE	TIME	DESCRIPTION
1986	-	PMG Stator is manufactured by Siemens/Westinghouse
12/3/1998		EPRI developed a document on "Preventive Maintenance and Overhaul Experience for Rotating Brushless Exciters and other Exciter Systems". In this document under the section on Moisture it states "The presence of contaminated water, condensation, or any type of moisture can also cause failure of diode wheel components. Electrical "tracking", as described earlier, can occur with moisture in the same way as it does with dirt or fly ash. Moisture can also lower the insulation resistance of the diode wheel components and the windings. Outdoor generating units in high humidity areas are prone to having moisture form in the exciter house through condensation on the cooling coils. Condensation was so much of a problem at Florida Power & Lights (FPL) Martin, Manatee and Sanford stations that the cooling water would often be shut off when the units cycled off at night. Moisture can also be a problem on outdoor units, if the seal between the exciter house and the sole plate is not adequate. One of the units in southern Florida was found to be sucking water off the turbine deck and into the exciter house in the area of the PMG. The problem was found when the rotor ground detector indicated a problem. The unit was shut down and the exciter house was swabbed and then vacuumed. The base was temporarily sealed with a bead of RTV. A more permanent fix was enacted during the next refueling outage. Better seals and their correct installation solve the problem. Of course, cooler leaks, inside the exciter housing, can also be a source of moisture. Cooler leaks should be repaired immediately. Both issues mentioned in this section of the "Utility Generator Predictive Maintenance conference report" (internal and external water intrusion) have reoccurred at PTN subsequent to this report dated 12/3/1998. These issues are documented in the OE section of this RCE.
9/29/2001	-	PTN U3 Water Intrusion caused a forced power reduction due to severe weather and continuous heavy rains. A large pressure differential was created in the Exciter housing by the oversized blower, sucking water into the housing and blowing water on to exciter electrical components throughout the enclosure This was caused by a failure of gaskets and removal of pipe plugs which produced a leak path from the external environmental conditions to the internal exciter components.
10/27/2001 10/31/2001		Work order (WO 31019895-01) was written on 10/27/2001 to Repair U3 Exciter housing gaskets. The work order was taken to ready status

FPSC EXH No. 5
03/18/2024
NEXTera ENERGY
ADMITTED

		on 10/31/2001. Subsequently the repairs stated in the work order were not performed and the work order was placed back into the library.
6/17/2002		Subsequent water intrusion inside U3 exciter housing prompted engineering to issue an MSP 02-055 to provide direction on sealing the Exciter housing.
7/10/2002		WO 31019895-01 was taken to approved status and was awaiting implementation.
2/27/2004		On 2/27/2004 the work order (WO 31019895-01) was finally taken to working status and the repairs were made. The work was completed.
12/28/2004	-	Ten months later, a Manual reactor scram on U3 had to be initiated due to water intrusion inside the Turbine Exciter housing. The cause was due to improper gasket material and improper assembly of Exciter cooler by a vendor resulting in a (~`90 gpm) leak on the TPCW piping inside the housing.
4/18/2005	-	Siemens performs Generator Inspection under Job No. 0NIT05000022. As part of this activity the Exciter housing was inspected and found in satisfactory condition. The zone and door seals were in satisfactory condition. PMG meggers at 26.37MOhms, winding resistances are below 0.0062 Ohms.
10/15/2006	-	Siemens performs Generator and Exciter inspections per Siemens Job No. 0NIT07001A52. The Exciter housing doors were found with excessively worn hardware. The door sealing rubber was found deteriorated. The door sealing rubber was replaced with new rubber. No Electrical testing of the PMG was performed as part of this activity.
4/6/02008	-	Siemens performs Exciter testing on the Unit 4 Exciter as part of the 1R PMRQ 50551-42 (FPL WO not found). The Exciter housing was inspected and found in satisfactory condition. No deficiencies observed on weather seals. PMG meggers at 48.7MOhms, winding resistances are below 0.0059 Ohms.
12/10/2008		0-GMM-090.1 was revised to include attachment 5 providing a drawing on how to properly seal the Exciter housing using in inner foam gasket to prevent water intrusion.
11/4/2009	-	Siemens performs Exciter testing on the Unit 4 Exciter as part of the 1R PMRQ 50551-42 (WO 39008715). The gasket on the Exciter housing top cover was replaced and weather sealed. The exciter PMG end rubber seal was found partially out of position and was replaced. The exciter was inspected to verify that no rubber from this or any other debris was present on any cooling passages or in the diode wheels. The inter-zone seals were replaced with new seal material. The affected inter-zone seals were removed and replaced with new seal material and Loctite 290 was applied to the bolting threads prior to torqueing. The entire seal on the right-side exciter end door was replaced with new seal material. The seal on the latch side of the right-side turbine end door was also replaced. As part of the door seal replacements, the doors were adjusted to ensure proper sealing. PMG meggers at 6MOhms, winding resistances are below 0.0059 Ohms.

FPSC EXH No. 5
03/18/2024
NEXTera ENERGY
ADMITTED

1/7/2010		NAMS shows 0-GMM-090.1 first revision was done on 1/7/2010. Page 69 of the procedure at that time showed section 6.23.8, an FPL Supervisor/Engineer verification step, existed prior to this time due to the date of page 69 being 8/9/2007. It also shows page 77, attachment 5 having an approval date of the page as 12/10/08.
3/25/2011	-	Siemens performs Exciter testing on the Unit 4 Exciter as part of the 1R PMRQ 50551-42 (WO 40015985). No deficiencies observed on weather seals. PMG meggers at 52.1MOhms, winding resistances are below 0.0059 Ohms.
1/6/2013	-	Siemens Field Services performs Generator Stator Rewind under Siemens Job No. 0NIT12004403. As part of this work, Electrical tests are performed on the PMG, AC stator and armature. PMG meggers at 9.62GMOhms, winding resistances are below 0.0062 Ohms.
9/29/2014	-	Siemens performs Exciter testing on the Unit 4 Exciter as part of the 1R PMRQ 50551-42 (WO 40213082). No deficiencies observed on weather seals. PMG meggers at 10MOhms, winding resistances are below 0.0059 Ohms. No task was found where the Exciter housing was removed, reinstalled and base sealing was inspected or performed.
4/2/2016	-	Siemens performs Exciter testing on the Unit 4 Exciter as part of the 1R PMRQ 50551-42 (WO 40370429). No deficiencies observed on weather seals. PMG meggers at 1.18GOhms, winding resistances are below 0.0059 Ohms. No task was found where the Exciter housing was removed, reinstalled and base sealing was inspected or performed.
10/10/2017	-	Siemens performs Exciter testing on the Unit 4 Exciter as part of the 1R PMRQ 50551-42 (WO 40497050). The top of the Exciter housing was found with opening that could allow for leaks above the diode wheel. Report states repairs are expected to be performed by FPL. PMG meggers at 1MOhms, winding resistances are below 0.0059 Ohms.
10/25/2017	-	WO 40497050-02 performs inspection of the U4 Exciter Door Seals and hardware. All seals were found in good condition. This work did not require the housing to be removed. Sealing of the base was not inspected or performed.
3/21/2019	-	Refurbished Exciter Rotor is installed on Unit 4 as part of 5R PMRQ 50551-39 (WO 40642780).
3/21/2019	-	Siemens performs Exciter testing on the Unit 4 Exciter as part of the 5R PMRQ 50551-56 (WO 40642780). The Exciter housing was inspected for signs of damage and wear. Seals were inspected for hardness and fit. Several teardrop seals were found hard and torn. Windows and doors were inspected for cracks and signs of degradation and found to be in satisfactory condition. The end wall coupling air seal was found with large clearances. Degraded seals were replaced. PMG electrical tests results are satisfactory. PMG meggers at 232 M/Ohms, winding resistances measure below 0.0059 Ohms. Siemens concluded equipment was acceptable for return to service.
3/21/2019		PT4-31 RFO Activities: 1. PMG Stator (removed from base, inspected, insulation resistance

FPSC EXH No. 5
03/18/2024
NEXTera ENERGY
ADMITTED

		measured) 2. AC Exciter Stator (disassembled, horizontally split for rotor removal and inspected, insulation resistance, pole balance and impedance calc. of field winding and resistance measured) 3. AC Exciter Armature (Including Diode Wheels and PMG Pole Support, insulation resistance w/rotor install-diode wheels to shaft and to diode wheel, replacement of complete rotating element with a spare (complete rotor overhaul at Siemens) PMG pole support w/magnets, AC Armature, diode wheels)).
8/11/2019	0840	H.B. Robinson Nuclear Plant (RNP) Unit 2 experiences an automatic trip caused by a failure of the Generator Exciter Armature. The Root Cause Evaluation concluded the precise cause of failure is indeterminate. However, the failure was most likely attributed to a latent failure of the exciter armature due to either coil or core failure.
9/9/2019	-	Level 1 Assessment AR 2327198 for Fleet Exciter PM/Spare is issued in response to the H.B. Robinson event. The Level 1 Assessment identifies Exciter windings (both stationary and rotating) at PTN have not been rewound since installation. Assessment recommends rewinding of Exciter rotating and stationary windings based on age of components. 5R Exciter overhaul PMs are recommended to include component rewind.
12/4/2019	-	PMC-19-006814 is initiated to create new 15R PMs to rewind both stationary and rotating Exciter windings.
2/3/2020	-	PMC-19-006814 is approved by supervision. PMC recommends the start date of new PMs align with the next scheduled 5R overhaul activities (PT3-32 and PT4-36). An action is assigned to PM coordinators to create new PMRQs for the Exciter rewind activities.
3/14/2020	-	New PMRQs 45986-58 (3K2) and 50551-60 (4K2) are activated with a 15R frequency and initial due dates of PT3-32 and PT4-36 to align with 5R overhaul activities.
Prior to Event Date		Various supplemental sealants historically used on Units 3 & 4 exciter housing to prevent water intrusion • Dowsil 732 • 3M 5200 Marine sealant • Duromar SAR-UW • Closed-Cell Foam (Last-A-Foam Model FRL 3704 or FRL 6704 by General Plastics Mfg. Co. or Equiv.) or Dymeric Caulk (or Equiv.) However, no supplemental sealant was found during the post event inspection.
7/5/2020	Various	Significant amount of lightning and storms with very heavy rain occurring during the afternoon. Several components alarmed for

FPSC EXH No. 5
03/18/2024
NEXTera ENERGY
ADMITTED

		trouble or ground or tripped.
7/5/2020	1844	Received AN-E-8/3: GEN CONTACT FIELD BRUSH CONTACT FAIL/GROUND.
7/5/2020	1850	Turbine Operator reports no observed water inside the Exciter housing.
7/5/2020	1900	Per 4-ARP-097.CR.E, the Turbine Operator depresses the RESET pushbutton above the generator field breaker and the following occurs: • AN-E-8/3 momentarily resets then re-alarms. • AN-E-9/3 GEN VOLT REG LOSS OF BACKUP alarms • AN-E-7/6 GEN VOLT REG TRANSFER TO MANUAL alarms AN-E-9/3 cleared as soon as it was acknowledged. AN-E-8/3 and AN-E-7/6 remain locked in.
7/5/2020	1901	The light indication at the Voltage Regulator switch on the Control Room console shows the red ON light off and the green OFF light on; indicating that the voltage regulator has swapped from AC regulator to the DC regulator.
7/5/2020	1930	During management call, Shift Manager reported water observed in the Voltage Regulator housing and herculite installed above housing. Shift Manager also reported that housing temperature was 68 deg F. Subject Matter Expert Hiten Patel stated to validate no alarms on local Voltage Regulator panel before swapping console switch from "On" to "Test"
7/5/2020	1940	Operations notifies System Dispatch of U4 AC Voltage Regulator automatic transfer to MANUAL (DC voltage regulator manual adjust). System dispatcher understands status of U4 AVR and generator voltage controls.
7/5/2020	2045	Operations reports one alarm on local Voltage Regulator panel: "Loss of XDCR No. 1"
7/5/2020	2050	Received annunciators AN-E-9/3 GEN VOLT REG LOSS OF BACKUP and AN-E-8/6 GEN VOLT REG TROUBLE several times. Reactive load on the Unit 4 Generator has moved up suddenly from 115 MVAR to 200 MVAR in the last 5-minutes.
7/5/2020	2100	Operations reports Exciter field volts are oscillating.
7/5/2020	2107	Unit 4 Reactor Trip caused by Turbine Trip (First Out). Investigated generator exciter switchgear control cabinet and found the following alarms: Power Supply #1 Power Supply #2 Firing Circuit #2 Loss of XDCR #1
7/8/2020		On 7/8/2020 the following was documented in the Siemens JWR attached to WO 40731687-08 (FAR 4,9,5 Remove / Install Exciter

FPSC EXH No. 5
03/18/2024
NEXTera ENERGY
ADMITTED


		housing): Performed visual inspection of Exciter housing door seals, partition seals and floor seals. All require replacement due to normal wear and environmental degradation. All doors need minor adjustments. Floor seals need to be replaced. All window seals appear to be in adequate condition. Partition seals need to be replaced.
7/18/2020		On 7/18/2020 the following was documented in the Siemens JWR attached to WO 40731687-08 (FAR 4,9,5 Remove / Install Exciter housing): Rigged and installed Exciter housing and torqued bolting. It was verified through the work order that the team used scotch grip 1300 rubber cement to attach the rubber strips between the Exciter housing and the mating surfaces. It was also verified that new 2" x 10' pieces were issued to the team to support replacement of the degraded rubber seals identified on 7/8/2020 entry above.
7/19/2020		MM was tasked with sealing the Exciter housing on U4. MM did this as skill of the craft. Discussions with the journeyman who performed the task verified that they sealed all removable hatches on top of the housing and the hold down bolts. The WR did not direct them to seal the lower sections where the housing sits on the rubber gaskets as shown in 0-GMM-090.1 Attachment 5.
7/29/2020 7/31/2020		BHI was asked to seal the U4 Exciter housing to the turbine deck. A work order was written on 7/29/2020 (WO 40731687-52) and the crew went to the field and sealed the area that was found to be sucking air. Discussions with the Site Coatings supervisor verified that on Friday 7/31/2020 the BHI team was directed to seal the entire bottom of the Exciter housing. The crew used a backing material and 5200 Marine caulking to seal the housing. One area of concern is that the work order does not reference 0-GMM-090.1 section 6.23.8 FPL Supervisor / Engineer verification step or direct the workers to use 0-GMM-090.1 Attachment 5 as a reference.
7/31/2020		On 7/31/2020 MM was tasked with sealing the Exciter housing on Unit 3. The crew worked to a minor work request (WR 94212618) which only stated "U3 Exciter doghouse bottom edge needs sealing". Again, the work documents did not capture the requirements shown in 0-GMM-090.1 relating to the proper way to seal the Exciter housing or the type of material to use. The team used clear RTV caulking. MM found that the U3 Turbine Exciter had not been sealed per 0-GMM-090.1 instructions. The team applied DOWSIL 732 multi-purpose sealant around the base of the housing to prevent water intrusion.
8/3/2020		Verified that damaged PMG stator was received at Siemens Charlotte facility on Friday 7/31/2020. No preliminary inspection results are available at his time.
8/3/2020		A follow-up with Siemens planning revealed that the Siemens work documents only have them inspect and replace degraded seals and then land and torque the housing down. It does not have them seal the

FPSC EXH No. 5
03/18/2024
NEXTera ENERGY
ADMITTED


		housing as outlined in the FPL procedure (0-GMM-090.1).

FPSC EXH No. 5
03/18/2024
NEXTera ENERGY
ADMITTED

Attachment 9: Potential Paths of Water Ingress



EXCITER HOUSING PLAN



FPSC EXH No. 5
03/18/2024

ADMITTED

C3-418

Florida Power & Light Company
Docket No. 20220001-EI
Staff's 2nd Set of Interrogatories
Interrogatory No. 4
Page 1 of 1

QUESTION:
The following questions are with respect to Florida Power & Light's (FPL or Company) Petition for Approval of Fuel Cost Recovery and Capacity Cost Recovery Net Final True-Ups for the Period Ending December 2021 and 2021 Asset Optimization Incentive Mechanism Results (Petition).

Please refer to the Direct Testimony of FPL witness Dean Curtland for the following question. Please provide the replacement power costs, if any, associated with the: July 2020 outage of Turkey Point Unit No. 4; November 2020 outage of Turkey Point Unit No. 3; January 2021 outage of St. Lucie Unit No. 2; March 2021 outage of Turkey Point Unit No. 3; May 2021 outage of St. Lucie Unit No. 1; and the August 2021 outage of Turkey Point Unit No. 3. Please also show how any replacement power cost amounts were calculated.

RESPONSE:
The replacement power cost for July 2020 outage of Turkey Point Unit No. 4 was $1,453,970; November 2020 outage of Turkey Point Unit No. 3 was $1,290,604; January 2021 outage of St. Lucie Unit No. 2 was $1,180,450; March 2021 outage of Turkey Point Unit No. 3 was $1,206,743; May 2021 outage of St. Lucie Unit No. 1 was $1,517,511; August 2021 outage of Turkey Point Unit No. 3 was $2,766,857. The calculations are provided in Attachment No. I to this Interrogatory. FPL applies the proportion of fuel used during the same period for each fuel type, as summarized on Schedule A3, to the amount of outage time, in hours, experienced. Fixed natural gas costs are removed from the calculation since those expenses have already been incurred.

C3-316

FPSC EXH No. 5
03/18/2024

ADMITTED

C3-419

NEXTera ENERGY



Turkey Point
Root Cause Evaluation
Unit 3 Trip During Restoration from RPS Testing

Event Date: March 1, 2021 CR 2385529

Revision 1

Root Cause Team	Name	Dept/Group
Management Sponsor	Bob Tomonto	Engineering
Team Leader/RC Evaluator	Bob Murrell	Licensing
Team Member	Luis Mazo	Maintenance
Team Member	Richard Jackson	Operations
Team Member	Robert Rodriguez	Training
Team Member	Orlando Carol	Engineering

Root Cause Evaluator: Bob Murrell/ RgMurrell Print/Sign **Date:** 7/20/21

Management Sponsor: Bob Tomonto/ Robert J. Tomonto Print/Sign **Date:** 7/28/21

MRC Chair: RgMurrell for Cashwell Print/Sign Per telecon **Date:** 7/29/21

Electronic Signature may be obtained by assigning actions in NAMS.

Refer to PI-AA-104-1000 for details.

The root cause process is designed to be self critical to drive improvement. As such, specific organizational and/or programmatic causes within the plant's span of control are identified. The root cause process determines a functional cause and not a legal or contractual cause.

C3-317

FPSC EXH No. 5
03/18/2024
ADMITTED

Unit 3 Reactor Trip During Restoration from RPS Testing
Root Cause Evaluation
Turkey Point

1.0 Problem Statement: 2
2.0 Executive Summary: 2
3.0 Event Details, Analysis, and Presentation of Findings: 4
4.0 Extent of Condition 11
5.0 Analysis of Risk and Safety Consequences 11
6.0 Barrier Analysis 12
7.0 Event and Causal Factor (E&CF) Analysis 13
8.0 Organizational and Programmatic (O&P) Analysis 13
9.0 Training Performance Analysis 13
10.0 Operating Experience (OE) Review 14
11.0 Safety Culture (SC) Analysis 15
13.0 Extent of Cause (EOCa) 15
14.0 Corrective Actions 16
15.0 Effectiveness Review 22
16.0 CRs Generated During the Common Cause Evaluation 23
17.0 Proof Statement and Lessons Learned 23
Attachments: 23
Attachment 1: Root Cause Evaluation Team Charter 24
Attachment 2: Extent of Condition Evaluation 25
Attachment 3: Extent of Cause Evaluation 27
Attachment 4: Operating Experience Analysis 30
Attachment 5: Support Refute Matrix 35
Attachment 6: Barrier Analysis 55
Attachment 7: Event and Causal Factor (E&CF) Analysis 60
Attachment 8: Organizational and Programmatic (O&P) Analysis 61
Attachment 9: Safety Culture (SC) Analysis 63
Attachment 10: Corrective Action Line of Sight (LOS) Table 65
Attachment 11: List of Documents Reviewed 68
Attachment 12: Industry Maintenance Practices on Cell Switches 69

FPSC EXH No. 5
03/18/2024
ADMITTED

1.0 Problem Statement:

On March 1, 2021 at 1112, Unit 3 experienced an unplanned automatic reactor trip during restoration of the 3B Reactor Protection System Logic Test, 3-SMI-049.02B (AR 2385529, WR 94220021). During performance of the SMI, the 3B Reactor Trip Bypass Breaker (BYB) is closed. As part of the restoration, the 3B Reactor Trip Breaker (RTB) breaker (Stamp 12) is closed and the BYB is locally tripped. When the BYB was tripped open, Unit 3 experienced an automatic reactor trip.

2.0 Executive Summary:

As a result of the unit trip, a Failure Investigation Process (FIP) team was established to conduct a post trip review prior to restarting the unit. The FIP team was not able to identify that cause of the trip but did identify several potential causes that this RCE evaluated in order to determine the root and contributing cause(s).

After completion of troubleshooting and replacement of the 3B Reactor Trip Breaker (RTB), Unit 3 was restarted.

Root/Contributing Causes:

RC1 - IAW 0-PME-049.01, steps for cleaning and lubricating cell switch contacts is conditional based, rather than prescriptive.

CC1 – Test points to detect failed contacts were not installed.

CC2 - Failure to follow WEC MPM cell switch maintenance and replacement frequency.

Corrective Actions:

Corrective Actions to Prevent Occurrence

CAPR1 - Revise procedure 0-PME-049.01 to require cleaning and lubrication of cell switch contacts.

Corrective Actions for Contributing Causes

CC1CA1 - Implement modification for Unit 4 to detect for standing trip signal from failed breaker cubicle cell switch contact. Scope modification into PT4-33 or the first available opportunity.

CC2CA1 - Replace cell switches in remaining Reactor Trip and Reactor Trip Bypass Breaker cubicles during upcoming refueling outages.

1. WR for Remaining Unit 3 Reactor Trip and Trip Bypass Breaker cubicles
2. Scope work into upcoming PT3-32 outage or the first available opportunity
3. WR for Unit 4 Reactor Trip and Trip Bypass Breaker cubicles

FPSC EXH No. 5
03/18/2024
ADMITTED

4. Scope work into upcoming PT4-33 outage or the first available opportunity

CC2CA2 – Create new PMID for Reactor Trip and Trip Bypass Breaker Cell Switch replacements and establish frequency commensurate with 100 cycle service life.

Corrective Actions for Extent of Cause (EOCa)

RC1 EOCa CA1 - Review maintenance procedures for Reactor Trip Breaker switchgear cubicles inspections for other conditional steps, which if not performed, can result in equipment failure. Revise procedures as necessary.

RC1 EOCa CA2 - Review maintenance procedures for CRDM MG set output breaker and Generator Field breaker cubicles inspections and ensure cleaning of cell switch contacts (if installed) is prescriptive. Revise procedures as necessary.

RC1 EOCa CA3 - Review maintenance procedures for Generator Field breaker cubicles inspections and ensure cleaning of cell switch contacts (if installed) is prescriptive. Revise procedures as necessary

RC1 EOCa CA4 - Review maintenance procedures for CRDM MG set output breaker and Generator Field breaker cubicles inspections for other conditional steps, which if not performed, can result in equipment failure. Revise procedures as necessary.

Corrective Actions for Extent of Condition (EOC)

RC1 EOC CA1 - Review Westinghouse Maintenance Program Manual (MPM) and ensure all components used in Reactor Trip Switchgear have a maintenance strategy established commensurate with the MPM.

RC1 EOC CA2 - Review Westinghouse Maintenance Program Manual (MPM) and ensure all components used for CRDM MG set output breaker and Generator Field applications have a maintenance strategy established commensurate with the MPM.

RC1 EOC CA3 - Review Westinghouse Maintenance Program Manual (MPM) and ensure all components used for the Generator Field applications have a maintenance strategy established commensurate with the MPM

CC1 EOC CA1 - Investigate whether a similar vulnerability exists for CRDM MG set output breaker and Generator Field breaker control circuits. Initiate ECs to install test points if necessary.

CC2 EOC CA1 - Create new PMID for CRDM MG set output breaker and Generator Field breaker cubicle cell switch replacements as necessary.

Other Corrective Actions

Other CA - Revise Reactor Protection System Surveillance Test Interval for Tech Spec Table 4.3-1, Functional Units Items 19, 20, 21 to 18 months.

FPSC EXH No. 5
03/18/2024
ADMITTED

3.0 Event Details, Analysis, and Presentation of Findings:

Investigation Scope and Methodology:

Perform a Root Cause Evaluation in accordance with PI-AA-100-1005. Analysis methodologies should include Barrier Analysis, Organizational and Programmatic Affects, Safety Culture Analysis, and Event and Causal Factors Charting.

Event Description/Problem Statement

Problem Statement

On March 1, 2021, at 1112, PTN Unit 3 automatically tripped during restoration from Reactor Protection System Testing 3-SMI-049.02B. The reactor trip was caused by an unknown failure of the 3B reactor trip breaker.

Event Description

The following is the timeline leading up to the event on March 1, 2021 (all actions occurred on day shift, times added where time stamps existed):

- Performed brief in the Control Room with Ops Supervision and I&C IAW OD-CO-044
- 10:13, entered T.S. Table 3.3.1 Action 8 for RPS Testing on B Train IAW 3-SMI-049.2B
- Closed in Reactor Trip Bypass Breaker B IAW 3-SMI-049.2B, Section 4.1.
- Performed Section 4 of 3-SIM-049.02B, Train B RPS Logic Test Above P-8
- Locally Verified Reactor Trip Breaker B properly RACKED IN by opening the cubicle door IAW steps 5.1.1.a and 5.1.1.b
- Reactor Operator CLOSES Reactor Trip Breaker B by holding Reactor Trip Reset pushbutton on the console for at least 3 seconds IAW step 5.1.1.d
- Check Reactor Trip Breaker 3B properly RACKED IN IAW 5.1.1.d
- Close Reactor Trip Breaker 3B cubicle door IAW 5.1.1.g
- Reactor Operator verifies that no reactor trip relays are tripped using DCS RPS SOE IAW 5.2
- 2 additional Reactor operators verify that BOTH Reactor Trip Breakers 3A and 3B are closed on the console and VPB
- Reactor Operator gives permission to perform steps 5.1.3-5.1.6
- Locally Verified Reactor Trip Breaker B RACKED IN and CLOSED IAW 5.1.3
- Locally Verified Reactor Trip Breaker A RACKED IN and CLOSED IAW 5.1.4
- Swapped protective cover from Reactor Trip Bypass Breaker 3B and placed over Reactor Trip Breaker B IAW 5.1.5
- Opened Reactor Trip Bypass Breaker 3B locally using mechanical trip pushbutton IAW 5.1.6
- 11:12:30.717 Turbine trip HDR Press 2/3
- 11:12:30.769 Reactor Trip breaker ‘A’ Opens

FPSC EXH No. 5
03/18/2024
ADMITTED

- 11:12:30.772 Reactor Trip Breaker 'B' Opens

The post trip Failure Investigation Process (FIP) team investigation was not able to identify the cause of the trip with complete certainty. A review of the sequence of events (SOE) identified that the turbine trip signal came in before the reactor trip signal. In review of the associated logic drawings, the two likely breaker parameters that would result in a turbine trip are the auxiliary contact from the RTB breaker, and the RTB cell switch (TOC) associated with the relay 94/ASB. For the 3B RTB, both the breaker and the cell switch have been replaced.

Cause Analysis

RTB Maintenance History

The Turkey Point RTBs and BYBs are DB-50 breakers originally supplied from Westinghouse Electric Corporation (WEC).

As part of the FIP investigation, Maintenance and Engineering reviewed the Unit 3 and 4 Reactor trip breaker maintenance strategy, testing, and history. A summary of work order review and PM strategy for Turkey Point reactor trip breakers was developed in Table 1 showing maintenance frequency requirement for these breakers. Table 2 shows last performed dates of each PM.

In addition to the frequencies, the scope of each PM was reviewed to ensure that PTN work orders covered the recommendations established by Westinghouse maintenance program manual for the DB breakers. The Site procedure that covers maintenance aspects is 0-PME-049.01, Reactor trip and trip bypass breaker inspection and maintenance. Overall the maintenance strategy is based on cycles. The reactor trip breakers cycle more often than the bypass breakers hence the importance for breaker overhaul frequency.

Table 1: Frequencies

Maintenance type	**OEM/EPRI frequency**	**Site frequency**
Breaker Test/inspection	200 operations or 18 months	18 months
Breaker Overhaul	8 – 12 yrs. (4,000 operations)	8 yrs. plus grace
Cubicle inspection	5 yrs.	18-month

Table 2: Current PM status

Component	**Last performed Test/inspection**	**Last Breaker Overhaul**	**Last Cubicle inspection**

FPSC EXH No. 5
03/18/2024
ADMITTED

3A Reactor trip breaker	4/2020	3/2011	4/2020
3A Reactor trip bypass breaker	4/2020	2005	4/2020
3B Reactor trip breaker	4/2020	4/2012	4/2020
3B Reactor trip bypass breaker	4/2020	2019	4/2020
4A Reactor trip breaker	10/2020	10/2017	10/2020
4A Reactor trip bypass breaker	10/2020	9/2020	10/2020
4B Reactor trip breaker	10/2020	9/2020	10/2020
4B Reactor trip bypass breaker	10/2020	9/2020	10/2020

Maintenance and engineering representatives on the FIP team reviewed work scope against the maintenance scheduled recommendations and concluded the following:

Both Unit 3 RTBs have been overhauled by WEC in their required 8 to 12 years periodicity. Current time since their last full overhaul is 8 years for 3B and 9 years for 3A. The 18-month inspection is performed through our procedures with EM resources. The scope of the 18-month PM matches the vendor recommendations for checks at an 18-month frequency. Based on WEC reports they do incorporate their WCAPs into the overhaul and parts replacements.

As part of the RCE investigation,

Actions Taken by FIP Team

The following table lists the Work Orders (WOs) and Field Action Request (FARs) completed as part of the initial investigation.

WO40766915-01 FAR 1	The purpose of this work order task was to monitor contact change of state on the RTB B breaker installed in cubicle.
WO40766915-02 FAR 2	The purpose of this work order task was to perform RTB and BYB RTB cubicle inspections. This task was performed as per procedure 0-PME-049.01 Section 4.25. Cubicles were inspected for cracking, overheating and paths which could track to ground. As per journeymen report, no issues were noted.
WO40766915-03 FAR 3 (FAR 5&6 were performed	The purpose of this work order task was to inspect the removed RTB. Inspection was performed per 0-PME-049.01. As per journeymen report, no issues were noted, auxiliary switch contacts were found to meet their acceptance criteria.

FPSC EXH No. 5
03/18/2024
ADMITTED

during this inspection.)	
WO40766915-04 FAR 4	The purpose of this work order task was to perform Control Voltage check for UVTA Coil. As per journeymen report voltages were satisfactory.
WO40766915-05 FAR 7	The purpose of this work order task was to inspect Reactor Trip Breaker B Cubicle and replace the 2 Cell Switches mounted on the bottom rear of the cubicle. In addition, this work order checked voltages that satisfy EC295954 PMT for train B. Voltage checks were performed after replacement with satisfactory results.
WO40766915-06	Task was canceled.
WO40766915-07 FAR 9	The purpose of this work order task was to inspect the cell switches located on the bottom rear of the RT Breaker A, Bypass Breaker A and Bypass Breaker B cubicles. In addition, this work order checked voltages that satisfy EC295954 PMT for train A. Results were sat.
WO40766915-08 FAR 8 EC40766915	The Purpose of this work order task was to install permanent U3 reactor trip and bypass breakers contacts test points to support RPS testing. Modification was completed with SAT PMT.

Westinghouse Investigation Results

Westinghouse Electric Company (WEC) conducted an exhaustive inspection and testing of the 3B RTB in order to identify any equipment related condition that could explain the cause of the RTB malfunction. WEC performed a formal failure analysis.

See Enclosure 1 for the complete WEC report.

WEC Failure Analysis Conclusions:

> The breaker was received in very good condition and properly lubricated. This breaker as received was acceptable for use. The possible cause of failure could have been the bent breaker lock-out tabs on the front of the operating mechanism, they were found to be slightly bent, however the breaker operated without incident during all mechanical and electrical testing.
>
> The cell switches appeared to be original supplied equipment. They were not properly maintained, and the hardened lubrication could cause the stationary contacts to become dislodged, as documented above. In addition, to contributing to the dislodging the stationary contacts, excess or dry grease can cause improper indications from the switch contacts. This could be considered a possible cause of failure.

WEC Recommendations:

> It is recommended that the breaker be handled outside the switchgear cubicle with additional care. The breaker lock-out tabs on the front of the operating mechanism can cause the breaker not to function properly.

FPSC EXH No. 5
03/18/2024
ADMITTED

Please remove the Lock-Out Bar before testing and use of the breaker. It is also recommended that all DB breakers receive the attention during maintenance that this breaker has received.

The cell switches have a few areas of concern and recommendations will be provided for each concern.

If these were the original cell switches that were provided with the switchgear, it is recommended that they be replaced with safety related switch assemblies provided by Westinghouse Electric Company.

> P/N: 302C517G01 Y, please include the proper switch configuration with your orders.

The Maintenance Program Manual for Westinghouse Safety Related Type DB Circuit Breakers and Associated Switchgear, Revision 1, July 2011 defines that the DB cell switch is a Category B item and the procedure provided should not exceed 5 Years. These requirements are included in Section 7.3, Item 6. The two cell switches provided for this investigation appeared to be beyond the 5-year requirement based on the hardening of the graphite grease on the switch contacts.

In addition, the spring and plunger of the cell switch may be lubricated per the recommendations in the MPM manual, Chapter 9. It is acceptable to apply 53701GW lubricant to the spring during maintenance intervals. Furthermore, the 53701GW lubricant can be applied to the cell switch plunger's penetration point through the mounting plate. The cell switches included in this investigation did not have any lubrication applied to the spring and the plungers were lubricated with a foreign type grease.

It is recommended that after the cell switches are replaced that they be maintained to the requirements provided in the Maintenance Program Manual for Westinghouse Safety Related Type DB Circuit Breakers and Associated Switchgear, Revision 1, July 2011.

After a detailed review of the data from the RTB maintenance history, WEC investigation and the FIP team actions, causal analysis was completed to determine the root and contributing causes for this event. The analysis included a Support/Refute Matrix (Attachment 5), Barrier Analysis (Section 6 and Attachment 6), Event and Causal Factor Chart (Section 7 and Attachment 7), and an Organization and Programmatic Assessment (Section 8 and Attachment 8).

FPSC EXH No. 5
03/18/2024
ADMITTED

Discussion on bent breaker lock-out tabs:

Although the WEC report states bent breaker lock-out tabs is a possible cause of failure for DB-50 breakers, the RCE team did not find any supporting evidence that the bent breaker lock-out tabs were causal to this event. The WEC report also stated the following:

> "These photos show that without the face plate attached to the operating mechanism the Push to Trip button is free to fall below its normal position. This is not a concern as it shows that the tabs are not tight enough to hold the Push to Trip button."

In addition, FAR 06 performed numerous cycling of the breaker once removed from the cubicle. The Trip Pushbutton was used to open the circuit breaker. No mechanical binding or resistance was noted, and no other issues were identified during cycling. If bent breaker lock-out tabs were the cause of the event, it would be expected that the first alarm to come in following the Unit trip in the SOE report would be 'RX TRIP BKR B OPEN'. Instead, the turbine trip alarms came in first and the reactor trip breakers were opening in response to the event. See section of SOE report below:

```
LOG PRINT DATE: 03/01/21 11:12:49
Sequence of Events (NEW)
LOG DATE: 03-01-21 11:12:48
03-01-21 11:12:30.716 3SOE_01:E301S16.TBASOLC2_A      ALARM   TURB TRIP HDR PRESS CHNL 2
03-01-21 11:12:30.717 3SOE_01:E301S16.TBASOL23_A      ALARM   TURB TRIP HDR PRESS 2/3
03-01-21 11:12:30.718 3SOE_01:E301S16.TBASOLC1_A      ALARM   TURB TRIP HDR PRESS CHNL 1
03-01-21 11:12:30.718 3SOE_01:E301S16.TBASOLC3_A      ALARM   TURB TRIP HDR PRESS CHNL 3
03-01-21 11:12:30.725 3SOE_01:E301S12.RT9_10RL_A      ALARM   RT 9 & 10 RELAYS
03-01-21 11:12:30.728 3SOE_01:E301S16.ASTPT_A_A       ALARM   AUTO SHUNT TRIP TEST A
03-01-21 11:12:30.730 3SOE_01:E301S16.ASTPT_B_A       ALARM   AUTO SHUNT TRIP TEST B
03-01-21 11:12:30.769 3SOE_01:E301S17.RXTPBKA_A       ALARM   RX TRIP BKR A OPEN
03-01-21 11:12:30.772 3SOE_01:E301S17.RXTPBKB_A       ALARM   RX TRIP BKR B OPEN
```

Discussion on MPM cell switch 100 cycle recommendation and Industry Practices:

Westinghouse MPM recommends a service life of 100 cycles for cell switches. PTN currently does not have a 100 cycle replacement PM in place and only performs inspections every 18 months. To gather information on industry practices for Westinghouse DB-50 cell switches, PTN polled the Circuit Breaker Users Group (CBUG). Three plants responded and only one plant has a replacement PM in place. Procedure steps from other sites were reviewed and they are similar to what is performed at PTN. Deficiencies in PTN procedures were noted when compared to other sites and include lack of plunger and spring lubrication, and confirmation of free movement of the plunger when actuated. Procedure 0-PME-049.01 should be enhanced to include these steps.

The industry review demonstrates that the majority of sites are crediting inspection PM's for continued reliability of the cell switches and are extending the recommended service life of 100 cycles. This is in line with the recommendations provided in the Westinghouse MPM which states:

> *With proper maintenance and inspections of the circuit breaker and cell at the interval recommended the breaker and cell values can be exceeded as addressed later in this section. The service/cycle life of the DB circuit breaker and its components are based on industry*

FPSC EXH No. 5
03/18/2024
ADMITTED

standards, testing and analysis. Westinghouse does not recommend these components be considered run-to-failure components, however with proper maintenance and inspection of the breaker and cell components, the recommended lives could be justified beyond the values provided.

The basis for the design life of the cell switch, primary finger clusters and the secondary contacts is American National Standards Institute/Institute of Electrical and Electronics Engineers (ANSI/IEEE) C37.20.1-1987, "An American National Standard, IEEE Standard for Metal-Enclosed Low-Voltage Power Circuit-Breaker Switchgear," subsection 5.2.5. This section defines a low voltage (LV) switchgear with draw-out circuit breakers shall have mechanical endurance test cycles consisting of at least 100 operations between connected and test position. With proper maintenance and analysis of the components the 100 operation/cycle life of the cell components could be extended. The end of life condition of these components is not known. The switch that is used as the cell switch is the same switch used as an auxiliary switch on the DB breaker with a qualified life of 4,000 cycles on the DB-50 breaker. The remaining components of the cell switch consist of a metal frame, a metal operations bar and a metal return spring. None of these components are sensitive to age within 100 cycles.

If proper maintenance has been performed the breakers and cell components will operate beyond the service life recommendation. However, the support for the extended service life will be based on the documentation for those parts that have been collected during the maintenance activities.

This review demonstrates that PTN is not an outlier with regards to maintenance practices for Westinghouse DB-50 cell switches. Although, there is no 100 cycle replacement PM in place, the cell switches are being maintained via routine 18 month inspections which allows for extended service life.

Direct Cause:

While no exact direct cause was identified, the RCE team determined the most probable direct cause was hardened graphite grease on the cell switch #2 contact 1-2 causing a tracking path which incorrectly indicated the contact was closed when the contact was in an open state.

Root Cause:

RC1 - IAW 0-PME-049.01, steps for cleaning and lubricating cell switch contacts is conditional based, rather than prescriptive.

Conclusion:

DB-50 breakers and switchgear cubicles are inspected in accordance with 0-PME-049.01 which provides a methodical and proven approach to maintain the equipment. However, steps to clean and lubricate the cell switch contacts located inside the cubicle are conditional based, rather than prescriptive. This can lead to lack of proper cleaning of the cell switch and relies on skill of the craft and judgement of the journeyman performing the

FPSC EXH No. 5
03/18/2024
ADMITTED

inspection. A review of 0-PME-049.0.01 revision history showed that this procedural deficiency has existed since issuance of Rev 0 of the procedure in August 2009.

Contributing Causes:

CC1 - Test points to detect failed contacts were not installed.

Conclusion:

Point Beach modified their Reactor Trip and Trip Bypass breaker circuits circa 1984 in response to Generic Letter 83-28 to meet the Westinghouse Owner's Group (WOG) recommendations. The modification included test points upstream of their turbine trip relay. However, these test points were not part of the WOG recommendations. Therefore, these test points were a unique PB design. This is considered a legacy issue and would not have been identified as part of OE reviews.

CC2 - Failure to follow WEC MPM cell switch maintenance and replacement frequency.

Conclusion:

Procedure 0-PME-049.01 was developed using Westinghouse vendor manual V000211, and Westinghouse Maintenance Program Manual MPM-DB for Safety Related DB-50 Circuit Breakers and Associated Switchgear, E224A. All criteria in the site procedure meet vendor recommendations, with the exception of cell switch recommended life. Procedure does not check for cell switch cycles. There is no established PM for cell switch replacement.

4.0 Extent of Condition

The EOC was completed for this event. Corrective actions are required for Reactor Trip Breaker, Bypass Breakers, CRDM MG Set Output Breaker, and Main Generator Field Breaker Cell Switches. See Attachment 2 for full details.

5.0 Analysis of Risk and Safety Consequences

As documented in the Post Trip Review Restart Report for the U3 reactor trip, there were equipment issues related to the transient. Below is a summary of each.

- Steam dump to condenser valve, CV-3-2830, was slow to close and remained open when the other dump valves closed (AR 2385531).
- The 3A RCP had a locked in high pressure alarm (AR 2835559).
- The 3B RCP vertical vibrations increased from 11.5 mils to a peak of 16.5 mils before finally lowering to 12.5 mils (AR2385558).
- A TCS System Fault alarm associated with a chassis failure (AR 2385558).
- The U3 hotwell sample pumps tripped off (AR 2385565)

FPSC EXH No. 5
03/18/2024
ADMITTED

The equipment issues noted had no impact on environmental, radiological, or nuclear safety. In addition, there were no personnel safety issues associated with the event. Therefore, there were no adverse safety consequences related to the event.

The RCE team also reviewed whether the issues associated with the cell switches could lead to the breakers not opening on a open demand signal. The cell switch contacts in the Reactor Trip A and B applications are not wired to the OPEN circuits of the breakers. Therefore, the condition identified would not have prevented these breakers from opening on demand. With regards to the Reactor Trip Bypass A and B breakers, the cell switches are wired to the OPEN circuits for local manual tripping, and trip interlock circuits which prevent both Bypass A and B breakers from being racked in and closed at the same time. This interlock function is considered a backup function to administrative barriers which prevent both Bypass breakers from being racked in and closed at the same time.

This event is reportable to the NRC pursuant of 10 CFR 50.73(a)(2)(iv).

6.0 Barrier Analysis

A barrier analysis was completed as part of the causal analysis for this root cause evaluation. The following Hazard, Barriers, and Targets were evaluated:

Hazard	Barrier	Target
Quarterly Reactor Trip Testing performed IAW 3-SMI-049.02B results in a reactor trip.	Train Separation / Channel Redundancy	Successful surveillance test without automatic reactor trip.
	Plastic Barrier on Reactor Trip Breakers	
	Train Separation	
	Procedural surveillance testing	
	Training and Qualifications	
	Review and Incorporation of Fleet OE	
Westinghouse DB-50 Breaker and Cubicle Maintenance is inadequate to prevent breaker or cubicle reliability issues.	Procedural inspections	Breakers and cubicle perform reliably without issues.
	Preventive Maintenance Program Established	
	Training and Qualifications	
	Vendor Recommendations Incorporated	

<u>Barrier Analysis Summary</u>

The analysis identified one root cause and two contributing cause.

See Attachment 6 for more detail.

FPSC EXH No. 5
03/18/2024
ADMITTED

7.0 Event and Causal Factor (E&CF) Analysis

An E&CF chart was developed as part of the causal analysis. This technique was used in support of the barrier analysis to provide a means to graphically display the relationship between the sequence of events, inappropriate actions (IAs), and failed or weak barriers.

See Attachment 7 for more details.

8.0 Organizational and Programmatic (O&P) Analysis

The Root Cause Evaluation team identified Programmatic weaknesses that were causal to this event. Specifically, procedural inspections, implementation of WEC recommendations and the failure to install test points were all Programmatic issues.

See Attachment 8 for full details.

9.0 Training Performance Analysis

The RCE team performed a Training Analysis in order to determine if there were training gaps/deficiencies that could have contributed to this event. This review analyzed the training from both the maintenance training and operations training perspectives.

From the maintenance training perspective, every task that the Electrical Maintenance (EM) Technicians perform is analyzed and reviewed periodically (in accordance with the Maintenance ACAD requirements). As part of the Job Analysis, the Difficulty, Importance, and Frequency (DIF) is evaluated with the incumbents' input (normally 2 Senior Technicians, 2 Experienced Technicians, and 2 Junior Technician participate in the DIF process). The latest Task List Review/Job Analysis for the EM Training Program was approved on 10/08/2019. "Reactor Trip Breaker (Westinghouse DB-50) Maintenance", which is an Advanced Site-Specific Qualification (Block 4), DIF'd as "no retraining", due to the analyzed Difficulty, Importance, and Frequency of the task. Furthermore, racking in/out the RTB is not an EM task; this task belongs to Operations.

With regards to improper cleaning of cell switches in the DB-50 switchgear, Maintenance noted that the switches are difficult to get to even with a clearance on the equipment established, making inspection and cleaning of the cell switch contacts prohibitive. Therefore, the fact that the cell switches were found in a less than desirable condition does not reflect a weakness in Maintenance staff proficiency and is not considered a low level contributing cause to the event.

From the Operations Training perspective, likewise, every task that the Non-Licensed Operators perform is analyzed and reviewed periodically (in accordance with the Operations ACAD requirements), utilizing the same Task List Review/Job Analysis process delineated above. The "Rack-In & Out the Reactor Trip & Bypass Breakers" Qualification

FPSC EXH No. 5
03/18/2024
ADMITTED

DIF'd as "no retraining", due to the analyzed Difficulty, Importance, and Frequency of the task. The latest Task List Review/Job Analysis for the PTN Non-Licensed Operator Training Program was approved on 08/02/2019.

Based on the training analysis performed by the RCE team, training was not found to be a contributor to this event.

10.0 Operating Experience (OE) Review

The Institute of Nuclear Power Operations (INPO) Industry Reporting and Information System (IRIS) database was searched for keywords 'reactor trip breaker.' This search yielded 79 events of which 14 were screened as being relevant to this event. None of the 14 events were evaluated as OE by the site. This is aligned with the requirements of PI-AA-102-1001, Operating Experience Program Screening and Responding to Incoming Operating Experience. Since the OE was not of a high enough level to screen into the PTN OE program, there was no failure of the OE program. See Attachment 4 for a complete list of OE reviewed.

A review of LERs from the past 5 years did not identify any reactor trips related to Reactor Trip Breaker malfunctions, therefore, this is not a repeat event.

IER L2-11-2 Scram Analysis

Per LI-AA-100-1005, a review of PTN's response to INPO IER L2-11-2, 2009 – 2010 Scram Analysis, is required since this event resulted in a reactor scram. PTN's response to IER L2-11-2 is documented under CR 1673959. The IER recommendations related to the cause of this event (less than adequate maintenance procedure guidance for cleaning and lubricating RPS cell switch contacts) are contained under Maintenance recommendations. The specific recommendation was to evaluate work instructions and maintenance technical procedure details that involve SPVs, critical components, and systems that have contributed to 5 percent or more to scrams for PWRs. Attachment 5 to the IER shows that RPS contributed to > 5 percent of PWR scrams. PTN's response limited the RPS SPVs to the following:

- RPS Eagle 21
- RPS Hagan Controllers
- RPS AC Relays

Since the site response to the IER did not contain SPVs associated with RTB, RBB, and their associated cell switches, there is a gap in the response. Actions will be generated out of this RCE to revise the sites IER response. Note that corrective actions from this RCE close the gaps that would have been identified if the IER response included the RPS cell switches.

FPSC EXH No. 5
03/18/2024
ADMITTED

11.0 Safety Culture (SC) Analysis

The following aspects were determined to be actual or potential weaknesses contributing to the cause of this event. Corrective actions to address the root and contributing causes of this event address these safety culture aspects. See Attachment 9 for the detailed Nuclear Safety Culture Evaluation Table.

H.1	Resources: Leaders ensure that personnel, equipment, procedures, and other resources are available and adequate to support nuclear safety (LA.1).	This is directly tied to RC1.

13.0 Extent of Cause (EOCa)

Extent of Cause Summary Results:

The Root Cause Evaluation team completed an Extent of Cause (EOCa)evaluation for the root cause of this event. The team identified two corrective actions to address EOCa.

RC1 EOCa CA1 - Review maintenance procedures for Reactor Trip Breaker switchgear for other conditional steps, which if not performed, can result in equipment failure. Revise procedures as necessary.

RC1 EOCa CA2 - Review maintenance procedures for CRDM MG set output breaker and Generator Field breaker cubicles inspections and ensure cleaning of cell switch contacts (if installed) is prescriptive. Revise procedures as necessary.

RC1 EOCa CA3 - Review maintenance procedures for CRDM MG set output breaker and Generator Field breaker cubicles inspections for other conditional steps, which if not performed, can result in equipment failure. Revise procedures as necessary.

See Attachment 3 for analysis details.

FPSC EXH No. 5
03/18/2024
ADMITTED

14.0 Corrective Actions

Causes	NAMS #	Corrective Actions to Prevent Occurrence	Assigned Dept. or Individual and Due Date
RC1 - IAW 0-PME-049.01, steps for cleaning and lubricating cell switch contacts is conditional based, rather than prescriptive.	CAPR 2385529-27	Revise procedure 0-PME-049.01 to require cleaning and lubrication of cell switch contacts.	Juan Pallin Due 5/21/2021
	CA 2385529-28	Revise procedure 0-PME-049.01 to require Engineering be notified in order to observe the cleaning and lubricating of the cell switch contacts as revised in CAPR 2385529-27. This step will be annotated with a note stating the step can be removed from the procedure once.	Juan Pallin Due 5/21/2021

FPSC EXH No. 5
03/18/2024
ADMITTED

Corrective Actions for Contributing Causes			
Causes	**NAMS #**	**Assignment Description**	**Assigned Dept. or Individual and Due Date**
CC1 - Test points to detect failed contacts were not installed.	CA 2385529-29	Implement modification for Unit 4 to detect for standing trip signal from failed breaker cubicle cell switch contact. Scope modification into PT4-33 or the first available opportunity.	Rafael de la Torre Due 7/30/2021
CC2 - Failure to follow WEC MPM cell switch maintenance and replacement frequency.	CA 2385529-30	Replace cell switches in remaining Reactor Trip and Reactor Trip Bypass Breaker cubicles during upcoming refueling outages. 1. WR for Remaining Unit 3 Reactor Trip and Trip Bypass Breaker cubicles 2. Scope work into upcoming PT3-32 outage or the first available opportunity. 3. WR for Unit 4 Reactor Trip and Trip Bypass Breaker cubicles 4. Scope work into upcoming PT4-33 outage or the first available opportunity	Juan Pallin Due 5/7/2021

FPSC EXH No. 5
03/18/2024
ADMITTED

Corrective Actions for Contributing Causes			
Causes	**NAMS #**	**Assignment Description**	**Assigned Dept. or Individual and Due Date**
	CA 2385529-31	Create new PMID for Reactor Trip and Trip Bypass Breaker Cell Switch replacements and establish frequency commensurate with 100 cycle service life.	Rafael Leavitt Due 5/27/2021
Extent of Cause Corrective Actions			
Causes	**NAMS #**	**Assignment Description**	**Assigned Dept. or Individual and Due Date**
EOCa for RC1 IAW 0-PME-049.01, steps for cleaning and lubricating cell switch contacts is conditional based, rather than prescriptive.	CA 2385529-32	Review maintenance procedures for Reactor Trip Breaker switchgear cubicles inspections for other conditional steps, which if not performed, can result in equipment failure. Revise procedures as necessary.	Rafael Leavitt Due 7/30/2021
EOCa for RC1 IAW 0-PME-049.01, steps for cleaning and lubricating cell switch contacts is conditional based, rather	CA 2385529-33	Review maintenance procedures for CRDM MG set output breaker and Generator Field breaker cubicles inspections and ensure cleaning of cell	Ramiro Duarte Due 7/30/2021

FPSC EXH No. 5
03/18/2024
ADMITTED

Corrective Actions for Contributing Causes			
Causes	**NAMS #**	**Assignment Description**	**Assigned Dept. or Individual and Due Date**
than prescriptive		switch contacts (if installed) is prescriptive. Revise procedures as necessary.	
	CA 2385529-34	Review maintenance procedures for Generator Field breaker cubicles inspections and ensure cleaning of cell switch contacts (if installed) is prescriptive. Revise procedures as necessary.	Randy Kerkes Due: 7/30/21
EOCa for RC1 IAW 0-PME-049.01, steps for cleaning and lubricating cell switch contacts is conditional based, rather than prescriptive.	CA 2385529-35	Review maintenance procedures for CRDM MG set output breaker and Generator Field breaker cubicles inspections for other conditional steps, which if not performed, can result in equipment failure. Revise procedures as necessary.	Randy Kerkes Due: 7/30/21

FPSC EXH No. 5
03/18/2024
ADMITTED

Extent of Condition Corrective Actions			
Causes	**NAMS #**	**Assigned Description**	**Assigned Dept. or Individual and Due Date**
EOC for RC1 - Failure to follow WEC MPM cell switch maintenance and replacement frequency for Reactor Trip Breakers.	CA 2385529-36	Review Westinghouse Maintenance Program Manual (MPM) and ensure all components used in Reactor Trip Switchgear have a maintenance strategy established commensurate with the MPM.	Rafael Leavitt Due 7/15/2021
	CA 2385529-37	Review Westinghouse Maintenance Program Manual (MPM) and ensure all components used for CRDM MG set output breaker and Generator Field applications have a maintenance strategy established commensurate with the MPM.	Ramiro Duarte Due 7/15/2021
	CA 2385529-38	Review Westinghouse Maintenance Program Manual (MPM) and ensure all components used for the Generator Field applications have a maintenance strategy established commensurate with the MPM.	Randy Kerkes Due 7/15/2021
EOC for CC1 - Failure to incorporate PB/GL 83-28 action of installing test points.	CA 2385529-39	Investigate whether a similar vulnerability exists for CRDM MG set output breaker and Generator Field breaker control circuits. Initiate ECs to install test points if necessary.	Rafael Leavitt Due 6/30/2021

FPSC EXH No. 5
03/18/2024
ADMITTED

Extent of Condition Corrective Actions			
Causes	**NAMS #**	**Assigned Description**	**Assigned Dept. or Individual and Due Date**
EOC for CC2 - Failure to follow WEC MPM cell switch maintenance and replacement frequency.	CA 2385529-40	Create new PMID for CRDM MG set output breaker and Generator Field breaker cubicle cell switch replacements as necessary.	Rafael Leavitt Due 5/27/2021
Other Corrective Actions			
NAMS #	**Assignment Description**		**Assigned Dept. or Individual and Due Date**
CA 2385529-41	Revise Reactor Protection System Surveillance Test Interval for Tech Spec Table 4.3-1, Functional Units Items 19, 20, 21 to 18 months.		Michael Murphy Due 6/30/2021
CA 2385529-42	Revise PTN's response to INPO IER L2-11-2, 2009 – 2010 Scram Analysis per Section 10.0, Operating Experience.		Bob Hess Due 6/30/2021

FPSC EXH No. 5
03/18/2024
ADMITTED

15.0 Effectiveness Review

Number:	EFR 2385529-XX		
Corrective Action:	**CAPR1 -** Revise procedure 0-PME-049.01 to require cleaning and lubrication of cell switch contacts. Note – If Effectiveness review determines the CAPR was effective, 0-PME-049.01 can be revised to not require observation of cleaning and lubrication of the cell switches. This step was added to ensure the CAPR was adequately addressed by the procedure revision to 0-PME-049.01.		
Method:	Review of U3 and U4 reactor trip breaker and bypass breaker cell switch inspection results		
Attributes:	Cell switches have been adequately lubricated		
Success:	All of U3 and U4 Reactor Trip and Trip Bypass Breakers cell switches are lubricated properly		
Timeliness:	Complete final effectiveness review 3 years after completion of corrective actions		
Owner Group:	Christopher Boyd	**Due Date:**	6/30/2022

FPSC EXH No. 5
03/18/2024
ADMITTED

16.0 CRs Generated During the Common Cause Evaluation

CR Number	Description
NA	NA

17.0 Proof Statement and Lessons Learned

Proof Statement

The Unit 3 trip **was caused by** inadequate procedure guidance in 0-PME-049.01 for cleaning and lubricating cell switch contacts. **and is corrected by** revising procedure 0-PME-049.01 to require cleaning and lubrication of cell switch contacts.

Lessons Learned

Lessons learned from this Root Cause Evaluation team are captured in the causal analysis and associated corrective actions.

Attachments:

Attachment 1: Root Cause Evaluation Team Charter

Attachment 2: Extent of Condition Evaluation

Attachment 3: Extent of Cause Evaluation

Attachment 4: Operating Experience Analysis

Attachment 5: Support Refute Matrix

Attachment 6: Barrier Analysis

Attachment 7: Event and Causal Factor (E&CF) Analysis

Attachment 8: Organizational and Programmatic (O&P) Analysis

Attachment 9: Safety Culture (SC) Analysis

Attachment 10: Corrective Action Line of Sight (LOS) Table

Attachment 11: List of Documents Reviewed

Attachment 12: Industry Practices on Cell Switch Maintenance

FPSC EXH No. 5
03/18/2024
ADMITTED

Attachment 1: Root Cause Evaluation Team Charter

Root Cause Charter

Facility/CR Number: PTN / CR# 2385529
Manager Sponsor: Bob Tomonto

Event Description: Reactor Trip During Restoration from RPS Testing

Problem Statement: On March 1, 2021, at 1112, PTN Unit 3 automatically tripped during restoration from Reactor Protection System Testing 3-SMI-049.02B. The reactor trip was caused by an unknown failure of the 3B reactor trip breaker.

Preliminary Extent of Condition: The preliminary Extent of Condition (EOC) has been analyzed as part of the FIP conducted in response to the trip. The EOC will be further analyzed by this RCE utilizing guidance from PI-AA-100-1005 to determine final Extent of Condition.

Investigation Scope and Methodology: Perform a Root Cause Evaluation in accordance with PI-AA-100-1005. Analysis methodologies should include Barrier Analysis, Organizational and Programmatic Affects, Safety Culture Analysis, and Event and Causal Factors Charting. Note: Failure Analysis of the breaker and cell switch will be performed by Westinghouse.

Team Members
Team Lead: (Qualified RCE Evaluator): Bob Murrell, Duane Arnold Licensing
Team Member: Luis Mazo, Maintenance
Team Member: Richard Jackson, Operations
Team Member: Robert Rodriguez, Training
Team Member: Orlando Carol, Engineering
Management Sponsor: Bob Tomonto, Engineering

Milestones:
Date Assigned: 3/08/21
Status Update: 3/15/21
Draft Report: 3/25/21
Final Report: 4/02/21

Communications Plan:
RCE Team Lead to hold regular briefs with PTN/Fleet managers.

Sponsor Approval: _____ Date: _____

MRC Approval: _____ Date: _____
Electronic signatures may be obtained by assigning actions in NAMS or using a routing list.

FPSC EXH No. 5
03/18/2024
ADMITTED

Attachment 2: Extent of Condition Evaluation

Extent of Condition (EOC) Analysis:

Extent of Condition (EOC) Evaluations were completed in order to identify other deficiencies that need to be addressed by the corrective actions from this RCE.

The following table implements the Same-Similar techniques as outlined in PI-AA-100-1005, Root Cause Analysis, Attachment 13.

Condition Statement:		On March 1, 2021 at 1112, Unit 3 experienced an unplanned automatic reactor trip during restoration of the 3B Reactor Protection System Logic Test, 3-SMI-049.02B. During performance of the SMI, the 3B Reactor Trip Bypass Breaker (BYB) is closed. As part of the restoration, the 3B Reactor Trip Breaker (RTB) breaker is closed and the BYB is locally tripped. When the BYB was tripped open, Unit 3 experienced an automatic reactor trip.	
Object:	Reactor Trip Breaker Cubicle Cell Switch	*Defect:*	Cell Switch Contact malfunctioned, resulting in an automatic reactor trip
Tier	Object	Defect	Comments
(a) Same-Same	Reactor Trip Breaker Cubicle Cell Switch	Cell Switch Contact malfunctioned, resulting in an automatic reactor trip	The EOC for this event must include all U3 and U4 Reactor Trip Breaker Cubicle Cell Switches, including BYP Breakers that could malfunction, resulting in a reactor trip
(b) Same-Similar	Reactor Trip Breaker Cubicle Cell Switch	Cell Switch Contact malfunctioned, resulting events outside of reactor trip	The EOC for this event must include all U3 and U4 Reactor Trip Breaker Cubicle Cell Switches, including BYP Breakers that could malfunction, resulting in an event other than a reactor trip

FPSC EXH No. 5
03/18/2024
ADMITTED

(c) Similar-Same	CRDM MG Set Output Breaker Cubicle Cell Switch And Main Generator Field Breaker Cubicle Cell Switch (Breaker Model DS-206)	Cell Switch Contact malfunctioned, resulting in an automatic reactor trip	The EOC for this event must include all U3 and U4 CRDM MG Set Output and Main Generator Field Breaker Cubicle Cell Switches that could malfunction, resulting in a reactor trip
(d) Similar-Similar	CRDM MG Set Output Breaker Cubicle Cell Switch And Main Generator Field Breaker Cubicle Cell Switch (Breaker Model DS-206)	Cell Switch Contact malfunctioned, resulting events outside of reactor trip	The EOC for this event must include all U3 and U4 CRDM MG Set Output and Main Generator Field Breakers, including BYP Breaker Cubicle Cell Switches that could malfunction, resulting in an event other than a reactor trip

Extent of Condition Conclusions

a) Same-Same

Corrective actions associated with CC2 for this event will address all issues associated with all U3 and U4 Reactor Trip Breaker, including BYP Breaker cell switches. No further actions are required for Same-Same.

b) Same-Similar

There were no events that could be initiated by a malfunction of the Reactor Trip and Bypass Breakers. Therefore, corrective actions associated with CC2 for this event will address all issues associated with U3 and U4 Reactor Trip Breaker, including BYP Breaker cell switches that could malfunction, resulting in an event other than a reactor trip. No further actions are required for Same-Similar.

c) Similar-Same

Corrective actions will be required to create a new PMID for the CRDM MG Set Output Breaker and Generator Field Breaker cubicle cell switch replacement. In addition, a review Westinghouse Maintenance Program Manual (MPM) will be conducted to ensure all components used for CRDM MG set output breaker and Generator Field applications have a maintenance strategy established commensurate with the MPM.

d) Similar-Similar

Corrective actions to address CC2 adequately address Similar-Similar. Therefore, no further actions are required for Similar-Similar.

FPSC EXH No. 5
03/18/2024
ADMITTED

Attachment 3: Extent of Cause Evaluation

Extent of Cause (EOCa) Analysis:

Extent of Cause (EOCa) Evaluation was completed in order to identify other deficiencies that need to be addressed by the corrective actions from this RCE.

The following table implements the Same-Similar techniques as outlined in PI-AA-100-1005, Root Cause Analysis, Attachment 14.

Condition Statement:		On March 1, 2021 at 1112, Unit 3 experienced an unplanned automatic reactor trip during restoration of the 3B Reactor Protection System Logic Test, 3-SMI-049.02B. During performance of the SMI, the 3B Reactor Trip Bypass Breaker (BYB) is closed. As part of the restoration, the 3B Reactor Trip Breaker (RTB) breaker is closed and the BYB is locally tripped. When the BYB was tripped open, Unit 3 experienced an automatic reactor trip.	
Object:	Procedure 0-PME-049.01	*Defect:*	Step for Cell Switch contact cleaning and lubrication is conditional, rather than prescriptive, thereby relying on skill of the craft to determine if cleaning and lubrication is required
Tier	Object	Defect	Comments
(a) Same-Same	Procedure 0-PME-049.01	Step for Cell Switch contact cleaning and lubrication is conditional, rather prescriptive.	The EOCa for this event must address all U3 and U4 Reactor Trip Breaker switchgear procedures used for inspection of the Cubicle Cell Switch. Procedure 0-PME-049.01 applies to both Unit 3 and 4 Reactor Trip Breaker switchgears and is the only procedure used for Cubicle Cell Switch inspections.

FPSC EXH No. 5
03/18/2024
ADMITTED

(b) Same-Similar	Procedure 0-PME-049.01	Procedure includes other conditional inspection steps which if not performed can result in a failure of Reactor Trip Breaker equipment	The EOCa for this event must include all other conditional steps in procedure 0-PME-049.01 which if not performed, can result in a failure of Reactor Trip Breaker equipment
(c) Similar-Same	CRDM MG Set Output Breaker switchgear and Main Generator Field Breaker switchgear inspection procedures	Step for Cell Switch contact cleaning and lubrication is conditional, rather prescriptive	The EOCa for this event must include Cell Switch inspection steps for procedures used on CRDM MG Set Output Breaker switchgear and Main Generator Field Breaker switchgear
(d) Similar-Similar	CRDM MG Set Output Breaker switchgear and Main Generator Field Breaker switchgear inspection procedures	Procedure includes other conditional inspection steps which if not performed can result in a failure of CRDM MG Set Output Breaker switchgear and Main Generator Field Breaker switchgear	The EOCa for this event must include all other conditional steps in procedures used on CRDM MG Set Output Breaker switchgear and Main Generator Field Breaker switchgear which if not performed can result in equipment failure

Extent of Cause Conclusions

a) Same-Same

Corrective actions associated with the Root Cause for this event will address all issues associated with all U3 and U4 Reactor Trip and Bypass Breaker cell switches, as well as conditional cell switch inspection steps for these components. Procedure 0-PME-049.01 is used for both units. No further actions are required for Same-Same.

b) Same-Similar

Corrective actions associated with the Root Cause for this event will address all issues associated with U3 and U4 Reactor Trip and Bypass Breaker cell switches that could malfunction, resulting in an event other than a reactor trip. Corrective actions will also include other conditional steps in procedure 0-PME-049.01 that, if not performed, can result in equipment failure. No further actions are required for Same-Similar.

c) Similar-Same

FPSC EXH No. 5
03/18/2024
ADMITTED

Corrective actions will be required to investigate whether the same cell switches are used in the CRDM MG Set Output Breakers and Generator Field Breakers and generate work requests as needed. Additionally, Corrective actions will be needed to investigate consequence of failure of cell switch contacts on CRDM MG set output breaker and Generator Field breakers and develop interim/final resolution actions as necessary. Corrective actions will also include review of inspection procedures for CRDM MG Set Output Breaker and Generator Field Breaker switchgears to ensure cell switch inspection steps are not conditional.

d) Similar-Similar

Corrective actions to address the root cause will include a review of inspection procedures for CRDM MG Set Output Breaker and Generator Field Breaker switchgears to ensure other conditional steps, which if not performed, can result in equipment failure.

FPSC EXH No. 5
03/18/2024
ADMITTED

Attachment 4: Operating Experience Analysis

Internal and External Operating Experience (OE) Review Summary

Details

Internal OE:

A review of LERs from the previous 5 years failed to identify any other reactor trips due to spurious RTB breaker trips.

External OE:

An INPO OE search yielded 79 items of which 14 items were screened as being relevant to issue identified in AR 2355529. The outcome of this review is as follows:

Surry Unit 1 - Reactor Trip Breaker Failed to Trip During Reactor Protection Testing

While performing the monthly Reactor Protection testing of train "B" Reactor Protection the shunt trip test failed to actuate properly and did not trip the "B" Reactor Trip Breaker (RTB) as expected. The cause of this event was misalignment of the contact spring on the contact block for the S1 pushbutton test switch

Conclusion - Not applicable.

Surry Unit 2 - Reactor Trip Due to Loose Lead in Reactor Protection System

Source of the trip was a spurious opening of the 'B' reactor trip breaker. Troubleshooting in the protection relay racks found a loose electrical connection on a contact pair on a relay that provides the control power for the 'B' reactor trip breaker. This loose terminal caused a reduced voltage on the UV coil opening the B reactor trip breaker (RTB) and initiating a reactor trip

Conclusion - Applicable - Failure of control power added to Support/Refute Matrix.

Salem Unit 1 - OE4022 - DEFORMED CONTACTS ON WESTINGHOUSE TYPE DB-50 CIRCUIT BREAKERS DISCOVERED DURING TESTING

Shunt trip function failed to trip the breaker; shunt coil did not energize. The coil is in series with the #7 moving contact which is installed in the DB secondary moving contact assembly. Contact was found to be compressed to the point where it was not in contact with the stab. It is currently hypothesized that the retaining hook opening on the moving contact escaped the retaining hook and protruded too far below the bottom of the contact base. As a result, when the breaker is racked in, the stab pushes against the contact and deforms the shape of the contact. Further inspection of the Unit 1 breakers identified 5

FPSC EXH No. 5
03/18/2024
ADMITTED

additional deformed contacts. All deformed contacts were replaced. Westinghouse feels that the failure may be related to the breaker/cell alignment.

Conclusion - Not directly applicable. Issue was not a failure to trip; breaker was not racked out during testing when failure occurred. FIP team FARs exercised breaker alignment with no issues identified.

Cook Unit 2 - OE4271 - FAULTY AUXILIARY CONTACTS IN REACTOR TRIP BYPASS BREAKER CAUSE UNEXPECTED REACTOR TRIP ACTUATION

Cause of the event was attributed to a failure of the train B bypass breaker auxiliary contacts to make up properly and provide the electrical interlock necessary to allow closure of the Train A bypass breaker. A subsequent investigation of the train B bypass breaker found an excess of lubricant on all the auxiliary contacts, causing high electrical resistance and incorrect position indication to the Reactor Protection System. The breaker's preventive maintenance procedure was found to closely follow the manufacturer's recommendations but did not contain specific inspection guidance to ensure satisfactory auxiliary contact performance. All auxiliary contacts of the breaker were cleaned, burnished and tested for proper continuity. The remaining reactor trip and bypass breakers were also inspected. One additional breaker was found with contacts having slightly high resistance and was cleaned and burnished as well. The breaker inspection procedure was revised to include checks of continuity and excessive grease. The Startup Instrumentation Check procedure was enhanced to include General Warning signal clearing verification when opening of bypass breakers prior to closing the opposite train bypass breaker.

Conclusion - Applicable – Aux contact failure was failure mode of excessive grease on the Support/Refute Matrix.

Cook Unit 2 - OE4998 - DB-50 REACTOR TRIP BREAKER UNDERVOLTAGE TRIP ATTACHMENT PREVENTS BREAKER CLOSURE

Unable to close Reactor Trip Breaker "B" with the control switch. The undervoltage trip attachment (UVTA) found the reset arm latch would intermittently fail to engage. This situation places the UVTA in a semi-tripped condition in which temperature, vibration or lower coil voltage could cause the breaker to trip instantaneously when closed. In 1986, the Westinghouse DB-50 maintenance manual was revised and added a recommendation for UVTA reset arm calibration when initially installed. The reasons for not calibrating the 1985 vintage UVTA after receipt of the revised manual could not be determined.

Conclusion - Not applicable, issue was not a breaker that tripped instantaneously when closed.

Cook Unit 2 - OE18287 - REACTOR TRIP DURING BREAKER RACKING

FPSC EXH No. 5
03/18/2024
ADMITTED

Reactor trip occurred while an equipment operator was attempting to rack out a DB-50 reactor trip bypass breaker. The racking bar incorrectly positioned and contacted an energized component, causing an arc inside the breaker cubicle. This resulted in loss of one phase of the power supply to the rod control cabinets, causing multiple control rods to drop into the core and triggering the reactor trip

Conclusion - Not applicable.

Diablo Canyon Unit 2 - Reactor Trip Breaker Failed to Close During Start-Up (OE27837)

Reactor trip breaker RTB failed to close and the control power fuse opened when the control switch was placed in the closed position. Breaker inertial latch was sluggish on the pivot pin and would occasionally catch the "CATCH" pin on the closing lever. Latch pivot pin and bushing was found with excessive dry lubricant which caused the sluggish motion. The apparent cause is inadequate procedural guidance to 1. Clean the latch pin and bushing and, 2. Quantitatively limit the amount of lubricant applied.

Conclusion - Not applicable.

Ginna Unit 1 - OE21379 - Westinghouse DB-50 breaker abnormal trip bar movement

Westinghouse DB-50 breaker (containment spray motor) abnormal trip bar, the trip bar rose when the breaker frame was tapped. The bar rose slightly each time the frame was tapped until the breaker tripped. Westinghouse investigation found multiple operating mechanism component tolerance deviations. The combination of these deviations resulted in the abnormal mechanism operation.

Conclusion - Not applicable.

Salem Unit 2 - OE22435 - Reactor Trip Breaker Failed to Electrically Close

Reactor Trip Breaker failed to electrically close. A loose pin inside the operating mechanism was found to have rubbed against the housing and resulted in a breaker failing to remain electrically closed (tripping free).

Conclusion - Not applicable issue was not a breaker that tripped free.

Sequoyah Unit 1 - OE23458 - Failure of Westinghouse Type DB Reactor Trip Breaker to Close and Remain Closed

Reactor Trip Breaker RT A was given a close signal from the Main Control Room immediately opened after attempting to close. After developing a list of possible causes, troubleshooting was performed but could not recreate the problem nor identify a root or apparent cause. Troubleshooting during the next outage could not recreate the problem and the most probable cause was identified as the MCR hand switch.

FPSC EXH No. 5
03/18/2024
ADMITTED

Conclusion - Not applicable.

Turkey Point Unit 3 - OE23298 - Failure of Unit 3 Reactor Trip Breaker to close

3A Reactor Trip Breaker failed to close, when the Reactor Trip Reset was pressed, the breaker went closed but immediately reopened. The removed breaker was found to have a loose pivot screw on the UVTA adjustable reset lever. The screw was loose enough that the adjustable part of the reset lever had moved to one side of the reset adjustment screw causing a gross mis-adjustment of the reset lever. The UVTA could not reset causing the breaker to be in a continuous trip condition.

Conclusion - Not applicable.

Kewaunee Unit 1 - OE21282 - Reactor Trip Bypass Breaker A Failed to Remain Closed During Testing

I&C Maintenance was performing SP-47-316A, Channel 1(Red) Instrument Channel Test. Step 6.7.11 requires the 52/BYA reactor trip breaker to be closed using the 52/BYA pushbutton in RR121. When the technician pushed the button, the breaker closed and then immediately opened. The apparent cause of the breaker to not close was a cotter pin that had turned 180 degrees. This positioned the long leg of the bent cotter pin against the closing mechanism. This forced the operating mechanism to go out of alignment preventing the breaker from latching closed. It is not known why the cotter pin turned 180 degrees in its mounting hole.

Conclusion - Not applicable

Prairie Island Unit 1 - Failure of contact(s) in Plant Protection System circuit breaker 1-52/RTA.

Reactor trip breaker 1-52/RTA failed to close after several attempts. No cause was identified.

Conclusion - Not applicable.

Cooper Unit 1 - Westinghouse DB 50 Breaker Reliability

Westinghouse DB 50 480-volt breaker was removed from service because of unreliable performance. It had been installed to provide power to a station air compressor and experienced several instances of blown closing coil fuses. The cause of these failures was inadequate clearance between the inertia latch and the main contact cross bar. This caused binding, resulting in an extended flow of current through the closing coil and the blown fuses.

Conclusion - Not applicable.

FPSC EXH No. 5
03/18/2024
ADMITTED

There have been a number of NSALs, Bulletins, etc., issued, some of which are listed below. None of these have been found to be directly applicable to this event.

1. NSAL-93-020, "DB/DHP Breaker Control Relay," dated 10/5/93.
2. NSAL-98-009, DB Breaker Failure to Close, dated 9/28/99.
3. NSD-TB 91 -03, DB Breaker Secondary Contact Failure, dated 4/22/91.
4. NSD-TB 92-04, DB Breaker Maintenance, Breakdown of Primary Insulation and Incorrect Torqueing of Bolts, dated 5/18/92.
5. NSD-TB-93-05-R0, "Unauthorized Switchgear Maintenance Manuals," dated 1/10/94
6. MR-H-98-0138, 10 CFR Part 21, Sticking Inertial Latch in Model DB-50.
7. IE BULLETIN 83-01, "Failure of Reactor Trip Breakers (Westinghouse DB-50) to Open on Automatic Signal," dated, 2/25/1983.
8. IE BULLETIN 83-04, "Failure of the Undervoltage Trip Function of Reactor Trip Breakers," dated March 11, 1983.
9. IE BULLETIN 85-02, "Undervoltage Trip Attachments of Westinghouse DB-50 Type Reactor Trip Breakers," dated 11/5/1985.
10. IN 83-18, "Failures of the Under voltage, Trip Function of Reactor Trip System Breakers," dated April 1, 1983.
11. IN 93-85, "Problems with X-Relays in DB- and DBH-Type Circuit Breakers Manufactured By Westinghouse," dated 10/20/1993.
12. IN 95-19, "Failure of Reactor Trip Breaker to Open Because of Cutoff Switch Material Lodged in the Trip Latch Mechanism," dated March 22v,1995.
13. IN 95-22, "Hardened or Contaminated Lubricants Cause Metal-Clad Circuit Breaker Failure," dated April 21, 1995.
14. IN 96-44, "Failure off Reactor Trip Breaker from Cracking of Phenolic Material in Secondary Contact Assembly," dated 8/5/1996.
15. IN 96-44, Supplement 1, "Failure of Reactor Trip Breaker from Cracking of Phenolic Material in a Secondary Contact Assembly," dated July 2, 1997.
16. IN 96-46, "Zinc Plating of Hardened Metal Parts and Removal of Protective Coatings in Refurbished Circuit Breakers," dated August 12, 1996.
17. NSTB-83-03 Westinghouse Models DB& DS Circuit Breaker Shunt & Under voltage (UV) Coils, dated 3/24/83.

<u>OE Conclusions</u>

There were no internal events that could be considered precursor events to the event being evaluated by the RCE team. Where applicable operating experience was identified, this information was added to the Fault Tree to ensure that branch element was reviewed. In accordance with PI-AA-104-1000, this was not a repeat event. There were several external events that were found to be applicable and the causes were added to the Support/Refute Matrix.

FPSC EXH No. 5
03/18/2024
ADMITTED

Attachment 5: Support Refute Matrix

Support/Refute Matrix

Unit 3 Automatic Reactor Trip during restoration from B Train RPS testing 3-SMI-049.02B

Problem statement: During restoration step 5.1.6 of Train B RPS testing procedure 3-SMI-049.02B step which opens the Reactor Trip Bypass breaker B, Unit 3 experienced an automatic reactor trip. A review of the Sequence of Events report following the trip revealed the first alarm in was Turbine Trip HDR Pressure Channels, followed by Reactor Trip Relays 9 and 10, and then Reactor Trip Breakers A and B Trip. The SOE report demonstrates that the initiating event of the Reactor Trip was Turbine Trip which is driven by the 94/AST (primary) and 94/ASB (backup) relays. The Reactor Trip Breaker B and Bypass Breaker B provide trip logic to the 94/ASB relay.

Potential Cause	Discussion	Supporting / Refuting Evidence	Evidence Status / Source	Cause
PEOPLE				
I&C personnel depressed the wrong pushbutton (i.e. tripped Reactor Trip Breaker B) when performing step 5.1.6.	Tripping of the Reactor Trip breaker B instead of the Bypass breaker would not explain the event. With the Bypass breaker B closed, not automatic unit trip is expected.	**Refuted** Interview with site personnel and SOE report do not support a Human Error occurring.	**Closed** Interviews and SOE reports.	**Not a Cause**
ORGANIZATIONAL/PROGRAMMATIC/PROCESS				
Preventive Maintenance	Inadequate maintenance strategy	**Supporting**	**Closed**	**Contributing Cause (CC2) - Failure to follow WEC**

FPSC EXH No. 5
03/18/2024
ADMITTED

Support/Refute Matrix

Unit 3 Automatic Reactor Trip during restoration from B Train RPS testing 3-SMI-049.02B

Problem statement: During restoration step 5.1.6 of Train B RPS testing procedure 3-SMI-049.02B step which opens the Reactor Trip Bypass breaker B, Unit 3 experienced an automatic reactor trip. A review of the Sequence of Events report following the trip revealed the first alarm in was Turbine Trip HDR Pressure Channels, followed by Reactor Trip Relays 9 and 10, and then Reactor Trip Breakers A and B Trip. The SOE report demonstrates that the initiating event of the Reactor Trip was Turbine Trip which is driven by the 94/AST (primary) and 94/ASB (backup) relays. The Reactor Trip Breaker B and Bypass Breaker B provide trip logic to the 94/ASB relay.

Potential Cause	Discussion	Supporting / Refuting Evidence	Evidence Status / Source	Cause
Program on cubicle cell switch inadequate	can lead to end of life failures of cubicle cell switch.	Westinghouse Maintenance Program Manual (MPM) recommends a service life of 100 cycles for cell switches. Cell switches are not normally replaced as part of routine maintenance. There is no PM in place to perform cell switch replacements. The cell switches are original plant equipment. Forensic testing identified two failed normally open contacts (one on each switch) from fatigued (aged) stationary contacts. **Refuting Evidence** Forensic report provided by Westinghouse has stated the following with regards to the 100 cycle recommended service life:	Although forensics identified two normally open contacts with age related failures, this failure mode would not have resulted in the unit trip event.	**MPM cell switch maintenance and replacement frequency**

FPSC EXH No. 5
03/18/2024
ADMITTED

Support/Refute Matrix

Unit 3 Automatic Reactor Trip during restoration from B Train RPS testing 3-SMI-049.02B

Problem statement: During restoration step 5.1.6 of Train B RPS testing procedure 3-SMI-049.02B step which opens the Reactor Trip Bypass breaker B, Unit 3 experienced an automatic reactor trip. A review of the Sequence of Events report following the trip revealed the first alarm in was Turbine Trip HDR Pressure Channels, followed by Reactor Trip Relays 9 and 10, and then Reactor Trip Breakers A and B Trip. The SOE report demonstrates that the initiating event of the Reactor Trip was Turbine Trip which is driven by the 94/AST (primary) and 94/ASB (backup) relays. The Reactor Trip Breaker B and Bypass Breaker B provide trip logic to the 94/ASB relay.

Potential Cause	Discussion	Supporting / Refuting Evidence	Evidence Status / Source	Cause
		The basis for the design life of the cell switch, primary finger clusters and the secondary contacts is American National Standards Institute/Institute of Electrical and Electronics Engineers (ANSI/IEEE) C37.20.1-1987, "An American National Standard, IEEE Standard for Metal-Enclosed Low-Voltage Power Circuit-Breaker Switchgear," subsection 5.2.5. This section defines a low voltage (LV) switchgear with draw-out circuit breakers shall have mechanical endurance test cycles consisting of at least 100 operations between connected and test position. *With proper maintenance and analysis of the components the 100 operation/cycle*		

FPSC EXH No. 5
03/18/2024
ADMITTED

Support/Refute Matrix

Unit 3 Automatic Reactor Trip during restoration from B Train RPS testing 3-SMI-049.02B

Problem statement: During restoration step 5.1.6 of Train B RPS testing procedure 3-SMI-049.02B step which opens the Reactor Trip Bypass breaker B, Unit 3 experienced an automatic reactor trip. A review of the Sequence of Events report following the trip revealed the first alarm in was Turbine Trip HDR Pressure Channels, followed by Reactor Trip Relays 9 and 10, and then Reactor Trip Breakers A and B Trip. The SOE report demonstrates that the initiating event of the Reactor Trip was Turbine Trip which is driven by the 94/AST (primary) and 94/ASB (backup) relays. The Reactor Trip Breaker B and Bypass Breaker B provide trip logic to the 94/ASB relay.

Potential Cause	Discussion	Supporting / Refuting Evidence	Evidence Status / Source	Cause
		life of the cell components could be extended. The end of life condition of these components is not known. *The switch that is used as the cell switch is the same switch used as an auxiliary switch on the DB breaker with a qualified life of 4,000 cycles on the DB-50 breaker. The remaining components of the cell switch consist of a metal frame, a metal operations bar and a metal return spring. None of these components are sensitive to age within 100 cycles.* In addition, response from Robinson Nuclear regarding PM strategy on cell switches revealed they previously had a 12 year replacement PM which was subsequently retired to an 8 year		

FPSC EXH No. 5
03/18/2024
ADMITTED

Support/Refute Matrix

Unit 3 Automatic Reactor Trip during restoration from B Train RPS testing 3-SMI-049.02B

Problem statement: During restoration step 5.1.6 of Train B RPS testing procedure 3-SMI-049.02B step which opens the Reactor Trip Bypass breaker B, Unit 3 experienced an automatic reactor trip. A review of the Sequence of Events report following the trip revealed the first alarm in was Turbine Trip HDR Pressure Channels, followed by Reactor Trip Relays 9 and 10, and then Reactor Trip Breakers A and B Trip. The SOE report demonstrates that the initiating event of the Reactor Trip was Turbine Trip which is driven by the 94/AST (primary) and 94/ASB (backup) relays. The Reactor Trip Breaker B and Bypass Breaker B provide trip logic to the 94/ASB relay.

Potential Cause	Discussion	Supporting / Refuting Evidence	Evidence Status / Source	Cause
		inspection. D.C. Cook does not have a replacement PM and inspects their switches every refueling cycle.		
Inadequate inspection and cleaning of cell switch contacts during routine PM.	Improper cleaning of cell switch contacts can lead to grease hardening and dust accumulation, thereby resulting in tracking paths on the switch. This can result in switches which indicate closed when they are expected to be open.	**Supporting** Westinghouse forensic report noted that cell switches removed from the RTB cubicle were identified has having hardened grease on the contacts. This is indicative of improper cleaning and application of grease on the cell switch contacts. This condition most likely created a tracking path across normally closed cell switch #2 contact 1-2 when the breaker was racked in, resulting in a standing trip signal to the 94/ASB Turbine Trip relay.	**Closed** **FAR 10 –** forensics identified hardened grease on switch contacts	**Root Cause –IAW 0-PME-049.01, steps for cleaning and lubricating cell switch contacts is conditional based, rather than prescriptive.**

FPSC EXH No. 5
03/18/2024
ADMITTED

Support/Refute Matrix

Unit 3 Automatic Reactor Trip during restoration from B Train RPS testing 3-SMI-049.02B

Problem statement: During restoration step 5.1.6 of Train B RPS testing procedure 3-SMI-049.02B step which opens the Reactor Trip Bypass breaker B, Unit 3 experienced an automatic reactor trip. A review of the Sequence of Events report following the trip revealed the first alarm in was Turbine Trip HDR Pressure Channels, followed by Reactor Trip Relays 9 and 10, and then Reactor Trip Breakers A and B Trip. The SOE report demonstrates that the initiating event of the Reactor Trip was Turbine Trip which is driven by the 94/AST (primary) and 94/ASB (backup) relays. The Reactor Trip Breaker B and Bypass Breaker B provide trip logic to the 94/ASB relay.

Potential Cause	Discussion	Supporting / Refuting Evidence	Evidence Status / Source	Cause
		0-PME-049.01 cell switch cleaning and application of grease is conditional and is left the judgement of the journeyman performing the inspection. Discussions with previous maintenance personnel noted that the switches are difficult to get to even with a clearance on the equipment established, which may be prohibitive to cleaning and inspecting. **Refuting** Breaker and cubicle inspection procedure 0-PME-049.01 includes steps to remove switch cover and inspect contacts for cleanliness. Cleaning and lubrication is performed as required. Resistance across		

FPSC EXH No. 5
03/18/2024
ADMITTED

Support/Refute Matrix

Unit 3 Automatic Reactor Trip during restoration from B Train RPS testing 3-SMI-049.02B

Problem statement: During restoration step 5.1.6 of Train B RPS testing procedure 3-SMI-049.02B step which opens the Reactor Trip Bypass breaker B, Unit 3 experienced an automatic reactor trip. A review of the Sequence of Events report following the trip revealed the first alarm in was Turbine Trip HDR Pressure Channels, followed by Reactor Trip Relays 9 and 10, and then Reactor Trip Breakers A and B Trip. The SOE report demonstrates that the initiating event of the Reactor Trip was Turbine Trip which is driven by the 94/AST (primary) and 94/ASB (backup) relays. The Reactor Trip Breaker B and Bypass Breaker B provide trip logic to the 94/ASB relay.

Potential Cause	Discussion	Supporting / Refuting Evidence	Evidence Status / Source	Cause
		contacts is also measured to be less than 1 ohm.		
EQUIPMENT				
Reactor Trip Breaker/Cubicle Malfunction				
Reactor Trip Breaker B bounced out of position during opening of Bypass breaker B.	If the Reactor Trip Breaker B and its associated aux contacts 'bounce out' and momentarily change state with Bypass breaker B open, trip logic to the 94/ASB relay is made	**Refuted** Review of DB-50 breaker OE did not reveal any instances of these model breakers bouncing out of position. FAR 02 did not reveal any abnormalities.	**Closed** WO: 40766915 FAR 01 - SAT FAR 02 - SAT	**Not a Cause**

FPSC EXH No. 5
03/18/2024
ADMITTED

Support/Refute Matrix

Unit 3 Automatic Reactor Trip during restoration from B Train RPS testing 3-SMI-049.02B

Problem statement: During restoration step 5.1.6 of Train B RPS testing procedure 3-SMI-049.02B step which opens the Reactor Trip Bypass breaker B, Unit 3 experienced an automatic reactor trip. A review of the Sequence of Events report following the trip revealed the first alarm in was Turbine Trip HDR Pressure Channels, followed by Reactor Trip Relays 9 and 10, and then Reactor Trip Breakers A and B Trip. The SOE report demonstrates that the initiating event of the Reactor Trip was Turbine Trip which is driven by the 94/AST (primary) and 94/ASB (backup) relays. The Reactor Trip Breaker B and Bypass Breaker B provide trip logic to the 94/ASB relay.

Potential Cause	Discussion	Supporting / Refuting Evidence	Evidence Status / Source	Cause
	up and can cause Turbine Trip.			
Reactor Trip Breaker B pushbutton trip binding with lock-out tabs.	The Reactor Trip Breakers are equipped with lockout tabs that surround the face of pushbutton trip on the front of the breaker. Site experience has demonstrated that binding of the lockout tabs with the pushbutton trip can occur, preventing the trip pushbutton from fully seating back to its	**Refuted** Forensic investigation performed by Westinghouse has not found any evidence of binding between the trip pushbutton and the lockout tabs. The breaker has been cycled numerous times without issues. FAR 03 - performed a partial breaker inspection on the bench IAW sections of 0-PME 049.01 and found no evidence of binding. FAR 06 performed numerous cycling of the breaker once removed from the cubicle and found no	**Closed** WO: 40766915 FAR 03 – SAT FAR 06 - SAT FAR 10 – Forensic results find no evidence of binding between trip pushbutton and lockout tabs.	**Not a Cause**

FPSC EXH No. 5
03/18/2024
ADMITTED

Support/Refute Matrix

Unit 3 Automatic Reactor Trip during restoration from B Train RPS testing 3-SMI-049.02B

Problem statement: During restoration step 5.1.6 of Train B RPS testing procedure 3-SMI-049.02B step which opens the Reactor Trip Bypass breaker B, Unit 3 experienced an automatic reactor trip. A review of the Sequence of Events report following the trip revealed the first alarm in was Turbine Trip HDR Pressure Channels, followed by Reactor Trip Relays 9 and 10, and then Reactor Trip Breakers A and B Trip. The SOE report demonstrates that the initiating event of the Reactor Trip was Turbine Trip which is driven by the 94/AST (primary) and 94/ASB (backup) relays. The Reactor Trip Breaker B and Bypass Breaker B provide trip logic to the 94/ASB relay.

Potential Cause	Discussion	Supporting / Refuting Evidence	Evidence Status / Source	Cause
	shelf state and placing the breaker in a trip-sensitive state whereby a shock or vibration can cause the breaker to trip open from a closed state.	issues with mechanical binding or resistance.		
Reactor Trip Breaker B aux contact malfunctioned and dropped load.	A malfunction of Reactor Trip Breaker B aux contact 13-14b following opening of the Bypass B breaker would cause an actuation of the 94/ASB relay and	**Refuting** Review of SOE report indicates first alarm in was Turbine Trip, not Reactor Trip breakers. This indicates breaker malfunction was not the initiating event. FAR 03 - performed a partial breaker inspection on the bench IAW sections of 0-PME 049.01 and found no issues.	**Closed** WO: 40766915 FAR 03 - SAT FAR 05 - SAT FAR 06 - SAT FAR 10 –Breaker forensic testing	**Not a Cause**

FPSC EXH No. 5
03/18/2024
ADMITTED

Support/Refute Matrix

Unit 3 Automatic Reactor Trip during restoration from B Train RPS testing 3-SMI-049.02B

Problem statement: During restoration step 5.1.6 of Train B RPS testing procedure 3-SMI-049.02B step which opens the Reactor Trip Bypass breaker B, Unit 3 experienced an automatic reactor trip. A review of the Sequence of Events report following the trip revealed the first alarm in was Turbine Trip HDR Pressure Channels, followed by Reactor Trip Relays 9 and 10, and then Reactor Trip Breakers A and B Trip. The SOE report demonstrates that the initiating event of the Reactor Trip was Turbine Trip which is driven by the 94/AST (primary) and 94/ASB (backup) relays. The Reactor Trip Breaker B and Bypass Breaker B provide trip logic to the 94/ASB relay.

Potential Cause	Discussion	Supporting / Refuting Evidence	Evidence Status / Source	Cause
	subsequent Turbine Trip.	FAR 05 and 06 – Aux contacts were inspected for proper change of state. Breaker was cycled 25 times without issues. FAR 10 – Forensics testing by Westinghouse did not find any evidence of aux contact failure. Contacts performed as expected 100% of the time.	did not identify any issues with the breaker aux contacts	
Loss of control power on Reactor Trip Breaker 'B' and Bypass Breaker 'B' UV Trip Circuit.	A loss of control power to the RTB and BYB breakers' control circuits would cause the UVTA coil to de-energize and trip the breakers, thereby	**Refuted** FAR 04 verified proper voltage at the UVTA coil for the Reactor Trip B Breaker.	**Closed** WO: 40766915 FAR 04 - SAT	**Not a Cause**

FPSC EXH No. 5
03/18/2024
ADMITTED

Support/Refute Matrix

Unit 3 Automatic Reactor Trip during restoration from B Train RPS testing 3-SMI-049.02B

Problem statement: During restoration step 5.1.6 of Train B RPS testing procedure 3-SMI-049.02B step which opens the Reactor Trip Bypass breaker B, Unit 3 experienced an automatic reactor trip. A review of the Sequence of Events report following the trip revealed the first alarm in was Turbine Trip HDR Pressure Channels, followed by Reactor Trip Relays 9 and 10, and then Reactor Trip Breakers A and B Trip. The SOE report demonstrates that the initiating event of the Reactor Trip was Turbine Trip which is driven by the 94/AST (primary) and 94/ASB (backup) relays. The Reactor Trip Breaker B and Bypass Breaker B provide trip logic to the 94/ASB relay.

Potential Cause	Discussion	Supporting / Refuting Evidence	Evidence Status / Source	Cause
	causing actuation of the 94/ASB and subsequent Turbine Trip			
Loose wiring in Reactor Trip B or Bypass B breaker cubicles.	Loose wiring in Reactor Trip B or Bypass B breaker cubicles can cause unexpected actuation of circuit interlocks when the Bypass B breaker was open.	**Refuted** FAR 07 inspected wiring inside the Reactor Trip B and Bypass B breaker cubicles and found no loose wires.	**Closed** WO: 40766915 FAR 07 - SAT	**Not a Cause**
Reactor Trip B Breaker cell switch malfunction.	The cell switch changes state when the breaker is racked in and out of the cubicle. If the cell	**Supporting** Westinghouse Maintenance Program Manual (MPM) recommends a service life of 100 cycles for cell switches. Cell	**Closed** FAR 10 – forensic testing of removed cell switches in	**Direct Cause**

FPSC EXH No. 5
03/18/2024
ADMITTED

Support/Refute Matrix

Unit 3 Automatic Reactor Trip during restoration from B Train RPS testing 3-SMI-049.02B

Problem statement: During restoration step 5.1.6 of Train B RPS testing procedure 3-SMI-049.02B step which opens the Reactor Trip Bypass breaker B, Unit 3 experienced an automatic reactor trip. A review of the Sequence of Events report following the trip revealed the first alarm in was Turbine Trip HDR Pressure Channels, followed by Reactor Trip Relays 9 and 10, and then Reactor Trip Breakers A and B Trip. The SOE report demonstrates that the initiating event of the Reactor Trip was Turbine Trip which is driven by the 94/AST (primary) and 94/ASB (backup) relays. The Reactor Trip Breaker B and Bypass Breaker B provide trip logic to the 94/ASB relay.

Potential Cause	Discussion	Supporting / Refuting Evidence	Evidence Status / Source	Cause
	switch for the Reactor Trip B breaker cubicle did not properly change state when breaker was racked in, it would make up the logic to actuate the 94/ASB relay once the Bypass breaker B is opened.	switches are not normally replaced as part of routine maintenance. However, they are inspected. **Forensics results.** FAR 10 - Westinghouse forensics testing noted that the cell switches were most likely original plant equipment and were not properly maintained. The switch contacts had hardened grease, the switch plunger had foreign lubrication applied, and the return springs lacked lubrication. Testing of the left cell switch identified a failed 7-8 Normally Open contact. This contact remained open with both the plunger actuated and not actuated. Testing of the right cell switch identified the same failure mode for the 3-4	RTB cubicle will be performed by Westinghouse.	

FPSC EXH No. 5
03/18/2024
ADMITTED

Support/Refute Matrix

Unit 3 Automatic Reactor Trip during restoration from B Train RPS testing 3-SMI-049.02B

Problem statement: During restoration step 5.1.6 of Train B RPS testing procedure 3-SMI-049.02B step which opens the Reactor Trip Bypass breaker B, Unit 3 experienced an automatic reactor trip. A review of the Sequence of Events report following the trip revealed the first alarm in was Turbine Trip HDR Pressure Channels, followed by Reactor Trip Relays 9 and 10, and then Reactor Trip Breakers A and B Trip. The SOE report demonstrates that the initiating event of the Reactor Trip was Turbine Trip which is driven by the 94/AST (primary) and 94/ASB (backup) relays. The Reactor Trip Breaker B and Bypass Breaker B provide trip logic to the 94/ASB relay.

Potential Cause	Discussion	Supporting / Refuting Evidence	Evidence Status / Source	Cause
		Normally Open contact. Although these failure modes would have been inconsequential in the Reactor Trip Switchgear given these contacts are not wired out to the plant, it is indicative of wear and aging of the cell switch. The most probable direct cause is a tracking path created on the old hardened grease on the 1-2 Normally Closed contact that made up the trip logic to the 94/ASB turbine trip relay once the BYB breaker was opened. FAR 07 replaced cell switches for the Reactor Trip B cubicle.		
Excessive grease on breaker aux contacts.	OE review has identified an event where excessive	**Refuting evidence**	**Closed** FAR 03 - SAT	**Not a Cause**

FPSC EXH No. 5
03/18/2024
ADMITTED

Support/Refute Matrix

Unit 3 Automatic Reactor Trip during restoration from B Train RPS testing 3-SMI-049.02B

Problem statement: During restoration step 5.1.6 of Train B RPS testing procedure 3-SMI-049.02B step which opens the Reactor Trip Bypass breaker B, Unit 3 experienced an automatic reactor trip. A review of the Sequence of Events report following the trip revealed the first alarm in was Turbine Trip HDR Pressure Channels, followed by Reactor Trip Relays 9 and 10, and then Reactor Trip Breakers A and B Trip. The SOE report demonstrates that the initiating event of the Reactor Trip was Turbine Trip which is driven by the 94/AST (primary) and 94/ASB (backup) relays. The Reactor Trip Breaker B and Bypass Breaker B provide trip logic to the 94/ASB relay.

Potential Cause	Discussion	Supporting / Refuting Evidence	Evidence Status / Source	Cause
	grease on breaker aux contacts caused a unit trip to occur.	This failure mode would not explain the trip event. The concern with excess grease is creating an open circuit in closed contact. The trip event would require an unexpected closed circuit in an open contact. Also, breaker inspection 0-PME-049.01 instructs to apply a small amount of grease on aux contact surfaces. FAR 03 performed a partial inspection of the RTB breaker IAW 0-PME-049.01. Aux contacts were inspected per section 4.19. No anomalies were identified. Resistance readings were 0.2 Ohms or lower which indicates no concerns for excessive grease.		
RPS Trip Relays RT-9/RT-10 Malfunction				

FPSC EXH No. 5
03/18/2024
ADMITTED

Support/Refute Matrix

Unit 3 Automatic Reactor Trip during restoration from B Train RPS testing 3-SMI-049.02B

Problem statement: During restoration step 5.1.6 of Train B RPS testing procedure 3-SMI-049.02B step which opens the Reactor Trip Bypass breaker B, Unit 3 experienced an automatic reactor trip. A review of the Sequence of Events report following the trip revealed the first alarm in was Turbine Trip HDR Pressure Channels, followed by Reactor Trip Relays 9 and 10, and then Reactor Trip Breakers A and B Trip. The SOE report demonstrates that the initiating event of the Reactor Trip was Turbine Trip which is driven by the 94/AST (primary) and 94/ASB (backup) relays. The Reactor Trip Breaker B and Bypass Breaker B provide trip logic to the 94/ASB relay.

Potential Cause	Discussion	Supporting / Refuting Evidence	Evidence Status / Source	Cause
Reactor Trip Relays RT-9 and RT-10 actuate due to Pressurizer High Water Level, causing Reactor Trip.	Although SOE reports first alarm in was from Turbine Trip, time stamps for Turbine Trip Signals and RT 9 and 10 actuating are within milliseconds. There is a very small possibility RT 9 and 10 actuated first.	**Refuted** Absence of Pressurizer High Level alarm in SOE report. PI tag PZHLTR23_A does not insert prior to event.	**Closed** Review of PI and SOE did not indicate PRZ High Level.	**Not a Cause**
Reactor Trip Relays RT-9 and RT-10 actuate due to Pressurizer Low Water Level, causing Reactor Trip.	Although SOE reports first alarm in was from Turbine Trip, time stamps for Turbine Trip Signals and RT 9 and 10 actuating are within milliseconds.	**Refuted** Absence of Pressurizer High Level alarm in SOE report. PI tag PZHLTR23_A does not insert prior to event.	**Closed** Review of PI and SOE did not indicate PRZ Low Level.	**Not a Cause**

FPSC EXH No. 5
03/18/2024
ADMITTED

Support/Refute Matrix

Unit 3 Automatic Reactor Trip during restoration from B Train RPS testing 3-SMI-049.02B

Problem statement: During restoration step 5.1.6 of Train B RPS testing procedure 3-SMI-049.02B step which opens the Reactor Trip Bypass breaker B, Unit 3 experienced an automatic reactor trip. A review of the Sequence of Events report following the trip revealed the first alarm in was Turbine Trip HDR Pressure Channels, followed by Reactor Trip Relays 9 and 10, and then Reactor Trip Breakers A and B Trip. The SOE report demonstrates that the initiating event of the Reactor Trip was Turbine Trip which is driven by the 94/AST (primary) and 94/ASB (backup) relays. The Reactor Trip Breaker B and Bypass Breaker B provide trip logic to the 94/ASB relay.

Potential Cause	Discussion	Supporting / Refuting Evidence	Evidence Status / Source	Cause
	There is a very small possibility RT 9 and 10 actuated first.			
Reactor Trip Relays RT-9 and RT-10 actuate due to Power Range Hi Flux, causing Reactor Trip.	Although SOE reports first alarm in was from Turbine Trip, time stamps for Turbine Trip Signals and RT 9 and 10 actuating are within milliseconds. There is a very small possibility RT 9 and 10 actuated first.	**Refuted** Absence of Pressurizer High Level alarm in SOE report. PI tag NIPWRHTP_A does not insert prior to event.	**Closed** Review of PI and SOE did not indicate Power Range Hi Flux.	**Not a Cause**
Failure/malfunction of RT 9 and RT 10 relays.	A failure of Reactor Trip Relays RT 9 and 10 would cause a trip	**Refuted** Subject relays were tested SAT under WO 40766903-01 as part of U3 Train B RPS	**Closed** WO 40766903-01 SAT	**Not a Cause**

FPSC EXH No. 5
03/18/2024
ADMITTED

Support/Refute Matrix

Unit 3 Automatic Reactor Trip during restoration from B Train RPS testing 3-SMI-049.02B

Problem statement: During restoration step 5.1.6 of Train B RPS testing procedure 3-SMI-049.02B step which opens the Reactor Trip Bypass breaker B, Unit 3 experienced an automatic reactor trip. A review of the Sequence of Events report following the trip revealed the first alarm in was Turbine Trip HDR Pressure Channels, followed by Reactor Trip Relays 9 and 10, and then Reactor Trip Breakers A and B Trip. The SOE report demonstrates that the initiating event of the Reactor Trip was Turbine Trip which is driven by the 94/AST (primary) and 94/ASB (backup) relays. The Reactor Trip Breaker B and Bypass Breaker B provide trip logic to the 94/ASB relay.

Potential Cause	Discussion	Supporting / Refuting Evidence	Evidence Status / Source	Cause
	of the Reactor Trip Breakers.	Logic Testing. Both relays would have to fail simultaneously to cause reactor trip.		
94/ASB Inadvertent Actuation				
94/ASB Backup Turbine Trip relay was actuated from an AMSAC signal.	AMSAC initiation would lead to an actuation of the 94/ASB relay and subsequent Turbine Trip.	**Refuted** A review of SOE report shows no AMSAC alarm at the time of the Reactor Trip. PI trends also show no AMSAC actuation at the time of trip.	**Closed** Review of PI and SOE did not indicate AMSAC actuation at the time of reactor trip.	**Not a Cause**

FPSC EXH No. 5
03/18/2024
ADMITTED

Support/Refute Matrix

Unit 3 Automatic Reactor Trip during restoration from B Train RPS testing 3-SMI-049.02B

Problem statement: During restoration step 5.1.6 of Train B RPS testing procedure 3-SMI-049.02B step which opens the Reactor Trip Bypass breaker B, Unit 3 experienced an automatic reactor trip. A review of the Sequence of Events report following the trip revealed the first alarm in was Turbine Trip HDR Pressure Channels, followed by Reactor Trip Relays 9 and 10, and then Reactor Trip Breakers A and B Trip. The SOE report demonstrates that the initiating event of the Reactor Trip was Turbine Trip which is driven by the 94/AST (primary) and 94/ASB (backup) relays. The Reactor Trip Breaker B and Bypass Breaker B provide trip logic to the 94/ASB relay.

Potential Cause	Discussion	Supporting / Refuting Evidence	Evidence Status / Source	Cause
94/ASB Backup Turbine Trip relay was actuated from Feedwater Isolation signal.	A Feedwater Isolation signal would lead to an actuation of the 94/ASB relay and subsequent Turbine Trip.	**Refuted** A review of SOE report shows no Feedwater Isolation alarm at the time of the Reactor Trip. PI trends also show no Feedwater Isolation actuation at the time of trip.	**Closed** Review of PI and SOE did not indicate Feedwater Isolation actuation at the time of reactor trip.	**Not a Cause**
94/ASB Backup Turbine Trip relay was actuated from a Generator Lockout signal.	A Generator Lockout signal would lead to an actuation of the 94/ASB relay and	**Refuted** A review of SOE report shows no Generator Lockout alarm at the time of the Reactor Trip. PI trends also show no GENLORLY_A actuation at the time of trip.	**Closed** Review of PI and SOE did not indicate Generator Lockout actuation	**Not a Cause**

FPSC EXH No. 5
03/18/2024
ADMITTED

Support/Refute Matrix

Unit 3 Automatic Reactor Trip during restoration from B Train RPS testing 3-SMI-049.02B

Problem statement: During restoration step 5.1.6 of Train B RPS testing procedure 3-SMI-049.02B step which opens the Reactor Trip Bypass breaker B, Unit 3 experienced an automatic reactor trip. A review of the Sequence of Events report following the trip revealed the first alarm in was Turbine Trip HDR Pressure Channels, followed by Reactor Trip Relays 9 and 10, and then Reactor Trip Breakers A and B Trip. The SOE report demonstrates that the initiating event of the Reactor Trip was Turbine Trip which is driven by the 94/AST (primary) and 94/ASB (backup) relays. The Reactor Trip Breaker B and Bypass Breaker B provide trip logic to the 94/ASB relay.

Potential Cause	Discussion	Supporting / Refuting Evidence	Evidence Status / Source	Cause
	subsequent Turbine Trip.		at the time of reactor trip.	
94/ASB Backup Turbine Trip relay was actuated from inadvertent pushbutton trip.	An inadvertent actuation of the Pushbutton Trip would lead to an actuation of the 94/ASB relay and subsequent Turbine Trip.	**Refuted** Review of PI point TMANPBCO_A did not assert prior or during reactor trip.	**Closed** PI traces show no actuation of Pushbutton Trip.	**Not a Cause**

FPSC EXH No. 5
03/18/2024
ADMITTED

Support/Refute Matrix

Unit 3 Automatic Reactor Trip during restoration from B Train RPS testing 3-SMI-049.02B

Problem statement: During restoration step 5.1.6 of Train B RPS testing procedure 3-SMI-049.02B step which opens the Reactor Trip Bypass breaker B, Unit 3 experienced an automatic reactor trip. A review of the Sequence of Events report following the trip revealed the first alarm in was Turbine Trip HDR Pressure Channels, followed by Reactor Trip Relays 9 and 10, and then Reactor Trip Breakers A and B Trip. The SOE report demonstrates that the initiating event of the Reactor Trip was Turbine Trip which is driven by the 94/AST (primary) and 94/ASB (backup) relays. The Reactor Trip Breaker B and Bypass Breaker B provide trip logic to the 94/ASB relay.

Potential Cause	Discussion	Supporting / Refuting Evidence	Evidence Status / Source	Cause
Malfunction of 94/ASB relay causing inadvertent Turbine Trip.	A malfunctioning 94/ASB relay can cause an inadvertent Turbine Trip actuation.	**Refuted** Relay was tested and replaced recently during PT3-31 under WO 41542117-02. Likelihood of relay malfunctioning at the same time the Bypass B breaker was opened, with the relay located in a completely separate cabinet (3C89C).	**Closed**	**Not a Cause**

FPSC EXH No. 5
03/18/2024
ADMITTED

Attachment 6: Barrier Analysis

Hazard	Barrier	Assessment (Missing Barrier, Barrier Not Used, Inadequate Barrier, Successful Barrier)	Target	Insights
Quarterly Reactor Trip Testing performed IAW 3-SMI-049.02B results in a reactor trip	Design Barrier Train Separation / Channel Redundancy	RPS system is designed with redundant trains and channels to allow for successful testing online. **Successful Barrier**	Successful surveillance test without automatic reactor trip.	NA
	Physical Barrier Plastic Barrier on Reactor Trip Breakers	Surveillance procedure instructs personnel to place plastic barrier over RTB faceplate when manipulating BYB breaker **Successful Barrier**		NA
	Administrative Barrier Surveillance Testing Procedure	The subject RPS test is performed in accordance with 3-SMI-049.02B which provides a methodical and proven approach to testing which has been successfully performed in the past. **Successful Barrier**		NA
	Administrative Barrier	I&C Journeymen performing the work have proper training and		NA

FPSC EXH No. 5
03/18/2024
ADMITTED

Hazard	Barrier	Assessment (Missing Barrier, Barrier Not Used, Inadequate Barrier, Successful Barrier)	Target	Insights
	Training and Qualifications	qualifications to perform surveillance testing. **Successful Barrier**		
	<u>Administrative Barrier</u> Review and incorporation of fleet OE	Point Beach modified their Reactor Trip and Trip Bypass breaker circuits circa 1984 in response to Generic Letter 83-28 to meet the Westinghouse Owner's Group (WOG) recommendations. The modification included test points upstream of their turbine trip relay. However, these test points were not part of the WOG recommendations. Therefore, these test points were a unique PB design. This is considered a legacy issue and would not have been identified as part of OE reviews. **Barrier Not Used**		The installation of the test points would have provided a means of detecting a malfunction with the reactor trip breaker. This was not root to the issue but contributed to it. **CC1 - Test points to detect failed contacts were not installed.**
Westinghouse DB-50 Breaker and Cubicle Maintenance is	<u>Administrative:</u> Procedural inspections	DB-50 breakers and switchgear cubicles are inspected in accordance with 0-PME-049.01 which provides a methodical	Breakers and cubicle perform reliably without issues	**RC1 - IAW 0-PME-049.01, steps for cleaning and lubricating cell switch contacts is conditional**

FPSC EXH No. 5
03/18/2024
ADMITTED

Hazard	Barrier	Assessment (Missing Barrier, Barrier Not Used, Inadequate Barrier, Successful Barrier)	Target	Insights
inadequate to prevent breaker or cubicle reliability issues		and proven approach to maintain the equipment. However, steps to clean and lubricate the cell switch contacts located inside the cubicle are conditional based, rather than prescriptive. This can lead to lack of proper cleaning of the cell switch and relies on skill of the craft and judgement of the journeyman performing the inspection. **Inadequate Barrier**		**based, rather than prescriptive.**
	<u>Administrative Barrier</u> Preventive Maintenance Program Established	Reactor Trip and Bypass breakers, and cubicles are inspected on an 18-month frequency which meets Westinghouse MPM-DB recommendations of no more than 24 months. Each breaker cubicle has a unique PMID established in NAMS to track and drive work. **Successful Barrier**		NA


FPSC EXH No. 5
03/18/2024
ADMITTED

Hazard	Barrier	Assessment (Missing Barrier, Barrier Not Used, Inadequate Barrier, Successful Barrier)	Target	Insights
	Administrative Barrier Training and Qualifications	Electrical Maintenance journeymen are properly trained and maintain required qualifications to work on DB-50 breakers and switchgears. **Successful Barrier**		NA
	Administrative Barrier Vendor Recommendations Incorporated.	Procedure 0-PME-049.01 was developed using Westinghouse vendor manual V000211, and Westinghouse Maintenance Program Manual MPM-DB for Safety Related DB-50 Circuit Breakers and Associated Switchgear, E224A. All criteria in the site procedure meet vendor recommendations, with the exception of cell switch recommended life. Procedure does not check for cell switch cycles. There is no established PM for cell switch replacement. **Inadequate Barrier**		Forensics performed by vendor Westinghouse on the two removed cell switches noted that the switches appeared to be original plant equipment. The contacts had hardened grease, a foreign lubrication on the plunger rod, and no lubrication on the return spring. This is indicative of no maintenance performed on these components. Additionally, testing of the two cell switches identified one failed Normally Open contact in each switch. The contacts remained in the Open state when the plunger was either actuated or not actuated. Although this failure mode

FPSC EXH No. 5
03/18/2024
ADMITTED

Hazard	Barrier	Assessment (Missing Barrier, Barrier Not Used, Inadequate Barrier, Successful Barrier)	Target	Insights
				would not have resulted in a unit trip, it is indicative of an age related failure. **CC2 - Failure to follow WEC MPM cell switch maintenance and replacement frequency**

Attachment 7: Event and Causal Factor (E&CF) Analysis



FPSC EXH No. 5
03/18/2024
ADMITTED

Attachment 8: Organizational and Programmatic (O&P) Analysis

Causal Factor Categorization Analysis:

People

Summary:

The Root Cause Evaluation team did not identify any human performance or people related issues that contributed to this event.

Discussion:

As detailed in the Training Analysis, Barrier Analysis, and the Support/Refute Matrix, there were no people related issues identified.

Organizational

Summary:

The Root Cause Evaluation team did not identify any human performance or People related issues that contributed to this event.

Discussion:

As detailed in the Training Analysis, Barrier Analysis, and the Support/Refute Matrix, there were no Organizational related issues identified.

Programmatic

Summary:

Inadequate procedure steps for cell switch lubrication, implementation of WEC recommendations and the failure to install test points were all Programmatic issues.

Discussion:

RC1 – IAW 0-PME-049.01, steps for cleaning and lubricating cell switch contacts is conditional based, rather then prescriptive.
CC1 - Failure to incorporate PB/GL 83-28 action of installing test points

Causal Factor Characterization		
Cause Type	**Cause Statement**	**Category**

FPSC EXH No. 5
03/18/2024
ADMITTED

Root Cause (RC1)	**RC1** - IAW 0-PME-049.01, steps for cleaning and lubricating cell switch contacts is conditional based, rather than prescriptive	Programmatic
Contributing Cause (CC1)	**CC1** - Test points to detect failed contacts were not installed	Programmatic
Contributing Cause (CC2)	**CC2 -** Failure to follow WEC MPM cell switch maintenance and replacement frequency	Programmatic

FPSC EXH No. 5
03/18/2024
ADMITTED

Attachment 9: Safety Culture (SC) Analysis

06.01 Human Performance (H)

#	Criteria	Comment
H.1	**Resources:** Leaders ensure that personnel, equipment, procedures, and other resources are available and adequate to support nuclear safety (LA.1).	This is directly tied to RC1.
H.2	**Field Presence:** Leaders are commonly seen in the work areas of the plant observing, coaching, and reinforcing standards and expectations. Deviations from standards and expectations are corrected promptly. Senior managers ensure supervisory and management oversight of work activities, including contractors and supplemental personnel (LA.2).	Not observed.
H.3	**Change Management:** Leaders use a systematic process for evaluating and implementing change so that nuclear safety remains the overriding priority (LA.5).	Not observed.
H.4	**Teamwork:** Individuals and work groups communicate and coordinate their activities within and across organizational boundaries to ensure nuclear safety is maintained (PA.3).	Not observed.
H.5	**Work Management:** The organization implements a process of planning, controlling, and executing work activities such that nuclear safety is the overriding priority. The work process includes the identification and management of risk commensurate to the work and the need for coordination with different groups or job activities (WP.1).	Not observed.
H.6	**Design Margins:** The organization operates and maintains equipment within design margins. Margins are carefully guarded and changed only through a systematic and rigorous process. Special attention is placed on maintaining fission product barriers, defense-in-depth, and safety related equipment (WP.2).	Not observed.
H.7	**Documentation:** The organization creates and maintains complete, accurate and, up-to-date documentation (WP.3).	Not observed.
H.8	**Procedure Adherence:** Individuals follow processes, procedures, and work instructions (WP.4).	Not observed.
H.9	**Training:** The organization provides training and ensures knowledge transfer to maintain a knowledgeable, technically competent workforce and instill nuclear safety values (CL.4).	Not observed.
H.10	**Bases for Decisions:** Leaders ensure that the bases for operational and organizational decisions are communicated in a timely manner (CO.2).	Not observed.
H.11	**Challenge the Unknown:** Individuals stop when faced with uncertain conditions. Risks are evaluated and managed before proceeding (QA.2).	Not observed.

FPSC EXH No. 5
03/18/2024
ADMITTED

C3-383

H.12	**Avoid Complacency:** Individuals recognize and plan for the possibility of mistakes, latent issues, and inherent risk, even while expecting successful outcomes. Individuals implement appropriate error reduction tools (QA.4).	Not observed.
H.13	**Consistent Process:** Individuals use a consistent, systematic approach to make decisions. Risk insights are incorporated as appropriate (DM.1).	Not observed.
H.14	**Conservative Bias:** Individuals use decision making practices that emphasize prudent choices over those that are simply allowable. A proposed action is determined to be safe in order to proceed, rather than unsafe in order to stop (DM.2).	Not observed.

06.02 Problem Identification and Resolution (P)

#	Criteria	Comment
P.1	**Identification:** The organization implements a corrective action program with a low threshold for identifying issues. Individuals identify issues completely, accurately, and in a timely manner in accordance with the program (PI.1).	Not observed.
P.2	**Evaluation:** The organization thoroughly evaluates issues to ensure that resolutions address causes and extent of conditions commensurate with their safety significance (PI.2).	Not observed.
P.3	**Resolution:** The organization takes effective corrective actions to address issues in a timely manner commensurate with their safety significance (PI.3).	Not observed.
P.4	**Trending:** The organization periodically analyzes information from the corrective action program and other assessments in the aggregate to identify programmatic and common cause issues (PI.4).	Not observed.
P.5	**Operating Experience:** The organization systematically and effectively collects, evaluates, and implements relevant internal and external operating experience in a timely manner (CL.1).	Not observed.
P.6	**Self-Assessment:** The organization routinely conducts self-critical and objective assessments of its programs and practices (CL.2).	Not observed.

C3-381

FPSC EXH No. 5
03/18/2024
ADMITTED

Attachment 10: Corrective Action Line of Sight (LOS) Table

Event Description
On March 1, 2021 at 1112, Unit 3 experienced an unplanned automatic reactor trip during restoration of the 3B Reactor Protection System Logic Test, 3-SMI-049.02B (AR 2385529, WR 94220021). During performance of the SMI, the 3B Reactor Trip Bypass Breaker (BYB) is closed. As part of the restoration, the 3B Reactor Trip Breaker (RTB) breaker (Stamp 12) is closed and the BYB is locally tripped. When the BYB was tripped open, Unit 3 experienced an automatic reactor trip.
Extent of Condition
U4 Reactor Trip and Bypass Breaker Cell Switches, CRDM MG Set Output Breaker Cubicle Cell Switches, and Main Generator Field Breaker Cubicle Cell Switches (Breaker Model DS-206).

Cause	**Extent of Cause**	**Corrective Actions CAPRs and Related CAs**	**Effectiveness Review**
RC1 - IAW 0-PME-049.01, steps for cleaning and lubricating cell switch contacts is conditional based, rather than prescriptive.	CRDM MG Set Output Breaker Cubicle Cell Switch and Main Generator Field Breaker Cubicle Cell Switch inspection procedures	**CAPR1 -** Revise procedure 0-PME-049.01 to require cleaning and lubrication of cell switch contacts. **RC1 EOCa CA1 -** Review maintenance procedures for CRDM MG set output breaker and Generator Field breaker cubicles inspections and ensure cleaning of cell switch	**Method -** Review of U3 and U4 reactor trip breaker and bypass breaker cell switch inspection results. **Attributes -** Cell switches have been adequately lubricated. **Success Criteria -** All of U3 and U3 Reactor Trip and Trip

FPSC EXH No. 5
03/18/2024
ADMITTED

		contacts (if installed) is prescriptive. Revise procedures as necessary. **RC1 EOCa CA2** - Review maintenance procedures for CRDM MG set output breaker and Generator Field breaker cubicles inspections for other conditional steps, which if not performed, can result in equipment failure. Revise procedures as necessary. **CC1 EOC CA1 -** Investigate whether a similar vulnerability exists for CRDM MG set output breaker and Generator Field breaker control circuits. Initiate ECs to install test points if necessary. **CC2 EOC CA1 –** Create new PMID for CRDM MG set output breaker and Generator Field breaker cubicle cell switch replacements as necessary.	Bypass Breakers have new PMIDs for cell switch are properly lubricated

FPSC EXH No. 5
03/18/2024
ADMITTED

		CC2 EPC CA2 - Review Westinghouse Maintenance Program Manual (MPM) and ensure all components used for CRDM MG set output breaker and Generator Field applications have a maintenance strategy established commensurate with the MPM.	

FPSC EXH No. 5
03/18/2024
ADMITTED

Attachment 11: List of Documents Reviewed

Document #	Title
PI-AA-100-1005	Root Cause Analysis
PI-AA-104-1000	Condition Reporting
PI-AA-102-1001	Operating Experience Program Screening and Responding to Incoming Operating Experience
PTN 1507092	Inspect Reactor Trip Breaker OJT-TPE
PTN 1518092	Reactor Trip Breakers Lesson Plan
PTN ICM	RPS Logic Test JITT
Westinghouse MBM	Safety Related Type DB Breakers and Associated Switchgear
NAP-418	Equipment Repair and Refurbishment
0-ADM-115	Notification of Plant Events
0-ADM-511	Post Trip Review (PTR)
INPO	INPO OE Search Program
3-SMI-049-02B	3B Reactor Protection System Logic Test
0-PME-09.01	RTB Cubicle and Breaker Inspections
ODI-CO-044	Operations Pre-Job Briefs

FPSC EXH No. 5
03/18/2024
NEXTera ENERGY
ADMITTED

Attachment 12: Industry Maintenance Practices on Cell Switches

INDUSTRY MAINTENANCE PRACTICES FOR DB-50 SWITCHGEAR CELL SWITCHES				
PLANT	INSPECTION PM FRQ	REPLACEMENT PM FRQ	INSPECTION INCLUDES:	COMMENTS
Turkey Point	18M	N/A	• Cover removal • Verification of clean switch contacts • If contacts require cleaning or lubrication, then: o Clean contacts o Apply graphite grease 53701AN00T • Plunger actuation and confirmation of: o Correct contact configuration o Contact resistance	When compared to two other plants listed below, PTN does not validate for free movement of plunger. Cleaning and application of graphite grease is conditional.
Robinson Nuclear Plant	8Y	N/A	• Cover removal • Plunger actuation and confirmation of: o Free movement o Proper contact operation o Presence of graphite grease on contacts • Application of 53701GW lubricant to spring and plunger penetration point • Removal of old graphite grease and reapplication if no grease is present. • Contact resistance checks with switch in OPEN and CLOSED position	RNP previously had a 12Y replacement PM but was subsequently retired to inspection PM. Cleaning and application of graphite grease is conditional.
D.C. Cook	18M	N/A	• Switch removal from cubicle • Plunger actuation and confirmation of: o Free movement o Proper contact operation • Cleaning of switch • Inspection of switch contacts for: o Cracked cases	D.C. Cook has no replacement PM for cell switches. Cleaning of switch is prescriptive. Application of graphite grease is conditional.

FPSC EXH No. 5
03/18/2024
NEXTera ENERGY
ADMITTED

			○ Burned or pitted contacts ○ Loss of silver plating (exposed copper) • Replacement of switch IF binding, damaged, burned or pitted contacts, loss of silver plating • Inspection for very light coating of graphite grease on switch contact segments (interface with fingers)	
Sequoyah	36M	7RO	• Switch removal from cubicle • Inspect switch for: ○ Loose hardware ○ Loose wiring ○ Overheating ○ Burning and pitting of contacts ○ Cracking or abnormal wear of phenolic contact housing • Plunger actuation and confirmation of: ○ Free movement ○ Proper contact operation • Clean contacts to remove hardened grease • Lubricate contacts and plunger • Resistance checks across contacts (0.1ohm or less)	The 7RO replacement frequency is based on the 100 cycle recommendation from the MPM and assumes 15 cycles per RO.

FPSC EXH No. 5
03/18/2024
ADMITTED

Enclosure 1

WESTINGHOUSE PROPRIETARY CLASS 2

Westinghouse Electric Company Nuclear Parts Operations New Stanton, Pennsylvania

Failure Analysis Report

Florida Power & Light Company Turkey Point Nuclear Station
Purchase Order (PO): 02423936 Westinghouse Sales Order: 160387

Westinghouse was contacted on March 3rd concerning an experienced automatic reactor trip and was provided the following information:

"Background:

On 3/2/2021, with Unit 3 at 100% power, Turkey Point Nuclear was performing a scheduled Interlock, Logic and Actuation Test in Unit 3 Train B of Reactor Protection System (RPS). This test requires the 3B RPS reactor bypass breaker to be racked-in and closed, so that actuation tests could be performed on the 3B RPS reactor trip breaker, without initiating a reactor trip. Test restoration phase includes closing the 3B reactor trip breaker and, subsequently, opening the reactor bypass breaker. With the 3B reactor trip breaker closed, and right after opening of the 3B bypass breaker, Unit 3 experienced an automatic reactor trip. A failure investigation is ongoing and, although the condition has not been replicated, currently the investigation team suspects about an equipment-related stressor that may have affected the 3B reactor trip breaker performance; thus, causing the unanticipated reactor trip. The suspected reactor trip breaker has been removed from the field.

Request:

Turkey Point Nuclear requests from Westinghouse to conduct exhaustive inspection and testing, in order to identify an equipment related condition that could explain the scenario discussed above. It is requested that a formal Failure Analysis Report be transmitted to Turkey Point that includes: basis for testing methodology, test sequence and results (including pictures), conclusions, and recommendations. Upon test completion, Turkey Point Nuclear requests Westinghouse to conduct a Turkey Point-standard refurbishment/overhaul scope and return to Turkey Point Nuclear for future use."

The Reactor Trip Breaker was received at the Westinghouse New Stanton facility at the end of the day, March 10, 2021. Also received were 2, DB cell switch assemblies. The next morning the breaker and switches were unboxed and photographed and shown here.

FPSC EXH No. 5
03/18/2024

ADMITTED

C3-491


Failure Analysis Report

WESTINGHOUSE PROPRIETARY CLASS 2

Purchase Order (PO): 02423936
Westinghouse Sales Order: 160387



As Received Front of Breaker




As Received Rear of Breaker



As Received Left Side of Breaker Platform



As Received Right Side of Breaker Platform



As Received Left Side of Breaker



As Received Right Side of Breaker

This breaker was received looking as it had just been refurbished, there were no visible areas of concern.

C3-389

FPSC EXH No. 5
03/18/2024
ADMITTED

C3-392

WESTINGHOUSE PROPRIETARY CLASS 2

Failure Analysis Report

Purchase Order (PO): 02423936
Westinghouse Sales Order: 160387



As Received Left-Side Cell Switch



As Received Right-Side Cell Switch

These cell switches were received and looked like they were the original switches provided with the switchgear. The switch plungers were improperly lubricated, and the plunger return spring was not lubricated.

An acceptable Purchase Order was received on March 16th and the investigation was initiated. 16-

Mar-21

Information collected from the breaker.

Breaker Shop Order Tag Number:	850.181-2
Breaker Serial Numbers:	880.510-3, 206.041-1 / IT-10 and 212.025-1 / IT-10
Customer Tag Information:	Stamp 12 (4-20-2000)
CAT ID: 0000344772 1	
UTC #: 0000402246	
Operating Mechanism Serial Number:	212.025-1 / IT-10
Closing Solenoid Part Number:	28A2154G25
Closing Solenoid Coil Style Number:	300P606G01
Closing Solenoid Operating Voltage:	125 V DC
Control Relay Part Number:	2A10090G01
Control Relay Coil Style Number:	1529444
Control Relay Operating Voltage:	125 V DC
Control Relay Blow-Out Coil Style Number:	1589341
Shunt Trip Attachment (STA) Part Number:	508B504G01
STA Serial Number:	02YN222-083
STA Coil Style Number:	677C903G07
STA Operating Voltage:	125 V DC

C3-390

FPSC EXH No. 5
03/18/2024
ADMITTED

C3-393

WESTINGHOUSE PROPRIETARY CLASS 2

Failure Analysis Report

Purchase Order (PO): 02423936
Westinghouse Sales Order: 160387

Under Voltage Trip Attachment (UVTA) Part #:	5365C50G01
UVTA Coil Style Number:	677C903G07
UVTA Operating Voltage:	125 V DC
Cycle Counter Reading:	01699

After being refurbished, this breaker shipped from Westinghouse on 3-Jul-2012 with a counter reading of 01400. This breaker was cycled less than 300 times before being returned to Westinghouse for this investigation. The Maintenance Program Manual for Westinghouse Safety Related Type DB Circuit Breakers and Associated Switchgear, Revision 1, July 2011 provides the following recommendations:

With proper maintenance and inspections of the circuit breaker and cell at the interval recommended the breaker and cell values can be exceeded as addressed later in this section. The service/cycle life of the DB circuit breaker and its components are based on industry standards, testing and analysis. Westinghouse does not recommend these components be considered run-to-failure components, however with proper maintenance and inspection of the breaker and cell components, the recommended lives could be justified beyond the values provided.

The basis for the design life of the cell switch, primary finger clusters and the secondary contacts is American National Standards Institute/Institute of Electrical and Electronics Engineers (ANSI/IEEE) C37.20.1-1987, "An American National Standard, IEEE Standard for Metal-Enclosed Low-Voltage Power Circuit-Breaker Switchgear," subsection 5.2.5. This section defines a low voltage (LV) switchgear with draw-out circuit breakers shall have mechanical endurance test cycles consisting of at least 100 operations between connected and test position.
With proper maintenance and analysis of the components the 100 operation/cycle life of the cell components could be extended. The end of life condition of these components is not known.
The switch that is used as the cell switch is the same switch used as an auxiliary switch on the DB breaker with a qualified life of 4,000 cycles on the DB-50 breaker. The remaining components of the cell switch consist of a metal frame, a metal operations bar and a metal return spring. None of these components are sensitive to age within 100 cycles.

If proper maintenance has been performed the breakers and cell components will operate beyond the service life recommendation. However, the support for the extended service life will be based on the documentation for those parts that have been collected during the maintenance activities.

Westinghouse recommends that DB switchgear be maintained to the requirements of this Maintenance Program Manual, Westinghouse uses additional requirements and additional margin when testing a new or refurbished breaker. These requirements are included in Commercial Dedication Instructions (CDI) that are proprietary to Westinghouse Electric Company. The CDI that was used as a guide for this investigation was CDI-3416, "DB-25 and DB-50 Air Circuit Break Refurbishment Instructions," Revision 08, dated 30-May-2024.

The investigation involved the assistance of engineering, of a quality assurance technician and a mechanical or electrical technician.

C3-391

FPSC EXH No. 5
03/18/2024

ADMITTED

C3-494

WESTINGHOUSE PROPRIETARY CLASS 2

Failure Analysis Report

Purchase Order (PO): 02423936
Westinghouse Sales Order: 160387

Provided by Florida Power & Light Company was Drawing 5613-E-29, Revision 5, Sheet 22A, "Turbine Auxiliaries Turbine Trip Solenoids," that shows the breaker and cell switch series parallel contact arrangement. The applicable breaker Normally Closed (NC) auxiliary switches are in series and are wired to breaker secondary terminals 13 and 14. Before cycling the breaker or removing any item from the breaker a hand-held multimeter was used to monitor the NC contact wired to terminals 13 and 14 as shown here.

The UVTA reset arm was restrained to allow the breaker to be closed, the breaker was manually closed. These photos show that this NC contact changed state when the breaker was closed. Also verified was that there was no interference from closing the breaker.




Breaker Open, Switch Contact Closed



Breaker Closed, Switch Contact Open

The arc chute assemblies were removed, and no concerns were found. The assemblies were not disassembled at this time.



Breaker Open, With Arc Chutes Removed



Breaker Contacts

The front auxiliary switch covers were removed, and the switches were visually inspected. No concerns were found, and the switch contacts appeared to be properly lubricated.

FPSC EXH No. 5
03/18/2024


ADMITTED

C3-495


WESTINGHOUSE PROPRIETARY CLASS 2

Failure Analysis Report

Purchase Order (PO): 02423936
Westinghouse Sales Order: 160387




Front of Auxiliary Switches



Auxiliary Switch Lubrication

The front cover of the control relay was removed, and the relay was visually inspected, no concerns were found.



Control Relay with Front Cover Removed

The breaker escutcheon plate assembly, face plate, operating mechanism cover and counter were all removed. The plating was visually inspected, the metal structure was plated with yellow zinc dichromate and the main and secondary current carrying were parts were silver plated with no flaking, peeling or bubbling. The insulating materials were inspected for cracks, voids or any other damage.

The entire breaker was inspected for cleanliness. The internal parts of the operating mechanism were inspected and found to be free of foreign material. The breaker was visibly free of foreign materials.

The operating mechanism, inertia latch, UVTA, STA assembly, pole unit hinges and auxiliary switch contacts were visually inspected for proper lubrication. The breaker appeared to be sufficiently lubricated.

All retaining rings were verified to be present on the breaker and accessories. The welds and brazes were also visually inspected and found to be acceptable as received.

The breaker escutcheon plate assembly, face plate, operating mechanism cover and counter and the ground contact were all removed so that the breaker could be inserted into the alignment fixture. The meter connected to secondary terminals 13 and 14 and the switch contacts were monitored visually.

C3-393

FPSC EXH No. 5
03/18/2024
ADMITTED


Failure Analysis Report

Purchase Order (PO): 02423936
Westinghouse Sales Order: 160387


The breaker is shown in the alignment fixture. The back panel was properly aligned with the rear stops, the four rollers were all aligned to make contact with the rail assemblies, and the door could be properly closed without interference. The breaker was manually closed, and the DB-50 positioning trip lever trip tab and the operating trip bar gap was verified to be acceptable (0.122").

The main and secondary contact alignment were verified and found to be acceptable. The


alignment fixture door was opened to verify that the breaker would trip open, it did.
The auxiliary switches changed state. The breaker was removed and moved to a breaker work cart.




Breaker in Alignment Fixture



Breaker in Alignment Fixture



Alignment Fixture Rear Stop



Breaker in the Connect Position


FPSC EXH No. 5
03/18/2024
ADMITTED

C3-497


WESTINGHOUSE PROPRIETARY CLASS 2

Failure Analysis Report

Purchase Order (PO): 02423936
Westinghouse Sales Order: 160387



Breaker Stud Alignment



Breaker Secondary Alignment

The hand-held multimeter was used to monitor the NC contact wired to terminals 13 and 14, The


operating mechanism trip bar was gently lifted to verify that it moved freely, it did.

The main and arcing contacts were inspected and were found to be properly setup.

The operating mechanism operation was verified manually. There was no binding of parts. When holding the trip bar in an up position and attempting to manually close the breaker it was found to be trip free as is expected.

The breaker trip force measured and found acceptable:	18.1 ounces
The distance to trip was measured and found acceptable:	0.101”
The breaker trip bar to platform height was measured and found acceptable:	L. H. 0.084”
R.H. 0.094”	

The face plate was reinstalled onto the breaker operating mechanism so that the gap between the Push to Trip arm and the rear of the operating mechanism trip pan can be verified, as shown below.



Operating Mechanism Inspection Hole

C3-395

FPSC EXH No. 5
03/18/2024
ADMITTED

C3-398

WESTINGHOUSE PROPRIETARY CLASS 2

Failure Analysis Report

Purchase Order (PO): 02423936
Westinghouse Sales Order: 160387

The manually closing shaft was rotated in each direction to verify it was free and to verify that the manual closing roller did not make contact with the rear of the trip pan. The face plate was removed from the operating mechanism.

The secondary contact gap was verified to be less than 0.010" as required. The clearances around the inertia latch were inspected and found to be acceptable. The inertia latch was removed to verify the there was no plating on the pin or bushing. The inertia latch was reinstalled. The NC auxiliary switch (terminals 13 & 14) operated as required 100 % of the time the breaker was cycled. The breaker was moved to the electrical shop.

The wiring of the breaker was verified, and all of the auxiliary switches were verified to change state when the breaker was cycled.

Secondary Contact Number	Auxiliary Switch	Contact Configuration Terminal	Auxiliary Switch	Secondary Contact Number
		Bottom Auxiliary Switch		
3 – STA Coil	1	NO	2	7
4	3	NC	4	8 + Closing + Relay Coils
9	5	NO	6	10
5	7	NC	8	6
		Middle Auxiliary Switch		
19	1	NO	2	20
17	3	NC	4	18
15	5	NO	6	16
13	7	NC	8	14
		Top Auxiliary Switch		
23	1	NO	2	24
21	3	NC	4	22
	5	NO	6	
	7	NC	8	

11 UVTA Coil 12

The resistance of the coils were measured and recorded:

Closing Coil:	6.1 Ω
Control Relay Coil:	1273 Ω
Control Relay Blow-out Coil:	0.052 Ω
STA Coil:	56.7 Ω
UVTA Coil:	997 Ω

Millivolt drop tests were performed with 100 Amps DC, between the main upper stud and the lower main stud, with a barrier between the main contacts the millivolt drop tests between the stationary and moving arcing contacts and with the barrier still installed , between the main upper stud and the lower main stud. The results are provided here:

C3-396

FPSC EXH No. 5
03/18/2024
ADMITTED

Failure Analysis Report

Purchase Order (PO): 02423936
Westinghouse Sales Order: 160387

Millivolt Drop Testing

Upper - Lower Stud, Phase 'A'	(< 4 mV):	11.9 mV
Upper - Lower Stud, Phase 'B'	(< 4 mV):	82.1 mV
Upper - Lower Stud, Phase 'C'	(< 4 mV):	33.9 mV

Millivolt Drop Testing


Stationary - Moving Arcing Contact, Phase 'A'	(<6.5 mV):	270.6 mV
Stationary - Moving Arcing Contact, Phase 'B'	(<6.5 mV):	192.2 mV
Stationary - Moving Arcing Contact, Phase 'C'	(<6.5 mV):	52.5 mV

Millivolt Drop Testing


Upper - Lower Stud, Phase 'A'	(< 20 mV):	325.2 mV
Upper - Lower Stud, Phase 'B'	(< 20 mV):	139.7 mV
Upper - Lower Stud, Phase 'C'	(< 20 mV):	69.6 mV

These values were greater than expected. Photos were taken of these contacts and then the contacts were cleaned with Scotchbrite and isopropyl alcohol. Additional photos were taken to show the cleaned contacts.

Stationary Arcing Contacts



Phase A



Phase B



Phase C

FPSC EXH No. 5
03/18/2024
ADMITTED


C3-500

WESTINGHOUSE PROPRIETARY CLASS 2

Failure Analysis Report

Purchase Order (PO): 02423936
Westinghouse Sales Order: 160387

Moving Arcing Contacts



Phase A




Phase B




Phase C

Main Moving Contacts



Before Cleaning



Cleaned Contacts

C3-398

FPSC EXH No. 5
03/18/2024
ADMITTED


C3-501

WESTINGHOUSE PROPRIETARY CLASS 2


Failure Analysis Report

Purchase Order (PO): 02423936
Westinghouse Sales Order: 160387

Stationary Arcing Contacts After Cleaning



Phase A



Phase B



Phase C

Moving Arcing Contacts After Cleaning



Phase A



Phase B



Phase C

Millivolt drop tests were repeated as described above.

Millivolt Drop Testing

Upper - Lower Stud, Phase 'A'	(< 4 mV):	3.1 mV
Upper - Lower Stud, Phase 'B'	(< 4 mV):	2.1 mV
Upper - Lower Stud, Phase 'C'	(< 4 mV):	2.5 mV

C3-399

FPSC EXH No. 5
03/18/2024
ADMITTED

C3-502

WESTINGHOUSE PROPRIETARY CLASS 2

Failure Analysis Report

Purchase Order (PO): 02423936
Westinghouse Sales Order: 160387

Millivolt Drop Testing

Stationary - Moving Arcing Contact, Phase 'A'	(<6.5 mV):	3.9 mV
Stationary - Moving Arcing Contact, Phase 'B'	(<6.5 mV):	32.0 mV
Stationary - Moving Arcing Contact, Phase 'C'	(<6.5 mV):	6.1 mV

Millivolt Drop Testing


Upper - Lower Stud, Phase 'A'	(< 20 mV):	19.9 mV
Upper - Lower Stud, Phase 'B'	(< 20 mV):	47.9 mV
Upper - Lower Stud, Phase 'C'	(< 20 mV):	22.6 mV

After receiving values greater than expected the pole bases will need to be disassembled and cleaned as a standard part of a DB breaker refurbishment. These values are not a concern for the tripping of the breaker, simply that the contacts were slightly oxidized. After applying operating current to the pole bases the oxidation would burn off and the breaker would operate fine.

The hand-held multimeter was used to monitor the NC contact wired to terminals 13 and 14, 17-

Mar-21

The mechanical set-up of the control relay was verified and the closing solenoid moving core relay release arm was verified to be correct by manually slow closing the breaker and having the closing solenoid relay trip window assembly moving before the operating mechanism pawl drops. The anti-pump function of the relay was verified, and the contact sequence was correct and the contact overtravel was also found to be acceptable.



Control Relay with Arc Chamber Pulled Down The breaker was electrically cycled

as outlined here.

125 V DC		70 V DC
87 V DC (x 3)		100 V DC
144 V DC (x3)		110 V DC
	120 V DC	
	130 V DC	
	140 V DC	

C3-400

FPSC EXH No. 5
03/18/2024
ADMITTED

At each of these voltages the breaker successfully closed and the NC contact on terminals 13 and 14 operated as expected.

The focus of the investigation moved to the Shunt Trip Attachment.
The moving core of the shunt trip was held in to contact the stationary core, simulating the energization of the shunt trip coil. In this position an attempt was made to manually close the breaker, the breaker was trip free as was expected. The moving core was then released, and it returned to the original position. A visible gap was verified between the shunt trip attachment trip paddle and the operating mechanism trip bar. The moving core was then rotated while moving the core into the stationary core and verified that each time it returned to the original position. This was performed 12 times or at approximately 30 degree intervals. This test verified that the moving core and brass tube that it moves through is free to move without effecting the operation of the STA.


The breaker was electrically closed with 125 V DC. The STA trip lever gap was measured.

Trip Lever / Bar Gap Measured (0.031" – 0.203"): 0.130"

While the breaker was still closed a weight was added to the operating mechanism trip bar to achieve a minimum of 48 ounces, as determined by measuring the breaker trip force.

Trip bar force with added weight: 48.16 Ounces

After this weight was established the weight was removed and the breaker was closed with 125 V DC, the weight was added back onto the trip bar and the STA was energized with 69 V DC, thus tripping the breaker showing margin in the weight that the STA is able to pull with the minimum voltage applied. The breaker was successfully tripped 3 times with this setup. A photo has been provided to show the weight hung of the trip bar.



Additional Weight Added to the Operating Mechanism Trip Bar

FPSC EXH No. 5
03/18/2024
ADMITTED

WESTINGHOUSE PROPRIETARY CLASS 2

Failure Analysis Report

Purchase Order (PO): 02423936
Westinghouse Sales Order: 160387

With the weights removed from the trip bar the breaker was cycled 1 time at 125 V DC. The breaker was then cycled 1 time with 144 V DC.
The moving core of the shunt trip was again held in to contact the stationary core, simulating the energization of the shunt trip coil. In this position an attempt was made to manually close the breaker, the breaker was trip free as was expected.

The focus of the investigation moved to the Under-Voltage Trip Attachment.
The breaker was closed with 125 V DC and the UVTA restraining string was slowly released. The UVTA had a positive snap action before tripping the breaker open.
The reset of the UVTA was verified by pushing the center moving contact arm towards the closed position. The UVTA tripped. Then by slowly releasing the center moving contact arm. The UVTA reset just as the closing lever returns to a fully open position.
With the UVTA deenergized the manual closing handle is used to verify the breaker is trip free, it was.

The UVTA was energized with 125 V DC and the breaker was electrically closed with 125 V DC.
The distance from the centerline of the UVTA trip lever pin to the edge of the mechanism trip bar was measured and recorded.
Trip Lever Pin – Trip Bar (0.406" – 0.531"): 0.515"

With the breaker closed, the gap between the UVTA trip lever and the mechanism trip bar was measure and recorded
Trip Lever / Bar Gap Measured (0.031" – 0.094"): 0.054"

The UVTA was energized with rated voltage for a minimum of 15 minutes before proceeding.
As described above, while the breaker was closed a weight was added to the operating mechanism trip bar to achieve a minimum of 48 ounces, as determined by measuring the breaker trip force.
Trip bar force with added weight: 51.04 Ounces

The removal of the voltage from the UVTA did not caused the breaker to trip. The weight required to trip the breaker was reduced to 48.0 Ounces

The removal of the voltage from the UVTA successfully caused the breaker to trip.
The UVTA was lubricated and then cycled several times for the lubrication to work its way into the pins. The UVTA was again energized and the breaker was electrically closed. Trip weight was added onto the trip bar (51.04 ounces). Again, the removal of the voltage from the UVTA caused the breaker to trip successfully. The weight was removed.

The UVTA drop-out voltage was measured: 1.) 53.8 V DC
2.) 51.8 V DC
3.) 51.9 V DC

The UVTA was again energized with 125 V DC and the breaker was closed with 125 V DC. A plastic head hammer was used to shock the breaker platform in an attempt to shock out the UVTA or cause the breaker to trip open. A photo of this is provided below. The UVTA did not release and the breaker did not open.

The UVTA and breaker operated successfully. Cycles added to the UVTA – 17.

FPSC EXH No. 5
03/18/2024
ADMITTED

C3-505

WESTINGHOUSE PROPRIETARY CLASS 2

Failure Analysis Report

Purchase Order (PO): 02423936
Westinghouse Sales Order: 160387



Breaker Platform Shock Test Timing tests were performed on this breaker:

The breaker open by energizing the STA	29.2 m Sec.
The breaker open by de-energizing the UVTA	61.3 m Sec.
The breaker was electrically closed	164.6 m Sec

The NC auxiliary switch (terminals 13 & 14) operated as required 100 % of the time the breaker was cycled.
The incoming electrical testing of the breaker was completed.

C3-403

FPSC EXH No. 5
03/18/2024
ADMITTED

Purchase Order (PO): 02423936
Westinghouse Sales Order: 160387

DB Cell Switches, P/N: 302C517G01

The breaker was moved a side and the investigation of the DB cell switches began

The switches are identified as Left-Side Switch and Right-Side Switch as labeled in the photos.



Left-Side Switch




Right-Side Switch

The push rod of the cell switches were lubricated with a foreign lubrication and the return springs were not lubricated with anything. These two locations are to be lubricated with Molybdenum Disulfide in Isopropyl Alcohol (53701GW) lubricant during maintenance intervals.



Left-Side Switch



Right-Side Switch


FPSC EXH No. 5
03/18/2024
ADMITTED

C3-507


WESTINGHOUSE PROPRIETARY CLASS 2

Failure Analysis Report

Purchase Order (PO): 02423936
Westinghouse Sales Order: 160387



Left-Side Switch



Right-Side Switch

The front switch covers were removed and both switches appeared to have grease that had hardened on the contacts.

The left side switch was clamped to a bench, a multimeter was connected to a NC switch to monitor the operation of the switch.



Left-Side Switch



Left-Side Switch Monitoring

C3-405

FPSC EXH No. 5
03/18/2024

ADMITTED

C3-508

WESTINGHOUSE PROPRIETARY CLASS 2

Failure Analysis Report

Purchase Order (PO): 02423936
Westinghouse Sales Order: 160387

Plunger force testing and distance to change state testing were performed on this switch, the photos provided show the force test setup.

Left-Side Switch



Force Test Set-Up



Force Test Set-Up

The force was measured when the plunger started to move, when the contact changed state and the maximum force achieved. The results are:

Start of Moving:	7.23 Lbs.	6.79 Lbs.	6.98 Lbs.
Change of State:	15.21 Lbs.	14.92 Lbs.	15.34 Lbs.
Maximum Force:	21.98 Lbs.	23.49 Lbs.	20.76 Lbs.

The distance required to move the plunger to cause the switch contacts to change state was measured.

Distance required to change the switch state: 0.524”

The single contact that was monitored worked 100%of the time. Four multimeters were then connected to each of the 4 switches. The switch was cycled and the switch at the end (switch terminals 7 & 8) remained open in both states of the switch as shown in these photos.



Breaker Open Switch Position
(Plunger Not Actuated)



Breaker Closed Switch Position
(Plunger Actuated)

FPSC EXH No. 5
03/18/2024
ADMITTED


Failure Analysis Report

Purchase Order (PO): 02423936
Westinghouse Sales Order: 160387

Expected switch configuration / state.

Left Side Switch	Contact 1	Contact 2	Contact 3	Contact 4
	Terminals 1 & 2	Terminals 3 & 4	Terminals 5 & 6	Terminals 7 & 8
Plunger not actuated	CLOSED	OPEN	CLOSED	OPEN
Plunger actuated	OPEN	CLOSED	OPEN	CLOSED

The rear cover of the switch was removed, the contact rotor can be seen moving. The resistance was then measured between the terminal screws and the stationary contacts. It was a closed circuit between terminal 7 and the top stationary contact, it was an open circuit between terminal 8 and the bottom stationary contact. The switch plunger was cycled 50 times while monitoring the switch contacts. Switch contacts 1, 2 and 3 changed state each time the plunger was cycled. Switch contact 4 (terminals 7 & 8) remained open for each of the cycles. The bottom stationary contact associated with terminal 8 appears to be out of place as seen in the photo below.




Left Side Switch - Switch Contact 4, Terminal 8

The right-side switch was clamped to a bench, a multimeter was connected to a NC switch to monitor the operation of the switch.



Right-Side Switch



Right-Side Switch Monitoring

FPSC EXH No. 5
03/18/2024
ADMITTED

Failure Analysis Report

Purchase Order (PO): 02423936
Westinghouse Sales Order: 160387

Plunger force testing and distance to change state testing were performed on this switch, the same set-up was used as shown above.

The force was measured when the plunger started to move, when the contact changed state and the maximum force achieved. The results are:

Start of Moving:	7.46 Lbs.	6.21 Lbs.	6.23 Lbs.
Change of State:	13.77 Lbs.	13.06 Lbs.	13.23 Lbs.
Maximum Force:	20.48 Lbs.	19.55 Lbs.	22.37 Lbs.


The distance required to move the plunger to cause the switch contacts to change state was measured.

Distance required to change the switch state: 0.588”

The single contact that was monitored worked 100% of the time. Four multimeters were then connected to each of the 4 switches. The switch was cycled and the switch at the end (switch terminals 3 & 4) remained open in both states of the switch as shown in these photos.



Right-Side Switch Monitoring



Right-Side Switch Monitoring Connections



Breaker Open Switch Position



Breaker Closed Switch Position

FPSC EXH No. 5
03/18/2024
ADMITTED


Failure Analysis Report

Purchase Order (PO): 02423936
Westinghouse Sales Order: 160387

Expected switch configuration / state.


Right Side Switch	Contact 1	Contact 2	Contact 3	Contact 4
	Terminals 1 & 2	Terminals 3 & 4	Terminals 5 & 6	Terminals 7 & 8
Plunger not actuated	CLOSED	OPEN	CLOSED	OPEN
Plunger actuated	OPEN	CLOSED	OPEN	CLOSED

The rear cover of the switch was removed, the contact rotor can be seen moving. The resistance was then measured between the terminal screws and the stationary contacts. It was a closed circuit between terminal 3 and the top stationary contact, it was an open circuit between terminal 4 and the bottom stationary contact. The switch plunger was cycled 50 times while monitoring the switch contacts. Switch contacts 1, 3 and 4 changed state each time the plunger was cycled. Switch contact 2 (terminals 3 & 4) remained open for each of the cycles. The bottom stationary contact associated with terminal 4 appears to be out of place as seen in the photo below.



Switch Contact 2, Terminal 4

Both the left-side switch and right-side switch were removed from their base plates and were verified per drawing to be assembled correctly.



Switch Contact Verification

FPSC EXH No. 5
03/18/2024
ADMITTED

C3-512

WESTINGHOUSE PROPRIETARY CLASS 2

Failure Analysis Report

Purchase Order (PO): 02423936
Westinghouse Sales Order: 160387

The switch rotors were removed from each of the switches and the bottom stationary contact finger in each case had come loose from the terminal point as shown here (left-hand switch and right)



Left-Side Switch Stationary Contacts



Right-Side Switch Stationary Contacts



Left-Side Switch Stationary Contacts



Right-Side Switch Stationary Contacts A

brief overview of the findings with the 2 cell switches was provided to site on 17-Mar-21.

18-Mar-21

After having a discussion with Bob Tomonto and Orlando Carol from FP&L, we all agreed that it was time to start the disassembly of the breaker.

The disassembly began with pulling on every wire connected to a terminal that could be accessed. No terminal connections were found to be loose. The auxiliary switch wires were removed from their terminal screws and again the wires and terminals were verified. No issues found. The rear covers were removed, and photos were taken.

C3-410

FPSC EXH No. 5
03/18/2024
ADMITTED

C3-513

WESTINGHOUSE PROPRIETARY CLASS 2

Failure Analysis Report

Purchase Order (PO): 02423936
Westinghouse Sales Order: 160387



Front of Auxiliary Switches



Rear of Auxiliary Switches

The auxiliary switches were removed from the platform, visually inspected, and then disassembled.



Front of Auxiliary Switches



Rear of Auxiliary Switches

C3-411

FPSC EXH No. 5
03/18/2024
ADMITTED

C3-514

WESTINGHOUSE PROPRIETARY CLASS 2

Failure Analysis Report

Purchase Order (PO): 02423936
Westinghouse Sales Order: 160387



Disassembled Auxiliary Switches No issues were found with the auxiliary

switch assembly.

The control relay was removed from the breaker platform and the wires and terminals were verified.



Breaker with the Auxiliary Switches and Control Relay Removed


C3-412

FPSC EXH No. 5
03/18/2024
ADMITTED

WESTINGHOUSE PROPRIETARY CLASS 2

Failure Analysis Report


Purchase Order (PO): 02423936
Westinghouse Sales Order: 160387



Front of Control Relay



Rear of Control Relay



Side of Control Relay




Other Side of Control Relay

FPSC EXH No. 5
03/18/2024
ADMITTED

Failure Analysis Report

Purchase Order (PO): 02423936
Westinghouse Sales Order: 160387


After the control relay was removed from the platform it was visually inspected, and then disassembled.




Disassembled Control Relay No issues were found with the control

relay assembly.

The wires were removed from the secondary contact assembly and the wires and terminals were verified. The secondary contact assembly and the lifting bracket were removed from the breaker.



Secondary Contact Assembly on Breaker



Secondary Contact Assembly Removed

No issues were found with the secondary contact assembly.

The wires were removed from the Shunt Trip Attachment and it was removed from the breaker platform.

FPSC EXH No. 5
03/18/2024
ADMITTED

C3-517

WESTINGHOUSE PROPRIETARY CLASS 2

Failure Analysis Report

Purchase Order (PO): 02423936
Westinghouse Sales Order: 160387



Breaker without the STA



STA Assembly Removed

The STA was visually inspected and disassembled, no issues were found.



Disassembled STA


The wires were removed from the Under-Voltage Trip Attachment and it was removed from the breaker platform. The assembly was visually inspected but was not disassembled.

C3-415

FPSC EXH No. 5
03/18/2024
ADMITTED

Failure Analysis Report

Purchase Order (PO): 02423936
Westinghouse Sales Order: 160387



Breaker without the STA and UVTA



UVTA Assembly Removed


Side of UVTA



Other Side of UVTA

The visual inspection of the UVTA did not provide anything to be concerned about.

The cross bar was removed followed by the operating mechanism. The operating mechanism was visually inspected.



Breaker with the Operating Mechanism Removed



Operating Mechanism

FPSC EXH No. 5
03/18/2024
ADMITTED

Failure Analysis Report

Purchase Order (PO): 02423936
Westinghouse Sales Order: 160387

The breaker lock-out tabs on the front of the operating mechanism were found to be slightly bent, however the breaker operated without incident during all mechanical and electrical testing. If these tabs had been bent enough to prevent the Push to Trip button from fully returning to the reset position the linkage within the mechanism could prevent the breaker from closing or could cause a situation that the breaker might close, but not remain closed. These photos show that without the face plate attached to the operating mechanism the Push to Trip button is free to fall below its normal position. This is not a concern as it shows that the tabs are not tight enough to hold the Push to Trip button.



Bent Breaker Lock-Out Tabs



Bent Breaker Lock-Out Tabs

The following photos show the Push to Trip button in its normal position.



Push to Trip button



Push to Trip button

In either of these two positions above the Push to Trip lever would not make contact with the rear of the trip pan.


FPSC EXH No. 5
03/18/2024
ADMITTED

C3-520

WESTINGHOUSE PROPRIETARY CLASS 2

Failure Analysis Report

Purchase Order (PO): 02423936
Westinghouse Sales Order: 160387



Operating Mechanism Inspection Hole

If the Push to Trip button is held in like shown below, or if the breaker lock-out tabs on the front of the operating mechanism are bent sufficiently to hold this button in the Push to Trip lever would make contact with the rear of the trip pan. This scenario could cause the breaker to be trip free and it would not close, or if the trip pan was only partially held down the breaker may have closed, but the operating mechanism trip faces may not have been completely seated and a shock in the area of the breaker cell could cause the breaker to open. Either of these cases could cause the breaker to open unexpectedly.




Operating Mechanism Inspection Hole

C3-418

FPSC EXH No. 5
03/18/2024
ADMITTED


Failure Analysis Report

Purchase Order (PO): 02423936
Westinghouse Sales Order: 160387



Operating Mechanism Inspection Hole

The operating mechanism was disassembled and visually inspected. No issues were found.



Disassembled Operating Mechanism This photo shows the trip pan and the

Push to Trip linkage.


FPSC EXH No. 5
03/18/2024

ADMITTED

C3-522


Failure Analysis Report

Purchase Order (PO): 02423936
Westinghouse Sales Order: 160387




The pole bases were removed one at a time and were not disassembled at this time.


Phase 'A' Removed


Phase 'A' Removed


Phase 'B' Removed


Phase 'B' Removed

C3-420

FPSC EXH No. 5
03/18/2024

ADMITTED

C3-523

WESTINGHOUSE PROPRIETARY CLASS 2

Failure Analysis Report

Purchase Order (PO): 02423936
Westinghouse Sales Order: 160387



Phase 'C' Removed




Phase 'C' Removed

The closing solenoid was removed, and the closing solenoid relay release window assembly was removed and disassembled.



Closing Solenoid Assembly



Closing Solenoid Relay Release Window Disassembled No areas of concern were found with these items.

The wiring harness was removed from the breaker frame and was inspected.

FPSC EXH No. 5
03/18/2024
ADMITTED

C3-524

WESTINGHOUSE PROPRIETARY CLASS 2

Failure Analysis Report

Purchase Order (PO): 02423936
Westinghouse Sales Order: 160387



Breaker Wiring Harness

No areas of concern were found with the wiring harness or any of the terminations. 23-

Mar-21

A conference call was held on Tuesday, 23-Mar-21 to discuss the direction the testing was going in. A request was made to reassemble the cell switches and install them into a test cell and then use the breaker frame to verify the operation of the switches.

The left-side switch and right-side switch were properly assembled with all of the stationary fingers securely in place. The switch contacts were cleaned and properly lubricated during the assembly and each switch was mounted back onto the base plate and the plunger was attached to complete the assembly. Both the front and rear covers remained off of the switches so that the contacts could be monitored. Photos of the switches are provided:



Left-Side and Right-Side Switches

C3-422

FPSC EXH No. 5
03/18/2024
ADMITTED

C3-525


WESTINGHOUSE PROPRIETARY CLASS 2

Failure Analysis Report

Purchase Order (PO): 02423936
Westinghouse Sales Order: 160387



Left-Side Switch



Right Side Switch



Right-Side Switch Rear

Left Side Switch Rear



Right-Side Switch Rear



Left Side Switch Rear

C3-423

FPSC EXH No. 5
03/18/2024
ADMITTED

Failure Analysis Report

Purchase Order (PO): 02423936
Westinghouse Sales Order: 160387



Left-Side Switch and Right-Side Switch Installed in Test Cell




Left-Side Switch and Right-Side Switch Installed in Test Cell

FPSC EXH No. 5
03/18/2024
ADMITTED


C3-527

Failure Analysis Report

Purchase Order (PO): 02423936
Westinghouse Sales Order: 160387



Rear of Test Cell and Cell Switches



Cell Switch Monitoring Set-up

The Right-Side Switch is monitoring a Normally Open contact on switch terminals 3 and 4. The Left-Side Switch is monitoring a Normally Closed contact on switch terminals 5 and 6.

C3-425

FPSC EXH No. 5
03/18/2024
ADMITTED

C3-528


WESTINGHOUSE PROPRIETARY CLASS 2

Failure Analysis Report

Purchase Order (PO): 02423936
Westinghouse Sales Order: 160387



Right-Side Switch Monitoring (NO)



Left-Side Switch Monitoring (NC)



Breaker Frame on Test Cell Rails



Cell Switches shown through Breaker Rear Panel


C3-426

FPSC EXH No. 5
03/18/2024
ADMITTED



Failure Analysis Report

Purchase Order (PO): 02423936
Westinghouse Sales Order: 160387



The next series of photos are showing the breaker frame location as defined by the cell positioning stop bracket with Disconnected, Test and Connected positioning slots and then the distance between the cell switch plungers and the rear of the breaker panel.




Breaker Frame Located before the Cell Positioning Stop Bracket

Breaker Frame Located in the Disconnect Position Stop Bracket

Breaker Frame Located in the Test Position Stop Bracket

FPSC EXH No. 5
03/18/2024


ADMITTED

C3-530

WESTINGHOUSE PROPRIETARY CLASS 2


Failure Analysis Report

Purchase Order (PO): 02423936
Westinghouse Sales Order: 160387



Right-Side Switch Monitoring (NO) --- Left-Side Switch Monitoring (NC)





Breaker Frame Located in the Connect Position Stop Bracket



Switch Monitoring Shows a Change of State

FPSC EXH No. 5
03/18/2024
ADMITTED

C3-531

WESTINGHOUSE PROPRIETARY CLASS 2

Failure Analysis Report

Purchase Order (PO): 02423936
Westinghouse Sales Order: 160387

Both cell switches changed state as required between the Test and Connect breaker positions. 24-

Mar-21

The breaker frame was removed from the test cell and the cell switches were also removed. The cell switch return springs were removed for testing. The springs were given to QA for force testing. The reading recorded were acceptable.

Pole bases were disassembled and nothing of concern were found.

The closing solenoid assembly was disassembled and nothing of concern were found. With

the breaker disassembled the refurbishment of the breaker was initiated.

C3-429

FPSC EXH No. 5
03/18/2024
ADMITTED

C3-532

WESTINGHOUSE PROPRIETARY CLASS 2

Failure Analysis Report

Purchase Order (PO): 02423936
Westinghouse Sales Order: 160387

Conclusions:

The breaker was received in very good condition and properly lubricated. This breaker as received was acceptable for use. The possible cause of failure could have been the bent breaker lock-out tabs on the front of the operating mechanism, they were found to be slightly bent, however the breaker operated without incident during all mechanical and electrical testing.

The cell switches appeared to be original supplied equipment. They were not properly maintained, and the hardened lubrication could cause the stationary contacts to become dislodged, as documented above. In addition, to contributing to the dislodging the stationary contacts, excess or dry grease can cause improper indications from the switch contacts. This could be considered a possible cause of failure.

C3-430

FPSC EXH No. 5
03/18/2024

ADMITTED

C3-533

Recommendations:

It is recommended that the breaker be handled outside the switchgear cubicle with additional care. The breaker lock-out tabs on the front of the operating mechanism can cause the breaker not to function properly. When a breaker is shipped from Westinghouse the breaker lock-out tabs will include an operating mechanism lock-out bar as shown below.



Refurbished DB-50 Breaker with Operating Mechanism Lock-Out Bar

C3-431

FPSC EXH No. 5
03/18/2024
ADMITTED

Failure Analysis Report

Purchase Order (PO): 02423936
Westinghouse Sales Order: 160387

Please remove the Lock-Out Bar before testing and use of the breaker. It is also recommended that all DB breakers receive the attention during maintenance that this breaker has received.

The cell switches have a few areas of concern and recommendations will be provided for each concern.

If these were the original cell switches that were provided with the switchgear, it is recommended that they be replaced with safety related switch assemblies provided by Westinghouse Electric Company.

P/N: 302C517G01 Y, please include the proper switch configuration with your orders.

The Maintenance Program Manual for Westinghouse Safety Related Type DB Circuit Breakers and Associated Switchgear, Revision 1, July 2011 defines that the DB cell switch is a Category B item and the procedure provided should not exceed 5 Years. These requirements are included in Section 7.3, Item 6. The two cell switches provided for this investigation appeared to be beyond the 5-year requirement based on the hardening of the graphite grease on the switch contacts.

In addition, the spring and plunger of the cell switch may be lubricated per the recommendations in the MPM manual, Chapter 9. It is acceptable to apply 53701GW lubricant to the spring during maintenance intervals. Furthermore, the 53701GW lubricant can be applied to the cell switch plunger's penetration point through the mounting plate. The cell switches included in this investigation did not have any lubrication applied to the spring and the plungers were lubricated with a foreign type grease.

It is recommended that all original cell switches be replaced and after the cell switches are replaced that they be maintained to the requirements provided in the Maintenance Program Manual for Westinghouse Safety Related Type DB Circuit Breakers and Associated Switchgear, Revision 1, July 2011.



25-Mar-21
Patrick J. Folmar
DB Product Engineer

FPSC EXH No. 5
03/18/2024
ADMITTED

C3-535

WESTINGHOUSE PROPRIETARY CLASS 2

Failure Analysis Report

Westinghouse Electric Company LLC Nuclear
Parts Operations
Electro-Mechanical Parts Engineering
folmarpj@westinghouse.com
(724) 722-5969 – Phone

Purchase Order (PO): 02423936
Westinghouse Sales Order: 160387

C3-433

FPSC EXH No. 5
03/18/2024

ADMITTED

FILED 10/4/2022
DOCUMENT NO. 08636-2022
FPSC - COMMISSION CLERK

C3-536

BEFORE THE FLORIDA PUBLIC SERVICE COMMISSION

In re: Fuel and purchased power cost recovery clause with generating performance incentive factor.	DOCKET NO.: 20220001-EI FILED: October 4, 2022

NOTICE OF WITHDRAWAL OF PORTIONS OF DIRECT TESTIMONY OF RICHARD A. POLICH

The Citizens of Florida through the Office of Public Counsel ("OPC") serves notice of withdrawing the portions of the Direct Testimony of Richard A. Polich, filed on September 14, 2022, as shown below. The reason for the withdrawal is that the specific portion of testimony identified contains an error. The subject matter of this withdrawn portion of testimony was based on incorrect reliance on two discovery responses in the current 2022 fuel docket that indicated FPL's internal documents related to the August 2020 shutdowns at Turkey Point Unit 3 were subject to FPL's objections on grounds of relevance, thus not produced. During last year's fuel docket, some internal documents responsive to the subject outages were produced in Response to Citizens First Request for Production of Documents, Request No. 6 in Docket No. 20210001. Accordingly, the following portions of Mr. Polich's Testimony are withdrawn.

- Page 21, Line 18, beginning with the word "from" through line 19 up to and including the word "and" ;
- Page 24, Lines 5 -11;
- Page 27, Line 3, beginning with the word "Because" through all of Line 6;
- Page 27, Line 17, beginning with the word "Because" through all of Line 21; and
- Page 28, Line 15, beginning with the word "Because" through all of Line 18.

C3-434

FPSC EXH No. 5
03/18/2024
ADMITTED

Attached are the four pages from Mr. Polich's testimony referenced above showing the withdrawn portions in green highlighting for ease of reference.

Respectfully submitted this 4th day of October 2022.

Richard Gentry
Public Counsel

/s/ Charles J. Rehwinkel
Charles J. Rehwinkel
Deputy Public Counsel
rehwinkel.charles@leg.state.fl.us

Office of Public Counsel
c/o The Florida Legislature
111 West Madison Street
Room 812
Tallahassee, FL 32399-1400

Attorneys for the Citizens
of the State of Florida

FPSC EXH No. 5
03/18/2024

ADMITTED

C3-538

CERTIFICATE OF SERVICE
DOCKET NO. 20220001-EI

I HEREBY CERTIFY that a true and correct copy of the foregoing has been furnished by electronic mail on this 4th day of October 2022, to the following:

J. Wahlen/M. Means/V. Ponder
Ausley Law Firm
P.O. Box 391
Tallahassee FL 32302
jwahlen@ausley.com
mmeans@ausley.com
vponder@ausley.com

Dianne M. Triplett
Duke Energy
299 First Avenue North
St. Petersburg FL 33701
Dianne.triplett@duke-energy.com

Suzanne Brownless/Ryan Sandy
Florida Public Service Commission
Office of the General Counsel
2540 Shumard Oak Boulevard
Tallahassee, Florida 32399-0850
sbrownle@psc.state.fl.us
rsandy@psc.state.fl.us

Matthew R. Bernier/Robert L. Pickels/Stephanie A. Cuello
Duke Energy
106 E. College Avenue, Suite 800
Tallahassee FL 32301
FLRegulatoryLegal@duke-energy.com
matthew.bernier@duke-energy.com
robert.pickels@duke-energy.com
stephanie.cuello@duke-energy.com

Jon C. Moyle, Jr.
Florida Industrial Power Users Group
c/o Moyle Law Firm
118 North Gadsden Street
Tallahassee FL 32301
jmoyle@moylelaw.com
mqualls@moylelaw.com

Maria Jose Moncada/David Lee
Florida Power & Light Company
700 Universe Boulevard
Juno Beach FL 33408-0420
david.lee@fpl.com
maria.moncada@fpl.com

Kenneth A. Hoffman
Florida Power & Light Company
134 W. Jefferson Street
Tallahassee FL 32301-1859
ken.hoffman@fpl.com

Mr. Mike Cassel
Florida Public Utilities Company
208 Wildlight Ave.
Yulee FL 32097
mcassel@fpuc.com

C3-436

FPSC EXH No. 5
03/18/2024
ADMITTED

C3-539

Michelle D. Napier
Florida Public Utilities Company
1635 Meathe Drive
West Palm Beach FL 33411
mnapier@fpuc.com

Beth Keating
Gunster Law Firm
215 South Monroe St., Suite 601
Tallahassee FL 32301
bkeating@gunster.com

Corey Allain
Nucor Steel Florida, Inc.
22 Nucor Drive
Frostproof FL 33843
corey.allain@nucor.com

James W. Brew/Laura Wynn Baker
PCS Phosphate - White Springs
c/o Stone Law Firm
1025 Thomas Jefferson St., NW, 8th Floor, W. Tower
Washington DC 20007
jbrew@smxblaw.com
lwb@smxblaw.com

Ms. Paula K. Brown
Tampa Electric Company
Regulatory Affairs
P. O. Box 111
Tampa FL 33601-0111
regdept@tecoenergy.com

Peter J. Mattheis/Michael K. Lavanga/Joseph R. Briscar
Stone Law Firm
1025 Thomas Jefferson St., NW, Ste. 800 W.
Washington DC 20007
jrb@smxblaw.com
pjm@smxblaw.com
mkl@smxblaw.com

Robert Scheffel Wright/John T. LaVia III
Florida Retail Federation
1300 Thomaswood Drive
Tallahassee FL 32308
schef@gbwlegal.com
jlavia@gbwlegal.com

/s/ Charles J. Rehwinkel
Charles J. Rehwinkel
Deputy Public Counsel
Florida Bar No. 0527599

C3-437

FPSC EXH No. 5
03/18/2024
ADMITTED

incomplete and inaccurate information to FPL that was subsequently submitted by FPL to the NRC.

The NRC determined this was a Severity Level II violation of 10 C.F.R. §.50.7 and imposed the $232,000 civil penalty on FPL. As a result of this instance, FPL agreed to perform the following corrective actions:

1. Establish an Employee Concerns Program (ECP) investigation and Safety Conscious Work Environment ("SCWE") surveys in St. Lucie and Turkey Point radiation protection departments, and training of senior nuclear managers.
2. Conduct a nuclear fleet-wide communication that reinforced the SCWE policy.
3. Conduct personnel training, ECP third-party audits, and create a personnel action review board to review certain employment actions involving contractor personnel brought to FPL's attention.

Q. ARE YOU AWARE OF THE TURKEY POINT UNIT 3 OUTAGES THAT OCCURRED IN AUGUST 2020 FOR WHICH FPL IS NOT SEEKING COST RECOVERY?

A. Yes. I am aware of this situation, but FPL has blocked me from reviewing their records containing details of these events and from understanding the basis for their decision to exclude the replacement power costs from recovery in the Fuel Clause docket.[4] I have included in my testimony information related to these events from the publicly available

[4] See, FPL's April 2, 2022 *Petition for Approval of Fuel Cost Recovery and Capacity Cost Recovery Net Final True-Ups for the Period Ending December 2021 and 2021 Asset Optimization Incentive Mechanism Results*, Docket No. 2022001-EI.

FPSC EXH No. 5
03/18/2024
ADMITTED

and Commission are entitled to know the circumstances so that the parties can understand whether FPL is properly and prudently pursuing recovery from third parties in all instances where vendors or an insurance company may be obligated to compensate FPL; and if not, why not?

Q. WHAT DO YOU RECOMMEND WITH REGARD TO THESE EVENTS?

A. Given that I have not seen the information, I reserve the right to provide supplemental testimony that addresses any relevant issues related to these events. Furthermore, to the extent that discovery of information related to these events has a bearing on any aspect of my testimony – including any contrasts with contested claims of prudent replacement power cost – the Commission should allow the record to be reopened in a future proceeding, including but not limited to any spin-off investigation docket.

Q. PLEASE DESCRIBE THE INCIDENTS THAT LED TO THE NRC ISSUING THE APRIL 6, 2021 NOTICE OF VIOLATION AND IMPOSITION OF A $150,000 CIVIL PENALTY (EXHIBIT NO. ___(RAP-5)).

A. On April 6, 2021 the NRC issued a Notice of Violation and Civil Penalty related to three instances where FPL employees at Turkey Point falsified information, and/or provided inaccurate or incomplete information in maintenance records. The first incident occurred on July 10, 2019 when FPL mechanics falsified maintenance records on a work order, falsely stating maintenance activities associated with a *safety-related* check valve had been completed. They also recorded inaccurate information on the status of tools that were required (but not used) for conducting the maintenance work (that was not actually performed). The FPL employees also recorded inaccurate measurements using falsified values, copied from a prior actual performance of the work.

FPSC EXH No. 5
03/18/2024
ADMITTED

C3-542

low-pressure at the suction of the steam generator feedwater pump (SGFP). Investigation by FPL found a design modification in 2012 had not included this scenario in the turbine control system design analysis. Because I have been blocked from accessing and independently reviewing the FPL internal documents related to this event, I am unable to determine the nature of any human element (FPL employee or contractor) related to the prudence of this event as it relates to or affects the recovery of fuel costs.

Q. PLEASE DESCRIBE THE SECOND OF THE FOUR UNPLANNED REACTOR SCRAM EVENTS THAT OCCURRED BETWEEN AUGUST 2020 AND MARCH 2021.

A. The second event occurred on August 19, 2020 (two days after the first event), and was an automatic trip by the plant plant's reactor protection system during startup, caused by high neutron flux condition in the reactor. According to the NRC, *FPL's own root cause evaluation determined this was operator error committed by an FPL employee.* The FPL unit supervisor and FPL reactor plant operators were determined to have had knowledge gaps in conducting reactor startup operations. As a result of the discovery of knowledge gaps among its employees, FPL had to make procedural and training material changes for plant operators and supervisors. Because I have been blocked from accessing and independently reviewing the FPL internal documents related to this event, I am unable to fully formulate an opinion about this event as it relates to the prudence of FPL's culture, workforce staffing or other aspects of prudence as it relates to or affects the recovery of fuel costs.

C3-440

FPSC EXH No. 5
03/18/2024
ADMITTED

C3-543

Q. PLEASE DESCRIBE THE THIRD OF THE FOUR UNPLANNED REACTOR SCRAM EVENTS THAT OCCURRED BETWEEN AUGUST 2020 AND MARCH 2021.

A. The third event that occurred on August 20, 2020, the day after the second event occurred, was caused by improper valve alignment of the pump suction flow control valve and failure to place the recirculation to condenser control valves in automatic. According to the NRC, *FPL's own root cause evaluation determined this was operator error committed by an FPL employee.* FPL operators had not properly moved the master controller for the Turkey Point Unit 3 SGFP recirculation valve(s) to the appropriate position for the plant conditions. FPL operators attempted to adjust these recirculation valves after discovering the error, causing low suction pressure on the SGFP. The RCA investigation determined that the FPL operators had failed to properly review valve alignment and status of all components following an unplanned reactor scram. As a result of the discovery of the FPL employee errors, FPL had to implement procedural and training changes to prevent this event from recurring. Because I have been blocked from accessing and independently reviewing the FPL internal documents related to this event, I am unable to fully formulate and opinion about this event as it relates to the prudence of FPL's culture, workforce staffing or other aspects of prudence as it relates to or affects the recovery of fuel costs.

Q. PLEASE DESCRIBE THE FOURTH OF THE FOUR UNPLANNED REACTOR SCRAM EVENTS THAT OCCURRED BETWEEN AUGUST 2020 AND MARCH 2021.

A. The fourth event occurred on March 1, 2021, following testing of the Reactor Protection System. The restoration included reactor operators closing the reactor trip breaker and

C3-441

C3-544

FPSC EXH No. 6
03/18/2024

ADMITTED

Review of
Nuclear Operations

Florida Power & Light Company

January 2024

BY AUTHORITY OF

The Florida Public Service Commission
Office of Auditing and Performance Analysis

C3-442

FPSC EXH No. 6
03/18/2024

ADMITTED

C3-545

C3-443

FPSC EXH No. 6
03/18/2024

ADMITTED

Review of

Nuclear Operations

Florida Power & Light Company

Carl Vinson
Public Utilities Supervisor
Project Manager

LaDonna Cain
Public Utility Analyst

January 2024

By Authority of
The State of Florida
Public Service Commission
Office of Auditing and Performance Analysis

PA 23-03-002

FPSC EXH No. 6
03/18/2024

ADMITTED

C3-547

C3-445

FPSC EXH No. 6
03/18/2024

ADMITTED

TABLE OF CONTENTS

CHAPTER **Page**

1.0 Executive Summary
1.1 Scope and Objectives 1
1.2 Methodology 1
1.3 Commission Audit Staff Analysis 2
1.4 Commission Audit Staff Observations 4

2.0 FPL Nuclear Operations Internal Controls
2.1 Company Nuclear Review Board 5
2.2 Management Review Committee 18
2.3 FPL and Nuclear Industry Performance Indicator Controls 18
2.4 Nuclear Safety Culture Controls 20

3.0 PTN and PSL Forced Outage Causes and Costs
3.1 Commission Audit Staff Analysis – Forced Outages 23

4.0 Company Comments 39

FPSC EXH No. 6
03/18/2024

ADMITTED

TABLE OF EXHIBITS

EXHIBIT **Page**

1. FPL Unplanned Outages/SCRAMS 24
2. Selected Unplanned Outages/Scrams 2017 – 23 25
3. Commission Audit Staff Analysis of Selected Outages 26

FPSC EXH No. 6
03/18/2024

ADMITTED

1.0 Executive Summary

The Office of Auditing and Performance Analysis initiated this operational audit at the request of the Florida Public Service Commission's (FPSC or Commission's) Division of Engineering to assist its analysis of issues in Docket Number 20230001-EI.

This audit report addresses nuclear operations at Port Saint Lucie Units 1&2 (PSL) and Turkey Point Units 3&4 (PTN) over the period 2017-2023.

1.1 Scope and Objectives

The primary objectives of this audit were to review, evaluate, and document FPL's internal controls and procedures governing the following:

- FPL's execution and management of PSL and PTN operational activities including detecting and correcting observed deficiencies.
- FPL's outage management practices for both planned and forced outages, including cause determination through Root Cause Evaluations, and execution of the resulting corrective actions deemed necessary.
- FPL's formal internal monitoring and reporting of PSL and PTN operational deficiencies to Senior and Executive Management, and operations management's response to their directives.
- FPL's monitoring and use of operational performance indicators, internal and external audit reports, consultant reports, and QA/QC reviews.
- NRC's programmatic monitoring and inspection of FPL's nuclear performance, its compliance with 10 CFR Part 50, and management's response to NRC input.

1.2 Methodology

Commission audit staff gathered and analyzed hundreds of documents regarding the performance of FPL's nuclear plant operational performance over the period 2017-2023. Commission audit staff conducted multiple extended teleconference interviews with FPL Senior and Executive Managers responsible for the company's nuclear operations.

Commission audit staff elected to use a seven-year study period to provide a broad perspective for analysis and recognition of trends and patterns of behavior in FPL's management and operation of PSL and PTN. Commission audit staff placed emphasis on several key internal control processes including: NextEra's Company Nuclear Review Board (CNRB), FPL's Management

FPSC EXH No. 6
03/18/2024
ADMITTED

Review Committee, Nuclear Safety Culture Monitoring Panel, and Nuclear Assurance organization.

Commission audit staff also reviewed 10 CFR Part 50, applicable Florida Statutes, and selected portions of records from Docket Nos. 20210001-EI, 20220001-EI, and 20230001-EI.

As authorized by Sections 350.117(2) and (3), Florida Statutes, management audits are conducted by staff to assess utility performance and the adequacy of operations and controls:

> (2) The commission may perform management and operation audits of any regulated company. The commission may consider the results of such audits in establishing rates; however, the company shall not be denied due process as a result of the use of any such management or operation audit.
>
> (3) As used in this section, "management and operation audit" means an appraisal, by a public accountant or other professional person, of management performance, including a testing of adherence to governing policy and profit capability; adequacy of operating controls and operating procedures; and relations with employees, customers, the trade, and the public generally.

Commission audit staff's standard of review for internal controls is primarily the Institute of Internal Auditors' *Standards for the Professional Practice of Internal Auditing* and the *Internal Control - Integrated Framework* developed by the Committee of Sponsoring Organizations (COSO) of the Treadway Commission. Internal controls assessments focus on the COSO framework's five key elements of internal control: control environment, risk assessment, control activities, information and communication, and monitoring. Commission audit staff seeks to comply with the Institute of Internal Auditors Performance Standards 2000 through 2500.

1.3 Commission Audit Staff Analysis

During 2019, FPL experienced 12 forced outages; seven at PTN, and five at PSL. In 2020, PTN forced outages increased to 16, while PSL outages dropped to four. In 2021, PSL forced outages rose to 12 and PTN forced outages dropped to 10. During 2022, forced outages at both PTN and PSL dropped to zero and three, respectively.

As the trend of increased forced outages grew, so did FPL management's recognition of operational performance deficiencies and problems at all four units. From at least 2018, Senior and Executive Management increasingly recognized and sought to address deficiencies in management engagement, FPL and vendor work quality, equipment reliability, procedural compliance, and other significant shortcomings at PTN and PSL.

Between 2017 and 2023, FPL's formal Root Cause Evaluations of forced outages cited issues such as vendor performance errors, deficient FPL human performance, repeat outage causes, latent design issues, and failures to comply with FPL procedures.

FPSC EXH No. 6
03/18/2024
ADMITTED

During 2019, a handful of incidents at PSL and PTN led the company to conduct a Common Cause Evaluation. This report described "integrity issues" involving eight FPL employees and managers. These incidents led to substantial fines imposed by NRC for violation of federal regulations. In September 2019, the NRC issued a $232,000 Civil Penalty for FPL's 2017 violation of 10 CFR 50.7(a) for a Regional Vice-President's removal of a contractor employee who raised safety concerns. In 2019, FPL discovered that several craft level employees and three supervisory level employees had falsified maintenance records and engaged in a cover-up of the violation. The NRC eventually imposed a $150,000 Civil Penalty for these violations.

FPL initiated ongoing training of managers and monitoring to achieve and maintain a respectful and safety-conscious work environment. Improvement in these areas was achieved and no similar issues regarding FPL's safety culture appear to have arisen since 2019.

During 2020, in response to the observed operational deficiencies and outages, FPL established a task force to determine the extent of the wide-spread operational performance decline. This effort initially focused on PTN, was later broadened to include PSL. In late 2020 FPL developed a performance improvement correction action plan, which led to ongoing improvement initiatives into 2021 and 2022.

Over the period 2020 to date, FPL's objectives included re-establishing managers' commitment to high performance standards, effective operational oversight, improving plant operational proficiency, and reversing a decline in maintenance and equipment reliability performance. Other actions included replacement of key managers, obtaining consulting assistance from the Institute of Nuclear Power Operations, and initiating additional monitoring of Turkey Point operations by NextEra's Corporate Governance and Oversight organization.

These improvement initiatives began to yield beneficial results during 2021. Forced outage numbers decreased in 2022 and 2023, and performance indicator metrics scores improved.

FPSC EXH No. 6
03/18/2024
ADMITTED

C3-553

1.4 Commission Audit Staff Observations

Based upon the extensive information gathered and analyzed, commission audit staff made the following observations regarding FPL's operational performance at St. Lucie Units 1&2 and Turkey Point Units 3&4 over the period 2017-2023.

Observation 1
As early as 2018, significant operational performance concerns were noted by FPL Executive Management, as evidenced by minutes of meetings of both the Company Nuclear Review Board and the Management Review Committee.

Observation 2
As early as 2018, inadequate operational performance at PTN and PSL was observable from the results of the performance metrics monitored and used by FPL to evaluate PTN and PSL.

Observation 3
FPL's Root Cause Evaluations for six of its forced outages over the period 2020 through 2022 raise questions regarding whether actions FPL either took, or failed to take, may have caused the company to incur replacement power costs.

Observation 4
During 2020, FPL launched a performance improvement program, with a goal of attaining excellent performance at PTN and PSL.

Observation 5
FPL's performance improvement efforts appropriately made changes among FPL nuclear program management personnel at various levels and targeted the Maintenance, Operations, and Engineering functions.

Observation 6
During 2021, the performance improvement efforts provided positive results in the operational effectiveness of PTN as reflected in the number and duration of outages.

Observation 7
During 2022, the performance improvement efforts provided positive results in the operational effectiveness of PSL as reflected in the number and duration of outages.

Observation 8
PTN and PSL presently perform in the first quartile of the U.S. nuclear industry-standard performance rating system.

Observation 9
FPL's internal controls maintain a healthy Nuclear Safety Culture that provides a safety-conscious and respectful work environment at PTN and PSL.

FPSC EXH No. 6
03/18/2024
ADMITTED

2.0 FPL Nuclear Operations Internal Controls

Commission audit staff believes the collective set of internal controls related to the management and operation of FPL's nuclear units is complete and adequate for their intended purposes. Focused attention to standards and performance quality over the past few years have refined and improved internal controls.

In this review, Commission audit staff focused its efforts on obtaining a clear understanding of the events, trends, and practices that drove FPL nuclear operational performance over the study period. To obtain a clear picture of key events of the past five years, Commission audit staff focused on what it determined to be the key internal control processes that both guided, and documented, FPL's nuclear operational performance:

- Company Nuclear Review Board
- Management Review Meetings
- Key Performance Indicators
- Nuclear Safety Culture Controls

These control processes provide self-evaluation of operations, problem identification and implementation of corrective action. They serve to keep all levels of management up to date on performance quality, emerging problems and risks, and corrective action. For the purposes of its analysis, Commission audit staff found that a clear understanding of the track record of PTN and PSL operations over the study period could be gained by examining the documented record of the functioning of these key controls.

This documented record exists mainly in the form of internal and external audit reports, meeting minutes, outage Root Cause Evaluations, and performance indicator metrics results.

2.1 Company Nuclear Review Board

FPL's Company Nuclear Review Board (CNRB) is organized as an advisory group to the Executive Vice President/Chief Nuclear Officer. The board is composed of NextEra's corporate Vice Presidents, Site Vice Presidents, and key site leaders, as well as guest utility employee members and contract consultants.

The CNRB provides a review and evaluation mechanism for executive and senior management regarding plant operations and results. It meets twice a year to discuss the status of FPL/NextEra's nuclear fleet operations. Meetings usually take place over two days.

Extensive preparation precedes each CNRB meeting. Subcommittees representing the site departments (e.g. Maintenance, Engineering) hold meetings to discuss challenges and results relevant to their duties.

FPSC EXH No. 6
03/18/2024
ADMITTED

The CNRB Chairman prepares for meetings by interviewing various levels of plant management and the senior NRC resident inspector. As the following excerpts reflect, the CNRB Chairman presents his analysis of the various areas of operation, including discussion of identified notable "gaps" and their causes. The CNRB assigns corrective actions to address gaps and deficiencies. These are entered into a corrective action tracking system and resolution and follow-up are addressed in subsequent CNRB meetings.

Commission audit staff reviewed the CNRB minutes over the period 2017 to date. As expected, the minutes reflect a rigorous self-examination which appropriately reflects a prioritization of both safety and productivity. The participants exhibit a critical, questioning attitude, vigorously probing and challenging performance gaps and deficiencies. Each meeting addresses trends and events, recent outages, NRC inspection results, and performance indicator results.

Commission audit staff believes the CNRB was and is an effective and appropriate control for bringing observed deficiencies to the attention of all levels of management. The CNRB is vigorously used in keeping with its written charter. This process leads to identification of corrective actions, promotes ongoing monitoring of results and direction of corrective action needed.

Commission audit staff notes that the CNRB minutes often reflect dissatisfaction with the performance of managers and employees at PTN and PSL. Over a period of years, criticisms cite management being inadequately engaged, allowing erosion of high standards, failing to model appropriate leadership behavior, and failing to deliver acceptable operational results.

More specific to operations, CNRB members repeatedly refer to chronic equipment reliability issues, work proficiency gaps, and inadequate planned outage preparation. Commission audit staff notes that in multiple instances, CNRB members and participants directly blame forced outages or increased outage duration on FPL errors and performance deficiencies. Detailed discussion of specific outages is provided in Chapter 3 of this report.

The following quoted passages from the CNRB Minutes record the unvarnished and often harsh observations and conclusions of FPL's most senior managers responsible for obtaining maximum productivity from the company's most valuable generation assets. Commission audit staff believes these words were not chosen casually and the comments were not made lightly.

Commission audit staff believes that a thorough review of these minutes provides a valuable perspective on how FPL Executive Management viewed the performance of PSL and PTN over this seven-year period. In the following pages, extensive excerpts are reproduced to underscore the continuing themes and tone of dissatisfaction present in feedback recorded. Italics have been used to denote direct quotes from FPL's minutes.

FPSC EXH No. 6
03/18/2024
ADMITTED

2.1.2 CNRB Minutes - 2018 Issues

Chairman's Report, CNRB Meeting #677, 7/26/18

GAP Problem Statement: The station [PSL] *is not meeting fleet expectations for execution of the attributes of active leadership resulting in risk not being recognized, acceptance of poor equipment performance and failures to call out substandard leadership behaviors.*

Commission audit staff notes a CNRB directive was issued to "identify and close gaps in work quality" [and take] "action to include identifying repeats, assignment extensions, operating experience, and extent of condition."

Chairman's Report, CNRB Meeting #680, 1/23/19

Two issues were identified…

1. *Station leadership* [PTN] *is not engaged with the workforce or processes at the right level to ensure consistent and sustainable results.*
   As a result, performance in engineering is declining (indicated by poor equipment reliability including multiple repeat equipment issues) and there have been multiple Maintenance human errors and near misses. Additionally, the station is behind in their outage preparations…
2. *The pace of resolving important regulatory issues has not been improved.*

Commission audit staff notes the referenced "regulatory issues" relate to NRC resident inspectors' concerns regarding a non-cited violation involving improper close-outs of incomplete work orders.

The issue that leadership was "not engaged with the workforce or processes at the right level" was repeatedly cited by the CNRB. Managers and supervisors were urged to become more accessible to employees for coaching and to improve communications skills.

Operations Subcommittee Summary: CNRB Meeting #680, 1/22/19

GAP Problem Statement: The [PTN] *Operations department standards in the control room have degraded to the point where* [we] *have serious concern about performance if intervention is not taken…based on past successes, the site is overconfident and this has led to a casual approach and an erosion of standards. …Recommendations: Improve awareness of conditional risk, degraded equipment, or off normal evolutions that may require a formal strategy to ensure over confidence and complacency are eliminated.*

Commission audit staff notes that during this January 2019 timeframe, these comments would apply to conditions that existed during some portion of 2018. The issue of managers accepting lower standards of work and diligence is cited in minutes over period 2019-2022.

FPSC EXH No. 6
03/18/2024
ADMITTED

2.1.2 CNRB Minutes – 2019 Issues

Chairman's Report, CNRB Meeting #682 3/25/19

Two issues were identified…

1. *The pace of addressing fleet expectations for sustaining performance and gaining margin is slow and not well defined…with very specific actions that are driven by the* [PSL] *site director. This is resulting in declining performance in several important areas…*
2. *Station regulatory performance* [with NRC] *is declining and does not have the attention of the senior leadership team and therefore lacks very detailed actions to quickly correct the declining performance and improve margin.*
   a) The [PSL] *station will receive a repeat non-cited violation* [from NRC]*... in the next quarterly exit on control of transient combustibles. The station received a very similar NCV during the third quarter 2018 exit and corrective actions for this issue are ineffective.*
   b) The NRC has identified corrosion control as an issue based on the recent corroded support for a [Component Cooling Water] *flow instrument which placed the unit in shutdown limiting condition for operations action statement. The corroded support was first identified in 2016 and was not classified as a yellow work order and no action was taken until the support was inspected in March of this year.* [2019]
   c) There are recent examples where operations failed to notify the resident [NRC] *inspectors of plant events in a timely manner…The* [NRC] *senior resident identified this as a declining trend.*

Turkey Point Summary, CNRB Meeting #690 1/22/20

The following Gaps were noted by the CNRB:

1. *There is an adverse trend in Equipment Reliability at PTN. Troubleshooting evolutions, including those involving enactment of the Failure Investigation Process lack rigor and formality to ensure equipment issues are resolved in a timely manner….*

   Driver: Lack of leadership engagement through the entire complex trouble shooting process from initiation to closure.

Commission audit staff notes the continuing references to leadership deficiencies including station senior leadership. The noted failure to address a specific adverse condition refers to NRC non-cited violations in 2018 and 2019 for close-out of incomplete work orders. Commission audit staff notes the control of the referenced transient combustibles issue, raised by the NRC in 2018 and 2019, was not resolved by FPL until December 2022.

2.1.3 CNRB Minutes – 2020 Issues

St. Lucie Summary, CNRB Meeting #690 1/22/20

The Safety Culture Evaluations of four recent Root Cause Evaluations (RCE) were reviewed and found to be cursory with few conclusions or lessons learned.

FPSC EXH No. 6
03/18/2024
ADMITTED

This represents a missed opportunity to use the RCEs to drive behavior changes and improve safety culture….

The following Gaps were noted by the CNRB:

1. *The common cause analysis of reactor trips does not address personnel or leadership behaviors that have contributed to the events….*
   In addition, individually, the root cause evaluations of some of the most recent trips [outages] *lack analysis of personnel and leadership behaviors that have contributed to the events….*
3. [PSL] *has the worst Operational Focus in the* [U.S. nuclear] *industry and Unit 2 is in the bottom quartile. These results are driven by operational transients driven by equipment failures. One of the two drivers the station has identified to resolve the numerous equipment failures is: the risk assessment process system did not ensure critical information is translated into work plans, procedures and testing plans for implementation at the working level.*

Due to the important role Root Cause Evaluations of forced outages play in correcting deficiencies, Commission audit staff believes these criticisms of inadequate post-outage analyses and failure to identify and apply lessons learned are noteworthy.

Commission audit staff also notes the mention of recurring poor equipment reliability at both PTN and PSL. This issue contributed to making 2020 a low point in PTN's operational history, prompting recognition of needed changes and the development of a strategic improvement plan.

Turkey Point Chairman's Report, CNRB Meeting #690 1/22/20

- *Based on interviews, observations and a review of program documentation, the CNRB did not identify issues with the functioning of the Safety Culture and Safety Conscious Work Environment programs. However, subsequent to the CNRB, the Chairman reviewed the Common Cause Evaluation (CCE) for the "Trend in Integrity Issues" in 2019 which addressed behaviors that were inconsistent with the station's safety culture. Among the proposed corrective actions is increased engagement with and by the bargaining unit to help create a better understanding of fleet standards for the completeness and accuracy of information. However, the CNRB Chairman concluded that sustainable improvement in the culture of integrity will also require an increase in the frequency and quality of first-line (non-bargaining unit) supervision in the field, including timely coaching, counseling, and accountability actions.*

Commission audit staff notes that this early 2020 CNRB meeting addressed a 2019 Common Cause Evaluation document, subtitled "Trend in Integrity Issues." This report evaluated three 2019 instances of falsification of work-related documentation at St. Lucie. Six bargaining unit personnel were terminated, as was one supervisor level employee. A second supervisor opted to retire voluntarily due to his involvement.

FPSC EXH No. 6
03/18/2024
ADMITTED

Also during 2019, a significant ethics event at Turkey Point resulted in an NRC Notice of Violation of 10-CFR 50.7(a) which protects employees reporting safety concerns from adverse action such as termination. This violation indicated an inadequate Nuclear Safety Culture at the plant. Both investigations caused the NRC to impose substantial civil penalties against FPL.

The lasting impact of these actions included ongoing self-evaluation of FPL's Nuclear Safety Culture practices and recognition of significant failures by managers, including a Regional Vice-President who was responsible for the violation of 1-CFR 50.7(a).

> ***Turkey Point Executive Summary, CNRB Meeting #693 12/02-04/20***
> *The following Gaps were noted by the CNRB: …*
> 4. *Gap - PTN improvement plan lacks a vision, strategy, and sustainable actions. Multiple department plans are not yet integrated into a concise, prioritized, risk-based plan with metrics/success measures …*
>
> *Formal CNRB Action: Site Leaders should enhance the PTN improvement plan using the guidance contained in INPO 12-011, "Continuing the Journey to Excellence – An Implementation Framework to Significantly Improve Nuclear Plant Performance, Recovery Guidance for Corporate and Station Leaders."*

Commission audit staff notes INPO 12-011 is a management guide available only to member utilities. It is a resource widely used by nuclear plant managers seeking to diagnose or correct performance problems. INPO 12-011 focuses on the following leadership behaviors: active management engagement, accountability for detecting and correcting deficiencies, intrusive corporate governance/oversight, close monitoring of performance metrics, motivating initiative in supervisors in operating the plant, maintaining a questioning attitude, and emphasis on continuous learning.

As FPL developed and refined its recovery plan for PTN in late 2020, it relied heavily on these foundational elements for success promoted by INPO. Present executive management stated that extensive interaction with INPO personnel and peer nuclear industry managers provided valuable and productive guidance. Other INPO guide documents were consulted and applied in corrective action planning.

Commission audit staff believes that as of 2020 many of these key behaviors emphasized by INPO had been employed by FPL's nuclear division. However, FPL realized a renewed effort and re-emphasis of these basic principles was needed. A key decision was made to install a new Chief Nuclear Officer, resulting in a renewed focus.

> ***Turkey Point Executive Summary, CNRB Meeting #693, 12/04/20***
> - *The CNRB reviewed the draft Turkey Point improvement plan and reported a decline in operational, maintenance, and equipment reliability performance at the station since the last CNRB review.* [January 22, 2020] *The CNRB concluded that continued elevated intervention will be necessary to arrest the performance decline and sustain performance improvement….*

FPSC EXH No. 6
03/18/2024
ADMITTED

- *NRC Senior Resident Inspector (SRI) – SRI informed the CNRB that there have been a "step change" in improvement in the quality of communications with the* [new] *site leadership team. SRI also stated that station leaders were "not very self-critical and had grown complacent with their level of performance prior to the reactor trips the week of August 17* [2020]….

Commission audit staff notes that the NRC SRI's recognition of improved communication with new site leadership is positive in the light of prior issues the NRC had noted with PTN communication and responsiveness.

St. Lucie Actions Reviewed and Closed, CNRB Meeting #693 12/02-03/20

MS-AI-20-690-3…There was a recent HU [human performance] issue in electrical maintenance with lifted landed leads that revealed the HU plan did not validate the craft and leadership understand how to perform their HU tools. Interviews with several craft reflect very limited leadership field presence… to reinforce with HU tools.

FPL's Root Cause Evaluation of the outage noted complacency by the technicians due to past success landing leads had resulted in failure to use a protective insulating barrier in the work.

At the December 2020 meeting, the Closure Comments regarding an action item stated, "This action is closed based on a review of the additional actions taken…The additional actions taken are addressing the gaps in leadership presence and reinforcing behaviors…."

Despite these efforts related to corrective action MS-AI-20-690-3, on December 10, 2021 a two-day PSL1 outage occurred, once again involving lifted leads. FPL's RCE noted a maintenance supervisor chose to deviate from the work management process and also failed to validate readiness and adequately execute drawings review.

2.1.4 CNRB Minutes - 2021 Issues

Turkey Point Executive Summary, CNRB Meeting #695 3/23/21

- *CNRB's assessment of the Nuclear Assurance (NA) Function –* [PTN] *Station engagement with NA is lacking and therefore is not contributing to some issues or achieving accelerated improvement. Numerous directors/managers highlighted they did not partake in actions to engage NA because it was not a part of their mental model or because they felt experience was lacking to the point where they would not add value. There was little response when asked what efforts were taken by them to improve it.*

The referenced Nuclear Assurance function establishes, maintains, and interprets Quality Assurance practices and policies. It also conducts and oversees a program of internal audits and evaluations of nuclear unit operations. Commission audit staff notes the referenced lack of cooperation with, and confidence in, the Nuclear Assurance function by operations managers represents disregard for FPL policies and procedures.

FPSC EXH No. 6
03/18/2024

ADMITTED

Turkey Point Summary, CNRB Meeting #695 3/23/21

Licensing/Performance Improvement

- *The station currently has a Root Cause Evaluation in process as a result of the most recent reactor trip and is expecting a supplemental IP 95001 inspection letter from the NRC as a result of exceeding white criteria for Scrams per 7000* [operating] *hours…. In addition, Turkey Point has also incurred classifications of two OE* [Operational Experience] *preventable events resulting from 2 Trip/Transient events…. In addition, an OE preventable classification was assigned as a result of the 8/19/20 Reactor Trip…Most notable were knowledge gaps and an incorrect mental model for conducting a reactor startup….*

Commission audit staff notes the Scrams per 7000 Hours metric is used by the NRC to measure outage frequency. In this instance three outages in August 2020 decreased Turkey Point's rating for this metric. Significantly, both the August 17 and August 19 outages were classified as "OE preventable" by FPL.

St. Lucie Summary, CNRB Meeting #695 3/22/21

INPO 19-003, "Staying on Top"

- *The station has implemented a "Staying on Top" strategy to reinforce the five INPO 19-003 values. The station is focused mainly on identification of deviations from excellence standards and being self-aware and self-correcting. PSL Operations management has developed scoring and trending tools to assess each individual and the entire crew against the leadership team and effectiveness-essential outcomes. In addition, indexes have been developed to assess, score and trend observational criticality, shift manager leadership and overall crew engagement. Results are reviewed daily and observations of poor quality are rejected and coached.*

Commission audit staff notes that the INPO 19-003 document is a resource used by member utilities to instill a self-aware, self-correcting mindset that values continuous learning and leadership engagement. Use of INPO 19-003 was a central focus in FPL's ongoing improvement plan efforts in 2021.

Turkey Point Summary, CNRB Meeting #697 12/01/21

- *Online schedule execution has declined…for the last four months. Current performance is the lowest in the last two years and is fourth quartile.*
- *CNRB interviews indicated that Maintenance leaders lack sufficient understanding or regarding vulnerabilities created by vendor work. Examples included:*
  - *Outage delays due to gripper issues on the fuel handling mast despite Framatome having had challenges with the equipment [during] the previous outage.*
  - *Several rework items associated with Siemens turbine maintenance.*

FPSC EXH No. 6
03/18/2024
ADMITTED

C3-562

> *Several performance gaps were evident during the Fall 2021* [refueling] *outage which ultimately extended the outage 16 days beyond the duration goal. Many of the issues that extended the outage were due to poor vendor performance.*
>
> *Items that have historically challenged the station and which the station has means of addressing were not included in the schedule to ensure they were addressed prior to negatively impacting the outage….*
>
> *Action: Develop and implement core business monitoring within Maintenance to ensure: (i) plant repairs receive first priority; (ii) proper oversight of vendor performance is conducted; and (iii) critical maintenance station responsibilities such as predictable and timely work execution are maintained at acceptable levels…*

Commission audit staff notes the CNRB's reference to "performance gaps" ultimately causing a 16-day extension to a refueling outage relates to a PTN Unit 3 outage on November 7, 2021. Multiple references to performance gaps, bring the adequacy of FPL's vendor oversight efforts into question. The CNRB cites prior vendor failures and difficulties as possible missed signals and implies that demanding closer accountability from vendors would have been prudent. The CNRB specifically requires measures be taken to ensure that "proper oversight of vendor performance is conducted."

Turkey Point Executive Summary, CNRB Meeting #697 12/02/21

- *Safety Culture and Safety Conscious Work Environment (SCWE)*
  The CNRB assessed the health of the SCWE at Turkey Point. The CNRB's review of Employee Concerns Program [ECP] data revealed the continued steady use of the program since the last review. Noteworthy trends from the investigations indicated a degradation in employee trust due to management behaviors and [deficient] *quality and clarity of leader communications.*

  While there was no widespread evidence that employees fear harassment, intimidation, or discrimination from raising concerns, the CNRB gained insights from interviewees and review of the Nuclear Safety Culture Monitoring Panel documents which reinforce the opportunity for station leaders to enhance the rigor and professionalism of communications to strengthen trust and respect.

Commission audit staff notes that due to the NRC's self-described primary focus on the issue of safety, all U.S. nuclear units must monitor the health of their plant safety culture. This includes providing a work environment where plant workers feel comfortable in raising safety concerns to managers. To promote free reporting of safety concerns, FPL's Employee Concerns Program provides a mechanism for reporting concerns for further inquiry overseen by the Nuclear Assurance function. At this CNRB meeting, the Nuclear Safety Culture Monitoring Panel reported that based on employee surveys and analysis of ECP reports, workers are comfortable raising safety concerns.

C3-460

FPSC EXH No. 6
03/18/2024
ADMITTED

A related goal for managers is to foster a respectful work environment where managers' behaviors exhibit appropriate degree of respect in dealing with workers. This respectful tone also promotes the degree of comfort in reporting safety concerns.

This December 2021 CNRB discussion of Nuclear Safety Culture reflects ongoing attention to this issue, and need for improvement in providing a Respectful Work Environment. An improvement initiative was launched using a management approach called Intent Based Leadership. The concept of Intent Based Leadership centers on ownership. It encourages *giving* more control and responsibility for work to those closest to it, as opposed to *taking* control, given they are at greater distance from that work. FPL also developed and delivered targeted communication training for managers to listen and communicate respectfully.

Turkey Point Executive Summary, CNRB Meeting #697 12/01/21

- *Equipment Performance Index Lacks Specific Behavior-Based Drivers*
  The stated Driver indicates that "station leaders have not driven high standards as evidenced by shortfalls…leading to multiple repeat reactor trips caused by water intrusion mitigation, latent design vulnerabilities, and oversight fundamentals.
  Interviews with Engineering managers indicated that no aggregate actions have been taken yet to address the…Critical Equipment Failure metric. PTN is currently in the fourth quartile for this metric.

Commission audit staff notes that as 2021 ended, though FPL was a year into its improvement program efforts, the CNRB continued to cite issues such as failure to motivate adherence to high performance standards. The CNRB appears to express frustration in noting specific causal connections to reactor trips.

2.1.5 CNRB Minutes - 2022 Issues

Turkey Point Executive Summary, CNRB Meeting #699 5/04/22

- *Safety Culture and Safety Conscious Work Environment*
  The CNRB noted a focused effort on improving the safety culture of the station. The 2022 One Fleet One Team…focused on four site priorities. One of these priorities is Treat People with Respect using the Intent-Based Leadership principles.
- *Nuclear Safety Culture Monitoring Panel*
- *The CNRB reviewed the meeting minutes for the 4Q2021 Nuclear Safety Culture Monitoring Panel. The panel moved* [the performance rating for] *Respectful Work Environment from Red* [Poor] *to Yellow* [Acceptable] *based on completion of respectful workplace training by the leadership team and a site wide survey that showed improvements in the Nuclear Safety Culture Trait Attributes of: Respect is Evident and High Level of Trust.*

FPSC EXH No. 6
03/18/2024
ADMITTED

FPL's efforts to leadership maintaining a respectful work environment appears to have showed positive results by mid-2022. At this meeting the CNRB observed a steady or declining rate of use of the Employee Concerns Program, possibly indicating fewer operations and safety concerns were being handled with supervisors rather than by anonymous ECP reports. The board also noted that Employee Concerns Program reports were being used as learning opportunities. The CNRB noted the rate of Employee Concerns Program feedback was lower than in 2021.

Summary, CNRB Meeting #699 5/04/22

- *Progress has been made with improving leadership focus on core business monitoring and execution…. However, at the time of this review significant progress has not been made with indicators to provide direct evidence of the effectiveness of these actions. For example, the total backlog for Non-Preventive Maintenance online Work Orders continued to increase from 7,185 in April 2021 to 7,873 in April of 2022.* [increase of 9.6%] *Additionally, critical and non-critical Preventive Maintenance items in the second half of grace continues to be* [rated in the] *fourth quartile* [among U.S. nuclear units.] *A follow-up item is recommended for the next review to determine progress on metrics to demonstrate long term effectiveness of these initiatives.*

St. Lucie Executive Summary, CNRB Meeting #699 5/04/22

Action Items *[From CNRB #697 12/02/21, reviewed for closure]*

MS-AI-21-697-1*…Maintenance core business is insufficient to ensure key aspects of maintenance fundamentals, specifically preparation, performance, and ownership are being demonstrated. These gaps have led to increased outage durations, 4th quartile performance* [of Key Performance Indicators] *and increasing backlogs…. Maintenance leadership has been content with recovery and has yet to establish the fundamentals of core business monitoring required to ensure sustainable high performance. Action: Develop and develop core business monitoring within Maintenance to ensure: (i) plant repairs receive first priority; (ii) proper oversight of vendor performance is conducted; and (iii) critical maintenance station responsibilities such as predictable and timely work execution are maintained at acceptable levels….*

Progress has been made with improving leadership focus on core business monitoring and execution. However, a follow-up item is recommended for the next review to determine progress on metrics to demonstrate long term effectiveness of these initiatives.

Commission audit staff notes that repeat backlogs of maintenance work was noted by the CNRB as a deficiency as early as 2017.

St. Lucie Executive Summary, CNRB Meeting #699 5/04/22

- *INPO 19-003, Staying on Top*
  The station's focus on improving performance using the "Intent Based Leadership" model was evident at senior level meetings. In contrast, two recent plant shutdowns caused by [deficient] *worker performance indicate continued weakness in either* [the INPO traits of] *Excellence in Standards or Self Awareness/Self Control….*

  The following Gaps were noted by the CNRB:

1) *Operations experienced several refueling outage delays due to a gap in proficiency for plant recovery and startup.*
   Driver: Proficiency gaps exist in the department for plant recovery and startup from refueling outages that was not corrected from previous outages by incorporating into procedures for consistent performance.
   Action: Develop a plan to address proficiency gaps…. Consider a review of all Operations previous Outage delays and Operational Experience for quality of closure and adding additional detail to startup procedures for consistent performance….

4) *Outage lessons learned are not sufficiently corrected and codified to provide long term sustainability of the actions.*

Commission audit staff notes that in 2022 while FPL continued its efforts to implement an improved managerial model, it was apparent that changing worker performance habits and trends would require an ongoing effort. Unsatisfactory worker performance, proficiency gaps, and failure to benefit from lessons learned hampered planned outage execution and forced outage prevention.

2.1.6 CNRB Minutes – 2023 Issues

At the time Commission audit staff completed its data gathering and analysis, one 2023 CNRB meeting had been conducted on June 21, 2023.

Turkey Point Summary, CNRB Meeting #703 6/21/23

GAP: Setting organizational direction and oversight (Resolution will require fleet and site collaboration.)
Inconsistencies with the implementation of fleet and site strategic initiatives:

- *Proficiency: Practice-Like-We-Play is inconsistently implemented across the station departments…*

FPSC EXH No. 6
03/18/2024
ADMITTED

- *1F1T team meetings are tactical versus strategic in nature and lack formality.*
- *Communications of ongoing organizational changes within engineering, chemistry and operations has not resulted in a true understanding of the change by the technicians.*

Driver: *Senior leaders have not ensured the organization understands the importance and priority for the implementation of strategic initiatives. Additionally, communications provided for the strategic plan have not clearly delineated the importance of each focus area and penetrated throughout the leadership team….*

Commission audit staff notes the continuing theme of deficiencies in management communication and oversight are called out and are directed up to the senior plant level.

- *Online Work Management (Site Ops & Jupiter West Site Specific)*
  Previous CNRBs (699 & 701) noted increasing backlogs. A formal action was assigned and backlog trends arrested…The poor work management behaviors that resulted in the increasing backlogs appear to still exist and are now resulting in poor critical scope survival. The CNRB recommends the site perform benchmarking of the northern fleet to replicate actions taken to improve performance.

Commission audit staff notes though work order backlogs appeared to have been eliminated, the CNRB noted the causal behaviors have still persisted. The CNRB suggested contacting other NextEra nuclear units for assistance.

The following Gaps were noted by the CNRB, new actions listed:
Gap: *The Reactor Coolant System overfill operating experience was an example of a missed opportunity to learn from such incidents as a 4.0 critique was not performed. Additionally, the causal evaluation performed was insufficient to ensure that crew dynamics* [and] *leadership are fully engrained in the culture of PSL operations….*

Gap: *Managers and Supervisors have not validated that understanding of online 1F1T* [One Fleet One Team] *work management roles and responsibilities have penetrated down and across the organization…*

Drivers: *Fleet and site leaders have not consistently verified their understanding of the process amongst one another that would allow provision for a consistent platform for embedding the core value elements within the workforce….*

FPSC EXH No. 6
03/18/2024
ADMITTED

2.2 Management Review Committee

Management Review Meetings are held bimonthly to provide forums at both corporate and site levels for the corporate senior management team to conduct oversight and monitoring of operational performance, production, and goal attainment. Management Review Meetings, though more frequently held than Company Nuclear Review Board meetings, largely involve the same set of participants.

NextEra's Executive Vice President/Chief Nuclear Officer sponsors these meetings, the FPL Site Vice Presidents serve as chair, and the Vice President – Nuclear has authority over the agenda, attendees, and presentations made. Like CNRB meetings, Management Review Meetings are attended by site senior leaders who participate and make presentations regarding their areas of responsibility.

The meeting agendas include updates and briefings on functional area performance metrics data, status updates on fleet and site improvement initiatives, and address abnormal or unanticipated events. Both CNRB meetings and Management Review Meetings serve to inform Senior and Executive Managers, and to address key operational issues, events, results, goals and objectives.

Management Review Meetings clearly provide the key information needed by corporate and FPL Senior and Executive Management to understand the status of operations, the challenges being faced, and the plans for resolution. Like CNRB meetings, discussions at Management Review Meetings result in the creation and assignment of action items. They are systematically tracked and revisited at following meetings until resolved.

Following a Management Review Meeting, the actual set of presentation documents from each meeting serves as the formal minutes. In contrast, the CNRB minutes capture transcribed questions, answers, and comments of the participants. Comparison shows similar topics being discussed at each by many of the same participants. However Commission audit staff notes the CNRB meeting minutes give a more tangible picture of reactions to information presented and tones of comments made.

Commission audit staff believes that the benefits of Management Review Meetings complement those provided by the Company Nuclear Review Board. Both provide effective means of maintaining focus on excellence in nuclear operations at PTN and PSL.

2.3 FPL and Nuclear Industry Performance Indicator Controls

Performance indicator metrics are an essential tool to monitor the functioning and management of FPL's nuclear units. The company monitors sets of metrics that provide a "rating system" for the results and trends of PSL's and PTN's operational performance. Customized metrics

FPSC EXH No. 6
03/18/2024
ADMITTED

documented the execution of all aspects of maintenance, engineering, operations/operational focus, work management, organizational effectiveness, and equipment performance.

2.3.1 Institute of Nuclear Power Operations Performance Indicators

As a member of the Institute of Nuclear Power Operations (INPO), FPL provides operational performance-related data for assessment and analysis. Using this data, and proprietary analytical tools, INPO prepares a full set of nuclear operations performance metrics for its member utilities' internal use. The set of INPO metrics and ratings have become the "gold standard" by which U.S. nuclear units measure themselves. As a condition of INPO membership, all participating utilities, including FPL, are bound by non-disclosure agreements regarding metrics results. Therefore this full set of INPO data regarding FPL was not available to Commission audit staff for review and analysis. As of fourth quarter 2023, FPL internally reported the performance metrics scores for both PTN and PSL had returned to the highest ratings in a number of years.

2.3.2 FPL Performance Indicators

Similar to the INPO metrics, FPL has developed and customized a set of performance metrics to analyze operational data. The FPL performance metrics results are monitored by management to maintain awareness of operational performance. These performance indicator results are discussed and analyzed extensively at FPL's bimonthly Management Review Meetings. Commission audit staff believes FPL's internal performance metrics set is an appropriate and effective internal control.

PTN Performance Indicator Trends

As expected, performance in many of FPL's indicators is driven by the impact of events such as forced outages, power reductions and extended refueling outages. In general terms, PTN performance metric results between 2017 and 2023 can be divided into three periods.

At the beginning of this period many of PTN's metrics scores reflected unsatisfactory to poor performance. However between late 2017 and 2019, PTN's scores steadily improved notably. In 2020, scores maintained stability until July and August 2020 when a series of four outages resulted in poor scores for measures related to SCRAM frequency and Generation Loss.

As described previously, these problems at PTN led to a comprehensive improvement initiative. Despite some setbacks from occasional outages in late 2020 and 2021, the improvement efforts began to show positive results in early 2022. Since then, PTN performance indicator scores had markedly improved as of mid-2023.

PSL Performance Indicator Trends

As noted, many indicator scores are driven by the impact of events such as forced outages, power reductions and extended refueling outages. Over the period 2017 through mid 2023, trends in PSL metrics scores are less distinct than those at PTN.

FPSC EXH No. 6
03/18/2024
ADMITTED

In late 2017 some lagging PSL performance indicators improved and then maintained stability through much of 2018. However, outages in October 2018, December 2018, and September 2019 led to a run of unsatisfactory metrics scores. Indicator scores were largely stable from late 2020 through late 2021. In December 2021 and September 2022, and three partial forced outages in October and November 2022 led to unsatisfactory scores.

2.4 Nuclear Safety Culture Controls

In addition to inspections monitoring nuclear operations performance, the NRC requires nuclear utilities to monitor their Nuclear Safety Culture. The NRC defines this as "the core values and behaviors resulting from a collective commitment by leaders and individuals to emphasize safety over competing goals to ensure protection of people and the environment." The NRC's ongoing evaluation of safety culture is part of its Reactor Oversight Process, which includes inspections and ongoing observation by resident inspectors at all plants.

FPL relies on a variety of Nuclear Safety Culture controls including the Nuclear Safety Culture Monitoring Panel, Nuclear Safety Culture Assessments, and the Nuclear Assurance and Assessment function. Commission audit staff believes these and related controls provide an appropriate system of monitoring and supporting the health of safety culture at PTN and PSL.

2.4.1 Nuclear Safety Culture Assessments

Nuclear safety Culture Assessments are required by FPL procedures to be performed separately for PTN and PSL approximately every two years. These assessments consider the presence of key organizational traits that support healthy safety focus such as personal accountability, effective safety communication, respectful work environment, leadership safety values, and promotion of a questioning attitude. These assessments also review Root Cause Evaluations to gain awareness of safety risks revealed through events such as outages.

2.4.2 Safety Conscious and Respectful Work Environment Surveys

Workers' attitudes towards safety are studied using Safety Conscious Work Environment and Respectful Work Environment surveys. These surveys assess the degree of comfort plant staff has with raising a work concern regarding safety. Results are tracked over time to identify trends and patterns with employee perceptions of management's willingness to accept and listen to safety concerns.

2.4.3 Nuclear Safety Culture Monitoring Panel

The Nuclear Safety Culture Monitoring Panel plays an ongoing oversight role in monitoring safety culture status. The panel is comprised of plant staff representing all operational areas and functions to provide a cross-functional viewpoint. NSCMP meetings occur three times a year. At meetings, the status of each of the organizational safety traits mentioned above is discussed. A color-coded rating system is used for each trait to measure status and allow tracking of trends. The panel reports periodically to the Management Review Committee.

FPSC EXH No. 6
03/18/2024
ADMITTED

C3-570

2.4.4 Nuclear Assurance Organization

The Nuclear Assurance organization plays a key role in safeguarding FPL's Nuclear Safety Culture efforts, primarily in directing the administration of the Employee Concerns Program (ECP). The ECP provides an alternative channel for plant employees to report concerns about safety practices and other problems.

Employees may also opt to report such concerns directly to their supervisor or managers, or to the NRC. The ECP option gives an employee with safety concerns the ability to make a report anonymously. This allows FPL to learn of potential problems when employees fear possible negative impacts from direct contact with superiors. If plant workers are not comfortable reporting their concerns about any safety issue, significant problems could remain unaddressed. This risk makes a healthy ECP program vital to Safety Culture.

Nuclear Assurance oversees investigating reported employee concerns, maintaining auditing procedures, overseeing investigation quality, and documenting case history, findings, and corrective action taken.

Commission audit staff carefully reviewed the handling of concerns by FPL employees over the study period. Though questions regarding investigation quality arose in 2019, FPL engaged a consultant who recommended process improvements. Commission audit staff believes FPL responded appropriately to the recommendations and documented closure of its corrective action plans.

Subsequent to these improvements, Commission audit staff found no evidence of attempts by PTN or PSL management to suppress employees reporting safety concerns. The results of ongoing Safety Conscious Work Environment surveys provide additional evidence that employees are willing to report their concerns.

Nuclear Assurance also plans and executes a system of internal audits that address Quality Assurance and Quality Controls issues, organizational effectiveness, verifying performance improvement through corrective actions, and compliance with NRC regulations. Periodic status reports are provided to the Chief Nuclear Officer, and CNRB meetings regularly include statements regarding the effectiveness of Nuclear Assurance operations.

FPSC EXH No. 6
03/18/2024

ADMITTED

C3-571

C3-469

FPSC EXH No. 6
03/18/2024
ADMITTED

3.0 PTN and PSL Forced Outage Causes and Costs

Generating unit outages fall into two basic categories - forced outages and planned outages. Planned outages include cyclical refueling outages that are carefully scheduled and executed to minimize generation loss. Maintenance activities are often scheduled to coincide with refueling outages to minimize their impact. On occasion, a refueling outage may be extended one or more days if an unexpected maintenance issue is discovered while the unit is down.

Forced outages are caused by either unexpected automatic trips or by manual trips executed by plant personnel upon detection of abnormal operating conditions and performance. Because of their unexpected and often complex nature, forced outages generally pose a higher risk of lost of days of operation and higher costs than planned outages.

3.1 Commission Audit Staff Analysis - Forced Outages

Once a forced outage occurs and safety assessments are made, the highest priority task is cause determination. The utility marshals resources to identify the root cause and extent of the problems identified. The Root Cause Evaluation (RCE) entails a highly technical and precise examination of plant components, reconstruction of operator actions, review of plant maintenance and operating records, and application of expert knowledge and judgement.

The utility focuses on cause determination, identifying appropriate corrective actions, and returning the plant to operational condition. Because the RCE may identify a root cause that is deemed preventable (such as operator error or failure to perform maintenance that caused a key component failure) it may give indications regarding responsibility for the outage.

Ultimately, the disposition of the incremental repair and restoration costs must be accounted for by the utility and regulators. The NRC may be involved in the RCE process, focusing on operational and compliance issues as part of its Reactor Oversight Process.

The replacement power costs resulting from a forced outage may come before the Florida Public Service Commission. The Commission's examination and decision-making necessarily involve application of traditional prudence standards used by PSCs and PUCs.

Commission audit staff reviewed the outage record for both PTN and PSL over the years 2017 through mid-2023, a period during which over 80 planned, forced, and partially-forced outages occurred. **Exhibit 1** below depicts FPL's unplanned outages and SCRAMS for each units separately over the 2017 through 2023 period. Unplanned outages for both PTN 3 and PTN 4 peaked in 2020. PSL 1 and PSL 2 unplanned outages peaked in 2021.

FPSC EXH No. 6
03/18/2024

C3-573

ADMITTED

FPL Unplanned Outages/SCRAMS




Exhibit 1

Source: Document Response 1-20

Commission audit staff conducted interviews with FPL Executive Management to obtain understanding regarding selected outages. This information was compared with the Root Cause Evaluations, and the records of minutes and reports from the Company Nuclear Review Board and Management Review Meetings.

Through this process, Commission audit staff selected the eight forced outages listed in **Exhibit 2.** These involve various problematic issues such as quality of vendor oversight, human performance failures, repeat causality, latent design issues, and procedural non-compliance.

FPSC EXH No. 6
03/18/2024
ADMITTED

C3-574

Selected FPL Unplanned Outages/SCRAMS 2017 – 2023			
Plant	**Begin Date**	**Duration**	**Outage Description**
PSL 2	10/26/17	3 days	Unit 2 turbine control system malfunction and turbine trip
PTN 4	07/05/20	15 days	Unit 4 reactor trip due to generator lockout from loss of exciter
PTN 3	08/19/20	1 day	Reactor trip caused by N-3-31 source range counts
PSL 2	01/20/21	3 days	Unit 2 automatic reactor trip due to an unexpected deenergization of the 480v motor control center 2B2
PTN 3	03/01/21	3 days	Unit 3 trip during restoration from Reactor Protection System (RPS) testing
PSL 1	05/14/21	4 days	Outage SL1-30 extension due to failure of four Control Element Assembly (CEA) lower gripper coils
PSL 1	12/10/21	2 days	Unit 1 manual trip due to insufficient feed flow to 1A steam generator
PSL 2	01/06/22	14 days	Unit 2 CEA #27 Control Element Drive Mechanism (CEDM) failure

Exhibit 2 *Source: FPL Response to D.R. 1-20*

The eight selected forced outages are chronologically discussed in detail in subsections **3.1.1** through **3.1.8** below. Excerpts from FPL's Root Cause Evaluations are included and italicized for emphasis in these subsections.

Exhibit 3 presents excerpts taken from the associated Root Cause Evaluations and an NRC Special Investigation Report performed to analyze these eight outages.

FPSC EXH No. 6
03/18/2024

ADMITTED

Commission Audit Staff Analysis of Selected Outages

Begin Date	FPL Root Cause Evaluation Excerpts
PSL 2 Automatic Reactor Trip Begin Date: 10/26/17 End Date: 10/28/17 Duration: 3 days CE: CR 2232849	**UNIT 2 TURBINE CONTROL SYSTEM MALFUNCTION AND TURBINE TRIP** **RC:** The direct cause of the spurious solenoid malfunctions could not be determined conclusively... The most probable root cause is the Turbine Control System design is inadequate to prevent common cause failure in the fail-safe Emergency Trip coincidence logic, and lacks adequate indications or diagnostic features for detecting malfunctions when they occur. .. ...Previous similar malfunctions have occurred in single solenoids and these were found to be due to malfunction of Digital Output (DO) modules. Evaluations of the prior events revealed that the DO circuit cards had surface contamination and corrosion. Based on these findings (along with the overnight temperature drop) the Failure Investigation Process (FIP) concluded that malfunction of a DO module (or modules) due to environmental conditions played a role in the trip... **CC:**... An adverse trend in spurious TDM solenoid operations was identified in 2016, which required long term corrective action to fully address; however, interim actions for increased condition monitoring and/or proactive component replacement were not adequately developed as a bridging strategy for the long term actions... **Per Safety Culture Evaluation RC:** ...the legacy design changes implemented remote I/O cabinets and did not rigorously review environmental aspects of the design. The Engineering Change implementing the TCS replacement was developed more than 5 years ago under a larger scope, and independently managed, Extended Power Uprate project. This aspect is considered as a legacy and no longer indicative of current plant performance...
PTN 4 Automatic Reactor Trip Begin Date: 7/5/20 End Date: 7/20/20 Duration: 15 days RCE: AR 2361794	**UNIT 4 REACTOR TRIP DUE TO GEN LOCKOUT FROM LOSS OF EXCITER.** **RC:** A weakness in the Exciter PM Program resulted from a failure to fully assess risk of PMG stator winding age making it more susceptible to failure when exposed to water/moisture. **SC1:** Weakness in Exciter PM Program based on existing OEM and Industry recommendations which were Condition Based, and did not require Time-Based PMG stator rewind, thereby increasing susceptibility to failure from other stressors. **SC2:** OEM procedure 3.2.2.1 did not include site specific weather sealing requirements based on OE [operating experience] - latent error. **CC:** Instructions in PTN procedure 0-GMM-090.1, 'Exciter Removal, Inspection and Installation,' in providing discretionary guidance in lieu of a mandated requirement on Exciter housing application of site specific weather seals for prevention of water intrusion. **Lessons Learned:** Vendor recommendations and current industry practices alone with regards to equipment maintenance may not be sufficient to support equipment reliability. The PM philosophy at PTN developed for maintain the Exciter and Generator components relied upon the recommendations of the OEM and the Industry (CONDITION-BASED) and are considered robust. However, they lacked a requirement to perform a TIME-BASED rewind of the Exciter components. This lack of a rewind requirement allowed the equipment to age which increased susceptibility to failure from other external stressors. Single Point Vulnerability SPV components which are similar in design...should be reviewed for appropriate Life Cycle Management (LCM) activities which specifically address age.

FPSC EXH No. 6
03/18/2024

ADMITTED

Commission Audit Staff Analysis of Selected Outages

Begin Date	FPL Root Cause Evaluation Excerpts
PTN 3 Automatic Reactor Trip Begin Date: 8/19/20 End Date: 8/20/2 0Duration: 1 day RCE: CR 2365970	**REACTOR TRIP CAUSED BY N-3-31 SOURCE RANGE COUNTSRC:** Knowledge gaps and incorrect mental model for conducting a reactor startup and operating below the Point of Adding Heat (POAH.) **Direct Cause:** ...Contrary to procedural requirements, the Reactor Operator (RO) failed to verify proper Source Range (SR) and Intermediate Range (IR) overlap and block the SR Nuclear Instruments prior to reaching the reactor trip setpoint of 1x10^5 CPS... **Conclusion:** This is a people failure with a safety culture gap in training. **CC:** ...Lack of operator and operations leadership's self-awareness of proficiency gaps and procedure deficiencies. **Conclusion**: ...This is are [sic] organizational and programmatic failures with safety culture gaps in procedure use and adherence, teamwork, avoiding complacency, and conservative bias. **NRC SPECIAL INSPECTION REPORT: [December 9, 2020]** The team determined that the following were contributing factors to the human performance errors identified:[Experience level of the crew, JIT Training, Operator Fundamentals breakdowns, Oversight and Control of the Startup Evolution, Confusing Indications, and Distractions.]The team determined that numerous plant procedures were not adhered to during this event, including the following:[Procedure 3-GOP-301, 'Hot Standby to Power Operations,' Rev. 53, Step 5.21, Procedure 3-GOP-301, caution statement prior to Step 5.16.3 and procedure OP-AA-103-1000, Rev. 13, Section 3.7 caution statement, Procedure OP-AA-100-1000 'Conduct of Operations,' Rev. 25, Attachment 5, Section 3.2, Procedure OP-AA-100-1000 'Conduct of Operations,' Rev. 25, Attachment 4, Section 3.3, Procedure OP-AA-100-1000 'Conduct of Operations,' Rev. 25, Attachment 4, Section 3.1, Procedure OP-AA-103-1000, Reactivity Management, Rev. 13.] ...During correspondence with the vendor, the licensee was informed that they were not following the guidance described in vendor document RRS-VICO-02-326, 'A Predictive Maintenance and Evaluation Guide for Ex-Core and In-Core Detectors used in Westinghouse Pressurized Water Reactors,' dated May 2002... The licensee failed to establish a preventive maintenance for the SRNIs which rendered a required SRNI N32 inoperable and unable to perform its special function.

FPSC EXH No. 6
03/18/2024

ADMITTED

Commission Audit Staff Analysis of Selected Outages

Begin Date	FPL Root Cause Evaluation Excerpts
PSL 2 Automatic Reactor Trip Begin Date: 1/20/21 End Date: 01/22/21 Duration: 3 days RCE: CR 2381509	**Unit 2 AUTOMATIC REACTOR TRIP DUE TO AN UNEXPECTED DEENERGIZATION OF THE 480V MOTOR CONTROL CENTER 2B2RC:** The legacy drawings for the undervoltage relay assemblies in the Control Element Drive Mechanism Control System (CEDMCS) did not conform to PSL 2 train and channel design conventions such that design details including power supply assignments were not clearly defined. …Previous Occurrences: 4/20/1987 - This event is similar in that a 1987 reactor trip resulted from a similar SPV. Summary: The LER documents that the CEDMCS wiring discrepancy was corrected before the LER was submitted. It is evident that the 1987 corrective action was not complete or not sustained so that it prevented the 2021 reactor trip… 7/26/1983 - This event is similar in that a 1983 reactor trip resulted from a similar SPV. Summary: PC/M 392-283 (D-11) documents the 2-out-of-4 trip logic of the turbine trip by reactor trip as the cause for the actual plant trips (D-02.) It is evident that the 1983 corrective action was not complete or not sustained so that it prevented the 1987 reactor trip…. ...This meets the definition of Repeat Event provided in PI-AA-104-1000, Condition Reporting: Two or more independent occurrences of the same or similar event resulting from the same fundamental problem for the same fundamental cause for which previous root cause analysis has occurred and corrective action failed.... ...Even though the previous event occurred at St. Lucie over thirty years ago, the corrective actions from the 1983 and 1987 events should have been expected to prevent this event. The potential inadequacy of these legacy corrective actions is analyzed further into the support/refute matrix.
PTN3 Automatic Reactor Trip Begin Date: 3/1/21 End Date: 3/4/21 Duration: 3 days RCE: CR 2385529	**UNIT 3 TRIP DURING RESTORATION FROM RPS TESTING** **RC:** IAW 0-PMR-049.01, steps for cleaning and lubricating cell switch contacts is conditional based, rather than prescriptive. **CC1:** Test points to detect failed contacts were not installed. **CC2:** Failure to follow WEC MPM cell switch maintenance and replacement frequency. **Direct Cause:** ...While no exact direct cause was identified, The RCE team determined the most probable direct cause was hardened graphite grease on the cell switch #2 contact 1-2 causing a tracking path which incorrectly indicated the contact was in an open state.... **Proof Statement:** ...The Unit 3 trip was caused by inadequate procedure guidance in 0-PME-049.01 for cleaning and lubricating cell contacts and is corrected by revising procedure 0-PME-049.01 to require cleaning and lubrication of cell switch contacts... ...**Westinghouse Failure Analysis Conclusions:** ...The cell switches appeared to be original supplied equipment. They were not properly maintained, and the hardened lubrication could cause the stationary contacts to become dislodged, as documented above. In addition, to contributing to the dislodging the stationary contacts, excess or dry grease can cause improper indications from the switch contacts. This could be considered a possible cause of failure.

FPSC EXH No. 6
03/18/2024

ADMITTED

C3-578

Commission Audit Staff Analysis of Selected Outages	
Begin Date	**FPL Root Cause Evaluation Excerpts**
PSL 1 Outage Extension Begin Date: 5/14/21 End Date: 5/17/21 Duration: 4 days RCE: CR 2392617	**OUTAGE SL1-30 EXTENSION DUE TO FAILURE OF FOUR CONTROL ELEMENT ASSEMBLY LOWER GRIPPER COILS.** **RC:** ...Loss of software configuration control by the vendor. While revising the Coil power Management Drawer (CPMD) firmware, ...an unplanned software change was inadvertently coded into the firmware revision. The unplanned firmware change removed overcurrent protection for the impacted CEA coils that would otherwise have protected these coils prior to change being implemented. **CC:** Event triggered when the CPMD in question shifted its AC to DC rectification to extreme firing angles, after sensing high disconnect switch resistance in the circuit. This high resistance in the sensed loop had never been encountered at any of the operating units using similar systems worldwide, nor was it encountered during a lengthy Factory Acceptance Test (FAT) from May through August 2019. ...The offending CPMD firmware revisions did not conform to the vendor's 'Standard Rod Control Systems Software Development Process' (WNA-IG-00874-GEN) in that a software change was made to CPMD firmware without proper requirements definition, software design and code review in advance. Nor did a 2-way software audit occur after the code change...Had WNA-IG-00874-GEN been followed, then the LG overcurrent protection would not have been removed during SL-30 [refueling outage,] and the damage to the four CEA's LG coils would have been obviated. **Proof Statement:** ...Excessive current supplied to four CEA LG Coils causing their failure was caused by error in software configuration that removed overcurrent protection during a revision and is corrected by restoring overcurrent protection to CRC firmware and improved the rigor of software configuration management process for future revisions.
PSL 1 Manual Reactor Trip Begin Date: 12/10/21 End Date: 12/11/21 Duration: 2 days RCE: CR 2413519	**UNIT 1 MANUAL TRIP DUE TO INSUFFICIENT FEED FLOW TO 1A STEAM GENERATOR** **RC:** FIN (Fix It Now) Supervisor chose to deviate from the FIN work management process and failed to validate readiness to perform FIN work prior to work execution. **CC1:** The Planner developed the work instructions based on a historical work order and did not adequately review the controlled drawings to identify the interaction between this circuit and the other control valves. **CC2:** The technicians were complacent due to past success landing leads and did not use an insulating barrier to prevent impacting the circuit from inadvertent contact and an assumption that all affected valves were isolated.

FPSC EXH No. 6
03/18/2024

ADMITTED

C3-579

Commission Audit Staff Analysis of Selected Outages	
Begin Date	**FPL Root Cause Evaluation Excerpts**
PSL 2 Outage By Tech. Spec. Begin Date: 1/6/22 End Date: 1/20/22 RCE: CR 2415359	**UNIT 2 CEA #27 CEDM FAILURE** **RC:** Station leaders and stakeholders in refueling work activities have not ensured that Reactor Services activities are aligned with FME program requirements for complex tools. The resulting inadequate plans prevented discovery of a pin broken from the SCOUT tool during CEA coupling, which migrated into CEDM #27. **Safety Culture Evaluation:** The causal factors are related to Cross-Cutting Aspect H.5 Work Management: The organization implements a process of planning, controlling, and executing work activities such that nuclear safety is the overriding priority. The work process includes the identification and management of risk commensurate to the work and the need for coordination with different groups or job activities. The Foreign Material Intrusion Risk posed by a SCOUT tool failure was not managed adequately under the work process for CEA coupling. In accordance with FME program requirements the Complex Tooling Inspection Checklist should have been used to identify and mitigate these risks. The RSS FME plan did not address complex tooling activities. A work order applicable to the RSS support tasks was not used, therefore, the associated planning inputs and FME program interfaces (work steps, briefing prompts, forms, etc.) normally included in work orders by work planners were not available to the crew.

Exhibit 3

Source: FPL Root Cause Evaluations dated 12/15/17, 9/28/20, 3/9/21, 7/29/21, 6/2/22, and NRC Special Investigation Report dated 12/9/20.

Commission audit staff believes that all eight of these outages raise questions relating to circumstances and causation. These eight forced outages, their circumstances, and resulting root cause evaluations are discussed chronologically in subsections **3.1.1** and **3.1.3.**

3.1.1 PSL 2 Automatic Reactor Trip 10/26/17 – 10/28/17
Unit 2 Turbine Control System Malfunction and Turbine Trip

Though no single Root Cause was determined as a result of FPL's analysis of this outage, the "Most Probable Root Cause" noted "The Turbine Control System design is inadequate to prevent common cause failure in the fail-safe Emergency Trip coincidence logic, and lacks adequate indications or diagnostic features for detecting malfunctions when they occur." Commission audit staff believes this statement calls into question the adequacy and prudence of FPL's decision-making regarding outage prevention controls.

The Root Cause Evaluation also refers to FPL's 2016 identification of the solenoid malfunctions and realization that both interim and long-term corrective actions were needed. Commission audit staff notes that despite awareness of needed actions, the Root Cause evaluation states "however, interim actions for increased condition monitoring and/or proactive component replacement were not adequately developed …." Commission audit staff believes that this lack

FPSC EXH No. 6
03/18/2024
ADMITTED

of proactivity in 2016 may constitute failure to take prudent corrective action based upon the information that was known to FPL at the time.

> ***Root Cause:*** *The direct cause of the spurious solenoid malfunctions could not be determined conclusively.*
> ***Most Probable Root Cause:*** *The Turbine Control System design is inadequate to prevent common cause failure in the fail-safe Emergency Trip coincidence logic, and lacks adequate indications or diagnostic features for detecting malfunctions when they occur….*
> *…Previous similar malfunctions have occurred in single solenoids and these were found to be due to malfunction of Digital Output (DO) modules. Evaluations of the prior events revealed that the DO circuit cards had surface contamination and corrosion. Based on these findings (along with the overnight temperature drop) the Failure Investigation Process (FIP) concluded that malfunction of a DO module (or modules) due to environmental conditions played a role in the trip….*
> ***Contributing Cause:*** *…An adverse trend in spurious TDM solenoid operations was identified in 2016, which required long term corrective action to fully address; however, interim actions for increased condition monitoring and/or proactive component replacement were not adequately developed as a bridging strategy for the long term actions….*
> ***Per Safety Culture Evaluation Root Cause:*** *…The legacy design changes implemented remote I/O cabinets and did not rigorously review environmental aspects of the design. The Engineering Change implementing the TCS [Turbine Control System] replacement was developed more than 5 years ago under a larger scope, and independently managed, Extended Power Uprate project. This aspect is considered as a legacy and no longer indicative of current plant performance….*

3.1.2 PTN 4 Automatic Reactor Trip 7/5/20 – 7/20/20

Unit 4 Reactor Trip Due To Gen Lockout from Loss of Exciter

FPL's Root Cause statement labels the lack of routinized ongoing preventive maintenance as a "weakness." More importantly, it notes FPL's "failure to fully assess the [Permanent Magnetic Generator] stator winding age making it more susceptible to failure when exposed to water/moisture.

Significant Cause 2 noted that the OEM procedure did not include site specific weather sealing requirements and apparently labeled the lack of weather sealing requirements based on OE as a "latent error." The Contributing Cause stated that the applicable PTN procedure also included no mandate for site specific seals to prevent water intrusion and damage.

Ultimately at issue was the advisability of the lack of routine calendar-based inspections of the Permanent Magnet Generator Stator. Instead, under FPL's condition based approach, action was taken in response to an observed adverse condition.

FPSC EXH No. 6
03/18/2024
ADMITTED

FPL's ARCE Executive Summary notes, "In summary, failure of the Unit 4 Permanent Magnet Generator stator occurred due to an aged winding in combination with water intrusion."

Commission audit staff observes that an effort to assess the risk that the stator's age combined with water intrusion would make it vulnerable to failure would have necessarily observed the *lack* of a requirement for weather sealing. Given the open precipitation exposure of the plant's design, Commission audit staff believes such a risk analysis would reasonably have led to the addition of weather sealing protection. Since FPL observed that the stator winding failed due the "combined effects of aging and water intrusion," the lack of proper risk assessment is responsible for the winding failure.

> ***Root Cause:*** *A weakness in the Exciter PM [Preventive Maintenance] resulted from a failure to fully assess risk of PMG [Permanent Magnet Generator] stator winding age making it more susceptible to failure when exposed to water/moisture.*
> ***Significant Cause 1:*** *Weakness in Exciter PM Program based on existing OEM and Industry recommendations which were Condition Based, and did not require Time-Based PMG stator rewind, thereby increasing susceptibility to failure from other stressors.*
> ***Significant Cause 2:*** *OEM procedure 3.2.2.1 did not include site specific weather sealing requirements based on OE (operating experience) - latent error.*
> ***Contributing Cause:*** *Instructions in PTN procedure 0-GMM-090.1, 'Exciter Removal, Inspection and Installation,' in providing discretionary guidance in lieu of a mandated requirement on Exciter housing application of site specific weather seals for prevention of water intrusion.*
>
> ***Lessons Learned:*** *Vendor recommendations and current industry practices alone with regards to equipment maintenance may not be sufficient to support equipment reliability. The PM* [Preventive Maintenance] *philosophy at PTN developed for maintain the Exciter and Generator components relied upon the recommendations of the OEM and the Industry (CONDITION-BASED) and are considered robust. However, they lacked a requirement to perform a TIME-BASED rewind of the Exciter components. This lack of a rewind requirement allowed the equipment to age which increased susceptibility to failure from other external stressors. Single Point Vulnerability SPV components which are similar in design…should be reviewed for appropriate Life Cycle Management (LCM) activities which specifically address age.*

3.1.3 PTN 3 Automatic Reactor Trip 8/19/20 – 8/20/20
Reactor Trip Caused By N-3-31 Source Range Counts

Commission audit staff notes this outage involved numerous human performance failures. FPL's Root Cause Evaluation variously cites shortcomings such as "Knowledge gaps and incorrect mental mode for conducting a reactor startup…." It also notes the Reactor Operator's failure to

FPSC EXH No. 6
03/18/2024
ADMITTED

follow procedures. Finally, the RCE states, "This is a people failure with a safety culture gap in training."

The NRC, in its own Special Investigation Report, identified several contributing factors to the human performance errors including the crew's lack of experience with the specific tasks involved, breakdown in operator fundamentals, and distractions. The NRC also noted FPL's lack of adherence to seven of the company's procedures. The report stated, "The licensee failed to establish a preventive maintenance for the [Source Range Nuclear Instruments] which rendered a required SRNI N32 [Channel] inoperable and unable to perform its special function." In all, 15 corrective action tasks were developed to remedy this event.

> ***Root Cause:*** *Knowledge gaps and incorrect mental model for conducting a reactor startup and operating below the POAH [Point of Adding Heat.]*
> ***Direct Cause:*** *...Contrary to procedural requirements, the RO [Reactor Operator] failed to verify proper Source Range (SR) and Intermediate Range (IR) overlap and block the SR Nuclear Instruments prior to reaching the reactor trip set point of 1x10^5 CPS....*
> ***Conclusion:*** *This is a people failure with a safety culture gap in training.*
> ***Contributing Cause:*** *...Lack of operator and operations leadership's self-awareness of proficiency gaps and procedure deficiencies.*
> ***Conclusion****: ...This is are [sic] organizational and programmatic failures with safety culture gaps in procedure use and adherence, teamwork, avoiding complacency, and conservative bias.*
> ***NRC Special Inspection Report: [December 9, 2020]***
> *The team determined that the following were contributing factors to the human performance errors identified:*
> *[Experience level of the crew, JIT Training, Operator Fundamentals breakdowns, Oversight and Control of the Startup Evolution, Confusing Indications, and Distractions.]*
> *The team determined that numerous plant [FPL]procedures were not adhered to during this event, including the following:*
> *[Procedure 3-GOP-301, 'Hot Standby to Power Operations,' Rev. 53, Step 5.21, Procedure 3-GOP-301, caution statement prior to Step 5.16.3 and procedure OP-AA-103-1000, Rev. 13, Section 3.7 caution statement, Procedure OP-AA-100-1000 'Conduct of Operations,' Rev. 25, Attachment 5, Section 3.2, Procedure OP-AA-100-1000 'Conduct of Operations,' Rev. 25, Attachment 4, Section 3.3, Procedure OP-AA-100-1000 'Conduct of Operations,' Rev. 25, Attachment 4, Section 3.1, and Procedure OP-AA-103-1000, 'Reactivity Management,' Rev. 13.] ...During correspondence with the vendor, the licensee was informed that they [FPL] were not following the guidance described in vendor document RRS-VICO-02-326, 'A Predictive Maintenance and Evaluation Guide for Ex-Core and In-Core Detectors used in Westinghouse Pressurized Water Reactors,' dated May 2002...The licensee failed to establish a preventive maintenance for the SRNIs*

FPSC EXH No. 6
03/18/2024
ADMITTED

which rendered a required SRNI N32 inoperable and unable to perform its special function.

3.1.4 PSL 2 Automatic Reactor Trip 1/20/21 – 1/22/21

Unit 2 Automatic Reactor Trip Due to Unexpected De-energization of 480v Motor Control Center 2B2

Commission audit staff notes that this 2021 outage is noted by FPL's RCE to have similarities with trips in both 1983 and 1987. The Root Cause was identified to be legacy drawings for under voltage relay assemblies not conforming to PSL 2 train conventions, leaving power supply assignments not clearly defined. The corrective actions for the 1983 trip proved to be incomplete or not sustained since they did not prevent the subsequent 1987 trip. Once again, the corrective actions for the 1987 trip proved to be incomplete or not sustained, thus failing to prevent this 2021 trip.

FPL observed "this meets the definition of Repeat Event provided in PI-AA-104-1000, Condition Reporting: Two or more independent occurrences of the same or similar event resulting from the same fundamental problem for the same fundamental cause for which previous root cause analysis has occurred and corrective action failed."

Commission audit staff notes that FPL's RCE states, "Even though the previous event occurred at St. Lucie over thirty years ago, the corrective actions from the 1983 and 1987 events should have been expected to prevent this event."

Finally, after the automatic reactor trip, FPL took corrective action by "revising control system wiring drawings to show under voltage relay assembly assignments between assigned power supply channels." Commission audit staff believes the repeat nature of this outage calls into question the adequacy and prudence of FPL's prior corrective actions and attention to Operational Experience.

> ***Root Cause:*** *The legacy drawings for the under voltage relay assemblies in the CEDMCS [Control Element Drive Mechanism Control System] did not conform to PSL 2 train and channel design conventions such that design details including power supply assignments were not clearly defined.*
> *Previous Occurrences:*
> *…This event involved a reactor trip due to an undesired recreation of a single point vulnerability (SPV). While most reasonable repeat event reviews look back as much as five years, significant events such as plant trip warrant a life of the plant review.*
> *4/20/1987 - This event is similar in that a 1987 reactor trip resulted from a similar SPV. Summary: The LER [Licensee Event Report] `documents that the CEDMCS wiring discrepancy was corrected before the LER was submitted. It is evident that the 1987 corrective action was not complete or not sustained so that it prevented the 2021 reactor trip….*

FPSC EXH No. 6
03/18/2024

ADMITTED

C3-584

1/27/1983 - This event is similar in that a 1983 reactor trip resulted from a similar SPV. Summary: PC/M 392-283 (D-11) documents the 2-out-of-4 trip logic of the turbine trip by reactor trip as the cause for the actual plant trips (D-02.) It is evident that the 1983 corrective action was not complete or not sustained so that it prevented the 1987 reactor trip….
…This meets the definition of Repeat Event provided in PI-AA-104-1000, Condition Reporting: Two or more independent occurrences of the same or similar event resulting from the same fundamental problem for the same fundamental cause for which previous root cause analysis has occurred and corrective action failed….
…Even though the previous event occurred at St. Lucie over thirty years ago, the corrective actions from the 1983 and 1987 events should have been expected to prevent this event. The potential inadequacy of these legacy corrective actions is analyzed further into the support/refute matrix….

3.1.5 PTN 3 Automatic Reactor Trip 3/1/21 – 3/4/21
Unit 3 Trip in Restoration from Reactor Protection System Testing

Similar to the July 5, 2020 PTN Unit 4 Generator Lockout from Loss of Exciter, facts surrounding this trip and the resulting RCE raise issues concerning preventive maintenance practices.

FPL's RCE states, "The reactor trip was caused by an unknown failure of the 3B reactor trip breaker." However, the Root Cause statement notes "[Procedure] IAW 0-PMR-049.01, steps for cleaning and lubricating cell switch contacts is conditional based, rather than prescriptive [required on a time basis.]" The Direct Cause states "While no exact direct cause was identified, the RCE team determined the most probable cause was hardened graphite grease on the cell switch #2 contact 1-2, causing a tracking path which incorrectly indicated the contact was in an open state." FPL's RCE Proof Statement notes "inadequate procedure guidance…for cleaning and lubrication of cell switch contacts."

Root Cause: *IAW 0-PMR-049.01, steps for cleaning and lubricating cell switch contacts is conditional based, rather than prescriptive.*
Contributing Cause 1: *Test points to detect failed contacts were not installed.*
Contributing Cause 2: *Failure to follow WEC MPM cell switch maintenance and replacement frequency.*
Direct Cause: *…While no exact direct cause was identified, the RCE team determined the most probable direct cause was hardened graphite grease on the cell switch #2 contact 1-2 causing a tracking path which incorrectly indicated the contact was in an open state….*
Proof Statement: *…The Unit 3 trip was caused by inadequate procedure guidance in 0-PME-049.01 for cleaning and lubricating cell contacts and is corrected by revising procedure 0-PME-049.01 to require cleaning and lubrication of cell switch contacts….*

FPSC EXH No. 6
03/18/2024
ADMITTED

Westinghouse Failure Analysis Conclusions: *…The cell switches appeared to be original supplied equipment. They were not properly maintained, and the hardened lubrication could cause the stationary contacts to become dislodged, as documented above. In addition to contributing to the dislodging the stationary contacts, excess or dry grease can cause improper indications from the switch contacts. This could be considered a possible cause of failure.*

3.1.6 PSL 1 Outage Extension 5/14/21 – 5/17/21

Outage SL1-30 Extension Due To Failure of Four Control Element Assembly (CEA) Lower Gripper Coils

Commission audit staff notes that this outage extension was caused by a vendor error resulting in an unplanned software change that was "inadvertently coded" into a firmware revision. FPL did not have access to the vendor's proprietary software. Regardless, it is not clear what vendor oversight efforts FPL made such as verifying the vendor's firmware controls.

In describing the identified Contributing Root Cause, FPL stated "The offending [inadvertent] firmware revisions did not conform to the vendor's 'Standard Rod Control Systems Software Development Process' (WNA-IG-00874-GEN) in that a software change was made to CPMD firmware without proper requirements definition, software design and code review in advance. Nor did a 2-way software audit occur after the code change…Had WNA-IG-00874-GEN been followed, then the LG overcurrent protection would not have been removed during SL-30 [refueling outage,] and the damage to the four CEAs' LG coils would have been obviated.

Root Cause: ..*Loss of software configuration control by the vendor. While revising the Coil power Management Drawer (CPMD) firmware, …an unplanned software change was inadvertently coded into the firmware revision. The unplanned firmware change removed overcurrent protection for the impacted CEA coils that would otherwise have protected these coils prior to change being implemented.*

Contributing Root Cause: *The event was triggered when the CPMD in question shifted its AC to DC rectification to extreme firing angles, after sensing high disconnect switch resistance in the circuit. This high resistance in the sensed loop had never been encountered at any of the operating units using similar systems worldwide, nor was it encountered during a lengthy Factory Acceptance Test (FAT) from May through August 2019.*

…The offending firmware revisions did not conform to the vendor's 'Standard Rod Control Systems Software Development Process' (WNA-IG-00874-GEN) in that a software change was made to CPMD firmware without proper requirements definition, software design and code review in advance. Nor did a 2-way software audit occur after the code change…Had WNA-IG-00874-GEN been followed, then the LG overcurrent protection would not have been removed during SL-30 [refueling outage,] and the damage to the four CEAs' LG coils would have been obviated.

FPSC EXH No. 6
03/18/2024
ADMITTED

C3-586

Proof Statement: *...Excessive current supplied to four CEA LG Coils causing their failure was caused by error in software configuration that removed overcurrent protection during a revision and is corrected by restoring overcurrent protection to CRC firmware and improved the rigor of software configuration management process for future revisions.*

3.1.7 PSL 1 Manual Reactor Trip 12/10/21 – 12/11/21

Unit 1 Manual Trip Due To Insufficient Feed Flow To 1A Steam Generator

Commission audit staff notes that FPL's identified Root Cause and Contributing Causes 1 and 2 involve FPL employee performance gaps and deficiencies. A supervisor's willful deviation from a defined management process, failure to review necessary drawings, complacency in performing of key tasks, and failure to use an insulating barrier led to questions about prudence of actions.

> ***Root Cause:*** *FIN [Fix It Now] Supervisor chose to deviate from the FIN work management process and failed to validate readiness to perform FIN work prior to work execution.*
> ***Contributing Cause 1:*** *The Planner developed the work instructions based on a historical work order and did not adequately review the controlled drawings to identify the interaction between this circuit and the other control valves.*
> ***Contributing Cause 2:*** *The technicians were complacent due to past success landing leads and did not use an insulating barrier to prevent impacting the circuit from inadvertent contact and an assumption that all affected valves were isolated.*

Sixteen months earlier, two August 2020 PSL 1 incidents also involved lifted leads and human performance issues. According to FPL's Root Cause Evaluation, "…there were human performance issues that led to this event." A presentation to the December 2020 Management Review Meeting described this gap as follows: "Maintenance managers have not developed the necessary skills and abilities of the [General Maintenance Leaders] and maintenance supervisors to effectively identify, coach and correct human performance behaviors which have resulted in station events." The first event involved an Instrument Bus loss of power due to 1B Inverter Trip. The second occurred when an intake cooling water header non-essential header isolation valve failed to close. The occurrences of these human performance gaps, during consecutive years, and FPL's 2021 reference to "complacency" appear to indicate inadequate corrective action was taken in 2020.

3.1.8 PSL 2 Outage by Technical Specification 1/6/22 – 1/20/22

Unit 2 CEA #27 Control Element Drive Mechanism (CEDM) Failure

Commission audit staff notes FPL's language in the RCE is critical of the company's handling of Foreign Material Intrusion risks involving "complex tooling activities." The Safety Culture

C3-484

FPSC EXH No. 6
03/18/2024
ADMITTED

Evaluation points out, "The Foreign Material Intrusion Risk posed by a SCOUT tool failure was not managed adequately under the work process for CEA coupling. In accordance with FME program requirements the Complex Tooling Inspection Checklist should have been used to identify and mitigate these risks. The RSS FME plan did not address complex tooling activities.

> ***Direct Cause:*** *An L-Slot pin fractured from the SCOUT tool during CEA #27 coupling. The pin later migrated into the #27 CEDM and lodged between the upper gripper lath magnet and pull-down magnet resulting in binding of the CEDM motor.*
> ***Root Cause:*** *Station leaders and stakeholders in refueling work activities have not ensured that Reactor Services activities are aligned with FME program requirements for complex tools. The resulting inadequate plans prevented discovery of a pin broken from the SCOUT tool during CEA coupling, which migrated into CEDM #27.*
> ***Safety Culture Evaluation:*** *The causal factors are related to Cross-Cutting Aspect H.5 Work Management: The organization implements a process of planning, controlling, and executing work activities such that nuclear safety is the overriding priority. The work process includes the identification and management of risk commensurate to the work and the need for coordination with different groups or job activities.*
> *The Foreign Material Intrusion Risk posed by a SCOUT tool failure was not managed adequately under the work process for CEA coupling. In accordance with FME program requirements the Complex Tooling Inspection Checklist should have been used to identify and mitigate these risks. The RSS FME plan did not address complex tooling activities. A work order applicable to the RSS support tasks was not used, therefore, the associated planning inputs and FME program interfaces (work steps, briefing prompts, forms, etc.) normally included in work orders by work planners were not available to the crew.*

FPSC EXH No. 6
03/18/2024

ADMITTED

C3-588

4.0 Company Comments

On December 11, 2023 Commission Audit Staff provided a copy of the draft report to FPL to review for factual accuracy and identification of any material that might be considered confidential and proprietary. FPL had the opportunity to file a formal request for confidential classification in accordance with *Rule 25-22.006 (3), F.A.C.* Staff also invited FPL to submit written comments that each wanted included in the final report. FPL's comments appear in their entirety below.

Maria Jose Moncada
Assistant General Counsel
Florida Power & Light Company
700 Universe Boulevard
Juno Beach, FL 33408-0420
(561) 304-5795
(561) 691-7135 (Facsimile)
Email: maria.moncada@fpl.com

January 5, 2024

Carl Vinson
Florida Public Service Commission
Office of Auditing and Performance Analysis
2540 Shumard Oak Boulevard, Room 110
Tallahassee, FL 32399-0850

Re: Office of APA, Review of FPL Nuclear Plant Operations

Dear Mr. Vinson:

This letter is Florida Power & Light Company's ("FPL") response to the Office of Auditing and Performance Analysis's draft report regarding its Review of FPL Nuclear Plant Operations. FPL has reviewed the draft report and has numerous concerns, including fundamental disagreements with many of the statements, inferences and conclusions included therein.

In light of staff's representations of its intent to include the report with staff testimony that will be filed in the formal proceeding in Docket No. 20240001-EI, FPL will address its concerns and areas of disagreement and will raise any legal challenges associated with and in response to the report at the appropriate juncture in this proceeding.

FPL requests that this response letter be appended to the final report. Please feel free to contact me with any questions regarding this transmittal.

Sincerely,

Maria Jose Moncada

:21798490

C3-486

C3-589

FPSC EXH No. 7
03/18/2024

ADMITTED

UNITED STATES
NUCLEAR REGULATORY COMMISSION
REGION II
245 PEACHTREE CENTER AVENUE N.E., SUITE 1200
ATLANTA, GEORGIA 30303-1200

December 9, 2020

Mr. Don Moul
Executive Vice President, Nuclear Division and Chief Nuclear Officer
Florida Power & Light Company
Mail Stop: EX/JB
700 Universe Blvd.
Juno Beach, FL 33408

SUBJECT: TURKEY POINT UNITS 3 AND 4 – SPECIAL INSPECTION REPORT 05000250/2020050 AND 05000251/2020050

Dear Mr. Moul:

On August 26, 2020, the U.S. Nuclear Regulatory Commission (NRC) completed its initial assessment of three reactor trips, which occurred on August 17, 2020, August 19, 2020 and August 20, 2020 at Turkey Point Unit 3. The NRC's initial evaluation satisfied the criteria in NRC Management Directive (MD) 8.3, "NRC Incident Investigation Program," (Agencywide Documents Access and Management System (ADAMS) Accession No. ML18073A200), for conducting a special inspection. The basis for initiating this special inspection is further discussed in the Special Inspection Charter, which is included as Attachment B, to the enclosed report.

On October 30, 2020, the NRC completed its special inspection and the NRC inspection team discussed the results of this inspection with Mr. Michael Pearce, Site Vice President, and other members of your staff. The results of this inspection are documented in the enclosed report.

Six findings of very low safety significance (Green) are documented in this report. Five of these findings involved violations of NRC requirements. We are treating these violations as non-cited violations (NCVs) consistent with Section 2.3.2 of the Enforcement Policy.

If you contest the violations or the significance or severity of the violations documented in this inspection report, you should provide a response within 30 days of the date of this inspection report, with the basis for your denial, to the U.S. Nuclear Regulatory Commission, ATTN: Document Control Desk, Washington, DC 20555-0001; with copies to the Regional Administrator, Region II; the Director, Office of Enforcement; and the NRC Resident Inspector at Turkey Point.

If you disagree with a cross-cutting aspect assignment or a finding not associated with a regulatory requirement in this report, you should provide a response within 30 days of the date of this inspection report, with the basis for your disagreement, to the U.S. Nuclear Regulatory Commission, ATTN: Document Control Desk, Washington, DC 20555-0001; with copies to the Regional Administrator, Region II; and the NRC Resident Inspector at Turkey Point.

C3-487

FPSC EXH No. 7
D. Moul
03/18/2024

ADMITTED

This letter, its enclosure, and attachments, and your response (if any) will be made available for public inspection and copying at http://www.nrc.gov/reading-rm/adams.html and at the NRC Public Document Room in accordance with Title 10 of the *Code of Federal Regulations* 2.390, "Public Inspections, Exemptions, Requests for Withholding."

Sincerely,

/RA/

Randall A. Musser, Chief
Reactor Projects Branch 3
Division of Reactor Projects

Docket Nos. 05000250 and 05000251
License Nos. DPR-31 and DPR-41

Enclosure: As stated with attachments
cc w/ encl: Distribution via LISTSERV®

FPSC EXH No. 7
D. Moul
03/18/2024

ADMITTED

SUBJECT: TURKEY POINT UNITS 3 AND 4 – SPECIAL INSPECTION REPORT 05000250/2020050 AND 05000251/2020050 Dated December 9, 2020

DISTRIBUTION:
M. Kowal
S. Price
L. Gibson
H. Akhavannik
RidsNrrPMTurkeyPoint Resource
Public
RidsNrrDro Resource

ADAMS ACCESSION NUMBER: ML20344A126

X SUNSI Review		X Non-Sensitive ☐ Sensitive		X Publicly Available ☐ Non-Publicly Available	
OFFICE	DRP	DRP	DRP	DRP	DRP
NAME	J. Zeiler	J. Orr	A. Rosebrook	A. Wilson	L. Pressley
DATE	12/2/2020	12/2/2020	12/2/2020	12/3/2020	12/4/2020
OFFICE	DRP	DRS	DRS	DRS	DRS
NAME	R. Taylor	N. Lacy	R. Patterson	M. Riley	M. Schwieg
DATE	12/3/2020	12/2/2020	12/2/2020	12/2/2020	12/2/2020
OFFICE	DRP				
NAME	R. Musser				
DATE	12/9/2020				

OFFICIAL RECORD COPY

FPSC EXH No. 7
03/18/2024
ADMITTED

U.S. NUCLEAR REGULATORY COMMISSION
Inspection Report

Docket Numbers:	05000250 and 05000251
License Numbers:	DPR-31 and DPR-41
Report Numbers:	05000250/2020050 and 05000251/2020050
Enterprise Identifier:	I-2020-050-0003
Licensee:	Florida Power & Light Company
Facility:	Turkey Point Unit 3 & 4
Location:	Homestead, FL 33035
Inspection Dates:	August 31, 2020 to October 30, 2020
Inspectors:	N. Lacy, Operations Engineer D. Orr, Senior Resident Inspector - Turkey Point R. Patterson, Senior Reactor Inspector M. Riley, Reactor Inspector A. Rosebrook, Senior Reactor Analyst M. Schwieg, Reactor Inspector R. Taylor, Senior Project Engineer J. Zeiler, Senior Resident Inspector - Harris (Team Lead)
Approved By:	Randall A. Musser, Chief Reactor Projects Branch 3 Division of Reactor Projects

FPSC EXH No. 7
03/18/2024

ADMITTED

C3-593

TABLE OF CONTENTS

Summary (List of Violations) Page 3

.1 Description of Events and Reactive Inspection Basis Page 5

.3 Assessment of operator performance and crew decision making:
- .3.1 Event #1 Page 6
- .3.2 Event #2 Page 7
- .3.3 Event #3 Page 12

.4 Adequacy of JIT training and licensed operator startup certification training Page 13

.5 Evaluation of the extent of condition to the other operating crews Page 13

.6 Assessment of the licensee's response:
- .6.1 Event #1 Page 15
- .6.2 Event #2 Page 18
- .6.3 Event #3 Page 19

.7 Evaluation of authorizations for each restart:
- .7.1 Event #1 Page 20
- .7.2 Event #2 Page 20
- .7.3 Event #3 Page 21

.8 Assessment of schedule pressure and safety culture Page 21

.9 Evaluation of operating experience Page 22

.10 Evaluation equipment reliability and configuration control Page 22

Inspection Results:
- FIN 2020050-01, (Inadequate Design Analysis for CV-3-2011) Page 24
- NCV 2020050-02, (Failure to Manage Reactivity During Startup) Page 26
- NCV 2020050-03, (Failure to Monitor SRNI N-32) Page 29
- NCV 2020050-04, (Failure to Implement Corrective Actions for SRNI N-32) Page 31
- NCV 2020050-05, (Failure to Implement Procedures for Feedwater Control) Page 34
- NCV 2020050-06, (Failure to Establish Preventive Maintenance for SRNI) Page 36

Exit Meetings Page 39

Attachment A, Sequence of Events:
- Event #1 Page A-1
- Event #2 Page A-2
- Event #3 Page A-5

Attachment B, SIT Charter Page B-1

Attachment C, IMC 0609 Appendix M, Significance Determination Process Page C-1

Attachment D, Documents Reviewed Page D-1

Attachment E, Acronyms Page E-1

C3-491

FPSC EXH No. 7
03/18/2024

ADMITTED

C3-594

SUMMARY

The U.S. Nuclear Regulatory Commission (NRC) continued monitoring the licensee's performance by conducting a special inspection at Turkey Point Units 3 and 4, in accordance with the Reactor Oversight Process. The Reactor Oversight Process is the NRC's program for overseeing the safe operation of commercial nuclear power reactors. Refer to https://www.nrc.gov/reactors/operating/oversight.html for more information.

List of Findings and Violations

Inadequate Design Analysis of Automatic Turbine Runback Actuation Coincident with Inadvertent Opening of CV-3-2011			
Cornerstone	Significance	Cross-Cutting Aspect	Report Section
Initiating Events	Green FIN 05000250/2020050-01 Open/Closed	None (NPP)	93812
A self-revealed Green Finding was identified for the licensee's failure to implement adequate design change controls associated with the 2012 Unit 3 extended power uprate (EPU) modification that added an automatic medium turbine runback coincident with the opening of the low-pressure feedwater heater bypass valve CV-3-2011. Specifically, the licensee failed to implement procedure EN-AA-205-1100, "Design Change Packages," and to evaluate the effect of the valve opening without a valid demand signal in the Failure Modes and Effects Analysis (FMEA) and to adequately review the calculational design inputs and assumptions required by design change procedures.			

Failure to Adequately Manage Reactivity During Startup			
Cornerstone	Significance	Cross-Cutting Aspect	Report Section
Barrier Integrity / Initiating Events	Green NCV 05000250/2020050-02 Open/Closed	[H.4] - Teamwork	93812
The NRC identified a Green finding and associated non-cited violation (NCV) of Unit 3 Technical Specification (TS) 6.8.1, "Procedures and Programs," for the failure to follow procedure 3-GOP-301, "Hot Standby to Power Operation," which provided instructions for reactor startup. Specifically, the operating crew failed to implement 3-GOP-301 which resulted in an excessive reactivity addition and caused an RPS trip which automatically shut down the reactor.			

Failure to Adequately Monitor Source Range Nuclear Instrument (SRNI) N-32			
Cornerstone	Significance	Cross-Cutting Aspect	Report Section
Mitigating Systems	Green NCV 05000250/2020050-03 Open/Closed	[H.11] - Challenge the Unknown	93812
The NRC Identified a Green NCV of TS 3.3.1, "Instrumentation," for not entering the Limiting Condition for Operation (LCO) and completing the action statement for one of the required SRNI Hi Flux Trip channels being inoperable in a mode where it was required. Specifically, the licensee conducted a reactor startup, and entered Mode 2 with the SRNI N32 and its associated SR High Flux RPS trip channel inoperable.			

C3-492

FPSC EXH No. 7
03/18/2024
ADMITTED

C3-595

Failure to Implement Adequate Corrective Action for Degraded Source Range Nuclear Instrument (SRNI) N32 Condition			
Cornerstone	Significance	Cross-Cutting Aspect	Report Section
Mitigating Systems	Green NCV 05000250/2020050-04 Open/Closed	[P.2] - Evaluation	93812
The NRC identified a Green NCV of 10 CFR 50, Appendix B, Criterion XVI, “Corrective Action,” for failure to identify and correct a condition adverse to quality related to the SRNI N32 and its associated RPS SR high flux trip channel during the post trip review of the August 19, 2020, trip which resulted in a subsequent reactor startup on August 20, 2020, with an inoperable RPS trip channel.			

Failure to Implement Procedures for Feedwater Recirculation Control in Automatic			
Cornerstone	Significance	Cross-Cutting Aspect	Report Section
Initiating Events	Green NCV 05000250,05000251/2020050-05 Open/Closed	None (NPP)	93812
A self-revealed Green NCV of TS 6.8.1, “Procedures and Programs,” was identified for the licensee’s failure to establish, implement, and maintain adequate procedures for properly controlling the configuration of the Master Controller for the steam generator feedwater pump (SGFP) recirculation valves during Unit 3 plant startup.			

Failure to Develop and Establish a Preventive Maintenance Schedule to Measure Source Range Nuclear Instrument (SRNI) Detector Performance			
Cornerstone	Significance	Cross-Cutting Aspect	Report Section
Mitigating Systems	Green NCV 05000250,05000251/2020050-06 Open/Closed	[P.5] - Operating Experience	93812
An NRC-identified Green NCV of TS 6.8.1, “Procedures and Programs,” was identified for the licensee’s failure to develop and establish a preventive maintenance schedule to perform source range nuclear instruments (SRNI) detector baseline and trending tests.			

Additional Tracking Items

None.

C3-493

FPSC EXH No. 7
03/18/2024
INSPECTION SCOPES ADMITTED

C3-596

Inspections were conducted using the appropriate portions of the inspection procedure (IP) in effect at the beginning of the inspection unless otherwise noted. Currently approved IPs with their attached revision histories are located on the public website at http://www.nrc.gov/reading-rm/doc-collections/insp-manual/inspection-procedure/index.html. Samples were declared complete when the IP requirements most appropriate to the inspection activity were met consistent with Inspection Manual Chapter (IMC) 2515, "Light-Water Reactor Inspection Program - Operations Phase." The inspectors reviewed selected procedures and records, observed activities, and interviewed personnel to assess licensee performance and compliance with Commission rules and regulations, license conditions, site procedures, and standards. Starting on March 20, 2020, in response to the National Emergency declared by the President of the United States on the public health risks of the coronavirus (COVID-19), inspectors were directed to begin telework and to remotely access licensee information using available technology. During this time the inspectors performed site visits as local COVID-19 conditions permitted. In some cases, portions of the IP were completed remotely and on site. A significant portion of IP 93812 was performed on site during the week of August 31, 2020.

OTHER ACTIVITIES – TEMPORARY INSTRUCTIONS, INFREQUENT AND ABNORMAL

93812 - Special Inspection Team (1 Sample)

In accordance with the attached Special Inspection Team (SIT) Charter, the inspection team conducted inspection activities associated with a review of three separate reactor trip events that occurred at Turkey Point Unit 3 on August 17, August 19, and August 20, 2020.

.1 Description of Events and Reactive Inspection Basis

During the week of August 17, 2020, Turkey Point Unit 3 experienced three reactor trips, one of which was automatically initiated by the reactor protection system (RPS) and two were the result of plant operator actions to manually trip the reactor:

1) The first trip, manually initiated by plant operators, occurred on August 17, 2020, at 2111 from approximately 91 percent power in response to rising steam generator (SG) water levels that approached the automatic turbine trip setpoint.

2) The second trip was automatically initiated by the plant's RPS and occurred on August 19, 2020, at 1324. Specifically, the source range nuclear instrument (SRNI), N31, sensed a high neutron flux condition and initiated the trip during reactor startup.

3) The third trip, manually initiated by plant operators, occurred on August 20, 2020, at 2358 from approximately 34 percent power in response to the loss of the single operating 3B steam generator feedwater pump (SGFP).

NRC Management Directive (MD) 8.3, "NRC Incident Investigation Program," and IMC 0309, "Reactive Inspection Decision Basis for Reactors," was used to evaluate the level of NRC response for the three reactor trips that occurred at Turkey Point Unit 3 during the week of August 17, 2020. Based on the deterministic criteria detailed in MD 8.3 and risk insights related to the three events, NRC Region II management determined that the appropriate level of NRC response was to conduct a Special Inspection. A SIT was chartered to review the causes of the three events and Turkey Point's organizational and operator responses to these events.

C3-494

FPSC EXH No. 7
03/18/2024
ADMITTED

C3-597

.2 Review the circumstances leading up to the events on August 17, August 19, and August 20, 2020, and develop a Sequence of Events leading up to the incidents and details of the operator actions in response to events.

The Special Inspection (SI) conducted a detailed review of the three events; the August 17, 2020, manual reactor trip (hereafter, referred to as "Event #1"), the August 19, 2020, automatic reactor trip (hereafter, referred to as "Event #2"), and the August 20, 2020, manual reactor trip (hereafter, referred to as "Event #3"). The team gathered information from operations logs, post-trip analyses, plant computer data systems, licensee cause analyses, sequence of events printouts, condition reports, and interviews to develop a timeline of the three events. See Attachment A for the Sequence of Events for Event #1, Event #2, and Event #3.

.3 For each event, assess crew operator performance and crew decision making, including their adherence to procedures, expected roles and responsibilities, including reactivity management by the operators, reactivity management plans provided by nuclear engineering, the command and control function associated with reactivity manipulations, the use of procedures, log keeping, and overall communications.

.3.1 Inspection Activities Related Specifically to Event #1:

The team reviewed plant operating parameter data from the event, control room logs and procedures, the completed Post Trip Report (PTR), action requests (ARs) generated for the problems identified during the event, and interviewed members of the control room operations crew that were on-shift during Event #1, as well as selected operations personnel and engineering staff directly involved in evaluating the post-event issues.

On August 17, 2020, with the plant operating at 100 percent power, a "Medium" turbine runback to 85 percent turbine power was automatically initiated as a result of the spurious opening of the low-pressure feedwater heater bypass valve (CV-3-2011). The operations crew diagnosed the condition due to expected control room annunciation alarms that alerted the operators that both valve CV-3-2011 had repositioned open and a turbine runback had initiated. In addition, the control room valve controller for CV-3-2011 position indication lights confirmed that the valve was in the open position. The operators appropriately responded to the event using off-normal operating procedure 3-ONOP-089, "Turbine Runback." While implementing the actions in this procedure, the operations crew observed that the turbine did not runback to and remain at the expected 85 percent setpoint. Instead, after approximately 30 seconds, turbine power reduced to approximately 87 percent turbine power and then stopped, indicating the runback was completed. Shortly thereafter, the runback again initiated down to approximately 85 percent turbine power. Over the next approximately 60 seconds, the turbine control system (TCS) runback circuitry armed and disarmed multiple times, cycling around 82 percent to 85 percent turbine power setpoint. The team noted that the repeated cycling created operator distractions and eventually led to the Unit Supervisor (US) directing the operators to take manual control of the TCS to mitigate the cycling. During this period of managing the unexpected turbine runback operation, the operators were distracted from monitoring the increasing SG levels, resulting in the Shift Manager (SM) identifying and alerting the operators of rising SG levels (approximately 60-65 percent level at the time), especially in the 3B and 3C SGs.

C3-495

FPSC EXH No. 7
03/18/2024
ADMITTED

C3-598

Subsequently, operators took manual level control of the 3C SG feedwater regulating valve, to arrest the rising level. Operator manual actions were unsuccessful in lowering level and once the 3C SG level reached approximately 78 percent, the SM directed a manual reactor trip due to the potential to challenge the automatic reactor trip that occurs at the 80 percent level. The time from initiation of the transient with the spurious opening of CV-3-2011 until insertion of the manual reactor trip was approximately 2.5 minutes. The team determined that based on the increasing SG level conditions, the operator actions to manually trip the reactor were appropriate.

Following the manual reactor trip, the operators entered emergency operating procedure 3-EOP-E-0, “Reactor Trip or Safety Injection.” While performing the immediate operator actions associated with procedure 3-EOP-E-0, the operators identified that the position indication light for the 3B moisture separator reheater (MSR) main steam stop valve (MOV-3-1432), was not illuminated and the valve could not be verified closed. This valve gets an automatic closure signal as part of a turbine trip actuation. After attempts to manually close the valve from the control room switch did not result in a positive indication that the valve was closed, the operators implemented the required procedural actions to close the upstream main steam isolation valves (MSIVs) to isolate all sources of steam from the SGs in order to prevent a potential uncontrolled reactor coolant system (RCS) cooldown. No further complications were encountered while completing the remaining actions in 3-EOP-E-0 and the operators entered procedure 3-EOP-ES-0.1, “Reactor Trip Response,” in order to stabilize and control the plant following a reactor trip without a safety injection present. The plant was stabilized in Mode 3 at normal operating temperature and pressure without any further noteworthy plant complications. The team determined that the operators took appropriate actions as required by the procedure when faced with the uncertainty of the position for valve MOV-3-1432 and closed the MSIVs as required.

Following the event, the licensee initiated ARs and related work orders (WOs) to address the issues identified during the event. These ARs included the following:

- AR 2365707, Indicating lights on valve MOV-3-1432 lost during reactor trip
- AR 2365708, Valve CV-3-2011 failed open
- AR 2365714, 3B and 3C feedwater regulating valves were slow to respond during turbine runback
- AR 2365716, Unit 3 reactor manually tripped
- AR 2365717, Unexpected TCS response during turbine runback
- AR 2365722, Reheat intercept valve 3-10-012 indicates bad indication on TCS panel
- AR 2365723, Reheat stop valve 3-10-015 indicates bad indication on TCS panel

The team determined that appropriate actions were initiated to document problems and issues identified during the event.

.3.2 Inspection Activities Related Specifically to Event #2:

The Turkey Point Unit 3 main control room operating crew members who were present during the startup and subsequent automatic reactor trip on high source range (SR) counts were interviewed with two NRC team members present. Additionally, the reactor engineer present during the startup was also interviewed.

C3-496

FPSC EXH No. 7
03/18/2024
ADMITTED

C3-599

While each interviewee had a different perspective during the event, their answers were provided with openness and an obvious effort to meet the goals of the interviewers. They described the event in a consistent manner with enough detail which allowed the NRC to gain insight into the details of Event #2.

On August 19, 2020, operators were conducting a reactor startup of Turkey Point Unit 3 after experiencing a manual reactor trip on August 17, 2020. The operators were performing procedure 3-GOP-301, "Hot Standby to Power Operation," and conducting a normal plant startup using control rods. The operating crew consisted of a three-person reactivity team, including the reactor Operator at the Controls (OATC), a peer checker, and one reactivity Senior Reactor Operator (SRO). The responsibility of the reactivity team was managing reactivity during the startup. The crew also had a Unit 3 Reactor Operator (RO), with overall responsibility of Unit 3 operations, and a third RO, who was providing administrative support (i.e., log keeping, plant announcements, etc.). A US was responsible for the overall Unit 3 activities and a SM was overseeing all crew activities. Also present during the startup was a Reactor Engineer who was supporting the startup by plotting the SRNI inverse count rate (1/M) plot, and a training department observer. Additionally, two Assistant Operations Managers and the Site Vice President (SVP) were present in the main control room observing the startup.

After declaring the reactor critical at 1316 hours, the OATC was given the order from the reactivity SRO to perform Step 5.21 of procedure 3-GOP-301 to “raise power to 10^{-8} amps and do not exceed a 1.0 decade per minute (dpm) startup rate (SUR).” However, the OATC did not announce his intentions to the rest of the reactivity team or crew as to how he intended to carry out the step. The OATC intended to perform a continuous rod withdrawal of control rod group D until a 0.7 dpm SUR was achieved and stop. His rationale for 0.7 dpm was that with a steady state 0.7 dpm SUR power would not double in less than a minute. Had the OATC announced his intentions both the SM and US stated they would have recommended not taking that action and withdrawing rods in steps and establishing a lower SUR of 0.5 dpm. The OATC withdrew control bank D for 45 seconds, which was 53 steps, until rod motion was stopped when a valid SR Hi Flux RPS trip signal was generated and the reactor automatically tripped. The SUR was greater than 1.0 dpm for the final 25 seconds of the 45 second rod pull and reached a maximum indicated value of 3.0 dpm, with an instantaneous SUR of 7.4 dpm at the time of the trip.

No member of the operating crew, nor any of the observers, recognized that the OATC had exceeded the SUR limits of the procedure, or that the plant was approaching an RPS trip threshold, and that the OATC was withdrawing rods continuously. Approximately 20 seconds before the trip, the SR Block Permissive (P-6) came in as expected and the third RO had been directed to take the procedural actions to deenergize SR High Volts. The third RO announced the expected alarm and had only just opened the procedure before the trip.

While the operators had attended Just-in-Time (JIT) training there were missed opportunities and shortfalls in their performance as related to “Conduct of Operations” which culminated in the failure to follow procedure and exceeding the allowed SUR of 1.0 dpm which ultimately led to the automatic reactor trip. The team determined that the following were contributing factors to the human performance errors identified:

C3-497

FPSC EXH No. 7
03/18/2024
ADMITTED

C3-600

Experience Level of the Crew: Two of the three members of the reactivity team and the US had never conducted a reactor startup using control rods to pull to criticality on the plant. It was known that this was the first startup for the reactivity SRO since he had recently qualified, but it was not recognized that the OATC, a qualified RO for 8 years, nor the US had also never performed this evolution in the plant. The SM thought he had paired an experienced RO with an inexperienced SRO.

- JIT Training: Required JIT training was conducted for the start-up crew the afternoon prior to the startup. All members of the crew attended, with exception of the Unit 3 RO and the Reactor Engineer. A table-top walkthrough of the startup procedure was performed emphasizing 3-way communications. However, simulator training was only performed for the turbine synchronization to the grid and not the startup and power ascension. The training crew was also unaware that the OATC had never performed this evolution in the plant.

- Operator Fundamentals breakdowns: The OATC never informed the reactivity team of his startup intentions or which key plant parameters to monitor and at what point to stop withdrawing control rods. Thus, the operating crew did not have an opportunity to coach the OATC or to provide backup when the SUR exceeded the intended 0.7 dpm. Also, operators did not follow fundamental principles to ensure they understood the expected plant response for an action, (i.e., take the action, observe plant response, and stop if expected plant response was not achieved). The OATC did not know how much rod motion was needed to establish a steady 0.7 dpm SUR and did not recognize that not “seeing” a 0.7 dpm for such an extended rod withdrawal was an abnormal system response.
  Note: The indicated SUR was well above 1.0, based on review of plant computer historical data after the event, however, none of the crew noticed this at the time.

- Oversight and Control of the Startup Evolution: The reactivity team provided no meaningful assistance to the OATC during the power ascension, nor did the US or SM. Key reactor plant indications were displayed on the ROs vertical panel. Additionally, the SROs had monitoring capability digitally displayed in other areas of the control room. The reactivity SRO and the US were in direct line of site of nuclear instrumentation and the OATC’s hand on the rod control switch, yet did not notice the excessive startup rate or appropriately stop the withdrawal of control rods. Audio of SR counts and rod motion was energized and loud enough to be heard, and plant computer data was available in multiple locations. Additionally, the action to deenergize SR high volts after the P-6 Permissive light came in was delegated to the third RO. If this action had been assigned to the OATC as normally performed, the OATC would have had to stop withdrawing rods when P-6 was announced while SUR was approximately 1.0. Instead the OATC continued withdrawing control rods during this time limited evolution.

- Confusing Indications: Prior to criticality during the startup, it was noted that SRNI channels N31 and N32 were deviating by approximately 1.0 decade. As the startup progressed this deviation continued to increase. During the continuous rod withdrawal, plant computer data also showed that SRNI N32 SUR was also lagging the other three SUR indications (i.e., intermediate range nuclear instruments (IRNI) channels N35 and N36 and SRNI N31). At the time of the trip, SUR was 3.0 dpm on three channels and 1.5 dpm on SRNI N32. It was possible that some operators may have been confused by this or focused on this incorrect indication.

C3-498

FPSC EXH No. 7
03/18/2024
ADMITTED

C3-601

Distractions: The P-6 permissive coming in shifted the focus of many operations crew away from key parameters. This alarm and the actions to secure SR high volts was occurring adjacent to the RO's panel, and was happening up until the trip, which may have shifted the focus of the OATC.

The team determined that numerous plant procedures were not adhered to during this event, including the following:

1. Procedure 3-GOP-301, "Hot Standby to Power Operation," revision (Rev.) 53, Step 5.21, required operators to establish a steady state SUR of 1.0 dpm or less while raising power to and stabilizing at 10^{-8} amps on IRNI. In addition, "Precautions and Limitations," Step 4.14, stated the SUR should not be permitted to exceed a steady state value of 1.0 dpm below the Point of Adding Heat (POAH). Contrary to the procedure, operators failed to follow Step 5.21 and continuously withdrew control bank D from 83 steps to 136 steps over a 45 second period, resulting in a SUR in excess of 1.0 dpm for approximately the last 25 seconds of the rod pull on both IRNI and SRNI reaching a maximum displayed value of 3.0 dpm. This action added excessive reactivity which resulted in an automatic reactor trip on SR high flux of 10^{5} counts per second (cps).

2. Procedure 3-GOP-301, caution statement prior to Step 5.16.3 stated, "Excessive boration/dilution rates and rod motion shall be avoided." Additionally, procedure OP-AA-103-1000, "Reactivity Management," Rev. 13, Section 3.7, caution statement stated, "Inadequate reactivity control has the potential to cause core damage. As a result, licensed operators are responsible for conservative, deliberate reactivity control, in accordance with approved procedures, to prevent challenging the integrity of the fuel cladding or the RCS pressure boundary." Contrary to the procedure, the operating crew failed to adequately control reactivity additions and the OATC performed an excessive continuous rod withdrawal of 53 steps for 45 seconds, which resulted in a SUR greater than 3 dpm and a SR high flux RPS trip. This was a reactivity addition of 270 percent mille (pcm) which was 130 pcm in excess of what was necessary to achieve a 1.0 dpm SUR.

3. Procedure OP-AA-100-1000, "Conduct of Operations," Rev. 25, Attachment 5, Section 3.2, stated the OATC was responsible for monitoring for the effects of primary reactivity manipulations on the unit (control rods, boration, dilution and TCS adjustments). Contrary to the procedure, the OATC did not adequately monitor key reactor parameters for the effects of continuously withdrawing the control rods while raising power to 10^{-8} amps. Specifically, the OATC did not recognize plant response (SRNIs, IRNIs, and associated SURs) was not as expected and outside procedural limits and did not appropriately stop withdrawing control rods. The OATC was attempting to withdraw control rods when the RPS actuation occurred.

4. Procedure OP-AA-100-1000, "Conduct of Operations," Rev. 25, Attachment 4, Section 3.3, stated that the Command and Control SRO, or US, was expected to stay in a position of oversight for all control room activities, remain fully involved, and assert authority when standards were not being maintained. Contrary to the procedure, the US did not assert authority to ensure the OATC withdrawing the control rods maintained a SUR less than 1.0 dpm. Specifically, no communications

C3-499

FPSC EXH No. 7
03/18/2024
ADMITTED

C3-602

were conducted to understand how the OATC intended to withdraw control rods and the US did not ensure how the reactivity team, (Reactivity SRO, OATC and RO peer checker), intended to adequately monitor key parameters during the power increase to 10^{-8} amps.

5. Procedure OP-AA-100-1000, “Conduct of Operations,” Rev. 25, Attachment 4, Section 3.1, stated that licensed operators were responsible for complying with the conditions of their license and intervening in system or component operation as necessary. Contrary to the procedure, the Reactivity SRO, OATC peer checker, US, Unit 3 RO, Administrative third RO, and SM each had an opportunity to recognize and respond to the conditions listed below:

    1) The OATC was continuously withdrawing control rods for 45 seconds; and
    2) Key plant parameters, which were clearly displayed in the control room, were greater than procedural limits and rapidly approaching the RPS trip limit.

6. Procedure OP-AA-103-1000, “Reactivity Management,” Rev. 13, stated that no significant discrepancies exist between reactor power level indicators and/or indirect power indications such as turbine first stage pressure. If significant discrepancies exist, power ascension shall cease until the situation was investigated. Approval of the Operations Director/Manager was required to resume power ascension. Contrary to the procedure, the reactor startup was continued with a deviation between SRNI channels N31 and N32 with increasing magnitude as the startup progressed. The OATC and his peer checker identified the deviation as a concern to the Reactivity SRO who then discussed the concern with the US and SM. The SROs determined the current deviation to be acceptable and directed the OATC and his peer checker to continue the startup and monitor N32.

The team also reviewed the crew’s decision making process for continuing the startup with a degraded SRNI N32 on August 19, 2020, the post trip review of the August 19, 2020 trip, and decision-making process associated with the licensee’s decision to startup on August 20, 2020, with SRNI N32 in a known degraded state.

In each of these cases, licensee staff and management did not adequately evaluate the operability of the SRNI and additionally, its associated RPS SR High Flux Trip Function. In each case, the operability of the instrument was performed qualitatively, and available quantitative information was not considered. The reviews appeared to focus on the instrumentation and display function as opposed to the operability of the RPS trip function. This RPS trip function was challenged during the August 19, 2020, event and the SRNI N32 channel was demonstrated to not to have been able to perform its safety function. The post trip review and Onsite Review Group’s (ORG) restart readiness process failed to identify this and authorized the August 20, 2020, startup to proceed.

See NCV 05000250/2020050-02, “Failure to Adequately Manage Reactivity During Startup,” NCV 05000250/2020050-03, “Failure to Adequately Monitor SRNI N-32,” and NCV 05000250/2020050-04, “Failure to Implement Adequate Corrective Action for Degraded SRNI N32 Condition,” in the inspection results for additional details.

C3-500

FPSC EXH No. 7
03/18/2024
ADMITTED

C3-603

.3.3 Inspection Activities Related Specifically to Event #3:

The team reviewed data for plant operating parameters, reviewed station logs and procedures, interviewed the operating crew on duty at the time of the event and engineering personnel.

3.3.1 Manual Reactor Trip

The team determined that the operating crew took appropriate actions to perform a manual reactor trip and manual closure of MSIVs in response to conditions that resulted from the incorrect SGFP recirculation valves alignment. The reactor trip was required after the trip of the only running SGFP. The MSIV closure was required by procedure EOP-ES-0.1, “Reactor Trip Response,” to limit the cooldown due to excessive steam flow. Both actions were the result of procedural response requirements.

3.3.2 Control Room Alarm Response

Leading up to Event #3 the Unit 3 operating crew received two alarms in the main control room on August 20, 2020. The first alarm was the Distributed Control System (DCS) trouble alarm. The operating crew followed the alarm response procedure (ARP), 3-ARP-097-CR.D, “Control Room Response – Panel D,” and navigated to procedure Step A to the DCS secondary trouble page. This page identified alarm conditions for the 3A/3B/3C/3D MSR, 3A reheater drain tank (RHDT), and 3A/3B heater drain tank (HDT) controllers given they were in manual instead of automatic. The operators took appropriate actions to restore level control valves for 3A/3B/3C/3D MSR, 3A RHDT, and 3A/3B HDT to automatic control on DCS to support closing the main generator output breakers and synchronizing to the grid. However, the operating crew failed to navigate to Step B of the procedure as they believed Step A had corrected the alarm conditions. The DCS secondary trouble display panel did not list the recirculation valves master controller, instead, this page listed the individual recirculation valve controllers. Because the individual valve controllers were in Automatic, they were not alarming. The team determined that had the recirculation valves master controller been included on the DCS secondary trouble page in Step A, operators may have recognized that the recirculation valves master controller was not in automatic. The team determined the failure to navigate to Step B, was a missed opportunity, however this was not the primary cause of the failure to configure the recirculation valves master controller in automatic during the plant startup. The second alarm was the SG C Level Deviation / Controller Trouble alarm. The team determined the operating crew took proper actions and followed the ARP to open Feedwater Bypass Valve, (FCV-3-499), and take manual control of the feedwater controller to maintain SG level.

3.3.3 Master Recirculation Controller in Manual Recovery

When the operating crew discovered the SGFP recirculation valves controller was in manual at 34 percent reactor power, the operating crew closed the recirculation valves with the master controller. This action closed all three recirculation valves at the same time. When the valves were closed from 100 percent demand to 60 percent demand, the feedwater pump tripped on low suction pressure. The operating crew should have more appropriately closed the recirculation valves in a controlled manner using each of the valve controllers. A controlled closing of the three recirculation valves may have potentially maintained SGFP suction pressure and prevented a trip on low suction

C3-501

FPSC EXH No. 7
03/18/2024
ADMITTED

C3-604

However, the team noted the time pressure created by the lowering SG water level. When the operating crew discovered the master controller was in manual, the C SG water level was already at 40 percent and lowering. This time pressure may have impacted the operating crew recovery actions by choosing not to close the SGFP recirculation valves in a more controlled manner.

.4 Review the adequacy of JIT training and licensed operator startup certification training as it relates to reactivity control.

.4.1 Inspection Activities Related Specifically to Event #1:

There was no JIT training with Event #1 as it occurred from full power operations.

.4.2 Inspection Activities Related Specifically to Event #2:

The team interviewed members of the training staff that conducted the JIT training for the crew that conducted the startup associated with Event #2, and reviewed training procedures related to the conduct of the JIT training. The team also observed a startup on the simulator utilizing the training staff and discussed how training was conducted related to a reactor startup and reactivity control.

While the reactor restart JIT training met training requirements there was a missed opportunity to reinforce conservative operation of the control rods after the reactor was critical. This observation was based on the use of a tabletop discussion for the reactor startup portion of the JIT training. The remaining JIT training to roll the turbine and synchronize the generator to the grid was conducted in the simulator versus the use of tabletop discussions.

.4.3 Inspection Activities Related Specifically to Event #3:

The team interviewed the training staff that conducted the JIT training for the crew that conducted the startup associated with Event #3. The team determined that adequate JIT training was provided to these operators. The crew members attended JIT training on the July 20, 2020 for startup and power ascension. While the JIT power ascension training did not cover any issues with the feedwater regulating valve response or the closure of valve CV-3-2011 that occurred with Event #1, these issues were not the direct cause of Event #3. This manual trip was initiated by the loss of the only running SGFP when the operators attempted a fast closure of the SGFP recirculation valves.

.5 Evaluate the extent of condition for identified issues with respect to the other operating crews.

.5.1 Inspection Activities Related Specifically to Event #1:

The team assessed the extent of condition for the identified issues associated with Event #1 and interviewed other crews and operations personnel knowledgeable with the circumstances associated with the event. None of the operators interviewed either from Event #1 or from other crews recalled the unusual turbine TCS arming/disarming or slower than expected SG level control system responses during simulator training for scenarios involving the spurious opening of CV-3-2011 coincident with a turbine Medium Runback. The team requested and reviewed simulator data involving the simulator

C3-502

FPSC EXH No. 7
03/18/2024
ADMITTED

C3-605

Despite this specific transient, which confirmed that there were significant transient response differences between the simulator and the actual plant. The simulator response did not exhibit either the TCS runback anomaly or the unexpected rise in SG levels. Particularly noteworthy was the difference in feedwater flows. Unlike the simulator, feedwater flows remained high throughout the actual plant transient indicating a slow response of the feedwater regulating valves resulting in the higher SG levels. The team determined that these differences contributed to the operators not anticipating the abnormal plant responses and a weakness in monitoring rising SG levels. Additionally, the equipment challenges faced by the operators during this event would have been common to all the operators based on the nature of the issues. While other crews may have taken action earlier to place the SG feedwater regulating valves in manual in an attempt to control SG water level had they recognized the abnormally rising levels earlier, it was clear that simulator training had not adequately prepared the operators with the understanding and expectations that added focus and attention to unexpected SG levels would be necessary for such a transient. As interim corrective actions, operations management issued a Night Order for all the operators explaining the circumstances associated with the event and the learnings related to the issues identified with the TCS runback logic and SG level controls. The team noted that the licensee is performing a root cause of the event which included understanding the anomaly associated with TCS arming and disarming multiple times.

.5.2 Inspection Activities Related Specifically to Event #2:

The team interviewed a sample of operators from other crews, managers, and training department personnel, to assess the extent of condition for the performance issues that contributed to the automatic trip on August 19, 2020. Interviews focused on command and control of reactor startups, and how the operators performed and controlled 3-GOP-301, "Hot Standby to Power Operation," procedure step 5.21 that stated, “establish a steady state startup rate of 1.0 dpm or less to 10^{-8} amps and stabilize reactor power at 10^{-8} amps on the Intermediate Range (IR) Monitors.” The team determined that one of the major contributors to this event was the experience level of the crew. Two of the three members of the reactivity team and the US had never conducted a reactor startup using control rods rather than boron dilution to establish a steady state SUR less than 1.0 dpm using control rods and then leveling at 10^{-8} amps in the IR.

It was known that this was the first startup for the reactivity SRO since he had recently qualified, but it was not recognized that the OATC, a qualified RO for 8 years, nor the US never performed this evolution on the plant. The SM assumed the crew makeup consisted of an experienced RO with an inexperienced SRO. This also contributed to the level of oversight given to the OATC, since the other team members erroneously assumed the OATC was the most experienced and did not closely question or monitor the OATC actions. During the JIT training, the trainer asked if anyone on the crew had not performed the evolution before, but only the reactivity SRO was identified as a first-time performer.

The team determined the issue was specific to this crew. Given interviews with the training department and other operators there was no evidence of any training lapses. Interviews revealed that operators most likely would not have performed this evolution in the manner the OATC did on August 19, 2020, and furthermore, it was not trained to be

C3-503

FPSC EXH No. 7
03/18/2024

ADMITTED

C3-606

done in this manner. The expectations of the crew backing each other up and independently monitoring plant parameters were also clear to all personnel interviewed.

The team also interviewed several other reactor engineers and management with regards to the reactivity management procedure implementation and the roles and responsibilities of the reactor engineer during reactor startup and their insights about the SRNI N32 engineering evaluation and historical performance. The team determined that the reactor engineer was following current station procedures and guidance by only plotting one channel of SRNI on the 1/M plot.

.5.3 Inspection Activities Related Specifically to Event #3:

The team interviewed a sample of operating crews, managers, and training department personnel, to assess the extent of condition for the performance issues that contributed to the manual scram on August 20, 2020. Procedure 3-GOP-301, "Hot Standby to Power Operation," was determined to be inadequate due to the lack of positive configuration control of feedwater control systems. Specifically, the procedure did not verify the proper configuration of the SGFP recirculation system to support power ascension. The licensee took corrective actions to update procedure 3-GOP-301 to add specific actions for verifying the recirculation valves were closed and the master controller was in automatic during power ascension.

Likewise, ARP, 3/4-ARP-097-CR.D, "Control Room Response – Panel D," did not have an operator action to ensure Secondary Controls Auto/Manual controllers were in the required position to support current plant status. The ARP was inadequate. The licensee took interim actions to provide information via a Night Order that described the actual operation of the DCS secondary trouble screen including inputs, and what caused the alarms to come in, and how to respond using procedure 3/4-ARP-097-CR.D.

.6 Review and assess the effectiveness of the licensee's response to these events and corrective actions taken to date.

.6.1 Inspection Activities Related Specifically to Event #1:

The licensee prepared a PTR for Event #1, and entered the issues identified into the corrective action program (CAP), initiated a root cause evaluation, and planned to issue a licensee event report (LER) for the event. At the time of this inspection, only the PTR was completed and available for review.

.6.1.1 Spurious Opening of CV-3-2011, Low Pressure Feedwater Bypass Control Valve

Following the August 17, 2020, Unit 3 manual trip event, the licensee initiated AR 2365708 to address the spurious opening of CV-3-2011. In addition, WO 40737414 was initiated to perform immediate troubleshooting to determine the cause for why CV-3-2011 opened and to implement repairs. The team reviewed the results of the troubleshooting activities which identified that one of the two pressure switches (i.e., PS-3-2011) that automatically opened CV-3-2011 was faulty and required replacement. Maintenance personnel identified evidence of water intrusion into the pressure switch housing. The licensee suspected that the heavy rain event on the day of the trip allowed water to enter the pressure switch housing due to a degraded gasket. This water intrusion provided a false signal to the air actuator solenoid of CV-3-2011

C3-504

FPSC EXH No. 7
03/18/2024
ADMITTED

C3-607

opened the valve without a valid demand signal. Given that Unit 4 turbine building, was also open to the environment, and had two similar pressure switches that control the opening of a similar valve CV-4-2011, the licensee's immediate extent of condition, inspected Unit 4 for potential water intrusion impact. No similar water intrusion problems were identified. In addition, the licensee planned further extent of condition actions to inspect other vulnerable Unit 3 and Unit 4 turbine building equipment for potential water intrusion. The team determined that appropriate licensee actions were taken or were planned to identify the cause of the spurious opening of CV-3-2011 and to address extent of condition.

.6.1.2 Loss of Position Indication of MOV-3-1432, 3B MSR Main Steam Stop Valve

The team reviewed the licensee's actions to address the loss of position indication on MOV-3-1432, the 3B MSR Main Steam Stop Valve, that required the operators to close the MSIVs following the manual reactor trip to isolate all sources of steam from the SGs in order to prevent a potential excessive RCS cooldown rate. The licensee initiated AR 2365717 to address the issue and conducted troubleshooting and repair under WO 40737415. The team reviewed the completed WO which identified a tripped valve motor thermal overload relay on the C phase that de-energized the valve motor operator upon receipt of the automatic close signal and prevented the valve from closing. A broken wire at a terminal lug connection in the valve control circuit was found and repaired. This broken wire and tripped relay also explained why the valve position indication was lost during the event. The circumstances on how the wire connection could have broken and when it occurred could not be readily identified. Pictures of the terminals and broken connection did not indicate any obvious damage attributed to poor termination or existing wiring stresses. The licensee planned to conduct further evaluation of the issue under AR 2365717. The team determined the licensee's immediate and planned corrective actions to address the issue were appropriate.

.6.1.3 Abnormal Turbine Control System Runback Oscillations

As discussed in Sections .3.1 and .5.1 of this report, the TCS runback system did not operate as expected during Event #1. The operations crew observed that the turbine did not runback to and remain at the expected 85 percent setpoint. Instead, after approximately 30 seconds, the runback completed but turbine power only reduced to approximately 87 percent turbine power. Subsequently, the runback logic armed and disarmed multiple times until the manual reactor trip was initiated, cycling around the 82 to 85 percent turbine power setpoints. The licensee's initial review of the TCS runback response documented in the PTR, determined that the TCS Medium Runback circuitry allowed the arming/disarming phenomenon to occur based on the manner that the installed software was setup which used turbine inlet pressure as the basis for the setting that was used by the runback arming/disarming circuitry. During the event, turbine inlet pressure oscillated around the software arming setpoint (i.e., 584.3 psig), which resulted in the Medium Runback logic arming and disarming multiple times. At the time of the inspection, the licensee was still evaluating whether the TCS runback and related software had operated per design as part of the actions to address AR 2365717. In addition, the licensee's root cause of Event #1 was not complete but was also expected to evaluate in detail the exact cause of the TCS runback arming and disarming anomaly. As interim corrective actions, operations management issued a Night Order to the operators explaining the circumstances associated with the event including the anomalies identified with the TCS runback arming and disarming anomaly.

C3-505

FPSC EXH No. 7
03/18/2024

C3-608

.6.1.4 ADMITTED Steam Generator Level Control Issues during Transient

During Event #1, it was observed that the SG level control system did not respond as expected in automatic to maintain the SG levels below the automatic trip setpoint of 80 percent narrow range level which required the operators to manually trip the reactor prior to reaching the trip setpoint. As discussed in Section .5.1 of this report, higher than expected feedwater flows were observed during periods when the feedwater regulating valves were being demanded to close which resulted in unexpected rising SG levels. The team reviewed ARs 2365714 and 2365716 that were initiated to address the issue, as well as preliminary engineering evaluations and documents related to the Extended Power Uprate (EPU) modification that was implemented in 2012 which modified the SG level control system, feedwater regulating valve controller setup, and the TCS.

Operational transient functions associated with CV-3-2011 were added as part of the EPU modification for the new digital TCS runback logic system. This included automatic opening of CV-3-2011 during several automatic turbine runback conditions. These conditions included: 1) Medium Runback to 85 percent on a trip of one of the three condensate pumps above 88 percent turbine power, 2) Fast Runback to 50 percent on a trip of one of the two feedwater pumps above 60 percent turbine power, and 3) Medium Runback to 85 percent on manual activated runback above 60 percent turbine power. In addition, as it relates to Event #1, the EPU modification added the Medium Runback to 85 percent whenever CV-3-2011 indicated open via two valve position limit switches with the turbine above 88 percent power.

The team determined that a design analysis error in the 2012 EPU modification for the digital TCS runback logic system and feedwater regulating valve controller setup was the primary cause of the inability of the SG level control system to control rising SG levels during the event. When the 2012 EPU analyses were performed, valve CV-3-2011 opening without a valid demand, was not included in the Failure Modes and Effects Analysis (FMEA) performed by the licensee or its engineering contractor, nor was the runback transient analyzed correctly in calculation CN-CPS-09-67, “Steam Generator Water Level Analysis for the Turkey Point Units 3 and 4 Extended Power Uprate,” due to a lack of acknowledgement in the design phase that a pressure switch failure could cause CV-3-2011 to inadvertently open. In accordance with licensee design procedures, EN-AA-205-1100, “Design Changes Packages,” a FMEA was required for such a condition. The lack of analysis of the specific transient that occurs when CV-3-2011 opens without a valid demand signal contributed to not considering the impact of the transient analysis in the setup and tuning of the feedwater regulating valves. The inadequate setup and tuning of the feedwater regulating valves, via calculation CN-PCSA-12-10, “Steam Generator Water Level Analysis to Support Feedwater Control System Tuning at EPU Conditions for Turkey Point Unit 3,” was most likely the reason for the unexpected rising SG water levels during Event #1.

In addition, an opportunity to have identified the design analysis discrepancy was missed during the licensee’s engineering review of a supporting EPU calculation, PTN-BSHM-08-011, “Feedwater & Condensate Equipment Selection, Performance Evaluation, and Operation Transients Review.” Specifically, a review comment was documented in this calculation which identified that the runback due to CV-3-2011 spuriously opening was not one of the analyzed transients and questioned whether the transient needed to be analyzed. Subsequent actions were not taken to adequately address the comment. As a result, the inadvertent opening of CV-3-2011 along with a turbine Medium Runback

C3-506

FPSC EXH No. 7
03/18/2024
ADMITTED

C3-609

was not analyzed because the licensee, and engineering contractor, mistakenly determined that the total loss of heater drain flow transient evaluation would include the effects of this specific runback. However, calculation CN-CPS-09-67, section 4.4.4, "Assumptions for Complete Loss of Heater Drain Flow Transient," explicitly assumed only conditions as a result of a valid opening signal due to an actual loss of heater drain flow were included. Licensee design procedure ENG-QI-1.5, "Calculations," required an engineer who was knowledgeable of the subject matter shall review calculations to ensure that assumptions and judgements have sufficient rationale, and inputs were from an appropriate source, were correct, and incorporated into analysis, and were consistent with the plant design and operation. The team determined that the licensee failed to follow ENG-QI-1.5, which contributed to not recognizing the need to analyze the transient in more detail.

The team determined that the licensee's failure to follow design procedures EN-AA-205-1100 and ENG-QI-1.5 during implementation of the 2012 EPU modifications, were the primary cause of Event #1. See FIN 05000250/2020050-01, "Inadequate Design Analysis of Automatic Turbine Runback Actuation Coincident with Inadvertent Opening of CV-3-2011," in the inspection results for additional details.

.6.1.5 Interim Corrective Actions to Disable Unit 3 Medium Turbine Runback for Spurious CV-3-2011 Opening

The team reviewed the licensee's actions to address the failure to conduct an adequate design analysis for the spurious opening of CV-3-2011 coincident with an automatic turbine Medium Runback to 85 percent when operating greater than 88 percent turbine power. The licensee developed a temporary design change package to block the TCS runback logic circuitry associated with CV-3-2011 going open, preventing a TCS Medium Runback initiation until a permanent modification could be developed and installed. This modification (EC 295196) was implemented on August 25, 2020, prior to Unit 3 going above 88 percent turbine power following the initial manual reactor trip that occurred on August 17, 2020. Along with this modification, plant procedures were modified which directed the operators to take prompt actions to reduce turbine load manually by approximately 50 megawatts (MW) in order to maintain reactor power less than 100 percent during an inadvertent opening of CV-3-2011. To prevent a similar occurrence on Turkey Point Unit 4, the licensee planned to implement a similar modification during the upcoming Fall 2020 refueling outage. The team determined that adequate interim licensee corrective actions were implemented or planned to address the issue until further corrective actions were implemented following the completion of the ongoing root cause evaluation associated with the event.

.6.2 Inspection Activities Related Specifically to Event #2:

The licensee prepared a PTR for Event #2, and entered the issues into the CAP. The licensee initiated a root cause evaluation for the operator performance issues and planned to issue an LER for this event. Immediate corrective actions included removal of operators from their licensed duties pending remediation, JIT training, crew briefings, and increased oversight of startup operations. Additional corrective actions were to be developed upon completion of the root cause evaluation. Additionally, ARs 2366002 and 2366093 were written to evaluate the concerns raised about the SRNI performance. Immediate corrective actions included troubleshooting and an engineering evaluation of the condition. The team determined that licensee's immediate corrective actions were

C3-507

FPSC EXH No. 7
03/18/2024
ADMITTED

C3-610

Inspection, and the engineering evaluation did not determine that the issues that rendered SRNI N32 inoperable were related to the degraded boron trifluoride (BF3) proportional detector. See NCV 05000250/2020050-04, "Failure to Implement Adequate Corrective Action for Degraded Source Range Nuclear Instrument N32 Condition," in the inspection results for additional details. Following the August 20, 2020 trip, the licensee contacted the vendor for assistance with the SRNI. Subsequently, SRNI N32, was repaired, retested, and returned to an operable status on August 24, 2020.

.6.3 Inspection Activities Related Specifically to Event #3:

The licensee prepared a PTR for Event #3, entered the issues identified into the CAP, initiated a root cause evaluation, and planned to issue a LER for the event. At the time of this inspection, only the event PTR was completed and available for review.

.6.3.1 Feedwater Recirculation Valves Controller Configuration Control Problem

Event #3 was caused by the SGFP master recirculation controller being in manual mode instead of automatic during power ascension. This incorrect configuration resulted in the recirculation valves being left fully open with reactor power at 34 percent. Under normal operation these valves would have fully closed above 20 percent power had the controller been in automatic. When the operating crew took manual control and attempted to close the recirculation valves, it resulted in a rapid increase in feedwater flow and lowered the suction pressure to the operating 3B SGFP, and subsequently caused a SGFP trip on low suction pressure. Due to the loss of the only running SGFP, the operators inserted a manual reactor trip.

The team identified the SGFP master controller and associated recirculation valves were not in the correct configuration during power ascension. The team identified two operating procedures that were inadequate to ensure the proper configuration: 1) The general operating procedure (GOP), 3/4-GOP-301, "Hot Standby to Power Operation," did not include a requirement to verify the status of the SGFP Recirculation valve controllers prior to entering Mode 1; and 2) The ARP, 3/4-ARP-097-CR.D "Control Room Response – Panel D," did not have an operator action to ensure Secondary Controls Auto/Manual controllers were in the required position to support the current plant status.

The licensee took the following initial corrective actions to update procedure 3-GOP-301:

- When at 200 Megawatts Electric (MWe), the SGFP recirculation valves were checked to be closed and in Automatic
- Prior to entering Mode 1, the 3B SGFP stations on DCS will be verified to be in Automatic for recirculation valves CV-3-1414, CV-3-1417, and CV-3-1418

The team reviewed the licensee's initial corrective actions and determined it was adequate to verify the SGFP master recirculation controller was in automatic and recirculation valves were properly aligned during power ascension.

See NCV 05000250,05000251/2020050-05, "Failure to Implement Procedures for Feedwater Recirculation Control in Automatic," in the inspection results for additional details.

C3-508

FPSC EXH No. 7
03/18/2024

C3-611

ADMITTED

.7 Review and evaluate the actions and reviews taken by the licensee prior to authorization for each restart of Turkey Point Unit 3, including the effectiveness of the Onsite Review Group.

.7.1 Inspection Activities Related Specifically to Event #1:

The team reviewed the meeting minutes to the Onsite Review Group (ORG) meeting conducted on August 19, 2020, for the post trip review of the August 17, 2020, Unit 3 manual trip event, and decision to grant the subsequent restart of the unit. Additionally, the team interviewed all the members of the ORG who participated in the meeting.

The inspectors determined that the ORG was convened in accordance with procedure LI-AA-1000, "Onsite Review Group," with appropriately qualified individuals with a membership that represented all necessary disciplines. The team determined that the ORG was effective in their review of the event. The ORG reviewed the equipment problems associated with the event that were documented in the PTR including the failed pressure switch which caused the spurious opening of valve CV-3-2011, the position indication failure associated with valve MOV-3-1432, which required the closure of the MSIVs, the abnormal TCS runback response, and the unexpected SG level control problems. At the time of the ORG review, it was recognized that the abnormal SG level control issue was most likely due to the feedwater regulating controller setup issue and the failure to conduct an adequate design analysis of the Medium Runback for the spurious opening of CV-3-2011 coincident with an automatic 85 percent turbine runback transient. Reactor restart authorization was approved with the understanding that prior to Unit 3 resuming operation above 88 percent turbine power, either the feedwater regulating valves would need to be re-tuned to respond to the transient or the automatic turbine Medium Runback would need to be disabled. Ultimately, management decided to implement a temporary modification to disable this Medium Runback and provided the operators with procedural guidance to manually reduce turbine power during any future spurious opening of CV-3-2011 until a permanent resolution could be developed and implemented.

.7.2 Inspection Activities Related Specifically to Event #2:

The team interviewed all the members of the ORG who participated in the restart authorization following Event #2.

The team determined that the ORG was ineffective in their review of this event. The ORG was convened in accordance with procedure LI-AA-1000, with appropriately qualified individuals with a membership that represented all necessary disciplines. However, several factors may have contributed to the ORG's ineffectiveness and their ultimate decision to restart Unit 3 with an inoperable SRNI. These factors included:

- The ORG was not provided an electronic or hardcopy of the reactor engineering evaluation that reviewed the disparity between the SRNIs (N31 and N32) identified during the reactor startup and the automatic trip on August 19, 2020.

- The ORG accepted the verbal explanation of the reactor engineering evaluation and the ORG members did not challenge the lack of vendor input, the qualifications or experience of the engineers that prepared and reviewed the engineering evaluation related to the BF3 proportional detectors, the lack of objective channel check criteria,

C3-509

FPSC EXH No. 7
03/18/2024
ADMITTED

C3-612

take the credit for surveillance testing that was limited to testing those portions of the SRNIs in the control room vertical panels and consoles. The reactor engineering evaluation additionally discovered that SRNI N32 lagged SRNI N31 in previous reactor startups yet concluded that this was acceptable SRNI behavior. The ORG did not challenge the conclusion that the disparity discovered during the engineering evaluation on previous startups was acceptable.

- The ORG membership on August 20, 2020, included members with previous reactor engineering experience, yet those members did not understand that the current revision of procedure 3-GOP-301, "Hot Standby to Power Operation," directed reactor engineers to collect and calculate inverse count rate data using a single designated SRNI. Those members assumed the reactor startup conducted on August 19, 2020, was compared to inverse count rate data using both SRNIs.

- The PTR that was provided to the ORG members to determine Unit 3's readiness to return to power operation included a graph, obtained from plant computer data, and a software program used to visualize plant computer data, of the observed disparity between SRNI N31 and N32. The graph included both SRNI (N31 and N32) but on two different scales. SRNI N31 was displayed from 0 to 80,000 cps and SRNI N32 was displayed from 0 to 900 cps. Some of the ORG members admitted to not recognizing that the two instruments were displayed on scales with almost two decades difference.

- The ORG was originally scheduled for 0700 on August 20, 2020 and was still scheduled for this time as late as 2209 on August 19, 2020. The ORG was changed to 0500 at 0457 on August 20, 2020. Some of the ORG members participated remotely and received little to no advance notice to participate in the ORG quorum.

See NCV 05000250/2020050-04, "Failure to Implement Adequate Corrective Action for Degraded SRNI N32 Condition," in the inspection results for additional details regarding the Unit 3 reactor restart on April 20, 2020, with SRNI N32 inoperable.

.7.3 Inspection Activities Related Specifically to Event #3:

The team interviewed all the members of the ORG who participated in the restart authorization following Event #3.

The team determined that the ORG was effective in their review of the event. The ORG was convened in accordance with procedure LI-AA-1000, with appropriately qualified individuals and a membership that represented all necessary disciplines.

.8 Assess the decision making and actions taken by the licensee's personnel to determine if there are any implications related to schedule pressure or the site's safety culture.

Common Event Discussions:

None of the licensee personnel interviewed during the inspection stated that they felt schedule pressure was a factor in the errors during these events. The team noted the ORG's decision to conduct a restart readiness meeting without having all the supporting documentation available and with 3 minutes notice at 0457 on August 20, 2020, appears to be a case when indirect schedule pressure influenced the organization.

C3-510

FPSC EXH No. 7
03/18/2024
ADMITTED

C3-613

The team assessed the decision making and actions taken by licensee personnel to determine if there were any implications related to schedule pressure or the site's safety culture on the circumstances surrounding the reactor trips. This assessment focused on the adequacy of licensee activities which monitor the traits of a healthy nuclear safety culture. Those activities included:

- Nuclear Safety Culture Monitoring Panel (NSCMP) and Site Leadership Team (SLT) meeting results. The purpose of the NSCMP was to identify negative contributors and trends related to nuclear safety culture which were then rolled up to the SLT for additional monitoring and action.
- Employee Concerns Program (ECP) pulsing results
- Licensee cognitive trending of issues raised to ECP, Human Resources, Licensing, Nuclear Assurance, and Bargaining Unit organizations.

The team did not identify implications related to schedule pressure or the site's safety culture that were precursors to the circumstances surrounding the events, with the exception of, the apparent indirect schedule pressure on August 20, 2020. In addition, the assessment did not identify any safety culture issues at the time of this inspection.

.9 Evaluate the licensee's application of pertinent industry operating experience.

The team reviewed select operating experience from the NRC, licensee, and industry that was applicable to the events. Additionally, the team reviewed how the licensee evaluated that operating experience.

The team determined that the licensee had typically performed adequate evaluations of applicable operating experience. However, opportunities were missed which included: Surry Power Station reported a similar issue with SRNIs in November 2018. Surry's monitoring program identified that one of their SRNIs was inoperable. The associated report detailed their monitoring program and how it detected the condition. The licensee missed an opportunity to identify the lack of a monitoring program and to communicate this condition to operators, engineers, and instrumentation and control (I&C) technicians. See NCV 05000250,05000251/2020050-06, "Failure to Develop and Establish a Preventive Maintenance Schedule to Measure SRNI Detector Performance," for additional details.

Many of the breakdowns of operator fundamentals related to human error prevention and operator performance were trained upon extensively following Institute of Nuclear Power Operations (INPO) significant operating experience reports (SOERs) issued in 2010 and 2011. While the initial training in response to these SOERs was adequate, the refresher training had not been adequately reinforced, (see section .3.2 for specific examples).

.10 Evaluate equipment reliability and configuration control for the systems that were challenged during the trips which occurred on August 17 and August 20, considering the relationship with the Extended Power Uprate (EPU) with additional focus on EPU single point trip vulnerability.

C3-511

FPSC EXH No. 7
03/18/2024
ADMITTED

C3-614

.10.1 Inspection Activities Related Specifically to Event #1:

The team determined that the primary cause of Event #1 was a design analysis error in the implementation of the 2012 EPU modification for the digital TCS runback logic system and feedwater regulating valve controller setup which resulted in the inability of the SG level control system to adequately control level while in automatic. In addition, the TCS runback logic program, which was also part of the EPU modification, did not respond as expected. Specifically, the TCS Medium Runback stopped initially at 87 percent turbine power and received multiple runback requests which caused operator distractions in focusing on unexpected rising SG level conditions that ultimately resulted in the need to manually trip the reactor due to SG levels approaching the turbine trip setpoint. At the time of this inspection, the licensee's root cause of the event was not completed but was expected to evaluate in detail the exact cause of the TCS runback logic problem and unexpected SG water level anomalies and address the multiple problems involving the implementation of the EPU design modification.

.10.2 Inspection Activities Related Specifically to Event #3:

The team determined the primary cause of Event #3 was a configuration control problem with the feedwater recirculation system created by the implementation of the EPU modification in 2012. The modification did not revise the plant procedures 3/4-GOP-301, "Hot Standby to Power Operation" or 3/4-ARP-097-CR.D, "Control Room Response – Panel D," to ensure that the SGFP master controller and the associated recirculation valves were in the proper configuration during power ascension.

Additionally, the team identified an equipment reliability problem with the feedwater regulating valves following the EPU modification. Specifically, the 3C feedwater regulating valve (FCV-3-478) response was slow and the C SG water level lagged the other SGs during Event #3. The slow feedwater regulating valve was not the primary cause of Event #3, however, it did complicate the operating crew's recovery actions in order to stabilize the C SG water level. The licensee has had past issues during previous transient events with slow response from the 3C FCV-3-478 valve.

C3-512

FPSC EXH No. 7
03/18/2024

INSPECTION RESULTS ADMITTED

C3-615

Inadequate Design Analysis of Automatic Turbine Runback Actuation Coincident with Inadvertent Opening of CV-3-2011			
Cornerstone	Significance	Cross-Cutting Aspect	Report Section
Initiating Events	Green FIN 05000250/2020050-01 Open/Closed	None (NPP)	93812

A self-revealed Green Finding was identified for the licensee's failure to implement adequate design change controls associated with the 2012 Unit 3 extended power uprate (EPU) modification that added an automatic medium turbine runback coincident with the opening of the low-pressure feedwater heater bypass valve CV-3-2011. Specifically, the licensee failed to implement procedure EN-AA-205-1100, "Design Change Packages," and to evaluate the effect of the valve opening without a valid demand signal in the Failure Modes and Effects Analysis (FMEA) and to adequately review the calculational design inputs and assumptions required by design change procedures.

Description: On August 17, 2020, with Unit 3 operating at full power, the control room received indication of an automatic medium turbine runback coincident with the spurious opening of the low-pressure feedwater heater bypass valve CV-3-2011. As a result of unexpected rising SG water levels, the operators took manual control of the feedwater regulating valve for the 3C SG that had the highest level at the time, however, operators were unsuccessful in reducing the increasing level trend. The operators manually tripped the reactor at approximately 91 percent reactor power as SG water levels approached the setpoint for an automatic turbine trip.

The licensee's investigation into the cause of the unexpected rising SG levels identified a design change error when the digital TCS automatic runback logic system was modified during the implementation of the EPU modification in 2012. While the design analysis for the modified TCS runback logic included adequate analysis of a turbine runback due to CV-3-2011 opening in response to an actual SGFP low pressure condition, it did not include the design analysis of an inadvertent opening of CV-3-2011 with a medium turbine runback. Specifically, in accordance with licensee design change procedure EN-AA-205-1100, "Design Change Packages," a FMEA was required to be performed for the inclusion of the transient, but design engineering personnel failed to conduct the required FMEA transient analysis for the event. In addition, licensee design procedure ENG-QI-1.5, "Calculations," required an engineer who was knowledgeable of the subject matter to review calculations to ensure that assumptions and judgements had sufficient rationale and that inputs were from appropriate sources, correct, incorporated into the analysis, and were consistent with the plant design and operation. A missed opportunity to have identified the design analysis discrepancy occurred during engineering review of the supporting EPU calculations. An engineer identified that the runback due to CV-3-2011 spuriously opening was not one of the analyzed transients; however, it was mistakenly determined that the total loss of heater drain flow transient evaluation would bound the effects of this specific runback.

As a result of not conducting the required transient analysis for the spurious opening of CV-3-2011 coincident with an automatic Medium Runback, it was not recognized that this transient was more severe than the other analyzed runback conditions. The lesser severity transients formed the basis for the setup and tuning of the feedwater regulating valve controllers. Due to the more challenging plant conditions experienced during a spurious

C3-513

FPSC EXH No. 7
03/18/2024
ADMITTED

C3-616

opening of valve CV-3-2011, the feedwater regulating valves and their controllers were not setup and tuned (in automatic) to be able to manage the needed response that was required to prevent the unexpected rise in SG levels that was experienced. Corrective Actions: The licensee entered the issues identified during the manual reactor trip into the CAP and initiated a root cause evaluation for the event. Prior to Unit 3 restart, the pressure switch which caused the spurious opening of CV-3-2011 was repaired and a temporary modification was implemented to modify the TCS logic, to eliminate the automatic medium turbine runback during an inadvertent opening of CV-3-2011. Corrective Action References: AR 2365716
Performance Assessment: Performance Deficiency: A performance deficiency was identified for the licensee's failure to evaluate the spurious opening of valve CV-3-2011 and its effect on the ability of the main feedwater regulating valves to control SG water levels and prevent a plant trip. Specifically, the licensee failed to implement procedure EN-AA-205-1100, "Design Change Packages," and to evaluate the effect of the valve opening without a valid demand signal in the Failure Modes and Effects Analysis (FMEA) and to adequately review the calculational design inputs and assumptions required by design change procedures. Screening: The inspectors determined the performance deficiency was more than minor because it was associated with the Design Control attribute of the Initiating Events cornerstone and adversely affected the cornerstone objective to limit the likelihood of events that upset plant stability and challenge critical safety functions during shutdown as well as power operations. Specifically, operators were unsuccessful in controlling SG level and manually tripped the reactor as levels approached the setpoint for an automatic turbine trip. Significance: The inspectors assessed the significance of the finding using IMC 0609, Attachment 4, "Initial Characterization of Findings," for Initiating Events, and IMC 0609, Appendix A, "The Significance Determination Process For Findings At-Power," and using Exhibit 1, "Initiating Events Screening Questions," determined the finding to be of very low safety significance (Green) because the finding, when screened as a transient initiator, did not cause both a reactor trip AND the loss of mitigation equipment relied upon to transition the plant from the onset of the trip to a stable shutdown condition (e.g., loss of condenser, loss of feedwater). Cross-Cutting Aspect: Not Present Performance (NPP). No cross-cutting aspect was assigned to this finding because the inspectors determined the finding did not reflect present licensee performance given that the EPU modification was implemented in 2012.
Enforcement: Inspectors did not identify a violation of regulatory requirements associated with this finding.

C3-514

FPSC EXH No. 7
03/18/2024

C3-617

ADMITTED

Failure to Adequately Manage Reactivity During Startup

Cornerstone	Significance	Cross-Cutting Aspect	Report Section
Barrier Integrity / Initiating Events	Green NCV 05000250/2020050-02 Open/Closed	[H.4] - Teamwork	93812

The NRC identified a Green finding and associated non-cited violation (NCV) of Unit 3 Technical Specification (TS) 6.8.1, “Procedures and Programs,” for the failure to follow procedure 3-GOP-301, "Hot Standby to Power Operation,” which provided instructions for reactor startup. Specifically, the operating crew failed to implement 3-GOP-301 which resulted in an excessive reactivity addition and caused an RPS trip which automatically shut down the reactor.

Description: On August 19, 2020, operators were conducting a reactor startup of Unit 3 after experiencing a manual reactor trip on August 17, 2020. The operators were performing procedure 3-GOP-301, "Hot Standby to Power Operation,” conducting a normal plant startup using control rods. The operating crew consisted of a three-person reactivity team: the OATC, a peer checker, and a reactivity SRO. The responsibility of the reactivity team was to manage reactivity during the startup. The crew also had a Unit 3 RO, and a third RO, to provide administrative support (i.e., log keeping, plant announcements, etc.). A US was responsible for the overall Unit 3 startup activities and a SM was overseeing all crew activities. Also present during the startup was a Reactor Engineer supporting the startup by plotting the SRNI inverse count rate, (1/M plot), and a training department observer. Additionally, two assistant operations managers and the SVP were present in the main control room observing the startup.

After declaring the reactor critical at 1316 on August 19, 2020, the OATC was given the order from the reactivity SRO to perform step 5.21 of procedure 3-GOP-301 to “raise power to 10^{-8} amps and do not exceed a 1.0 dpm SUR.” The OATC intended to perform a continuous rod withdrawal of control rod group D until a 0.7 dpm SUR was achieved and stop withdrawing control rods. The rationale for 0.7 dpm was that with a steady state 0.7 dpm SUR power would not double in less than a minute. The OATC withdrew control bank D for 45 seconds which was 53 steps until rod motion was stopped when a valid SR Hi Flux RPS trip signal was generated and the reactor automatically tripped. SUR was greater than 1.0 dpm for the final 25 seconds of the 45 second rod withdrawal and reached a maximum indicated value of 3.0 dpm, with an instantaneous SUR of 7.4 dpm at the time of the trip.

No member of the operating crew recognized that the OATC had exceeded the SUR limits of the procedure, or that the plant was approaching an RPS trip threshold, and that the OATC was withdrawing rods continuously. Contributing factors included:

- JIT Training: Required JIT training was conducted for the startup crew the afternoon prior to the startup. All members of the crew attended, with exception of the Unit 3 RO and the Reactor Engineer. A tabletop walkthrough of the startup procedure was performed emphasizing 3-way communications. However, simulator training was only performed for the turbine synchronization to the grid and not the startup and power ascension. The training crew was also unaware that the OATC had never performed this evolution on the plant.

- Operator Fundamentals Breakdowns: The OATC never informed the reactivity team of his startup intentions or which key plant parameters to monitor and at what point to

C3-515

FPSC EXH No. 7
03/18/2024
ADMITTED

C3-618

stop withdrawing control rods. Thus, the operating crew did not have an opportunity to coach the OATC or to provide backup when the SUR exceeded the intended 0.7 dpm. Also, operators did not follow fundamental principles to ensure they understood the expected plant response for an action, (i.e. take the action, observe plant response, and stop if expected plant response was not achieved). The OATC did not know how much rod motion was needed to establish a steady 0.7 dpm SUR and did not recognize that not "seeing" a 0.7 dpm for such an extended rod withdrawal was an abnormal system response. Note: The indicated SUR was well above 1.0 dpm, based on a review of plant computer historical data after the event, however, none of the crew noticed this at the time.

- Oversight and Control of the Startup Evolution: The reactivity team provided no meaningful assistance to the OATC during the power ascension, nor did the US or SM. Key reactor plant indications were displayed on the ROs vertical panel. Additionally, the SROs had monitoring capability digitally displayed in other areas of the control room. The reactivity SRO and the US were in direct line of site of nuclear instrumentation and the OATC's hand on the rod control switch, yet did not notice the excessive SUR or appropriately stop the withdrawal of control rods. Audio of SR counts and rod motion was energized and loud enough to be heard, and plant computer data was available in multiple locations. Additionally, the action to deenergize SR high volts after the P-6 Permissive light came in was delegated to the third RO. If this action had been assigned to the OATC as normally performed, the OATC would have had to stop withdrawing rods when P-6 was announced while SUR was approximately 1.0 dpm. Instead the OATC continued withdrawing control rods during this time limited evolution.

- Confusing Indications: Prior to criticality, during the startup, it was noted that SRNI channels N31 and N32 were deviating by approximately 1.0 decade. As the startup progressed this deviation continued to increase. During the continuous rod withdrawal, plant computer data also showed that SRNI N32 SUR was also lagging the other three SUR indications (i.e., IRNI N35 and N36 and SRNI N31). At the time of the trip, SUR was 3.0 dpm on three channels and 1.5 dpm on SRNI N32. It was possible that some operators may have been confused by this or focused on this incorrect indication.

Corrective Actions: The licensee prepared a PTR for the event on August 19, 2020, entered the issues identified into the CAP, and initiated a root cause evaluation for the operator performance issues. Immediate corrective actions included removing operators from watch standing duties for remediation, increased oversight of startup activities, and JIT training. Additional corrective actions were to be developed as part of the root cause evaluation.

Corrective Action References: AR 2365970

Performance Assessment:

Performance Deficiency: A performance deficiency was identified for the licensee's operating crew's failure to adequately manage reactivity additions to the core, and failure to adequately monitor key reactor plant parameters during reactivity additions. Specifically, the operating crew did not identify procedure 3-GOP-301 SUR limits were exceeded, which resulted in an automatic RPS actuation and reactor trip.

Screening: The inspectors determined the performance deficiency was more than minor because it was associated with the Human Performance attribute of both the Barrier Integrity

C3-516

FPSC EXH No. 7
03/18/2024
ADMITTED

C3-619

and Mitigating Events Cornerstones and adversely affected the cornerstone objectives to provide reasonable assurance that physical design barriers protect the public from radionuclide releases caused by accidents or events. Specifically, operators challenged the SUR limits which resulted in an automatic RPS trip actuation.

Significance: The inspectors assessed the significance of the finding using IMC 0609, Attachment 4, "Initial Characterization of Findings." Subsequently, the inspection staff and applicable Senior Risk Analyst (SRA), with support from management, determined IMC 0609, Appendix M, "Significance Determination Process Using Qualitative Criteria," was an appropriate evaluation tool, given that this event was caused by multiple human performance errors, involved an error of commission, and involved low power operations for which the NRC and Licensee do not have plant specific risk models. A planning Significance and Enforcement Review Panel (SERP) was conducted on October 7, 2020, which confirmed the use of IMC 0609, Appendix M, was warranted for this evaluation.

To conduct a risk assessment in accordance with IMC 0609, Appendix M, the SRA consulted with the licensee and Idaho National Laboratory (INL), to develop a low power event tree model for a SR Continuous Rod Withdrawal Event using the guidance in WCAP-15381-NP-A, Revision 2, "WOG Risk-Informed ATWS Assessment and Licensing Implementation Process," (ADAMS Accession No. ML072550560). Additionally, the SRA identified several operator time critical actions which were required to be performed in the event RPS fails. These actions all required the operators to diagnose the condition, enter the appropriate Emergency Operating Procedures (EOPs), and perform the actions. Given the performance deficiency directly related to the operator's ability to monitor key plant parameters and identify that an RPS threshold was met, applicable human error probabilities (HEPs) needed to be adjusted to account for operators not diagnosing the event.

The Appendix M worksheet used to reach the SDP conclusion is included in Attachment C of this report. The finding was determined to be of very low safety significance (Green).

Cross-Cutting Aspect: H.4 - Teamwork: Individuals and work groups communicate and coordinate their activities within and across organizational boundaries to ensure nuclear safety is maintained. The failure of the OATC to communicate their intentions and coordinate monitoring activities was a primary contributor to this event.

Enforcement:
Violation: Unit 3, TS 6.8.1.a, stated in part, that written procedures shall be established, implemented, and maintained covering the activities referenced in the applicable procedures required by the NextEra Energy Quality Assurance Topical Report (QATR). NextEra QATR, Appendix B, "Procedures," stated in part that, NextEra Energy committed to use Appendix A of Regulatory Guide 1.33 as guidance for establishing the types of procedures that are necessary to control and support plant operation. Regulatory Guide 1.33, Appendix A, item 2, "General Plant Operating Procedures," subsection 'a,' included procedures for Hot Standby to Minimum Load (nuclear startup). The licensee implemented procedure 3-GOP-301, "Hot Standby to Power Operation," to provide instructions for reactor startup, to satisfy TS procedure requirements. Procedure step 5.21 provided instructions to "establish a steady state startup rate of 1.0 dpm or less to 10^{-8} amps and stabilize reactor power at 10^{-8} amps on the IR Monitors."

Contrary to the above, on August 19, 2020, during reactor startup using 3-GOP-301, licensee personnel failed to properly raise power to 10^{-8} amps while maintaining a startup rate of

C3-517

FPSC EXH No. 7
03/18/2024
ADMITTED

C3-620

1.0 ADMITTED which resulted in an automatic reactor trip on the 10^5 cps SRNI high flux trip setpoint.

Enforcement Action: This violation is being treated as a non-cited violation, consistent with Section 2.3.2 of the Enforcement Policy.

Failure to Adequately Monitor Source Range Nuclear Instrument (SRNI) N-32			
Cornerstone	Significance	Cross-Cutting Aspect	Report Section
Mitigating Systems	Green NCV 05000250/2020050-03 Open/Closed	[H.11] - Challenge the Unknown	93812

The NRC Identified a Green NCV of TS 3.3.1, "Instrumentation," for not entering the Limiting Condition for Operation (LCO) and completing the action statement for one of the required SRNI Hi Flux Trip channels being inoperable in a mode where it was required. Specifically, the licensee conducted a reactor startup, and entered Mode 2 with the SRNI N32 and its associated SR High Flux RPS trip channel inoperable.

Description: On August 19, 2020, operators were conducting a reactor startup following the August 17, 2020, reactor trip. During the startup, the OATC and the RO peer checker identified that SRNI channels N31 and N32 had deviated by a full decade. The operators stopped rod withdrawal and brought their concern to the reactivity SRO and US who discussed the concern with the SM. At this time, SRNI channel N31 had doubled twice while SRNI channel N32 was still close to its pre-startup value. The SM and other SROs reviewed plant data traces for both SRNI channels and observed that both channels appeared to be responding to the rod pulls but at different magnitudes. Based upon this observation and the operator rounds limit of a 1.5-decade channel deviation, the crew believed that SRNI N32 was still operable. The operators were instructed to monitor SRNI N32 and continue with the reactor startup. The reactor engineer who was present in the control room performing the 1/M plot, using SRNI N31, was not consulted. If SRNI N32 was used for on the 1/M plot, it would have been clear that SRNI N32 was not responding properly. Both the startup and reactivity management procedures had steps to compare the estimated critical position, 1/M plot projected criticality values, and provided clear guidance for stopping the startup and evaluating. If SRNI N32 had been used, those limits would have been exceeded prior to the reactor reaching criticality and it would have been clear that SRNI N32 was inoperable.

The established monitoring criteria for the SRNI deviation was 1.5 decades. As control rods were withdrawn to criticality, the deviation between the channels continued to increase. At approximately 1.4 dpm deviation, SRNI N32 counts had only doubled once, while SRNI N31 had doubled approximately 5 times as expected. During the OATC's rod withdrawal to raise power to 10^{-8} amps in the IR, the channels deviated by greater than 1.5 decades for most of the withdrawal reaching a maximum deviation of 2 decades at the time of the SR High Flux trip. The SRNI SUR indications for the two channels also began to deviate noticeably, (3.0 dpm for N31 and 1.5 dpm for N32). These key reactor plant parameters were being displayed and were required to be continuously monitored during a plant startup.

TS 3.3.1 required that two of two channels of SRNIs and SR High Flux RPS Trips be operable during Mode 2. The action statement for not maintaining minimum required channels was to immediately stop all reactivity additions. Had the TS LCO action statement been entered, the SR High Flux Trip would have been avoided.

C3-518

FPSC EXH No. 7
03/18/2024

C3-621

ADMITTED

Although not related to the performance deficiency, no technical basis for the 1.5 decade deviation channel check criteria for SRNIs could be found, however, the vendor recommended a channel deviation of 1.0 decade. Personnel had raised this concern previously, in 2001 and 2010, and licensee evaluations had made the same observation and proposed enhancements to update the criterion, however, this was never implemented.

Procedure OP-AA-103-1000, "Reactivity Management," Rev. 13, stated that no significant discrepancies exist between reactor power level indicators and/or indirect power indications such as turbine first stage pressure. If significant discrepancies exist, power ascension shall cease until the situation is investigated.

The operations crew had numerous opportunities to challenge the operability of SRNI N32 during the August 19, 2020, reactor startup and had many different indications and resources available which were not used. Reviews of past startup data showed that SRNI N32 frequently deviated from SRNI N31. Subsequent past operability reviews concluded that channel SRNI N32 had been inoperable since at least April 2020. The degraded RPS trip function was challenged and the redundant channel actuated and tripped the reactor during the August 19, 2020, startup.

Corrective Actions: The licensee prepared a PTR for the event on August 19, 2020, and entered the issues identified into the CAP. Troubleshooting was performed on the SRNIs and IRNIs under WO Packages 40737616-01 and -02 which included directing the staff to perform procedure 3-SMI-059.03, "SRNI N32 Calibration." These corrective actions were ineffective. Ultimately, the licensee implemented a repair plan with vendor support to restore the sensitivity of the SRNI N32 detector to an operable condition in WO 40738044, "U3 N32 Increase Detector Sensitivity." WO 40738044 increased N32 high voltage detector setting from a nominal 1,500 VDC to 1,750 VDC. A successful post maintenance test for SRNI N32 was completed on August 24, 2020, during a Unit 3 reactor startup, which invoked TS 3.0.6 to demonstrate SRNI N32 operability by comparing cps levels at six discrete points in the reactor startup sequence and verifying that SRNI N31 and N32 channels did not deviate beyond 1.0 decade.

Corrective Action References: AR 2366002

Performance Assessment:

Performance Deficiency: The failure to properly monitor SRNI N32 performance during a reactor startup and the failure to identify that the SRNI N32 was inoperable was a performance deficiency. Specifically, operators failed to follow procedure OP-AA-103-1000 by continuing a reactor startup with power level indication discrepancies present.

Screening: The inspectors determined the performance deficiency was more than minor because it was associated with the Equipment Performance attribute of the Mitigating Systems cornerstone and adversely affected the cornerstone objective to ensure the availability, reliability, and capability of systems that respond to initiating events to prevent undesirable consequences. Specifically, the SRNI N32 and associated High Flux RPS trip channel function was unable to perform its TS required safety function in a mode where it was required.

Significance: The inspectors assessed the significance of the finding using IMC 0609, Attachment 4, "Initial Characterization of Findings," for Mitigating Systems, and IMC 0609, Appendix A, "The Significance Determination Process for Findings At-Power." Using the

C3-519

FPSC EXH No. 7
03/18/2024
ADMITTED

C3-622

screening questions in IMC 0609, Appendix A, Exhibit 2, “Mitigating Systems Screening Questions,” section C, “Reactor Protection System (RPS),” the performance deficiency screened to very low safety significance (Green) because the finding only affected a single RPS trip signal to initiate a reactor trip AND the function of other redundant trips or diverse methods of reactor shutdown (e.g., other automatic RPS trips, alternate rod insertion, or manual reactor trip capacity) was not affected. The redundant channel of the SR High Flux RPS trip functioned when called upon and IR Hi Flux and Power Range Low Power High Flux RPS trips were also not affected by the performance deficiency and were available.

Cross-Cutting Aspect: H.11 - Challenge the Unknown: Individuals stop when faced with uncertain conditions. Risks are evaluated and managed before proceeding. Specifically, operators did not adequately challenge the degraded performance of SRNI N32 at multiple points during the reactor startup and elected to proceed with the startup versus evaluating the issue more thoroughly.

Enforcement:
Violation: Unit 3 TS 3.3.1, “Instrumentation,” required that in Mode 2, two of two SR High Flux RPS trip channels be operable.

Contrary to the above, on August 19, 2020, the licensee conducted a reactor startup, and entered Mode 2 with the SRNI N32 and its associated SR High Flux RPS trip channel inoperable.

Enforcement Action: This violation is being treated as a non-cited violation, consistent with Section 2.3.2 of the Enforcement Policy.

Failure to Implement Adequate Corrective Action for Degraded Source Range Nuclear Instrument (SRNI) N32 Condition			
Cornerstone	Significance	Cross-Cutting Aspect	Report Section
Mitigating Systems	Green NCV 05000250/2020050-04 Open/Closed	[P.2] - Evaluation	93812

The NRC identified a Green NCV of 10 CFR 50, Appendix B, Criterion XVI, “Corrective Action,” for failure to identify and correct a condition adverse to quality related to the SRNI N32 and its associated RPS SR high flux trip channel during the post trip review of the August 19, 2020, trip which resulted in a subsequent reactor startup on August 20, 2020, with an inoperable RPS trip channel.

Description: On August 19, 2020, Unit 3 had an automatic RPS actuation due to a valid High SR flux signal from SRNI N31. A post trip review was conducted, and statements were taken from the operators. The purpose of the post trip review was to gather all relevant equipment and human performance data to ensure immediate performance issues were identified and corrective and/or compensatory actions can be developed. The post trip review identified several issues related to the SRNIs including:

1) At the time of the trip, SRNI N31 indicated 78,000 cps and SRNI N32 indicated 760 cps,
2) During the startup a concern had been raised that SRNI N31 and SRNI N32 had diverged by greater than one decade, and
3) There were concerns about SR and IR SUR indications since no operator recalled seeing greater than a 0.7 SUR.

C3-520

FPSC EXH No. 7
03/18/2024

C3-623

ADMITTED

The concerns were documented in AR 2366002, however, an operability review was not documented until the following day, after the August 20, 2020, startup occurred. The SM verbally discussed the issue with operations management and concluded the instrument was operable and documented that position in writing the next day.

As part of the post trip review, the Outage Control Center (OCC) was directing troubleshooting activities for both SRNI and all SUR indications. WO Packages 40737616-01 and -02 included directions to perform procedure 3-SMI-059.03, "SRNI N32 Calibration." This calibration only tests the instrumentation portion of the channel using a test signal. The SRNI detector and interconnected wiring were not tested. The troubleshooting verified that the instrumentation upstream of the detector and control room indications were operating properly. Procedure 3-SMI-059.03, Sections 4.13 and 4.14 had acceptance criteria for neutron level instrumentation when 10^5 cps test signal was inserted of 8 x 10^4 to 1.2 x 10^5 cps. The post trip review clearly identified that SRNI N32 was well outside this tolerance band when actual plant conditions warranted an RPS trip.

An engineering evaluation was also developed to present to the ORG during the restart readiness meeting. The engineer who developed the evaluation was the Reactor Engineer on shift during the August 19, 2020, reactor trip. The evaluation was reviewed by another engineer; however, this engineer was not a Reactor Engineer and was not familiar with the equipment. The evaluation used engineering judgement and qualitative observations to conclude SRNI N32 was operable, based on the channel response to rod retractions when plant computer data was viewed on a lower scale. This was the same rationale the SM had used when the deviation was identified, for the August 19, 2020, startup. The evaluation also used plant data from previous startups to show that the instrument had behaved similarly in the past. For example, the April 2020 startup data showed the two SR instruments diverged by a factor of seven as the reactor power was raised to the P-6 permissive. None of the quantitative criteria available were used to evaluate the performance of the SRNI and its associated RPS trip channel. These included:

- The SRNI N31 and N32 had diverged by 2 decades at the time of the trip, a fact captured in the executive summary of the PTR. The monitoring criteria in surveillance requirements and operator rounds was SR channels should not diverge by greater than 1.5 decades.
- When actual plant conditions provided a 10^5 count rate, SRNI N32 was well outside the acceptance bands in surveillance procedure 3-SMI-059.03, Sections 4.13 and 4.14 of 8 x 10^4 to 1.2 x 10^5 cps for a test signal of 10^5 present. The PTR documented the observed count rate was 820 cps.
- SRNI N32 only doubled 4.5 times at the time of the trip while N31 had doubled 11 times.
- When the reactor was called critical, SRNI N32 had only doubled one time, versus the five times as expected, which had occurred on SRNI N31.
- When SRNI N32 data was plotted on the 1/M plot, the guidelines in procedure 3-GOP-301, "Hot Standby to Power Operations," step 4.26 were clearly not met. The same guidance was also in the reactivity management procedure. Specifically, if the projected critical rod position deviated from Estimated Critical Configuration (ECC) by greater than 500 percent mille (pcm), control banks should be reinserted and the

C3-521

FPSC EXH No. 7
03/18/2024
ADMITTED

C3-624

IMC 0609 evaluated. Additionally, the reactor shall not be made critical with a difference greater than 1,000 pcm. This was a reasonable criterion that could have been used when addressing SRNI operability during the PTR and the operability determination.

- SRNI N32 SUR indications also diverged from SRNI N31 and IRNI SURs, (3.0 dpm versus 1.5 dpm at the time of the trip).

These quantitative factors contradicted the conclusion of the engineering evaluation and were not adequately considered.

The evaluation was presented orally to the ORG restart review meeting. The actual evaluation was not sent to ORG members until after the meeting and the decision to restart Unit 3 was already made. ORG member's questions focused on human performance factors related to the trip and did not challenge the operability of SRNI N32.

After the August 20, 2020, startup and subsequent manual reactor trip, the licensee requested technical assistance from the vendor. The vendor did not support the operability call made by the licensee. The vendor provided guidance to address the condition temporarily to restore operability and recommended replacing the SRNI detector at the next available opportunity.

Corrective Actions: The licensee entered the issue into their CAP as AR 2366002. Short term repairs were implemented and SRNI N32 was retested and returned to an operable status on August 24, 2020.

Corrective Action References: AR 2366002 and AR 2366093

Performance Assessment:
Performance Deficiency: The licensee failed to identify and correct a condition adverse to quality in accordance with 10 CFR 50, Appendix B, Criterion XVI. Specifically, SRNI N32 and its associated RPS trip channel were inoperable during the post trip review and restart authorization process.

Screening: The inspectors determined the performance deficiency was more than minor because it was associated with the Equipment Performance attribute of the Mitigating Systems cornerstone and adversely affected the cornerstone objective to ensure the availability, reliability, and capability of systems that respond to initiating events to prevent undesirable consequences. Specifically, SRNI N32 and the associated High Flux RPS trip channel function was unable to perform their TS required safety function in a mode where it was required.

Significance: The inspectors assessed the significance of the finding using IMC 0609, Attachment 4, "Initial Characterization of Findings," and IMC 0609, Appendix A, "The Significance Determination Process (SDP) for Findings At-Power." Using the screening questions in IMC 0609, Appendix A, Exhibit 2, "Mitigating Systems Screening Questions," section C, "Reactor Protection System (RPS)," the performance deficiency screened to very low safety significance (Green) because the finding only affected a single RPS trip signal to initiate a reactor trip AND the function of other redundant trips or diverse methods of reactor shutdown (e.g., other automatic RPS trips, alternate rod insertion, or manual reactor trip capacity) was not affected. The redundant channel of the SR High Flux RPS trip was operable and IR Hi Flux and Power Range Low Power High Flux RPS trips were also not affected by the performance deficiency.

C3-522

FPSC EXH No. 7
03/18/2024

C3-625

ADMITTED

Cross-Cutting Aspect: P.2 - Evaluation: The organization thoroughly evaluates issues to ensure that resolutions address causes and extent of conditions commensurate with their safety significance. Specifically, the licensee did not thoroughly evaluate the performance of the SRNI N32, in that they did not properly consider quantitative information that was available to them during the post trip review process when determining operability.

Enforcement:
Violation: 10 CFR 50 Appendix B Criterion XVI, Corrective Actions, required, in part, that "Measures shall be established to assure that conditions adverse to quality, such as failures, malfunctions, deficiencies, deviations, defective material and equipment, and nonconformances are promptly identified and corrected."

Contrary to the above, on August 20, 2020, the licensee failed to promptly identify and correct a condition adverse to quality. Specifically, the SRNI N32 and its associated RPS trip Channel were inoperable during the post trip review of the August 19, 2020, reactor trip, and the licensee subsequently performed a reactor startup without fully identifying, and correcting the required equipment.

Enforcement Action: This violation is being treated as a non-cited violation, consistent with Section 2.3.2 of the Enforcement Policy.

Failure to Implement Procedures for Feedwater Recirculation Control in Automatic			
Cornerstone	Significance	Cross-Cutting Aspect	Report Section
Initiating Events	Green NCV 05000250,05000251/2020050-05 Open/Closed	None (NPP)	93812

A self-revealed Green NCV of TS 6.8.1, "Procedures and Programs," was identified for the licensee's failure to establish, implement, and maintain adequate procedures for properly controlling the configuration of the Master Controller for the steam generator feedwater pump (SGFP) recirculation valves during Unit 3 plant startup.

Description: The Unit 3 manual reactor trip, that occurred on August 20, 2020, was caused by the SGFP Recirculation Valves Master Controller being in manual instead of automatic during power ascension. This alignment resulted in the recirculation valves being left fully open with reactor power at 34 percent. These valves would have been fully closed above 20 percent power had the controller been in automatic. When the operating crew took manual control and attempted to close the recirculation valves, it resulted in lowering suction pressure and eventual trip of the 3B feedwater pump due to low suction pressure. Subsequently, due to the loss of the only running feedwater pump, the operators inserted a manual reactor trip as required by procedures.

The team identified two examples where the licensee failed to establish, implement, and maintain plant procedures to ensure the SGFP Recirculation Valves Master Controller and associated recirculation valves were in the correct configuration during power ascension. The first example was the general operating procedure (GOP), 3/4-GOP-301, "Hot Standby to Power Operation," which did not include a requirement to verify the status of the SGFP Recirculation valve controllers prior to entering Mode 1. The second example involved the alarm response procedure (ARP), 3/4-ARP-097-CR.D, "Control Room Response – Panel D,"

C3-523

FPSC EXH No. 7
03/18/2024
ADMITTED

C3-626

which also did not have an operator action to ensure the Secondary Controls Auto/Manual controllers were in the correct position required to support power ascension.

The team reviewed modification EC 246935, that was part of the 2012 EPU which introduced a new SGFP recirculation valve controller scheme. This included the addition of two recirculation to condenser valves and one suction recirculation valve, as well as their associated controllers and one master controller for all three valves. The new controller system provided automatic valve control during power operations. The system included a design that transferred valve control from automatic to manual upon receipt of signals indicating variations in the flow transmitters for each of the three recirculation valves. The new secondary controls provided many inputs to a single Control Room Annunciator D-4/5 (DCS Secondary Trouble).

The team determined that the EPU modification did not revise plant procedures 3/4-GOP-301 and 3/4-ARP-097-CR.D, as part of its implementation to ensure that the SGFP master controller and the associated recirculation valves would be verified for the proper configuration during power ascension.

Corrective Actions: The licensee took immediate corrective actions to update procedure 3-GOP-301 to include an operator action when the unit reaches 200 MWe, to verify the SGFP recirculation valves are closed and the valve controllers are in automatic. In addition, actions were added prior to entering Mode 1, to verify the SGFP control stations on the DCS display panel were in automatic for recirculation valves CV-3-1414, CV-3-1417, and CV-3-1418. The licensee initiated a corrective action to revise ARPs 3/4-ARP-097.CR.D, to add an operator action to ensure the DCS Secondary Controls were in the proper configuration to support power ascension. Additional corrective actions were expected following the completion of the licensee's root cause evaluation of the event that was ongoing at the time of the inspection.

Corrective Action References: AR 2366158

Performance Assessment:
Performance Deficiency: The licensee's failure to ensure plant condensate and feedwater systems were properly aligned to support plant startup was a performance deficiency. Specifically, GOP 3-GOP-301, "Hot Standby to Power Operation," and ARP 3-ARP-097-CR.D, "Control Room Response – Panel D," did not contain instructions to ensure that the SGFP Recirculation Valves Master Controller was in automatic and the associated feedwater pump recirculation valves were in the proper configuration during power ascension.

Screening: The inspectors determined the performance deficiency was more than minor because it was associated with the Configuration Control attribute of the Initiating Events cornerstone and adversely affected the cornerstone objective to limit the likelihood of events that upset plant stability and challenge critical safety functions during shutdown as well as power operations. Specifically, a manual reactor trip was initiated due to a configuration control problem on August 20, 2020.

Significance: The inspectors assessed the significance of the finding using IMC 0609, Attachment 4, "Initial Characterization of Findings," for Initiating Events, and IMC 0609, Appendix A, "The Significance Determination Process For Findings At-Power," and using Exhibit 1, Initiating Events, for "Transient Initiators," determined the finding to be of very low safety significance (Green) because the finding did not cause both a reactor trip AND the loss

C3-524

FPSC EXH No. 7
03/18/2024
ADMITTED

C3-627

of mitigation equipment relied upon to transition the plant from the onset of the trip to a stable shutdown condition (e.g., loss of condenser, loss of feedwater). Cross-Cutting Aspect: Not Present Performance. No cross-cutting aspect was assigned to this finding because the inspectors determined the finding did not reflect present licensee performance. The EPU modification was implemented in 2012.
Enforcement: Violation: TS 6.8.1.a, stated in part, that written procedures shall be established, implemented, and maintained covering the activities referenced in the applicable procedures required by the NextEra QATR. NextEra QATR, Appendix B, “Procedures,” stated in part, that NextEra Energy committed to use Appendix A, of Regulatory Guide 1.33, as guidance for establishing the types of procedures that are necessary. Regulatory Guide 1.33, Appendix A, item 2, “General Plant Operating Procedures”, included (2)(b) Hot Standby to Minimum Load, and item 5, included, Procedures for Abnormal, Off-normal, or Alarm Conditions. The licensee implemented 3/4-GOP-301, "Hot Standby to Power Operation," and 3/4-ARP-097-CR.D, “Control Room Response – Panel D,” as part of these procedure requirements. Contrary to the above, from 2012 until the present, the licensee failed to establish, implement, and maintain plant procedures 3/4-GOP-301, "Hot Standby to Power Operation," and 3/4-ARP-097-CR.D, “Control Room Response – Panel D,” following the EPU modification. Specifically, GOP 3-GOP-301, “Hot Standby to Power Operation,” and ARP 3-ARP-097-CR.D, “Control Room Response – Panel D,” did not contain instructions to ensure that the SGFP Recirculation Valves Master Controller was in automatic and the associated feedwater pump recirculation valves were in the proper configuration during power ascension. As a result, a manual reactor trip occurred due the lack of adequate condensate and feedwater system configuration controls associated with systems modified under the EPU modification. Enforcement Action: This violation is being treated as a non-cited violation, consistent with Section 2.3.2 of the Enforcement Policy.

Failure to Develop and Establish a Preventive Maintenance Schedule to Measure Source Range Nuclear Instrument (SRNI) Detector Performance			
Cornerstone	Significance	Cross-Cutting Aspect	Report Section
Mitigating Systems	Green NCV 05000250,05000251/2020050-06 Open/Closed	[P.5] - Operating Experience	93812
An NRC-identified Green NCV of TS 6.8.1, “Procedures and Programs,” was identified for the licensee’s failure to develop and establish a preventive maintenance schedule to perform source range nuclear instruments (SRNI) detector baseline and trending tests.			
Description: During the Unit 3 reactor startup on August 19, 2020, control room operators observed that, SRNI N31 and N32, cps were deviating, specifically SRNI N32 was lagging N31. In response to the SRNI N32 behavior, the licensee initiated AR 2366002, "N31/N32 Source Range Detector Response Disparity." AR 2366002 was initiated after the reactor startup and subsequent automatic trip on SR neutron high flux and required reactor engineering to determine and document the acceptability of the disparity in response observed. The results of the reactor engineering evaluation were presented to the ORG that convened on August 20, 2020, at 0500 hours and was additionally reviewed by a SM to support the operability screening. Although the SM recognized that the condition described in			

C3-525

FPSC EXH No. 7
03/18/2024

C3-628

ADMITTED

AR 2366002 called into question the operability of a TS required component, the SM inadvertently entered “not applicable” for the operability screening in the Nuclear Assets Management System (NAMS). Control room operators ultimately commenced a Unit 3 reactor startup on August 20, 2020, at 0730 hours with SRNI N32 inoperable.

On August 20, 2020, an off-shift SRO recognized that AR 2366002, did not receive an immediate operability determination and was screened as not applicable. The off-shift SRO initiated AR 2366093, "Potential Inoperability of NI-31 [-32]," and notified the control room operators of the concern. While the SM inadvertently screened AR 2366002 as “not applicable,” the intention was to screen the issue as operable but degraded. The resident inspectors also disagreed with the SM’s assessment of the operability of SRNI N32 and applied the guidance in IMC 0326, “Operability Determinations,” (ADAMS Accession No. ML19273A878), Section 06.12, Issue Resolution and Internal Alignment. Regional NRC staff consulted with Headquarters technical experts in the Office of Nuclear Reactor Regulation (NRR) and together, prepared questions and information requests for the licensee to respond. NRC staff recognized that Unit 3 had returned to Mode 1 and the SRNI operability was no longer applicable in Mode 1. NRC staff intended to challenge the licensee on its assessment of the operability of SRNI N32 as soon as possible in the event of an unscheduled Mode 3 entry that would require two operable SRNIs in accordance with TS 3.3.1, “Reactor Trip System Instrumentation.” Subsequently, on the evening of August 20, 2020, Unit 3 was manually tripped. On August 21, 2020, the resident inspectors presented the questions and information requests regarding the operability assessment of SRNI N32 to licensee management with the expectation that the questions and information requests should be responded to prior to Unit 3 reactor startup. The resident inspectors and NRC technical experts disagreed with the SM’s operability assessment and reactor engineers’ conclusions in the associated technical evaluation. The resident inspectors’ concern for disparity between SRNIs N31 and N32 was communicated to licensee management on August 19, 2020, after the reactor trip on SR high neutron flux when it was identified that SRNI N32 was reading almost two decades below SRNI N31 when the automatic reactor trip occurred.

On August 22, 2020, the licensee completed its prompt operability determination for the observed disparity between the SRNI N31 and N32 channels and concluded that N32 was unable to achieve its specified safety function due to a slow response to changing neutron flux. The prompt operability determination was informed by a vendor review of the historical data and determined the sensitivity of N32 was degrading over time as the detector approached the end of its service life. The degradation progressed to the point that continued operability of N32 was challenged as it would not likely provide a trip signal when conditions in the core would warrant one, as occurred on August 19, 2020. On August 22, 2020, control room operators declared N32 inoperable at 0017 hours.

During correspondence with the vendor, the licensee was informed that they were not following the guidance described in vendor document RRS-VICO-02-326, “A Predictive Maintenance and Evaluation Guide for Ex-Core and In-Core Detectors used in Westinghouse Pressurized Water Reactors,” dated May 2002. The SRNI detectors were boron trifluoride (BF3) gas proportional counters. Specifically, the Unit 3 and Unit 4 SRNI detectors were Westinghouse NY-10032 low voltage detectors. SRNI N32 on Unit 3 had been in service since April 2006 and was the SRNI detector with the longest time in service for both Units 3 and 4. Unit 3 SRNI N31 was installed in May 2015, Unit 4 SRNI N31 in April 2011, and Unit 4 SRNI N32 was installed in September 2017. The BF3 proportional counters had aging

C3-526

FPSC EXH No. 7
03/18/2024
ADMITTED

C3-629

characteristics and failure mechanisms that would reduce their sensitivity to neutron flux. The expected service life of the NY-10032 detectors was ten to twenty years.

The guidance in vendor document RRS-VICO-02-326 was intended to provide reactor engineers with specific criteria for deciding when ex-core and in-core detectors were approaching their end-of-life and should be replaced. As an alternative, the licensee also had not established a preventive maintenance schedule to periodically replace the SRNI detectors prior to their expected end of service life.

Although the vendor recommended program described in RRS-VICO-02-326, was dated May 2002, a more recent opportunity existed for the licensee to identify its lack of a preventive maintenance schedule to routinely measure SRNI detector gas multiplication factors. Surry Nuclear Power Station entered report number 452589, dated October 27, 2018, and last updated on April 5, 2019, into Institute of Nuclear Power Operations (INPO) Consolidated Event System (ICES). ICES report 452589 was titled, "Unusually Low Reading on Source Range Nuclear Instrument Channel During Shutdown," and described a disparity between SRNI channels with one channel reading significantly lower than expected due to a low gas multiplication factor. The ICES report referenced RRS-VICO-02-326 and the associated recommended testing and trending to identify the low gas multiplication factor.

Corrective Actions: The licensee implemented a repair plan with vendor support to restore the sensitivity of the SRNI N32 detector to an operable condition in WO 40738044, "U3 N32 Increase Detector Sensitivity." WO 40738044 increased N32 high voltage detector setting from a nominal 1,500 Volts Direct Current (VDC) to 1,750 VDC. A successful post maintenance test for SRNI N32 was completed on August 24, 2020, during a Unit 3 reactor startup, which invoked TS 3.0.6 to demonstrate SRNI N32 operability by comparing cps levels at six discrete points in the reactor startup sequence and verifying that SRNI N31 and N32 channels did not deviate beyond 1.0 decade.

The licensee also initiated AR 2366359, "Apply Multiplication Factor Trends to NI Detector Monitoring." AR 2366359 included actions to replace the SRNI N32 detector during the next refueling outage and to perform multiplication factor trending during the fall 2021 Unit 4 refueling outage for both SRNIs.

Corrective Action References: WO 40738044 and AR 2366359

Performance Assessment:

Performance Deficiency: The licensee's failure to implement a preventive maintenance plan consistent with vendor document RRS-VICO-02-326, to ensure the SRNI N32 detector was replaced prior to age-related degradation rendering the instrument inoperable was a performance deficiency.

Screening: The inspectors determined the performance deficiency was more than minor because it was associated with the Equipment Performance attribute of the Mitigating Systems cornerstone and adversely affected the cornerstone objective to ensure the availability, reliability, and capability of systems that respond to initiating events to prevent undesirable consequences. Specifically, the licensee failed to establish a preventive maintenance for the SRNIs which rendered a required SRNI N32 inoperable and unable to perform its specified safety function.

Significance: The inspectors assessed the significance of the finding using IMC 0609, Appendix A, "The Significance Determination Process for Findings At-Power." Using the

C3-527

FPSC EXH No. 7
03/18/2024
ADMITTED

C3-630

screening questions in IMC 0609, Appendix A, Exhibit 2, “Mitigating Systems Screening Questions,” section C, “Reactor Protection System (RPS),” the performance deficiency screened to very low safety significance (Green) because the finding only affected a single RPS trip signal to initiate a reactor trip AND the function of other redundant trips or diverse methods of reactor shutdown (e.g., other automatic RPS trips, alternate rod insertion, or manual reactor trip capacity) was not affected. The redundant channel of the SR High Flux RPS trip was operable and IR Hi Flux and Power Range Low Power High Flux RPS trips were also not affected by the performance deficiency and remained available. Cross-Cutting Aspect: P.5 - Operating Experience: The organization systematically and effectively collects, evaluates, and implements relevant internal and external operating experience in a timely manner. Specifically, the licensee did not appropriately evaluate the relevancy of the operating experience in ICES report 452589 and recognize their failure to implement vendor recommended testing described in vendor document RRS-VICO-02-326.
Enforcement: Violation: Unit 3, TS 6.8.1.a, stated in part, that written procedures shall be established, implemented, and maintained covering the activities referenced in the applicable procedures required by the NextEra QATR. NextEra QATR, Appendix B, “Procedures,” in part stated, NextEra committed to use Appendix A, of Regulatory Guide 1.33, as guidance for establishing the types of procedures that are necessary. Regulatory Guide 1.33, Appendix A, item 9, Procedures for Performing Maintenance, subsection b, stated in part, preventive maintenance schedules should be developed to specify inspection of parts that have a specified lifetime. The SRNI BF3 detectors had a specified lifetime of ten to twenty years. Contrary to the above, from the beginning of plant operation until this inspection, the licensee failed to establish or implement a preventive maintenance schedule or predictive monitoring program to ensure the SRNI BF3 detectors were replaced prior to the end of their useful life. Enforcement Action: This violation is being treated as a non-cited violation, consistent with Section 2.3.2 of the Enforcement Policy.

EXIT MEETINGS AND DEBRIEFS

The inspectors verified no proprietary information was retained or documented in this report.

- On September 18, 2020, the inspectors presented the initial special inspection results to Mr. Michael Pearce, Site Vice President (SVP), and other members of the licensee staff.

- On October 30, 2020, the inspectors presented the final special inspection results to Mr. Michael Pearce, SVP, and other members of the licensee staff.

C3-528

FPSC EXH No. 7
03/18/2024

ADMITTED

Attachment A

C3-631

Sequence of Events for Event #1

Turkey Point Unit 3 Event #1 - Manual Reactor Trip on 08/17/2020	
Date/Time	**Description**
~2012	The licensee implemented EPU modification at Unit 3. As part of the EPU modification, the TCS runback logic was modified to initiate an automatic turbine runback to a setpoint of 85 percent ("Medium Runback") if CV-3-2011, the low pressure feedwater heater bypass control valve, indicated open by 1-out-of-2 valve position limit switches, whenever the turbine was initially operating greater than 88 percent turbine load.
8/17/2020 pre-event plant status	Unit 3 was operating at rated thermal power by average power range nuclear instrumentation at a turbine load of 888 MWe. The operators recently completed successful surveillance testing of the 3A emergency diesel generator (EDG), and the engine was being returned to standby alignment. A thunderstorm with heavy rain and lightning was ongoing during the late evening hours.
8/17/2020 ~21:08:30	CV-3-2011 spuriously opened resulting in actuating an automatic Medium Runback to a setpoint of 85 percent turbine power per the TCS runback logic circuitry. The operations crew identified that a Medium Runback occurred with the spurious opening of CV-3-2011 and entered off-normal operating procedure 3-ONOP-089, "Turbine Runback."
~21:08:30-21:08:56	During this period the TCS began closing the turbine control valves to the turbine medium runback setpoint and narrow range SG water levels initially lowered from their nominal starting point of 50 percent to around 45 percent. Lowering SG levels resulted in the opening of the feedwater regulating valves to restore level back to program level.
~21:08:56	The automatic turbine runback setpoint was reached, although the runback stopped at ~87 percent versus 85 percent. Also, turbine power did not remain stable at the setpoint, it began to gradually rise and then the turbine runback circuitry actuated again and stopped at ~82 percent turbine power. This cycling around the 82-85 percent turbine power setpoint continued multiple times.
~21:09:15	SG water levels returned to their nominal 50 percent level setpoints but continued to rise.
~21:10:00	The operations crew observed continued unexpected rising SG water levels, especially pronounced were the 3B and 3C SG water levels, that were around 65 percent narrow range level.
~21:10:30	The US directed the operators to take manual control of feedwater regulating valve for SG 3C, which was at ~75 percent level at the time and highest of the three SG.
~21:10:50	With reactor power at ~91 percent, the SM observed that all SG water levels were continuing to rise with the 3C SG narrow range water level reaching ~78 percent. Since an automatic turbine trip occurred at a setpoint of 80 percent level which would result in an automatic reactor trip, the SM directed the operations crew to manually initiate a reactor trip. Following the manual reactor trip, the operations crew entered emergency operating procedure 3-EOP-E-0, "Reactor Trip or Safety Injection."

FPSC EXH No. 7
03/18/2024

Attachment A

C3-632

ADMITTED

Sequence of Events for Event #1 (Cont.)

~21:12:00	While performing the immediate operator actions associated with procedure 3-EOP-E-0, the operators identified that the position indication lights for valve MOV-3-1432, 3B MSR Main Steam stop valve, was not illuminated. This valve receives an automatic closure signal as part of a turbine trip actuation. Attempts to manually close the valve from the control room were unsuccessful. In accordance with procedure 3-EOP-E-0, the operators took action to close the upstream Main Steam Isolation Valves (MSIVs) in order to isolate all sources of steam from the SGs and prevent an unnecessary RCS cooldown.
~21:12:05	All MSIVs were shut in accordance with 3-EOP-E-0.
~21:15	The operations crew completed the required actions for procedure 3-EOP-E-0 and entered procedure 3-EOP-ES-0.1, “Reactor Trip Response,” in order to stabilize and control the plant following a reactor trip without a safety injection present. The plant was stabilized in Mode 3 at normal operating temperature and pressure. No further noteworthy plant complications were encountered while completing the actions in procedure 3-EOP-ES-0.1.
~21:57	The operations crew completed the required actions for procedure 3-EOP-ES-0.1 and entered GOP 3-GOP-103, “Power Operation to Hot Standby,” in order to maintain the plant in Mode 3, conduct plant repairs, and prepare the plant for restart.

Sequence of Events for Event #2

Turkey Point Unit 3 Event #2 - Automatic Reactor Trip on 08/19/2020	
Date/Time	**Description**
8/19/2020 ~12:19	Reactor startup commenced, SRNI N31 was reading 44 cps and SRNI N32 was reading 36 cps according to plant computer data as determined by the licensee’s PTR. Plant startup procedure 3-GOP-301, “Hot Standby to Power Operation,” recorded N31 as the highest reading SRNI at 60 cps for initial count rate in Attachment 1.
After 12:19 during 2nd or 3rd control rod bank withdrawal	The reactor OATC on control rods and RO peer checker identified a disparity between N31 and N32 source count levels and discussed with the reactivity SRO and Unit 3 SRO. SROs discussed with SM and concurred that SRNIs were trending similarly and were operable. The SM provided direction to SROs and ROs to continue to monitor the SRNI behavior. No additional monitoring criteria were discussed.
12:53	Mode 2 entered
13:19	The OATC declared the reactor critical with control rod bank D (CBD) at 83 steps.
~13:22	The Reactivity SRO directed the OATC not to exceed 1.0 dpm SUR and to raise power in the IR to a level at 10^{-8} amps.
13:24:30	The OATC initiated a continuous 53 step rod pull from CBD 83 to CBD 136. The OATC was still attempting to withdraw control rods at the time of the automatic reactor trip
~13:24:47	SR and IR SURs on PI data reaches 0.7 dpm which was the OATC’s intended stop point.

FPSC EXH No. 7
03/18/2024

Attachment A

C3-633

ADMITTED

Sequence of Events for Event #2 (Cont.)

~13:24:50	1.0 dpm SR SUR on plant computer data, OATC and all other operators and observers stated they never saw any SUR meters exceed 0.7 dpm which was the OATC's intended control rod withdrawal
~13:24:55	Permissive (P-6) light was received. The third RO had been previously directed to deenergize SRNIs and was standing by to do so. Continuous rod withdrawal was still in progress. Operators may have been distracted by the P6 light and evolution to deenergize SRNIs.
13:25:19	Automatic reactor trip was initiated on N31 SR High flux neutron cps at about 76,660 cps. N32 was reading 814 cps (from PTR). Plant computer data indicated SUR for N31, N35, and N36 was about 3 dpm. N32 SUR was approximately 1.5 dpm. N31 was 89,421 cps and N32 was at 820 cpm per Plant computer data.
8/19/2020	The NRC Senior Resident Inspector (SRI) was informed prior to leaving the control room that N31 was about 80,000 cps and N32 was about 800 cps when the automatic reactor trip occurred.
8/19/2020	The SRI was informed by the SVP that the automatic reactor trip occurred as a result of operator error and that a 45 second/50 step rod withdrawal occurred when the OATC was attempting to establish a SUR less than 1.0 dpm. The SRI stated to the SVP that there was an instrument anomaly issue between the two SRNIs that required explanation.
8/19/2020 21:23	AR 2366002 was originated titled, "N31/32 SR Detector Response Disparity." AR 2366002 was initiated to require "reactor engineering to determine and document the acceptability of the disparity in response observed."
8/20/2020 02:45	WO 40737616 was completed to troubleshoot N31/N32/N35/N36 instrument level and SUR indications. No issues were identified. No troubleshooting for detector or cabling was directed to be performed. All troubleshooting was performed at the control room consoles and vertical panels.
~05:00	ORG convened and approved plant restart. The ORG reviewed the plant trip review restart report and discussed the status of plant equipment, including N31 and N32 responses during the August 19, 2020, reactor startup and automatic high flux trip, and human performance enhancements to ensure Unit 3 was ready for restart. Reactor Engineers verbally presented the results of an engineering evaluation performed in response to AR 2366002. The Reactor Engineering evaluation was not provided in advance or during the ORG meeting.
07:37	Unit 3 reactor startup sequence was initiated by withdrawing shutdown bank A. AR 2366002 did not have a documented immediate operability review by an SRO, but according to the Operations Director (OD), it was reviewed and verbally discussed between the SM and OD. When the SM eventually screened AR 2366002 in NAMS, the SM inadvertently screened AR 2366002 as, not applicable, but intended to screen the N32 low count rate issue compared to N31 as operable but degraded.

FPSC EXH No. 7
03/18/2024

Attachment A

C3-634

ADMITTED

Sequence of Events for Event #2 (Cont.)

14:30	NRC Region II and NRR technical staff conferenced to discuss N32 operability. Region II and NRR technical experts prepared several questions and information requests for the licensee to answer and provide. NRC staff recognized that Unit 3 had returned to Mode 1 and SRNI operability was not applicable in Mode 1. However, the NRC staff intended to challenge the licensee on its assessment of the operability of SRNI N32 as soon as possible in case of an unplanned shutdown and Mode 3 entry that required two SRNIs be operable in accordance with TS 3.3.1, Reactor Trip System Instrumentation.
8/20/2020	An off-shift SRO recognized that AR 2366002 did not receive an immediate operability determination and was screened as not applicable. The off-shift SRO initiated AR 2366093, “Potential Inoperability of N31 [32],” and notified the control room operators of the concern.
23:59	Unit 3 was manually tripped and stabilized in Mode 3, Hot Standby. TSs required two SRNIs be operable in accordance with TS 3.3.1, Reactor Trip System Instrumentation.
8/21/2020	AR 2366002 operability notes changed from not applicable to operable but degraded and a prompt operability determination was scheduled to complete at 2300 on 8/21/2020.
8/21/2020 14:11	NRC Resident Inspectors provided questions and information requests to the licensee that challenged N32 operability and requested those answers be provided prior to the next Unit 3 reactor startup.
8/22/2020	AR 2366002 Prompt Operability Determination was completed and associated with AR 2366093. The conclusion was N32 would not have been able to perform its safety function and was made after vendor support countered the original reactor engineering evaluation and suspected that the order of magnitude of the sensitivity disparity between the SR channels was larger than previously documented and appeared to be increasing over time.
8/22/2020 00:17	Control room operators declared N32 inoperable.
8/24/2020	The licensee implemented a repair plan with vendor support to restore the sensitivity of the SRNI N32 detector to an operable condition in WO 40738044, “U3 N32 Increase Detector Sensitivity.” WO 40738044 increased N32 high voltage detector setting from a nominal 1,500 VDC to 1,750 VDC. A successful post maintenance test for N32 was completed on August 24, 2020, during a Unit 3 reactor startup and invoking TS 3.0.6 to demonstrate N32 operability by comparing its cps level at six discrete points in the reactor startup sequence and verifying that N31 and N32 channels did not deviate beyond 1.0 dpm.
8/24/2020	The licensee initiated AR 2366359, “Apply Multiplication Factor Trends to NI Detector Monitoring.” AR 2366359 included actions to replace the N32 detector during the next refueling outage and to perform multiplication factor trending during the fall 2021 Unit 4 refueling outage for both Unit 4 SRNIs.

FPSC EXH No. 7
03/18/2024

ADMITTED

Attachment A

C3-635

Sequence of Events for Event #3

Turkey Point Unit 3 Event #3 – Manual Reactor Trip on 08/20/2020	
Date/Time	**Description**
08/20/2020 07:52	Unit 3 reactor was critical
08/20/2020 15:30	Unit 3 entered Mode 1
08/20/2020 19:23	The operating crew received a Distributed Control System (DCS) Secondary Trouble Alarm and checked the ARP, 3-ARP-097-CR.D, “Control Room Response – Panel D.” An operator navigated to step A to the DCS Secondary Trouble page that identified the 3A/3B/3C/3D MSR, 3A RHDT, and 3A/3B HDT controllers were in manual instead of automatic. Operators restored Level Control Valves for 3A/3B/3C/3D MSR, 3A RHDT, and 3A/3B HDT to Automatic Control on DCS to support Unit 3 going online.
08/20/2020 23:53	When reactor power was 34 percent, operators noted lowering SG water level below program band of 50 percent and the feedwater regulating valves demand was higher than the expected 60 percent.
08/20/2020 23:54	The operating crew took manual control of the feedwater regulating valves and opened the valves. SG level continued to lower.
08/20/2020 23:54	The operating crew received a SG C Level Deviation / Cntrl Trouble alarm at 40 percent level. The operating crew followed the ARP to open FCV-3-499, FW Bypass Valve, and take manual control of the feedwater controller to maintain SG level. The 3C SG level was stabilized at 35 percent.
08/20/2020 23:55	The operating crew discovered the feedwater recirculation master controller was in manual and all three recirculation valves were fully open. The SM directed the operator to close the recirculation valves. The master control was selected in manual and demanded closure of the feedwater recirculation valves.
08/20/2020 23:55	The feedwater recirculation valves were closed from 100 percent to 60 percent. Due to the lowering of feedwater pump suction pressure, the 3B SGFP tripped on low suction pressure (220 psig).
08/20/2020 23:58	The SM directed the operators to insert a manual reactor trip due to the loss of the only running SGFP.
08/20/2020 23:59	Unit 3 reactor trip occurred.
08/20/2020 23:59	Auxiliary Feedwater (AFW) auto started and provided feedwater to the SGs as expected.
08/20/2020 23:59	Due to lowering RCS T-average and pressurizer level, the MSIVs were closed to limit the cooldown
08/21/2020 00:02	SG level continued to rise until AFW flow was reduced by the operators to control level.

FPSC EXH No. 7
03/18/2024
ADMITTED

Attachment B

C3-636

UNITED STATES
NUCLEAR REGULATORY COMMISSION
REGION II
245 PEACHTREE CENTER AVENUE N.E., SUITE 1200
ATLANTA, GEORGIA 30303-1200

August 28, 2020

MEMORANDUM TO: John Zeiler, Senior Resident Inspector, Team Lead
Projects Branch 4
Division of Reactor Projects

FROM: Laura A. Dudes **/RA/**
Regional Administrator

SUBJECT: SPECIAL INSPECTION CHARTER TO EVALUATE PLANT PERFORMANCE DURING MULTIPLE REACTOR TRIPS AT TURKEY POINT NUCLEAR POWER STATION

You have been selected to conduct a Special Inspection (SI) to assess the circumstances surrounding three reactor trips that occurred at Turkey Point Unit 3 on August 17, August 19; and August 20, 2020.

A. Background

During the week of August 17, 2020, Turkey Point Unit 3 experienced three reactor trips, one of which was automatically initiated by the reactor protection system and two were the result of plant operators taking action to manually trip the reactor. The first trip, manually initiated by plant operators, occurred on August 17, 2020, at 2113 from approximately 92 percent power in response to rising steam generator water levels that approached the automatic turbine trip setpoint. The second trip was automatically initiated by the plant's reactor protection system and occurred on August 19, 2020, at 1324. Specifically, the source range nuclear instrument (SRNI) N31 sensed a high neutron flux condition and initiated the trip during reactor startup. The third trip, manually initiated by plant operators, occurred on August 20, 2020, at 2354 from approximately 35 percent power in response to the loss of the single operating steam generator feedwater pump (SGFP).

Management Directive (MD) 8.3, NRC Incident Investigation Program, and Inspection Manual Chapter 0309, Reactive Inspection Decision Basis for Reactors, directs staff to provide a detailed list of deterministic criteria that can be used on their own or in conjunction with a probabilistic risk assessment as a basis for decision making when considering a Special Inspection (SI) following a significant operational event. In the case of the Turkey Point unit 3 reactor trips that occurred during the week of August 17, 2020, operational performance, equipment performance and licensee decision making was deemed to meet the deterministic-only criteria specified in enclosure 2 of MD 8.3. As a result, Region II decided to initiate an SI.

CONTACT: Randall Musser, RII/DRP
(404) 997-4603

FPSC EXH No. 7
03/18/2024
B. Saple ADMITTED

C3-637

The Special Inspection Team (Team) will review the causes of the events, and Turkey Point's organizational and operator responses to the events. The Team will perform interviews to understand the scope of operator actions performed during the events.

To accomplish these objectives, the Team will:

1. Review the circumstances leading up to the events on August 17, 2020, August 19, 2020, and August 20, 2020, and develop a Sequence of Events leading up to the incidents and the actions taken by Turkey Point to date to address issues raised by the events;

2. For each event, review and assess crew operator performance and crew decision making, including their adherence to procedures, expected roles and responsibilities, including reactivity management by the operators, reactivity management plans provided by nuclear engineering, the command and control function associated with reactivity manipulations, the use of procedures, log keeping, and overall communications;

3. Review the adequacy of just-in-time training and licensed operator startup certification training as it relates to reactivity control;

4. Evaluate the extent of condition for identified issues with respect to the other operating crews;

5. Review and assess the effectiveness of the licensee's response to these events and corrective actions taken to date;

6. Review and evaluate the actions and reviews taken by the licensee prior to authorization for each restart of Turkey Point Unit 3, including the effectiveness of the Onsite Review Group;

7. Assess the decision making and actions taken by the licensee's personnel to determine if there are any implications related to schedule pressure or the site's safety culture;

8. Evaluate the licensee's application of pertinent industry operating experience;

9. Evaluate equipment reliability and configuration control for the systems that were challenged during the trips which occurred on August 17 and August 20, considering the relationship with the Extended Power Uprate (EPU) with additional focus on EPU single point trip vulnerability.

10. Conduct an entrance and exit meeting; and

11. Document the inspection findings and conclusions in a Special Inspection Team final report within 45 days of inspection completion.

C3-635

FPSC EXH No. 7
03/18/2024
C. GADDIS ADMITTED

C3-638

Inspection Procedure (IP) 93812, Special Inspection Team, provides additional guidance to be used during the conduct of the inspection. Your duties will be as described in IP 93812 and should emphasize fact-finding in its review of the circumstances surrounding the events. Safety concerns identified that are not directly related to the event should be reported to the Region II office for appropriate action. You will conduct an entrance and begin inspection no later than August 31, 2020. Decisions regarding whether and what activities need to be performed onsite will take into account concerns related to COVID-19. Discuss any planned onsite activities with regional management before proceeding.
It is anticipated that the on-site portion of the inspection will be completed during the same week. An initial briefing to Region II management will be provided at approximately 4:00 p.m., August 31, 2020. In accordance with IP 93812, you should promptly recommend a change in inspection scope or escalation if information indicates that the assumptions used in the MD 8.3 analysis were not accurate. If, during your investigation you identify matters that involve potential wrongdoing on the part of licensee employees or licensee contract employees, you are reminded to follow the guidance in MD 8.8, Management of Allegations. At the completion of the inspection you should provide recommendations for improving the Reactive Inspection (RI) process based on any lessons learned.

This charter may be modified should you develop significant new information that warrants review.

ADAMS ACCESSION NUMBER:**ML20241A055**

OFFIC	RII:DRPRP	RII:DRP	RII:ORA	
NAME	R. Musser	M. Miller	L. Dudes	
DATE	8/27/2020	8/27/2020	8/28/2020	

C3-536

FPSC EXH No. 7
03/18/2024

Attachment C

C3-639

IMC 0609 Appendix M ADMITTED

Appendix M, "Significance Determination Process Using Qualitative Criteria"
(ADAMS Accession No. ML18183A043)

EXHIBIT 1 - Results of the Initial Evaluation

1. Describe the influential assumptions used in the initial evaluation. Because the performance deficiency involved errors of commission and involved multiple errors by an entire crew of licensed operators, it was assumed that time critical operator actions will have some level of dependency to the original error. SPAR-H and THERP would treat all of these Human Error Probabilities (HEPs) as being completely dependent due to the same crew, in the same spot, in a very short time frame, with mostly the same cues, must diagnose the plant conditions in order to take the required actions. This assumption was overly conservative. Using Appendix M allows an opportunity to make more realistic assumptions with respect to operator actions.

   Additionally the normal 100 percent power models, used by both the licensee and SPAR models, do not accurately capture the unique nature of a SR Continuous Rod Withdrawal Casualty (No temperature moderation, more positive moderator temperature coefficient, Xenon not at equilibrium since less than 50 hours since shutdown, system designed to mitigate an ATWS were not in service such as AMSAC and ESFAS, and minimal decay heat loading, and AFW system already being in service for startup.) The licensee and SRA developed a Low Power Model of this event using WCAP-15381-NP-A revision 2, "WOG Risk-Informed ATWS Assessment and Licensing Implementation Process," (ADAMS Accession No. ML072550560). This methodology addressed dependency of operator actions and the unique equipment line up.

   A modified Initiating events risk assessment approach was being proposed for use in this case vice a conditional assessment as this event was centered around the performance of a single crew of operators during a normal start up evolution. The unaffected base case sequences for an ATWS were subtracted from the conditional case (Where HEPs were adjusted for dependency and influence of the performance deficiency.) This ensured the change in risk due to the performance deficiency was accurately illustrated.

   1) Dummy IEV, Operator Action for Reactivity Management Causes Source Range High Flux set point to be reached was set to 1.0
   2) All other IEs were set to False.
   3) Since a reactor startup was in progress per 3-GOP-301, "Hot Standby to Power Operation," Rev. 53, the following equipment was in service: Both Primary PORVs were in service and unblocked, the motor driven start up feedwater pump (a credited AFW source) was in service and lined up to feed both Steam Generators. Therefore the Basic Events PPR-MOV-FC-535, PORV 1 (PCV-456) BLOCK VALVE 535 CLOSED DURING POWER, and PPR-MOV-FC-536, PORV 2 (PCV-455A) BLOCK VALVE 536 CLOSED DURING POWER were set to FALSE since the valves were open, and AFW-XHE-XM-START, OPERATOR FAILS TO START AFW GIVEN NO SIGNAL was set to FALSE since AFW was already in service.
   4) Operator Actions RPS-XHE-XM-OAMG, Operators fail to manually trip reactor by opening breakers to MG set, and OAMG-XE-BRKLOC, Operators fail to open RPS trip breakers locally were not considered dependent on the performance deficiency since they only performed if RPS trip Breakers fail mechanically and diagnosis was implied on that path.

FPSC EXH No. 7
03/18/2024

Attachment C

C3-640

5) ADMITTED Action OAMG-XE-CRIN, Operators failed to manually insert control rods for 60 secs, can occur during all paths even without diagnosis as the next major cue the operator will get was power in the IR reaching 10^{-8} amps and the order 3-GOP-301 was to level power at 10^{-8} amps. The HEP would have to be adjusted to account for fact operator would have to be monitoring IR power levels which was affected by the performance deficiency (but operator does not have to recognize an RPS failure has occurred.)

6) RPS-XHE-XE-NSIGNL, Operators manually trip reactor with RPS failure and no RPS signal present was Set to TRUE for all Conditional Cases. The same operators would have to diagnose the same cues, in the same location and recognize an RPS action did not occur. SPAR-H and THERP tools would determine this action was completely dependent upon the original human performance error.

7) Operator Actions RPS-XHE-XE-SIGN, Operators manually trip reactor with RPS failure and RPS signal present, CVC-XHE-XM-BORATION, Operator fails to initiate emergency boratian and OAMG-XE-CRIN, Operators fail to manually insert control rods for 60 secs, were not assumed to be completely dependent to the original error due to the additional cues and additional time for the operators to take those actions despite the SPAR-H and THERP guidance. These HEPs were varied from Nominal to True using the human error tools discussed in order to develop the conditional cases presented below.

8) All rod motion was assumed to stop at the time the RPS actuation did or should have occurred. If RPS failed and the operator continued to withdraw control rods, there would be less time available and HEPs would have to be adjusted to reflect this. The conditional cases performed for sensitivity would address this fact.

2. Provide sensitivity results on the key influential assumptions. The uncertainty associated with the HEPs interrelation and magnitude of adjustments creates some degree of sensitivity so multiple cases were being presented around the most representative case as part of the quantitative section of the Appendix M worksheet. Four HEPs were adjusted from Nominal to 1.0 using multiple approaches to develop a sensitivity. SPAR-H and THERP dependency principles, use of the IDHEAS-ECA human reliability calculator tool developed by NRC Research, the guidance in the WCAP, and analysis judgement. The Operators failing to initiate Emergency Boration HEP was the most sensitive. The conditional case table attached illustrates these sensitivities.

3. Identify any information gaps in defining the influential assumptions used in the initial evaluation. The human factors presented several problems. The same operating crew must properly diagnose the condition using many of the same cues within a relatively short time period. However, the large number of observers and operators on shift does make it more likely that someone would diagnose the ATWS before power reached the Power Range and direct action to be taken. Since the operator response times were based off an ATWS from 100 percent power, the crew would have had additional time available. To account for this the immediate actions by the operator were treated separately from emergency boration when performing the sensitivities.

Initial Evaluation Result: 3.95E-7

FPSC EXH No. 7
03/18/2024

C3-641

ADMITTED EXHIBIT 2

- Considerations for Evaluation of Decision Attributes

Table 1 - Qualitative Decision-Making Attributes for NRC Management Review

Decision Attribute	Basis for Input to Decision - Provide qualitative and/or quantitative information for management review and decision making.
Defense-in-Depth	Degraded by PD. Operators actions were credited to backup RPS and trip the plant and to Emergency Borate in order to prevent core damage in some accident sequences. PD also affect probability of future human errors since the follow up operator actions were dependent on the original PD human error. (Note: Factor is accounted for in the SPAR models as existing HEPs)
Safety Margin	RPS has 3 levels of protection for a continuous rod withdrawal casualty, SR Hi Flux, IR Hi Flux, and Power Range Low Range Hi Flux trips. Both SR and IR trips only require one trip signal of two available channels to cause a scram. The accident analysis does not credit operator action for this event. Overall change in safety margin was minimal. Note: the accident analysis was not required to consider an RPS Failure/ATWS at that time.
Extent of Condition	None. Inspectors concluded this PD was specific to this crew and these specific circumstances.
Degree of Degradation	Entire crew and observers present failed to diagnose the condition prior to the scram. Not limited to one operator. Same crew would have to diagnose and take required operator actions as plant conditions changed. Group think was observed by this organization with respect to the operability of the SRNI N32 the following day, so it cannot be ruled out. However, given the number of additional cues which would present themselves as the event progressed (power entering IR and PR, PORVs Lifting, steaming to condenser, AFW flows increasing) it was likely to “break” the dependency particularly later in the event given the number of crew and observers present. (Note: this factor was represented in the SPAR model through the HEP adjustments considering dependency.)

C3-539

FPSC EXH No. 7
03/18/2024
ADMITTED

C3-642

	Limited to this reactor startup. Not believed to be a generic negative training issue among operators.
Recovery Actions	Recovery would require operators diagnosing the condition. The milestone the crew was looking for was 10^{-8} amps in the IR. It would be expected that this cue would cause the operator to stop shimming out and shim rods in to attempt to level power (arresting the CRW) and draw attention to other plant parameter including SUR. Diagnosis of an ATWS should be clearly obvious and credited operator actions directed and taken (IE attempt to manually trip the reactor, initiate auxiliary feedwater and emergency boration.) As additional cues become available, and with the crew size and number of observers, the probability of diagnosing the condition increases. Recovery actions could still be performed, from the control room and provide mitigation even if performed late. (Note: The quantitative review conservatively did not consider recovery.)
Additional Qualitative Considerations	SUR NI 32 was inoperable and SR SUR indication for N32 was lagging N31 and IR SUR channels N35 and N36. This false indication may have confused operators but even N32 SUR was <1.5 DPM at the time of the scram and would help diagnosis. Note: this factor was considered using the HEP tool IHDEAS-ECA.) The SR N32 Instrument Channel was functional and would eventually have processed a Hi Flux Scram, albeit in a untimely manner (Approximately 60+ seconds late).

C3-540

FPSC EXH No. 7
03/18/2024

C3-643

ADMITTED

While certainly warranted a reactive inspection via the IMC 0309, “Reactive Inspection Decision Basis for Reactors,” (ADAMS Accession No. ML111801157), and MD 8.3 processes, quantitative tools were developed and identified to address the wide range of uncertainty and better model the specifics of this event. The representative case has a CCDP of 3.95E-7 which was consistent with the results the licensee developed (once modeling differences were resolved.) The methodology used has been reviewed by the NRC and a Safety Evaluation Report (SER) was developed, (Final Safety Evaluation for Pressurized Water Reactor Owners Group (PWROG) Topical Report (TR) WCAP-15831-P, Revision 1, "WOG Risk-Informed ATWS Assessment and Licensing Implementation Process" (TAC NO. MB5741) (ADAMS Accession No. ML070880469), dated May 8, 2007).

Taking the qualitative factors into account, the SRA compared this event with four other reactivity management events, most of which used, Appendix M; respectively, (with SDP): Millstone (White), Pilgrim (White), Callaway (Green) and Oyster Creek (Green). In each event, operators failed to adequately monitor key reactor plant parameters during reactivity additions and involved multiple members of the operating crew. The events where positive reactivity was being added to the core by the operators were considered more significant.

1) The Millstone example sets a particularly high bar. Operators defeated an automatic RPS trip 4 times during the event and were independently adding multiple sources of both positive and negative reactivity simultaneously. Since this operator action reduced defense in depth in addition to initiating the event, this event was clearly more significant than Turkey Point’s event.
2) The Pilgrim example; the reactivity control team was operating independently with respect to inserting and withdrawing control rods to control heat up rate. They did not consult with reactor engineering and did not have any direct oversight by the SROs or Shift Manager. They inadvertently drove the reactor subcritical and then did not account for changes in temperature when restoring rods to their original positions. It was discovered that this knowledge gap was not isolated to one crew. It should be noted there was no quantitative analysis to balance this evaluation. The underlying Turkey Point event was much more significant but based upon the qualitative factors alone Pilgrim was more significant due to multiple errors, more widespread extent of condition, and not engaging oversite or support.
3) The Callaway example was less significant than Turkey Point’s event since in the Callaway event no positive reactivity was being added, operators were distracted by other indications and stopped in the startup procedure.
4) The Oyster Creek example was similar to Callaway’s in that operators stopped in the shutdown procedure and had two re-criticality events due to plant cool down. Operators were aware of the condition and ranged up IR Channels. Turkey Point was more significant in that positive reactivity was being added and the Oyster Creek event did not result in a transient.

The analyst also considered the fact that IMC 0609, Appendix M, has been revised since 2011 and more human performance evaluation tools were available. If the new tools and procedures were applied to the Pilgrim case, it was the analyst’s opinion that Pilgrim would be characterized as a Green while Millstone would remain a White. This was based upon the emphasis in section I of the worksheet to consider the best available quantitative review of the event with uncertainties and consider that along with qualitative factors. For the Pilgrim case, the trip occurred in the IR due to multiple channels over ranging and the reactor was above the POAH. Any reactivity mismatch would be self-corrected by temperature feedback without any actions required. Even if RPS had failed, thermal limits would not have been challenged.

C3-541

FPSC EXH No. 7
03/18/2024

C3-644

ADMITTED

While Millstone event, operators actively defeated RPS, a level of defense in depth designed to mitigate the condition seen, as well as mismanage reactivity. Additionally, this was an act of commission which the PRA models do not account for and HRA tools still cannot accurately quantify.

Based on these factors, the qualitative factors in the Turkey Point case did not justify escalating the finding's significance an order of magnitude above the quantitative evaluation results.

Conclusion:

Considering both the quantitative and qualitative factor involved and comparing this case to past precedence, the SRA recommended characterizing this PD as very low safety significance (Green) based upon the quantitative factors and using qualitative factors to address sensitivity.

C3-542

FPSC EXH No. 7
DOCUMENTS REVIEWED
03/18/2024
ADMITTED

C3-645

Inspection Type Procedure		Designation	Description or Title	Revision or Date
93812	Calculations	CN-CPS-09-67	Steam Generator Water Level Analysis for the Turkey Point Units 3 and 4 Extended Power Uprate	Rev. 0
		CN-PCSA-12-10	Steam Generator Water Level Analysis to Support Feedwater Control System Tuning at EPU Conditions for Turkey Point 3	Rev. 0
		PTN-BSHM-08-011	Feedwater & Condensate System Equipment Selection, Performance Evaluation, and Operation Transients Review	Rev. 3
	Corrective Action Documents	AR 2299046	Slow Response from FCV-3-478 during Unit 3 Manual Runback	1/23/2019
		AR 2365707	Indicating lights lost during reactor trip	8/17/2020
		AR 2365708	CV-3-2011 valve failed open	8/17/2020
		AR 2365714	3B and 3C feedwater regulating valves slow to respond during turbine runback	8/18/2020
		AR 2365716	Unit 3 reactor manually tripped	8/18/2020
		AR 2365716	PTR Restart Report - Unit 3 Manual Reactor Trip for CV-3-2011 Failed Open	8/17/2020
		AR 2365717	Unexpected response during turbine runback in TCS	8/18/2020
		AR 2365722	Low pressure turbine reheat intercept valve 3-10-012 has bad indication	8/18/2020
		AR 2365723	Low pressure turbine reheat stop valve 3-10-015 has bad indication	8/18/2020
		AR 2365970	PTR Restart Report - Unit 3 Automatic Trip on Source Range High Flux N31	8/19/2020
		AR 2366158	PTR Restart Report - Unit 3 Manual Reactor Trip on Loss of Las Feed Pump	8/20/2020
		PCR 2366174	GOP-301 procedure changes to check controllers in Auto	8/21/2020
	Drawings	5613-M-3074	Feedwater System PI&D	Rev. 36
	Engineering Changes	EC-246849	Turbine Digital Control System	Rev. 1
		EC-246870	Design Change Package Description: Feedwater Regulating Valve Upgrade	Rev. 8
		EC-246935	Main Feedwater Pump Rotating Assembly Replacement – Extended Power Uprate	Rev. 3
		EC-295196	Temporary Modification Change: Disable Unit 3 Medium Runback on CV-3-2011	Rev. 0

FPSC EXH No. 7
DOCUMENTS REVIEWED
03/18/2024
ADMITTED

C3-646

Inspection Type Procedure		Designation	Description or Title	Revision or Date
93812	Miscellaneous		ORG Agenda/Meeting Number 20-028: Unit 3 Post Trip Review (Event on 08/19/20)	8/20/2020
			ORG Agenda/Meeting Number 20-029: Disable Unit 3 Medium Runback on CV-3-2011 Opening	8/20/2020
			ORG Agenda/Meeting Number 20-030: U3 Manual Reactor Trip – Loss of last Feed Pump (3B SGFP Tripped)	8/26/2020
			ORG Agenda/Meeting Number 20-027: Unit 3 Post Trip Review (Event on 08/17/2020)	8/19/2020
		JIT Training	Just in Time Training documents related to Events #1 - #3	8/18/2020-8/20/2020
		Operator Logs	Unit 3 operator logs between 08/16/2020 – 08/26/2020	
	Procedures	3-ARP-097.CR.C	Annunciator Response Procedure Control Room Response – Panel C	Rev. 8
		3-ARP-097.CR.D	Annunciator Response Procedure Control Room Response – Panel D	Rev. 21
		3-EOP-E-0	Reactor Trip or Safety Injection	Rev. 16
		3-EOP-ES-0.1	Reactor Trip Response	Rev. 16
		3-GOP-103	Power Operation to Hot Standby	Rev. 31A
		3-GOP-301	Hot Standby to Power Operations, completed for 8-19-20 startup	Rev. 53
		3-ONOP-089	Turbine Runback	Revs. 3, 4
		EN-AA-205-1100	Design Change Packages	Rev. 4
		ENG-QI-1.5	Calculations	Rev. 12
		LI-AA-1000	On-Site Review Group	Rev. 14
		OP-AA-1000	Conduct of Infrequently Performed Tests or Evolutions	Rev. 16
	Work Orders	40629402	FCV-3-498 SG C main feedwater flow control valve link test	11/04/2018
		40649557	FCV-3-498 slow response (runback) - install valve link laptop	3/12/2019
		40657590	Boroscope inspect feedwater piping with valve FCV-3-478 out of service	4/05/2020
		40737414	Investigate CV-3-2011 valve failed open	8/17/2020
		40737415	MOV-3-1432 indicating lights lost during 8/17/20 manual reactor trip event	8/17/2020

C3-544

FPSC EXH No. 7
03/18/2024

C3-647

LIST OF ACRONYMS

ADAMS Agencywide Documents Access and Management System
ADMITTED

AFW	Auxiliary Feedwater
AMSAC	ATWS Mitigating System Actuation Circuitry
AR	Action Request
ARP	Alarm Response Procedure
ATWS	Anticipated Transient Without Scram
BF3	Boron Trifluoride
CAP	Corrective Action Program
CBD	Control Rod Bank D
CCDP	Conditional Core Damage Probability
cps	Counts Per Second
DCS	Distributed Control System
dpm	Decade Per Minute
ECC	Estimated Critical Configuration
ECP	Employee Concerns Program
EDG	Emergency Diesel Generator
EOP	Emergency Operating Procedure
EPU	Extended Power Uprate
ESFAS	Engineered Safety Features Actuation System
FIN	Finding
FMEA	Failure Modes and Effects Analysis
GOP	General Operating Procedure
HDT	Heater Drain Tank
HEP	Human Error Probabilities
ICES	INPO Consolidated Event System
IMC	Inspection Manual Chapter
INL	Idaho National Laboratory
INPO	Institute of Nuclear Power Operations
IP	Inspection Procedure
IR	Intermediate Range
IRNI	Intermediate Range Nuclear Instrument
I&C	Instrumentation and Control
JIT	Just-in-Time
LCO	Limiting Condition for Operation
LER	Licensee Event Report
MD	Management Directive
MSIV	Main Steam Isolation Valve
MSR	Moisture Separator Reheater
MW	Megawatts
MWe	Megawatts Electric
NAMS	Nuclear Assets Management System
NCV	Non-Cited Violation
NPP	Not Present Performance
NRC	Nuclear Regulatory Commission
NRR	Office of Nuclear Reactor Regulation
NSCMP	Nuclear Safety Culture Monitoring Panel
OATC	Operator at the Controls
OCC	Outage Control Center
OD	Operations Director
OP	Operating Procedure
ORG	Onsite Review Group

C3-545

FPSC EXH No. 7
03/18/2024
ADMITTED

C3-648

LIST OF ACRONYMS

P-6	Source Range Block Permissive
pcm	Percent Mille
PD	Performance Deficiency
POAH	Point of Adding Heat
PORV	Power-Operated Relief Valve
PRA	Probabilistic Risk Analysis
PTR	Post Trip Report
PWROG	Pressurized Water Reactor Owners Group
QATR	Quality Assurance Topical Report
RCS	Reactor Coolant System
RHDT	Reheater Drain Tank
RO	Reactor Operator
RPS	Reactor Protection System
SDP	Significance Determination Process
SER	Safety Evaluation Report
SERP	Significance and Enforcement Review Panel
SG	Steam Generator
SGFP	Steam Generator Feedwater Pump
SI	Special Inspection
SIT	Special Inspection Team
SLT	Site Leadership Team
SM	Shift Manager
SOER	Significant Operating Experience Report
SPAR	Simplified Plant Analysis Risk
SR	Source Range
SRA	Senior Risk Analyst
SRI	Senior resident inspector
SRNI	Source Range Nuclear Instrument
SRO	Senior Reactor Operator
SUR	Startup Rate
SVP	Site Vice President
TCS	Turbine Control System
TS	Technical Specification
US	Unit Supervisor
VDC	Volts Direct Current
WO	Work Order
1/M	Inverse Count Rate

C3-546

2020 Outages			
Unit	**Description**	**Duration**	**Replacement Power Costs**
TP 4	The Exciter Permanent Magnet Generator failed due to a combination of the aged condition of the stator windings and exposure to moisture.	July 5 - 20	$1,453,970
TP 3	Unit 3 experienced an automatic turbine runback, initiated after failure of multiple valves on the secondary feed system. These valve failures were a result of an equipment failure with the plant Secondary Control.	November 7 - 21	$ 1,290,604

FPSC EXH No. 9
03/18/2024
ADMITTED

C5-711

2021 Outages

Unit	Description	Duration	Replacement Power Costs
SL 2	The 4kV breaker for the 1A Auxiliary Transformer had a leaking SF6 gas suppression bottle. The unit was required to be removed from service for replacement of the breaker.	January 14 -16	$ 220,926
SL 2	The legacy drawings for the UV relay assemblies in the control element drive mechanism control system were changed in 1983 and did not conform to St. Lucie Unit 2 train and channel design conventions. This legacy defect resulted in inadvertently mis-assigning power to two of the four UV relays to the incorrect train of power when the rod control system was replaced in 2019.	January 20 - 24	$ 959,524
TP 3	A power reduction caused by a condenser tube leak.	February 2 - 10	$ 1,146,159
TP 3	During the restoration phase after planned testing the unit experienced an automatic shut down. FPL determined the most probable cause was hardened graphite grease on the cell switch.	March 1 - 4	$ 1,206,743
SL 1	During a restart from a planned outage, FPL determined the Lower Gripper Coils for a group of control element assemblies had malfunctioned due to damage from excessive current.	May 14 - 17	$ 1,517,511
TP 3	The units Turbine Control Valve (TCV) unexpectedly closed. During inspection the actuator stem (rod) was found sheared.	August 13 - 25	$ 2,766,857
TP 3	An outage at TP3 was extended when the Manipulator Gripper encountered issues during replacement and a reactor coolant system leak was identified while bringing the unit back online during inspections.	November 7 - 20	$ 10,054,734
SL 1	SL1 was manually tripped due to the loss of the feedwater level control system. While replacing a Pressure Differential Indicating Switch, the technician made inadvertent contact with the enclosure housing resulting in the supply fuse to blow.	December 10 - 12	$ 1,434,048

C5-593

2022 Outages

Unit	Description	Duration	Replacement Power Costs
SL 2	During testing of the Rod Control system, the #27 Control Element Drive Mechanism (CEDM) motor malfunctioned and the unit was manually shut down.	January 6 - 21	$ 8,693,593
TP 4	Turkey Point Unit 4 suspended the power ascension after a refueling outage to hold power at 50% in order to troubleshoot and repair a malfunctioning Flux Map Detector system.	Apr 14 (23.67 hrs.)	$ 94,275
SL 2	This was a power reduction as a result of a 2A Heater Drain Pump motor tripping due to the motor windings electrically failing to ground during an extreme weather event. This occurred simultaneous with a Tornado Warning being issued by the State Watch office.	June 6 - 12	$ 328,110
SL 1	During the final scheduled power reduction to take the unit offline, the 1A Main Feed Pump tripped due to its recirculation valve failing to open. The valve failed to open due to an internal pneumatic blockage.	Sep 22 (1.22 hrs.)	$ 33,117
SL 1	On October 28, 2022, the St. Lucie Unit 1B drain cooler developed a tube leak. To maintain reactor coolant temperature within limits reactor power was reduced to approximately 98% for 3.57 days.	Oct 28 – Nov 1	$ 40,077
SL 1	On November 1, 2022, reactor power was further reduced to approximately 97% for 13.4 days to get a safe boundary and isolate the issue to facilitate a repair power for the drain leak.	November 1 -14	$ 271,023
SL 1	On November 14, reactor power was again reduced to approximately 75% to allow for isolation and repair of the 1B drain cooler for 4.76 days.	November 14 -18	$ 868,523
SL 2	AC fuse blew causing the loss of a circuit that powered the condensate pump recirculating valve. As a result, this required down powering the unit to 91%.	Dec 19 (12.07 hrs.)	$ 28,676
TOTAL			$32,408,470

FPSC EXH No. 10
03/20/2024
ADMITTED

E2

10

As filed in Docket No. 20220001-EI, FPL's Response to Staff's Second Set of Interrogatories Nos. 4 and 9

(Including Attachments)

E1

FPSC EXH No. 10
03/20/2024

ADMITTED

E3

Florida Power & Light Company
Docket No. 20220001-EI
Staff's 2nd Set of Interrogatories
Interrogatory No. 4

QUESTION:
The following questions are with respect to Florida Power & Light's (FPL or Company) Petition for Approval of Fuel Cost Recovery and Capacity Cost Recovery Net Final True-Ups for the Period Ending December 2021 and 2021 Asset Optimization Incentive Mechanism Results (Petition).

Please refer to the Direct Testimony of FPL witness Dean Curtland for the following question. Please provide the replacement power costs, if any, associated with the: July 2020 outage of Turkey Point Unit No. 4; November 2020 outage of Turkey Point Unit No. 3; January 2021 outage of St. Lucie Unit No. 2; March 2021 outage of Turkey Point Unit No. 3; May 2021 outage of St. Lucie Unit No. 1; and the August 2021 outage of Turkey Point Unit No. 3. Please also show how any replacement power cost amounts were calculated.

RESPONSE:
The replacement power cost for July 2020 outage of Turkey Point Unit No. 4 was $1,453,970; November 2020 outage of Turkey Point Unit No. 3 was $1,290,604; January 2021 outage of St. Lucie Unit No. 2 was $1,180,450; March 2021 outage of Turkey Point Unit No. 3 was $1,206,743; May 2021 outage of St. Lucie Unit No. 1 was $1,517,511; August 2021 outage of Turkey Point Unit No. 3 was $2,766,857. The calculations are provided in Attachment No. I to this Interrogatory. FPL applies the proportion of fuel used during the same period for each fuel type, as summarized on Schedule A3, to the amount of outage time, in hours, experienced. Fixed natural gas costs are removed from the calculation since those expenses have already been incurred.

E2

FPSC EXH No. 10
03/20/2024

ADMITTED

E4

Florida Power & Light Company
Docket No. 20220001-EI
Staff's 2nd Set of Interrogatories
Attachment No. I, Interrogatory No. 4
Page 1 of 6

Turkey Point Unit 4

Event Start	Event End	Seq. #	Event Title	MW Loss	Outage Hours	MWh Loss	Replacement Cost ($/MWh)	Replacement Cost ($)	TN4 Fuel Cost ($/MWh)	Nuclear Fuel Cost ($)	Net Replacement Cost ($)
A	B	C	D	E	F = (B - A) * 24	G = E * F	H = WA $/MWh	I = G * H	J = TN4 $/MWh	K = J * G	L = I - K
7/5/2020 21:09	7/20/2020 14:54	1	Automatic Rx Trip due to main gen lockout from loss of exciter	821.00	353.75	290,429	$11.30	$3,281,797	$6.42	$1,863,313	$1,418,484
7/20/2020 14:55	7/21/2020 15:00	2	Automatic Rx Trip due to main gen lockout from loss of exciter	301.69	24.08	7,266	$11.30	$82,101	$6.42	$46,615	$35,486
					377.83	**297,694**					**$1,453,970**
											$92,356 /Day

July 2020 - A4 Data	
TN4 Fuel Cost	**TN4 Heat Rate**
0.57	11,271
TN4 $/MWh	
$6.42	

July 2020 - A3 Data								
Fuel	**MWh**	**% Mix**	**Fuel Cost $**	**$/MWh**	**Demand $**	**Rev. Fuel Cost $**	**$/MWh**	**WA $/MWh**
Heavy Oil	7,443	0.07%	$967,596	$130.01	$0	$967,596	$130.01	$0.10
Light Oil	3,894	0.04%	$500,080	$128.44	$0	$500,080	$128.44	$0.05
Coal	185,425	1.85%	$6,010,505	$32.41	$0	$6,010,505	$32.41	$0.60
Gas	9,811,388	98.03%	$192,410,990	$19.61	$86,798,731	$105,612,259	$10.76	$10.55
Total	**10,008,149**	**100.00%**	**$199,889,172**		**$86,798,731**	**$113,090,440**		**$11.30**

E3

FPSC EXH No. 10
03/20/2024

ADMITTED

E5

Florida Power & Light Company
Docket No. 20220001-EI
Staff's 2nd Set of Interrogatories
Attachment No. I, Interrogatory No. 4
Page 2 of 6

Turkey Point Unit 3

Event Start	Event End	Seq. #	Event Title	MW Loss	Outage Hours	MWh Loss	Replacement Cost ($/MWh)	Replacement Cost ($)	TN3 Fuel Cost ($/MWh)	Nuclear Fuel Cost ($)	Net Replacement Cost ($)
A	B	C	D	E	F = (B - A) * 24	G = E * F	H = WA $/MWh	I = G * H	J = TN4 $/MWh	K = J * G	L = I - K
11/7/2020 3:18	11/21/2020 11:39	1	PTN Unit 3 Unplanned Auto Turbine Runback	169.83	344.35	58,481	$19.76	$1,155,566	$5.19	$303,476	$852,090
11/21/2020 11:40	11/24/2020 1:00	2	PTN Unit 3 downpower to support FBM replacement	490.70	61.33	30,096	$19.76	$594,693	$5.19	$156,179	$438,514
					405.68	**88,577**					**$1,290,604**
											$76,351 /Day

November 2020 - A4 Data	
TN3 Fuel Cost	**TN3 Heat Rate**
0.48	10,872
TN3 $/MWh	
$5.19	

November 2020 - A3 Data								
Fuel	**MWh**	**% Mix**	**Fuel Cost $**	**$/MWh**	**Demand $**	**Rev. Fuel Cost $**	**$/MWh**	**WA $/MWh**
Heavy Oil	696	0.01%	$92,932	$133.49	$0	$92,932	$133.49	$0.01
Light Oil	982	0.01%	$170,546	$173.64	$0	$170,546	$173.64	$0.02
Coal	166,720	2.25%	$5,184,226	$31.10	$0	$5,184,226	$31.10	$0.70
Gas	7,226,805	97.72%	$218,636,264	$30.25	$77,956,955	$140,679,309	$19.47	$19.02
Total	**7,395,204**	**100.00%**	**$224,083,968**		**$77,956,955**	**$146,127,013**		**$19.76**

E4

FPSC EXH No. 10
03/20/2024

ADMITTED

E6

Florida Power & Light Company
Docket No. 20220001-EI
Staff's 2nd Set of Interrogatories
Attachment No. I, Interrogatory No. 4
Page 3 of 6

St. Lucie Unit 2

Event Start	Event End	Seq. #	Event Title	MW Loss	Outage Hours	MWh Loss	Replacement Cost ($/MWh)	Replacement Cost ($)	SL2 Fuel Cost ($/MWh)	Nuclear Fuel Cost ($)	Net Replacement Cost ($)
A	B	C	D	E	F = (B - A) * 24	G = E * F	H = WA $/MWh	I = G * H	J = SL2 $/MWh	K = J * G	L = I - K
1/14/2021 0:58	1/14/2021 8:31	1	2B2 4KV Breaker Power Reduction	511.15	7.55	3,859	$17.77	$68,583	$4.43	$17,105	$51,478
1/14/2021 8:31	1/14/2021 15:16	2	2B2 4KV Breaker Shut down	987.00	6.75	6,662	$17.77	$118,397	$4.43	$29,529	$88,868
1/14/2021 15:16	1/16/2021 6:24	3	2B2 4KV Breaker Power Ascension	154.37	39.13	6,041	$17.77	$107,356	$4.43	$26,775	$80,581
1/20/2021 18:22	1/23/2021 14:28	4	2B2 Automatic shut down Motor Control Center	987.00	68.10	67,215	$17.77	$1,194,490	$4.43	$297,913	$896,576
1/23/2021 14:28	1/24/2021 3:12	5	2B2 Motor Control Center Power Ascension	370.61	12.73	4,719	$17.77	$83,864	$4.43	$20,916	$62,948
					134.27	**88,496**					**$1,180,450**
											$211,004 /Day

January 2021 - A4 Data	
SL2 Fuel Cost	**SL2 Heat Rate**
0.43	10,215
SL2 $/MWh	
$4.43	

January 2021 - A3 Data

Fuel	MWh	% Mix	Fuel Cost $	$/MWh	Demand $	Rev. Fuel Cost $	$/MWh	WA $/MWh
Heavy Oil	(1,846)	-0.03%	$0	$0.00	$0	$0	$0.00	$0.00
Light Oil	5,374	0.09%	$779,832	$145.10	$0	$779,832	$145.10	$0.14
Coal	152,748	2.67%	$1,830,141	$11.98	$0	$1,830,141	$11.98	$0.32
Gas	5,570,003	97.27%	$179,842,136	$32.29	$80,688,936	$99,153,200	$17.80	$17.32
Total	**5,726,280**	**100.00%**	**$182,452,109**		**$80,688,936**	**$101,763,174**		**$17.77**

E5

FPSC EXH No. 10
03/20/2024

ADMITTED

E7

Florida Power & Light Company
Docket No. 20220001-EI
Staff's 2nd Set of Interrogatories
Attachment No. I, Interrogatory No. 4
Page 4 of 6

Turkey Point Unit 3

Event Start	Event End	Seq. #	Event Title	MW Loss	Outage Hours	MWh Loss	Replacement Cost ($/MWh)	Replacement Cost ($)	TN3 Fuel Cost ($/MWh)	Nuclear Fuel Cost ($)	Net Replacement Cost ($)
A	B	C	D	E	F = (B - A) * 24	G = E * F	H = WA $/MWh	I = G * H	J = TN3 $/MWh	K = J * G	L = I - K
3/1/2021 11:08	3/4/2021 21:19	1	Automatic trip during reactor protection system testing	837.00	82.18	68,787	$20.64	$1,419,632	$4.99	$343,552	$1,076,080
3/4/2021 21:20	3/5/2021 17:00	2	Automatic trip during reactor protection system power ascension	306.04	19.67	6,019	$20.64	$124,215	$4.99	$30,060	$94,155
3/24/2021 19:15	3/25/2021 20:00	3	Power reduction due to turbine runback	94.29	24.75	2,334	$20.64	$48,162	$4.99	$11,655	$36,507
					126.60	**77,140**					**$1,206,743**
											$228,766 /Day

March 2021 - A4 Data	
TN3 Fuel Cost	**TN3 Heat Rate**
0.48	10,385
TN3 $/MWh	
$4.99	

March 2021 - A3 Data

Fuel	MWh	% Mix	Fuel Cost $	$/MWh	Demand $	Rev. Fuel Cost $	$/MWh	WA $/MWh
Heavy Oil	7,493	0.11%	$967,310	$129.09	$0	$967,310	$129.09	$0.15
Light Oil	3,724	0.06%	$490,603	$131.73	$0	$490,603	$131.73	$0.07
Coal	167,673	2.53%	$5,388,631	$32.14	$0	$5,388,631	$32.14	$0.81
Gas	6,441,824	97.30%	$212,154,964	$32.93	$82,363,543	$129,791,421	$20.15	$19.60
Total	**6,620,714**	**100.00%**	**$219,001,508**		**$82,363,543**	**$136,637,965**		**$20.64**

E6

FPSC EXH No. 10
03/20/2024

ADMITTED

E8

Florida Power & Light Company
Docket No. 20220001-EI
Staff's 2nd Set of Interrogatories
Attachment No. I, Interrogatory No. 4
Page 5 of 6

St. Lucie Unit 1

Event Start	Event End	Seq. #	Event Title	MW Loss	Outage Hours	MWh Loss	Replacement Cost ($/MWh)	Replacement Cost ($)	SL1 Fuel Cost ($/MWh)	Nuclear Fuel Cost ($)	Net Replacement Cost ($)
A	B	C	D	E	F = (B - A) * 24	G = E * F	H = WA $/MWh	I = G * H	J = SL1 $/MWh	K = J * G	L = I - K
5/14/2021 0:01	5/17/2021 21:32	1	Outage Extension (no power ascension since part of planned outage)	981.00	93.52	91,740	$21.48	$1,970,698	$4.94	$453,187	$1,517,511
					93.52	**91,740**					**$1,517,511**
											$389,452 /Day

May 2021 - A4 Data	
SL1 Fuel Cost	**SL1 Heat Rate**
0.47	10,595
SL1 $/MWh	
$4.94	

May 2021 - A3 Data								
Fuel	**MWh**	**% Mix**	**Fuel Cost $**	**$/MWh**	**Demand $**	**Rev. Fuel Cost $**	**$/MWh**	**WA $/MWh**
Heavy Oil	10,934	0.13%	$1,449,517	$132.57	$0	$1,449,517	$132.57	$0.17
Light Oil	8,988	0.11%	$1,242,013	$138.18	$0	$1,242,013	$138.18	$0.15
Coal	179,098	2.12%	$10,707,125	$59.78	$0	$10,707,125	$59.78	$1.27
Gas	8,253,106	97.65%	$252,830,400	$30.63	$84,665,773	$168,164,627	$20.38	$19.90
Total	**8,452,126**	**100.00%**	**$266,229,054**		**$84,665,773**	**$181,563,281**		**$21.48**

E7

FPSC EXH No. 10
03/20/2024

ADMITTED

E9

Florida Power & Light Company
Docket No. 20220001-EI
Staff's 2nd Set of Interrogatories
Attachment No. I, Interrogatory No. 4
Page 6 of 6

Turkey Point Unit 3

Event Start	Event End	Seq. #	Event Title	MW Loss	Outage Hours	MWh Loss	Replacement Cost ($/MWh)	Replacement Cost ($)	TN3 Fuel Cost ($/MWh)	Nuclear Fuel Cost ($)	Net Replacement Cost ($)
A	B	C	D	E	F = (B - A) * 24	G = E * F	H = WA $/MWh	I = G * H	J = TN3 $/MWh	K = J * G	L = I - K
8/5/2021 1:30	8/13/2021 21:59	1	Unplanned power reduction due to Turbine Control Valve Auto Close	249.63	212.48	53,042	$28.46	$1,509,680	$5.38	$285,444	$1,224,236
8/13/2021 22:00	8/16/2021 19:38	2	Shutdown to repair Turbine Control Valve	837.00	69.63	58,283	$28.46	$1,658,845	$5.38	$313,648	$1,345,198
8/16/2021 19:39	8/17/2021 23:00	3	Turbine Control Valve Power Ascension	312.75	27.35	8,554	$28.46	$243,455	$5.38	$46,031	$197,423
					309.47	**119,879**					**$2,766,857**
											$214,577 /Day

August 2021 - A4 Data	
TN3 Fuel Cost	**TN3 Heat Rate**
0.50	10,833
TN3 $/MWh	
$5.38	

August 2021 - A3 Data

Fuel	MWh	% Mix	Fuel Cost $	$/MWh	Demand $	Rev. Fuel Cost $	$/MWh	WA $/MWh
Heavy Oil	2,246	0.02%	$314,781	$140.14	$0	$314,781	$140.14	$0.03
Light Oil	3,425	0.03%	$446,656	$130.40	$0	$446,656	$130.40	$0.04
Coal	151,047	1.50%	$5,557,391	$36.79	$0	$5,557,391	$36.79	$0.55
Gas	9,913,334	98.44%	$365,832,640	$36.90	$85,539,072	$280,293,568	$28.27	$27.83
Total	**10,070,052**	**100.00%**	**$372,151,468**		**$85,539,072**	**$286,612,396**		**$28.46**

E8

FPSC EXH No. 10
03/20/2024

ADMITTED

E10

Florida Power & Light Company
Docket No. 20220001-EI
Staff's 2nd Set of Interrogatories
Interrogatory No. 9

QUESTION:
The following questions are with respect to Florida Power & Light's (FPL or Company) Petition for Approval of Fuel Cost Recovery and Capacity Cost Recovery Net Final True-Ups for the Period Ending December 2021 and 2021 Asset Optimization Incentive Mechanism Results (Petition).

Please refer to FPL's Generating Performance Incentive Factor Actual Unit Performance Data Schedules covering the month of January 2022 for the following questions.

a. Please explain the events or factors leading to the forced outage of approximately 335 hours of Plant St. Lucie Unit No. 2 for the month.

b. Please specify the replacement power costs, if any, associated with the January 2022 outage. If applicable, please also show how any replacement power costs were calculated.

RESPONSE:

a. Prior to the January 2022 outage, FPL was conducting surveillance testing on St. Lucie Unit 2 Rod Control. Control Element Assembly (CEA) #27 malfunctioned during this surveillance testing. Unit 2 reduced power to attempt to move the CEA without success, therefore the unit was manually shut down to address the issue. The #27 Control Element Drive Mechanism (CEDM) motor was removed and sent to a Westinghouse facility for further inspection, disassembly, and analysis. FPL is conducting an investigation and will supplement this response upon completion of the root cause evaluation.

b. The net replacement power cost related to the St. Lucie Unit No. 2 January 2022 outage was $8,693,593. The calculation is provided in Attachment No. 1 to this Interrogatory. FPL applies the proportion of fuel used during the same period for each fuel type, as summarized on Schedule A3, to the amount of outage time, in hours, experienced. Fixed natural gas costs are removed from the calculation since those costs have already been incurred.

FPSC EXH No. 10
03/20/2024

ADMITTED

E11

Florida Power & Light Company
Docket No. 20220001-EI
Staff's 2nd Set of Interrogatories
Attachment No. I, Interrogatory No. 9
Page 1 of 1

St Lucie Unit 2

Event Start	Event End	Seq. #	Event Title	MW Loss	Outage Hours	MWh Loss	Replacement Cost ($/MWh)	Replacement Cost ($)	SL2 Fuel Cost ($/MWh)	Nuclear Fuel Cost ($)	Net Replacement Cost ($)
A	B	C	D	E	F = (B - A) * 24	G = E * F	H = WA $/MWh	I = G * H	J = SL2 $/MWh	K = J * G	L = I - K
1/6/2022 13:00	1/6/2022 21:13	1	Control Element Assembly 27 Power Reduction	329.00	8.22	2,703	$30.76	$83,147	$5.16	$13,955	$69,192
1/6/2022 21:13	1/19/2022 16:43	2	Control Element Assembly 27 Repair	987.00	307.50	303,503	$30.76	$9,335,069	$5.16	$1,566,708	$7,768,361
1/19/2022 16:43	1/20/2022 20:28	3	Control Element Assembly 27 Extension for MG Set Repair	987.00	27.75	27,389	$30.76	$842,433	$5.16	$141,386	$701,047
1/20/2022 20:28	1/21/2022 14:30	4	Control Element Assembly 27 Power Ascension	335.79	18.03	6,055	$30.76	$186,251	$5.16	$31,259	$154,993
					361.50	**339,650.45**					**$8,693,593**
											$577,168 /Day

January 2022 - A4 Data	
SL2 Fuel Cost	**SL2 Heat Rate**
0.42	12,160
SL2 $/MWh	
$5.16	

January 2022 - A3 Data								
Fuel	**MWh**	**% Mix**	**Fuel Cost $**	**$/MWh**	**Demand $**	**Rev. Fuel Cost $**	**$/MWh**	**WA $/MWh**
Heavy Oil	23	0.00%	$79	$3.44	$0	$79	$3.44	$0.00
Light Oil	65,535	0.87%	$711,418	$10.86	$0	$711,418	$10.86	$0.09
Coal	171,979	2.29%	$7,202,821	$41.88	$0	$7,202,821	$41.88	$0.96
Gas	7,266,559	96.83%	$304,733,593	$41.94	$81,838,429	$222,895,164	$30.67	$29.70
Total	**7,504,096**	**100.00%**	**$312,647,911**		**$81,838,429**	**$230,809,482**		**$30.76**

E10

FPSC EXH No. 10
03/20/2024

ADMITTED

E12

DECLARATION

I sponsored the answer to Interrogatory Nos. 3, 4, and 9b from **STAFF'S SECOND SET OF INTERROGATORIES (NOS. 3-10)** to Florida Power & Light Company in Docket No. 20220001-EI. The responses are true and correct based on my personal knowledge.

Under penalties of perjury, I declare that I have read the foregoing declaration and the interrogatory answers identified above, and that the facts stated therein are true.

Gerard J. Yupp

Date: 5/10/22

E11

FPSC EXH No. 10
03/20/2024

ADMITTED

DECLARATION

I sponsored the answer to Interrogatory No. 9a from **STAFF'S SECOND SET OF INTERROGATORIES (NOS. 3-10)** to Florida Power & Light Company in Docket No. 20220001-EI. The responses are true and correct based on my personal knowledge.

Under penalties of perjury, I declare that I have read the foregoing declaration and the interrogatory answers identified above, and that the facts stated therein are true.

Dean Curtland

Date: 5/11/22

FPSC EXH No. 11
03/20/2024
ADMITTED

11

As filed in Docket No. 20220001-EI, FPL's Response to Staff's Third Set of Interrogatories Nos. 11, 12, 13, 14, 15, and 16

FPSC EXH No. 11
03/20/2024

ADMITTED

QUESTION:
Please refer to witness Curtland's testimony, Page 3, Line 13 through Page 8, Line 7 for the following questions.

a. Provide a full timeline of the July 2020 Turkey Point Unit 4 outage event.

b. Detail when the corrective replacement of exciter components is expected to be completed for all other FPL nuclear units. As a part of this response, please detail if FPL has observed any signs of a similar problem as the one that occurred at Turkey Point Unit 4 occurring at these units.

c. Explain if FPL is seeking damages from Siemen for failing to install the weather sealing during the last housing installation. If not, explain why not.

RESPONSE:

a. This event is referred to as "Unit 4 Automatic Reactor Trip caused by Main Generator Lockout due to Exciter Fault."

On 7/5/2020 at 21:09 hours, while Unit 4 was operating in Mode 1 at 100% power, a Main Generator Lockout caused the Unit 4 Turbine to trip, automatically tripping the Reactor. The Main Generator Lockout was caused by a loss of two Voltage Regulator power supplies. All safety systems operated as required in response to the equipment failure.

The event was initiated by an electrical fault of the Exciter Permanent Magnet Generator (PMG), which caused both Voltage Regulator power supplies to fail. The resulting actuation of the Voltage Regulator lockout relay caused a lockout of the Unit 4 Main Generator, tripping the Turbine as designed. As a design input to Reactor Protection System actuation logic, the turbine trip caused an automatic Reactor trip. Investigation found that the PMG fault was caused by a combination of the aged condition of the stator windings and exposure to moisture that was present due to a degraded weather seal on the exterior housing.

The corrective action was replacement of the PMG and rotating assembly. The Exciter housing was re-sealed following reassembly.

Unit 4 reactor was critical on 7/18/20 at 17:17. Unit 4 was online on 7/20/20 at 14:55 and returned to 100% power on 7/21/20 at 15:00.

b. St. Lucie Unit 1 PMG was replaced April 2021. The AC Stator and Armature are scheduled for replacement September 2022.

FPSC EXH No. 11
03/20/2024

ADMITTED

St. Lucie Unit 2 PMG replacement is scheduled for March 2023.

Turkey Point Unit 3 PMG, AC Stator and Armature replacement was completed November 2021.

Turkey Point Unit 4 PMG was replaced April 2022. The AC Stator and Armature replacement is scheduled September 2023.

FPL has not observed signs of similar problems as experienced at Turkey Point Unit 4.

c. No. All Preventative Maintenance for the PMG were being performed in accordance with Siemens (original equipment manufacturer "OEM") recommendations. The failure was determined to be due to degraded windings on the PMG combined with moisture. There are no Siemens (OEM) recommendations for rewinding the PMG.

In addition, review of Siemens documents revealed that Siemens performed the housing sealing work in the manner required by the work order documents.

FPSC EXH No. 11
03/20/2024

ADMITTED

QUESTION:
Please refer to witness Curtland's testimony, Page 5, Line 21 through Page 6, Line 14 for the following questions.

a. Provide a full timeline of the November 2020 Turkey Point Unit 3 outage event.

b. Detail the maintenance schedule of the faulty field control processor.

c. Detail the historic use of this specific faulty field control processor. As a part of this response, detail the expected lifespan of a field control processor.

RESPONSE:

a. This event is referred to as "Unit 3 Turbine Runback initiated due to low Heater Drain Tank Level and Heater Drain Pump trips."

On 11/7/2020 at 03:20, Unit 3 experienced an automatic turbine runback to approximately 85% reactor power, initiated after failure of multiple valves on the secondary feed system. These valves included the 3A Heater Drain Tank Normal Control valve, 6A/B Feedwater Normal Control valve, 3A Moisture Separator Reheater Normal drain, 3A Condensate Pump recirculation to condenser control valve and the 3A/B steam generator feed pump recirculating control valves. These valve failures were a result of failed Foxboro Field Control Processor associated with the plant Secondary Control.

In order to correct the deficiency, the plant reduced power to approximately 25% reactor power on 11/21 at 11:40 to support replacement of the Field Control Processors.

Unit 3 returned to approximately 100% reactor power on 11/24/20 at 01:00.

A forensics report concluded the event was caused by faulty optocouplers.

b. There was no Preventative Maintenance associated with the Field Control Processors. These are run-to-maintenance components

c. The Foxboro Field Control Processor had been in use since initial installation (2012). There had not been issues with this processor prior to the event. In response to the failure, all other field control processors with the associated optocouplers were replaced.

Since then, the Distributed Control System has been completely upgraded to the latest series of Foxboro IA on both Turkey Point Units 3 and 4. This included replacing the Field Control Processors with an updated series (FCP270 replaced with FCP 280).

FPSC EXH No. 11
03/20/2024

ADMITTED

The expected lifespan of the Foxoboro Field Control Processor will be evaluated for upgrades starting at 15 to 20 years, as determined by failure rates, which is monitored by the vendor and in accordance with the vendor recommendations.

FPSC EXH No. 11
03/20/2024

ADMITTED

Florida Power & Light Company
Docket No. 20220001-EI
Staff's Third Set of Interrogatories
Interrogatory No. 13

QUESTION:
Please refer to witness Curtland's testimony, Page 7, Line 8 through Page 8, Line 7 for the following questions.

a. **Please provide a full timeline of the January 2021 St. Lucie Unit 2 outage event.**

b. **Explain if FPL has redesigned UV relay power supplies at all other FPL nuclear units. If so, has FPL verified that the legacy drawings match the design conventions in the other units? If FPL has not verified that the drawings match, explain why not.**

RESPONSE:
a. St. Lucie Unit 2 January 2021 outage event timeline below.

Date	Time	Event Description
01/20/21	18:22	Reactor trip on Reactor Protection System (RPS) Loss of Load Actuation concurrent with an unexpected de-energization of the 480V Motor Control Center (MCC) 2B2.
01/20/21	20:34	Outage Control Center Activated due to Unit 2 Trip.
01/21/21	00:00	Electrical Maintenance reports that the installed circuit breaker 2-40404 had a fault light lit (as found condition). When the breaker was racked out, the fault light extinguished. The breaker was cycled in the test position satisfactorily. The breaker has been removed for forensic testing. There was no evidence of soot in the arc chutes.
01/21/21	08:40	The Failure Investigation Process issued a work order to validate a suspected wiring discrepancy for the undervoltage relay wiring.
01/21/21	17:13	Validation confirmed the undervoltage relay wiring was incorrect.
01/21/21	19:12	Electrical Maintenance completed bench testing of MCC 2B2 breaker.
01/22/21	14:43	The field work associated with wiring modification for the control element cabinet undervoltage relays is completed. Post Maintenance Testing (PMT) is in progress.
01/22/21	18:30	PMT for under voltage relay modification for the legacy Control Element Drive Mechanism wiring issue has been completed satisfactory (SAT).
01/22/21	22:20	Unit 2 Reactor Startup commenced.
01/22/21	23:47	Unit 2 entered Mode 2.
01/23/21	01:25	Unit 2 reached 2-5% power.
01/23/21	01:55	Unit 2 entered Mode 1.
01/23/21	14:31	Turbine generator sync'd to the grid and came on-line
01/24/21	03:03	Unit 2 reached 100% power.

FPSC EXH No. 11
03/20/2024

ADMITTED

b. The MCC malfunction event from January 2021 was reviewed at the other FPL nuclear units. No similar conditions were identified.

FPSC EXH No. 11
03/20/2024

ADMITTED

QUESTION:
Please refer to witness Curtland's testimony, Page 8, Line 12 through Page 9, Line 17 for the following questions.

a. Please provide a full timeline of the March 2021 Turkey Point Unit 3 outage event.

b. Detail the maintenance schedule of the affected cell switch.

c. Detail the Westinghouse recommended service life for the cell switch.

d. Detail the industry review that FPL performed. As a part of this response, explain if industry practices involve operating cell switches longer than the vendor recommended design life.

e. Explain if the revised time-based cleaning and lubrication of cell switch contact procedures will be used for all other FPL nuclear units.

f. Detail the costs associated with purchasing and installing a new cell switch.

RESPONSE:
a. This event is referred to as "Unit 3 Automatic Reactor Trip due to Reactor Trip Breaker Cell Switch Malfunction."

On 3/1/21 at 11:08 hours, Turkey Point Unit 3 experienced an unplanned reactor trip from 100% power. Restoration from a routine test of the Reactor Protection System (RPS) was in progress when the reactor trip occurred. As expected for the conditions, the Auxiliary Feedwater System (AFW) automatically initiated in response to the reactor trip to maintain Steam Generator levels in normal bands. All equipment required for the immediate reactor trip response functioned normally.

A malfunction of the B-train Reactor Trip Breaker (RTB) cubicle cell switch during the RPS test restoration caused the reactor trip. The breaker and cell switch have since been replaced and Unit 3 returned to normal power operation.

FPSC EXH No. 11
03/20/2024

ADMITTED

Reactor Trip and Bypass breaker cubicle cell switches provide logic inputs to the turbine trip primary and backup relays. The Sequence of Event report revealed that the reactor trip signal was initiated by turbine trip logic. The most likely cause identified by the Engineering team was that following the RPS surveillance, with the B-train RTB racked in, an RTB cell switch was incorrectly providing racked-out position logic input to the backup turbine trip relay. When the B-train Bypass Reactor Trip breaker (BYB) was tripped open during restoration, the logic to actuate the backup turbine trip relay was completed, tripping the turbine, and initiating reactor trip signals.

The Westinghouse DB-50 Reactor Trip and Bypass breakers utilize cell switch contacts located inside the breaker cubicles that provide open position logic to the turbine trip relays if the breaker is racked out. Failure analysis performed jointly between FPL Engineering and Westinghouse revealed that the most likely cause of the incorrect RTB position logic was failure of the cell switch contact. Graphite grease used for lubrication was found accumulated and hardened, creating an electrical tracking path for the incorrect logic signal. A review of the FPL preventive maintenance procedure showed that steps to clean and reapply grease on the switch contacts is condition-based rather than time-based.

Turkey Point has since implemented a modification which installed voltage test points to monitor for cell switch state. These test points are used to ensure that a similar condition which caused the unexpected trip is not present when performing and restoring from surveillance activities.

Unit 3 was critical on 3/4/21 at 13:48, online 3/4/21 at 2120 and reached 100% power on 3/5/21 at 17:00.

b. The current maintenance inspection schedule is as follows:

- Cubicle inspection (which would include the cell switches) – once every 18 months
- Reactor Trip Breaker cell switch replacement (new following reactor trip event) – every 5 refueling cycles
- Bypass Reactor Trip Breaker cell switch replacement (new following reactor trip event) – every 10 refueling cycles

c. Westinghouse recommends a service life of 100 cycles for cell switches. Turkey Point did not have a 100-cycle replacement Preventative Maintenance (PM) in place and at the time only performed inspections once every 18 months. Since this event, Turkey Point has created new PM plans for the replacement of cell switches every refueling outage (less than 100 cycles).

FPSC EXH No. 11
03/20/2024
ADMITTED

d. In determining industry operating experience for Westinghouse DB-50 cell switches, FPL contacted the Circuit Breaker Users Group (CBUG). Three plants responded and only one plant has a replacement PM in place. Procedure steps from other sites were reviewed and they are similar to what is performed at Turkey Point.

   Westinghouse does state in their Maintenance PM Manual that the switch used in the cell switch is the same switch used as an auxiliary switch on the DB breaker with a qualified life of 4000 cycles on the DB-50 breaker. The remaining components of the cell switch consist of a metal frame, a metal return spring, which are not sensitive to age within 100 cycles.

   Also, please see FPL's response to Staff's First Request For Production of Documents, No. 1.

e. The proposed cleaning and lubrication have been applied to other breakers at Turkey Point, which includes the Control Rod Drive Mechanism (CRDM) MG set and the Main Generator Cubicle cell switch.

   St. Lucie reactor trip breakers are not supplied by Westinghouse.

f. The cost associated with purchasing and installing a new cell switch was approximately $80,000.

FPSC EXH No. 11
03/20/2024

ADMITTED

QUESTION:
Please refer to witness Curtland's testimony, Page 9, Line 20 through Page 10, Line 11.

a. Provide a full timeline of the August 2021 Turkey Point Unit 3 outage event.

b. Explain if maintenance could have detected the issue prior to the outage event.

c. Detail the maintenance procedure for the actuator assembly. As a part of this response, explain if FPL maintenance procedure is consistent with industry maintenance practice.

d. Explain if this outage affected the unit meeting its GPIF target for the month.

RESPONSE:

a. On 8/5/21 at approximately 01:30, Unit 3 #2 turbine control valve (3-10-035) unexpectedly closed. The plant commenced (8/5/21 at 0217) a fast load reduction and reduced power to approximately 73% to stabilize stresses on the turbine and steam generator levels.

Following an initial investigation, Unit 3 was shut down on 8/13/21 at 22:00 for further investigation and repairs.

Following the Unit 3 shutdown, the #2 turbine control valve was disassembled and inspected. During the inspection, the actuator stem was found sheared right inside the threaded location inside the coupling. Fractographic examination, chemical analysis, mechanical testing, and optical microscopy revealed that corrosion induced low cycle fatigue was the most likely cause for the referenced #2 turbine control valve actuator rod failure. Contributing causes associated with potential misalignment of the actuator relative to the valve.

Unit 3 went critical on 8/16 at 1108. Unit 3 was on-line on 8/16 at 19:39 and reached 100% power on 8/17 at 23:00.

b. No, maintenance could not have detected the issue prior to the August 5, 2021 event. Catastrophic failure of the stem rod involves fracture mechanisms that are microscopic in nature and virtually undetectable during power operation. These mechanisms do not create detectable variables that can be trended for degradation and predicted. During overhauls, the affected components can be tested using non-destructive methods (such as UT, liquid penetrant, etc.). However, operating experience for this type of actuator has not revealed similar failures that would necessitate such testing.

FPSC EXH No. 11
03/20/2024

ADMITTED

c. Work on the turbine is performed by the original equipment manufacturer, Siemens, consistent with the vendor recommendations. Consistent with industry best practices during maintenance, the actuator is fully disassembled and inspected. After reassembly, the actuator is hydraulically tested.

   In addition, FPL has revised the turbine control valve actuator stem non-destructive inspection to include:

   - Light coating of turbine oil prior to shipment on all components
   - New piston rods with every actuator rebuild
   - Visual inspection/crawl through on valves that are not scheduled to be replaced each cycle

d. The GPIF procedure does not set monthly GPIF targets, only year-end targets. However, if this forced outage event had not occurred and Turkey Point Unit 3's availability otherwise remained the same for the year, the Unit would have received a reward. Therefore, one can conclude that this outage affected the unit meeting its GPIF year-end target and contributed to an availability penalty.

FPSC EXH No. 11
03/20/2024

ADMITTED

QUESTION:
Please refer to witness Curtland's testimony, Page 10, Line 16 through Page 11, Line 8.

a. Please provide a full timeline of the May 2021 St. Lucie Unit 1 outage event.

b. Explain if FPL is seeking damages from the vendor. If not, why not.

RESPONSE:
a. St. Lucie Unit 1 May 2021 outage event below.

Date	Time	Event Description
5/7/21	15:23	Trouble shooting due to urgent alarm of Control Rod Group 1 Subgroup 7 which affects rods 27, 29, 31 and 33 determined that the rods will not move and there appears to be an issue in the lower gripper coil drawer.
5/8/21	09:10	Complex Troubleshooting Team has kicked off. Westinghouse Subject Matter Experts are in route to site to support. Issue will follow the Complex Troubleshooting process.
5/8/21	15:30	Outage Control Center (OCC) Key Decision: Field Measurements confirm degraded Coil Stack on Control Rod Group 1 Subgroup 7. Decision to return to Cold Shutdown (Mode 5) to make repairs was briefed in the OCC.
5/8/21	17:19	Entered Cold Shutdown to replace affected rods coil stacks.
5/11/21	17:10	Physical coil stack replacements complete.
5/13/21	21:31	Coil Stacks installation complete and verified functioning properly.
5/15/21	05:11	Unit 1 has entered Mode 4. (Hot Shutdown)
5/15/21	16:11	Unit 1 has entered mode 3. (Hot Standby)
5/17/21	08:25	Unit 1 has entered Mode 2. (Start up)
5/17/21	15:25	Unit 1 has entered mode 1. (Power Operation)
5/17/21	21:32	Turbine Generator Synched to the Grid and came on-line.
5/19/21	17:00	Unit 1 is at 100% Reactor Power.

FPSC EXH No. 11
03/20/2024

ADMITTED

b. FPL did not pursue seeking damages from the supplier as we were outside of the contractual warranty period.

FPSC EXH No. 11
03/20/2024

ADMITTED

E30

DECLARATION

I, Dean Curtland, sponsored the answers to Interrogatory Nos. 11-14 and 16 and I co-sponsored the answers to Interrogatory No. 15 from **Staff's Third Set of Interrogatories (Nos. 11-24)** to Florida Power & Light Company in Docket No. 20220001-EI, and the responses are true and correct based on my personal knowledge.

Under penalties of perjury, I declare that I have read the foregoing declaration and the interrogatory answers identified above, and that the facts stated therein are true.

Dean Curtland

Date: 7/13/2022

E27

FPSC EXH No. 11
03/20/2024

ADMITTED

E31

DECLARATION

I, Charles Rote, co-sponsored the answer to Interrogatory No. 15 from **Staff's Third Set of Interrogatories (Nos. 11-24)** to Florida Power & Light Company in Docket No. 20220001-EI, and the response is true and correct based on my personal knowledge.

Under penalties of perjury, I declare that I have read the foregoing declaration and the interrogatory answer identified above, and that the facts stated therein are true.

Charles Rote

Charles Rote

Date: 2/13/2022

E28

FPSC EXH No. 12
03/20/2024
ADMITTED

12

As filed in Docket No. 20220001-EI, FPL's Response to Staff's Fourth Set of Interrogatories No. 30

FPSC EXH No. 12
03/20/2024

ADMITTED

QUESTION:
Please refer to the Direct Testimony of FPL witness Dean Curtland, filed as part of the Petition, for the following request. Please provide the replacement power costs, if any, associated with the: February 2021 outage of Turkey Point Unit No. 3, the November 2021 outage of Turkey Point Unit No. 3, and the December 2021 outage of St. Lucie Unit No. 1. Please also show how any replacement power cost amounts were calculated.

RESPONSE:

Outage	Replacement Power Cost
February 2021 - Turkey Point Unit No. 3	$1,146,159
November 2021 - Turkey Point Unit No. 3	$10,054,734
December 2021 - St. Lucie Unit No. 2	$1,434,048

The calculation is provided in Attachment No. 1 to this Interrogatory. FPL applies the proportion of fuel used during the same period for each fuel type, as summarized on Schedule A3, to the amount of outage time, in hours, experienced. Fixed natural gas costs are removed from the calculation because those costs have already been incurred.

FPSC EXH No. 12
03/20/2024
ADMITTED

Florida Power & Light Company
Docket No. 20220001-EI
Staff's Fourth Set of Interrogatories
Interrogatory No. 30
Attachment 1 of 1
Tab 1 of 3

Turkey Point Unit 3

Event Start	Event End	Seq. #	Event Title	MW Loss	Outage Hours	MWh Loss	Replacement Cost ($/MWh)	Replacement Cost ($)	TN3 Fuel Cost ($/MWh)	Nuclear Fuel Cost ($)	Net Replacement Cost ($)
A	B	C	D	E	F = (B - A) * 24	G = E * F	H = WA $/MWh	I = G * H	J = TN3 $/MWh	K = J * G	L = I - K
2/2/2021 13:57	2/9/2021 4:00	1	Power reduction due to condenser tube leak	380.52	158.05	60,141	$25.01	$1,504,320	$5.96	$358,161	$1,146,159
					158.05	**60,141**					**$1,146,159**
											$174,045 /Day

February 2021 - A4 Data	
TN3 Fuel Cost	**TN3 Heat Rate**
0.58	10,220
TN3 $/MWh	
$5.96	

February 2021 - A3 Data								
Fuel	**MWh**	**% Mix**	**Fuel Cost $**	**$/MWh**	**Demand $**	**Rev. Fuel Cost $**	**$/MWh**	**WA $/MWh**
Heavy Oil	2,971	0.05%	$395,439	$133.09	$0	$395,439	$133.09	$0.07
Light Oil	35,269	0.58%	$3,582,725	$101.58	$0	$3,582,725	$101.58	$0.59
Coal	204,183	3.39%	$6,128,978	$30.02	$0	$6,128,978	$30.02	$1.02
Gas	5,787,680	95.98%	$214,300,687	$37.03	$73,575,996	$140,724,691	$24.31	$23.34
Total	**6,030,103**	**100.00%**	**$224,407,829**		**$73,575,996**	**$150,831,833**		**$25.01**

FPSC EXH No. 12
03/20/2024
ADMITTED

Florida Power & Light Company
Docket No. 20220001-EI
Staff's Fourth Set of Interrogatories
Interrogatory No. 39
Attachment 1 of 1
Tab 2 of 3

Turkey Point Unit 3

Event Start	Event End	Seq. #	Event Title	MW Loss	Outage Hours	MWh Loss	Replacement Cost ($/MWh)	Replacement Cost ($)	TN3 Fuel Cost ($/MWh)	Nuclear Fuel Cost ($)	Net Replacement Cost ($)
A	B	C	D	E	F = (B - A) * 24	G = E * F	H = WA $/MWh	I = G * H	J = TN3 $/MWh	K = J * G	L = I - K
11/7/2021 0:01	11/20/2021 15:24	1	Unit 3 refueling outage extension	837.00	327.38	274,020	$41.87	$11,474,228	$5.18	$1,419,494	$10,054,734
					327.38	**274,020**					**$10,054,734**
											$737,098 /Day

November 2021 - A4 Data	
TN3 Fuel Cost	**TN3 Heat Rate**
0.48	10,701
TN3 $/MWh	
$5.18	

November 2021 - A3 Data								
Fuel	**MWh**	**% Mix**	**Fuel Cost $**	**$/MWh**	**Demand $**	**Rev. Fuel Cost $**	**$/MWh**	**WA $/MWh**
Heavy Oil	1	0.00%	$158	$155.00	$0	$158	$155.00	$0.00
Light Oil	2,069	0.03%	$396,671	$191.72	$0	$396,671	$191.72	$0.06
Coal	148,290	2.34%	$6,541,161	$44.11	$0	$6,541,161	$44.11	$1.03
Gas	6,194,067	97.63%	$339,183,639	$54.76	$80,456,908	$258,726,731	$41.77	$40.78
Total	**6,344,427**	**100.00%**	**$346,121,629**		**$80,456,908**	**$265,664,721**		**$41.87**

FPSC EXH No. 12
03/20/2024
ADMITTED

Florida Power & Light Company
Docket No. 20220001-EI
Staff's Fourth Set of Interrogatories
Interrogatory No. 50
Attachment 1 of 1
Tab 3 of 3

St Lucie Unit 1

Event Start	Event End	Seq. #	Event Title	MW Loss	Outage Hours	MWh Loss	Replacement Cost ($/MWh)	Replacement Cost ($)	TN3 Fuel Cost ($/MWh)	Nuclear Fuel Cost ($)	Net Replacement Cost ($)
A	B	C	D	E	F = (B - A) * 24	G = E * F	H = WA $/MWh	I = G * H	J = SL1 $/MWh	K = J * G	L = I - K
12/10/2021 10:24	12/12/2021 1:10	1	Manual Reactor Scram - Maintenance Personnel Error	981.00	38.77	38,030	$35.65	$1,355,924	$4.99	$189,905	$1,166,019
12/12/2021 1:10	12/12/2021 19:11	2	Manual Reactor Scram - Maintenance Personnel Error - Return to full power	485.21	18.02	8,742	$35.65	$311,682	$4.99	$43,653	$268,029
					56.78	**46,772**					**$1,434,048**
											$606,114 /Day

December 2021 - A4 Data	
SL1 Fuel Cost	**SL1 Heat Rate**
0.48	10,373
SL1 $/MWh	
$4.99	

December 2021 - A3 Data								
Fuel	**MWh**	**% Mix**	**Fuel Cost $**	**$/MWh**	**Demand $**	**Rev. Fuel Cost $**	**$/MWh**	**WA $/MWh**
Heavy Oil	1	0.00%	$79	$158.08	$0	$79	$158.08	$0.00
Light Oil	9,004	0.14%	$1,088,121	$120.85	$0	$1,088,121	$120.85	$0.16
Coal	167,208	2.52%	$5,989,715	$35.82	$0	$5,989,715	$35.82	$0.90
Gas	6,453,841	97.34%	$310,613,664	$48.13	$81,303,888	$229,309,776	$35.53	$34.59
Total	**6,630,053**	**100.00%**	**$317,691,579**		**$81,303,888**	**$236,387,691**		**$35.65**

FPSC EXH No. 12
03/20/2024

ADMITTED

E37

DECLARATION

I, Gerard J. Yupp, sponsored the answers to Interrogatory Nos. 29 and 30 and co-sponsored the answer to Interrogatory No. 26 from **Staff's Fourth Set of Interrogatories (Nos. 25-30)** to Florida Power & Light Company in Docket No. 20220001-EI, and the responses are true and correct based on my personal knowledge.

Under penalties of perjury, I declare that I have read the foregoing declaration and the interrogatory answers identified above, and that the facts stated therein are true.

Gerard J. Yupp

Date: 8/26/22

E34

FPSC EXH No. 13
03/20/2024
ADMITTED

13

As filed in Docket No. 20220001-EI, FPL's Response to Staff's Fifth Set of Interrogatories Nos. 31, 33, and 34

FPSC EXH No. 13
03/20/2024
ADMITTED

QUESTION:
Please refer to FPL's Response to OPC's First Interrogatories, No. 3.

a. Provide a full timeline of the February 2021 Turkey Point Unit 3 outage event from the outage occurring to the unit returning to service.

b. Identify the cause of the condenser tube leak, if available.

c. Explain if preventative maintenance would have prevented this outage. If not, explain why not.

d. Explain the preventative maintenance procedures that FPL followed regarding the condenser tube. As a part of this response, describe the manufacturer recommended replacement/maintenance schedule for this part and FPL's internal replacement/maintenance procedure for this part at the time that the outage occurred.

e. Provide the full maintenance schedule for the condenser tube. As a part of this response, explain if this maintenance schedule met either the manufacturer's recommended replacement/maintenance schedule or FPL's internal replacement/maintenance schedule at the time that the outage occurred. If not, explain why the procedure was not followed.

RESPONSE:
a.

DATE/ TIME	LOG ENTRY
2/2/2021 17:00	Outage Command Center (OCC) Staffed due to Unit 3 Sodium Intrusion. Unit 3 Down powered to 55% power to secure the 3A2 and 3A1 Circulating Water Pumps (CWP). Following the securing of the 3A CWPs sodium levels began to trend to pre-event values.
2/2/2021 19:00	Chemistry department to review trends, and/or water chemistry analyzer response to indicated increase in Hot well and Steam Generator sodium levels and/or other means available to ascertain approximate size of suspect condenser tube and/or tube to tube sheet leak(s). During a previous down power several tubes were plugged, either preventatively with rubber expandable plugs and/or with titanium "pop-a-plugs". This review is to check the condition of existing plugs i.e., looseness, or missing and to perform a verification that all tubes indicated as plugged from previous double-blind validations are still plugged on both ends

FPSC EXH No. 13
03/20/2024
ADMITTED

DATE/ TIME	LOG ENTRY
2/3/2021 9:00	3AS Waterboxes Open
2/3/2021 14:30	Engineering completed initial inspection of 3AS Waterbox Inspected and found clean Waterboxes and tubes, no need for hydrolazing at this time. Potentially will still require some cleaning of tubes selected for Eddy Current Testing ("ECT") or Borescope exam Some degradation found of water box to tube sheet Duromar coating which was applied December down power. Recommend to re-perform this down power as a preventative. Also recommend helium test of the areas where the coating degraded in the joint. Tube plugs that were accessible all looked intact, tight, properly installed. No loose tube plugs found laying in the inlet floor.
2/3/2021 15:59	Inspected and found overall clean Inlet/Outlet 3AS Waterboxes and tubes, no need for hydrolazing at this time. Note: potentially will still require some cleaning of tubes selected for ECT or Borescope exam. Tube plugs that were accessible all looked intact, tight, & properly installed. No loose tube plugs were found lying in the inlet floor. Some degradation found of water box to tube sheet Duromar coating, which was applied during the December down power, (approximate 6 linear inches near the floor and south wall) Note this initial inspection was performed without scaffold access to the entire tube sheet. Recommend helium test of the area especially where the coating degraded in the joint. Recommend: Remove plugs, clean tubes, and perform Non-Destructive Evaluation and visual inspection of known leakers; more coatings at the tube sheet to water box interface this down power as a preventative measure; Side note: Amertap screen patch plates installed 4/2020 look intact, no degradation noted. Minimal amounts of brown 20 mm soft Amertap balls and dimple plugs and pine tree needles in inlet water box. Minimal thin calcium pieces, one small piece metal recovered, inlet water box. See photos in folder.
2/4/2021 1:06	PTN U-3 OCC Update: U-3 Main Condenser Water Box Dimple Plug Installation progress. This is appx 80 percent complete.
2/4/2021 2:01	PTN OCC Update: U-3 AS Water Box Dimple Plug Progress. Maintenance reports the dimple leak test plug installation is complete.
2/4/2021 3:24	PTN OCC: Unit 3 A South Water Box Dimple Plug Leak Status Engineering Inspection Indications found on Dimple plugs in 3 separate tubes (Tubes showing leakage) Found on Inlet Side.
2/4/2021 3:33	Initial inspection following dimple plug installation was performed. Also inspected Duromar coating along tubesheet to waterbox seam towards the top of each waterbox. Outlet waterbox Duromar coating appeared intact. Inlet waterbox Duromar coating on the North side has several inches where coating needs to be re-touched (near Rows 50 and 75 of Section 1).

FPSC EXH No. 13
03/20/2024
ADMITTED

DATE/ TIME	LOG ENTRY
2/4/2021 8:28	Current plans are to remove the plugs on the existing known leakers. Prior to removing any existing tube plugs Shift Manager approval needs to be granted. OCC will look at risk associated with removing the plugs and schedule any High-Risk Challenge Meetings as required.
2/5/2021 1:39	System Engineer prepared spread sheet with tubes recommended for ECT in the 3AS bundle. A total of 105 tubes are being recommended for ECT.
2/5/2021 22:12	43 Tubes have been tested. Analysis is in progress. Appx 50%
2/6/2021 2:58	U-3 Water Box Phased Array ECT in progress: 59 Tested with Phase Array of 124. Results: 59 Analysis Complete. No defects noted
2/6/2021 5:11	Phased Array ECT in progress: 28 additional Tested with Phase Array of 124. Total of 87 completed.
2/6/2021 8:00	Current Status of 3AS Waterbox: • U3 remains at 55% power for investigation of the cause of the tube leaks. • ECT testing status: Data acquisition is complete on 122 of 124 tubes. The two tubes not completed are the tubes with recently identified leaks. The ECT was not done due to obstructions in the tubes. Borescope inspections of these tubes will occur this morning. We were unsuccessful performing ECT on the two previous leaking tubes due to a stuck plug in one and concern with challenging the unit due to air in-leakage on the other. Analysis of the ECT data will be complete today. This will define any scope expansion needed prior to returning the unit to 100%. • Duromar coating repair will happen in parallel
2/6/2021 10:00	Final two tubes have completed ECT. section 2 row 1 tube 8 and section 2 row 30 tube 31. Data review still in progress.
2/6/2021 10:30	Coatings in 3AS Waterbox performing Duromar repair.
2/6/2021 14:00	Duromar coating repair complete.

FPSC EXH No. 13
03/20/2024
ADMITTED

DATE/ TIME	LOG ENTRY
2/6/2021 20:40	PTN OCC Update: U-3 A South Water Box Boroscope Observations of the A South Water Box Tubes (From Outlet side) Tube 2-193-34 was observed to have debris obstructions with a fiberoptic scope and verified with a camera scope. The debris was broken up with a rod, and an Amertap ball was observed, and removed from the tube. During camera scope inspection several "rock-like" objects were observed and removed from the tube. 2-193-34 was inspected with two different camera scopes and from both the inlet and outlet side of the tube. Results: 2-193-34 was observed to have scale build-up throughout the tube (with a significant restriction 3"-6" from the outlet end of the tube). No indications were observed during the inspection that would indicate leakage (hole, crack, fissure). (From Outlet side) Tube 2-192-34 was observed to have an Amertap ball stuck in the tube at the outlet end. The ball was removed, and another Amertap ball was identified "behind" it. After removal of the second ball, a third Amertap ball was observed "behind" the second. When the third ball was removed a significant amount of water came out of the tube (> 2 gal). There was a scale ring on the ID of the tube that appeared to be restricting the Amertap balls from transiting the tube. (From Outlet side) Tube 2-30-31 was inspected with a camera scope from the outlet side approximately 40' length. No indications were observed during the inspection that would indicate leakage (hole, crack, fissure). Tube was relatively "clean" with only small areas of scale. (From Outlet side) Tube 2-1-8 was inspected with a camera scope from the outlet side approximately 40' length. No indications were observed during the inspection that would indicate leakage (hole, crack, fissure). Tube was relatively "clean" with only small areas of scale.
2/6/2021 22:12	PTN OCC Update: U-3 Main Condenser A South update 1: BHI is the water box cleaning the 24 tubes to be plugged with a poppet plug. 2: Operations place the U-3 Hogging Jet in service to support the Tube poppet plug replacement
2/6/2021 22:31	PTN OCC Update: U-3 A South Main Condenser Water Box Additional 20 Main Condenser tube to be plugged. (Obstructed Tubes)
2/6/2021 23:32	PTN U-3 OCC Update: Main Condenser A South Work BHI completed cleaning the tube ends on the first 24 tubes to be plugged.

FPSC EXH No. 13
03/20/2024
ADMITTED

DATE/ TIME	LOG ENTRY
2/7/2021 1:44	BHI completed poppet plug replacement. Vacuum remained steady at 27.22".
2/7/2021 1:45	PTN Unit 3 OCC Update: Main Condenser A South Water Box Repair the 2-149-1 Condenser tube replacement Outlet Titanium Poppet plug repair was completed. The old poppet plug was pushed into the tube. No issues were observed. This Tube repair was complete.
2/7/2021 3:49	PTN U-3 OCC Update: Main Condenser A South Water Box Repair Work BHI has completed 24 Tube Plugs on the Outlet Side and has completed 10 plugs on the Inlet Side. This rate is 34 plugs in 2 hours. The remaining plugs on the Inlet side is 14. The next 20 plugs require tube end cleaning and plug installation.
2/7/2021 4:39	PTN OCC Update: U-3 A South Water Box Repair Approved FAR 14 Plug tubes surrounding tube 2-149-1 by installing a PERMA PLUG .804" TITANIUM Pop-A-Plug Part Number VT804T on both ends of tubes IAW Vendor Manual V000944 "INSTRUCTION MANUAL FOR INSTALLATION OPERATION AND MAINTENANCE OF THE STEAM SURFACE CONDENSER REPLACEMENT TUBE BUNDLE MODULES" Additional Tubes To be plugged with Pop-A-Plugs
2/7/2021 7:00	Current Status: Completed initial 24 plugs on tubes that identified potential leaks (dimple test, Helium test or ECT) Tube end cleaning in progress (plug additional tubes that were obstructed) Validation that Conco cleaning equipment is staged and tested to support cleaning bottom rows of waterbox AES and BHI have coordinated to allow post maintenance testing with helium to overlap final tube plugging. identified 4 additional tubes that require plugging. • ECT status: Complete • Plug status: 24 tubes are plugged. The remaining 24 are in progress. Helium checks will start in parallel once the plugging team moves out of one side of the box. All tube plugs needed are on site. Flushing the bottom 16 rows has been sequence to tonight. Any tubes noted as blocked will be plugged. The current schedule does not reflect any contingency time for this work • 3rd party review is complete for return to power, and all agree with the scope. Future for the Fall refueling outage will be developed over the next few weeks.
2/7/2021 10:58	Work Order ready for - Check Cathodic Protection in 3AS Waterbox.

FPSC EXH No. 13
03/20/2024
ADMITTED

DATE/ TIME	LOG ENTRY
2/7/2021 11:00	BHI reported plugging is complete in the 3AS inlet waterbox. AES contacted for helium Post Maintenance Testing.
2/7/2021 12:18	Electrical Maintenance completed cathodic protection inspection inside Waterboxes. All anodes sat except for three that are blocked by scaffold. These will be inspected following scaffold removal.
2/7/2021 13:11	3AS Waterbox Inlet Waterbox plug installation verified by Maintenance.
2/7/2021 15:00	BHI reports all plugs have been installed. American Efficiency Services (AES) has commenced helium testing on inlet waterbox
2/7/2021 16:12	Inspect Cathodic Protection in the 3AS waterbox is complete no anomalies noted.
2/7/2021 16:15	AES has completed helium testing of inlet waterbox with no positive indications.
2/7/2021 17:26	PTN OCC U-3: Main Condenser A South Update AES Completed the Post Maintenance Testing with no Helium Indications on the Inlet or Outlet Water boxes.
2/7/2021 18:45	Engineering tube sheet plug validation complete.
2/7/2021 19:24	Final cleaning of the Waterbox is in progress with equipment set up
2/8/2021 1:11	3AS Waterbox tube cleaning 17/17 rows complete 1/4 tubes additional tubes are cleaned out
2/8/2021 1:24	PTN OCC Update: U-3 Main Condenser Work A South Box The Tube cleaning for the lower 17 rows is complete. 4 Tubes were rodded out to clean them. AES is signing on the clearance to start the Helium Leak Testing of the 17 lower rows
2/8/2021 4:32	engineering and maintenance inspection of plugs completed SAT
2/8/2021 4:56	Inlet DURAMAR coatings complete
2/8/2021 16:28	Informed System Dispatch that the U3 power ascension will commence at 1630 and return to full power 14 hours from now.
2/9/2021 2:05	Unit 3 Reactor Power is 90%
2/9/2021 4:00	Unit 3 Reactor Power is 100%.

FPSC EXH No. 13
03/20/2024
ADMITTED

b. The cause of the tube leak in the 3AS condenser was determined to be outer diameter mechanical wear due to loose material that was lodged in the condenser tube bundle. The source of the loose material was feedwater heater lagging that had broken loose from the condenser neck feedwater heaters during the cycle. The tubes found to be leaking were removed and sent out for forensic analysis. The Structural Integrity report concluded that there was no indication of hydride embrittlement and that the indentations/perforations in the tube sections containing flaws were all due to mechanical damage on the external surfaces.

c. Preventative maintenance would not have prevented this outage. Preventative maintenance on the condensers includes cleaning and eddy current testing ("ECT"). Scope of the ECT includes approximately 25% inspection of the condenser tubes, which includes peripheral tubing, previous indications, and a rotating sample of the remaining population that is targeted to achieve the nuclear industry standards of inspecting 100% of tubing within a 10-year timeframe. Routine outage maintenance for the condenser aids in identifying the foreign material and wear if it had existed at the time of the outage inspection. It is most likely the foreign material was generated during the cycle that followed the prior outage inspection. Additionally, FPL schedules routine inspections to ensure that all components are secured.

d. The preventative maintenance includes condenser tubing cleaning of all tubes using hydrolazing. Following cleaning, an ECT is conducted. The inspection uses bobbin coil eddy current probes to inspect all peripheral tubing, tubing with previous damage, and a rotating sample of existing tubing per industry standards. A rotating sample is tested because it is not possible to inspect each of the hundreds of thousands of tubes in the condenser. FPL plugs any of the inspected tubes that are found to be leaking. The leaking condenser tube in question was tube plugged to seal leaks during the emergent down power. The OEM recommended maintenance guidelines suggested performing inspections on a regular basis for possible trouble areas before major damage occurs. FPL follows this guidance by performing maintenance on the condenser tubing during every refueling outage, which occurs every 18 months.

   The OEM manual for replacement/maintenance recommends plugging tubes identified as leaking. OEM manual suggests not replacing tubing in the condenser unless significant tube plugging occurs (~10% plugged tubes), as this would cause impact to thermal performance of the unit. FPL adheres to the OEM recommendation. Since this level was not met at the time of the February 2021 event, tube replacement was not warranted.

FPSC EXH No. 13
03/20/2024

ADMITTED

e. FPL's full maintenance had been met prior to the February 2021 outage. The preventative maintenance schedule is executed only during a refueling outage which occurs every 18 months. For this tube, the last inspection would have been conducted in April 2020. Both the exterior and the interior components were inspected for signs of damage. The external inspection examined for areas around the condenser which had scorched paint and warped or cracked plates which would indicate possible overloading. Also, the shell plates are inspected for signs of abnormal pulling/pushing on plate which could be signs of over-stressed areas. Internal inspections occurred around the wall dump, waterbox, and hotwell. The inspections were conducted by managing supervisors, engineers, and chemistry personnel. As noted above, tube replacement is not pursued on a routine basis due to thermal performance margin available in the design of the component.

FPSC EXH No. 13
03/20/2024

ADMITTED

QUESTION:
Please refer to FPL's Response to OPC's First Production of Documents, No. 9, Document "PSL 12.10.21. CR 2413519".

a. Explain how the FIN Supervisor deviated from the FIN work management process. As a part of this response, describe the proper processes the FIN Supervisor should have followed.

b. Explain if the technician working on the electrical connections is an FPL employee. As a part of this response, describe the procedure that the technician should have followed.

c. Provide a list of training that the FIN Supervisor has received. In this response, highlight training that would be directly related to reviewing work plans and drawings, evaluation of clearance requests, review of work instructions, validating impact reviews and ensuring the control room is informed of the complete scope of work.

d. Provide a list of training that the technician working on the electrical connection has received. In this response, highlight training that would be directly related to use of an insulating barrier to prevent impacting the circuit from inadvertent contact.

e. Provide a list of training that the Maintenance Planner has received. In this response, highlight training that would be directly related to proper work package preparation and referencing drawings to provide accurate information to the FIN team.

RESPONSE:
a. The FIN Supervisor was informed that the Work Control Center (WCC) Senior Reactor Operators ("SRO") would be assisting with the performance of FIN work during the week of this event. However, the WCC SRO was not present when the FIN Supervisor went to the WCC to discuss the scope of the work to be performed. The designated WCC SRO for the day was briefing a crew for the restoration of an unrelated system at the station. The FIN Supervisor did not inform this SRO that the scope of work planned for the evolution included the replacement of the pressure differential indicating switch his did not give the SRO the opportunity to identify the potential impact of the work execution. If the FIN Supervisor would have followed procedure and notified the SRO that he was working with the electrical portion it would have alerted the SRO to review the drawings and identify that the electrical part of the circuit was not on the equipment clearance order and informed the FIN supervisor he could not proceed.

FPSC EXH No. 13
03/20/2024
ADMITTED

The FIN supervisor is responsible to ensure that the activities with operational impact receive the correct risk assessment per the Work Activity Risk Management process. In this case, the FIN supervisor did not challenge the work order planning and the proposed clearance boundaries that required mechanical isolation.

b. Yes, technician was an FPL employee. The employee should have followed existing FIN process procedure, all requirements provided in the Equipment Clearance Order, and the procedure for lifting and landing electrical connections.

c. The FIN Supervisor completed the following training: First Line Supervisor training, Maintenance Leadership Academy, and Instrument and Controls continuing training. All these listed are directly related to reviewing work plans and drawings, evaluation of clearance requests, review of work instructions, validating impact reviews and ensuring the control room is informed of the complete scope of work.

d. The Technician completed the following training: Level instrumentation, Fleet Instrument & Control Technician, Maintenance Fundamentals, Lifted Lead Verification, and Print Reading. Fleet IC Technician and Maintenance Fundamentals is directly related to the use of an insulating barrier to prevent impacting the circuit from inadvertent contact.

e. The maintenance planner completed the following training: Fleet Planner Initial training, Fleet Planner Continuing training, Functional and Post Maintenance Testing for Planners. Fleet Planner Initial training and Fleet Planner Continuing training is directly related to proper work package preparation and referencing drawings to provide accurate information to the FIN team.

FPSC EXH No. 13
03/20/2024

ADMITTED

QUESTION:
Please refer to FPL's Response to Staff's Second Interrogatories, No. 9, including the Company's Supplemental response.

a. **Provide a full timeline of the January 2022 St Lucie No. 2 outage event from the outage occurring to the unit returning to service.**

b. **If this outage event continued outside of the month of January, specify the monthly replacement power costs associated with the outage.**

c. **Explain if preventative maintenance would have prevented this outage. If not, explain why not. As a part of this response, explain the preventative maintenance procedures that FPL had in place at the time of the event and whether they were followed.**

d. **Explain the preventative maintenance procedures that FPL followed regarding the #27 Control Element Drive Mechanism. As a part of this response, describe the manufacturer's recommend replacement/maintenance schedule for this part and FPL's internal replacement/maintenance procedure for this part when the outage occurred.**

e. **Provide the full maintenance schedule of the #27 Control Element Drive Mechanism. As a part of this response, explain if this maintenance schedule met either the manufacturer's recommended replacement/maintenance schedule or FPL's internal replacement/maintenance schedule when the outage occurred. If not, explain why the procedure was not followed.**

FPSC EXH No. 13
03/20/2024
ADMITTED

RESPONSE:
a.

DATE/ TIME	LOG ENTRY
1/6/2022 8:42	Commenced Control Element Assembly (CEA) Exercise in accordance with procedure 2-OSP-66.01. Will be entering and exiting the PLANNED technical specification T.S.A.S 3.1.3.1 action f (1 hour) for each CEA, one at a time in accordance with 2-OSP-66.01, control element assembly exercise, due to each CEA being inserted >7" from its group. Also entering and exiting PLANNED technical specification T.S.A.S 3.1.3.5 for periodically inserting a shutdown CEA to less than 129 inches withdrawn. No action required; shutdown CEA insertion due to surveillance testing pursuant to specification 4.1.3.1.2.
1/6/2022 11:52	While withdrawing CEA #27, Reg group 2 per 2-OSP-66.01, CONTROL ELEMENT ASSEMBLY EXCERCISE, CEA# 27 slipped from 133 inches to 120 inches. All other REG Group 2 CEAs are at 135.75. (Major Deviation per 2-AOP-66.01). Entered 2-AOP-66.01. SM informed. AR# 02415359, wr# 94231142.
1/6/2022 13:09	U2 Control Room announces rapid down power in progress
1/7/2022 3:23	Shift Manager reported that CEA 24 CEA 25 and CEA 26 were fully exercised with no noted issues. CEA 27 had no motion.
1/7/2022 8:34	Lift Coil Cycling CEA #27 Obtained resistance readings on CEA1, CEA2, CEA3 and CEA4 and has provided to Engineering for evaluation.
1/7/2022 14:19	(Further Confirmation of Subgroup Electrical Circuit) Swap of cables for CEA 26 and CEA 27. No difference in CEA 27 movement with new cable.
1/7/2022 20:18	Shift Manger reports CEA Reg Groups 3, 4 and 5 were exercised with all performing satisfactorily.
1/9/2022 3:02	DRAIN PRESSURIZER TO 40%
1/9/2022 18:00	Westinghouse has commenced removing Control Element Drive Mechanism (CEDM) cables on the west end panels
1/10/2022 16:00	CEDM mechanical components (motor, motor housing, and upper pressure housing forming an assembly) have been released to maintenance (at risk) for removal of the motor assembly.
1/11/2022 4:29	Westinghouse reported 91 of 91 CEDM, RSPT, SPND cables have been disconnected.
1/11/2022 5:34	The cable tray has been removed from above the reactor head and has been placed on the "B" steam generator. Rigging is being disconnected from the cable tray.
1/11/2022 22:13	Coil Stack Removal Complete
1/13/2022 19:38	REPLACE CEA #27 - Sever and Prep Mid Canopy Seal Second cut is complete. Vacuuming is complete. Next steps are to perform inspection with a camera, followed by inspection with a feeler gauge. The inspections will be independently reviewed by Westinghouse management to confirm cut completeness.
1/13/2022 22:42	REPLACE CEA #27 - De-torque and Remove Upper Pressure Housing – Complete
1/14/2022 3:10	CEA #27 REMOVE LATCH MECHANISM

FPSC EXH No. 13
03/20/2024

ADMITTED

DATE/ TIME	LOG ENTRY
	Lifting in progress.
1/14/2022 5:04	CEA #27 ENHANCED VISUAL INSPECTION OF LATCH HOUSING WELD PREP -Complete
1/14/2022 6:03	Transfer New Motor to Motor Housing
1/14/2022 6:53	REPLACE CEA #27 - Clean Weld Prep
1/14/2022 7:48	REPLACE CEA #27 - Lower and install UPH (Upper Pressure Housing)
1/15/2022 1:21	CEDM: REINSTALL COIL STACK #27
1/15/2022 5:36	OPERATIONS PERFORM FUNCTIONAL TESTING OF CEDM #27
1/15/2022 7:40	REINSTALL COIL STACK #19
1/15/2022 8:10	REINSTALL COIL STACK #11
1/15/2022 8:39	REINSTALL COIL STACK #18
1/15/2022 9:05	REINSTALL COIL STACK #34
1/15/2022 9:36	REINSTALL COIL STACK #54
1/15/2022 10:10	REINSTALL COIL STACK #47
1/15/2022 10:39	REINSTALL COIL STACK #55
1/15/2022 11:08	REINSTALL COIL STACK #35
1/15/2022 13:54	SET RX CABLE TRAY IN PLACE & BOLT
1/15/2022 17:35	Pressurizer manway is installed and torqued.
1/17/2022 14:45	HEATUP TO 200 F, ENTER MODE 4
1/20/2022 17:32	Unit 2 Reactor is Critical.
1/20/2022 18:21	INCREASE RX POWER TO 2-5%
1/20/2022 18:41	OP INCREASE POWER TO 10% FOR TURB ROLL
1/20/2022 19:21	OP LATCH AND ROLL TURBINE TO 520 RPM
1/20/2022 20:28	Placed Unit 2 on the grid, Closed 8W49 bkr.
1/20/2022 22:26	INCREASE POWER TO 30%
1/20/2022 23:20	INCREASE POWER 30 TO 45%
1/21/2022 2:44	Current Status: In progress (64% power).
1/21/2022 3:39	Current Status: Stopped power ascension due to steam leak identified in C MSR drain line (78% power).
1/21/2022 7:46	Started the 2A Heater Drain Pump IAW 2-NOP-11.02 "HEATER DRAIN AND VENTS SYSTEM OPERATION"
1/21/2022 12:20	Secured power ascension at Full power

FPSC EXH No. 13
03/20/2024

ADMITTED

b. This event did not continue outside of the month of January. For the calculation of replacement power cost, please see FPL's response to Staff's Second Set of Interrogatories, No. 9.

c. Control Element Drive Mechanisms ("CEDM") are designed as life of the plant components and are integral to the Reactor Coolant System pressure boundary on the reactor vessel head. CEDMs are exercised through surveillance testing every 18 months. Through this preventative maintenance it was identified that CEDM #27 was not functioning properly.

d. CEDMs do not have a manufacturer's recommended replacement schedule. They are designed to function for the life of the plant. To perform the replacement, the failed CEDM # 27 had to be cut from the reactor vessel head and the replacement CEDM was installed and welded in place.

e. As mentioned in response subpart (d), there is no replacement frequency recommended by the manufacturer or an FPL internal replacement schedule. CEDMs are designed for life of the plant.

FPSC EXH No. 13
03/20/2024

ADMITTED

E53

DECLARATION

I, Dean Curtland, sponsored the answers to Interrogatory Nos. 31-34 from **Staff's Fifth Set of Interrogatories (Nos. 31-34)** to Florida Power & Light Company in Docket No. 20220001-EI, and the responses are true and correct based on my personal knowledge.

Under penalties of perjury, I declare that I have read the foregoing declaration and the interrogatory answers identified above, and that the facts stated therein are true.

Dean Curtland

Dean Curtland

Date: 10/3/22

E50

FPSC EXH No. 14
03/20/2024
ADMITTED

14

As filed in Docket No. 20220001-EI, FPL's Response to OPC's First Set of Interrogatories Nos. 1, 2, 3, 4, 5, 6, 7, 7 Supplemental, 8, 9, 10, and 11

FPSC EXH No. 14
03/20/2024

ADMITTED

QUESTION:
Please reference the January 20, 2021 GPIF Actual Unit Performance data schedules for December 2020:

Regarding Sheet No. 6.202.008 (Turkey Point Unit 4), please state if the EAF % of 51.3 for the month of July 2020 is attributable fully or in part to the Full Forced Outage (FFO) hours totaling 353.8 for 821 MW, beginning July 5, 2020 and the Partial Forced Outage (PFO) of 24.1 hours for 301.69 MW, beginning July 20, 2020, as shown on Sheet No. 6.202.039.

RESPONSE:
Yes. The decrease in Turkey Point Unit 4 July 2020 EAF from 97.5% (projected) to 51.3% is fully attributable to the event beginning July 5, 2020 totaling 397.9 hours. Per North American Electric Reliability Corporation (NERC) guidelines, the first 353.8 hours are coded as a Full Forced Outage (FFO). The remaining 24.1 hours of the outage, which are associated with the power ascension (returning the unit back to full capacity), are coded as a Partial Forced Outage (PFO).

FPSC EXH No. 14
03/20/2024

ADMITTED

QUESTION:
If the answer to Interrogatory No. 1 is yes, please identify the amount of replacement power cost attributable to the unit unavailability below an EAF of 100%. Please also identify the workpapers calculating such replacement power costs.

RESPONSE:
The net replacement power cost related to the Turkey Point Unit 4 event noted in FPL's response to Interrogatory No. 1 was $1,452,504. The calculation is provided in Attachment I to this Interrogatory.

FPSC EXH No. 14
03/20/2024

ADMITTED

QUESTION:
Sheet No. 6.202.041 (Turkey Point Unit 3) describes a power reduction on February 2, 2021 being caused by a condenser tube leak.

a. What was the cause of the condenser tube leak?

b. How was it corrected?

c. Was this condenser tube leak related to the condenser tube leak that occurred on December 16, 2020?

RESPONSE:

a. There are two potential apparent causes to this event: (1) A tube thru-wall leak, or (2) a crack due to external erosion / fatigue from steam in the condenser and foreign object impact damage. The tube was removed for forensics analysis. The analysis is not finalized.
b. FPL plugged the tubes with a mechanical plug device.
c. No.

FPSC EXH No. 14
03/20/2024

ADMITTED

QUESTION:

Please identify all documents related to any root cause analysis (or the functional equivalent, regardless of title), including drafts and related commentary correspondence, involving the forced outages which occurred at Turkey Point, Unit 3 in February 2021.

RESPONSE:
Please see FPL's response to OPC's 1st Request for Production of Documents, No. 19, Bates Nos. FCR-22-001907 through FCR-22-002103.

FPSC EXH No. 14
03/20/2024

ADMITTED

QUESTION:
Sheet No. 6.202.041 (Turkey Point Unit 3) describes a full forced outage on March 1, 2021.

a. Please describe in detail the events causing the reactor trip.

RESPONSE:
On March 1, 2021, Turkey Point Unit 3 was performing performed a planned test of the Reactor Protection System. The test restoration phase included closing the 3B reactor trip breaker and followed by opening the reactor bypass breaker. With the 3B reactor trip breaker closed and right after opening the 3B bypass breaker, the unit experienced an automatic shut down. FPL was not able to determine exact cause, but determined most probable cause was hardened graphite grease on the cell switch that resulted in incorrectly indicating the contact was closed when the contact was actually in an open state. The reactor trip breakers and switchgear cubicles were inspected in accordance with FPL procedures which provides a methodical and proven approach to maintain the equipment.

FPSC EXH No. 14
03/20/2024

ADMITTED

QUESTION:
Sheet No. 6.202.041 (Turkey Point Unit 3) describes a full forced outage on August 13, 2021 to repair the turbine control valve.

a. Please describe in detail the events causing the forced outage and the components of the turbine control valve that failed.

b. Please identify all work performed on the turbine control valve.

RESPONSE:

a. On August 13, 2021, Turkey Point Unit 3 reduced power to investigate the unexpected closure of the No. 2 Turbine Control Valve (TCV). FPL performed on-line verification activities before determining the unit was required to shut down to complete trouble shooting and implement repairs. FPL disassembled and inspected the TCV and found the actuator stem (rod) was found sheared right inside the treaded location inside the coupling. Testing determined that corrosion induced low cycle fatigue and potential misalignment were the most likely causes for the TCV actuator rod failure.

b. FPL replaced the actuator assembly and tested to ensure it was operating as designed.

FPSC EXH No. 14
03/20/2024

ADMITTED

QUESTION:
Sheet No. 6.202.041 (Turkey Point Unit 3) describes an outage extension of Cycle 32 RFO, beginning on November 7, 2021.

a. Please describe in detail the cause of the outage extension.

b. Provide describe in detail the original outage scope and what additional work was not included in the original scope that resulted in the outage extension.

RESPONSE:
Causal documents were not finalized in time to fully respond to this Interrogatory. FPL will supplement this response as soon as it is able.

FPSC EXH No. 14
03/20/2024

ADMITTED

QUESTION:
Sheet No. 6.202.041 (Turkey Point Unit 3) describes an outage extension of Cycle 32 RFO, beginning on November 7, 2021.

a. Please describe in detail the cause of the outage extension.
b. Provide describe in detail the original outage scope and what additional work was not included in the original scope that resulted in the outage extension.

RESPONSE:

a. The Turkey Point outage schedule development targets "best achievable" performance for each particular work scope and activity to perform maintenance and refuel the reactor safely and event free. FPL spends 18 months scoping, planning, and scheduling the work that is broken down into approximately 10,000 individual activities that are precisely scripted.

The outage includes hundreds of inspection activities to monitor the condition and validate the health of equipment and interconnecting system components. In the process of performing these inspections, there is often discovery which is not accounted for in a best achievable schedule and leads to extended time in every outage. Delays during an outage are not uncommon and FPL invests time in preparing to respond to those type of issues to mitigate their impact.

In the case of the Turkey Point Unit 3 November 2021 outage, the outage was extended a net 328 hours, which includes 91 hours recovered that mitigated the overall extension of the outage. Refer to FPL's supplemental response to OPC's First Request for Production of Documents No. 19 for additional information.

The largest impact on the outage extension was associated with equipment issues due to troubleshooting and replacement of the Manipulator Gripper and a reactor coolant system leak identified while bringing the unit back online during reactor vessel inspections. While performing scheduled gripper inspection prior to core offload, the manipulator gripper did not work as designed and was replaced. During post-maintenance testing following replacement of the gripper, the manipulator crane reported having load oscillations and relay chattering. The Relay Down Slack (RDS) relay (slack cable relay) was replaced to address the issue.

In addition, during the normal operating pressure and operating temperature reactor vessel inspections, a boric acid leak was identified on Core Exit Thermocouple (CET) 51 and 57 tubing. Based on initial available information, a thru-wall tube leak was suspected of causing the boric acid accumulation. Consequently, Unit 3 was cooled down from Mode 3 to Mode 5 to perform repairs. FPL repaired the affected fitting by cutting and capping the damaged tubing. FPL confirmed no leakage was present before returning the unit back to service.

FPSC EXH No. 14
03/20/2024
ADMITTED

The CET tubing was sent to Southwest Research Institute for a leak cause determination. The analysis determined no through-wall tubing pressure boundary flaw was identified. The forensic analysis determined that the connection fitting was the likely cause of the leakage. These combined issues, the Manipulator Gripper and reactor coolant system leak, resulted in a 169-hour impact to the outage extension.

Other impacts to the outage extension are summarized below:

Loss of 16 hours due to bulk activities prior to core reload. Electrical delays and loss of resources due to 3A Residual Heat Removal Pump Work and solenoid valve for containment air monitor failure.

Loss of 15 hours due to low resistance readings in the Turbine End and a damaged gasket that had to be replaced.

Loss of 22 hours due to having to repair the Steam Generator Blowdown Valve (SGB-3-020) and not able to drain the B Steam Generator. This delayed a mode change.

The remaining hours associated with the outage extension can be broken down into the following categories:

- Emergent issues with equipment discovered during the outage that either needed replacement or repair to remedy an issue
- Resource availability
- Unexpected and unplanned re-performance of work
- Weather-related delays

In addition, please see FPL's supplemental response to OPC's First Request for Production of Documents No. 19 for details describing the gains and losses that contributed to the total number of additional hours required for the outage.

b. As discussed in subpart (a) above, during a typical planned refueling outage, there are thousands of work orders that define the original outage scope. The equipment issues described in FPL's supplemental response to subpart (a) and the documents provided in FPL's supplemental response to OPC's First Request for Production of Documents No. 19 provide details of the work that was not part of the original outage scope.

FPSC EXH No. 14
03/20/2024

ADMITTED

QUESTION:
Sheet No. 6.202.039 (St. Lucie Unit 1) describes an outage extension of SL 1-30, beginning on May 14, 2021.

a. Please describe in detail the cause of the outage extension.

b. Describe in detail the original outage scope and what additional work was not included in the original scope that resulted in the outage extension.

RESPONSE:

a. In May 2021, while St. Lucie Unit 1 was in plant restart from this outage, FPL determined the Lower Gripper Coils for a group of control element assemblies had malfunctioned. Future troubleshooting revealed these coils were damaged by excessive current. While revising the firmware for the Rod Control System Coil Power Management Drawer (CPMD) for these coils, the firmware vendor inadvertently coded an unplanned software change. This removed the overcurrent protection for the impacted control element assemblies.

b. The corrected software was programmed in into the CPMD. The vendor validated that all software was correct. This work was not included in the original outage scope.

FPSC EXH No. 14
03/20/2024

ADMITTED

QUESTION:
Regarding Sheet No. 6.202.039 (St. Lucie Unit 1), please describe in detail the cause of the manual trip that occurred on December 12, 2021.

a. How was it corrected?

RESPONSE:
St. Lucie Unit 1 was manually tripped in response to Steam Generator Water Level lowering to less than 50% from a secondary transient initiated from the loss of the feedwater level control system. The event was initiated while replacing a Pressure Differential Indicating Switch (PDIS) that was isolated earlier in the week in response to a steam leak at the PDIS. In the process of landing the wires from the new PDIS on the terminal strip, the technician made inadvertent contact with the enclosure housing resulting in the supply fuse to blow and a loss of high-pressure heater level control, and a reduction of Steam Generator feed flow.

a. FPL replaced the supply fuse, restored the heater level control circuit and PDIS.

FPSC EXH No. 14
03/20/2024

ADMITTED

QUESTION:
Regarding Sheet No. 6.202.040 (St. Lucie Unit 2), please describe in detail the event on January 14, 2021 associated with the "4kV Breaker Down" and subsequent events associated with this breaker.

a. What was the failure mechanism?

b. How was it corrected?

RESPONSE:
The 4kV breaker for the 1A Auxiliary Transformer had a leaking SF6 gas suppression bottle. In order to avoid failure as a result of a bottle having no gas, the unit was required to be removed from service in order to deenergize the respective bus. This facilitated the replacement of the respective breaker to ensure there was no arc created during the opening of the breaker.

a. The failure mechanism was a leaking bottle.

b. FPL replaced the entire breaker with a refurbished and tested breaker. All the breakers that would require reducing power and or taking the unit offline have been changed out to the new style breaker on both units. FPL has an ongoing project to remove all SF6 gas bottle style breakers at the site.

FPSC EXH No. 14
03/20/2024

ADMITTED

QUESTION:
Regarding Sheet No. 6.202.040 (St. Lucie Unit 2), please describe in detail the events on January 20th and 23rd of 2021 associated with the "Auto Trip 2B2 MCC Trip" and subsequent associated events.

a. What was the failure mechanism?

b. How was it corrected?

RESPONSE:

On January 20, 2021, Unit 2 automatically shut down due to the Reactor Protection System trip as a result of a turbine trip. The turbine trip was caused by an unexpected deenergization of the 480V Motor Control Center (MCC) 2B2. The plant equipment responded as designed. The loss of the MCC caused two of the four undervoltage (UV) relays in the Diverse Turbine Trip (DTT) to deenergize to their failed condition which created a turbine trip. FPL investigated the root cause and determined the legacy drawings for the UV relay assemblies in the control element drive mechanism control system (CEDMCS) were changed in 1983 and did not conform to St. Lucie Unit 2 train and channel design conventions such that design details including power supply assignments were not clearly defined. This latent legacy defect resulted in inadvertently mis-assigning power to two of the four UV relays to the incorrect train of power when the rod control system was replaced 38 years later in 2019. There was no adequate basis upon which to reasonably expect that the latent channel misassignments should have been identified during the work performed in 2019.

On January 23, 2021, the unit was in power ascension back to 100% power from the event described above.

a. See event description above.

b. FPL redesigned the UV relay power supplies such that the loss of a single power supply will not result in a turbine trip. FPL also revised UV Relay Assembly drawing to show applicable train channel assignments to each UV Relay Assembly and revised the CEDMCS Power Supply drawing to show the UV Relay Assembly assignment to each power supply.

FPSC EXH No. 14
03/20/2024

ADMITTED

E68

DECLARATION

I sponsored the answer to Interrogatory No. 7 Supplemental from **CITIZEN'S FIRST SET OF INTERROGATORIES (NOS. 1-13)** to Florida Power & Light Company in Docket No. 20220001-EI. The responses are true and correct based on my personal knowledge.

Under penalties of perjury, I declare that I have read the foregoing declaration and the interrogatory answers identified above, and that the facts stated therein are true.

Dean Curtland

Dean Curtland

Date: 5/27/22

E65

FPSC EXH No. 15
03/20/2024
ADMITTED

15

As filed in Docket No. 20220001-EI, FPL's Response to OPC's Second Set of Interrogatories No. 14

FPSC EXH No. 15
03/20/2024

ADMITTED

Florida Power & Light Company
Docket No. 20220001-EI
OPC's 2nd Set of Interrogatories
Interrogatory No. 14

QUESTION:
Gain/Loss Form. Please state the purpose of the document produced at the page field from Bates Nos. FCR-22-002142 through FCR22-002252. Also, please state the term by which you commonly refer to this type of document.

RESPONSE:
This form is commonly referred to as a Gain Loss form. This document is used to capture lessons learned and best practices for current and future outages. It is also used to take immediate actions to preserve any schedule gains or minimize losses.

FPSC EXH No. 15
03/20/2024
ADMITTED

DECLARATION

I, Dean Curtland, sponsored the answers to Interrogatory Nos. 14-35 from **OPC's Second Set of Interrogatories (Nos. 14-35)** to Florida Power & Light Company in Docket No. 20220001-EI, and the responses are true and correct based on my personal knowledge.

Under penalties of perjury, I declare that I have read the foregoing declaration and the interrogatory answers identified above, and that the facts stated therein are true.

Dean Curtland

Date: 8/15/2022

FPSC EXH No. 16
03/20/2024
ADMITTED

16

As filed in Docket No. 20220001-EI, FPL's Response to OPC's Third Set of Interrogatories Nos. 36, 41, 42, 43, 44, 45, 46, 47, 48, 49, and 50

FPSC EXH No. 16
03/20/2024

ADMITTED

Florida Power & Light Company
Docket No. 20220001-EI
OPC's Third Set of Interrogatories
Interrogatory No. 36

QUESTION:
Regarding the Turkey Point Unit 4 July 2020 outage – PMG Failure & Exciter Water Intrusion, when was the maintenance performed on the exciter in which Siemens failed to install the weather seal?

RESPONSE:
The Turkey Point Unit 4 exciter enclosure was last removed during the Spring 2019 outage. Exciter base seals were inspected for serviceability prior to re-installation. There was no known indication of a leak in the PMG compartment when the unit was returned to service.

FPSC EXH No. 16
03/20/2024
ADMITTED

QUESTION:
The following question relates to St. Lucie Unit 2, January 2021 MCC Malfunction:

Regarding Mr. Curtland's testimony, page 7 lines 8-22,

a. Please provide a description of the rod control system replacement that occurred in 2019.

b. Please describe the testing of the rod control system after replacement in 2019.

c. Please describe the interface between the rod control system and the 480 V MCC that deenergized in January 2021.

d. Was circuit breaker 2-40404 tested as part of the rod control system?

RESPONSE:

a. The rod control system replacement that occurred in 2019 was a large project that followed the Enterprise Risk Process. This project replaced the original Combustion Engineering Electro-Mechanical Rod Control System with a state-of-the-art Westinghouse Advanced Rod Control Hybrid (ARCH) digital control system. The system was replaced due to obsolescence and reliability issues.

   The new rod control system is based on the design developed for the new Westinghouse AP1000 and APR1400 Second Generation Nuclear Plants. The generic ARCH design was slightly modified to interface with existing St. Lucie rod control hardware configuration and other equipment that was not replaced.

   The control logic portions of the new rod control system (RCS) were implemented using the Ovation hardware/software platform that interfaced the operator controls with the coil power portion of the system. The Ovation system also interfaces with plant annunciators and provides the rod control system interlocks and permissives.

b. As part of the Enterprise Risk Process, extensive testing was performed on the rod control system consisting of the following phases: (1) Factory Acceptance Testing, (2) Site Acceptance Testing, and (3) Functional Testing.

   The Factory Acceptance Testing consisted of 2 months of rigorously testing the fully assembled equipment at Westinghouse prior to shipment. These tests were performed under an approved test plan with oversight provided by both FPL and an independent third party vendor.

FPSC EXH No. 16
03/20/2024
ADMITTED

The Site Acceptance Testing consisted of testing every aspect of the installed equipment. Every component and every circuit within the project boundary were exercised. Site Acceptance testing included the following:

- Continuity checks for all conductors installed.
- Insulation resistance tests on all affected conductors.
- Performed dB Loss test for all installed Fiber Optic communications.

The following Site Acceptance Testing was subject to the following procedures:

- o FSP-I&CFS-19-05 "SAT Rod Control System"
- o FSP-I&CFS-19-07 "SAT Rod Position Indication"
- o FSP-I&CFS-19-09 "SAT Turbine Control System"

The Functional Testing included the following:

- Withdrawal and insertion checks of control element drive mechanism (CEDM) to validate that the RCS interface with St. Lucie CEDMs is performing per design and to ensure all CEDM coil current traces are proper.
- Control Element Assembly (CEA) Block Circuit Testing to validate RCS CEA motion inhibit interlocks are fully functional.
- Reed Switch Position Transmitter (RSPT) Calibration and Circuit Checks to validate RPI interface with St. Lucie RSPTs performs per design.
- Turbine Throttle Valve Calibration and Circuit Checks to validate Turbine Control System (TCS) interface with PSL throttle valves performs per design.
- Turbine Governor Valve Calibration and Circuit Checks to validate the TCS interface with PSL governor valves performs per design.

All tests were completed satisfactory

c. The 480V motor control center (MCC) that was deenergized in January 2021 is outside of the rod control system's boundary. However, two of the four under voltage relays (UVs) powered from this MCC reside within a rod control cabinet. These UVs were not replaced as part of the project. However, all the power cabling within the cabinet was removed during construction and new cabling was re-installed in accordance with the design drawings. Nevertheless, there was a legacy drawing omission that was not apparent, nor reasonably should have been apparent, to the project engineers. This omission eliminated the redundancy

FPSC EXH No. 16
03/20/2024

ADMITTED

provided by the intended UV trip logic of two out of four taken twice. Therefore, the loss of the single MCC caused a reactor trip.

d. Circuit Breaker 2-40404 was tested during its normal scheduled preventive maintenance (February 2017), but it was not tested as part of the Rod Control System tests. The breaker was outside of the project's scoped boundary.

FPSC EXH No. 16
03/20/2024

ADMITTED

Florida Power & Light Company
Docket No. 20220001-EI
OPC's Third Set of Interrogatories
Interrogatory No. 42

QUESTION:
The following question pertains to Turkey Point Unit 3 RFO 32, and the problems encountered with the Manipulator Gripper during Cycle 32 RFO:

Prior to the start of the Cycle 32 RFO in November 2021, when was the last time the Manipulator Gripper had been used?

RESPONSE:
The manipulator gripper is only used to move fuel during refueling outages. The last time the Manipulator Gripper was used prior to the start of Cycle 32 RFO was during the immediately preceding March 2020 outage (Cycle 31 outage).

FPSC EXH No. 16
03/20/2024

ADMITTED

Florida Power & Light Company
Docket No. 20220001-EI
OPC's Third Set of Interrogatories
Interrogatory No. 43

QUESTION:
The following question pertains to Turkey Point Unit 3 RFO 32, and the problems encountered with the Manipulator Gripper during Cycle 32 RFO:

How is the Manipulator Gripper stored between outages? Provide specifications for Manipulator Gripper storage.

RESPONSE:
The manipulator gripper is permanent installed hardware that remains inside containment during the operating cycle. When not in use, the refueling bridge that supports the manipulator gripper is locked in a safe storage location. The gripper remains attached to the inner refueling mast which hangs freely from the bridge with no other contact.

FPSC EXH No. 16
03/20/2024

ADMITTED

Florida Power & Light Company
Docket No. 20220001-EI
OPC's Third Set of Interrogatories
Interrogatory No. 44

QUESTION:
The following question pertains to Turkey Point Unit 3 RFO 32, and the problems encountered with the Manipulator Gripper during Cycle 32 RFO:

When was the Manipulator Gripper first tested in preparation for the outage?

RESPONSE:
The manipulator gripper is tested every outage, including RFO 32, prior to fuel moves.

FPSC EXH No. 16
03/20/2024

ADMITTED

Florida Power & Light Company
Docket No. 20220001-EI
OPC's Third Set of Interrogatories
Interrogatory No. 45

QUESTION:
The following question pertains to Turkey Point Unit 3 RFO 32, and the problems encountered with the Manipulator Gripper during Cycle 32 RFO:

Please describe the Manipulator Gripper testing procedures.

RESPONSE:
The manipulator gripper is tested every outage prior to fuel moves. The manipulator gripper testing consists of both "dry" and "wet" checks. Dry checks are performed prior to the cavity being flooded in preparation for the fuel off-load. The dry checks include manipulator gripper physical inspections, as well as load testing. The inspections are performed under site procedure 0-PMM-038.01, Section 4.7, Manipulator Crane Gripper Inspection. Load testing is performed under site procedure 3-OSP-038.2, Section 7.4, Load Test Using Installed Test Weight (Cavity Not Flooded). Wet checks are performed after the cavity is flooded but before fuel movements under site procedure 3-OSP-038.2, Manipulator Crane Operability Test. The final wet checks involve the use of dummy assembly to fully simulate actual fuel moves.

FPSC EXH No. 16
03/20/2024

ADMITTED

Florida Power & Light Company
Docket No. 20220001-EI
OPC's Third Set of Interrogatories
Interrogatory No. 46

QUESTION:
The following question pertains to Turkey Point Unit 3 RFO 32, and the problems encountered with the Manipulator Gripper during Cycle 32 RFO:

Please describe the outage contingency plans in the event the Manipulator Gripper fails during the refueling outage.

RESPONSE:
Contingency outage plans are developed in accordance with fleet procedure, OM-AA-101-1013, Fleet Outage Milestones, provided in FPL's response to OPC's Request for Production of Documents, No. 33. In addition, the Reactor Support Services group, which is responsible for the operation and maintenance of the Manipulator Gripper, ensures their outage preparedness accords with fleet procedure, OM-AA-101-1007, High Impact Teams. Finally, the manipulator gripper original equipment manufacturer provides 24/7 on-site emergent issue support during the operation of the refueling equipment.

FPSC EXH No. 16
03/20/2024

ADMITTED

Florida Power & Light Company
Docket No. 20220001-EI
OPC's Third Set of Interrogatories
Interrogatory No. 47

QUESTION:
The following question pertains to Turkey Point Unit 3 RFO 32, and the problems encountered with the Manipulator Gripper during Cycle 32 RFO:

Please describe the failure mechanism for the Manipulator Gripper.

RESPONSE:
The failure investigation included an off-site forensics analysis performed under Framatome Report 51-9341663-000, Turkey Point Unit 3 15x15 Gripper Evaluation. The evaluation found that the manipulator gripper fingers were outside of design tolerances, resulting in the latching issues.

FPSC EXH No. 16
03/20/2024

ADMITTED

Florida Power & Light Company
Docket No. 20220001-EI
OPC's Third Set of Interrogatories
Interrogatory No. 48

QUESTION:
The following question pertains to Turkey Point Unit 3 RFO 32, and the problems encountered with the Manipulator Gripper during Cycle 32 RFO:

Please provide the RCA for the Manipulator Gripper failure.

RESPONSE:
An RCA was not prepared for this event. However, forensics examination was performed as discussed in FPL's answer to OPC's Third Set of Interrogatories No. 47.

FPSC EXH No. 16
03/20/2024

ADMITTED

Florida Power & Light Company
Docket No. 20220001-EI
OPC's Third Set of Interrogatories
Interrogatory No. 49

QUESTION:
The following question pertains to the core exit thermocouple tubing leaks after completion of Cycle 32 RFO:

Were there any maintenance activities during the outage on Core Exit Thermocouples 51 and 57?

RESPONSE:
There are four core exit thermocouple (CET) columns that penetrate the reactor head that contain multiple CETs and pressure boundary tubing.

Consistent with routine refueling activities required to remove the reactor head, the CET columns were electrically disconnected, seals removed, and the columns were covered with protective "bullet noses" to seal the electrical connections during cavity flood-up. In addition, the electrical connections of each CETs were tested and cleaned as part of a CET replacement project. However, these activities were not performed in the area where the leaks were discovered.

The leaks occurred on Swagelok connections on individual CET tubing associated with the column 51 and 57. Column 51 has twelve CETs and Column 57 has thirteen CETs. The tubing leaks occurred on CET N-8 for column 51 and CET H-9 for column 57. The leaks were repaired by cutting-out the effected tubing sections and replacing the Swagelok fittings and capping the ends.

A CET replacement project was performed during the outage. However, CETs H-9 and N-8 were not included in the scope of that project.

Forensic testing and inspections were performed on the replaced parts. However, the inspections did not identify any material issues or evidence of physical damage that could have caused the leaks.

FPSC EXH No. 16
03/20/2024

ADMITTED

Florida Power & Light Company
Docket No. 20220001-EI
OPC's Third Set of Interrogatories
Interrogatory No. 50

QUESTION:
The following question pertains to the core exit thermocouple tubing leaks after completion of Cycle 32 RFO:

Was there any inspection of the core exit thermocouples tubing during the outage?

RESPONSE:
The thermocouple pressure boundary is inspected following plant shutdown in accordance with the Boric Acid Inspection Program. The thermocouple pressure boundary is also subject to the ASME Section XI pressure test requirements prior to returning the unit service. No leaks were identified during this inspection

FPSC EXH No. 16
03/20/2024

ADMITTED

E86

DECLARATION

I, Dean Curtland, sponsored the answers to Interrogatory Nos. 36, 37(a) and (b), 38(a) and (b), 39(a) and (b), 40(a) and (b), and 41-50 from **OPC's Third Set of Interrogatories (Nos. 36-50)** to Florida Power & Light Company in Docket No. 20220001-EI, and the responses are true and correct based on my personal knowledge.

Under penalties of perjury, I declare that I have read the foregoing declaration and the interrogatory answers identified above, and that the facts stated therein are true.

Dean Curtland

Dean Curtland

Date: 8/16/2022

E83

FPSC EXH No. 17
03/20/2024
ADMITTED

17

As filed in Docket No. 20220001-EI, FPL's Response to OPC's First Request for Production of Documents Nos. 3, 8, 9, 13, 14, 15, 16, 18, 19, and 19 Supplemental

(Including Attachments)

FPSC EXH No. 17
03/20/2024

ADMITTED

Florida Power & Light Company
Docket No. 20220001-EI
OPC's First Request for Production
Request No. 3

QUESTION:
Provide all copies of root cause analysis of all reactor events for all Turkey Point Units issued in calendar years 2019 through 2022.

RESPONSE:
Subject to and without waiving FPL's general objections and specific objections to this discovery request, FPL produces responsive documents on CD as Bates Nos. FCR-22-000336 through FCR-22-000650.

FPSC EXH No. 17
03/20/2024

ADMITTED

Florida Power & Light Company
Docket No. 20220001-EI
OPC's First Request for Production
Request No. 8

QUESTION:
Provide copies of all event reports associated with reactor operations provided to the Nuclear Regulatory Commission for all St. Lucie Units issued in calendar years 2019 through 2022.

RESPONSE:
Subject to and without waiving FPL's general objections and specific objections to this discovery request, FPL produces responsive documents on CD as Bates Nos. FCR-22-000913 through FCR-22-000940.

FPSC EXH No. 17
03/20/2024

ADMITTED

E90

Florida Power & Light Company
Docket No. 20220001-EI
OPC's First Request for Production
Request No. 9

QUESTION:
Provide all copies of root cause analysis of all reactor events for all St. Lucie Units issued in calendar years 2019 through 2022.

RESPONSE:
Subject to and without waiving FPL's general objections and specific objections to this discovery request, FPL produces responsive documents on CD as Bates Nos. FCR-22-000941 through FCR-22-001243.

E87

FPSC EXH No. 17
03/20/2024

ADMITTED

Florida Power & Light Company
Docket No. 20220001-EI
OPC's First Request for Production
Request No. 13

QUESTION:
Please produce all event descriptions, notices to the NRC, and any root cause analyses related to the March 1, 2021 event referenced in Interrogatory No. 5.

RESPONSE:
Documents responsive to this request are provided on CD as Bates Nos. FCR-22-001373 through FCR-22-001409. Additionally, see FPL's response to OPC's First Request for Production of Documents Nos. 1 through 4.

FPSC EXH No. 17
03/20/2024

ADMITTED

E92

Florida Power & Light Company
Docket No. 20220001-EI
OPC's First Request for Production
Request No. 14

QUESTION:
Please produce all documents and correspondence, including but not limited to emails, related to the December 12, 2021 manual trip at St. Lucie Unit 1, referenced in Interrogatory No. 9.

RESPONSE:
Documents responsive to this request are provided on CD as Bates Nos. FCR-22-000283 through FCR-22-000316 and FCR-22-001540 and FCR-22-001667. Additionally, see FPL's response to OPC's First Request for Production of Documents No. 9.

FPSC EXH No. 17
03/20/2024

ADMITTED

E93

Florida Power & Light Company
Docket No. 20220001-EI
OPC's First Request for Production
Request No. 15

QUESTION:
Please produce all documents and correspondence, including but not limited to emails, related to the January 14, 2021 event at St. Lucie Unit 2, referenced in Interrogatory No. 10.

RESPONSE:
Documents responsive to this request are provided on CD as Bates Nos. FCR-22-001668 through FCR-22-001801.

FPSC EXH No. 17
03/20/2024

ADMITTED

E94

Florida Power & Light Company
Docket No. 20220001-EI
OPC's First Request for Production
Request No. 16

QUESTION:
Please produce all documents and correspondence, including but not limited to emails, related to the January 20 and 23, 2021 St. Lucie Unit 2 Auto Trip 2B2 MCC Trip referenced in Interrogatory No. 11.

RESPONSE:
Documents responsive to this request are provided on CD as Bates Nos. FCR-22-001802 through FCR-22-001873 and FCR-22-001902 through FCR-22-001906. Additionally, see FPL's response to OPC's First Request for Production of Documents No. 9.

E91

FPSC EXH No. 17
03/20/2024

ADMITTED

E95

Florida Power & Light Company
Docket No. 20220001-EI
OPC's First Request for Production
Request No. 18

QUESTION:
Please produce all documents and correspondence, including but not limited to emails, related to the October 2, 2021 St. Lucie Unit 2 2B1 Water Box event referenced in Interrogatory No. 13.

RESPONSE:
Document responsive to this request are provided on CD as Bates No. FCR-22-001875.

FPSC EXH No. 17
03/20/2024
ADMITTED

AT-01.16 Single AR Report

Report Date: E96
03/16/2022 10:16:13 AM

AR No: **02405998** Subject: **DOCUMENTATION OF SODIUM TRENDS DURING SL2-26 START-UP**

Facility	Type	Status	Significance	Originated On	Discovered On	Due Date	How Event Identified
PSL	CR	COMP-NA	3	Oct 2, 2021	Oct 2, 2021	Nov 4, 2021	SELF REVEALING

Orginator	Orig Dept	Originating Facility	Owed To Name	Owed To Grp	Owed To Dept	Owed To Facility
Schroth, Patrik M	PSL Chemistry-00 (620014)	PSL	Feightner, Erik C		PSL Training-00 (620008)	PSL

Attribute	Value
Sub Category: OPD	
A AFFECT STATUS OF SSC	N
B DEGRADED/NONCONFORM	N
C EQ OPERABLE PER TS	N
D MODE SSC OPERABLE	N
E PAST OPERABILITY	N
F REPORTABLE TO NRC	N
G REQ SR MGMT NOTIFY	N
H NON-TAMPERING ISSUE	Y
Sub Category: SCREEN	
A CND ADVRS TO QUALITY	NCAQ
B GOOD CATCH?	N
C SECURITY SENSITIVE	N
D MODE/MILESTONE RESTRICTION	N
E MAINT RULE SYS	Y
F MAINT RULE FUNC FAIL	N
G MAINT RULE PREV FAIL	N
H PART 21 ISSUE	N
I HUMAN PERFORMANCE ISSUE	N
J TRENDING VALIDATED?	Y
K INTERNAL/EXTERNAL OE	N
L ADDTL REVIEW REQ	N
M MRC EVAL REV REQUIRED	N
N IST SCREEN COMP?	Y
O MRC SCREEN COMPL	Y
P DRY FUEL STORAGE RETENTION	N
Q EQUIPMENT FAILURE	NA
R ENTERPRISE RISK	N

Key Coding	Keys	Keyword Description
Key Coding	CHEMCEI	CHEMISTRY EFFECTIVENESS INDICATOR

Description

This CR is being generated for documentation of sodium trends that Chemistry observed during Unit 2 start up from SL2-26.
During start-up, SG sodium was trending down as expected until ~1300. At 1300 SG sodium began trending up with no changes in blowdown. This correlates with the starting of the 2A2 Circulating Water Pump. At the time that the 2A2 Circulating Water Pump was started, the 2B1 HW sodium analyzer was not available due to the 2B1 Hotwell Sample Pump being out of service. Because the 2B1 Hotwell could not be directly monitored, the 2B1 sodium analyzer was aligned to the U2 Condensate discharge header. At the time that the 2A2 Circulating water pump was started the following trends were observed:
Cond Discharge Sodium: 1st indication of rising sodium and highest magnitude of sodium increase
2A1 Hotwell Sodium: 2nd indication of rising sodium, but lowest magnitude
2A2 Hotwell Sodium: 3rd indication of rising sodium, 2nd highest magnitude
2B2 Hotwell Sodium: 4th indication of rising sodium, 2nd lowest magnitude
2B1 Hotwell Sodium: unable to be observed at the time due to the sample pump being out of service
Both SG's Sodium increased at a proportional magnitude correlating to the start of the 2A2 Circulating water pump. Since this event, SG sodium has lowered at a significantly slower rate and has seen small increases periodically correlating to condensate sodium increases.
Following this event, the combination of Hotwell, Condensate and SG sodium trends suggest that there is a very small constant seawater ingress to the condenser and intermittent, short increases in the leak rate as seen by small "Spikes" in condensate discharge sodium.
On only 2 occasions following this event, the 2A2 hotwell saw very slight increases in sodium consistent in timing with increases in condensate sodium but of much lower magnitude. The 2A1 and 2B2 hotwells continued to trend down with no "spikes" following this event.
The inability to directly monitor the 2B1 hotwell hiders the analysis of this event, however by comparing the condensate discharge sodium to all other sodium indications it can be implied that the most likely source of ingress is a leak from the 2B1 tubes. Based on the magnitude of sodium "spikes" and correlation the other hotwells it is suspected that the likely location of the leak is a tube or tubes on the north side of the 2B1 tube bundle, closest to the 2A2 hotwell. Additionally, since the leak is constant with some intermittent spiking, a tube plug issue could be a likely source.
This event correlates with the starting of the 2A2 Circulating Water Pump, since the most likely source is in the 2B1 tube bundle, a likely cause is thermal stresses due to the rapid change in thermal conditions in the 2A2 tube bundle region or the condenser, which could have interrupted a "weak spot" in the 2B1 tube bundle.
Unit: 02
Equipment Name:
Unit 2 Condenser Sodium
Equipment Location:
Unit 2

Notes

IMMEDIATE ACTIONS

FPSC EXH No. 17
03/20/2024

ADMITTED

E97

Notes
Added wood flour to the 2B1 Intake well Secured the 2B1 Circulating Water Pump
MANAGEMENT NOTIFIED
OCC
MRC NOTES
10/6: Waterbox removed from service, tubes plugged and returned to service.
OPERABILITY NOTES
The condition does not constitute a new degraded or unanalyzed condition involving an SSC that is either required to be OPERABLE per TS or required to perform a support function for such SSCs. Therefore, an OPERABILITY determination is not required. Also, the condition does not constitute a new degraded or unanalyzed condition that involves the ability of a non-TS SSC to perform its specified CLB function. Therefore, a Functionality Assessment is not required. The condition does not meet the reporting criteria of 10 CFR 50.72.
RECOMMENDED ACTIONS
Open the 2B1 water box and investigate for potential sources
SCREENING NOTES
CAT 3/20. Close to actions taken. Wood flour additions were made, and inspection and repairs were completed for the 2B1 water box. DJO 10/04/2021.

Doc No	Doc Title	Type/ Sub-Type	Mjr/Mnr Rev No
02405998	DOCUMENTATION OF SODIUM TRENDS DURING SL2-26 START-UP	AR/CR	

Trend Rank	TC 1	TC 2	TC 3	Organization
	CPE	CP23	9	NA
	PROC	P2	5	NA

E94

FPSC EXH No. 17
03/20/2024

ADMITTED

Florida Power & Light Company
Docket No. 20220001-EI
OPC's First Request for Production
Request No. 19

QUESTION:
Produce copies of the documents identified in or related to the answers to Interrogatory Nos. 2 through 13.

RESPONSE:
Documents responsive to this request are provided on CD as Bates Nos. FCR-22-001876 through FCR-22-001901 and FCR-22-001907 through FCR-22-002103. Additionally, see FPL's response to OPC's First Request for Production of Documents Nos. 3, 9 and 13 through 18.

FPSC EXH No. 17
03/20/2024

ADMITTED

Florida Power & Light Company
Docket No. 20220001-EI
OPC's First Request for Production
Request No. 19 Supplemental

QUESTION:
Produce copies of the documents identified in or related to the answers to Interrogatory Nos. 2 through 13.

RESPONSE:
Documents responsive to this request are provided on CD as Bates Nos. FCR-22-002104 through FCR-22-002354.

FPSC EXH No. 18
03/20/2024
ADMITTED

18

As filed in Docket No. 20220001-EI, FPL's Response to OPC's Third Request for Production of Documents Nos. 30, 31, 32, 33, 34, 35, 36, 37, and 38

(Including Attachments)

FPSC EXH No. 18
03/20/2024

ADMITTED

Florida Power & Light Company
Docket No. 20220001-EI
OPC's Third Request for Production of Documents
Request No. 30

QUESTION:
The following request relates to Turkey Point Unit 4, July 2020 – PMG Failure & Exciter Water Intrusion:

Please provide pictures of the Turkey Point Unit 4 permanent magnet generator failure.

RESPONSE:
Documents responsive to this request are provided as Bates Nos. FCR-22-003168 -- FCR-22-003169.


FPSC EXH No. 18
03/20/2024
ADMITTED
E1762
E99
FCR-22-003168


FPSC EXH No. 18
03/20/2024
ADMITTED
E1763
TURKEY POINT
OMAX 60120 JetMachining Center
E100
FCR-22-003169

FPSC EXH No. 18
03/20/2024

ADMITTED

Florida Power & Light Company
Docket No. 20220001-EI
OPC's Third Request for Production of Documents
Request No. 31

QUESTION:
The following request relates to Turkey Point Unit 4, July 2020 – PMG Failure & Exciter Water Intrusion:

a. Regarding any maintenance performed on the exciter (regarding which you stated Siemens failed to install the weather seal), a. Please provide all documentation of FPL's verification and/or inspection of the work performed on the Turkey Point Unit 4 exciter during the maintenance event described in FPL witness Mr. Curtland's testimony, page 4, lines 16-20.

b. Please provide a copy of FPL's site-specific procedure, procedure 0-GMM- 10 090.1 "Exciter Removal, Inspection and Installation."

c. Please provide a copy of Siemen's procedure 3.2.2.1, which governs installation of the exciter housing.

d. Please provide all documentation of FPL's review of the Siemen's procedure 3.2.2.1, documentation associated with QA/QC sign offs on those procedures and any other documentation associated with review and approval of Siemen's procedure 3.2.2.1.

e. Provide all documentation of the verification process described in Mr. Curtland's testimony, page 4, lines 16-20, including but not limited to, documentation on whether the verification process was performed in accordance with FPL's site-specific procedure, procedure 0-GMM- 10 090.1 "Exciter Removal, Inspection and Installation."

RESPONSE:

a. Confidential documents responsive to this request are provided as Bates Nos. FCR-22-003271 -- FCR-22-003422.

b. Documents responsive to this request are provided as Bates Nos. FCR-22-003170 -- FCR-22-003268.

c. No responsive documents.

d. Documents responsive to this request are provided as Bates Nos. FCR-22-003269 and FCR-22-003270.

e. Please see documents responsive to OPC's Third Production of Documents No. 32.

FPSC EXH No. 18
03/20/2024

ADMITTED

Florida Power & Light Company
Docket No. 20220001-EI
OPC's Third Request for Production of Documents
Request No. 32

QUESTION:
The following request relates to Turkey Point Unit 4, July 2020 – PMG Failure & Exciter Water Intrusion:

Please provide any RCA analysis of the Turkey Point Unit 4 permanent magnet generator failure.

RESPONSE:
Documents responsive to this request are provided as Bates Nos. FCR-22-003423 -- FCR-22-003576.

FPSC EXH No. 18
03/20/2024

ADMITTED

E1766

Florida Power & Light Company
Docket No. 20220001-EI
OPC's Third Request for Production of Documents
Request No. 33

QUESTION:
The following request relates to Turkey Point Unit 4, July 2020 – PMG Failure & Exciter Water Intrusion:

Please provide inspection reports for the Turkey Point Unit 4 permanent magnet generator since 2010 and the last time the Turkey Point Unit 4 permanent magnet generator was inspected.

RESPONSE:
Confidential documents responsive to this request are provided as Bates Nos. FCR-22-003577 -- FCR-22-003856.

FPSC EXH No. 18
03/20/2024

ADMITTED

Florida Power & Light Company
Docket No. 20220001-EI
OPC's Third Request for Production of Documents
Request No. 34

QUESTION:
The following request relates to Turkey Point Unit 4, July 2020 – PMG Failure & Exciter Water Intrusion:

Please provide FPL's inspection and maintenance programs for the Turkey Point Unit 4 permanent magnet generator.

RESPONSE:
Documents responsive to this request are provided as Bates Nos. FCR-22-003857 -- FCR-22-003859.

FPSC EXH No. 18
03/20/2024
ADMITTED

Attachment 4: Exciter PM Description and Status

There are five Westinghouse Frame A201C Exciters shared between PTN and PSL. Four are permanently installed (two at each site) with one spare shared between the sites. However, the spare Exciter base is not interchangeable and as a result only the individual parts (PMG, rotating element, AC Exciter Stator) are considered viable spares. The Brushless Exciters have never been fully refurbished. Maintenance strategy currently consists of the following:

i. Minor Inspection - Each Exciter is inspected and tested in place every 18 months (each refueling outage)
   a. PMG Stator
      i. Insulation resistance
      ii. Resistance measurement
      iii. Visual inspection
   b. AC Exciter Field
      i. Insulation resistance
      ii. Pole balance and impedance calculation of Field Winding
      iii. Resistance measurement
   c. AC Exciter Armature (including Diode Wheels)
      i. Diode Fuse resistance measurements
      ii. Pole balance and impedance calculation of Field Winding
      iii. Insulation resistance
      iv. Resistance measurement
      v. Visual inspection

ii. Major Inspection – At 7.5 years (5 refueling outages) each Exciter is disassembled. Inspections and tests are as with the Minor inspection with the following additions:
   a. PMG Stator
      i. Stator removed from base, inspected
   b. AC Exciter Stator
      i. Disassembled (horizontally split for rotor removal) and inspected
   c. AC Exciter Armature (including Diode Wheels and PMG Pole Support)
      i. Insulation resistance with rotor install -Diode Wheels to Shaft
      ii. Insulation resistance with rotor install - Diode Wheel to Diode Wheel

iii. Replacement of complete rotating element with an overhauled spare

iii. Each rotating element (including the spare) is fully refurbished at 7.5 years (Siemens Shop Overhaul). Work occurs between outages.
   a. PMG Magnets requalified or replaced
   b. AC Armature cleaned, inspected, tested
   c. Diode wheels disassembled and overhauled
      i. Fuses
      ii. Heat sinks with diodes installed
      iii. Supports and insulation
      iv. Forward resistance and reverse leakage current check of diodes
      v. Fuse resistance checks
      vi. Charge capacitors, capacitance check
      vii. Replace heat sink insulation
      viii. Test heat sink hardness
   d. NDE
   e. High speed balance

iv. FPL Exciter rewind status
   a. Rotating Elements: Two of the five rotating elements (AC Armatures) have been rewound for cause
      i. Spare: Rewound in 2010. Removed from PTN4 after 2020 PMG failure and currently at Siemens for refurbishment
      ii. PSL1: Not Rewound (~40 years old)
      iii. PSL2: Rewound 2015
      iv. PTN3: Not Rewound (~40 years old)
      v. PTN4: Not Rewound (~40 years old)
   b. Stationary Components: There is no record available of rewind of any of the stationary components (PMG Stator or AC Exciter Stator). However, PTN and PSL exciters and PMGs are current for minor and major maintenance.
   c. Status of PTN4 Exciter prior to 2020 PMG failure:
      i. Major overhaul Spring 2019

FPSC EXH No. 18
03/20/2024
ADMITTED

1. Major inspection performed on PMG and AC field
2. Spare rotating element was installed; rotating element was rewound in 2010 and overhauled in 2018 prior to installation

v. The proposed schedule for implementation of the rewind schedule for PMG Stator, AC Exciter Field, and AC Exciter Armature is as follows
   a. SL1-30 April 2021
   b. PTN3-32 Fall 2021
   c. PTN4-33 Spring 2022
   d. SL2-27 Spring 2023

FPSC EXH No. 18
03/20/2024

ADMITTED

Florida Power & Light Company
Docket No. 20220001-EI
OPC's Third Request for Production of Documents
Request No. 35

QUESTION:
The following request pertains to Turkey Point Unit 3 RFO 32, and the problems encountered with the Manipulator Gripper during Cycle 32 RFO:

Please provide the Manipulator Gripper testing procedures.

RESPONSE:
Documents responsive to this request are provided as Bates Nos. FCR-22-003860 -- FCR-22-003904.

FPSC EXH No. 18
03/20/2024

ADMITTED

Florida Power & Light Company
Docket No. 20220001-EI
OPC's Third Request for Production of Documents
Request No. 36

QUESTION:
The following request pertains to Turkey Point Unit 3 RFO 32, and the problems encountered with the Manipulator Gripper during Cycle 32 RFO:

Please provide the outage contingency plans in the event the Manipulator Gripper fails during the refueling outage.

RESPONSE:
Please see documents responsive to OPC's Third Request for Production of Document No. 39 provided as Bates Nos. FCR-22-004105 – FCR-22-004107.

FPSC EXH No. 18
03/20/2024

ADMITTED

E1773

TURKEY POINT NUCLEAR
OUTAGE: PT3-32

Is this a Shutdown Risk Contingency Plan? ☐ Yes No ☒

If Yes then refer to OM-AA-101-1000, Shutdown Risk Management for additional contingency plan requirements, attributes and approvals.

ACTIVTY: FUEL HANDLING EQUIPMENT

RESPONSIBLE INDIVIDUALS AND CONTACTS:

Refueling Services Support:

- Elmehdi Elaadil Days
- Bradford Hurrell Nights
- Klay Nordin Days
- Jeremy Jackson Nights

PROBLEM STATEMENT:

During fuel movement unloading or loading the core, we could experience a spent fuel crane/manipulator crane equipment issue or failure.

IMPACT AND PROBABILITY INCLUDING BASIS:

- We do not have a good track record with respect to the performance of our fuel handling equipment

Fuel Handling Equipment-

- Fuel Transfer System/Spent Fuel Bridge
  - There are no GEMCO Drives – (position controls for the transfer system) remaining in stock or in any inventory that can be located. PTN's last remaining GEMCO drive was used in the Unit 4 Fall outage
  - Unit 4 will have to cannibalized for parts and or equipment to bridge any parts gaps that are identified
  - In Place is a contingency work order for the Fuel Transfer System.
- Fuel Handling Equipment- Spent Fuel Bridge
  - In Place is a contingency work order for the Spent Fuel Handling Crane.
- Fuel Handling Equipment- Manipulator Crane
  - In Place is a work order for Manipulator Crane covers maintaining and troubleshooting for the outage.

IMPACT AND PROBABILITY INCLUDING BASIS:

- Due to the aging equipment on these units we are working with the vendors to finalize the fault matrix for the outages.
- Although the parts are on the other units great care must be used to remove the parts if needed that is why we do not remove all contingency parts from the other machines for most of the parts that would be removed would be one of a kind
- Unit 4 Manipulator crane cabinets will be staged and out of the box to facilitate any cannibalizing that is needed.
  - Medium due to aging component probability - Equipment failure
  - High impact – Greater than 1 Hour Critical Path Loss

E110

FPSC EXH No. 18
03/20/2024
ADMITTED

E1774

CONTINGENCY ACTIONS TO ADDRESS THE ISSUE/PROBLEM:

The following actions have been taken to mitigate the problem of a tensioner failing;

- Stearns Technician will be actively monitoring the performance of the Spent Fuel Crane and the Manipulator Crane and will respond immediately to any equipment issue or failure for troubleshooting/repair.
- Stearns Technician is available around the clock. This will minimize the time required for repair and retest should we experience an issue or failure of this equipment.
- Stearns Technician will be actively monitoring the performance of the Fuel Transfer System and will respond immediately to any issue or failure.
- Critical spare parts have been identified and locations are known
- FPL cranes subject matter expert is on site and available to respond.
- If necessary - EQUIPMENT TROUBLESHOOTING, MA-AA-100-1011 procedure will be followed for troubleshooting and repair – procedure has been validated and given to vendor for review.
- Refueling Services Support War this will be the location for any Troubleshooting or issue management teams

ADDITIONAL RESOURCE REQUIREMENTS AND ASSOCIATED COSTS:

- Costs associated with immediate failure or contingency implementation
  - Possible long term cost would depend on extent of repair.
  - Additional cost associated would be any repair parts needed
  - Polar crane resources for pics. Cost already in place

APPROVALS:

Prepared By:	Elaadil, Elmehdi signature on file)	Date: September, 9th 2021
* Risk Assessment Team:	Not Applicable	Date:
Responsible Director:		Date:
Outage Manager:		Date:
** Director of Operations: or PGM / Site Director	Not Applicable	Date:

Notes:

- * Risk Assessment Team approval required for Shutdown Risk Contingency Plans only. Approval signifies a sound plan and compliance with the additional attributes required for Shutdown Risk Contingency Plans in accordance with OM-AA-101-1000, Shutdown Risk Management.

- Outage Manager approval signifies that contingency plans, developed prior to the outage, have received a site challenge in accordance with OM-AA-101-1013, Fleet Outage Milestones, MS46.

- ** Director of Operations or Plant General Manager / Site Director approval required for Shutdown Risk Contingency Plans only, with Director Operations for ≤ YELLOW and Plant General Manager / Site Director for ≥ ORANGE risk.

E111

FPSC EXH No. 18
03/20/2024
ADMITTED

E1775

- The completed plan will be written in a manner that if an entry point is achieved, the OCC and issue owner can immediately identify; who to contact, what material is on-hand, and what services will be required, along with any contingency WOs to be implemented.

- Where applicable, decision tables are established to determine possible events and actions to implement associated with each event.

- Roles and responsibilities for implementing contingency actions are outlined for workers, the outage control center staff, and control room personnel (for shutdown risk management issues). Individuals are identified in advance, and contact lists are maintained with a predetermined communication protocol for initiating contingency actions.

- Walkthroughs and drills are conducted to validate contingency plan assumptions, where feasible. For example, time-critical operation and maintenance activities such as placing gravity feed in service, powering a bus from a blackout diesel, establishing temporary power feeds, and closing the containment equipment hatch are determined.

E112

FPSC EXH No. 18
03/20/2024

ADMITTED

Florida Power & Light Company
Docket No. 20220001-EI
OPC's Third Request for Production of Documents
Request No. 37

QUESTION:
The following request pertains to Turkey Point Unit 3 RFO 32, and the problems encountered with the Manipulator Gripper during Cycle 32 RFO:

Please provide the RCA for the Manipulator Gripper failure.

RESPONSE:
No responsive documents.

FPSC EXH No. 18
03/20/2024

ADMITTED

Florida Power & Light Company
Docket No. 20220001-EI
OPC's Third Request for Production of Documents
Request No. 38

QUESTION:
The following request pertains to Turkey Point Unit 3 RFO 32, and the problems encountered with the Manipulator Gripper during Cycle 32 RFO:

Regarding the core exit thermocouple tubing leaks after completion of Cycle 32 RFO, please provide any photographs showing the boric acid accumulation on the core exit thermocouple 51 and 57 tubing.

RESPONSE:
Documents responsive to this request are provided as Bates Nos. FCR-22-004024 -- FCR-22-004030.

FPSC EXH No. 18
03/20/2024
ADMITTED

E1778



FCR-22-004024

E115

FPSC EXH No. 18
03/20/2024
ADMITTED

E1779



FCR-22-004025

E116

FPSC EXH No. 18
03/20/2024
ADMITTED



FCR-22-004026

FPSC EXH No. 18
03/20/2024
ADMITTED

FCR-22-004027

FPSC EXH No. 18
03/20/2024
ADMITTED



FCR-22-004028

FPSC EXH No. 18
03/20/2024
ADMITTED



FCR-22-004029

FPSC EXH No. 18
03/20/2024
ADMITTED



FCR-22-004030

FPSC EXH No. 19
03/20/2024
ADMITTED

19

As filed in Docket No. 20230001-EI, FPL's Response to OPC's First Set of Interrogatories Nos. 8 and 9

FPSC EXH No. 19
03/20/2024

ADMITTED

QUESTION:
Turkey Point Unit 3, Cycle 32 refueling outage (Cycle 32 RFO)

The following question pertains to the problems encountered with the Manipulator Gripper during Cycle 32 RFO:

a. Prior to the start of the Cycle 32 RFO in November 2021, when was the last time the Manipulator Gripper had been used?

b. How is the Manipulator Gripper stored between outages? Provide the FPL specifications for Manipulator Gripper storage.

c. When was the Manipulator Gripper first tested in preparation for this outage?

d. Please identify any and all documentation regarding the FPL procedures for Manipulator Gripper testing and maintenance.

e. Please provide the FPL outage contingency plans in the event the Manipulator Gripper fails during the refueling outage.

f. Please describe the failure mechanism for the Manipulator Gripper.

g. Please provide the root cause analysis (RCA) or similar documents identifying and describing the cause of the Manipulator Gripper failure.

h. Please identify all video or photographic evidence collected or reviewed during the root cause investigation.

RESPONSE:

a. The manipulator gripper is used only during refueling outages for the purpose of moving fuel. The last time the Manipulator Gripper was used prior to the start of Cycle 32 RFO was during the immediately preceding March 2020 outage (Cycle 31 outage).

b. The manipulator gripper is permanent installed hardware that remains inside containment during the operating cycle. When not in use, the refueling bridge that supports the manipulator gripper is locked in a safe storage location. The gripper remains attached to the inner refueling mast which hangs freely from the bridge with no other contact.

FPSC EXH No. 19
03/20/2024
ADMITTED

c. The manipulator gripper is tested every outage, including RFO 32, prior to fuel moves.

d. The inspections are performed under site procedure 0-PMM-038.01, Section 4.7, Manipulator Crane Gripper Inspection. Load testing is performed under site procedure 3-OSP-038.2, Section 7.4, Load Test Using Installed Test Weight (Cavity Not Flooded). Wet checks are performed after the cavity is flooded but before fuel movements under site procedure 3-OSP-038.2, Manipulator Crane Operability Test.

e. Contingency outage plans are developed in accordance with fleet procedure, Fleet Outage Milestones. In addition, the Reactor Support Services group, which is responsible for the operation and maintenance of the Manipulator Gripper, ensures their outage preparedness accords with fleet procedure, High Impact Teams. Finally, the manipulator gripper original equipment manufacturer provides 24/7 on-site emergent issue support during the operation of the refueling equipment.

f. The failure investigation included an off-site forensics analysis performed under Framatome Report 51-9341663-000, Turkey Point Unit 3 15x15 Gripper Evaluation. The evaluation found that the manipulator gripper fingers were outside of design tolerances, resulting in the latching issues.

g. An RCA was not prepared for this event. However, forensics examination was performed as discussed in FPL's answer to part f.

h. An RCA was not prepared for this event.

FPSC EXH No. 19
03/20/2024

ADMITTED

QUESTION:
Turkey Point Unit 3, Cycle 32 refueling outage (Cycle 32 RFO)

The following questions pertain to the core exit thermocouple tubing leaks after completion of Cycle 32 RFO:

a. Were there any maintenance activities during the outage on Core Exit Thermocouples 51 and 57?

b. Was there any inspection of the core exit thermocouples tubing during the outage?

c. Please identify all video or photographic evidence showing the boric acid accumulation on the core exit thermocouple 51 and 57 tubing.

RESPONSE:

a. There are four core exit thermocouple (CET) columns that penetrate the reactor head that contain multiple CETs and pressure boundary tubing.

Consistent with routine refueling activities required to remove the reactor head, the CET columns were electrically disconnected, seals removed, and the columns were covered with protective "bullet noses" to seal the electrical connections during cavity flood-up. In addition, the electrical connections of each CETs were tested and cleaned as part of a CET replacement project. However, these activities were not performed in the area where the leaks were discovered.

The leaks occurred on Swagelok connections on individual CET tubing associated with the column 51 and 57. Column 51 has twelve CETs and Column 57 has thirteen CETs. The tubing leaks occurred on CET N-8 for column 51 and CET H-9 for column 57. The leaks were repaired by cutting-out the effected tubing sections and replacing the Swagelok fittings and capping the ends.

A CET replacement project was performed during the outage. However, CETs H-9 and N-8 were not included in the scope of that project.

Forensic testing and inspections were performed on the replaced parts. However, the inspections did not identify any material issues or evidence of physical damage that could have caused the leaks.

FPSC EXH No. 19
03/20/2024
ADMITTED

E2089

b. The thermocouple pressure boundary is inspected following plant shutdown in accordance with the Boric Acid Inspection Program. The thermocouple pressure boundary is also subject to the ASME Section XI pressure test requirements prior to returning the unit service. No leaks were identified during this inspection.

c. See documents produced as Bates Nos. FCR-23-000163 through FCR-23-000176 in response to OPC's First Request for Production No. 7.

E126

FPSC EXH No. 19
03/20/2024

ADMITTED

E2090

DECLARATION

I, Dean Curtland, sponsored the answers to Interrogatory Nos. 1-9, and 23-26 from **OPC's First Set of Interrogatories (Nos. 1-26)** to Florida Power & Light Company in Docket No. 20230001-EI, and the responses are true and correct based on my personal knowledge.

Under penalties of perjury, I declare that I have read the foregoing declaration and the interrogatory answers identified above, and that the facts stated therein are true.

Dean Curtland

Date: 3/7/2023

E127

FPSC EXH No. 20
03/20/2024
ADMITTED

20

As filed in Docket No. 20230001-EI, FPL's Response to Staff's Sixth Set of Interrogatories Nos. 14, 15, 16, 17, 18, 19, 20, 21, 22, 23, 23 supplemental, 24, and 25

(Including Attachments)

FPSC EXH No. 20
03/20/2024

ADMITTED

QUESTION:
Please provide the following information regarding the April 14, 2022 partial forced outage that took place at Turkey Point Unit 4:

a. What caused the partial forced outage?

b. What was the duration of the partial forced outage (hours/days).

c. What replacement power costs were incurred as a result of the partial forced outage?

RESPONSE:

a. Turkey Point Unit 4 suspended the power ascension after a refueling outage to hold power at 50% in order to troubleshoot and repair a malfunctioning Flux Map Detector system. Prior to this issue Turkey Point Unit 4 had completed a scheduled refueling outage on April 11 and had begun power ascension over a three-day period. A full core flux map is required to be completed prior to ascending power to verify the health of the reactor core.

b. Power was reduced for 23.67 hours.

c. The net replacement power cost related to the Turkey Point Unit 4 April 14, 2022 outage was $94,275. The calculation is provided in Attachment No. 1 to this response. FPL applies the proportion of fuel used during the same period for each fuel type, as summarized on Schedule A3, to the amount of outage time, in hours, experienced. Fixed natural gas costs are removed from the calculation since those costs have already been incurred.

FPSC EXH No. 20
03/20/2024

ADMITTED

Florida Power & Light Company
Docket No. 20230001-EI
Staff's Sixth Set of Interrogatories
Interrogatory No. 14
Attachment 1 of 1
Page 1 of 1

E2093

Turkey Point Unit 4 (Staff's 6th Set No. 14c)

Event Start	Event End	Seq. #	Event Title	MW Loss	Outage Hours	MWh Loss	Replacement Cost ($/MWh)	Replacement Cost ($)	TP4 Fuel Cost ($/MWh)	Nuclear Fuel Cost ($)	Net Replacement Cost ($)
A	B	C	D	E	F = (B - A) * 24	G = E * F	H = WA $/MWh	I = G * H	J = TP4 $/MWh	K = J * G	L = I - K
4/14/2022 18:20	4/15/2022 18:00	1	PT4-33 RFO Power Ascension Unplanned	118.75	23.67	2,810	$38.82	$109,112	$5.28	$14,837	$94,275
					23.67	**2,810.42**					**$94,275**
											$95,603 /Day

April 2022 - A4 Data	
TP4 Fuel Cost	**TP4 Heat Rate**
0.50	10,464
TP4 $/MWh	
$5.28	

TP4 2022 - A3 Data								
Fuel	**MWh**	**% Mix**	**Fuel Cost $**	**$/MWh**	**Demand $**	**Rev. Fuel Cost $**	**$/MWh**	**WA $/MWh**
Heavy Oil	0	0.00%	$0	$0.00	$0	$0	$0.00	$0.00
Light Oil	34,330	0.43%	$6,554,250	$190.92	$0	$6,554,250	$190.92	$0.81
Coal	220,393	2.74%	$11,718,787	$53.17	$0	$11,718,787	$53.17	$1.46
Gas	7,794,179	96.84%	$379,545,499	$48.70	$85,326,223	$294,219,276	$37.75	$36.55
Total	**8,048,902**	**100.00%**	**$397,818,535**		**$85,326,223**	**$312,492,312**		**$38.82**

E130

FPSC EXH No. 20
03/20/2024

ADMITTED

QUESTION:
Please provide the following information regarding the June 6, 2022 partial forced outage that took place at St. Lucie Unit 2:

a. What caused the partial forced outage?

b. What was the duration of the partial forced outage (hours/days)?

c. What replacement power costs were incurred as a result of the partial forced outage?

RESPONSE:
For FPL responses to Staff's Sixth Set of Interrogatories Nos. 15 and 17-21, please note Plant St. Lucie inadvertently transposed the figures for Net Available Capacity and MW Curtailed when it entered its generation data into FPL's Generating Available Data System ("GADS"). For correction, see Attachment No. 1 to this Interrogatory response. GADS is used as the basis for reporting generation data in FPL's monthly GPIF reports. The impacted GPIF reports will be corrected and refiled with the Commission.

a. This was a power reduction as a result of a 2A Heater Drain Pump motor tripping due to the motor windings electrically failing to ground during an extreme weather event. This occurred simultaneous with a Tornado Warning being issued by the State Watch office and subsequent high wind rainfall. As a result, the spare motor had to be swapped into place which was offsite with a vendor being refurbished.

b. Power was reduced for 6.27 days. See Attachment No. 1 to this Interrogatory response.

c. The net replacement power cost related to the St. Lucie Unit 2 June 6, 2022 outage was $328,110. The calculation is provided in Attachment No. 2 to this response. FPL applies the proportion of fuel used during the same period for each fuel type, as summarized on Schedule A3, to the amount of outage time, in hours, experienced. Fixed natural gas costs are removed from the calculation since those costs have already been incurred.

FPSC EXH No. 20
03/20/2024

ADMITTED

Florida Power & Light Company
Docket No. 20230001-EI
Staff's Sixth Set of Interrogatories
Interrogatory No. 15
Attachment 1 of 2
Page 1 of 1

E2095

					Reported GPIF Values (incorrect figures)			Corrected Values		
Int. No.	Outage	Start	End	Title	Duration Hours	Duration Days	MW Loss	MW Loss	MWh Loss	Replacement Cost
15	June 6, 2022 partial forced outage	2022-06-06 20:32:00	2022-06-13 02:59:00	Heater Drain Pump 2A Motor Replacement	150.45	6.27	38.36	39.36	5,922.00	$328,110
17	September 2, 2022 full forced outage	2022-09-02 22:47:00	2022-09-03 00:00:00	SL1-30 090222 Reactor Trip 1A MFP Unplanned Energy Loss	1.22	0.05	981.00	412.02	502.66	$33,117
18	October 28, 2022 partial forced outage	2022-10-28 10:15:00	2022-11-01 00:00:00	UEL SL1-31 1B Heater Drain Tube Leak	85.75	3.57	970.82	10.18	873.09	$40,077
19	November 1, 2022 partial forced outage	2022-11-01 00:00:00	2022-11-14 08:40:00	UEL SL1-31 1B Drain Cooler	321.67	13.40	880.45	22.51	7,239.78	$271,023
20	November 14, 2022 partial forced outage	2022-11-14 08:40:00	2022-11-19 02:59:00	UEL SL1-31 1B Drain Cooler Repair	114.32	4.76	778.04	202.95	23,200.65	$868,523
21	December 19, 2022 partial forced outage	2022-12-19 13:56:00	2022-12-20 02:00:00	UEL 2B Condensate Recirc Valve 121922	12.07	0.50	932.85	53.17	641.55	$28,676

E132

FPSC EXH No. 20
03/20/2024

ADMITTED

Florida Power & Light Company
Docket No. 20230001-EI
Staff's Sixth Set of Interrogatories
Interrogatory No. 15
Attachment 2 of 2
Page 1 of 1

E2096

St. Lucie Unit 2 (Staff's 6th Set No. 15c)

Event Start	Event End	Seq. #	Event Title	MW Loss	Outage Hours	MWh Loss	Replacement Cost ($/MWh)	Replacement Cost ($)	SL2 Fuel Cost ($/MWh)	Nuclear Fuel Cost ($)	Net Replacement Cost ($)
A	B	C	D	E	F = (B - A) * 24	G = E * F	H = WA $/MWh	I = G * H	J = SL2 $/MWh	K = J * G	L = I - K
6/6/2022 20:32	6/13/2022 2:59	1	Heater Drain Pump 2A Motor Replacement	39.36	150.45	5,922	$60.63	$359,054	$5.23	$30,944	$328,110
					150.45	**5,922.00**					**$328,110**
											$52,341 /Day

June 2022 - A4 Data	
SL2 Fuel Cost	**SL2 Heat Rate**
0.43	12,191
SL2 $/MWh	
$5.23	

June 2022 - A3 Data								
Fuel	**MWh**	**% Mix**	**Fuel Cost $**	**$/MWh**	**Demand $**	**Rev. Fuel Cost $**	**$/MWh**	**WA $/MWh**
Heavy Oil	0	0.00%	$0	$0.00	$0	$0	$0.00	$0.00
Light Oil	10,479	0.11%	$1,525,053	$145.53	$0	$1,525,053	$145.53	$0.15
Coal	268,702	2.73%	$10,862,129	$40.42	$0	$10,862,129	$40.42	$1.10
Gas	9,564,919	97.16%	$669,548,867	$70.00	$85,082,502	$584,466,365	$61.11	$59.37
Total	**9,844,100**	**100.00%**	**$681,936,050**		**$85,082,502**	**$596,853,547**		**$60.63**

E133

FPSC EXH No. 20
03/20/2024

ADMITTED

QUESTION:
Please provide the following information regarding the August 31, 2022 partial forced outage that took place at St. Lucie Unit 1:

a. What caused the partial forced outage?

b. What was the duration of the partial forced outage (hours/days)?

c. What replacement power costs were incurred as a result of the partial forced outage?

RESPONSE:
a. St. Lucie Unit 1 did not have a forced outage (partial or full) on August 31, 2022.

b. See response to subsection a.

c. See response to subsection a.

FPSC EXH No. 20
03/20/2024

ADMITTED

QUESTION:
Please provide the following information regarding the September 2, 2022 full forced outage that took place at St. Lucie Unit 1:

a. What caused the full forced outage?

b. What was the duration of the full forced outage (hours/days)?

c. What replacement power costs were incurred as a result of full forced outage?

RESPONSE:
For FPL responses to Staff's Sixth Set of Interrogatories Nos. 15 and 17-21, please note Plant St. Lucie inadvertently transposed the figures for Net Available Capacity and MW Curtailed when it entered its generation data into FPL's Generating Available Data System ("GADS"). For correction, see Attachment No. 1 to FPL's response to Staff's Sixth Set of Interrogatories, No. 15. GADS is used as the basis for reporting generation data in FPL's monthly GPIF reports. The impacted GPIF reports will be corrected and refiled with the Commission.

a. On September 2, there was a scheduled power reduction in preparation to perform Main Steam Safety Valve testing prior to the start of the refueling outage scheduled for Fall 2022. During the final scheduled power reduction to take the unit offline, when the unit already had been brought down to 45% power/capacity, the 1A Main Feed Pump tripped due to its recirculation valve failing to open. The valve failed to open due to an internal pneumatic blockage which adversely affected valve operation.

b. Total duration of the outage was 1.22 hours. See Attachment No. 1 to FPL's response to Staff's Sixth Set of Interrogatories, No. 15.

c. The net replacement power cost related to the St. Lucie Unit 1 September 2, 2022 outage was $33,117. The calculation is provided in Attachment No. 1 to this response. FPL applies the proportion of fuel used during the same period for each fuel type, as summarized on Schedule A3, to the amount of outage time, in hours, experienced. Fixed natural gas costs are removed from the calculation since those costs have already been incurred.

FPSC EXH No. 20
03/20/2024

ADMITTED

St. Lucie Unit 1 (Staff's 6th Set No. 17c)

Event Start	Event End	Seq. #	Event Title	MW Loss	Outage Hours	MWh Loss	Replacement Cost ($/MWh)	Replacement Cost ($)	SL1 Fuel Cost ($/MWh)	Nuclear Fuel Cost ($)	Net Replacement Cost ($)
A	B	C	D	E	F = (B - A) * 24	G = E * F	H = WA $/MWh	I = G * H	J = SL1 $/MWh	K = J * G	L = I - K
9/2/2022 22:47	9/3/2022 0:00	1	SL1-30 090222 Reactor Trip 1A MFP Unplanned Energy Loss	412.02	1.22	501	$66.42	$33,297	$0.36	$180	$33,117
					1.22	**501.29**					**$33,117**
											$653,268 /Day

September 2022 - A4 Data	
SL1 Fuel Cost	**SL1 Heat Rate**
0.03	12,410
SL1 $/MWh	
$0.36	

September 2022 - A3 Data								
Fuel	**MWh**	**% Mix**	**Fuel Cost $**	**$/MWh**	**Demand $**	**Rev. Fuel Cost $**	**$/MWh**	**WA $/MWh**
Heavy Oil	0	0.00%	$0	$0.00	$0	$0	$0.00	$0.00
Light Oil	20,868	0.21%	$3,342,807	$160.19	$0	$3,342,807	$160.19	$0.34
Coal	75,503	0.77%	$4,160,820	$55.11	$0	$4,160,820	$55.11	$0.42
Gas	9,749,860	99.02%	$729,845,980	$74.86	$83,334,111	$646,511,869	$66.31	$65.66
Total	**9,846,232**	**100.00%**	**$737,349,608**		**$83,334,111**	**$654,015,496**		**$66.42**

FPSC EXH No. 20
03/20/2024

ADMITTED

QUESTION:
Please provide the following information regarding the October 28, 2022 partial forced outage that took place at St. Lucie Unit 1:

a. What caused the partial forced outage?

b. What was the duration of the partial forced outage (hours/days)?

c. What replacement power costs were incurred as a result of the partial forced outage?

RESPONSE:
For FPL responses to Staff's Sixth Set of Interrogatories Nos. 15 and 17-21, please note Plant St. Lucie inadvertently transposed the figures for Net Available Capacity and MW Curtailed when it entered its generation data into FPL's Generating Available Data System ("GADS"). For correction, see Attachment No. 1 to FPL's response to Staff's Sixth Set of Interrogatories, No. 15. GADS is used as the basis for reporting generation data in FPL's monthly GPIF reports. The impacted GPIF reports will be corrected and refiled with the Commission.

a. On October 28, 2022, the St. Lucie Unit 1B drain cooler developed a tube leak. To maintain reactor coolant temperature within limits reactor power was reduced to approximately 98% for 3.57 days. On November 1, 2022, reactor power was further reduced to approximately 97% for 13.4 days to get a safe boundary and isolate the issue to facilitate a repair power for the drain leak. In total, 11 leaking tubes and 14 surrounding tubes were plugged. And, on November 14, reactor power was again reduced to approximately 75% to allow for isolation and repair of the 1B drain cooler for 4.76 days. Repair was complete and power was fully restored on November 18.

b. Power was reduced for 3.57 days. See Attachment No. 1 to FPL's response to Staff's Sixth Set of Interrogatories, No. 15.

c. The net replacement power cost related to the St. Lucie Unit 1 October 28, 2022 outage was $40,077. The calculation is provided in Attachment No. 1 to this response. FPL applies the proportion of fuel used during the same period for each fuel type, as summarized on Schedule A3, to the amount of outage time, in hours, experienced. Fixed natural gas costs are removed from the calculation since those costs have already been incurred.

FPSC EXH No. 20
03/20/2024

ADMITTED

Florida Power & Light Company
Docket No. 20230001-EI
Staff's Sixth Set of Interrogatories
Interrogatory No. 18
Attachment 1 of 1
Page 1 of 1

E2101

St. Lucie Unit 1 (Staff's 6th Set No. 18c)

Event Start	Event End	Seq. #	Event Title	MW Loss	Outage Hours	MWh Loss	Replacement Cost ($/MWh)	Replacement Cost ($)	SL1 Fuel Cost ($/MWh)	Nuclear Fuel Cost ($)	Net Replacement Cost ($)
A	B	C	D	E	F = (B - A) * 24	G = E * F	H = WA $/MWh	I = G * H	J = SL1 $/MWh	K = J * G	L = I - K
10/28/2022 10:15	11/1/2022 0:00	1	SL1-31 UEL 1B Heater Drain Tube Leak	10.18	85.75	873	$48.00	$41,909	$2.10	$1,832	$40,077
					85.75	**873.09**					**$40,077**
											$11,217 /Day

October 2022 - A4 Data	
SL1 Fuel Cost	**SL1 Heat Rate**
0.20	10,505
SL1 $/MWh	
$2.10	

October 2022 - A3 Data								
Fuel	**MWh**	**% Mix**	**Fuel Cost $**	**$/MWh**	**Demand $**	**Rev. Fuel Cost $**	**$/MWh**	**WA $/MWh**
Heavy Oil	0	0.00%	$82	$0.00	$0	$82	$0.00	$0.00
Light Oil	7,809	0.10%	$1,093,387	$140.01	$0	$1,093,387	$140.01	$0.14
Coal	72,778	0.92%	$2,755,387	$37.86	$0	$2,755,387	$37.86	$0.35
Gas	7,868,227	98.99%	$461,660,745	$58.67	$83,960,419	$377,700,325	$48.00	$47.52
Total	**7,948,814**	**100.00%**	**$465,509,600**		**$83,960,419**	**$381,549,181**		**$48.00**

E138

FPSC EXH No. 20
03/20/2024

ADMITTED

QUESTION:
Please provide the following information regarding the November 1, 2022 partial forced outage that took place at St. Lucie Unit 1:

a. What caused the partial forced outage?

b. What was the duration of the partial forced outage (hours/days)?

c. What replacement power costs were incurred as a result of the partial forced outage?

RESPONSE:
For FPL responses to Staff's Sixth Set of Interrogatories Nos. 15 and 17-21, please note Plant St. Lucie inadvertently transposed the figures for Net Available Capacity and MW Curtailed when it entered its generation data into FPL's Generating Available Data System ("GADS"). For correction, see Attachment No. 1 to FPL's response to Staff's Sixth Set of Interrogatories, No. 15. GADS is used as the basis for reporting generation data in FPL's monthly GPIF reports. The impacted GPIF reports will be corrected and refiled with the Commission.

a. See FPL's response to Staff's Sixth Set of Interrogatories, No. 18(a), which explains the interrelated events that occurred on October 28, November 1, and November 14.

b. Power was reduced for 13.4 days. See Attachment No. 1 to FPL's response to Staff's Sixth Set of Interrogatories, No. 15.

c. The net replacement power cost related to the St. Lucie Unit 1 November 1, 2022 outage was $271,023. The calculation is provided in Attachment No. 1 to this response. FPL applies the proportion of fuel used during the same period for each fuel type, as summarized on Schedule A3, to the amount of outage time, in hours, experienced. Fixed natural gas costs are removed from the calculation since those costs have already been incurred.

FPSC EXH No. 20
03/20/2024

ADMITTED

E2103

St. Lucie Unit 1 (Staff's 6th Set No. 19c)

Event Start	Event End	Seq. #	Event Title	MW Loss	Outage Hours	MWh Loss	Replacement Cost ($/MWh)	Replacement Cost ($)	SL1 Fuel Cost ($/MWh)	Nuclear Fuel Cost ($)	Net Replacement Cost ($)
A	B	C	D	E	F = (B - A) * 24	G = E * F	H = WA $/MWh	I = G * H	J = SL1 $/MWh	K = J * G	L = I - K
11/1/2022 0:00	11/14/2022 8:40	1	UEL SL1-31 1B Drain Cooler November	22.51	321.67	7,240	$38.00	$275,087	$0.56	$4,064	$271,023
					321.67	**7,239.78**					**$271,023**
											$20,221 /Day

November 2022 - A4 Data	
SL1 Fuel Cost	**SL1 Heat Rate**
0.05	10,510
SL1 $/MWh	
$0.56	

November 2022 - A3 Data								
Fuel	**MWh**	**% Mix**	**Fuel Cost $**	**$/MWh**	**Demand $**	**Rev. Fuel Cost $**	**$/MWh**	**WA $/MWh**
Heavy Oil	0	0.00%	$571	$0.00	$0	$571	$0.00	$0.00
Light Oil	12,377	0.16%	$1,893,039	$152.94	$0	$1,893,039	$152.94	$0.25
Coal	72,253	0.95%	$1,683,779	$23.30	$0	$1,683,779	$23.30	$0.22
Gas	7,523,123	98.89%	$366,311,683	$48.69	$80,819,901	$285,491,782	$37.95	$37.53
Total	**7,607,754**	**100.00%**	**$369,889,072**		**$80,819,901**	**$289,069,171**		**$38.00**

E140

FPSC EXH No. 20
03/20/2024

ADMITTED

QUESTION:
Please provide the following information regarding the November 14, 2022 partial forced outage that took place at St. Lucie Unit 1:

a. What caused the partial forced outage?

b. What was the duration of the partial forced outage (hours/days)?

c. What replacement power costs were incurred as a result of the partial forced outage?

RESPONSE:
For FPL responses to Staff's Sixth Set of Interrogatories Nos. 15 and 17-21, please note Plant St. Lucie inadvertently transposed the figures for Net Available Capacity and MW Curtailed when it entered its generation data into FPL's Generating Available Data System ("GADS"). For correction, see Attachment No. 1 to FPL's response to Staff's Sixth Set of Interrogatories, No. 15. GADS is used as the basis for reporting generation data in FPL's monthly GPIF reports. The impacted GPIF reports will be corrected and refiled with the Commission.

a. See FPL's response to Staff's Sixth Set of Interrogatories, No. 18(a), which explains the interrelated events that occurred on October 28, November 1, and November 14.

b. Power was reduced for 4.76 days. See Attachment No. 1 to FPL's response to Staff's Sixth Set of Interrogatories, No. 15.

c. The net replacement power cost related to the St. Lucie Unit 1 November 14, 2022 outage was $868,523. The calculation is provided in Attachment No. 1 to this response. FPL applies the proportion of fuel used during the same period for each fuel type, as summarized on Schedule A3, to the amount of outage time, in hours, experienced. Fixed natural gas costs are removed from the calculation since those costs have already been incurred.

FPSC EXH No. 20
03/20/2024

ADMITTED

E2105

St. Lucie Unit 1 (Staff's 6th Set No. 20c)

Event Start	Event End	Seq. #	Event Title	MW Loss	Outage Hours	MWh Loss	Replacement Cost ($/MWh)	Replacement Cost ($)	SL1 Fuel Cost ($/MWh)	Nuclear Fuel Cost ($)	Net Replacement Cost ($)
A	B	C	D	E	F = (B - A) * 24	G = E * F	H = WA $/MWh	I = G * H	J = SL1 $/MWh	K = J * G	L = I - K
11/14/2022 8:40	11/19/2022 2:59	1	UEL SL1-31 1B Drain Cooler Repair	202.95	114.32	23,201	$38.00	$881,545	$0.56	$13,023	$868,523
					114.32	**23,200.65**					**$868,523**
											$182,340 /Day

November 2022 - A4 Data	
SL1 Fuel Cost	SL1 Heat Rate
0.05	10,510
SL1 $/MWh	
$0.56	

November 2022 - A3 Data								
Fuel	MWh	% Mix	Fuel Cost $	$/MWh	Demand $	Rev. Fuel Cost $	$/MWh	WA $/MWh
Heavy Oil	0	0.00%	$571	$0.00	$0	$571	$0.00	$0.00
Light Oil	12,377	0.16%	$1,893,039	$152.94	$0	$1,893,039	$152.94	$0.25
Coal	72,253	0.95%	$1,683,779	$23.30	$0	$1,683,779	$23.30	$0.22
Gas	7,523,123	98.89%	$366,311,683	$48.69	$80,819,901	$285,491,782	$37.95	$37.53
Total	**7,607,754**	**100.00%**	**$369,889,072**		**$80,819,901**	**$289,069,171**		**$38.00**

FPSC EXH No. 20
03/20/2024

ADMITTED

QUESTION:
Please provide the following information regarding the December 19, 2022 partial forced outage that took place on December 19, 2022 at St. Lucie Unit 2:

a. What caused the partial forced outage?

b. What was the duration of the partial forced outage (hours/days)?

c. What replacement power costs were incurred as a result of the partial forced outage?

RESPONSE:
For FPL responses to Staff's Sixth Set of Interrogatories Nos. 15 and 17-21 please note Plant St. Lucie inadvertently transposed the figures for Net Available Capacity and MW Curtailed when it entered its generation data into FPL's Generating Available Data System ("GADS"). For correction, see Attachment No. 1 to FPL's response to Staff's Sixth Set of Interrogatories, No. 15. GADS is used as the basis for reporting generation data in FPL's monthly GPIF reports. The impacted GPIF reports will be corrected and refiled with the Commission.

a. On December 19, 2022, a vital AC fuse blew causing the loss of a circuit that powered the condensate pump recirculating valve that failed to open. As a result, this required downpowering the unit to 91%. Investigation and testing were indeterminant as to the failure mechanism and did not identify an overcurrent condition that was created. Subsequent testing of the circuit and replacement of fuses allowed restoration of the plant.

b. Power was reduced for approximately 12 hours. See Attachment No. 1 to FPL's response to Staff's Sixth Set of Interrogatories, No. 15.

c. The net replacement power cost related to the St. Lucie Unit 2 December 19, 2022 outage was $28,676. The calculation is provided in Attachment No. 1 to this response. FPL applies the proportion of fuel used during the same period for each fuel type, as summarized on Schedule A3, to the amount of outage time, in hours, experienced. Fixed natural gas costs are removed from the calculation since those costs have already been incurred.

FPSC EXH No. 20
03/20/2024

ADMITTED

Florida Power & Light Company
Docket No. 20230001-EI
Staff's Sixth Set of Interrogatories
Interrogatory No. 21
Attachment 1 of 1
Page 1 of 1

E2107

St. Lucie Unit 2 (Staff's 6th Set No. 21c)

Event Start	Event End	Seq. #	Event Title	MW Loss	Outage Hours	MWh Loss	Replacement Cost ($/MWh)	Replacement Cost ($)	SL2 Fuel Cost ($/MWh)	Nuclear Fuel Cost ($)	Net Replacement Cost ($)
A	B	C	D	E	F = (B - A) * 24	G = E * F	H = WA $/MWh	I = G * H	J = SL2 $/MWh	K = J * G	L = I - K
12/19/2022 13:56	12/20/2022 2:00	1	UEL 2B Condensate Recirc Valve 121922	53.17	12.07	642	$50.14	$32,168	$5.44	$3,493	$28,676
					12.07	**641.55**					**$28,676**
											$57,035 /Day

December 2022 - A4 Data	
SL2 Fuel Cost	**SL2 Heat Rate**
0.46	11,962
SL2 $/MWh	
$5.44	

December 2022 - A3 Data								
Fuel	**MWh**	**% Mix**	**Fuel Cost $**	**$/MWh**	**Demand $**	**Rev. Fuel Cost $**	**$/MWh**	**WA $/MWh**
Heavy Oil	0	0.00%	$326	$0.00	$0	$326	$0.00	$0.00
Light Oil	37,779	0.52%	$7,620,607	$201.72	$0	$7,620,607	$201.72	$1.05
Coal	58,212	0.80%	$4,033,865	$69.30	$0	$4,033,865	$69.30	$0.56
Gas	7,161,210	98.68%	$435,847,896	$60.86	$83,614,595	$352,233,301	$49.19	$48.54
Total	**7,257,200**	**100.00%**	**$447,502,694**		**$83,614,595**	**$363,888,099**		**$50.14**

E144

FPSC EXH No. 20
03/20/2024

ADMITTED

QUESTION:
Please refer to the June 9, 2023, Direct Testimony of Florida Power & Light (FPL) witness Dean Curtland, pages 3-9, and the Direct Testimony of FPL witness Joel Gebbie, pages 7-12 for the following request. Did FPL engage in any action seeking compensation from the vendor who performed the work related to this outage event? Please explain any response.

RESPONSE:
No. Damages were not recovered from Siemens as the failure was not solely the result of seal installation. All Preventative Maintenance for the PMG were being performed in accordance with Siemens (the original equipment manufacturer or "OEM") recommendations. The failure was determined to be due to degraded windings on the PMG combined with moisture. There are no OEM recommendations for rewinding the PMG. In addition, review of Siemens documents revealed that Siemens performed the housing sealing work in the manner required by the work order documents.

FPSC EXH No. 20
03/20/2024

ADMITTED

QUESTION:
Please refer to FPL witness Curtland's testimony, pages 16-17, and FPL witness Gebbie's testimony, pages 19-20 for the following request. Did FPL engage in any action seeking compensation from the vendor who performed the work related to this outage event? Please explain any response.

RESPONSE:
No, there was no evidence to determine the vendor workmanship was the cause of the failure. The likely cause was determined to be induced low cycle fatigue.

FPSC EXH No. 20
03/20/2024

ADMITTED

QUESTION:
Please refer to FPL witness Curtland's testimony, pages 16-17, and FPL witness Gebbie's testimony, pages 19-20 for the following request. Did FPL engage in any action seeking compensation from the vendor who performed the work related to this outage event? Please explain any response.

RESPONSE:
As the Original Equipment Manufacturer (OEM) for many of our plant systems, Westinghouse is a key stakeholder in our business and FPL works closely with them. For the software error that occurred for this outage extension, Westinghouse corrected the software at no cost to FPL. In addition, Westinghouse replaced the damaged coils at no cost to FPL.

FPSC EXH No. 20
03/20/2024

ADMITTED

QUESTION:
Please refer to FPL witness Curtland's testimony, pages 21-23, and FPL witness Gebbie's testimony, pages 33-35 for the following request. Did FPL engage in any action seeking compensation from the vendor who performed the work related to this outage event? Please explain any response.

RESPONSE:
No, the vendor performed work in accordance with station procedures and vendor tool manuals. The latching tool failed and parts detached from the tool and magnetically attached to the lead screw which was not seen.

FPSC EXH No. 20
03/20/2024

ADMITTED

QUESTION:
Please re-submit the following discovery responses that were originally filed in Docket No. 20220001-EI. If any information has changed since the previous filing, please update the response(s) to include the new or updated information:

a. **FPL's Responses to Staff's 2nd Set of Interrogatories, No. 4 (including attachment).**

   The following questions are with respect to Florida Power & Light's (FPL or Company) Petition for Approval of Fuel Cost Recovery and Capacity Cost Recovery Net Final True-Ups for the Period Ending December 2021 and 2021 Asset Optimization Incentive Mechanism Results (Petition).

   Please refer to the Direct Testimony of FPL witness Dean Curtland for the following question. Please provide the replacement power costs, if any, associated with the: July 2020 outage of Turkey Point Unit No. 4; November 2020 outage of Turkey Point Unit No. 3; January 2021 outage of St. Lucie Unit No. 2; March 2021 outage of Turkey Point Unit No. 3; May 2021 outage of St. Lucie Unit No. 1; and the August 2021 outage of Turkey Point Unit No. 3. Please also show how any replacement power cost amounts were calculated.

b. **FPL's Responses to Staff's 2nd Set of Interrogatories, No. 9 (including attachment).**

   The following questions are with respect to Florida Power & Light's (FPL or Company) Petition for Approval of Fuel Cost Recovery and Capacity Cost Recovery Net Final True-Ups for the Period Ending December 2021 and 2021 Asset Optimization Incentive Mechanism Results (Petition).

   Please refer to FPL's Generating Performance Incentive Factor Actual Unit Performance Data Schedules covering the month of January 2022 for the following questions.

   a. **Please explain the events or factors leading to the forced outage of approximately 335 hours of Plant St. Lucie Unit No. 2 for the month.**

   b. **Please specify the replacement power costs, if any, associated with the January 2022 outage. If applicable, please also show how any replacement power costs were calculated.**

FPSC EXH No. 20
03/20/2024

ADMITTED

c. FPL's Responses to Staff's Fourth Set of Interrogatories, No. 30 (including attachment).

Please refer to the Direct Testimony of FPL witness Dean Curtland, filed as part of the Petition, for the following request. Please provide the replacement power costs, if any, associated with the: February 2021 outage of Turkey Point Unit No. 3, the November 2021 outage of Turkey Point Unit No. 3, and the December 2021 outage of St. Lucie Unit No. 1. Please also show how any replacement power cost amounts were calculated.

RESPONSE:

a. Please see Attachment No. 1 to this response.

b. Please see Attachment No. 2 to this response.

c. Please see Attachment No. 3 to this response.

FPSC EXH No. 20
03/20/2024

ADMITTED

E2114

Florida Power & Light Company
Docket No. 20220001-EI
Staff's 2nd Set of Interrogatories
Interrogatory No. 4
Page 1 of 1

QUESTION:
The following questions are with respect to Florida Power & Light's (FPL or Company) Petition for Approval of Fuel Cost Recovery and Capacity Cost Recovery Net Final True-Ups for the Period Ending December 2021 and 2021 Asset Optimization Incentive Mechanism Results (Petition).

Please refer to the Direct Testimony of FPL witness Dean Curtland for the following question. Please provide the replacement power costs, if any, associated with the: July 2020 outage of Turkey Point Unit No. 4; November 2020 outage of Turkey Point Unit No. 3; January 2021 outage of St. Lucie Unit No. 2; March 2021 outage of Turkey Point Unit No. 3; May 2021 outage of St. Lucie Unit No. 1; and the August 2021 outage of Turkey Point Unit No. 3. Please also show how any replacement power cost amounts were calculated.

RESPONSE:
The replacement power cost for July 2020 outage of Turkey Point Unit No. 4 was $1,453,970; November 2020 outage of Turkey Point Unit No. 3 was $1,290,604; January 2021 outage of St. Lucie Unit No. 2 was $1,180,450; March 2021 outage of Turkey Point Unit No. 3 was $1,206,743; May 2021 outage of St. Lucie Unit No. 1 was $1,517,511; August 2021 outage of Turkey Point Unit No. 3 was $2,766,857. The calculations are provided in Attachment No. I to this Interrogatory. FPL applies the proportion of fuel used during the same period for each fuel type, as summarized on Schedule A3, to the amount of outage time, in hours, experienced. Fixed natural gas costs are removed from the calculation since those expenses have already been incurred.

FPSC EXH No. 20
03/20/2024

ADMITTED

Florida Power & Light Company
Docket No. 20220001-EI
Staff's 2nd Set of Interrogatories
Attachment No. I, Interrogatory No. 4
Page 1 of 6

Turkey Point Unit 4

Event Start	Event End	Seq. #	Event Title	MW Loss	Outage Hours	MWh Loss	Replacement Cost ($/MWh)	Replacement Cost ($)	TN4 Fuel Cost ($/MWh)	Nuclear Fuel Cost ($)	Net Replacement Cost ($)
A	B	C	D	E	F = (B - A) * 24	G = E * F	H = WA $/MWh	I = G * H	J = TN4 $/MWh	K = J * G	L = I - K
7/5/2020 21:09	7/20/2020 14:54	1	Automatic Rx Trip due to main gen lockout from loss of exciter	821.00	353.75	290,429	$11.30	$3,281,797	$6.42	$1,863,313	$1,418,484
7/20/2020 14:55	7/21/2020 15:00	2	Automatic Rx Trip due to main gen lockout from loss of exciter	301.69	24.08	7,266	$11.30	$82,101	$6.42	$46,615	$35,486
					377.83	**297,694**					**$1,453,970**
											$92,356 /Day

July 2020 - A4 Data	
TN4 Fuel Cost	TN4 Heat Rate
0.57	11,271
TN4 $/MWh	
$6.42	

July 2020 - A3 Data								
Fuel	MWh	% Mix	Fuel Cost $	$/MWh	Demand $	Rev. Fuel Cost $	$/MWh	WA $/MWh
Heavy Oil	7,443	0.07%	$967,596	$130.01	$0	$967,596	$130.01	$0.10
Light Oil	3,894	0.04%	$500,080	$128.44	$0	$500,080	$128.44	$0.05
Coal	185,425	1.85%	$6,010,505	$32.41	$0	$6,010,505	$32.41	$0.60
Gas	9,811,388	98.03%	$192,410,990	$19.61	$86,798,731	$105,612,259	$10.76	$10.55
Total	**10,008,149**	**100.00%**	**$199,889,172**		**$86,798,731**	**$113,090,440**		**$11.30**

Florida Power & Light Company
Docket No. 20230001-EI
Staff's Sixth Set of Interrogatories
Interrogatory No. 25
Attachment 1 of 3
Page 2 of 8

FPSC EXH No. 20
03/20/2024

ADMITTED

Florida Power & Light Company
Docket No. 20220001-EI
Staff's 2nd Set of Interrogatories
Attachment No. I, Interrogatory No. 4
Page 2 of 6

Turkey Point Unit 3

Event Start	Event End	Seq. #	Event Title	MW Loss	Outage Hours	MWh Loss	Replacement Cost ($/MWh)	Replacement Cost ($)	TN3 Fuel Cost ($/MWh)	Nuclear Fuel Cost ($)	Net Replacement Cost ($)
A	B	C	D	E	F = (B - A) * 24	G = E * F	H = WA $/MWh	I = G * H	J = TN4 $/MWh	K = J * G	L = I - K
11/7/2020 3:18	11/21/2020 11:39	1	PTN Unit 3 Unplanned Auto Turbine Runback	169.83	344.35	58,481	$19.76	$1,155,566	$5.19	$303,476	$852,090
11/21/2020 11:40	11/24/2020 1:00	2	PTN Unit 3 downpower to support FBM replacement	490.70	61.33	30,096	$19.76	$594,693	$5.19	$156,179	$438,514
					405.68	**88,577**					**$1,290,604**
											$76,351 /Day

November 2020 - A4 Data	
TN3 Fuel Cost	**TN3 Heat Rate**
0.48	10,872
TN3 $/MWh	
$5.19	

November 2020 - A3 Data								
Fuel	**MWh**	**% Mix**	**Fuel Cost $**	**$/MWh**	**Demand $**	**Rev. Fuel Cost $**	**$/MWh**	**WA $/MWh**
Heavy Oil	696	0.01%	$92,932	$133.49	$0	$92,932	$133.49	$0.01
Light Oil	982	0.01%	$170,546	$173.64	$0	$170,546	$173.64	$0.02
Coal	166,720	2.25%	$5,184,226	$31.10	$0	$5,184,226	$31.10	$0.70
Gas	7,226,805	97.72%	$218,636,264	$30.25	$77,956,955	$140,679,309	$19.47	$19.02
Total	**7,395,204**	**100.00%**	**$224,083,968**		**$77,956,955**	**$146,127,013**		**$19.76**

Florida Power & Light Company
Docket No. 20230001-EI
Staff's Sixth Set of Interrogatories
Interrogatory No. 25
Attachment 1 of 3
Page 3 of 8

E2116

E153

FPSC EXH No. 20
03/20/2024

ADMITTED

Florida Power & Light Company
Docket No. 20220001-EI
Staff's 2nd Set of Interrogatories
Attachment No. I, Interrogatory No. 4
Page 3 of 6

St. Lucie Unit 2

Event Start	Event End	Seq. #	Event Title	MW Loss	Outage Hours	MWh Loss	Replacement Cost ($/MWh)	Replacement Cost ($)	SL2 Fuel Cost ($/MWh)	Nuclear Fuel Cost ($)	Net Replacement Cost ($)
A	B	C	D	E	F = (B - A) * 24	G = E * F	H = WA $/MWh	I = G * H	J = SL2 $/MWh	K = J * G	L = I - K
1/14/2021 0:58	1/14/2021 8:31	1	2B2 4KV Breaker Power Reduction	511.15	7.55	3,859	$17.77	$68,583	$4.43	$17,105	$51,478
1/14/2021 8:31	1/14/2021 15:16	2	2B2 4KV Breaker Shut down	987.00	6.75	6,662	$17.77	$118,397	$4.43	$29,529	$88,868
1/14/2021 15:16	1/16/2021 6:24	3	2B2 4KV Breaker Power Ascension	154.37	39.13	6,041	$17.77	$107,356	$4.43	$26,775	$80,581
1/20/2021 18:22	1/23/2021 14:28	4	2B2 Automatic shut down Motor Control Center	987.00	68.10	67,215	$17.77	$1,194,490	$4.43	$297,913	$896,576
1/23/2021 14:28	1/24/2021 3:12	5	2B2 Motor Control Center Power Ascension	370.61	12.73	4,719	$17.77	$83,864	$4.43	$20,916	$62,948
					134.27	88,496					$1,180,450
											$211,004 /Day

January 2021 - A4 Data	
SL2 Fuel Cost	SL2 Heat Rate
0.43	10,215
SL2 $/MWh	
$4.43	

January 2021 - A3 Data								
Fuel	MWh	% Mix	Fuel Cost $	$/MWh	Demand $	Rev. Fuel Cost $	$/MWh	WA $/MWh
Heavy Oil	(1,846)	-0.03%	$0	$0.00	$0	$0	$0.00	$0.00
Light Oil	5,374	0.09%	$779,832	$145.10	$0	$779,832	$145.10	$0.14
Coal	152,748	2.67%	$1,830,141	$11.98	$0	$1,830,141	$11.98	$0.32
Gas	5,570,003	97.27%	$179,842,136	$32.29	$80,688,936	$99,153,200	$17.80	$17.32
Total	**5,726,280**	**100.00%**	**$182,452,109**		**$80,688,936**	**$101,763,174**		**$17.77**

FPSC EXH No. 20
03/20/2024

ADMITTED

Florida Power & Light Company
Docket No. 20220001-EI
Staff's 2nd Set of Interrogatories
Attachment No. I, Interrogatory No. 4
Page 4 of 6

Turkey Point Unit 3

Event Start	Event End	Seq. #	Event Title	MW Loss	Outage Hours	MWh Loss	Replacement Cost ($/MWh)	Replacement Cost ($)	TN3 Fuel Cost ($/MWh)	Nuclear Fuel Cost ($)	Net Replacement Cost ($)
A	B	C	D	E	F = (B - A) * 24	G = E * F	H = WA $/MWh	I = G * H	J = TN3 $/MWh	K = J * G	L = I - K
3/1/2021 11:08	3/4/2021 21:19	1	Automatic trip during reactor protection system testing	837.00	82.18	68,787	$20.64	$1,419,632	$4.99	$343,552	$1,076,080
3/4/2021 21:20	3/5/2021 17:00	2	Automatic trip during reactor protection system power ascension	306.04	19.67	6,019	$20.64	$124,215	$4.99	$30,060	$94,155
3/24/2021 19:15	3/25/2021 20:00	3	Power reduction due to turbine runback	94.29	24.75	2,334	$20.64	$48,162	$4.99	$11,655	$36,507
					126.60	**77,140**					**$1,206,743**
											$228,766 /Day

March 2021 - A4 Data	
TN3 Fuel Cost	TN3 Heat Rate
0.48	10,385
TN3 $/MWh	
$4.99	

March 2021 - A3 Data								
Fuel	MWh	% Mix	Fuel Cost $	$/MWh	Demand $	Rev. Fuel Cost $	$/MWh	WA $/MWh
Heavy Oil	7,493	0.11%	$967,310	$129.09	$0	$967,310	$129.09	$0.15
Light Oil	3,724	0.06%	$490,603	$131.73	$0	$490,603	$131.73	$0.07
Coal	167,673	2.53%	$5,388,631	$32.14	$0	$5,388,631	$32.14	$0.81
Gas	6,441,824	97.30%	$212,154,964	$32.93	$82,363,543	$129,791,421	$20.15	$19.60
Total	**6,620,714**	**100.00%**	**$219,001,508**		**$82,363,543**	**$136,637,965**		**$20.64**

Florida Power & Light Company
Docket No. 20230001-EI
Staff's Sixth Set of Interrogatories
Interrogatory No. 25
Attachment 1 of 3
Page 5 of 8

E2118

FPSC EXH No. 20
03/20/2024
ADMITTED

St. Lucie Unit 1

Event Start	Event End	Seq. #	Event Title	MW Loss	Outage Hours	MWh Loss	Replacement Cost ($/MWh)	Replacement Cost ($)	SL1 Fuel Cost ($/MWh)	Nuclear Fuel Cost ($)	Net Replacement Cost ($)
A	B	C	D	E	F = (B - A) * 24	G = E * F	H = WA $/MWh	I = G * H	J = SL1 $/MWh	K = J * G	L = I - K
5/14/2021 0:01	5/17/2021 21:32	1	Outage Extension (no power ascension since part of planned outage)	981.00	93.52	91,740	$21.48	$1,970,698	$4.94	$453,187	$1,517,511
					93.52	**91,740**					**$1,517,511**
											$389,452 /Day

May 2021 - A4 Data	
SL1 Fuel Cost	SL1 Heat Rate
0.47	10,595
SL1 $/MWh	
$4.94	

May 2021 - A3 Data								
Fuel	MWh	% Mix	Fuel Cost $	$/MWh	Demand $	Rev. Fuel Cost $	$/MWh	WA $/MWh
Heavy Oil	10,934	0.13%	$1,449,517	$132.57	$0	$1,449,517	$132.57	$0.17
Light Oil	8,988	0.11%	$1,242,013	$138.18	$0	$1,242,013	$138.18	$0.15
Coal	179,098	2.12%	$10,707,125	$59.78	$0	$10,707,125	$59.78	$1.27
Gas	8,253,106	97.65%	$252,830,400	$30.63	$84,665,773	$168,164,627	$20.38	$19.90
Total	**8,452,126**	**100.00%**	**$266,229,054**		**$84,665,773**	**$181,563,281**		**$21.48**

FPSC EXH No. 20
03/20/2024

ADMITTED

Florida Power & Light Company
Docket No. 20220001-EI
Staff's 2nd Set of Interrogatories
Attachment No. I, Interrogatory No. 4
Page 6 of 6

Turkey Point Unit 3

Event Start	Event End	Seq. #	Event Title	MW Loss	Outage Hours	MWh Loss	Replacement Cost ($/MWh)	Replacement Cost ($)	TN3 Fuel Cost ($/MWh)	Nuclear Fuel Cost ($)	Net Replacement Cost ($)
A	B	C	D	E	F = (B - A) * 24	G = E * F	H = WA $/MWh	I = G * H	J = TN3 $/MWh	K = J * G	L = I - K
8/5/2021 1:30	8/13/2021 21:59	1	Unplanned power reduction due to Turbine Control Valve Auto Close	249.63	212.48	53,042	$28.46	$1,509,680	$5.38	$285,444	$1,224,236
8/13/2021 22:00	8/16/2021 19:38	2	Shutdown to repair Turbine Control Valve	837.00	69.63	58,283	$28.46	$1,658,845	$5.38	$313,648	$1,345,198
8/16/2021 19:39	8/17/2021 23:00	3	Turbine Control Valve Power Ascension	312.75	27.35	8,554	$28.46	$243,455	$5.38	$46,031	$197,423
					309.47	**119,879**					**$2,766,857**
											$214,577 /Day

August 2021 - A4 Data	
TN3 Fuel Cost	TN3 Heat Rate
0.50	10,833
TN3 $/MWh	
$5.38	

August 2021 - A3 Data								
Fuel	MWh	% Mix	Fuel Cost $	$/MWh	Demand $	Rev. Fuel Cost $	$/MWh	WA $/MWh
Heavy Oil	2,246	0.02%	$314,781	$140.14	$0	$314,781	$140.14	$0.03
Light Oil	3,425	0.03%	$446,656	$130.40	$0	$446,656	$130.40	$0.04
Coal	151,047	1.50%	$5,557,391	$36.79	$0	$5,557,391	$36.79	$0.55
Gas	9,913,334	98.44%	$365,832,640	$36.90	$85,539,072	$280,293,568	$28.27	$27.83
Total	**10,070,052**	**100.00%**	**$372,151,468**		**$85,539,072**	**$286,612,396**		**$28.46**

FPSC EXH No. 20
03/20/2024

ADMITTED

E2121

DECLARATION

I sponsored the answer to Interrogatory Nos. 3, 4, and 9b from **STAFF'S SECOND SET OF INTERROGATORIES (NOS. 3-10)** to Florida Power & Light Company in Docket No. 20220001-EI. The responses are true and correct based on my personal knowledge.

Under penalties of perjury, I declare that I have read the foregoing declaration and the interrogatory answers identified above, and that the facts stated therein are true.

Gerard J. Yupp

Date: 5/10/22

FPSC EXH No. 20
03/20/2024

ADMITTED

E2122

Florida Power & Light Company
Docket No. 20220001-EI
Staff's 2nd Set of Interrogatories
Interrogatory No. 9
Page 1 of 1

QUESTION:

The following questions are with respect to Florida Power & Light's (FPL or Company) Petition for Approval of Fuel Cost Recovery and Capacity Cost Recovery Net Final True-Ups for the Period Ending December 2021 and 2021 Asset Optimization Incentive Mechanism Results (Petition).

Please refer to FPL's Generating Performance Incentive Factor Actual Unit Performance Data Schedules covering the month of January 2022 for the following questions.

a. Please explain the events or factors leading to the forced outage of approximately 335 hours of Plant St. Lucie Unit No. 2 for the month.

b. Please specify the replacement power costs, if any, associated with the January 2022 outage. If applicable, please also show how any replacement power costs were calculated.

RESPONSE:

a. Prior to the January 2022 outage, FPL was conducting surveillance testing on St. Lucie Unit 2 Rod Control. Control Element Assembly (CEA) #27 malfunctioned during this surveillance testing. Unit 2 reduced power to attempt to move the CEA without success, therefore the unit was manually shut down to address the issue. The #27 Control Element Drive Mechanism (CEDM) motor was removed and sent to a Westinghouse facility for further inspection, disassembly, and analysis. FPL is conducting an investigation and will supplement this response upon completion of the root cause evaluation.

b. The net replacement power cost related to the St. Lucie Unit No. 2 January 2022 outage was $8,693,593. The calculation is provided in Attachment No. 1 to this Interrogatory. FPL applies the proportion of fuel used during the same period for each fuel type, as summarized on Schedule A3, to the amount of outage time, in hours, experienced. Fixed natural gas costs are removed from the calculation since those costs have already been incurred.

FPSC EXH No. 20
03/20/2024
ADMITTED

St Lucie Unit 2

Event Start	Event End	Seq. #	Event Title	MW Loss	Outage Hours	MWh Loss	Replacement Cost ($/MWh)	Replacement Cost ($)	SL2 Fuel Cost ($/MWh)	Nuclear Fuel Cost ($)	Net Replacement Cost ($)
A	B	C	D	E	F = (B - A) * 24	G = E * F	H = WA $/MWh	I = G * H	J = SL2 $/MWh	K = J * G	L = I - K
1/6/2022 13:00	1/6/2022 21:13	1	Control Element Assembly 27 Power Reduction	329.00	8.22	2,703	$30.76	$83,147	$5.16	$13,955	$69,192
1/6/2022 21:13	1/19/2022 16:43	2	Control Element Assembly 27 Repair	987.00	307.50	303,503	$30.76	$9,335,069	$5.16	$1,566,708	$7,768,361
1/19/2022 16:43	1/20/2022 20:28	3	Control Element Assembly 27 Extension for MG Set Repair	987.00	27.75	27,389	$30.76	$842,433	$5.16	$141,386	$701,047
1/20/2022 20:28	1/21/2022 14:30	4	Control Element Assembly 27 Power Ascension	335.79	18.03	6,055	$30.76	$186,251	$5.16	$31,259	$154,993
					361.50	**339,650.45**					**$8,693,593**
											$577,168 /Day

January 2022 - A4 Data	
SL2 Fuel Cost	SL2 Heat Rate
0.42	12,160
SL2 $/MWh	
$5.16	

January 2022 - A3 Data								
Fuel	MWh	% Mix	Fuel Cost $	$/MWh	Demand $	Rev. Fuel Cost $	$/MWh	WA $/MWh
Heavy Oil	23	0.00%	$79	$3.44	$0	$79	$3.44	$0.00
Light Oil	65,535	0.87%	$711,418	$10.86	$0	$711,418	$10.86	$0.09
Coal	171,979	2.29%	$7,202,821	$41.88	$0	$7,202,821	$41.88	$0.96
Gas	7,266,559	96.83%	$304,733,593	$41.94	$81,838,429	$222,895,164	$30.67	$29.70
Total	**7,504,096**	**100.00%**	**$312,647,911**		**$81,838,429**	**$230,809,482**		**$30.76**

FPSC EXH No. 20
03/20/2024

ADMITTED

E2124

DECLARATION

I sponsored the answer to Interrogatory No. 9a from **STAFF'S SECOND SET OF INTERROGATORIES (NOS. 3-10)** to Florida Power & Light Company in Docket No. 20220001-EI. The responses are true and correct based on my personal knowledge.

Under penalties of perjury, I declare that I have read the foregoing declaration and the interrogatory answers identified above, and that the facts stated therein are true.

Dean Curtland

Date: 5/11/22

FPSC EXH No. 20
03/20/2024

ADMITTED

E2125

DECLARATION

I sponsored the answer to Interrogatory Nos. 3, 4, and 9b from **STAFF'S SECOND SET OF INTERROGATORIES (NOS. 3-10)** to Florida Power & Light Company in Docket No. 20220001-EI. The responses are true and correct based on my personal knowledge.

Under penalties of perjury, I declare that I have read the foregoing declaration and the interrogatory answers identified above, and that the facts stated therein are true.

Gerard J. Yupp

Date: 5/10/22

FPSC EXH No. 20
03/20/2024

ADMITTED

E2126

Florida Power & Light Company
Docket No. 20220001-EI
Staff's Fourth Set of Interrogatories
Interrogatory No. 30
Page 1 of 1

QUESTION:
Please refer to the Direct Testimony of FPL witness Dean Curtland, filed as part of the Petition, for the following request. Please provide the replacement power costs, if any, associated with the: February 2021 outage of Turkey Point Unit No. 3, the November 2021 outage of Turkey Point Unit No. 3, and the December 2021 outage of St. Lucie Unit No. 1. Please also show how any replacement power cost amounts were calculated.

RESPONSE:

Outage	Replacement Power Cost
February 2021 - Turkey Point Unit No. 3	$1,146,159
November 2021 - Turkey Point Unit No. 3	$10,054,734
December 2021 - St. Lucie Unit No. 2	$1,434,048

The calculation is provided in Attachment No. 1 to this Interrogatory. FPL applies the proportion of fuel used during the same period for each fuel type, as summarized on Schedule A3, to the amount of outage time, in hours, experienced. Fixed natural gas costs are removed from the calculation because those costs have already been incurred.

Florida Power & Light Company
Docket No. 20220001-EI
Staff's Fourth Set of Interrogatories
Interrogatory No. 30
Attachment 1 of 1
Tab 1 of 3

ADMITTED

FPSC EXH No. 20
03/20/2024

Turkey Point Unit 3

Event Start	Event End	Seq. #	Event Title	MW Loss	Outage Hours	MWh Loss	Replacement Cost ($/MWh)	Replacement Cost ($)	TN3 Fuel Cost ($/MWh)	Nuclear Fuel Cost ($)	Net Replacement Cost ($)
A	B	C	D	E	F = (B - A) * 24	G = E * F	H = WA $/MWh	I = G * H	J = TN3 $/MWh	K = J * G	L = I - K
2/2/2021 13:57	2/9/2021 4:00	1	Power reduction due to condenser tube leak	380.52	158.05	60,141	$25.01	$1,504,320	$5.96	$358,161	$1,146,159
					158.05	**60,141**					**$1,146,159**
											$174,045 /Day

February 2021 - A4 Data	
TN3 Fuel Cost	TN3 Heat Rate
0.58	10,220
TN3 $/MWh	
$5.96	

February 2021 - A3 Data								
Fuel	MWh	% Mix	Fuel Cost $	$/MWh	Demand $	Rev. Fuel Cost $	$/MWh	WA $/MWh
Heavy Oil	2,971	0.05%	$395,439	$133.09	$0	$395,439	$133.09	$0.07
Light Oil	35,269	0.58%	$3,582,725	$101.58	$0	$3,582,725	$101.58	$0.59
Coal	204,183	3.39%	$6,128,978	$30.02	$0	$6,128,978	$30.02	$1.02
Gas	5,787,680	95.98%	$214,300,687	$37.03	$73,575,996	$140,724,691	$24.31	$23.34
Total	**6,030,103**	**100.00%**	**$224,407,829**		**$73,575,996**	**$150,831,833**		**$25.01**

Florida Power & Light Company
Docket No. 20220001-EI
Staff's Fourth Set of Interrogatories
Interrogatory No. 30
Attachment 1 of 1
Tab 2 of 3

ADMITTED

FPSC EXH No. 20
03/20/2024

Turkey Point Unit 3

Event Start	Event End	Seq. #	Event Title	MW Loss	Outage Hours	MWh Loss	Replacement Cost ($/MWh)	Replacement Cost ($)	TN3 Fuel Cost ($/MWh)	Nuclear Fuel Cost ($)	Net Replacement Cost ($
A	B	C	D	E	F = (B - A) * 24	G = E * F	H = WA $/MWh	I = G * H	J = TN3 $/MWh	K = J * G	L = I - K
11/7/2021 0:01	11/20/2021 15:24	1	Unit 3 refueling outage extension	837.00	327.38	274,020	$41.87	$11,474,228	$5.18	$1,419,494	$10,054,734
					327.38	**274,020**					**$10,054,734**
											$737,098 /Day

November 2021 - A4 Data	
TN3 Fuel Cost	**TN3 Heat Rate**
0.48	10,701
TN3 $/MWh	
$5.18	

November 2021 - A3 Data								
Fuel	**MWh**	**% Mix**	**Fuel Cost $**	**$/MWh**	**Demand $**	**Rev. Fuel Cost $**	**$/MWh**	**WA $/MWh**
Heavy Oil	1	0.00%	$158	$155.00	$0	$158	$155.00	$0.00
Light Oil	2,069	0.03%	$396,671	$191.72	$0	$396,671	$191.72	$0.06
Coal	148,290	2.34%	$6,541,161	$44.11	$0	$6,541,161	$44.11	$1.03
Gas	6,194,067	97.63%	$339,183,639	$54.76	$80,456,908	$258,726,731	$41.77	$40.78
Total	**6,344,427**	**100.00%**	**$346,121,629**		**$80,456,908**	**$265,664,721**		**$41.87**

Florida Power & Light Company
Docket No. 20230001-EI
Staff's Sixth Set of Interrogatories
Interrogatory No. 25
Attachment 3 of 3
Page 3 of 5

Florida Power & Light Company
Docket No. 20220001-EI
Staff's Fourth Set of Interrogatories
Interrogatory No. 30
Attachment 1 of 1
Tab 3 of 3

ADMITTED

FPSC EXH No. 20
03/20/2024

St Lucie Unit 1

Event Start	Event End	Seq. #	Event Title	MW Loss	Outage Hours	MWh Loss	Replacement Cost ($/MWh)	Replacement Cost ($)	TN3 Fuel Cost ($/MWh)	Nuclear Fuel Cost ($)	Net Replacement Cost ($)
A	B	C	D	E	F = (B - A) * 24	G = E * F	H = WA $/MWh	I = G * H	J = SL1 $/MWh	K = J * G	L = I - K
12/10/2021 10:24	12/12/2021 1:10	1	Manual Reactor Scram - Maintenance Personnel Error	981.00	38.77	38,030	$35.65	$1,355,924	$4.99	$189,905	$1,166,019
12/12/2021 1:10	12/12/2021 19:11	2	Manual Reactor Scram - Maintenance Personnel Error - Return to full power	485.21	18.02	8,742	$35.65	$311,682	$4.99	$43,653	$268,029
					56.78	**46,772**					**$1,434,048**
											$606,114 /Day

December 2021 - A4 Data	
SL1 Fuel Cost	SL1 Heat Rate
0.48	10,373
SL1 $/MWh	
$4.99	

December 2021 - A3 Data								
Fuel	MWh	% Mix	Fuel Cost $	$/MWh	Demand $	Rev. Fuel Cost $	$/MWh	WA $/MWh
Heavy Oil	1	0.00%	$79	$158.08	$0	$79	$158.08	$0.00
Light Oil	9,004	0.14%	$1,088,121	$120.85	$0	$1,088,121	$120.85	$0.16
Coal	167,208	2.52%	$5,989,715	$35.82	$0	$5,989,715	$35.82	$0.90
Gas	6,453,841	97.34%	$310,613,664	$48.13	$81,303,888	$229,309,776	$35.53	$34.59
Total	**6,630,053**	**100.00%**	**$317,691,579**		**$81,303,888**	**$236,387,691**		**$35.65**

FPSC EXH No. 20
03/20/2024

ADMITTED

E2130

DECLARATION

I, Gerard J. Yupp, sponsored the answers to Interrogatory Nos. 29 and 30 and co-sponsored the answer to Interrogatory No. 26 from **Staff's Fourth Set of Interrogatories (Nos. 25-30)** to Florida Power & Light Company in Docket No. 20220001-EI, and the responses are true and correct based on my personal knowledge.

Under penalties of perjury, I declare that I have read the foregoing declaration and the interrogatory answers identified above, and that the facts stated therein are true.

Gerard J. Yupp

Date: 8/26/22

FPSC EXH No. 20
03/20/2024

ADMITTED

E2131

DECLARATION

I, Dean Curtland, sponsored the answers to Interrogatory Nos. 22-24 and I co-sponsored the answers to 14-21 and 25 from **Staff's Sixth Set of Interrogatories (Nos. 14-25)** to Florida Power & Light Company in Docket No. 20230001-EI, and the responses are true and correct based on my personal knowledge.

Under penalties of perjury, I declare that I have read the foregoing declaration and the interrogatory answers identified above, and that the facts stated therein are true.

Dean Curtland

Dean Curtland

Date: 7/23/23

FPSC EXH No. 20
03/20/2024

ADMITTED

DECLARATION

I, Gerard J. Yupp, co-sponsored the answers to Interrogatory Nos. 14-21 and 25 from **Staff's Sixth Set of Interrogatories (Nos. 14-25)** to Florida Power & Light Company in Docket No. 20230001-EI, and the responses are true and correct based on my personal knowledge.

Under penalties of perjury, I declare that I have read the foregoing declaration and the interrogatory answers identified above, and that the facts stated therein are true.

Gerard J. Yupp

Date: 7/20/23

FPSC EXH No. 20
03/20/2024

ADMITTED

E2133

DECLARATION

I, Dean Curtland, sponsored the supplemental answer to No. 23 from **Staff's Six Set of Interrogatories (Nos. 14-25)** to Florida Power & Light in Docket No. 20230001-EI, and the responses are true and correct based on my personal knowledge.

Under penalties of perjury, I declare that I have read the foregoing declaration and the interrogatory answers identified above, and that the facts stated therein are true.

Dean Curtland

Date: 8/3/2023

E170

FPSC EXH No. 21
03/20/2024

ADMITTED

21

As filed in Docket No. 20230001-EI, FPL witness, Edward Anderson's prefiled exhibit EJA-1 – Schedule E1-B

FPSC EXH No. 21
03/20/2024

ADMITTED

E2135

FLORIDA POWER & LIGHT COMPANY
FUEL COST RECOVERY CLAUSE
CALCULATION OF TRUE-UP AMOUNT

SCHEDULE: E1-B

FOR THE PERIOD: JANUARY 2022 THROUGH DECEMBER 2022

(1)	(2)	(3)	(4)	(5)	(6)	(7)	(8)	(9)	(10)	(11)	(12)	(13)	(14)	(15)
Line No.		a-Jan - 2022	a-Feb - 2022	a-Mar - 2022	a-Apr - 2022	a-May - 2022	a-Jun - 2022	a-Jul - 2022	a-Aug - 2022	a-Sep - 2022	a-Oct - 2022	a-Nov - 2022	a-Dec - 2022	a-2022
1	**Fuel Costs & Net Power Transactions**													
2	Fuel Cost of System Net Generation (E3)[1]	325,398,468	358,063,187	352,804,653	409,572,796	608,597,458	695,078,798	708,420,306	937,703,971	747,045,301	476,659,633	379,734,685	461,032,007	6,460,111,261
3	Lease Costs[2]	164,079	166,054	162,394	164,792	1,234,450	155,342	72,907	143,184	215,333	161,746	157,656	152,985	2,950,922
4	Fuel Cost of Stratified Sales	(7,894,625)	(7,444,876)	(7,720,906)	(10,186,256)	(15,279,638)	(16,809,524)	(22,207,265)	(20,041,191)	(15,056,088)	(12,290,424)	(6,419,095)	(10,246,491)	(151,596,379)
5	Fuel Cost of Power Sold (E6)	(23,377,963)	(20,758,991)	(17,229,531)	(16,298,269)	(14,974,996)	(47,228,143)	(35,148,184)	(7,018,095)	(5,990,945)	(7,458,604)	(6,936,472)	(23,114,276)	(225,534,469)
6	Gains from Off-System Sales (E6)	(7,477,925)	(4,137,028)	(2,761,969)	(3,865,678)	(3,478,570)	(1,762,585)	(4,316,426)	(4,633,917)	(2,360,826)	(2,863,756)	(3,165,654)	(23,603,110)	(64,427,444)
7	Fuel Cost of Purchased Power, Exclusive of Economy (E7)	21,216,881	15,486,959	25,780,273	18,074,267	32,693,567	42,494,487	44,304,808	32,698,133	30,449,158	15,615,484	22,832,670	26,474,982	328,121,670
8	Energy Payments to Qualifying Facilities (E8)	1,538,128	1,603,711	2,961,536	2,070,822	2,119,817	3,426,103	3,276,161	1,704,471	2,766,218	2,535,052	1,752,103	1,597,594	27,351,716
9	Energy Cost of Economy Purchases (E9)	1,478,115	97,212	7,050,663	3,013,609	1,906,825	5,314,317	6,563,247	10,178,360	4,539,071	1,369,501	2,315,711	28,471	43,855,103
10		311,045,158	343,076,227	361,047,113	402,546,083	612,818,912	680,668,796	700,965,555	950,734,916	761,607,221	473,728,633	390,271,605	432,322,161	6,420,832,380
11														
12	**Optimization Activities**[3]													
13	Incremental Personnel, Software, and Hardware Costs	41,384	39,251	43,506	41,333	43,930	47,923	43,094	45,090	48,007	45,412	50,145	38,411	527,488
14	Variable O&M Costs Attributable to Off-Systems Sales (E6)	191,405	157,002	110,778	91,793	87,224	75,349	88,666	91,776	70,441	82,272	76,348	188,923	1,311,977
15	Variable O&M Costs Avoided due to Economy Purchases (E9)	(2,609)	2,580	(35,530)	(7,307)	(2,531)	(4,323)	(11,523)	(27,163)	(17,316)	(5,249)	(12,707)	(231)	(123,908)
16	Optimization Credits	(3,938,217)	(11,087,286)	(8,733,161)	(2,444,476)	(1,772,976)	(2,338,628)	(6,254,149)	(878,074)	(1,773,046)	(2,385,475)	(2,177,049)	(2,912,312)	(46,694,849)
17		(3,708,037)	(10,888,453)	(8,614,407)	(2,318,656)	(1,644,353)	(2,219,679)	(6,133,911)	(768,370)	(1,671,914)	(2,263,039)	(2,063,262)	(2,685,209)	(44,979,291)
18														
19	**Adjustments to Fuel Cost**													
20	Energy Imbalance Fuel Revenues	(227,661)	200,200	(579,701)	(208,182)	(133,470)	(433,881)	(14,182)	(1,204,793)	(678,699)	(782,371)	(187,410)	(201,475)	(4,451,626)
21	Fuel Replacement Cost Credit	0	0	0	0	0	(1,471,683)	0	0	0	0	0	0	(1,471,683)
22	Inventory Adjustments	(58,319)	99,894	127,993	52,853	(82,348)	(129,181)	630,087	296,454	(336,887)	(184,032)	(102,382)	(450,953)	(136,821)
23	Other O&M Expense	0	0	0	27,704	39,217	239,587	27,704	221,631	0	0	0	5,686	561,529
24		(285,980)	300,094	(451,708)	(127,625)	(176,602)	(1,795,158)	643,609	(686,709)	(1,015,586)	(966,404)	(289,792)	(646,742)	(5,498,601)
25														
26	**Adjusted Total Fuel Costs & Net Power Transactions**	307,051,141	332,487,868	351,980,999	400,099,802	610,997,958	676,653,959	695,475,253	949,279,836	758,919,722	470,499,190	387,918,550	428,990,210	6,370,354,488
27														
28	**kWh Sales**													
29	Retail kWh Sales	9,043,095,245	8,775,165,920	9,133,542,059	9,773,113,541	10,173,414,502	11,585,135,488	12,719,543,482	12,955,889,557	12,712,201,779	10,555,164,783	9,631,263,354	9,389,488,821	126,447,018,531
30	Sale for Resale	432,888,349	438,613,956	399,606,881	478,324,377	490,684,821	542,723,795	563,110,856	620,193,751	609,877,471	518,849,475	425,975,509	451,396,903	5,972,246,144
31		9,475,983,594	9,213,779,876	9,533,148,940	10,251,437,918	10,664,099,323	12,127,859,283	13,282,654,338	13,576,083,308	13,322,079,250	11,074,014,258	10,057,238,863	9,840,885,724	132,419,264,675
32														
33	**Retail % of Total kWh Sales**	95.43173%	95.23959%	95.80824%	95.33408%	95.39872%	95.52498%	95.76055%	95.43172%	95.42205%	95.31471%	95.76449%	95.41305%	
34														
35	**Revenues Applicable to Period**													
36	Jurisdictional Fuel Revenues	322,581,789	329,035,290	341,877,789	368,759,398	384,315,518	443,397,579	490,270,485	499,177,837	488,934,079	400,278,780	363,880,711	353,122,508	4,785,631,763
37	Prior Period True-Up (Collected)/Refunded This Period[4]	(56,958,324)	(56,958,324)	(56,958,324)	(56,958,324)	(56,958,324)	(56,958,324)	(56,958,324)	(56,958,324)	(56,958,324)	(56,958,324)	(56,958,324)	(56,958,324)	(683,499,887)
38	GPIF[5]	(395,683)	(395,683)	(395,683)	(395,683)	(395,683)	(395,683)	(395,683)	(395,683)	(395,683)	(395,683)	(395,683)	(395,683)	(4,748,196)
39	Asset Optimization - Company Portion[6]	(291,934)	(291,934)	(291,934)	(291,934)	(291,934)	(291,934)	(291,934)	(291,934)	(291,934)	(291,934)	(291,934)	(291,934)	(3,503,210)
40	SolarTogether (ST) Credit	(7,019,108)	(7,224,912)	(7,470,919)	(10,168,215)	(10,756,423)	(11,269,911)	(10,278,688)	(10,598,427)	(10,016,597)	(8,099,392)	(9,140,436)	(6,193,564)	(108,236,595)
41		257,916,739	264,164,437	276,760,929	300,945,241	315,913,154	374,481,726	422,345,857	430,933,469	421,271,541	334,533,447	297,094,333	289,283,002	3,985,643,876

Docket No. 20230001-EI
2022 FCR Final True-Up
Exhibit EJA-1, Page 2 of 4

E172

FPSC EXH No. 21
03/20/2024

ADMITTED

E2136

FLORIDA POWER & LIGHT COMPANY
FUEL COST RECOVERY CLAUSE
CALCULATION OF TRUE-UP AMOUNT

SCHEDULE: E1-B

FOR THE PERIOD: JANUARY 2022 THROUGH DECEMBER 2022

(1)	(2)	(3)	(4)	(5)	(6)	(7)	(8)	(9)	(10)	(11)	(12)	(13)	(14)	(15)
Line No.		a-Jan - 2022	a-Feb - 2022	a-Mar - 2022	a-Apr - 2022	a-May - 2022	a-Jun - 2022	a-Jul - 2022	a-Aug - 2022	a-Sep - 2022	a-Oct - 2022	a-Nov - 2022	a-Dec - 2022	a-2022
42	**True-Up Calculation**													
43	Adjusted Total Fuel Costs & Net Power Transactions	307,051,141	332,487,868	351,980,999	400,099,802	610,997,958	676,653,959	695,475,253	949,279,836	758,919,722	470,499,190	387,918,550	428,990,210	6,370,354,488
44	Jurisdictional Sales % of Total kWh Sales	95.43173%	95.23959%	95.80824%	95.33408%	95.39872%	95.52498%	95.76055%	95.43172%	95.42205%	95.31471%	95.76449%	95.41305%	
45	Retail Total Fuel Costs & Net Power Transactions	293,513,567	317,188,905	337,789,969	382,068,456	583,857,647	647,453,003	667,103,132	907,426,952	725,386,131	449,203,858	372,108,607	409,996,196	6,093,096,422
46	True-Up Provision for the Month-Over/(Under) Recovery	(35,596,828)	(53,024,468)	(61,029,040)	(81,123,214)	(267,944,493)	(272,971,277)	(244,757,276)	(476,493,483)	(304,114,591)	(114,670,410)	(75,014,273)	(120,713,193)	(2,107,452,546)
47	Interest Provision for the Month	(60,735)	(102,913)	(197,753)	(346,074)	(612,868)	(1,195,796)	(2,079,304)	(2,998,145)	(4,281,926)	(5,470,633)	(6,278,410)	(7,293,894)	(30,918,452)
48	True-Up & Interest Prov. Beg of Period-Over/(Under) Recovery	(683,499,887)	(662,199,126)	(658,368,182)	(662,636,652)	(687,147,616)	(898,746,653)	(1,115,955,402)	(1,305,833,658)	(1,728,366,962)	(1,979,805,155)	(2,042,987,875)	(2,067,322,235)	(683,499,887)
49	Deferred True-up Beginning of Period - Over/(Under) Recovery	10,256,384	10,256,384	10,256,384	10,256,384	10,256,384	10,256,384	10,256,384	10,256,384	10,256,384	10,256,384	10,256,384	10,256,384	10,256,384
50	Prior Period True Up Collected/(Refunded) This Period	56,958,324	56,958,324	56,958,324	56,958,324	56,958,324	56,958,324	56,958,324	56,958,324	56,958,324	56,958,324	56,958,324	56,958,324	683,499,887
51	**End of Period Net True-up Amount Over/(Under) Recovery**	(651,942,742)	(648,111,798)	(652,380,268)	(676,891,232)	(888,490,269)	(1,105,699,018)	(1,295,577,274)	(1,718,110,578)	(1,969,548,771)	(2,032,731,491)	(2,057,065,851)	(2,128,114,614)	(2,128,114,614)
52														
53														

54 (1) Actuals include various adjustments as noted on the A-schedules
55 (2) Includes $1.1MM for 50% of a partial Cedar Bay railcar lease early termination fee
56 (3) Amounts reflected in this section are in accordance with FPL's Stipulation and Settlement approved by the Commission in Order No. PSC-2021-0446-S-EI
57 (4) Prior Period 2021 Actual/Estimated True-up
58 (5) Generating Performance Incentive Factor is ($4,748,196/12) - See Order No. PSC-2021-0442-FOF-EI
59 (6) Jurisdictionalized Asset Optimization - Company Portion is ($3,503,210/12) - See Order No. PSC-2021-0442-FOF-EI

FPSC EXH No. 21
03/20/2024

ADMITTED

FLORIDA POWER & LIGHT COMPANY
FUEL COST RECOVERY CLAUSE
CALCULATION OF VARIANCE

SCHEDULE: E1-B

FOR THE PERIOD: JANUARY 2022 THROUGH DECEMBER 2022

(1)	(2)	(3)	(4)	(5)	(6)
Line No.		Current	Prior	Difference	% Difference
1	**Fuel Costs & Net Power Transactions**				
2	Fuel Cost of System Net Generation (E3)[1]	6,460,111,261	5,859,215,042	600,896,219	10.3%
3	Lease Costs[2]	2,950,922	2,822,965	127,957	4.5%
4	Fuel Cost of Stratified Sales	(151,596,379)	(137,107,162)	(14,489,217)	10.6%
5	Fuel Cost of Power Sold (E6)	(225,534,469)	(185,296,112)	(40,238,357)	21.7%
6	Gains from Off-System Sales (E6)	(64,427,444)	(37,628,753)	(26,798,690)	71.2%
7	Fuel Cost of Purchased Power, Exclusive of Economy (E7)	328,121,670	267,246,037	60,875,633	22.8%
8	Energy Payments to Qualifying Facilities (E8)	27,351,716	31,146,961	(3,795,245)	(12.2%)
9	Energy Cost of Economy Purchases (E9)	43,855,103	27,308,841	16,546,262	60.6%
10		6,420,832,380	5,827,707,819	593,124,561	10.2%
11					
12	**Optimization Activities**[3]				
13	Incremental Personnel, Software, and Hardware Costs	527,488	480,304	47,184	9.8%
14	Variable O&M Costs Attributable to Off-System Sales (E6)	1,311,977	1,199,791	112,186	9.4%
15	Variable O&M Costs Avoided due to Economy Purchases (E9)	(123,908)	(123,759)	(148)	0.1%
16	Optimization Credits	(46,694,849)	(37,830,771)	(8,864,078)	23.4%
17		(44,979,291)	(36,274,436)	(8,704,856)	24.0%
18					
19	**Adjustments to Fuel Cost**				
20	Energy Imbalance Fuel Revenues	(4,451,626)	(1,382,695)	(3,068,931)	222.0%
21	Fuel Replacement Cost Credit	(1,471,683)	(1,471,683)	0	N/A
22	Inventory Adjustments	(136,821)	10,892	(147,713)	(1,356.2%)
23	Other O&M Expense	561,529	578,674	(17,145)	(3.0%)
24		(5,498,601)	(2,264,813)	(3,233,789)	142.8%
25					
26	**Adjusted Total Fuel Costs & Net Power Transactions**	6,370,354,488	5,789,168,571	581,185,917	10.0%
27					
28	**kWh Sales**				
29	Retail kWh Sales	126,447,018,531	124,729,758,057	1,717,260,474	1.4%
30	Sale for Resale	5,972,246,144	5,771,735,886	200,510,258	3.5%
31		132,419,264,675	130,501,493,943	1,917,770,732	1.5%
32					
33	**Retail % of Total kWh Sales**	95.4130%	95.8419%		
34					
35	**Revenues Applicable to Period**				
36	Jurisdictional Fuel Revenues	4,785,631,763	4,704,014,117	81,617,646	1.7%
37	Prior Period True-Up (Collected)/Refunded This Period[4]	(683,499,887)	(683,499,887)	0	N/A
38	GPIF[5]	(4,748,196)	(4,748,196)	0	N/A
39	Asset Optimization - Company Portion[5]	(3,503,210)	(3,503,210)	0	(0.0%)
40	SolarTogether (ST) Credit	(108,236,595)	(112,882,511)	4,645,917	(4.1%)
41		3,985,643,876	3,899,380,313	86,263,563	2.2%
42					
43	**True-Up Calculation**				
44	Adjusted Total Fuel Costs & Net Power Transactions	6,370,354,488	5,789,168,571	581,185,917	10.0%
45	Jurisdictional Sales % of Total kWh Sales	95.4130%	95.8419%		
46	Retail Total Fuel Costs & Net Power Transactions	6,093,096,422	5,542,717,956	550,378,466	9.9%
47	True-Up Provision for the Month-Over/(Under) Recovery	(2,107,452,546)	(1,643,337,643)	(464,114,903)	28.2%
48	Interest Provision for the Month	(30,918,452)	(14,949,800)	(15,968,652)	106.8%
49	True-Up & Interest Prov. Beg of Period-Over/(Under) Recovery	(683,499,887)	(683,499,887)	0	N/A
50	Deferred True-up Beginning of Period - Over/(Under) Recovery	10,256,384	10,256,384	0	N/A
51	Prior Period True Up Collected/(Refunded) This Period	683,499,887	683,499,887	0	N/A
52	End of Period Net True-up Amount Over/(Under) Recovery	(2,128,114,614)	(1,648,031,059)	(480,083,555)	29.1%
53					
54					
55	[1] Actuals include various adjustments as noted on the A-schedules				
56	[2] Includes $1.1MM for 50% of a partial Cedar Bay railcar lease early termination fee				
57	[3] Amounts reflected in this section are in accordance with FPL's Stipulation and Settlement approved in Order No. PSC-2021-0446-S-EI				
58	[4] Prior Period 2021 Actual/Estimated True-up				
59	[5] Approved in Order No. PSC-2021-0442-FOF-EI				

FPSC EXH No. 22
03/20/2024
ADMITTED

22

As filed in Docket No. 20240001-EI, FPL's Response to Staff's Second Set of Interrogatories, No. 9

(Including Attachments)

FPSC EXH No. 22
03/20/2024

ADMITTED

QUESTION:
Please refer to the Florida Public Service Commission – Office of Auditing and Performance Analysis *Review of Nuclear Operations – Florida Power & Light Company*, dated January 2024, page 25 for the following request.[1] Please provide the replacement power costs, if any, associated with the: October 26, 2017 outage of St. Lucie Unit No. 2; August 19, 2020 outage of Turkey Point Unit No. 3; December 10, 2021 outage of St. Lucie Unit No. 1; and the January 6, 2022 outage of St. Lucie Unit No. 2. Please also show how any replacement power cost amounts were calculated.

RESPONSE:
Please see FPL's objections served on February 12, 2024. Notwithstanding, and without waiver of those objections, FPL responds as follows:

The replacement power cost for the October 26, 2017 outage of St. Lucie Unit No. 2 was $1,258,382; August 19, 2020 outage of Turkey Point Unit No. 3 was $277,781; December 10, 2021 outage of St. Lucie Unit No. 1 was $1,434,048; January 6, 2022 outage of St. Lucie Unit No. 2 was $8,679,692. The calculations are provided in Attachment No. 1 to this Interrogatory. FPL applies the proportion of fuel used during the same period for each fuel type, as summarized on Schedule A3, to the amount of outage time, in hours, experienced. Fixed costs associated with natural gas are removed from the total natural gas costs prior to being incorporated into the weighted average allocation because these costs would have been incurred regardless of whether the outage occurred.

[1]This document may be accessed via the Florida Public Service Commission's website through the following link: https://www.floridapsc.com/pscfiles/website-files/PDF/Publications/Reports/General//Electricgas/FPL_Nuclear_Operations_Audit.pdf

FPSC EXH No. 22
03/20/2024

ADMITTED

E2140

St Lucie Unit 2

Event Start	Event End	Seq. #	Event Title	MW Loss	Outage Hours	MWh Loss	Replacement Cost ($/MWh)	Replacement Cost ($)	SL2 Fuel Cost ($/MWh)	Nuclear Fuel Cost ($)	Net Replacement Cost ($)
A	B	C	D	E	F = (B - A) * 24	G = E * F	H = WA $/MWh	I = G * H	J = SL2 $/MWh	K = J * G	L = I - K
10/26/2017 2:12	10/29/2017 1:09	1	PSL 2 UEL Auto SCRAM - Turbine Control System Fault 102617	987.00	70.57	69,653	$22.62	$1,575,614	$6.10	$425,046	$1,150,568
10/29/2017 1:09	10/29/2017 17:05	2	PSL 2 UEL Power Ascension - Turbine Control System SCRAM 102917	419.46	15.56	6,527	$22.62	$147,643	$6.10	$39,829	$107,814
					86.1	**76,179**					**$1,258,382**
											$350,646 /Day

October 2017 - A4 Data	
SL2 Fuel Cost	**SL2 Heat Rate**
0.59	10,343
SL2 $/MWh	
$6.10	

October 2017 - A3 Data								
Fuel	**MWh**	**% Mix**	**Fuel Cost $**	**$/MWh**	**Demand $**	**Rev. Fuel Cost $**	**$/MWh**	**WA $/MWh**
Heavy Oil	38,341	0.45%	$5,148,454	$134.28	$0	$5,148,454	$134.28	$0.61
Light Oil	2,917	0.03%	$409,868	$140.51	$0	$409,868	$140.51	$0.05
Coal	406,724	4.83%	$11,659,143	$28.67	$0	$11,659,143	$28.67	$1.38
Gas	7,979,967	94.68%	$250,937,280	$31.45	$77,505,784	$173,431,496	$21.73	$20.58
Total	**8,427,949**	**100.00%**	**$268,154,745**		**$77,505,784**	**$190,648,961**		**$22.62**

FPSC EXH No. 22
03/20/2024

ADMITTED

Turkey Point Unit 3

Event Start	Event End	Seq. #	Event Title	MW Loss	Outage Hours	MWh Loss	Replacement Cost ($/MWh)	Replacement Cost ($)	TN3 Fuel Cost ($/MWh)	Nuclear Fuel Cost ($)	Net Replacement Cost ($)
A	B	C	D	E	F = (B - A) * 24	G = E * F	H = WA $/MWh	I = G * H	J = TN3 $/MWh	K = J * G	L = I - K
8/19/2020 13:23	8/20/2020 18:16	1	PTN Unit 3 Automatic Rx trip caused by N-3-31 Source Range Counts	837.00	28.88	24,175	$14.76	$356,871	$4.99	$120,564	$236,307
8/20/2020 18:17	8/20/2020 23:54	2	PTN Unit 3 power ascension following Auto Rx trip	755.44	5.62	4,243	$14.76	$62,635	$4.99	$21,160	$41,475
					34.50	**28,418**					**$277,781**
											$193,239 /Day

August 2020 - A4 Data	
TN3 Fuel Cost	TN3 Heat Rate
0.47	10,640
TN3 $/MWh	
$4.99	

August 2020 - A3 Data								
Fuel	MWh	% Mix	Fuel Cost $	$/MWh	Demand $	Rev. Fuel Cost $	$/MWh	WA $/MWh
Heavy Oil	2,586	0.03%	$340,645	$131.74	$0	$340,645	$131.74	$0.03
Light Oil	2,843	0.03%	$355,148	$124.93	$0	$355,148	$124.93	$0.03
Coal	183,830	1.79%	$5,989,567	$32.58	$0	$5,989,567	$32.58	$0.58
Gas	10,068,811	98.16%	$232,689,231	$23.11	$87,947,458	$144,741,772	$14.38	$14.11
Total	**10,258,069**	**100.00%**	**$239,374,591**		**$87,947,458**	**$151,427,133**		**$14.76**

FPSC EXH No. 22
03/20/2024

ADMITTED

Florida Power & Light Company
Docket No. 20240001-EI
Staff's 2nd Set of Interrogatories
Interrogatory No. 9
Attachment 1 of 1
Page 3 of 4

E2142

St Lucie Unit 1

Event Start	Event End	Seq. #	Event Title	MW Loss	Outage Hours	MWh Loss	Replacement Cost ($/MWh)	Replacement Cost ($)	SL1 Fuel Cost ($/MWh)	Nuclear Fuel Cost ($)	Net Replacement Cost ($)
A	B	C	D	E	F = (B - A) * 24	G = E * F	H = WA $/MWh	I = G * H	J = SL1 $/MWh	K = J * G	L = I - K
12/10/2021 10:24	12/12/2021 1:10	1	Manual Reactor Scram - Maintenance Personnel Error	981.00	38.77	38,030	$35.65	$1,355,924	$4.99	$189,905	$1,166,019
12/12/2021 1:10	12/12/2021 19:11	2	Manual Reactor Scram - Maintenance Personnel Error - Return to full power	485.21	18.02	8,742	$35.65	$311,682	$4.99	$43,653	$268,029
					56.78	**46,772**					**$1,434,048**
											$606,114 /Day

December 2021 - A4 Data	
SL1 Fuel Cost	**SL1 Heat Rate**
0.48	10,373
SL1 $/MWh	
$4.99	

December 2021 - A3 Data								
Fuel	**MWh**	**% Mix**	**Fuel Cost $**	**$/MWh**	**Demand $**	**Rev. Fuel Cost $**	**$/MWh**	**WA $/MWh**
Heavy Oil	1	0.00%	$79	$158.08	$0	$79	$158.08	$0.00
Light Oil	9,004	0.14%	$1,088,121	$120.85	$0	$1,088,121	$120.85	$0.16
Coal	167,208	2.52%	$5,989,715	$35.82	$0	$5,989,715	$35.82	$0.90
Gas	6,453,841	97.34%	$310,613,664	$48.13	$81,303,888	$229,309,776	$35.53	$34.59
Total	**6,630,053**	**100.00%**	**$317,691,579**		**$81,303,888**	**$236,387,691**		**$35.65**

FPSC EXH No. 22
03/20/2024

ADMITTED

E2143

St Lucie Unit 2

Event Start	Event End	Seq. #	Event Title	MW Loss	Outage Hours	MWh Loss	Replacement Cost ($/MWh)	Replacement Cost ($)	SL2 Fuel Cost ($/MWh)	Nuclear Fuel Cost ($)	Net Replacement Cost ($)
A	B	C	D	E	F = (B - A) * 24	G = E * F	H = WA $/MWh	I = G * H	J = TN4 $/MWh	K = J * G	L = I - K
1/6/2022 13:00	1/6/2022 21:13	1	Control Element Assembly 27 Power Reduction	328.00	8.22	2,695	$30.76	$82,894	$5.16	$13,912	$68,982
1/6/2022 21:13	1/19/2022 16:43	2	Control Element Assembly 27 Repair	986.00	307.50	303,195	$30.76	$9,325,611	$5.16	$1,565,120	$7,760,490
1/19/2022 16:43	1/20/2022 20:28	3	Control Element Assembly 27 Extension for MG Set Repair	986.00	27.75	27,362	$30.76	$841,579	$5.16	$141,243	$700,337
1/20/2022 20:28	1/21/2022 14:30	4	Control Element Assembly 27 Power Ascension	324.72	18.03	5,856	$30.76	$180,111	$5.16	$30,228	$149,883
					361.50	**339,107.35**					**$8,679,692**
											$576,245 /Day

January 2022 - A4 Data	
SL2 Fuel Cost	SL2 Heat Rate
0.42	12,160
SL2 $/MWh	
$5.16	

January 2022 - A3 Data								
Fuel	MWh	% Mix	Fuel Cost $	$/MWh	Demand $	Rev. Fuel Cost $	$/MWh	WA $/MWh
Heavy Oil	23	0.00%	$79	$3.44	$0	$79	$3.44	$0.00
Light Oil	65,535	0.87%	$711,418	$10.86	$0	$711,418	$10.86	$0.09
Coal	171,979	2.29%	$7,202,821	$41.88	$0	$7,202,821	$41.88	$0.96
Gas	7,266,559	96.83%	$304,733,593	$41.94	$81,838,429	$222,895,164	$30.67	$29.70
Total	**7,504,096**	**100.00%**	**$312,647,911**		**$81,838,429**	**$230,809,482**		**$30.76**

E180

FPSC EXH No. 22
03/20/2024

ADMITTED

DECLARATION

I, Gerard J. Yupp, sponsored the answer to Interrogatory No. 9 from **Staff's Second Set of Interrogatories (No. 9)** to Florida Power & Light Company in Docket No. 20240001-EI, and the response is true and correct based on my personal knowledge.

Under penalties of perjury, I declare that I have read the foregoing declaration and the interrogatory answer identified above, and that the facts stated therein are true.

Gerard J. Yupp

Date: 2/15/24