

ORIGINAL
FILE COPY

BEFORE THE FLORIDA PUBLIC SERVICE COMMISSION

TESTIMONY OF J. BRIAN DIETZ

ON BEHALF OF PANDA-KATHLEEN, L.P.

DOCKET NO. 950110-EI

DOCUMENT NUMBER-DATE

00264 JAN-88

FPSC-RECORDS/REPORTING

1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
17
18
19
20
21
22
23
24
25
26
27
28
29

BEFORE THE FLORIDA PUBLIC SERVICE COMMISSION
TESTIMONY OF J. BRIAN DIETZ
ON BEHALF OF PANDA-KATHLEEN, L.P.
DOCKET NO. 950110-EI

I. INTRODUCTION AND QUALIFICATION

Q. Please state your name, profession, and business address.

A. My name is J. Brian Dietz. I am the Director of Engineering and Operations of Panda Energy International, Inc. Panda Energy International, Inc. is engaged in the development and operation of cogeneration facilities. Panda-Kathleen, L.P. is engaged in the development, ownership and operation of independent power facilities and a qualified cogeneration facility in Lakeland, Florida pursuant to a contract between Panda-Kathleen, L.P. and Florida Power Corporation. My business address is 4100 Spring Valley, Dallas, Texas 75244.

Q. State briefly your educational and professional background.

A. I earned a Bachelor of Science degree in mechanical engineering from the University of Maryland in 1960 and a Master of Science degree in mechanical engineering from Rensselaer Polytechnic Institute in 1966.

From 1960-61, I was employed by Vitro Laboratories of Silver Spring, Maryland. From 1961-66, I was employed by

1 United Technologies as a Senior Engineer, leaving in 1966
2 to join Vought Corporation of Dallas, Texas as a Senior
3 Engineering Specialist. I left Vought in 1977 to become
4 the Director of Engineering and Development for Lone Star
5 Energy Company of Dallas, Texas.

6
7 In 1983, I left Lone Star to become the Manager of
8 Business Development for CSW Energy, Inc. of Dallas. In
9 that position, I directed project development activities
10 for cogeneration, small power production and energy
11 management activities for CSW, a then newly-formed
12 subsidiary of Central and Southwest Corporation, a public
13 utility holding company. At CSW, I led a business
14 development team that obtained four letters of intent to
15 develop more than 300 MW of cogeneration projects.

16
17 In 1985, I left CSW to become the Director of Project
18 Development for Ford, Bacon & Davis of Monroe, Louisiana.
19 While employed in this position from 1985-87, I marketed
20 and developed cogeneration projects for this engineering
21 and construction firm specializing in pulp and paper
22 projects.

23
24 In 1987, I returned to Lone Star Energy as a Vice-
25 President, serving as executive manager for Lone Star,
26 directing engineering, operations and profit-loss

1 performance for five large thermal energy plants
2 representing a \$170 million investment.

3

4 In 1989, I left Lone Star to become an independent
5 consultant specializing in the development, analysis and
6 operations and maintenance of industrial energy and
7 cogeneration projects. During that time, in addition to
8 my work for other clients, I reviewed the operational
9 readiness of the operations contractor, and performed
10 owners representative overview activities for the
11 commissioning, start-up and testing of a 165 MW combined
12 cycle cogeneration facility for Panda Energy Corporation,
13 the predecessor to Panda Energy International, Inc..

14

15 I joined Panda Energy Corporation in September 1992 as
16 its Director of Engineering and Operations.

17

18 I am a registered professional engineer in the state of
19 Texas and have held numerous offices in the American
20 Society of Mechanical Engineers.

1 Q. On whose behalf are you appearing in this proceeding?

2

3 A. I am appearing on behalf of Panda-Kathleen, L.P.

4

5 Q. Please describe your duties with Panda Energy
6 International, Inc.

7

8 A. As Panda's chief engineer, I have the responsibility for
9 the direction of the design, analyses, selection and
10 specification of all major equipment and systems for the
11 Panda-Kathleen project and the 230 MW Panda Brandywine
12 project. These responsibilities also include, and have
13 included, participation in the negotiation of the turnkey
14 engineering/procurement/construction contracts for these
15 cogeneration plants.

16

17 As Panda's chief of plant operations, I have total
18 management responsibility for the operation and
19 maintenance of Panda's existing 175 MW cogeneration
20 facility in North Carolina. The plant consists of one GE
21 Frame 7 and one GE Frame 6 gas turbine in a combined
22 cycle configuration. My responsibilities also include
23 corporate management and the administration of the power
24 purchase contract and thermal sales contract, and
25 responsibility for the financial performance (profit and
26 loss) of the plant.

27

1 Q. Have you ever testified before the Florida Public Service
2 Commission?

3

4 A. No, I have not.

5

6 II. PURPOSE OF TESTIMONY

7 Q. What is the purpose of your testimony?

8

9 A. The purpose of my testimony is to state the facts
10 underlying Panda's attempts to comply with its
11 contractual obligation to ensure that it will be able to
12 supply Florida Power Corporation with wholesale electric
13 power for 30 years at a net 74.9 MW or greater of
14 capacity, under all operating conditions. My testimony
15 will also state the facts regarding the engineering and
16 permitting necessities that Panda attempted to comply
17 with throughout the configuration selection process.

18

19

20 III. CONTRACTUAL CONSIDERATIONS IN CONFIGURATION SELECTION

21 Q. What considerations went into the choice of configuration
22 for the Panda facility?

23 A. Panda must select a plant configuration which meets the
24 performance and interconnection requirements set forth in
25 the contract executed by Panda and Florida Power
26 Corporation ("FPC"). These include requirements for the
27 Facility to:

1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
17
18
19
20
21
22
23
24
25
26

1. Make available to FPC the Committed Capacity of 74.9 MW, at all times, at the Point of Delivery from the Contract In-Service Date throughout the entire term of the power agreement (30 years);
2. Demonstrate, each year, the Commercial In-Service Status of the Facility within 60 days of when FPC demands that demonstration;
3. Maintain an hourly kW output, as metered at the Point of Delivery, equal to or greater than the Committed Capacity for a consecutive twenty-four hour period or during the on-peak hours for two consecutive days;
4. Be in compliance with all applicable permits;
5. Be a Qualifying Facility ("QF") delivering steam during all hours of plant operation (as opposed to the avoided or deferred unit which is a combustion turbine operating as a peaking unit in a simple cycle configuration);
6. Be capable of delivering the Committed Capacity using back-up fuel; and

1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
17
18
19
20
21

7. Operate at 74.9 MWH per hour or more for 90% of the on-peak hours and 42% of the total hours in each year of the Contract term to approximate the availability and capacity factor of the utility's avoided unit as required by the Contract.

There are no constraints in the power agreement on the technology, equipment or plant configuration that may be utilized.

Q. Did Panda consider size restrictions in its contract with Florida Power in selecting a configuration for the Panda facility?

A. There are no provisions in the power purchase agreement that restrict the electrical generating capability of the plant. In fact, the contract requires Panda to deliver 74.9 MW of Committed Capacity at the Point of Delivery at all times under all weather conditions and states of maintenance.

1 IV. ENGINEERING CONSIDERATIONS IN CONFIGURATION SELECTION

2 Q. Why would Panda need to select a configuration for the
3 facility that would have an ultimate capability exceeding
4 74.9 MW at the generator?

5
6 A. Given the realities of electrical generation, the
7 contract required Panda to construct a facility with an
8 ultimate capability exceeding 74.9 MW at the generator
9 because:

10
11 1. The Committed Capacity is determined after
12 parasitic electrical usage (the electricity needed
13 to run auxiliary equipment and systems in the plant
14 that are necessary to generate electricity) is
15 subtracted;

16
17 2. The Committed Capacity is determined at, and must
18 be delivered to, the Point of Delivery, after line
19 and transformation losses have occurred;

20
21 3. The Committed Capacity must be delivered under all
22 weather conditions and without regard to
23 degradation occurring as a result of normal wear
24 and tear;

25
26 4. The Committed Capacity must be deliverable using
27 the back-up fuel; and

1 5. The Contract requires demonstrating this capability
2 on 60 days notice throughout the term of the
3 Contract, and prudence requires assuming that such
4 notice will take place under worst case conditions.

5
6 To satisfy all of these requirements requires the
7 construction of a plant with a maximum total capability
8 greater than the 74.9 MW Committed Capacity.

9
10 Q. What design issues went into this configuration selection
11 process?

12
13 A. To meet its obligations under its contract with Florida
14 Power, Panda proposed to construct a combustion turbine
15 in a combined cycle configuration for this Facility.
16 Under this configuration, the waste heat from the
17 combustion turbine is captured to make steam, which in
18 turn is used to generate more electricity with great
19 efficiency. The steam is extracted for process uses
20 which is what makes it a cogeneration facility. This is
21 the only viable QF configuration that could be built
22 whereby the capacity and energy payment streams under the
23 Contract will match up with the project's fixed and
24 variable costs and that also will ensure that the
25 facility is in full compliance with the Public Utilities
26 Regulatory Policies Act ("PURPA"). Combined cycle
27 technology has a number of characteristics that require

1 the application of a unit with a maximum total capability
2 greater than the Committed Capacity of 74.9 MW.

3

4 Q. Was ambient temperature degradation an issue in
5 configuration selection?

6

7 A. Yes. The output of a combined cycle plant varies
8 significantly with changes in ambient temperature and
9 relative humidity. The Contract does not set the ambient
10 conditions for the plant design nor does it set any upper
11 limit for temperature under which the 74.9 MW Committed
12 Capacity performance requirements must be met. Since a
13 combined cycle facility is subject to substantial
14 performance degradation under conditions of high ambient
15 temperature, the plant had to be sized to meet the
16 Committed Capacity under the maximum expected ambient
17 temperature. Florida Power had expressly requested
18 facility performance numbers for temperatures as high as
19 110° F and temperatures of 100° F are commonly
20 experienced in Lakeland in at least three different
21 calendar months of the year. The maximum recorded
22 temperature is 102° F. During the 30-year term of the
23 Contract, a 102° F temperature must be anticipated.

24

25 At a temperature of 102° F, the performance of a combined
26 cycle plant degrades from approximately 15% to 19% of
27 rated capacity (depending on the exact equipment

1 selected) compared with the performance of the unit at
2 59° F at sea level. Plant rated performance is typically
3 quoted at 59° F at sea level.

4

5 Q. What other performance degradation issues were considered
6 in the configuration selection process?

7

8 A. A combined cycle facility also is subject to substantial,
9 performance degradation, both non-recoverable and
10 maintenance-recoverable, due to operational wear and tear
11 on the plant. Maintenance-recoverable degradation is
12 experienced between the major overhauls of the combustion
13 turbine, steam turbine, and other plant auxiliary
14 equipment. Published figures by major turbine suppliers
15 show that non-recoverable and maintenance-recoverable
16 degradation can be up to 6%.

17

18 In addition, a combined cycle facility experiences
19 operationally-recoverable degradation. This degradation
20 includes that due to combustion turbine compressor and
21 air cleaner fouling. This can amount to 2% of rated
22 capacity. This degradation can be recovered by thorough,
23 off-line "washing" of the compressor and/or cleaning of
24 the air filter. This "washing" can be accomplished when
25 the combustion turbine is off-line.

26

1 Q. How must the design capability account for parasitic
2 loads?

3
4 A. The facility will consume approximately 2% of its total
5 output for internal purposes, including operating pumps,
6 fans, controls, and other auxiliary equipment. The
7 design must account for these parasitic loads.

8
9 Q. How did Panda account for projected transformation and
10 transmission line losses?

11
12 A. These losses have been estimated at 1/2% to 1-1/2% and
13 will continue over the thirty year period of the
14 agreement.

15
16 Q. Based on the analysis you've just described, what did
17 Panda consider to be the total effects of degradation,
18 parasitic loads and transformation and line losses?

19
20 A. For the combined cycle facility to meet the Committed
21 Capacity of 74.9 MW at the Point of Delivery at all times
22 during the 30-year term of the power purchase agreement,
23 the plant must be designed to include the cumulative
24 effects of temperature degradation, nonrecoverable
25 degradation, recoverable degradation, and transformation
26 and line losses to the Point of Delivery. These
27 degradations in output do not include reduced plant

1 output or degradation due to random auxiliary equipment
2 failure over the 30 year term of the power agreement.
3 These random equipment failures include such things as
4 loss of a cooling tower fan, heat recovery steam
5 generator tube failures, malfunctioning of combustion or
6 steam turbine controls, valve failures, etc. Prudent
7 engineering practice would include an extra margin of
8 several percent above design rated plant output of the
9 plant. Panda considered 2% to be a conservative margin.
10 In the aggregate, all of these factors, conservatively,
11 can total 27% to 31% of the Facility's initial generation
12 capability rated under standard conditions. As a result
13 the plant must be designed conservatively with a minimum
14 rated output of 100 MW at 59° F net of parasitic loads.
15 This is the minimum size that the Facility must be
16 capable of producing to be able to meet its contractual
17 commitments for the entire 30-year term of the Contract.

18
19

20 **IV. ENVIRONMENTAL CONSIDERATIONS IN CONFIGURATION SELECTION**

- 21 Q. How did environmental regulations play a part in the
22 configuration selection process?
23
24 A. When Panda signed the contract with Florida Power, the
25 State of Florida limited nitrogen oxide ("NO_x") emissions
26 to the atmosphere from a generating facility to 25 parts
27 per million ("PPM") at 15% excess oxygen. However, when

1 Panda began the facility permitting process in late 1992,
2 the State of Florida had limited those emissions to the
3 atmosphere to 15 PPM at 15% excess oxygen. This
4 regulatory change had a significant effect on the
5 technology selection and configuration selection process.

6
7 Uncontrolled, most combustion turbine models emit well
8 over 150 PPM NO_x at 15% excess oxygen. There are
9 currently two methods to achieve compliance with NO_x
10 emission standards for a combined cycle plant: (i)
11 through the use of dry low NO_x combustors ("DLN") in the
12 combustion turbine; or (ii) through the injection of
13 water or steam in the combustion turbine combustors in
14 conjunction with injection of ammonia and catalytic
15 reduction in Selective Catalytic Reduction equipment
16 ("SCR") located in the heat recovery steam generator.

17
18 Q. Would the use of Selective Catalytic Reduction equipment
19 ("SCR") enable Panda to comply with these Florida
20 environmental regulations?

21
22 A. No. While both the DLN and, to some extent, SCR
23 technologies are sufficiently developed to be accepted by
24 the engineering, regulatory, and financial communities,
25 the SCR technology has particular problems associated
26 with it that would make it difficult, if not impossible,

1 to meet the 15 PPM requirement over the 30 year contract
2 term.

3
4 Application of SCR to combustion turbines has been
5 primarily limited to natural gas fueled units. In
6 California, the state with the most significant
7 experience with SCR, only 11 of 41 permitted SCR
8 facilities have been permitted to fire oil as a backup
9 fuel, as is required for the facility. This is due to
10 the fact that the SCR catalyst promotes the oxidation of
11 flue gas SO₂ to SO₃, which in turn reacts with un-reacted
12 ammonia to form compounds that foul equipment downstream,
13 including the SCR catalyst, rendering it ineffective.
14 Only one of these facilities has ever been fired on oil
15 (resulting in catalyst failure) and it no longer operates
16 with liquid fuels. This factor alone virtually
17 disqualifies SCR technology, and any turbines that cannot
18 meet environmental standards without it, for use by
19 Panda-Kathleen.

20
21 In addition, there are certain inherent safety and
22 environmental risks associated with the use of SCR
23 technology. The safety risks include leaks in an urban
24 environment during the transportation, storage, and
25 handling of the ammonia required for the SCR. Ammonia is
26 designated as an "Extraordinarily Hazardous Substance"
27 under Federal Superfund Regulations. The environmental

1 risks include malfunctioning of the SCR and its control
2 system, ammonia slip (i.e., the mismatch between the
3 ammonia injected and the ammonia needed for NO_x reduction
4 during operation), and the disposal at the end of its
5 useful life of spent SCR catalyst, which contains
6 substantial amounts of heavy metals and metal oxides that
7 are classified as hazardous (e.g., titanium, vanadium,
8 platinum, and rhodium). These safety and environmental
9 risks translate into financial risks for operator, owner,
10 and lenders. In addition, a facility using SCR
11 technology will have a higher capital cost and
12 substantially higher operating and maintenance costs than
13 one using DLN technology.

14
15 In addition to the advantages of DLN over SCR technology
16 for safety, environmental protection, and cost, DLN
17 technology also offers operability advantages. These
18 include smoothness and reliability during combustor mode
19 changes, gas turbine load changes, and system transients.
20 In addition, unlike SCR equipment, the DLN system
21 operation is transparent to the plant operator.

22
23 The use of SCR technology is not preferred by either
24 engineers or regulators in several areas of the country
25 for the aforementioned reasons. Many consider the use of
26 SCR to control NO_x emissions as "extraordinary means" or
27 "heroic technology." The Panda-Kathleen project

1 considered using SCR technology only as a last resort in
2 the event that plant configurations using DLN could not
3 be employed.

4

5 V. FINANCING CONSIDERATIONS IN CONFIGURATION SELECTION

6 Q. How did all of the factors you've described affect plant
7 financeability?

8

9 A. Potential lending and equity participants in the
10 Panda-Kathleen project will look not only at its
11 financial strength but also at the plant design and
12 selection of equipment. To be financeable, the plant
13 must incorporate previously applied technology that has
14 been thoroughly proven in other applications and must
15 incorporate that equipment to produce a plant with high
16 reliability over the term of the power contract. The
17 only viable plant option that would meet all these
18 requirements and could be built and operated as a QF with
19 the capacity and energy payment streams provided under
20 the Contract is a combined cycle facility.

21

22

23 VI. EQUIPMENT SELECTION TO COMPLY WITH THE PANDA-FPC CONTRACT

24 Q. What brands of equipment and models did Panda consider in
25 the configuration selection process?

26

1 A. Based on the Contract performance requirements and design
2 issues, Panda performed a detailed evaluation of six
3 combustion turbine alternatives for the combined cycle
4 plant. Several other configurations were evaluated on a
5 preliminary basis. The number of alternative combustion
6 turbines is limited by equipment availability since,
7 unlike conventional steam plants that custom-tailor the
8 steam turbine performance, combustion turbines come only
9 in standard sizes predetermined by the manufacturers.
10 The six configurations evaluated cover a wide range of
11 performance. These were the ABB 8C, Siemens V64.3, GE
12 LM2500, GE LM6000, GE Frame 7EA, and the ABB 11N1
13 combustion turbines.

14
15 The ABB 8C combined cycle facility was unable to produce
16 the necessary minimum rated output of 100 MW at 59° F net
17 of parasitic loads (to overcome expected degradation and
18 line losses) without extensive supplemental firing of the
19 heat recovery steam generator (HRSG) and the use of SCR
20 technology for NOx control to 15 PPM. Supplemental
21 firing of the HRSG is not the most efficient use of fuel
22 for the QF concept. The disadvantages of SCR technology
23 have already been discussed. This configuration was
24 rejected for these reasons.

25
26 Similarly, the Siemens V64.3 combined cycle facility also
27 was unable to produce the necessary minimum rated output

1 of 100 MW at 59° F net of parasitic loads without
2 supplemental firing of the HRSG. Further, NO_x emissions
3 cannot be controlled to 15 PPM without the use of SCR.
4 For these reasons, this configuration was rejected.

5
6 As with facilities using the ABB 8C or Siemens V64.3
7 units, a combined cycle facility using three combined GE
8 aero derivative LM2500 combustion turbines was unable to
9 produce the necessary minimum rated output of 100 MW at
10 59° F net of parasitic loads without supplemental firing
11 of the HRSG. NO_x emissions cannot be controlled to 15
12 PPM without the use of SCR. For these reasons, this
13 configuration was rejected.

14
15 The GE LM6000 aero derivative combined cycle facility
16 using two combustion turbines was determined to produce
17 109 MW net of parasitic loads at 59° F. This is 9 MW more
18 than the necessary minimum rated output. However, the
19 use of SCRs to control the NO_x emissions to 15 PPM is
20 required. In addition, the capital and O&M costs for
21 this configuration were greater than the costs associated
22 with more acceptable configurations. This configuration
23 was rejected for these reasons.

24
25 When new, the GE Frame 7EA combined cycle facility was
26 rated to produce 118 MW net of parasitic loads at 59° F.
27 Control of NO_x emissions to less than 15 PPM can be

1 obtained using DLN technology. Thus, this unit was
2 deemed to be acceptable.

3

4 When new, the ABB11N1 combined cycle facility was rated
5 to produce 116 MW net of parasitic loads at 59° F.
6 Control of NO_x emissions to 15 PPM can be obtained using
7 DLN technology. Therefore this unit also was deemed to
8 be acceptable.

9

10 **VII. PLANT CONFIGURATIONS SELECTED**

11 Q. What brands of equipment and models did Panda ultimately
12 select based on this analysis?

13

14 A. Based on the foregoing analysis, Panda determined that
15 the GE Frame 7EA and ABB11N1 combustion turbines are the
16 only reasonable plant configurations that could reliably
17 provide the Committed Capacity of 74.9 MW at the Point of
18 Delivery at all times over the 30-term of the Contract
19 under all weather conditions with the expected
20 degradation, parasitic loads, and losses. These
21 configurations are the lowest capacity units that meet
22 these criteria. The analysis indicated that both were
23 equally capable from a technical and economic standpoint.
24 Both combustion turbine manufacturers were willing to
25 guarantee DLN technology to meet 15 PPM. While Panda
26 submitted both configurations for permitting, ultimately
27 only ABB was able to guarantee timely delivery of its

1 combustion and steam turbines in accordance with the
2 schedule set forth in Panda's EPC contract to assure the
3 plant would achieve Commercial In-Service Status in
4 accordance with the power purchase contract.

5

6 Q. Does this conclude your testimony?

7

8 A. Yes, it does.

9

1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
17
18
19
20

J. Brian Dietz

STATE OF TEXAS)
COUNTY OF Dallas) SS: 467-54-6763

The foregoing instrument was acknowledged before me this 4th day of January, 1995 by J. Brian Dietz. He is personally known me, and did take an oath.

[NOTARIAL SEAL]

Notary: Theresia M. Bone
Print Name: THERESIA M. BONE
Notary Public, State of Texas
My commission expires: 6-23-97

