



# Department of Environmental Protection

Panama City Branch Office

2353 Jenks Avenue

Panama City, FL 32405

Phone: (850)-872-4375

Fax: (850) 872-7790

Jeb Bush  
Governor

David B. Struhs  
Secretary

December 6, 2001

Gulf Power Company  
C/o Richard Markey, Environmental Affairs  
One Energy Place  
Pensacola, Florida 32520-0328

REF.: **STORMWATER GENERAL PERMIT - TYPE B**  
Project: Sinai Substation  
File #: 32-0192195-001-RG  
County: Jackson

Dear Mr. Markey:

We have reviewed your Notice of General Permit received by the Department on November 13, 2001, concerning the above referenced project. The project appears to qualify for the General Permit specified by Rule 62-25.801, Florida Administrative Code (F.A.C.).

Please review and be aware of the general conditions associated with this General Permit as outlined in Rule 62-4.540, F.A.C. This General Permit does not relieve you, the permittee, from obtaining a dredge and fill permit or other permits (local, state or federal) which may be required.

We wish to point out that Section 62-25.801, F.A.C. also requires that the permittee file an As-Built Certification with the Department within thirty (30) days after the facility's completion. This certification is included as Page 4 of DEP form 62-1.215(2), the General Permit for Stormwater Discharge Facilities.

If you have any questions about the need to obtain additional permits, or any other matters, please call Robert Taylor at (850) 872-4375.

Sincerely,

Gary L. Shaffer  
Branch Manager

GLS:rft

cc: DEP/PEN-Cliff Street, P.E.  
Harry V. Durden, P.E.

*"More Protection, Less Process"*

Printed on recycled paper.

FPL 026837  
20210015-EI

One Energy Place  
Pensacola, Florida 32520

Tel 850.444.6111



November 9, 2001

Mr. Bob Taylor  
Florida Department of Environmental Protection  
2353 Jenks Avenue  
Panama City, Florida 32405

**RE: Sinai Substation Project - NOI to Use a General Permit for a New Stormwater Facility**

Dear Mr. Taylor:

Enclosed please find the Notice of Intent to use a general permit for a new stormwater discharge facility. This new Sinai Substation stormwater discharge facility is located in Section 14, Township 3 North, Range 7 West, Jackson County Florida. A permit fee in the amount of \$250 has been enclosed as specified in F.A.C. Rule 62-4.050(4)(p)a. In addition, the following attachments are included:

1. Topographic map illustrating the proposed location of the stormwater pond.
2. Notice of Intent to use a general permit for a new stormwater discharge facility.
3. Project summary/conclusions, and calculations, and pertinent drawings of the proposed project.

If you should have any questions regarding this permit application, please feel free to give me a call at (850) 444-6573. Thank you very much for your time in this matter.

Sincerely,

A handwritten signature in black ink, appearing to read "Mike Markey".

Richard "Mike" Markey, P.G.  
Environmental Affairs

Cc: Gulf Power Company  
Rachel Allen Terry  
Tracy Judson  
Jim Vick

Alabama Power Company  
Harry Durden

H:\sinaisub\stormwaterpond.doc



FLORIDA DEPARTMENT OF ENVIRONMENTAL PROTECTION  
2815 Remington Green Circle, Ste. A, Tallahassee, Florida 32308-1513

Form Title	_____
Effective Date	_____
DER Application No.	_____ (Filed in by DEP)

NOTICE OF INTENT TO USE GENERAL PERMIT (SECTION 17-4.71 F.A.C.)  
FOR NEW STORMWATER DISCHARGE FACILITY CONSTRUCTION  
CHAPTER 17-25 FLORIDA ADMINISTRATIVE CODE

**PREFACE**

This form is to be completed and submitted to the Department along with the information specified in Part I-3, AT LEAST 30 DAYS PRIOR TO INITIATING CONSTRUCTION. Those facilities which qualify for a general permit are listed in Florida Administrative Code Rules 17-4.71 and 17-25.035.

Please provide the information listed below. Fill in all blanks and answer all questions in Parts I and III and the appropriate sections of Part II.

**PART I: GENERAL INFORMATION**

1. Person(s) or entity that owns the discharge facility:

Name and Title: GULF POWER COMPANY  
Address: ONE ENERGY PLACE  
PENSACOLA, FL 32520-0328  
Phone: ( 850 ) 444.6573

2. Stormwater Discharge Facility Identity and Location:

Source (Project) Name: SINAI SUBSTATION  
Source (Project) Location: Street OFF HAMMOND ROAD  
City SINAI County JACKSON  
14 T3N R7W 30 ° 39 '44.5 "N 84 ° 53 ' 57.7 "W  
Section Township Range Latitude Longitude

Name(s) of surface waters\* into which stormwater will be discharged:  
Not Applicable

\*(Please see Sections 403.031 and 403.817 F.S. and 17-4.02(17), F.A.C. for definition of surface waters of the state.)

The surface waters into which stormwater will be discharged are classified as Class N/A waters. These waters are/are not an Outstanding Florida Water and are/are not subject to the additional treatment required by Section 17-25.025(9). Please see Section 17-3.041, F.A.C., for a list of Outstanding Florida Waters and Section 17-3.161 to determine the appropriate classification of the waters.

Please attach a map(s) with sufficient detail to enable someone to locate the subject property.

3. Please submit the following information about your Stormwater Discharge Facility:
  - A. One set of engineering plans and specifications.
  - B. One set of appropriate design analyses, calculations, drawings, narrative description or other information necessary to document and verify that the proposed stormwater discharge facility qualifies for the general permit indicated in Part II.
4. Other DER Permits for this project have been:
  - A. Denied (date) \_\_\_\_\_ DER # \_\_\_\_\_
  - B. Issued (date) \_\_\_\_\_ DER # \_\_\_\_\_
  - C. Pending (date submitted) \_\_\_\_\_ DER # \_\_\_\_\_

**PART II: SPECIAL INFORMATION RELATIVE TO GENERAL PERMITS REQUIRING A NOTICE BY CHAPTER 17-25.035 and BY SECTION 17-4.71, FLORIDA ADMINISTRATIVE CODE CODE RULES**

1. Please indicate the GENERAL PERMIT category for which you qualify.
  - A. Facilities which discharge into a stormwater discharge facility which is permitted pursuant to Fla. Admin. Code Rule 17-25.040 or was exempted pursuant to Fla. Admin. Code Rule 17-25.030 where the appropriate treatment criteria specified in Chapter 17-25 and applied to the permitted or exempt facility are not exceeded by the discharge. (Place a check mark in the space provided and proceed to number 2 of this section.)
  - B. Facilities which provide retention, or detention with filtration, of the runoff from the first one inch of rainfall; or, as an option, for projects or project subunits with drainage areas less than 100 acres, facilities which provide retention, or detention with filtration, of the first one-half inch of runoff. (Place a check mark in the space provided and proceed to number 3 of this section.)
  - C. Modification or reconstruction by a city, county, state agency, special district with drainage responsibility, or water management district of an existing stormwater management system which is not intended to serve new development, and which will not increase pollution loading, or change points of discharge in a manner that would adversely affect the designated uses of waters of the state. (Place a check mark in the space provided and proceed to number 3 of this section.)
  - D. Facilities of stormwater management systems that include a combination of best management practices including but not limited to retention basins, swales, pervious pavement, landscape or natural retention storage that will provide for the percolation of the runoff from a three-year one-hour design storm. (Place a check mark in the space provided and proceed to number 3 of this section.)
2. Please attach a letter of consent signed by the owner or his agent indicating that you have obtained the owner's permission to discharge into the permitted or exempt storm water discharge facility which you propose to utilize. (Complete number 3 of this section.)
3. The GENERAL PERMIT listed above required that a professional engineer certify that the criteria specified will be met by the facility as designed. You must complete Sections A and B in Part III and have your engineer complete Section C in order to qualify for the GENERAL PERMIT. Please note that Chapter 17-25 F.A.C. requires a professional engineer to certify within 30 days after completion of construction that the new stormwater discharge facility has been built in substantial compliance with the appropriate General Permit criteria. (Please use Section III-D of this form.)

**PART III:**

**A. STATEMENT BY APPLICANT**

The undersigned owner or authorized representative\* of Gulf Power Company is fully aware that the statements made in this notice are true, correct and complete to the best of his or her knowledge and belief. The undersigned also agrees to retain the design engineer, or another professional engineer registered in Florida, to conduct on-site observations of construction.

James O. Vick  
Signature of the owner or \*authorized representative  
James O. Vick, Manager of Environmental  
Name and title (Please type)

\*Attach a letter of authorization.

Date: 11/12/01 Phone: (850) 444-6311

**B. STATEMENT BY PERSON RESPONSIBLE FOR MAINTENANCE**

The undersigned agrees to maintain and operate the discharge facilities in such a manner as to comply with the provisions of Chapter 17-25, F.A.C. Responsibility for maintenance and operation may be transferred to another entity upon written notice to the Department from the undersigned and from the entity assuming responsibility, certifying that the transfer of responsibility for maintenance and operation in compliance with Chapter 17-25, F.A.C. has been accepted.

Richard M. Markey  
Signature of the person responsible for maintenance  
(May be the applicant)  
Richard M. Markey Senior Geologist  
Name and title (Please type.)

One Energy Place  
Address  
Pensacola, FL 32520-0328

Date: 11/12/01 Phone: 850.444.6573

**C. STATEMENT BY PROFESSIONAL ENGINEER REGISTERED IN FLORIDA**  
(where required by Chapter 471, Florida Statutes)

This is to certify that the engineering features of this stormwater discharge facility have been designed/examined by me and found to be in conformity with modern engineering principles applicable to the treatment and disposal of stormwater pollutants. I further certify that the facility has been designed in accordance with the appropriate specifications required under Chapter 17-25, Florida Administrative Code. It is also stated that the undersigned has furnished the applicant with a set of instructions for the maintenance and operation of the stormwater discharge facility.

Harry V. Durden  
Signature of Engineer

Harry V. Durden 46278  
Name (Please type) Florida Reg. No.  
Alabama Power Company  
Company Name  
P.O. Box 2641  
Company Address  
Birmingham, AL. 35291



(Affix Seal)

Date: 11/7/01 Telephone Number: (205) 257-4263

**Gulf Power Company  
Sinai Cemetery Substation  
Stormwater Management Plan  
BY: H.V. Durden Jr.  
Date: November 7, 2001**

The subject site is located near Sneads, Florida in Jackson County and is the site of a proposed Gulf Power Company electrical substation. The property is in the northwest  $\frac{1}{4}$  of the northeast  $\frac{1}{4}$  and the west  $\frac{1}{2}$  of the west  $\frac{1}{2}$  of the northeast  $\frac{1}{4}$  of the northeast  $\frac{1}{4}$  of section 14, township 3 north, range 7 west, Jackson County, Florida and comprises approximate 53.5 total acres. The site is surrounded to the east, west and south by undeveloped forest land recently logged. The terrain of the site is a gradual to steep slope to the southeast.

The substation will be constructed in the northwest portion of the property with a developed area approximately equal to 7.62 acres. Stormwater from the substation area will be routed via inlets and piping to a proposed stormwater detention pond located southeast of the substation. The pond will have a top of dike elevation of 97'-0 and a bottom elevation of 88'-0. The emergency overflow weir will be a vertical grate inlet with the bottom at elevation 93'-0. This will release runoff at a rate of 4.72 cfs, from the 100 year-24 hour storm, which is below the predevelopment rate of 6.16 cfs. The maximum pool elevation is allowed to be 96'-0 with 1'-0 freeboard. This results in a maximum pond capacity of approximately 178,768 cubic feet, which exceeds the 100 year-24 hour storm volume of 63,617 cubic feet.

Permeability testing in the area of the proposed pond indicates a rate of 8.97 inches per hour. Groundwater was not encountered at elevations above 86'-0. The pond will drawdown in approximately 1.5 hours for the  $\frac{1}{2}$ " runoff.

The stormwater design exceeds the criteria established by FDEP. Please refer to the enclosed calculations and drawings for details.



*H.V. Durden Jr.*  
11/7/01



Gulf Power Company  
Sinai Site Substation  
Stormwater Detention Pond  
Summary/Conclusions  
November, 2001

**Total Site Drainage Area**                      7.62 Ac = 0.0119 mi<sup>2</sup>

**Pre-Development Conditions**

$C_{pre} = 0.20$   
 $T_{c\ pre} = 12.0\ \text{min}$   
 $I_{10yr} = 6.46\ \text{in/hr}$   
 $Q_{peak\ pre} = 9.84\ \text{cfs}$  (rational method)

$CN = 39$   
 $T_c = 0.20\ \text{hr}$   
 $Q_{peak\ pre} = 6.16\ \text{cfs}$  (TR-20 method) use

**Post-Development Conditions**

- a) Routing 10 yr-24 hr storm through proposed detention pond using TR-20 computer program

$CN_{weighted} = 75$   
 $T_c = 20\ \text{min} = 0.333\ \text{hrs}$     SCS Overland Method  
 $R_{10\ yr} = 7.40\ \text{in}$   
 $Q_{peak\ post\ to\ pond} = 35.13\ \text{cfs}$  use

- b) Rational Method Check

$C_{post} = 0.70$   
 $T_{c\ post} = 20\ \text{min}$                       Kirpich Nomograph  
 $I_{10yr} = 5.34\ \text{in/hr}$   
 $Q_{peak\ post\ to\ pond} = 23.48\ \text{cfs}$

**Storm Routing Results from TR-20 Program**

Using riser weir at elevation 91.0 for both principal spillway and emergency spillway.

- a) For 10yr-24hr storm                       $R = 7.4\ \text{in}$

$Q_{peak\ post\ to\ pond} = 35.13\ \text{cfs}$   
 $Q_{post\ out\ of\ pond} = 0.94\ \text{cfs} < 6.16\ \text{cfs}$   
 $WS_{elevation} = 91.14$

b) For 100 yr – 24 hr storm R = 10.6 in

$$Q_{\text{peak post to pond}} = 57.15 \text{ cfs}$$

$$Q_{\text{post out of pond}} = 4.72 \text{ cfs}$$

$$WS_{\text{elevation}} = 91.74$$

### Required Pond Volumes by State and Local Regulations

1) Required FDEP Volume

$$\frac{1}{2} \text{ inch} * 1 \text{ ft}/12 \text{ in} * 7.62 \text{ Ac} * 43560 \text{ ft}^2/\text{Ac} = \underline{13830 \text{ ft}^3}$$

(req'd (total site) storage)

2) More Strict Local Requirements (if applies)

$$1 \text{ inch} * 1 \text{ ft}/12 \text{ in} * 7.62 \text{ Ac} * 43560 \text{ ft}^2/\text{Ac} = \underline{27660 \text{ ft}^3}$$

(req'd (total site) storage)

### Proposed Pond

$$\text{Top elevation} = 97.0 \quad \text{Area} = 34848 \text{ ft}^2$$

$$\text{Max Pool, 1 ft Freeboard elevation} = 96.0 \quad \text{Area} = 32365 \text{ ft}^2$$

$$\text{Weir top, final Selection for retention} = 93.0 \quad \text{Area} = 24829 \text{ ft}^2$$

$$\text{Weir top, for Detention, principal And emergency spillway} = 91.0 \quad \text{Area} = 19820 \text{ ft}^2$$

$$\text{Bottom elevation} = 88.0 \quad \text{Area} = 12327 \text{ ft}^2$$

Proposed volume, total pond

$$(32365 \text{ ft}^2 + 12327 \text{ ft}^2)/2 * 8 \text{ ft (depth)} = 178768 \text{ ft}^3$$

$$\begin{array}{ll} \text{Area at} & \text{Area at} \\ \text{El. 96.0} & \text{El. 88.0} \end{array}$$

For weir elevation of 91.0

$$(19820 \text{ ft}^2 + 12327 \text{ ft}^2)/2 * 3 \text{ ft (depth)} = 48220 \text{ ft}^3$$



48220 ft<sup>3</sup> > 13830 ft<sup>3</sup>      Ok      FDEP  
48220 ft<sup>3</sup> > 27660 ft<sup>3</sup>      Ok      County or local

For weir elevation of 93.0  
(24829 ft<sup>2</sup> + 123327 ft<sup>2</sup>)/2 \* 5 ft (depth) = 92890 ft<sup>3</sup>

92890 ft<sup>3</sup> > 48220 ft<sup>3</sup>      Ok

### Drawdown

Permeability rate calculated = 8.97 in/hr

Use 9 inch per hour = 0.75 ft per hour

Pond bottom area = 123327 ft<sup>2</sup>

Drawdown rate = 12327 ft<sup>2</sup> \* 0.75 ft/hr = 9245 ft<sup>3</sup>/hr

FDEP time = 13830 ft<sup>3</sup>/9245 ft<sup>3</sup>/hr = 1.5 hr

1.5 hours < 36 hours      Ok

County or local time = 27660 ft<sup>3</sup>/9245 ft<sup>3</sup>/hr = 3.0 hr

3.0 hours < 36.0 hours      Ok

Sinai3b.out

1

\*\*\*\*\*80-80 LIST OF INPUT DATA FOR TR-20 HYDROLOGY\*\*\*\*\*

JOB TR-20	FULLPRINT	NOPLOTS	10
TITLE 001	SINAI SUBSTATION SITE TRIAL 3	10YR-24HR	20
TITLE	STORM ROUTING CALCS - DETENTION POND W/ RISER PIPE		30
3 STRUCT	04		110
8	88.00	0.000	0.000
8	89.00	0.060	0.312
8	90.00	0.070	0.681
8	91.00	0.080	1.107
8	91.10	0.490	1.153
8	91.20	1.390	1.200
8	91.30	2.560	1.247
8	91.40	3.930	1.294
8	91.50	4.640	1.342
8	91.60	4.670	1.391
8	91.70	4.710	1.440
8	91.80	4.740	1.490
8	91.90	4.770	1.541
8	92.00	4.810	1.592
8	92.10	4.840	1.643
8	92.20	4.870	1.695
8	93.00	5.130	2.133
8	94.00	5.430	2.732
8	95.00	5.720	3.388
8	96.00	5.990	4.102
9 ENDTBL			228
6 RUNOFF 1 001	1 0.0119	75.	0.333
6 RESVOR 2 04 1	1 88.00		
7 INCREM 6	0.10		
7 COMPUT 7 001	04	7.40	1.0
ENDCMP 1			
ENDJOB 2			

\*\*\*\*\*END OF 80-80 LIST\*\*\*\*\*

1

TR20 XEQ 10-23-01 16:56	SINAI SUBSTATION SITE TRIAL 3	10YR-24HR	20
JOB 1 PASS 1			
REV PC 09/83(.2)	STORM ROUTING CALCS - DETENTION POND W/ RISER PIPE		30
PAGE 1			

EXECUTIVE CONTROL OPERATION INCREM  
RECORD ID 280

MAIN TIME INCREMENT = .10 HOURS

EXECUTIVE CONTROL OPERATION COMPUT  
RECORD ID 290

FROM XSECTION 1 TO STRUCTURE 4

STARTING TIME = .00 RAIN DEPTH = 7.40 RAIN DURATION= 1.00 RAIN TABLE NO.= 2 ANT.  
 MOIST. COND= 2  
 ALTERNATE NO.= 1 STORM NO.= 1 MAIN TIME INCREMENT = .10 HOURS

OPERATION RUNOFF CROSS SECTION 1  
 OUTPUT HYDROGRAPH= 1  
 AREA= .01 SQ MI INPUT RUNOFF CURVE= 75. TIME OF CONCENTRATION= .33 HOURS  
 INTERNAL HYDROGRAPH TIME INCREMENT= .0444 HOURS

\*\*\*ELEVATION OUTPUT OPTION REQUESTED BUT NO ELEVATIONS GIVEN\*\*\*

PEAK TIME (HRS)	PEAK DISCHARGE (CFS)	PEAK ELEVATION (FEET)
12.10	35.13	(RUNOFF)

TIME (HRS)	FIRST HYDROGRAPH POINT =	Sinai3b.out .00 HOURS	TIME INCREMENT =	.10 HOURS	DRAINAGE AR
EA = .01	SQ.MI.				
6.00	DISCHG	.00	.00	.00	.00
.01	.02				
7.00	DISCHG	.02	.03	.04	.05
.10	.11				
8.00	DISCHG	.11	.13	.14	.16
.27	.28				
9.00	DISCHG	.30	.32	.35	.38
.52	.55				
10.00	DISCHG	.57	.60	.64	.69
1.17	1.31				
11.00	DISCHG	1.47	1.62	1.80	1.99
10.75	18.36				
12.00	DISCHG	29.50	35.13	28.83	19.05
5.05	4.48				
13.00	DISCHG	3.98	3.64	3.34	3.10
2.27	2.16				
14.00	DISCHG	2.06	1.98	1.90	1.82
1.44	1.40				
15.00	DISCHG	1.39	1.38	1.37	1.37
1.19	1.19				
16.00	DISCHG	1.18	1.18	1.18	1.18
1.05	1.02				
17.00	DISCHG	1.00	1.00	.99	.99
.99	.95				
18.00	DISCHG	.89	.84	.82	.81
.80	.80				
19.00	DISCHG	.80	.80	.80	.80
.80	.76				
20.00	DISCHG	.69	.65	.62	.61
.60	.60				
21.00	DISCHG	.60	.60	.60	.60
.60	.60				
22.00	DISCHG	.60	.60	.60	.60
.60	.60				
23.00	DISCHG	.61	.61	.61	.61
.60	.56				
24.00	DISCHG	.50	.41	.27	.14
.00					

RUNOFF VOLUME ABOVE BASEFLOW = 4.50 WATERSHED INCHES, 34.54 CFS-HRS, 2.85 ACRE-FEET; BASEFLOW = .00 CFS

OPERATION RESVOR STRUCTURE 4  
 INPUT HYDROGRAPH= 1 OUTPUT HYDROGRAPH= 1  
 SURFACE ELEVATION= 88.00

\*\*\* WARNING-NO PEAK FOUND, MAXIMUM DISCHARGE = .88 CFS.

1

TR20 XEQ 10-23-01 16:56 SINAI SUBSTATION SITE TRIAL 3 10YR-24HR 20  
 JOB 1 PASS 1  
 REV PC 09/83(.2) STORM ROUTING CALCS - DETENTION POND W/ RISER PIPE 30  
 PAGE 2

TIME (HRS)	FIRST HYDROGRAPH POINT =	.00 HOURS	TIME INCREMENT =	.10 HOURS	DRAINAGE AR
EA = .01	SQ.MI.				
9.00	DISCHG	.00	.00	.00	.00
.00	.01				
9.00	ELEV	88.00	88.00	88.00	88.00
88.00	88.09				
10.00	DISCHG	.01	.01	.01	.01
.01	.01				
10.00	ELEV	88.10	88.10	88.11	88.12
88.18	88.20				

Sinai3b.out

11.00	DISCHG	.01	.01	.02	.02	.02	.02	.02	.03
.04	.05								
11.00	ELEV	88.22	88.24	88.27	88.29	88.32	88.35	88.40	88.49
88.63	88.87								
12.00	DISCHG	.06	.07	.07	.07	.07	.07	.07	.07
.08	.08								
12.00	ELEV	89.22	89.61	89.94	90.13	90.25	90.34	90.41	90.46
90.51	90.55								
13.00	DISCHG	.08	.08	.08	.08	.08	.08	.08	.08
.08	.08								
13.00	ELEV	90.59	90.63	90.66	90.69	90.71	90.74	90.76	90.79
90.81	90.83								
14.00	DISCHG	.08	.08	.08	.08	.08	.08	.08	.08
.08	.08								
14.00	ELEV	90.85	90.87	90.88	90.90	90.92	90.93	90.95	90.96
90.97	90.99								
15.00	DISCHG	.08	.13	.17	.21	.25	.29	.32	.35
.38	.41								
15.00	ELEV	91.00	91.01	91.02	91.03	91.04	91.05	91.06	91.07
91.07	91.08								
16.00	DISCHG	.44	.46	.49	.54	.59	.63	.67	.70
.73	.75								
16.00	ELEV	91.09	91.09	91.10	91.11	91.11	91.12	91.12	91.12
91.13	91.13								
17.00	DISCHG	.77	.79	.80	.82	.83	.84	.85	.86
.87	.88								
17.00	ELEV	91.13	91.13	91.13	91.14	91.14	91.14	91.14	91.14
91.14	91.14								
18.00	DISCHG	.88	.88	.87	.87	.86	.86	.85	.85
.84	.84								
18.00	ELEV	91.14	91.14	91.14	91.14	91.14	91.14	91.14	91.14
91.14	91.14								
19.00	DISCHG	.84	.84	.83	.83	.83	.83	.82	.82
.82	.82								
19.00	ELEV	91.14	91.14	91.14	91.14	91.14	91.14	91.14	91.14
91.14	91.14								
20.00	DISCHG	.81	.80	.78	.77	.76	.75	.74	.73
.72	.71								
20.00	ELEV	91.14	91.13	91.13	91.13	91.13	91.13	91.13	91.13
91.13	91.12								
21.00	DISCHG	.70	.69	.69	.68	.68	.67	.66	.66
.66	.65								
21.00	ELEV	91.12	91.12	91.12	91.12	91.12	91.12	91.12	91.12
91.12	91.12								
22.00	DISCHG	.65	.65	.64	.64	.64	.63	.63	.63
.63	.63								
22.00	ELEV	91.12	91.12	91.12	91.12	91.12	91.12	91.12	91.12
91.12	91.12								
23.00	DISCHG	.63	.62	.62	.62	.62	.62	.62	.62
.62	.61								
23.00	ELEV	91.12	91.11	91.11	91.11	91.11	91.11	91.11	91.11
91.11	91.11								
24.00	DISCHG	.60	.59	.57	.54	.50	.48	.46	.45
.43	.41								
24.00	ELEV	91.11	91.11	91.11	91.11	91.10	91.10	91.09	91.09
91.09	91.08								
25.00	DISCHG	.40	.39	.37	.36	.35	.33	.32	.31
.30	.29								
25.00	ELEV	91.08	91.07	91.07	91.07	91.06	91.06	91.06	91.06
91.05	91.05								
26.00	DISCHG	.28	.27	.26	.25	.24	.23	.22	.22
.21	.20								
26.00	ELEV	91.05	91.05	91.04	91.04	91.04	91.04	91.04	91.03
91.03	91.03								
27.00	DISCHG	.19	.19	.18	.17	.17	.16	.16	.15
.15	.14								
27.00	ELEV	91.03	91.03	91.02	91.02	91.02	91.02	91.02	91.02
91.02	91.01								
28.00	DISCHG	.14	.13	.13	.12	.12	.11	.11	.10
.10	.10								
28.00	ELEV	91.01	91.01	91.01	91.01	91.01	91.01	91.01	91.01
91.01	91.00								
29.00	DISCHG	.09	.09	.09	.08	.08	.08	.08	.08
.08	.08								

29.00 ELEV 91.00 91.00 91.00 91.00 91.00 91.00 91.00 91.00  
 91.00 91.00

RUNOFF VOLUME ABOVE BASEFLOW = 1.01 WATERSHED INCHES, 7.77 CFS-HRS, .64 ACRE-FEET; BASEFL  
 OW = .00 CFS  
 1

TR20 XEQ 10-23-01 16:56 SINAI SUBSTATION SITE TRIAL 3 10YR-24HR 20  
 JOB 1 PASS 2  
 REV PC 09/83(.2) STORM ROUTING CALCS - DETENTION POND W/ RISER PIPE 30  
 PAGE 3

EXECUTIVE CONTROL OPERATION ENDCMP  
 RECORD ID 300

+ COMPUTATIONS COMPLETED FOR PASS 1

EXECUTIVE CONTROL OPERATION ENDJOB  
 RECORD ID 310

1

TR20 XEQ 10-23-01 16:56 SINAI SUBSTATION SITE TRIAL 3 10YR-24HR 20  
 JOB 1 SUMMARY  
 REV PC 09/83(.2) STORM ROUTING CALCS - DETENTION POND W/ RISER PIPE 30  
 PAGE 4

SUMMARY TABLE 1 - SELECTED RESULTS OF STANDARD AND EXECUTIVE CONTROL INSTRUCTIONS IN THE ORDER PERFORMED  
 (A STAR(\*) AFTER THE PEAK DISCHARGE TIME AND RATE (CFS) VALUES INDICATES A FLAT TOP HY  
 DROGRAPH

A QUESTION MARK(?) INDICATES A HYDROGRAPH WITH PEAK AS LAST POINT.)

SECTION/ PEAK DISCHARGE STRUCTURE	STANDARD CONTROL	DRAINAGE AREA	RAIN TABLE	ANTEC MOIST	MAIN TIME	PRECIPITATION BEGIN	AMOUNT (IN)	DURATION (HR)	RUNOFF AMOUNT (IN)	ELEVATION (FT)	P T
---	---------------------	------------------	---------------	----------------	--------------	------------------------	----------------	------------------	--------------------------	-------------------	--------

ID	OPERATION RATE	AREA RATE (SQ MI)	#	COND	INCREM (HR)	BEGIN (HR)	AMOUNT (IN)	DURATION (HR)	AMOUNT (IN)	ELEVATION (FT)	T	
ALTERNATE	1	STORM	1									
XSECTION	1	RUNOFF	.01	2	2	.10	.0	7.40	24.00	4.50	---	12
.10	35.13	2952.4										
STRUCTURE	4	RESVOR	.01	2	2	.10	.0	7.40	24.00	1.01	91.14	18
.00?	.88?	73.8										

PEAK FLEV

TR20 XEQ 10-23-01 16:56 SINAI SUBSTATION SITE TRIAL 3 10YR-24HR 20  
 JOB 1 SUMMARY  
 REV PC 09/83(.2) STORM ROUTING CALCS - DETENTION POND W/ RISER PIPE 30  
 PAGE 5

SUMMARY TABLE 3 - DISCHARGE (CFS) AT XSECTIONS AND STRUCTURES FOR ALL STORMS AND ALTERNATES

XSECTION/ STRUCTURE ID	DRAINAGE AREA (SQ MI)	STORM NUMBERS..... 1
------------------------------	-----------------------------	-------------------------

Sinai3b.out

0	STRUCTURE	4	.01	
+	<hr/>			
	ALTERNATE	1		.88
0	XSECTION	1	.01	
+	<hr/>			
	ALTERNATE	1		35.13
1END OF 1 JOBS IN THIS RUN				

*Qp*

Sinai4.out

1

\*\*\*\*\*80-80 LIST OF INPUT DATA FOR TR-20 HYDROLOGY\*\*\*\*\*

JOB TR-20	FULLPRINT	NO PLOTS	
TITLE 001	SINAI SUBSTATION SITE TRIAL 3	100YR-24HR	20
TITLE	STORM ROUTING CALCS - DETENTION POND W/ RISER PIPE		30
3 STRUCT	04		110
8	88.00 0.000 0.000		160
8	89.00 0.060 0.312		165
8	90.00 0.070 0.681		180
8	91.00 0.080 1.107		185
8	91.10 0.490 1.153		190
8	91.20 1.390 1.200		210
8	91.30 2.560 1.247		212
8	91.40 3.930 1.294		213
8	91.50 4.640 1.342		214
8	91.60 4.670 1.391		215
8	91.70 4.710 1.440		216
8	91.80 4.740 1.490		217
8	91.90 4.770 1.541		218
8	92.00 4.810 1.592		220
8	92.10 4.840 1.643		221
8	92.20 4.870 1.695		222
8	93.00 5.130 2.133		224
8	94.00 5.430 2.732		225
8	95.00 5.720 3.388		226
8	96.00 5.990 4.102		227
9 ENDTBL			228
6 RUNOFF 1 001	1 0.0119 75. 0.333	1 1 1 1 1	230
6 RESVOR 2 04 1 1	88.00	1 1 1 1 1	260
ENDATA			270
7 INCREM 6	0.10		280
7 COMPUT 7 001 04	10.60 1.0	2 2 01 01	290
ENDCMP 1			300
ENDJOB 2			310

\*\*\*\*\*END OF 80-80 LIST\*\*\*\*\*

TR20 XEQ 10-23-01 17:10 SINAI SUBSTATION SITE TRIAL 3 100YR-24HR 20  
 JOB 1 PASS 1  
 REV PC 09/83(.2) STORM ROUTING CALCS - DETENTION POND W/ RISER PIPE 30  
 PAGE 1

EXECUTIVE CONTROL OPERATION INCREM  
 RECORD ID 280  
 MAIN TIME INCREMENT = .10 HOURS

EXECUTIVE CONTROL OPERATION COMPUT  
 RECORD ID 290  
 FROM XSECTION 1 TO STRUCTURE 4  
 STARTING TIME = .00 RAIN DEPTH = 10.60 RAIN DURATION= 1.00 RAIN TABLE NO.= 2 ANT.  
 MOIST. COND= 2  
 ALTERNATE NO.= 1 STORM NO.= 1 MAIN TIME INCREMENT = .10 HOURS

OPERATION RUNOFF CROSS SECTION 1  
 OUTPUT HYDROGRAPH= 1  
 AREA= .01 SQ MI INPUT RUNOFF CURVE= 75. TIME OF CONCENTRATION= .33 HOURS  
 INTERNAL HYDROGRAPH TIME INCREMENT= .0444 HOURS  
 \*\*\*ELEVATION OUTPUT OPTION REQUESTED BUT NO ELEVATIONS GIVEN\*\*\*

PEAK TIME(HRS)	PEAK DISCHARGE(CFS)	PEAK ELEVATION(FEET)
12.09	57.15	(RUNOFF)



TIME(HRS)	FIRST HYDROGRAPH POINT =	Sinai4.out .00 HOURS	TIME INCREMENT =	.10 HOURS	DRAINAGE AR
EA = .01	SQ.MI.				
5.00	DISCHG	.00	.00	.01	.02 .03 .04 .05 .06
.08	.09				
6.00	DISCHG	.10	.12	.14	.16 .18 .20 .22 .24
.25	.27				
7.00	DISCHG	.28	.30	.32	.33 .34 .36 .37 .39
.40	.41				
8.00	DISCHG	.43	.45	.49	.53 .59 .65 .69 .73
.76	.78				
9.00	DISCHG	.80	.84	.89	.95 1.00 1.03 1.07 1.14
1.21	1.26				
10.00	DISCHG	1.30	1.35	1.42	1.50 1.62 1.78 1.94 2.17
2.40	2.66				
11.00	DISCHG	2.94	3.22	3.53	3.84 4.24 4.72 6.59 11.96
19.00	31.40				
12.00	DISCHG	48.95	57.11	46.32	30.38 20.24 14.37 10.99 9.04
7.84	6.93				
13.00	DISCHG	6.16	5.61	5.16	4.78 4.48 4.20 3.96 3.71
3.48	3.31				
14.00	DISCHG	3.16	3.03	2.90	2.79 2.67 2.55 2.44 2.31
2.20	2.14				
15.00	DISCHG	2.12	2.10	2.10	2.09 2.03 1.94 1.86 1.83
1.81	1.81				
16.00	DISCHG	1.80	1.80	1.80	1.80 1.80 1.80 1.78 1.69
1.60	1.55				
17.00	DISCHG	1.53	1.52	1.51	1.51 1.51 1.51 1.51 1.51
1.50	1.44				
18.00	DISCHG	1.35	1.27	1.24	1.22 1.22 1.21 1.21 1.21
1.21	1.21				
19.00	DISCHG	1.21	1.21	1.21	1.21 1.21 1.21 1.21 1.21
1.21	1.15				
20.00	DISCHG	1.05	.98	.94	.92 .92 .91 .91 .91
.91	.91				
21.00	DISCHG	.91	.91	.91	.91 .91 .91 .91 .91
.91	.91				
22.00	DISCHG	.91	.91	.91	.91 .91 .91 .91 .91
.91	.91				
23.00	DISCHG	.91	.91	.91	.91 .91 .91 .91 .91
.91	.85				
24.00	DISCHG	.75	.62	.41	.21 .10 .05 .02 .01
.00					

RUNOFF VOLUME ABOVE BASEFLOW = 7.43 WATERSHED INCHES, 57.04 CFS-HRS, 4.71 ACRE-FEET; BASEFLOW = .00 CFS

OPERATION RESVOR STRUCTURE 4  
 INPUT HYDROGRAPH= 1 OUTPUT HYDROGRAPH= 1  
 SURFACE ELEVATION= 88.00

PEAK TIME(HRS) 13.30 PEAK DISCHARGE(CFS) 4.72 PEAK ELEVATION(FEET) 91.74  
 \* FIRST POINT OF FLA

+  
 T PEAK  
 1

TR20 XEQ 10-23-01 17:10 SINAI SUBSTATION SITE TRIAL 3 100YR-24HR 20  
 JOB 1 PASS 1  
 REV PC 09/83(.2) STORM ROUTING CALCS - DETENTION POND W/ RISER PIPE 30  
 PAGE 2

TIME(HRS)	FIRST HYDROGRAPH POINT =	.00 HOURS	TIME INCREMENT =	.10 HOURS	DRAINAGE AR
EA = .01	SQ.MI.				
8.00	DISCHG	.00	.01	.01	.01 .01 .01 .01 .01
.01	.01				
8.00	ELEV	88.00	88.09	88.09	88.10 88.11 88.12 88.13 88.14
88.15	88.16				
9.00	DISCHG	.01	.01	.01	.01 .01 .01 .01 .02
.02	.02				

Sinai4.out

9.00	ELEV	88.17	88.18	88.19	88.20	88.21	88.23	88.24	88.26
88.27	88.29								
10.00	DISCHG	.02	.02	.02	.02	.02	.02	.03	.03
.03	.03								
10.00	ELEV	88.31	88.32	88.34	88.36	88.38	88.41	88.43	88.46
88.49	88.53								
11.00	DISCHG	.03	.04	.04	.04	.05	.05	.05	.06
.06	.07								
11.00	ELEV	88.56	88.61	88.65	88.70	88.76	88.82	88.91	89.05
89.27	89.62								
12.00	DISCHG	.07	.08	.74	3.44	4.64	4.66	4.68	4.70
4.71	4.71								
12.00	ELEV	90.14	90.70	91.13	91.36	91.50	91.58	91.63	91.67
91.70	91.72								
13.00	DISCHG	4.72	4.72	4.72	4.72	4.72	4.72	4.72	4.72
4.71	4.71								
13.00	ELEV	91.73	91.74	91.74	91.74	91.74	91.73	91.73	91.72
91.71	91.70								
14.00	DISCHG	4.70	4.70	4.69	4.69	4.68	4.67	4.67	4.66
4.65	4.65								
14.00	ELEV	91.68	91.67	91.65	91.64	91.62	91.60	91.58	91.56
91.54	91.52								
15.00	DISCHG	4.64	4.51	4.37	4.24	4.11	3.98	3.80	3.59
3.40	3.23								
15.00	ELEV	91.50	91.48	91.46	91.44	91.43	91.41	91.39	91.38
91.36	91.35								
16.00	DISCHG	3.08	2.94	2.82	2.71	2.61	2.53	2.46	2.39
2.31	2.24								
16.00	ELEV	91.34	91.33	91.32	91.31	91.30	91.30	91.29	91.29
91.28	91.27								
17.00	DISCHG	2.18	2.11	2.06	2.01	1.96	1.92	1.88	1.84
1.81	1.78								
17.00	ELEV	91.27	91.26	91.26	91.25	91.25	91.25	91.24	91.24
91.24	91.23								
18.00	DISCHG	1.74	1.69	1.65	1.61	1.58	1.54	1.51	1.48
1.46	1.43								
18.00	ELEV	91.23	91.23	91.22	91.22	91.22	91.21	91.21	91.21
91.21	91.20								
19.00	DISCHG	1.41	1.39	1.38	1.37	1.36	1.35	1.34	1.33
1.32	1.30								
19.00	ELEV	91.20	91.20	91.20	91.20	91.20	91.20	91.19	91.19
91.19	91.19								
20.00	DISCHG	1.29	1.26	1.24	1.22	1.19	1.17	1.15	1.14
1.12	1.10								
20.00	ELEV	91.19	91.19	91.18	91.18	91.18	91.18	91.17	91.17
91.17	91.17								
21.00	DISCHG	1.09	1.08	1.07	1.05	1.04	1.03	1.02	1.02
1.01	1.00								
21.00	ELEV	91.17	91.17	91.16	91.16	91.16	91.16	91.16	91.16
91.16	91.16								
22.00	DISCHG	1.00	.99	.98	.98	.97	.97	.96	.96
.96	.95								
22.00	ELEV	91.16	91.16	91.15	91.15	91.15	91.15	91.15	91.15
91.15	91.15								
23.00	DISCHG	.95	.95	.95	.94	.94	.94	.94	.94
.93	.93								
23.00	ELEV	91.15	91.15	91.15	91.15	91.15	91.15	91.15	91.15
91.15	91.15								
24.00	DISCHG	.91	.89	.86	.81	.76	.71	.66	.61
.56	.52								
24.00	ELEV	91.15	91.14	91.14	91.14	91.13	91.12	91.12	91.11
91.11	91.10								
25.00	DISCHG	.49	.47	.45	.44	.42	.41	.39	.38
.36	.35								
25.00	ELEV	91.10	91.10	91.09	91.09	91.08	91.08	91.08	91.07
91.07	91.07								
26.00	DISCHG	.34	.33	.32	.30	.29	.28	.27	.26
.25	.25								
26.00	ELEV	91.06	91.06	91.06	91.05	91.05	91.05	91.05	91.04
91.04	91.04								
27.00	DISCHG	.24	.23	.22	.21	.20	.20	.19	.18
.18	.17								
27.00	ELEV	91.04	91.04	91.03	91.03	91.03	91.03	91.03	91.03
91.02	91.02								

Sinai4.out									
28.00	DISCHG	.16	.16	.15	.15	.14	.14	.13	.13
.12	.12								
28.00	ELEV	91.02	91.02	91.02	91.02	91.02	91.01	91.01	91.01
91.01	91.01								
29.00	DISCHG	.11	.11	.11	.10	.10	.10	.09	.09
.09	.03								
29.00	ELEV	91.01	91.01	91.01	91.01	91.00	91.00	91.00	91.00
91.00	91.00								

RUNOFF VOLUME ABOVE BASEFLOW = 3.94 WATERSHED INCHES, 30.23 CFS-HRS, 2.50 ACRE-FEET; BASEFLOW = .00 CFS

TR20 XEQ 10-23-01 17:10 SINAI SUBSTATION SITE TRIAL 3 100YR-24HR 20  
 JOB 1 PASS 2  
 REV PC 09/83(.2) STORM ROUTING CALCS - DETENTION POND W/ RISER PIPE 30  
 PAGE 3

EXECUTIVE CONTROL OPERATION ENDCMP  
 RECORD ID 300  
 + COMPUTATIONS COMPLETED FOR PASS 1

EXECUTIVE CONTROL OPERATION ENDJOB  
 RECORD ID 310  
 1

TR20 XEQ 10-23-01 17:10 SINAI SUBSTATION SITE TRIAL 3 100YR-24HR 20  
 JOB 1 SUMMARY  
 REV PC 09/83(.2) STORM ROUTING CALCS - DETENTION POND W/ RISER PIPE 30  
 PAGE 4

SUMMARY TABLE 1 - SELECTED RESULTS OF STANDARD AND EXECUTIVE CONTROL INSTRUCTIONS IN THE ORDER PERFORMED (A STAR (\*) AFTER THE PEAK DISCHARGE TIME AND RATE (CFS) VALUES INDICATES A FLAT TOP HYDROGRAPH  
 A QUESTION MARK (?) INDICATES A HYDROGRAPH WITH PEAK AS LAST POINT.)

SECTION/ PEAK DISCHARGE STRUCTURE	STANDARD CONTROL	DRAINAGE AREA (SQ MI)	RAIN TABLE #	ANTEC MOIST COND	MAIN TIME INCREM (HR)	PRECIPITATION BEGIN (HR)	AMOUNT (IN)	DURATION (HR)	RUNOFF AMOUNT (IN)	ELEVATION (FT)	P T (
---	---------------------	-----------------------------	--------------------	------------------------	--------------------------------	--------------------------------	----------------	------------------	--------------------------	-------------------	-------------

ALTERNATE	1	STORM	1									
XSECTION	1	RUNOFF	.01	2	2	.10	.0	10.60	24.00	7.43	---	12
.09	57.15	4802.9										
STRUCTURE	4	RESVOR	.01	2	2	.10	.0	10.60	24.00	3.94	91.74	13
.30*	4.72*	396.8										

PEAK ELEV.

TR20 XEQ 10-23-01 17:10 SINAI SUBSTATION SITE TRIAL 3 100YR-24HR 20  
 JOB 1 SUMMARY  
 REV PC 09/83(.2) STORM ROUTING CALCS - DETENTION POND W/ RISER PIPE 30  
 PAGE 5

SUMMARY TABLE 3 - DISCHARGE (CFS) AT XSECTIONS AND STRUCTURES FOR ALL STORMS AND ALTERNATES

XSECTION/ STRUCTURE ID	DRAINAGE AREA (SQ MI)	STORM NUMBERS..... 1
0 STRUCTURE 4	.01	
+		
ALTERNATE 1		4.72
0 XSECTION 1	.01	
+		
ALTERNATE 1		57.15
1END OF 1 JOBS IN THIS RUN		

*Op*

Sinai1.out

1

\*\*\*\*\*80-80 LIST OF INPUT DATA FOR TR-20 HYDROLOGY\*\*\*\*\*

```

JOB TR-20          ECON      FULLPRINT      SUMMARY  NOPLOTS    100
TITLE 001         SINAI SUBSTATION SITE      10YR-24HR    200
TITLE 001         STORM DRAINAGE CALCS - DET. POND PRE-CONDITION 300
6 RUNOFF 1 001    1 0.0119    39.      0.200      1 1 1 1 400
  ENDDATA
7 INCREM 6              0.10
7 COMPUT 7 001    001      7.40      1.0      2 2 01 01 700
  ENDCMP 1
  ENDJOB 2

```

0\*\*\*\*\*END OF 80-80 LIST\*\*\*\*\*

MAIN - UNEXPECTED RECORD FOUND(IGNORED) >>>
<<<

MAIN - UNEXPECTED RECORD FOUND(IGNORED) >>>
<<<

1

```

TR20 XEQ 11-02-01 07:14          SINAI SUBSTATION SITE      10YR-24HR    200
      JOB 1 PASS 1
      REV PC 09/83(.2)          STORM DRAINAGE CALCS - DET. POND PRE-CONDITION 300
      PAGE 1

```

EXECUTIVE CONTROL OPERATION INCREM
RECORD ID 600

+ MAIN TIME INCREMENT = .10 HOURS

EXECUTIVE CONTROL OPERATION COMPUT
RECORD ID 700

```

+ FROM XSECTION 1
+ TO XSECTION 1
STARTING TIME = .00 RAIN DEPTH = 7.40 RAIN DURATION= 1.00 RAIN TABLE NO.= 2 ANT.
MOIST. COND= 2
ALTERNATE NO.= 1 STORM NO.= 1 MAIN TIME INCREMENT = .10 HOURS

```

```

OPERATION RUNOFF CROSS SECTION 1
OUTPUT HYDROGRAPH= 1
AREA= .01 SQ MI INPUT RUNOFF CURVE= 39. TIME OF CONCENTRATION= .20 HOURS
INTERNAL HYDROGRAPH TIME INCREMENT= .0267 HOURS

```

TIME(HRS)	PEAK TIME(HRS)	PEAK DISCHARGE(CFS)	PEAK ELEVATION(FEET)	(RUNOFF)	DRAINAGE AR
EA = .01 SQ.MI.	12.09	6.16			
11.00 DISCHG	.00	.00	.00	.00	.00
.01 .90					
12.00 DISCHG	4.48	6.14	3.58	2.52	1.90
1.30 1.18					
13.00 DISCHG	1.10	1.04	.96	.93	.87
.72 .69					
14.00 DISCHG	.67	.65	.62	.61	.58
.49 .49					
15.00 DISCHG	.49	.49	.50	.49	.46
.44 .44					
16.00 DISCHG	.44	.44	.44	.44	.45
.38 .38					

Sinai1.out									
17.00	DISCHG	.38	.38	.38	.38	.38	.39	.39	.39
.38	.35								
18.00	DISCHG	.32	.32	.32	.32	.32	.32	.32	.32
.32	.32								
19.00	DISCHG	.32	.32	.32	.32	.32	.32	.32	.33
.32	.28								
20.00	DISCHG	.26	.25	.25	.25	.25	.25	.25	.25
.25	.25								
21.00	DISCHG	.25	.25	.25	.25	.25	.25	.25	.25
.25	.25								
22.00	DISCHG	.25	.25	.25	.25	.25	.26	.26	.26
.26	.26								
23.00	DISCHG	.26	.26	.26	.26	.26	.26	.26	.26
.25	.21								
24.00	DISCHG	.19	.13	.04	.01	.00			

RUNOFF VOLUME ABOVE BASEFLOW = .92 WATERSHED INCHES, 7.04 CFS-HRS, .58 ACRE-FEET; BASEFLOW = .00 CFS

EXECUTIVE CONTROL OPERATION ENDCMP  
RECORD ID 800

COMPUTATIONS COMPLETED FOR PASS 1

EXECUTIVE CONTROL OPERATION ENDJOB  
RECORD ID 900

TR20 XEQ 11-02-01 07:14 SINAI SUBSTATION SITE 10YR-24HR 200  
JOB 1 SUMMARY  
REV PC 09/83(.2) STORM DRAINAGE CALCS - DET. POND PRE-CONDITION 300  
PAGE 2

SUMMARY TABLE 1 - SELECTED RESULTS OF STANDARD AND EXECUTIVE CONTROL INSTRUCTIONS IN THE ORDER PERFORMED (A STAR(\*) AFTER THE PEAK DISCHARGE TIME AND RATE (CFS) VALUES INDICATES A FLAT TOP HYDROGRAPH

A QUESTION MARK(?) INDICATES A HYDROGRAPH WITH PEAK AS LAST POINT.)

SECTION/ PEAK DISCHARGE STRUCTURE	STANDARD CONTROL	DRAINAGE AREA	RAIN TABLE	ANTEC MOIST	MAIN TIME	PRECIPITATION			RUNOFF	ELEVATION	P	
ID	OPERATION RATE	AREA RATE	#	COND	INCREM	BEGIN	AMOUNT	DURATION	AMOUNT	ELEVATION	T	
IME	(CFS)	(SQ MI) (CSM)			(HR)	(HR)	(IN)	(HR)	(IN)	(FT)	(	
ALTERNATE	1	STORM	1									
XSECTION	1	RUNOFF	.01	2	2	.10	.0	7.40	24.00	.92	---	12
.09	6.16	518.0										

TR20 XEQ 11-02-01 07:14 SINAI SUBSTATION SITE 10YR-24HR 200  
JOB 1 SUMMARY  
REV PC 09/83(.2) STORM DRAINAGE CALCS - DET. POND PRE-CONDITION 300  
PAGE 3

SUMMARY TABLE 3 - DISCHARGE (CFS) AT XSECTIONS AND STRUCTURES FOR ALL STORMS AND ALTERNATES

XSECTION/ STRUCTURE	DRAINAGE AREA	STORM NUMBERS.....
------------------------	------------------	--------------------

ID (SQ MI)  
0 XSECTION 1 .01  
+  
ALTERNATE 1  
1END OF 1 JOBS IN THIS RUN

1 Sinai1.out

6.16 *CPS*



Gen

~~JEN~~  
JHN

G. Edison "Ed" Holland, Jr.  
Vice President - Power Generation, Transmission  
and Corporate Counsel

the southern electric system

February 22, 1996

CERTIFIED MAIL

Mr. Rick Bradburn  
Florida Department of Environmental Protection  
160 Governmental Center  
Pensacola, Florida 32501-5794

Dear Mr. Bradburn:

FL 000 2275 CRIST ELECTRIC GENERATING PLANT  
FL 000 2267 SMITH ELECTRIC GENERATING PLANT  
FL 000 2283 SCHOLZ ELECTRIC GENERATING PLANT

This letter is written to inform the Department of a change in the authorized agent for Gulf Power Company. M. L. Gilchrist, who is currently Gulf Power Company's authorized agent, will retire at the end of this month. The new authorized agent, effective March 1, 1996, will be Jim Vick.

If any questions arise concerning this information, please call me or Joe Neese at (904) 444-6429.

Sincerely,



cc: J. A. Babbitt	P. Parker
J. M. Dominey	K. Peacock
M. L. Gilchrist	J. L. Sherouse
S. H. Houston, Jr.	R. A. Terry
J. W. Martin	J. O. Vick
J. H. Neese	

"Our business is customer satisfaction"

*WMM*  
*RAT*  
*TJ*  
*RMM (lost)*

**GULF POWER COMPANY**  
**ENVIRONMENTAL AFFAIRS AGENCY ACCT.**  
ONE ENERGY PLACE  
BIN 0328  
PENSACOLA, FL 32520-0328

1746

DATE Nov. 9, 2001 32-1/1110 TX 0

PAY TO THE ORDER OF Florida Dept. of Environmental Protection \$ 250.<sup>00</sup>/<sub>100</sub>

Two Hundred Fifty & no/100 ----- DOLLARS

**Bank of America**  
Customer Connection


FOR Sinai Sub - stormwater permit

Golconda Cottman

⑆001746⑆ ⑆11000012⑆ 375 152 7884⑆

GUARDIAN SAFETY





Stormwater Pond Site Map