

BEFORE THE
FLORIDA PUBLIC SERVICE COMMISSION

DOCKET NO. 20210034-EI
IN RE: PETITION FOR RATE INCREASE
BY TAMPA ELECTRIC COMPANY

DIRECT TESTIMONY AND EXHIBIT
OF
CHARLES R. BEITEL
ON BEHALF OF TAMPA ELECTRIC COMPANY

BEFORE THE FLORIDA PUBLIC SERVICE COMMISSION

PREPARED DIRECT TESTIMONY

OF

CHARLES R. BEITEL

ON BEHALF OF TAMPA ELECTRIC COMPANY

Q. Please state your name, address, occupation, and employer.

A. My name is Charles R. Beitel. My business address is 55 East Monroe Street, Chicago, IL 60603-5780. I am Senior Vice President & Project Director for Sargent & Lundy.

Q. Please provide a brief outline of your educational background and business experience.

A. I have a Bachelor of Science degree in mechanical engineering from the University of Missouri, and I am a licensed professional engineer. In the course of my twenty-five-year career in the power industry I have served as a mechanical engineer, on-site field engineer during construction, project manager, director, and vice president for a large variety of projects in the electric power industry. This includes new construction of generating facilities (coal and gas fired), large scale environmental air quality control systems, plant services betterment and

1 upgrades, multiple plant demolition studies and
2 evaluations, and a large amount of project cost estimating
3 services for the above array of projects.

4
5 **Q.** What are the purposes of your direct testimony in this
6 proceeding?

7
8 **A.** The purposes of my prepared direct testimony are to (1)
9 discuss the dismantlement studies Sargent & Lundy conducted
10 for Tampa Electric and submitted to the Commission on
11 December 30, 2020 in Docket No. 20200264-EI and (2) support
12 the reasonableness of our dismantlement study costs
13 included in the company's rate request in this docket.

14
15 **Q.** Have you prepared an exhibit to support your direct
16 testimony?

17
18 **A.** Yes. Exhibit No. CRB-1 was prepared under my direction and
19 supervision. My exhibit consists of two documents:

20
21 Document No. 1 Big Bend Power Station Unit 1 and
22 2 Dismantling Study
23 Document No. 2 Big Bend Power Station Unit 3
24 Dismantling Study
25

1 **Q.** What dismantlement studies did Sargent & Lundy perform for
2 Tampa Electric?

3
4 **A.** We performed two dismantlement studies, one for Big Bend
5 Power Station ("Big Bend") Units 1 and 2 and one for Big
6 Bend Unit 3.

7
8 **Q.** What was the reason for performing two dismantlement
9 studies as opposed to a single study addressing all three
10 units?

11
12 **A.** At the time Tampa Electric engaged Sargent & Lundy to
13 perform a dismantlement study for Big Bend Units 1 and 2,
14 the company had not finalized its plans with respect to Big
15 Bend Unit 3. After the dismantlement study for Big Bend
16 Units 1 and 2 was nearly completed, Tampa Electric engaged
17 Sargent & Lundy to perform the dismantlement study for Big
18 Bend Unit 3.

19
20 **Q.** What were the purposes of the two dismantlement studies you
21 performed?

22
23 **A.** The purposes of both studies were the same. We were asked
24 to document the scope, strategy, costs, cash flows, and
25 provide recommendations for execution of selective

1 dismantlement of Big Bend Units 1 and 2 in the first study
2 and Big Bend Unit 3 in the second study.

3
4 **Q.** What are the differences in the preparation of the Big Bend
5 Unit 3 dismantlement study, compared to the Big Bend Units
6 1 and 2 study?

7
8 **A.** Apart from fundamental differences in the installed systems
9 and equipment of the operating units, the primary
10 difference between the two studies is that in the Units 1
11 and 2 study, the Unit 1 turbine equipment and auxiliaries
12 are to remain in service since this turbine generator is
13 being heavily modified and "repowered" with natural gas
14 fired combined cycle technology as part of the Big Bend
15 Modernization project.

16
17 **Q.** How do the two studies differ from a standard dismantlement
18 study?

19
20 **A.** A "standard" dismantlement study of this type would involve
21 wholesale demolition of an entire facility. Dismantlement
22 of Big Bend Units 1 and 2 as well as Unit 3 are a selective
23 demolition of certain portions of the facility, given that
24 some equipment and operating units at this site must
25 continue uninterrupted, safe operation during and after the

1 demolition activities have taken place. Selective
2 demolition requires a site-specific understanding of the
3 overall design of the facility structure and process
4 systems and an ability to detangle the physical
5 infrastructure that must remain in operation from the
6 portions that are being demolished, from a structural,
7 mechanical, electrical, and controls perspective. An
8 example of this is the coal tripper conveyor structure and
9 systems which will only serve Unit 4 following
10 dismantlement yet are structurally integral to Units 1, 2,
11 and 3. The costs for selective demolition are substantially
12 higher than for wholesale demolition for the reasons I
13 previously mentioned, and given that new structural
14 reinforcements, electrical and control feeds, and process
15 systems are required in certain cases to provide for the
16 aforementioned safe uninterrupted operation of the balance
17 the facility.

18
19 **Q.** Did Sargent & Lundy utilize the same processes, apply the
20 same standards and methods, and utilize the same types of
21 data, key assumptions, and cost estimates for both the Big
22 Bend 1 and 2 dismantlement study and the Big Bend Unit 3
23 dismantlement study?

24
25 **A.** Yes, we did.

1 **Q.** What process did you follow in preparing the Big Bend Units
2 1 and 2 dismantlement study and the Big Bend Unit 3
3 dismantlement study?
4

5 **A.** Sargent & Lundy has developed our process of demolition
6 scoping and estimating over the course of over two hundred
7 evaluations and estimates performed for power industry
8 clients. We utilize staff that are well versed in power
9 plant design and construction to develop a site-specific
10 plan for the required selective dismantlement. From this
11 plan, our teams use our firm's knowledge of the quantities
12 of materials (concrete, steel, pipe, electrical, etc.)
13 present to prepare detailed "bottoms up" demolition
14 estimates of the work required, factoring in benchmarked
15 labor rates, specialized knowledge to remove equipment
16 containing certain materials, scrap value, and the addition
17 of any new materials, systems, and equipment that must be
18 installed to facilitate uninterrupted, safe operation of
19 the balance of the facility. Our plans and estimates are
20 checked in a "top down" manner against past similar work
21 performed by our firm and our clients, scaled appropriately
22 for unit size.
23

24 **Q.** Are there industry-standard methods used when preparing
25 such studies?

1 **A.** Yes. Various organizations and industry committees provide
2 guidance, recommendations, position papers, and lessons
3 learned for the demolition planning and estimating methods
4 that are utilized in a study of this nature. Sargent & Lundy
5 has had continuous participation in national and
6 international technical groups and advisory committees of
7 this type, including the Construction Management
8 Association of America ("CMAA"), Electric Utility and
9 Environmental Conference ("EUEC"), American Nuclear Society
10 ("ANS"), International Atomic Energy Association ("IAEA"),
11 Health Physics Society ("HPS"), Organisation for Economic
12 Cooperation Nuclear Energy Agency ("NEA"), and we include
13 such input into our approach and procedures for performing
14 such work.

15
16 **Q.** Did you apply these industry standards when preparing Tampa
17 Electric's Big Bend Units 1 and 2 dismantlement study and
18 the Big Bend Unit 3 dismantlement study?

19
20 **A.** Yes, we relied on these standards.

21
22 **Q.** Did Tampa Electric provide data to you for use in the Big
23 Bend Units 1 and 2 dismantlement study and the Big Bend
24 Unit 3 dismantlement study?

1 **A.** Yes.

2
3 **Q.** What data did the company provide?

4
5 **A.** Tampa Electric provided guidance regarding the specific
6 areas of the facility that were to remain in safe,
7 uninterrupted operation during and after dismantlement, as
8 well as input regarding scope and costs for asbestos
9 removal, disposal of consumables, and owner's costs that
10 were factored into our estimates. Tampa Electric
11 stakeholders also collaborated with Sargent & Lundy staff
12 regarding the selection of an appropriate overall
13 contingency based on the level of certainty in the study
14 efforts.

15
16 **Q.** Please describe the key assumptions of the Big Bend Units
17 1 and 2 dismantlement study and the Big Bend Unit 3
18 dismantlement study.

19
20 **A.** Assumptions regarding scrap value, forecasted escalation,
21 and certain labor cost parameters were made as documented.
22 See Section L of each report, included as Document Nos. 1
23 and 2 of my exhibit, for a concise list of technical
24 assumptions.

1 **Q.** How were costs estimated for purposes of the Big Bend Units
2 1 and 2 dismantlement study and the Big Bend Unit 3
3 dismantlement study?

4
5 **A.** As stated earlier, based on the site-specific demolition
6 scope, our teams use our firm's knowledge of the quantities
7 of materials (concrete, steel, pipe, electrical, etc.)
8 present to prepare detailed "bottoms up" demolition
9 estimates of the work required, factoring in benchmarked
10 labor rates, scrap value, and the addition of any new
11 materials, systems, and equipment that must be installed to
12 facilitate uninterrupted and safe operation of the balance
13 of the facility. Our plans and estimates are checked in a
14 "top down" manner against past similar work performed by
15 our firm and our clients, scaled appropriately for unit
16 size.

17
18 **Q.** What are the results of the Big Bend Units 1 and 2
19 dismantlement study?

20
21 **A.** The selective dismantlement costs for Units 1 and 2 are
22 based on the April 2020 and November 2021 retirement dates
23 for Units 1 and 2, respectively. The total cost estimate is
24 \$81,816,224, including engineering, demolition, and pre-
25 and post-demolition costs.

1 The engineering phase includes developing the scope of
2 work, performing detailed engineering for modifications,
3 developing the specifications, bidding the contracts, and
4 evaluating proposals. Pre-demolition activities required to
5 prepare for demolition include removing consumables,
6 remediation of material containing asbestos, adding
7 bracing, and relocating utilities. Demolition is the
8 physical removal of the identified equipment and structures
9 while allowing the rest of the plant to continue safe,
10 reliable operations. Post-demolition activities are actions
11 necessary to leave the site in a safe, usable site with
12 proper drainage and access.

13
14 The selective dismantlement costs by unit follow, and the
15 study is provided as Document No. 1 of my exhibit.

16 (000)

17 Unit 1 \$35,075

18 Unit 2 \$46,740

19
20 **Q.** What are the results of the Big Bend Unit 3 dismantlement
21 study?

22
23 **A.** The selective dismantlement costs for Unit 3 are based on
24 its April 2023 retirement date. The total cost estimate is
25 \$50,568,243, including engineering, demolition, and pre-

1 and post-demolition costs. These phases are as previously
2 defined for the Units 1 and 2 dismantlement study. The study
3 is provided as Document No. 2 of my exhibit.
4

5 **Q.** Is it your conclusion that the Big Bend Units 1 and 2
6 dismantlement study results and those of the Big Bend Unit
7 3 dismantlement study are reasonable estimates?
8

9 **A.** Yes, the Big Bend Units 1 and 2 dismantlement study and the
10 Big Bend Unit 3 dismantlement study results and cost
11 estimates are reasonable and are useful for planning
12 purposes. It is appropriate for the company to rely on these
13 estimates for inclusion in their dismantlement reserve
14 needs. The subject estimates have been benchmarked against
15 real world projects of similar scope, including past
16 similar work performed at Tampa Electric's former Gannon
17 Station which was converted to the Bayside Station.
18

19 **Q.** Please summarize your direct testimony.
20

21 **A.** My direct testimony describes Sargent & Lundy's work in
22 performing two dismantlement studies for Tampa Electric,
23 one addressing the selective dismantlement of Big Bend
24 Units 1 and 2 and one addressing the selective dismantlement
25 of Big Bend Unit 3. I describe Sargent & Lundy's

1 qualifications and my experience performing dismantlement
2 studies. I also explain the processes, industry standards
3 and methods, data analyses, key assumptions, and cost
4 estimates Sargent & Lundy utilized for both dismantlement
5 studies. I conclude that the study results and cost
6 estimates for both studies are reasonable, are useful for
7 planning purposes, and are appropriate for Tampa Electric
8 to rely on in determining their dismantlement reserve
9 needs.

10
11 **Q.** Does this conclude your direct testimony?
12

13 **A.** Yes.
14
15
16
17
18
19
20
21
22
23
24
25

DOCKET NO. 20210034-EI
WITNESS: BEITEL

EXHIBIT

OF

CHARLES R. BEITEL

ON BEHALF OF TAMPA ELECTRIC COMPANY

Table of Contents

DOCUMENT NO.	TITLE	PAGE
1	Big Bend Power Station Unit 1 and 2 Dismantling Study	15
2	Big Bend Power Station Unit 3 Dismantling Study	115



BIG BEND POWER STATION
Tampa Electric Company

UNIT 1 AND 2 DISMANTLING STUDY

BASIS OF COST ESTIMATE & SCOPE OF WORK



REV. 1, DECEMBER 28, 2020
FOR USE

Project No.: A09476.301

Prepared by:



55 East Monroe Street • Chicago, IL 60603 USA • 312-269-2000

Tampa Electric Company
 Big Bend Station Units 1-2
 Dismantling Study



Project No.: A09476.301
 Date: December 28, 2020
 Rev. 1, Use

Table of Contents

Executive Summary.....	3
A. General Information	7
B. Estimate Approach.....	14
C. Estimate Scope of Work	15
D. Pricing and Quantities	21
E. Labor Wage Rates	22
F. Construction Equipment.....	22
G. Construction Direct/Indirect Costs and General Conditions	23
H. Scrap Value	24
I. Contingency	24
J. Escalation	24
K. Costs Excluded	24
L. Scope Assumptions/Clarifications/Exclusions	25
M. Cost Comparison to 2018 Estimate	27
N. Schedule	28

Attachments:

1. Cost Estimate Summary, Cash Flow and Individual Estimates
2. Boiler Building Demolition and Bracing Schematics
3. Dismantling Sequence Schedule
4. Repowering List
5. Pullman Chimney Demolition Budgetary Quote
6. Application of Gannon Lessons Learned to Big Bend Dismantling

Tampa Electric Company
Big Bend Station Units 1-2
Dismantling Study



Project No.: A09476.301
Date: December 28, 2020
Rev. 1, Use

EXECUTIVE SUMMARY

This report documents the scope and cost associated with partial dismantlement of Big Bend Units 1 and 2. An extensive study was completed during 2018 and included Units 1 through 3. This 2020 version is an update to reflect 1) changes in the retirement schedule, 2) eliminate Unit 3 from the scope, 3) address recent 2020 TEC comments, 4) incorporating additional lessons learned from Gannon dismantling and 5) new coal yard partial dismantlement. In addition, modifications to the cost estimate categorizes the costs into the project phases. Cash flows have also been broken down into quarters rather than a monthly basis.

Detail of the five significant changes are:

- 1 - The schedule used in developing the cash flows utilizes an April 2020 retirement date for Unit 1 and a fourth quarter 2021 retirement for Unit 2. The Unit 1 retirement date has been moved up 15 months from the 2018 study and Unit 2 has been pushed back approximately four months.
- 2 - The 2018 Dismantlement Study included Unit 3, which has been eliminated from the current dismantlement plan. As such, the slag dewatering facility that serves Units 1 through 3 has been removed from the demolition estimate.
- 3 - The dismantlement effort has changed hands internally with TEC and that has led to new comments to the 2018 Dismantlement Study as well as better maintenance areas for Unit 1 turbine deck. Turbine deck openings where the turbine-generator and other areas can be filled in with beams and grating, which will reclaim approximately 4,300 square feet of usable maintenance space during major U1 turbine outages.
- 4 - Gannon lessons learned were passed on to the project during the 2018 Dismantlement Study. Some of the lessons were incorporated into the cost estimates, but the lessons were not explicitly discussed the report. Attachment 6 has been added to identify whether each of Gannon's lesson learned has been account for in the estimate, will require consideration during detailed engineering, or should be required as contractor scope.
- 5 - Coal yard partial dismantlement was a late addition to the 2020 estimate and added significant additional costs. The assumptions with this area will be reviewed during a TEC internal meeting on June 29.

New estimating categories are established to segregate each unit costs into the suggested project four phases: engineering, pre-demolition, demolition, and post-demolition. The previous cost estimate only segregated each unit into either demolition or addition activities.

The electrical work to maintain operability of remaining equipment was re-evaluated by staff knowledgeable with BB Modernization electrical scope. In 2018 the modernization project was in progress for determining the scope of modifications to the electrical systems of Unit 1 associated with the repowering of the steam turbine. The Modernization project is now advanced to a point where assumptions no longer need to be made for estimating the Unit 2 costs and remaining Unit 1 cost related to repowering essential equipment not addressed by U1 Modernization. This thorough effort to establish electrical cost has been reviewed with Big Bend electrical staff and the changes incorporated into the cost estimates.

Tampa Electric Company
 Big Bend Station Units 1-2
 Dismantling Study



Project No.: A09476.301
 Date: December 28, 2020
 Rev. 1, Use

A summary of the costs associated with each unit for the four categories:

	Unit 1	Unit 2
Engineering ⁴	\$3,402,450	\$3,893,150
Pre-Demolition ⁴	\$4,569,293	\$14,682,411
Demolition ⁴	\$22,362,788	\$23,126,554
Post-Demolition ⁴	\$4,835,665	\$5,632,435
Total each unit	\$35,170,196	\$47,334,550
Cost Adjustments ⁷	\$(95,336)	\$(593,186)
Adjusted Total each unit	\$35,074,860	\$46,741,364
Adjusted Total for both units	\$81,816,224*	

*Notes on cost summary:

1. The above totals do not include scrap value for the demolition materials. Scrap pricing is volatile and should not be relied upon to reduce the cost of the project during the planning phase.
2. The total cost for dismantlement of Units 1 and 2 has increased by 6.8% (\$5.23 million) from the 2018 estimate. Project directs, indirects and contingency increased \$8.75 million but were partially offset by a reduction in escalation of \$3.52 million.
3. Unit 2 costs are higher primary due to new electrical equipment and cables needed for pre-demolition. The direct costs of U2 electrical are about \$6.4 million higher than Unit 1.
4. Each of these estimates is based on a 20% contingency, consistent with the 2018 estimate. See page 30 (Attachment A) for a further breakout of contingency, escalation, general conditions, direct and indirect costs. During early 2020 TEC had site meetings with potential demolition contractors on the scope and economic feasibility of the dismantlement effort. Based on these meetings and the contractor's similar project experience, it was recommended to reduce the contingency to 15%. The 5% reduction to contingency is not included in the detailed cost estimates but has been included as a "Cost Adjustments" in the table above and in the Attachment 1 cost summary page.
5. Proposed coal yard changes due to reduced fuel requirements make possible the removal of unnecessary coal yard equipment and backfilling/grading the northern third of the coal storage area. High level costs have been assigned to the identified equipment removals and regrading of the area. The coal yard demolition and regrading amount to direct costs of \$4.3 million split equally between Units 1 and 2 in the demolition cost estimate.
6. For the 2020 electrical review with TEC, direct costs increased by about \$1.6 million due to additional large cables for electrical redundancy. Added 48,000 LF of 500 kcmil cables from U1 to U3/U4.
7. "Cost Adjustments" include the reduction of contingency and an allowance for Turbine Building ventilation improvements, which includes contingency and escalation.

Tampa Electric Company
Big Bend Station Units 1-2
Dismantling Study



Project No.: A09476.301
Date: December 28, 2020
Rev. 1, Use

Schedule

The schedule of the dismantlement end date was reviewed with TEC in April and this estimate assumes a completion date of third quarter 2024 and project is started in September 2020. It is recommended to have engineering for the additional electrical feeds and structural bracing be started in the Fall of 2020. These systems are part of the "Pre-demolition" scope that is required to be installed prior to dismantlement of these key structures and systems.

Tampa Electric Company
Big Bend Station Units 1-2
Dismantling Study



Project No.: A09476.301
Date: December 28, 2020
Rev. 1, Use

Basis of Estimate – Big Bend Dismantling Units 1-2

Estimates:

Cost estimates associated with this study are as follows.

35156A – Unit 1 Pre-Demolition Modifications
35157A – Unit 1 Demolition
35158A – Unit 1 Post Demolition
35159A – Unit 1 Engineering Demolition Support
35160A – Unit 2 Pre-Demolition Modifications
35161A – Unit 2 Demolition
35162A – Unit 2 Post Demolition
35163A – Unit 2 Engineering Demolition Support
34565B – Scrap Value

A summary of the estimated costs, cash flow and the estimates are included as Attachment 1. Given that the basis of this project consists of a “decoupling” followed by “demolition”, the costs are substantially higher than would be the case for pure demolition. Total rounded off cost for each unit without scrap value:

Unit 1 \$35,075,000

Unit 2 \$46,740,000

These values are considered appropriate for project planning purposes. **Opportunities for savings during the course of demolition project execution do exist, and include but are not limited to the following:**

- Optimization of the project execution plan in the early phase of the project. This includes detailed scope development, refinement of the schedule as well as the contracting plan through a well-conceived division of responsibility.
- Use of competitively bid, firm price construction work packages, based on “issued for construction (IFC)” level engineering deliverables, rather than vague references to perceived scope or material takeoffs that create opportunities for contractor change orders.
- Developing a collaborative, value-based working relationship with the successful construction teams, via immediately responsive and capable engineering and construction management staff from both of our organizations. TEC and S&L have a long history of doing this and this project should be no exception.
- Identification of the high value scrap commodities and the means to maximize payback to TEC, at the appropriate time during execution.

We are fully prepared to facilitate the development of these and other cost savings opportunities during the course of project execution.

Tampa Electric Company
Big Bend Station Units 1-2
Dismantling Study



Project No.: A09476.301
Date: December 28, 2020
Rev. 1, Use

A. General Information

Big Bend Station is located in Hillsborough County Florida, just north of Apollo Beach. There are four coal-fired boiler units. Units 1 and 2 are to be modernized to a single two-on-one combined cycle configuration utilizing Heat Recovery Steam Generators (HRSG) and a single Steam Turbine Generator (STG) located in the current Unit 1 STG location (Modernization Project). The commercial operation date for the full modernization improvements is January 2023.

Commissioning of Units 1 and 2 occurred 1970 and 1973, respectively. Both units are comprised of 440 MW Riley Power Turbo-Fired Boilers, which have the capability to co-fire natural gas as well. Each unit has an Electrostatic Precipitator (ESP) and Selective Catalytic Reduction (SCR) system with associated ductwork and support structures. The two units share a Flue Gas Desulfurization (FGD) system with a shared chimney.

Project location – 13031 Wyandotte Road, Apollo Beach, FL 33572
Contracting strategy – Multiple lump sum

Decommissioning and Dismantlement Plan (D&D Plan)

Unit 1 has officially ceased operation as of April 2020 and Unit 2 will cease operation the fourth quarter of 2021. The Dismantling Project's scope for Units 1 and 2 is to remove equipment and structure down to the top of foundation to the greatest extent possible while maintaining full function of the turbine building and coal feed conveyor in support of Units 3 and 4. The Modernization Project is responsible for decommissioning and dismantling Unit 1 areas north of column row F $\frac{1}{2}$; therefore, cost associated with Unit 1 north of column row F $\frac{1}{2}$ will not be part of the dismantling study.

Modifications are not required to common systems such as coal delivery, storage and feed limestone preparation, gypsum dewatering, workshops, warehouses or ponds. However, such systems must be maintained, and many are powered from Unit 1. For example, the coal handling and storage is electrically fed from Unit 1 and that power feed will need to be maintained by the Modernization Project.

The objective of the Decommissioning and Dismantlement (D&D) Plan is to provide information for planning, cost estimating and execution of the Dismantlement of the Big Bend Units 1-3. The dismantlement activities will be performed on an operating power plant site so methods will be restricted so as not to interfere with generating operations or damage infrastructure and systems that are to remain in service.

Given the precise nature of this demolition, it is important that contractors be pre-qualified to ensure that only capable contractors with a good safety record and similar experience be allowed to bid the work. Contractors will be required to consider:

- Effects of ground bearing from demolition equipment on underground utilities, sumps, and the seawall
- Prevention of iron dust in wastewater and storm water drains with regular housekeeping
- Productivity due to LOTO constraints
- Limit vibrations of the demolition due to operating equipment for the remaining unit(s)
- Structural stability during removal of equipment and structures
- Impact of demolition equipment on underground pipes and sumps

Tampa Electric Company
Big Bend Station Units 1-2
Dismantling Study



Project No.: A09476.301
Date: December 28, 2020
Rev. 1, Use

- Maintain function of floodwalls and site drainage, being careful not to damage the wall or plug up the drains with debris

TEC is evaluating closure of the northern third of the coal yard operation. A study report created by CBCL Limited provides five options with TEC indicating Option 4 to be preferred. With less coal being consumed due to the retirements, there is not the same need for on hand storage of fuel. TEC requested S&L to incorporate costs for demolition of conveyors, transfer towers and buildings that will no longer be required for operations. The demolition costs for these items is included in the estimates and split equally between Units 1 and 2. However, this CBCL information was made available toward the end of the study and has not been developed to the same level of detail as the remainder of the estimate. Based on CBCL Limited's Option 4, a listing of structures included for demolition is included in Part C, Paragraph 1.c.ii.

The coal yard portion of the study has not been developed to the same level of detail as the other costs presented in the estimates. The costs were prorated from another dismantlement project using bid quotes for the coal yard and upscaling to the Big Bend scope. Additional costs for new conveyors, modifications to existing transfer towers, modification to chute work, permitting or stormwater modifications of the coal yard changes have not been considered as the demo scope. TEC will need to assess the extent of demolition considered and advise if changes are required.

The execution of the dismantling project is broken into four phases.

1. Engineering
This first phase will develop the scope of work, perform detailed engineering for modifications, develop the specifications, bid out the contracts and evaluate proposals. Work is split between TEC internal staff and an outside engineering firm.
2. Pre-Demolition Construction
This phase begins preparation for the demolition process with activities to remove consumables, remediate asbestos containing material (ACM), add bracing, and relocate utilities.
3. Demolition
Physical removal of equipment and structures.
4. Post-Demolition
Activities required to leave the site in safe, usable state that allows for proper drainage and access.

A level 2 schedule has been developed to illustrate a logical progression and duration of activities. This schedule is included as Attachment 3. **Figure 1** provides a visual of the general sequence of demolition for the major backend structure of Units 1 and 2. Sequenced areas are numbered 1 through 12.

Tampa Electric Company
Big Bend Station Units 1-2
Dismantling Study



Project No.: A09476.301
Date: December 28, 2020
Rev. 1, Use




Figure 1 – Demolition Sequence of Units 1 and 2 Backend Major Structures

Phase 1 – Engineering activities

- Secure all necessary permits and authorizations.
- Perform Environmentally Regulated Material Survey
- Conduct a detailed study to determine the method by which the existing equipment and systems will be repowered when the existing unit power distribution system is removed from service.
- Conduct a detailed study of the fire protection system to identify those portions of the existing system that will need to be preserved.
- Conduct a detailed study of all high energy systems and utilities to identify “air gap” points that the owner will be responsible to isolate services supplying the equipment and facilities to be dismantled. Systems should include electrical power, steam, compressed gases and air, water including fire protection and any other utilities present in the impacted area.
- Design new power distribution system to equipment that remains in service.
- Design drainage and stormwater modifications for northern third of the coal yard no longer required.
- Develop a list of services and material that TEC will provide to the contractor.
- Develop a list of materials, equipment and services that the contractor is responsible to provide as part of the scope.
- Hazardous material mitigation plan for pre-demolition activities and development of mitigation procedure to support dismantlement activities

Tampa Electric Company
Big Bend Station Units 1-2
Dismantling Study



Project No.: A09476.301
Date: December 28, 2020
Rev. 1, Use

- Design vertical bracing additions to ensure stabilization of structures after removal of the boiler building structure (See "blue" braces in **Figure 2** as a typical braced row).




Figure 2 – New Vertical Bracing and Boiler Steel Demolition

- Develop a procurement package for supply and installation of new elements necessary to complete the dismantlement (vertical bracing, power distribution, piping, etc.).
- Develop a procurement package for the dismantlement.

Phase 2 – Pre-dismantlement activities

- Removal of hazardous materials such as ash and SCR catalyst. Drain and decontaminate all equipment and piping, which includes removal of all liquids, gas and solids.
- Abatement of ACM once removal of all the other waste materials is complete.
- Install new vertical bracing to stabilize the Turbine Building prior to removing the boiler area steel (**Figure 2**) in several braced rows.
- "Air Gap" all energy systems.
- Install new power distribution necessary to maintain essential services.
- Mark dismantlement area and contractor access routes. Mark plant personnel access requirement in the impacted area.

Tampa Electric Company
Big Bend Station Units 1-2
Dismantling Study



Project No.: A09476.301
Date: December 28, 2020
Rev. 1, Use

Phase 3 – Demolition activities

- Development of a one acre Scrap processing area where materials will be sorted and placed in bins for recycling. See **Figure 3** for plan view of potential scrap processing area.



Figure 3 – Demolition Scrap Processing Area (Outage Laydown Area)

- Removal of Unit 1 booster fans and ESP.
- Removal of transformer and intake area equipment.
- Removal of the Unit 1&2 FGD with the exception that the electrical building is to remain for powering essential equipment (**Figure 4, next page**).
- The combined Unit 1&2 chimney demolition will begin once the Unit 1&2 FGD demolition is complete.
- Removal of Ash Silo #1, Unit 2 booster fans and ESP.
- Demolition of the partial chimney.
- Removal of the Unit 2 Turbine area equipment may begin once the ACM is abated.
- Fill Unit 2 circulating water intake and discharge lines with flowable fill and remove the discharge flume (**Figure 5, next page**).
- Partial demolition of select coal yard conveyors, transfer towers and buildings as well as regrading and seeding the area for proper drainage.

Tampa Electric Company
Big Bend Station Units 1-2
Dismantling Study



Project No.: A09476.301
Date: December 28, 2020
Rev. 1, Use



Figure 4 – Units 1 and 2 WFGD Electrical Building-to remain




Figure 5 – Unit 1 and 2 Circulation Water Discharge Area

- After ACM abatement, begin removal of Unit 1&2 back end equipment and steel starting from the south and working north. Portions of the boiler area stairs will need to remain in place until the new stair towers can be built in order to maintain adequate egress from the Tripper Room.
- Remove Unit 1&2 pipe support steel from the Turbine Building roof to the area above the Tripper Room roof.
- Remove the Unit 2 cooling tower.

Tampa Electric Company
Big Bend Station Units 1-2
Dismantling Study



Project No.: A09476.301
Date: December 28, 2020
Rev. 1, Use

Phase 4 – Post-Demolition activities

- Install new passenger elevator between Units 1 and 2.
- Install new stair tower between Units 1 and 2.
- In fill of floor openings needs to occur immediately after equipment removal. The operating floor of the Unit 2 Turbine Building has large areas that will be filled in with grating to promote storage area and space for outage maintenance, about 5,700 SF. See **Figure 6** for operating floor areas to be filled in with grating.
- Perform Unit 1-2 Boiler area paving to promote area drainage.
- Repair any flood wall damage.
- Inspect and clean out site drains.
- Repaint remaining indoor and outdoor structural steel.
- Close wall openings created in the south wall of the Turbine building after removing equipment.
- Install new area lighting.
- Perform roof repairs.




Figure 6 – Turbine Building Operating Floor In-Fill Areas

Tampa Electric Company
Big Bend Station Units 1-2
Dismantling Study



Project No.: A09476.301
Date: December 28, 2020
Rev. 1, Use

B. Estimate Approach

The cost estimate is based largely on Sargent & Lundy's experience on similar projects as well as our past project experience at the Big Bend station. This study is not a detailed engineering document, but a cost estimate prepared in advance of the detailed engineering preparations that will be necessary to carry out the full dismantling activities.

Some preliminary engineering was utilized to develop the conceptual modification to lateral load resisting system for the remaining structures and the power distribution system for remaining Unit 1 and 2 equipment that must be repowered. S&L assigned allowances where necessary to cover issues that lack full development at this time. TEC supplied the costs for ACM abatement, removal of hazardous liquids and waste in 2018.

Dismantlement estimates normally achieve a Class 4 level by applying scaling factors to account for size of unit in comparison to demolition costs developed from a past reference project. This estimate uses better-defined quantities to account for known aspects of the equipment and structure slated for removal. The goal is to estimate a level of detail necessary to achieve an estimate in line with Class 3 accuracy.

Project methods to attain this accuracy are:

Electrical:

- The demolition is covered by concentrating on large equipment (large transformers and isophase bus duct systems) using drawings and data.
- Remaining electrical equipment and commodities are included in the demolition quantities used in the estimating group's base estimate, which is used to ratio demolition costs.
- The approach accounts for relighting areas that remain in use or are repurposed after the dismantling. The estimate will include new fixtures and equipment as necessary. The extent of the scope and quantities will be developed based on conceptual engineering.
- The approach to repower any loads that will need to remain in use after the dismantling will be using new cable, raceway, and electrical equipment as necessary. The extent of the scope and quantities will be developed based on conceptual engineering and re-verification of the 2018 assumed scope split between BB modernization and Dismantlement.
- Items that are not quantifiable at this time will be assigned allowances. Such items include lightning protection, DCS modifications, electrical equipment reconfiguration, etc.

Mechanical:

- The demolition estimate for Unit 1 is adjusted to reflect the work covered by the Modernization project (turbine area and mill area north of column row F½) and mechanical equipment that will be left in service (air compressors, sump pumps, building ventilation, etc.) for both units.
- Critical pipe quantities and major equipment tonnages are used to supplement and validate the estimate quantities.
- Based on the information provided by S&L environmental, we will confirm that TEC is managing the SCR catalyst for end of life to coincide with dismantlement, thereby resulting in no salvage value of the catalyst.
- The estimate will not include the design for relocation or re-piping of any mechanical equipment.

Tampa Electric Company
Big Bend Station Units 1-2
Dismantling Study



Project No.: A09476.301
Date: December 28, 2020
Rev. 1, Use

- Items that are not quantifiable at this time will be assigned allowances. Such items include new sumps, ventilation equipment, disintegration of Units 3 & 4, etc.

Structural:

- Steel tonnage for the boiler buildings and ESP structures will be estimated based upon the volume of the structure and typical densities of such structures determined from S&L's extensive experience designing these structures.
- Steel & ductwork tonnages for the SCRs were taken from S&L's historical records based upon quantities determined during the design/construction of these structures.
- Steel & ductwork tonnages for the FGD system are determined using a scaling factor applied to known quantities based upon the power generation rating of each unit.
- Demolition estimates for the stacks were obtained from Pullman based upon existing construction documents of the Big Bend stacks.
- Quantities for the demolition of miscellaneous concrete for all units/structures are determined based upon items identified for removal during the site walk down.

Lessons Learned from Gannon:

A listing of lessons learned from the demolition effort of the Gannon Power Plant is included as Attachment 6. The approach that the study has taken to address each of the items is categorized as being addressed by estimate, engineering, or contractor. The intent of each category is the following.

- | | |
|-------------|--|
| Estimate | – indicates that quantities have been included in the estimate to account for that item. |
| Engineering | – indicates an item that will require engineering assessment and direction to the contractor. |
| Contractor | – indicates which items should be specifically included in the contract documentation as part of the contractor's scope. |

C. Estimate Scope of Work

In general, all mechanical equipment and facilities used to generate electricity by firing coal will be dismantled for Unit 2. Dismantlement scope for Unit 1 is limited to structures and equipment south of the coal conveyor since the Modernization project is performing modifications to the Turbine Building as part of repowering effort. Continued operation of the repowered Unit 1 turbine, and the continued operation of Unit 3 and Unit 4 require both a careful demolition approach and the need to keep essential systems in operation at the Big Bend station. The turbine building will not be demolished, and the part of the boiler steel required to support the coal conveyors and the turbine building south wall will not be demolished.

The extent of demolition for the units follows these guidelines:

- Removal of hazardous materials, liquids, ash, catalyst and waste materials takes place prior to demolition.
- Demolition will remove as much of the structure as possible up to the tripper support steel. In order to accomplish this, installation of new vertical bracing and a new stair tower is planned. Painting of remaining steel is also included.
- Structures and equipment pedestals will be removed down to the top of foundation.

Tampa Electric Company
Big Bend Station Units 1-2
Dismantling Study



Project No.: A09476.301
Date: December 28, 2020
Rev. 1, Use

- Select equipment must remain in service after the demolition. The equipment that serves a common function or is required to stay operational after the dismantlement will be repowered from a new distribution system with new cable routing. See Attachment 4 for a listing of assumptions related to repowering equipment.
- The scope considers removal of the Unit 2 circulating water intake equipment and discharge flume. Filling of the intake and discharge lines with flowable fill is included.
- Demolished equipment and material to be stockpiled by the contractor and disposed by TEC. A one acre scrap processing area at the southeast corner of the coal pile area will be used for this purpose.
- The Unit 2 branch off the existing ammonia loop will be capped. The Unit 1 branch has been modified to supply ammonia to the HRSG SCR as part of the Modernization project. Existing valves on the ammonia loop are to be replaced due to their tendency to leak.
- The natural gas header will be capped downstream of Unit 3.
- One personnel elevator (Unit 1) and one freight elevator (Unit 2) will be removed. A new personnel elevator is included near Unit 2.
- LED fixtures are utilized for any areas requiring new lighting.
- Large floor openings created by equipment removal at the Turbine Operating level will be filled in by grating to provide future storage and outage laydown area.
- The existing flood walls that protect the remaining facilities and area drainage must remain in service after the demolition. The contractor will need to protect both the wall and drainage system from damage during the demolition. Portions of the flood wall that are not required will be removed (i.e., Unit 1 ESP area).
- Removal scope for Unit 2 GSU and SST transformers only extends to the bushings. The high voltage line work will be handled by TEC. The GSU will be saved by TEC and stored in a location on site.

Listed below is a summary level scope (not all inclusive) of facilities included in the estimate:

1. Major Systems Identified for Demolition by Disciplines

a. Mechanical:

i. Unit 1

- Environmentally Regulated Materials removal - All disciplines
 - Survey
 - Pre demolition removal activities
 - On-going removal activities to support dismantlement
- Ash Handling system
- Boiler Feed pumps and Auxiliaries
- Boiler Pressure Systems (steam and water Circuits)
- Chemical Additive Systems Chemical Feed and water sampling system
- Combustion air and Gas System (Fans/soot blowers etc.)
- Controls, Ovation (All systems BBC001)
- Feedwater System

Tampa Electric Company
Big Bend Station Units 1-2
Dismantling Study



Project No.: A09476.301
Date: December 28, 2020
Rev. 1, Use

- Fuel Burning system (Natural Gas Systems): 12" NG pipeline will be capped downstream of Unit 4
- SCR System
- Slag Handling System
- ii. Unit 2
 - Environmentally Regulated Materials removal - All disciplines
 - Survey
 - Pre demolition removal activities
 - On-going removal activities to support dismantlement
 - Ash Handling system
 - Boiler Feed pumps and Auxiliaries
 - Boiler Pressure Systems (steam and water Circuits)
 - Circulating water System
 - Chemical Additive Systems
 - Chemical Feed and water sampling system
 - Combustion air and Gas System (Fans/soot blowers etc.)
 - Controls, Ovation (All systems BBC001)
 - Feedwater System
 - Fuel Burning system (Natural Gas Systems): 12" NG pipeline will be capped downstream of Unit 4
 - SCR System
 - Ammonia pipeline to Unit 2 SCR
 - Slag Handling System
- iii. Unit 1 & 2 Flue Gas Desulfurization System
 - Environmentally Regulated Materials removal - All disciplines
 - Survey
 - Pre demolition removal activities
 - On-going removal activities to support dismantlement
 - Absorber Tower
 - Absorber Agitators
 - Absorber Bleed Pumps
 - Absorber Ductwork
 - Absorber recycle pumps
 - Absorber instrument and controls
 - Make up water header
 - Mist eliminator wash system
 - Oxidation air sparger system

Tampa Electric Company
Big Bend Station Units 1-2
Dismantling Study



Project No.: A09476.301
Date: December 28, 2020
Rev. 1, Use

- Quenching nozzle spray system
 - Reagent Feed Loops
 - Continuous emissions monitoring system
 - Defoamer Storage tank and pumps
 - Forced oxidation blowers
 - Unit 1 & 2 Process Gas Flow (dampers)
 - Organic acid system
 - Primary Dewater system
 - Wet chimney
 - FGD Common systems are not included in the dismantlement scope
 - Limestone Slurry preparation system
 - Common Gypsum dewatering system
- b. Electrical:
- i. Unit 1
 - 13.8kV Switchgear Bus – 1NPS-SWG-101
 - 13.8kV Switchgear Bus A – 1NPS-SWG-102A
 - 13.8kV Switchgear Bus B – 1NPS-SWG-102B
 - Low voltage switchgears and motor control centers south of column row F½.
 - Electrical and control systems associated with the mechanical systems identified in item 1.a.
 - ii. Unit 2
 - Generator 2
 - Generator Step up Transformer – MTX2 – to be saved as a spare by TEC
 - Station Service Transformer A – SST2A
 - Station Service Transformer B – SST2B
 - Isolated phase bus duct system
 - 4160V Switchgear West Bus – 2NNS-SWGW
 - 4160V Reserve Switchgear West Bus – 2RNS-SWGW
 - 4160V Switchgear East Bus – 2NNS-SWGE
 - 13.8kV Switchgear Bus – 2NPS-SWG-201
 - 13.8kV Switchgear Bus A – 2NPS-SWG-202A
 - 13.8kV Switchgear Bus B – 2NPS-SWG-202B
 - Low voltage switchgears and motor control centers.
 - Electrical and control systems associated with the mechanical systems identified in item 1.a.
 - iii. Reserve Auxiliary System
 - Reconfigure to keep in service.

Tampa Electric Company
Big Bend Station Units 1-2
Dismantling Study



Project No.: A09476.301
Date: December 28, 2020
Rev. 1, Use

- iv. Instrumentation and Controls
 - Instruments for all units associated with systems being removed.
- c. Structural:
 - i. Units 1 & 2
 - Shared FGD stack
 - FGD vessel, ductwork, and structural steel
 - SCR reactors, ductwork and structural steel
 - Out of service stack
 - ESP box, ductwork and structural steel
 - Cap and fill circulating water tunnels, Unit 2 only
 - Discharge flume, Unit 2 only
 - Structural demolition extent
 - Steel removal shall be maximized to decrease future steel maintenance
 - Existing lateral bracing shall be modified, and additional steel shall be added to provide an adequate load path for the new configuration
 - Painting of existing steel
 - Identify and maintain required means of egress per building code including the removal of many existing platforms and eliminating walkways and platforms that will no longer be required
 - Stairways should be modified in order to streamline travel paths and eliminate confusing evacuation routes
 - Elevators should only provide access to areas required for operations.
 - Coal bunker walls and hoppers
 - Boiler building to be removed to column row F½
 - Coal Conveyor remains in service for Units 3 and 4.
 - Current truck aisle between column rows C and D to remain open.
 - Current plan is for existing steel to be re-painted, there will be no siding added to the structures that don't currently have siding for this scope of work.
 - ii. Coal Yard – (demo scope added per TEC request in June 2020)
 - Usable coal from the northern third of coal pile will be lowered by TEC as part of normal coal handling operations.
 - No cost for excavation or disposal of material is included.
 - Area backfilled and graded for proper drainage (2.5 feet of fill over an 11 acre area assumed for the estimate). Evaluation of final grading scheme with respect to overall plant stormwater management will be required.
 - Area hydroseeded for dust and erosion control.
 - Demolition of conveyors J1, J2, Q1, Q2, R1, R2, T1, T2, U1, W1, W2, and Z1
 - Demolition of the Polk and Superior conveyors.

Tampa Electric Company
Big Bend Station Units 1-2
Dismantling Study



Project No.: A09476.301
Date: December 28, 2020
Rev. 1, Use

- Demolition of G1 Stacker Reclaimer conveyor. TEC plans to sell the north stacker reclaimer.
 - Demolition of transfer towers T-4, T-5, T-6, and T-7 (crusher house).
 - Demolition of BF Building, Blending Bins, and Polk Truck Loadout & Scale.
 - The demolition of the Blending Bins structure requires that the coal yard control room be relocated. Detailed costs to relocate this control room are beyond the scope of the study but are considered captured in the contingency for the coal yard portion.
2. Major installations and replacements required due to dismantlement
- a. Mechanical
- i. Separation of the following systems:
 - Common steam line for each units' main steam attemperator
 - ii. Natural gas system to be capped downstream of Unit 3.
 - iii. Hydrogen and Ammonia System branched to Unit 2 to be capped
 - iv. Fill the circulating water intake and discharge tunnels for Unit 2
- b. Structural
- i. Turbine roofing to be replaced
 - Replace roofing at the Unit 2 cooling tower after removal
 - Replace any dismantlement related damaged areas along south edge of roof
 - Roof drains to be replaced
 - ii. One new elevator to tripper room to be located between Units 1 and 2
 - Landings only to access areas of remaining operations. (Tripper room, cooling tower, turbine deck, turbine mezzanine, and ground floor)
 - iii. New stair tower to tripper room to be located between Units 1 and 2
 - iv. Entry way canopies where applicable
 - v. Turbine building siding
 - South side of turbine building to close in the remaining structure
 - vi. Structural steel bracing to support the structural demolition extent
 - vii. Provide floor framing and grating to fill in large openings created by equipment removal in Unit 2. Small opening will also be filled in with grating.
 - Examples:
 - Turbine & Generator voids
 - Coal Handling equipment voids
 - Large open area east of the Turbine at the operating level
 - viii. Grating and handrails as required to access Unit 1 operations. (cooling tower, turbine deck, turbine mezzanine, and ground floor)
 - ix. Removal of checkered plating and replaced with grating
 - x. Paving of dismantled area to promote drainage and provide a smooth walking surface

Tampa Electric Company
Big Bend Station Units 1-2
Dismantling Study



Project No.: A09476.301
Date: December 28, 2020
Rev. 1, Use

- xi. Painting of existing interior and exterior steel
- c. Electrical/I&C
 - i. Reconfiguration of the DCS system (Emerson) to move remaining equipment controls to common highway
 - ii. New PDC building for repowering remaining equipment loads
 - iii. Lightning protection for unprotected structures subsequent to demolition
 - iv. Lighting
 - Lighting to account for areas still being utilized by Unit 1 and 2 operations. (cooling tower, turbine deck, turbine mezzanine, and ground floor)
 - v. Equipment that will need to be repowered (refer to Attachment 4 for detailed breakout of equipment)
 - Turbine Shop
 - Tagging Office
 - Units 1 and 2 Floor Drain sump equipment
 - Units 1 and 2 Settling Basin sump equipment
 - Sanitary Lift station OPBS STU15 (Unit 2) sump equipment
 - Sanitary Lift station OPBS STU6 (Main) sump equipment
 - Stormwater sumps within the unit boundaries.
 - Air Compressor #3
 - Turbine Building vent fans
 - Unit 4 Clean & Dirty oil tank equipment
 - Turbine Hall cranes
 - Unit 2 Fire Protection Panel

D. Pricing and Quantities

- Costs for bulk materials were derived from S&L database
- Asbestos abatement costs provided by TEC
- Decommissioning (removal and disposal of regulated waste) costs provided by TEC
- TEC's project staffing and security costs provided by TEC
- Permit costs provided by TEC

Bulk quantities and weights of equipment and material commodities used in this cost estimate are intended to be reasonable and representative of projects of this type. Quantities were estimated from Sargent & Lundy in-house database and numerous assumptions. See "Estimate Approach" for further discussion on quantity development.

TEC cost estimate input and assumptions:

Decommissioning – Decommissioning includes boiler draining, contaminate removal (fly ash, coal, slag, lead paint, oil, mercury, radiation, natural gas, hydrogen, and ammonia), elevators repairs as required by an outage, FGD tanks and ducts to be washed out, and condenser and ZBL system

Tampa Electric Company
Big Bend Station Units 1-2
Dismantling Study



Project No.: A09476.301
Date: December 28, 2020
Rev. 1, Use

cleaning. Estimated are based off previous work orders found in TEC's Work Management System (Workman).

Asbestos Abatement – Asbestos abatement includes abating known areas of asbestos (turbine building and elevators siding, piping insulation, cable trays, etc.) as well as an allowance for unknown areas that may be discovered. Cost includes an allowance for scaffolding and half of an asbestos supervisor's time during the length of the dismantlement. Estimated are based off previous work orders found in TEC's Work Management System (Workman).

Payroll – Payroll was estimated by accounting for all the TEC team members assumed to work on the project. A total cost was calculated by using their hourly rate and amount of time assumed to be spent on the project. It was assumed that there was less payroll cost for Unit 1 since BBMOD will be removing most of the turbine building equipment.

Security – During dismantlement, the number of contractors onsite will increase resulting in some additional security measures.

Permitting & Compliance – Includes an allowance for environmental studies, environmental compliance fees, legal fees, FAA permits, and Asbestos notifications.

E. Labor Wage Rates

Craft labor rates were developed for TEC as part of the Modernization project through a labor study conducted by S&L. The labor study based rates used in the 2018 study and cost estimates have been escalated for 2020. Costs have been added to cover social security, workmen's compensation, federal and state unemployment insurance. The resulting burdened craft rates were then used to develop typical crew rates applicable to the task being performed. No adjustments to labor rates or productivity have been accounted for in the estimate for long term COVID-19 impacts.

Demolition Estimates: Labor Work Schedule and Incentives - Assumed 5 days x8 hr day work week.

Pre and Post Demolition Estimates: Labor Work Schedule and Incentives - Assumed 5 days x10 hr day work week.

Per diem is not required.

For addition estimates only, a regional labor productivity multiplier of 1.1 is included based on Compass International Global Construction Yearbook. The use of this productivity factor is an approach to compare construction productivity in various locations in the USA to a known basis or benchmark of 1.00 for Texas, Gulf Coast productivity. Productivity multiplier does not include weather related delays.

F. Construction Equipment

Construction equipment cost is included on each estimate line as needed based on the type of activity and construction equipment requirements to perform the work.

Tampa Electric Company
Big Bend Station Units 1-2
Dismantling Study



Project No.: A09476.301
Date: December 28, 2020
Rev. 1, Use

G. Construction Direct/Indirect Costs and General Conditions

The estimate is constructed in such a manner where most of the direct construction costs are determined directly and several direct construction cost accounts are determined indirectly by taking a percentage of the directly determined costs. These percentages are based on our experience with similar type and size projects. Listed below are the additional costs included, unless noted as not included.

- Additional Labor Costs:
 - Labor Supervision
 - Show-up time
 - Cost of overtime
 - Per diem – not included
- Site Overheads:
 - Construction Management
 - Field Office Expenses
 - Material & Quality Control
 - Site Services
 - Safety
 - Temporary Facilities
 - Temporary Utilities
 - Mobilization/Demobilization
 - Legal Expenses/Claims
- Other Construction Indirect costs:
 - Small Tools and Consumables
 - Scaffolding
 - General Liability Insurance
 - Construction Equipment Mobilization/Demobilization
 - Freight on Material
 - Freight on Process Equipment – included with equipment cost
 - Sales Tax – not included
 - Contractors General & Administration (G&A) Expense
 - Contractors Profit
- Project Indirect Costs:
 - A/E Engineering Services
 - A/E Construction Management
 - A/E Start-up and Commissioning support
 - Start-Up Spare Parts
 - Owner's cost
 - EPC Fee – not included
 - AFUDC - not included

Tampa Electric Company
Big Bend Station Units 1-2
Dismantling Study



Project No.: A09476.301
Date: December 28, 2020
Rev. 1, Use

H. Scrap Value

The scrap values used are the credit to the utility based on current industry data.

- Mixed Steel value @ \$191/Ton
- #2 Copper @ \$4130/Ton
- #1 Insulated copper wire 65% @ \$2175/Ton

Note: 1 ton = 2000 Lbs.

Scrap values have decreased from the 2018 cost estimates. The mixed steel value is down 23% and the copper values are down 9%. Scrap values can fluctuate month-to-month and should not be relied upon to reduce the cost of demolition during the planning stage.

The coal yard demolition has not been factored into the scrap values at this time.

I. Contingency

A 20% contingency was initially used for all costs in the Unit 1 and 2 estimates included with Attachment 1. We consider this to be appropriate and consistent with AACE guidelines, given our experience with fossil plant demolition as well as the level of project definition that has been achieved to date. However, TEC requested that the contingency be modified to 15%. Since this request occurred after completion of the estimates, an adjustment to the total project cost has been included.

Contingency is applied at 10% to scrap value since this decreases the credit from scrap material in the cost estimate.

J. Escalation

Escalation cost is included and calculated based on the following rates, project schedule and cash flow expenditures as reflected in the cash flow curves for each cost category.

Escalation is included considering Unit 1 dismantling beginning in the third quarter of 2021 and Unit 2 beginning in the fourth quarter of 2021.

2.5% / year for materials
3% / year for subcontract costs
3% / year for labor
2.5% / year for construction equipment
3% / year for project indirect costs
0% / year for scrap metal

K. Costs Excluded

All known scope of required physical facilities as provided by the project team to encompass a complete project has been included in the estimate. There are no known intentional omissions.

Tampa Electric Company
Big Bend Station Units 1-2
Dismantling Study



Project No.: A09476.301
Date: December 28, 2020
Rev. 1, Use

The cost estimate represents only the costs listed in the estimate. The estimate does not include allowances for any other costs not listed and incurred by the owner. Excluded costs (and some of which are also listed in "Assumptions/Clarifications") are any that are not listed in the estimate.

There may be additional costs that the Owner should consider such as (the list below is not all inclusive):

- Legal costs
- Owner's Bond Fees
- Taxes
- Station insurance costs and taxes are not included
- Performance Bonds

L. Scope Assumptions/Clarifications/Exclusions

Electrical

- All plant systems will be drained, electrical equipment and wiring is de-energized and tagged out by the client prior to demolition activities.
- Switchyards within the plant boundaries are not part of the scope; neither are access roads and rail lines to these facilities
- Overhead transmission towers are not included in this study.
- U4 intake structure loads are already fed from Unit 4. No repowering is necessary.
- Loads are based on expected loading of equipment of this nature.
- New raceway (cable tray/conduit) is included for repowering of the existing loads.
- New raceway is supported from existing steel members.
- An allowance is included to cross tie Unit 1 reserve switchgear to Unit 4 switchgear.
- Cabling between the Modernization Unit 1 switchgear connects to the reserve 3 current limiting reactor. An allowance for this cable to be replaced is included in the estimate.
- Unit 4 reserve switchgear has available capacity and spare feeder breaker to feed the new repowering medium voltage switchgear.
- Coal field is fed from the existing Station reserve system. No repowering is necessary.
- Station reserve system is to remain in place. An allowance is included for some reconfiguration.
- An allowance is included for lighting protection.
- Allowances are included for new access lighting for areas that will remain in use after the dismantling.
- New repowering PDC building will reside on the back end (south) of Unit 2.
- An allowance is included for any DCS reconfiguration and control modifications are required after dismantling.
- Estimate excludes TEC Energy Delivery costs for removal of high voltage lines to the switchyard.

Decommissioning

- All chemicals and oils will be removed by TEC prior to demolition.
- Cleaning and flushing of chemical and oil storage pipes and tanks are by TEC.
- All storage tanks will be emptied by TEC.
- No remediation or removal of contaminated spills is required (no known spills exist).
- Coal bunkers and ash silos will be emptied by TEC.

Tampa Electric Company
Big Bend Station Units 1-2
Dismantling Study



Project No.: A09476.301
Date: December 28, 2020
Rev. 1, Use

Structural

- All items that extend more than 1'-0" above top of foundation will be demolished to grade level. Any other items will remain in place.
- A 6" asphalt layer (average thickness) shall be laid in areas where overhead steel will be removed to create a better walking surface, provide adequate drainage and prevent pooling.
- All borrow and backfill soil material is assumed to be purchased from offsite sources.
- Coating system for new steel is galvanized.

Mechanical

- Large diameter cooling water pipes/tunnels will be abandoned in place and filled to prevent ingress of water or collapse.
- The Station Air compressors for Unit 2 (Compressors #3 & #4) must be kept in service. Repowering and controls modifications are required. Additionally, a source of cooling water will be required, preserving of either the Unit 2 cooling tower is being considered as a potential cost savings in the detail engineering phase.
- The Units 1 and 2 Settling Basins must stay in service.
- The Units 1 and 2 Floor Drain Sumps must stay in operation, which will require repowering and controls modification. The Floor and Equipment Drain system in the Boiler and Turbine area must stay in operation, with modifications at equipment drains.
- Auxiliary steam will be routed from Unit 1 to Unit 4 by the Modernization project.
- A new Natural gas header vent will be required at Unit 4 when the header is removed from Units 1 and 2.
- Close Coal chutes in the tripper room for Unit 2 and Unit 3 bunkers.
- Flyash pipe between Ash silos # 1 and # 2 must be cut and capped at #2.
- Unit 1-2 Gypsum pipes to dewatering are to be demolished.
- Fire protection panel for Unit 2 must be interfaced with the DCS.
- Ammonia loop valves will be replaced and the branch to Unit 2 SCR will be capped.
- Detailed design phase required to further investigate assumptions.

General

- All demolished non-metal materials except concrete are considered debris and shall be transported to a licensed landfill.
- It is assumed that concrete will be processed for recycling onsite and removed offsite by a concrete recycling company at no cost or credit to the Utility.
- Scrap value for recoverable metals is included in the estimate as a credit. No resale of equipment or material is included.
- The estimate assumes that all structural steel, miscellaneous building steel, decking grating, piping, and equipment will be removed to drop-off containers as provided by the scrap metal recycling company. The recycling company will assume all responsibility for the safe removal/disposal of lead paint and processing of the steel, which is reflected in the value of scrap metal.
- Cost of removing mobile equipment and machinery is by TEC.
- Site Construction Management costs assume one CM per unit for the duration of pre-demolition and demolition.

Tampa Electric Company
 Big Bend Station Units 1-2
 Dismantling Study



Project No.: A09476.301
 Date: December 28, 2020
 Rev. 1, Use

M. Cost Comparison to 2018 Estimate

The organization of the estimates into new categories does not allow for direct comparison of the individual estimates created for this study; however, the total cost by unit can be compared.

	2018	2020	Change
Unit 1	\$33,143,556	\$35,074,860	\$1,931,304 (5.8%)
Unit 2	\$43,440,936	\$46,741,364	\$3,300,428 (7.6%)
Total for both units	\$76,584,492	\$81,816,224	\$5,231,732 (6.8%)
Scrap Value Unit 1	\$(4,609,221)	\$(3,548,900)	
Scrap Value Unit 2	\$(5,468,548)	\$(4,217,943)	

The total 2020 cost for dismantlement of Units 1 and 2 has increased by 6.8% from the 2018 estimate. The increase can be attributed to several factors.

While labor rates have increased from those used in the 2018 study, other factors such as escalation and chimney demolition have decreased. Escalation has decreased due Unit 1 retirement having already occurred allowing for work to begin immediately. Unit 2 retirement is now only one year away compared to three years in future during the 2018 estimate. The cost for demolishing the Unit 1 and 2 wet FGD chimney and the partial Unit 1 and 2 concrete shell are based on a budget quote from Pullman. They also provided a budgetary quote in 2018. However, they state a reduced cost based on having obtained new equipment that allows for a more efficient means of chimney demolition. This reduced their cost from 2018 by \$1,220,000 (a 25% reduction).

A large portion on the direct cost increase can be attributed to the coal yard demolition and regrading. Those changes make up \$4.3 million of the \$6.3 million increase in direct costs. Electrical reviews also added \$1.6 million in new large cables (48 – 500 kcmil, 48000LF) to add redundancy for Unit 1 with a cross tie.

The decrease of the contingency of the base estimates from 20% to 15% results in a contingency decrease of approximately \$3.25 million.

Tampa Electric Company
Big Bend Station Units 1-2
Dismantling Study



Project No.: A09476.301
Date: December 28, 2020
Rev. 1, Use

N. Schedule

A level 2 schedule has been developed to reflect the latest retirement dates for Units 1 and 2. See Attachment 3 for the schedule. Planning and engineering can start at any time. The schedule basis is beginning activities in September 2020, which provides a completion date four years after project start.

Near term activities that should begin in 2020:

Task	Responsibility
Project Scope Authorization (PSA)	TEC
Assign internal staff responsibilities	TEC
Hazardous Material Survey	TEC/AE
Pre-demolition design activities – Electrical feed modifications	AE
Pre-demolition design activities – Structural stability bracing	AE
Demolition – Develop Scoping	AE
Permitting	TEC/AE

This schedule was reviewed with TEC in April and is used to develop the cost estimate escalation values and as the cash flow basis. Key engineering activities should start soon after project authorization in order to ensure adequate time is allotted to install essential "Pre-demolition" scope modifications prior to demolition start.

Tampa Electric Company
Big Bend Station Units 1-2
Dismantling Study



Project No.: A09476.301
Date: December 28, 2020
Rev. 1, Use

ATTACHMENT 1

Cost Estimate Summary, Cash Flow and Individual Estimates

Tampa Electric Company
 Big Bend Station Units 1-2
 Dismantling Study



Project No.: A09476.301
 Date: December 28, 2020
 Rev. 1, Use


COST ESTIMATE SUMMARY						
	Direct Cost	General Conditions	Project Indirect Costs	Contingency	Escalation	Total
Unit 1						
Pre Demolition Modifications	\$2,236,875	\$1,341,113	\$71,560	\$729,910	\$189,835	\$4,569,293
Demolition	\$11,459,211	\$1,975,702	\$4,160,295	\$3,519,041	\$1,248,539	\$22,362,788
Post Demolition	\$2,421,821	\$571,936	\$617,695	\$722,291	\$501,922	\$4,835,665
Engineering Demolition Support	\$0	\$0	\$2,705,250	\$541,100	\$156,100	\$3,402,450
Contingency Adjustment to 15%	\$0	\$0	\$0	\$(1,378,086)	\$0	\$(1,378,086)
Allowance - Turbine Building Ventilation	\$1,000,000	\$0	\$0	\$150,000	\$132,750	\$1,282,750
Total	\$17,117,907	\$3,888,751	\$7,554,800	\$4,284,256	\$2,229,146	\$35,074,860
Unit 2						
Pre Demolition Modifications	\$8,518,417	\$3,294,121	\$236,251	\$2,409,758	\$223,864	\$14,682,411
Demolition	\$12,848,141	\$2,263,374	\$2,945,415	\$3,611,386	\$1,458,238	\$23,126,554
Post Demolition	\$2,422,165	\$1,149,600	\$733,370	\$861,000	\$466,300	\$5,632,435
Engineering Demolition Support	\$0	\$0	\$3,108,050	\$621,600	\$163,500	\$3,893,150
Contingency Adjustment to 15%	\$0	\$0	\$0	\$(1,875,936)	\$0	\$(1,875,936)
Allowance - Turbine Building Ventilation	\$1,000,000	\$0	\$0	\$150,000	\$132,750	\$1,282,750
Total	\$24,788,723	\$6,707,095	\$7,023,086	\$5,777,808	\$2,444,652	\$46,741,364
Grand Total Unit 1 and 2	\$41,906,630	\$10,595,846	\$14,577,886	\$10,062,064	\$4,673,798	\$81,816,224
Unit 1 Scrap Value	\$3,548,900					
Unit 2 Scrap Value	\$4,217,943					
Total Scrap Value	\$7,766,843					

Project No.: A09476-301
Date: December 28, 2020
Rev. 1, Use

Tampa Electric Company
Big Bend Station Units 1-2
Dismantling Study

	2020				2021				2022				2023				2024			
	1st Quarter	2nd Quarter	3rd Quarter	4th Quarter	1st Quarter	2nd Quarter	3rd Quarter	4th Quarter	1st Quarter	2nd Quarter	3rd Quarter	4th Quarter	1st Quarter	2nd Quarter	3rd Quarter	4th Quarter	1st Quarter	2nd Quarter	3rd Quarter	4th Quarter
Total (000s)	0	12	265	912	4,520	4,471	4,471	4,471	2,861	2,176	3,178	2,938	1,893	1,375	1,113	2,277	2,940	1,489	309	0
Unit 1 Total Project Cost	0	12	265	912	4,520	4,471	4,471	4,471	2,861	2,176	3,178	2,938	1,893	1,375	1,113	2,277	2,940	1,489	309	0
Cumulative	0	12	278	1,190	5,712	10,183	14,654	19,125	22,006	24,182	27,360	30,538	32,731	34,106	35,219	36,496	38,436	40,925	43,414	45,741
Unit 2 Total Project Cost	0	12	169	1,089	4,007	3,031	3,031	3,031	5,402	5,492	5,747	4,894	5,289	1,968	1,012	1,273	2,301	1,072	28	0
Cumulative	0	12	181	1,271	5,226	8,257	11,288	14,319	19,721	25,213	30,960	35,854	39,088	41,056	42,068	43,341	45,741	46,813	46,841	46,841

Big Bend 2020 Dismantlement Study Cash Flow



TEC
 BIG BEND STATION
 UNIT 1 PRE DEMOLITION

Estimator	GA
Labor rate table	20FLTAM DEMO
Project No.	A09476-073
Estimate Date	6/18/20
Reviewed By	BA
Approved By	BA
Estimate No.	35156A
Cost index	FLTAM

Estimate No.: 35156A
 Project No.: A09476-073
 Estimate Date: 6/18/20
 Prep/Rev/App: ON6A8A

TEC
 BIG BEND STATION
 UNIT 1 PRE DEMOLITION



Group	Description	Subcontract Cost	Process Equipment Cost	Material Cost	Man Hours	Labor Cost	Equip Amount	Total Cost
21.00.00	CIVIL WORK			11,580	137	7,957	2,140	21,687
22.00.00	CONCRETE			10,704	471	21,386	3,614	35,703
23.00.00	STEEL			284,540	4,732	261,681	108,869	655,090
35.00.00	PIPING	350,000						350,000
42.00.00	RACEWAY, CABLE TRAY & CONDUIT	200,000		158,630	10,572	618,465	12,974	990,069
43.00.00	CABLE			80,747	1,406	83,380	20,198	184,325
	TOTAL DIRECT	550,000		546,201	17,369	992,880	147,794	2,236,875

DOCKET NO. 20210034-EI
 EXHIBIT NO. CRB-1
 WITNESS: BEITEL
 DOCUMENT NO. 1
 PAGE 33 OF 100
 FILED: 04/09/2021

TEC
 BIG BEND STATION
 UNIT 1 PRE DEMOLITION



Estimate Totals

Description	Amount	Totals	Hours
Labor	992,890		17,369
Material	546,201		
Subcontract	550,000		
Construction Equipment	147,794		
Process Equipment		2,236,875	
General Conditions			
Additional Labor Costs			
90-1 Labor Supervision	59,573		
90-2 Show-up Time	19,558		
90-3 Cost Plus Fee 5-10's	194,259		
90-4 Cost Plus Fee 10-15's			
90-5 Per Diem			
Site Overheads			
91-1 Construction Management	214,923		
91-2 Field Office Expenses	132,119		
91-3 Material&Quality Control	33,488		
91-4 Site Services	27,505		
91-5 Safety	21,183		
91-6 Temporary Facilities	16,117		
91-7 Temporary Utilities	17,000		
91-8 Mobilization/Demob	16,985		
91-9 Legal Expenses/Claims	2,509		
Other Construction Indirects			
92-1 Small Tools & Consumables	32,169		
92-2 Scaffolding	75,062		
92-3 General Liability Insur.	10,723		
92-4 Constr. Equip. Mob/Demob	1,478		
92-5 Freight on Material	27,310		
92-6 Freight on Process Equip			
92-7 Insurance	180,432		
92-8 Contractions G&A	257,759		
92-9 Contractions Profit		3,577,988	
Project Indirect Costs			
93-1 Engineering Services			
93-2 CM Support	71,560		
93-3 Start-Up/Commissioning			
93-4 Start-Up/Spare Parts			
93-5 Excess Liability Insur.			
93-6 Sales Tax On Indirects			
93-7 Overhead Cost			
93-8 EPC Fee	71,560	3,649,548	
Contingency			
94-1 Contingency on Const Eq	34,879		
94-3 Contingency on Material	134,202		
94-4 Contingency on Labor	436,517		
94-5 Contingency on Subcontr.	110,000		
94-6 Contingency on Process Eq			
94-7 Contingency on Indirect	14,312		
	729,910	4,379,468	
Escalation			
96-1 Escalation on Const Equip	6,503		
96-3 Escalation on Material	25,287		
96-4 Escalation on Labor	122,416		
96-5 Escalation on Subcontract	30,848		
96-6 Escalation on Process Equip			
96-7 Escalation on Indirects	4,781		
	189,835	4,569,293	
98 Interest During Constr		4,569,293	
Total		4,569,293	

Estimate No.: 35156A
 Project No.: A09476-073
 Estimate Date: 6/19/20
 Prep/Rev/Appr: GAB/GA

TEC
 BIG BEND STATION
 UNIT 1 PRE DEMOLITION



Group	Phase	Description	Notes	Quantity	Subcontract Cost	Process Equipment Cost	Material Cost	Man Hours	Labor Cost	Equip Amount	Total Cost
21.00.00		CIVIL WORK									
21.17.00		EXCAVATION FOUNDATION EXCAVATION, COMMON EARTH USING 1 CY BACKHOE EXCAVATION	FOUNDATION FOR CABLE RACK	335.11 CY	-	-	-	55	3,213	883	4,076
								55	3,213	883	4,076
21.19.00		DISPOSAL DISPOSAL OF EXCESS MATERIAL USING DUMP TRUCK, 4 MI ROUND TRIP DISPOSAL	FOUNDATION FOR CABLE RACK	335.11 CY	-	-	-	22	1,285	345	1,630
								22	1,285	345	1,630
21.20.00		BACKFILL FOUNDATION BACKFILL, SELECT STRUCTURAL FILL BACKFILL	FOUNDATION FOR CABLE RACK	361.87 CY	-	-	11,580	60	3,469	932	15,981
							11,580	137	7,967	2,140	21,687
22.00.00		CONCRETE									
22.13.00		CONCRETE MAT FOUNDATION LESS THAN 5 FT THICK, 4500 PSI CONCRETE	FOUNDATION FOR CABLE RACK	27.70 CY	-	-	3,463	38	1,449	438	5,350
							3,463	38	1,449	438	5,350
22.15.00		EMBEDMENT EMBEDMENTS, CARBON STEEL EMBEDMENT	FOUNDATION FOR CABLE RACK	277.04 LB	-	-	831	15	659	25	1,515
							831	15	659	25	1,515
22.17.00		FORMWORK BUILT UP INSTALL & STRIP FORMWORK	FOUNDATION FOR CABLE RACK	1,712.00 SF	-	-	4,280	377	17,188	2,739	24,207
							4,280	377	17,188	2,739	24,207
22.25.00		REINFORCING UNCOATED #615 GR60 REINFORCING	FOUNDATION FOR CABLE RACK	2.08 TN	-	-	2,130	41	2,090	411	4,631
							2,130	41	2,090	411	4,631
		CONCRETE					10,704	471	21,386	3,614	35,703
23.00.00		STEEL									
23.25.00		ROLLED SHAPE MEDIUM WEIGHT MEMBERS, 21 LBLF TO 40 LBLF, GALVANIZED GALVANIZED MEDIUM WEIGHT MEMBERS, 21 LBLF TO 40 LBLF, GALVANIZED REINFORCING EXISTING STRUCTURAL STEEL WITH COVER PLATES ROLLED SHAPE	CABLE RACK STABILITY BRACING FOR TURBINE BUILDING	22.00 TN 46.00 TN 20.00 TN	-	-	66,410 145,130 70,000	411 1,290 3,080	22,514 70,612 168,554	10,592 21,521 77,066	102,217 237,263 315,610
							284,540	4,782	261,681	108,869	655,090
		STEEL					284,540	4,782	261,681	108,869	655,090
35.00.00		PIPING									
35.13.45		MISC. ABOVE GROUND, PROCESS AREA MODIFICATIONS TO EXISTING PIPE SYSTEMS: NATURAL GAS HEADER, AMMONIA SUPPLY HEADER, FIRE PROTECTION, SERVICE WATER, COMPRESS AIR AND GASES PIPING		1.00 LS	350,000	-	-	-	-	-	350,000
		PIPING									
		MISC. ABOVE GROUND, PROCESS AREA			350,000	-	-	-	-	-	350,000
42.00.00		RACEWAY, CABLE TRAY & CONDUIT									
42.13.02		CABLE TRAY COVER, ALUMINUM 24 IN WIDE INCLUDING FITTINGS CABLE TRAY COVER, ALUMINUM		1,000.00 LF	-	-	2,880	76	4,441	93	7,414
							2,880	76	4,441	93	7,414
42.13.37		CABLE TRAY, ALUMINUM 24 IN WIDE LADDER TYPE INCLUDING SUPPORTS AND FITTINGS		1,000.00 LF	-	-	25,630	1,924	112,559	2,381	140,551

Estimate No.: 35156A
 Project No.: A09476-073
 Estimate Date: 6/19/20
 Prep/Rev/Appr: GAB/BA

TEC
 BIG BEND STATION
 UNIT 1 PRE DEMOLITION



Group	Phase	Description	Notes	Quantity	Subcontract Cost	Process Equipment Cost	Material Cost	Man Hours	Labor Cost	Equip Amount	Total Cost
CABLE TRAY, ALUMINUM											
42.15.13		CONDUIT, ALUMINUM					25,630	1,924	112,559	2,361	140,551
		1 IN DIA INCLUDING ELBOWS, UNISTRUT SUPPORTS, AND MISC HARDWARE		21,000.00 LF	-	-	50,220	4,987	290,569	6,095	355,885
		2 IN DIA INCLUDING ELBOWS, UNISTRUT SUPPORTS, AND MISC HARDWARE		2,000.00 LF	-	-	9,400	563	32,951	691	43,042
		2 IN DIA INCLUDING ELBOWS, UNISTRUT SUPPORTS, AND MISC HARDWARE		2,000.00 LF	-	-	12,800	697	40,802	856	54,459
		2-1/2 IN DIA INCLUDING ELBOWS, UNISTRUT SUPPORTS, AND MISC HARDWARE		2,000.00 LF	-	-	18,500	906	53,030	1,112	72,642
		3 IN DIA INCLUDING ELBOWS, UNISTRUT SUPPORTS, AND MISC HARDWARE		1,000.00 LF	-	-	12,150	639	37,391	784	50,325
		4 IN DIA INCLUDING ELBOWS, UNISTRUT SUPPORTS, AND MISC HARDWARE		1,000.00 LF	-	-	18,050	799	46,723	980	65,753
		MISCELLANEOUS SIZE CONDUITS		1.00 LS	200,000	-	-	-	-	-	200,000
		CONDUIT, ALUMINUM			200,000		130,120	8,572	501,465	10,519	842,105
		RACEWAY, CABLE TRAY & CONDUIT			200,000		158,630	10,572	618,465	12,974	990,069
43.00.00		CABLE									
43.20.00		600V CABLE & TERMINATION									
		600V #10 3/C CU XLPE LSZH	11 CABLES x 1000FT=	11,000.00 LF	-	-	15,840	339	20,089	4,866	40,795
		600V #8 4/C CU EPR TS-CPE	10 CABLES x 1000FT=	10,000.00 LF	-	-	22,400	495	29,351	7,110	59,861
		600V #4 3/C CU EPR TS-CPE	2 CABLES x 1000FT=	2,000.00 LF	-	-	6,140	119	7,044	1,708	14,891
		600V #10 3/C W/G CU EPR TS-CPE	2 CABLES x 1000FT=	2,000.00 LF	-	-	11,700	172	10,175	2,465	24,340
		600V #4/0 3/C CU	2 CABLES x 1000FT=	2,000.00 LF	-	-	23,640	213	12,654	3,065	39,359
		TERMINATION - COMPRESSION LUG, #10, 1 HOLE, COPPER	11 CABLES x 3 x 2=	66.00 EA	-	-	145	18	1,076	281	1,482
		TERMINATION - COMPRESSION LUG, #8, 2 HOLE, COPPER	10 CABLES x 3 x 2=	60.00 EA	-	-	390	20	1,174	284	1,848
		TERMINATION - COMPRESSION LUG, #4, 2 HOLE, COPPER	2 CABLES x 3 x 2=	12.00 EA	-	-	111	7	391	95	597
		TERMINATION - COMPRESSION LUG, #10, 2 HOLE, COPPER	2 CABLES x 3 x 2=	12.00 EA	-	-	165	10	564	137	865
		TERMINATION - COMPRESSION LUG, #40, 2 HOLE, COPPER	2 CABLES x 3 x 2=	12.00 EA	-	-	216	15	861	209	1,286
		600V CABLE & TERMINATION					80,747	1,406	83,380	20,198	184,325
		CABLE					80,747	1,406	83,380	20,198	184,325

TEC
 BIG BEND STATION
 UNIT 1 DEMOLITION

Estimator	GA
Labor rate table	20FL TAM DEMO
Project No.	A09476-073
Estimate Date	6/18/20
Reviewed By	BA
Approved By	BA
Estimate No.	35157A

Estimate No.: 351.57A
 Project No.: A09476-073
 Estimate Date: 6/18/20
 Prep/Rev/App: ON6A8A

TEC
 BIG BEND STATION
 UNIT 1 DEMOLITION



Group	Description	Subcontract Cost	Process Equipment Cost	Material Cost	Man Hours	Labor Cost	Equip Amount	Total Cost
10.00.00	WHOLE PLANT DEMOLITION	6,616,897			52,972	2,502,332	1,112,503	10,233,733
11.00.00	DEMOLITION				367	20,096	10,107	30,203
21.00.00	CIVIL WORK	595,310		64,178	226	10,368	10,471	680,328
22.00.00	CONCRETE	40,000						40,000
23.00.00	STEEL			316,965	1,921	105,117	52,866	474,948
	TOTAL DIRECT	7,254,207		381,143	55,486	2,637,914	1,185,947	11,459,211

DOCKET NO. 20210034-EI
 EXHIBIT NO. CRB-1
 WITNESS: BEITEL
 DOCUMENT NO. 1
 PAGE 38 OF 100
 FILED: 04/09/2021

TEC
 BIG BEND STATION
 UNIT 1 DEMOLITION



Estimate Totals

Description	Amount	Totals	Hours
Labor	2,637,914		55,486
Material	381,143		
Subcontract	7,254,207		
Construction Equipment	1,185,947		
Process Equipment		11,459,211	
General Conditions			
Additional Labor Costs			
90-1 Labor Supervision	158,275		
90-2 Show-up Time	52,758		
90-3 Cost Plus Fee 5-10%			
90-4 Cost Plus Fee 10-15%			
90-5 Per Diem			
Site Overheads			
91-1 Construction Management	571,014		
91-2 Field Office Expenses	62,677		
91-3 Material & Quality Control			
91-4 Site Services			
91-5 Safety	56,281		
91-6 Temporary Facilities	42,520		
91-7 Temporary Utilities			
91-8 Mobilization/Demob	45,127		
91-9 Legal Expenses/Claims	6,667		
Other Construction Indirects			
92-1 Small Tools & Consumables	28,489		
92-2 Scaffolding			
92-3 General Liability Insur.	28,489		
92-4 Constr. Equip. Mob/Demob	11,859		
92-5 Freight on Material	19,057		
92-6 Freight on Process Equip			
92-7 Insurance	367,372		
92-8 Contingency G&A	524,817		
92-9 Contractors Profit	1,975,702	13,434,913	
Project Indirect Costs			
93-1 Engineering Services			
93-2 CM Support			
93-3 Start-Up/Commissioning			
93-4 Start-Up/Spare Parts			
93-5 Excess Liability Insur.			
93-6 Sales Tax On Indirects	4,160,295		
93-7 Owners Cost			
93-8 EPC Fee	4,160,295	17,595,208	
Contingency			
94-1 Contingency on Const Eq	279,883		
94-3 Contingency on Material	93,647		
94-4 Contingency on Labor	862,611		
94-5 Contingency on Subcontr.	1,450,841		
94-6 Contingency on Process Eq			
94-7 Contingency on Indirect	832,059	21,114,249	
Escalation			
96-1 Escalation on Const Equip	81,110		
96-3 Escalation on Material	18,251		
96-4 Escalation on Labor	377,908		
96-5 Escalation on Subcontract	513,334		
96-6 Escalation on Process Equip			
96-7 Escalation on Indirects	257,936	22,362,788	
98 Interest During Constr	1,248,539		
Total		22,362,788	

Estimate No.: 35157A
 Project No.: A0976/073
 Estimate Date: 6/19/20
 Prepared By: GAB/BA

TEC
 BIG BEND STATION
 UNIT 1 DEMOLITION



Group	Phase	Description	Notes	Quantity	Subcontract Cost	Process Equipment Cost	Material Cost	Man Hours	Labor Cost	Equip Amount	Total Cost
10.00.00		WHOLE PLANT DEMOLITION									
10.21.00		CIVIL WORK									
		REMOVE GEOTEXTILE FABRIC	SCRAP PROCESSING AREA	5,220.00 SY	-	-	-	52	1,895	217	2,103
		CIVIL WORK						52	1,895	217	2,103
10.22.00		CONCRETE									
		BUILDING EQUIPMENT FOUNDATION/PAD		1,213.00 CY	-	-	-	2,456	135,147	53,204	188,351
		CONCRETE						2,456	135,147	53,204	188,351
10.23.00		STEEL									
		STRUCTURAL GIRT AND GALLERY STEEL	BOILER	2,347.00 TN	-	-	-	3,815	190,612	61,655	252,267
		STRUCTURAL GIRT AND GALLERY STEEL	PRECIP BOX	1,388.00 TN	-	-	-	1,807	90,270	29,199	119,469
		STRUCTURAL GIRT AND GALLERY STEEL	PRECIP STEEL	603.00 TN	-	-	-	796	39,790	12,871	52,661
		STRUCTURAL GIRT AND GALLERY STEEL	FGD (50% SPLIT BETWEEN UNITS 1 & 2)	389.00 TN	-	-	0	514	25,669	8,303	33,972
		STRUCTURAL GIRT AND GALLERY STEEL	FLY ASH SILO #1 AND STEEL (50% SPLIT UNIT 1 & 2)	46.00 TN	-	-	-	61	3,035	982	4,017
		STRUCTURAL GIRT AND GALLERY STEEL	BALANCED DRAFT STEEL	212.00 TN	-	-	-	280	13,989	4,525	18,514
		STRUCTURAL GIRT AND GALLERY STEEL	DUCTWORK REMOVAL	980.00 TN	-	-	-	1,255	62,868	20,277	83,145
		DUCTWORK AND STEEL SUPPORTS	DUCTWORK REMOVAL	1,640.00 TN	-	-	-	2,054	104,816	34,966	139,782
		STEEL	SCR DUCTWORK REMOVAL	764.00 TN	-	-	-	2,854	112,124	59,952	171,676
								16,281	753,621	311,790	1,065,411
10.25.00		CONCRETE CHIMNEY & STACK									
		CONCRETE CHIMNEY	50% OF WET STACK COST	0.50 LS	1,725,000	-	-	-	-	-	1,725,000
		CONCRETE CHIMNEY	50% DRY STACK COST	0.50 LS	150,000	-	-	-	-	-	150,000
		CONCRETE CHIMNEY & STACK			1,875,000						1,875,000
10.26.00		MISCELLANEOUS STRUCTURAL ITEM									
		PROTECT WFGD ELECTRICAL BUILDING		1.00 LS	125,000	-	-	-	-	-	125,000
		MISCELLANEOUS STRUCTURAL ITEM			125,000						125,000
10.31.00		MECHANICAL EQUIPMENT									
		MAIN BOILER AND APPURTENANCES	QUANTITY REFLECTS MATERIALS REMOVED BY MODERNIZATION PROJECT	7,500.00 TN	-	-	-	21,720	1,085,146	467,638	1,552,784
		FEEDWATER DEAIRATING EQUIPMENT	QUANTITY REFLECTS MATERIALS REMOVED BY MODERNIZATION PROJECT	147.00 TN	-	-	-	387	16,350	8,684	25,034
		BOP EQUIPMENT INCLUDING PUMPS, HEAT EXCHANGERS, AND VALVES, ETC.	QUANTITY REFLECTS MATERIALS REMOVED BY MODERNIZATION PROJECT	800.00 TN	-	-	-	2,106	88,979	47,259	136,237
		FEEDWATER AND OIL SYSTEMS, ETC.	QUANTITY REFLECTS MATERIALS REMOVED BY MODERNIZATION PROJECT	183.00 TN	-	-	-	482	20,354	10,810	31,164
		ASH / DUST COLLECTOR EQUIPMENT	DUST COLLECTOR CONVEYING EQUIPMENT INCLUDING BLOWERS, PUMPS, VALVES, ETC.	220.00 TN	-	-	-	579	24,469	12,996	37,465
		FGD EQUIPMENT						25,274	1,235,297	547,387	1,792,684
		MECHANICAL EQUIPMENT									
10.33.00		MATERIAL HANDLING EQUIPMENT									
		COAL HANDLING FACILITIES	50% SPLIT BETWEEN UNITS 1 & 2	1.00 LS	1,600,000	-	-	-	-	-	1,600,000
		MATERIAL HANDLING EQUIPMENT			1,600,000						1,600,000
10.35.00		PIPING									
		PIPING, VALVES AND HANGERS	QUANTITY REFLECTS MATERIALS REMOVED BY MODERNIZATION PROJECT, INCLUDING PIPING SYSTEMS WITHIN THE BOILER AND TURBINE AREA SUCH AS: MAIN STEAM, HOT/COLD REHEAT, BOILER FEED, FEEDWATER, CONDENSATE, SERVICE WATER, ETC.	1,500.00 TN	-	-	-	5,210	220,139	116,921	337,061
10.37.00		ASBESTOS REMOVAL									
		ASBESTOS ABATEMENT	COST PROVIDED BY TECO	1.00 LS	2,938,897	-	-	-	-	-	2,938,897
		ASBESTOS REMOVAL			2,938,897						2,938,897
10.41.00		ELECTRICAL EQUIPMENT									
		MISCELLANEOUS ELECTRICAL EQUIPMENT	MCC'S, CABINETS, PANELS, ETC.	256.00 TN	-	-	-	684	28,900	15,350	44,250
		ELECTRICAL EQUIPMENT						684	28,900	15,350	44,250
10.42.00		RACEWAY, CABLE TRAY, & CONDUIT									
		CONDUIT		76.00 TN	-	-	-	494	20,872	11,085	31,957

Estimate No.: 35157A
 Project No.: A09476-073
 Estimate Date: 6/19/23
 Prepared By: GAB/BA

TEC
 BIG BEND STATION
 UNIT 1 DEMOLITION



Group	Phase	Description	Notes	Quantity	Subcontract Cost	Process Equipment Cost	Material Cost	Man Hours	Labor Cost	Equip Amount	Total Cost
10.42.00	10.42.00	RACEWAY, CABLE TRAY, & CONDUIT		200.00 TN	-	-		1,200	50,700	26,928	77,628
		CABLE TRAY						1,694	71,572	38,013	109,585
		RACEWAY, CABLE TRAY, & CONDUIT									
10.43.00	10.43.00	CABLE		132.00 TN	-	-		1,320	55,770	29,621	85,391
		CABLE STRIPPABLE						1,320	55,770	29,621	85,391
		CABLE									
10.99.00	10.99.00	DEMOLITION, MISCELLANEOUS		1.00 LS	80,000	-					80,000
		DRAIN PROTECTION									
		DEMOLITION, MISCELLANEOUS									
11.00.00	11.00.00	WHOLE PLANT DEMOLITION			6,618,897			52,972	2,502,332	1,112,503	10,233,733
		DEMOLITION									
		STEEL									
11.23.00	11.23.00	STRUCTURAL STEEL	REMOVE TEMPORARY STEEL FOR SCR	75.00 TN	-	-		244	13,338	6,708	20,046
		STRUCTURAL STEEL	REMOVE TEMPORARY STEEL FOR BOILER	38.00 TN	-	-		124	6,758	3,399	10,157
		STEEL						367	20,096	10,107	30,203
21.00.00	21.00.00	DEMOLITION						367	20,096	10,107	30,203
		CIVIL WORK									
		STRIP & STOCKPILE									
21.14.00	21.14.00	STRIP TOPSOIL 4" DEEP 300 FT HAUL		1.08 AC	-	-		35	1,987	3,268	5,255
		STRIP CRUSHED ROCK 12" DEEP 300 FT HAUL		1.08 AC	-	-		35	1,987	3,268	5,255
		STRIP & STOCKPILE	STRIP ROCK SURFACING IN "SCRAP PROCESSING AREA"			69	3,974	6,536	10,510		
21.21.00	21.21.00	MASS FILL									
		MASS FILL, COMMON EARTH	BACKFILL COAL PILE AREA WITH 2.5 FT OF SOIL	22,250.00 CY	534,000						534,000
		MASS FILL									
21.41.00	21.41.00	SURFACING									
		CRUSHED ROCK SURFACING, 12" DEEP	SCRAP PROCESSING AREA	5,222.00 SY	-	-	55,614	104	4,508	3,718	63,840
		GEOTEXTILE FABRIC	SCRAP PROCESSING AREA	5,222.00 SY	-	-	8,564	52	1,886	217	10,668
21.47.00	21.47.00	SURFACING						157	6,394	3,935	74,568
		LANDSCAPING									
		HYDRO SEEDING	COAL PILE AREA	7.50 AC	17,310	-	-				17,310
21.52.00	21.52.00	LANDSCAPING									
		WASTE DISPOSAL									
		WASTE DISPOSAL									
22.00.00	22.00.00	CIVIL WORK									
		CIVIL WORK									
		CONCRETE									
22.13.00	22.13.00	CONCRETE									
		CONCRETE FLOOD WALL REPAIRS		1.00 LS	40,000	-	-				40,000
		CONCRETE									
23.00.00	23.00.00	STEEL									
		ROLLED SHAPE									
		STEEL									
23.25.00	23.25.00	STEEL									
		STEEL									
		STEEL									
23.94.00	23.94.00	STEEL									
		STEEL									
		STEEL									

TEC
 BIG BEND STATION
 UNIT 1 POST DEMOLITION

Estimator	GA
Labor rate table	20FLTAM DEMO
Project No.	A09476-073
Estimate Date	6/18/20
Reviewed By	BA
Approved By	BA
Estimate No.	35158A
Cost index	FLTAM

Estimate No.: 351.58A
 Project No.: A09476-073
 Estimate Date: 6/18/20
 Prep/Rev/App: ON6A8A

TEC
 BIG BEND STATION
 UNIT 1 POST DEMOLITION



Group	Description	Subcontract Cost	Process Equipment Cost	Material Cost	Man Hours	Labor Cost	Equip Amount	Total Cost
10.00.00	WHOLE PLANT DEMOLITION	250,000						250,000
21.00.00	CIVIL WORK			149,886	433	20,843	8,944	179,672
24.00.00	ARCHITECTURAL	1,272,000		23,200	503	23,154	3,692	1,322,046
27.00.00	PAINTING & COATING			103,500	7,970	371,974	44,629	520,103
41.00.00	ELECTRICAL EQUIPMENT	150,000						150,000
	TOTAL DIRECT	1,672,000		276,586	8,907	415,970	57,265	2,421,821

DOCKET NO. 20210034-EI
 EXHIBIT NO. CRB-1
 WITNESS: BEITEL
 DOCUMENT NO. 1
 PAGE 43 OF 100
 FILED: 04/09/2021

TEC
 BIG BEND STATION
 UNIT 1 POST DEMOLITION



Estimate Totals

Description	Amount	Totals	Hours
Labor	415,970		8,907
Material	276,586		
Subcontract	1,672,000		
Construction Equipment	57,265		
Process Equipment		2,421,821	
General Conditions			
Additional Labor Costs			
90-1 Labor Supervision	24,598		
90-2 Show-up Time	8,319		
90-3 Cost Plus Fee 5-10's	81,585		
90-4 Cost Plus Fee 10-15's			
90-5 Per Diem			
Site Overheads			
91-1 Construction Management	90,043		
91-2 Field Office Expenses	55,352		
91-3 Material&Quality Control	14,030		
91-4 Site Services	11,523		
91-5 Safety	8,875		
91-6 Temporary Facilities	6,752		
91-7 Temporary Utilities	7,358		
91-8 Mobilization/Demob	7,116		
91-9 Legal Expenses/Claims	1,051		
Other Construction Indirects			
92-1 Small Tools & Consumables	13,477		
92-2 Scaffolding	31,447		
92-3 General Liability Insur.	4,492		
92-4 Constr. Equip. Mob/Demob	573		
92-5 Freight on Material	13,829		
92-6 Freight on Process Equip			
92-7 Insurance	78,777		
92-8 Contingency G&A	112,538		
92-9 Contractors Profit	571,936	2,993,757	
Project Indirect Costs			
93-1 Engineering Services			
93-2 CM Support			
93-3 Start-Up/Commissioning			
93-4 Start-Up/Spare Parts			
93-5 Excess Liability Insur.			
93-6 Sales Tax On Indirects	617,695		
93-7 Owners Cost	617,695		
93-8 EPC Fee	617,695	3,611,452	
Contingency			
94-1 Contingency on Const Eq	13,515		
94-3 Contingency on Material	67,957		
94-4 Contingency on Labor	182,880		
94-5 Contingency on Subcontr.	334,400		
94-6 Contingency on Process Eq			
94-7 Contingency on Indirect	123,539		
	722,291	4,333,743	
Escalation			
96-1 Escalation on Const Equip	6,474		
96-3 Escalation on Material	40,989		
96-4 Escalation on Labor	133,320		
96-5 Escalation on Subcontract	231,621		
96-6 Escalation on Process Equip			
96-7 Escalation on Indirects	89,518		
	501,922	4,835,665	
98 Interest During Constr		4,835,665	
Total		4,835,665	

Estimate No.: 35159A
 Project No.: A09476-073
 Estimate Date: 6/19/20
 Prep/Rev/Appr: GAB/BA

TEC
 BIG BEND STATION
 UNIT 1 POST DEMOLITION



Group	Phase	Description	Notes	Quantity	Subcontract Cost	Process Equipment Cost	Material Cost	Man Hours	Labor Cost	Equip Amount	Total Cost
10.00.00	10.99.00	WHOLE PLANT DEMOLITION DEMOLITION, MISCELLANEOUS INSPECT CLEAN OUT AND REPAIR DRAINS DEMOLITION, MISCELLANEOUS WHOLE PLANT DEMOLITION		1.00 LS	250,000 250,000 250,000	-	-				250,000 250,000 250,000
21.00.00	21.57.00	CIVIL WORK ROAD, PARKING AREA, & SURFACED AREA BITUMINOUS ASPHALT (60,000 - 99,999 SF) ROAD, PARKING AREA, & SURFACED AREA CIVIL WORK	ASPHALT TO REPAVE REMOVED BOILER AREA AND TO THE SOUTH	1.514.00 TN	-	-	149,886 149,886	433 433	20,843 20,843	8,944 8,944	179,672 179,672
24.00.00	24.17.00	ARCHITECTURAL ELEVATOR PERSONNEL ELEVATOR ELEVATOR		1.00 LS	1,272,000 1,272,000	-	-				1,272,000 1,272,000
24.37.00	24.37.00	ROOFING REPAIR ROOF ROOFING	TURBINE BUILDING ROOF	2,400.00 SF	-	-	10,200 10,200	143 143	5,578 5,578	365 365	16,143 16,143
24.41.00	24.41.00	SIDING METAL UNINSULATED, 24 GA. GALVANIZED CORRUGATED CORRUGATED SIDING	CLOSING OPENINGS AND REPLACING SIDING AS REQUIRED	4,000.00 SF	-	-	13,000 13,000	361 361	17,576 17,576	3,326 3,326	33,903 33,903
27.00.00	27.17.00	PAINTING & COATING PAINTING STEEL PAINTING STEEL PAINTING PAINTING PAINTING & COATING	EXTERIOR PAINTING, POST DISMANTLEMENT INTERIOR PAINTING, TURBINE BUILDING	35,500.00 SF 68,000.00 SF	- -	- -	35,500 103,500	2,734 7,970	127,585 371,974	15,308 44,629	178,393 520,103
41.00.00	41.35.00	ELECTRICAL EQUIPMENT LIGHTNING PROTECTION LIGHTNING PROTECTION	ALLOWANCE	1.00 LS	100,000 100,000	-	-				100,000 100,000
41.37.00	41.37.00	LIGHTING ACCESSORY (FIXTURE) LIGHTING - FIXTURES, ACCESSORY LIGHTING ACCESSORY (FIXTURE) ELECTRICAL EQUIPMENT	ALLOWANCE	1.00 LS	50,000 50,000	-	-				50,000 50,000
					150,000						150,000

TEC
BIG BEND STATION
UNIT 1 ENGINEERING DEMOLITION SUPPORT

Estimator	GA
Labor rate table	20FLTAM DEMO
Project No.	A09476-073
Estimate Date	6/18/20
Reviewed By	BA
Approved By	BA
Estimate No.	35159A
Cost index	FLTAM

DOCKET NO. 20210034-EI
EXHIBIT NO. CRB-1
WITNESS: BEITEL
DOCUMENT NO. 1
PAGE 46 OF 100
FILED: 04/09/2021

Group	Description	Subcontract Cost	Process Equipment Cost	Material Cost	Man Hours	Labor Cost	Equip Amount	Total Cost
-------	-------------	------------------	------------------------	---------------	-----------	------------	--------------	------------

TEC
 BIG BEND STATION
 UNIT 1 ENGINEERING DEMOLITION SUPPORT



Estimate Totals

Description	Amount	Totals	Hours
Labor			
Material			
Subcontract			
Construction Equipment			
Process Equipment			
General Conditions			
Additional Labor Costs			
90-1 Labor Supervision			
90-2 Show-up Time			
90-3 Cost Plus 10% TO T 5-10's			
90-4 Cost Plus 10% TO T 6-10's			
90-5 Per Dem			
Site Overheads			
91-1 Construction Management			
91-2 Field Office Expenses			
91-3 Material&Quality Control			
91-4 Site Services			
91-5 Safety			
91-6 Temporary Facilities			
91-7 Temporary Utilities			
91-8 Mobilization/Demob			
91-9 Legal Expenses/Claims			
Other Construction Indirects			
92-1 Small Tools & Consumables			
92-2 Scaffolding			
92-3 General Liability Insur.			
92-4 Constr. Equip. Mob/Demob			
92-5 Freight on Material			
92-6 Freight on Process Equip			
92-7 Insurance			
92-8 Contractions G&A			
92-9 Contractions Profit			
Project Indirect Costs			
93-1 Engineering Services	1,480,250		
93-2 CM Support	1,225,000		
93-3 Start-Up/Commissioning			
93-4 Start-Up/Spare Parts			
93-5 Excess Liability Insur.			
93-6 Sales Tax On Indirects			
93-7 Overhead Cost			
93-8 EPC Fee		2,705,250	
Contingency			
94-1 Contingency on Const Eq			
94-3 Contingency on Material			
94-4 Contingency on Labor			
94-5 Contingency on Subcontr.			
94-6 Contingency on Process Eq			
94-7 Contingency on Indirect			
Escalation			
96-1 Escalation on Const Equip			
96-3 Escalation on Material			
96-4 Escalation on Labor			
96-5 Escalation on Subcontract			
96-6 Escalation on Process Equip			
96-7 Escalation on Indirects			
98 Interest During Constr	156,100		
Total		3,402,450	

TEC
 BIG BEND STATION
 UNIT 2 PRE DEMOLITION MODIFICATIONS

Estimator	GA
Labor rate table	20FLTAM DEMO
Project No.	A09476-073
Estimate Date	6/18/20
Reviewed By	BA
Approved By	BA
Estimate No.	35160A
Cost index	FLTAM

Estimate No.: 35160A
 Project No.: A09476-073
 Estimate Date: 6/18/20
 Prep/Rev/App: ONBABA

TEC
 BIG BEND STATION
 UNIT 2 PRE DEMOLITION MODIFICATIONS



Group	Description	Subcontract Cost	Process Equipment Cost	Material Cost	Man Hours	Labor Cost	Equip Amount	Total Cost
21.00.00	CIVIL WORK				53	3,102	833	3,935
22.00.00	CONCRETE			52,836	874	39,234	7,833	99,904
23.00.00	STEEL			199,355	4,230	231,491	96,237	527,084
35.00.00	PIPING	350,000						350,000
41.00.00	ELECTRICAL EQUIPMENT	130,000	2,800,000		3,357	181,107	38,466	3,149,573
42.00.00	RACEWAY, CABLE TRAY & CONDUIT	400,000		302,540	20,411	1,194,069	25,048	1,921,657
43.00.00	CABLE	300,000		913,553	12,935	766,932	185,779	2,166,264
44.00.00	CONTROL & INSTRUMENTATION	300,000						300,000
	TOTAL DIRECT	1,480,000	2,800,000	1,468,284	41,862	2,415,936	354,197	8,518,417

DOCKET NO. 20210034-EI
 EXHIBIT NO. CRB-1
 WITNESS: BEITEL
 DOCUMENT NO. 1
 PAGE 50 OF 100
 FILED: 04/09/2021

TEC
 BIG BEND STATION
 UNIT 2 PRE DEMOLITION MODIFICATIONS



Estimate Totals

Description	Amount	Totals	Hours
Labor	2,415,936		41,862
Material	1,468,284		
Subcontract	1,480,000		
Construction Equipment	354,197		
Process Equipment	2,800,000		
	8,518,417	8,518,417	
General Conditions			
Additional Labor Costs			
90-1 Labor Supervision	144,566		
90-2 Show-up Time	48,319		
90-3 Cost Plus 10% TO T 5-10's	472,653		
90-4 Cost Plus 10% TO T 6-10's			
90-5 Per Dem			
Site Overheads			
91-1 Construction Management	522,964		
91-2 Field Office Expenses	321,481		
91-3 Material&Quality Control	81,486		
91-4 Site Services	66,926		
91-5 Safety	51,545		
91-6 Temporary Facilities	39,216		
91-7 Temporary Utilities	42,574		
91-8 Mobilization/Demob	41,330		
91-9 Legal Expenses/Claims	6,106		
Other Construction Indirects			
92-1 Small Tools & Consumables	78,276		
92-2 Scaffolding	182,645		
92-3 General Liability Insur.	26,092		
92-4 Constr. Equip. Mob/Demob	3,542		
92-5 Freight on Material	73,414		
92-6 Freight on Process Equip			
92-7 Insurance	448,892		
92-8 Contractions G&A	641,274		
92-9 Contractions Profit	3,294,121	11,812,538	
Project Indirect Costs			
93-1 Engineering Services			
93-2 CM Support			
93-3 Start-Up/Commissioning	236,251		
93-4 Start-Up/Spare Parts			
93-5 Excess Liability/Insur.			
93-6 Sales Tax On Indirects			
93-7 Owners Cost			
93-8 EPC Fee			
	236,251	12,048,789	
Contingency			
94-1 Contingency on Const Eq	83,591		
94-3 Contingency on Material	360,757		
94-4 Contingency on Labor	1,062,160		
94-5 Contingency on Subcontr.	296,000		
94-6 Contingency on Process Eq	560,000		
94-7 Contingency on Indirect	47,280	14,455,547	
	2,409,736		
Escalation			
96-1 Escalation on Const Equip	7,650		
96-3 Escalation on Material	26,366		
96-4 Escalation on Labor	145,656		
96-5 Escalation on Subcontract	34,953		
96-6 Escalation on Process Equip			
96-7 Escalation on Indirects	9,239	14,682,411	
	223,864		
98 Interest During Constr			
		14,682,411	
Total		14,682,411	

Estimate No.: 35160A
 Project No.: A09476-073
 Estimate Date: 6/19/20
 Prep/Rev/Appr: GAB/BA

TEC
 BIG BEND STATION
 UNIT 2 PRE DEMOLITION MODIFICATIONS



Group	Phase	Description	Notes	Quantity	Subcontract Cost	Process Equipment Cost	Material Cost	Man Hours	Labor Cost	Equip Amount	Total Cost
21.00.00		CIVIL WORK									
21.17.00		EXCAVATION FOUNDATION EXCAVATION, COMMON EARTH USING 1 CY BACKHOE	65FT L x 24FT W X 3FTD FOUNDATION FOR PDC BUILDING	202.50 CY	-	-	-	33	1,941	522	2,463
		EXCAVATION						33	1,941	522	2,463
21.19.00		DISPOSAL DISPOSAL OF EXCESS MATERIAL USING DUMP TRUCK, 4 MI ROUND TRIP	65FT L x 24FT W X 3FTD FOUNDATION FOR PDC BUILDING	135.74 CY	-	-	-	9	521	140	660
		DISPOSAL						9	521	140	660
21.20.00		BACKFILL FOUNDATION BACKFILL, PREVIOUSLY EXCAVATED MATERIAL	65FT L x 24FT W X 3FTD FOUNDATION FOR PDC BUILDING	66.76 CY	-	-	-	11	640	172	812
		BACKFILL						11	640	172	812
		CIVIL WORK						53	3,102	833	3,935
22.00.00		CONCRETE									
22.13.00		CONCRETE MAT FOUNDATION LESS THAN 5 FT THICK, 4500 PSI	65FT L x 24FT W X 3FTD FOUNDATION FOR PDC BUILDING	173.33 CY	-	-	21,667	238	9,067	2,739	33,472
		CONCRETE						43	1,644	408	6,068
		CONCRETE						282	10,711	3,235	39,540
22.15.00		EMBEDMENT EMBEDMENTS, CARBON STEEL	65FT L x 24FT W X 3FTD FOUNDATION FOR PDC BUILDING	1,733.33 LB	-	-	5,200	95	4,123	198	9,480
		EMBEDMENT						17	737	28	1,896
		EMBEDMENT						112	4,860	186	11,176
22.17.00		FORMWORK BUILT UP INSTALL & STRIP	65FT L x 24FT W X 3FTD FOUNDATION FOR PDC BUILDING	534.00 SF	-	-	1,335	117	5,361	854	7,551
		FORMWORK						26	1,205	192	3,749
		FORMWORK						144	6,566	1,046	11,299
22.25.00		REINFORCING UNCOATED A615 GR60	65FT L x 24FT W X 3FTD FOUNDATION FOR PDC BUILDING	13.00 TN	-	-	13,325	257	13,075	2,574	28,974
		REINFORCING						79	4,023	702	8,915
		REINFORCING						337	17,098	3,366	37,889
		CONCRETE						874	39,234	7,833	99,904
23.00.00		STEEL									
23.25.00		ROLLED SHAPE MEDIUM WEIGHT MEMBERS, 21 LB/LF TO 40 LB/LF, GALVANIZED	BRACING FOR ADDITIONS	41.00 TN	-	-	129,355	1,150	62,937	19,181	211,473
		ROLLED SHAPE						3,080	168,554	77,066	315,610
		STEEL						4,230	231,491	96,237	527,084
		STEEL						4,230	231,491	96,237	527,084
35.00.00		PIPING									
35.13.45		MISC. ABOVE GROUND, PROCESS AREA MODIFICATIONS TO EXISTING PIPE SYSTEMS, NATURAL GAS, STEAM, CONDENSATE, PROCESS WATER, AIR, PROTECTION, SERVICE WATER, COMPRESS AIR AND GASES PIPING		1.00 LS	350,000	-	-				350,000
		MISC. ABOVE GROUND, PROCESS AREA									
		PIPING									
		PIPING									
		ELECTRICAL EQUIPMENT									
41.00.00											

Estimate No.: 35160A
 Project No.: A09476-073
 Estimate Date: 6/19/20
 Prep/Rev/Appr: GAB/BA

TEC
 BIG BEND STATION
 UNIT 2 PRE DEMOLITION MODIFICATIONS



Group	Phase	Description	Notes	Quantity	Subcontract Cost	Process Equipment Cost	Material Cost	Man Hours	Labor Cost	Equip Amount	Total Cost
41.45.00		MOTOR CONTROL CENTER (MCC), COMPLETE 1600A, 480V (MCC-A)	(15) VERTICAL SECTIONS, MAIN BREAKER, STARTERS, FUSED DISCONNECTS, INSTALL IN PDC ENCLOSURE	1.00 EA	-	150,000	-	360	19,210	1,148	170,358
		1600A, 480V (MCC-B)	(15) VERTICAL SECTIONS, MAIN BREAKER, STARTERS, FUSED DISCONNECTS, INSTALL IN PDC ENCLOSURE	1.00 EA	-	150,000	-	360	19,210	1,148	170,358
		CALIBRATION, LOAD ADJUSTMENT, TESTING	INSTALL IN PDC ENCLOSURE TEST & DOCUMENTATION	1.00 LT	-	-	-	53	3,131	768	3,889
		MOTOR CONTROL CENTER (MCC), COMPLETE				300,000		773	41,550	3,055	344,605
41.47.00		PANEL: CONTROL, DISTRIBUTION, & RELAY STATION RESERVE SYSTEM RECONFIGURATION	ALLOWANCE	1.00 LS	100,000	-	-				100,000
		PANEL: CONTROL, DISTRIBUTION, & RELAY			100,000						100,000
41.51.00		POWER TRANSFORMER 2500/3333 KVA, 4160V-480V DRY TYPE TRANSFORMER, A	INSTALL ON BOTH END OF SUBSTATION - INSTALL INSIDE OF PDC BUILDING (ALLOWANCE)	2.00 EA	-	300,000	-	330	17,558	4,883	322,241
		2500/3333 KVA, 4160V-480V DRY TYPE TRANSFORMER, B	INSTALL ON BOTH END OF SUBSTATION - INSTALL INSIDE OF PDC BUILDING (ALLOWANCE)	2.00 EA	-	300,000	-	330	17,558	4,883	322,241
		POWER TRANSFORMER				600,000		660	35,116	9,366	644,482
41.52.00		POWER DISTRIBUTION CENTER (PDC) POWER DISTRIBUTION CENTER (PDC)	ASSUMED 1600SF. INCLUDING: HVAC, LIGHTING, COMMUNICATION, FIRE ALARM, POWER BACKUP UPS SYSTEMS, ASSOCIATED CONDUIT WIRE AND STAIRS, 8" MIN. THICK SIDE OF PREFAB. ENCLOSURE W/ STEEL FRAME SUPPORT (ALLOWANCE)	1.560.00 SF	-	750,000	-	858	46,954	21,466	818,420
		POWER DISTRIBUTION CENTER (PDC)			30,000	750,000		858	46,954	21,466	848,420
41.55.00		SWITCHGEAR, COMPLETE 4000A, 480V, SWITCHGEAR: A DOUBLE END SUBSTATION	(4) VERTICAL SECTIONS, (2) MAIN BREAKERS, (1) 4000A BREAKER, INSTALL IN PDC ENCLOSURE	1.00 LS	-	275,000	-	240	12,806	766	288,572
		4000A, 480V, SWITCHGEAR: B DOUBLE END SUBSTATION	(4) VERTICAL SECTIONS, (2) MAIN BREAKERS, (1) 400A BREAKER, INSTALL IN PDC ENCLOSURE	1.00 LS	-	275,000	-	240	12,806	766	288,572
		3000A, 4160V, SWITCHGEAR: A DOUBLE END SUBSTATION	(4) VERTICAL SECTIONS, INSTALL IN PDC ENCLOSURE	1.00 LS	-	300,000	-	240	12,806	766	313,572
		3000A, 4160V, SWITCHGEAR: B DOUBLE END SUBSTATION	(4) VERTICAL SECTIONS, INSTALL IN PDC ENCLOSURE	1.00 LS	-	300,000	-	240	12,806	766	313,572
		CALIBRATION, LOAD ADJUSTMENT, TESTING	TEST & DOCUMENTATION	1.00 LS	-	-	-	106	6,262	1,517	7,778
		SWITCHGEAR, COMPLETE				1,150,000		1,066	57,487	4,579	1,212,066
		ELECTRICAL EQUIPMENT			130,000	2,800,000		3,357	181,107	38,466	3,149,573
42.00.00		RACEWAY, CABLE TRAY & CONDUIT CABLE TRAY COVER, GALVANIZED STEEL 36 IN WIDE INCLUDING FITTINGS	RACEWAY TO THE NEW 4.16KB GEAR	2,000.00 LF	-	-	13,240	385	22,525	473	36,237
42.13.06		CABLE TRAY COVER, GALVANIZED STEEL					13,240	385	22,525	473	36,237
42.13.47		CABLE TRAY, GALVANIZED STEEL 36 IN WIDE LADDER TYPE INCLUDING SUPPORTS AND FITTINGS	RACEWAY TO THE NEW 4.16KB GEAR	3,000.00 LF	-	-	103,560	6,941	406,025	8,517	518,102
		CABLE TRAY, GALVANIZED STEEL					103,560	6,941	406,025	8,517	518,102
42.15.13		CONDUIT, ALUMINUM 1 IN DIA INCLUDING ELBOWS, UNISTRUT SUPPORTS, AND MISC HARDWARE 1-1/2 IN DIA INCLUDING ELBOWS, UNISTRUT SUPPORTS, AND MISC HARDWARE 2 IN DIA INCLUDING ELBOWS, UNISTRUT SUPPORTS, AND MISC HARDWARE		37,000.00 LF	-	-	104,340	8,751	511,955	10,739	627,035
				4,000.00 LF	-	-	18,800	1,127	65,901	1,382	86,083
				4,000.00 LF	-	-	25,600	1,395	81,604	1,712	108,916

Estimate No.: 35160A
 Project No.: A09476-073
 Estimate Date: 6/19/20
 Prep/Rev/Appr: GAB/BA

TEC
 BIG BEND STATION
 UNIT 2 PRE DEMOLITION MODIFICATIONS



Group	Phase	Description	Notes	Quantity	Subcontract Cost	Process Equipment Cost	Material Cost	Man Hours	Labor Cost	Equip Amount	Total Cost
42.15.13		CONDUIT, ALUMINUM	2-1/2" DIA INCLUDING ELBOWS, UNISTRUT SUPPORTS, AND MISC HARDWARE	4,000.00 LF	-	-	37,000	1,813	106,059	2,225	145,284
		MISCELLANEOUS SIZE CONDUITS	ALLOWANCE	1.00 LS	400,000	-	-	-	-	-	400,000
		CONDUIT, ALUMINUM			400,000		185,740	13,086	765,520	16,068	1,367,318
		RACEWAY, CABLE TRAY & CONDUIT			400,000		302,540	20,411	1,194,069	25,048	1,921,657
43.00.00		CABLE									
43.10.00		CONTROL INSTRUMENTATION/COMMUNICATION									
		CABLE & TERMINATION	ALLOWANCE	1.00 LS	200,000	-	-	0	0	0	200,000
		CABLES + TERMINATION	ALLOWANCE	1.00 LS	100,000	-	-	0	0	0	100,000
		CONTROL INSTRUMENTATION/COMMUNICATION			300,000			0	0	0	300,000
43.20.00		600V CABLE & TERMINATION									
		600V #10 3/C CU XLPE LSZH	36 CABLES x 1000FT=	36,000.00 LF	-	-	51,840	1,109	65,747	15,926	133,514
		600V #8 3/C CU EPRTS-CPE	22 CABLES x 1000FT=	22,000.00 LF	-	-	41,580	774	45,919	11,123	98,622
		600V #6 3/C CU EPRTS-CPE	11 CABLES x 1000FT=	11,000.00 LF	-	-	27,060	557	33,004	7,985	68,059
		600V #4 3/C CU EPRTS-CPE	4 CABLES x 1000FT=	4,000.00 LF	-	-	12,280	238	14,089	3,413	29,782
		600V #10 3/C W/G CU EPRTS-CPE	8 CABLES x 1000FT=	8,000.00 LF	-	-	46,800	686	40,701	9,859	97,360
		600V #40 3/C CU	6 CABLES x 1000FT=	6,000.00 LF	-	-	70,920	640	37,961	9,196	118,077
		600V #750 KCMIL 3/C CU	FOR TURBINE SHOP FEEDER	1,000.00 LF	-	-	29,350	274	16,241	3,934	49,525
		TERMINATION - COMPRESSION LUG, #10, 1 HOLE, COPPER	36 CABLES x 3 x 2=	216.00 EA	-	-	475	59	3,522	853	4,851
		TERMINATION - COMPRESSION LUG, #8, 2 HOLE, COPPER	22 CABLES x 3 x 2=	132.00 EA	-	-	858	44	2,553	626	4,067
		TERMINATION - COMPRESSION LUG, #6, 2 HOLE, COPPER	11 CABLES x 3 x 2=	66.00 EA	-	-	594	29	1,722	417	2,733
		TERMINATION - COMPRESSION LUG, #4, 2 HOLE, COPPER	4 CABLES x 3 x 2=	24.00 EA	-	-	222	13	783	190	1,194
		TERMINATION - COMPRESSION LUG, #4, 2 HOLE, COPPER	8 CABLES x 3 x 2=	48.00 EA	-	-	660	38	2,254	546	3,460
		TERMINATION - COMPRESSION LUG, #4/0, 2 HOLE, COPPER	6 CABLES x 3 x 2=	36.00 EA	-	-	648	44	2,553	626	3,857
		TERMINATION - COMPRESSION LUG, #750, 2 HOLE, COPPER	FOR TURBINE SHOP FEEDER TERMINATIONS	6.00 EA	-	-	372	20	1,186	287	1,945
		600V CABLE & TERMINATION					283,659	4,525	268,295	64,991	616,945
43.40.00		5/8KV CABLE & TERMINATION									
		5KV #10 3/C CU EPRTS-CPE	FOR AIR COMPRESSOR-3	1,000.00 LF	-	-	12,550	79	4,664	1,130	18,343
		5/8KV #500 KCMIL 1/C CU	48 CABLES, CROSS TIE BETWEEN UNIT 1 SWITCHGEAR TO UNIT 4 EXISTING SWITCHGEAR FOR RESERVE 1 CONNECTION, CROSS TIE BETWEEN UNIT 1 RESERVE SWITCHGEAR TO RESERVE 3 CONNECTION, FOR MAIN FEEDER TO 4180V SWITCHGEAR - (2) X 2 CIRCUIT 12 CABLES x 1000FT, FOR NEW 4.18KV SWITCHGEAR "A" FEED 12 CABLES x 1000FT, FOR NEW 4.18KV SWITCHGEAR "B" FEED FOR AIR COMPRESSOR-3	48,000.00 LF	-	-	318,240	4,488	2,661,200	64,464	648,324
		5/8KV #750 KCMIL 1/C CU	CROSS TIE BETWEEN UNIT 1 SWITCHGEAR FOR RESERVE 1	6,000.00 LF	-	-	58,380	640	37,961	9,196	105,137
		5/8KV #750 KCMIL 1/C CU	FOR MAIN FEEDER TO 4180V SWITCHGEAR - (2) X 2 CIRCUIT 12 CABLES x 1000FT, FOR NEW 4.18KV SWITCHGEAR "A" FEED	12,000.00 LF	-	-	116,760	1,281	75,923	18,391	211,074
		5/8KV #750 KCMIL 1/C CU	12 CABLES x 1000FT, FOR NEW 4.18KV SWITCHGEAR "B" FEED FOR AIR COMPRESSOR-3	12,000.00 LF	-	-	116,760	1,281	75,923	18,391	211,074
		TERMINATION - COMPRESSION LUG, #1/0, 2 HOLE, COPPER	CROSS TIE BETWEEN UNIT 1 SWITCHGEAR TO UNIT 4 EXISTING SWITCHGEAR FOR RESERVE 1	6.00 EA	-	-	84	13	783	190	1,096
		TERMINATION - COMPRESSION LUG, #500, 2 HOLE, COPPER	CROSS TIE BETWEEN UNIT 1 SWITCHGEAR TO UNIT 4 EXISTING SWITCHGEAR FOR RESERVE 1	96.00 EA	-	-	3,648	349	20,663	5,005	29,317
		5/8KV CABLE & TERMINATION									
		5/8KV CABLE & TERMINATION	TERMINATION - COMPRESSION LUG, #750, 2 HOLE, COPPER	8.00 EA	-	-	486	40	2,372	574	3,442
		5/8KV CABLE & TERMINATION	TERMINATION - COMPRESSION LUG, #750, 2 HOLE, COPPER	48.00 EA	-	-	2,976	240	14,230	3,447	20,653
		5/8KV CABLE & TERMINATION					629,894	8,410	498,637	120,788	1,249,320



TEC
BIG BEND STATION
UNIT 2 PRE DEMOLITION MODIFICATIONS

Estimate No.: 35160A
Project No.: A09476-073
Estimate Date: 6/19/20
Prep/Rev/Appr: GAB/BA

Group	Phase	Description	Notes	Quantity	Subcontract Cost	Process Equipment Cost	Material Cost	Man Hours	Labor Cost	Equip Amount	Total Cost
44,00.00	44.13.00	CABLE CONTROL & INSTRUMENTATION CONTROL SYSTEM DISTRIBUTED CONTROL SYSTEM, RE-PROGRAMMING COST	SERVICE BY VENDOR (ALLOWANCE)	1.00 EA	300,000		913,553	12,935	766,932	185,779	2,166,264
		CONTROL SYSTEM			300,000						300,000
		CONTROL & INSTRUMENTATION			300,000						300,000

TEC
BIG BEND STATION
UNIT 2 DEMOLITION

Estimator	GA
Labor rate table	20FL TAM DEMO
Project No.	A09476-073
Estimate Date	6/18/20
Reviewed By	BA
Approved By	BA
Estimate No.	35161A

DOCKET NO. 20210034-EI
EXHIBIT NO. CRB-1
WITNESS: BEITEL
DOCUMENT NO. 1
PAGE 56 OF 100
FILED: 04/09/2021

Estimate No.: 35161A
 Project No.: A09476-073
 Estimate Date: 6/18/20
 Prep/Rev/App: ON6ABA

TEC
 BIG BEND STATION
 UNIT 2 DEMOLITION



Group	Description	Subcontract Cost	Process Equipment Cost	Material Cost	Man Hours	Labor Cost	Equip Amount	Total Cost
10.00.00	WHOLE PLANT DEMOLITION	7,333,198			60,553	2,818,845	1,285,679	11,437,722
11.00.00	DEMOLITION				374	20,452	10,286	30,737
21.00.00	CIVIL WORK	595,310						595,310
22.00.00	CONCRETE	40,000		206,055	1,085	41,254	13,708	301,017
23.00.00	STEEL			322,575	1,955	106,978	53,802	483,354
	TOTAL DIRECT	7,968,508		528,630	63,966	2,987,528	1,363,475	12,848,141

DOCKET NO. 20210034-EI
 EXHIBIT NO. CRB-1
 WITNESS: BEITEL
 DOCUMENT NO. 1
 PAGE 57 OF 100
 FILED: 04/09/2021

TEC
 BIG BEND STATION
 UNIT 2 DEMOLITION



Estimate Totals

Description	Amount	Totals	Hours
Labor	2,987,528		63,966
Material	528,630		
Subcontract	7,988,508		
Construction Equipment	1,383,475		
Process Equipment		12,848,141	
General Conditions			
Additional Labor Costs			
90-1 Labor Supervision	179,252		
90-2 Show-up Time	59,751		
90-3 Cost Plus Fee 5-10's			
90-4 Cost Plus Fee 10-15's			
90-5 Per Diem			
Site Overheads			
91-1 Construction Management	646,694		
91-2 Field Office Expenses	70,984		
91-3 Material&Quality Control			
91-4 Site Services			
91-5 Safety	63,740		
91-6 Temporary Facilities	48,495		
91-7 Temporary Utilities			
91-8 Mobilization/Demob	51,108		
91-9 Legal Expenses/Claims	7,550		
Other Construction Indirects			
92-1 Small Tools & Consumables	32,265		
92-2 Scaffolding			
92-3 General Liability Insur.	32,265		
92-4 Constr. Equip. Mob/Demob	13,635		
92-5 Freight on Material	26,432		
92-6 Freight on Process Equip			
92-7 Insurance	424,613		
92-8 Contractions G&A	606,590		
92-9 Contractions Profit	2,263,374	15,111,515	
Project Indirect Costs			
93-1 Engineering Services			
93-2 CM Support			
93-3 Start-Up/Commissioning			
93-4 Start-Up/Spare Parts			
93-5 Excess Liability Insur.			
93-6 Sales Tax On Indirects	2,945,415		
93-7 Overhead Cost	2,945,415	18,056,930	
93-8 EPC Fee			
Contingency			
94-1 Contingency on Const Eq	321,780		
94-3 Contingency on Material	129,884		
94-4 Contingency on Labor	976,937		
94-5 Contingency on Subcontr.	1,593,702		
94-6 Contingency on Process Eq			
94-7 Contingency on Indirect	589,033		
	3,611,566	21,668,316	
Escalation			
96-1 Escalation on Const Equip	103,304		
96-3 Escalation on Material	28,641		
96-4 Escalation on Labor	474,683		
96-5 Escalation on Subcontract	602,941		
96-6 Escalation on Process Equip			
96-7 Escalation on Indirects	248,669		
	1,458,238	23,126,554	
98 Interest During Constr		23,126,554	
Total		23,126,554	

Estimate No.: 35161A
 Project No.: A09476-073
 Estimate Date: 6/19/20
 Prepared By: GAB/BA

TEC
 BIG BEND STATION
 UNIT 2 DEMOLITION



Group	Phase	Description	Notes	Quantity	Subcontract Cost	Process Equipment Cost	Material Cost	Man Hours	Labor Cost	Equip Amount	Total Cost
10.00.00	10.22.00	WHOLE PLANT DEMOLITION									
		CONCRETE		1,130.00 CY	-	-		2,288	125,900	49,564	175,463
		BUILDING/EQUIPMENT FOUNDATION/PAD						2,288	125,900	49,564	175,463
		CONCRETE									
10.23.00		STEEL									
		STRUCTURAL, GIRT AND GALLERY STEEL	BOILER	2,347.00 TN	-	-		3,815	190,612	61,655	252,267
		STRUCTURAL, GIRT AND GALLERY STEEL	PRECIP BOX	1,292.00 TN	-	-		1,706	85,255	27,577	112,832
		STRUCTURAL, GIRT AND GALLERY STEEL	PRECIP STEEL	401.00 TN	-	-		530	26,461	8,559	35,020
		STRUCTURAL, GIRT AND GALLERY STEEL	FGD (50% SPLIT UNIT 1 & 2)	389.00 TN	-	-		514	25,669	8,303	33,972
		STRUCTURAL, GIRT AND GALLERY STEEL	PLY ASH SILO #1 AND STEEL (50% SPLIT UNIT 1 & 2)	46.00 TN	-	-		61	3,035	982	4,017
		STRUCTURAL, GIRT AND GALLERY STEEL	UNBALANCED DRAFT STEEL	243.00 TN	-	-		321	16,035	5,187	21,222
		STRUCTURAL, GIRT AND GALLERY STEEL	SCR	950.00 TN	-	-		1,255	62,888	20,277	82,965
		DEMO CIRCULATING WATER DISCHARGE STRUCTURE		1.00 LS	500,000	-		5,332	225,276	119,650	500,000
		DUCTWORK AND STEEL SUPPORTS	DUCTWORK REMOVAL	1,535.00 TN	-	-		2,654	112,124	59,552	171,676
		DUCTWORK AND STEEL SUPPORTS	SCR DUCTWORK REMOVAL	764.00 TN	-	-		16,187	747,155	311,740	1,558,896
		STEEL			500,000						
10.25.00		CONCRETE CHIMNEY & STACK									
		CONCRETE CHIMNEY	50% OF WET STACK COST	0.50 LS	1,725,000	-					1,725,000
		CONCRETE CHIMNEY	50% OF DRY STACK COST	0.50 LS	150,000	-					150,000
		CONCRETE CHIMNEY & STACK			1,875,000						1,875,000
10.26.00		MISCELLANEOUS STRUCTURAL ITEM									
		PROTECT WFGD ELECTRICAL BUILDING		1.00 LS	125,000	-					125,000
		MISCELLANEOUS STRUCTURAL ITEM			125,000						125,000
10.31.00		MECHANICAL EQUIPMENT									
		MAIN BOILER AND APPURTENANCES		8,279.00 TN	-	-		21,794	1,089,852	489,235	1,588,086
		STEAM TURBINE GENERATOR		1,392.00 TN	-	-		3,664	154,823	52,230	207,053
		STEAM TURBINE CONDENSER		1,447.00 TN	-	-		3,742	163,350	53,634	216,984
		BOP EQUIPMENT INCLUDING PUMPS, HEAT EXCHANGERS, COMPRESSORS, TANKS, CHEMICAL FEED, WATER AND OIL SYSTEMS, ETC.		1,043.00 TN	-	-		2,746	116,366	61,619	177,985
		ASH / DUST COLLECTOR EQUIPMENT		183.00 TN	-	-		482	20,354	10,810	31,164
		FGD EQUIPMENT		220.00 TN	-	-		579	24,469	12,996	37,465
		CONDENSER		349.00 TN	-	-		919	38,817	20,617	59,433
		MECHANICAL EQUIPMENT						30,571	1,459,670	666,185	2,125,855
10.33.00		MATERIAL HANDLING EQUIPMENT									
		COAL HANDLING FACILITIES	50% SPLIT BETWEEN UNITS 1 & 2	1.00 LS	1,600,000	-					1,600,000
		MATERIAL HANDLING EQUIPMENT			1,600,000						1,600,000
10.35.00		PIPING									
		PIPING, VALVES AND HANGERS	INCLUDES ALL PIPING SYSTEMS WITHIN THE BOILER AND TURBINE AREA SUCH AS: MAIN STEAM, HOT/COLD REHEAT, BOILER FEED, FEEDWATER, CONDENSATE, SERVICE WATER, ETC.	1,832.00 TN	-	-		6,364	269,864	142,800	411,664
10.37.00		ASBESTOS REMOVAL									
		ASBESTOS ABATEMENT	COST PROVIDED BY TECO	1.00 LS	3,153,198	-					3,153,198
		ASBESTOS REMOVAL			3,153,198						3,153,198
10.41.00		ELECTRICAL EQUIPMENT									
		TRANSFORMERS	GSUIT, PRD, SST	40.00 TN	-	-		107	4,516	2,308	6,914
		MISCELLANEOUS ELECTRICAL EQUIPMENT	MCC'S, SWITCHGEAR, BATTERIES, CABINETS, PANELS, MOTORS, ETC.	368.00 TN	-	-		983	41,544	22,065	63,609
		ELECTRICAL EQUIPMENT						1,090	46,060	24,464	70,523
10.42.00		RACEWAY, CABLE TRAY, & CONDUIT									
		CABLE TRAY		168.00 TN	-	-		1,092	46,137	24,454	70,641
		RACEWAY, CABLE TRAY, & CONDUIT		200.00 TN	-	-		1,290	55,100	28,928	77,628
		CABLE						2,292	96,837	51,432	148,269

Estimate No.: 35161A
 Project No.: A09476-073
 Estimate Date: 6/16/20
 Prepared By: GAB/BA

TEC
 BIG BEND STATION
 UNIT 2 DEMOLITION



Group	Phase	Description	Notes	Quantity	Subcontract Cost	Process Equipment Cost	Material Cost	Man Hours	Labor Cost	Equip Amount	Total Cost
10.43.00	CABLE	CABLE STRIPPABLE		176.00 TN	-	-	-	1,760	74,360	39,494	113,854
	CABLE	CABLE						1,760	74,360	39,494	113,854
10.99.00	DEMOLITION, MISCELLANEOUS	DEMOLITION, MISCELLANEOUS									
	DEMOLITION, MISCELLANEOUS	DEMOLITION, MISCELLANEOUS		1.00 LS	80,000	-	-				80,000
	DEMOLITION, MISCELLANEOUS	DEMOLITION, MISCELLANEOUS			80,000	-	-				80,000
	DEMOLITION, MISCELLANEOUS	DEMOLITION, MISCELLANEOUS			7,333,198	-	-	60,553	2,818,845	1,285,679	11,437,722
	DEMOLITION, MISCELLANEOUS	DEMOLITION, MISCELLANEOUS									
11.00.00	DEMOLITION	DEMOLITION									
	STEEL	STEEL									
11.23.00	STEEL	STRUCTURAL STEEL	REMOVE TEMPORARY STEEL FOR SCR	77.00 TN	-	-	-	250	13,694	6,887	20,581
	STEEL	STRUCTURAL STEEL	REMOVE TEMPORARY STEEL FOR BOILER	38.00 TN	-	-	-	124	6,758	3,389	10,157
	STEEL	STEEL						374	20,452	10,286	30,737
	STEEL	STEEL						374	20,452	10,286	30,737
21.00.00	CIVIL WORK	CIVIL WORK									
	MASS FILL	MASS FILL									
21.21.00	MASS FILL	MASS FILL, COMMON EARTH	BACKFILL COAL PILE AREA WITH 2.5 FT OF SOIL	22,250.00 CY	534,000	-	-				534,000
	MASS FILL	MASS FILL			534,000	-	-				534,000
21.47.00	LANDSCAPING	LANDSCAPING									
	LANDSCAPING	LANDSCAPING		7.50 AC	17,310	-	-				17,310
	LANDSCAPING	LANDSCAPING			17,310	-	-				17,310
21.52.00	WASTE DISPOSAL	WASTE DISPOSAL									
	WASTE DISPOSAL	WASTE DISPOSAL		4,000.00 CY	44,000	-	-				44,000
	WASTE DISPOSAL	WASTE DISPOSAL			44,000	-	-				44,000
	WASTE DISPOSAL	WASTE DISPOSAL			595,310	-	-				595,310
22.00.00	CONCRETE	CONCRETE									
	CONCRETE	CONCRETE									
22.13.00	CONCRETE	CONCRETE									
	CONCRETE	CONCRETE		2,169.00 CY	-	-	206,055	1,085	41,254	13,708	261,017
	CONCRETE	CONCRETE		1.00 LS	40,000	-	206,055	1,085	41,254	13,708	301,017
	CONCRETE	CONCRETE			40,000	-	206,055	1,085	41,254	13,708	301,017
23.00.00	STEEL	STEEL									
	ROLLED SHAPE	ROLLED SHAPE									
23.25.00	ROLLED SHAPE	ROLLED SHAPE									
	ROLLED SHAPE	ROLLED SHAPE		77.00 TN	-	-	215,985	1,309	71,628	36,024	323,637
	ROLLED SHAPE	ROLLED SHAPE		38.00 TN	-	-	106,590	646	35,349	17,778	159,717
	ROLLED SHAPE	ROLLED SHAPE					322,575	1,955	106,978	53,802	483,354
	ROLLED SHAPE	ROLLED SHAPE					322,575	1,955	106,978	53,802	483,354

TEC
 BIG BEND STATION
 UNIT 2 POST DEMOLITION

Estimator	GA
Labor rate table	20FLTAM DEMO
Project No.	A09476-073
Estimate Date	6/18/20
Reviewed By	BA
Approved By	BA
Estimate No.	35162A
Cost index	FLTAM

Estimate No.: 35162A
 Project No.: A09476-073
 Estimate Date: 6/18/20
 Prep/Rev/App: ON6A8A

TEC
 BIG BEND STATION
 UNIT 2 POST DEMOLITION



Group	Description	Subcontract Cost	Process Equipment Cost	Material Cost	Man Hours	Labor Cost	Equip Amount	Total Cost
10.00.00	WHOLE PLANT DEMOLITION							
21.00.00	CIVIL WORK	250,000		145,431	420	20,223	8,678	250,000
23.00.00	STEEL			776,909	5,779	315,023	74,998	174,332
24.00.00	ARCHITECTURAL			23,888	729	31,993	4,920	1,166,930
27.00.00	PAINTING & COATING			103,500	7,970	371,974	44,629	60,801
41.00.00	ELECTRICAL EQUIPMENT							520,103
	TOTAL DIRECT	250,000		1,049,727	14,899	739,213	133,225	250,000
		500,000						2,422,166

DOCKET NO. 20210034-EI
 EXHIBIT NO. CRB-1
 WITNESS: BEITEL
 DOCUMENT NO. 1
 PAGE 62 OF 100
 FILED: 04/09/2021

TEC
 BIG BEND STATION
 UNIT 2 POST DEMOLITION



Estimate Totals

Description	Amount	Totals	Hours
Labor	739,213		14,899
Material	1,049,727		
Subcontract	500,000		
Construction Equipment	133,225		
Process Equipment		2,422,165	
General Conditions			
Additional Labor Costs			
90-1 Labor Supervision	44,400		
90-2 Show-up Time	14,800		
90-3 Cost Plus Fee 5-10's	144,500		
90-4 Cost Plus Fee 10-15's			
90-5 Per Diem			
Site Overheads			
91-1 Construction Management	160,000		
91-2 Field Office Expenses	98,400		
91-3 Material/Quality Control	24,500		
91-4 Site Services	20,500		
91-5 Safety	15,800		
91-6 Temporary Facilities	12,000		
91-7 Temporary Utilities	12,000		
91-8 Mobilization/Demob	12,600		
91-9 Legal Expenses/Claims	1,900		
Other Construction Indirects			
92-1 Small Tools & Consumables	24,000		
92-2 Scaffolding	55,900		
92-3 General Liability Insur.	8,000		
92-4 Constr. Equip. Mob/Demob	1,300		
92-5 Freight on Material	52,500		
92-6 Freight on Process Equip			
92-7 Insurance	183,200		
92-8 Contractions G&A	261,700		
92-9 Contractions Profit	1,149,600	3,571,765	
Project Indirect Costs			
93-1 Engineering Services			
93-2 CM Support			
93-3 Start-Up/Commissioning			
93-4 Start-Up/Spare Parts			
93-5 Excess Liability Insur.			
93-6 Sales Tax On Indirects			
93-7 Overhead Cost			
93-8 EPC Fee	733,370	4,305,135	
Contingency			
94-1 Contingency on Const Eq	31,400		
94-3 Contingency on Material	257,900		
94-4 Contingency on Labor	325,000		
94-5 Contingency on Subcontr.	100,000		
94-6 Contingency on Process Eq			
94-7 Contingency on Indirect	146,700	5,165,155	
Escalation			
96-1 Escalation on Const Equip	11,600		
96-3 Escalation on Material	120,000		
96-4 Escalation on Labor	182,500		
96-5 Escalation on Subcontract	57,800		
96-6 Escalation on Process Equip			
96-7 Escalation on Indirects	94,400	5,632,455	
98 Interest During Constr	466,300	5,632,455	
Total		5,632,435	

Estimate No.: 35162A
 Project No.: A09476-073
 Estimate Date: 6/19/20
 Prep/Rev/Appr: GAB/BA

TEC
 BIG BEND STATION
 UNIT 2 POST DEMOLITION



Group	Phase	Description	Notes	Quantity	Subcontract Cost	Process Equipment Cost	Material Cost	Man Hours	Labor Cost	Equip Amount	Total Cost
10.00.00	10.99.00	WHOLE PLANT DEMOLITION DEMOLITION, MISCELLANEOUS INSPECT, CLEAN OUT AND REPAIR DRAINS DEMOLITION, MISCELLANEOUS		1.00 LS	250,000 250,000	-	-				250,000 250,000
		WHOLE PLANT DEMOLITION			250,000						250,000
21.00.00	21.57.00	CIVIL WORK ROAD, PARKING AREA, & SURFACED AREA BITUMINOUS ASPHALT	ASPHALT TO REPAVE REMOVED BOILER AREA AND TO THE SOUTH	1,469.00 TN	-	-	145,431	420	20,223	8,678	174,332
		ROAD, PARKING AREA, & SURFACED AREA					145,431	420	20,223	8,678	174,332
		CIVIL WORK					145,431	420	20,223	8,678	174,332
23.00.00	23.17.00	STEEL GALLERY BAR WITH HOLD DOWN CLIPS GALVANIZED GRATING, 1 1/4" DEEP x 3/16" BEARING WITH HOLD DOWN CLIPS GALVANIZED GRATING, 2" DEEP x 3/16" BEARING BAR WITH HOLD DOWN CLIPS DOUBLE PIPE HANDRAIL WITH POSTS AND GUARD PLATES, PAINTED DOUBLE PIPE HANDRAIL WITH POSTS AND GUARD PLATES, PAINTED METAL GRATING STAIR TREADS 4 FT WIDE, INCLUDING STRINGER, HANDRAIL NOT INCLUDED	EGRESS STAIR TOWER LOCATED AT UNIT 2 FOR TURBINE DECK GRATING EGRESS STAIR TOWER LOCATED AT UNIT 2 FOR TURBINE DECK GRATING EGRESS STAIR TOWER LOCATED AT UNIT 2 FOR TURBINE DECK GRATING EGRESS STAIR TOWER LOCATED AT UNIT 2	650.00 SF 6,190.00 SF 1,100.00 LF 43.00 LF 320.00 EA	-	-	9,750 173,072 58,300 2,279 134,400	114 1,382 218 9 528	6,198 73,776 11,799 461 28,605	811 9,666 1,544 60 3,744	16,769 256,695 71,644 2,801 186,749
		STEEL					377,801	2,231	120,839	15,816	514,457
23.25.00	23.25.00	ROLLED SHAPE MEDIUM WEIGHT MEMBERS, 21 LBLF TO 40 LBLF, GALVANIZED MEDIUM WEIGHT MEMBERS, 21 LBLF TO 40 LBLF, GALVANIZED	EGRESS STAIR TOWER LOCATED AT UNIT 2 FOR TURBINE DECK GRATING	63.00 TN 63.50 TN	-	-	198,765 200,343	1,767 1,781	96,708 97,476	29,474 29,708	324,947 327,526
		ROLLED SHAPE					399,108	3,549	194,184	59,182	652,473
		STEEL					776,909	5,779	315,023	74,998	1,166,930
24.00.00	24.37.00	ARCHITECTURAL ROOFING METAL UNINSULATED	REPLACE ROOF AT COOLING TOWER WITH ALLOWANCE FOR OPENINGS AND OTHER LOCATIONS	3,350.00 SF	-	-	10,888	369	14,417	1,889	27,194
		ROOFING					10,888	369	14,417	1,889	27,194
24.41.00	24.41.00	SIDING METAL UNINSULATED, 24 GA. GALVANIZED CORRUGATED SIDING	CLOSING OPENINGS AND REPLACING SIDING AS REQUIRED	4,000.00 SF	-	-	13,000	361	17,576	3,031	33,607
		ARCHITECTURAL					23,888	729	31,993	4,920	60,801
27.00.00	27.17.00	PAINTING & COATING PAINTING STEEL PAINTING	EXTERIOR PAINTING, POST DISMANTLEMENT INTERIOR PAINTING, TURBINE BUILDING	35,500.00 SF 68,000.00 SF	-	-	35,500 68,000	2,734 5,237	127,585 244,389	15,308 29,322	178,393 341,710
		PAINTING					103,500	7,970	371,974	44,629	520,103
		PAINTING & COATING					103,500	7,970	371,974	44,629	520,103
41.00.00	41.35.00	ELECTRICAL EQUIPMENT LIGHTNING PROTECTION LIGHTNING PROTECTION	ALLOWANCE	1.00 LS	100,000	-	-				100,000
		LIGHTING ACCESSORY (FIXTURE)			100,000						100,000



TEC
 BIG BEND STATION
 UNIT 2 POST DEMOLITION

Estimate No.: 35162A
 Project No.: A09476-073
 Estimate Date: 6/19/20
 Prep/Rev/Appr: GAB/BA

Group	Phase	Description	Notes	Quantity	Subcontract Cost	Process Equipment Cost	Material Cost	Man Hours	Labor Cost	Equip Amount	Total Cost
	41.37.00	LIGHTING ACCESSORY (FIXTURE)		1.00 LS	150,000	-	-				150,000
		LIGHTING - FIXTURES ACCESSORY	ALLOWANCE		150,000						150,000
		LIGHTING ACCESSORY (FIXTURE)			250,000						250,000
		ELECTRICAL EQUIPMENT									

TEC
BIG BEND STATION
UNIT 2 ENGINEERING DEMOLITION SUPPORT

Estimator	GA
Labor rate table	20FLTAM DEMO
Project No.	A09476-073
Estimate Date	6/18/20
Reviewed By	BA
Approved By	BA
Estimate No.	35163A
Cost index	FLTAM

DOCKET NO. 20210034-EI
EXHIBIT NO. CRB-1
WITNESS: BEITEL
DOCUMENT NO. 1
PAGE 66 OF 100
FILED: 04/09/2021

Group	Description	Subcontract Cost	Process Equipment Cost	Material Cost	Man Hours	Labor Cost	Equip Amount	Total Cost
-------	-------------	------------------	------------------------	---------------	-----------	------------	--------------	------------

TEC
 BIG BEND STATION
 UNIT 2 ENGINEERING DEMOLITION SUPPORT



Estimate Totals

Description	Amount	Totals	Hours
Labor			
Material			
Subcontract			
Construction Equipment			
Process Equipment			
General Conditions			
Additional Labor Costs			
90-1 Labor Supervision			
90-2 Show-up Time			
90-3 Cost Plus 10% TO T 5-10's			
90-4 Cost Plus 10% TO T 6-10's			
90-5 Per Dem.			
Site Overheads			
91-1 Construction Management			
91-2 Field Office Expenses			
91-3 Material&Quality Control			
91-4 Site Services			
91-5 Safety			
91-6 Temporary Facilities			
91-7 Temporary Utilities			
91-8 Mobilization/Demob.			
91-9 Legal Expenses/Claims			
Other Construction Indirects			
92-1 Small Tools & Consumables			
92-2 Scaffolding			
92-3 General Liability Insur.			
92-4 Constr. Equip. Mob/Demob			
92-5 Freight on Material			
92-6 Freight on Process Equip			
92-7 Insurance			
92-8 Contractions G&A			
92-9 Contractions Profit			
Project Indirect Costs			
93-1 Engineering Services	2,023,050		
93-2 CM Support	1,085,000		
93-3 Start-Up/Commissioning			
93-4 Start-Up/Spare Parts			
93-5 Excess Liability/Insur.			
93-6 Sales Tax On Indirects			
93-7 Overhead Cost			
93-8 EPC Fee		3,108,050	
Contingency			
94-1 Contingency on Const Eq			
94-3 Contingency on Material			
94-4 Contingency on Labor			
94-5 Contingency on Subcontr.			
94-6 Contingency on Process Eq			
94-7 Contingency on Indirect			
Escalation			
96-1 Escalation on Const Equip			
96-3 Escalation on Material			
96-4 Escalation on Labor			
96-5 Escalation on Subcontract			
96-6 Escalation on Process Eqm			
96-7 Escalation on Indirects			
98 Interest During Constr	163,500		
Total		3,893,150	

TEC
BIG BEND STATION DEMOLITION
SCRAP VALUE

Estimator	GA
Labor rate table	20FLTAM DEMO
Project No.	A09476-073
Estimate Date	6/18/20
Reviewed By	BA
Approved By	BA
Estimate No.	34565B

Area	Description	Subcontract Cost	Scrap Value	Material Cost	Man Hours	Labor Cost	Equip Amount	Total Cost
UNIT 1	UNIT 1 SCRAP VALUE		(3,548,900)					(3,548,900)
UNIT 2	UNIT 2 SCRAP VALUE		(4,217,943)					(4,217,943)
	TOTAL DIRECT		(7,766,843)					(7,766,843)

TEC
 BIG BEND STATION DEMOLITION
 SCRAP VALUE



Estimate Totals

Description	Amount	Totals	Hours
Labor			
Material			
Subcontract			
Construction Equipment			
Process Equipment	(7,766,843)	(7,766,843)	
General Conditions			
Material Subcontract			
90-1 Labor Supervision			
90-2 Show-up Time			
90-3 Cost Due To OT 5-10's			
90-4 Cost Due To OT 6-10's			
90-5 Rep. Demol.			
Site Operations			
91-1 Construction Management			
91-2 Field Office Expenses			
91-3 Material/Quality Control			
91-4 Safety Services			
91-5 Staking			
91-6 Temporary Facilities			
91-7 Temporary Utilities			
91-8 Mobilization/Demob.			
91-9 Fuel/Transportation			
Other Construction Indirects			
92-1 Small Tools & Consumables			
92-2 Scaffolding			
92-3 General Liability Insur.			
92-4 Const. Equip. Mob/Demob			
92-5 Construction Insurance			
92-6 Freight on Process Equip			
92-7 Sales Tax			
92-8 Contractors G&A			
92-9 Contractor's Profit			
Project Indirect Costs			
93-1 Engineering Services			
93-2 CM Support			
93-3 Construction Management			
93-4 Start-Up Spare Parts			
93-5 Excess Liability Insur.			
93-6 Sales Tax On Indirects			
93-7 Owners Cost			
93-8 EPC Fee			
Contingency			
94-1 Contingency on Const Eq			
94-2 Contingency on Material			
94-3 Contingency on Labor			
94-4 Contingency on Subcontr			
94-5 Contingency on Process Eq			
94-7 Contingency on Indirect			
Escalation			
95-1 Escalation on Const Equip			
95-2 Escalation on Material			
95-3 Escalation on Labor			
95-4 Escalation on Subcontract			
95-5 Escalation on Process Equip			
95-7 Escalation on Indirects			
99 Interest During Constr			
Total		(7,766,843)	



TEC
BIG BEND STATION DEMOLITION
SCRAP VALUE

Estimate No.: 345658
Project No.: A08476-073
Estimate Date: 6/18/20
Prep/Rev/Appr: GABABA

Area	Group	Phase	Description	Notes	Quantity	Subcontract Cost	Scrap Value	Material Cost	Man Hours	Labor Cost	Equip Amount	Total Cost
UNIT 1	18.00.00	18.10.00	UNIT 1 SCRAP VALUE									
			SCRAP VALUE									
			MIXED STEEL	INCLUDES CONTINGENCY	-19,142.00 TN	-	(3,290,510)	-	-	-	-	(3,290,510)
			CARBON STEEL, FREIGHT INCLUDED				(3,290,510)					(3,290,510)
			MIXED STEEL				(3,290,510)					(3,290,510)
UNIT 2	18.00.00	18.30.00	UNIT 2 SCRAP VALUE									
			SCRAP VALUE									
			COPPER	INCLUDES CONTINGENCY	-132.00 TN	-	(258,390)	-	-	-	-	(258,390)
			#1 INSULATED COPPER WIRE 65% FREIGHT INCLUDED				(258,390)					(258,390)
			COPPER				(258,390)					(258,390)
UNIT 3	18.00.00	18.10.00	UNIT 3 SCRAP VALUE									
			SCRAP VALUE									
			MIXED STEEL	INCLUDES CONTINGENCY	-22,458.00 TN	-	(3,860,530)	-	-	-	-	(3,860,530)
			CARBON STEEL, FREIGHT INCLUDED				(3,860,530)					(3,860,530)
			CARBON STEEL, FREIGHT INCLUDED				(3,860,530)					(3,860,530)
UNIT 4	18.00.00	18.30.00	UNIT 4 SCRAP VALUE									
			SCRAP VALUE									
			COPPER	INCLUDES CONTINGENCY	-176.00 TN	-	(344,520)	-	-	-	-	(344,520)
			#1 INSULATED COPPER WIRE 65% FREIGHT INCLUDED				(344,520)					(344,520)
			COPPER				(344,520)					(344,520)


Tampa Electric Company
Big Bend Station Units 1-2
Dismantling Study





Project No.: A09476.301
Date: December 28, 2020
Rev. 1, Use


ATTACHMENT 2


Boiler Building Demolition and Bracing Schematics
























Tampa Electric Company
Big Bend Station Units 1-2
Dismantling Study




Project No.: A09476.301
Date: December 28, 2020
Rev. 1, Use

ATTACHMENT 3

Dismantling Sequence Schedule





Tampa Electric Company
Big Bend Station Units 1-2
Dismantling Study



Project No.: A09476.301
Date: December 28, 2020
Rev. 1, Use

ATTACHMENT 4

Repowering List

UNIT 1 AND 2 DISMANTLING STUDY
TAMPA ELECTRIC COMPANY
PROJECT #: A09476-301

ATTACHMENT 4

AUGUST 5, 2020
REV 0

SERVICE		LOAD	TYPE	CONNECTED LOAD (KVA)	DIVERSITY FACTOR	OPERATING LOAD (KVA)	REMARKS
4160V SWGR A							
AIR COMPRESSOR #3		700	HP	659.3	50%	329.7	REVISED TO 700 HP
LOAD CENTER TRANSFORMER 1A		3325	KVA	3325.0	80%	2660.0	FEEDER
LOAD CENTER TRANSFORMER 1B		3325	KVA	3325.0	80%	2660.0	FEEDER
CONCEPTUAL TOTAL				7309.3		5649.7	
ADDITIONAL CAPACITY (50%)				3654.7		2824.8	
TOTAL				10964.0		8474.5	
AMPERAGE				1521.7		1176.1	

DOCKET NO. 20210034-EI
EXHIBIT NO. CRB-1
WITNESS: BEITEL
DOCUMENT NO. 1
PAGE 87 OF 100
FILED: 04/09/2021

UNIT 1 AND 2 DISMANTLING STUDY
TAMPA ELECTRIC COMPANY
PROJECT #: A09476-301

ATTACHMENT 4

AUGUST 5, 2020
REV 0

4160V SWGR B									
SERVICE	LOAD	TYPE	CONNECTED LOAD (KVA)	DIVERSITY FACTOR	OPERATING LOAD (KVA)	REMARKS			
LOAD CENTER TRANSFORMER 2A	3325	KVA	3325.0	80%	2660.0	FEEDER			
LOAD CENTER TRANSFORMER 2B	3325	KVA	3325.0	80%	2660.0	FEEDER			
CONCEPTUAL TOTAL			6650.0		5320.0				
ADDITIONAL CAPACITY (50%)			3325.0		2660.0				
TOTAL			9975.0		7980.0				
AMPERAGE			1384.4		1107.5				

DOCKET NO. 20210034-EI
EXHIBIT NO. CRB-1
WITNESS: BEITEL
DOCUMENT NO. 1
PAGE 88 OF 100
FILED: 04/09/2021

UNIT 1 AND 2 DISMANTLING STUDY
TAMPA ELECTRIC COMPANY
PROJECT #: A09476-301

ATTACHMENT 4

AUGUST 5, 2020
REV 0

480V SWGR A	SERVICE	LOAD	TYPE	CONNECTED LOAD (KVA)	DIVERSITY FACTOR	OPERATING LOAD (KVA)	REMARKS
MCC A		1600	A	1330.2	80%	1064.2	FEEDER
TURBINE SHOP		400	A	332.6	80%	266.0	FEEDER
MCC-0WP1		800	KVA	800.0	50%	400.0	FEEDER
CONCEPTUAL TOTAL				2462.8		1730.2	
ADDITIONAL CAPACITY (50%)				1231.4		865.1	
TOTAL				3694.2		2595.3	
AMPERAGE				4443.4		3121.7	

DOCKET NO. 20210034-EI
EXHIBIT NO. CRB-1
WITNESS: BEITEL
DOCUMENT NO. 1
PAGE 89 OF 100
FILED: 04/09/2021

UNIT 1 AND 2 DISMANTLING STUDY
TAMPA ELECTRIC COMPANY
PROJECT #: A09476-301

ATTACHMENT 4

AUGUST 5, 2020
REV 0

480V SWGR B							
SERVICE	LOAD	TYPE	CONNECTED LOAD (KVA)	DIVERSITY FACTOR	OPERATING LOAD (KVA)	REMARKS	
MCC B	1600	A	1330.2	80%	1064.2	FEEDER	
CONSTRUCTION TRAILERS	400	A	332.6	80%	266.0	FEEDER	
A&B FLYASK SOUTH WALL	400	KVA	400.0	50%	200.0	FEEDER	
CONCEPTUAL TOTAL			2062.8		1530.2		
ADDITIONAL CAPACITY (50%)			1031.4		765.1		
TOTAL			3094.2		2295.3		
AMPERAGE			3721.7		2760.8		

DOCKET NO. 20210034-EI
EXHIBIT NO. CRB-1
WITNESS: BEITEL
DOCUMENT NO. 1
PAGE 90 OF 100
FILED: 04/09/2021

MCC A					
SERVICE	LOAD	TYPE	CONNECTED LOAD (KVA)	DIVERSITY FACTOR	OPERATING LOAD (KVA)
"A" EXHAUST FAN PEF-13 NORTH WALL	0.5	HP	0.5	50%	0.2
VIBRATOR MOTOR 1	3	HP	2.8	50%	1.4
TRIPPER ROOM EX FAN 1A	5	HP	4.7	50%	2.4
AUX BAY EXH FAN 2C	5	HP	4.7	50%	2.4
TURBINE RM EXH FAN 2A	5	HP	4.7	50%	2.4
TURBINE RM EXH FAN 2C	5	HP	4.7	50%	2.4
AUX BAY EXH FAN 2A	5	HP	4.7	50%	2.4
TURBINE RM EXH FAN 2D	5	HP	4.7	50%	2.4
TURBINE RM EXH FAN 2F	5	HP	4.7	50%	2.4
TRIPPER ROOM RXH FAN 2	5	HP	4.7	50%	2.4
MILL AREA EXH FAN 2B	5	HP	4.7	50%	2.4
CONT ROOM VENT FAN 1A	7.5	HP	7.1	50%	3.5
M1 TRIPPER DRIVE	7.5	HP	7.1	50%	3.5
LTG TRANSFORMER 2C1	10	KVA	10.0	50%	5.0
POWER PNL 2P1	10	KVA	10.0	50%	5.0
TRIPPER ROOM UNIT 1 WALL EXH FANS	15	KVA	15.0	50%	7.5
TRIPPER ROOM UNIT 2 WALL EXH FANS	15	KVA	15.0	50%	7.5
LTG TRANS 2B5	15	KVA	15.0	50%	7.5
DEMIM WASTE WATER SUMP PUMP 007A	15	HP	14.1	50%	7.1
#2 NORTH WALL SUPPLY FAN	20	HP	18.8	50%	9.4
FLOOR DRAIN SUMP PP 2A	20	HP	18.8	50%	9.4
LTG TRANS 2B3	25	KVA	25.0	50%	12.5
LIGHTING PANEL SLAG	25	KVA	25.0	50%	12.5
SLAG BIN LOCAL AREA SUMP PUMP A	25	HP	23.5	50%	11.8
NORTH PLANT BB2, 3, AREA MN OFFICE SANITARY LIFT STATION	30	KVA	30.0	50%	15.0
MODULAR BUILDING TURBINE FLOOR	30	KVA	30.0	50%	15.0
JIB CRANE HOIST - SLAG	35	KVA	35.0	50%	17.5
LTG TRANS 2B4	37.5	KVA	37.5	50%	18.8
LIGHTING TRANSFORMER 2B7	37.5	KVA	37.5	50%	18.8
CONVEYOR MOTOR 1	40	HP	37.7	50%	18.8
DEMIM WASTE WATER SUMP PUMP 007C	50	HP	47.1	50%	23.5
STORM WATER SUMP PUMP 8A	50	HP	47.1	50%	23.5
WELDING RECPT	60	KVA	60.0	50%	30.0
HVAC UNIT 1 - SLAG	60	KVA	60.0	50%	30.0
480V FEED FOR SOUTH ROAD LIGHTS	60	KVA	60.0	50%	30.0
FEEDER MOTOR	60	HP	56.5	50%	28.3
SETTLING BASIN SUMP NO 1 PP1A	100	HP	94.2	50%	47.1
#1 SETTLING BASIN SPARGING PP	100	KVA	100.0	50%	50.0
LTG TRANS 2B1	100	KVA	100.0	50%	50.0
2A SETTLING BASIN SUMP PUMP	100	HP	94.2	50%	47.1
CONVEYOR M-1 TRIPPER ROOM	125	HP	117.7	50%	58.9
OVERFLOW PUMP A	150	HP	141.3	50%	70.6
EAST COAL FEED SUMP PUMP 4A	150	HP	141.3	50%	70.6
CONCEPTUAL TOTAL			1577.2		788.6
ADDITIONAL CAPACITY (50%)			788.6		394.3
TOTAL			2365.9		1182.9
AMPERAGE			2845.7		1422.9

MCC B					
SERVICE	LOAD	TYPE	CONNECTED LOAD (KVA)	DIVERSITY FACTOR	OPERATING LOAD (KVA)
MAIN OIL PP AIR COMP NO.3	2	HP	1.9	50%	0.9
VIBRATOR MOTOR 2	3	HP	2.8	50%	1.4
TRIPPER ROOM EX FAN 1B	5	HP	4.7	50%	2.4
TURBINE RM EXH FAN 2C	5	HP	4.7	50%	2.4
TURBINE RM EXH FAN 2E	5	HP	4.7	50%	2.4
AUX BAY EXH FAN 2B	5	HP	4.7	50%	2.4
AUX BAY EXH FAN 2D	5	HP	4.7	50%	2.4
TURBINE RM EXH FAN 2B	5	HP	4.7	50%	2.4
TURBINE RM EXH FAN 2H	5	HP	4.7	50%	2.4
TRANS 5KVA AIR COMP #3 OIL HEATER	5	KVA	5.0	50%	2.5
CONT ROOM VENT FAN 1B	7.5	HP	7.1	50%	3.5
HYDRAULIC UNIT MOTOR	7.5	HP	7.1	50%	3.5
WELDING RECP T	15	KVA	15.0	50%	7.5
LIGHTING TRANSFORMER 2B6	15	KVA	15.0	50%	7.5
FLOOR DRAIN SUMP PP 2B	20	HP	18.8	50%	9.4
LTG TRANSFORMER 2T2	25	KVA	25.0	50%	12.5
#2 INSTRUMENT AIR DRYER	25	KVA	25.0	50%	12.5
LIGHTING TRANSFORMER 2B2	25	KVA	25.0	50%	12.5
LIGHTING TRANSFORMER 2T1	25	KVA	25.0	50%	12.5
SLAG BIN LOCAL AREA SUMP PUMP B	25	HP	23.5	50%	11.8
DISTRIBUTION PANEL	25	KVA	25.0	50%	12.5
HTR LIFTING TOOL	30	KVA	30.0	50%	15.0
POWER PNL 2P2	30	KVA	30.0	50%	15.0
TURBINE HALL CRANE 2	30	HP	28.3	50%	14.1
LTG TRANSFORMER 2T3	37.5	KVA	37.5	50%	18.8
WELDING RECP T OUTSIDE COMPUTER ROOM E	40	KVA	40.0	50%	20.0
BACK FLUSH PUMP	40	HP	37.7	50%	18.8
CONVEYOR MOTOR 2	40	HP	37.7	50%	18.8
DEMIN WASTE WATER SUMP PUMP 007B	50	HP	47.1	50%	23.5
DEMIN WASTE WATER SUMP PUMP 007B	50	HP	47.1	50%	23.5
#2 SETTLING BASIN SPARGING PP	50	HP	47.1	50%	23.5
STORM WATER SUMP PUMP 8B	50	HP	47.1	50%	23.5
HVAC UNIT 2 - SLAG	60	KVA	60.0	50%	30.0
PLASMA ARC MACHINE	80	KVA	80.0	50%	40.0
1B SETTLING BASIN SUMP PP1B	100	HP	94.2	50%	47.1
WELDING RECP T	100	KVA	100.0	50%	50.0
2B SETTLING BASIN SUMP PUMP	100	HP	94.2	50%	47.1
DEMINERALIZER WATER MAKEUP PP B	100	HP	94.2	50%	47.1
OVERFLOW PUMP B	150	HP	141.3	50%	70.6
EAST COAL FEED SUMP PUMP 4B	150	HP	141.3	50%	70.6
EAST COAL FEED SUMP PUMP 4C	150	HP	141.3	50%	70.6
CONCEPTUAL TOTAL			1630.1		815.1
ADDITIONAL CAPACITY (50%)			815.1		407.5
TOTAL			2445.2		1222.6
AMPERAGE			2941.1		1470.6

Tampa Electric Company
Big Bend Station Units 1-2
Dismantling Study



Project No.: A09476.301
Date: December 28, 2020
Rev. 1, Use

ATTACHMENT 5

Pullman Chimney Demolition Budgetary Quote



A STRUCTURAL TECHNOLOGIES COMPANY

May 12, 2020

Mr. Gregory Amen
Sargent & Lundy LLC
55 E Monroe St.
Chicago, IL 60603

Subject: TECO Big Bend Power Station – Apollo Beach, FL
Demolition of Two Concrete Chimneys
PULLMAN Budgetary Quote R201835R2

Dear Mr. Amen:

We have performed an initial cost and feasibility evaluation for the removal of the subject chimneys. Based on the provided general information and available images of the chimneys upon which this budgetary quotation is based and are pleased to provide you with this summary evaluation of estimated costs, duration, and methodology for the piece-meal demolition of these two chimneys.



Complete Demolition of Chimney Liner & Concrete Shell

- Pullman would mobilize a crew of experienced chimney demolition technicians to the site along with their specialized rigging and scaffolding equipment to perform the demolition. We would include a full-time site safety supervisor to administer our Front Line Safety and Health Program.
- The work would commence with establishing a safety exclusion zone and protocols for controlling access within the perimeter of the chimney demolition project. The first portion of the work would be enlarging a clean-out opening in the bottom of the concrete shell and fitting the door with a movable closure. We would then install an internal work platform supported from the top of the concrete shell from which to wash down the liner interior to remove surface contaminants. Typically, Owner would provide for vacuum trucks and disposal efforts for this phase of the work.

- The next phase of the work would be removing the existing chimney rainhood and full-height brick or steel chimney liner, which we would accomplish from the same internal work platform. The brick liner would be broken apart with sledge and pneumatic hammers and the brick debris would be allowed to fall down the interior of the liner to be removed through a clean-out opening that we would cut in the bottom of the liner corresponding to the location of the opening in the concrete column. The liner would be cut apart. The debris would be allowed to fall down the interior of the liner to be removed through a clean-out opening that we would cut in the bottom of the liner corresponding to the location of the opening in the concrete column.
- The next phase of the work would be to install our proprietary exterior chimney bracket scaffold around the top of the chimney and enclose it to prevent debris from falling down the exterior of the chimney. Some of the electrical components would also need to be removed during this phase of the work and temporary measures for compliance with FAA aviation obstruction lighting would be put into place.
- Once our exterior bracket scaffolding is set in place and air supply lines would be installed and the breaching opening(s) would be closed off with cables and steel plate to prevent debris from escaping through them.
- From the bracket scaffold, our crew would operate a chimney shell demolition machine (AKA: A Spider) which would be used to cut slots in the concrete wall to create sections of a manageable size that would be directed to fall into the chimney interior. These sections, along with corresponding smaller debris, would then be periodically removed at grade through the existing construction opening and placed in dumpsters for removal from site.
- We do not anticipate that the existing chimneys exterior paint contains enough lead to pose a hazard to our personnel; however, TCLP testing will have to be done on samples of the chimney concrete in order to determine whether or not special disposal measures will be required. We would encourage the taking of core samples from the concrete wall to have this sampling done ahead of mobilization for demolition operations to facilitate appropriate planning. In the meantime, our estimated pricing is based on our being able to handle all the brick and concrete debris without the need to implement special measures to accommodate lead levels above the OSHA action levels.
- For chimneys A and B, the concrete shell would be demolished down to a height of approximately 90ft above grade, at which point our subcontractor would demolish the remaining concrete column using ground-based equipment.
- PULLMAN would move all brick, steel and concrete debris during our phase of the work to a location near the chimney for others to arrange for disposal. No monies are included for any debris disposal of any kind in the budgetary estimate.

Chimney A – 90ft Concrete Shell Only with Cross Over Duct

- We estimate that performing the work described above for chimney A, (no liner to remove) would require about 1 month in the field with our subcontractor having adequate access to operate their ground-based equipment.
- Based on a 1-month schedule, disposal of debris as clean fill, no special measures to cope with lead paint, asbestos, or other hazardous materials, we estimate the cost of this work to be:

Three Hundred Thousand Dollars (\$300,000)

Chimney B – 485ft Tall with Brick Liner (AKA: #1&2 Wet Chimney/Common)

- We estimate that the work described above would require about 8 months in the field.
- Based on an 8-month schedule, disposal of debris as clean fill, no special measures to cope with lead paint, asbestos, or other hazardous materials, we estimate the cost of this work to be:

Three Million Four Hundred Fifty Thousand Dollars (\$3,450,000)

We appreciate the opportunity of assisting Sargent & Lundy with developing a plan for the decommissioning of these chimneys and stand ready to engage the resources necessary to establish a path forward for this project. Please don't hesitate to let us know if you have questions or would like to further discuss our approach to this work.

Sincerely,



Joshua Muder, PMP
Project Director

CC: Lance Lucas – llucas@pullman-services.com
JR Biggs – jbiggs@pullman-services.com

Tampa Electric Company
Big Bend Station Units 1-2
Dismantling Study



Project No.: A09476.301
Date: December 28, 2020
Rev. 1, Use

ATTACHMENT 6

Application of Gannon Lessons Learned to Big Bend Dismantling

Attachment 6
Application of Gannon Lessons Learned to Big Bend Dismantling

Sargent & Lundy

Lesson Learned Category and Description		Address Lesson Learned with:			Remarks
		Estimate	Engineering	Contract	
1 COORDINATION					
1.1	The plant required constant communication of the status.			X	The execution contracts will include regular status meetings.
1.2	Walk-downs were performed weekly with plant managers, and every single time revealed issues that were added to the scope.	X			The dismantlement study has used these lessons learned to minimize the potential for extra work.
1.3	The duration it took to demolish the last unit boiler was much greater than the contractor had estimated.	X		X	The study schedule uses long durations for demolition. The contractor will be required to maintain a schedule.
2 DRAWINGS					
2.1	Most drawings had outdated information.		X		Reference drawings will be reviewed during engineering.
2.2	The drawings were never updated after the dismantlement because Jim Montgomery retired.		X		TEC will need to develop a plan on how to handle the drawing cleanup after demolition.
3 ARCHITECTURAL / BUILDING ENVELOPE					
3.1	New roofs had to be put on several structures. Roofs need to be designed to Factory Mutual standards. Installation must be well-documented.				Not applicable; no roofs have been identified as requiring replacement.
3.2	New siding was required where the boiler voids had been. There was significant effort to design, fabricate, and install the girts and wind columns to receive the siding.	X			Closing off of wall opening created by demolition has been included in the estimated quantities.
3.3	When we re-roofed the slab areas over the former boilers, we had to raise the height of the handrail which took engineering and construction effort.				Not applicable; Big Bend is not saving the boiler structures and any roof access is not changing.
3.4	The plant required additional interior and exterior lighting in the older areas of the plant.	X			New lighting has been included in the estimated quantities.
3.5	While areas of roofing and siding were exposed, there were problems controlling rainwater infiltration. We got complaints from operations a number of times.			X	Requirement to be placed on the contractor to provide temporary shielding when large openings are not sealed immediately after an opening is created.
3.6	Lightning protection was added to the entire turbine building.	X			Lightning protection has been included in the estimated quantities.
3.7	After the boilers were demolished, water was blowing in a door, so the plant made us add a canopy.			X	Similar to 3.5 above.
3.8	Many areas of roofing were damaged by the activities of the demolition, falling objects, and water infiltration. Roof deck was found to be rusted out and had to be replaced.	X			Roof replacement areas have been included in the estimate to account for known problems and potential damage during demolition.

Attachment 6
Application of Gannon Lessons Learned to Big Bend Dismantling

Sargent & Lundy

Lesson Learned Category and Description		Address Lesson Learned with:			Remarks
		Estimate	Engineering	Contract	
4	CIVIL (YARD)				
4.1	Earth crane pads were built for the very large crane that was used. These crane pads were spread around the site when the crane was relocated for the next unit. This resulted in a lot of extra fill that cost money to remove.			X	Contractor will be responsible for the means and methods of their work.
4.2	I had to review multiple lift plans and also evaluate pit walls for crane surcharge.		X	X	Contractor is responsible for lift plans as part of means and methods. Engineering should only be reviewing those plans.
4.3	Underground concrete was frequently in the way of new light pole bases and drains when we re-paved.		X		Addressed through adequate engineering planning of new lights.
4.4	Knowing the location of the circulating water tunnels was vital at all times. It would have paid to paint them on the ground surface at the start.			X	Intake lines are painted at grade. Requirement can be added to specification for contractor to mark discharge locations.
4.5	The plant made us revise the entrance gate with a new guard house, fencing, gates, and card readers.				Not applicable; new entrance is not anticipated for Big Bend.
5	CONCRETE				
5.1	At the screenwell structure, we had to design infill framing where the pumps and screens were removed.	X			In fill quantities are included in the estimate.
5.2	We had to infill pits around the old boiler feed pumps. This required engineering and construction.				This was not identified as necessary during the 2018 study.
5.3	Cable cutting was used to demo pedestals. It left some rough surfaces that were not great for walking.	X			The estimate includes asphalt paving to lessen the uneven surfaces created by demolition.

Attachment 6
Application of Gannon Lessons Learned to Big Bend Dismantling

Sargent & Lundy

Lesson Learned Category and Description		Address Lesson Learned with:			Remarks
		Estimate	Engineering	Contract	
6	STEEL				
6.1	Much grating and handrail had to be replaced.				Not considered in the estimate; no areas of concern were identified during the 2018 study.
6.2	Checkered plate was rusty and had to be replaced in large areas.				Not considered in the estimate; no areas of concern were identified during the 2018 study.
6.3	Corroded pieces of steel were continuously discovered and had to be mitigated on an almost daily basis.				It is understood that this is likely the case at Big Bend; however, it was decided that a value could not be assigned to cover this situation.
6.4	The cost to repaint the steel inside the turbine building was estimated and was prohibitively expensive. We painted the exterior steel only.	X			Painting of both interior and remaining exterior steel is included in the estimate.
6.5	The entire structure had to be modeled to design the supplemental bracing steel and ensure that the turbine building was safely braced.		X		Some modeling was done during the 2018 study and is anticipated for the full design effort.
6.6	I was regularly asked to design field splices because beams could not be flown in between the webs of two columns.		X	X	Engineering should consider this when developing details; the project will need to work with the contractor.
6.7	I was asked to evaluate existing floors for lifts.		X	X	This should be the contractor's responsibility with review by engineering.
6.8	An over-height structure was required to ensure that trucks would not hit the pipe rack.				Not applicable to Big Bend
6.9	I was asked to evaluate beams for rigging loads many times. Rigging was especially difficult for the very heavy steam pipes.			X	This should be the contractor's responsibility.
6.10	The plate girders were hard to demolish. They are too large to lift at once, so we had to demo them in sections. We had the contractor hire a structural engineer to provide a sequencing plan. Even then, one of the pieces folded over while it was being flown.			X	Contractor is responsible for lift plans as part of means and methods. They will be required to hire a structural engineer to facilitate their work.
6.11	Some items that had tied back to the tripper building had to be resupported or replaced. For example, a hydrogen vent and a jib crane serving the cooling tower.	X			These were evaluated during the 2018 study and included in the estimate.
7	MECHANICAL				
7.1	Floor drains were filled with debris over time and had to be cleaned at great cost.	X			The estimate includes an allowance for cleaning out and fixing the drains.
7.2	Roof drains were leaking, missing, etc. and had to be refurbished. The scaffold was expensive, because it had to be suspended from the main turbine building roof trusses. This may not be an issue at Big Bend.	X			The estimate includes replacing some of the roof drains.



BIG BEND POWER STATION
Tampa Electric Company

UNIT 3 DISMANTLING STUDY

BASIS OF COST ESTIMATE & SCOPE OF WORK



REV. 0, DECEMBER 28, 2020

USE

Project No.: A09476.301

Prepared by:



55 East Monroe Street • Chicago, IL 60603 USA • 312-269-2000

Tampa Electric Company
 Big Bend Station Unit 3
 Dismantling Study



Project No.: A09476.301
 Date: December 28, 2020
 Rev. 0, Use

Table of Contents

Executive Summary.....3

A. General Information 5

B. Estimate Approach..... 13

C. Estimate Scope of Work 14

D. Pricing and Quantities 19

E. Labor Wage Rates 20

F. Construction Equipment..... 20

G. Construction Direct/Indirect Costs and General Conditions 20

H. Scrap Value 21

I. Contingency 21

J. Escalation 22

K. Costs Excluded 22

L. Scope Assumptions/Clarifications/Exclusions 22

M. Cost Comparison to 2018 Estimate 24

N. Schedule 25

Attachments:

1. Cost Estimate Summary, Cash Flow and Individual Estimates
2. Boiler Building Demolition and Bracing Schematics
3. Dismantling Sequence Schedule
4. Application of Gannon Lessons Learned to Big Bend Dismantling

Tampa Electric Company
Big Bend Station Unit 3
Dismantling Study



Project No.: A09476.301
Date: December 28, 2020
Rev. 0, Use

EXECUTIVE SUMMARY

This report documents the scope and cost associated with partial dismantlement of Big Bend Unit 3. An extensive study was completed during 2018 and included Units 1 through 3. This 2020 version is an update to reflect 1) changes in the retirement schedule, 2) segregate Unit 3 from Units 1 and 2, 3) address recent 2020 TEC comments and 4) incorporating additional lessons learned from Gannon dismantling. In addition, modifications to the cost estimate categorizes the costs into the project phases. Cash flows have also been broken down into quarters rather than a monthly basis.

Detail of the six significant changes are:

- 1 - The schedule used in developing the cash flow initially utilized an April 2024 retirement date for Unit 3. This retirement date has been pushed back approximately nine months from the 2018 study. TEC recently determined the Unit 3 retirement date to be April 2023. This does not significantly impact the report cash flow as other factors such as available budget and dismantlement activities for Units 1 and 2 drive the Unit 3 schedule.
- 2 - The 2018 Dismantlement Study included Units 1 through 3. A separate study completed earlier this year covers the dismantlement of Units 1 and 2. This study is only for Unit 3 and assumes that the dismantlement of Units 1 and 2 precedes Unit 3. As such, cost for removing the slag dewatering facility that serves Units 1 through 3 has been allocated to the Unit 3 demolition estimate.
- 3 - The dismantlement effort has changed hands internally with TEC and that has led to new comments to the 2018 Dismantlement Study as well as a request for increased maintenance areas on the Unit 3 turbine deck. Turbine deck openings where the turbine-generator and other areas can be filled in with beams and grating, which will reclaim approximately 3,100 square feet of usable maintenance space during outages.
- 4 - Gannon lessons learned were passed on to the project during the 2018 Dismantlement Study. Attachment 4 has been added to identify whether each of Gannon's lesson learned has been accounted for in the estimate, will require consideration during detailed engineering, or should be required as contractor scope.
- 5 - The cost for demolishing the Unit 3 wet FGD chimney is based on an updated 2020 budget quote from Pullman for the Unit 1 and 2 Chimney. They identified improved methods and equipment for removing concrete chimneys that allows for a 25% cost reduction.
- 6 - TEC requested that the contingency be decreased from 20% to 15% and inclusion of an allowance to refurbish the Turbine Building ventilation system and repurpose the turbine area offices and warehouse space. The 5% reduction to contingency and requested modifications with escalation account for an additional \$3.24 million.

New estimating categories are established to segregate each unit costs into the suggested project four phases: engineering, pre-demolition, demolition, and post-demolition. The previous cost estimate only segregated each unit into either demolition or addition activities.

Coal yard partial dismantlement was a late addition to the 2020 Units 1 and 2 estimates. All the costs associated with the changes to the coal yard have been allocated to Units 1 and 2.

Tampa Electric Company
 Big Bend Station Unit 3
 Dismantling Study



Project No.: A09476.301
 Date: December 28, 2020
 Rev. 0, Use

A summary of the costs associated with Unit 3 for the four categories:

	Unit 3
Engineering	\$4,348,050
Pre-Demolition	\$8,366,867
Demolition	\$28,978,073
Post-Demolition	\$5,637,055
Unit 3 Sub-Total	\$47,330,045
Additional Cost ^{4,5}	\$3,238,198
Unit 3 Total	\$50,568,243

Notes on cost summary:

1. The above totals do not include scrap value for the demolition materials. Scrap pricing is volatile and should not be relied upon to reduce the cost of the project during the planning phase.
2. The total cost for dismantlement of Unit 3 has increased by 11.4% (\$5.2 million) from the 2018 estimate.
3. The two main additions to the estimate are Turbine operating floor opening in-fill with grating and removal of the discharge flume. However, the savings related to an improved method of chimney demolition offset the increases such that direct costs increased less than 2 percent.
4. The cost estimates included in Attachment 1 initially included a 20% contingency, consistent with the 2018 estimate. During early 2020 TEC had site meetings with potential demolition contractors on the scope and economic feasibility of the dismantlement effort. Based on these meetings and the contractor's similar project experience, it was recommended to reduce the contingency to 15%. The 5% reduction to contingency is not included in the detailed cost estimates but has been added to the "Additional Cost" line in the table above and in the Attachment 1 cost summary page. See Attachment 1 for a further breakout of contingency, escalation, general conditions, direct and indirect costs.
5. Three additional cost items were added during the TEC comment cycle that were not captured during the 2018 estimate. TEC requested that allowances be included to account for Turbine Building ventilation improvements required after unit retirements, costs to renovate the warehouse and office areas adjacent to the Turbine Building, and water usage for dust control during dismantlement activities. The "Additional Cost" line in the table above includes the requested additions with contingency and escalation.

Schedule

The schedule of the dismantlement end date was reviewed with TEC in October and this estimate assumes a completion date of January 2027 and project start in January 2023. It is recommended to have engineering for the structural bracing be started in the early 2023. This is part of the "Pre-demolition" scope that is required to be installed prior to dismantlement of these key structures and systems. Performing the engineering during 2023 allows time to bid and award the construction package with issued for construction drawings sufficiently early to support mid-year 2024 installation.

Tampa Electric Company
Big Bend Station Unit 3
Dismantling Study



Project No.: A09476.301
Date: December 28, 2020
Rev. 0, Use

Basis of Estimate – Big Bend Dismantling Units 1-2

Estimates:

Cost estimates associated with this study are as follows.

- 35256A – Unit 3 Pre-Demolition Modifications
- 35257A – Unit 3 Demolition
- 35258A – Unit 3 Post Demolition
- 35259A – Unit 3 Engineering Demolition Support
- 35225A – Unit 3 Scrap Value

A summary of the estimated costs, cash flow and the estimates are included as Attachment 1. Given that the basis of this project consists of a “decoupling” followed by “demolition”, the costs are substantially higher than would be the case for pure demolition. Total rounded off cost for Unit 3 without scrap value:

Unit 3 \$50,570,000

This value is considered appropriate for project planning purposes. **Opportunities for savings during the course of demolition project execution do exist, and include but are not limited to the following:**

- Optimization of the project execution plan in the early phase of the project. This includes detailed scope development, refinement of the schedule as well as the contracting plan through a well-conceived division of responsibility.
- Use of competitively bid, firm price construction work packages, based on “issued for construction (IFC)” level engineering deliverables, rather than vague references to perceived scope or material takeoffs that create opportunities for contractor change orders.
- Developing a collaborative, value-based working relationship with the successful construction teams, via immediately responsive and capable engineering and construction management staff from both of our organizations. TEC and S&L have a long history of doing this and this project should be no exception.
- Identification of the high value scrap commodities and the means to maximize payback to TEC, at the appropriate time during execution.

We are fully prepared to facilitate the development of these and other cost savings opportunities during project execution.

A. General Information

Big Bend Station is located in Hillsborough County Florida, just north of Apollo Beach. There are four coal-fired boiler units. Units 1 and 2 are being modernized to a single two-on-one combined cycle configuration utilizing Heat Recovery Steam Generators (HRSG) and a single Steam Turbine Generator (STG) located in the current Unit 1 STG location (Modernization Project).

Tampa Electric Company
Big Bend Station Unit 3
Dismantling Study



Project No.: A09476.301
Date: December 28, 2020
Rev. 0, Use

Unit 3 is a 450 MW Riley Power Pulverized Coal Fueled Boiler commissioned in 1976, which also has the capability to run on natural gas. The unit has an Electrostatic Precipitator and Selective Catalytic Reduction system with associated ductwork and support structures. Units 3 and 4 have an integrated Flue Gas Desulfurization system with each having an individual stack.

Project location – 13031 Wyandotte Road, Apollo Beach, FL 33572
Contracting strategy – Multiple lump sum

Decommissioning and Dismantlement Plan (D&D Plan)

Unit 3 shutdown is planned for April 2023¹. The Dismantling Project's scope for Unit 3 is to remove equipment and structure down to the top of foundation to the greatest extent possible while maintaining full function of the turbine building and coal feed conveyor in support of Unit 4. The goal is to remove equipment and structure south of column row F½.

Modifications are not required to common systems such as coal delivery, storage and feed limestone preparation, gypsum dewatering, workshops, warehouses or ponds. However, such systems must be maintained, and many are powered from other units. For example, the coal handling and storage is electrically fed from Unit 1 and that power feed will need to be maintained by the Modernization Project.

The objective of the Decommissioning and Dismantlement (D&D) Plan is to provide information for planning, cost estimating and execution of the Dismantlement of the Big Bend Unit 3. The dismantlement activities will be performed on an operating power plant site so methods will be restricted so as not to interfere with generating operations or damage infrastructure and systems that are to remain in service.

Given the precise nature of this demolition, it is important that contractors be pre-qualified to ensure that only capable contractors with a good safety record and similar experience be allowed to bid the work. Contractors will be required to consider:

- Effects of ground bearing from demolition equipment on underground utilities, sumps, and the seawall
- Prevention of iron dust in wastewater and storm water drains with regular housekeeping
- Productivity due to LOTO constraints
- Limit vibrations of the demolition due to operating equipment for the remaining unit(s)
- Structural stability during removal of equipment and structures
- Impact of demolition equipment on underground pipes and sumps
- Maintain function of floodwalls and site drainage, being careful not to damage the wall or plug up the drains with debris

TEC is evaluating closure of the northern third of the coal yard operation. Costs associated with coal yard modifications have been included in the Units 1 and 2 dismantlement cost estimates and are not part of this study.

¹ See Section N for discussion of schedule used in the report verses current planned retirement date.

Tampa Electric Company
Big Bend Station Unit 3
Dismantling Study



Project No.: A09476.301
Date: December 28, 2020
Rev. 0, Use

The execution of the dismantling project is broken into four phases.

1. Engineering
This first phase will develop the scope of work, perform detailed engineering for modifications, develop the specifications, bid out the contracts and evaluate proposals. Work is split between TEC internal staff and an outside engineering firm.
2. Pre-Demolition Construction
This phase begins preparation for the demolition process with activities to remove consumables, remediate asbestos containing material (ACM), add bracing, and relocate utilities.
3. Demolition
Physical removal of equipment and structures.
4. Post-Demolition
Activities required to leave the site in safe, usable state that allows for proper drainage and access.

A level 2 schedule has been developed to illustrate a logical progression and duration of activities. This schedule is included as Attachment 3. **Figures 1 and 2** provide a visual of the general demolition sequence for the major Unit 3 structures. Sequenced areas are numbered 1 through 8.




Figure 1 – Demolition Sequence of Unit 3 Backend Major Structures

Tampa Electric Company
Big Bend Station Unit 3
Dismantling Study



Project No.: A09476.301
Date: December 28, 2020
Rev. 0, Use




Figure 2 – Demolition Sequence of Unit 3 Tripper and Turbine Area Structures

Phase 1 – Engineering activities

- Secure all necessary permits and authorizations.
- Perform Environmentally Regulated Material Survey
- Conduct a detailed study to determine the method by which the existing equipment and systems will be repowered when the existing unit power distribution system is removed from service.
- Conduct a detailed study of the fire protection system to identify those portions of the existing system that will need to be preserved.
- Conduct a detailed study of all high energy systems and utilities to identify “air gap” points that the owner will be responsible to isolate services supplying the equipment and facilities to be dismantled. Systems should include electrical power, steam, compressed gases and air, water including fire protection and any other utilities present in the impacted area.
- Design new power distribution system to equipment that remains in service.
- Develop a list of services and material that TEC will provide to the contractor.
- Develop a list of materials, equipment and services that the contractor is responsible to provide as part of the scope.
- Hazardous material mitigation plan for pre-demolition activities and development of mitigation procedure to support dismantlement activities

Tampa Electric Company
Big Bend Station Unit 3
Dismantling Study



Project No.: A09476.301
Date: December 28, 2020
Rev. 0, Use

- Design vertical bracing additions to ensure stabilization of structures after removal of the boiler building structure (See “blue” braces in **Figure 3** as a typical braced row).




Figure 3 – New Vertical Bracing and Boiler Steel Demolition

- Develop a procurement package for supply and installation of new elements necessary to complete the dismantlement (vertical bracing, power distribution, piping, etc.).
- Develop a procurement package for the dismantlement.

Phase 2 – Pre-dismantlement activities

- Removal of hazardous materials such as ash and SCR catalyst. Drain and decontaminate all equipment and piping, which includes removal of all liquids, gas and solids.
- Abatement of ACM once removal of all the other waste materials is complete.
- Install new vertical bracing to stabilize the Turbine Building prior to removing the boiler area steel (**Figure 3**) in several braced rows.
- “Air Gap” all energy systems.
- Install new power distribution necessary to maintain essential services.
- Mark dismantlement area and contractor access routes. Mark plant personnel access requirement in the impacted area.

Tampa Electric Company
Big Bend Station Unit 3
Dismantling Study



Project No.: A09476.301
Date: December 28, 2020
Rev. 0, Use

Phase 3 – Demolition activities

- Sequencing of the dismantlement will allow for use of the same scrap processing area used by the Unit 1 and 2 dismantlement effort. This area is used for material sorting and placing in bins for recycling. **Figure 4** provides a plan view of the planned scrap processing area.



Figure 4 – Demolition Scrap Processing Area (Outage Laydown Area)

- After ACM abatement is complete, begin removal of Unit 3 back end equipment and steel starting from the south and working north.
- Removal of Ash Silo #2 and booster fan area.
- Removal of ESP's and SCR.
- Removal of Boiler and associated equipment.
- Removal of boiler area structural steel.
- Removal of pipe support steel above tripper and cooling tower.
- Removal of concrete chimney
- Removal of structure and equipment associated with Unit 3 FGD system, except the oxidation air blowers that are to remain in service as spares for Unit 4.
- Removal of Turbine area equipment.
- Removal of transformers and intake equipment as well as fill circulating water intake and discharge.
- Demolish discharge flume (**Figure 5**)
- Demolish slag dewatering area

Tampa Electric Company
Big Bend Station Unit 3
Dismantling Study



Project No.: A09476.301
Date: December 28, 2020
Rev. 0, Use



Figure 5 – Unit 3 and 4 Circulation Water Discharge Area

Phase 4 – Post-Demolition activities

- Install new freight elevator.
- In fill of Turbine building floor openings, which needs to occur immediately after equipment removal. The operating floor of the Unit 3 Turbine Building has large areas that will be filled in with grating to promote storage area and space for outage maintenance, about 3,100 square feet. See **Figure 6** for operating floor areas to be filled in with grating.
- Perform Unit 3 Boiler area paving to promote area drainage.
- Repair any flood wall damage.
- Inspect and clean out site drains.
- Repaint remaining indoor and outdoor structural steel.
- Close wall openings created in the south wall of the Turbine building after removing equipment.
- Install new area lighting.
- Perform roof repairs.
- Refurbish the Turbine building roof ventilation (**Figure 7**)
- Refurbish the Turbine area offices and warehouse area

Tampa Electric Company
Big Bend Station Unit 3
Dismantling Study

Sargent & Lundy

Project No.: A09476.301
Date: December 28, 2020
Rev. 0, Use




Figure 6 – Turbine Building Operating Floor In-Fill Areas



Figure 7 – Turbine Building Ventilation Fans

Tampa Electric Company
Big Bend Station Unit 3
Dismantling Study



Project No.: A09476.301
Date: December 28, 2020
Rev. 0, Use

B. Estimate Approach

The cost estimate is based largely on Sargent & Lundy's experience on similar projects as well as our past project experience at the Big Bend station. This study is not a detailed engineering document, but a cost estimate prepared in advance of the detailed engineering preparations that will be necessary to carry out the full dismantling activities.

Some preliminary engineering was utilized to develop the conceptual modification to lateral load resisting system for the remaining structures and the power distribution system for remaining Unit 3 equipment that must be repowered. S&L assigned allowances where necessary to cover issues that lack full development at this time. TEC supplied the costs for ACM abatement, removal of hazardous liquids and waste in 2018.

Dismantlement estimates normally achieve a Class 4 level by applying scaling factors to account for size of unit in comparison to demolition costs developed from a past reference project. This estimate uses better-defined quantities to account for known aspects of the equipment and structure slated for removal. The goal is to estimate a level of detail necessary to achieve an estimate in line with Class 3 accuracy.

Project methods to attain this accuracy are:

Electrical:

- The demolition is covered by concentrating on large equipment (large transformers and isophase bus duct systems) using drawings and data.
- Remaining electrical equipment and commodities are included in the demolition quantities used in the estimating group's base estimate, which is used to ratio demolition costs.
- The approach accounts for relighting areas that remain in use or are repurposed after the dismantling. The estimate will include new fixtures and equipment as necessary. The extent of the scope and quantities will be developed based on conceptual engineering.
- The approach to repower any loads that will need to remain in use after the dismantling will be using new cable, raceway, and electrical equipment as necessary. The extent of the scope and quantities will be developed based on conceptual engineering from 2018.
- Items that are not quantifiable at this time will be assigned allowances. Such items include lightning protection, DCS modifications, electrical equipment reconfiguration, etc.

Mechanical:

- The demolition estimate includes mechanical equipment that will be left in service (air compressors, sump pumps, building ventilation, etc.).
- Critical pipe quantities and major equipment tonnages are used to supplement and validate the estimate quantities.
- TEC is managing the SCR catalyst for end of life to coincide with dismantlement, thereby resulting in no salvage value of the catalyst.
- The estimate will not include the design for relocation or re-piping of any mechanical equipment.
- Items that are not quantifiable at this time will be assigned allowances. Such items include new sumps, ventilation equipment, disintegration of Units 3 & 4, etc.

Tampa Electric Company
Big Bend Station Unit 3
Dismantling Study



Project No.: A09476.301
Date: December 28, 2020
Rev. 0, Use

Structural:

- Steel tonnage for the boiler buildings and ESP structures will be estimated based upon the volume of the structure and typical densities of such structures determined from S&L's extensive experience designing these structures.
- Steel & ductwork tonnages for the SCRs were taken from S&L's historical records based upon quantities determined during the design/construction of these structures.
- Steel & ductwork tonnages for the FGD system are determined using a scaling factor applied to known quantities based upon the power generation rating of each unit.
- Demolition estimate for the U3 chimney is based on the 2020 Unit 1 and 2 Pullman estimate.
- Quantities for the demolition of miscellaneous concrete for all units/structures are determined based upon items identified for removal during the site walk down.

Lessons Learned from Gannon:

A listing of lessons learned from the demolition effort of the Gannon Power Plant is included as Attachment 4. The approach that the study has taken to address each of the items is categorized as being addressed by estimate, engineering, or contractor. The intent of each category is the following.

- | | |
|-------------|--|
| Estimate | – indicates that quantities have been included in the estimate to account for that item. |
| Engineering | – indicates an item that will require engineering assessment and direction to the contractor. |
| Contractor | – indicates which items should be specifically included in the contract documentation as part of the contractor's scope. |

C. Estimate Scope of Work

In general, all mechanical equipment and facilities used to generate electricity by firing coal will be dismantled for Unit 3. Continued operation of Unit 4 requires both a careful demolition approach and the need to keep essential systems in operation at the Big Bend station. The turbine building will not be demolished, and the part of the boiler steel required to support the coal conveyors and the turbine building south wall will not be demolished.

The Unit 1 and 2 dismantlement of the boiler and backend structures is assumed to be completed to allow construction access to Unit 3. If Unit 3 is rescheduled to be before Unit 1 and 2, additional costs due to limited construction access and distant dismantlement stockpile areas would need further review.

The extent of demolition for the units follows these guidelines:

- Removal of hazardous materials, liquids, ash, catalyst and waste materials takes place prior to demolition.
- Demolition will remove as much of the structure as possible up to the tripper support steel. In order to accomplish this, installation of new vertical bracing and a new stair tower is planned. Painting of remaining steel is also included.
- Structures and equipment pedestals will be removed down to the top of foundation.

Tampa Electric Company
Big Bend Station Unit 3
Dismantling Study



Project No.: A09476.301
Date: December 28, 2020
Rev. 0, Use

- Select equipment must remain in service after the demolition. The equipment that serves a common function or is required to stay operational after the dismantlement will be repowered from a new distribution system with new cable routing. The 2018 basis for items for electrical repowering is conservatively used.
- The scope considers removal of the Unit 3 circulating water intake equipment and discharge flume. Filling of the intake and discharge lines with flowable fill is included.
- Demolished equipment and material to be stockpiled by the contractor and disposed by TEC. A one acre scrap processing area at the southeast corner of the coal pile area will be used for this purpose.
- The Unit 3 branch off the existing ammonia loop will be capped. Existing valves on the ammonia loop are to be replaced due to their tendency to leak.
- The natural gas header will be capped downstream of Unit 4.
- One personnel elevator will be removed. A new freight elevator is included near Unit 3.
- LED fixtures are utilized for any areas requiring new lighting.
- Large floor openings created by equipment removal at the Turbine Operating level will be filled in by grating to provide future storage and outage laydown area.
- The existing flood walls that protect the remaining facilities and area drainage must remain in service after the demolition. The contractor will need to protect both the wall and drainage system from damage during the demolition. Portions of the flood wall that are not required will be removed.
- Removal scope for Unit 3 GSU and SST transformers only extends to the bushings. The high voltage line work will be handled by TEC.
- The slag dewatering system is not required for the operation of Unit 4 and can be removed.
- Unit 3 oxidation air blowers remain in service as additional redundancy for Unit 4.

Listed below is a summary level scope (not all inclusive) of facilities included in the estimate:

1. Major Systems Identified for Demolition by Disciplines

a. Mechanical:

i. Unit 3

- Environmentally Regulated Materials removal - All disciplines
 - Survey
 - Pre demolition removal activities
 - On-going removal activities to support dismantlement
- Ash Handling system
- Boiler Feed pumps and Auxiliaries
- Boiler Pressure Systems (steam and water Circuits)
- Circulating water System
- Chemical Additive Systems
- Chemical Feed and water sampling system
- Combustion air and Gas System (Fans/soot blowers etc.)
- Controls, Ovation (All systems BBC001)

Tampa Electric Company
Big Bend Station Unit 3
Dismantling Study



Project No.: A09476.301
Date: December 28, 2020
Rev. 0, Use

- Feedwater System
- Fuel Burning system (Natural Gas Systems): 12" NG pipeline will be capped downstream of Unit 4
- SCR System
 - Ammonia pipeline to Unit 3 SCR
- Slag Handling System and dewatering
- ii. Unit 3 FGD Mechanical Items
 - Environmentally Regulated Materials removal - All disciplines
 - Survey
 - Pre demolition removal activities
 - On-going removal activities to support dismantlement
 - Absorber Tower and Feed Tank
 - Absorber Agitators
 - Absorber Bleed Pumps
 - Absorber Ductwork
 - Absorber recycle pumps
 - Absorber instrument and controls
 - Make up water header
 - Mist eliminator wash system
 - Oxidation air sparger system
 - Quenching nozzle spray system
 - Reagent Feed Loops
 - Continuous emissions monitoring system
 - Defoamer Storage tank and pumps
 - Forced oxidation blowers (save as backup for Unit 4)
 - Organic acid system
 - Primary Dewater system
 - Wet chimney
 - FGD Common systems
 - Limestone Slurry prep system is not included in SOW
 - Common Gypsum dewatering system is not included in SOW
- b. Electrical:
 - i. Unit 3
 - Generator 3
 - Generator Step up Transformer – MTX3
 - Station Service Transformer A – SST3A
 - Station Service Transformer B – SST3B

Tampa Electric Company
Big Bend Station Unit 3
Dismantling Study



Project No.: A09476.301
Date: December 28, 2020
Rev. 0, Use

- 4160V Switchgear West Bus – 3NNS-SWG-1W
 - 4160V Switchgear East Bus – 3NNS-SWG-1E
 - 13.8kV Switchgear Bus A – 3NPS-SWG-301A
 - 13.8kV Switchgear Bus B – 3NPS-SWG-301B
 - Low voltage switchgears and motor control centers.
 - Electrical and control systems associated with the mechanical systems identified in item 1.a.
 - ii. Reserve Auxiliary System
 - Reconfigure to keep in service.
 - iii. Instrumentation and Controls
 - Instruments for all units associated with systems being removed.
 - c. Structural:
 - i. Unit 3
 - FGD stack
 - FGD vessels, ductwork, and structural steel
 - SCR reactors, ductwork and structural steel
 - ESP box, ductwork and structural steel
 - Cap and fill circulating water tunnels
 - Structural demolition extent
 - a. Steel removal shall be maximized to decrease future steel maintenance
 - Existing lateral bracing shall be modified, and additional steel shall be added to provide an adequate load path for the new configuration
 - Painting of existing steel
 - b. Identify and maintain required means of egress per building code including the removal of many existing plat forms and eliminating walkways and platforms that will no longer be required
 - Stairways should be modified in order to streamline travel paths and eliminate confusing evacuation routes
 - Elevators should only provide access to areas required for operations.
 - c. Coal bunker walls and hoppers
 - Boiler building to be removed to column row F $\frac{1}{2}$
 - a. Coal Conveyor remains in service for Unit 4.
 - b. Current truck path to remain open.
 - Current plan is for existing steel to be painted, there will be no siding added to the buildings for this scope of work.
2. Major installations and replacements required due to dismantlement
 - a. Mechanical
 - i. Separation of the following systems:

Tampa Electric Company
Big Bend Station Unit 3
Dismantling Study



Project No.: A09476.301
Date: December 28, 2020
Rev. 0, Use

- Unit 3 and 4 Fish Return System
 - FGD Unit 3 and 4 common systems
 - Common steam line for each units' main steam attemperator
 - ii. Natural gas system to be capped downstream of Unit 4.
 - iii. Hydrogen and Ammonia System branched to Unit 3 to be capped
 - iv. Fill the circulating water intake and discharge tunnels for Unit 3
 - v. Turbine roof ventilation refurbishment
- b. Structural
- i. Turbine roofing to be replaced
 - Replace roofing at the Unit 3 cooling tower after removal
 - Replace any dismantlement related damaged areas along south edge of roof
 - Roof drains to be replaced
 - ii. Entry way canopies where applicable
 - iii. Turbine building siding
 - South side of turbine building to close in the remaining structure
 - iv. Structural steel bracing to support the structural demolition extent
 - v. Provide floor framing and grating to fill in large openings created by equipment removal in Unit 3. Small opening will also be filled in with grating.
 - Examples:
 - a. Turbine & Generator voids
 - b. Coal Handling equipment voids
 - c. Large open area east of the Turbine at the operating level
 - vi. Grating and handrails as required to access Unit 1 and 4 operations. (cooling tower, turbine deck, turbine mezzanine, and ground floor)
 - vii. Removal of checkered plating and replaced with grating
 - viii. Paving of dismantled area to promote drainage and provide a smooth walking surface
 - ix. Painting of existing interior and exterior steel
- c. Electrical/I&C
- i. Reconfiguration of the DCS system (Emerson) to move remaining equipment controls to common highway
 - ii. Lightning protection for unprotected structures subsequent to demolition
 - iii. Lighting
 - Lighting to account for areas still being utilized by operations. (cooling tower, turbine deck, turbine mezzanine, and ground floor)
 - iv. Equipment that will need to be repowered
 - Unit 3 Floor Drain sump equipment
 - Unit 3 Settling Basin sump equipment

Tampa Electric Company
Big Bend Station Unit 3
Dismantling Study



Project No.: A09476.301
Date: December 28, 2020
Rev. 0, Use

- #3 Transfer sump equipment
- Unit 3 and 4 Polisher equipment
- Unit 3 FGD Oxidation Air Compressors
- Unit 4 Chimney and CEMS shelter
- Stormwater sumps within the unit boundaries
- Air Compressor #5 and #6
- Turbine Building vent fans
- Unit 4 Clean & Dirty oil tank equipment
- Turbine Hall crane
- Unit 3 Fire Protection Panel

D. Pricing and Quantities

- Costs for bulk materials were derived from S&L database
- Asbestos abatement costs provided by TEC
- Decommissioning (removal and disposal of regulated waste) costs provided by TEC
- TEC's project staffing and security costs provided by TEC
- Permit costs provided by TEC

Bulk quantities and weights of equipment and material commodities used in this cost estimate are intended to be reasonable and representative of projects of this type. Quantities were estimated from Sargent & Lundy in-house database and numerous assumptions. See "Estimate Approach" for further discussion on quantity development.

TEC cost estimate input and assumptions:

Decommissioning – Decommissioning includes boiler draining, contaminate removal (fly ash, coal, slag, lead paint, oil, mercury, radiation, natural gas, hydrogen, and ammonia), elevators repairs as required by an outage, FGD tanks and ducts to be washed out, and condenser and ZBL system cleaning. Estimated are based off previous work orders found in TEC's Work Management System (Workman).

Asbestos Abatement – Asbestos abatement includes abating known areas of asbestos (turbine building and elevators siding, piping insulation, cable trays, etc.) as well as an allowance for unknown areas that may be discovered. Cost includes an allowance for scaffolding and half of an asbestos supervisor's time during the length of the dismantlement. Estimated are based off previous work orders found in TEC's Work Management System (Workman).

Payroll – Payroll was estimated by accounting for all the TEC team members assumed to work on the project. A total cost was calculated by using their hourly rate and amount of time assumed to be spent on the project.

Security – During dismantlement, the number of contractors onsite will increase resulting in some additional security measures.

Permitting & Compliance – Includes an allowance for environmental studies, environmental compliance fees, legal fees, FAA permits, and Asbestos notifications.

Tampa Electric Company
Big Bend Station Unit 3
Dismantling Study



Project No.: A09476.301
Date: December 28, 2020
Rev. 0, Use

E. Labor Wage Rates

Craft labor rates were developed for TEC as part of the Modernization project through a labor study conducted by S&L. The labor study based rates used in the 2018 study and cost estimates have been escalated for 2020. Costs have been added to cover social security, workmen's compensation, federal and state unemployment insurance. The resulting burdened craft rates were then used to develop typical crew rates applicable to the task being performed. No adjustments to labor rates or productivity have been accounted for in the estimate for long term COVID-19 impacts.

Demolition Estimates:

Labor Work Schedule and Incentives – Assumed 5 days x 8 hour day work week.

Pre and Post Demolition Estimates:

Labor Work Schedule and Incentives – Assumed 5 days x 10 hour day work week.

Per diem is not required.

For addition estimates only, a regional labor productivity multiplier of 1.1 is included based on Compass International Global Construction Yearbook. The use of this productivity factor is an approach to compare construction productivity in various locations in the USA to a known basis or benchmark of 1.00 for Texas, Gulf Coast productivity. Productivity multiplier does not include weather related delays.

F. Construction Equipment

Construction equipment cost is included on each estimate line as needed based on the type of activity and construction equipment requirements to perform the work.

G. Construction Direct/Indirect Costs and General Conditions

The estimate is constructed in such a manner where most of the direct construction costs are determined directly and several direct construction cost accounts are determined indirectly by taking a percentage of the directly determined costs. These percentages are based on our experience with similar type and size projects. Listed below are the additional costs included, unless noted as not included.

➤ Additional Labor Costs:

- Labor Supervision
- Show-up time
- Cost of overtime
- Per diem – not included

➤ Site Overheads:

- Construction Management
- Field Office Expenses
- Material & Quality Control
- Site Services
- Safety
- Temporary Facilities

Tampa Electric Company
Big Bend Station Unit 3
Dismantling Study



Project No.: A09476.301
Date: December 28, 2020
Rev. 0, Use

- Temporary Utilities
- Mobilization/Demobilization
- Legal Expenses/Claims
- Other Construction Indirect costs:
 - Small Tools and Consumables
 - Scaffolding
 - General Liability Insurance
 - Construction Equipment Mobilization/Demobilization
 - Freight on Material
 - Freight on Process Equipment – included with equipment cost
 - Sales Tax – not included
 - Contractors General & Administration (G&A) Expense
 - Contractors Profit
- Project Indirect Costs:
 - A/E Engineering Services
 - A/E Construction Management
 - A/E Start-up and Commissioning support
 - Start-Up Spare Parts
 - Owner's cost
 - EPC Fee – not included
 - AFUDC - not included

H. Scrap Value

The scrap values used are the credit to the utility based on current industry data.

- Mixed Steel value @ \$207/Ton
- #2 Copper @ \$5090/Ton
- #1 Insulated copper wire 65% @ \$2684/Ton

Note: 1 ton = 2000 Lbs.

Scrap values have changed since the 2018 cost estimates. The mixed steel value is down 17% and the copper values are up 12%. Scrap values can fluctuate month-to-month and should not be relied upon to reduce the cost of demolition during the planning stage.

I. Contingency

A 20% contingency was initially used for all costs in the Unit 3 estimates included with Attachment 1. We consider this to be appropriate and consistent with AACE guidelines, given our experience with fossil plant demolition as well as the level of project definition that has been achieved to date. However, TEC requested that the contingency be modified to 15%. Since this request occurred after completion of the estimates, an adjustment to the total project cost has been included.

Contingency is applied at 10% to scrap value since this decreases the credit from scrap material in the cost estimate.

Tampa Electric Company
Big Bend Station Unit 3
Dismantling Study



Project No.: A09476.301
Date: December 28, 2020
Rev. 0, Use

J. Escalation

Escalation cost is included and calculated based on the following rates, project schedule and cash flow expenditures as reflected in the cash flow curves for each cost category.

Escalation is included considering Unit 3 dismantling beginning in the second quarter of 2024.

2.5% / year for materials
3% / year for subcontract costs
3% / year for labor
2.5% / year for construction equipment
3% / year for project indirect costs
0% / year for scrap metal

K. Costs Excluded

All known scope of required physical facilities as provided by the project team to encompass a complete project has been included in the estimate. There are no known intentional omissions.

The cost estimate represents only the costs listed in the estimate. The estimate does not include allowances for any other costs not listed and incurred by the owner. Excluded costs (and some of which are also listed in "Assumptions/Clarifications") are any that are not listed in the estimate.

There may be additional costs that the Owner should consider such as (the list below is not all inclusive):

- Legal costs
- Owner's Bond Fees
- Taxes
- Station insurance costs and taxes are not included
- Performance Bonds

L. Scope Assumptions/Clarifications/Exclusions

Electrical

- All plant systems will be drained, electrical equipment and wiring is de-energized and tagged out by the client prior to demolition activities.
- Switchyards within the plant boundaries are not part of the scope; neither are access roads and rail lines to these facilities
- Overhead transmission towers are not included in this study.
- U4 intake structure loads are already fed from Unit 4. No repowering is necessary.
- Loads are based on expected loading of equipment of this nature.
- New raceway (1,500 feet of cable tray and over 40,000 feet of conduit) is conservatively included for repowering of the existing Unit 3 loads.
- New raceway is supported from existing steel members.
- Cabling between the Modernization Unit 1 switchgear connects to the reserve 3 current limiting reactor. An allowance of over 10,000 feet of 5kV cable to be replaced is included in the estimate.

Tampa Electric Company
Big Bend Station Unit 3
Dismantling Study



Project No.: A09476.301
Date: December 28, 2020
Rev. 0, Use

- Unit 4 reserve switchgear has available capacity and spare feeder breaker to feed the new repowering medium voltage switchgear.
- An allowance is included for lightning protection.
- Allowances are included for new access lighting for areas that will remain in use after the dismantling.
- An allowance is included for any DCS reconfiguration and control modifications are required after dismantling.
- Estimate excludes TEC Energy Delivery costs for removal of high voltage lines to the switchyard.

Decommissioning

- All chemicals and oils will be removed by TEC prior to demolition.
- Cleaning and flushing of chemical and oil storage pipes and tanks are by TEC.
- All storage tanks will be emptied by TEC.
- No remediation or removal of contaminated spills is required (no known spills exist).
- Coal bunkers and ash silos will be emptied by TEC.

Structural

- All items that extend more than 1'-0" above top of foundation will be demolished to grade level. Any other items will remain in place.
- A 6" asphalt layer (average thickness) shall be laid in areas where overhead steel will be removed to create a better walking surface, provide adequate drainage and prevent pooling.
- All borrow and backfill soil material is assumed to be purchased from offsite sources.
- Coating system for new steel is galvanized.

Mechanical

- Large diameter cooling water pipes/tunnels will be abandoned in place and filled to prevent ingress of water or collapse.
- The Station Air compressors for Unit 3 (Compressors #5 & #6) must be kept in service. Repowering and controls modifications are required. A source of cooling water will be required.
- The Unit 3 Settling Basin must stay in service.
- The Unit 3 Floor Drain Sumps must stay in operation, which will require repowering and controls modification. The Floor and Equipment Drain system in the Boiler and Turbine area must stay in operation, with modifications at equipment drains.
- Auxiliary steam will be routed from Unit 1 to Unit 4 by the Modernization project.
- Close Coal chutes in the tripper room for Unit 3 bunkers.
- Unit 3 Gypsum pipes to dewatering are to be demolished.
- Repower Unit 4 Clean and Dirty Oil tank system from Unit 4
- The Unit 3-4 Polisher must stay in service and be repowered from Unit 4 and requires controls modification.
- Fire protection panel for Unit 3 must be interfaced with the DCS.
- Ammonia loop branch to Unit 3 SCR will be capped.
- Detailed design phase required to further investigate assumptions.

Tampa Electric Company
 Big Bend Station Unit 3
 Dismantling Study



Project No.: A09476.301
 Date: December 28, 2020
 Rev. 0, Use

General

- All demolished non-metal materials except concrete are considered debris and shall be transported to a licensed landfill.
- It is assumed that concrete will be processed for recycling onsite and removed offsite by a concrete recycling company at no cost or credit to the Utility.
- Scrap value for recoverable metals is included in the estimate as a credit. No resale of equipment or material is included.
- The estimate assumes that all structural steel, miscellaneous building steel, decking grating, piping, and equipment will be removed to drop-off containers as provided by the scrap metal recycling company. The recycling company will assume all responsibility for the safe removal/disposal of lead paint and processing of the steel, which is reflected in the value of scrap metal.
- Cost of removing mobile equipment and machinery is by TEC.
- Site Construction Management costs assume one CM per unit for the duration of pre-demolition and demolition.

M. Cost Comparison to 2018 Estimate

The organization of the estimates into new categories does not allow for direct comparison of the individual estimates created for this study; however, the total cost by unit can be compared.

	2018	2020	Change
Unit 3	\$45,378,044	\$50,568,243	\$5,190,199 (11.4%)
Scrap Value Unit 3	\$(6,154,126)	\$(5,226,829)	

The total 2020 cost for dismantlement of Unit 3 has increased by 11.4% from the 2018 estimate. The increase can be attributed to several factors.

While labor rates have increased from those used in the 2018 study, the chimney demolition has decreased. The cost for demolishing the Unit 3 wet FGD chimney is based on the updated 2020 budget quote from Pullman for the Unit 1 and 2 Chimney. Their updated 2020 quote for the Unit 1 and 2 Chimney identified a 25% cost reduction based on having obtained new equipment that allows for a more efficient means of chimney demolition. This reduced their cost from 2018 by \$1,300,000.

TEC requested some major additions after completion of the cost estimates contained in Attachment 1. These additions include:

- Allowance to refurbish the Turbine Building ventilation based on Gannon lessons learned. The ventilation will require rework once the structures and equipment are removed south of the tripper bay. Due to the open Turbine Building between all the units, a cost of \$2,500,000 has been included to address the ventilation for Units 3 and 4. This value becomes \$3.45 million with 15% contingency and escalation.
- Allowance to renovate the office, warehouse and shop space adjacent to the Turbine Building. These renovations are estimated at \$1,000,000. This value becomes \$1.38 million with 30% contingency and escalation.

Tampa Electric Company
Big Bend Station Unit 3
Dismantling Study



Project No.: A09476.301
Date: December 28, 2020
Rev. 0, Use

- Allowance for water usage for dust control during dismantlement activity has been added in at \$120,000.
- Decrease of the contingency of the base estimates from 20% to 15%, which results in a decrease of approximately \$1.71 million.

See Attachment 1 for further breakdown of the additional allowances.

N. Schedule

A level 2 schedule has been developed to reflect the latest retirement date for Unit 3. The schedule in Attachment 3 uses April 2024 for the retirement date of Unit 3; however, TEC recently confirmed that retirement of Unit 3 will be one year earlier. The earlier retirement date has very little impact to the finish date since the main schedule drivers are budgetary constraints and the Units 1 and 2 dismantlement schedules. The dismantlement budget allocations do not allow for any significant construction spending until 2024 and removal of the Unit 2 boiler structure is essential to allowing adequate operating space for Unit 3 dismantlement activities. The schedule can only be improved by two months with the earlier retirement date due to these schedule limitations. This small gain has not been incorporated into the report.

Planning and engineering can start at any time. The schedule basis is beginning activities in the second quarter of 2023, which provides a completion date four years after project start.

Activities that should begin in 2023:

Task	Responsibility
Project Scope Authorization (PSA)	TEC
Assign internal staff responsibilities	TEC
Hazardous Material Survey	TEC/AE
Pre-demolition design activities – Electrical feed modifications	AE
Pre-demolition design activities – Structural stability bracing	AE
Demolition – Develop Scoping	AE
Permitting	TEC/AE

This schedule was reviewed with TEC in October and is used to develop the cost estimate escalation values and as the cash flow basis. Key engineering activities should start soon after project authorization in order to ensure adequate time is allotted to install essential “Pre-demolition” scope modifications prior to demolition start.

Tampa Electric Company
Big Bend Station Unit 3
Dismantling Study



Project No.: A09476.301
Date: December 28, 2020
Rev. 0, Use

ATTACHMENT 1

Cost Estimate Summary, Cash Flow and Individual Estimates

Tampa Electric Company
 Big Bend Station Unit 3
 Dismantling Study



Project No.: A09476.301
 Date: December 28, 2020
 Rev. 0, Use

INITIAL ESTIMATE SUMMARY						
	Direct Cost	General Conditions	Project Indirect Costs	Contingency	Escalation	Total
Unit 3						
Pre Demolition Modifications	\$3,869,185	\$1,959,403	\$116,572	\$1,189,032	\$1,232,675	\$8,366,867
Demolition	\$13,372,055	\$2,816,507	\$4,932,320	\$4,224,176	\$3,633,015	\$28,978,073
Post Demolition	\$2,787,735	\$733,100	\$436,020	\$791,300	\$888,900	\$5,637,055
Engineering Demolition Support	\$0	\$0	\$3,213,250	\$642,700	\$492,100	\$4,348,050
Total	\$20,028,975	\$5,509,010	\$8,698,162	\$6,847,208	\$6,246,690	\$47,330,045
Unit 3 Scrap Value	\$5,226,829	SEE BELOW FOR ADJUSTED TOTALS				

ADJUSTMENTS TO UNIT 3 COST ESTIMATES						
	Direct Cost	General Conditions	Project Indirect Costs	Contingency	Escalation	Total
Unit 3						
Change in Contingency from 20% to 15%	\$0	\$0	\$0	\$(1,711,802)	\$0	\$(1,711,802)
Turbine Building Allowance for Ventilation	\$2,500,000	\$0	\$0	\$375,000	\$575,000	\$3,450,000
Offices & Warehouse Renovation Allowance	\$1,000,000	\$0	\$0	\$150,000	\$230,000	\$1,380,000
Water Usage During Dismantlement for Dust Control	\$0	\$120,000	\$0	\$0	\$0	\$120,000
Additional Cost Total	\$3,500,000	\$120,000	\$0	\$(1,186,802)	\$805,000	\$3,238,198


ADJUSTED TOTAL FOR UNIT 3 COST ESTIMATES						
	Direct Cost	General Conditions	Project Indirect Costs	Contingency	Escalation	Total
Unit 3 – Adjusted Total						
Estimate Total	\$20,028,975	\$5,509,010	\$8,698,162	\$6,847,208	\$6,246,690	\$47,330,045
Adjustments	\$3,500,000	\$120,000	\$0	\$(1,186,802)	\$805,000	\$3,238,198
Adjusted Total	\$23,528,975	\$5,629,010	\$8,698,162	\$5,660,406	\$7,051,690	\$50,568,243

Project No.: A09476-301
 Date: December 28, 2020
 Rev. 0, Use

Tampa Electric Company
 Big Bend Station Unit 3
 Dismantlement Study

2022	2023				2024				2025				2026				2027	
	1st Quarter	2nd Quarter	3rd Quarter	4th Quarter	1st Quarter	2nd Quarter	3rd Quarter	4th Quarter	1st Quarter	2nd Quarter	3rd Quarter	4th Quarter	1st Quarter	2nd Quarter	3rd Quarter	4th Quarter	1st Quarter	2nd Quarter
Total (\$000s)	314	1,074	1,074	1,555	2,092	3,622	3,814	3,694	3,904	3,840	3,647	4,048	4,783	5,298	5,536	1,881	132	50,568
Unit 3 Total Project Cost	574	1,647	2,721	4,276	6,368	9,990	13,804	17,498	21,402	25,242	28,889	32,937	37,720	43,018	48,555	50,436	132	50,568
Cumulative	260																	

Big Bend 2020 Unit 3 Dismantlement Study Cash Flow



TEC
BIG BEND STATION
UNIT 3 PRE DEMOLITION MODIFICATIONS

Estimator	GA
Labor rate table	20FLTAM DEMO
Project No.	A09476-301
Estimate Date	10/23/20
Reviewed By	BA
Approved By	BA
Estimate No.	35256A
Cost index	FLTAM

DOCKET NO. 20210034-EI
EXHIBIT NO. CRB-1
WITNESS: BEITEL
DOCUMENT NO. 2
PAGE 29 OF 63
FILED: 04/09/2021

Estimate No.: 35256A
 Project No.: A09476-301
 Estimate Date: 10/23/20
 Prep/Rev/App: ONENBA

TEC
 BIG BEND STATION
 UNIT 3 PRE DEMOLITION MODIFICATIONS



Group	Description	Subcontract Cost	Process Equipment Cost	Material Cost	Man Hours	Labor Cost	Equip Amount	Total Cost
21.00.00	CIVIL WORK			13,826	166	9,639	2,589	26,054
22.00.00	CONCRETE			19,604	857	35,683	6,695	65,361
23.00.00	STEEL			245,990	4,194	229,475	96,485	571,950
35.00.00	PIPING	350,000						350,000
41.00.00	ELECTRICAL EQUIPMENT	100,000	205,000		352	18,728	4,995	328,723
42.00.00	RACEWAY, CABLE TRAY & CONDUIT	400,000		235,015	16,251	950,699	19,943	1,605,657
43.00.00	CABLE	200,000		256,333	3,599	213,394	51,692	721,420
44.00.00	CONTROL & INSTRUMENTATION	200,000						200,000
	TOTAL DIRECT	1,250,000	205,000	770,968	25,419	1,460,818	182,399	3,869,185

DOCKET NO. 20210034-EI
 EXHIBIT NO. CRB-1
 WITNESS: BEITEL
 DOCUMENT NO. 2
 PAGE 30 OF 63
 FILED: 04/09/2021

TEC
 BIG BEND STATION
 UNIT 3 PRE DEMOLITION MODIFICATIONS



Estimate Totals

Description	Amount	Totals	Hours
Labor	1,450,818		25,419
Material	770,968		
Subcontract	1,250,000		
Construction Equipment	182,399		
Process Equipment	295,000		
	3,869,185	3,869,185	
General Conditions			
Additional Labor Costs			
90-1 Labor Supervision	87,649		
90-2 Show-up Time	29,216		
90-3 Cost Plus 10% TO T 5-10's	255,513		
90-4 Cost Plus 10% TO T 6-10's			
90-5 Per Dem			
Site Overheads			
91-1 Construction Management	316,215		
91-2 Field Office Expenses	194,386		
91-3 Material&Quality Control	49,271		
91-4 Site Services	40,468		
91-5 Safety	31,167		
91-6 Temporary Facilities	23,713		
91-7 Temporary Utilities	25,544		
91-8 Mobilization/Demob	24,690		
91-9 Legal Expenses/Claims	3,692		
Other Construction Indirects			
92-1 Small Tools & Consumables	47,330		
92-2 Scaffolding	110,438		
92-3 General Liability Insur.	15,777		
92-4 Constr. Equip. Mob/Demob	1,824		
92-5 Freight on Material	38,548		
92-6 Freight on Process Equip			
92-7 Insurance	260,615		
92-8 Contractions G&A	372,307		
92-9 Contractions Profit	1,959,403	5,828,558	
Project Indirect Costs			
93-1 Engineering Services			
93-2 CM Support			
93-3 Start-Up/Commissioning	116,572		
93-4 Start-Up/Spare Parts			
93-5 Excess Liability Insur.			
93-6 Sales Tax On Indirects			
93-7 Owners Cost			
93-8 EPC Fee	116,572	5,945,160	
Contingency			
94-1 Contingency on Const Eq	43,046		
94-3 Contingency on Material	189,427		
94-4 Contingency on Labor	642,245		
94-5 Contingency on Subcontr.	250,000		
94-6 Contingency on Process Eq	41,000		
94-7 Contingency on Indirect	23,312		
	1,169,032	7,134,192	
Escalation			
96-1 Escalation on Const Equip	27,462		
96-3 Escalation on Material	158,784		
96-4 Escalation on Labor	724,532		
96-5 Escalation on Subcontract	293,489		
96-6 Escalation on Process Equip			
96-7 Escalation on Indirects	28,408		
	1,232,675	8,366,867	
98 Interest During Constr			
		8,366,867	
Total		8,366,867	

Estimate No.: 35256A
 Project No.: A09476-301
 Estimate Date: 10/23/20
 Prep/Rev/Appr: GAB/GA

TEC
 BIG BEND STATION
 UNIT 3 PRE DEMOLITION MODIFICATIONS



Group	Phase	Description	Notes	Quantity	Subcontract Cost	Process Equipment Cost	Material Cost	Man Hours	Labor Cost	Equip Amount	Total Cost	
21.00.00	21.17.00	CIVIL WORK										
		EXCAVATION										
		FOUNDATION EXCAVATION, COMMON EARTH USING 1 CY BACKHOE	FOUNDATION FOR CABLE RACK	335.11 CY	-	-	-	55	3,213	863	4,076	
		FOUNDATION EXCAVATION, COMMON EARTH USING 1 CY BACKHOE	15FT L. x 12FT W. x 3FT D. FOR BMVA TRANSFORMER	74.37 CY	-	-	-	12	713	192	905	
	21.19.00	EXCAVATION										
		DISPOSAL										
		DISPOSAL OF EXCESS MATERIAL USING DUMP TRUCK, 4 MI ROUND TRIP	15FT L. x 12FT W. x 3FT D. FOR BMVA TRANSFORMER	74.37 CY	-	-	-	5	285	77	362	
		DISPOSAL OF EXCESS MATERIAL USING DUMP TRUCK, 4 MI ROUND TRIP	FOUNDATION FOR CABLE RACK	335.11 CY	-	-	-	22	1,285	345	1,630	
	21.20.00	DISPOSAL										
		BACKFILL										
		FOUNDATION BACKFILL, SELECT STRUCTURAL FILL	15FT L. x 12FT W. x 3FT D. FOR BMVA TRANSFORMER	70.19 CY	-	-	-	12	673	181	3,100	
		FOUNDATION BACKFILL, SELECT STRUCTURAL FILL	FOUNDATION FOR CABLE RACK	361.87 CY	-	-	-	60	3,469	932	15,981	
13,826 1,113 19,081												
22.00.00	22.13.00	CIVIL WORK										
		CONCRETE										
		CONCRETE										
		MAT FOUNDATION LESS THAN 5 FT THICK, 4500 PSI	15FT L. x 12FT W. x 3FT D. FOR BMVA TRANSFORMER	16.94 CY	-	-	-	23	886	288	3,272	
	22.15.00	CONCRETE										
		CONCRETE										
		MAT FOUNDATION LESS THAN 5 FT THICK, 4500 PSI	FOUNDATION FOR CABLE RACK	27.70 CY	-	-	-	38	1,449	438	5,350	
		CONCRETE WALL, 4500 PSI	TRANSFORMER FIRE WALL	9.00 CY	-	-	-	20	753	228	2,106	
	6,706 933 10,728											
	22.17.00	FORMWORK										
		FORMWORK										
		BUILT UP INSTALL & STRIP	15FT L. x 12FT W. x 3FT D. FOR BMVA TRANSFORMER	315.02 SF	-	-	-	69	3,163	504	4,454	
BUILT UP INSTALL & STRIP		FOUNDATION FOR CABLE RACK	1,712.00 SF	-	-	-	377	17,188	2,739	24,207		
22.25.00	REINFORCING											
	REINFORCING											
	UNCOATED A615 GR60	TRANSFORMER FIRE WALL	1,024.00 SF	-	-	-	225	10,281	1,638	14,479		
	UNCOATED A615 GR60	FOUNDATION FOR CABLE RACK		-	-	-	671	30,631	4,892	43,140		
7,628 4,892 43,140												
23.00.00	23.25.00	STEEL										
		STEEL										
		ROLLED SHAPE										
		MEDIUM WEIGHT MEMBERS, 21 LB/LF TO 40 LB/LF, GALVANIZED	CABLE RACK	22.00 TN	-	-	-	411	22,514	10,292	102,217	
	23.27.00	STEEL										
		STEEL										
		MEDIUM WEIGHT MEMBERS, 21 LB/LF TO 40 LB/LF, GALVANIZED	BRACING FOR ADDITIONS	36.00 TN	-	-	-	1,010	55,262	16,842	185,584	
		REINFORCING EXISTING STRUCTURAL STEEL WITH COVER PLATES	STABILITY BRACING FOR TURBINE BUILDING	18.00 TN	-	-	-	2,772	151,699	69,350	284,049	
	245,990 4,194 571,950											
	35.00.00	35.13.45	STEEL									
			STEEL									
			STEEL									
MISC. ABOVE GROUND, PROCESS AREA												
245,990 4,194 571,950												
35.13.45		STEEL										
		STEEL										
		STEEL										
		MISC. ABOVE GROUND, PROCESS AREA										
245,990 4,194 571,950												
35.13.45		STEEL										
		STEEL										
	STEEL											
	MISC. ABOVE GROUND, PROCESS AREA											
245,990 4,194 571,950												

Estimate No.: 35256A
Project No.: A09476-301
Estimate Date: 10/23/20
Prep/Rev/Appr: GAB/BA

TEC
BIG BEND STATION
UNIT 3 PRE DEMOLITION MODIFICATIONS



Group	Phase	Description	Notes	Quantity	Subcontract Cost	Process Equipment Cost	Material Cost	Man Hours	Labor Cost	Equip Amount	Total Cost	
35.13.45		MISC. ABOVE GROUND, PROCESS AREA	MODIFICATIONS TO EXISTING PIPE SYSTEMS, NATURAL GAS HEADER, AMMONIA SUPPLY HEADER, FIRE PROTECTION, SERVICE WATER, COMPRESS AIR AND GASES PIPING	1.00 LS	350,000	-					350,000	
		MISC. ABOVE GROUND, PROCESS AREA									350,000	
		PIPING									350,000	
41.00.00	41.47.00	ELECTRICAL EQUIPMENT	ALLOWANCE	1.00 LS	100,000	-					100,000	
		PANEL: CONTROL, DISTRIBUTION, & RELAY									100,000	
		STATION RESERVE SYSTEM RECONFIGURATION									100,000	
41.51.00		POWER TRANSFORMER	INCLUDING OIL, PAD MOUNTED TRANSFORMER (ALLOWANCE)	1.00 LS	-	205,000		352	18,728	4,995	228,723	
		8MVA, 13.8KV/4160V TRANSFORMER, INCLUDING OIL									228,723	
		POWER TRANSFORMER									228,723	
42.00.00	42.13.02	RACEWAY, CABLE TRAY & CONDUIT	SUPPORTED FROM EXISTING STEEL STRUCTURE	1,500.00 LF	-	-	4,320	114	6,661	140	11,121	
		CABLE TRAY COVER, ALUMINUM									11,121	
		24 IN WIDE INCLUDING FITTINGS									11,121	
42.13.37		CABLE TRAY, ALUMINUM	SUPPORTED FROM EXISTING STEEL STRUCTURE	1,500.00 LF	-	-	38,445	2,886	168,839	3,542	210,826	
		CABLE TRAY, ALUMINUM									210,826	
		24 IN WIDE LADDER TYPE INCLUDING SUPPORTS AND FITTINGS									210,826	
42.15.13		CONDUIT, ALUMINUM	FOR OXIDATION BLOWER, 1, 2, 3 & 4 (4 CONDUITS x 500FT) ON EXISTING STEEL SUPPORT	37,000.00 LF	-	-	104,340	8,751	511,955	10,739	627,035	
		1 IN DIA INCLUDING ELBOWS, UNISTRUT SUPPORTS, AND MISC HARDWARE									627,035	
		1-1/2 IN DIA INCLUDING ELBOWS, UNISTRUT SUPPORTS, AND MISC HARDWARE									627,035	
42.15.13		CONDUIT, ALUMINUM	FOR OXIDATION BLOWER, 1, 2, 3 & 4 (4 CONDUITS x 500FT) ON EXISTING STEEL SUPPORT	2,000.00 LF	-	-	9,400	563	32,951	691	43,042	
		2 IN DIA INCLUDING ELBOWS, UNISTRUT SUPPORTS, AND MISC HARDWARE									43,042	
		2 IN DIA INCLUDING ELBOWS, UNISTRUT SUPPORTS, AND MISC HARDWARE									43,042	
42.15.13		CONDUIT, ALUMINUM	FOR OXIDATION BLOWER, 1, 2, 3 & 4 (4 CONDUITS x 500FT) ON EXISTING STEEL SUPPORT	2,000.00 LF	-	-	12,800	697	40,802	866	54,468	
		2 IN DIA INCLUDING ELBOWS, UNISTRUT SUPPORTS, AND MISC HARDWARE									54,468	
		2 IN DIA INCLUDING ELBOWS, UNISTRUT SUPPORTS, AND MISC HARDWARE									54,468	
42.15.13		CONDUIT, ALUMINUM	FOR OXIDATION BLOWER, 1, 2, 3 & 4 (4 CONDUITS x 500FT) ON EXISTING STEEL SUPPORT	2,000.00 LF	-	-	18,500	908	53,030	1,112	72,642	
		3 IN DIA INCLUDING ELBOWS, UNISTRUT SUPPORTS, AND MISC HARDWARE									72,642	
		3 IN DIA INCLUDING ELBOWS, UNISTRUT SUPPORTS, AND MISC HARDWARE									72,642	
42.15.13		CONDUIT, ALUMINUM	FOR OXIDATION BLOWER, 1, 2, 3 & 4 (4 CONDUITS x 500FT) ON EXISTING STEEL SUPPORT	2,000.00 LF	-	-	24,300	1,278	74,782	1,589	100,651	
		3 IN DIA INCLUDING ELBOWS, UNISTRUT SUPPORTS, AND MISC HARDWARE									100,651	
		3 IN DIA INCLUDING ELBOWS, UNISTRUT SUPPORTS, AND MISC HARDWARE									100,651	
42.15.13		CONDUIT, ALUMINUM	FOR OXIDATION BLOWER, 1, 2, 3 & 4 (4 CONDUITS x 500FT) ON EXISTING STEEL SUPPORT	400.00 LF	-	-	4,860	256	14,956	314	20,130	
		3 IN DIA INCLUDING ELBOWS, UNISTRUT SUPPORTS, AND MISC HARDWARE									20,130	
		3 IN DIA INCLUDING ELBOWS, UNISTRUT SUPPORTS, AND MISC HARDWARE									20,130	
43.00.00	43.10.00	CABLE	ALLOWANCE	1,000.00 LF	-	-	18,050	799	46,723	980	65,753	
		ON EXISTING STEEL MEMBERS									65,753	
		MISCELLANEOUS SIZE CONDUITS									65,753	
43.00.00		RACEWAY, CABLE TRAY & CONDUIT	ALLOWANCE	1.00 LS	400,000	-	192,250	13,251	775,199	16,261	1,383,710	
		CONDUIT, ALUMINUM									1,383,710	
		RACEWAY, CABLE TRAY & CONDUIT									1,383,710	
43.10.00		CABLE	ALLOWANCE	1.00 LS	400,000	-	235,015	16,251	950,699	19,943	1,605,657	
		CONDUIT, ALUMINUM									1,605,657	
		RACEWAY, CABLE TRAY & CONDUIT									1,605,657	
43.20.00		CABLE	ALLOWANCE	1.00 LS	400,000	-	235,015	16,251	950,699	19,943	1,605,657	
		CONDUIT, ALUMINUM									1,605,657	
		RACEWAY, CABLE TRAY & CONDUIT									1,605,657	
43.20.00		CABLE	ALLOWANCE	1.00 LS	400,000	-	235,015	16,251	950,699	19,943	1,605,657	
		CONDUIT, ALUMINUM									1,605,657	
		RACEWAY, CABLE TRAY & CONDUIT									1,605,657	
43.20.00		CABLE	ALLOWANCE	1.00 LS	400,000	-	235,015	16,251	950,699	19,943	1,605,657	
		CONDUIT, ALUMINUM									1,605,657	
		RACEWAY, CABLE TRAY & CONDUIT									1,605,657	
43.20.00		CABLE	ALLOWANCE	1.00 LS	400,000	-	235,015	16,251	950,699	19,943	1,605,657	
		CONDUIT, ALUMINUM									1,605,657	
		RACEWAY, CABLE TRAY & CONDUIT									1,605,657	
43.20.00		CABLE	ALLOWANCE	1.00 LS	400,000	-	235,015	16,251	950,699	19,943	1,605,657	
		CONDUIT, ALUMINUM									1,605,657	
		RACEWAY, CABLE TRAY & CONDUIT									1,605,657	
43.20.00		CABLE	ALLOWANCE	1.00 LS	400,000	-	235,015	16,251	950,699	19,943	1,605,657	
		CONDUIT, ALUMINUM									1,605,657	
		RACEWAY, CABLE TRAY & CONDUIT									1,605,657	
43.20.00		CABLE	ALLOWANCE	1.00 LS	400,000	-	235,015	16,251	950,699	19,943	1,605,657	
		CONDUIT, ALUMINUM									1,605,657	
		RACEWAY, CABLE TRAY & CONDUIT									1,605,657	
43.20.00		CABLE	ALLOWANCE	1.00 LS	400,000	-	235,015	16,251	950,699	19,943	1,605,657	
		CONDUIT, ALUMINUM									1,605,657	
		RACEWAY, CABLE TRAY & CONDUIT									1,605,657	
43.20.00		CABLE	ALLOWANCE	1.00 LS	400,000	-	235,015	16,251	950,699	19,943	1,605,657	
		CONDUIT, ALUMINUM									1,605,657	
		RACEWAY, CABLE TRAY & CONDUIT									1,605,657	
43.20.00		CABLE	ALLOWANCE	1.00 LS	400,000	-	235,015	16,251	950,699	19,943	1,605,657	
		CONDUIT, ALUMINUM									1,605,657	
		RACEWAY, CABLE TRAY & CONDUIT									1,605,657	
43.20.00		CABLE	ALLOWANCE	1.00 LS	400,000	-	235,015	16,251	950,699	19,943	1,605,657	
		CONDUIT, ALUMINUM									1,605,657	
		RACEWAY, CABLE TRAY & CONDUIT									1,605,657	
43.20.00		CABLE	ALLOWANCE	1.00 LS	400,000	-	235,015	16,251	950,699	19,943	1,605,657	
		CONDUIT, ALUMINUM									1,605,657	
		RACEWAY, CABLE TRAY & CONDUIT									1,605,657	
43.20.00		CABLE	ALLOWANCE	1.00 LS	400,000	-	235,015	16,251	950,699	19,943	1,605,657	
		CONDUIT, ALUMINUM									1,605,657	
		RACEWAY, CABLE TRAY & CONDUIT									1,605,657	
43.20.00		CABLE	ALLOWANCE	1.00 LS	400,000	-	235,015	16,251	950,699	19,943	1,605,657	
		CONDUIT, ALUMINUM									1,605,657	
		RACEWAY, CABLE TRAY & CONDUIT									1,605,657	
43.20.00		CABLE	ALLOWANCE	1.00 LS	400,000	-	235,015	16,251	950,699	19,943	1,605,657	
		CONDUIT, ALUMINUM									1,605,657	
		RACEWAY, CABLE TRAY & CONDUIT									1,605,657	
43.20.00		CABLE	ALLOWANCE	1.00 LS	400,000	-	235,015	16,251	950,699	19,943	1,605,657	
		CONDUIT, ALUMINUM									1,605,657	
		RACEWAY, CABLE TRAY & CONDUIT									1,605,657	
43.20.00		CABLE	ALLOWANCE	1.00 LS	400,000	-	235,015	16,251	950,699	19,943	1,605,657	
		CONDUIT, ALUMINUM									1,605,657	
		RACEWAY, CABLE TRAY & CONDUIT									1,605,657	
43.20.00		CABLE	ALLOWANCE	1.00 LS	400,000	-	235,015	16,251	950,699	19,943	1,605,657	
		CONDUIT, ALUMINUM									1,605,657	
		RACEWAY, CABLE TRAY & CONDUIT									1,605,657	
43.20.00		CABLE	ALLOWANCE	1.00 LS	400,000	-	235,015	16,251	950,699	19,943	1,605,657	
		CONDUIT, ALUMINUM									1,605,657	
		RACEWAY, CABLE TRAY & CONDUIT									1,605,657	
43.20.00		CABLE	ALLOWANCE	1.00 LS	400,000	-	235,015	16,251	950,699	19,943	1,605,657	
		CONDUIT, ALUMINUM									1,605,657	
		RACEWAY, CABLE TRAY & CONDUIT									1,605,657	
43.20.00		CABLE	ALLOWANCE	1.00 LS	400,000	-	235,015	16,251	950,699	19,943	1,605,657	
		CONDUIT, ALUMINUM									1,605,657	
		RACEWAY, CABLE TRAY & CONDUIT									1,605,657	
43.20.00		CABLE	ALLOWANCE	1.00 LS	400,000	-	235,015	16,251	950,699	19,943	1,605,657	
		CONDUIT, ALUMINUM									1,605,657	
		RACEWAY, CABLE TRAY & CONDUIT									1,605,657	
43.20.00		CABLE	ALLOWANCE	1.00 LS	400,000	-	235,015	16,251	950,699	19,943	1,605,657	
		CONDUIT, ALUMINUM									1,605,657	
		RACEWAY, CABLE TRAY & CONDUIT									1,605,657	
43.20.00		CABLE	ALLOWANCE	1.00 LS	400,000	-	235,015	16,251	950,699	19,943	1,605,657	
		CONDUIT, ALUMINUM									1,605,657	
		RACEWAY, CABLE TRAY & CONDUIT									1,605,657	
43.20.00		CABLE	ALLOWANCE	1.00 LS	400,000	-	235,015	16,251	950,699	19,943	1,605,657	
		CONDUIT, ALUMINUM									1,605,657	
		RACEWAY, CABLE TRAY & CONDUIT									1,605,657	
43.20.00		CABLE	ALLOWANCE	1.00 LS	400,000	-	235,015	16,251	950,699	19,943	1,605,657	
		CONDUIT, ALUMINUM									1,605,657	
		RACEWAY, CABLE TRAY & CONDUIT									1,605,657	
43.20.00		CABLE	ALLOWANCE	1.00 LS	400,000	-	235,015	16,251	950,699	19,943	1,605,657	
		CONDUIT, ALUMINUM									1,605,657	
		RACEWAY, CABLE TRAY & CONDUIT									1,605,657	
43.20.00		CABLE	ALLOWANCE	1.00 LS	400,000	-	235,015	16,251	950,699	19,943	1,605,657	
		CONDUIT, ALUMINUM									1,605,657	
		RACEWAY, CABLE TRAY & CONDUIT									1,605,657	
43.20.00		CABLE	ALLOWANCE	1.00 LS	400,000	-	235,015	16,251	950,699	19,943	1,605,657	
		CONDUIT, ALUMINUM									1,605,657	
		RACEWAY, CABLE TRAY & CONDUIT									1,605,657	
43.20.00		CABLE	ALLOWANCE	1.00 LS	400,000	-	235,015	16,251	950,699	19,943	1,605,657	
		CONDUIT, ALUMINUM									1,605,657	
		RACEWAY, CABLE TRAY & CONDUIT									1,605,657	
43.20.00		CABLE	ALLOWANCE	1.00 LS	400,000	-	235,015	16,251	950,699	19,943	1,605,657	
		CONDUIT, ALUMINUM									1,605,657	
		RACEWAY, CABLE TRAY & CONDUIT									1,605,657	
43.20.00		CABLE	ALLOWANCE	1.00 LS	400,000	-	235,015	16,251	950,699	19,943	1,605,657	
		CONDUIT, ALUMINUM									1,605,657	
		RACEWAY, CABLE TRAY & CONDUIT									1,605,657	
43.20.00		CABLE	ALLOWANCE	1.00 LS	400,000	-	235,015	16,251	950,699	19,943	1,605,657	
		CONDUIT, ALUMINUM									1,605,657	
		RACEWAY, CABLE TRAY & CONDUIT									1,605,657	
43.20.00		CABLE	ALLOWANCE	1.00 LS	400,000	-	235,015	16,251	950,699	19,943	1,605,657	
		CONDUIT, ALUMINUM									1,605,657	
		RACEWAY, CABLE TRAY & CONDUIT									1,605,657	
43.20.00		CABLE	ALLOWANCE	1.00 LS	400,000	-	235,015	16,251	950,699	19,943	1,605,657	
		CONDUIT, ALUMINUM									1,605,657	
		RACEWAY, CABLE TRAY & CONDUIT									1,605,657	
43.20.00		CABLE	ALLOWANCE	1.00 LS	400,000	-	235,015	16,251	950,699	19,943	1,605,657	
		CONDUIT, ALUMINUM									1,605,657	
		RACEWAY, CABLE TRAY & CONDUIT									1,605,657	
43.20.00		CABLE	ALLOWANCE	1.00 LS	400,000	-	235,015	16,251	950,699	19,943	1,605,657	
		CONDUIT, ALUMINUM									1,605,657	
		RACEWAY, CABLE TRAY & CONDUIT									1,605,657	
43.20.00		CABLE	ALLOWANCE	1.00 LS	400,000	-	235,015	16,251	950,699	19,943	1,605,657	
		CONDUIT, ALUMINUM									1,605,657	
		RACEWAY, CABLE TRAY & CONDUIT									1,605,657	
43.20.00		CABLE	ALLOWANCE	1.00 LS	400,000	-	235,015	16,251	950,699	19,943	1,605,657	
		CONDUIT, ALUMINUM									1,605,657	
		RACEWAY, CABLE TRAY & CONDUIT									1,605,657	
43.20.00		CABLE	ALLOWANCE	1.00 LS	400,000	-	235,015	16,251	950,699	19,943	1,605,657	
		CONDUIT, ALUMINUM									1,605,657	
		RACEWAY, CABLE TRAY & CONDUIT									1,605,657	
43.20.00		CABLE	ALLOWANCE	1.00 LS	400,000	-	235,015	16,251	950,699	19,943	1,605,657	
		CONDUIT, ALUMINUM									1,60	

Estimate No.: 35256A
 Project No.: A09476-301
 Estimate Date: 10/23/20
 Prep/Rev/Appr: GAB/BA

TEC
 BIG BEND STATION
 UNIT 3 PRE DEMOLITION MODIFICATIONS



Group	Phase	Description	Notes	Quantity	Subcontract Cost	Process Equipment Cost	Material Cost	Man Hours	Labor Cost	Equip Amount	Total Cost
43.20.00		600V CABLE & TERMINATION									
		TERMINATION - COMPRESSION LUG, #10, 1 HOLE, COPPER	22 CABLES x 3 x 2"	132.00 EA	-	-	290	36	2,152	521	2,864
		TERMINATION - COMPRESSION LUG, #8, 2 HOLE, COPPER	15 CABLES x 3 x 2"	90.00 EA	-	-	585	30	1,761	427	2,773
		TERMINATION - COMPRESSION LUG, #4, 2 HOLE, COPPER	2 CABLES x 3 x 2"	12.00 EA	-	-	111	7	391	95	597
		TERMINATION - COMPRESSION LUG, #10, 2 HOLE, COPPER	2 CABLES x 3 x 2"	12.00 EA	-	-	165	10	564	137	865
		TERMINATION - COMPRESSION LUG, #40, 2 HOLE, COPPER	2 CABLES x 3 x 2"	12.00 EA	-	-	216	15	861	209	1,286
		TERMINATION - COMPRESSION LUG, #250, 2 HOLE, COPPER	2 CABLES x 3 x 2"	6.00 EA	-	-	126	9	540	131	797
		TERMINATION - COMPRESSION LUG, #750, 2 HOLE, COPPER	FOR CEMES SHELTER FEEDER TERMINATION (3 x 2) FOR CONSTRUCTION TRAILER FEEDER TERMINATIONS	6.00 EA	-	-	372	20	1,186	287	1,845
		600V CABLE & TERMINATION					142,583	2,369	140,437	34,019	317,039
43.40.00		5/8KV CABLE & TERMINATION									
		5KV #10 3/C CU EPRTS-CPE	FOR OXIDATION BLOWER-1	500.00 LF	-	-	6,275	39	2,332	565	9,172
		5KV #10 3/C CU EPRTS-CPE	FOR OXIDATION BLOWER-2	500.00 LF	-	-	6,275	39	2,332	565	9,172
		5KV #10 3/C CU EPRTS-CPE	FOR OXIDATION BLOWER-3	500.00 LF	-	-	6,275	39	2,332	565	9,172
		5KV #750 KMIL 1/C CU	4160KV SWGRB TO 8MVA TRANSFORMER FEEDER - CABLE RUN VIA CABLE TRAY (1500FT x 6")	9,000.00 LF	-	-	87,570	960	56,942	13,793	159,305
		TERMINATION - COMPRESSION LUG, #10, 2 HOLE, COPPER	FOR OXIDATION BLOWER-1	6.00 EA	-	-	84	13	783	190	1,056
		TERMINATION - COMPRESSION LUG, #10, 2 HOLE, COPPER	FOR OXIDATION BLOWER-2	6.00 EA	-	-	84	13	783	190	1,056
		TERMINATION - COMPRESSION LUG, #10, 2 HOLE, COPPER	FOR OXIDATION BLOWER-3	6.00 EA	-	-	84	13	783	190	1,056
		TERMINATION - COMPRESSION LUG, #10, 2 HOLE, COPPER	FOR OXIDATION BLOWER-4	6.00 EA	-	-	84	13	783	190	1,056
		TERMINATION - COMPRESSION LUG, #750, 2 HOLE, COPPER	6 x 2"	12.00 EA	-	-	744	60	3,557	882	5,163
		5/8KV CABLE & TERMINATION					113,750	1,231	72,957	17,673	204,380
		CABLE			200,000		256,333	3,599	213,394	51,692	721,420
44.00.00		CONTROL & INSTRUMENTATION									
44.13.00		CONTROL SYSTEM									
		DISTRIBUTED CONTROL SYSTEM, RE-PROGRAMMING COST	SERVICE BY VENDOR (ALLOWANCE)	1.00 EA	200,000	-	-	-	-	-	200,000
		CONTROL SYSTEM			200,000						200,000
		CONTROL & INSTRUMENTATION			200,000						200,000

TEC
BIG BEND STATION
UNIT 3 DEMOLITION

Estimator	GA
Labor rate table	20FLTAM DEMO
Project No.	A09476-301
Estimate Date	10/23/20
Reviewed By	BA
Approved By	BA
Estimate No.	35257A

Estimate No.: 35257A
 Project No.: A0476-301
 Estimate Date: 10/23/20
 Prep./Rev./App.: GA/BA/BA

TEC
 BIG BEND STATION
 UNIT 3 DEMOLITION



Group	Description	Subcontract Cost	Scrap Value	Material Cost	Man Hours	Labor Cost	Equip Amount	Total Cost
10.00.00	WHOLE PLANT DEMOLITION	7,203,198			74,355	3,434,737	1,576,964	12,214,899
11.00.00	DEMOLITION				601	32,900	16,546	49,447
22.00.00	CONCRETE	40,000		229,045	1,206	45,857	15,238	330,140
23.00.00	STEEL			518,925	3,145	172,094	86,550	777,570
	TOTAL DIRECT	7,243,198		747,970	79,307	3,685,689	1,695,298	13,372,055

DOCKET NO. 20210034-EI
 EXHIBIT NO. CRB-1
 WITNESS: BEITEL
 DOCUMENT NO. 2
 PAGE 36 OF 63
 FILED: 04/09/2021

TEC
 BIG BEND STATION
 UNIT 3 DEMOLITION



Estimate Totals

Description	Amount	Totals	Hours
Labor	3,695,689		79,307
Material	747,970		
Subcontract	7,243,198		
Construction Equipment	1,695,298		
Process Equipment		13,372,055	
General Conditions			
Additional Labor Costs			
90-1 Labor Supervision	221,135		
90-2 Show-Up Time	73,712		
90-3 Cost Due To E-10s			
90-4 Cost Due To OT 6-10s			
90-5 Per Diem			
Site Overheads			
91-1 Construction Management	797,799		
91-2 Field Office Expenses	87,570		
91-3 Material/Quality Control			
91-4 Site Services			
91-5 Safety	78,634		
91-6 Temporary Facilities	59,826		
91-7 Temporary Utilities			
91-8 Mobilization/Demob.	63,050		
91-9 Legal Expenses/Claims	9,314		
Other Construction Indirects			
92-1 Small Tools & Consumables	39,804		
92-2 Scaffolding			
92-3 General Liability Insur.	39,804		
92-4 Constr. Equip. Mob/Demob	16,953		
92-5 Freight on Material	37,399		
92-6 Freight on Process Equip			
92-7 Insurance			
92-8 Contractors G&A	531,797		
92-9 Contractors Profit	759,710	16,188,562	
Project Indirect Costs	2,816,507		
93-1 Engineering Services			
93-2 CM Support			
93-3 Start-Up/Commissioning			
93-4 Start-Up/Spare Parts			
93-5 Excess Liability Insur.			
93-6 Sales Tax On Indirects			
93-7 Owners Cost	4,932,320		
93-8 EPC Fee		21,120,882	
Contingency	4,932,320		
94-1 Contingency on Const Eq	400,090		
94-3 Contingency on Material	183,776		
94-4 Contingency on Labor	1,205,206		
94-5 Contingency on Subcontr.	1,448,640		
94-6 Contingency on Process Eq	986,464		
94-7 Contingency on Indirects	4,224,176	25,345,058	
Escalation			
96-1 Escalation on Const Equip	265,618		
96-2 Escalation on Material	172,004		
96-4 Escalation on Labor	1,256,638		
96-5 Escalation on Subcontract	1,256,600		
96-6 Escalation on Process Eq			
96-7 Escalation on Indirects	782,005	28,978,073	
98 Interest During Constr	3,633,015	28,978,073	
Total		28,978,073	

Estimate No. : 35257A
Project No. A09476-301
Estimate Date: 10/23/20
Prep/Rev/Appr: GA/BA/BA

TEC
BIG BEND STATION
UNIT 3 DEMOLITION



Group	Phase	Description	Notes	Quantity	Subcontract Cost	Scrap Value	Material Cost	Man Hours	Labor Cost	Equip Amount	Total Cost
10.00.00		WHOLE PLANT DEMOLITION									
	10.22.00	CONCRETE	BUILDING/EQUIPMENT FOUNDATION/PAD	1,003.00 CY	-	-	-	2,031	111,750	43,993	155,743
		CONCRETE						2,031	111,750	43,993	155,743
10.23.00		STEEL									
		STRUCTURAL, GIRT AND GALLERY STEEL	BOILER	2,347.00 TN	-	-	-	4,292	214,438	69,382	283,800
		STRUCTURAL, GIRT AND GALLERY STEEL	PRECIP BOX	1,344.00 TN	-	-	-	1,912	95,509	30,893	126,402
		STRUCTURAL, GIRT AND GALLERY STEEL	PRECIP STEEL	689.00 TN	-	-	-	952	47,541	15,378	62,919
		STRUCTURAL, GIRT AND GALLERY STEEL	FGD	773.00 TN	-	-	-	1,100	54,932	17,768	72,700
		STRUCTURAL, GIRT AND GALLERY STEEL	FLY ASH SILO #2 AND STEEL	153.00 TN	-	-	-	218	10,873	3,517	14,390
		STRUCTURAL, GIRT AND GALLERY STEEL	BALANCED DRAFT STEEL	716.00 TN	-	-	-	1,018	50,881	16,458	67,339
		STRUCTURAL, GIRT AND GALLERY STEEL	SCR	977.00 TN	-	-	-	1,390	69,429	22,457	91,886
		DUCTWORK AND STEEL SUPPORTS	DUCTWORK REMOVAL	2,816.00 TN	-	-	-	10,534	445,065	236,385	681,450
		DUCTWORK AND STEEL SUPPORTS	SCR DUCTWORK REMOVAL	899.00 TN	-	-	-	3,363	142,086	75,465	217,551
		DEMO CIRCULATING WATER DISCHARGE STRUCTURE		1.00 LS	500,000	-	-				500,000
		STEEL			500,000			24,778	1,130,754	487,683	2,118,437
10.25.00		CONCRETE CHIMNEY & STACK									
		CONCRETE CHIMNEY		1.00 LS	3,550,000	-	-				3,550,000
		CONCRETE CHIMNEY & STACK			3,550,000						3,550,000
10.31.00		MECHANICAL EQUIPMENT									
		MAIN BOILER AND APPURTENANCES		8,391.00 TN	-	-	-	23,788	1,188,473	512,166	1,700,639
		STEAM TURBINE GENERATOR		1,411.00 TN	-	-	-	4,000	169,008	89,764	258,772
		FEEDWATER DEARATING EQUIPMENT		149.00 TN	-	-	-	422	17,847	9,479	27,326
		BOP EQUIPMENT INCLUDING PUMPS, HEAT EXCHANGERS, COMPRESSORS, TANKS, CHEMICAL		1,050.00 TN	-	-	-	3,005	126,965	67,434	194,400
		FEED, WATER AND OIL SYSTEMS, ETC.									
		ASH / DUST COLLECTOR EQUIPMENT		186.00 TN	-	-	-	527	22,279	11,833	34,112
		FGD EQUIPMENT		220.00 TN	-	-	-	624	26,351	13,996	40,347
		SLAG DEWATERING EQUIPMENT		465.00 TN	-	-	-	1,224	51,719	27,469	79,188
		CONDENSER		353.00 TN	-	-	-	1,001	42,282	22,457	64,739
10.35.00		MECHANICAL EQUIPMENT						34,592	1,644,924	754,598	2,399,522
		PIPING									
		PIPING, VALVES AND HANGERS	INCLUDES ALL PIPING SYSTEMS WITHIN THE BOILER AND TURBINE AREA SUCH AS: MAIN STEAM, HOT/COLD REHEAT, BOILER FEED, FEEDWATER, CONDENSATE, SERVICE WATER, ETC.	1,856.00 TN	-	-	-	6,943	293,339	155,799	449,138
10.37.00		ASBESTOS REMOVAL									
		ASBESTOS ABATEMENT		1.00 LS	3,153,198	-	-				3,153,198
		ASBESTOS REMOVAL	COST PROVIDED BY TECO		3,153,198						3,153,198
10.41.00		ELECTRICAL EQUIPMENT									
		TRANSFORMERS		370.00 TN	-	-	-	989	41,770	22,185	63,955
		MISCELLANEOUS ELECTRICAL EQUIPMENT	MCC'S, CABINETS, PANELS, ETC.	346.00 TN	-	-	-	925	39,061	20,746	59,807
10.42.00		ELECTRICAL EQUIPMENT						1,913	80,831	42,931	123,762
		RACEWAY, CABLE TRAY, & CONDUIT									
		CONDUIT		172.00 TN	-	-	-	1,118	47,236	25,088	72,323
10.43.00		RACEWAY, CABLE TRAY, & CONDUIT									
		CABLE		200.00 TN	-	-	-	1,200	50,700	26,928	77,628
		CABLE STRIPPABLE CABLE		178.00 TN	-	-	-	2,318	97,936	52,016	149,951
WHOLE PLANT DEMOLITION											
				178.00 TN	-	-	-	1,780	75,205	39,943	115,148
				74,355	7,203,198			74,355	3,434,737	1,576,964	12,214,899

Estimate No.: 35257A
 Project No.: A09476-301
 Estimate Date: 10/23/20
 Prep/Rev/Appr: GA/BABA

TEC
 BIG BEND STATION
 UNIT 3 DEMOLITION



Group	Phase	Description	Notes	Quantity	Subcontract Cost	Scrap Value	Material Cost	Man Hours	Labor Cost	Equip Amount	Total Cost
11.00.00	11.23.00	DEMOLITION									
		STEEL									
		STRUCTURAL STEEL	REMOVE TEMPORARY STEEL FOR SCR	140.00 TN	-	-	-	455	24,898	12,522	37,419
		STRUCTURAL STEEL	REMOVE TEMPORARY STEEL FOR BOILER	45.00 TN	-	-	-	146	8,003	4,025	12,028
		STEEL						601	32,900	16,546	49,447
		DEMOLITION						601	32,900	16,546	49,447
22.00.00	22.13.00	CONCRETE									
		CONCRETE									
		FLOWABLE FILL, 1500 PSI	FILL CIRCULATING WATER TUNNEL	2,411.00 CY	-	-	229,045	1,206	45,857	15,238	290,140
		CONCRETE FLOOD WALL REPAIRS		1.00 LS	40,000	-	-				40,000
		CONCRETE			40,000		229,045	1,206	45,857	15,238	330,140
		CONCRETE			40,000		229,045	1,206	45,857	15,238	330,140
23.00.00	23.25.00	STEEL									
		ROLLED SHAPE									
		MEDIUM WEIGHT MEMBERS, 21 LB/LF TO 40 LB/LF, PRIME PAINTED ONLY	TEMPORARY STEEL FOR SCR	140.00 TN	-	-	392,700	2,380	130,234	65,498	588,431
		MEDIUM WEIGHT MEMBERS, 21 LB/LF TO 40 LB/LF, PRIME PAINTED ONLY	TEMPORARY STEEL FOR BOILER	45.00 TN	-	-	126,225	765	41,861	21,053	189,139
		STEEL					518,925	3,145	172,094	86,550	777,570
		STEEL					518,925	3,145	172,094	86,550	777,570

TEC
 BIG BEND STATION
 UNIT 3 POST DEMOLITION

Estimator	GA
Labor rate table	20FLTAM DEMO
Project No.	A09476-301
Estimate Date	10/23/20
Reviewed By	BA
Approved By	BA
Estimate No.	35258A
Cost index	FLTAM

Estimate No.: 35258A
 Project No.: A09476-301
 Estimate Date: 10/23/20
 Prep/Rev/App: ONBABA

TEC
 BIG BEND STATION
 UNIT 3 POST DEMOLITION



Group	Description	Subcontract Cost	Process Equipment Cost	Material Cost	Man Hours	Labor Cost	Equip Amount	Total Cost
10.00.00	WHOLE PLANT DEMOLITION							
21.00.00	CIVIL WORK	250,000		146,797	430	20,691	8,879	250,000
23.00.00	STEEL			227,215	1,691	92,016	25,733	175,367
24.00.00	ARCHITECTURAL	1,200,000		20,800	444	19,117	4,384	344,965
27.00.00	PAINTING & COATING			103,500	7,970	371,974	44,629	1,244,301
41.00.00	ELECTRICAL EQUIPMENT	250,000						520,103
	TOTAL DIRECT	1,700,000		500,312	10,536	503,798	83,625	2,787,735

DOCKET NO. 20210034-EI
 EXHIBIT NO. CRB-1
 WITNESS: BEITEL
 DOCUMENT NO. 2
 PAGE 41 OF 63
 FILED: 04/09/2021

TEC
 BIG BEND STATION
 UNIT 3 POST DEMOLITION



Estimate Totals

Description	Amount	Totals	Hours
Labor	503,798		10,536
Material	500,312		
Subcontract	1,700,000		
Construction Equipment	83,625		
Process Equipment		2,787,735	
General Conditions			
Additional Labor Costs			
90-1 Labor Supervision	30,200		
90-2 Show-up Time	10,100		
90-3 Cost Plus Fee 5-10%	98,600		
90-4 Cost Plus Fee 10-15%			
90-5 Per Diem			
Site Overheads			
91-1 Construction Management	109,100		
91-2 Field Office Expenses	67,000		
91-3 Material&Quality Control	17,000		
91-4 Site Services	14,000		
91-5 Safety	10,700		
91-6 Temporary Facilities	8,200		
91-7 Temporary Utilities	6,000		
91-8 Mobilization/Demob	8,600		
91-9 Legal Expenses/Claims	1,300		
Other Construction Indirects			
92-1 Small Tools & Consumables	16,300		
92-2 Scaffolding	38,100		
92-3 General Liability Insur.	5,400		
92-4 Constr. Equip. Mob/Demob	800		
92-5 Freight on Material	25,000		
92-6 Freight on Process Equip			
92-7 Insurance	108,600		
92-8 Contractions G&A	155,100		
92-9 Contractions Profit	733,100	3,520,835	
Project Indirect Costs			
93-1 Engineering Services			
93-2 CM Support			
93-3 Start-Up/Commissioning			
93-4 Start-Up/Spare Parts			
93-5 Excess Liability Insur.			
93-6 Sales Tax On Indirects			
93-7 Overhead Cost	436,020		
93-8 EPC Fee	436,020	3,956,855	
Contingency			
94-1 Contingency on Const Eq	19,700		
94-3 Contingency on Material	122,900		
94-4 Contingency on Labor	221,500		
94-5 Contingency on Subcontr.	340,000		
94-6 Contingency on Process Eq			
94-7 Contingency on Indirect	87,200		
	791,500	4,748,355	
Escalation			
96-1 Escalation on Const Equip	14,300		
96-3 Escalation on Material	104,600		
96-4 Escalation on Labor	246,800		
96-5 Escalation on Subcontract	413,000		
96-6 Escalation on Process Equip			
96-7 Escalation on Indirects	110,200		
	888,900	5,637,055	
98 Interest During Constr		5,637,055	
Total		5,637,055	

Group	Phase	Description	Notes	Quantity	Subcontract Cost	Process Equipment Cost	Material Cost	Man Hours	Labor Cost	Equip Amount	Total Cost
10.00.00	10.99.00	WHOLE PLANT DEMOLITION DEMOLITION, MISCELLANEOUS INSPECT, CLEAN OUT AND REPAIR DRAINS DEMOLITION, MISCELLANEOUS WHOLE PLANT DEMOLITION		1.00 LS	250,000 250,000 250,000	-	-				250,000 250,000 250,000
21.00.00	21.57.00	CIVIL WORK ROAD, PARKING AREA, & SURFACED AREA BITUMINOUS ASPHALT ROAD, PARKING AREA, & SURFACED AREA CIVIL WORK	ASPHALT TO REPAVE REMOVED BOILER AREA AND TO THE SOUTH	1,503.00 TN	-	-	148,797 148,797	430 430	20,691 20,691	8,879 8,879	178,367 178,367
23.00.00	23.17.00	STEEL GALLERY GALVANIZED GRATING, 2" DEEP x 3/16" BEARING BAR WITH HOLD DOWN CLIPS GALLERY ROLLED SHAPE MEDIUM WEIGHT MEMBERS, 21 LBLF TO 40 LBLF, GALVANIZED ROLLED SHAPE STEEL	FOR TURBINE DECK GRATING	4,200.00 SF	-	-	97,860 97,860	924 924	50,058 50,058	6,552 6,552	154,470 154,470
24.00.00	24.17.00	ARCHITECTURAL ELEVATOR FREIGHT ELEVATOR ELEVATOR ROOFING METAL, UNINSULATED ROOFING SIDING METAL, UNINSULATED, 24 GA, GALVANIZED CORRUGATED SIDING ARCHITECTURAL	FOR TURBINE DECK GRATING	41.00 TN	-	-	129,355 129,355 227,215	767 767 1,691	41,958 41,958 92,016	19,181 19,181 25,733	190,494 190,494 344,965
27.00.00	27.17.00	PAINING & COATING PAINTING STEEL PAINTING STEEL PAINTING PAINTING PAINING & COATING	REPAIRING ROOF, CLOSING OPENINGS AND OTHER LOCATIONS	2,400.00 SF	-	-	7,800 7,800	264 264	10,329 10,329	1,354 1,354	19,482 19,482
41.00.00	41.35.00	ELECTRICAL EQUIPMENT LIGHTNING PROTECTION LIGHTNING PROTECTION LIGHTING ACCESSORY (FIXTURE) LIGHTING - FIXTURES, ACCESSORY LIGHTING ACCESSORY (FIXTURE) ELECTRICAL EQUIPMENT	ALLOWANCE	1.00 LS	100,000 100,000	-	-				100,000 100,000
41.00.00	41.37.00	ELECTRICAL EQUIPMENT LIGHTNING PROTECTION LIGHTNING PROTECTION LIGHTING ACCESSORY (FIXTURE) LIGHTING - FIXTURES, ACCESSORY LIGHTING ACCESSORY (FIXTURE) ELECTRICAL EQUIPMENT	ALLOWANCE	1.00 LS	150,000 150,000	-	-				150,000 150,000
					250,000						250,000

TEC
BIG BEND STATION
UNIT 3 ENGINEERING DEMOLITION SUPPORT

Estimator	GA
Labor rate table	20FLTAM DEMO
Project No.	A09476-301
Estimate Date	10/23/20
Reviewed By	BA
Approved By	BA
Estimate No.	35259A
Cost index	FLTAM

DOCKET NO. 20210034-EI
EXHIBIT NO. CRB-1
WITNESS: BEITEL
DOCUMENT NO. 2
PAGE 44 OF 63
FILED: 04/09/2021

Group	Description	Subcontract Cost	Scrap Value	Material Cost	Man Hours	Labor Cost	Equip Amount	Total Cost
-------	-------------	------------------	-------------	---------------	-----------	------------	--------------	------------

TEC
 BIG BEND STATION
 UNIT 3 ENGINEERING DEMOLITION SUPPORT



Estimate Totals

Description	Amount	Totals	Hours
Labor			
Material			
Subcontract			
Construction Equipment			
Process Equipment			
General Conditions			
Additional Labor Costs			
90-1 Labor Supervision			
90-2 Show-Up Time			
90-3 Cost Due To E-10s			
90-4 Cost Due To OT 6-10s			
90-5 Per Diem			
Site Overheads			
91-1 Construction Management			
91-2 Field Office Expenses			
91-3 Material/Quality Control			
91-4 Site Services			
91-5 Safety			
91-6 Temporary Facilities			
91-7 Temporary Utilities			
91-8 Mobilization/Demob.			
91-9 Legal Expenses/Claims			
Other Construction Indirects			
92-1 Small Tools & Consumables			
92-2 Scaffolding			
92-3 General Liability Insur.			
92-4 Constr. Equip. Mob/Demob			
92-5 Freight on Material			
92-6 Freight on Process Equip			
92-7 Insurance			
92-8 Contractors G&A			
92-9 Contractors Profit			
Project Indirect Costs			
93-1 Engineering Services	2,023,250		
93-2 CM Support	1,190,000		
93-3 Start-Up/Commissioning			
93-4 Start-Up/Spare Parts			
93-5 Excess Liability Insur.			
93-6 Sales Tax On Indirects			
93-7 Owners Cost			
93-8 EPC Fee			
	<u>3,213,250</u>	<u>3,213,250</u>	
Contingency			
94-1 Contingency on Const Eq			
94-3 Contingency on Material			
94-4 Contingency on Labor			
94-5 Contingency on Subcontr.			
94-6 Contingency on Process Eq			
94-7 Contingency on Indirect			
	<u>642,700</u>	<u>642,700</u>	
		<u>3,855,950</u>	
Escalation			
96-1 Escalation on Const Equip			
96-3 Escalation on Material			
96-4 Escalation on Labor			
96-5 Escalation on Subcontract			
96-6 Escalation on Process Eq			
96-7 Escalation on Indirects			
	<u>492,100</u>	<u>492,100</u>	
		<u>4,348,050</u>	
98 Interest During Constr			
		<u>4,348,050</u>	
Total		4,348,050	

TEC
BIG BEND STATION UNIT 3 DEMOLITION
DEMOLITION UNIT 3 SCRAP VALUE

Estimator	GA
Labor rate table	20FLTAM DEMO
Project No.	A09476-301
Estimate Date	10/23/20
Reviewed By	BA
Approved By	BA
Estimate No.	35225A

DOCKET NO. 20210034-EI
EXHIBIT NO. CRB-1
WITNESS: BEITEL
DOCUMENT NO. 2
PAGE 47 OF 63
FILED: 04/09/2021

Group	Description	Subcontract Cost	Scrap Value	Material Cost	Man Hours	Labor Cost	Equip Amount	Total Cost
18.00.00	SCRAP VALUE TOTAL DIRECT		(5,226.829) (5,226.829)					(5,226.829) (5,226.829)

TEC
 BIG BEND STATION UNIT 3 DEMOLITION
 DEMOLITION UNIT 3 SCRAP VALUE



Estimate Totals

Description	Amount	Totals	Hours
Labor			
Material			
Subcontract			
Construction Equipment			
Scrap Value	(5,226,829)	(5,226,829)	
General Conditions			
Additional Labor Costs			
90-1 Labor Supervision			
90-2 Show-Up Time			
90-3 Cost Due To T 5-10s			
90-4 Cost Due To OT 6-10s			
90-5 Per Diem			
Site Overheads			
91-1 Construction Management			
91-2 Field Office Expenses			
91-3 Material&Quality Control			
91-4 Site Services			
91-5 Safety			
91-6 Temporary Facilities			
91-7 Temporary Utilities			
91-8 Mobilization/Demob.			
91-9 Legal Expenses/Claims			
Other Construction Indirects			
92-1 Small Tools & Consumables			
92-2 Scaffolding			
92-3 General Liability Insur.			
92-4 Constr. Equip. Mob/Demob			
92-5 Freight on Material			
92-6 Freight on Scrap			
92-7 Insurance			
92-8 Contractors G&A			
92-9 Contractors Profit		(5,226,829)	
Project Indirect Costs			
93-1 Engineering Services			
93-2 CM Support			
93-3 Start-Up/Commissioning			
93-4 Start-Up/Spare Parts			
93-5 Excess Liability Insur.			
93-6 Sales Tax On Indirects			
93-7 Owners Cost			
93-8 EPC Fee		(5,226,829)	
Contingency			
94-1 Contingency on Const Eq			
94-3 Contingency on Material			
94-4 Contingency on Labor			
94-5 Contingency on Subcontr.			
94-6 Contingency on Scrap			
94-7 Contingency on Indirect			
Escalation			
96-1 Escalation on Const Equip			
96-3 Escalation on Material			
96-4 Escalation on Labor			
96-5 Escalation on Subcontract			
96-6 Escalation on Scrap			
96-7 Escalation on Indirects			
98 Interest During Constr		(5,226,829)	
Total		(5,226,829)	

Group	Phase	Description	Notes	Quantity	Subcontract Cost	Scrap Value	Material Cost	Man Hours	Labor Cost	Equip Amount	Total Cost
18.00.00		SCRAP VALUE									
	18.10.00	MIXED STEEL									
		CARBON STEEL, FREIGHT INCLUDED	INCLUDES CONTINGENCY	-25,748.00 TN	-	(4,796,852)	-				(4,796,852)
		MIXED STEEL				(4,796,852)					(4,796,852)
	18.30.00	COPPER									
		#1 INSULATED COPPER WIRE 65%, FREIGHT INCLUDED	INCLUDES CONTINGENCY	-178.00 TN	-	(429,977)	-				(429,977)
		COPPER				(429,977)					(429,977)
		SCRAP VALUE				(5,226,829)					(5,226,829)


Tampa Electric Company
Big Bend Station Unit 3
Dismantling Study





Project No.: A09476.301
Date: December 28, 2020
Rev. 0, Use

ATTACHMENT 2

Boiler Building Demolition and Bracing Schematics







Tampa Electric Company
Big Bend Station Unit 3
Dismantling Study



Project No.: A09476.301
Date: December 28, 2020
Rev. 0, Use

ATTACHMENT 3

Dismantling Sequence Schedule

Elisavinda E. Laursen

Tampa Electric Company
Big Bend Station Unit 3
Dismantling Study



Project No.: A09476.301
Date: December 28, 2020
Rev. 0, Use

ATTACHMENT 4

Application of Gannon Lessons Learned to Big Bend Dismantling

Attachment 4
Application of Gannon Lessons Learned to Big Bend Dismantling

Sargent & Lundy

Lesson Learned Category and Description		Address Lesson Learned with:			Remarks
		Estimate	Engineering	Contract	
1 COORDINATION					
1.1	The plant required constant communication of the status.			X	The execution contracts will include regular status meetings.
1.2	Walk-downs were performed weekly with plant managers, and every single time revealed issues that were added to the scope.	X			The dismantlement study has used these lessons learned to minimize the potential for extra work.
1.3	The duration it took to demolish the last unit boiler was much greater than the contractor had estimated.	X		X	The study schedule uses long durations for demolition. The contractor will be required to maintain a schedule.
2 DRAWINGS					
2.1	Most drawings had outdated information.		X		Reference drawings will be reviewed during engineering.
2.2	The drawings were never updated after the dismantlement because Jim Montgomery retired.		X		TEC will need to develop a plan on how to handle the drawing cleanup after demolition.
3 ARCHITECTURAL / BUILDING ENVELOPE					
3.1	New roofs had to be put on several structures. Roofs need to be designed to Factory Mutual standards. Installation must be well-documented.				Not applicable; no roofs have been identified as requiring replacement.
3.2	New siding was required where the boiler voids had been. There was significant effort to design, fabricate, and install the girts and wind columns to receive the siding.	X			Closing off of wall opening created by demolition has been included in the estimated quantities.
3.3	When we re-roofed the slab areas over the former boilers, we had to raise the height of the handrail which took engineering and construction effort.				Not applicable; Big Bend is not saving the boiler structures and any roof access is not changing.
3.4	The plant required additional interior and exterior lighting in the older areas of the plant.	X			New lighting has been included in the estimated quantities.
3.5	While areas of roofing and siding were exposed, there were problems controlling rainwater infiltration. We got complaints from operations a number of times.			X	Requirement to be placed on the contractor to provide temporary shielding when large openings are not sealed immediately after an opening is created.
3.6	Lightning protection was added to the entire turbine building.	X			Lightning protection has been included in the estimated quantities.
3.7	After the boilers were demolished, water was blowing in a door, so the plant made us add a canopy.			X	Similar to 3.5 above.
3.8	Many areas of roofing were damaged by the activities of the demolition, falling objects, and water infiltration. Roof deck was found to be rusted out and had to be replaced.	X			Roof replacement areas have been included in the estimate to account for known problems and potential damage during demolition.

Attachment 4
Application of Gannon Lessons Learned to Big Bend Dismantling

Sargent & Lundy

Lesson Learned Category and Description		Address Lesson Learned with:			Remarks
		Estimate	Engineering	Contract	
4	CIVIL (YARD)				
4.1	Earth crane pads were built for the very large crane that was used. These crane pads were spread around the site when the crane was relocated for the next unit. This resulted in a lot of extra fill that cost money to remove.			X	Contractor will be responsible for the means and methods of their work.
4.2	I had to review multiple lift plans and also evaluate pit walls for crane surcharge.		X	X	Contractor is responsible for lift plans as part of means and methods. Engineering should only be reviewing those plans.
4.3	Underground concrete was frequently in the way of new light pole bases and drains when we re-paved.		X		Addressed through adequate engineering planning of new lights.
4.4	Knowing the location of the circulating water tunnels was vital at all times. It would have paid to paint them on the ground surface at the start.			X	Intake lines are painted at grade. Requirement can be added to specification for contractor to mark discharge locations.
4.5	The plant made us revise the entrance gate with a new guard house, fencing, gates, and card readers.				Not applicable; new entrance is not anticipated for Big Bend.
5	CONCRETE				
5.1	At the screenwell structure, we had to design infill framing where the pumps and screens were removed.	X			In fill quantities are included in the estimate.
5.2	We had to infill pits around the old boiler feed pumps. This required engineering and construction.				This was not identified as necessary during the 2018 study.
5.3	Cable cutting was used to demo pedestals. It left some rough surfaces that were not great for walking.	X			The estimate includes asphalt paving to lessen the uneven surfaces created by demolition.

DOCKET NO. 20210034-EI
EXHIBIT NO. CRB-1
WITNESS: BEITEL
DOCUMENT NO. 2
PAGE 61 OF 63
FILED: 04/09/2021

Attachment 4

Application of Gannon Lessons Learned to Big Bend Dismantling

Sargent & Lundy

Lesson Learned Category and Description		Address Lesson Learned with:			Remarks
		Estimate	Engineering	Contract	
6	STEEL				
6.1	Much grating and handrail had to be replaced.				Not considered in the estimate; no areas of concern were identified during the 2018 study.
6.2	Checkered plate was rusty and had to be replaced in large areas.				Not considered in the estimate; no areas of concern were identified during the 2018 study.
6.3	Corroded pieces of steel were continuously discovered and had to be mitigated on an almost daily basis.				It is understood that this is likely the case at Big Bend; however, it was decided that a value could not be assigned to cover this situation.
6.4	The cost to repaint the steel inside the turbine building was estimated and was prohibitively expensive. We painted the exterior steel only.	X			Painting of both interior and remaining exterior steel is included in the estimate.
6.5	The entire structure had to be modeled to design the supplemental bracing steel and ensure that the turbine building was safely braced.		X		Some modeling was done during the 2018 study and is anticipated for the full design effort.
6.6	I was regularly asked to design field splices because beams could not be flown in between the webs of two columns.		X	X	Engineering should consider this when developing details; the project will need to work with the contractor.
6.7	I was asked to evaluate existing floors for lifts.		X	X	This should be the contractor's responsibility with review by engineering.
6.8	An over-height structure was required to ensure that trucks would not hit the pipe rack.				Not applicable to Big Bend
6.9	I was asked to evaluate beams for rigging loads many times. Rigging was especially difficult for the very heavy steam pipes.			X	This should be the contractor's responsibility.
6.10	The plate girders were hard to demolish. They are too large to lift at once, so we had to demo them in sections. We had the contractor hire a structural engineer to provide a sequencing plan. Even then, one of the pieces folded over while it was being flown.			X	Contractor is responsible for lift plans as part of means and methods. They will be required to hire a structural engineer to facilitate their work.
6.11	Some items that had tied back to the tripper building had to be resupported or replaced. For example, a hydrogen vent and a jib crane serving the cooling tower.	X			These were evaluated during the 2018 study and included in the estimate.

Attachment 4
Application of Gannon Lessons Learned to Big Bend Dismantling

Sargent & Lundy

Lesson Learned Category and Description		Address Lesson Learned with:		Remarks
		Estimate	Engineering	Contract
7	MECHANICAL			
7.1	Floor drains were filled with debris over time and had to be cleaned at great cost.	X		
7.2	Roof drains were leaking, missing, etc. and had to be refurbished. The scaffold was expensive, because it had to be suspended from the main turbine building roof trusses. This may not be an issue at Big Bend.	X		
7.3	Turbine building ventilation refurbishment due to demolition changing the building configuration.	X		
8	Construction Utilities			
8.1	Water usage fees associated with dust mitigation during demolition were in excess of \$100,000.	X		

The estimate includes an allowance for cleaning out and fixing the drains.

The estimate includes replacing some of the roof drains.

The adjusted costs to the estimate includes an allowance to replace the ventilation system.

An allowance has been included in the adjusted costs.