


**ORIGINAL  
FILE COPY**



**Florida  
Power**  
CORPORATION

**James A. McGee**  
SENIOR COUNSEL

February 25, 1989

Mr. Steven C. Tribble  
Director of Records and Reporting  
Florida Public Service Commission  
101 East Gaines Street  
Tallahassee, FL 32399-0872

Re: Docket No. 870098-EI

Dear Mr. Tribble:

Enclosed for filing in the subject matter are fifteen (15) copies of the Direct Testimony of Elizabeth A. Czura, Thomas S. LaGuardia, and Kenneth E. McDonald.

- ACK
- AFA 3
- APP
- CAF
- CMU
- CTR orig
- EAG 2
- LEG 1
- LIN 6
- OPC
- RCH
- SEC 1 JAM/jw
- WAS  Enclosures
- OTH  cc: Parties of Record

Please acknowledge receipt and filing of the above by completing the form provided on the enclosed copy of this letter and returning same to this writer.

Very truly yours,

James A. McGee

*Czura - 02111-89*  
*LaGuardia - 02112-89*  
*McDonald - 02113-89*

RECEIVED & FILED

FPSC-BU DEPT. OF RECORDS


**CERTIFICATE OF SERVICE**  
Docket No. 870098-EI

I HEREBY CERTIFY that a copy of the Direct Testimony of Elizabeth A. Czura, Thomas S. LaGuardia, and Kenneth E. McDonald have been served by delivery or U.S. Mail this 27th day of February, 1989, to the following:

Matthew M. Childs, Esquire  
Steel, Hector & Davis  
301 West College Avenue  
Tallahassee, FL 32301-1406

Gail P. Fels, Esquire  
Assistant City Attorney  
Dade County Attorney's Office  
111 NW First Street, Suite 2810  
Miami, FL 33128-1993

M. Robert Christ, Esquire  
Florida Public Service Commission  
101 East Gaines Street  
Fletcher Building - Room 226  
Tallahassee, FL 32399-0863

  
\_\_\_\_\_  
Attorney

FLORIDA POWER CORPORATION

DOCKET NO. 870098-EI

PREPARED DIRECT TESTIMONY OF

THOMAS S. LAGUARDIA

**ORIGINAL  
FILE COPY**

1 Q. Please state your name and business address.

2 A. My name is Thomas S. LaGuardia. My business address is 148  
3 New Milford Road East, Bridgewater, Connecticut 06752.

4 Q. With whom and in what capacity are you employed?

5 A. I am employed by TLG Engineering, Inc. in the capacity of  
6 president.

7 Q. What are your responsibilities as president of TLG  
8 Engineering, Inc.?

9 A. I am responsible for the technical and business management  
10 of the engineering consulting services in the areas of  
11 decontamination, decommissioning, waste management and  
12 general engineering for nuclear and fossil fueled  
13 generating stations.

14 Q. Please describe briefly your educational and professional  
15 background.

16 A. I completed my BSME at Polytechnic Institute of Brooklyn in  
17 1962 and my MSME at the University of Connecticut in 1968.  
18 I am a registered professional engineer in Connecticut (No.

1           10393) and New York (No. 059389). Prior to founding TLG  
2           Engineering in April, 1982, I was employed by Gulf Nuclear  
3           Fuels Corporation (formerly United Nuclear Corporation  
4           [UNC]), Combustion Engineering, and Nuclear Energy  
5           Services.

6   **Q.**     **Would you please describe your experience specific to the**  
7           **field of nuclear decommissioning?**

8   **A.**     My decommissioning experience began at site representative  
9           for UNC during the BONUS reactor decommissioning in 1969  
10          and 1970. BONUS was a 17 MWe demonstration power reactor  
11          and the largest reactor decommissioned by entombment up to  
12          that time. The program involved extensive chemical  
13          decontamination of radioactive systems, selective piping  
14          and component removal, and entombment of the reactor vessel  
15          within a massive concrete barrier. The entombment has a  
16          design life of 125 years. My role as site representative  
17          was to act as a technical liaison and provide project  
18          engineering and schedule management assistance during  
19          system decontamination, component removal, vessel  
20          entombment and facility closeout.

21           Following the BONUS program, I was lead engineer for UNC  
22           during the Elk River Reactor decommissioning between 1970-  
23           1974. Elk River was a 20 MWe demonstration power reactor  
24           that was decommissioned by complete dismantlement. The

1 program involved segmentation of the reactor vessel and  
2 internals using remotely operated cutting torches, as well  
3 as the packaging, shipping and controlled burial of the  
4 segments.

5 Similarly, radioactive piping and components were removed,  
6 packaged, shipped and buried. Radioactive concrete was  
7 demolished by controlled blasting, and nonradioactive  
8 concrete demolished by wrecking ball to completely  
9 dismantle the facility. Initially, my role for UNC was  
10 consulting engineer and later lead engineer for UNC  
11 technical support for on-site activities.

12 I was Project Engineer for the detailed engineering and  
13 planning of the Shippingport Station Decommissioning  
14 Project from 1979 - 1982. Shippingport was a 72 MWe light  
15 water breeder reactor. The facility is now almost  
16 completely dismantled, and TLG, with its joint venture  
17 partner Cleveland Wrecking Company, dismantled all of the  
18 piping and components and removing contaminated concrete.  
19 My role for TLG/Cleveland was Project Director, and I  
20 selected and managed an on-site project management team to  
21 hire and supervise work crews to accomplish the  
22 dismantling. Our work is complete and was performed on  
23 schedule and within budget.

1 I also assisted Atomic Energy of Canada, Ltd. in the  
2 detailed engineering and planning of the 238 MWe Gentilly  
3 Unit 1 reactor. My role was to provide overall  
4 decommissioning consulting services and detailed cost  
5 estimated of alternatives.

6 Q. Have you any prepared or co-authored any studies or reports  
7 on decommissioning cost estimating and technology?

8 A. While at Nuclear Energy Services, I was principal  
9 investigator for the Atomic Industrial Forum  
10 decommissioning study entitled "An Engineering Evaluation  
11 of Nuclear Power Reactor Decommissioning Alternatives"  
12 (AIF/NESP-009). This study evaluated the costs, schedule  
13 and environmental impacts of decommissioning 1100 MWe  
14 reactors (Pressure Water Reactors [PWRs], Boiling Water  
15 Reactors [BWRs], and High Temperature Gas Reactors  
16 [HTGRs]).

17 I also co-authored the "Decommissioning Handbook" for the  
18 U.S. Department of Energy (DOE). The Handbook reported the  
19 state of the art in decommissioning technology (as of  
20 1980), including decontamination, piping and component  
21 removal, vessel segmentation, concrete demolition, cost  
22 estimating and environmental impacts.

1           At TLG Engineering, I co-authored "Guidelines for Producing  
2           Commercial Nuclear Power Plant Decommissioning Cost  
3           Estimates" (AIF/NESP-036) for the Atomic Industrial Forum,  
4           National Environmental Studies Project. The Guidelines  
5           identify the elements of costs to be included in the  
6           estimation of decommissioning activities for each of the  
7           principal decommissioning alternatives. Specific guidance  
8           in cost estimating methodology and reference cost data is  
9           provided in this study. The major objective of this study  
10          is to provide a basis for consistent cost estimating  
11          methodology.

12          TLG Engineering also prepared a study entitled,  
13          "Identification and Evaluation of Facilitation Techniques  
14          for Decommissioning Light Water Power Reactors" (NUREG/CR-  
15          3587) for the Nuclear Regulatory Commission (NRC). The  
16          study evaluated the costs and benefits of techniques to  
17          reduce occupational exposure and waste volume from  
18          decommissioning. TLG Engineering has prepared site-  
19          specific decommissioning studies for most of the nuclear  
20          units in the United States at 21 fossil-fueled power  
21          plants. In addition, TLG prepared the Decommissioning Plan  
22          and Environmental Report (ER) for Dresden Unit 1, and the  
23          ER for Indian Point Unit 1.

24    Q.       What is the purpose of your testimony?

1 A. I am presenting the results of the decommissioning cost  
2 study dated April, 1986, which was prepared by TLG  
3 Engineering, Inc. for the Crystal River Unit 3 (CR3)  
4 Nuclear Plant. This study was commissioned by the Florida  
5 Power Corporation (FPC) as owner and operator of the  
6 station. My testimony includes the decommissioning  
7 alternatives evaluated, cost and schedule estimates, and a  
8 discussion of decommissioning feasibility.

9 Q. Do you have an exhibit to your testimony?

10 A. Yes, I will sponsor the decommissioning cost study  
11 identified in the preceding answer, which is contained in  
12 Section H of the Crystal River Nuclear Plant  
13 Decommissioning Study filed by FPC in this proceeding on  
14 January 26, 1987.

15 Q. What was the objective of the decommissioning cost study  
16 your firm prepared for Florida Power Corporation?

17 A. The objective of this study was to estimate the cost of  
18 decommissioning CR3 so that the contributions required to  
19 establish a decommissioning fund can be determined. The  
20 study is not a detailed decommissioning engineering plan,  
21 and therefore does not commit the participants to a  
22 specific course of action for the station following  
23 ultimate plant shutdown.



1 Q. Would you please summarize the decommissioning costs  
2 identified by your study?

3 A. The total cost to decommission and completely dismantle CR3  
4 is estimated to be \$176,576,500. This cost was developed  
5 in constant 1985 dollars and includes a 25% contingency  
6 allowance for the 72 month program. The cost estimate does  
7 not include future inflation or consider the cost of money  
8 over the time period involved.

9 Q. Please describe how the decommissioning study was  
10 performed.

11 A. The study was developed using the detailed engineering  
12 drawings, together with plant description and inventory  
13 documents provided by FPC as owner and operator. These  
14 drawings and documents were used to identify the general  
15 arrangement of the facility and to determine an estimate of  
16 building concrete volumes, steel quantities, numbers and  
17 size of components and degree of site restoration required.  
18 I personally made a site inspection of the plant, including  
19 access to the facility to determine movement of heavy  
20 equipment (cranes, fork-lifts, front-end loaders) close to  
21 the structures for demolition and removal work.

22 Decommissioning is a labor-intensive program.  
23 Representative labor rates for each geographical region and  
24 each craft or salaried work group are essential for

1           development of a meaningful site-specific decommissioning  
2           cost estimate. Accordingly, FPC provided typical craft  
3           labor rates and utility salary data.

4           Rates for shipping radioactive wastes for burial were  
5           obtained from tariffs published by Tri-State Motor Transit.  
6           Tri-State Motor Transit is a reputable carrier with many  
7           years of experience in handling radioactive fuel and low  
8           level radioactive wastes. Transportation costs are an  
9           important element of decommissioning costs and recent rates  
10          must be used for accurate site-specific cost estimates.  
11          For this study, we assumed all low-level radioactive waste  
12          would be shipped to a hypothetical regional burial ground  
13          within 500 miles of the CR3 site. For cost estimating  
14          purposes, the burial costs for radioactive materials were  
15          developed using the rate schedule of an existing disposal  
16          facility, i.e., the Barnwell Low-Level Radioactive Waste  
17          Management Facility.

18    **Q.    What Federal Regulations applicable to decommissioning were**  
19          **taken into account by your study?**

20    **A.    The Nuclear Regulatory Commission (NRC) has regulations**  
21          **dealing with the issue of decommissioning. These**  
22          **regulations are identified in Title 10 of the US Code of**  
23          **Federal Regulations (CFR) Parts 20, 30, 40, 50, 51, 70, and**

1           72, and specific guidance for their implementation is  
2           provided in NRC Regulatory Guide 1.86 (June, 1974).

3           The NRC published the Final Rule entitled "General  
4           Requirements for Decommissioning Nuclear Facilities" in the  
5           Federal Register on June 27, 1988 to establish technical  
6           and financial criteria for decommissioning licensed  
7           facilities. The new NRC Rule recognizes the advantages of  
8           a site-specific cost estimate for decommissioning funding,  
9           and recommends that decommissioning be accomplished in the  
10          shortest practical time following cessation of operations.  
11          It identifies three acceptable decommissioning  
12          alternatives: DECON (prompt removal/dismantling), SAFSTOR  
13          (mothballing), and under special circumstances ENTOMB  
14          (entombment). Delayed decommissioning following initial  
15          mothballing or entombment activities should not exceed more  
16          than 60 years, unless it can be shown necessary to protect  
17          public health and safety. The Rule appears to discourage  
18          the ENTOMB alternative unless specific advantages can be  
19          shown. Both the DECON and SAFSTOR alternatives are  
20          considered reasonable options for decommissioning light  
21          water power reactors. The Rule also requires utilities to  
22          perform a periodic review of the funding plan over the life  
23          of the facility. The site-specific cost estimate and  
24          decommissioning alternatives for CR3 fully satisfy this new  
25          regulation.

1 Q. Would you next discuss the methodology used to prepare the  
2 decommissioning cost estimate for CR3?

3 A. The methodology used to develop the cost estimate followed  
4 the basic approach presented in the AIF/NESP-036 study  
5 report, "Guidelines for Producing Commercial Nuclear Power  
6 Plant Decommissioning Cost Estimates", and the U.S. DOE  
7 "Decommissioning Handbook" referred to earlier. These  
8 references use a unit cost factor method for estimating  
9 decommissioning activity costs to standardize the  
10 estimating calculations. Unit cost factors for activities  
11 such as concrete removal (\$/cu yd), steel removal (\$/ton),  
12 and cutting costs (\$/in.) were developed from the labor and  
13 material information provided by FPC. With the item  
14 quantity (cu. yds, tons, inches, etc.) developed from  
15 plant drawings and inventory documents, the activity-  
16 dependent costs for decontamination, removal, packaging,  
17 shipping and burial were estimated. The activity duration  
18 critical path derived from such key activities, e.g., the  
19 disposition of the Nuclear Steam Supply System (NSSS), was  
20 used to determine the total decommissioning program  
21 schedule.

22 The program schedule is used to determine the period-  
23 dependent costs such as program management, administration,  
24 field engineering, equipment rental, quality assurance and

1 security. the salary and hourly rates are typical for  
2 personnel associated with period-dependent costs. The  
3 costs for conventional demolition of non-radioactive  
4 structures, materials, backfill, landscaping and equipment  
5 rental were obtained from conventional demolition  
6 references such as R. S. Means, "Building Construction  
7 Cost Data 1985." In addition, collateral costs were  
8 included for heavy equipment rental or purchase, safety  
9 equipment and supplies, energy costs, permits, taxes, and  
10 insurance.

11 The activity-dependent, period-dependent, and collateral  
12 costs were added to develop the total decommissioning  
13 costs. A 25% contingency was added to allow for the effect  
14 of unpredictable program problems on costs. Such a  
15 contingency is appropriate for a project of this size and  
16 type, as will be discussed later in this testimony.

17 One of the primary objectives of every decommissioning  
18 program is to protect public health and safety. The cost  
19 estimate for CR3 decommissioning activities includes the  
20 necessary planning, engineering and implementation to  
21 provide this protection to the public.

1 Q. What effect does the removal of spent fuel and other high  
2 level waste have on decommissioning costs identified in the  
3 CR3 study?

4 A. None. Although decommissioning of a site cannot be  
5 complete without the removal of all spent fuel and source  
6 material, the disposition of high-level waste is outside  
7 the scope of decommissioning. In accordance with the  
8 Nuclear Waste Policy Act of 1982 (Public Law 94-425), the  
9 DOE is required by law to enter into contracts with owners  
10 and/or generators of spent fuel, with the DOE responsible  
11 for final disposition of spent fuel as high-level nuclear  
12 waste. To cover the cost of spent fuel disposition, the  
13 DOE assesses the facility operator 1 mill/kWh on net  
14 electrical generation. Therefore, the cost and disposal of  
15 spent fuel is accounted for separately and is specifically  
16 excluded from the decommissioning estimates.

17 All radioactive wastes generated during the decommissioning  
18 process are low-level radioactive wastes and will be  
19 transported to a federal or state licensed commercial low-  
20 level waste facility or state licensed commercial low-level  
21 waste facility for ultimate disposal, as required by the  
22 appropriate regulations in effect at the time of  
23 decommissioning.

1 Q. What Decommissioning alternative was utilized in preparing  
2 CR3's cost estimate?

3 A. The NRC has stated that a decommissioning alternative is  
4 acceptable if it provides for completion of decommissioning  
5 within 60 years. Consideration will be given to an  
6 alternative which provides for completion of  
7 decommissioning beyond 60 years only when necessary to  
8 protect the public health and safety.

9 The decommissioning cost estimate prepared for CR3 was  
10 based on the prompt removal/dismantling alternative known  
11 as DECON. The DECON alternative consists of removing from  
12 the site the spent fuel assemblies discharged from the  
13 reactor and stored on site. (As noted earlier, the cost  
14 associated with the disposition of fuel and source  
15 material is not included in this estimate.) All  
16 radioactive wastes from plant operation would be packaged  
17 and shipped for controlled burial. The operating license  
18 would be converted to a possession-only license for the  
19 decommissioning operations. A possession-only license  
20 permits the owner to possess the radioactive material under  
21 reduced Technical Specification requirements, but prohibits  
22 operation of the reactor. The radioactive fission and  
23 corrosion products and all other radioactive materials  
24 having activities above accepted unrestricted levels would  
25 be removed, packaged and shipped for disposal. The site

1           may then be released following NRC approval, for  
2           unrestricted use with no requirement for a license. The  
3           remainder of the reactor facility could then be dismantled  
4           to make the site available for alternative use.

5    Q.       Why do you consider the DECON alternative to be the  
6           preferred decommissioning method for CR3?

7    A.       The DECON alternative provides the most reasonable means  
8           for terminating the license for the site in the shortest  
9           possible time, and consequently relieves FPC of its  
10          regulatory and liability obligations at the site.  
11          Furthermore, this scenario avoids the long-term costs and  
12          commitments associated with the maintenance, surveillance  
13          and security requirements of the conventional delayed  
14          dismantling alternatives, SAFSTOR and ENTOMB.

15          This alternative also allows use of the plant's  
16          knowledgeable current operating staff, a valuable asset to a  
17          well managed, efficient decommissioning program. All  
18          equipment needed to support decommissioning operations such  
19          as cranes, ventilation systems and radwaste processing  
20          equipment would be fully operational. In addition, the  
21          site would be available for alternative uses in the near  
22          term.



1 Q. Would you describe the various stages and activities  
2 involved in the decommissioning of a nuclear power reactor  
3 such as CR3?

4 A. Approximately two years prior to final shutdown,  
5 engineering and planning would begin on the preparation of  
6 the Decommissioning Engineering Plan and Environmental  
7 Assessment. The Plan describes the status of the facility  
8 at shutdown, work to be accomplished, safety analyses  
9 associated with each of the major activities, general  
10 procedures and sequence to be followed, and final site  
11 condition upon completion of all work. Similarly, the  
12 environmental assessment would evaluate environmental  
13 effects (radiation exposure) to workers and the public, and  
14 waste generation effects on the site and environment.  
15 These documents would be submitted to the NRC and other  
16 regulatory agencies for review and approval, and  
17 authorization to proceed. Decommissioning activities would  
18 then be conducted in three stages.

19 Period 1 - Site Preparations. The first stage would begin  
20 upon shutdown of the facility, and would involve site  
21 preparations to initiate decommissioning. The operating  
22 license may be converted to a possession-only license which  
23 permits decommissioning activities to be performed, while  
24 reducing unnecessary Technical Specifications requirements  
25 associated with normal plant operations. All spent fuel

1 would be removed from the reactor vessel and loaded into  
2 casks for transport to a federal repository.  
3 Alternatively, the fuel could be transferred to storage  
4 facilities on-site so as not to impact the decommissioning  
5 process. As noted earlier, fuel removal activities,  
6 packaging, shipping and disposal are not considered part of  
7 decommissioning and no costs are included in the  
8 decommissioning estimate for this work nor is any impact on  
9 decommissioning from the presence of such material on-site  
10 considered in the estimates. All fluids and wastes  
11 remaining from plant operations would be removed from the  
12 site and all systems nonessential to decommissioning would  
13 be isolated and drained. This work is expected to require  
14 approximately 12 months to accomplish.

15 Period 2 - Decommissioning Operations. The principle  
16 decommissioning activities would begin upon receipt of the  
17 dismantling order from the NRC. This phase of the work  
18 involves the removal of radioactivity from the site and  
19 termination of the license. The activities include  
20 selective decontamination of contaminated systems, e.g.,  
21 using aggressive chemical solvents to dissolve corrosion  
22 films holding radionuclides, thereby reducing radiation  
23 levels.

1           While effective, the decontamination processes are not  
2           expected to reduce residual radioactivity to the levels  
3           necessary to release the material as clean scrap.  
4           Therefore, all contaminated components will have to be  
5           removed for controlled burial. However, decontamination  
6           will reduce personnel exposure and permit workers to  
7           operate in the immediate vicinity of most components,  
8           cutting and removing them for controlled disposition at a  
9           low-level waste burial facility.

10           All piping to and from major components such as the steam  
11           generators will be cut and removed. The steam generators  
12           and other major components will be removed intact and  
13           sealed so that they may be shipped as their own containers  
14           for disposal. Smaller components will be loaded into  
15           containers and shipped for burial. The reactor vessel and  
16           its internals will be segmented into sections and remotely  
17           loaded into steel liners for transport to the burial  
18           facility in heavily shielded shipping casks. The reactor  
19           vessel and internals have sufficiently high radiation  
20           levels to require all cutting to be done underwater (to  
21           shield the workers), or behind heavy shields, using  
22           cutting torches operated by remote control.

23           Concrete immediately surrounding the reactor vessel is  
24           expected to be radioactive (activated) and will be removed

1 by controlled blasting. This blasting process is well  
2 developed and safe and is the most cost effective way to  
3 remove the heavily-reinforced concrete from the structure.  
4 Sections of interior floors within areas of the containment  
5 and other buildings in the power block are expected to be  
6 surface contaminated from exposure to contaminated  
7 air/water as a result of plant operations. This  
8 contamination will be removed by scarification (surface  
9 removal) so the remaining surface will be clean and not  
10 require costly controlled burial. All contaminated process  
11 equipment, pipe hangers, supports and electrical components  
12 will be removed and disposed of by controlled burial. An  
13 extensive radiation survey will be performed to ensure all  
14 radioactivity above the levels specified has been removed  
15 from the site. The facility may then be released for  
16 unrestricted access. Once verified the NRC can then  
17 terminate the license for the site. This period is  
18 expected to require approximately three years to accomplish  
19 all activities.

20 Period 3 - Dismantling Remaining Structures. The final  
21 stage would involve the demolition of all remaining  
22 structures, typically to a depth of three feet below grade.  
23 Clean rubble would be used on-site for fill and additional  
24 soil would be used to cover each subgrade structure. The

1 site would be graded. This period is expected to require  
2 approximately two years to accomplish all activities.

3 Q. How should the cost estimate developed in your study be  
4 viewed with respect to its validity for future  
5 application?

6 A. The decommissioning cost estimate prepared for CR3 is based  
7 on current state-of-the-art technology and on existing  
8 federal regulations. No provision has been made to include  
9 the future effect on costs of such factors as improvements  
10 in technology, major regulatory changes, inflation levels,  
11 etc., to ensure there will be no double accounting for such  
12 factors when projecting costs to the expected date of  
13 decommissioning. It is my recommendation that FPC  
14 thoroughly review this estimate periodically and revise it,  
15 if necessary, to account for cost increases or decreases  
16 which may result from future technology and regulations.  
17 It is my understanding that the practice followed by this  
18 Commission is consistent with this recommendation.

19 Q. What is the basis for the 25% contingency allowance  
20 included in CR3's cost estimate?

21 A. The purpose of the contingency allowance is to provide for  
22 the costs of high probability program problems where the  
23 occurrence, duration, and severity cannot be accurately

1 predicted. The American Association of Cost Engineers  
2 (AACE) defines contingency in their "Cost Engineers  
3 Notebook" as follows:

4 Contingency - specific provision for unforeseeable  
5 elements of cost within the defined project scope;  
6 particularly important where previous experience  
7 relating estimates and actual costs has shown that  
8 unforeseeable events which will increase costs are  
9 likely to occur.

10 Therefore, the objective of the contingency is to account  
11 for the costs of high probability program problems where  
12 the occurrence, duration, and severity cannot be accurately  
13 predicted and have not been included in the basic estimate.  
14 Past decommissioning experience has shown that these  
15 problems are likely to occur and may have a cumulative  
16 impact.

17 A more extensive discussion of contingency is included in  
18 the AIF/NESP-036 Guidelines Study (Chapter 13) referred to  
19 earlier. In that study, we examined the major activity-  
20 related problems (decontamination, segmentation, equipment  
21 handling, packaging, shipping and burial) with respect to  
22 reasons for contingency. Individual activity contingencies  
23 ranged from 10% to 75%, depending on the degree of  
24 difficulty judged to be appropriate from our actual  
25 decommissioning experience. The overall contingency, when  
26 applied to the appropriate components of a standard cost  
27 estimate, results in an average of approximately 25%.

1           Therefore, we recommend that a 25% contingency be added to  
2           the total estimated costs for financial planning purposes.

3           Independent of our preparation of the AIF/NESP-036 study  
4           and its predecessor report, AIF/NESP-009, Battelle Pacific  
5           Northwest Labs prepared independent decommissioning cost  
6           estimates for the NRC for a 1175 MWe PWR (NUREG CR-0130)  
7           and an 1155 MWe BWR (NUREG CR-0672). Battelle concurred  
8           with the 25% contingency allowance.

9           Furthermore, the Federal Energy Regulatory Commission  
10          (FERC) adopted 25% contingency as reasonable, following the  
11          ruling of Judge Liebman in the Middle South Energy/Grand  
12          Gulf Case (Docket ER82-616), decision issued February 3,  
13          1984. Numerous state public utility commissions have  
14          adopted 25% contingency, as evidenced by an American Gas  
15          Association/Edison Electric Institute Depreciation  
16          Committee Survey which showed that at least 21 of 32  
17          utility survey respondents had included 25% contingency in  
18          their estimates. Of the 15 utilities who filed rate cases,  
19          11 had approval to use 25% contingency for their plant  
20          decommissioning studies.

21    Q.       Is there any empirical evidence that complete dismantlement  
22               is a feasible decommissioning alternative for CR3?

1 A. There is extensive experience in the United States and in  
2 other countries for the complete dismantling of nuclear  
3 plants. This experience includes the chemical  
4 decontamination, component removal, packaging, shipping and  
5 burial, and building demolition. This directly related  
6 experience is evidence that FPC's nuclear unit can be  
7 completely dismantled.

8 Between 1960 and 1979, 68 licensed nuclear reactors had  
9 been or were in the process of being decommissioned in the  
10 United States. Of these, five were nuclear power plants,  
11 four were demonstration nuclear power plants, six were  
12 licensed test reactors, 28 were research reactors, and the  
13 remaining 25 were critical reactors and/or facilities  
14 decommissioned or scheduled to be decommissioned. These  
15 reactors have been or will be totally dismantled, with  
16 their licenses terminated. Many other reactor facilities  
17 in the U.S., Canada and Europe have been successfully  
18 decommissioned using demonstrated techniques. France has  
19 decommissioned 13 reactors, West Germany 6, Italy 8, Japan  
20 7, Switzerland 2, United Kingdom 5, and Canada 2.

21 The feasibility of decommissioning in the U.S. is well  
22 documented in the successful dismantling of Shippingport  
23 Atomic Power Station, Elk River Reactor, Walter Reed Army  
24 Research Reactor, Ames Laboratory Reactor and Sodium



1           Reactor Experiment (SRE) Facilities. Internationally, the  
2           decommissioning programs underway in England (Windscale  
3           Reactor), West Germany, (Gundremmingen), and Japan (Japan  
4           Power Demonstration Reactor) are further evidence of  
5           demonstrated technology. The basic activities of cutting  
6           pipe, segmenting vessels, demolishing reinforced concrete  
7           and decontaminating contaminated systems and structures are  
8           independent of the size of the structure or megawatt rating  
9           of the plant on a unit cost factor basis (\$/cut, \$/cu yd,  
10          etc.). A contaminated 12-inch diameter pipe in a 3000 Mwt  
11          plant takes as long to cut as it does in a 50 Mwt plant,  
12          although the number of cuts will be greater in the larger  
13          plant. The technology of such cutting is well established.

14          The major activities include removal and burial of  
15          contaminated piping and components using conventional power  
16          hack saws, oxyacetylene or plasma arc torches within a  
17          contamination control tent. Removal of the reactor vessel  
18          and internals can be accomplished using an arc-gouging  
19          fuel gas torch or an arc saw which is currently capable of  
20          cutting through carbon and stainless steel up to 12 inches  
21          thick (current vessels are less than 10 inches thick). The  
22          remote manipulator technology required to cut the reactor  
23          vessel and internals was developed by Oak Ridge National  
24          Laboratory for the Elk River Reactor dismantling. This

1           technology uses the plasma arc torch for cutting. This  
2           same tool was used in the SRE vessel cutting activity.

3           Many of the tools and techniques used in decommissioning  
4           have been used in operating plants for maintenance and  
5           equipment replacement programs. This technology is,  
6           therefore, not unique and provides further evidence of the  
7           feasibility of decommissioning.

8           In 1979, Virginia Electric and Power Company removed and  
9           replaced the contaminated 823 MWe steam generators in its  
10          Surry plants. The contaminated steam generators (measuring  
11          65 feet high by 170 inches outside diameter with 3.5 inch  
12          thick walls) each weighted 340 tons. The reactor coolant  
13          system stainless steel piping (34 inch inside diameter),  
14          steam piping (30 inch diameter) and feedwater piping (14  
15          inch diameter) were cut with a plasma arc torch to isolate  
16          the steam generator from the primary and secondary systems.

17          The steam generator shell was circumferentially cut at the  
18          transition cone with the plasma arc torch. The two lower  
19          shell sections were removed through the existing equipment  
20          hatch for disposal. In 1981, a similar steam generator  
21          removal program was initiated and successfully performed by  
22          Florida Power & Light Company at its Turkey Point Station.  
23          Controlled blasting concrete demolition methods are well

1            developed. They have been used in the mining industry, and  
2            were successfully demonstrated in the demolition of the Elk  
3            River Reactor. Heavily reinforced eight feet thick  
4            concrete sections of the biological shield were safely  
5            removed with explosives, without damaging or interfering  
6            with the operation of adjacent operating power generating  
7            units. The successful application of these decommissioning  
8            techniques in both small and large nuclear power plants  
9            demonstrates assurance of decommissioning feasibility.  
10           Both the technology and the methodology for efficient  
11           decommissioning are available and fully tested.

12    Q.        Does that conclude your testimony?

13    A.        Yes.