

Ms. Blanca S. Bayo
June 30, 1998
Page Two

CERTIFICATE OF SERVICE

I HEREBY CERTIFY that a true copy of the foregoing testimony and exhibits filed on behalf of Tampa Electric Company has been furnished by hand delivery (*) or U. S. Mail on this 30th day of June 1998 to the following:

Ms. Grace A. Jaye*
Staff Counsel
Division of Legal Services
Florida Public Service
Commission
2540 Shumard Oak Blvd.
Tallahassee, FL 32399-0850

Mr. Joseph A. McGlothlin*
Ms. Vicki Gordon Kaufman
McWhirter, Reeves, McGlothlin,
Davidson, Rief & Bakas, P.A.
117 South Gadsden Street
Tallahassee, FL 32301

Mr. John W. McWhirter, Jr.
McWhirter, Reeves, McGlothlin,
Davidson, Rief & Bakas, P.A.
Post Office Box 3350
Tampa, Florida 33601



ATTORNEY

ORIGINAL



TAMPA ELECTRIC

TAMPA ELECTRIC COMPANY

BEFORE THE

FLORIDA PUBLIC SERVICE COMMISSION

DOCKET NO. 980693-EI

**TESTIMONY
AND EXHIBIT OF**

CHARLES R. BLACK

980693-EI

1 **BEFORE THE PUBLIC SERVICE COMMISSION**

2 **PREPARED DIRECT TESTIMONY**

3 **OF**

4 **CHARLES R. BLACK**

5
6 **Q.** Please state your name, address and occupation.
7

8 **A.** My name is Charles R. Black. My business address is 702
9 North Franklin Street, Tampa, Florida 33602. I am Vice
10 President-Energy Supply for Tampa Electric Company
11

12 **Q.** Mr. Black, please furnish a brief outline of your
13 educational background and business experience.
14

15 **A.** I graduated from the University of South Florida in August
16 1973 with a bachelor of science degree in Engineering,
17 majoring in Chemical Engineering. I am a Registered
18 Professional Engineer in the State of Florida. I began my
19 career with Tampa Electric Company in September 1973 as a
20 staff engineer in the Production Department. Between 1973
21 and 1989, I held various engineering and management
22 positions in the Production Department, Power Plant
23 Engineering Department, and the Budget Department. In
24

1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
17
18
19
20
21
22
23
24
25

March of 1989, I joined our affiliated company, TECO Power Services as Director Engineering and Construction. In December of 1990, I was elected Vice President of Engineering and Construction. In December of 1991, I returned to Tampa Electric as Vice President of Project Management. In December 1996 I assumed my present role as Vice President-Energy Supply.

Q. Have you previously testified before this Commission?

A. Yes. I testified in support of the prudence of Polk Unit One in Docket No. 960409-EI.

Q. What is the purpose of your testimony?

A. The purpose of my testimony is to demonstrate that the cost estimates associated with the proposed flue gas desulfurization ("FGD") system, and the other project alternatives considered in the economic analysis described by Mr. Hernandez are reasonable. As discussed below, the proposed FGD system will enable Tampa Electric to comply with the SO₂ emission limitations set forth in Phase II of the Clean Air Act Amendments of 1990 ("CAAA").

1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
17
18
19
20
21
22
23
24
25

Q. Have you prepared an exhibit in support of your testimony?

A. Yes I have. My Exhibit No. ____ (CRB-1) consisting of 6 documents, was prepared under my direction and supervision.

Q. Please explain the Phase I and Phase II environmental compliance requirements related to SO₂ emissions created by the CAAA.

A. The Acid Rain Program of the 1990 CAAA set as its primary goal the reduction of annual SO₂ emissions by 10 million tons below 1980 levels. To achieve these reductions, the law requires a two-phase program which establishes annual SO₂ tonnage emission limits for fossil fuel-fired power plants. Compliance with Phase I was required by January 1, 1995. Phase I placed initial emission limitations on certain units named in the CAAA.

Tampa Electric has complied with Phase I and this Commission has approved the company's cost of compliance for cost recovery as part of its environmental cost recovery ("ECRC") in docket No. 960688-EI. The purpose of this proceeding is to review the company's plan for compliance with Phase II.

1
2
3 Compliance with Phase II is required by January 1, 2000 and
4 further reduces annual emissions from Phase I plants. Phase
5 II also sets SO₂ emission limits for additional fossil fuel
6 fired plants encompassing more than 2,000 units in all. As
7 such, the program imposes SO₂ emissions limits on existing
8 steam electric units serving generators with an output
9 capacity of greater than 25 MW and all new utility units.
10

11 Q. For background purposes, please summarize how Phase I of
12 the CAAA imposed limits on Tampa Electric.
13

14 A. Units of Tampa Electric's system affected by Phase I are
15 Big Bend Units 1, 2 and 3. These units were granted a
16 combined total of 80,085 SO₂ allowances. This number
17 defines the maximum SO₂ emissions allowed under this
18 program, without further mitigation measures, for these
19 three units. Each allowance held allows for the discharge
20 of one ton of SO₂ emissions. In addition, Tampa Electric
21 Company voluntarily substituted Big Bend Unit 4 into the
22 Phase I requirements of the CAAA program. As a designated
23 Phase I Substitution Unit, Big Bend 4 was granted a total
24 of 6,400 additional annual allowances during Phase I. This
25 measure provided Tampa Electric with a total of 86,485

1 Phase I allowances.

2

3

4 Q. How do the Phase II compliance requirements impact Tampa
5 Electric?

6

7 A. All current and future Tampa Electric units, except
8 Phillips and existing combustion turbines, are affected by
9 Phase II compliance requirements. In Phase II, Tampa
10 Electric will be allocated 83,882 allowances, thereby
11 reducing the amount of allowances available to the company
12 while increasing the number of units affected. This
13 effectively reduces the amount of SO₂ emissions allowed
14 without further mitigation measures.

15

16 Q. How do the limitations in Phase II compare to those in
17 Phase I?

18

19 A. As shown in my Document 1, approximately twice the amount
20 of Tampa Electric's generating capacity is covered by Phase
21 II than by Phase I, yet we will receive approximately 2,600
22 fewer allowances.

23

24 Q. Can you briefly describe Tampa Electric's Phase I
25 compliance strategy?

1 A. Tampa Electric began its CAAA compliance plan in 1990 and
2 sought relevant input from across many areas of the
3 company. In 1994 the SO₂ compliance plan evaluation of
4 Phase I was completed. That plan was to blend fuel with
5 low sulfur coal and purchase SO₂ allowances to meet the CAAA
6 limits. Following the implementation of that plan Tampa
7 Electric engineers, working with EPRI, DOE and others,
8 determined that it would be possible to treat all of the
9 flue gas from Big Bend Unit 3 in the existing FGD system
10 that was currently treating the flue gas from Big Bend Unit
11 4. This was accomplished in 1995 at a very low cost. This
12 modification, in conjunction with fuel blending and
13 allowance purchases, provided a much lower compliance cost
14 for Phase I than fuel blending and allowance purchases
15 alone.

16
17 Q. Has Tampa Electric's Phase I compliance effort been
18 successful to date?

19
20 A. Implementation of our plan has been very successful. We
21 have been able to achieve compliance with the CAAA Phase I
22 with high unit availability, efficiency, and reliability.
23 Treating the flue gas from a second unit has allowed us to
24 be flexible in our fuel utilization as well.

25

1 Q. How did Tampa Electric determine the options for complying
2 with Phase II of the CAAA?

3
4 A. We began this process by compiling a list of viable
5 compliance options for initial screening studies. Options
6 that were not viable were eliminated. These remaining
7 options went through both quantitative and qualitative
8 analysis to screen the options. This process is described
9 in Mr. Hernandez's testimony. These options were compared
10 to the best "non-build" option of fuel blending and
11 allowance purchases at all of Tampa Electric's coal units.

12
13 Q. How were the capital and operating costs developed for use
14 in the economic studies for the screening analysis as
15 described in Mr. Hernandez's testimony?

16
17 A. The screening process began with an evaluation of adding an
18 FGD system to Gannon Station Units 4,5, and 6. Tampa
19 Electric Company retained an architect engineering firm
20 with considerable expertise with FGD systems to develop a
21 cost estimate for installing one of two different
22 technology FGD systems at that location. Tampa Electric
23 engineers, with experience in design and operation of FGD
24 systems, reviewed these costs and found them to be
25 reasonable. As the screening process continued we looked

1 at FGD options at Big Bend Station, including a new stand
2 alone FGD system for Big Bend 1&2 or treating the flue gas
3 from Big Bend 2 in the existing FGD system for Big Bend
4 Units 3&4. The costs for these options were determined by
5 Tampa Electric's engineers using the Gannon FGD study cost
6 as the basis for the Big Bend 1&2 stand alone option. The
7 Big Bend 3 FGD integration was used as the basis for the
8 Big Bend 2 integration feasibility assessment. These
9 capital and operating costs estimates were utilized in the
10 economic evaluations.

11
12 Q. How did Tampa Electric forecast the fuel and SO₂ allowance
13 prices utilized in the economic studies?

14
15 A. Tampa Electric monitors the prices of all fuels and SO₂
16 allowances on a regular basis. The prices are tracked
17 through numerous periodicals, actual buying experience, and
18 through market information obtained through supply
19 representatives. A forecast of expected fuel prices is
20 developed annually to support the company's planning
21 process. The forecast used in this analysis is the same
22 forecast utilized in the Tampa Electric 1998 Ten Year Site
23 Plan. The development of the forecast includes a review of
24 historical fuel prices compared with new projections
25 obtained from various consultants and agencies including

1 Energy Information Administration, American Gas
2 Association, Cambridge Energy Research Associates, Resource
3 Data International, and Energy Ventures Analysis. Fuel
4 Pricing publications include: Coal Outlook, Coal Daily,
5 Natural Gas Week, Platt's Oilgram, Oil and Gas Journal, and
6 Pace Petroleum Coke Quarterly.
7

8 Q. How did these forecasts impact the base case and FGD case
9 analysis?
10

11 A. The base case achieves compliance by switching from high
12 sulfur and medium sulfur coals to low sulfur coals in
13 conjunction with allowance purchases. As we reviewed the
14 forecasts from consultants for high sulfur and low sulfur
15 coal, we determined that our forecast for low sulfur coal
16 was less expensive than the consultant's estimates, and
17 that our forecast for high sulfur coal was more expensive
18 than the consultant's. These comparisons are shown in my
19 Documents 2, Pages 1 and 2. Consequently, the consultants
20 forecasts would favor the FGD option more than the
21 forecasts we used in our cost recovery studies.
22

23 Q. The screening process described in Mr. Hernandez's
24 testimony indicated that the Big Bend 1&2 FGD addition was
25 our best Phase II compliance choice. How did Tampa

1 Electric proceed to ensure their estimates were reasonable?

2

3 **A.** To ensure Tampa Electric's estimated cost of the Big Bend
4 1&2 FGD system was reasonable, we hired a second
5 experienced architect engineering firm to provide us with
6 a more refined cost estimate of this system. This firm
7 developed a design basis for the FGD system with Tampa
8 Electric's engineers. It then developed a conceptual
9 design with site layouts, arrangement drawings, equipment
10 lists, electric load lists, piping lists and materials of
11 construction. This firm also received vendor quotes for
12 the major equipment and utilized published data or its
13 internal cost databases to come up with an accurate
14 estimate of the cost. This more refined estimate supported
15 the previous costs utilized in the screening analysis.
16 Based upon these two cost studies, which were reviewed by
17 Tampa Electric's engineering personnel experienced in FGD
18 technology, we found the FGD cost estimates to be
19 reasonable. These revised costs were then utilized in the
20 cost effectiveness analyses described in Mr. Hernandez's
21 testimony.

22

23 **Q.** Please describe the proposed FGD system and explain how it
24 operates.

25

- 1 A. An overview of the FGD system is shown in my Document 3.
2 An FGD System, or "scrubber", consists of equipment capable
3 of removing sulfur dioxide from the flue gas generated by
4 the combustion of coal. The flue gas is directed to an
5 absorber tower where it is treated with a slurry spray of
6 limestone and water. The SO₂ in the flue gas is absorbed
7 by the slurry to form an acid which is then neutralized by
8 the dissolved limestone. The reaction of the SO₂ and
9 limestone produces calcium sulfite which is then oxidized
10 by the introduction of air into the reaction tank. The
11 product of this forced oxidation is gypsum which then
12 precipitates out of solution. The resulting gypsum slurry
13 is then dewatered to produce a near dry gypsum cake which
14 is sold as a raw material, predominately to wallboard
15 producers.
- 16
- 17 Q. What are the estimated capital costs of the new FGD sytem?
18
- 19 A. It is estimated to cost approximately \$90 million
20 (including AFUDC). This estimate is based on the
21 conceptual design and the detailed cost estimate performed
22 by an outside consulting firm described previously in my
23 testimony. Tampa Electric added costs that were not
24 included in the detailed estimate and adjusted some of the
25 costs based upon our past large project experience. The

1 adjusted costs include owner's costs and contingency. My
2 Document 4 sets forth a detailed breakdown of the
3 components of the total capital cost.
4

5 Q. What are the estimated annual O & M expenses of the Big
6 Bend 1 and 2 FGD system?
7

8 A. Tampa Electric has thirteen years of experience operating
9 the FGD system on Big Bend Units 3 and 4 which is very
10 similar to the technology proposed for the new FGD system.
11 The operations and maintenance requirements for the new FGD
12 system were developed by comparing new equipment
13 requirements to the existing equipment requirements. Cost
14 information gathered from actual operations was obtained
15 for each system area and used to estimate the O&M cost for
16 the new equipment. These present day costs were then
17 escalated to year 2000 dollars.
18

19 The annual O & M expense for the FGD system is estimated to
20 be approximately \$3.5 million. My Document 5 sets forth
21 a detailed breakdown of the estimated O & M expense for
22 this project. The \$3.5 million estimate is stated in year
23 2000 dollars. Reagent costs were based on limestone costs
24 of \$2.1 million and dibasic acid costs of \$0.27 million.
25 The remainder amounts to about \$1.17 million and consists

1 of plant O & M. We have assumed that all O&M costs will
2 escalate at a rate of 3% per year.

3
4 Q. What assumptions did you make regarding the efficiency and
5 availability of the FGD for Big Bend Units 1 and 2?

6
7 A. The FGD case assumes that Big Bend Units 1 and 2 would burn
8 high sulfur coal with treatment at 95% efficiency with a
9 98% FGD availability. This option results in all coal
10 units at Big Bend Station being fitted with an FGD system.
11 Because Tampa Electric is restricted to a system SO₂ cap,
12 the flue gas treatment of Big Bend Station allows Gannon
13 units to burn a lower cost fuel and still meet the system
14 SO₂ cap. Consequently, fuel savings are realized at both
15 Gannon and Big Bend Stations. In addition, by blending
16 higher sulfur coal at Gannon, those units are able to
17 regain some of the operational derations associated with
18 burning low sulfur coal.

19
20 Q. What is Tampa Electric's compliance plan implementation
21 schedule for this project?

22
23 A. Tampa Electric will proceed on a very aggressive schedule
24 to place the FGD system in service in June of the year
25 2000. We are, however, attempting to achieve an even

1 earlier in service date by continuing to expedite all
2 facets of environmental permitting, engineering and
3 construction. During the short time between the compliance
4 date and the in service date of the new FGD system we will
5 comply with the more stringent CAAA requirements through
6 fuel blending and allowance purchases.

7
8 With respect to the permitting schedule, Tampa Electric
9 plans to submit required environmental permit applications
10 in mid-1998. Based on communications with the Department
11 of Environmental Protection, Tampa Electric anticipates the
12 release to initiate construction to be received in
13 September 1998. As shown in my document 6, all project
14 environmental permits should be obtained by December 1999.

15
16
17 Q. Please summarize your testimony.

18
19 A. Tampa Electric has a legal obligation to comply with the
20 CAAA. Phase II of the CAAA requires that Tampa Electric
21 reduce its emissions of SO₂ by approximately 50% by January
22 1, 2000. Tampa Electric has determined the capital and O&M
23 costs of the viable options. These costs were developed
24 with the assistance of professional engineering firms with
25 specific expertise in the design and construction of FGD

1 systems. Tampa Electric staff have reviewed the cost
2 estimates developed and have determined that these cost
3 estimates are reasonable. The selection of an FGD system
4 for Big Bend Units 1 and 2 will allow Tampa Electric to
5 meet the requirement of the CAAA while maintaining its
6 system capability and availability.

7
8 Q. Does this conclude your testimony?

9
10 A. Yes

TAMPA ELECTRIC COMPANY

INDEX

<u>Document No.</u>	<u>Title</u>	<u>Page</u>
1.	CAAA SO ₂	1
2.	Forecast Comparison East Kentucky vs. West Kentucky	2
3.	Big Bend 1 & 2 FGD System	4
4.	Big Bend Units 1 & 2 FGD Project Detailed A/E Engr. Test	5
5.	Big Bend Stations Units 1 & 2 FGD System Estimated O&M Cost	6
6.	Big Bend 1 & 2 FGD Project Raytheon's Preliminary Schedule	7



CAAA SO₂ COMPLIANCE

Phase I

BB4
6,400 allowances
447 MW

86,485 allowances
1,742 MW

BB 1,2,3
80,085 allowances
1,295 MW

80,085 allowances
1,295 MW

Phase II

BB 1,2,3,4
GN 1,2,3,4,5,6
HP 1,2,3,4,5
PPS 1


(This represents
all Tampa Electric
units except Phillips
Station and
existing CT's)

83,882 allowances
3,372 MW

1


FIGURE 3-3


FORECAST COMPARISON EAST KENTUCKY vs. WEST KENTUCKY



FORECAST COMPARISON EAST KENTUCKY vs WEST KENTUCKY

FIGURE 3-4





**BIG BEND 1 & 2
FGD SYSTEM**

EXISTING CHIMNEY
TO BE USED AS
SCRUBBER BYPASS

UNITS 1 AND 2
ELECTROSTATIC
PRECIPITATOR

BOOSTER
FANS

OXIDATION AIR
COMPRESSORS

SO₂ ABSORBER

RECYCLE
PUMPS

GYPSUM
BLEED
PUMPS

GYPSUM
DEWATERING

GYPSUM
STORAGE

LIMESTONE
GRINDING

BIG BEND UNITS 1 & 2 FGD PROJECT

DETAILED A/E ENGR. EST

Site Development	\$	117,000
Earthwork & Piling		2,169,100
Structural Concrete		8,153,500
Structural Steel		2,699,100
Mechanical Process Equipment		9,032,700
FGD System		25,477,320
Ash Handling System		614,100
Piping		1,371,700
Insulation		179,600
Instrumentation		2,007,800
Electrical		4,766,300
Painting		113,500
Building Architectural		190,500
Craft Indirects-Dewatering		<u>257,500</u>

SUBTOTAL A/E EST. 57,149,720


TECO Provided Cost Information

Construction Management	2,708,216
Professional Engineering Services	5,212,152
Owner Controlled Costs	7,299,863
Contingency	2,465,049
Added 2nd Vacuum Filter	1,000,000
County Water Supply	1,000,000
Waste Water System	<u>5,000,000</u>
TOTAL PROJECT W/O AFUDC	81,835,000
AFUDC	<u>7,245,954</u>
TOTAL PROJECT EST.	\$ 89,080,954

BIG BEND STATION UNITS 1 & 2 FGD SYSTEM

ESTIMATED ANNUAL O&M COSTS

LIMESTONE SYSTEM	\$ 125,114
ABSORBER SYSTEM	309,339
WASTE HANDLING SYSTEM	93,996
FGD SUPPORT/CONTROLS	7,935
STAFFING (OPERATIONS)	315,346
WATER COSTS	212,180
WASTE WATER TREATMENT	<u>106,090</u>
 SUBTOTAL PLANT O&M	1,170,000
LIMESTONE COSTS	2,064,775
DIBASIC ACID COSTS	265,225
 SUBTOTAL REAGENTS	<u>2,330,000</u>
TOTAL ANNUAL O&M EXPENSE (YEAR 2000)	\$ 3,500,000



Project Start: 22FEB98
 Project Finish: 01JUN00
 Data Date: 01JUN98
 Print Date: 01JUN98

Early Bar: _____
 Progress Bar: _____
 Critical Activity: _____

TAMPA ELECTRIC COMPANY
 RAYTHEON'S PRELIMINARY SCHEDULE
 BIG BEND 1 & 2 FGD PROJECT

PROJECT NO. 98-001
 PREPARED BY: [Signature]
 DATE: 01/06/98

TAMPA ELECTRIC COMPANY
 PROJECT NO. 98-001
 PREPARED BY: [Signature]
 DATE: 01/06/98

