

ORIGINAL

BEFORE THE FLORIDA PUBLIC SERVICE COMMISSION

In Re: Petition for Determination of )  
Need for an Electrical Power Plant in ) DOCKET NO. 000442-EI  
Polk County by Calpine Construction )  
Finance Company, L.P. )  

---

DIRECT TESTIMONY AND EXHIBITS

OF

TED S. BALDWIN

ON BEHALF OF

CALPINE CONSTRUCTION FINANCE  
COMPANY, L.P.

DOCUMENT NUMBER-DATE

10170 AUG 18 8

FPSC-RECORDS/REPORTING

BEFORE THE FLORIDA PUBLIC SERVICE COMMISSION

IN RE: PETITION FOR DETERMINATION OF NEED  
FOR AN ELECTRICAL POWER PLANT IN POLK COUNTY  
BY CALPINE CONSTRUCTION FINANCE COMPANY, L.P.  
FPSC DOCKET NO. 000442-EI

DIRECT TESTIMONY OF TED S. BALDWIN, P.E.

1 Q: Please state your name and business address.

2 A: My name is Ted S. Baldwin, and my business address is Two  
3 Urban Center, 4890 West Kennedy Boulevard, Suite 600, Tampa,  
4 Florida, 33609.

5

6 Q: Where are you employed and in what position?

7 A: I am employed by Calpine Eastern Corporation as a Regional  
8 Engineer.

9

10 Q: Please describe your duties with Calpine Corporation.

11 A: I am responsible for the technical aspects related to the  
12 development of power plant projects. These responsibilities  
13 include selection of the plant configuration, the preliminary  
14 plant layout, calculation of plant performance, and oversight  
15 of the environmental permitting process.

16

17 QUALIFICATIONS AND EXPERIENCE

18 Q: Please summarize your educational background and experience.

19 A: I received a Bachelor of Science degree in Mechanical

DOCUMENT NUMBER-DATE

1

10170 AUG 18 8

FPSC-RECORDS/REPORTING

**DIRECT TESTIMONY OF TED S. BALDWIN**

1 Engineering from the University of Texas in Austin in 1981.  
2 I also received a Masters of Science degree in Mechanical  
3 Engineering from the University of Michigan in 1982.

4  
5 **Q: Please summarize your experience in power plant design,**  
6 **engineering, construction, operations, permitting, and**  
7 **licensing.**

8 **A: I have approximately 18 years of experience in the electric**  
9 **power industry, working as an equipment engineer, analytical**  
10 **engineer, boiler engineer, thermal cycle systems engineer,**  
11 **engineering group manager, director of engineering and now**  
12 **Regional Engineer for Calpine Eastern Corporation. In those**  
13 **positions, I have gained a wide range of experience in**  
14 **electrical power plant design, engineering, construction,**  
15 **operations, permitting and licensing. As part of my job, I**  
16 **have assisted in the design of more than a dozen gas-fired**  
17 **electrical generating plants. Exhibit \_\_\_\_\_ (TSB-1) is my**  
18 **current resume'.**

19  
20 **Q: Are you a member of any professional organizations?**

21 **A: I have been a member of the American Society of Mechanical**  
22 **Engineers for the past twelve years.**

23

24

**DIRECT TESTIMONY OF TED S. BALDWIN**

**SUMMARY AND PURPOSE OF TESTIMONY**

1

2 **Q: What is the purpose of your testimony?**

3 A: I am testifying on behalf of Calpine Construction Finance  
4 Company, L.P. ("Calpine"), the applicant for the Commission's  
5 determination of need for the Osprey Energy Center (the  
6 "Osprey Project" or "Project"). I will describe the main  
7 design features of the Project, as well as the Project's  
8 operational reliability and flexibility. I also will describe  
9 the performance characteristics and environmental profile of  
10 the Project, and present the engineering, procurement, and  
11 construction schedule for the Project.

12

13 **Q: What are your responsibilities with respect to the Osprey**  
14 **Project?**

15 A: In my position as Regional Engineer for Calpine Eastern  
16 Corporation, I oversee the preliminary engineering effort and  
17 regulatory support activities associated with the Project.

18

19 **Q: Please summarize the key features of the Project.**

20 A: The Osprey Project is a state-of-the-art natural gas-fired  
21 combined cycle generation facility. The plant will have  
22 approximately 529 megawatts ("MW") of net generating capacity  
23 based on anticipated manufacturer's guarantees at average  
24 ambient site conditions. The Osprey Project's rated winter

**DIRECT TESTIMONY OF TED S. BALDWIN**

1 capacity will be approximately 578 MW and its rated summer  
2 capacity will be approximately 496 MW. The Osprey Project  
3 will have a high thermal efficiency with a projected heat rate  
4 of approximately 6800 British thermal units ("Btu") per  
5 kilowatt-hour ("kWh"), based on the Higher Heating Value  
6 ("HHV") of natural gas at ambient site conditions. The  
7 Project will utilize state-of-the-art dry low-NO<sub>x</sub> combustion  
8 technology to minimize emissions of nitrogen oxides (NO<sub>x</sub>). In  
9 addition, a selective catalytic reduction ("SCR") system will  
10 be used to further reduce NO<sub>x</sub> emissions.

11 The Osprey Project will be a highly reliable power  
12 generation facility, with an estimated annual equivalent  
13 availability factor of approximately 94.5 percent. The  
14 operations and maintenance plan for the Project will be in  
15 accordance with the equipment manufacturer's recommended  
16 maintenance schedules.

17  
18 **Q: Are you sponsoring any exhibits to your testimony?**

19 **A:** Yes. I am sponsoring the following exhibits.

20 (TSB-1): Current resume' of Ted S. Baldwin.

21 (TSB-2): Osprey Energy Center, Project Profile.

22 (TSB-3): Osprey Energy Center, Site Plan.

23 (TSB-4): Osprey Energy Center, Proposed Plot Plan.

24 (TSB-5): Osprey Energy Center, Computer-Generated

**DIRECT TESTIMONY OF TED S. BALDWIN**

1 Perspective Rendition.

2 (TSB-6): Estimated Plant Performance and Emissions.

3 (TSB-7): Osprey Energy Center, Cycle Schematic Diagram.

4 (TSB-8): Summary of the Design Basis for the Project.

5 (TSB-9): Osprey Energy Center, Electrical One-Line Diagram.

6 (TSB-10): Preliminary Average Annual Water Balance for the  
7 Project.

8 (TSB-11): Preliminary Peak Monthly Daily Water Balance for  
9 the Project.

10 (TSB-12): EPC Schedule for the Project.

11 I am also sponsoring Tables 2 and 3 and Figures 3-10 and  
12 16 in the Exhibits to Calpine's Petition for Determination of  
13 Need filed with the Commission on June 19, 2000, and the text  
14 that accompanies those tables and figures.

15

16 **PROJECT DESCRIPTION AND ENGINEERING DESIGN**

17 **Q: Please describe the Osprey Project.**

18 **A:** The Osprey Project is a state-of-the-art natural gas-fired  
19 combined cycle generation facility. The plant consists of two  
20 combustion turbine generators ("CTGs"), two heat recovery  
21 steam generators ("HRSGs") and one steam turbine generator  
22 ("STG"). The Project will use wet cooling towers to condense  
23 steam back to water for reuse in the HRSGs and STG. The plant  
24 will have approximately 529 MW of net generating capacity

**DIRECT TESTIMONY OF TED S. BALDWIN**

1 (based on anticipated manufacturer's guarantee) at average  
2 ambient site conditions. The average ambient conditions at  
3 the Project site are 74°F. and 80% relative humidity. A  
4 general profile of the Project is shown in Exhibit \_\_\_\_ (TSB-  
5 2).

6 The Project will also have a net output capability,  
7 without duct-firing or power augmentation, of 545 MW (nominal)  
8 at ISO temperature (59°F.) and relative humidity (60%)  
9 conditions.

10 The Project will utilize dry low-NO<sub>x</sub> combustion  
11 technology to minimize emissions of NO<sub>x</sub>. In addition, an SCR  
12 system will be used to further reduce NO<sub>x</sub> emissions.  
13

14 **Q: Please describe the SCR system that will be used to reduce the**  
15 **Project's NO<sub>x</sub> emissions.**

16 **A:** The SCR system for the Project will consist of a catalyst and  
17 an ammonia injection grid located within the HRSG. When NO<sub>x</sub>  
18 is exposed to ammonia in the presence of the catalyst, the NO<sub>x</sub>  
19 is converted to elemental nitrogen and oxygen.  
20

21 **Q: Please give a brief description of the site for the Osprey**  
22 **Project.**

23 **A:** The site for the Project consists of approximately 19.5 acres,  
24 situated approximately 1.5 miles southwest of downtown

**DIRECT TESTIMONY OF TED S. BALDWIN**

1       Auburndale, in Polk County. The site is a non-producing  
2       citrus grove and is currently unused. A detailed description  
3       of the Project site is presented in the testimony of Mr.  
4       Richard Zwolak, AICP, in support of the Project, and in the  
5       exhibits that he is sponsoring in support of the Project.

6  
7       **Q: Please summarize the general arrangement and layout of the**  
8       **Project on the site.**

9       A: The general arrangement of the Project is shown on the Site  
10       Plan in Exhibit \_\_\_\_ (TSB-3). Exhibit \_\_\_\_ (TSB-4) shows a  
11       detailed layout of the main Project structures on the site,  
12       and Exhibit \_\_\_\_ (TSB-5) presents a computer-generated  
13       perspective rendition of the Project.

14  
15       **Q: Please describe the generating technology of the Osprey**  
16       **Project.**

17       A: The Osprey Energy Center will have an expected net output  
18       capability, without duct-firing or power augmentation, of  
19       approximately 529 MW based on the anticipated manufacturer's  
20       guarantee at average ambient site conditions. As I previously  
21       noted, the power block will consist of two advanced technology  
22       Siemens-Westinghouse Model 501F CTGs, two matched HRSGs that  
23       include duct-firing capability, and one STG, which has the  
24       ability to utilize steam for power augmentation to increase



DIRECT TESTIMONY OF TED S. BALDWIN

1 output from the CTGs.

2

3 Q: Please define the terms "duct-firing" and "power  
4 augmentation."

5 A: Duct-firing is a process whereby additional gas burners are  
6 placed within the HRSGs to increase the gas temperature and  
7 generate more steam, thus increasing power generation from the  
8 STG. Power augmentation refers to a process in which steam  
9 from the HRSGs is injected into the gas turbines for the  
10 purpose of increasing mass flow through the CTGs, thereby  
11 increasing the electrical power output from the CTGs.

12

13 Q: What will the peak generating capacity of the Osprey Project  
14 be?

15 A: Without duct-firing and power augmentation, the Osprey  
16 Project's rated winter capacity will be approximately 578 MW  
17 and its rated summer capacity will be approximately 496 MW.  
18 With duct-firing and power augmentation, the Project's winter  
19 capacity will be approximately 666 MW and its summer capacity  
20 will be approximately 575 MW.

21

22 Q: What are the Osprey Project's expected heat rate and thermal  
23 efficiency?

24 A: The Project is projected to have a heat rate of approximately

**DIRECT TESTIMONY OF TED S. BALDWIN**

1 6,800 Btu per kWh, based on the HHV of natural gas at average  
2 ambient site conditions, reflecting a net thermal efficiency  
3 of approximately 50.2 percent.

4  
5 **Q: Please describe the performance characteristics of the Osprey**  
6 **Project.**

7 **A:** The performance characteristics of the generating facility are  
8 summarized in the Plant Performance Table, Exhibit \_\_\_\_\_  
9 (TSB-6). This table presents facility generating output and  
10 emissions data for the Project at various expected ambient  
11 site conditions, at full and part load operation.

12  
13 **Q: Please describe the power generation cycle for the Project.**

14 **A:** The power generation cycle of the Project is depicted on the  
15 overall cycle schematic diagram for the Project on Exhibit  
16 \_\_\_\_ (TSB-7). In brief, natural gas is burned in the CTG  
17 where the expanding combustion gases turn the CTG's shaft to  
18 produce electricity; and exhaust gases exit the CTG and enter  
19 the HRSG at approximately 1100°F. Two HRSGs, one per CTG, are  
20 used to recover heat from the exhaust gases by producing steam  
21 at three different pressure levels. The steam produced in the  
22 HRSGs is then expanded through a single STG to produce  
23 additional electrical power. The successive uses of thermal  
24 energy, first in the CTGs and second in the HRSGs and STG, to

**DIRECT TESTIMONY OF TED S. BALDWIN**

1 produce electricity is why this generating technology is  
2 called "combined cycle."  
3

4 **Q: Please describe the design basis for the Project.**

5 A: The design basis for the Project is summarized in Exhibit \_\_\_\_  
6 (TSB-8). The description contained in Exhibit \_\_\_\_\_ (TSB-8)  
7 is accurate and is hereby incorporated by reference into my  
8 testimony.  
9

10 **Q: Please describe the basic electrical characteristics of the**  
11 **Osprey Project.**

12 A: The basic electrical characteristics of the Project are set  
13 forth in the Project's electrical one-line diagram, Exhibit  
14 \_\_\_\_\_, (TSB-9). In brief, electrical power is produced at 18  
15 kilovolts (kV) in the CTGs and 16 kV in the STG. Each  
16 generator is connected to a transformer which steps up the  
17 electrical voltage to 230 kV, which is the operating voltage  
18 of the Tampa Electric Company ("TECO") transmission system in  
19 the vicinity of the Osprey Project. Electricity is delivered  
20 to the transmission system through the Recker high voltage  
21 substation owned by TECO. This substation is an existing  
22 substation that will be expanded to accommodate the  
23 interconnection of the Project.  
24

DIRECT TESTIMONY OF TED S. BALDWIN

1 Q: Please describe the projected fuel use for the Project.

2 A: At full load, the Project will use approximately 86 million  
3 standard cubic feet of natural gas per day at annual average  
4 site conditions.

5

6 Q: Please summarize the start-up and emergency power supplies for  
7 the Project.

8 A: The Project will obtain station service and start-up power  
9 from Tampa Electric Company in order to maintain normal plant  
10 auxiliary loads during periods in which the facility is off-  
11 line and to accelerate the CTGs to a self-sustaining operating  
12 speed during start-up. In the event of a loss of the  
13 transmission system, emergency power for critical components  
14 necessary for safe shutdown of the plant will be provided from  
15 a stationary battery system. The plant is also equipped with  
16 emergency diesel generators to keep the battery system charged  
17 and to provide supplemental power to the plant for other loads  
18 that are not critical. The plant's battery system and  
19 emergency diesel generators will be capable of providing  
20 sufficient power for safe shutdown of each unit and to keep  
21 certain prioritized auxiliaries operating, but will not be  
22 capable of restarting the units.

23

24 Q: Please give a brief description of the control systems for the

**DIRECT TESTIMONY OF TED S. BALDWIN**

1       Osprey Project.

2       A: The Project is controlled by a distributed control system  
3       ("DCS"). A DCS is a fiber optic cable network that runs  
4       throughout the plant that picks up control input signals such  
5       as pressure, temperature, or flow, delivers the signals to the  
6       central control computer and then distributes control output  
7       signals such as the opening or closing of a valve or the  
8       starting and stopping of a motor. The control system is  
9       designed to provide full automation of the unit. The gas  
10      turbine sequencer allows the operator to start and stop the  
11      gas turbines automatically. Operator stations are designed to  
12      allow a graphical, intuitive navigation through the plant  
13      processes from a central control room.

14

15                                   OPERATIONAL RELIABILITY

16      Q: Please discuss the operational reliability of the Osprey  
17      Project.

18      A: The Osprey Project will have a high degree of reliability  
19      similar to other state-of-the-art combined cycle generating  
20      facilities.

21              Reliability is often measured in terms of the percentage  
22      of hours a unit is available to produce electricity within a  
23      specified period of time, usually one year. The Osprey  
24      Project is expected to achieve an annual equivalent

**DIRECT TESTIMONY OF TED S. BALDWIN**

1 availability factor of 94.5 percent. This factor will vary  
2 depending on the planned maintenance activities in a given  
3 year, the forced outage rate, the need to take the CTGs off-  
4 line to clean compressor blades, and the need to perform  
5 occasional minor maintenance.

6  
7 **Q: What are the expected forced outage and maintenance outage**  
8 **rates for the Osprey Project?**

9 **A:** The forced outage rate for the plant is expected to average  
10 approximately two percent per year.

11 The maintenance (also known as planned) outage rate for  
12 the plant is expected to average 3.5 percent per year, but the  
13 actual rate will vary from year to year in accordance with the  
14 vendor's recommended maintenance cycle for the CTGs. The  
15 Siemens-Westinghouse Model 501F turbines have an 8,000 hour  
16 maintenance cycle. A minor inspection, referred to as a  
17 combustor inspection, will be conducted at the end of each  
18 8,000 hours of operation. A slightly more detailed  
19 inspection, referred to as a hot gas inspection, along with  
20 the combustor inspection, will be conducted at the end of  
21 24,000 hours of operation. A major inspection will be  
22 conducted at 48,000 hours of operation. This cycle will be  
23 repeated for the life of the equipment. Combustor and hot gas  
24 inspections take approximately 7 days and 14 days

**DIRECT TESTIMONY OF TED S. BALDWIN**

1           respectively, and a major inspection takes approximately 21  
2           days.

3  
4       **Q: Who will operate the Osprey Project?**

5       **A:** The Osprey Project will be operated either by an operating  
6           subsidiary of Calpine or by a subcontractor engaged for that  
7           purpose by Calpine.

8  
9       **Q: Please describe any special design features or other**  
10           **considerations that are relevant to the Osprey Project's**  
11           **operational reliability.**

12       **A:** The Osprey Project will be constructed utilizing the most  
13           advanced CTG design with extensive operating experience. The  
14           building configuration and balance of plant equipment will be  
15           typical of designs used throughout the industry for combined  
16           cycle plants. Use of such standard equipment offers the  
17           highest possible reliability.

18

19                                   **ENVIRONMENTAL PROFILE**

20       **Q: Please summarize the environmental profile of the Osprey**  
21           **Project.**

22       **A:** The Project will be fueled by natural gas. The Project has  
23           been designed with careful consideration of environmental  
24           issues and will be one of the cleanest power plants in Florida

**DIRECT TESTIMONY OF TED S. BALDWIN**

1 and in the United States. It will utilize dry low-NO<sub>x</sub>  
2 combustion technology and an SCR system to minimize NO<sub>x</sub>  
3 emissions. The Project's emissions of critical pollutants are  
4 projected to be approximately as follows (based on an average  
5 ambient conditions of 74°F., 80% relative humidity, with both  
6 CTGs operating at 100% load, and without power augmentation or  
7 duct-firing):

8 Sulfur Dioxide: negligible, less than 19.8 lbs. per hour  
9 (less than 87 tons per year)

10 Nitrogen Oxides: 3.5 parts per million dry volume at 15%  
11 oxygen, or 46.3 lbs. per hour (203 tons  
12 per year)

13 Volatile Organic Compounds: 10.4 lbs. per hour (46 tons  
14 per year)

15 Particulate Matter: 40.1 lbs. per hour (176 tons per year) as  
16 PM<sub>10</sub>

17 Carbon Monoxide: 10 parts per million dry volume at 15%  
18 oxygen, 82 lbs. per hour (359 tons per  
19 year)

20 Operation of the Project is likely to result in  
21 measurable reductions in emissions of SO<sub>2</sub>, CO<sub>2</sub>, NO<sub>x</sub>, and other  
22 air pollutants in Peninsular Florida, due to the Project's  
23 displacement of generation from: (a) units that burn fuels  
24 that produce more pollution than is produced by the natural



**DIRECT TESTIMONY OF TED S. BALDWIN**

1 gas fuel used in the Project, (b) less efficient units, and  
2 (c) units that do not include the types of pollution controls  
3 being utilized by the Project.

4  
5 **Q: Please summarize the projected water requirements and water**  
6 **supply plan for the Osprey Energy Center Project.**

7 **A:** The Project will require approximately 3.82 million gallons  
8 per day ("MGD") of water calculated on an annual average basis  
9 based on the assumption that 1.6 MGD of reclaimed water will  
10 be available to the Project. At peak conditions with power  
11 augmentation and duct-firing for six hours per day, the  
12 Project will require approximately 4.80 MGD of water (also  
13 based on the assumption that 1.6 MGD of reclaimed water will  
14 be available to the Project).

15 The Osprey Project will utilize a combination of  
16 reclaimed water and ground water for its process and makeup  
17 water supply. Reclaimed water will be supplied from the City  
18 of Auburndale's Allred Wastewater Treatment Plant and Westside  
19 Regional Wastewater Treatment Plant. The Project will require  
20 the construction of reclaimed water pipelines to connect with  
21 the City of Auburndale's wastewater treatment facilities. The  
22 pipelines to the Allred wastewater treatment facilities will  
23 be approximately one mile in length and will be constructed in  
24 existing public rights-of-way. The pipelines to the Westside

**DIRECT TESTIMONY OF TED S. BALDWIN**

1 Regional Wastewater Treatment Plant will be approximately 8  
2 miles in length and will be constructed in public rights-of-  
3 way. Additionally, other minor pipeline modifications will be  
4 made to enhance discharge capability. The reclaimed water  
5 supply and return pipelines to Allred will run along the north  
6 Recker Highway right-of-way to the Osprey Project site  
7 boundary. The reclaimed water supply and return pipelines to  
8 Westside Regional are planned to run west along the Polk  
9 County Parkway right-of-way to U.S. Highway 92 and then on an  
10 existing City of Auburndale right-of-way east along Highway  
11 92, to Recker Highway, to Derby Avenue, and onto the Osprey  
12 Project site. The City of Auburndale will obtain the  
13 necessary permits for the water and wastewater pipelines. The  
14 remainder of the Osprey Project's water supply will be  
15 provided by new on-site wells withdrawing water from the Upper  
16 Floridan aquifer.

17 The preliminary water balance for the Project at average  
18 conditions is shown in Exhibit \_\_\_\_\_ (TSB-10), and the  
19 preliminary water balance for peak monthly conditions is shown  
20 in Exhibit \_\_\_\_\_ (TSB-11).

21

22

**PROJECT SCHEDULE**

23 Q: Who will be the engineering, procurement, and construction  
24 contractor for the Project?

**DIRECT TESTIMONY OF TED S. BALDWIN**

1 A: Calpine Corporation's construction management group will  
2 manage the engineering and construction of the Osprey Project.  
3 Calpine Corporation's construction management group will  
4 specify and procure the major equipment for the Osprey Project  
5 including the CTGs, HRSGs, and the STG. Parsons Energy and  
6 Chemical Group will perform the detailed engineering for the  
7 Project. Calpine Corporation's construction management group  
8 will competitively bid the construction of the Osprey Project  
9 to qualified general contractors with experience in the power  
10 industry, such as H.B. Zachary or The Industrial Company.

11  
12 Q: Please describe the engineering, procurement, and construction  
13 schedule for the Project.

14 A: The engineering, procurement, and construction schedule (the  
15 "EPC schedule"), Exhibit \_\_\_\_ (TSB-12), provides for the  
16 Project to be designed and brought into commercial service --  
17 i.e., "on-line" -- by the second quarter of 2003. Preliminary  
18 engineering design has already begun and detailed engineering  
19 will begin in February 2001. The general contractor for  
20 construction will be selected in the first quarter of 2001.  
21 The Project schedule provides for approximately 24 months from  
22 Project release to commercial operation.

23  
24 Q: What is the current status of the engineering design work for

**DIRECT TESTIMONY OF TED S. BALDWIN**

1       the Osprey Project?

2       A: Conceptual engineering is complete. A site plan, plot plan,  
3       process flow diagram, electrical one-line diagram, water  
4       balance, capital cost estimate, and operation and maintenance  
5       estimate are also complete.

6

7       Q: Does this conclude your direct testimony?

8       A: Yes, it does.

BEFORE THE FLORIDA PUBLIC SERVICE COMMISSION

In Re: Petition for Determination of )  
Need for an Electrical Power Plant in ) DOCKET NO. 000442-EI  
Polk County by Calpine Construction )  
Finance Company, L.P. )  

---

**EXHIBITS**

OF

**TED S. BALDWIN**

ON BEHALF OF

**CALPINE CONSTRUCTION FINANCE  
COMPANY, L.P.**

**TED S. BALDWIN**  
Calpine Corporation  
Two Urban Center  
4890 W. Kennedy Blvd., Suite 600  
Tampa, FL 33609

**JOB EXPERIENCE:**

REGIONAL ENGINEER, Calpine Corporation, Tampa, FL, May 2000 to present.

- Responsible for technical support of all business development activities in the Southeastern United States. Project locations include Florida, Alabama, Mississippi, and Kentucky.

Tasks managed include due diligence on existing facilities, conceptualization of project technical configuration, preparation of project heat balances, site selection and site development (including environmental permits), preparation of capital cost estimates, participation in the negotiation of power purchase agreements and tolling agreements, development and negotiation of engineering and construction contracts, review of fuel supply contracts and other project documents, and interface with financing parties regarding technical aspects of the projects.

DIRECTOR OF ENGINEERING AND CONSTRUCTION, Nations Energy Corporation (Independent Power Subsidiary of Tucson Electric Power), Winter Park, Fl., May 1995 to present.

- Involved in the startup of a new energy development company. Responsibilities include managing all technical aspects of developing domestic and international energy projects, including acquisitions and greenfield/brownfield projects. Successfully closed two projects and carried two other projects through advanced stages of development with closings expected in 1999 and 2000.

Tasks managed include due diligence on existing facilities, conceptualization of project technical configuration, site selection and site development (including environmental permits), preparation of capital cost estimates, preparation of operation and maintenance (O&M) estimates, participation in the negotiation of power purchase agreements and tolling agreements, development and negotiation of engineer, procurement, and construction (EPC) contracts and O&M agreements, review of fuel supply contracts and other project documents, and interface with financing parties regarding technical aspects of the projects. Also manage the implementation of one international EPC contract by providing direction to project manager directly responsible for the project.

Country involvement includes U.S.A. (Colorado, Florida, and Louisiana), Mexico, Panama, Honduras, Netherlands Antilles, and Czech Republic. Fuel technologies include gas, pulverized coal, waste coal, biomass, diesel, residual oil, and refinery byproducts such as refinery gas and asphalt. Projects often involve the integration of existing facilities with new facilities and the supply of power, steam, and other utilities to industrial complexes such as refineries and breweries.

Resume of  
**TED S. BALDWIN**  
Page 2 of 3

APPLICATION ENGINEERING MANAGER, Power Generation Business Unit, Westinghouse Electric Corp., Orlando, Fl., April 1992-April 1995.

- Managed a multi-disciplined group of twenty-three engineers and technicians including thermal design, mechanical design, controls, and electrical engineers. The group was responsible for the technical content of bids and the technical negotiation of all new construction orders within the business unit, including combustion turbine and steam turbine equipment, extended scope thermal island (combined cycle and conventional steam), and extended scope turnkey (simple cycle and combined cycle) projects. Annual sales in 1994 significantly in excess of one billion dollars. Responsible for technical negotiation of EPC contracts and risk management of all technical related warranties including plant performance, emissions, availability, reliability, etc. Oversaw transformation of organization into regional business teams with application engineering personnel stationed at four different locations throughout the world.

THERMAL CYCLE SYSTEM GROUP MANAGER, Power Generation Projects Division, Westinghouse Electric Corp., Orlando, Fl., April 1990-March 1992.

- Responsible for the implementation of combined cycle power projects from contract signing to completion of plant performance testing. Managed a group of ten engineers and technicians responsible for thermal cycle design, preparation of plant mass and material balances, and specification/evaluation of major thermal equipment (heat recovery steam generator, steam turbine, condenser, deaerator, cooling tower, auxiliary boiler, etc.) within the power plant. The group was also responsible for performance testing of the power plant after commissioning.

THERMAL CYCLE SYSTEMS ENGINEER, Power Generation Projects Division, Westinghouse Electric Corp., Orlando, Fl., May 1987-March 1990.

- Responsible for application support and implementation support of combined cycle power projects, mostly in the domestic market. Prepared preliminary and final cycle design, final plant mass and material balances, major equipment specifications for heat recovery steam generators, condensers, deaerators, etc. Participated in the evaluation and vendor negotiations for these pieces of equipment.

BOILER ENGINEER, Machinery Technology Division, Westinghouse Electric Corp., Pittsburgh, Pa., December 1985-April 1987.

- Provided thermal design engineering support to the U.S. Navy in the field of marine propulsion boilers.

Resume of  
**TED S. BALDWIN**  
Page 3 of 3

EQUIPMENT ENGINEER/ANALYTICAL ENGINEER, Machinery Division/Furnace Division, The M.W. Kellogg Company, Houston, Texas, June 1982-November 1985.

- Responsible for preparation of equipment specifications, evaluation of vendors' bids, requisition preparation, technical follow-up, drawing review, and performance testing on major power generation equipment items including package boilers, gas turbine waste heat recovery units, and associated auxiliaries.

**EDUCATION:**

Masters of Science in Mechanical Engineering, 1982. The University of Michigan, Ann Arbor. Graduate Fellowship Program. Curriculum emphasis in the thermal sciences.

Bachelor of Science in Mechanical Engineering, 1981. The University of Texas, Austin. Scholarship Program.



TABLE 2

OSPREY ENERGY CENTER  
PROJECT PROFILE

**Expected Plant Capacity:**

a.	Average ambient rating (74°F, 80% R.H.):	529 MW
b.	Summer (95°F, 80% R.H.):	496 MW
	With Duct-firing & Power Augmentation:	575 MW
c.	Winter (32°F, 60% R.H.):	578 MW
	With Duct-firing & Power Augmentation:	666 MW
d.	ISO (59°F, 60% R.H.):	545 MW

**Project Energy Production:** Approximately 4,300,000 MWH/year  
(not including duct-firing or power augmentation)

**Technology Type:** Two Siemens-Westinghouse 501F advanced firing temperature technology combustion turbines, two heat recovery steam generators, and one steam turbine generator in combined cycle configuration

**Anticipated Construction Schedule:**

a.	Engineering release date:	February 2001
b.	Construction mobilization date:	June 2001
c.	Commercial in-service date:	2nd quarter 2003

**Fuel Use:** Approximately 86 million Standard Cubic Feet of natural gas/day, annual average conditions (74°F, 80% R.H.), full load

**Air Pollution Control Strategy:** Dry low-NOx burners and SCR

**Cooling Method:** Wet Cooling Tower

**Total Site Area:** 19.5 acres (approximate)

**Construction Status:** Planned

**Certification Status:** Need Determination Petition and Site Certification Application filed.

**Status with Federal Agencies:** FERC has issued its order granting Calpine market-based rate authority.

TABLE 2

OSPREY ENERGY CENTER  
PROJECT PROFILE  
(CONTINUED)

**Projected Unit Performance Data:**

Planned Outage Factor (POF):	3.5%
Forced Outage Factor (FOF):	2.0%
Equivalent Availability Factor (EAF):	94.5%
Estimated Annual Average Capacity Factor (%):	91.0%

Average Net Operating Heat Rate (ANOHR): 6800 Btu/kWh (HHV)  
(74°F, 80°R.H.) expected

**Project Unit Financial Data (per Calpine Corporation):**

Book Life (years):	35 years
Direct Construction Cost:	Approx. \$194.8 million
AFUDC Amount:	Not applicable
Escalation (\$/kW):	Not applicable
Fixed O&M (\$/kW per year):	Proprietary
Variable O&M (¢/MWH):	Proprietary
K-Factor:	Not applicable
Project Life:	35 years

**Expected Plant Air Emissions:** NO<sub>x</sub>: 3.5 ppmvd @15% O<sub>2</sub>  
SO<sub>2</sub>: 20.8 lbs/hour  
CO: 10 ppm

**New Transmission Lines Required:** None


**Gas Pipeline Required:** None

**Water Requirements:** Approx. 4.80 MGD, summer peak  
(Including Reclaimed Water) Conditions (95°F, 80 R.H.),  
(with power augmentation and duct-firing)  
Approx. 3.82 MGD average  
(74°F, 80 R.H.), (without  
power augmentation or duct-firing)


**Wastewater Discharge:** Approx. 1.27 MGD, summer peak  
conditions (with power  
augmentation and duct-firing)  
Approx. 0.90 MGD, average  
conditions (3.9 cycles of  
concentration without power  
augmentation and duct-firing)



### Legend

1. ADMINISTRATION AND MAINTENANCE BUILDING
2. SERVICE WATER TANK
3. COOLING TOWER
4. CIRCULATING WATER PUMPS
5. FUEL GAS HEATER
6. COMBUSTION TURBINE AIR INLET FILTER
7. KETTLE BOILER
8. LUBE OIL SKID
9. ST GENERATOR
10. CT MECHANICAL PACKAGE
11. STEAM TURBINE
12. COMBUSTION TURBINE
13. CT GENERATOR
14. AMMONIA INJECTION SKID
15. HEAT RECOVERY STEAM GENERATOR
16. HRSG STACK
17. HRSG BLOWDOWN TANK
18. BOILER FEED PUMP HOUSE
19. CEWS
20. AMMONIA STORAGE TANKS
21. CONDENSATE PUMPS
22. CONDENSER
23. DEMINERALIZED WATER STORAGE TANK
24. WET SURFACE AIR COOLER
25. GENERATOR STEP-UP TRANSFORMER
26. WASTEWATER TANK
27. RAW WATER STORAGE TANK
28. FUEL GAS SCRUBBER
29. UNIT AUX. TRANSFORMER
30. ISO-PHASE BUS DUCT
31. STANDBY GENERATOR
32. ELECTRICAL EQUIPMENT PACKAGE
33. GENERATOR VT & SURGE CUBICLE
34. GENERATOR EXCITATION SKID
35. COMPRESSOR WATER WASH SKID
36. STEAM JET AIR EJECTORS
37. CLAND STEAM CONDENSER
38. OIL/WATER SEPARATOR
39. GAS METER BUILDING
40. HYDRAULIC SKID
41. EXCITATION TRANSFORMER
42. CENTRAL PUMP HOUSE



FPSC Docket No. 000442-E1  
 Calpine Construction Finance Co., L.P.  
 Witness: Baldwin  
 Exhibit \_\_\_\_\_ (TSB-3)

 <b>Golder Associates</b> Client / Project Calpine Construction Finance Company, L.P. Gennev Energy Center	Tampa, Florida		Site Plan	
	CAD BY: CDT CHK BY: HCB	SCALE: 1"=120' DATE: 08/11/00	Job No. 993-9570 FIGURE 7000	Revision 1




**Golder Associates**  
Tampa, Florida

Client / Project  
Calpine Construction Finance Copany, L.P.  
Osprey Energy Center

FPSC Docket No. 000442-EI  
Calpine Construction Finance Co., L.P.  
Witness: Baldwin  
Exhibit \_\_\_\_\_ (TSB-4)

**PLOT PLAN**

DAD BY: CDT	SCALE: 1"=400'	Job No. 993-9570
CHK BY: RAZ	DATE: 03/02/00	FIGURE
REV BY: -	FILE No.: plot-plan.dwg	



FPSC Docket No. 000442-EI  
 Calpine Construction Finance Co., L.P.  
 Witness: Baldwin  
 Exhibit \_\_\_\_\_ (TSB-5)



Tampa, Florida

PERSPECTIVE RENDITION

Client / Project

Calpine Construction Finance Company, L.P.  
 Osprey Energy Center

CAD BY: CDT	SCALE: NTS
CHK BY: RAZ	DATE: 03/04/00
REV BY: -	FILE No.: flg1_3_3-1.dwg

Job No. 993-9570


FIGURE

**TABLE 2**  
**OSPREY ENERGY CENTER**  
 Estimated Plant Performance and Emissions Data

Percent Load		100%	100%	100%	100%	70%	70%	70%	70%	60%	60%	60%	60%	100%
Ambient Temperature	F	95	74	59	32	95	74	59	32	95	74	59	32	95
Ambient Relative Humidity	%	80%	80%	60%	60%	80%	80%	60%	60%	80%	80%	60%	60%	80%
Gas Turbine Power	MW	324	347	362	390	222	240	253	272	190	205	216	233	357
Steam Turbine Power	MW	185	195	197	203	145	153	152	154	135	143	149	148	233
Net Cycle Power	MW	496	529	545	578	358	383	395	416	317	339	356	371	575
Net Cycle LHV Heat Rate	BTU/KW-hr	6,187	6,122	6,125	6,137	6,497	6,430	6,359	6,373	6,599	6,529	6,478	6,457	6,576
Net Cycle LHV Efficiency	%	55.2%	55.7%	55.7%	55.6%	52.5%	53.1%	53.7%	53.5%	51.7%	52.3%	52.7%	52.9%	51.9%
Net Cycle HHV Heat Rate	BTU/KW-hr	6,871	6,798	6,802	6,815	7,215	7,140	7,062	7,077	7,329	7,251	7,193	7,170	7,303
CTG fuel flow (lb/h)- total for two CTGs	lb/hr	146,325	154,237	159,099	168,918	110,864	117,346	119,634	126,212	99,806	105,621	109,911	114,296	155,858
CTG heat input, HHV basis (mmBtu/h)- total for two CTGs	MMBtu/hr	3,409	3,594	3,707	3,936	2,583	2,734	2,787	2,941	2,325	2,461	2,561	2,663	3,631
Duct burner fuel flow (lb/h)- total for two burners	lb/hr	0	0	0	0	0	0	0	0	0	0	0	0	24,308
Duct burner heat input, HHV basis (mmBtu/h)- two burners	MMBtu/hr	0	0	0	0	0	0	0	0	0	0	0	0	566
CTG exhaust gas flow (lb/h)- total for two CTGs (two duct burners when on)	lb/hr	6,630,800	6,973,469	7,218,232	7,578,580	5,692,996	5,888,867	6,028,774	6,258,506	5,081,836	5,240,757	5,354,272	5,539,920	6,655,108
CTG exhaust gas composition (% by volume)														
Nitrogen	%	72.64	73.47	74.37	74.82	72.93	73.82	74.63	75.07	72.93	73.77	74.56	75.04	68.31
Argon	%	0.91	0.92	0.93	0.94	0.92	0.99	0.94	0.94	0.92	0.93	0.94	0.94	0.86
Oxygen	%	12.13	12.28	12.51	12.53	13.00	13.11	13.26	13.26	12.99	12.97	13.07	13.15	9.85
Carbon dioxide	%	3.70	3.74	3.74	3.79	3.31	3.37	3.40	3.47	3.31	3.43	3.49	3.52	4.26
Water	%	10.62	9.59	8.44	7.92	9.85	8.77	7.77	7.26	9.86	8.90	7.94	7.36	16.73
NOx as NO2 (lb/h)- total for two stacks	lb/hr	44.1	46.3	48.6	51.5	34.2	35.4	36.7	38.9	30.4	32.0	33.5	34.8	55.0
based on ppmvd @ 15% O2	ppm	3.5	3.5	3.5	3.5	3.5	3.5	3.5	3.5	3.5	3.5	3.5	3.5	3.5
CO (lb/h)- total for two stacks	lb/hr	78	82	86	90	60	62	64	68	266	279	292	304	279
based on ppmvd @ 15% O2	ppm	10	10	10	10	10	10	10	10	50	50	50	50	29
VOC as CH4 (lb/h)- total for two stacks	lb/hr	9.9	10.4	10.9	11.5	14.1	14.7	15.3	16.0	12.7	13.3	14.0	14.5	24.8
based on ppmvd @ 15% O2	ppm	2.3	2.3	2.3	2.3	4.2	4.2	4.2	4.2	4.2	4.2	4.2	4.2	4.6
SO2 (lb/h)- total for two stacks	lb/hr	18.8	19.8	20.7	22.0	14.4	15.0	15.6	16.4	13.0	13.7	14.3	14.9	23.9
Particulates as PM10 (lb/h)- total for two stacks	lb/hr	38.0	40.1	42.2	44.5	32.1	33.4	34.6	36.1	28.7	29.8	30.9	32.1	45.6

FPSC Docket No. 000442-EI  
 Calpine Construction Finance Co., L.P.  
 Witness: Baldwin  
 Exhibit (TSB-6)

# FIGURE 6 COMBINED-CYCLE GENERATION SCHEMATIC DIAGRAM



## **OSPREY ENERGY CENTER**

### **DESIGN BASIS**

#### **INTRODUCTION**

The Osprey Project is a highly efficient combined cycle electric power plant that will be fueled by natural gas. The Project will be nominally rated to produce 545 MW at ISO temperature and relative humidity, and 529 MW at average ambient site conditions. This Design Basis describes the Project and its supporting systems.

#### **PROJECT LOCATION**

The Osprey Project site will be located in the City of Auburndale, in Polk County, Florida, on approximately 19.5 acres situated approximately 1.5 miles southwest of downtown Auburndale and approximately 37 miles east of Tampa Bay. The site is a non-producing citrus grove zoned "Light Industry" and is currently unused. Land uses adjacent to the site include the TECO Recker Substation and 230 kV transmission line; the existing Auburndale Power Plant, which is a 150 MW natural gas-fired (with oil backup fuel) cogeneration plant owned by Auburndale Power Partners; two small residential enclaves; a cemetery; and commercial and industrial businesses. Access to the site will be from West Derby Avenue, a two-lane county collector road.



## OVERVIEW

The proposed Project will consist of two gas-fired advanced technology, dry low-NO<sub>x</sub> combustion turbine generators ("CTGs") with the capability to use power augmentation to increase the CTGs' power output, two heat recovery steam generators (HRSGs) that include duct-firing capability to increase the steam generation capability of the HRSGs, and one steam turbine generator ("STG") rated for the full steam production capacity (including duct-firing) of the HRSGs. The CTGs will generate approximately 65 percent of the Project's output and the STG will generate approximately 35 percent of the Project's output. Thermal energy will be recovered from the hot combustion gases exiting the CTGs to generate steam in the HRSGs. Steam from the HRSGs will be expanded through an STG which will produce the remaining balance of the Project's output. This process of utilizing both the power generated in the combustion turbines as well as that generated by the STG is commonly referred to as "combined cycle" generation. To enhance power output during peak demand periods, the HRSGs are equipped with duct burners which burn additional natural gas inside the HRSGs to produce additional steam that is then used in the STG to produce additional power. Further peaking power can also be provided by extracting steam from the STG and injecting it into the CTGs. These two methods of providing peaking power will be utilized primarily during the summer months. Cooling water will be used in conjunction with cooling towers to condense steam back to water for reuse in the HRSGs. The

Project's water supply will be a combination of reclaimed water and well water.

The Project will emit nitrogen oxides (NO<sub>x</sub>), carbon monoxide (CO), non-methane hydrocarbons, small quantities of particulate matter (PM<sub>10</sub>), and sulfur oxides (SO<sub>x</sub>). The Project will be designed to control NO<sub>x</sub> using an advanced dry low-NO<sub>x</sub> combustion system and a selective catalytic reduction (SCR) system. This represents state-of-the-art emissions control technology, capable of achieving approximately 3.5 ppmvd NO<sub>x</sub> levels. Only trace amounts of SO<sub>2</sub> will be emitted when burning natural gas. CO and non-methane hydrocarbon emissions will be minimized through the use of good combustion practice.

## **PROJECT DESCRIPTION**

### **Project Structures and Buildings**

The Osprey Project will include the following structures and buildings:

- A common control room, warehouse and administration building which will contain a workshop, a maintenance area, and offices.
- Each HRSG will be located adjacent to its CTG and will connect to an approximate 135 foot high emission stack. There will be one stack for each unit.
- Mechanical induced draft evaporative cooling towers.
- Water storage tanks.
- An electrical switchyard.

### **Combustion Turbine Generators**

The Project will employ Siemens-Westinghouse 501F industrial frame advanced technology CTGs equipped with dry low-NO<sub>x</sub> combustors. The CTGs will be housed in an enclosure which provides thermal insulation, acoustical attenuation, and fire extinguishing media containment. The enclosure will allow access for routine inspections and maintenance.

### **Heat Recovery Steam Generators**

One of the significant features of a combined cycle plant is the utilization of the hot exhaust gas from the CTGs to produce steam which, in turn, is expanded in a STG to drive an electric generator and produce electricity. The HRSGs are the key pieces of equipment necessary to the production of this steam. The HRSGs will be multiple-pressure, reheat units. The various pressure sections will each consist of economizer, evaporator and superheater sections. The HRSGs will also be equipped with a reheater to further improve cycle efficiency.

### **Steam Turbine**

The STG will be a multiple admission, reheat, condensing turbine designed for sliding pressure operation. The high pressure portion of the STG receives high pressure superheated steam from the HRSG and then exhausts steam into the reheat section of the

HRSG. Reheated steam from the HRSG is supplied to the intermediate pressure turbine, and the intermediate pressure turbine exhausts into the low pressure turbine. The low pressure turbine receives low pressure superheated steam from the HRSG and exhausts steam into the condenser.

### **Stacks**

CTG combustion gases will discharge through two approximate 19 foot diameter, 135 foot high carbon steel stacks. The stacks will be designed to minimize the potential for aerodynamic down wash of stack emissions.

### **Cooling System**

After the steam passes through the STG, it is condensed in a shell and tube heat exchanger (surface condenser) utilizing cooling water from the cooling tower. Each condenser will include a shell, tubes, a water box, and hot well. Condensed water in the hot well is pumped back to the HRSG to begin the thermal cycle again.

Cooling water for the condensers will be provided from evaporative (wet) induced draft cooling towers. Fans at the top of the cooling tower maintain a draft within the cooling tower. The water will be cooled by evaporation as it falls through baffles from the top of the cooling tower to a basin at the bottom of the tower where it is again pumped back through the condenser. Cooling tower components will include a basin, fans, fan decks,

drift eliminators, fill material (baffles), and other necessary components. Average water usage will be approximately 3.82 million gallons per day when operating at full load, but without duct-firing or power augmentation, at average site conditions. Maximum water usage will be approximately 4.80 million gallons per day when operating at 95° F, 80% relative humidity while using both power augmentation and duct-firing.

### **Fuel Supply and Storage Systems**

Natural gas will be the primary fuel for the Project. The Project's gaseous fuel system will interconnect to the Gulfstream gas metering station located on the site. The gas fuel system will also include fuel gas heaters, meters, and an isolation system in accordance with governing engineering codes.

### **Condensate and Feedwater Systems**

The condensate system will deliver de-aerated water from the condenser hotwell to the HRSG. The condensate system will also provide water to other Project subsystems.

The feedwater system will provide feedwater to the economizer sections of the HRSG.

The feedwater system will also supply water to interstage desuperheaters.

### **Demineralized Water System**

The demineralizer plant will consist of a permanently installed demineralizer system to

produce demineralized water for the Project from the raw water source. The product water from the demineralizer system will be stored in a demineralized water storage tank for use as steam cycle makeup water.

The tank will be constructed of lined carbon steel. Demineralizer system wastewater treatment will be done on-site and then discharged to the City of Auburndale's wastewater treatment plants.

#### **Boiler Feedwater Treatment System**

The boiler feedwater treatment system would likely consist of hydrazine (or a suitable substitute) for oxygen scavenging (injected into condensate system); phosphate for boiler water solids control (utilized in the HRSG steam drums); and neutralizing amine for pH control (fed into condensate).

#### **Waste Water Treatment System**

The process waste streams will be combined, collected, and disposed of separately or in combination, depending on the type of treatment required and the ultimate discharge point. Plant wastewater that could potentially contain small quantities of oil (including wastewater from the plant area washdown floor drains, equipment and sample drains) will be treated in an oil/water separator, from which the clean effluent may be recycled for use as cooling tower makeup. Oil and sludge collected in the oil/water separator will

be disposed of off-site. Wastewater grab sample points will be provided in accordance with the requirements of all applicable permits.

Sanitary waste will be discharged to the local wastewater treatment plant for disposal.

Approximately 2,880 gallons of sanitary waste will be generated per day.

HRSB blowdown will be collected in a dedicated sump and recycled to a small wastewater cooling tower before being discharged to the City of Auburndale's Allred and Westside Regional Wastewater Treatment Plants. Cooling tower blowdown will also be routed to the Allred and Westside Regional Wastewater Treatment Plants.

Spill prevention and control measures will include dikes around acid tanks and other chemical tanks. The dikes will be sized to contain a volume larger than that of the enclosed tank or tanks. Curbed enclosures will be provided for boiler feedwater treatment chemicals and water pretreatment chemicals.

Oil-filled transformers will be located in a sump. Storm water that collects in the sumps will drain to a common corner sump.

### **Compressed Air System**

The compressed air system will be designed to provide dry, oil-free, control air for plant instrumentation, controls and maintenance activities.

The primary source of plant compressed air will be from permanently installed air compressors. The instrument air supply will be oil-filtered and dried. The system will

also include a compressed air receiver.

The system will be complete with piping, valves, locally mounted instrumentation, and controls.

### **Fire Protection System**

An on-site fire protection system will be provided for the plant. The water supply for the fire protection system will be stored on-site in either the raw water tank or cooling tower basin. A main underground fire header will be provided to serve strategically placed yard hydrants and sprinkler/deluge systems for the Project.

The fire water distribution system will incorporate sectionalizing valves so that a failure in any part of the system can be isolated while allowing the remainder of the system to function properly.

The fire protection system will also include:

- An extinguishing system for the gas turbine/generator set;
- A dry pipe, automatic sprinkler system to envelop, as required, oil piping and equipment associated with the steam turbine lubrication oil system;
- Wet pipe sprinkler systems for the turbine building and warehouse storage area;
- and
- A protective signaling system with main panel in the control room.



### **Control System**

Each unit will have a state-of-the-art, integrated microprocessor-based control system for plant control, data acquisition, and data analysis. The plant control system will provide for startup, shutdown, and control of plant operation within limits and for protection of equipment.

### **Electric Power System**

The electric output of each of the Project's generators will be connected to main step-up transformers. The output from the main step-up transformers will be connected to the Project's on-site switchyard.

### **Emissions Monitoring**

A continuous emissions monitoring system for airborne pollutants will be installed to provide monitoring and alarming of NO<sub>x</sub> and CO concentrations in the HRSG exhaust systems. The emissions monitoring system will provide input signals to the microprocessor-based data acquisition system and will meet all the requirements of the Florida Department of Environmental Protection (FDEP) for monitoring and reporting.


### **Stormwater Drainage**

A permanent stormwater management basin will be provided to collect stormwater from

the Project. Stormwater will be collected by a system of drains and catch basins which will connect to underground piping and swales to provide a gravity drain system. The basin will be sized to allow collected sediment to settle out before it is discharged, as well as to ensure that peak runoff rates are not increased.

**Associated Facilities**

No linear facilities are being permitted in connection with the proposed Osprey Project. Natural gas will be provided to the Project from a natural gas pipeline and lateral to be constructed by Gulfstream.



**Legend**  
 — Existing  
 - - - Future  
 - - - Site Boundaries

**Notes:**  
 1. Switchyard breaker ratings are 2000 amp/40 Ka typical

FPSC Docket No. 000442-EI  
 Calpine Construction Finance Co., L.P.  
 Witness: Baldwin  
 Exhibit \_\_\_\_\_ (TSB-9)



Tampa, Florida


**Station One-Line  
 Electrical Diagram**

Client / Project

Calpine Construction Finance Company, L.P.  
 Osprey Energy Center

CAD BY: CDT	SCALE: NTS
CHK BY: RAZ	DATE: 08/10/00
REV BY: -	FILE No.: fig3_1_0-3.dwg

Job No. 993-9570
FIGURE Revision 01 3.1.0-3



FPSC Docket No. 000442-EI  
 Calpine Construction Finance Co., L.P.  
 Witness: Baldwin  
 Exhibit (TSB-10)



Client / Project

Calpine Construction Finance Company, L.P.  
 Osprey Energy Center

Tampa, Florida


**Average Annual Daily Water Balance Diagram  
 (Preliminary)**

CAD BY: CDT	SCALE: NTS
CHK BY: RAZ	DATE: 03/11/00
REV BY: -	FILE No.: fig3_5_0-1.dwg

Job No. 993-9570

FIGURE

1



Note: All values reported in gallons per minute (GPM)

FPSC Docket No. 000442-EI  
 Calpine Construction Finance Co., L.P.  
 Witness: Baldwin  
 Exhibit (TSB-11)



Client / Project


Calpine Construction Finance Company, L.P.  
 Osprey Energy Center

Tampa, Florida

Peak Monthly Daily Water Balance Diagram  
 (Preliminary)

CAD BY: CDT	SCALE: NTS	Job No. 993-9570
CHK BY: RAZ	DATE: 03/10/00	FIGURE
REV BY: --	FILE No.: fig3_5_0-2.dwg	2

# OSPREY ENERGY CENTER PRELIMINARY PROJECT SCHEDULE



Start Date 01JAN99  
 Finish Date 28MAR03  
 Data Date 30JAN00  
 Run Date 07MAR00 14:33

Early Bar  
 Progress Bar  
 Critical Activity

© Primavera Systems, Inc.


OSPR

CAMPINE  
OSPREY ENERGY PROJECT  
Campine Preliminary Schedule

Sheet 1 of 3

FPSC Docket No. 000442-EI  
 Calpine Construction Finance Co., L.P.  
 Witness: Baldwin  
 Exhibit (TSB-12)

# OSPREY ENERGY CENTER PRELIMINARY PROJECT SCHEDULE (continued)



# OSPREY ENERGY CENTER PRELIMINARY PROJECT SCHEDULE (continued)

