ORIGINAL

1		REBUTTAL TESTIMONY OF MR. JAMES W. STEGEMAN
2		ON BEHALF OF BELLSOUTH TELECOMMUNICATIONS, INC.
3		BEFORE THE FLORIDA PUBLIC SERVICE COMMISSION
4		DOCKET NO. 990649-TP
5		(PHASE II)
6		August 21, 2000
7		
8	INTI	RODUCTION
9		
10	Q.	PLEASE STATE YOUR NAME AND BUSINESS AFFILIATION.
11		
12	A.	My name is James W. Stegeman. I am the President of CostQuest Associates, Inc. I am
13		testifying on behalf of BellSouth Telecommunications ("BellSouth", "BST" or the
14		"Company").
15		
16	Q.	ARE YOU THE SAME JAMES STEGEMAN WHO FILED DIRECT
17		TESTIMONY IN THIS PROCEEDING ON MAY 1, 2000?
18		
19	A.	Yes.
20		
21	Q.	WHAT IS THE PURPOSE OF YOUR REBUTTAL TESTIMONY?
22		
23	A.	In my rebuttal testimony, I address BSTLM issues raised in the rebuttal testimony of
24		John C. Donovan and Brian F. Pitkin, on behalf of AT&T Communications of the
25		Southern States, Inc. ("AT&T") and MCI WorldCom, Inc. ("MCI").

-	
1	

Also, for the reader's convenience, I have provided a list of acronyms used as an attachment to my testimony as Exhibit JWS-1.

5 Q. BELLSOUTH RECENTLY MADE AN UPDATED FILING OF BSTLM IN THIS 6 PROCEEDING ON AUGUST 16, 2000. DOES THIS NEW VERSION OF THE 7 BSTLM ADDRESS SOME OF THE ISSUES RAISED BY MR. DONOVAN AND 8 MR. PITKIN?

10 A. Yes. Mr. Donovan and Mr. Pitkin raise several issues concerning the speed of BSTLM,

11 structure costs in the model, and drop routing.

BellSouth has addressed their concerns as follows:

Speed:

On pages 6 and 8, Mr. Donovan and Mr. Pitkin make mention of the fact that BSTLM requires a significant amount of time to process the state of Florida. We are aware of the speed issue and are constantly looking for ways to increase the granularity and accuracy of reported information while decreasing the model's run time and improving the response time of reporting. The new version of BSTLM has made major strides in this area. First, the new version's summary process has been reengineered so that the state of Florida can be processed in ONE run. This eliminates 3 of 6 runs that need to be processed. Second, the processing time for Florida has been reduced so that the entire state can now be run in well under 24 hours (machine dependent). Third, the reports from the system can now be obtained in a fraction of the time needed in Version 1.2.

Fourth, the process wizard has been improved to allow the user to set up all processing, all reports, and all CostCalculator files in one step. Finally, the interaction of the system with Excel has been modified to reduce the possibility of system shutdown that has been noted on a few machines.

Structure:

On page 30, Mr. Donovan and Mr. Pitkin state that they are prevented from developing structure costs within the BSTLM. In the original filing, the structure tables were hidden and the associated documentation was omitted. This was due to the fact that BellSouth applies in-plant factors in the CostCalculator to the material investment generated by BSTLM rather than using BSTLM to produce the structure costs. In recognition of the fact that other parties may want to have BSTLM produce the structure costs, the new version of BSTLM has all structure input tables turned on and the associated documentation added into the BSTLM Methodology Manual.

Drop Routing:

On pages 42 and 43, Mr. Donovan and Mr. Pitkin take issue with how the model routes the drop. They recommend that the drop be run from the corner of a lot at an angle to the geocoded customer position rather than the rectilinear approach used in Version 1.2 of BSTLM. In the new version of BSTLM, the user is now able to select the method used to route the drop. By selecting the appropriate value for the input, the drop is either run rectilinearly or at an angle from the corner of the lot¹. BellSouth chose to use the angled drop approach in the August 16th, 2000 filing.

¹ The maximum lot width must be specified as a new GIS Rule.

However, the impact of this change for Florida is not the 21.7 percent change postulated by Mr. Donovan and Mr. Pitkin. Their analysis is based on a DTBT being placed at a lot corner. In this situation, the angled drop change compared to the rectilinear distance will result in the highest percentage change compared to any other DTBT placements that may actually occur in the model. In reality, the model's approach to DTBT placements results in some DTs being placed directly in front of a customers location or some DTs being placed so that the drop route first must run in front of other customer lots. For these non-lot corner placed DTBTs, the percentage change will be less than what Mr. Donovan and Mr. Pitkin demonstrate. In fact, the realized impact of the drop routing change is minimal as it only changes costs by less than a penny a month.

Q. ON PAGE 7, MR. DONOVAN AND MR. PITKIN STATE THAT THE
INABILITY TO PRODUCE MAPS LIKE THOSE IN MY DIRECT TESTIMONY
IS A DISADVANTAGE IN REVIEWING BSTLM. CAN YOU COMMENT?

A.

BellSouth has provided to AT&T/MCI the MapInfo tables used to develop the charts presented in my direct testimony. These tables allow AT&T and MCI to not only produce the maps I used, but also lets AT&T and MCI view the results of the model for the entire wire center. In addition to these mapping tables, BSTLM has a "Tree" viewing capability. This auditing function allows the user to graphically depict the modeled network. While this is not as "pretty" as the MapInfo picture, it is a useful tool in understanding the network that has been designed. Further, the Audit Tree view is dynamic, allowing a user to review Node information such as equipment size, quantity and capacity demanded. This information can even be translated to the investment logic

1		allowing an interested party to determine the BSTLM investment for a specific element
2		within the modeled network.
3		
4	Q.	MR. DONOVAN AND MR. PITKIN RECOMMEND THAT "WORKAROUND"
5		TECHNIQUES BE USED TO CORRECT PERCEIVED SHORTCOMINGS IN
6		BSTLM. SPECIFICALLY THEY MENTION THE DLC VENDOR SELECTION
7		AND THE APPORTIONMENT OF FIBER AND DLC COSTS. SHOULD THE
8		"WORKAROUNDS" PROPOSED BY MR. DONOVAN AND MR. PITKIN BE
9		IMPLEMENTED?
10		
11	A.	No. First, I believe the new version of the model produces accurate estimates of
12		material costs for BellSouth UNE purposes. Second, I am concerned that some of the
13		changes Mr. Donovan and Mr. Pitkin recommend would introduce more bias than
14		exists in the claimed deficiencies that they are trying to correct. Let me cover the two
15		items discussed by Mr. Donovan and Mr. Pitkin.
16		
17		DLC Vendor Selection:
18		• While this is partially an input issue that is covered by Daonne Caldwell, it is
19		also a BSTLM modeling issue. The current DLC costing approach in BSTLM
20		uses a melded cost at each DLC location. While this approach does not reflect
21		the reality that a single vendor is typically used at each location, it does
22		represent the true proportion of vendor equipment installed in the state of
23		Florida.
24		Mr. Donovan's and Mr. Pitkin's proposed approach on the other hand, may be.

too simplistic and does not reflect the real proportion of vendor equipment

installed in Florida by BST, nor the engineering rationale beyond cost. Their approach ignores the fact that DLC vendor selection is not only a function of material cost, but also a function of installation costs, maintenance costs, and efficient deployment criteria. In addition to the problem of using a single vendor, the analysis of the two vendors' total DLC cost in Exhibit JCD/BFP 9 simplistically assumes that all DLC installations use 100% POTS cards and ignores the fact that there are many instances of Indoor DLC systems.

Allocation of Fixed costs

- I agree that any allocation of shared costs should be competitively neutral and fair, but it should also produce unbiased results. The DS0 approach to apportioning the Fiber and portions of the DLC is reasonable and no more "arbitrary" than the use of Service counts or copper pair counts. Indeed, it appears that Mr. Donovan and Mr. Pitkin agree that DS0 capacity is a valid approach to use to size the DLC systems. This seems to indicate that there is some cost causality between DS0 and required DLC equipment. Such cost causality indicates merit to apportioning costs by DS0s.
 - However, even assuming that service counts or pair counts were an appropriate allocation method, Mr. Donovan's and Mr. Pitkin's workaround is still unacceptable, particularly since they recognize (page 39) that their approach may underbuild the network. This introduction of a bias should be a major cause of concern.

To test their approach and determine if a true bias is introduced, I performed a comparison run of the new BSTLM (BST2000 scenario). One run was made

1	using the model as filed on August 16, 2000. A second run was made using Mr.
2	Donovan's and Mr. Pitkin's proposed DS0 equivalents contained in Exhibit
3	JCD/BFD 10. As correctly assumed by Mr. Donovan and Mr. Pitkin on page
4	39, the use of their proposed workaround did in fact underbuild the Florida
5	network by almost 3%. It should also be noted that the services listed by Mr.
6	Donovan and Mr. Pitkin in Exhibit JCD/BFD 10 represent less than 1% of the
7	services provisioned off of fiber fed DLC systems.

An underbuilding of the network by 3% seems an unreasonable bias for dealing with services that represent less than 1% of the services provisioned out of fiber fed DLC systems. Therefore, I would recommend that it is best to continue with the current BSTLM's use of DS0s to apportion the costs of Fiber and portions of the DLC equipment. The DS0 approach is fair, neutral, unbiased, and is supported by some amount of cost causality.

Q. MR. DONOVAN AND MR. PITKIN CONTEND THAT THE FACT THAT
SOURCE CODE HAS NOT BEEN OPENED UP FOR MODIFICATION MAKES
THIS SYSTEM UNREVIEWABLE AND HAVE CALLED IT A "PROTOTYPE"
SYSTEM. DO YOU AGREE?

A.

No. It is true that the source code has not been released in electronic format for other parties to modify. However, we have released the code in a document that parties could review and have been willing to entertain and implement suggested changes from other parties based upon such review. Finally, I would not characterize the model as a prototype. A prototype is typically a proof of concept model that is used in the

1		development of portions of complex models. This model is a complete platform that has
2		been tested, verified, and shown to work.
3		
4	Q.	MR. DONOVAN AND MR. PITKIN STATE ON PAGE 35 THAT "BECAUSE IT
5		IS SERVICE ORIENTED, RATHER THAN ELEMENT ORIENTED, THE
6		BSTLM MUST ALLOCATE THE SHARED EQUIPMENT INVESTMENT TO
7		THE INDIVIDUAL SERVICES THAT USE THE EQUIPMENT". IS THIS
8		CORRECT?
9		
10	A.	It is not clear what Mr. Donovan and Mr. Pitkin mean by this statement. Nor is
11		BellSouth clear as to any real implications this has for estimating costs. BSTLM is a
12		model that builds a network to services purchased by customers. BSTLM does look at
13		services and their impact on the network that needs to be constructed. In this regard,
14		BSTLM is different from proxy models that Mr. Donovan and Mr. Pitkin have previously
15		endorsed. The proxy models simplified the complex task of building a network to serve
16		the multitude of services that are actually demanded. However, I am not sure how the
17		BSTLM's approach would impact the allocation and definition of what is a shared
18		facility. If in the end, we are looking at a forward-looking approach to costs, BSTLM
19		simply builds up the costs of elements used by each service, which is the approach used
20		by proxy models elsewhere.
21		
22	Q.	MR. DONOVAN AND MR. PITKIN MAKE COMPARISONS OF THIS MODEL
23		TO THE BCPM AND HAI TO SUPPORT THE RATIONALE FOR THEIR
24		MUCH LOWER RESULTING UNE COSTS. IS THIS A VALID COMPARISON?

No. I recommend that Mr. Donovan's and Mr. Pitkin's comparison to the HAI and BCPM and their resulting conclusions be dismissed, since there are a number of issues that make their comparison of BSTLM to these proxy models invalid. First, the BCPM and HAI were designed as universal service models. In fact, the BCPM was never touted as a UNE model, contrary to the statement of Mr. Donovan and Mr. Pitkin on page 23 that "BCPM...estimates ...cost of providing UNEs". This is important in that a universal service model is based on a different set of assumptions. The most important of which is that the model reflect the cost of the most efficient potential provider in an area based upon publicly available inputs. By comparison, a UNE model is typically based upon as much actual data that represents the costs the incumbent carrier is expected to incur in providing service on a going forward basis. While the UNE and USF approaches may be similar, they can lead to differences in modeling and results. Second, the BCPM and HAI relied upon public sources of customers, wire centers, and inputs that do not reflect the actual network, practices, customers, and wire centers of BellSouth. Third, the networks built are based upon different engineering inputs, guidelines, and modeling approaches. For example, both the BCPM and HAI build to an abstraction of where customers may be. The BSTLM builds to the roads customers live on. In addition, the BCPM was based upon a maximum DLC size of approximately 1344 lines while the BSTLM uses a maximum design size of 2016. In addition, in their use of route distances, Mr. Donovan and Mr. Pitkin have compared

20

21

22

23

24

25

1

2

3

4

5

6

7

8

9

10

11

12

13

14

15

16

17

18

19

A.

apples to oranges. The BCPM and HAI do not break out the shared routing of Feeder and Distribution. Therefore, if 5 miles, for example, of route were shared between a distribution and feeder route, the BCPM and HAI would have reported this in both the distribution and feeder distances. On the other hand, the way the BSTLM route mileage

is reported by Mr. Donovan and Mr. Pitkin, this distance shows up in NEITHER the distribution nor feeder. Rather, it shows up as a shared route. If we restated Exhibit JCD/BFP 3 to reflect these differences, it would show the following:

			=
Equipment Type	ВСРМ	BSTLM	HAI
Distribution Route Miles	44,504	43,063	47,751
Feeder Route Miles	17,466	7,853	10,819
Total	61,970	50,916	58,570

From this restated table, we can see that the differences are not as great as represented by Mr. Donovan and Mr. Pitkin. As a final point, the models design the network differently. Customers are neatly laid out in the BCPM and HAI with drop conveniently running from the corner of a lot. The BSTLM places the distribution terminals more realistically to serve actual customer locations. This may mean that the models may define portions of the route as feeder, distribution or drop differently. When one considers that the BSTLM places over 50,000 miles of drop cable in addition to the route mileage of distribution and feeder, the classification of the route distance as either drop, distribution, or feeder could have a dramatic influence on any potential comparisons between the models.

Q. MR. DONOVAN AND MR. PITKIN MAKE NUMEROUS REFERENCES TO
BSTLM'S USE OF COST OPTIMIZATION. DOES THE MODEL OPTIMIZE
ROUTE COST OR ROUTE DISTANCE?

1	A.	The BSTLM minimizes total network component placements (D1B1s, DLCs) while
2		minimizing the route distance in between the components using the Minimum Spanning
3		Road Tree (MSRT). We believe that this approach will result in minimized cost.
4		However, the model does not minimize costs directly in the optimization. Part of the
5		confusion stems from the fact that there was unused variable in the model left from our
6		true "Prototyping". This variable "MinimizeTotDistFDICost" is not used in the model.
7		In the latest release, this variable has been removed from the inputs to eliminate any
8		confusion.
9		
10	Q.	ON PAGES 40-42 OF THEIR REBUTTAL, MR. DONOVAN AND MR. PITKIN
11		CLAIM THAT THE MODEL'S MSRT APPROACH MAY OVERSTATE THE
12		NETWORK FACILITIES. IS THIS TRUE?
13		
14	A.	No. In part, these claims may stem from the fact that the original documentation on the
15		MSRT was not clear. This section of the documentation has been rewritten as part of the
16		August 16 th , 2000 filing to provide a clearer overview of how the model constructs both
17		the feeder and distribution routes. We believe that the following explanation and the
18		improved documentation should clear up AT&T's and MCI's purported issue. In fact, as
19		explained below, the BSTLM's route distance is the minimum realistic route distance
20		needed to connect the distribution terminals within a CSA.
21		
22		BSTLM Usage of the MSRT for Cable Routing
23		The BSTLM uses the Minimum Spanning Road Tree (MSRT) to efficiently route
24		cable to the network elements of a wire center. This overview introduces an

important property of the MSRT and how that property is used to produce optimal cable routes for both Allocation Areas (AAs) and Carrier Serving Areas (CSAs).

The MSRT is analogous to the classic Minimum Spanning Tree (MST) with the exception that points must be connected using road segments. The points of the MSRT are optimally connected using the shortest length set of road-based paths. The strategy for each step of the MSRT algorithm is to connect the point that is closest to the *current* tree via a path along roads.

This strategy requires that a point be specified as the starting point, or *source node*, for the algorithm. When the BSTLM builds the MSRT for AA generation and the "big" MSRT for CSA generation, the source node is the location of the switch. The points that the algorithm connects to the switch are the Distribution Terminal (DT) locations established in an earlier process. It is important to note that the location of the source node plays a significant part in the resulting configuration of an MSRT. Using the algorithm to connect the same set of points to two different source nodes may produce two different MSRTs. The important aspect of this is that the points are optimally connected as a whole to the source node.

Every point in the MSRT has a path in the tree that can be followed back to the source node. A point's source path may course through other points in the MSRT. If the source path for point B goes through point A, then both points share the same path back to the source *starting* at point A. This produces a relationship between the two points:

- 2 or conver

- point B is *downline* from A, or *further* from the source following MSRT paths or conversely,
- point A is *upline* from B, or *closer* to the source following MSRT paths

There is an important property regarding the MSRT paths of points that are downline from another point. The sub-tree defined by paths of all downline points back to a common upline point is also an MSRT, having that common upline point as the source node. For example, points A, B and C are three of many points in an MSRT. If points B and C are downline from point A, then the paths from B and C back to A define a sub-tree that is the MSRT of A, B and C using A as the source node. The BSTLM takes advantage of this property during AA and CSA generation.

The BSTLM generates AAs by constructing the MSRT connecting all DTs that are close enough to the switch to be handled by copper alone (based on the user input for the design limit). The switch is used as the source node for building the MSRT. The model generates an AA by looking for a point in the original MSRT where the service demand of all downline DTs is close to but does not exceed the design limits for an AA. This point becomes the Allocation Area Node (AAN), a common node in the distribution network of an AA. The MSRT that connects the DTs to the AAN would define optimal cable routes for the AA. Since the DTs of the AA are all downline from the AAN, the sub-tree of paths from the original MSRT back to the AAN is the MSRT for the AA. Generating AAs with optimal cable routes is as simple as splitting up the original MSRT into AA-sized sub-trees.

Generating CSAs is almost as simple as generating AAs. The first step is to construct the MSRT connecting every DT in the wire center that did not get included in an AA. Once again, the switch is used as the source node for building the MSRT. To generate a CSA, the model starts with the DT that is furthest downline. The model follows this initial DT's path back to the switch until it finds the last point X where:

i. the service demand of all DTs downline from point X is not greater than
 the service capacity of a Digital Loop Carrier (DLC)

- ii. the number of extenders downline is not greater than a specified limit, where extenders are the customers of DTs with MSRT paths to point X that are longer than the design limit for copper distribution
- iii. there are no DTs downline with MSRT paths to point X that are longer than the hard limit for copper distribution

All DTs downline from X become members of the CSA. Point X is the furthest upline the DLC may be placed to serve these downline DTs. The service demand of the downline DTs is often lower than the capacity of a DLC. Therefore, the model looks upline from X for more DTs that may be included in the CSA. Upline DTs are added to the CSA as long as their MSRT paths to X do not exceed the design limit for copper and they do not add more service demands to the CSA than can be handled by the DLC. The DLC is then optimally placed along the path of the MSRT to the initial DT, but no further upline than point X.

1 The or	iginal MS
2 that is	the MSRT
3 origina	al MSRT p
4 CSA.	However,
5 to the	DLC locat
6 the MS	SRT of CS
7	
8 Q. MR. DONOV	AN AND
9 BSTLM (EX	HBIT JO
10 LEAD TO T I	HE EXCL
11	
12 A. Yes. While D	aonne Cal
13 and Mr. Pitkir	n, there are
14 Mr. Pitkin tha	t would re
These appear	to be the re
16 troublesome in	nput chang

19

20

21

22

23

The original MSRT paths for all DTs downline from the DLC define a sub-tree that is the MSRT for those DTs using the DLC as the source node. Therefore, the original MSRT paths for downline DTs are used as the optimal cable paths for the CSA. However, the MSRT paths of DTs upline may not be optimal with respect to the DLC location (new source node). The model recognizes this and rebuilds the MSRT of CSAs to upline DTs using the DLC location as the source node.

Q. MR. DONOVAN AND MR. PITKIN PROPOSE CERTAIN INPUT CHANGES TO BSTLM (EXHIBIT JCD/BFP-10). DO ANY OF THE PROPOSED CHANGES LEAD TO THE EXCLUSION OF RELEVANT INVESTMENTS?

- Yes. While Daonne Caldwell will cover the value of the inputs used by Mr. Donovan and Mr. Pitkin, there are several material input changes proposed by Mr. Donovan and Mr. Pitkin that would result in the omission of material costs for modeled equipment.

 These appear to be the result of model misunderstandings or input errors. The troublesome input changes are as follows:
 - It appears that FDIs of sizes 4800, 5400, and 7200 have had their material inputs levels effectively set to 0. Exhibit JCD/BFP-10, pages 3 and 4, list the new inputs as "#DIV/0!". This value would be treated the same as a 0 input level in the model.
 - It appears that a fiber cable size of 6 has had its material investment level effectively set to 0. Exhibit JCD/BFP-10, pages 4 and 5, list the new inputs as "#DIV/0!". This value would be treated the same as a 0 input level in the model.

It appears that all indoor FDI costs have been zeroed out. Exhibit JCD/BFP-10, 1 2 page 6, list all of the FDI primitive inputs as "-" or "0". These primitives are used 3 to develop the cost of the Indoor FDI equipment. This change also has an impact on DTBT material levels. Due to an error in 4 5 the previous version of BSTLM, the user-provided DTBT investment levels 6 did not flow to the Investment determination in the model. Instead, the model relied on the FDI primitives to build up the costs of the various DTBT sizes. 8 This did not cause major problems in the BellSouth initial filing results since the actual DTBT inputs were derived in the same manner. However, since the 9 10 new FDI primitives recommended by Mr. Donovan and Mr. Pitkin appear to be 0, the DTBT investments resulting from their model run would be close to, 11 12 if not, 0. It appears that the HDSL Modem and NIU material levels do not have material 13 amounts represented. Based on the notes in Exhibit JCD/BFP-10, pages 6, the 14 input of 17.04 represents only labor costs. 15 16 Q. MR. DONOVAN AND MR. PITKIN RECOMMEND THE USE OF BCPM INPUT 17 VALUES FOR CABLE, FDIs, AND SOME OTHER ITEMS APPROVED BY 18 THIS COMMISSION IN DOCKET NO. 980696-TP FOR USE IN BSTLM FOR 19 THIS PROCEEDING. PLEASE COMMENT ON THIS APPROACH BASED ON 20 YOUR EXPERIENCE WITH BOTH MODELS. 21

A. On page 31, Mr. Donovan and Mr. Pitkin recommend the use of BCPM inputs approved by the Commission in Docket No. 980696-TP. However, it is interesting that they chose only certain input values and failed to use other of the Commission approved input

22

23

24

25

values. As I mentioned previously, the BCPM was designed as a universal service model. Inputs were argued from the standpoint of developing the engineering practices and resulting costs of the most efficient provider in Florida. As such, numerous inputs developed and approved in Docket 980696-TP did not and still do not represent BellSouth in Florida. In addition, directly transferring inputs from a universal service cost model (BCPM) to an unbundled network element model (BSTLM), without consideration of the basis for the inputs, their inter-relationships and the engineering practices reflected by each unique model, should be avoided unless it is done carefully and thoughtfully with a realization of what the outputs are applicable to. This is particularly true since BSTLM was not designed to be directly compatible with the BCPM and both models were designed with a different set of assumptions. As noted by Daonne Caldwell, the best set of inputs for BSTLM in this proceeding are those that represent the most up to date values for BellSouth's engineering practices, technology choices, and actual material and installation costs.

22 .

However, even if one were to use the inputs from Docket No. 980696-TP, they need to be used in whole and ideally brought up to date. First, one must consider that the BCPM inputs advocated by Mr. Donovan and Mr. Pitkin are more than 2 years old. Second, one must also consider that Docket No. 980696-TP was considered and decided in whole. If the inputs are used in this proceeding, the BSTLM inputs should mirror as close as possible all approved inputs to the BCPM. This includes engineering rules, material inputs, and contractor costs. To use only piece parts of the inputs would be incorrect without fully reviewing each input and its inter-relationships with other input values. For example, in Mr. Donovan's and Mr. Pitkin's Exhibit JCD/BFP-10, it appears that there has been no input of the trenching cost associated with the BCPM cable inputs.

1		These BCPM trenching costs represent a very significant cost of the network and could
2		lead to a large understatement of the resulting UNE costs.
3		
4	Q.	WAS BELLSOUTH ABLE TO CONVERT OVER THE BCPM INPUT VALUES
5		APPROVED IN DOCKET NO. 980696-TP?
6		
7	A.	Yes. BellSouth made its best efforts of converting all of the inputs approved in Docket
8		No. 980696-TP to the BSTLM. In certain instances where BCPM inputs were not
9		available or too difficult to translate (DLC and SONET), BellSouth left BSTLM inputs as
10		is. For engineering rule decisions, BellSouth made BSTLM mimic these rules as best as
11		possible for this analysis. A complete set of changes between BellSouth's BST2000-Fl-
12		Ref scenario and this new "BCPM" scenario is listed in Exhibit JWS-2. Please note that
13		no attempt was made to bring these values up to date.
14		
15	Q.	WHAT ARE THE RESULTS OF THIS "BCPM" RUN IN COMPARISON TO
16		BELLSOUTH'S AUGUST 16 th , 2000 FILING AND MR. DONOVAN'S AND MR.
17		PITKIN'S RESULTS?
18		
19	A.	After carefully setting BSTLM inputs to values mimicking BCPM inputs, a run was made
20		and compared to the August 16 th , 2000 filed results. As one can see from the table
21		below, when considering the inputs of Docket No. 980696-TP as a whole in BSTLM, the
22		results filed on August 16th, 2000 are very reasonable. The new "BCPM" results do
23		bring into question the results of Mr. Donovan and Mr. Pitkin.

	Average Loop	
Run	Investment	Average Monthly Cost
August 16 th , 2000	\$852	\$18.04
Donovan/Pitkin	436²	7.42
BSTLM with BCPM loop inputs	832	16.81

Q. GIVEN MR. DONOVAN'S AND MR. PITKIN'S RESULTS AND THE RESULTS YOU PRESENT, HOW CAN THIS COMMISSION BE ASSURED AS TO WHICH RESULTS ARE REASONABLE?

A. I understand the great difference in numbers between Mr. Donovan's and Mr. Pitkin's and BellSouth's results may raise a few questions. However, it appears that BellSouth's August 16th, 2000 filed results are reasonable when compared with the results of BSTLM run with a complete set of the inputs adopted in Docket No. 980696-TP. In addition to this comparison above, BellSouth compared the total network investment developed by the filed BSTLM and Mr. Donovan's and Mr. Pitkin's BSTLM results against what is on BellSouth's books in Florida. While I recognize that the BSTLM is a forward-looking model, the booked investments can serve as a "sanity check" for the BSTLM filed results. As one can see from the table below, BellSouth's results filed on August 16th, 2000 and those results of BSTLM run with a complete set of BCPM inputs appear fairly reasonable to the booked amount. However, it seems unlikely that Mr. Donovan's and Mr. Pitkin's resulting investments are plausible. While I realize that the booked amount

² This value was estimated using Mr. Donovan's and Mr. Pitkin's inputs in the August 16th, 2000 version of the BSTLM. The BSTLM value was then converted to investment by using the BellSouth CostCalculator that was populated with BST inputs. As such, this estimate represents an upper bound of the actual Mr. Donovan and Mr. Pitkin value.

of plant presented is not made up of the local loop only, I would surmise that 75-85% of this plant is local loop. I am also aware that the material investment in A.1.1 is not 100% of the local loop. However, over 93% of the investment generated by BSTLM is represented by A.1.1.

	Total Plant in Circuit, Poles, Aerial Fiber	
	and Copper, Intrabuilding Fiber and	
	Copper, Underground Fiber and Copper,	
	Buried Fiber and Copper, and Conduit.	
Booked Amount Year End 1998	\$7,147 million	
August 16 th , 2000	\$5,189 million	
Donovan/Pitkin	\$2,639 million ³	
BSTLM with BCPM loop inputs	\$5,034 million	

7 Q. DOES THIS CONCLUDE YOUR REBUTTAL TESTIMONY?

9 A. Yes it does.

³ This value was estimated using Mr. Donovan's and Mr. Pitkin's inputs in the August 16th, 2000 version of the BSTLM. The BSTLM value was then converted to investment by using the BellSouth CostCalculator that was populated with BST inputs. As such, this estimate represents an upper bound of the actual Mr. Donovan and Mr. Pitkin value.

List of Acronyms

AA Allocation Area (area within certain distance of the central office served over copper

loop)

BCPM Benchmark Cost Proxy Model (universal service model)

BSTLM BellSouth Telecommunications Loop Model

BT Building Terminal

CABS Carrier Access Billing System

CO Central Office

CRIS Customer Records Information System

CSA Carrier Serving Area (that portion of a local loop extending from a digital loop carrier

site to the distribution area drop terminal)

DLC Digital Loop Carrier (includes equipment to translate signals from optical to electrical)

DS0 Digital Signal Zero (a measure of single channel equivalence)

DT Distribution Terminal

EFI Engineered Furnished and Installed

FDI Feeder Distribution Interface

GIS Geographic Information System

HAI Previously Hatfield & Associates Inc proxy model

HCPM Hybrid Cost Proxy Model (created by the FCC)

ID Identification

MST Minimum Spanning Tree (provides a theoretical minimum distance for any network

connecting points).

MSRT Minimum Spanning Road Tree (provides a practical minimum distance to connect

customers along a road network)

NID Network Interface Device

RLAC Regional Landbase Administration Center

Rservice Reporting Service

TELRIC Total Element Long-Run Incremental Cost

UNE Unbundled Network Element

USPS United States Postal Service

Aerial Structure [Ma Scenario	terial] PlantType	TypeSz		MtrlCost
BST2000-FI-Ref	Pales		25	215.14
BCPM	Pales		25	229.89
BST2000-FI-Ref	Poles		30	215.14
BCPM	Poles		30	229.89
BST2000-FI-Ref	Poles		35	215.14
BCPM	Poles		35	229.89
BST2000-FI-Ref	Poles		40	215.14
BCPM	Poles		40	229.89
BST2000-FI-Ref	Poles		45	215.14
BCPM	Poles		45	229.89
BST2000-FI-Ref	Poles		50	215.14
BCPM	Poles		50	229.89
BST2000-FI-Ref	Poles		55	215.14
BCPM	Poles		55	229.89
BST2000-FI-Ref	Poles		60	215.14
BCPM	Poles		60	229.89
BST2000-FI-Ref	Anchor	NA		26.62
BCPM	Anchor	NA		71.34
Copper Cable 24 ga Scenario	uge [Material] PlantType	TypeSz		MtrlCost
BST2000-FI-Ref	Aerial		25	0.32
BCPM	Aerial		25	2.28
BST2000-FI-Ref	Aerial		50	0.57
BCPM	Aerial		50	2.51
BST2000-FI-Ref	Aerial		100	0.74
BCPM	Aerial		100	2.97
BST2000-FI-Ref	Aeriał		200	1.25
BCPM	Aeriał		200	4.23
BST2000-FI-Ref	Aeriał		300	1.68
BCPM	Aeriał		300	4.8
BST2000-FI-Ref	Aeriał		400	2.26
BCPM	Aeriał		400	5.78
BST2000-FI-Ref	Aerial		600	3.38
BCPM	Aerial		600	7.63
BST2000-FI-Ref	Aerial		900	4.84
BCPM	Aerial		900	9.79
BST2000-FI-Ref BCPM	Aerial Aerial		1,200 1,200	
BST2000-FI-Ref BCPM	Aerial Aerial		1,500 1,500	
BST2000-FI-Ref BCPM	Aerial Aerial		1,800 1,800	
BST2000-FI-Ref BCPM	Aerial Aerial		2,100 2,100	
BST2000-FI-Ref BCPM	Aerial Aerial		2,400 2,400	
BST2000-FI-Ref BCPM	Aerial Aerial		2,700 2,700	
BST2000-FI-Ref BCPM	Aerial Aerial		3,000 3,000	
BST2000-FI-Ref BCPM	Aerial Aerial		3,600 3,600	
BST2000-FI-Ref	Aerial		4,200	23.94

BCPM	Aerial	4,200	45.14
BST2000-FI-Ref	Buried	25	0.23
BCPM	Buried	25	2.27
BST2000-FI-Ref	Buried	50	0.38
BCPM	Buried	50	2.55
BST2000-FI-Ref	Buried	100	0.67
BCPM	Buried	100	3.07
BST2000-FI-Ref	Buried	200	1.24
BCPM	Buried	200	4.51
BST2000-FI-Ref	Buried	300	1,91
BCPM	Buried	300	5.27
BST2000-FI-Ref	Buried	400	2.37
BCPM	Buried	400	6.3
BST2000-FI-Ref	Buried	600	3.42
BCPM	Buried	600	7.55
BST2000-FI-Ref	Buried	900	5.04
BCPM	Buried	900	10.24
BST2000-FI-Ref	Buried	1,200	6.74
BCPM	Buried	1,200	11.46
BST2000-Fi-Ref	Buried	1,500	8.44
BCPM	Buried	1,500	15.43
BST2000-FI-Ref	Buried	1,800	10.04
BCPM	Buried	1,800	19.83
BST2000-FI-Ref	Buried	2,100	11.76
BCPM	Buried	2,100	23.18
BST2000-FI-Ref	Buried	2,400	13.44
BCPM	Buried	2,400	26.18
BST2000-FI-Ref	Buried	2,700	15.12
BCPM	Buried	2,700	31.58
BST2000-FI-Ref	Buried	3,000	16.8
BCPM	Buried	3,000	37.45
BST2000-FI-Ref	Buried	3,600	20.16
BCPM	Buried	3,600	43.21
BST2000-FI-Ref	Buried	4,200	23.52
BCPM	Buried	4,200	53.39
BST2000-FI-Ref	Riser/Intrabuilding	25	0.36
BCPM	Riser/Intrabuilding	25	2.28
BST2000-FI-Ref	Riser/Intrabuilding	50	0.54
BCPM	Riser/Intrabuilding	50	2.51
BST2000-FI-Ref	Riser/Intrabuilding	100	0.9 8
BCPM	Riser/Intrabuilding	100	2.97
BST2000-FI-Ref	Riser/Intrabuilding	200	1.63
BCPM	Riser/Intrabuilding	200	4.23
BST2000-FI-Ref	Riser/Intrabuilding	300	2.5
BCPM	Riser/Intrabuilding	300	4.8
BST2000-FI-Ref	Riser/Intrabuilding	400	3.2
BCPM	Riser/Intrabuilding	400	5.78
BST2000-Fi-Ref	Riser/Intrabuilding	600	4.42
BCPM	Riser/Intrabuilding	600	7.63
BST2000-Fi-Ref	Riser/Intrabuilding	900	6.65
BCPM	Riser/Intrabuilding	900	9.79
BST2000-FI-Ref	Riser/intrabuilding	1,200	8.57
BCPM	Riser/Intrabuilding	1,200	10.89
BST2000-FI-Ref	Riser/Intrabuilding	1,500	10.75
BCPM	Riser/Intrabuilding	1,500	14.17
BST2000-FI-Ref	Riser/Intrabuilding	1,800	13.14

всрм	Riser/Intrabuilding	1,800	17.68
BST2000-FI-Ref	Riser/Intrabuilding	2,100	15.33
BCPM	Riser/Intrabuilding	2,100	20.47
BST2000-FI-Ref	Riser/Intrabuilding	2,400	17.52
BCPM	Riser/Intrabuilding	2,400	22.82
BST2000-FI-Ref	Riser/Intrabuilding	2,700	19.71
BCPM	Riser/Intrabuilding	2,700	27.25
BST2000-FI-Ref	Riser/Intrabuilding	3,000	21.9
BCPM	Riser/Intrabuilding	3,000	32.03
BST2000-FI-Ref	Riser/Intrabuilding	3,600	26.28
BCPM	Riser/Intrabuilding	3,600	36.81
BST2000-Fi-Ref	Riser/Intrabuilding	4,200	30.66
BCPM	Riser/Intrabuilding	4,200	45.14
BST2000-FI-Ref	Underground	25	0.13
BCPM	Underground	25	3.23
BST2000-FI-Ref	Underground	50	0.27
BCPM	Underground	50	3.51
BST2000-FI-Ref	Underground	100	0.53
BCPM	Underground	100	4.03
BST2000-FI-Ref	Underground	200	1.06
BCPM	Underground	200	5.47
BST2000-FI-Ref	Underground	300	1.59
BCPM	Underground	300	7.1
BST2000-FI-Ref	Underground	400	2.12
BCPM	Underground	400	8.51
BST2000-FI-Ref	Underground	600	3.33
BCPM	Underground	600	8.95
BST2000-FI-Ref	Underground	900	
BCPM	Underground	900	
BST2000-FI-Ref	Underground	1,200	
BCPM	Underground	1,200	
BST2000-FI-Ref	Underground	1,500	
BCPM	Underground	1,500	
BST2000-FI-Ref	Underground	1,800	
BCPM	Underground	1,800	
BST2000-FI-Ref	Underground	2,100	
BCPM	Underground	2,100	
BST2000-FI-Ref	Underground	2,400	
BCPM	Underground	2,400	
BST2000-FI-Ref	Underground	2,700	
BCPM	Underground	2,700	
BST2000-FI-Ref BCPM	Underground Underground	3,000 3,000	
BST2000-FI-Ref	Underground	3,600	
BCPM	Underground	3,600	
BST2000-FI-Ref	Underground	4,200	
BCPM	Underground	4,200	
Copper Cable 26 Scenario	gauge [Material] PlantType	TypeSz	MtrlCost
BST2000-FI-Ref	Aerial	25	
BCPM	Aerial	25	
BST2000-FI-Ref	Aerial	50	
BCPM	Aerial	50	
BST2000-FI-Ref	Aeriał	100	
BCPM	Aerial	100	

BST2000-Fi-Ref	Aerial	200	0.98
BCPM	Aerial	200	3.87
BST2000-FI-Ref	Aerial	300	1.38
BCPM	Aerial	300	4.27
BST2000-FI-Ref	Aerial	400	1.72
BCPM	Aerial	400	5.07
BST2000-FI-Ref	Aerial	600	2.53
BCPM	Aerial	600	6.55
BST2000-FI-Ref	Aerial	900	3.81
BCPM	Aerial	900	8.18
BST2000-FI-Ref	Aerial	1,200	4.99
BCPM	Aerial	1,200	8.75
BST2000-FI-Ref	Aerial	1,500	6.41
BCPM	Aerial	1,500	11.5
BST2000-FI-Ref	Aerial	1,800	7.8 3
BCPM	Aerial	1,800	14.47
BST2000-FI-Ref	Aerial	2,100	9.59
BCPM	Aerial	2,100	16.72
BST2000-FI-Ref	Aerial	2,400	10.8
BCPM	Aerial	2,400	18.54
BST2000-FI-Ref	Aerial	2,700	12.42
BCPM	Aerial	2,700	24.84
BST2000-FI-Ref	Aerial	3,000	13.5
BCPM	Aerial	3,000	32.03
BST2000-FI-Ref	Aerial	3,600	16.2
BCPM	Aerial	3,600	36.81
BST2000-FI-Ref	Aerial	4,200	18.9
BCPM	Aerial	4,200	45.14
BST2000-FI-Ref	Buried	25	0.18
BCPM	Buried	25	2.22
BST2000-FI-Ref	Buried	50	0.31
BCPM	Buried	50	2.44
BST2000-FI-Ref	Buried	100	0.51
BCPM	Buried	100	2.85
BST2000-FI-Ref	Buried	200	0.87
BCPM	Buried	200	4.07
BST2000-FI-Ref	Buried	300	1.28
BCPM	Buried	300	4.61
BST2000-FI-Ref	Buried	400	
BCPM	Buried	400	
BST2000-FI-Ref	Buried	600	2.5 4
BCPM	Buried	600	6.21
BST2000-FI-Ref	Buried	900	3.88
BCPM	Buried		8.24
BST2000-FI-Ref	Buried	1,200	
BCPM	Buried	1,200	
BST2000-FI-Ref	Buried	1,500	
BCPM	Buried	1,500	
BST2000-FI-Ref	Buried	1,800	7.28
BCPM	Buried	1,800	15.83
BST2000-FI-Ref	Buried	2,100	
BCPM	Buried	2,100	
BST2000-FI-Ref	Buried	2,400	
BCPM	Buried	2,400	
BST2000-FI-Ref	Buried	2,700	
BCPM	Buried	2,700	

BST2000-Fi-Ref	Buried	3,000	12.69
BCPM	Buried	3,000	37.45
BST2000-FI-Ref	Buried	3,600	15.12
BCPM	Buried	3,600	43.21
BST2000-FI-Ref	Buried	4,200	17.64
BCPM	Buried	4,200	53.39
BST2000-FI-Ref	Riser/Intrabuilding	25	0.31
BCPM	Riser/Intrabuilding	25	2.23
BST2000-FI-Ref	Riser/Intrabuilding	50	0.39
BCPM	Riser/Intrabuilding	50	2.42
BST2000-FI-Ref	Riser/Intrabuilding	100	0.61
BCPM	Riser/Intrabuilding	100	2.79
BST2000-FI-Ref	Riser/Intrabuilding	200	0.98
BCPM	Riser/Intrabuilding	200	3.87
BST2000-FI-Ref	Riser/Intrabuilding	300	1.38
BCPM	Riser/Intrabuilding	300	4.27
BST2000-FI-Ref	Riser/Intrabuilding	400	1.72
BCPM	Riser/Intrabuilding	400	5.07
BST2000-FI-Ref	Riser/Intrabuilding	600	3.64
BCPM	Riser/Intrabuilding	600	6.55
BST2000-FI-Ref	Riser/Intrabuilding	900	3.81
BCPM	Riser/Intrabuilding	900	8.18
BST2000-FI-Ref	Riser/Intrabuilding	1,200	4.99
BCPM	Riser/Intrabuilding	1,200	8.75
BST2000-FI-Ref	Riser/Intrabuilding	1,500	6.41
BCPM	Riser/Intrabuilding	1,500	11.5
BST2000-FI-Ref	Riser/Intrabuilding	1,800	10.19
BCPM	Riser/Intrabuilding	1,800	14.47
BST2000-FI-Ref	Riser/Intrabuilding	2,100	9.59
BCPM	Riser/Intrabuilding	2,100	16.72
BST2000-FI-Ref	Riser/Intrabuilding	2,400	13.78
BCPM	Riser/Intrabuilding	2,400	18.54
BST2000-FI-Ref	Riser/Intrabuilding	2,700	15.94
BCPM	Riser/Intrabuilding	2,700	24.84
BST2000-FI-Ref	Riser/Intrabuilding	3,000	16.98
BCPM	Riser/Intrabuilding	3,000	32.03
BST2000-FI-Ref	Riser/Intrabuilding	3,600	20.38
BCPM	Riser/Intrabuilding	3,600	36.81
BST2000-FI-Ref	Riser/Intrabuilding	4,200	23.1
BCPM	Riser/Intrabuilding	4,200	45.14
BST2000-FI-Ref	Underground	25	0.1
BCPM	Underground	25	3.18
BST2000-FI-Ref	Underground .	50	0.2
BCPM	Underground	50	3.4
BST2000-FI-Ref	Underground	100	0.4
BCPM	Underground	100	3.82
BST2000-FI-Ref	Underground	200	0.8
BCPM	Underground	200	5.06
BST2000-Fi-Ref	Underground	300	1.2
BCPM	Underground	300	6.48
BST2000-FI-Ref	Underground	400	1.6
BCPM	Underground	400	7.69
BST2000-FI-Ref	Underground	600	2.59
BCPM	Underground	600	7.7
BST2000-FI-Ref	Underground	900	3.9
BCPM	Underground	900	10.51

BeilSouth Telecommunications, Inc. FPSC Docket No. 990649-TP Rebuttal Exhibit JWS-2 August 21, 2000

BST2000-FI-Ref BCPM	Underground Underground		1,200 1,200	4.54 11.71
BST2000-FI-Ref BCPM	Underground Underground		1,500 1,500	6 15.67
BST2000-FI-Ref BCPM	Underground Underground		1,800 1,800	7.09 20.05
BST2000-FI-Ref BCPM	Underground Underground		2,100 2,100	8.49 23.32
BST2000-FI-Ref BCPM	Underground Underground		2,400 2,400	8.97 26.53
BST2000-FI-Ref BCPM	Underground Underground		2,700 2,700	10.0 6 34.57
BST2000-FI-Ref BCPM	Underground Underground		3,000 3,000	11.34 43.65
BST2000-FI-Ref BCPM	Underground Underground		3,600 3,600	13.49 50.61
BST2000-FI-Ref BCPM	Underground Underground		4,200 4,200	18.74 61.69
Drop [Material] Scenario	PlantType	TypeSz		MtriCost
BST2000-FI-Ref BCPM	Aerial Aerial		2 2	0.0679 0.299
BST2000-FI-Ref BCPM	Aerial Aerial		6 6	0.1111 0.299
BST2000-FI-Ref BCPM	Buried Buried		2 2	0.0691 0.69
BST2000-FI-Ref	Buried		5	0.1511
ВСРМ	Buried		5	0.69
BCPM			5	0.69
		TypeSz	5	0.69
BCPM DTBT Material [Ma	aterial] A518	TypeSz	25 25	
DTBT Material [Ma Scenario BST2000-FI-Ref	aterial] A518 PlantType Aerial	TypeSz	25	MtriCost 0 288 0
BCPM DTBT Material [Ma Scenario BST2000-FI-Ref BCPM BST2000-FI-Ref BCPM BST2000-FI-Ref BCPM	aterial] A518 PlantType Aerial Aerial Aerial	TypeSz	25 25 50	MtriCost 0 288 0
BCPM DTBT Material [Ma Scenario BST2000-FI-Ref BCPM BST2000-FI-Ref BCPM BST2000-FI-Ref	aterial] A518 PlantType Aerial Aerial Aerial Aerial	TypeSz	25 25 50 50	Mtr/Cost 0 288 0 486.16 327.6
BCPM DTBT Material [Material [Material]] BST2000-FI-Ref BCPM BST2000-FI-Ref BCPM BST2000-FI-Ref BCPM BST2000-FI-Ref	Aerial	TypeSz	25 25 50 50 100 100	MtrlCost 0 288 0 486.16 327.6 885.46 646.33 1684.04
BCPM DTBT Material [Material [Material]] BST2000-FI-Ref BCPM BST2000-FI-Ref BCPM BST2000-FI-Ref BCPM BST2000-FI-Ref BCPM BST2000-FI-Ref	Aerial	TypeSz	25 25 50 50 100 100 200 200	MtrlCost 0 288 0 486.16 327.6 885.46 646.33 1684.04 973.93 2482.63
BCPM DTBT Material [Material [Material] Material [Material] Material [Material] Material] Material [Material] Material] Mater	Aerial	TypeSz	25 25 50 50 100 100 200 200 300 300	Mtr/Cost 0 288 0 486.16 327.6 885.46 646.33 1684.04 973.93 2482.63 1292.66 3281.22 1938.99
BCPM DTBT Material [Material [Mater	Aerial	TypeSz	25 25 50 50 100 100 200 200 300 400 400 600	Mtr/Cost 0 288 0 486.16 327.6 885.46 646.33 1684.04 973.93 2482.63 1292.66 3281.22 1938.99 4878.39 2912.92
BCPM DTBT Material [Mi Scenario BST2000-FI-Ref BCPM	Aerial	TypeSz	25 25 50 50 100 100 200 200 300 300 400 400 600 600	Mtr/Cost 0 288 0 486.16 327.6 885.46 646.33 1684.04 973.93 2482.63 1292.66 3281.22 1938.99 4878.39 2912.92 7274.15
BCPM DTBT Material [Material [Mater	Aerial Buried Buried	TypeSz	25 25 50 50 100 100 200 200 300 300 400 400 600 900 900	MtrlCost 0 288 0 486.16 327.6 885.46 646.33 1684.04 973.93 2482.63 1292.66 3281.22 1938.99 4878.39 2912.92 7274.15 0 220
BCPM DTBT Material [Material [Mater	Aerial	TypeSz	25 25 50 50 100 100 200 300 300 400 400 600 900 900 900	MtrlCost 0 288 0 486.16 327.6 885.46 646.33 1684.04 973.93 2482.63 1292.66 3281.22 1938.99 4878.39 2912.92 7274.15 0 220 0 356.01 327.6
BCPM DTBT Material [Material [Mater	Aerial Buried Buried Buried Buried Buried	TypeSz	25 25 50 50 100 100 200 200 300 400 400 600 600 900 900 25 25 50 50	Mtr/Cost 0 288 0 486.16 327.6 885.46 646.33 1684.04 973.93 2482.63 1292.66 3281.22 1938.99 4878.39 2912.92 7274.15 0 220 0 356.01 327.6 629.87 646.33

BCPM	Buried		300	1725.27
BST2000-FI-Ref BCPM	Buried Buried		400 400	1292.66 2272.98
BST2000-FI-Ref BCPM	Buried Buried		600 600	1938.99 3368.38
BST2000-FI-Ref BCPM	Buried Buried		900 900	2912.92 5011.49
FDI Terminals [Mate	rial]			
Scenario	PlantType	TypeSz		MtrlCost
BST2000-FI-Ref BCPM	Aerial Aerial		50 50	0 949.04
BST2000-FI-Ref BCPM	Aerial Aerial		100 100	139.52 1197.67
BST2000-FI-Ref BCPM	Aerial Aerial		200 200	279.04 1371.59
BST2000-Fi-Ref BCPM	Aerial Aerial		300 300	418.56 1590.54
BST2000-FI-Ref BCPM	Aerial Aerial		400 400	796.96 1794.08
BST2000-FI-Ref	Aerial Aerial		600 600	1061.11 2447.66
BST2000-Fi-Ref	Aerial Aerial		900	1429.52 3361.55
BST2000-FI-Ref	Aerial		1,000	1489.8
BCPM BST2000-FI-Ref	Aerial Aerial		1,000	1735.67
BCPM	Aerial		1,200	4039.73
BST2000-FI-Ref BCPM	Aerial Aerial		1,400 1,400	1953.28 4587.48
BST2000-FI-Ref BCPM	Aerial Aerial		1,500 1,500	2048.43 4915.16
BST2000-FI-Ref BCPM	Aerial Aerial		1,800 1,800	2240.25 5736.78
BST2000-FI-Ref BCPM	Aerial Aerial		2,100 2,100	2929.92 6684.45
BST2000-FI-Ref BCPM	Aerial Aerial		2,400 2,400	3348.48 7110.22
BST2000-FI-Ref BCPM	Aerial Aerial		2,700 2,700	
BST2000-Fi-Ref	Aerial Aerial		3,000 3,000	4185.6
BST2000-Fi-Ref	Aerial		3,300 3,300	4604.16
BCPM 	Aerial Aerial		3,600	
BCPM	Aerial		3,600	10348.31
BST2000-FI-Ref BCPM	Aerial Aerial		4,200 4,200	12073.03
BST2000-Fi-Ref BCPM	Aerial Aerial		4,800 4,800	6696.96 12020.68
BST2000-FI-Ref BCPM	Aerial Aerial		5,400 5,400	
BST2000-FI-Ref BCPM	Aerial Aerial		7,200 7,200	
BST2000-FI-Ref BCPM	Buried Buried		50 50	

BST2000-FI-Ref	Buried	100	150.09
BCPM	Buried	100	1197.67
BST2000-FI-Ref	Buried	200	300.18
BCPM	Buried	200	1371.59
BST2000-FI-Ref	Buried	300	450.27
BCPM	Buried	300	1590.54
BST2000-FI-Ref	Buried	400	976.38
BCPM	Buried	400	1794.08
BST2000-FI-Ref	Buried	600	1567.55
BCPM	Buried	600	2447,66
BST2000-FI-Ref	Buried	900	1758.38
BCPM	Buried	900	3361.55
BST2000-FI-Ref	Buried	1,000	1328.36
BCPM	Buried	1,000	3550.75
BST2000-FI-Ref	Buried	1,200	2135.97
BCPM	Buried	1,200	4039.73
BST2000-FI-Ref	Buried	1,400	2101.26
BCPM	Buried	1,400	4587.48
BST2000-FI-Ref	Buried	1,500	2263.17
BCPM	Buried	1,500	4915.16
BST2000-FI-Ref	Buried	1,800	2921.51
BCPM	Buried	1,800	5736.78
BST2000-FI-Ref	Buried	2,100	3221.89
BCPM	Buried	2,100	6684.45
BST2000-FI-Ref	Buried	2,400	3367.71
BCPM	Buried	2,400	7110.22
BST2000-FI-Ref	Buried	2,700	3929.32
BCPM	Buried	2,700	7880.11
BST2000-FI-Ref	Buried	3,000	4047.41
BCPM	Buried	3,000	8623.59
BST2000-FI-Ref	Buried	3,300	3841.3
BCPM	Buried	3,300	9485.95
BST2000-FI-Ref	Buried	3,600	5243.07
BCPM	Buried	3,600	10348.31
BST2000-FI-Ref	Buried	4,200	7862.27
BCPM	Buried	4,200	12073.03
BST2000-FI-Ref	Buried	4,800	6558.79
BCPM	Buried	4,800	11792.26
BST2000-FI-Ref	Buried	5,400	7212
	Buried	5,400	12966.69
BST2000-FI-Ref	Buried	7,200	10806.48
BCPM	Buried	7,200	19429.33
BST2000-FI-Ref	Underground	50	0
	Underground	50	949.04
BST2000-FI-Ref	Underground	100	0
	Underground	100	1197.67
BST2000-FI-Ref	Underground	200	0
BCPM	Underground	200	1371.59
BST2000-FI-Ref	Underground	300	0
BCPM	Underground	300	1590.54
BST2000-FI-Ref	Underground	400	0
BCPM	Underground	400	1794.08
BST2000-FI-Ref	Underground	600	0
BCPM	Underground	600	2447.66
BST2000-FI-Ref	Underground	900	0
BCPM	Underground	900	3361.55

BST2000-FI-Ref BCPM	Underground Underground		1,000 1,000	0 3550.75
BST2000-FI-Ref BCPM	Underground Underground		1,200 1,200	0 4039.73
BST2000-FI-Ref BCPM	Underground Underground		1,400 1,400	0 4587.48
BST2000-FI-Ref BCPM	Underground Underground		1,500 1,500	0 4915.16
BST2000-FI-Ref BCPM	Underground Underground		1,800 1,800	0 5736.78
BST2000-FI-Ref BCPM	Underground Underground		2,100 2,100	0 6684.45
BST2000-FI-Ref BCPM	Underground Underground		2,400 2,400	0 7110.22
BST2000-FI-Ref BCPM	Underground Underground		2,700 2,700	0 7880.11
BST2000-FI-Ref BCPM	Underground Underground		3,000 3,000	0 8623.59
BST2000-FI-Ref BCPM	Underground Underground		3,300 3,300	0 9485.95
BST2000-FI-Ref BCPM	Underground Underground		3,600 3,600	0 10348.31
BST2000-FI-Ref BCPM	Underground Underground		4,200 4,200	0 12073.03
BST2000-FI-Ref BCPM	Underground Underground		4,800 4,800	0 11792.26
BST2000-FI-Ref BCPM	Underground Underground		5,400 5,400	0 12969.69
BST2000-FI-Ref	Underground		7,200	0
BCPM	Underground		7,200	19429.33
BCPM Fiber Cable [Material	Underground	TvneSz		
BCPM Fiber Cable [Material Scenario	Underground] PlantType	TypeSz	7,200	MtrlCost
BCPM Fiber Cable [Material	Underground	TypeSz		
BCPM Fiber Cable [Material Scenario BST2000-Fi-Ref	Underground PlantType Aerial	TypeSz	7,200	MtrlCost 0.44
BCPM Fiber Cable [Material Scenario BST2000-FI-Ref BCPM	Underground PlantType Aerial Aerial	TypeSz	7,200 6 6 12	MtrlCost 0.44 2.35 0.53
BCPM Fiber Cable [Material Scenario BST2000-Fi-Ref BCPM BST2000-Fi-Ref BCPM BST2000-Fi-Ref	Underground PlantType Aerial Aerial Aerial Aerial Aerial	TypeSz	7,200 6 6 6 12 12	0.44 2.35 0.53 2.83 0.64
Fiber Cable [Material Scenario BST2000-FI-Ref BCPM BST2000-FI-Ref BCPM BST2000-FI-Ref BCPM BST2000-FI-Ref BST2000-FI-Ref	Underground PlantType Aerial Aerial Aerial Aerial Aerial Aerial	TypeSz	7,200 6 6 12 12 18 18	MtriCost 0.44 2.35 0.53 2.83 0.64 3.03 0.72
BCPM Fiber Cable [Material Scenario BST2000-FI-Ref BCPM BST2000-FI-Ref BCPM BST2000-FI-Ref BCPM BST2000-FI-Ref BCPM BST2000-FI-Ref BCPM	Underground PlantType Aerial Aerial Aerial Aerial Aerial Aerial Aerial Aerial Aerial	TypeSz	7,200 6 6 6 12 12 18 18 24 24	MtriCost 0.44 2.35 0.53 2.83 0.64 3.03 0.72 3.22 0.84
BCPM Fiber Cable [Material Scenario BST2000-Fi-Ref BCPM	Underground PlantType Aerial	TypeSz	7,200 6 6 6 12 12 18 18 24 24 24 30 30 30	MtriCost 0.44 2.35 0.53 2.83 0.64 3.03 0.72 3.22 0.84 3.55 0.88
BCPM Fiber Cable [Material Scenario BST2000-Fi-Ref BCPM BST2000-Fi-Ref	Underground PlantType Aerial	TypeSz	7,200 6 6 6 6 12 12 18 18 18 24 24 30 30 32 32 32	MtriCost 0.44 2.35 0.53 2.83 0.64 3.03 0.72 3.22 0.84 3.55 0.88 3.79 0.91
BCPM Fiber Cable [Material Scenario BST2000-FI-Ref BCPM BST2000-FI-Ref	PlantType Aerial	TypeSz	7,200 6 6 6 6 12 12 18 18 24 24 24 30 30 32 32 36 36 36	MtriCost 0.44 2.35 0.53 2.83 0.64 3.03 0.72 3.22 0.84 3.55 0.88 3.79 0.91 3.7 1.08
BCPM Fiber Cable [Material Scenario BST2000-FI-Ref BCPM BST2000-FI-Ref	Underground PlantType Aerial Aerial Aerial	TypeSz	7,200 6 6 6 6 12 12 18 18 24 24 30 30 32 32 36 36 36 44 44	MtriCost 0.44 2.35 0.53 2.83 0.64 3.03 0.72 3.22 0.84 3.55 0.88 3.79 0.91 3.7 1.08 4.16 1.22
BCPM Fiber Cable [Material Scenario BST2000-Fi-Ref BCPM	Underground PlantType Aerial	TypeSz	7,200 6 6 6 8 12 12 18 18 24 24 30 30 32 32 36 36 44 44 48 48 60	MtriCost 0.44 2.35 0.53 2.83 0.64 3.03 0.72 3.22 0.84 3.55 0.88 3.79 0.91 3.7 1.08 4.16 1.22 4.15 1.35
BCPM Fiber Cable [Material Scenario BST2000-Fi-Ref BCPM BST2000-Fi-Ref	PlantType Aerial	TypeSz	7,200 6 6 6 6 12 12 18 18 18 24 24 30 30 32 32 32 36 36 44 44 48 48 60 60 72	MtriCost 0.44 2.35 0.53 2.83 0.64 3.03 0.72 3.22 0.84 3.55 0.88 3.79 0.91 3.7 1.08 4.16 1.22 4.15 1.35 4.68 1.58

BST2000-FI-Ref	Aerial	96	1.93
BCPM	Aerial	96	5.96
BST2000-FI-Ref	Aerial	108	2.15
BCPM	Aerial	108	6.29
BST2000-FI-Ref	Aerial	120	2.36
BCPM	Aerial	120	6.98
BST2000-FI-Ref	Aerial	132	2.56
BCPM	Aerial	132	7.68
BST2000-FI-Ref	Aerial	144	2.77
BCPM	Aerial	144	7.82
BST2000-FI-Ref	Aerial	156	2. 96
BCPM	Aerial	156	8
BST2000-FI-Ref	Aerial	168	3.16
BCPM	Aerial	168	8.62
BST2000-FI-Ref	Aerial	216	3.97
BCPM	Aerial	218	11.08
BST2000-FI-Ref	Buried	6	0.44
BCPM	Buried	6	2.35
BST2000-FI-Ref	Buried	12	0.53
BCPM	Buried	12	2.68
BST2000-FI-Ref	Buried	18	0.64
BCPM	Buried	18	2.9
BST2000-FI-Ref	Buried	24	0.72
BCPM	Buried	24	3.06
BST2000-FI-Ref	Buried	30	0.84
BCPM	Buried	30	3.34
BST2000-FI-Ref	Buried	32	0.88
	Buried	32	3.56
BST2000-FI-Ref	Buried	36	0.91
BCPM	Buried	36	3.42
BST2000-FI-Ref	Buried	44	1.08
BCPM	Buried	44	3.96
BST2000-FI-Ref	Buried	48	1.22
BCPM	Buried	48	4.07
BST2000-FI-Ref	Buried	60	1.35
BCPM	Buried	60	4.64
BST2000-FI-Ref	Buried	72	1.58
BCPM	Buried	72	5.16
BST2000-FI-Ref	Buried	84	1.75
BCPM	Buried	84	5.74
BST2000-FI-Ref	Buried	96	1.93
BCPM	Buried	96	6.23
BST2000-FI-Ref	Buried	108	2.15
BCPM	Buried	108	6.61
BST2000-FI-Ref	Buried	120	2.36
BCPM	Buried	120	7.34
BST2000-FI-Ref	Buried	132	2.56
BCPM	Buried	132	8.08
BST2000-FI-Ref	Buried	144	2.77
BCPM	Buried	144	8.28
BST2000-FI-Ref	Buried	156	2. 96
BCPM	Buried	158	8.35
BST2000-FI-Ref	Buried	168	3.16
BCPM	Buried	168	8.99
BST2000-FI-Ref	Buried	216	3.97
BCPM	Buried	216	11.56

BST2000-FI-Ref	Riser/Intrabuilding	6	0.57
BCPM	Riser/Intrabuilding	6	2.35
BST2000-FI-Ref	Riser/Intrabuilding	12	1.14
BCPM	Riser/Intrabuilding	12	2.83
BST2000-FI-Ref	Riser/Intrabuilding	18	1.19
BCPM	Riser/Intrabuilding	18	3.03
BST2000-Fi-Ref	Riser/intrabuilding	24	1.59
BCPM	Riser/intrabuilding	24	3.22
BST2000-FI-Ref	Riser/intrabuilding	30	1.66
BCPM	Riser/intrabuilding	30	3.55
BST2000-FI-Ref	Riser/intrabuilding	32	1.77
BCPM	Riser/intrabuilding	32	3.79
BST2000-FI-Ref	Riser/Intrabuilding	36	1.99
BCPM	Riser/Intrabuilding	36	3.7
BST2000-FI-Ref	Riser/Intrabuilding	44	2.43
BCPM	Riser/Intrabuilding	44	4.16
BST2000-FI-Ref	Riser/Intrabuilding	48	2.68
BCPM	Riser/Intrabuilding	48	4.15
BST2000-FI-Ref	Riser/Intrabuilding	60	3.35
BCPM	Riser/Intrabuilding	60	4.68
BST2000-FI-Ref	Riser/Intrabuilding	72	3.63
BCPM	Riser/Intrabuilding	72	5.33
BST2000-FI-Ref	Riser/Intrabuilding	84	4.84
BCPM	Riser/Intrabuilding	84	5.72
BST2000-FI-Ref	Riser/Intrabuilding	96	5.45
BCPM	Riser/Intrabuilding	96	5.96
BST2000-FI-Ref	Riser/Intrabuilding	108	6.05
BCPM	Riser/Intrabuilding	108	6.29
BST2000-FI-Ref	Riser/Intrabuilding	120	6.66
BCPM	Riser/Intrabuilding	120	6.98
BST2000-Fi-Ref	Riser/Intrabuilding	132	7. 26
BCPM	Riser/Intrabuilding	132	7.68
BST2000-FI-Ref	Riser/Intrabuilding	144	8.5
BCPM	Riser/Intrabuilding	144	7.82
BST2000-FI-Ref	Riser/Intrabuilding	15 6	9.92
BCPM	Riser/Intrabuilding	15 6	8
BST2000-FI-Ref	Riser/Intrabuilding	168	12.75
	Riser/Intrabuilding	168	8.62
BST2000-FI-Ref	Riser/Intrabuilding	216	21.87
BCPM	Riser/Intrabuilding	216	11.08
BST2000-FI-Ref	Underground	6	0.44
BCPM	Underground	6	2.35
BST2000-FI-Ref	Underground	12	0.53
BCPM	Underground	12	4.23
BST2000-FI-Ref	Underground	18	0.64
BCPM	Underground	18	4.43
BST2000-FI-Ref	Underground	24	0.72
BCPM	Underground	24	4.58
BST2000-FI-Ref	Underground	30	0.84
BCPM	Underground	30	4.91
BST2000-FI-Ref	Underground	32	0.88
BCPM	Underground	32	5.24
BST2000-FI-Ref	Underground	36	0.91
BCPM	Underground	36	4.91
BST2000-FI-Ref	Underground	44	1.08
BCPM	Underground	44	5.53

BST2000-FI-Ref	Underground	48	1.22	
BCPM	Underground	48	5.51	
BST2000-FI-Ref	Underground	60	1.35	
BCPM	Underground	60	6.07	
BST2000-FI-Ref	Underground	72	1.58	
BCPM	Underground	72	6.55	
BST2000-FI-Ref	Underground	84	1.75	
BCPM	Underground	84	7.11	
BST2000-FI-Ref	Underground	96	1.93	
BCPM	Underground	96	7.51	
BST2000-FI-Ref	Underground	108	2.15	
BCPM	Underground	108	7.75	
BST2000-FI-Ref	Underground	120	2.36	
BCPM	Underground	120	8.61	
BST2000-FI-Ref	Underground	132	2.56	
BCPM	Underground	132	9.48	
BST2000-FI-Ref	Underground	144	2.77	
BCPM	Underground	144	9.41	
BST2000-FI-Ref	Underground	156	2.96	
BCPM	Underground	156	9.16	
BST2000-FI-Ref	Underground	168	3.16	
BCPM	Underground	168	9.87	
BST2000-FI-Ref	Underground	216	3.97	
BCPM	Underground	216	12.69	
Indoor FDI Terminal Scenario	s Primitives [Material] PlantType	Туре	Item Capacity M	ftriCost
BST2000-FI-Ref	Indoor FDI Terminals	FDI66Connector		5.46
BCPM	Indoor FDI Terminals	FDI66Connector		8.71
BST2000-FI-Ref	Indoor FDI Terminals	FDIBackboard	Backboard 200	8.87
	Indoor FDI Terminals	FDIBackboard	Backboard 200	14.15
BST2000-FI-Ref	Indoor FDI Terminals	FDI189Protector		307.81
BCPM	Indoor FDI Terminals	FDI189Protector		490.96
NID/NIU (Material) Scenario	PlantType	TypeSz	MtrlCost	
BST2000-FI-Ref BCPM	HDSLModem HDSLModem	1	144.34 50	
BST2000-FI-Ref BCPM	NID NID	2 2	14.52 30	
BST2000-FI-Ref	NID	6	18.0 6	
BCPM	NID	6	50	
BST2000-FI-Ref BCPM	NIDIntandProt NIDIntandProt	1	7.83 0	
BST2000-FI-Ref BCPM	NIU NIU	1	169.85 50	
Underground Materi Scenario	al [Material] Structure	item	TypeSz MtrlCost	
BST2000-FI-Ref		00.000.400	1 0	
BCPM	Manholes Manholes	SB 30'x12" SB 30'x12"	1 475.82	
ВСРМ				
BST2000-FI-Ref BCPM	Manholes Manholes	SB 30"x12" HH 3x5 or 4x6	1 475.82 2 0	

BST2000-FI-Ref	Duct	1-PTS-77-4"	CU	0
BCPM	Duct	1-PTS-77-4"	CU	0.91
BST2000-FI-Ref BCPM	Duct Duct	1-4" w/3 in-Du 1-4" w/3 in-Du	FO FO	0 0.91
Labor Rate [Labor R Scenario	ates And Loadings] Type	RatePerHr	LaborRate	
BST2000-FI-Ref BCPM	Placing Placing	29		Plant Direct Labor Costs per Hour Plant Direct Labor Costs per Hour
Aerial Contract Labo Scenario	or [Contract Labor] PlantType	TypeSz	ContractLb 1	TelcoInspe District
BST2000-FI-Ref BCPM	Poles Poles	25 25	138.9297 161.81	0
BST2000-FI-Ref BCPM	Poles Poles	30 30	138.9297 161.81	0
BST2000-FI-Ref BCPM	Poles Poles	35 35	138.9297 161.81	o o
BST2000-FI-Ref BCPM	Poles Poles	40 40	138.9297 161.81	0
BST2000-FI-Ref BCPM	Poles Poles	45 45	138.9297 161.81	o o
BST2000-FI-Ref BCPM	Pales Pales	50 50	138.9297 161.81	0 0
BST2000-FI-Ref BCPM	Poles Poles	55 55	138.9297 161.81	o o
BST2000-FI-Ref BCPM	Poles Poles	60 60	138.9297 161.81	o o
BST2000-FI-Ref BCPM	Anchor Anchor	NA NA	61.3249 180.56	0 0
ВСРМ	Anchor Labor [Contract Labor]		180.56	0
BCPM Excavation Contract	Anchor	NA	180.56	0
Excavation Contract Scenario BST2000-FI-Ref	Anchor Labor [Contract Labor] ExcvActivity Backhoe Trench	NA ContractLbrCost	180.56 ContractLb	0
Excavation Contract Scenario BST2000-FI-Ref BCPM BST2000-FI-Ref	Anchor Labor [Contract Labor] ExcvActivity Backhoe Trench Backhoe Trench Bore Cable	ContractLbrCost 2.89	180.56 ContractLb	0
Excavation Contract Scenario BST2000-FI-Ref BCPM BST2000-FI-Ref BCPM BST2000-FI-Ref	Anchor Labor [Contract Labor] ExcvActivity Backhoe Trench Backhoe Trench Bore Cable Bore Cable Cut & Restore Asphalt	ContractLbrCost 2.89 22.17	180.56 ContractLb 7.05 50.89	0
Excavation Contract Scenario BST2000-FI-Ref BCPM BST2000-FI-Ref BCPM BST2000-FI-Ref BCPM BST2000-FI-Ref BCPM	Anchor Labor [Contract Labor] ExcvActivity Backhoe Trench Backhoe Trench Bore Cable Bore Cable Cut & Restore Asphalt Cut & Restore Asphalt Cut & Restore Concrete	ContractLbrCost	180.56 ContractLb 1 7.05 50.89 10.35	0
Excavation Contract Scenario BST2000-FI-Ref BCPM BST2000-FI-Ref BCPM BST2000-FI-Ref BCPM BST2000-FI-Ref BCPM BST2000-FI-Ref	Anchor Labor [Contract Labor] ExcvActivity Backhoe Trench Backhoe Trench Bore Cable Bore Cable Cut & Restore Asphalt Cut & Restore Asphalt Cut & Restore Concrete Cut & Restore Concrete Cut & Restore Sod	ContractLbrCost	180.56 ContractLb -7.05 -50.89 -10.35 -12.40	0
Excavation Contract Scenario BST2000-FI-Ref BCPM BST2000-FI-Ref BCPM BST2000-FI-Ref BCPM BST2000-FI-Ref BCPM BST2000-FI-Ref BCPM BST2000-FI-Ref BCPM BST2000-FI-Ref	Anchor Labor [Contract Labor] ExcvActivity Backhoe Trench Backhoe Trench Bore Cable Bore Cable Cut & Restore Asphalt Cut & Restore Asphalt Cut & Restore Concrete Cut & Restore Concrete Cut & Restore Sod Cut & Restore Sod Free Trench (i.e. Developer)	ContractLbrCost 2.89 22.17 5.67 8.40 4.53	180.56 ContractLb 7.05 50.89 - 10.35 - 12.40 - 7.81	0
Excavation Contract Scenario BST2000-FI-Ref BCPM BST2000-FI-Ref BCPM BST2000-FI-Ref BCPM BST2000-FI-Ref BCPM BST2000-FI-Ref BCPM BST2000-FI-Ref BCPM BST2000-FI-Ref BCPM	Anchor Labor [Contract Labor] ExcvActivity Backhoe Trench Backhoe Trench Bore Cable Bore Cable Cut & Restore Asphalt Cut & Restore Asphalt Cut & Restore Concrete Cut & Restore Concrete Cut & Restore Sod Cut & Restore Sod Free Trench (i.e. Developer) Free Trench (i.e. Developer) Hand Dig Trench	ContractLbrCost 2.89 22.17 5.67 . 8.40	180.56 ContractLb 7.05 - 50.89 - 10.35 - 12.40 - 7.81 - 7.05	0
Excavation Contract Scenario BST2000-FI-Ref BCPM	Anchor Labor [Contract Labor] ExcvActivity Backhoe Trench Backhoe Trench Bore Cable Bore Cable Cut & Restore Asphalt Cut & Restore Asphalt Cut & Restore Concrete Cut & Restore Concrete Cut & Restore Sod Cut & Restore Sod Free Trench (i.e. Developer) Free Trench (i.e. Developer) Hand Dig Trench Hand Dig Trench Plow	ContractLbrCost 2.89 22.17 5.67 4.53 2.89	180.56 ContractLb 7.05 50.89 10.35 12.40 7.81 7.05	0
Excavation Contract Scenario BST2000-FI-Ref BCPM	Anchor Labor [Contract Labor] ExcvActivity Backhoe Trench Backhoe Trench Bore Cable Bore Cable Cut & Restore Asphalt Cut & Restore Asphalt Cut & Restore Concrete Cut & Restore Concrete Cut & Restore Sod Cut & Restore Sod Free Trench (i.e. Developer) Free Trench (i.e. Developer) Hand Dig Trench Hand Dig Trench Plow Plow Push Pipe & Pull Cable	ContractLbrCost 2.89 22.17 5.67 8.40 4.53 2.89	180.56 ContractLb 1 7.05 50.89 10.35 12.40 7.81 7.05 - 7.05	0
Excavation Contract Scenario BST2000-FI-Ref BCPM	Anchor Labor [Contract Labor] ExcvActivity Backhoe Trench Backhoe Trench Bore Cable Bore Cable Cut & Restore Asphalt Cut & Restore Asphalt Cut & Restore Concrete Cut & Restore Concrete Cut & Restore Sod Cut & Restore Sod Free Trench (i.e. Developer) Free Trench (i.e. Developer) Hand Dig Trench Hand Dig Trench Hand Dig Trench Plow Plow Push Pipe & Pull Cable Push Pipe & Pull Cable Rocky Plow	ContractLbrCost 2.89 22.17 5.67 8.40 4.53 2.89 2.89 2.89	180.56 ContractLb 1 7.05 50.89 10.35 12.40 7.81 7.05 - 7.05	0
Excavation Contract Scenario BST2000-FI-Ref BCPM BST2000-FI-Ref BCPM	Anchor Labor [Contract Labor] ExcvActivity Backhoe Trench Backhoe Trench Bore Cable Bore Cable Cut & Restore Asphalt Cut & Restore Asphalt Cut & Restore Concrete Cut & Restore Concrete Cut & Restore Sod Cut & Restore Sod Free Trench (i.e. Developer) Free Trench (i.e. Developer) Hand Dig Trench Hand Dig Trench Hand Dig Trench Plow Plow Push Pipe & Pull Cable Push Pipe & Pull Cable Rocky Plow Rocky Plow Rocky Trench	ContractLbrCost 2.89 22.17 5.87 . 8.40 . 4.53 2.89 . 2.89 . 2.89	180.56 ContractLb 7.05	0

Underground Contr Scenario	act Labor [Contract Labor] Structure	TypeSz	Contract	tLb District			
BST2000-Fi-Ref BCPM	Manholes Manholes	:		0 65			
BST2000-FI-Ref BCPM	Manholes Manholes		2 2 43 7	0 7.3			
Service Description Scenario	i [Lookup Tables] SvcType	Svc	SvcCate	ego Preferre	edM ExtendedR PairEquiv	DSOEquiv SvcCla	ss ChannelUnClustered
BST2000-FI-Ref BCPM	a a	LOCAL POTS/F		CU	14800 12000		POTS Yes
BST2000-FI-Ref BCPM	b b	PBX PBX	NSW NSW	CU	14800 1 12000 1		PBX Yes
BST2000-FI-Ref BCPM	c c	CENTREX CENTREX	NSW NSW	CU	14800 1 12000 1		CENTREX Yes CENTREX Yes
BST2000-FI-Ref BCPM	d d	COIN SMART L		CU	14800 1 12000 1		COIN Yes
8ST2000-FI-Ref	E	2WVG USL FE	EDNSW	CU	14800 1	1 1 Bus	POTS Yes
BCPM BST2000-FI-Ref	E e	2WVG USL FEI	R NSW	CU	14800 1	1 1 Bus	POTS Yes COIN Yes
BCPM BST2000-FI-Ref	е Н	COIN REGULAR		CU	12000 1 14800 1		COIN Yes POTS No
BCPM BST2000-FI-Ref	H	2WVG U LOCA SLV ANALOG 2		CU	12000 1 14800 1		POTS No
BCPM	j	SLV ANALOG 2	WNSW	CU	12000 1	1 Bus	POTS Yes
BST2000-FI-Ref BCPM	a a	UCL 2W UCL 2W	NSW NSW	CU	14800 1 12000 1		NSW-VGS Yes NSW-VGS Yes
Orop Placing Hours Scenario	[Splicing And Placing Hours]	Placing	Travel				
BST2000-FI-Ref BCPM	AerialCU AerialCU	:	1.039	92 0			
BST2000-FI-Ref BCPM	BuriedCU BuriedCU		1.421	1 6 0			
BST2000-FI-Ref BCPM	NIDCU NIDCU	:	0.2	2 5 0			
Aerial Structure Sp	acing [Engineering Rules]						
Scenario	PlantType	Size	Spacing	50			
BST2000-FI-Ref BCPM	Poles Poles	25 25	17				
BST2000-FI-Ref BCPM	Poles Poles	30 30	17	75			
BST2000-FI-Ref BCPM	Poles Poles	50 50		00 75			
BST2000-FI-Ref BCPM	Poles Poles	55 55		00 75			
BST2000-Fi-Ref BCPM	Poles Poles	60 60		00 75			
Excavation Cost De Scenario	ensity Adjustment (Engineering f PlantType	Rules] DensityGrp	AdjFctr				
BST2000-FI-Ref BCPM	Buri ed Buri ed	Rural Rural		0			
BST2000-FI-Ref BCPM	Underground Underground	Rural Rural		0			

				_							-
BST2000-Fi-Ref BCPM	Buried Buried	Suburban Suburban	-								
BST2000-FI-Ref BCPM	Underground Underground	Suburban Suburban	1								
BST2000-FI-Ref BCPM	Buried Buried	Urban Urban	1								
BST2000-Fi-Ref BCPM	Underground Underground	Urban Urban	1								
GIS Rules (Enginee Scenario	ering Rules] Rule	Value	UOM								
BST2000-FI-Ref BCPM	AALineDesignLimit AALineDesignLimit		Lines Lines								
BST2000-FI-Ref BCPM	DLCLengthHardLimit DLCLengthHardLimit	18,000 15,000									
BST2000-FI-Ref BCPM	DLCLineDesignLimit DLCLineDesignLimit	•	Lines Lines								
BST2000-FI-Ref BCPM	DTBTHHDesignLimit DTBTHHDesignLimit		нн нн								
BST2000-Fi-Ref BCPM	FDILineDesignLimit FDILineDesignLimit		Lines Lines								
BST2000-FI-Ref BCPM	MaxDropLen MaxDropLen	700 500	Feet Feet								
Network Rules [Eng Scenario	gineering Rules] Rule	Value	UOM								
BST2000-FI-Ref BCPM	AA24/26GaugeXover AA24/26GaugeXover	12,000 11,100									
BST2000-FI-Ref BCPM	CSA24/26GaugeXover CSA24/26GaugeXover	9,000 11,100									
BST2000-FI-Ref BCPM	MinimumPairsPerBusiness MinimumPairsPerBusiness		Pairs Pairs								
Outside Contractor Scenario	Use [Engineering Rules] NtwkSheet	UseContractor									
BST2000-FI-Ref BCPM	Conduit Conduit	N Y									
BST2000-FI-Ref BCPM	Manhole Manhole	N Y									
BST2000-FI-Ref BCPM	Trench Trench	N Y									
Plant Mix [Engineer Scenario	ing Rules] DensityLowerRange	DensityUpperRa	n DensityGr	p CostFamilyWat	terTableBed	rockDeTerrainDif	ffi CLLI	PctAer	PctBur	PctUG (OrderOfPro
BST2000-FI-Ref BCPM	0		Rural	Dist Dist	1000 1000	1000 * 1000 Normal	•	0.25 0.4	0.75 0.6	0	2 2
BST2000-FI-Ref BCPM	0	100,000,000 100		Dist Dist	1000 1000	1000 * 1000 Normal	•	0.15 0.37	0.85 0.61	0 0.02	3 3
BST2000-FI-Ref BCPM	0 100			Dist Dist	1000 1000	1000 * 1000 Normai	•	0.05 0.33	0.95 0.62	0 0.05	4 4
BST2000-FI-Ref BCPM	0 200	100,000,0 00 650		Fdr Dist	1000 1000	1000 ° 1000 Normal	•	0.25 0.3	0.75 0.62	0 0.08	5 5
BST2000-FI-Ref BCPM	0 650	100,000,000 850		Fdr Dist	1000 1000	1000 * 1000 Normal	•	0.15 0.2	0.5 0.65	0.35 0.15	6 6
BST2000-FI-Ref BCPM	0 850	100,000,000 2,550		Fdr Dist	1000 1000	1000 * 1000 Normai	•	0 0.1	0.25 0.65	0.75 0.25	7 7
BST2000-FI-Ref BCPM	0 2550	100,000,000 5,000		• Dist	15 1000	15 ° 1000 Normal	•	1 0.05	0 0.55	0 0.4	8 8

BST2000-FI-Ref	5000	10.000		1000	1000 *	• 0	o	•	•
BCPM	5000	10,000	Díst	1000	1000 Normal	* 0.05	0.35	0.6	9
BST2000-FI-Ref BCPM	0 10000	100,000,000		1000 1000	1000 ° 1000 Normai	ARCHFLM 8.86E-02 • 0	0.904902 0.1	6.54E-03 0.9	10 10
BST2000-FI-Ref BCPM	0 5	100,000,000		1000 1000	1000 * 1000 Softrock	BCRTFLBT 6.09E-02 * 0.37	0.718852 0.61	0.220242 0.02	11 11
BST2000-F1-Ref BCPM	0 100	100,000,000 1		1000 1000	1000 * 1000 Softrock	BCRTFLMA 0.16508 * 0.33	0.588953 0.62	0.245966 0.05	12 12
BST2000-FI-Ref BCPM	0 200	100,000,000 ° 650 °		1000 1000	1000 * 1000 Softrock	BCRTFLSA 4.62E-02 * 0.3	0.792619 0.62	0.161222 0.08	13 13
BST2000-FI-Ref BCPM	0 650	100,000,000		1000 1 <i>0</i> 00	1000 * 1000 Softrock	BGPIFLMA 0.805222 • 0.2	7.86E-02 0.65	0.116184 0.15	14 14
BST2000-FI-Ref BCPM	0 850	100,000,000 • 2,550 •		1000 1000	1000 ° 1000 Softrock	BKVLFLJF 0.118981 * 0.1	0.847649 0.65	3.34E-02 0.25	15 15
BST2000-FI-Ref BCPM	0 2550	100,000,000		1000 1000	1000 ° 1000 Softrock	BLDWFLM 0.24333 • 0.05	0.749097 0.55	7.57E-03 0.4	16 16
BST2000-FI-Ref BCPM	0 5000	100,000,000		1000 1000	1000 * 1000 Softrock	BLGLFLMA 0.298757 * 0.05	0.659723 0.35	4.15E-02 0.6	17 17
BST2000-FI-Ref BCPM	0 10000	100,000,000		1000 1000	1000 * 1000 Softrock	BNNLFLMA 5.17E-02 • 0	0.941812 0.1	6.50E-03 0.9	18 18
BST2000-Fi-Ref BCPM	0	100,000,000		1000 1000	1000 * 1000 Saftrock	BRSNFLMA 0.09632 • 0.4	0.897401 0.6	6.28E-03 0	19 19
BST2000-FI-Ref BCPM	0	100,000,000 • 5 •		1000 1000	1000 * 1000 Hardrock	BYBHFLMA 0.16786 • 0.5	0.680268 0.5	0.1518 72 0	20 20
BST2000-FI-Ref BCPM	0 5	100,000,000 •		1000 1000	1000 ° 1000 Hardrock	CCBHFLM 0.133174 * 0.47	0.469333 0.51	0.397493 0.02	21 21
BST2000-FI-Ref BCPM	0 100	100,000,000		1000 1000	1000 ° 1000 Hardrock	CDKYFLMA 7.86E-02 * 0.43	0.91116 0.52	1.02E-02 0.05	22 22
BST2000-FI-Ref	0 200	100,000,000 * 650 *		1000 1000	1000 * 1000 Hardrock	CFLDFLMA 0.117578 • 0.4	0.872434 0.52	9.99E-03 0.08	23 23
BST2000-FI-Ref BCPM	0 650	100,000,000 ° 850 °		1000 1000	1000 ° 1000 Hardrock	CHPLFLJA 0.165305 • 0.25	0.797861 0.6	3.68E-02 0.15	24 24
BST2000-FI-Ref BCPM	0 850	100,000,000 * 2,550 *		1000 1000	1000 * 1000 Hardrock	CNTMFLLE 0.365209 * 0.2	0.606297 0.62	2.85E-02 0.18	25 25
BST2000-FI-Ref BCPM	0 2550	100,000,000 • 5,000 •		1000 1000	1000 ° 1000 Hardrock	COCOFLM 0.275184 • 0.15	0. 605687 0.65	0.11913 0.2	26 26
BST2000-FI-Ref BCPM	0 5000	100,000,000 * 10,000 *		1000 1000	1000 * 1000 Hardrock	COCOFLM 0.273241 * 0.15	0.617521 0.4	0.109238 0.45	27 27
BST2000-FI-Ref BCPM	<i>0</i> 10 000	100,000,000 *		1000 1000	1000 * 1000 Hardrock	CSCYFLBA 0.124294 • 0.1	0.8679 7 5 0	7.73E-03 0.9	28 28
BST2000-FI-Ref BCPM	0	100,000,000 * 5 *		1000 1000	1000 * 1000 Normal	DBRYFLDL 5.55E-02 * 0.4	0.904788 0.5	3.97E-02 0.1	29 29
BST2000-FI-Ref BCPM	0 5	100,000,000 * 100 *		1000 1000	1000 ° 1000 Normal	DBRYFLMA 0.101284 * 0.4	0.848604 0.45	0.050113 0.15	30 30
BST2000-FI-Ref BCPM	0 100	100,000,000 * 200 *		1000 1000	1000 ° 1000 Normal	DELDFLMA 0.143387 * 0.4	0.76024 0.4	9.64E-02 0.2	31 31
BST2000-FI-Ref BCPM	0 200	100,000,000 • 650 •		1000 1000	1000 * 1000 Normal	DLBHFLKP 0.149334 * 0.4	0.7195 84 0.35	0.131082 0.25	32 32
BST2000-Fi-Ref BCPM	0 650	100,000,000 * 850 *		1000 1000	1000 * 1000 Normal	DLBHFLMA 0.240112 * 0.25	0.473271 0.3	0.286617 0.45	33 33
BST2000-FI-Ref BCPM	0 850	100,000,000 ° 2,550 °		1000 1000	1000 ° 1000 Normal	DLSPFLMA 0.113924 * 0.1	0.885079 0.25	9.97E-04 0.65	34 34
BST2000-FI-Ref BCPM	0 2550	100,000,000 • 5,000 •		1000 1000	1000 * 1000 Normal	DNLNFLW 3.19E-02 • 0	0.954028 0.2	1.40E-02 0.8	35 35
BST2000-FI-Ref BCPM	0 5000	100,000,000 • 10,000 •		1000 1000	1000 * 1000 Normal	DRBHFLM 0.157337	0.623342 0.1	0.219322	36 36

BST2000-FI-Ref BCPM		0 10000	100,000,000 100,000,000		1000 1000	1000 * 1000 Normai	DYBHFLFN 0.142406 • 0	0.653826 0.05	0.203768 0.95	37 37
BST2000-Fi-Ref BCPM		0	100,000,000		1000 1000	1000 * 1000 Softrock	DYBHFLMA 0.204282 • 0.4	0.56 449 1 0.5	0.231227 0.1	38 38
BST2000-FI-Ref BCPM		0 5	100,000,000 100		1000 1000	1000 * 1000 Softrock	DYBHFLOB 0.120489 • 0.4	0.778166 0.45	0.101345 0.15	39 39
BST2000-FI-Ref BCPM		0 100	100,000,000 200		1000 1000	1000 ° 1000 Softrock	DYBHFLOS 0.307441 • 0.4	0.474863 0.4	0.217696 0.2	40 40
BST2000-FI-Ref BCPM		0 200	100,000,000 650		1000 1000	1000 * 1000 Softrock	DYBHFLPO 8.89E-02 • 0.4	0.756177 0.35	0.154915 0.25	41 41
BST2000-FI-Ref BCPM		0 650	100,000,000 850		1000 1000	1000 ° 1000 Softrock	EGLLFLBG 0.16607 • 0.25	0.698229 0.3	0.135701 0.45	42 42
BST2000-FI-Ref BCPM		0 850	100,000,000 2,550		1000 1000	1000 ° 1000 Softrock	EGLLFLIHD 0.212618 • 0.1	0.584092 0.25	0.20329 0.65	43 43
BST2000-FI-Ref BCPM		0 2550	100,000,000 5,000		1000 1000	1000 * 1000 Softrock	EORNFLM 0.357638 • 0	0.623186 0.2	1.92E-02 0.8	44 44
BST2000-Fi-Ref BCPM		0 5000	100,000,000 10,000		1000 1000	1000 * 1000 Softrock	FLBHFLMA 8.48E-02	0.888644 0.1	2,65E-02 0.9	45 45
BST2000-FI-Ref BCPM		0 10 000	100,000,000 100,000,000		1000 1000	1000 ° 1000 Softrock	FRBHFLFP 0.174905 • 0	0.742607 0.05	0.08 2489 0.95	46 46
BST2000-FI-Ref BCPM		0 0	100,000,000 5		1000 1000	1000 ° 1000 Hardrock		0.963883 0.45	3.76E-03 0.05	47 47
BST2000-FI-Ref BCPM		0 5	100,000,000 1 <i>0</i> 0		1000 1000	1000 ° 1000 Hardrock	FTLDFLAP 7.65E-02 • 0.5	0.328585 0.4	0.594938 0.1	48 48
BST2000-FI-Ref BCPM		0 100	100,000,000 200		1000 1000	1000 ° 1000 Hardrock	FTLDFLCR 0.401337 • 0.5	0.194668 0.35	0.403995 0.15	49 49
BST2000-FI-Ref BCPM		0 200	100,000,000 650		1000 1000	1000 ° 1000 Hardrock	FTLDFLCY 0.335384 • 0.5	0.236767 0.25	0.427849 0.25	50 50
BST2000-Fi-Ref BCPM		0 650	100,000,000 850		1000 1000	1000 ° 1000 Hardrock	FTLDFLJAD0.124152 • 0.4	0.64616 0.25	0.229687 0.35	51 51
BST2000-FI-Ref BCPM		0 850	100,000,000 2,550		1000 1000	1000 * 1000 Hardrock	FTLDFLMR 0.315023 0.2	0.237898 0.2	0.447079 0.6	52 52
BST2000-FI-Ref BCPM		0 2550	100,000,000 5,000		1000 1000	1000 * 1000 Hardrock	FTLDFLOA 0.19707 * 0.1	0.539016 0.1	0.263913 0.8	53 53
BST2000-FI-Ref BCPM		0 5000	100,000,000 10,000		1000 1000	1000 * 1000 Hardrock	FTLDFLPL 0.357551 • 0.1	0.35581 0.05	0.28 6639 0.85	54 54
BST2000-FI-Ref BCPM		0 10000	100,000,000 100,000,000		1000 1000	1000 * 1000 Hardrock	FTLDFLSG 5.32E-02 * 0.05	0.515759 0	0.43108 0.95	55 55
BST2000-FI-Ref BCPM	No More Data	0	100,000,000	• •	1000	1000 *	FTLDFLSU 7.93E-02	0.7607	0.159994	56
BST2000-FI-Ref BCPM	No More Data	0	100,000,000	• •	1000	1000 *	FTLDFLWN 4.92E-02	0.742362	0.208434	57
BST2000-FI-Ref BCPM	No More Data	0	100,000,000	• •	1000	1000 *	FTPRFLMA 0.306625	0.547511	0.145863	58
BST2000-FI-Ref BCPM	No More Data	0	100,000,000	• •	1000	1000 *	GCSPFLCN 0.19871	0.762419	3.89E-02	59
BST2000-FI-Ref BCPM	No More Data	0	100,000,000	• •	1000	1000 *	GCVLFLMA 0.127741	0.862888	9.37E-03	60
BST2000-FI-Ref BCPM	No More Data	0	100,000,000	• •	1000	1000 *	GENVFLM 0.199755	0,7981	2.14E-03	61
BST2000-FI-Ref BCPM	No More Data	0	100,000,000	• •	1000	1000 *	GLBRFLMC0.157537			62
BST2000-FI-Ref BCPM	No More Data	0	100,000,000	• •	1000	1000 *	GSVLFLMA 0.12537	0.659176	0.215453	63
BST2000-FI-Ref BCPM	No More Data	0	100,000,000	• •	1000	1000 *	GSVLFLNW5.44E-02	0.814955	0.130631	64

BST2000-FI-Ref BCPM	No More Data	0	100,000,000 *	•	1000	1000 *	HAVNFLMA0.185114 0.799697 1.52E-02	65
BST2000-FI-Ref BCPM	No More Data	0	100,000,000 *	•	1000	1000 *	HBSDFLMA0.189797 0.695615 0.114589	66
BST2000-FI-Ref BCPM	No More Data	0	100,000,000 *	•	1000	1000 *	HLNVFLMA 0.329866 0.664047 6.09E-03	67
BST2000-FI-Ref BCPM	No More Data	0	100,000,000 *	•	1000	1000 *	HLWDFLH 0.258025 0.352357 0.389618	68
BST2000-FI-Ref BCPM	No More Data	0	100,000,000 *	•	1000	1000 •	HLWDFLM 0.330191 0.268425 0.401384	69
BST2000-FI-Ref BCPM	No More Data	0	100,000,000 *	•	1000	1000 •	HLWDFLP 0.151466 0.705851 0.142683	70
BST2000-FI-Ref BCPM	No More Data	0	100,000,000 *	•	1000	1000 *	HLWDFLW 0.323797	71
BST2000-FI-Ref BCPM	No More Data	0	100,000,000 *	•	1000	1000 *	HMSTFLAF 0.150576 0.866262 0.183161	72
BST2000-FI-Ref BCPM	No More Data	0	100,000,000 *	•	1000	1000 •	HMSTFLEA 0.419279 0.412082 0.168639	73
BST2000-FI-Ref BCPM	No More Data	0	100,000,000 *	•	1000	1000 *	HMSTFLHM0.318165 0.450129 0.231706	74
BST2000-FI-Ref BCPM	No More Data	0	100,000,000 *	•	1000	1000 *	HTISFLMA 9.79E-02 0.714834 0.187299	75
BST2000-FI-Ref BCPM	No More Data	0	100,000,000 *	•	1000	1000 •	HWTHFLM 0.215951 0.773182 1.09E-02	76
BST2000-FI-Ref BCPM	No More Data	0	100,000,000 *	*	1000	1000 *	ISLMFLMA 0.727772 0.167289 0.104939	77
BST2000-FI-Ref BCPM	No More Data	0	100,000,000 *	•	1000	1000 *	JAY-FLMA 0.108345 0.872393 1.93E-02	78
BST2000-FI-Ref BCPM	No More Data	0	100,000,000 *	*	1000	1000 *	JCBHFLAB 2.49E-02 0.978201 -3.14E-03	79
BST2000-FI-Ref BCPM	No More Data	0	100,000,000 *	•	1000	1000 •	JCBHFLMA 5.18E-02 0.745513 0.202695	80
BST2000-FI-Ref BCPM	No More Data	0	100,000,000 *	•	1000	1000 *	JCBHFLSP 0.061982 0.900953 3.71E-02	81
BST2000-FI-Ref BCPM	No More Data	0	100,000,000 *	•	1000	1000 *	JCVLFLAR 0.1587 0.626491 0.214808	82
BST2000-FI-Ref BCPM	No More Data	0	100,000,000 *	•	1000	1000 •	JCVLFLBW 7.54E-02 0.714861 0.209697	83
BST2000-FI-Ref BCPM	No More Data	0	100,000,000 *	*	1000	1000 •	JCVLFLCL 0.24047 0.355123 0.404407	84
BST2000-Fi-Ref BCPM	No More Data	0	100,000,000 *	•	1000	1000 *	JCVLFLFC 0.148254 0.728908 0.124837	85
BST2000-FI-Ref BCPM	No More Data	0	100,000,000 *	•	1000	1000 *	JCVLFLIAR 0.121716 0.545551 0.332733	86
BST2000-FI-Ref BCPM	No More Data	0	100,000,000 *	•	1000	1000 *	JCVLFLJTR 1.92E-02	87
BST2000-FI-Ref BCPM	No More Data	0	100,000,000 *	•	1000	1000 *	JCVLFLLFD 0.35384 0.464993 0.181367	88
BST2000-FI-Ref BCPM	No More Data	0	100,000,000 *	•	1000	1000 *	JCVLFLNO 0.233029	89
BST2000-FI-Ref BCPM	No More Data	0	100,000,000 *	•	1000	1000 *	JCVLFLOW 0.274777 0.587657 0.137566	90
BST2000-FI-Ref BCPM	No More Data	0	100,000,000 *	•	1000	1000 *	JCVLFLRV 0.324978 0.405641 0.269381	91
BST2000-FI-Ref BCPM	No More Data	0	100,000,000 *	•	1000	1000 •	JCVLFLSJ 0.106659 0.585133 0.308208	92

BST2000-FI-Ref BCPM	No More Data	0	100,000,000 *	•	1000	1000 •	JCVLFLSM 0.154807 0.419385 0.425808	93
BST2000-FI-Ref BCPM	No More Data	0	100,000,000 *	Ť	1000	1000 *	JCVLFLWC 0.144678 0.640065 0.215257	94
BST2000-FI-Ref BCPM	No More Data	0	100,000,000 *	•	1000	1000 *	JPTRFLMA 0.363888 0.540516 9.56E-02	95
BST2000-FI-Ref BCPM	No More Data	0	100,000,000 *	•	1000	1000 *	KYHGFLMA0.250093 0.740442 9.47E-03	96
BST2000-FI-Ref BCPM	No More Data	0	100,000,000 *	•	1000	1000 *	KYLRFLLS 0.6728 0.189898 0.137302	97
BST2000-FI-Ref BCPM	No More Data	0	100,000,000 *	•	1000	1000 •	KYLRFLMA 0.580587 0.169929 0.249484	98
BST2000-FI-Ref BCPM	No More Data	0	100,000,000 *	•	1000	1000 •	KYWSFLM 0.564621 0.110927 0.324453	99
BST2000-FI-Ref BCPM	No More Data	0	100,000,000 *	•	1000	1000 •	LKCYFLMA 7.74E-02 0.874565 4.81E-02	100
BST2000-FI-Ref BCPM	No More Data	0	100,000,000 *	•	1000	1000 *	LKMRFLMA 3.66E-02 0.748268 0.215089	101
BST2000-FI-Ref BCPM	No More Data	0	100,000,000 *	•	1000	1000 •	LYHNFLOH 0.215385 0.759438 2.52E-02	102
BST2000-FI-Ref BCPM	No More Data	0	100,000,000 *	•	1000	1000 •	MCNPFLM 0.170749 0.816732 1.25E-02	103
BST2000-FI-Ref BCPM	No More Data	0	100,000,000 *	•	1000	1000 •	MDBGFLP 0.32298 0.650991 2.60E-02	104
BST2000-FI-Ref BCPM	No More Data	0	100,000,000 *	•	1000	1000 •	MIAMFLAE 0.467372 0.129937 0.402691	105
BST2000-FI-Ref BCPM	No More Data	0	100,000,000 *	•	1000	1000 *	MIAMFLAL 0.472077 0.108913 0.41901	106
BST2000-FI-Ref BCPM	No More Data	0	100,000,000 *	•	1000	1000 *	MIAMFLAP 9.96E-02 0.171055 0.729374	107
BST2000-FI-Ref BCPM	No More Data	0	100,000,000 *	•	1000	1000 *	MIAMFLBA 0.439677 0.170021 0.390302	108
BST2000-FI-Ref BCPM	No More Data	0	100,000,000 *	•	1000	1000 *	MIAMFLBC 0.373512 0.146404 0.480084	109
BST2000-FI-Ref BCPM	No More Data	0	100,000,000 *	•	1000	1000 *	MIAMFLBR 0.207744 0.142179 0.650077	110
BST2000-FI-Ref BCPM	No More Data	0	100,000,000 *	•	1000	1000 *	MIAMFLCA 0.178447 0.464808 0.356745	111
BST2000-FI-Ref BCPM	No More Data	0	100,000,000 *	•	1000	1000 *	MIAMFLDB 0.116565 0.155919 0.727516	112
BST2000-FI-Ref BCPM	No More Data	0	100,000,000 *	•	1000	1000 *	MIAMFLFL 0.502017 0.123609 0.374374	113
BST2000-FI-Ref BCPM	No More Data	0	100,000,000 *	•	1000	1000 •	MIAMFLGR 9.79E-02 6.21E-02 0.84006	114
BST2000-FI-Ref BCPM	No More Data	0	100,000,000 *	•	1000	1000 *	MIAMFLHL 0.248386 0.498821 0.252793	115
BST2000-FI-Ref BCPM	No More Data	0	100,000,000 *	•	1000	1000 *	MIAMFLICD 0.259152 0.204084 0.536764	116
BST2000-FI-Ref BCPM	No More Data	0	100,000,000 *	•	1000	1000 *	MIAMFLKE 0.250551 0.460997 0.288452	117
BST2000-FI-Ref BCPM	No More Data	0	100,000,000 *	•	1000	1000 *	MIAMFLME 0.337837 0.135711 0.526451	118
BST2000-FI-Ref BCPM	No More Data	0	100,000,000 *	•	1000	1000 *	MIAMFLNM 0.354229 0.271518 0.374254	119
BST2000-FI-Ref BCPM	No More Data	0	100,000,000 *	*	1000	1000 *	MIAMFLNS 0.501769 0.205577 0.292654	120

BST2000-FI-Ref BCPM	No More Data	0	100,000,000 *	•	1000	1000 *	MIAMFLOL 0.456253 0.221824 0.321923	121
BST2000-FI-Ref BCPM	No More Data	0	100,000,000 *	•	1000	1000 *	MIAMFLPB 0.458535 0.19123 0.350234	122
BST2000-FI-Ref BCPM	No More Data	0	100,000,000 *	•	1000	1000 *	MIAMFLPL 0.180773 0.385471 0.433756	123
BST2000-FI-Ref BCPM	No More Data	0	100,000,000 *	•	1000	1000 •	MIAMFLRR 0.406989 0.306996 0.286015	124
BST2000-FI-Ref BCPM	No More Data	0	100,000,000 *	•	1000	1000 *	MIAMFLSH 0.426746 0.159162 0.414091	125
BST2000-FI-Ref BCPM	No More Data	0	100,000,000 *	•	1000	1000 *	MIAMFLSO 0.240414 0.497537 0.26205	126
BST2000-FI-Ref BCPM	No More Data	0	100,000,000 *	•	1000	1000 *	MIAMFLWD1.98E-02 0.74966 0.230549	127
BST2000-FI-Ref BCPM	No More Data	0	100,000,000 *	•	1000	1000 *	MIAMFLWM0.345339 0.199426 0.455235	128
BST2000-FI-Ref BCPM	No More Data	0	100,000,000 *	•	1000	1000 *	MICCFLBB 0.150889 0.798185 0.050926	129
BST2000-FI-Ref BCPM	No More Data	0	100,000,000 *	•	1000	1000 *	MLBRFLMA0.113645 0.764696 0.121659	130
BST2000-FI-Ref BCPM	No More Data	0	100,000,000 *	•	1000	1000 *	MLTNFLRA 0.22659 0.725419 4.80E-02	131
BST2000-FI-Ref BCPM	No More Data	0	100,000,000 *	•	1000	1000 *	MNDRFLA 2.42E-02 0.601234 0.374578	132
BST2000-FI-Ref BCPM	No More Data	0	100,000,000 *	•	1000	1000 *	MNDRFLLO0.073868 0.828398 0.097734	133
BST2000-FI-Ref BCPM	No More Data	0	100,000,000 *	•	1000	1000 •	MNDRFLLW0.170614 0.766362 6.30E-02	134
BST2000-FI-Ref BCPM	No More Data	0	100,000,000 *	•	1000	1000 •	MNSNFLM 0.020777 0.977807 1.42E-03	135
BST2000-FI-Ref BCPM	No More Data	0	100,000,000 *	•	1000	1000 *	MRTHFLVE 0.607192 0.123576 0.269232	136
BST2000-FI-Ref BCPM	No More Data	0	100,000,000 *	*	1000	1000 *	MXVLFLMA 0.226728 0.765233 8.04E-03	137
BST2000-FI-Ref BCPM	No More Data	0	100,000,000 *	•	1000	1000 *	NDADFLAC 0.294977 0.227332 0.477691	138
BST2000-FI-Ref BCPM	No More Data	0	100,000,000 *	•	1000	1000 *	NDADFLBR 0.30041 0.463534 0.236055	139
BST2000-FI-Ref BCPM	No More Data	0	100,000,000 *	•	1000	1000 *	NDADFLGG0.311693 0.33718 0.351128	140
BST2000-FI-Ref BCPM	No More Data	0	100,000,000 *	•	1000	1000 *	NDADFLOL 0.217031 0.250473 0.532495	141
BST2000-FI-Ref BCPM	No More Data	0	100,000,000 *	•	1000	1000 *	NKLRFLMA 0.370053 0.462803 0.167144	142
BST2000-FI-Ref BCPM	No More Data	0	100,000,000 *	•	1000	1000 *	NSBHFLMA0.124722 0.73686 0.138418	143
BST2000-FI-Ref BCPM	No More Data	0	100,000,000 *	•	1000	1000 *	NWBYFLM 8.27E-02 0.906408 1.09E-02	144
BST2000-FI-Ref BCPM	No More Data	0	100,000,000 *	•	1000	1000 *	OKHLFLMA 0.118411 0.86584 1.57E-02	145
BST2000-FI-Ref BCPM	No More Data	0	100,000,000 *	•	1000	1000 *	OLTWFLLN 8.90E-02 0.907666 3.30E-03	146
BST2000-FI-Ref BCPM	No More Data	0	100,000,000 *	•	1000	1000 *	ORLDFLAP 0.120164 0.709362 0.170474	147
BST2000-FI-Ref BCPM	No More Data	0	100,000,000 *	•	1000	1000 *	ORLDFLCL 0.148341 0.599098 0.252561	148

BST2000-FI-Ref BCPM	No More Data	0	100,000,000		10	000 1000	• ORLDFLMA0.1	14284 0.570384	0.315332	149
BST2000-FI-Ref BCPM	No More Data	0	100,000,000		10	000 1000	• ORLDFLPC 6.7	2E-02 0.732868	0.199972	150
BST2000-FI-Ref BCPM	No More Data	0	100,000,000	•	10	000 1000	ORLDFLPH 6.2	4E-02 0.799116	0.138449	151
BST2000-FI-Ref BCPM	No More Data	0	100,000,000	• •	10	000 1000	• ORLDFLSA 6.3	2E-02 0.679268	0.257573	152
BST2000-FI-Ref BCPM	No More Data	0	100,000,000		10	000 1000	ORPKFLM '9.6	7E-02 0.732552	0.170724	153
BST2000-FI-Ref BCPM	No More Data	0	100,000,000	• •	10	000 1000	• ORPKFLRW0.0	80678 0.758762	0.18056	154
BST2000-FI-Ref BCPM	No More Data	0	100,000,000		10	000 1000	* OVIDFLCA 9.0	0E-02 0.851712	5.83E-02	155
BST2000-FI-Ref BCPM	No More Data	0	100,000,000	• •	10	000 1000	• PACEFLPV 0.2	04991 0.738729	5.63E-02	156
BST2000-FI-Ref BCPM	No More Data	0	100,000,000	• •	10	000 1000	• PAHKFLMA 0.1	47394 0.814119	0.038486	157
BST2000-FI-Ref BCPM	No More Data	0	100,000,000	• •	10	000 1000	PCBHFLNT 0.11	03631 0.775439	0.12093	158
BST2000-FI-Ref BCPM	No More Data	0	100,000,000	• •	10	000 1000	PLCSFLMA 7.8	3E-03 0.959266	3.29E-02	159
BST2000-FI-Ref BCPM	No More Data	0	100,000,000	• •	10	000 1000	PLTKFLMA 0.1	35221 0.795679	6.91E-02	160
BST2000-FI-Ref BCPM	No More Data	0	100,000,000	* *	10	000 1000	• PMBHFLCS 6.4	2E-02 0.792628	0.143161	161
BST2000-FI-Ref BCPM	No More Data	0	100,000,000	* *	10	000 1000	• PMBHFLFE 0.	34874 0.316166	0.335094	162
BST2000-FI-Ref BCPM	No More Data	0	100,000,000		10	000 1000	PMBHFLM: 0.1	55338 0.54347	0.301192	163
BST2000-FI-Ref BCPM	No More Data	0	100,000,000	• •	10	000 1000	PMBHFLTA 3.7	6E-02 0.811218	0.151188	164
BST2000-FI-Ref BCPM	No More Data	0	100,000,000		10	000 1000	PMPKFLM 8.4	8E-02 0.914018	1.15E-03	165
BST2000-FI-Ref BCPM	No More Data	0	100,000,000	• •	10	1000	PNCYFLCA 0.1	71387 0.782399	4.62E-02	166
BST2000-FI-Ref BCPM	No More Data	0	100,000,000	•	10	000 1000	PNCYFLMA0.2	37199 0.598702	0.1641	167
BST2000-FI-Ref BCPM	No More Data	0	100,000,000	•	10	1000	* PNSCFLBL 0.3	05332 0.48214	0.212528	169
BST2000-FI-Ref BCPM	No More Data	0	100,000,000	•	10	000 1000	* PNSCFLFP 0.	19212 0.63138	0.1765	170
BST2000-FI-Ref BCPM	No More Data	0	100,000,000	• •	10	000 1000		31639 0.602289		171
BST2000-FI-Ref BCPM	No More Data	0	100,000,000	•	10	000 1000	PNSCFLPB 0.1	48736 0.843934	7.33E-03	172
BST2000-FI-Ref BCPM	No More Data	0	100,000,000	•	10	000 1000	* PNSCFLW 0.1	91642 0.640901		173
BST2000-FI-Ref BCPM	No More Data	0	100,000,000			000 1000			3.41E-02	174
BST2000-FI-Ref BCPM	No More Data	0	100,000,000			000 1000		41277 0.553163		175
BST2000-FI-Ref BCPM	No More Data	0	100,000,000			000 1000		28524 0.867858		176
BST2000-FI-Ref BCPM	No More Data	0	100,000,000	. •	10	000 1000	FTSLFLMA 0.3	27913 0.606742	: 6.53E-02	. 177

BST2000-FI-Ref BCPM	No More Data	0	100,000,000 *	•	1000	1000 *	PTSLFLSO 0.145804	0.727077	0.127119	178
BST2000-FI-Ref BCPM	No More Data	0	100,000,000 *	•	1000	1000 *	SBSTFLFE 0.57704	0.419877	0.003082	179
BST2000-FI-Ref BCPM	No More Data	0	100,000,000 *	•	1000	1000 *	SBSTFLMA 0.27011	0.645473	0.084417	180
BST2000-FI-Ref BCPM	No More Data	0	100,000,000 *	•	1000	1000 *	SGKYFLMA0.716827	0.131224	0.151949	181
BST2000-FI-Ref BCPM	No More Data	0	100,000,000 *	•	1000	1000 *	SNFRFLMA 0,126823	0.758023	0.115154	182
BST2000-FI-Ref BCPM	No More Data	0	100,000,000 *	•	1000	1000 *	STAGFLBS 3.14E-02	0.787262	0.181385	183
BST2000-FI-Ref BCPM	No More Data	0	100,000,000 *	•	1000	1000 •	STAGFLMA 0.207244	0.65966	0.133097	184
BST2000-Fi-Ref BCPM	No More Data	0	100,000,000 *	•	1000	1000 •	STAGFLSH 0.102857	0.837998	5.91E-02	185
BST2000-FI-Ref BCPM	No More Data	0	100,000,000 *	•	1000	1000 *	STAGFLW 0.151	0.7242	0.1248	186
BST2000-FI-Ref BCPM	No More Data	0	100,000,000 *	•	1000	1000 *	STRTFLMA 0.169998	0.663204	0.166798	187
BST2000-FI-Ref BCPM	No More Data	0	100,000,000 *	•	1000	1000 *	SYHSFLCC 0.132024	0.859675	8.30E-03	188
BST2000-FI-Ref BCPM	No More Data	0	100,000,000 *	•	1000	1000 *	TRENFLMA 7.59E-02	0.914763	9.35E-03	189
BST2000-FI-Ref BCPM	No More Data	0	100,000,000 *	•	1000	1000 *	TTVLFLMA 0.239212	0.642723	0.118065	190
BST2000-FI-Ref BCPM	No More Data	0	100,000,000 *	*	1000	1000 *	VERNFLMA0.144988	0.849916	0.005096	191
BST2000-FI-Ref BCPM	No More Data	0	100,000,000 *	•	1000	1000 *	VRBHFLBE 8.72E-02	0.753489	0.159265	192
BST2000-FI-Ref BCPM	No More Data	0	100,000,000 *	•	1000	1000 *	VRBHFLMA0.261912	0.637597	0.100491	193
BST2000-FI-Ref BCPM	No More Data	0	100,000,000 *	•	1000	1000 *	WELKFLM 0.133616	0.865241	1.14E-03	194
BST2000-Fi-Ref BCPM	No More Data	0	100,000,000 *	•	1000	1000 *	WPBHFLA 0.347013	0.252098	0.40089	195
BST2000-FI-Ref BCPM	No More Data	0	100,000,000 *	•	1000	1000 *	WPBHFLG 0.222622	0.615813	0.161565	196
BST2000-FI-Ref BCPM	No More Data	0	100,000,000 *	•	1000	1000 *	WPBHFLG 0.20633	0.649874	0.143796	197
BST2000-FI-Ref BCPM	No More Data	0	100,000,000 *	•	1000	1000 •	WPBHFLH 0.197202	0.572692	0.230106	198
BST2000-FI-Ref BCPM	No More Data	0	100,000,000 *	•	1000	1000 *	WPBHFLL 0.270216	0.405163	0.324621	199
BST2000-FI-Ref BCPM	No More Data	0	100,000,000 *	•	1000	1000 *	WPBHFLR 0.313467	0.410267	0.276267	200
BST2000-FI-Ref BCPM	No More Data	0	100,000,000 *	•	1000	1000 *	WPBHFLR 0.510264	0.452972	3.68E-02	201
BST2000-FI-Ref BCPM	No More Data	0	100,000,000 *	•	1000	1000 *	WWSPFLH 9.92E-02	0.874287	2.66E-02	202
BST2000-FI-Ref BCPM	No More Data	0	100,000,000 *	•	1000	1000 *	WWSPFLS 0.036533		3.32E-02	203
BST2000-FI-Ref BCPM	No More Data	0	100,000,000 *	•	1000	1000 *	YNFNFLMA 0.189451			204
BST2000-FI-Ref BCPM	No More Data	0	100,000,000 *	•	1000	1000 *	YNTWFLM 0.231111	0.760294	8.60E-03	205

BST2000-FI-Ref BCPM	No More Data	100,000,000	•	•	1000	1000 *	YULEFLMA	0.32399	0.667805	8.20E-03	206
Underground Spacir Scenario	ng [Engineering Rules] Structure	TypeSz	Spacing								
BST2000-FI-Ref BCPM	Manholes Manholes	1	300 600								
BST2000-FI-Ref BCPM	Manholes Manholes	3	900 600								
BST2000-FI-Ref BCPM	Manholes Manholes	5 5	900 600								
Buried Sharing [Plai Scenario	nt Sharing] ExcvActivity	UrbanShared	SuburbSha	RuralShared							
BST2000-FI-Ref BCPM	Backhoe Trench Backhoe Trench	- 0.9 6	0 0. 96	0 0.96							
BST2000-FI-Ref BCPM	Bore Cable Bore Cable	0.96	0 0.96	0 0.96							
BST2000-FI-Ref BCPM	Cut & Restore Asphalt Cut & Restore Asphalt	0.96	0 0.9 6	0 0.96							
BST2000-FI-Ref BCPM	Cut & Restore Concrete Cut & Restore Concrete	0.96	0 0. 96	0 0. 96							
BST2000-Fi-Ref BCPM	Cut & Restore Sod Cut & Restore Sod	0.96	0 0. 96	0 0.96							
BST2000-FI-Ref BCPM	Free Trench (i.e. Developer) Free Trench (i.e. Developer)	0.96	0 0. 96	0 0.96							
BST2000-FI-Ref BCPM	Hand Dig Trench Hand Dig Trench	- 0.96	0 0. 96	0 0.96							
BST2000-FI-Ref BCPM	Plow Plow	0.96	0 0. 96	0 0.96							
BST2000-FI-Ref BCPM	Push Pipe & Pull Cable Push Pipe & Pull Cable	0.96	0 0.96	0 0.9 6							
BST2000-FI-Ref BCPM	Rocky Plow Rocky Plow	0.96	0 0. 96	0 0.9 6							
BST2000-FI-Ref BCPM	Rocky Trench Rocky Trench	0.96	0 0. 96	0 0. 96							
BST2000-FI-Ref BCPM	Trench & Backfill Trench & Backfill	0.98	0 0. 96	0 0.96							
Underground Sharin Scenario	g [Plant Sharing] ExcvActivity	UrbanShared	SuburbSha	RuraiShared							
BST2000-FI-Ref BCPM	Backhoe Trench Backhoe Trench	0.99	0 0.99	0 0.99							
BST2000-Fi-Ref BCPM	Bore Cable Bore Cable	0.99	0 0.9 9	0 0. 99							
BST2000-FI-Ref BCPM	Cut & Restore Asphalt Cut & Restore Asphalt	0.99	0 0.99	0 0.99							
BST2000-Fi-Ref BCPM	Cut & Restore Concrete Cut & Restore Concrete	0.99	0 0.99	0 0.99							
BST2000-Fi-Ref BCPM	Cut & Restore Sod Cut & Restore Sod	0.99	0 0.99	0 0.99							
BST2000-FI-Ref BCPM	Free Trench (i.e. Developer) Free Trench (i.e. Developer)	0.99	0 0.99	0 0.99							
BST2000-FI-Ref BCPM	Hand Dig Trench Hand Dig Trench	0.99	0 0.99	0 0. 99							
BST2000-FI-Ref BCPM	Push Pipe & Pull Cable Push Pipe & Pull Cable	0.99	0 0.99	0 0.99							

Buried Rural Excava Scenario	tion Activity (Excavation Activity ExcvActivity	y] NormalPerc	SoftrockPe	HardrockP e	VaterPerc
BST2000-FI-Ref BCPM	Backhoe Trench Backhoe Trench	0.03	0 0.02	0 0.05	0
8ST2000-FI-Ref BCPM	Bore Cable Bore Cable		0 0.01	0 0.01	0
BST2000-FI-Ref BCPM	Cut & Restore Asphalt Cut & Restore Asphalt	- 0.02	0 0.02	0 0.02	0
BST2000-FI-Ref BCPM	Cut & Restore Concrete Cut & Restore Concrete	0.02	0 0.02	0 0.02	0
BST2000-Fi-Ref BCPM	Cut & Restore Sod Cut & Restore Sod	- 0.02	0 0.02	0 0. 02	0
BST2000-FI-Ref BCPM	Hand Dig Trench Hand Dig Trench	•	0 0.03	0 0.01	0
BST2000-FI-Ref BCPM	Plow Plow	0.80	0 0.46	0	0
BST2000-FI-Ref BCPM	Push Pipe & Pull Cable Push Pipe & Pull Cable		0	0 0.01	0
BST2000-FI-Ref BCPM	Rocky Plow Rocky Plow	-	0 0. 28	0 0.47	0
BST2000-FI-Ref BCPM	Rocky Trench Rocky Trench	•	0 0.0 4	0 0.29	0
BST2000-FI-Ref BCPM	Trench & Backfill Trench & Backfill	0.11	0 0.1	0 0.1	0
Buried Suburban Ex Scenario	cavation Activity [Excavation Activity	ctivity] NormalPerc	SoftrockPe	Hardrock P é	NaterPerc
BST2000-FI-Ref BCPM	Backhoe Trench Backhoe Trench	0.02	0 0.08	0 0.12	0
BST2000-FI-Ref BCPM	Bore Cable Bore Cable	0.02	0 0.02	0 0.02	0
BST2000-Fi-Ref BCPM	Cut & Restore Asphalt Cut & Restore Asphalt	0.13	0 0.13	0 0.13	0
BST2000-FI-Ref BCPM	Cut & Restore Concrete Cut & Restore Concrete	0.12	0 0.12	0 0.12	0
BST2000-FI-Ref BCPM	Cut & Restore Sod Cut & Restore Sod	0.20	0 0.2	0 0.2	0
BST2000-FI-Ref BCPM	Hand Dig Trench Hand Dig Trench	0.06	0 0.06	0.0 6	0
BST2000-FI-Ref BCPM	Plow Plow	0.20	0 0.02	0	0
BST2000-FI-Ref BCPM	Push Pipe & Pull Cable Push Pipe & Pull Cable	0.05	0 0.05	0 0. 05	0
BST2000-FI-Ref BCPM	Rocky Plow Rocky Plow	:	0 0. 02	0 0.03	0
BST2000-FI-Ref BCPM	Rocky Trench Rocky Trench		0 0.25	0 0.27	0
BST2000-FI-Ref BCPM	Trench & Backfill Trench & Backfill	0.20	0 0.05	0	0
Buried Urban Excav Scenario	ation Activity [Excavation Activit ExcvActivity	y] NormaiPerc	SoftrockPe	HardrockPe	VaterPerc (
BST2000-FI-Ref BCPM	Backhoe Trench Backhoe Trench	- 0.19	0 0.17	0 0.1	0
BST2000-FI-Ref BCPM	Bore Cable Bore Cable	0.15	0 0.15	0 0.15	0

BST2000-FI-Ref BCPM	Cut & Restore Asphalt Cut & Restore Asphalt	0.25	0 0.25	0 0.25	0
BST2000-FI-Ref BCPM	Cut & Restore Concrete Cut & Restore Concrete	0.20	0 0.2	0 0.2	0
BST2000-FI-Ref BCPM	Cut & Restore Sod Cut & Restore Sod	0.08	0 0.08	0 0.08	0
BST2000-FI-Ref BCPM	Hand Dig Trench Hand Dig Trench	0.08	0 0.08	0 0.08	0
BST2000-FI-Ref BCPM	Rocky Trench Rocky Trench	•	0 0.05	0 0.14	0
BST2000-FI-Ref BCPM	Trench & Backfill Trench & Backfill	0.05	0 0.02	0	0
Underground Rural Scenario	Excavation Activity [Excavation / ExcvActivity	Activity] NormalTerrainPerS	SoftrockTe l	HardrockP&	VaterPerc
			_	_	_
BST2000-FI-Ref BCPM	Backhoe Trench Backhoe Trench	0.19	0 0. 4 5	0 2.6151	0
BST2000-FI-Ref BCPM	Bore Cable Bore Cable	0.02	0.03	0.03	0
BST2000-Fi-Ref BCPM	Cut & Restore Asphalt Cut & Restore Asphalt	0.02	0 0.02	0 0.1176	0
BST2000-FI-Ref BCPM	Cut & Restore Concrete Cut & Restore Concrete	0.02	0 0.02	0 0.1014	0
BST2000-FI-Ref BCPM	Cut & Restore Sod Cut & Restore Sod	0.02	0 0. 02	0 0.1493	0
BST2000-FI-Ref BCPM	Free Trench (i.e. Developer) Free Trench (i.e. Developer)	0.71	0 0.05	0	0
BST2000-Fi-Ref BCPM	Hand Dig Trench Hand Dig Trench	0.02	0 0.04	0 0.3264	0
BST2000-FI-Ref BCPM	Push Pipe & Pull Cable Push Pipe & Pull Cable	-	0 0.37	0 4.4908	0
Underground Subur	ban Excavation Activity (Excavat	ion Activityl			
Scenario	ExcvActivity	NormaiTerrainPer S	SoftrockTe H	lardrockPe/	VaterPerc
BST2000-FI-Ref BCPM	Backhoe Trench Backhoe Trench	0.30	0 0.2	0 0.979 3	0
BST2000-FI-Ref BCPM	Bore Cable Bore Cable	0.02	0 0.02	0 0.02	0
BST2000-FI-Ref BCPM	Cut & Restore Asphalt Cut & Restore Asphalt	0.13	0 0.13	0 0.7641	0
BST2000-FI-Ref BCPM	Cut & Restore Concrete Cut & Restore Concrete	0.12	0 0.12	0 0. 6086	0
BST2000-FI-Ref BCPM	Cut & Restore Sod Cut & Restore Sod	0.10	0 0.1	0 0.7 464	0
BST2000-FI-Ref BCPM	Free Trench (i.e. Developer) Free Trench (i.e. Developer)	0.27	0 0.09	0 0	0
BST2000-FI-Ref BCPM	Hand Dig Trench Hand Dig Trench	0.06	0 0. 06	0 0.4897	0
BST2000-FI-Ref BCPM	Push Pipe & Pull Cable Push Pipe & Pull Cable	•	0 0.28	0 3.67 43	0
Underground Urban Scenario	Excavation Activity (Excavation Activity	Activity] NormalTerrainPerS	SoftrockTe H	iardrockPeV	VaterPerc
BST2000-FI-Ref BCPM	Backhoe Trench	- 0.20	0 0.18	0 0.8161	0
BST2000-FI-Ref BCPM	Bore Cable Bore Cable	0.15	0 0.15	0 0.15	0

BST2000-FI-Ref	Cut & Restore Asphalt	-	0	0	۵
BCPM	Cut & Restore Asphalt	0.25	0.25	1.4694	٥

BST2000-FI-Ref	Cut & Restore Concrete	•	0	٥	٥
BCPM	Cut & Restore Concrete	0.20	0.2	1.0143	0
BST2000-FI-Ref	Cut & Restore Sod		0	٥	Q
BCPM	Cut & Restore Sod	0.07	0.07	0.5225	0
BST2000-FI-Ref	Free Trench (i.e. Developer)	•	0	٥	0
всрм	Free Trench (i.e. Developer)	0.05	0.02	0	0

BST2000-FI-Ref	Hand Dig Trench	•	0	0	0
ВСРМ	Hand Dig Trench	0.08	0.08	0.6529	0
			_	_	_
BST2000-FI-Ref	Push Pipe & Pull Cable	•	0	0	0
BCPM	Push Pipe & Pull Cable	•	0.05	1.2248	0