

ORIGINAL

LAW OFFICES

ROSE, SUNDSTROM & BENTLEY, LLP

2548 BLAIRSTONE PINES DRIVE
TALLAHASSEE, FLORIDA 32301

FREDERICK L. ASCHAUER, JR.
CHRIS H. BENTLEY, P.A.
ROBERT C. BRANNAN
DAVID F. CHESTER
F. MARSHALL DETERDING
JOHN R. JENKINS, P.A.
STEVEN T. MINDLIN, P.A.
CHASITY H. O'STEEN
DAREN L. SHIPPY
WILLIAM E. SUNDSTROM, P.A.
DIANE D. TREMOR, P.A.
JOHN L. WHARTON

(850) 877-6555
FAX (850) 656-4029
www.rsbatorneys.com

REPLY TO CENTRAL FLORIDA OFFICE

December 7, 2006

RECEIVED FPSC

06 DEC 11 AM 9:18

CENTRAL FLORIDA OFFICE

SANLANDO CENTER
2180 W. STATE ROAD 434, SUITE 2118
LONGWOOD, FLORIDA 32779
(407) 830-6331
FAX (407) 830-8522

MARTIN S. FRIEDMAN, P.A.
VALERIE L. LORD
BRIAN J. STREET

WAYNE L. SCHIEFELBEIN, OF COUNSEL
ROBERT M. C. ROSE (1924-2006)

Ms. Blanca Bayo
Commission Clerk & Administrative Services Director
Florida Public Service Commission
2540 Shumard Oak Boulevard
Tallahassee, FL 32399

RE: Docket No.: 060256-SU; Alafaya Utilities, Inc.'s Application for Rate Increase in
Seminole County, Florida
Our File No.: 30057.112

Dear Ms. Bayo:

Enclosed for filing in the above-referenced docket is the response of Alafaya Utilities, Inc., to Staff's request for supplemental information dated December 6, 2006.

(1) According [to] the Alafaya Utilities WWTF Reclaimed Water Distribution Model prepared by CPH Engineers Inc, the recommendations on Page 5 for a system peaking factor of 4 indicates that by increasing the proposed 8-inch reclaimed main through phases 4 and 5 to a 10-inch main it would resolve the pressure issue in Live Oak. It appears from the map submitted in the application that an 8-inch reclaimed main was installed instead of the recommended 10-inch main. Please explain why the 10-inch main was not installed.

RESPONSE: The 8-inch reuse main is being installed at the present time in Phases 4 and 5 by the Live Oak developer and will become CIAC when completed in 2007. The developer agreed to increase the size of the main from its originally planned 6-inch size in Phases 4 and 5, even though the Live Oak preliminary

CMP _____
COM _____
CTR _____
ECR _____
GCL _____
OPC _____
RCA _____
SCR _____
SGA _____
SEC 1 _____
OTH _____

DOCUMENT NUMBER-DATE

11289 DEC 11 06

FPSC-COMMISSION CLERK

Ms. Blanca Bayo
Commission Clerk & Administrative Services Director
Florida Public Service Commission
December 7, 2006
Page 2


master plan had been previously approved with a 6-inch trunk line. The developer would not agree to increase the pipe size beyond 8-inch nor would he agree to provide a second connection to the reuse transmission main. Increasing the pipe size to 10-inch was predicated on a peaking factor of 4, which is no longer germane.

- (2) If the 10-inch main has not been installed in Live Oak as recommended to provide a system peaking factor of 4, does the utility plan to provide a peaking factor of 4 by another method in the Live Oak system. Please explain.

RESPONSE: The system peaking factor of 4 was based on a standard irrigation schedule where each half of the reuse customers water 2 specific days per week so that irrigation activity would occur on 4 days out of 7. Last spring, the Utility developed and implemented a comprehensive watering schedule that uses all 7 days of the week to disperse demand more evenly across the reuse customer base. Consequently the hydraulic analysis done by CPH is no longer applicable.

Should you have any questions, please do not hesitate to give me a call.

Very truly yours,



MARTIN S. FRIEDMAN
VALERIE L. LORD
For the Firm

VLL/tlc

Ms. Blanca Bayo
Commission Clerk & Administrative Services Director
Florida Public Service Commission
December 7, 2006
Page 3

cc: Ralph Jaeger, Esquire, Office of General Counsel
Mr. Troy Rendell, Division of Economic Regulation
Ms. Cheryl Bulecza-Banks, Div. Of Economic Regulation
Ms. Patti Daniel, Division of Economic Regulation
Mr. Richard Redemann, Division of Economic Regulation
Mr. Bart Fletcher, Division of Economic Regulation (by facsimile and U.S. Mail)
Steven M. Lubertozi, Chief Regulatory Officer
Kirsten Weeks, CPA
John Hoy, Regional Vice President for Operations
Patrick C. Flynn, Regional Director
Stephen Reilly, Esquire, Office of Public Counsel

M:\1 ALTAMONTE\UTILITIES INC\ALAFAYA UTILITIES\(.112) 2005 RATE CASE\PSC Clerk 019 (Staff supp).ltr.wpd