LAW OFFICES

ROSE, SUNDSTROM & BENTLEY, LLP

2548 Blairstone Pines Drive Tallahassee, Florida 32301

Frederick L. Aschauer, Jr.
Chris H. Bentley, P.A.
Robert C. Brannan
F. Marshall Deterding
John R. Jenkins, P.A.
Kyle L. Kemper
Steven T. Mindlin, P.A.
Chasity H. O'Steen
Daren L. Shippy
William E. Sundstrom, P.A.
Diane D. Tremor, P.A.
John L. Wharton
Robert M. C. Rose (1924-2006)

(850) 877-6555 Fax (850) 656-4029 www.rsbattorneys.com

Sanlando Center 2180 W. State Road 434, Sutte 2118 Longwood, Florida 32779 (407) 830-6331 Fax (407) 830-8522

REPLY TO CENTRAL FLORIDA OFFICE

MARTIN S. FRIEDMAN, P.A. VALERIE L. LORD BRIAN J. STREET

CENTRAL FLORIDA OFFICE

May 25, 2007

E-FILING

Ann Cole, Commission Clerk Office of Commission Clerk Florida Public Service Commission 2540 Shumard Oak Boulevard Tallahassee, FL 32399

RE: Docket No.: 060726-WS; Application of Silver Lake Utilities, Inc., to Operate a Water Utility in Glades and Highlands Counties, Florida, and a Wastewater Utility in Glades County, Florida

Our File No.: 40001.01

Dear Ms. Cole:

The following are the Utility's responses to Staff's First Data Request dated May 9, 2007:

Existing Water System

1. Can the utility provide evidence to show that the existing facilities were not costed off on the Lykes Bros. income tax?

<u>RESPONSE</u>: The Utility cannot provide evidence to show that the existing facilities were not costed off on the Lykes Bros. tax returns. The Utility cannot specifically identify any of the water assets since they are a part of larger projects. It is Lykes Bros.' policy to capitalize such fixed assets.

2. Staff cannot determine the reasonableness of the plant items in the format given. For each system, can the utility provide a schedule which identifies plant items by NARUC account number, short description, type of unit, number of units, cost per unit, and total costs? For instance:

Acct. No.	Description	<u>Unit</u>	No. of Units	<u>Unit Cost</u>	<u>Total Cost</u>
370	Lift Station	Each	20	\$20,000	\$400,000
XXXX	3" Lateral	Linear Ft.	2,000	\$ 100	\$ 20,000

(<u>Note</u>: The data needed is similar to that provided on Schedule F-5. However, staff could not verify the unit cost from that or any other schedule).

<u>RESPONSE:</u> The cost estimates are preliminary and based on a conceptual design at a planning level, and as such, it is difficult to provide a detailed estimate. However, Johnson Engineering, Inc. has attempted to provide further detail of the estimates. While revisiting the cost estimates, five items were found in need of revised cost estimates based on current trends and additional evaluation performed since the original estimate was prepared, as reflected in the original submittal to the PSC. Please see Schedule 2 attached hereto for revised and more detailed cost estimates. See, Note below regarding rate impact.

Injection Wells

3. Can the utility provide recent water quality analysis for the Muse which includes the mg/1 of total dissolved solids (TDS)?

RESPONSE: In 2006, a suite of water quality analyses was performed on two wells open to the Floridan aquifer located less than a mile from the proposed Muse Village utility site. Results from these analyses showed TDS of 920 and 956 mg/L and specific conductance values of 1,632 and 1,754 umohs/cm, respectively. Other Floridan aquifer wells in the area report similar ratios of TDS to specific conductance. Specific conductance value measured at the Muse Village Floridan aquifer test well was 1,749 umohs/cm following the completion of a 72-hour aquifer performance test. Based on the relationship between specific conductance and TDS established for this site, the Floridan aquifer test well has a TDS concentration of approximately 960 mg/L.

4. Can the utility provide information, such as engineering analysis, that shows that deep well injection is the least-cost alternative for disposal of brine concentrate and excess effluent?

<u>RESPONSE</u>: An engineering analysis of least-cost alternatives for disposal of brine concentrate and excess effluent has not been performed. Deep well injection is common practice. North Fort Myers Utility, City of Clewiston, Bonita Springs Utilities, Island Water Association, Greater Pine Island Water Association and Lee County Utilities have one or more injection wells in operation. Additionally, the City of LaBelle's Capital Improvement Plan includes an injection well and Town and County Utilities Company proposes to use a deep injection well as described in the publicly available Application for Master

Development Approval for the Babcock Ranch Community. The deep injection well method of disposal was not chosen on the basis of cost, but rather on the provision of permitting ability. Deep injection wells are favorably looked upon by FDEP rather than surface water, land application or shallow aquifer disposal mechanisms.

5. As staff understands it, the utility intends to construct two deep injection wells. One for bulk treated water and one for the Muse Development treated water and excess wastewater effluent disposal. Staff can see some breakdown in injection well costs in wastewater and bulk water. However, it is not broken out for potable water. Can the utility provide a complete breakdown of costs for the injection wells and the percentage assigned to each system?

<u>RESPONSE</u>: As originally submitted, the injection well cost was associated with the wastewater treatment facility. Both the water and wastewater facilities need the deep injection well on an equal basis to meet regulatory requirements so therefore cost has now been allocated on a 50/50 basis. See, Schedule 2 attached hereto. See, Note below regarding rate impact.

Reuse Irrigation

It is staff's understanding that the utility is using 250 gpd for water usage because irrigation from reuse will be available. As such, the utility is constructing facilities capable of providing high quality reuse and storage. It is also staff's understand that irrigation services are not included in the application because the service will be provided by the parent as an exempt service.

5. Please provide the rate the utility intends to charge the parent to purchase reuse from its facilities. Also, please provide a schedule which shows how the customers' rates have been offset by the proceeds from those sales.

<u>RESPONSE</u>: The Utility intends to charge \$0.05 per thousand for reuse water. See, Note below regarding rate impact.

Rate Structure

6. The utility has requested a two-tiered gallonage rate for potable water for the Muse Development. Since there is no historical data, what is the basis of the

utility's request and how was the 5kgal break point selected?

<u>RESPONSE</u>: Using 250 gpd average monthly usage equals 7,604 gallons per month. Using a 5,000 gallon breakpoint represents approximately 70% of the usage to be included in the first block.

7. If the rate structure was recommended by the local WMD, did the utility request a temporary pass on the IBRS for 12 to 24 months in favor of a uniform gallonage charge until historical data can be obtained?

<u>RESPONSE</u>: No. The Utility has requested an inclining block rate structure consistent with conservation goals in rate making.

Leases and Royalties

The application contains a proposed lease with Lykes Bros., Inc. for royalties of \$.20 per kgal for water withdrawn and \$1,000 per year rental for each lease site. It is staff's understanding that this was based on the amount approved for Town and Country in 1998. However, the most recent royalties approved for inclusion in rate base by the Commission were \$.10 for Farmton in 2002 and D & E in 2006.

8. The details in Appendix A to the engineering report, appear to be for 22 existing wells and 7 wells owned by the Seminole Indians. Please confirm the total number of well sites, both existing and proposed.

<u>RESPONSE</u>: Silver Lake Utilities currently has 22 existing wells and uses water from 7 bulk water connections with the Seminole Tribe potable water system. The bulk water connections are not well sites; they are tie-in points to the Seminole Tribe mainline running parallel with CR-721.

The Utility proposes a total of 7 new wells: 3 potable supply wells to serve the Muse Village development, 2 proposed wells to provide raw bulk water service, and 2 proposed wells to provide treated bulk water service.

9. Given the poor quality of water, can the utility justify the amount of the proposed royalty?

RESPONSE: Water quality data submitted in support of a South Florida Water Management District (SFWMD) water use permit application for Town and Country Utilities Company (SFWMD #060724-8) show similar water quality for the Floridan aquifer as that encountered at Muse Village. The PSC approved a rate based on a \$0.20/1,000 gallon royalty for Town and Country Utilities Company. Please refer to the Town and Country Utilities Company water quality data, which is attached hereto as Schedule 9. Additional information will be forthcoming.

10. The most recently approved well site leases for the Farmton and D&E were for \$100 per year, which is \$900 less than Lykes Bros., Inc. is proposing to charge. As such, leases are over 20% of the O&M for the existing systems. Can the utility justify the proposed lease cost?

RESPONSE: Yes, additional information will be forthcoming.

Salaries and Wages

11. Since the Utility is proposing to contract out some of its duties, can the utility provide a schedule for each service which shows the duties that are intended to be performed under salary and wages, verses contract costs, along with the total man-hours and hourly rate?

RESPONSE: See Schedule 11 attached hereto.

Meters

12. Can the utility provide the justification for the \$300 cost for 5/8" x 3/4" meter?

<u>RESPONSE</u>: Schedule C-6 (P.19) of the Special Report attached to the Application as Exhibit "E" provides that cost breakdown. The Utility will be installing electronic meters similar to those being utilized by O & S Water Company, Inc. A \$300.00 meter installation fee was approved for that type of meter in Order No. PSC-03-1474-TRF-WU. The cost breakdown for the meters the Utility proposes to install are substantially the same as those approved in that Order.

13. Can the utility provide cost justification for the other meter sizes?

RESPONSE: As is commonplace, the cost for meters larger than 5/8" x 3/4" will be actual cost.

14. Have the existing customers paid for meters?

RESPONSE: No. There are no existing meters.

Customer Deposits

15. Deposits. Since the utility has requested a late payment fee, can it provide the reason it did not request customer deposits?

<u>RESPONSE</u>: The Utility will amend its Application to include a request for customer deposits of twice an average monthly bill, once the initial rates have been established.

NOTE: The Utility next week will file revised revenue requirements and rates incorporating the more updated information provided herein.

Please contact me if you have any questions.

Very truly yours

MARTIN S. FRIEDMAN

For the Firm

MSF/tlc Enclosures

cc: Charles P. Lykes, Jr., Executive Vice President (w/enclosures - via U.S. Mail)

Frederick J. Bennett, Vice President & CFO (w/enclosures - via U.S. Mail)

Mr. Joe Collins (w/enclosures - via U.S. Mail)

Cari Lynn Roth, Esquire (w/enclosures - via U.S.Mail)

Lonnie Howard, P.E. (w/enclosures - via U.S. Mail)

Robert C. Nixon, CPA (w/enclosures - via U.S. Mail)

Ms. Patti Daniel, Division of Economic Regulation (w/enclosures - via U.S. Mail)

Mr. Richard Redemann, Division of Economic Regulation (w/enc. - via U.S. Mail)

Ms. Pat Brady, Division of Economic Regulation (w/enclosures - via U.S. Mail)

Schedule 2 **Supplemental Cost Estimate Information**

Johnson Engineering, Inc. has prepared a brief cost estimate for the utility systems described within Exhibit B, Application For An Initial Certification Of Authorization Before the Florida Public Service Commission Engineering Report, to provide further detail of the cost estimates. Five costs have been revised since the original application and are noted along side the revised cost estimate.

The cost estimates are based on conceptual planning level design. The costs are based on local knowledge and experience in Southwest Florida.

	ltem		Quantity	Unit Cost	Extended Cost
Muse Villag	ge Wastewater				
Wastew	ater Treatment Plant				
380	Headworks - Structure & Mechanical Bar Screen	ſ			\$767,724
354	Flow Equalization Facilities	İ			\$1,011,194
380	Closed Loop Reactor/Clarifier w/ tanks, walkway, equipment	: 1			\$3,252,799
380	Aerobic Digestors	Ì			\$365,672
380	ABW Effluent Polishing Filters	Ì			\$1,565,299
380	Chlorination Facilities, Tanks, Equipment	İ			\$629,664
370	Plant Site Lift Station	Ì			\$430,037
354	Site Work	Ì			\$298,974
380	Substandard Storage Pond	ŀ			\$298,974
380	Wet Weather Storage Pond	İ	~		\$573,694
354	Miscellaneous, Driveway, Fence, Seeding, Monitoring Wells Control/Lab Building, Site Lighting, Engine-Gen, etc	,			\$1,805,970
		Total			\$11,000,000
Master V	Vastewater Pump Stations - each				
371	Pumps (2 - 700gpm pumps and one low flow jockey pump)	Г	31	\$187,500	\$562,500
354	Concrete Wetwell	f	3	\$437,500	
380	Odor Control System	Ī	3	\$187,500	
355	Generator	ı	3	\$187,500	
381	Piping	ı	3	\$125,000	
339	Telemetry / SCADA Controls		3	\$125,000	
354	Electrical	-	3	\$125,000	
		Total		\$1,375,000	\$4,125,000
360	Spine Wastewater Force Mains - LF	Г	27.000	\$69	\$1,866,400

Item

Muse Village Injection Well

Deep Injection Well 380/339 Tubing & Packer Injection Well

380/339 Monitor Well 380/339 Well Heads, Piping, Monitoring Equipment

337 Percent of cost associated with Potable Water - 50% 320 Percent of cost associated with Wastewater - 50%

Quantity Unit Cost Extended Cost

		\$3,875,000
		\$1,000,000
		\$125,000
1	 	CC 000 000

ltem

Quantity Unit Cost Extended Cost

Muse Village Potable Water

Water Tr	reatment Plant			
309	Raw Water Main/Yard Appurtenances			\$222,531
320	Pretreatment Facilities - Mixer, Micron Filters			\$257,302
309	RO Trains w/ Feed Pump Unit			\$1,466,968
320	Chemical Feed Facilities, Caustic, Anti-scalant			\$260,779
320	Post Treatment - Clearwell, Degasifier, Transfer Pumps, Electrical			\$1,049,896
311	High Service Pumping Units			\$232,962
310	Miscellaneous Electrical Power, Instrumentation, Lighting, HVAC, Engine-Gen, CIP Tanks			\$785,814
320	Hypochlorite Storage Feed Systems			\$90,403
330	Water Storage Tanks			\$1,157,858
309	Yard Piping, Valves, etc.			\$295,376
304	Building - Process Office, Lab			\$1,161,335
304	Outside Electrical			\$69,541
304	Injection Pump Station, Surface Facilities, Controls and Valves			\$177,330
304	Site Work			\$271,905
	Total			\$7,500,000
		Previou	sly Submitted	\$10,500,000
Potable '	Wells			
307	Well - each	3	\$312,500	\$937,500
311	Pump/Controls - each	3	\$81,250	\$243,750
309	Discharge Head/Piping - each	3	\$31,250	\$93,750
310	Backup Power - each	3	\$50,000	\$150,000
339	SCADA each	3	\$25,000	\$75,000
·	Total		\$500,000	\$1,500,000
309	Potable Raw Water Transmission Pipeline - LF	5,000	\$37	\$183,750
331	Spine Potable Water Mains - LF	46,000	\$86	\$3,942,038

ltem

Quantity Unit Cost Extended Cost

0.5 MGD Bulk Raw Water

Potable	Wells				
307	Well - each	Γ	2	\$343,750	\$687,500
311	Pump/Controls - each		2	\$81,250	\$162,500
309	Discharge Head/Piping - each		2	\$31,250	\$62,500
310	Backup Power - each		2	\$50,000	\$100,000
339	SCADA - each	Γ	2	\$25,000	\$50,000
		Total		\$531,250	\$1,062,500
309	Raw Water Supply Line - LF		17,633	\$38	\$661,250
304	Access Road (Limerock Road) - LF	Г	4,752	\$28	\$130,680
,		L-	Previous	y Submitted	\$59,400

0.35 MGD Bulk Treated Water


0.35 MG	BD Bulk Water Treatment Plant				
309	Raw Water Main/Yard Appurtenances			T	\$79,696
320	Pretreatment Facilities - Mixer, Micron Filters				\$92,149
309	RO Trains w/ Feed Pump Unit				\$498,340
320	Chemical Feed Facilities, Caustic, Anti-scalant				\$93,394
320	Post Treatment - Clearwell, Degasifier, Transfer Pumps, Electronic	rical			\$331,238
311	High Service Pumping Units				\$270,932
310	Miscellaneous Electrical Power, Instrumentation, Lighting, HV Engine-Gen, CIP Tanks	AC,			\$281,428
320	Hypochlorite Storage Feed Systems	-			\$32,377
309	Yard Piping, Valves, etc.				\$164,670
304	Building - Process Office, Lab	-		,	\$415,916
304	Outside Electrical				\$24,905
304	Injection Pump Station, Surface Facilities, Controls and Valves	s			\$63,508
304	Site Work				\$070.447
					\$276,447
	l	otal	D (\$2,625,000
Storage	and pump station		Previous	sly Submitted	\$5,625,000
330	0.175 Above Ground Storage Reservoir		-11	\$437,500	\$437,500
311	Pump Station	-		\$125,000	\$125,000
211	·				
	,	otal	Danis	\$562,500 sly Submitted	\$562,500
Deen Ini	ection Well		Previous	siy Submitted	\$1,468,750
307	Tubing & Packer Injection Well				\$3,875,000
339	Monitor Well	-			\$1,000,000
307	Well Heads, Piping, Monitoring Equipment	-			\$1,000,000
	3 1 1	otal			\$5,000,000
	ı	otai			\$5,000,000
Potable	Wells				
307	Well - each		2	\$343,750	\$687,500
311	Pump/Controls - each	-	2	\$81,250	\$162,500
309	Discharge Head/Piping - each	-	2	\$31,250	\$62,500
310	Backup Power - each	<u> </u>	2	\$50,000	\$100,000
339	SCADA - each	 	2	\$25,000	\$50,000
	Т	otal		\$531,250	\$1,062,500
309	Raw Water Supply Line - LF		2,640	\$31	\$82,500
304	Access Road (Limerock Road) - LF		4,752	\$28	\$130,680
		•	Previous	ly Submitted	\$59,400
331	Treated Water Distribution Line - LF		15,000	\$31	\$468,750

All costs presented above are in 2006 dollars and include 25% contingency. The costs do not include engineering and permitting fees. Engineering, design, and permitting fees are estimated to be 12% of construction costs, not including construction services.

SCHEDULE 9

BENCHMARK

EnviroAnalytical Inc.



NELAC Certification # E84167

ANALYTICAL TEST REPORT THESE RESULTS MEET NELAC STANDARDS

Submission Number:

6090160

Johnson Engineering, Inc.

2158 Johnson Street Fort Myers, Fl 33901

20066400-01

Project Name : Date Received :

09/07/2006

Time Received:

1430

Tim Denison

Submission Number

6090160

Sample Number:

1A

Sample Description:

SPLH/Field

Sample Date:

09/06/2006

Sample Method:

Grab

Sample Time:

1033

D	Dogult	Ilmita	MDI	POL	Procedure	An	alysis	Analyst
Parameter	Result	Units	MDL	rųL	riocedure	Date	Time	Allaiyst
PH	7.55	UNITS	0.1	0.4	150.1	09/06/2006	10:33	JOHN INC
TEMPERATURE	29.0	DEG C.	0.1	0.4 150.1 0.4 170.1		09/06/2006	10:33	JOHN INC
SPECIFIC CONDUCTANCE, FIELD	1619	UMHOS	1.24	4.96	SM2510B	09/06/2006	10:33	JOHN INC
DISSOLVED OXYGEN	3.75	MG/L	0.05	0.20	SM4500 OC	09/06/2006	10:33	JOHN INC

Submission Number

6090160

Sample Number:

1B

Sample Description:

SPLH/Lab

Sample Date:

09/06/2006

Sample Method:


Grab

Sample Time:

1040

	D 14	¥ Y!4-	MINI	DOI.	Duggadung	An	alysis	Analyst
Parameter	Result	Units	MDL	PQL	Procedure	Date	Time	Allalyst
COLOR	5 U	PCU	5	20	110.2	09/07/2006	10:00	JS
PH	7.94	UNITS	0.1	0.4	150.1	09/07/2006	17:00	JSM
TOTAL DISSOLVED SOLIDS	916	MG/L	7.26	29.04	160.1	09/12/2006		СВ
TURBIDITY	0.05 U	NTU	0.05	0.20	180.1	09/08/2006	14:25	DS
BARIUM	11.7	UG/L	2	8	200.7	09/11/2006		RCB
CALCIUM	38.5	MG/L	0.03	0.12	200.7	09/11/2006		RCB
IRON	29 U	UG/L	29	116	200.7	09/11/2006		RCB
MAGNESIUM	42.0	MG/L	0.006	0.024	200.7	09/11/2006		RCB

EnviroAnalytical Inc.



NELAC Certification # E84167

MANGANESE	0.98 U	UG/L	0.98	3.92	200.7	09/11/2006		RCB
POTASSIUM	13.0	MG/L	0.169	0.676	200.7	09/11/2006		RCB
SODIUM	194	MG/L	0.034	0.136	200.7	09/11/2006		RCB
STRONTIUM	3.98	MG/L	0.001	0.004	200.7	09/11/2006		RCB
CHLORIDE	229	MG/L	0.353	1.412	300.0	09/12/2006		TDT
FLUORIDE	1.90	MG/L	0.030	0.120	300.0	09/12/2006		TDT
SULFATE	247	MG/L	0.339	1.356	300.0	09/13/2006		TDT
AMMONIA NITROGEN	0.006 U	MG/L	0.006	0.024	350.2			
NITRATE NITROGEN	0.004 U	MG/L	0.004	0.016	353.2	09/07/2006	17:33	JSM
NITRATE+NITRITE	0.004 U	MG/L	0.004	0.016	353.2	09/08/2006		СВ
TOTAL PHOSPHORUS	0.002 U	MG/L	0.002	0.008	365.3			
SILICA	14.3	MG/L	0.044	0.176	370.1	09/22/2006		YW
UNIONIZED HYDROGEN SULFIDE	0.328	MG/L	0.005	0.020	CALC.	09/28/2006		RBK
BICARBONATE ALKALINITY	144	MG/L	0.594	2.376	SM2320B	09/08/2006		DS
CARBONATE ALKALINITY	0.594 U	MG/L	0.594	2.376	SM2320B	09/08/2006		DS
TOTAL ALKALINITY	144	MG/L	0.594	2.376	SM2320B	09/08/2006		DS
SPECIFIC CONDUCTANCE	1571	UMHOS/CM	1.24	4.96	SM2510B	09/08/2006		DS
NITRITE NITROGEN	0.003 U	MG/L	0.003	0.012	SM4500NO2B	09/07/2006	17:33	JSM
SULFIDE	1.91	MG/L	0.028	0.112	SM4500S2D	09/08/2006		RCB
TOTAL ORGANIC CARBON	0.271 U	MG/L	0.271	1.084	SM5310B	09/12/2006		TDT

Submission Number

6090160

Sample Number:

2A

Sample Description:

HQLH/Field


Sample Date: 09/06/2006 Sample Method:

Grab

Sample Time: N/A

		Y1	MDI	no.	Dd	Ana	alysis	Analyst
Parameter	Result	Units	MDL	PQL	Procedure	Date	Time	Analyst
PH	7.28	UNITS	0.1	0.4	150.1	09/06/2006		JOHN INC
TEMPERATURE	28.4	DEG C.	0.1	0.4	170.1	09/06/2006		JOHN INC
SPECIFIC CONDUCTANCE, FIELD	858	UMHOS	1.24	4.96	SM2510B	09/06/2006		JOHN INC
DISSOLVED OXYGEN	5.89	MG/L	0.05	0.20	SM4500 OC	09/06/2006		JONH INC

EnviroAnalytical Inc.



NELAC Certification # E84167

Submission Number

6090160

Sample Number:

2B

09/06/2006

Sample Description:

Sample Method:

HQLH/Lab


Sample Date: Sample Time:

1500

Grab

	D 14	¥1	MOI	nor	Dunandur	An	alysis	Analyst
Parameter	Result	Units	MDL	PQL	Procedure	Date	Time	Analyst
COLOR	5 U	PCU	5	20	110.2	C9/07/2006	10:00	JS
PH	7.70	UNITS	0.1	0.4	150.1	09/07/2006	17:00	JSM
TOTAL DISSOLVED SOLIDS	512	MG/L	7.26	29.04	160.1	09/12/2006		СВ
TURBIDITY	0.05 U	NTU	0.05	0.20	180.1	09/08/2006	14:25	DS
BARIUM	19.3	UG/L	2	8	200.7	09/11/2006		RCB
CALCIUM	43.5	MG/L	0.03	0.12	200.7	09/11/2006		RCB
IRON	29 U	UG/L	29	116	200.7	09/11/2006		RCB
MAGNESIUM	31.1	MG/L	0.006	0.024	200.7	09/11/2006		RCB
MANGANESE	0.98 U	UG/L	0.98	3.92	200.7	09/11/2006		RCB
POTASSIUM	7.03	MG/L	0.169	0.676	200.7	09/11/2006		RCB
SODIUM	79.4	MG/L	0.034	0.136	200.7	09/11/2006		RCB
STRONTIUM	3.94	UG/L	0.001	0.004	200.7	09/11/2006		RCB
CHLORIDE	71.6	MG/L	0.353	1.412	300.0	09/12/2006		TDT
FLUORIDE	1.30	MG/L	0.030	0.120	300.0	09/12/2006		TDT
SULFATE	66.4	MG/L	0.339	1.356	300.0	09/13/2006		TDT
AMMONIA NITROGEN	0.006 U	MG/L	0.006	0.024	350.2			
NITRATE NITROGEN	0.004 U	MG/L	0.004	0.016	353.2	09/07/2006	17:33	JSM
NITRATE+NITRITE	0.004 U	MG/L	0.004	0.016	353.2	09/08/2006		CB
TOTAL PHOSPHORUS	0.002 U	MG/L	0.002	0.008	365.3			
SILICA	39.1	MG/L	0.044	0.176	370.1	09/22/2006		YW
UNIONIZED HYDROGEN SULFIDE	1.79	MG/L	0.008	0.032	CALC.	09/28/2006		RBK
BICARBONATE ALKALINITY	230	MG/L	0.594	2.376	SM2320B	09/08/2006		DS
CARBONATE ALKALINITY	0.594 U	MG/L	0.594	2.376	SM2320B	09/08/2006		DS
TOTAL ALKALINITY	230	MG/L	0.594	2.376	SM2320B	09/08/2006		DS
SPECIFIC CONDUCTANCE	832	UMHOS/CM	1.24	4.96	SM2510B	09/08/2006		DS
NITRITE NITROGEN	0.003 U	MG/L	0.003	0.012	SM4500NO2B	09/07/2006	17:33	JSM
SULFIDE	6.20	MG/L	0.028	0.112	SM4500S2D	09/08/2006		RCB
TOTAL ORGANIC CARBON	2.76	MG/L	0.271	1.084	SM5310B	09/12/2006		TDT

EnviroAnalytical Inc.



NELAC Certification # E84167

Dale D. Dixon / Laboratory Director

Robert L. Sullivan/ Laboratory Manager

DATA QUALIFIERS THAT MAY APPLY:

A = Value reported is an average of two or more determinations.

B = Results based upon colony counts outside the acceptable range.

H = Value based on field kit determination. Results may not be accurate.

I = Reported value is between the laboratory MDL and the PQL.

J1 = Est, value surrogate recovery limits exceeded.

J2 = Est. value. No quality control criteria exists for component.

J3 = Est. value quality control criteria for precision or accuracy rnot met.

J4 = Est. value. Sample matrix interference suspected.

J5 = Est. value. Data questionable due to improper lab or field protocols

K = Off-scale low. Value is known to be < the value reported.

L = Off-scale high. Value is known to be > the value reported

N = Presumptive evidence of presence of material.

Q = Sample held beyond accepted hold time.

T = Value reported is < MDL. Reported for informational purposes only and shall not be used in statistical analysis.

U = Analyte analyzed but not detected at the value indicated.

V = Analyte detected in sample and method blank.

Y = Analysis performed on an improperly preserved sample. Data may be inaccurate.

! = Data deviate from historically established concentration ranges.

? \Rightarrow Data rejected and should not be used. Some or all of QC data were outside criteria, and the Presence or absence of the analyte cannot be determined from the data.

* = Not reported due to interference.

NOTES:

POL = 4xMDL

MBAS calculated as LAS; molecular weight = 348.

X = Value exceed MCL.

G = CBOD accuracy standard does not meet method QC criteria, but does not meet lab control limits that are in agreement with USEPA generated data. USEPA letter available upon request.

For questions and comments regarding these results, please contact Katharine Dixon at (941) 723-9986

Johnson Engineering, Inc. Client:

Benchmark EnviroAnalytical, Inc.

1711 Twelfth Street East

Palmetto, FL 34221

(941) 723-986

×

2158 Johnson Street Fort Myers, FI 33901

(239) 461-2458 (Tim Denison) (239) 334-3661

BenchmarkEA@earthlink.net Chain of Custody Form: (941) 723-6061 fax

10-00 \$9,000 F

Laboratory Submission #:

0040100

									5	0010100
TDS SO, CI F Total Fe (EPA 200.7) T/B/C Alkalinity Ca, Mg, Na, K, Mn, NC PH Cond. Color ntu Sr, Ba	TOC, NO3-NO2, NO3,	Hydrogen 32, Sulfide				Field Parameters // Time:	1033 - SPLH	trids		Laboratory Sample #
(1) (2)	(3)	(4)	Temp	Specific	pH (s.u.s)	D.O.	H ₂ S	Turbidity	T/B/C	
Plain 1:4 HNO ₃ 1:4 F pH pH	1:4 H2SO4 pH<2 🛭	O4 ZnOAc 1 NaOH		ance (µmhos)		(1)		(nun)	Alkalinity	
1 x 2 Quart 1x 1 Pint Plastic 1 x 1 Quart	λua	art 1x1 Pint								
Time			000		\	\				1 A/R
1040 1040 1040	0		1040 AT. 1619 7.55 3.75	6/9/	7.53	3.75)
Time Time Time /500 /500	0		1500 28.40 0.83 7.28	0.63		5.89	-			2 A/B
Time	1									3 A/B

Sample must be refrigerated or stored in wet ice after collection. The maximum temperature during storage should be 4°C (39.2°F). 1. Sa Instructions

Each bottle has a label identifying sample ID, premeasured preservative contained in the bottle, sample type, client ID, and parameters for analysis.

He following information is hould be added to each bottle label after collection with parament black ink: date and time of collection, sampler's name or initials, and any field number or ID.

All bottles not containing preservative may be inseed with appropriate sample prior to collection.

The client is responsible for documentation of the sampling event. Please note special sampling events on the sample or documentation of the sampling event.



~	Collector: Wester Withham &	Date: 9/6/6	Time: /6%o	Received By:	Date:	Time:
2	126	Date: 7/6/06	Time;	Received By:	9/7/66	Time; 720
က	Refinalished by:	27/08	TIME	Received By: 1	Date:	Тіте:
4	Relinquished by	bake:	Time:	Received By: D	10/1/2	(8) Time 3

Ion Balance Sample 20066400-01SPLH


CATIONS	MG/L	FACTOR	MILLIEQUIVALENTS	ANIONS	MG/L	FACTOR	FACTOR MILLIEQUIVALENTS
BARIUM	11.7	0.014	0.1638	CHLORIDE	229	0.028	6.412
CALCIUM	38.5	0.049	1.8865	FLUORIDE	1.9	0.052	0.0988
IRON	29		1.537	SULFATE	247	0.02	4.94
MAGNESIUM	42		3.444	NITRATE as NO3	0.004	0.016	0.000064
MANGANESE	0.98		0.03528	PHOSPHORUS as PO4	0.025	0.031	0.000775
POTASSIUM	13		0.325	SILICA as SO3	14.3	0.026	0.3718
SODIUM	194	0.043	8.342	BICARBONATE	144	0.033	4.752
STRONTIUM	3.98	0.022	0.08756	CARBONATE	0.594	0.016	0.009504
AMMONIUM	0.347	0.055	0.019085				
TOTAL CATION MILLIEQUIVALENT	LLIEQUIVALENT		15.840225	TOTAL ANION MILLIEQUIYALENT	ALENT		16.584943

ion balance =100 (sum cations-sum anions)/(sum cations +sum anions)

Ion Balance=

-2.29672827

EnviroAnalytical Inc.



NELAC Certification # E84167

ANALYTICAL TEST REPORT

THESE RESULTS MEET NELAC STANDARDS

Submission Number:

7030158

Johnson Engineering, Inc.

2158 Johnson Street Fort Myers, Fl 33901 **Project Name:**

20066400-01

Date Received:

03/06/2007

Time Received:

1510

Submission Number

7030158

Sample Number:

03/05/2007

Sample Description:

JE-900

Sample Date:

Sample Method:


Grab

Sample Time:

0900

	~ L	**	MADI	no.	D	An	alysis	A malayat
Parameter	Result	Units	MDL	PQL	Procedure	Date	Time	Analyst
COLOR	5 U	PCU	5	20	110.2	03/06/2007	16:50	JS
РН	7.72	UNITS	0.1	0.4	150.1	03/06/2007	17:10	RCB
TOTAL DISSOLVED SOLIDS	932	MG/L	7.26	29.04	160.1	03/07/2007	15:45	СВ
TURBIDITY	16.4	NTU	0.05	0.20	180.1	03/06/2007	17:10	DS
BARIUM	44.1	UG/L	2	8	200.7	03/08/2007	12:00	RCB
CALCIUM	58.8	MG/L	0.03	0.12	200.7	03/08/2007	12:00	RCB
DISSOLVED IRON	29 U	UG/L	29	116	200.7	03/29/2007	16:00	RCB/RLS
MAGNESIUM	60.7	MG/L	0.006	0.024	200.7	03/08/2007	12:00	RCB
MANGANESE	55.1	UG/L	0.98	3.92	200.7	03/08/2007	12:00	RCB
POTASSIUM	13.6	MG/L	0.169	0.676	200.7	03/08/2007	12:00	RCB
SODIUM	196	MG/L	0.034	0.136	200.7	03/08/2007	12:00	RCB
STRONTIUM	5516	UG/L	1	4	2 00.7	03/08/2007	12:00	RCB
CHLORIDE	324	MG/L	0.353	1.412	300,0	03/08/2007	17:20	JSM
FLUORIDE	1.29	MG/L	0.030	0.120	300.0	03/08/2007	17:20	JSM
SULFATE	204	MG/L	0.339	1.356	300.0	03/08/2007	17:20	JSM
NITRATE NITROGEN	0.004 U	MG/L	0.004	0.016	353.2	03/07/2007	08:52	TDT
NITRATE+NITRITE	0.050 U	MG/L	0.050	0.200	353.2	03/07/2007	10:30	СВ
SILICA	18.9	MG/L	0.044	0.176	370.1	03/15/2007	10:20	TOT
BICARBONATE ALKALINITY	170	MG/L	0.594	2.376	SM2320B	03/08/2007	10:30	DS
CARBONATE ALKALINITY	0.594 U	MG/L	0.594	2.376	SM2320B	03/08/2007	10:30	DS
TOTAL ALKALINITY	170	MG/L	0.594	2.376	SM2320B	03/08/2007	10;30	DS
SPECIFIC CONDUCTANCE	1673	UMHOS/CM	1.24	4.96	SM2510B	03/07/2007	16:30	DS

EnviroAnalytical Inc.



NELAC Certification # E84167

NITRITE NITROGEN	0.003 1	MG/L	0.003	0.012	SM4500NO2B	03/07/2007	08;52	TDT
TOTAL SULFIDE	3.34	UG/L	0.028	0.112	SM4500S2D	03/07/2007	14;18	RCB
TOTAL ORGANIC CARBON	0.570 I	MG/L	0.271	1.084	SM5310B	03/11/2007	14:00	JS

Dale D. Dixon / Laboratory Director
Robert L. Sullivan/ Laboratory Manager

03/30/2007 Date

DATA QUALIFIERS THAT MAY APPLY:

A = Value reported is an average of two or more determinations.

B = Results based upon colony counts outside the acceptable range.

H = Value based on field kit determination. Results may not be accurate.

I = Reported value is between the laboratory MDL and the PQL.

J1 = Est, value surrogete recovery limits exceeded.

J2 = Est, value. No quality control criteria exists for component.

J3 = Est, value quality control criteria for precision or accuracy mot met.

J4 = Est. value. Sample matrix interference suspected.

US = Est, velue. Data questionable due to improper lab or field protocols

K = Off-scale low. Value is known to be < the value reported.

I. = Off-scale high. Value is known to be > the value reported

N = Presumptive evidence of presence of material.

Q = Sample held beyond accepted hold time.

T = Value reported is < MDL. Reported for informational purposes only and shall not be used in statistical analysis.

U = Analyte analyzed but not detected at the value indicated.

V = Analyte detected in semple and method blank.

Y = Analysis performed on an improperly preserved sample. Data may be inaccurate.

I = Data deviate from historically established concentration ranges.

7 = Data rejected and should not be used. Some or eff of QC data were outside criteria, and the Presence or absence of the analyte cannot be determined from the data.

* = Not reported due to interference.

NOTES:

PQL = 4xMOL.

MBAS calculated as LAS; molecular weight = 340.

X = Value exceed MCL.

G = CBOD ecouracy standard does not meet method QC criteria, but does not meet lab control limits that are in agreement with USEPA generated data. USEPA letter available upon request.

For questions and comments regarding these results, please contact Katharine Dixon at (941) 723-9986

Silver Lake Utilities
Analysis of Plant Operating Expenses - Salaries & Wages Component
Based on FDEP Plant Staffing Requirements

SCHEDULE 11

Revised Estimate - Salaries/Wages: Employee Count:	Part-time general labor 8 hours/week @ \$15/hour + 40% fringe benefit rate Sub-total:	Full-time general labor 40 hours/week @ \$15/hour + 40% fringe benefit rate Sub-total:	Full-time utility maintenance worker 40 hours/week @ \$20/hour + 40% fringe benefit rate Sub-total:	Part-time Class C certified operator 20 hours/week @ \$40/hour 8 hours/week @ \$40/hour + 40% fringe benefit rate Sub-total:	Full-time Class C certified operator 40 hours/week @ \$40/hour + 40% fringe benefit rate Sub-total:	Initial salary/wage estimates (annual): Plant avg daily flow operating at capacity (GPD):	Personnel Type
S						↔	Exi:
32,032 2	6,240 2,496 8,736			16,640 6,656 23,296		33,600 57,000	Existing Facilities
⇔						€	Muse (ph
218,400		31,200 12,480 43,680	41,600 16,640 58,240		83,200 33,280 116,480	300,000 466,667	Muse Potable (phase II)
 49						↔	Bu
23,296				16,640 6,656 23,296		25,000 500,000	Bulk Raw
₩						↔	Bulk
160,160 3		31,200 12,480 43,680	41,600 16,640 58,240	41,600 16,640 58,240		180,000 350,000	Bulk Treated
₩						↔	N Was
125,216 2	6,240 2,496 8,736				83,200 33,280 116,480	130,000 615,385	Muse Wastewater (phase II)