

REDACTED

EXHIBIT B

DOCUMENT NUMBER-DATE

05097 JUL 22 =

FPSC-COMMISSION CLERK

BEFORE THE FLORIDA PUBLIC SERVICE COMMISSION

DOCKET NO. 110009-EI

In re: Nuclear Cost
Recovery Clause.

REDACTED

CONFIDENTIAL TRANSCRIPT

TELEPHONE DEPOSITION OF: TERRY O. JONES

TAKEN ON BEHALF OF: Office of Public Counsel

DATE: June 22, 2011

TIME: Commenced at 9:34 a.m.
Concluded at 4:57 p.m.

LOCATION: 700 Universe Boulevard
Juno Beach, Florida

REPORTED BY: MARY ALLEN NEEL, RPR, FPR
Notary Public, State
of Florida at Large

ACCURATE STENOTYPE REPORTERS, INC.
2894-A REMINGTON GREEN LANE
TALLAHASSEE, FLORIDA 32308
850.878.2221

DOCUMENT NUMBER-DATE

05097 JUL 22 =

FPSC-COMMISSION CLERK

APPEARANCES:

FOR FLORIDA POWER & LIGHT COMPANY:

BRYAN J. ANDERSON, ESQUIRE
bryan.anderson@fpl.com
MITCHELL S. ROSS, ESQUIRE
mitch.ross@fpl.com
JESSICA CANO, ESQUIRE
jessica.cano@fpl.com
Florida Power & Light Company
700 Universe Boulevard
Juno Beach, Florida 33408-0420
Telephone: 561.304.5639

FOR FLORIDA INDUSTRIAL POWER USERS GROUP:

VICKI G. KAUFMAN, ESQUIRE
vkaufman@kagmlaw.com
Keefe Anchors Gordon & Moyle
118 North Gadsden Street
Tallahassee, Florida 32301
Telephone: 850.681.3828

FOR THE CITIZENS OF THE STATE OF FLORIDA:

JOSEPH A. MCGLOTHLIN, ESQUIRE
mcglothlin.joseph@leg.state.fl.us
Office of Public Counsel
111 West Madison Street, Suite 812
Tallahassee, Florida 32399-1400
Telephone: 850.488.9330

FOR THE FPSC STAFF:

KEINO YOUNG, ESQUIRE
kyoung@psc.state.fl.us
Florida Public Service Commission
2540 Shumard Oak Boulevard
Tallahassee, Florida 32399-0850
Telephone: 850.413.6248

APPEARANCES CONTINUED:

ALSO PRESENT TELEPHONICALLY:

JIM BREMAN
TIFFANY COHEN
JOHN COLEMAN
BILL JACOBS
MARK LAUX
JIM McGAUGHY
CLYDE NEWSON
BRIAN SMITH
CARL VINSON
BRUCE VEISLER

I N D E X

WITNESS	PAGE
TERRY O. JONES	
Direct Examination by Mr. McGlothlin	4
Cross-Examination by Ms. Kaufman	73
Cross-Examination by Mr. Young	102
EXHIBITS	
1 Answer to OPC's Interrogatory 50	20
2 Excerpt from 10/2010 ESC presentation, Bates 023298	27
3 Excerpt from 10/2010 ESC presentation, Bates 023299	30
4 (Late-filed) Explanation, Vertical Axis, Exhibit 3 to Jones Deposition	36
5 Excerpt from 09/2009 ESC presentation, Bates 000230	52
6 Answer to OPC's Interrogatory 77	63
7 (Late-filed) Finding of FPL's Audit for 2010 NCRC Costs	105
8 (Late-filed) Siemens Costs Associated With Rework Included in 2011 NCRC hearing	182
CERTIFICATE OF REPORTER	184
READ AND SIGN LETTER	185
ERRATA SHEET	186

PROCEEDINGS

1
2 The following deposition was taken on oral
3 examination, pursuant to notice, for purposes of
4 discovery, for use as evidence, and for such other uses
5 and purposes as may be permitted by the applicable and
6 governing rules. Reading and signing of the deposition
7 transcript by the witness was not waived.

8 * * *

9 THE NOTARY: My name is Annette Givens, and I
10 am a notary duly appointed and commissioned here in
11 the State of Florida.

12 Terry Jones, in the matter of Nuclear Cost
13 Recovery Clause by Florida Power & Light, Docket
14 No. 110009-EI, do you solemnly swear that the
15 testimony you're about to give is the truth, the
16 whole truth, and nothing but the truth?

17 THE WITNESS: Yes.

18 Thereupon,

19 TERRY O. JONES

20 the witness herein, having been first duly sworn, was
21 examined and testified as follows:

22 DIRECT EXAMINATION

23 BY MR. MCGLOTHLIN:

24 Q. Please state your name and business address
25 for the record, sir.

1 A. My name is Terry Jones. My business address
2 is 700 Universe Boulevard, Juno Beach, Florida.

3 Q. Mr. Jones, my name is Joe McGlothlin. You and
4 I have met before. I represent the Office of Public
5 Counsel in this case, and I have some questions for you
6 that relate to your prefiled testimony in this docket.

7 You've been deposed before, have you not, sir?

8 A. I'm sorry. I missed the last part of that
9 question.

10 Q. Have you been deposed in the past?

11 A. Yes.

12 Q. Then you're familiar with the procedure. If
13 at any point you don't understand my question, please
14 inform me of that so that we can work on it to the point
15 that you are comfortable that you're clear on what's
16 being asked of you. Will you do that for me?

17 A. Yes.

18 Q. I want to begin with a question that relates
19 to your May 2011 testimony. I'll give you a moment to
20 turn to page 7.

21 A. May 2011 testimony, page 7.

22 Q. Yes. At line 22, Mr. Jones, you say that FPL
23 has amended its EPC contract to include a target price,
24 and my question relates to that statement. But I would
25 like for you to begin by describing for me the overall

1 nature of the contract and the approach of the contract.
2 And specifically, for example, is it based primarily on
3 compensating the contractor on the basis of time and
4 materials?

5 MR. ANDERSON: Let's pause. We don't have a
6 problem with the question, but our testimony does
7 not line up with what you said there, Joe.

8 MR. MCGLOTHLIN: Well, we've had one other
9 instance of a difference in pagination, but give me
10 a moment.

11 THE WITNESS: Joe, line 22 for me starts with
12 the word "target price, better aligning FPL's and
13 Bechtel's project goals."

14 BY MR. MCGLOTHLIN:

15 Q. Well, you're very close to the area I'm asking
16 about, so I'll give you a moment to look at the larger
17 paragraph in context, and I think we can work from
18 there.

19 A. If you're asking me to read that paragraph,
20 I've read the paragraph.

21 Q. All right. And in that paragraph, do you
22 testify that FPL has amended the EPC contract to include
23 a target price?

24 A. That is correct.

25 Q. And in terms of the overall nature of the

1 contract, do I understand correctly that basically FPL
2 compensates Bechtel on the basis of time and materials?

3 A. That is correct. The Bechtel contract is a
4 time and material contract with a provision for target
5 pricing, [REDACTED]

6 [REDACTED]
7 [REDACTED]
8 [REDACTED]

9 Q. I'll follow up with that in a moment, but when
10 we talk about a contract that's based on time and
11 materials, does that mean that the contract specifies
12 hourly rates, and then the compensation is a function of
13 those hourly rates and the hours that the contractor
14 devotes to the task?

15 A. The contract does specify hourly rates,

16 [REDACTED]
17 [REDACTED]
18 [REDACTED]
19 [REDACTED]
20 [REDACTED]
21 [REDACTED]

22 [REDACTED]. Field non-manual is just a way of saying
23 hours spent on the project other than craft, like design
24 engineering hours, for example.

25 Q. Now, a portion of the tasks that are

1 encompassed by this contract relates to the
2 identification of modifications that surface in the
3 course of design engineering; is that correct?

4 A. I'm not sure I -- I don't understand your
5 question. Could you rephrase it or repeat it?

6 Q. I'll try. The project is currently in what is
7 described as the design engineering phase; correct?

8 A. It's in a couple of phases. One would be
9 still in the -- it's in the design engineering phase,
10 and it's also in the planning and implementation phase.
11 Those are happening in parallel.

12 Q. All right. And as part of the design
13 engineering phase, do the parties identify modifications
14 that must be performed as part of the overall EPU
15 project?

16 A. Yes, that's correct.

17 Q. What does the EPC contract envision with
18 respect to the contract for the construction of those
19 modifications?


20 A. I want to make sure I understand your
21 question. Are you asking me what does the contract
22 envision the construction to be in relationship to the
23 modification?

24 Q. And specifically, on what basis will the
25 contractor be paid with respect to the performance of


1 the construction of the modifications?

2 A. I understand the question. The contract is
3 structured such that for the construction portion of the
4 project, it's based on -- it is time and material. It
5 has a provision for target price that, for a scope of
6 work, if the two parties agree to a target price, then
7 the target price is established for that scope of work.

8
9
10
11
12
13
14
15
16
17
18
19
20
21
22
23
24
25




1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
17
18
19
20
21
22
23
24
25



Q. I believe you answered my question, but let me just follow up to make sure. With respect to the construction of the modifications, the compensation will be a function of time and materials as opposed to, for instance, separate bids for those projects; correct?

A.




1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
17
18
19
20
21
22
23
24
25



The further you get into -- let me pause there. There are a handful of modifications that we did not authorize Bechtel to perform the design engineering. Our evaluation was that there were other engineering firms that had performed work for us that could do that work more efficiently, and we in fact gave that work to those vendors.

The other part of that is, another example would be that for supplemental maintenance, we have contracts with other vendors to perform work such as, say, insulation or asbestos abatement or logistics support. And certainly we have some of that work parsed out to some of those competitors, because, again, with their familiarity with the site and their track record in performing that work,



Now, I wanted to go back to a statement I started to make. As you get further into these projects

1 and the complexity of the project, there's a
2 disadvantage to having too many cooks in the kitchen,
3 and we have to be very prudent in what work we hand off
4 and not have the unintended consequences of diluting
5 Bechtel's responsibility and accountability for the
6 performance of the project.

7 Q. Let's say hypothetically that you identify a
8 task or a project and decide that you're going to allow
9 entities other than Bechtel to bid for that. In that
10 instance, would Bechtel also be permitted to bid, or is
11 the contract its bid?

12 A. Bechtel would provide their detailed estimate
13 for what it would take to perform that scope of work,
14 and we would compare that to what a competitor would say
15 that that work could be done for.

16 Let me take that even a step further, in that

17
18

19 So in our view, if
20 there's a subcontractor that is very proficient in a
21 particular type of work -- for example, the connection
22 between the main generator to the main transformer that
23 transmits the power out to the yard, that connection is
24 referred to as an isophase bus, and there's a special
25 vendor that does that work for a living. We required

1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
17
18
19
20
21
22
23
24
25

[REDACTED]

Q. You mentioned in an earlier answer that the

[REDACTED]

A.

[REDACTED]

[REDACTED]

Q. Would you elaborate on that distinction?

You've anticipated my next question. On the one hand, you described a target price, and then you used the term "total installed cost." What is the difference?

A. The difference is that the total installed cost is -- I sound redundant. I'm answering the question with the answer. It is the total installed cost, in that -- let's say, for example, that Bechtel

1 had estimated 30,000 hours to replace feedwater heaters
2 -- that's a totally made-up number -- and it's a
3 well-vetted estimate, and we agree to that as the target
4 price, so it's well defined. And let's say that it
5 takes them 2,000 hours longer to do the work, but there
6 was no scope change. [REDACTED]

7

8

9

10

11

12

13

14

15

16

17

18

19

20

21

22

23

24


25



So why would -- let me explain how that --
what the push and the pull is then between our company
and why we have people directly managing Bechtel and
providing oversight. Bechtel would obviously -- let's
just set that name aside. It doesn't matter. Any EPC
that's on the target price would want an exact scope
definition, and if there was any scope addition, because
there's an incentive tied to the target price, they
would want the target price always to be adjusted to
exactly reflect a change in scope. That way, they're
not penalized in the incentive category for performing
their work exactly as planned.

That's only fair. [REDACTED]

1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
17
18
19
20
21



22 price. Does that make sense?

23 Q. That's helpful. I'm still not completely
24 clear on how you're using the two terms, target price
25 and total installed cost. Let me ask a question that

1 might get at it.

2 As you stated in an earlier answer, as the
3 design engineering process goes forward, FPL and the
4 contractor identify modifications that must be
5 constructed and implemented as part of the overall EPU
6 project; correct?

7 A. That's correct.

8 Q. Let's focus on a single such modification.
9 Under the EPC contract and under the process that you've
10 described, would FPL enter a separate contract specific
11 to that individual modification?

12 A. [REDACTED]
13 [REDACTED]

14 Q. [REDACTED]
15 [REDACTED]

16 A. [REDACTED]
17 [REDACTED]
18 [REDACTED]
19 [REDACTED]
20 [REDACTED]
21 [REDACTED]
22 [REDACTED]
23 [REDACTED]

24 Q. Well, let me modify my earlier question. Does
25 the target price apply to the overall EPU contract as


1 defined by the identified scope at a point in time?

2 A. I think the answer to that question is yes.
3 The target price is the agreed-upon price for the scope
4 of work at the time that we froze the date, so to speak,
5 for the modifications that had been identified up to
6 that point.

7 Q. Then how does the total installed cost, as you
8 are using that term, differ from the target price, as
9 you defined it a moment ago, for purposes of the EPC
10 contract?

11 A. For the purpose of the EPC vendor that you
12 entered into the target price negotiation and discussion
13 with, the total installed cost and the target price are
14 the same the day that you set it.

15 Q. All right. That answers my question.

16 A. Unless you set something aside. 

17
18
19
20



21 Q. I'm going to change subjects, and I'll ask you
22 to look at -- again, this is the May testimony, page 33.

23 A. I'm on page 33.

24 Q. And based on my copy, at lines 6 through 8 or
25 thereabouts, you should see this statement. You refer

1 to the approximately 50 percent completion of the design
2 modification phase of the project, which represents
3 approximately 625,000 hours of 940,000 hours of this
4 phase, as of April of 2011. Do you see that statement?

5 A. Yes, I do.

6 Q. And just so I'll understand any nuance with
7 respect to differences in terminology, you use the word
8 "design modification" there. Is that the same as design
9 engineering?

10 A. Yes, it is.

11 Q. How did you calculate the 50 percent that
12 appears in your testimony?

13 A. We looked at the number of earned hours on the
14 design engineering relative to the forecast of hours to
15 go for design engineering and came up with approximately
16 50 percent completion.

17 Q. What are earned hours?

18 A. Earned hours are a way of measuring the
19 progress of engineering work on construction, and that
20 would be that if it takes ten hours to complete five
21 calculations, if that's what the estimate is from an
22 engineering perspective, you don't -- even if you
23 worked, say, 15 hours to complete those 10 calculations,
24 you earned 10 hours on the project. You may have
25 expended 15, but you earned only 10. Similarly, if you

1 completed it in eight hours, you expended eight, but you
2 earned 10 hours on your forecast.

3 So we used that to measure productivity in
4 engineering. You look at the forecasted hours on a
5 modification-by-modification basis. And we track the
6 actual hours, and we track actual progress by looking at
7 the state of the deliverable and how far along that
8 modification is to come up with the earned hours, the
9 actual ratio.

10 Q. Okay. I understand then that the earned hours
11 concept relates to a measure of productivity. Is that
12 different than an assessment that is based upon the
13 degree to which modifications have been completed?

14 A. No. It's actually -- it's actually a measure
15 to know how complete a design modification is. In a
16 design modification, let's say, that someone wants to
17 complete, for example, there are, depending on the
18 complexity, hundreds of thousands of steps. So we
19 establish interim milestones and measurements along that
20 design modification process.

21 Q. Let me ask you to look at FPL's answer to
22 OPC's Interrogatory No. 50. That's in OPC's Sixth Set
23 of Interrogatories.

24 A. Okay. I'm there.

25 MR. MCGLOTHLIN: I'm going to provide a copy

1 of this to the court reporter and ask her to mark
2 it as Exhibit 1 to the deposition.

3 (Deposition Exhibit Number 1 was marked for
4 identification.)

5 BY MR. MCGLOTHLIN:

6 Q. You'll see in the -- let me just read for the
7 record the question. "Please refer to Exhibit TOJ-17.
8 Please break down the PCM standards numbers by Turkey
9 Point 3, Turkey Point 4, St. Lucie 1, and St. Lucie 2."
10 First all, what does the acronym "PCM" mean?

11 A. Plant change modification.

12 Q. So a single PCM would correspond to one of the
13 individual modifications that we've described in earlier
14 questions and answers; correct?

15 A. Yes. It's a design engineering package. That
16 would be the industry generic term.

17 Q. And you'll see in -- first of all, did you
18 supply the answer to this interrogatory, Mr. Jones?

19 A. This answer was prepared under my direction.

20 Q. Okay. You'll see that the information
21 provided is as of April 18, 2011; correct?

22 A. That's correct.

23 Q. And I'm looking at the right-hand column
24 captioned "Final." And at the bottom of that table,
25 there's a percent which I understand to mean the overall

1 percent of PCMs, and it says the final completion is
2 31 percent. Do you see that?

3 **A.** Yes, I do.

4 **Q.** Would you explain for me any differences
5 between the 31 percent that's calculated and reported
6 here in response to Interrogatory 50 and the 50 percent
7 figure that you include in your testimony?

8 **A.** Yes. This answers a very specific question
9 with regards to the status of the design modification
10 packages. So that 31 percent, as you'll note, is in the
11 column titled "Final," which means of the total number
12 of design modification packages that have been
13 identified as of that date, only 31 percent of that
14 total number of modification packages is complete.

15 Design modification packages are not equal.
16 Some design modification packages take 500 hours of
17 engineering. Some take 10,000 engineering man-hours to
18 complete. And so we have a number of tools that we use
19 to determine where we are in progress and productivity.

20 So this is another way to look at how many of
21 the modification packages are across the finish line and
22 ready for construction estimates. And that's very
23 important to us, because we're doing these in sequence,
24 and we need the modification packages for the first
25 outage first as opposed to the modification package for

1 the second outage.

2 Q. I think I understand. Let me ask a couple of
3 questions that will effectively read back to you what I
4 believe what you told me to make sure that I understand.

5 As I understand your answer, the response to
6 Interrogatory No. 50 indicates that of the 209 different
7 modifications, 31 percent of those 209 modifications
8 have reached the final stage of design engineering; is
9 that correct?

10 A. Yes, 31 percent of the 209 packages are final
11 and approved.

12 Q. And the other packages which have not reached
13 a state of completion are at various stages of
14 completion, and this reports the number that are at 30
15 percent and 90 percent; correct?

16 A. That is correct.

17 Q. And then in your testimony, you say
18 approximately 50 percent of design engineering has been
19 accomplished. But that 50 percent takes into account
20 not only those individual items that are final and
21 complete, but also those that are at various stages of
22 completion; is that correct?

23 A. That is correct.

24 Q. You would agree with me, wouldn't you, sir,
25 that a modification must be completed before procurement

1 can begin and implementation can begin?

2 A. No, I do not agree.

3 Q. Okay. On what basis do you disagree?

4 A. I disagree. With some engineering done, I can
5 develop a procurement spec and procure a long-lead item
6 without the design modification package being at
7 90 percent or even final. In some cases, it might even
8 be at 30 percent.

9 Q. So you're disagreeing with my earlier question
10 related to the procurement aspect of it. You would
11 agree that you can't construct and implement a
12 modification until the design engineering has been
13 completed; correct?

14 A. I disagree with that as well.

15 Q. On what basis?

16 A. You can start the plan and construction at
17 risk before the design modification is complete.

18 Q. Explain how that would work.

19 A. The way that would work is, you would spec it
20 out, rough out some drawings, issue procurement specs,
21 say, for structural steel. You would give preliminary
22 information to construction planners, who would take
23 that and produce work instructions at risk. Between the
24 construction organization and engineering organization,
25 they have the ability to say, "Well, we know for certain

1 that this I-beam is going to have to go here, and we're
2 going to need concrete pads at this location and this
3 location and this location," and so you can proceed at
4 risk doing that. There is less than a 1 percent chance
5 that we would have to rework that or change that.

6 And so that would allow you, again, with all
7 the appropriate project management approvals, to start
8 that procurement, start that construction at risk -- and
9 we have a process that controls that -- and allow the
10 further details of the structural modification, conduit
11 runs, cable pulls, to proceed in parallel.

12 Q. I would like to apply your answer to the
13 situation in which the work is going to be performed
14 during an outage of the nuclear unit. Is it true that
15 the -- and let's use the example of a specific
16 modification. Would the design engineering have to be
17 completed on that modification at some point during the
18 window of opportunity presented by the outage of the
19 nuclear unit before it could be constructed and
20 implemented?

21 A. The design engineering has to be completed to
22 turn the component or the system over to the operating
23 authority of the plant. The design engineering does not
24 necessarily have to be completed to complete the
25 physical construction and/or startup testing of the

1 component. Typically it is, or it is at such a point
2 that there may be a couple of remaining calculations to
3 do that are low risk and not going to change the output.

4 But typically, the typical construction
5 project engineering is done done, then you do planning
6 and construction, then implementation and testing, and
7 then turn over to operation. But I'm talking about our
8 fast track process that we're using on this project and
9 we've used on other nuclear projects.

10 Q. For my next question, I will be referring to a
11 PowerPoint slide taken from the October 2010
12 presentation to the Steering Committee. The Bates
13 number is 023298.

14 MR. ANDERSON: That's one we don't have handy
15 here, Joe. I don't think that was on your list,
16 but we can do some digging.

17 MR. MCGLOTHLIN: I would appreciate it if you
18 would do that. Rather than jump around, I would
19 like to progress in this sequence.

20 MR. ANDERSON: Could you tell us again the
21 document so we can look and verify?

22 MR. MCGLOTHLIN: Yes. I'm going to be
23 referring to two pages from that same presentation.
24 The first is FPL Bates 023298, and then the
25 following page, 023299.

1 MR. ANDERSON: Just give us a second and we'll
2 get that for you.

3 MR. MCGLOTHLIN: Sure. And I'm confident
4 that's is from the October 2010 ESC meeting.

5 MR. ANDERSON: Okay. October 2010. Just a
6 second.

7 MR. MCGLOTHLIN: Bryan, would you prefer to
8 take a five-minute break and then come back after
9 you've had a chance --

10 MR. ANDERSON: Just a second.

11 Yes, we're going to need to find that
12 document.

13 MR. MCGLOTHLIN: Okay. I'm going to put you
14 on mute, and let's just take five. I'll be back at
15 about 22, 23 after.

16 MR. ANDERSON: Okay. Thanks.

17 (Recess from 10:16 a.m. to 10:25 a.m.)

18 MR. ANDERSON: We have the two pages you
19 specifically asked for here, and I'll let you go
20 ahead.

21 BY MR. MCGLOTHLIN:

22 Q. Mr. Jones, my next question relates to a page
23 bearing FPL Bates stamp number 023298 taken from the
24 PowerPoint slides that were presented to the Executive
25 Steering Committee in October of 2010. Were you present

1 at that meeting of the Executive Steering Committee?

2 A. I don't recall.

3 Q. In your present capacity of vice president,
4 uprates, do you participate in the preparation of the
5 presentations for the Executive Steering Committee?

6 A. Yes, they're prepared under my direction.

7 Q. Would you have been involved in the
8 preparation of this particular document?

9 A. Yes. Yes, that's correct.

10 MR. McGLOTHLIN: Okay. I'm going to mark this
11 as Exhibit 2 to the deposition, and I'll provide a
12 copy to the court reporter.

13 (Deposition Exhibit Number 2 was marked for
14 identification.)

15 BY MR. McGLOTHLIN:

16 Q. I'm going to read the top caption under the
17 word "Confidential." The caption says, "The project is
18 in the design phase and is approximately 23 percent
19 complete." First of all, the word "project" relates to
20 the overall EPU project; correct?

21 A. Yes, that's correct.

22 Q. And looking at the table in the middle of
23 Exhibit 2 to the deposition, you'll see the same type of
24 format that was in the last document I inquired about,
25 and you'll see in the right-hand column, Final, the

1 23 percent that corresponds to the caption that I read.
2 Do you see that?

3 A. That is correct.

4 Q. And then underneath the table, there's a key
5 with four bullet points, and the last bullet point reads
6 as follows: "Final - Reviews completed and approved by
7 plant general manager for issuance."

8 Do I understand correctly that this last
9 bullet point is intended to describe how the 23 percent
10 figure was derived?

11 A. The last bullet point is to present to the
12 senior executives not that familiar with our processes
13 what "final" means. "Final" means the package is
14 complete.

15 This table was constructed to try and
16 demonstrate to those not familiar with the project that
17 you have a large number of modification packages and no
18 packages are entirely equal to each other, and paint a
19 picture of what has been initiated, to demonstrate
20 what's still left to even start, as well as the progress
21 of each one of these packages. That's the intent of the
22 slide, is to give them a feel for the number of
23 modification packages that are actually done done.

24 Q. And in terms of a basis for comparison, this
25 format and this definition of "final" squares with the

1 answer to Interrogatory 50 that I showed you earlier,
2 does it not, in terms of the meaning of "final" as used
3 in both those documents?

4 A. That's correct.

5 Q. And does it follow, based on your answer, that
6 between October 2010 and April 2011, the status of the
7 design engineering phase of the EPU project, as defined
8 by the word "final" as used in those two documents,
9 moved from 23 percent to 31 percent? Correct?

10 A. I'm looking to make sure that -- yes. As of
11 April 18, 2011, there were 209 modifications identified
12 as compared to -- (inaudible).

13 Q. Would you repeat that answer for the court
14 reporter? You faded there just a bit.

15 A. As of April 18, 2011, the total number of
16 packages that were final was 65, which represents
17 31 percent of the total number that were currently
18 identified, which was 209. That compares to 46 packages
19 that had been done at the time that the data was frozen
20 for the purposes of putting together the Executive
21 Steering Committee presentation, 46 packages of 202 that
22 had been known, which represented 23 percent of those
23 packages were in final status.

24 Q. You make a fair point, and I think your point
25 is that between October 2010 and April 2011, the number

1 of needed modifications increased; is that right?

2 A. That's correct.

3 Q. But in terms of assessing the extent to which
4 engineering and design has been completed, as measured
5 by the word "final" as defined, as of April 2011, that
6 degree of completion had increased only 8 percent;
7 correct?

8 A. That's right.

9 Q. Now, if you'll turn to the following page from
10 that presentation, 023299, based on your earlier answer,
11 I assume you would have been involved in either
12 preparing or supervising the preparation of this page as
13 well; correct?

14 A. That is correct.

15 MR. MCGLOTHLIN: I'm going to mark this as
16 Exhibit 3 to the deposition.

17 (Deposition Exhibit Number 3 was marked for
18 identification.)

19 BY MR. MCGLOTHLIN:

20 Q. I'll read for the record the top caption, and
21 then I'm going to ask a couple of questions about what's
22 displayed below the caption. The top caption reads as
23 follows: "Design for fall 2011 outage remains behind
24 plan. The bulk of remaining will be issued out by
25 December for the lead unit."

1 My first question is, it appears that
2 something either was omitted or was believed to be
3 implicit there. The bulk of remaining what, Mr. Jones?

4 **A.** I'm not 100 percent certain. The way I read
5 that is -- my understanding of that is that the
6 remaining packages for the first unit would be complete
7 by December.

8 **Q.** Okay. And the reference to the lead unit is
9 St. Lucie, which is first up in the order of
10 implementation; correct?

11 **A.** St. Lucie Unit 2.

12 **Q.** And then the caption above the table itself
13 reads, "St. Lucie Design Modification Status." And --

14 **A.** That's right. That's for both units.

15 **Q.** Okay. Well, thank you for that clarification.

16 You'll see some line graphs that appear in
17 three colors spanning the period from January '10 to
18 July '11. On the vertical axis is the degree of
19 completion expressed in percentages; is that right?

20 **A.** That's correct. And that means an actual
21 modification package complete as opposed to percentage
22 of engineering total hours.

23 **Q.** In other words, this is expressed in terms
24 that are consistent with the first page I showed you,
25 023298, in terms of how the word "final" is defined;

1 correct?

2 A. That's correct.

3 Q. And the green chart is captioned "Plan." How
4 is the word "plan" used there?

5 A. Plan was at a juncture in time the plan for
6 the completion of the modification packages, so that was
7 a base line plan.

8 Q. And was that plan developed for the purposes
9 of positioning FPL to undertake the implementation
10 during the refueling outages, the first of which is in
11 November 2011?

12 A. The plan is based on having the modifications
13 ready for the refueling outage as well as completing the
14 engineering within a certain forecast number of hours.
15 In other words, for each modification package, we did an
16 estimate for Bechtel of the number of engineering hours
17 it's going to take to complete that package. That was
18 the best available information at that time.

19 We load that into a detailed Level 3 schedule.
20 We monitor progress against that. Once a week we look
21 at the project progress, the design evolution, and
22 adjust the schedule forecast accordingly.

23 Q. Okay.

24 A. This would have been a plan based on some
25 known scope. At some given point in time, that plan

1 curve would have been established.

2 Q. Focusing for a moment -- did you finish your
3 answer?

4 A. Yes.

5 Q. Okay. Focusing for a moment on the green line
6 that represents the plan, I want to draw your attention
7 to the value on that line for the date October 2010,
8 which was the date of the Steering Committee meeting for
9 which this was formulated. Do you see that?

10 A. Yes.

11 Q. And if I'm reading the line graph correctly,
12 did the plan contemplate that the design modifications
13 would be -- that something like 34 percent of the
14 modifications would be at the final stage as of that
15 date?

16 A. Can you repeat the question?

17 Q. Yes. I'm focusing now on the date
18 October 2010, which you will see falls between the two
19 months of September and November on the horizontal axis.
20 And the value for October 10 represented by the green
21 line graph, which was the plan -- do you see that?

22 A. Yes, I do.

23 Q. Would that value be approximately 33,
24 34 percent represented by the little square on the line?

25 A. Maybe I'm not with you. I'm looking at the

1 blue line and the gold line where they join.

2 Oh, are you talking about the green line? The
3 green line would be 34 percent.

4 Q. Yes. The green line is the plan; right?

5 A. Yes. It's somewhere between 30 and 34
6 percent. Yes, I agree.

7 Q. And then the blue line represents the actual
8 state of completion as defined in the terms that you and
9 I discussed; correct?

10 A. That is correct.

11 Q. And that shows a value in the low 20s, which
12 corresponds to the 23 percent shown on page 023298;
13 correct?

14 A. That is correct.

15 Q. And then as you said in an earlier answer,
16 there is a junction between the --

17 MR. ANDERSON: Let's pause for a moment, Joe,
18 because there's no percentage indicator in the
19 left-hand column or anything, and it's unclear
20 whether that's percentage or number of mods, for
21 example. For example, on page 19, the following
22 page, it goes zero to 80, and I just want to make
23 sure we're clear on what this is or is not.

24 MR. MCGLOTHLIN: Well, let's put that question
25 to Mr. Jones.

1 BY MR. MCGLOTHLIN:

2 Q. Mr. Jones, what does the vertical axis
3 represent on page 023299?

4 A. I think it represents the percentage of total
5 packages complete, but I'm not entirely certain. I
6 would have to go back and validate that.

7 MR. ANDERSON: It's just not labeled, Joe.
8 That's why I'm being very cautious, so we're not
9 guessing.

10 MR. MCGLOTHLIN: Well, to the extent that
11 you're unsure, would you provide us a late-filed
12 exhibit that would either confirm your
13 understanding or inform us as to what the vertical
14 axis represents?

15 MR. ANDERSON: If you want us to just take a
16 second, we can probably run that down on the fly
17 here and not need to do that.

18 MR. MCGLOTHLIN: I would prefer that.

19 MR. ANDERSON: Okay. Just a second.

20 (Recess from 10:42 a.m. to 10:44 a.m.)

21 MR. ANDERSON: Joe, we've checked here and
22 really cannot determine from looking at the
23 document, so a late-filed will be the way to go.
24 We need to check back with some other business
25 people.

1 MR. MCGLOTHLIN: Okay. Late-filed Exhibit 4
2 will be "Explanation, Vertical Axis." And what did
3 we call this? Exhibit 3 to the deposition?

4 MR. ANDERSON: That's what you had done, yes.

5 MR. MCGLOTHLIN: "Explanation, Vertical Axis,
6 Exhibit 3 to Jones Deposition."

7 MR. ANDERSON: Agreed. Thanks.

8 BY MR. MCGLOTHLIN:

9 (Late-filed Deposition Exhibit Number 4 was
10 identified for the record.)

11 BY MR. MCGLOTHLIN:

12 Q. Mr. Jones, my questions to you about 023299
13 are premised on my understanding that the vertical axis
14 is intended to represent percentage of completion, and I
15 just want to finish my questions with that understanding
16 in place, and then if that has been in error, we can go
17 from there. But in earlier answers, you had agreed that
18 the green line called "Plan" contemplated that
19 34 percent or thereabouts of the modifications would be
20 -- the design engineering for about 34 percent would be
21 complete and final as defined by these documents. But
22 as of the date of the October meeting, October 2010
23 meeting, only about 23 percent had been completed.

24 Now, I draw your intention to the intersection
25 of the blue line representing actual and what appears on

1 my copy to be a yellow or gold line. Do you see that?

2 A. Yes.

3 Q. And the key indicates that the gold line
4 represents a forecast. Would that be a forecast of the
5 rate by which the design engineering for the remaining
6 items will be completed?

7 A. Yes, that would represent Bechtel's schedule,
8 their forecast for the design engineering for the known
9 scope.

10 Q. I see. So the information underlying the gold
11 line was based on representations by Bechtel as to what
12 they thought they could do; is that correct?

13 A. That's correct. We turn the schedule weekly
14 with Bechtel, look at their progress and their forecast
15 on an individual, modification-by-modification basis.

16 Q. And looking at the last entry on the
17 horizontal axis on the right-hand side, July 2011,
18 you'll see that the green line of the plan and the
19 yellow line of the forecast converge at about
20 90 percent. Do you see that?

21 A. Yes.

22 Q. And do I understand correctly that the
23 forecast represents the predicted effort to catch up,
24 for lack of a better term, to arrive at the same
25 90 percent called for by the plan, but with an

1 accelerated rate of completion? Is that correct?

2 A. Yes, that is correct, as a result of -- and
3 it's on the slide that they're behind on their
4 engineering. They identify the modifications as more
5 complex, requiring more engineering hours, and going to
6 require the addition of more engineers to perform that
7 engineering. So this is the forecast they provided
8 based on their assessment at that time; that is correct.

9 Q. Now, earlier I referred you to the answer to
10 Interrogatory 50, which reported that as of April 2011,
11 31 percent of the design engineering of the
12 modifications had been completed and were final. Do you
13 recall that document?

14 A. Yes.

15 Q. So if we were to look at the horizontal axis,
16 March and May are represented, so April would be halfway
17 between those. And if we would put a point at 31 on the
18 vertical axis, that would show us where the actual blue
19 line would have been as of April 2011; correct?

20 A. I'm sorry. Can you repeat that?

21 Q. Yes. We established through the answer to
22 Interrogatory 50 that as of April 18, 2011, the
23 percentage of the modifications for which design
24 engineering had been completed and are final was
25 31 percent; correct?

1 A. That's correct.

2 Q. So if we were to enter that value, 31 percent,
3 on this same 023299 that you have in front of you, we
4 would go to the horizontal axis and find March and May
5 and identify April as being halfway between those two,
6 and then we would go up on the vertical axis to the
7 point that corresponds to 31 percent on the vertical
8 axis; correct?

9 MR. ANDERSON: Joe, are you asking only as to
10 St. Lucie or both plants? Because your
11 Interrogatory No. 50 refers to both plants, and
12 your Exhibit 3 only refers to Lucie.

13 MR. McGLOTHLIN: I see. I think you make a
14 good point.

15 BY MR. McGLOTHLIN:

16 Q. Is there a way to break out from the
17 information shown on Interrogatory 50 the degree of
18 completion that relates to St. Lucie?

19 A. There is. Let's see. You would take the --
20 in Interrogatory No. 50, you would take the currently
21 identified modifications, 46 and 49, and combine those.
22 That would be a total of 95 design modification packages
23 identified as of April 18th, 2011. Clearly, there would
24 have been -- and then you would say 15 and 17 is 32 of
25 95, so that would be certainly greater than 32 percent.

1 Clearly, there would have been fewer
2 modifications for St. Lucie back in the September time
3 frame, early October time frame, but not -- let's see.
4 No, it doesn't look substantially different, because
5 looking at 023298, the currently identified number is
6 95, and in Interrogatory No. 50, St. Lucie is 95, so
7 that's the same. So that would be -- so 32 of 95 is
8 final, whatever percentage that is, 34 percent.

9 Q. So instead of the 31 percent that would apply
10 to both St. Lucie and Turkey Point, to enter the value
11 that would correspond to the actual percentage of
12 completion final as of April 2011, we would enter about
13 34 percent there; correct?

14 A. That's correct.

15 Q. And the forecast had contemplated that as of
16 April 2011, the percentage would be approximately 60 or
17 61 percent; correct?

18 A. Yes. That was contingent on Bechtel obtaining
19 the additional resources to perform the work.

20 Q. Now, does the current plan contemplate that
21 the percentage of modifications that have reached the
22 final stage will be 90 percent by July 2011?

23 A. By current plan, you mean today's plan?

24 Q. Yes, today's plan, and focusing on St. Lucie
25 for the purpose of this question.

1 A. Joe, the difficulty I have in answering that
2 question is that this is a gross level, intended for an
3 executive audience, number. The tracking mechanisms
4 that we use as an indicator are the total hours, earned
5 hours, and need date. We have dozens of milestones that
6 are established for each one of these modifications all
7 the way through implementation. So we want all the
8 engineering done as quickly as possible. That gives us
9 a larger planning horizon. Then we also have the need
10 date, which is it's needed by the next milestone for the
11 planning and for the outage. Does that answer your
12 question?

13 Q. I think it answers my question in part. Let
14 me --

15 A. I don't have the forecast in front of me.

16 Q. Okay. I'm going to give you an opportunity to
17 provide that explanation, but I want to ask a couple of
18 preliminary questions. It would appear to me that in
19 using the same definitions, the same bases that were
20 used for the presentations to the Steering Committee,
21 and given, as you agreed, that as of April 2011, the
22 percentage of modifications for which design engineering
23 had been declared final was 34 percent as opposed to the
24 60 percent or more that had been part of the forecast,
25 either the rate of completion would have to be

1 accelerated even more severely to reach 90 percent by
2 July 11 or the schedule itself would have to be pushed
3 back. Would you agree with that observation?

4 A. I agree that we either had to add additional
5 resources to complete the work or allow the schedule to
6 move to the right. What we did is, we made sure that
7 the design modification packages that were needed for
8 the outage that started January 2nd got completed and
9 made the balance of the modification packages a lower
10 priority, just as in the refueling outage, I made the
11 priority for design engineering to support the refueling
12 outage we were in, the engineering changes that had to
13 be made and the adjustments that had to be made to the
14 design modifications to support construction, I made
15 that a higher priority than advancing the engineering
16 schedule for the next outage.

17 The next outage is November 26th, and I made
18 it a priority of Bechtel to go get the additional
19 resources to complete those design modification packages
20 in time to support the planning for the November 26th,
21 up to and including frequent meetings with their
22 executive management every two weeks, including driving
23 down to subcontract out a portion of the engineering to
24 support what I call a recovery plan to ensure they did
25 not jeopardize the St. Lucie fall outage.

1 Q. Well, as of today, are you confident that the
2 resources are in place and the design engineering is
3 proceeding at a pace that will enable FPL to adhere to
4 the scope of work to be completed during the November
5 2011 outage?

6 A. I'm reasonably confident that the plan that we
7 have put in place -- and this plan has been in -- this
8 recovery plan and getting the resources, getting the
9 right resources and not just throwing bodies at it,
10 subcontracting out to a number of proven engineering
11 firms, it has actually taken several months to get to
12 the place as we now have the body -- qualified, I should
13 say. Take "body" out. We now have what I think is a
14 good, solid plan for the November outage for St. Lucie.

15 Q. Can you identify for us the specific
16 modifications that are essential for the November 2011
17 outage and the status of the engineering and design work
18 on those at this point?

19 A. That would take some time. There are a large
20 number of modifications, and I would have to go to the
21 detailed engineering report to give you the status on a
22 modification-by-modification basis. But that's doable.

23 Q. That's probably more detail than I want for
24 this purpose. But if it's possible to get a high level
25 description of the major tasks that need to be in place

1 for that outage, that would be helpful.

2 A. Joe, if I can have a minute to think about how
3 I could do that? Would it be okay if I take a minute or
4 two to think about how to do that?

5 MR. MCGLOTHLIN: Sure. As a matter of fact,
6 we've had you working for a while. It's right at
7 11:00. Let's take seven or eight minutes and come
8 back. That might be enough time for a comfort
9 break too.

10 (Recess from 11:01 a.m. to 11:12 a.m.)

11 BY MR. MCGLOTHLIN:

12 Q. I know there's a question pending, Mr. Jones,
13 but I would like to back up and lay the premise for that
14 in a bit better way, if I may. I think you can glean
15 from the questions the direction our questions are going
16 and the concern that they reflect, and it is this: I
17 think you agree that based upon the discussion of
18 023299, FPL observed that Bechtel was behind the plan,
19 and in October, it became apparent that Bechtel would
20 have to make up ground to get back on the plan. That
21 was in October 2010. As of April 11, they were even
22 further behind.

23 And my question to you was, based upon the
24 state of completion as it existed in April 2011 and the
25 degree of additional acceleration that would be required

1 to enable Bechtel to reach the target of 90 in July of
2 2011, does FPL continue to say it's realistic to
3 anticipate that FPL is going to be in a position to
4 accomplish everything required in the November 2011
5 outage to maintain the schedule for completion of the
6 the EPU project?

7 That was a long question, I understand, and if
8 you need, I'll break it down. But that's the source of
9 my inquiry, and that's why I asked you to give us a high
10 level description of those priorities that have to be in
11 place for you to stay on schedule.

12 A. The answer to that question is yes, and let me
13 elaborate. While I don't agree with the
14 characterization that Bechtel is behind, the
15 characterization is that the engineering isn't at the
16 point that we had originally planned it. Some of that
17 is because of the design evolution, the iterative nature
18 of the engineering where you go down one path and you
19 don't get an acceptable result, and you have to continue
20 to go further down that path or an alternate path to get
21 to what I would call an acceptable result. Typically
22 that involves margin or operational concerns. I sensed
23 a characterization of poor performance, and I completely
24 disagree with that.

25 Another portion of this is, that's part of

1 project management. You're looking at a high level
2 executive summary slide. We look at on a mod-by-mod
3 basis every single day the status of these
4 modifications, what are the hard spots, whose house is
5 it in, do we need a piece of information from a vendor
6 or manufacturer, do we need a response from a systems
7 engineer at the plant, does a particular Bechtel
8 engineer need help?

9 So that's a very detailed plan, and staff's
10 report has looked at every day detailed milestones,
11 intermediate mileposts along the way, including, because
12 there are thousands, literally thousands of activities,
13 we only roll the schedule once a week. But we know on a
14 mod-by-mod basis what the need date is to support the
15 construction plan. And the way this is constructed, the
16 way this project plan is put together -- you know, part
17 of project management is -- part of the reason the
18 engineering packages are not across the finish line is
19 that we redirected Bechtel's priorities based on
20 changing needs, based on outage support.

21 Now, once we made that change in priorities,
22 we said -- well, actually, when we made them. As we
23 contemplated the decision to put that resource there, we
24 knew that that would cause this schedule to move to the
25 right, that it would impact the downstream outage.

1 Having said that, we said that to be able to do these in
2 parallel is going to require more resources, and these
3 aren't the kind of people you just get off the street,
4 so we're using a number of specialty nuclear vendors to
5 do that.

6 So when you ask me am I worried about the fall
7 outage, I'm concerned. We expressed as early as October
8 that I was concerned, and we work daily with our vendors
9 to address that concern and mitigate those concerns.
10 That's what we do with these complex projects. And the
11 plan that we're on supports that November 26 start for
12 that outage, and we status it every day.

13 Now, in regards to what type modifications
14 we're doing for this Unit 1, I think the easiest way to
15 get there is if you refer to my May 2, 2011 testimony,
16 TOJ Exhibit 24, starting at page 4 of 16. You'll see
17 not only a list of the modifications, but you'll see a
18 description of the modifications and which vendor
19 organization has accountability for that modification.

20 I think another characterization here is that
21 Bechtel is doing all the design engineering. And as I
22 said, part of this project management is to choose the
23 most qualified, most efficient vendor, but not so much
24 that we wind up with too many cooks in the kitchen, to
25 be able to accomplish these modifications. So I would

1 call your attention to that exhibit and give you a
2 moment to get there.

3 Q. Yes. You have me scrambling here, which is
4 only fair, since I've done that to you numerous times.
5 What was that reference again?

6 A. That would be the May 2nd, 2011 filing, TOJ
7 Exhibit 24, page 4 of 16.

8 Q. Okay. I have it.

9 A. So at the top of that, you see 2011 Extended
10 Power Uprate (EPU) Project Work Activities, and then the
11 left-hand column, the far left-hand column labeled
12 "St. Lucie Unit 1 Fall 2011 Outage." So reading left to
13 right, you have the outage designator. Below that is a
14 short title in regards to the modification, then a
15 description, and then the governing contract for that
16 modification. The type of -- do you have it?

17 Q. Yes.

18 A. The type of modifications, some of the larger
19 scopes of work, if you go to page 5 of 16, feedwater
20 heater replacement, that's to replace the number 5
21 feedwater heaters. TEI is the vendor responsible for
22 building the heaters. The actual installation will be
23 done by Bechtel.

24 And generator core iron replacement, which is
25 at the bottom of page 5 of 16, that is part of a fixed

1 price contract with Siemens.

2 On the next page, page 6 of 16, the main
3 generator hydrogen coolers and the main generator rotor
4 replacement and stator rewind, those are two scopes of
5 work at Siemens that involve rewinding the main
6 generator.

7 At the bottom of that page is the replacement
8 of the HP rotor. That involves disassembling the high
9 pressure turbine casing, changing out the steam path,
10 and replacing the HP rotor. That will do the lion's
11 share of the work to produce the additional megawatts.

12 On the next page, page 7 of 16, the first two
13 items. Isophase bus duct cooling, that's how the
14 generator is connected to the transformer outlet to the
15 switch yard. And main turbine rotor refers to replacing
16 the two low pressure rotors, which is the scope of work
17 that was just completed on St. Lucie Unit 2 for the
18 additional megawatts there.

19 So as you can see, there's quite an extensive
20 list of mods here. And so in regards to the status of
21 each one of those modifications, engineering planning
22 has a much more detailed report that I don't have at my
23 fingertips, but that's something that is gone through by
24 them on a daily basis and I review on a weekly basis
25 with the project team. And they are on track for the

1 November 26 outage start.

2 Q. Okay. So each of the items that you've
3 identified in the left-hand column corresponds to one of
4 the modifications that are tallied in the documents that
5 we've been looking at?

6 A. Yes. The reason I pause is because TOJ
7 Exhibit 24 is a list contract by contract and purchase
8 order. I would have to look back to see what the first
9 TOJ-24 was, whether it was to list all the contracts or
10 list all the modifications. Suffice it to say, it's a
11 good, comprehensive list of the modifications that we're
12 doing.

13 Q. In some of the documents provided to us in
14 discovery, we've seen reference to what is called a
15 Bechtel recovery plan. Are you familiar with that term?

16 A. I'm sorry. A what?

17 Q. A Bechtel recovery plan.

18 A. I'm familiar with the term.

19 Q. Does that refer to the need for Bechtel to
20 accelerate the design engineering so as to get back on
21 schedule?

22 A. No. The Bechtel recovery plan is -- when we
23 decided to fast track these modifications, we decided to
24 follow our fast track process, which means we're already
25 beyond our normal design modification planning

1 milestones or construction planning and implementation
2 milestones. So to get back to that schedule is not
3 possible, because we were already beyond those
4 milestones when we initiated the project.

5 The recovery is really more about here's where
6 we are today, and how do we get to the next intermediate
7 milestone that we've established for the successful
8 implementation of the modifications during the outage.
9 It doesn't necessarily involve accelerating something.
10 It also involves moving modifications around or pulling
11 other modifications forward and pushing other
12 modifications aside. It also involves doing some
13 planning at risk. There's a number of levers to pull.

14 Q. Do you have available to you the document
15 bearing Bates stamp number 000230?

16 MR. ANDERSON: What is the document?

17 MR. MCGLOTHLIN: It's one of the PowerPoint
18 slides taken from the September 2009 presentation
19 to the Executive Steering Committee.

20 MR. ANDERSON: Just a second.

21 MR. MCGLOTHLIN: I hope it's one of the
22 documents that I identified to you prior to the
23 break.

24 MR. ANDERSON: It is, but we're just getting
25 it in front of us. Just a second.

1 MR. MCGLOTHLIN: Okay.

2 MR. ANDERSON: We have the document, and we're
3 prepared. Go ahead.

4 MR. MCGLOTHLIN: Okay. This will be what?
5 Number 5, Mary? This will be Exhibit 5 to the
6 deposition. And it's a one-page excerpt from the
7 September 2009 presentation to the ESC.

8 (Deposition Exhibit Number 5 was marked for
9 identification.)

10 BY MR. MCGLOTHLIN:

11 Q. At the bottom of the page you'll see
12 highlighted, Mr. Jones, this statement: "Engineering
13 and design will complete in December of 2010 improving
14 cost certainty." Do you see that?

15 A. Yes, I do. That was the belief at the time by
16 the project team based on the known scope and the plan
17 with our vendors.

18 Q. The preliminary question is this. Again, I
19 want to be careful that I understand any differences or
20 nuances in terminology. The term here is "engineering
21 and design." Is that the same thing as design
22 engineering?

23 A. It's hard for me at this juncture to know
24 exactly the context of that statement in regards to
25 whether we were referring to LAR engineering and design

1 engineering.

2 Also, I don't recall -- in fact, I don't --
3 it's not clear to me that that's intended to mean the
4 lead unit. There's just no way that we're all going to
5 be able to go back to September of 2009 and, without
6 doing a whole lot of research here, figure out what was
7 our outage implementation plan at that particular date,
8 which unit was the lead unit, and how many total
9 modifications were there at that time, and what our
10 thinking was. I'm just telling you where I'm at. We
11 have many outages, many issues past that.

12 Q. Well, given that the term is used in
13 conjunction with describing the status of cost
14 certainty, as I understand FPL's presentations, cost
15 certainty increases as design engineering progresses; is
16 that correct?

17 A. That is correct. As design engineering
18 completes, you gain greater certainty; as construction
19 planning completes, you gain even more certainty; and
20 you're really certain when you're done.

21 Q. My understanding, based upon the relationship
22 between the subject of cost certainty and the type of
23 engineering that's being discussed here, is that the
24 references to engineering completion that appear on the
25 top and engineering and design that appear in this lower

1 banner are interchangeable with design engineering. Do
2 you disagree?

3 A. That's speculation. The purpose of this slide
4 was to communicate to the senior executives a picture
5 of -- at this juncture in time, we were going through an
6 extensive effort to come up with a way to forecast the
7 total project cost that could be a sound basis, and so
8 any changes that would be known or understood, and we
9 were trying to explore ways to do that with not much
10 engineering done. And the purpose of this slide was for
11 the senior executives that don't have a major
12 construction project background to -- as I recall this
13 entire presentation, that's the theme, is what makes up
14 a major complex project like a nuclear power plant, what
15 are the uncertainties that you have to deal with, and
16 when can you expect certainty to come to the project.
17 That's what we were trying to communicate and convey and
18 give the Executive Steering Committee things by which
19 they could measure progress against, and so that slide
20 is part of that context.

21 Q. I'll change subjects for my next line of
22 questions. I have a couple of questions about the
23 estimate that was put together by Highbridge. Can you
24 describe to me whether and how the Highbridge estimate
25 was incorporated in the development of the range of

1 estimated costs in your testimony?

2 A. Joe, the question was -- I want to make sure
3 I'm answering your question. The question is how was
4 Highbridge used in determining the range, the nonbinding
5 cost estimate range?

6 Q. I guess it's in two parts. The first is was
7 it used, and if so, how?

8 A. Are you referring to the May 2, 2011?

9 Q. Yes.

10 A. Or are you referring to the May 2010 filing?

11 Q. I'm referring to the most current range of
12 estimates.

13 MR. ANDERSON: So you're referring, Joe, for
14 clarification, to the May 2, 2011 nonbinding cost
15 estimate range; is that right? You just used the
16 words "current estimate." I just want clarity
17 around what we're talking about.

18 MR. McGLOTHLIN: Okay. Well, you've reminded
19 me that I need to be careful in how I put this
20 question together.

21 BY MR. McGLOTHLIN:

22 Q. Was the Highbridge estimate used in either the
23 2010 or 2011 estimates, and if so, how?

24 A. Joe, I would like to start with the 2010 if
25 that's okay with you.

1 Q. Okay.

2 A. The second half of July -- the second half of
3 2009 and the first quarter of 2010, we went through an
4 extensive effort to come up with the nonbinding cost
5 estimate range for a major construction project to
6 operate a nuclear facility for which very little
7 engineering had been done. As we explored options and
8 opportunities, there were a number of firms out there
9 that perform what I call a bottoms-up estimate.

10 What a bottoms-up estimate is, they will
11 estimate a given modification as if the engineering is
12 100 percent complete and say, "How can they do that?"
13 Well, they will make assumptions on how many nuts,
14 bolts, hangers, pipe, pumps, whether it's 16-inch
15 diameter weld or a 14-inch diameter weld, and they will
16 reduce all that to writing. And then they will apply
17 unit rates, and they will roll that up into a
18 modification-by-modification estimate. So there are a
19 number of firms out there that do that, and Highbridge
20 is one of those firms.

21 We contracted Highbridge to do that for Turkey
22 Point Unit 3. There were a number of modification
23 packages that had been completed that would allow them
24 not to have to make -- really very few assumptions on
25 those packages. And then the balance of those packages,

1 there was essentially no engineering done, and they
2 would have to apply their process. They've done this on
3 a number of major projects, and we've reviewed those,
4 and they have a pretty good track record.

5 Our intent when we brought them in was to have
6 them complete all that work in time for our filing. It
7 turned out to take longer and be more complex than what
8 we had estimated. We had some preliminary information
9 on the early modifications, so we did use that as one of
10 our inputs to the nonbinding estimates.

11 Our other estimates were whether or not we
12 would self-perform all or a portion of the work, whether
13 or not we would bring in a competitor EPC to put out the
14 work, whether or not we would defer units to allow us to
15 better perform the work, any number of alternatives,
16 high risk specifically. That's how they were utilized
17 in 2010 for the nonbinding estimate.

18 The additional benefit that we got out of that
19 was, for the modification package that had been complete
20 and Bechtel had provided construction estimates, that we
21 now had something to leverage Bechtel with to have them
22 reduce their construction estimate, as it turned out,
23 for the best 2010.

24 Q. Was the Highbridge estimate used or
25 incorporated in the 2011 range of estimates?

1 A. Yes, in this manner: We used -- when we were
2 establishing the target price for St. Lucie, we again
3 engaged Highbridge to provide their input for the
4 modification packages that had been completed and those
5 in some form of completion for the St. Lucie power
6 plant, and that helped form the basis in negotiations
7 for the target price for St. Lucie. The target price
8 obviously is a significant input into the overall
9 project forecast, because we say the target price is X,
10 this is what we think we're going to spend for Turkey
11 Point, and that's why, and X plus Y equals Z.

12 As far as Turkey Point, the Highbridge work
13 stands as it is. And we built off of their work as we
14 continued to forecast the project on a month-over-month
15 basis. So their original work was the basis for the
16 going-forward forecast on that project with scope adds
17 and scope deletions. But to bring Highbridge back and
18 have them do another body of work at Turkey Point, that
19 was not done for the 2011 forecast.

20 Q. Focusing on the Highbridge estimate developed
21 for Turkey Point 3, as I understand it, Highbridge's
22 estimate was based upon its review of 40 modifications;
23 is that right?

24 A. I don't know. I would have to look that up.

25 Q. Highbridge reviewed fewer than the total

1 modifications that are required for Turkey Point 3; is
2 that right?

3 A. I don't know the answer to that question. I
4 don't have the Highbridge report in front of me. Am I
5 supposed to have that?

6 Q. That was one that we identified, at least a
7 portion of it.

8 A. Okay. Hold on.
9 I have the report.

10 Q. I don't intend to make that an exhibit, but --

11 A. It does say engineering and implementation
12 costs for Unit 3's specific modifications, direct costs.

13 And, Joe, I just -- let's see. What's the
14 date of this? Well, obviously, it's fewer than the old
15 number of modifications for the Turkey Point project.
16 It would have been the number -- we would have frozen
17 the line, and it would have been the number of
18 modifications that we had identified up to that point
19 that we authorized them to go work, if that makes sense.

20 Q. Yes. The answer to Interrogatory 50 indicates
21 that there were at that point 55 modifications for
22 Turkey Point 3. I was curious to understand better how
23 the fact that Highbridge reviewed fewer than the total
24 number of modifications would have affected the
25 estimate. Were those additional modifications taken

1 into account, or were they simply not part of the
2 Highbridge scope of work?

3 A. Interrogatory 50 was as of April 18, 2011.
4 The number of modifications for Turkey Point Unit 3 at
5 55 is -- it's certainly more than 40. But I'm certain
6 we didn't have 55 modifications back in -- I think we
7 actually started this in December of 2009, if I recall.
8 Give me just a second to take a look at this report.

9 I call your attention to the executive
10 summary, page 456 of the report. At about the third
11 line down, halfway through, it says the baseline cost
12 estimate was to include direct costs for design and
13 implementation for all projects and all associated
14 support and direct management cost. Initially the scope
15 of the estimate was to include as many as 55 individual
16 modification projects. However, due to incomplete and
17 ongoing LAR process, the project scope continues to
18 evolve.

19 The project scope for this baseline estimate
20 was frozen on January 19, 2010, and includes only the
21 44 -- I'm sorry, February 19, 2010, and includes only
22 the 44 expected projects as of that date. With design
23 in progress, those projects included in the fall 2010
24 outage, Highbridge incorporated all design information
25 available, but many of the 44 estimated projects had

1 been estimated from conceptual data only. That was the
2 scope of Highbridge's body of work.

3 Q. Yes, and that's consistent with my
4 understanding. And my question simply is, in view of
5 the fact that Highbridge reviewed 44 of the
6 modifications, which was fewer than the total that
7 existed at that time and an even smaller percentage of
8 the modifications that have been identified to date, did
9 FPL take any steps, by means of extrapolation or other
10 types of adjustment, to take into account that
11 Highbridge's work product reviewed less than the total
12 scope of the St. Lucie project -- I'm sorry, the Turkey
13 Point project?

14 A. Yes, I understand Joe. I don't think it was
15 less than the identified modifications at the time. I
16 think it said 44 were expected, and 44 is what they
17 estimated. I'm not sure what his reference is to 55. I
18 think that's purely coincidental to the 55 that's
19 currently identified. But as I explained, their job was
20 to even take a conceptual modification and reduce to
21 writing the assumptions and forecast what it will take
22 to do the design and what it will take to construct it.

23 Now, Highbridge was just one input into the
24 nonbinding cost estimate. We obviously had all of
25 Bechtel's information on what they thought they would

1 need for a total number of engineering man-hours, or I
2 should say man-years, and what they had estimated in
3 craft hours for that scope of work. And we certainly
4 had our construction experts reviewing those estimates
5 and assumptions, and we certainly had the projected head
6 counts going all the way into the out years, which is,
7 you know, one of the major cost drivers.

8 And so all those things were used to produce
9 the nonbinding cost estimate, including looking at -- we
10 even looked at the trend of discovery, at what rate were
11 we discovering things through engineering, whether it be
12 LAR engineering or design engineering, and where -- you
13 know, if we stayed on that current trend, where would we
14 expect that trend to break over and that rate of
15 discovery to decline. So we factored in a number of
16 inputs to come up with that cost estimate range.

17 Q. I think I understand.

18 I have one more line of questions for you, and
19 I'll refer to the answer to Interrogatory No. 77. And a
20 copy of that will be Exhibit 6 to the deposition.

21 MR. ANDERSON: We need to take a second to
22 find it. Just a second.

23 MR. MCGLOTHLIN: Okay.

24 (Deposition Exhibit Number 6 was marked for
25 identification.)

1 MR. ANDERSON: We have it, Joe. Go ahead.

2 BY MR. MCGLOTHLIN:

3 Q. Mr. Jones, did you provide the answer to OPC's
4 Interrogatory No. 77?

5 A. It was provided at my direction.

6 Q. Okay. This statement appears in your answer:
7 "FPL's nonbinding cost estimate range encompasses an
8 expected level of uncertainty with respect to project
9 scope and project cost at the time of the submission of
10 his testimony, which reflected a range of minus zero
11 percent to plus 7 percent." Do you see that statement?

12 A. Yes, I do.

13 Q. And this is in response to -- the question
14 reads, "At a stage of 50 percent design completion, what
15 is the expected level of uncertainty with respect to
16 project scope?" And as we've discussed earlier,
17 Mr. Jones, as used in your May testimony, 50 percent
18 design completion refers not to the percentage of
19 modifications for which design engineering has been made
20 final, but rather to the overall state of completion of
21 all of the modifications in various states; correct?

22 A. That's correct.

23 Q. Now, when you said in your answer that the
24 range is minus zero percent to plus 7 percent, does that
25 mean that the risk of incurring a cost in excess of the

1 stated range is that it will not exceed an additional
2 7 percent of costs?

3 A. No, that's not what that means. What that
4 means is that at the time of our March forecast, our
5 range that we established for our May testimony was
6 basically zero percent of the -- if you backed out the
7 undefined scope, it was based on backing out that
8 undefined scope, zero percent of that forecast, which
9 was the best information we had at that time, plus
10 7 percent to bind the upper range. And so the way that
11 we arrived at that, as I already mentioned -- just a
12 second.

13 We looked at what we had in our risk matrix,
14 looked at the rate of change of that risk, looked at
15 what was in our undefined scope and the rate of change
16 of that, compared that to our January forecast, which
17 was the upper end of the range. So we based it on the
18 maximum risk exposure that we've identified through
19 January the 20th, plus potential risk associated with
20 doing the generator core replacement at Turkey Point.
21 And we based it on what we felt the undefined scope may
22 grow to based on a line-item-by-line-item contingency
23 assessment.

24 By that I mean the long-lead materials are 95
25 percent committed, so really, you don't need much

1 contingency there. The LAR engineering, that has all
2 been submitted to the NRC, and our cost associated with
3 that in responding to their questions, and having to
4 submit those engineering man-hours to respond to their
5 questions, so a very, very small percentage of
6 contingency applied to that.

7 If we look at the to-go cost of each one of
8 those major categories, we said, "Where is all the
9 risk?" All the risk is in the implementation, trying to
10 predict that implementation in the out years for the
11 2012 outages. So that's where we -- that contingency
12 needs to be around 20 to 30 percent. So we adjusted our
13 undefined scope to establish that, and that established
14 an upper end of the range, but that range was based on
15 our information January through March and our to-go
16 forecast in each one of those categories.

17 So is there uncertainty in the nonbinding cost
18 estimate range? Yes, because we are about -- at this
19 juncture, about 60 percent of the way through our design
20 engineering. But as you can see, year over year, the
21 magnitude of the change is less, and I would expect it
22 to be -- I would expect that to continue on that trend
23 next year.

24 Q. I think I understand your answer, and I
25 believe your response to my question is that to the

1 extent there is uncertainty in the range, that has been
2 captured in the bottom and top of the range; is that
3 correct?

4 A. I want to make sure I'm crystal clear on this.
5 We have a project forecast. The project forecast is,
6 you know, we're just off the coast of Florida, and we're
7 headed to Spain, and we're plotting a certain course,
8 and based on our best available information, we've
9 forecasted what it's going to take to finish the
10 engineering and construction planning and do the
11 implementation. A portion of that forecast is really
12 solid, really firm, like long-lead material, like the
13 balance of the LAR engineering. And even the to-go
14 design engineering is becoming more firm in this latest
15 round of adding the additional resources. So we looked
16 at that, and we made a conscious decision to stick with
17 a range.

18 Anytime someone sees a number, they tend to
19 look at it like they're buying a pair of tennis shoes,
20 and it's \$23.99. That's not what we're dealing with
21 here, and it's misleading to put an exact number. So
22 we're really dealing with a range.

23 I think in our discussions, I said, "Well,
24 given those factors I just gave you, we have a project
25 forecast which rolls up to a number." And you said, "Is

1 it likely to go lower?" Well, there's some probability
2 it may go lower, but not much. There's a possibility it
3 could go higher. It could, but not in the immediate
4 short run. As we get through the engineering and
5 construction planning, the range may have to be adjusted
6 up. There is some probability of that. But I wanted to
7 make sure there was a strong basis for the upper end of
8 the current range.

9 Q. If I understood your answer, the basis for
10 that upper end relates to FPL's quantification of the
11 undefined scope that remains in the project?

12 A. Yes. When you put the project in buckets -- I
13 want to try this again. I think it's worth spending a
14 minute on if you'll indulge me a minute.

15 Q. Go ahead.

16 A. When I look at engineering, or when I look at
17 -- when I look at engineering, the LAR engineering
18 bucket and the LAR engineering resources to respond to
19 the regulatory requirements, could there be additional
20 modifications that come out of the NRC's review and
21 approval process? Yes. I've had that experience, even
22 as late breaking as a month before the outage. The
23 probability is low, but it's still there.

24 Then I have the project management, the FPL
25 infrastructure to oversee this complex project. There's

1 not a lot of variability there, so I would not have
2 assigned additional contingency to that.

3 Then I have my long-lead materials, which is
4 already 95 percent committed. If you look at my
5 contingency analysis, I don't have a lot of contingency
6 assigned to that.

7 Then when you get to my implementation, or
8 when you get to my design engineering, since I'm 60
9 percent of the way through, yes, I've assigned the
10 contingency that more resources may be necessary,
11 because we may have additional design evolution, and to
12 stay on track, we may need to apply additional
13 resources.

14 And then when you look at my construction,
15 that is at a very early stage. That's where I see our
16 greatest risk and where we should apply more
17 contingency.

18 And so when you asked me, "Terry, the upper
19 end of your range exceeds your forecast. If I go to
20 your project management book and I look at your
21 spreadsheet and it rolls up to a number, it exceeds your
22 project forecast. How is it that that's the case?"
23 Well, I'm trying to forecast what could happen in the
24 implementation or the design engineering, and a single
25 number would be misleading. It's inappropriate, because

1 we still have a number of these projects that are the
2 conceptual phase.

3 Q. You used some terms there that also appear
4 elsewhere in testimony and in discovery, and I want to
5 make sure that I understand how you're using these
6 terms. And I'm talking about risk, uncertainty, and
7 contingency, which all seem to be, at least to this
8 layman, related.

9 Do I understand correctly that uncertainty is
10 the risk that one's projected value may be in error or
11 inaccurate, and that the contingency is the measure
12 that's put in place to take into account and provide for
13 that uncertainty and that risk? I am saying that
14 correctly?

15 A. That's close. Here's the way I define
16 uncertainty. Uncertainty is that I don't know what I
17 don't know, and there's that potential for discovery.

18 Q. I've been there.

19 A. Okay. And being a nuclear guy, I don't like
20 that, but it is what it is. I'm an operations guy. I
21 like step-by-step procedures, and I like everything with
22 a nice, tight little bow around it.

23 So uncertainty is that I don't know what I
24 don't know. And actually, as a clear operations guy, I
25 was always trained that that's out there, even in

1 operations, so it actually serves me well in
2 construction.

3 Risk, as we define it, as we use it -- it's
4 true that in the overall context, risk and uncertainty
5 are the same thing. In the context that we use it
6 within the project, we have known risk, and we use a
7 risk register for someone to know that back 20 years ago
8 there was this problem with the Turkey Point steam
9 generators, and you may not be able to just dispose of
10 that secondary equipment or even salvage it. You may
11 have to treat it, give it special treatment, and that
12 could cost millions of dollars. If anyone on the
13 project, external or internal on the project raises a
14 concern that there is risk, we try and quantify it with
15 a probability and a dollar amount, so we'll give that
16 risk a weight.

17 But in the context of a project, I have a risk
18 matrix, and so in my everyday language, when I talk
19 about risk, I talk about those things that have bubbled
20 up and maybe not completely dispositioned yet, but
21 they've been identified, and they contribute to the
22 project forecast.

23 Does that make sense? Contingency and
24 undefined scope are words that are used interchangeably.

25 Q. So would it be fair -- based on your answer,

1 would it be fair to say that this 7 percent is the
2 contingency measure that has been incorporated in the
3 estimate of costs that you provided in your May
4 2nd testimony?

5 A. I would say the undefined scope that's part of
6 the forecast is based on our contingency analysis, where
7 we know from experience on major projects about what
8 percentage contingency you should have for
9 implementation or design for where you are right now in
10 the project. And obviously, if -- so our undefined
11 scope number, the upper end of the range reflects, based
12 on the to-go engineering today -- well, not today. I
13 should back it up to when we established this back in
14 March, right, or the January forecast. That day we said
15 we've got however many hundreds of thousands of
16 engineering hours left, and that equates to this amount
17 of cost. We said the right level of contingency for
18 that is X. And then we looked at implementation, and we
19 said the right amount of contingency for that is Y, and
20 we said that should establish the upper end of the
21 range.

22 As we move forward, there's language, there's
23 language that additional engineering hours will be
24 required, that additional implementation hours will be
25 required, and your contingency or your risk really

1 doesn't change that much. As you complete construction
2 or you complete design engineering, you would hope that
3 you could reduce that contingency, but if you have new
4 discoveries that add on a bulk of hours, what you've
5 reduced your contingency by because you made progress
6 just got offset by your new scope, if that makes sense.

7 Q. I think I follow. Let me just ask it this
8 way. You provide in your testimony a range of estimates
9 for the cost of the uprate projects. What contingency
10 factor have you incorporated in your estimate of costs?
11 How would you quantify it?

12 A. The undefined scope, the low end of that range
13 is -- of the 2,324 million dollars is about 72 million.
14 And for the upper end of that range, it's 190 -- of the
15 2,480 million dollars, it's 195 million. And that was
16 based on the undefined scope that existed on January 31,
17 2011.

18 MR. MCGLOTHLIN: I've completed my questions.
19 Thank you for your time, Mr. Jones.

20 MS. KAUFMAN: This is Vicki Kaufman. I have
21 some questions also. I didn't know if you all were
22 intending to take a lunch break or what.

23 MR. ANDERSON: We're going pause and just
24 check people for logistics.

25 (Discussion off the record.)

1 MR. ANDERSON: If we're looking at a lot of
2 time like that, we should probably take a break for
3 lunch.

4 MS. KAUFMAN: How long do you need, or how
5 long would you like? Do you want to come back at
6 1:00? Is that enough time?

7 MR. ANDERSON: We're just checking calendars.
8 12:45.

9 MS. KAUFMAN: Works for me.

10 MR. ANDERSON: Okay. We're going to hang up,
11 then, and redial in at that time.

12 MR. MCGLOTHLIN: All right. That will be
13 good.

14 (Recess from 12:07 p.m. to 12:46 p.m.)

15 CROSS-EXAMINATION

16 BY MS. KAUFMAN:

17 Q. Okay. Are you all set, Mr. Jones?

18 A. I'm ready. Thank you.

19 Q. Great. I'm Vicki Kaufman, and I'm here on
20 behalf of the Florida Industrial Power Users Group. I
21 hope you had a good lunch. I don't have as many
22 questions as Mr. McGlothlin, so maybe it won't take
23 quite as long for me.

24 I'm going to be starting out, though, with
25 your March 1, 2011 testimony, if you want to grab that.

1 A. This is Terry Jones. Are you referring to the
2 March 1, 2011 testimony?

3 Q. Yes, I am.

4 MS. CANO: And just for clarity, Vicki, you're
5 speaking about the March 1, 2011 testimony that
6 addresses 2009 or the March 1, 2011 testimony that
7 addresses 2010?

8 MS. KAUFMAN: I'm going to start with the
9 2009.

10 BY MS. KAUFMAN:

11 Q. Are you set?

12 A. Yes, I have it.

13 Q. And actually, before I go there, I wanted to
14 go back a minute and kind of step back. Mr. McGlothlin
15 asked you a series of questions regarding your cost
16 estimates and whatnot for the EPU project, and what I
17 would like to know -- I'm not sure I followed all that,
18 but what I would like know is, as we sit here today,
19 what is your estimate of the total installed cost for
20 that project?

21 A. The answer to that question is in my May 2,
22 2011 testimony. It's found on page 6, lines 9 through
23 14, which is that we've updated our nonbinding total
24 cost estimate range to reflect the progress made on the
25 project and information learned through the beginning of

1 2011 to approximately 2,324 million to 2,479 million,
2 which includes the transmission and carrying costs.

3 Q. Thank you for that reference.

4 What is the projected in-service date for the
5 project?

6 A. The projected in-service date, the megawatts
7 come on line in sequence with the refueling outages.
8 For example, we just placed megawatts in service with
9 the St. Lucie Unit 2 outage that completed -- the outage
10 dates are included in the testimony. I don't have them
11 all memorized off the top of my head. But St. Lucie
12 Unit 1 will be in the early part of 2012. Turkey Point
13 Unit 3 will be in the first half of 2012, and Unit 4
14 will carry over into -- will start at the end of 2012
15 and complete and go in service the first quarter of
16 2013.

17 Q. So is it fair to say that the entire project
18 it's estimated now will be in service by the beginning
19 of 2013?

20 A. It's correct to say that the project will be
21 completed in its entirety by the first quarter of 2013.
22 The majority of the megawatts will be in service by the
23 summer of 2012.

24 Q. I understand. Thank you.

25 Okay. Now, turning back to your testimony, at

1 the very beginning on page 1, you describe your position
2 and your responsibilities, and currently you're the Vice
3 President, Nuclear Power Uprate; correct?

4 A. Correct.

5 Q. And you assumed that position in August 2009;
6 is that right?

7 A. That's correct.

8 Q. Now, who held that position immediately prior
9 to your assuming it?

10 A. I'm thinking if there was an exact equivalent
11 position to my position. If you could give me a moment,
12 I'm looking up the organizational chart. Just a moment.
13 I'm looking.

14 Thank you. I have it in front of me. Rajiv
15 Kundalkar was the Vice President, Nuclear Power Uprate.

16 Q. He was in that position immediately prior to
17 you assuming it in August 2009?

18 A. Yes, but it wasn't a like-for-like position.
19 He had responsibility for the extended power uprate, all
20 other major capital projects outside of EPU, and also
21 the nuclear fuels organization that is responsible for
22 the reactor core designs and procurement of nuclear
23 fuel.

24 Q. So is it correct to say that a subset of what
25 your position involves now, and I guess when you took it

1 over in August of 2009, is a subset of what
2 Mr. Kundalkar's responsibilities were?

3 A. That's correct.

4 Q. What was your position prior to taking the
5 position in August 2009?

6 A. My position was Vice President of Operations,
7 Midwest Region.

8 Q. What did your responsibilities include there?

9 A. My responsibilities, I had -- I was directly
10 responsible for the operations of two nuclear power
11 plants in the Midwest, Duane Arnold located near Cedar
12 Rapids, and Point Beach Nuclear Power Plant located in
13 northern Wisconsin.

14 Q. So was the position you assumed in August 2009
15 the first time you had worked on a Florida nuclear
16 project for Florida Power & Light?

17 A. No. In fact, I started my career with Florida
18 Power & Light at Turkey Point Nuclear Power Plant in
19 operations.

20 Q. How long were you out in the Midwest Region?

21 A. That specific job assignment was a little over
22 a year. Prior to that, I was Vice President of Plant
23 Support, so I had responsibilities for -- I had
24 responsibilities associated with all five of our nuclear
25 sites in the area of security, turbine services, reactor

1 services, and others for two years. So that was a -- in
2 both that position and the Midwest position, I was
3 located at corporate here in Juno.

4 Q. This testimony that we're looking at involving
5 2009, did you have any familiarity with the uprate
6 project in 2009 prior to taking your position in August?

7 A. Yes. In fact, the extended power uprate was
8 under way at Point Beach Nuclear Power Plant.

9 Q. I'm talking about the uprate project that's
10 the subject of your testimony.

11 A. Yes, I was familiar with the project, familiar
12 in that this project was an organization under way. It
13 was a general familiarity.

14 Q. I'm sorry, but you kind of cut out on that
15 answer, if you wouldn't mind repeating it.

16 A. I was familiar in that, given my position at
17 corporate, I knew that there was an extended power
18 uprate under way for the Florida plants, an organization
19 that was performing that project, a general familiarity
20 with the type of project it was and the people involved.

21 Q. So is it fair to say that you were familiar
22 with it on a high level, but not regarding the
23 day-to-day operations of the project?

24 A. I was familiar with -- it is fair to say that
25 I was familiar with it at a high level.

1 Q. In this testimony that we're looking at
2 regarding 2009, did some of the activity that you are
3 discussing in that testimony occur prior to your
4 assuming your position in August?

5 A. To be clear, you're referring to the March 1,
6 2011 testimony on the extended power uprates, 2009?

7 Q. I am.

8 A. The question was, are there activities
9 described in this testimony before I became directly in
10 charge of extended power uprate?

11 Q. That's my question.

12 A. I'm just taking a moment to thumb through the
13 testimony.

14 Yes, I believe that is a fair
15 characterization.

16 Q. So for the information that you provided in
17 your testimony that concerns activities before
18 August 2009, where did you get that information from?

19 A. The information in my testimony is readily
20 available in the project reports, documents, emails,
21 auto reports, photographs, contracts, and provided by
22 the subject matter experts on the project.

23 Q. Did you review all this material before
24 drafting this testimony?

25 A. The testimony was prepared at my direction.

1 Q. Who prepared it?

2 A. There were a number of people involved that
3 prepared this testimony.

4 Q. Who were they?

5 A. Bruce Veisler --

6 Q. I'm sorry. Again, you're fading out.

7 A. Bruce Veisler, Clyde Newson --

8 Q. What? Go slowly, because some of these names
9 I'm not familiar with. The first one you said was
10 Mr. Feisler?

11 A. Veisler.

12 Q. Chrysler, like the car?

13 A. No.

14 Q. I'm sorry.

15 A. I'll spell it. V-e-i-s-t-e-r. I'm sorry, L,
16 V-e-i-s-l-e-r. And Clyde Newson, N-e-w-s-o-n. Those
17 are two that I interfaced with directly. They get
18 information from the project controls organization from
19 each site as well as contract information from our
20 integrated supply chain and other sources. With a
21 project this big, there's many sources to provide the
22 information.

23 Q. So were these two gentlemen the primary
24 drafters of the testimony? I assume they're gentlemen,
25 not ladies.

1 A. They are gentlemen. I don't know if they were
2 the primary drafters of the testimony.

3 Q. So are you saying that you don't know who
4 drafted your testimony? I'm just not clear.

5 A. I'm saying that I don't word for word, line by
6 line, who wrote the testimony. As I stated earlier, I
7 know of at least two contributors, and there may be
8 more. These are the two that I interfaced with on a
9 routine basis.

10 I read every word of my testimony. And we
11 have a verification means for the information that comes
12 in to verify that it's true and correct. And my
13 testimony is not filed without my approval.

14 Q. Did you verify personally all the information
15 in here to be sure it was true and correct, or did you
16 rely on someone else to do that?

17 A. We have a process for people to verify that
18 the information that they are providing is true and
19 correct. For example, if you look at the tables that I
20 referred to earlier, like TOJ-24 that lists all the
21 modifications and purchase order numbers, I do not go
22 and lay my hands on the hundreds of purchase orders and
23 verify that that purchase order is the exact right
24 number. So when people provide a purchase order number,
25 they are signing that they have verified that that

1 information that they are providing is correct.

2 Q. So as I understand what you're saying, you
3 rely on others to go and verify the information in the
4 testimony that you then review at the end of the
5 process?

6 A. I'm involved in process as well as final
7 process, that's correct. And, yes, I rely on the
8 subject matter experts to verify the veracity of the
9 information that they are providing.

10 Q. If you could, estimate how many people
11 contributed, provided information, or verified what was
12 in your testimony. Do you have any idea?

13 A. I don't know the exact number. It would be
14 several.

15 Q. Is that less than five? I mean, what does
16 several mean?

17 A. I'm thinking that between the project controls
18 organizations and my group here, there were probably at
19 least half a dozen people involved in the preparation of
20 my testimony.

21 Q. And can you name the other four people besides
22 the two gentlemen, or you don't know who they are?

23 A. Well, Don Fleetwood, my project controls
24 director, would be involved in the preparation of my
25 testimony. Steve Reuwer, R-e-u-w-e-r, the

1 implementation owner, would be involved in my testimony,
2 and the project controls supervisors at each one of the
3 sites.

4 Q. Did you say at each of the sites? I'm sorry.

5 A. Yes, the project controls supervisors at each
6 of the sites contribute. My license amendment
7 engineering manager, Liz Abbott, provides input and
8 contributes.

9 Q. Are you done? I'm sorry. I didn't know if
10 you were thinking or you were finished.

11 A. I'm finished. There may be others.

12 Q. To your knowledge, have any of those people
13 filed testimony in this docket?

14 A. No.

15 Q. Are you -- Mr. Jones, are you familiar with
16 the Concentric report?

17 A. Is the question am I familiar with the
18 Concentric report?

19 Q. I'm sorry. Let me get closer. Yes.

20 A. Yes, I am.

21 Q. Were you interviewed for that report?

22 A. Yes, I was.

23 Q. Do you know when that was?

24 A. No, I don't recall the specific point that
25 that interview occurred.

1 Q. Were you involved in the decision-making to
2 engage the firm that did the Concentric report?

3 A. No, I was not. That was our legal group.

4 Q. Have you reviewed the report?

5 A. Yes, I have.

6 Q. Were any of the changes that were recommended
7 in the report implemented in your area?

8 A. I provided verbal feedback to --

9 MR. ANDERSON: Vicki, what are you referring
10 to?

11 MS. KAUFMAN: Do you want me to refer him to a
12 page?

13 MR. ANDERSON: Yes.

14 MS. KAUFMAN: Hang on.

15 BY MS. KAUFMAN:

16 Q. I'll refer you to that page in a moment, but
17 tell me what sort of verbal feedback you provided,
18 Mr. Jones.

19 MR. ANDERSON: Just so record is clear, what
20 are you doing now, Vicki? You had asked about
21 implementation of recommendations in the report.
22 You're not asking that question now? You're moving
23 on; is that right?

24 MS. KAUFMAN: I'm going to go back because
25 Mr. Jones was beginning to tell me that he had

1 provided some verbal input when you asked your
2 question, Bryan, so I was just going to follow on
3 that.

4 MR. ANDERSON: Okay. Go ahead. Why don't you
5 ask your question?

6 BY MS. KAUFMAN:

7 Q. Mr. Jones, you were beginning to tell me that
8 you provided some verbal input in regard to the report.
9 Did I understand that?

10 A. Yes. I thought that's what your question was
11 as a follow-up to the review. When I reviewed the
12 report, I provided verbal feedback to Concentric.

13 Q. Did you review a draft report, or did you
14 review a final report?

15 A. I reviewed a draft report as well as
16 eventually a final report.

17 Q. Do you know when the draft was provided to
18 you?

19 A. I do not recall.

20 Q. Do you know if any of the changes you provided
21 verbally were made when the final report was issued?

22 A. I don't recall specific changes that were
23 made. My comments, as I recall, had to do with some of
24 the time lines and whether or not some of the facts were
25 appropriately characterized or not. Ultimately, the

1 authors of the report wrote what they wrote, the final
2 version.

3 Q. I didn't hear the last part. I'm sorry. And
4 what? They wrote what they wrote, and then what did you
5 say?

6 A. The final version is the final version. I'm
7 already on record as not agreeing.

8 Q. Understood.

9 MR. ANDERSON: I'm sorry, Vicki. Was that a
10 question? I couldn't hear you.

11 MS. KAUFMAN: I just said I understand that he
12 doesn't agree.

13 MR. ANDERSON: Okay. Thank you.

14 BY MS. KAUFMAN:

15 Q. Do you have the report, Mr. Jones?

16 A. Yes, I do.

17 Q. Okay. If you will take a look at page 22 of
18 23, and it actually goes over to page 23 of 23. Let me
19 know when you've had a chance to look at that.

20 A. I'm on page 22 of 23.

21 Q. Okay. At the very top, there's a
22 recommendation for improvements to FPL's internal
23 distribution cost estimates.

24 A. There's a list of recommendations. Which
25 recommendation are you referring to?

1 Q. Were any of them implemented by Florida Power
2 & Light?

3 A. Yes. My recollection is that a number of
4 these had already been implemented, and then there were
5 other implementations that followed, and one that we did
6 not implement, to my recollection.

7 Q. Which one was not implemented?

8 A. It would be listed on page 22 of 23, number 3.

9 Q. And with the exception of number 3, the
10 remaining recommendations have all been implemented? Is
11 that what you're telling me?

12 A. Yes. They were either already implemented or
13 implemented.

14 Q. Okay. If you would, flip back to page 17 in
15 the report.

16 A. I'm there.

17 Q. Do you see at the top there are four
18 recommendations listed there?

19 A. I see that.

20 Q. Do you know whether any or all of these have
21 been implemented?

22 A. Give me a moment.

23 Q. Sure.

24 A. Recommendation number 1 says it has already
25 been implemented. The characterization of that

1 recommendation, it's a little vague. We always are
2 timely and responsive in discovery, and the staff has
3 scheduled visits with the project team, and we provide
4 them full access to the project information.

5 Recommendation number 2 --

6 Q. Well, let's look at number 1. What you're
7 saying is that you were already doing this at the time
8 that Concentric made recommendation number 1?

9 A. Yes. In my opinion, we provide full
10 disclosure, and any request we get for information, we
11 respond fully and in a timely manner. The staff audit
12 group has regularly scheduled visits, and we provide
13 full disclosure of the project.

14 Q. Okay. I just wanted to be clear if that was
15 your view.

16 A. The recommendation does not outline any
17 step-by-step specific process. It's kind of open-ended.

18 Recommendation number 2, this is a similar
19 recommendation. FPL and the Florida PSC staff should
20 revisit the issue of intra- and inter-cycle
21 documentation production. The ongoing production of a
22 limited number of key project documents could enhance
23 the staff's understanding of the projects and how they
24 are developing on an ongoing basis.

25 We pretty much stay in discovery year-round.

1 Again, I would defer this to staff, if they believe
2 they're getting adequate document production. From our
3 viewpoint, we're providing a tremendous amount of data
4 and information to the PSC staff.

5 Q. So as to this recommendation as well, it's
6 your view that you do this now and you were doing it at
7 the time of the report?

8 A. Our position is that we have a tremendous
9 volume of document production year round. Whether or
10 not that meets John Reed's expectations, that would be a
11 question for him.

12 Q. Right. I'm just asking for your view. It's
13 your view that you were already doing this prior to the
14 report?

15 A. Yes.

16 Q. Okay. What about number 3?

17 A. Recommendation number 3 was implemented.

18 Q. All right. And number 4?

19 A. Number 4 is implemented.

20 Q. Can you tell me, if you know -- and it might
21 be different times, but when were recommendations 3 and
22 4 implemented?

23 A. Well, from the time that I came on the project
24 in July 2009, our legal folks were providing guidance
25 and instruction for people that were associated with

1 nuclear cost recovery. So I don't know when that
2 started, but it was already in place, because I received
3 guidance and instruction when I joined the team. So I
4 can't tell you exactly when that started.

5 Q. But it's your view that it was certainly in
6 place when you came on board in July '09?

7 A. I'm saying it was in place for me.

8 Q. Do you know the date of this report?

9 A. June 21, 2010.

10 Q. All right. I'm going to turn back to that
11 testimony we were looking at, the March 2009. And if
12 you turn to page 24.

13 A. March 1, 2011?

14 Q. The one we were looking at, uh-huh, page 24.

15 And let me ask you a background question
16 first. There was a reorganization of the EPU project
17 team; correct?

18 A. There was a reorganization of the nuclear
19 division, of which the EPU project team was a part of
20 that reorg.

21 Q. When did that happen?

22 A. That happened July 2009.

23 Q. Were you involved in that, or was that prior
24 to your coming?

25 A. I was involved in that. There was a nuclear

1 organizational change that was announced late in July,
2 and it involved taking the major capitals group, fuels
3 group, and EPU group and reorganizing that group so that
4 the EPU group was a stand-alone group that involved the
5 promotion of people to site vice president, plant
6 general manager, and reassignment of a couple of vice
7 presidential corporate positions to site positions and
8 from site positions to corporate positions. So it was
9 quite a large reorganization.

10 Q. When you said you were involved, were you part
11 of the team, if you will, that made the recommendation
12 for the reorganization, or were you more the one that
13 implemented them, or both?

14 A. I was involved in that. I was one of the
15 folks that changed positions.

16 Q. You were personally involved, then. I
17 understand. But were you involved in making the
18 recommendations, if you will, that led up to the
19 reorganization?

20 A. No.

21 Q. On page 24 that I directed you to, line 5 --

22 A. My involvement is that I was asked by my boss
23 -- in preparation for reorganization and moving people
24 around and making different assignments and redefining
25 some of the functional areas, I was asked to take a lead

1 for an EPU stand-alone project and work with Rajiv
2 Kundalkar and do a change of management plan and
3 transition from this very large organization to a --
4 basically split the projects groups in half, if you
5 will, and take it from a corporate-centric organization
6 to a site-centric organization. So obviously, when the
7 announcement came out of all the organizational changes,
8 neither I nor anyone else involved was surprised. We
9 were all talked to beforehand about what the overall
10 game plan was and what we were trying to accomplish. So
11 as a decision-maker, no; as a beneficiary, yes.

12 Q. Now, was Mr. Kundalkar involved as one of the
13 persons making these decisions regarding the
14 reorganization?

15 A. I don't know. Mr. Kundalkar is a very senior
16 individual with a tremendously successful track record
17 and background in a number of roles, everything from a
18 site vice president to a corporate engineering manager
19 to a major construction VP. And even though he was a
20 direct report to my boss, as was I, whether or not my
21 boss used him as a consultant or not, I would not know
22 that.

23 Q. And who was your boss at that time?

24 A. Mano Nazar, the executive vice president and
25 chief nuclear officer. He has responsibility for the

1 entire nuclear fleet.

2 Q. Is he still in that role?

3 A. Yes.

4 Q. Okay. Thank you.

5 All right. So on page 24, I wanted to ask you
6 about the question that starts line 5, which is did FPL
7 incur any imprudent costs in regards to the reorg, and
8 you say no. I'm assuming, therefore, that there must
9 have been some costs incurred for the reorganization.
10 Is that right?

11 A. I can't think of any costs that would have
12 been incurred as a result of the reorganization.

13 Q. Well, if there were no costs incurred, what is
14 the purpose of this question regarding whether there
15 were any imprudent costs incurred?

16 A. Just to make it clear that there were no
17 imprudent costs incurred in the reorganization.

18 Q. And your testimony is that there weren't any
19 costs incurred? Am I understanding that?

20 A. Well, I can't say that there was absolutely
21 zero cost. I can tell that you the way the
22 reorganization was done was reasonable, was prudent, and
23 benefited the project. I can't think of any costs at
24 all associated with the reorganization.

25 Q. Okay. I just wanted to be clear that your

1 testimony is that there are no costs.

2 A. Well, I'll tell you, I just don't like the
3 characterization of that. If you tell me, "Well, gee,
4 did you have a meeting and meet with people as a part of
5 the reorganization," the answer is yes. And if then you
6 say, "Well, did someone have to travel from St. Lucie to
7 Juno," well, yes. "Well, was there a mileage charge
8 associated with that?" Yes.

9 So there are no absolutes, but relative to
10 what we're talking about here, there was essentially no
11 cost. And certainly those things necessary to
12 accomplish the restructuring of a major department --
13 and by "major department" I'm talking about the capital
14 organization, the fuels organization, and the EPU
15 organization. We wanted to streamline those
16 organizations, and so that's what we did. In fact, I
17 would say that that saved costs over the long run.

18 Q. I wasn't trying to mischaracterize your
19 testimony, and I apologize if I did. I think what I
20 heard you say is that there were some costs, and I'm
21 just trying to get a handle on what those costs were.

22 A. Those costs would have been administrative in
23 nature.

24 Q. And do you have a dollar figure to attach to
25 that?

1 A. No.

2 Q. Is there anybody in the organization that
3 would know what that number was?

4 A. No, because the people on the project, their
5 cost is associated with their salaries and their
6 incidentals, and that really doesn't change.

7 Q. Did you have any involvement in preparing for
8 the nuclear cost recovery hearing that was held in 2009
9 in Florida?

10 A. No.

11 Q. You didn't review testimony or engage in any
12 witness preparation? You had no involvement?

13 A. That's correct.

14 Q. All right. I just have one more line of
15 testimony, and this refers, Mr. Jones, to your May
16 2nd testimony, if you can pull that out as well.

17 A. I have it.

18 Q. Okay. If you can turn to page 11, please.
19 Let me know when you get there.

20 A. Page 11.

21 Q. Yes. Are you there?

22 A. Yes, I am.

23 Q. Okay. I want to talk to you about the Q and A
24 that starts on line 14 where you're talking about the
25 unanticipated schedule change for this year. Do you see

1 where I am?

2 A. Yes, I'm with you.

3 Q. Sorry. That was my cell phone ringing in your
4 ear.

5 And you attribute it to an error by one of
6 your vendors, Siemens; correct?

7 A. That's correct.

8 Q. And it says the outage lasted longer than
9 planned. Can you tell me how much longer the outage
10 lasted than what you had planned?

11 A. That error in regards to Siemens with the
12 generator extended -- that had about a 22- to 23-day
13 impact, that particular event. And that would be the
14 extension of the Siemens scope of work. There were
15 other things that are going on in the outage that
16 contributed to the overall outage duration, but this
17 event caused the Siemens scope of work to extend by at
18 least 22 or 23 days.

19 Q. And will that have the impact of increasing
20 the project cost?

21 A. Well, yes, there is risk that it does increase
22 the project cost. We're working through that, and we're
23 in those commercial discussions right now with Siemens.

24 Of course, Siemens is the original equipment
25 manufacturer for the turbine generator, and that's why

1 we hired them. They are the subject matter experts.
2 They do this all over the world. They have great
3 procedures and a great track record, and it was our
4 decision to go with them.

5 Also, just to give you a feel for this, this
6 involves several hundred workers, this scope of work,
7 that are deployed by Siemens. So this isn't something
8 that we could do ourselves, and we certainly couldn't
9 put a single person in the hip pocket of every single
10 Siemens worker, because that's not cost-effective
11 either. We have a small group that provides direction
12 and oversight and logistics support for them.

13 Having said that, we can't prevent every
14 single error from occurring. And while it's certainly
15 not acceptable, it did occur. Now, the consequence is
16 large, because these are large, complicated assets, and
17 when a mistake is made, it has consequences.

18 Now, in our contracts -- and we are no
19 different than any other nuclear power plant out there.
20 The benefit for customers is for us to do refueling
21 outages in a cost-effective, efficient way. And we,
22 like the rest of the nuclear industry, instead of
23 carrying hundreds more people on our staff to do this
24 work on an infrequent basis, once every 18 months, we
25 bring in the subject matter experts, the vendors that do

1 this outage over outage. [REDACTED]

2 [REDACTED]

3 [REDACTED]

4 [REDACTED]

5 [REDACTED]

6 By the same token, given that these are large,
7 complex assets, when a mistake is made, as in this case,
8 it's usually multiple days or even weeks of impact. And
9 vendors, of course, will not perform the work, not here,
10 not there, not anywhere, without a limit to their
11 liability, because lost generation would put any one of
12 these vendors out of business, and so they have limits
13 to their liability. And so when I say we're in
14 commercial space with these folks right now, that's our
15 integrated supply chain and our legal department.

16 Of course, on any complex job like this,
17 Siemens also has their claims with the company, that
18 they could have gotten the work done faster had we not
19 delayed them or had this tool or crane or something been
20 available. So we keep book on each other on a
21 day-by-day basis, and when we get through the refueling
22 outage, we wind up debating that and settling that at
23 the end.

24 Q. I guess what I'm trying to find out is, as we
25 sit here today, am I right that there has been no dollar

1 amount placed on what this 22- to 23-day delay in the
2 outage is going to cost? I'm just trying to --

3 A. Yes, we've calculated what the impact is to
4 us. We know roughly what the impact to Siemens should
5 be. I don't have all those facts and figures in front
6 of me. The project team puts together all that detail
7 and provides that to our integrated supply chain and our
8 legal team, and that's their area of responsibility to
9 go after Siemens to protect our interests and our
10 customers' interests. So that's a hand-off from me to
11 those groups.

12 Q. Do you know what the dollar impact on FPL is
13 estimated to be?

14 A. No, not off the top of my head.

15 Q. Who in the organization would know that
16 number?

17 A. That would be the site-specific project
18 controls group and the integrated supply chain.

19 Q. Is there a person or persons?

20 A. There's a number of people that would have
21 that information.

22 Q. Can you tell me who they are?

23 A. Well, it would be the -- if you're asking me
24 if they know off the top of their head, the answer is
25 no. Do they have it in the documents? Yes.

1 Q. I was asking for their names. Who would know?
2 Who would have these figures regarding the estimated
3 impact of the outage?

4 A. The site director, Alan Fata.

5 Q. What's his name? I'm sorry.

6 A. Alan, last name Fata, F-a-t-a.

7 I'm only hesitating because I don't really
8 like putting employees' names out publicly. I just
9 don't think it's appropriate.

10 Q. Anybody else?

11 A. I'm going to give you the titles. Site
12 director, project controls --

13 MS. KAUFMAN: Well, I can't subpoena somebody
14 by their title. Bryan, is there some reason he
15 can't give me the names of these folks?

16 MR. ANDERSON: The names can be provided.

17 THE WITNESS: Do you want me to provide the
18 names?

19 MR. ANDERSON: Yes, the names can be provided.

20 MS. KAUFMAN: Thank you.

21 THE WITNESS: Alan Fata, site director.
22 Crawford English, project controls, the supervisor.
23 The integrated supply chain person for the EPU
24 project will be Mark Waronicki, W-a-r-o-n-i-c-k-i.

25 BY MS. KAUFMAN:

1 Q. Is that it?

2 A. Steve Reuwer, the implementation owner.

3 Q. Is that it? I'm sorry. It's hard when I
4 can't see you.

5 A. That's all I can think of. I don't want to
6 speculate on others.

7 Q. Now, in your view, is this outage going to
8 require the additional purchase of replacement fuel or
9 generation?

10 A. With St. Lucie Unit 2 not on line, there is
11 certainly some other power source, fuel source that is
12 in its place.

13 Q. Do you have any estimate of what that might
14 be?

15 A. No, I do not.

16 Q. Now, on the next page, page 12, beginning at
17 line 13 again, you're talking about pursuing your claim
18 against Siemens, and then you say beginning at line 20
19 that you're not seeking to recover these costs in the
20 nuclear cost recovery docket. Do you see that? It's on
21 lines 20 and 21 in my copy.

22 A. Yes, I see that.

23 Q. Do you know, are you going to seek to recover
24 them in the fuel docket?

25 A. That's not for me to decide.

1 Q. Is that out of your area?

2 A. That's out of my area.

3 MS. KAUFMAN: Okay. Just give me one second.
4 I'm going to put you on mute for a minute.

5 I think that's all I have, Mr. Jones. Thank
6 you for your patience.

7 MR. MCGLOTHLIN: This is Joe. The court
8 reporter requests a break. Can we take eight or
9 ten minutes?

10 MR. ANDERSON: We'll come back at ten to. Is
11 that okay?

12 MR. MCGLOTHLIN: That's fine.

13 (Recess from 1:41 p.m. to 1:51 p.m.)

14 CROSS-EXAMINATION

15 BY MR. YOUNG:

16 Q. Good afternoon, Mr. Jones. My name is Keino
17 Young. I'm with Commission staff.

18 A. Good afternoon, Mr. Young.

19 Q. I have a series of questions to ask you. I
20 have quite a bit, to be honest with you. What I would
21 like to do is go about 50 minutes to an hour, and then
22 after that take a break, take a five-minute break after
23 every 50 minutes to an hour. Okay?

24 A. That's fine.

25 Q. Also, during the course of my questioning, if

1 there is a question that you don't understand or you
2 want me to rephrase the question, please don't hesitate
3 to ask me to do that. Okay?

4 A. I appreciate that. Thank you. I will.

5 Q. Also, during the course of this deposition, I
6 may ask you some questions, and your attorney may
7 object. Unless he instructs you not to answer,
8 Mr. Jones, you understand you must answer; correct?

9 MR. ANDERSON: Keino, I'll give the legal
10 advice to the witness, but go ahead.

11 BY MR. YOUNG:

12 Q. Okay. Well, let me rephrase it. He might
13 object, but unless he instructs you not to answer, if
14 you can answer the question, please answer.

15 Did your attorney provide you a series of
16 documents that I asked you to bring to the deposition
17 today?

18 A. Yes.

19 Q. Okay. Great. Mr. Jones, you're sponsoring
20 the final true-up for the 2009-2010 for consideration in
21 this upcoming proceeding; correct?

22 A. That's correct.

23 Q. That's the final true-up filing for 2009-2010;
24 correct?

25 A. That's correct.

1 Q. Okay. As an FPL EPU project manager, do you
2 know the amount that FPL has requested for 2009-2010,
3 final and not subject to ongoing review for the true-up?

4 A. I have it here. I don't have those numbers
5 memorized off the top of my head. Give me just a moment
6 to look it up.

7 MR. ANDERSON: Do you want him to look it up?

8 BY MR. YOUNG:

9 Q. Do you know if all the numbers are final?
10 Basically, that's my question. Are the numbers final
11 for 2009-2010?

12 A. Yes, they are.

13 Q. Is there an internal report or memo stating
14 that the year-end amounts are final and fully audited?

15 A. I don't know the answer to that question.

16 MR. YOUNG: Okay. Bryan?

17 MR. ANDERSON: Yes, Keino.

18 MR. YOUNG: What I would like to do is ask for
19 a late-filed exhibit, if the court reporter can
20 tell me what number we're on.

21 MR. MCGLOTHLIN: Keino, we think it's Number
22 7.

23 MR. YOUNG: Number 7? Okay. Bryan, can we
24 get a late-filed exhibit? That will be Number 7,
25 and the title for that, Bryan, will be "Finding of

1 FPL's Audit for 2009 -- 2010, excuse me, NCRC
2 costs.

3 MR. ANDERSON: You're saying Finding of FPL's
4 Audit for 2010 Costs?

5 MR. YOUNG: Yes, 2010 NCRC costs.

6 (Late-filed Deposition Exhibit Number 7 was
7 identified for the record.)

8 BY MR. YOUNG:

9 Q. Mr. Jones, can you please turn to your May
10 2nd testimony?

11 MR. ANDERSON: Keino, before you go on, audit
12 staff I think has our audit reports. If that's
13 what you're wanting, you're welcome to them.

14 MR. YOUNG: Yes, that's what we want.

15 MR. ANDERSON: Okay.

16 BY MR. YOUNG:

17 Q. Mr. Jones, can you please turn to your May
18 2nd testimony filed for this year's proceeding, and
19 specifically, Mr. Jones, page 14 of the testimony.

20 A. I have it.

21 Q. Do you see where you discuss the internal
22 audit activities?

23 A. Yes.

24 Q. Okay. I'm not clear on the scope and purpose
25 of the internal audit activities. Can you explain more

1 in detail whether the audit is a financial audit, or is
2 it a Q and A audit?

3 A. Could you elaborate as to what the difference
4 is?

5 Q. What I'm talking about is a financial audit
6 that just looks at the numbers, a pure financial audit,
7 whereas Q and A looks at the performance and everything
8 else. Do you understand what I'm talking about now?

9 A. I think I do. The annual internal audit looks
10 at how we classify our costs. It looks at our project
11 controls organizations and the procedures that we have
12 in place and if we are following those procedures. It
13 also looks at expense reports to ensure that those are
14 reasonable and there aren't charges unrelated to EPU.

15 I think one of the findings in this year's
16 audit was that we had an employee who was doing some
17 general employee training that's require for nuclear
18 access. And that was challenged as to whether or not
19 that's really separate and apart, so we made some
20 changes in our instructions relative to that. Even
21 though at the time of the testimony it wasn't final, the
22 report is now final, and it was a very favorable report
23 with few recommendations.

24 If you're asking me does the internal audit
25 look at the cost estimate for replacing the steam

1 generator and feed pump and determine whether or not
2 that is a reasonable estimate, or if it goes out -- or
3 if we just replace the feed pump and spend X number of
4 dollars to replace the feed pump, and it then goes out
5 and looks and audits that, a financial audit does not do
6 that.

7 Q. Okay. Moving on, I would like to get your
8 understanding of what's being stated at page 3 in the
9 seventh numbered paragraph of FPL's 2011 petition.

10 A. I'm on page 3. Oh, wait a minute. I'm sorry.
11 I thought you were referring to the testimony.

12 Q. No, FPL's 2011 petition.

13 A. Okay. Could I have a moment read it?

14 Q. Yes. And specifically, let's look at the
15 bottom of page 3.

16 A. Okay. I'm there, the bottom of page 3.

17 Q. All right. And do you see the phrase, "FPL is
18 seeking approval of this amount and a prudence
19 determination with respect to the underlying actual 2009
20 EPU and Turkey Point 6 and 7 costs"? Do you see that?

21 A. Yes, I do.

22 Q. Now, I understand a request for approval of
23 the amount of prudence determination. What I'm not
24 clear on, Mr. Jones, is FPL's intent in using the word
25 "underlying." What do you believe is meant by that

1 word?

2 A. I think it's just linking the petition to or
3 referring to the actual costs associated with the 2009
4 EPU and Turkey Point 6 and 7 costs. I don't think that
5 word has any special meaning.

6 Q. Based on that response, does this mean that
7 you -- does it mean to you that FPL anticipates filing
8 subsequent revisions to the 2009 expenditures that are
9 currently not fully known or disclosed?

10 A. No, we are not.

11 Q. In reading FPL's 2011 petition, I didn't see
12 the word "final" associated with the actual 2009 costs.
13 Are you aware of any reason, including FPL's policy or
14 practice, that may indicate the 2009 costs are not
15 final?

16 A. No, I have no information that the 2009 costs
17 are not final.

18 Q. Also, in reading FPL's 2011 petition, I didn't
19 see the word "final" associated with the actual 2010
20 costs. A similar question: Are you aware of any
21 reason, including FPL's policy or practice, that may
22 indicate that the 2010 costs are not final?

23 A. No, I have no information or knowledge or any
24 reason to think that the 2010 costs are not final.

25 Q. Now, Mr. Jones, what I want to do is get some

1 clarification on the EPU project, your EPU 2010
2 testimony. Okay?

3 A. Okay.

4 Q. In that case, please turn to your March 1st
5 testimony for the period 2010, and let me know when
6 you're ready.

7 A. March 1, 2011, for the extended power uprates,
8 2010?

9 Q. Yes.

10 A. I'm there.

11 Q. Okay. On page 1, line 17.

12 A. Page 1, line 17. I'm there.

13 Q. You stated that you were appointed VP of
14 Nuclear Power Uprate on August 1, 2009. And I think you
15 went over this with Ms. Kaufman somewhat, but can you
16 elaborate on how it came about that you became appointed
17 to that position?

18 A. Yes. There was a reorganization of the
19 nuclear fleet that involved a number of reassignments
20 associated with reorganizing various groups and
21 functions for the nuclear fleet. That's not unusual.
22 It doesn't happen every year, but about once a year
23 there are some changes, and every few years there are
24 larger changes.

25 So I was the Vice President of Operations,

1 Midwest, in which I had accountability for the nuclear
2 plants in the Midwest. And as a part of realigning some
3 of the functions, and specifically the organization that
4 had accountability for all EPU across the fleet and all
5 major capital projects and engineering across the fleet,
6 as well as nuclear fuels, the decision was made to break
7 that down into smaller organizations and have the EPU as
8 a stand-alone organization, and basically, if you will,
9 divide the talent and responsibilities such that we had
10 an organization to run the major capital projects that
11 weren't directly related to EPU, which involves hundreds
12 of millions of dollars, and an organization to run the
13 EPU project. And then there was a realignment of the
14 fuels organization, training organization, security, and
15 all the rest, but that's not really -- that wasn't my
16 concern.

17 And so I was asked to lead the effort to
18 restructure this new EPU organization into a
19 site-centric organization, to integrate it with the
20 plant operations, given that -- and this was always
21 planned, similar to what we did for the reactor head
22 replacements that we had to do for four units. It
23 starts with a corporate effort to lay out the strategy
24 for contracts, procurement, and things like that, and
25 then you establish site project teams and push the

1 authority and the resources to the site. Those projects
2 aren't nearly as large or as complex as EPU, and there's
3 a tremendous amount of work that gets done and
4 incorporated during the online period.

5 One of my skill sets is really my operational
6 expertise in how to integrate these major efforts into
7 the plant operations without disrupting plant
8 operations, so that was one of my attributes that
9 determined that I would be suitable for the job. So I
10 was a part of reorganizing really the nuclear fleet in a
11 number of areas. I had the lead, and I worked with
12 Rajiv Kundalkar on the change of management plan to
13 separate out the two organizations and make sure that we
14 had the right resources and talent to maintain all the
15 going-forward functions.

16 Q. Well, let me ask you -- you talked about your
17 appointment. Who made the appointment? Was it FPL or
18 NextEra that made that appointment?

19 A. Well, I work for my boss. My boss is Mano
20 Nazar. He's the executive vice president, and that
21 assignment was made by him to me.

22 Q. And he was NextEra; right?

23 A. Correct. Actually, I don't know if he is
24 NextEra corporation or if he is FPL company and in the
25 affiliate fee. I know I'm an officer of the company and

1 a Florida Power & Light employee, and I'm in the
2 affiliate fee, my costs associated with the affiliate
3 company. But I don't know how the accounting is handled
4 for the senior executives that have responsibilities
5 across both companies.

6 Q. Okay. Now I'm going to ask you some general
7 questions. Are you familiar with Section 466.93,
8 Florida Statutes?

9 A. No, I'm not.

10 Q. Okay. Are you familiar with Rule 25-6.0423,
11 Florida Administrative Code, which implements the
12 statute I just mentioned above?

13 A. Mr. Young, I have no idea what you're
14 referring to. I'm not familiar with those numbers or
15 statutes of any of that. If you tell me what the
16 context is, I may have some knowledge that may have some
17 applicability to this project, but I would not recognize
18 that by statute numbers.

19 Q. Okay. Are you familiar with the function and
20 jurisdiction of the Florida Public Service Commission?

21 A. Yes, generally.

22 Q. Can you explain the nature and means by which
23 you became familiar and your familiarity with the
24 function and jurisdiction of the Florida Public Service
25 Commission, quickly and briefly, please?

1 A. I've been in training and preparation as a
2 fuel clause witness in other past proceedings and have a
3 general knowledge from having worked in a regulated
4 utility for 24 years, then specifically, you know,
5 nuclear cost recovery clause, training and briefings on
6 the requirements of the nuclear cost recovery clause.
7 That has been my exposure to the Florida Public Service
8 Commission.

9 Q. Okay. At line 22 of your testimony, which
10 we're dealing with the March 1, 2011 testimony, you
11 stated that your positions at FPL had included the VP of
12 Operations, Midwest Region. What geographical areas,
13 such as Florida counties, are included in FPL's Midwest
14 Region?

15 A. If I understand the question, if you're asking
16 me if there are any counties in Florida in the Midwest
17 Region, the answer to that would be no.

18 Q. Just to follow up quickly, when you say
19 Midwest, that means the Midwest United States, correct,
20 not Florida?

21 A. I'm talking about Iowa and Wisconsin.

22 Q. Okay. Do your duties as VP of Nuclear Power
23 Uprate include being familiar with the EPC contract and
24 general oversight of the EPC contract with Bechtel?

25 A. Yes.

1 Q. Can you briefly describe how you became
2 familiar with the terms and conditions of the EPC
3 contract and when you became familiar with that?

4 A. I became familiar with the EPC contract as
5 part of the transition to my new position.

6 Q. Okay. Prior to August 1, 2009, had you worked
7 on any major projects with Bechtel where -- excuse me.
8 Had you worked on any major projects where Bechtel was
9 the EPC contractor?

10 A. Prior to August 1, 2009, the answer to that is
11 yes. Bechtel was the procurer and constructor for the
12 EPU at Point Beach Nuclear Power Plant, where I had
13 direct responsibility for the operations of that
14 facility. If we go back a very, very long time ago,
15 when I worked at Turkey Point, Bechtel was onsite and
16 provided both engineering and construction services at
17 Turkey Point, but I was not in a managerial position at
18 that time.

19 Q. Okay. Can I get you turn to your Exhibit
20 TOJ-14?

21 A. I'm on TOJ-14.

22 Q. Okay. On TOJ-14, I noticed that you listed an
23 item that is Point Beach specific. Do you see that?

24 A. I see that. That's a mistake.

25 Q. Okay.

1 A. Probably from our -- what we do is, from our
2 list of -- as you can imagine, there are many procedures
3 that would apply across all the EPU projects. And we're
4 much more careful than that, obviously, and we'll make
5 sure that we remove any reference to Point Beach, so I
6 apologize.

7 Q. Well, that's not a problem. Let me ask you,
8 are there any other items listed here that do not apply
9 to the Florida uprate projects?

10 A. I'm checking.

11 These all are applicable to the Florida
12 project, with the one exception that we've already
13 talked about.

14 Q. Okay. Under the heading "Project Controls" --
15 do see that? Not including the word "Title," it's the
16 third bold on the left-hand side of the page.

17 A. Yes, I have it.

18 Q. The second item down titled -- do you see
19 that, "Forecast Variance and Trends?"

20 A. Yes, I've got it.

21 Q. Can you describe what the purpose of the
22 forecast variance and trends control is?

23 A. I haven't specifically read that particular
24 procedure. That procedure, the reason it's there under
25 project controls is that that whole series provides

1 direction for the project controls organization on how
2 to prepare forecast variances. And trends would be
3 relative to -- we refer to trends as those things that
4 our vendors have done that may have additional cost or
5 maybe an additional reduction. This would be the
6 specific instruction around building the forecast.

7 Q. On a going-forward basis, Mr. Jones, how will
8 you know that the control is effective?

9 A. We have monthly project review meetings where
10 we go through the forecasts and the trends. We also
11 have internal audits for our project controls
12 organization, as well as we will have an external
13 auditor look at our project controls organization, the
14 procedures, to see that they're following those. PSC
15 staff also looks at our project controls procedures and
16 requests source documents and invoices, at our project
17 controls process. So it's a combination of things that
18 we use.

19 Our nuclear business operations group, which
20 reports to the nuclear business controller, who reports
21 directly to the chief nuclear officer, audits our
22 project controls and looks at our accounting
23 classifications, our invoices, and provides oversight as
24 well. They are independent of the project.

25 Q. All right, Mr. Jones. Project scope control

1 process, do you see that on the project controls?

2 A. Yes, I do.

3 Q. If I were to ask you the same questions I
4 asked you just a minute ago, would the answers be the
5 same?

6 A. With the difference that project scope control
7 is how scope is added to the project, how it gets
8 identified, how it gets processed. There's a form to
9 use if someone wants to add scope or delete scope. And
10 it governs how the estimations occur, the reporting, and
11 approval levels. There are restrictions that are tied
12 directly to approval levels for scope changes to the
13 project.

14 Q. Okay. You show this control, the project
15 scope control process item, is on the tenth version. To
16 me -- I'm just trying to get a better understanding. To
17 me, this seems rather high for a project that's only two
18 or three years along. Can you briefly explain why the
19 project scope control item is in its tenth revision?

20 A. As a result of routine audits and
21 self-assessments we do, it's not unusual for us to make
22 enhancements to our project controls process procedure.
23 So each time we enhance the procedure, it's going to
24 show up as a revision. I don't have it here in front of
25 me, but I certainly can get it and go through the ten

1 revisions with you.

2 Some of them may have been -- they could have
3 been anything from an organizational change, a change of
4 reporting relationship and a title, to an additional
5 check and balance that was recommended as a result of an
6 audit that we may have added. So could it run the full
7 gamut of the scope changes. But if you would like, we
8 can get that document and sample those revisions.

9 Q. I don't think that will be necessary,
10 Mr. Jones.

11 Moving along, the controls that we have
12 reviewed today, is it your responsibility to verify that
13 your project teams are using the controls in a timely
14 and effective manner?

15 A. I'm accountable for everything that happens on
16 the project. And in regards to the project controls
17 organization, they directly report to me, so they're my
18 direct responsibility. In my project review meetings, I
19 look for anomalies or deviations. I'm a part of scope
20 control approval. I'm also the only one that can
21 authorize nuclear cost recovery scope changes, separate
22 and apart, and then I also rely on the self-assessments
23 and audits for my project controls organization to show
24 that they're following their procedures and process. I
25 myself do not go out and do a deep dive into assessment

1 of the project controls organization. I rely on others
2 that are subject matter experts in that area to do that.

3 MR. MCGLOTHLIN: This is Joe. The court
4 reporter says that the witness has been fading in
5 and out on her a bit. Going forward, just remember
6 that she needs to hear you.

7 THE WITNESS: I understand. I just have some
8 papers in front of me, so I'm trying to keep the
9 papers from rustling in front of the microphone.
10 I'll get closer to the mike.

11 MR. MCGLOTHLIN: That's better.

12 BY MR. YOUNG:

13 Q. All right. Mr. Jones, can I have you turn to
14 page 31 of your testimony?

15 MR. ANDERSON: Which one, Keino? Is it May,
16 March?

17 MR. YOUNG: We'll still in the March 1st
18 testimony.

19 MR. ANDERSON: Which hearing?

20 MR. YOUNG: 2010.

21 MR. ANDERSON: Thank you. I want to keep with
22 you.

23 MR. YOUNG: Okay.

24 A. Yes, I'm with you, page 31.

25 Q. Mr. Jones, on page 31 of your testimony, you

1 stated that you are supporting FPL's 2010
2 actual/estimated costs on line 15. Do you see that?

3 A. Yes, I do.

4 MR. ANDERSON: What line numbers, Keino?

5 THE WITNESS: Line 15 says, "Did FPL perform a
6 partial year true-up of 2010 costs in 2010?"

7 That's the question, and the answer is, "Yes. The
8 schedules presenting," that portion.

9 BY MR. YOUNG:

10 Q. Yes, sir. Now, let me ask you a question,
11 Mr. Jones. What role did you have in preparing FPL's
12 2010 estimated/actual projections filed originally in
13 May 2010 and then again in August 2010?

14 A. Those schedules are prepared by my project
15 controls organization, which directly reports to me.
16 Those are provided for my review in the form of this
17 exhibit, and I look at those, and those match with
18 what's in our monthly project control book as far as our
19 actuals and estimated, which actually I see those on a
20 week-to-week basis. When we close the books at the end
21 of the month, that's when the month is really final, but
22 we look at it on a week-to-week basis. But those are
23 prepared under my direction.

24 Q. All right. Keeping on page 31, beginning at
25 line 19, you discuss the development of the 2010 costs.

1 You discuss vendor information, and on page 32 you
2 discuss what appears to me to be an internal support
3 analysis. However, I don't see a specific reference to
4 the Executive Steering Committee or any other senior
5 management review and approval process in connection
6 with the development of the 2010 actual/estimated costs.

7 Mr. Jones, my question is, am I correct to
8 conclude that FPL's 2010 actual/estimated cost forecast
9 was not vetted or required to be vetted through the
10 senior review process?

11 A. The Executive Steering Committee, Senior
12 Executive Steering Committee, is exactly that. It's a
13 steering committee. And we made periodic reports to
14 that committee, which my boss is one on that committee,
15 obviously.

16 I just want to kind of frame that committee
17 for a moment, if I could.

18 Q. Sure. Go ahead.

19 A. We provide the project status. We provide
20 them with the risk that we're managing. We provide them
21 with our project forecast information. We provide them
22 with our actual spent for the year. And we provide them
23 with our recommendation for a going-forward strategy or
24 any significant changes that a senior executive may be
25 interested in, such as we want to change the sequence of

1 the refueling outages, or we want to move a major
2 portion of the outage from one year to the next, things
3 such as that, big things, big things.

4 As far as the year-over-year, month-over-month
5 budget, we're in our budget review cycle right now
6 preparing our budgets for next year. When I say "we," I
7 mean the entire company. And so with any large capital
8 project that goes over many years, we go through the
9 budget process no different than any other department.

10 And so we take the best information that we
11 have and what our forecast is, and we say, "This is how
12 much money we intend to spend in the next year." And
13 that goes to our nuclear business operations, the
14 nuclear controller, which is independent of the project.
15 And that goes through review and approval just like any
16 other business unit, all the way through the senior
17 executives.

18 The Executive Steering Committee is not the
19 one that actually authorizes my next year's budget. Are
20 they aware of it? Certainly. But that's more of a
21 policy setting, strategic direction kind of a -- it's
22 multi-disciplined. There's only one nuke on that
23 Executive Steering Committee, and that's my boss, and
24 the rest are from the other business units. And so
25 that's more senior executive oversight looking for

1 issues and problems and challenging us to make sure that
2 we're performing well. They're not a "I'm approving
3 that this spend is okay for next month." While
4 certainly you have the president and CEO of FPL and the
5 COO an president of NextEra Corporation, and they
6 certainly are aware of the budgets, the approval process
7 for budgets and expenditures goes through the normal
8 process like any other department at FPL.

9 We also -- when our budget for the following
10 year is set, if there's going to be a major change for
11 some reason, we certainly communicate that real-time.
12 We meet with our chief nuclear officer at least every
13 two weeks, and usually weekly, because there's a lot of
14 things that we're manging, to be quite frank.

15 In regards to your specific question, the very
16 formal senior executives signing off for the
17 year-to-date actuals for August -- I'm sorry, for 2010
18 and the going-forward forecast, we actually do that
19 every month. That comes to me, and we provide that in
20 our -- there's a monthly report that we provide to our
21 senior execs, not only my project, but enterprise-wide,
22 and it's called a monthly operating performance report
23 where the senior executives go through what the
24 expenditures are in each business organization. And
25 that's for the purpose of monitoring and whether we're

1 meeting our monthly forecasts and projections, whether
2 it be underruns or overruns.

3 Your question was kind of wide open, but I
4 felt I needed to tell you a lot about how we run our
5 enterprise to be able to answer that question. For the
6 purpose of this filing -- this is a filing. This is a
7 special request called nuclear cost recovery where
8 someone has said, "Tell me what you've spent
9 year-to-date, and tell me what you're going to spend the
10 rest of the year." I get that question every single
11 month and have to provide that to the Management --
12 MOBR. I know the acronym, but I forgot the name. But
13 as far as putting that information in here, the buck
14 stops with me.

15 Q. Okay. Thank you, Mr. Jones. Can you look at
16 page 32, line 12? On the one I have it's line 12,
17 Bryan. It might be a number different from yours, a
18 different line, probably line 13 or 14.

19 MR. ANDERSON: I think we're good.

20 MR. YOUNG: Great.

21 BY MR. YOUNG:

22 Q. Mr. Jones, you asserted -- on lines 12 through
23 15, you asserted that careful vendor oversight,
24 continued use of competitive bidding when appropriate,
25 and the application of the robust internal schedule and

1 cost controls and internal management processes all
2 support a finding that FPL's actual/estimated 2010
3 expenditures were reasonable.

4 Now, Mr. Jones, you made the statement in
5 reference to 2010 actual and estimated expenditures. Do
6 you have any reason to believe that the statement is
7 accurate with respect to the final 2009 expenditures?

8 A. The same statement would apply to the 2009
9 expenditures. I believe that should be in my other
10 testimony.

11 Q. All right. Just to follow up, you believe
12 that FPL had careful vendor oversight and robust
13 internal cost controls and a robust internal management
14 process during 2010?

15 A. Yes, I do.

16 Q. All right.

17 A. And that's the reason we have people come in
18 and audit those and help us maintain those controls in
19 place and enhance them where practical.

20 They're not perfect. I didn't say that. I
21 don't know anybody that is. I believe we work extremely
22 hard to do this right. In fact, I've never seen an
23 internal audit report that didn't have a recommendation
24 for improvement. If I ever do, then it wasn't a very
25 good audit.

1 Q. All right. Moving along, Mr. Jones, did FPL
2 file an errata sheet in the 2010 filing in Docket No.
3 100009-EI that included changes to the data and exhibits
4 you supported?

5 A. Yes, we did. You gave a specific number, so I
6 need to verify that number.

7 MR. ANDERSON: Do you have the document in
8 front of you, Keino? I just want to make sure
9 we're talking about the same thing.

10 MR. YOUNG: No, I don't have the document in
11 front of me right now.

12 BY MR. YOUNG:

13 Q. It's just -- subject to check, Mr. Jones,
14 would your answer be the same?

15 MR. ANDERSON: Do you want to reread your
16 question again?

17 BY MR. YOUNG:

18 Q. Did FPL file -- subject to check, did FPL file
19 an errata for its 2010 filing in Docket No. 100009-EI
20 that included changes to the data and exhibits that you,
21 Mr. Jones, supported, again, subject to check?

22 A. Yes, that sounds right.

23 Q. Mr. Jones, keeping with the same testimony,
24 could you please turn to page 38. Are you there?

25 A. I'm on page 38. Is that the page with the

1 conclusion?

2 Q. Yes.

3 A. Okay. I'm there.

4 Q. I'm looking at line 12, and what I'm looking
5 specifically at is, "FPL is confident that its EPU
6 management decisions are well-founded and prudent." Do
7 you see that sentence, and keep going until the end?

8 A. Yes. "All costs incurred in 2010 were the
9 product of such decisions, were reasonably and prudently
10 incurred, and should be approved."

11 Q. Assuming these assertions are correct and
12 true, can you conceive of any event that would trigger
13 FPL filing an errata on the final 2010 costs?

14 A. I can't conceive of any event that would cause
15 us to file errata relative specifically to the 2010
16 costs.

17 Q. Okay. Now, can you please turn to TOJ-16,
18 which is just a couple pages over, your Exhibit 16 to
19 this testimony?

20 A. I'm there.

21 Q. Other than a daily report, I did not see
22 anything that indicates the extent of the forward period
23 addressed by these reports. Can you please walk us
24 briefly through each report and tell briefly what the
25 forward period is, if any?

1 A. Well, on the -- I can start with report number
2 one if you would like, where it says PSL, PTN Daily
3 Report. Are we on the same page, TOJ-16, page 1 of 2?

4 Q. Yes.

5 A. Okay. PSL is the acronym for the St. Lucie
6 plant, and PTN is the acronym for the Turkey Point
7 plant. And there's a daily report that's produced that
8 has activities associated with license amendment
9 requests. It has activities associated with design
10 engineering, planning, issue management, and critical
11 station interfaces. And as it says, it can go out as
12 far as six weeks. It provides a look ahead.

13 Is that the type of information you're looking
14 for?

15 Q. Yes. (Inaudible.)

16 A. Yes. The executive VP --

17 MR. MCGLOTHLIN: This is OPC. We need to
18 break in. Keino, for some reason you broke up when
19 you were asking that last question. Would you
20 start that again, please?

21 MR. YOUNG: The TOJ-16?

22 MR. MCGLOTHLIN: You had referred him to that
23 exhibit, and then you posed a question that broke
24 up for some reason.

25 BY MR. YOUNG:

1 Q. I was just -- okay. Just to repeat the
2 question, can you please walk us through each report
3 briefly and tell us what the forward period is, if any,
4 briefly and succinctly, if you can?

5 MR. ANDERSON: You know, what does "forward
6 period" mean? I don't understand. Is that what
7 you're saying, f-o-r-w-a-r-d? Do you mean a report
8 about what's going to happen? What are you saying?

9 MR. YOUNG: Yes, a report that's going to
10 happen. For example, Mr. Jones mentioned the
11 six-week period moving forward for the daily PSL
12 and PTN daily report.

13 MR. ANDERSON: I see what you're saying.
14 Thank you.

15 BY MR. YOUNG:

16 Q. Mr. Jones, I think you mentioned -- you did
17 the PSL, PTN daily report, and then you were on the
18 executive VP and chief nuclear officer summary. Can you
19 please start from there?

20 A. Yes. At least once every two weeks we meet
21 with the chief nuclear officer. Really, it's pretty
22 much once a week, but a minimum of once every two weeks.

23 And in that meeting, we provide a summary of
24 LAR engineering, NRC activities, current status, what's
25 coming up. We provide a status of design engineering

1 and progress against the milestones. In a report for
2 the senior vice president, he's really interested in the
3 big issues and are there any actions that he needs to
4 take.

5 It also provides where we are in the planning,
6 and it provides -- we always provide the current cost
7 forecast relative to the previous filing. And we'll
8 provide the total cost forecast, which is just our best
9 view for the end of the project.

10 We'll also provide a risk matrix, which is
11 every risk that has been identified, and so that could
12 be the short-term risks or a risk that isn't going to --
13 something we're going to have to deal with in the fall
14 of 2012. So we show them the risk matrix. You can
15 imagine that it doesn't change a lot week over week,
16 obviously, and he becomes quite familiar with our risk
17 matrix and our project forecast.

18 Q. I'm sorry to cut you off. I'm sorry. I'm
19 just looking -- Mr. Jones, I'm just looking for the
20 forward period in terms of --

21 MR. ANDERSON: You're asking how far ahead the
22 things that are on the report they talk about?
23 You're just looking for that?

24 MR. YOUNG: Yes.

25 A. Sure. The weekly is the current status

1 report. What I'm trying to tell you, Mr. Young, is that
2 there are things that are listed on that report that are
3 in the out years. It's not -- I don't want you to think
4 it's a schedule, that I'm walking in there with a
5 schedule of 10,000 activities that I'm walking through
6 for the next six months. No. That's not appropriate
7 for a senior vice president. I'll tell you I don't go
8 through the engineering schedule. I'm looking high
9 level, when does this package come due, when that
10 package needs to be done. I'm looking at the milestone
11 schedules for the level of review that I do for
12 schedules.

13 But the forward-looking part of that piece
14 would be the overall project forecast, which is always
15 provided, and things in the risk matrix that are out
16 there in the future. That would be the most forward
17 looking part of that report.

18 Q. All right. What about PSL, PTN accrual
19 report?

20 A. Accrual report? That's just a report of the
21 accruals, which is what we're spending in each one of
22 the major vendor categories.

23 Q. All right. And the variance?

24 A. The variance is your -- the forward part of
25 that is, it gives your actual cost to date every month,

1 and it shows the forecasted expenditures on a
2 month-by-month basis in each one of the major categories
3 to the end of the project, and so from that, you can
4 derive cash flows. Now, the further out you get, the
5 more uncertainty there is with that. But that's our
6 best effort on predicting the cash flow for the project.

7 Q. Okay. The monthly operating performance
8 report?

9 A. The monthly operating report is a status
10 report that -- the forward-looking part of that is, we
11 put on there how we're doing against the plan schedule,
12 and we put the total project forecast on there. It has
13 much more than that, but the "much more than that" is
14 all real-time, month over month.

15 Q. Okay. The risk matrix?

16 A. The risk matrix, which is a part of the
17 project management report, we provide that in a number
18 of formats. I mentioned that it's in the work for the
19 chief nuclear officer, and it's in the monthly project
20 report. It has all the risks that we know to date, and
21 so that's risk that's real-time as well as any risk that
22 we're forecasting or worried about to the end of the
23 project. So the forward-looking part is -- most of the
24 risk matrix is forward-looking.

25 Q. All right. The LAR schedule?

1 A. The LAR schedule is all forward-looking,
2 because it's about where you are today, and you're
3 trying to anticipate what the NRC is going to do.

4 Q. Modification schedule?

5 A. That's all forward-looking. That has the --
6 for every single modification, the planned progress on a
7 mod-by-mod basis until the design is final.

8 Q. Okay. The monthly cash flow charts?

9 A. That's both backward-looking from the
10 beginning of the year, the actuals, and forward-looking
11 to the end of the project, what your planned cash flows
12 are month over month.

13 Q. Executive Steering Committee meeting
14 presentations?

15 A. The Executive Steering Committee
16 presentations, that's a high level project status,
17 indicator packet. It provides the total project
18 forecast. It provides a schedule and preparations to
19 meet those schedules. So it's basically -- the
20 forward-looking part of that is the communication for
21 how we see this unfolding from now to the end of the
22 project. It has a risk matrix in it. But primarily
23 it's a status report, what has transpired since the last
24 time we talked to you, and then what are the things that
25 are coming at us, but it's not a schedule.

1 Q. All right. I want to skip the Bechtel status
2 report and go to -- because I've got a question on the
3 Bechtel status report, and go to the vendor integration
4 meeting presentations.

5 MR. MCGLOTHLIN: Keino, this is Joe. I don't
6 like to interrupt, but if you're changing subjects,
7 would this be an appropriate point to take a short
8 break?

9 MR. YOUNG: We'll take a break after. We've
10 only got two more, Joe, and then we'll take a
11 break, because I want to go through this exhibit
12 first. Okay?

13 MR. MCGLOTHLIN: Okay. Just remember that the
14 court reporter has got the hardest job of any of
15 us, and she's about to that point.

16 BY MR. YOUNG:

17 Q. Okay. Quickly, Mr. Jones, can you explain the
18 vendor integration meeting presentations, the forward
19 period of it?

20 A. The forward period of it is what the vendors
21 plan to do going forward to improve or enhance their
22 performance. That's the forward period of that report.

23 Q. All right. And the Bechtel status?

24 A. The Bechtel status report, the forward-looking
25 part of that is their forecast for completion of their

1 engineering and planning projects, and also they provide
2 their forecast of what they think their costs are going
3 to be to the end of the project.

4 Q. Mr. Jones, quickly, we'll do that question
5 before we take a break. I notice that in the Bechtel
6 status report, it requires a weekly for the St. Lucie,
7 but only a monthly for Turkey Point. Why is the period
8 different for these two sites?

9 A. I don't know. There are two different site
10 organizations, two different site directors. I don't
11 want to speculate, but I guess one required it weekly
12 and the other one required it monthly.

13 MR. YOUNG: Joe, we can come back at 3:00.

14 Okay? Is that okay, Joe?

15 MR. MCGLOTHLIN: Let's take 10. That's 3:03.

16 MR. YOUNG: Okay.

17 (Recess from 2:53 p.m. to 3:04 p.m.)

18 BY MR. YOUNG:

19 Q. Mr. Jones?

20 A. Yes.

21 Q. A new line of subject. If I can have you turn
22 to TOJ-17 --

23 A. Mr. Young, before we go there, I did want
24 to -- you were asking me specific questions about
25 forward-looking, and I wanted to make sure that I

1 characterized these reports appropriately, you know,
2 given forward-looking, such as an engineering forecast.
3 The things in the near term, of course, that's much more
4 predictable and reliable. But those things, once they
5 get out several months or a year from now, we qualify
6 that information.

7 And you can see the frequency with which we
8 provide that information. And our senior executives are
9 very familiar with the variability and how subject to
10 change those forward looks are. You know, we meet
11 quarterly with the senior execs or as necessary if we
12 see a significant course correction coming.

13 Q. Okay. Mr. Jones --

14 A. I also just wanted to clear up the record a
15 little bit. I was asked earlier about the vertical axis
16 on the plant change modification, and that --

17 (Interruption.)

18 MR. YOUNG: We can go off the record for a
19 second.

20 (Discussion off the record.)

21 BY MR. YOUNG:

22 Q. Okay, Mr. Jones. We're back on the record.

23 A. Okay. For the record, the question in regard
24 to what is the Y axis, the Y axis is the number of
25 modifications, not the percentage of modifications. It

1 was just hard to distinguish, because 23 packages
2 complete versus 23 percent, the numbers were so close,
3 we just needed to go validate back to the source.

4 MR. ANDERSON: And, Joe, that was to clear out
5 your question on that subject.

6 MR. McGLOTHLIN: I understand. Thank you.

7 BY MR. YOUNG:

8 Q. Mr. Jones, we'll pick up on something that
9 Mr. McGlothlin asked you to look at, Exhibit TOJ-17. T
10 it's one exhibit after --

11 A. We're still in the March 21 testimony?

12 Q. Yes.

13 A. Okay. I'm on TOJ-17.

14 Q. All right. A question for you. Can you
15 please clarify what plant change modification means as
16 used here?

17 A. Plant change modification -- I'm sorry. I
18 heard some feedback. Plant change modification is a
19 term that's used to describe an engineering design
20 modification package.

21 Q. All right. Let me ask you something. An
22 increase in plant change modification, PCM, signifies
23 what about a project if all other factors are equal?

24 A. Could you be more specific?

25 Q. For example, if PCM increases and nothing else

1 about the project increases, meaning they stay the same,
2 what does that mean about -- what does that mean,
3 basically?

4 A. I think I understand the question. The number
5 of modifications can change throughout a major project,
6 certainly one of this magnitude. There are
7 modifications that get canceled. We get to a certain
8 point in the engineering, and we come up with an
9 alternative to the modification. There are
10 modifications that get added. And so if the number
11 net-net is going up, then that means that you're still
12 in discovery in regards to the design engineering.

13 So it could mean any number things, so let me
14 just run through the short list. It could mean as part
15 of the LAR engineering analysis that we're not able to
16 get an acceptable result, an adequate margin, and that
17 you may have to make a modification to the plan. An
18 example of that would be that through analyses, we're
19 not -- for a nuclear event inside the container
20 building, we did not get an acceptable result concerning
21 the pressure inside the container building, and to
22 address that, we may have to make a modification in
23 regards to the containment purge system, which would be
24 a physical plant modification. So it could be driven
25 from the accident analysis engineering.

1 It could also be driven by you're doing a
2 modification to install larger valves to accommodate
3 more flow, more energy, and as you're doing your
4 engineering to size the valves and orientate the piping,
5 that would now lead you to evaluate the structural steel
6 and the supports for that additional weight of the
7 valves, the piping, and the mass that's going to be
8 inside that pipe, and that could lead you to make a
9 structural modification, which would then spin off a
10 separate engineering package to address that structural
11 modification.

12 If it's minor and just needs additional piping
13 supports, you would make that a part of the valve/piping
14 modification package.

15 It could be that a modification has just
16 gotten too complex, like the example that I gave you,
17 and it is more efficient to break the modification up
18 into pieces to allow something that may have a long
19 lead, such as a safety-related value, to get through the
20 modification process, to get the material and get the
21 planning for the installation and do the structural
22 modification separately. So it may mean that you've
23 taken a modification that through iteration has gotten
24 quite large, and now it's holding up a line of work, but
25 if you broke it up into smaller pieces, you could

1 release a portion of that into construction planning.

2 It could also signify that -- I'm rethinking
3 what I thought. Some of these design packages are what
4 we call "document only." Those are around subpoint
5 changes, and those are driven as you get -- as you go
6 through the design phase, you discover changes that
7 you're going to have to make to other systems and the
8 integration, and it may be just what we call a "doc
9 only." No physical change in the plant is required.

10 So in answer to your question -- and I thought
11 your question was, if the absolute number of
12 modification packages is changing, what does that mean?
13 I answered it in regards to what are the drivers that
14 cause that number to change. Is that what you're
15 looking for?

16 Q. Yes, absolutely.

17 TOJ-18, Mr. Jones. Now, it's my understanding
18 you discussed this with, I think, Ms. Kaufman, if I'm
19 not mistaken.

20 A. Well, we started with -- okay. What's the
21 question?

22 Q. All right. All the contracts listed in this
23 Exhibit DOJ-18 refer to the same scoping document. I
24 observed the same for your Exhibit DOJ-9 addressing the
25 2009 period. Why is it that the same scoping documents

1 are shown over and over again?

2 A. I think this is the information that was
3 requested to be provided, which is, what are the
4 modifications, what was the source or the driver for the
5 modification. So therefore, a plant modification is
6 borne out of a scoping document, and so for the
7 condensate pump -- let's pick one.

8 Q. Mr. Jones, I would like -- I'm sorry. Did I
9 cut you off?

10 MR. ANDERSON: Do you have a question?

11 MR. YOUNG: I just wanted to make sure he got
12 to answer the question I asked. I didn't mean to
13 cut him off.

14 A. I want to make sure I fully answer your
15 question. Let's just pick main steam isolation valve
16 update, St. Lucie components, the very first one on the
17 list.

18 Q. Yes, sir.

19 A. If we go all the way over to the right-hand
20 side, scoping document, it's FPL Feasibility Study 2007,
21 St. Lucie Nuclear Power Plant, Balance of Plant,
22 Extended Power Uprate, Scoping Study, February 2008. So
23 initially -- and again, I would have to go back to these
24 scoping documents, but the way I read that is this
25 upgrade was predicted back in the feasibility study in

1 2007, and it looks like confirmed in a scoping study
2 that was done February 2008 as having to be necessary.
3 And so it was initially identified in '07 as a
4 probability, so that was the very first scoping document
5 that said, "You know what? You better go do some
6 engineering and look at this, because there's some
7 probability you'll have to do this upgrade." And then
8 there was a confirmatory scoping study that says, "Yes,
9 in fact you have to do that."

10 So year over year, this modification is not
11 going away. In fact, it's a modification that we're
12 going to do as a part of the uprate. So every place
13 it's going to show up in my testimony as a modification
14 that's listed, and what was the source document that
15 drove it into the scope, it's going to be the same.

16 Q. Okay. So let me ask you this. Am I correct
17 that FPL performed, for lack of a better term, a
18 bottom-up or line-by-line scoping review of the EPU
19 process for 2009?

20 A. I think that line-by-line has been
21 overcharacterized, and it means different things to
22 different people. As a part of the engineering for the
23 project, part of the iteration of the engineering is to
24 find the most efficient, effective way to accomplish the
25 goals, whether that be more flow, more energy, you know,

1 whatever the objective is of that modification to
2 support the higher power output. And as a result of
3 that, that scope could expand or contract around that
4 modification, or even be eliminated.

5 Case in point: We were able through the
6 engineering analysis to eliminate the replacement of the
7 low pressure feedwater heaters. So in July 2009, as we
8 were moving from a very conceptual stage -- as I recall,
9 in July, we were about 2 percent of the engineering done
10 -- there was a conscious effort to say, "Let's make sure
11 we're doing the engineering in a sequence that doesn't
12 just look at when it's needed."

13 Do you follow me? The EPU is being
14 accomplished over a number of outages, and so one view
15 would be that I don't need that modification or that
16 design work done until a year from now. But if it's a
17 big, complex modification that has a lot of risk and a
18 lot of cost with it, then you want to prioritize that
19 and potentially move that one forward and accelerate
20 that and determine whether it's really necessary or not
21 or give yourself more time to minimize the impact of
22 that, if that makes sense.

23 Q. Yes, sir.

24 A. A line-by-line to me is if I have a tremendous
25 amount of definition around what we're talking about,

1 including a basis document, right down to every last nut
2 and bolt, and assumptions well documented. That's what
3 I consider a line-by-line. And I keep hearing the term
4 over and over again. In fact, my own organization used
5 it, line-by-line, at the July 25th meeting. I was
6 there, and in my view, that doesn't fit the definition
7 of a line-by-line.

8 In my view, a line-by-line is a budget, a
9 financial review for a very well-defined scope of work,
10 very well-defined cost components. Like if I'm going to
11 overhaul an engine in a car, I know exactly what the
12 labor rate is, and I know exactly how many hours. It's
13 been done a hundred times before. I know exactly what
14 the rebuild kit is going to cost. So that level of
15 detail is there, something for me to really sink my
16 teeth into.

17 July 25th was -- while there's certainly lots
18 of lines on the paper, those were conceptual estimates
19 and nothing more.

20 Q. Okay. Let me ask you this, Mr. Jones. Are
21 any of the items listed in TOJ-18 in response to the
22 2009 review effort?

23 A. I really can't answer that question without
24 doing a lot of research. Clearly, I know some are, and
25 probably some aren't. The ones that aren't here could

1 have been a result of the scope review of 2009. Some of
2 the ones that aren't here could have been the result
3 of -- let's see. When was this filed? Was this
4 filed -- this is March 1, 2011. It certainly could have
5 been an effort of changes to this list between '08, '09,
6 and where it is today, because it is as of December
7 31st. It most certainly could have been the result of
8 engineering efforts in 2010.

9 Q. Okay. Can you please turn now to TOJ-19?

10 A. Before I do that, can I take a moment and see
11 if I can find an example?

12 Q. Yes, briefly.

13 A. Sure.

14 Q. Mr. Jones?

15 A. I'm here. I don't want to speculate, so I'm
16 ready to move on.

17 Q. No problem. We can move on, then.

18 A. Some I know were definitely identified in
19 2010, and I was going to look them up. It doesn't
20 matter.

21 Q. For example, would an example be the LAR
22 engineering scoping document?

23 A. Can you point me to a reference?

24 Q. No, that was just a question. Let's look at
25 TOJ-19.

1 A. TOJ-19. I'm there.

2 Q. Okay. What I would like to do, Mr. Jones, is
3 to confirm that I'm reading this chart correctly. Okay?
4 At Turkey Point Unit 3, there were approximately four
5 months from the time all the engineering would be
6 completed until the beginning of the outage
7 implementation phase; is that correct?

8 A. Turkey Point Unit 3?

9 Q. Yes.

10 A. Which outage? Are you talking like line 19,
11 or are you talking line -- approximately 23, 24?
12 Because we did EPU upgrades in the fall of 2010.

13 Q. No, I'm talking 23, 24.

14 A. So 23, 24, the final implementation.

15 Q. Yes.

16 A. As of December 31st, it shows the engineering
17 design completing a few months before the Unit 3 outage;
18 that is correct.

19 Q. Why was the time line a reasonable expectation
20 for Turkey Point 3 activities?

21 A. Could you repeat the question?

22 Q. Why was the time line a reasonable expectation
23 for the Turkey Point 3 activities?

24 A. I'm not following you. Reasonable in regards
25 to what?

1 Q. The short time frame in terms of the four
2 months?

3 A. Well, if you look, the engineering started
4 back in 2009. So the engineering package is complete.
5 The work order package and the construction are planned.
6 So all we're showing is when the last modification will
7 be done. And we've sequenced modifications so the
8 higher risk, more complicated modifications get done
9 first and the ones with less risk and less construction
10 impact are the lower priority and completed at the end
11 of the window, and we are working to that plan.

12 As I stated earlier today, we did have issues
13 with engineering and resources, and Bechtel has
14 responded accordingly and is following their revised
15 plan.

16 Q. Okay. Based on what we know today, is the
17 schedule for TP-3 still as shown, or has it changed?

18 A. Unit 3 EPU implementation, that shows starting
19 right around January 1. And since we filed this, we
20 revised our operating schedule about March or April, and
21 that one is -- I believe it's around the first week in
22 February. Last week in January, first week in February,
23 thereabouts.

24 Q. The St. Lucie Unit 2 outage that started in
25 January of 2011 --

1 A. Mr. Young, was there a question relative to
2 the LAR?

3 Q. No. St. Lucie Unit 2, the outage that started
4 in January of 2011 was planned for an 82-day outage;
5 correct?

6 A. I don't think that's correct. I'll have to go
7 back and look at what our business plan goal is at. We
8 have a stretch goal, and we have a business plan goal.
9 The stretch goal we use -- we want people to schedule
10 for the best and plan for the worst contingency. I
11 would have go back and look at that number.

12 Q. Okay. We'll come back to that.

13 TOJ-20.

14 A. Okay. I'm there.

15 Q. Page 1 of 5.

16 A. I'm there.

17 Q. What actions did you take to verify the
18 amounts that appear on these pages?

19 A. These dollar amounts come right out of our
20 cost reports that are validated and verified by our
21 project controls organization, and they are provided to
22 me by my director of project controls and certified that
23 those are accurate and correct, and those line up with
24 what's in our monthly reports. I see these numbers
25 every month.

1 Q. Okay. Mr. Jones, you are supporting the
2 prudence of FPL's action regarding the EPU project that
3 resulted in the 2009 actual and final true-up amounts;
4 correct?

5 A. That's correct.

6 Q. Do you have your March 2010 testimony
7 addressing the EPU -- I mean the 2009?

8 A. Yes, I do.

9 Q. Can you turn to that for me, please.

10 A. That's the March 2011 for the 2009 uprate?

11 Q. Yes.

12 A. I have it.

13 Q. Just for a point of information, I'm not going
14 to focus on the 2009 schedules. I'm just going to
15 address just the testimony and the exhibits attached to
16 the testimony. Okay?

17 A. Okay.

18 Q. All right. Page 1, line 17.

19 A. I'm there.

20 Q. One second, please.

21 Mr. Jones, are you aware of any Florida EPU
22 project decisions made prior to August 1, 2009?

23 A. Yes, I am. I'm aware of a lot of decisions
24 that were made prior to July 2001 (sic). That was a
25 part of the transition and turnover plan, and all

1 project documents were turned over for my examination.

2 Q. So prior to filing your testimony in this
3 proceeding, you did review the contracts listed in
4 TOJ-9?

5 A. I reviewed TOJ-9. Mr. Young, it's not
6 practical for me to review each and every contract on
7 this project. That is not possible. That would take me
8 out of my -- I would not be able to do my role and
9 responsibility of governance and oversight if I were to
10 take on that role. I have people that are subject
11 matter experts that have that accountability to make
12 sure that when they list a contract number, that is in
13 fact the right contract number.

14 Now, there are contracts I've taken a special
15 interest in and I've read personally, and one of those
16 would be the Bechtel contract, and the other one would
17 be the Siemens, because those are the lion's share, if
18 you will, of the implementation cost, which is where our
19 greatest risk is.

20 Q. In 2009, did you participate in the revisions
21 of the contracts listed in TOJ-9?

22 A. Those contracts that would have been amended
23 or revised that would require my approval, I would have
24 approved those once I was in charge of the project.
25 Those revisions or amendments that occurred prior to me

1 taking over the project, I would not have been in the
2 review or approval chain for those.

3 I don't approve every change to every
4 contract. It depends on the scope of the change to the
5 contract, driven by the dollar amount. At different
6 levels of my organization, people have different
7 approval authority, and then they're subject, as I am,
8 to internal auditing to make sure we're following that
9 process.

10 Q. Okay. Keeping with the testimony and the
11 exhibits in this March 1st, TOJ-2.

12 A. I'm there.

13 Q. Would it be fair and correct to say that what
14 you listed in TOJ-2 are the 2009 instructions and
15 procedures for the EPU project staff and managers to
16 follow and implement during 2009?

17 A. Those were the procedures as of December 31,
18 2009. Some of those, you will note -- you've got to pay
19 attention to the issue date. If there was one that was
20 issued late in 2009, obviously, it wasn't there to be
21 followed until the point of issue. For example, I just
22 spotted one. The very last one was issued November the
23 12th, 2009, EPPI number 920.

24 Q. All right. Mr. Jones, I want to ask a
25 foundation question and then do a follow-up. Do you

1 believe the EPU project staff and managers appropriately
2 followed and implemented all these instructions during
3 2009?

4 A. Yes, I do. And again, let me say that no one
5 is perfect, and we do have an occasional deviation from
6 the standard. And when we do that, we coach, we
7 counsel, you know, we correct. Sometimes it's because
8 the process is hard to follow, and sometimes it's a lack
9 of training, or maybe even awareness. But, yes, that is
10 the expectation, to follow these procedures and
11 processes and report any deviations therefrom.

12 Q. And what's the basis for this belief?

13 A. Self-assessments performed by the project,
14 where we have people on the project perform
15 self-assessments to check for compliance, and they will
16 find instances of noncompliance or deviations and
17 document that in a corrective action program, which
18 gives me an indication people are being self-critical.

19 Also, external audits as well as internal
20 audits that examine our processes and how we follow
21 those procedures. And I've mentioned nuclear business
22 ops that reviews our practices against those procedures,
23 including our accounting classifications and how we do
24 our accruals, as well as PSC audit staff comes in and --
25 of course, it's a short period, but they also try and

1 sample a couple of these processes and invoices while
2 they're here.

3 Q. Mr. Jones, you talked with Ms. Kaufman about
4 the Concentric report, and I think you might have talked
5 to Mr. McGlothlin about it also today. My question for
6 you is, are you familiar with the June 21, 2010
7 investigation report prepared by Concentric?

8 A. Yes, sir, I am.

9 Q. All right. Can you please turn to page 5 of
10 23 in the attached order?

11 A. I'm on page 5 of 23.

12 Q. Mr. Jones, this is one of the documents I
13 asked counsel, Mr. Anderson, to provide you for this
14 deposition. Okay?

15 A. Understood.

16 Q. And that's Order PSC-10-0542-CFO-EI. Do you
17 have that?

18 MR. ANDERSON: Keino, just to confirm,
19 PSC-10-0542-CFO-EI; is that right?

20 MR. YOUNG: Yes.

21 MR. ANDERSON: We have it.

22 BY MR. YOUNG:

23 Q. And looking at Attachment A.

24 A. Mr. Young, could you repeat the attachment
25 number? Did you say Attachment A?

1 Q. Yes. It's page 11 of the order, and you'll
2 see it has "Confidential" at the top and the bottom, and
3 it's page 5 of 23.

4 A. All right. I'm there.

5 Q. On page 5, it states that -- it's the last
6 paragraph that starts "In April 2008." Do you see that?

7 A. I see that.

8 Q. And it's the second sentence, the second
9 sentence, which states, "At this time, the PSL project
10 team initiated Condition Report 2008-11443." Do you see
11 that sentence?

12 A. Yes.

13 Q. "Which stated the EPU project feasibility
14 study may not have captured the full spectrum of
15 modifications necessary for the uprate." Do you see
16 that?

17 A. I do.

18 Q. You would agree with me, Mr. Jones, that the
19 condition report is critical of the original FPL and
20 Shaw scoping estimate; correct?

21 A. I have not read the condition report, so I can
22 neither agree nor disagree.

23 Q. Let me ask you this. Are you familiar with
24 the project management team fast track, the term "fast
25 track"?

1 A. Yes, I am.

2 Q. In 2008, the EPU project was fast tracked;
3 correct?

4 A. The EPU project is a fast track modification,
5 from the first day through today, and will be through
6 the end of the project. I just want to be clear about
7 that. In other words, when we started the project, we
8 were already past the normal design and planning
9 milestones. That was a conscious decision by the senior
10 executives to fast track the project rather than follow
11 the normal process. That way, the customers could get
12 the real benefit of the megawatts earlier.

13 If you put it through the normal process, then
14 you're going to do LAR engineering, and once the LAR is
15 reviewed and approved, then you go do the design
16 engineering. On a project of this magnitude, it would
17 take probably a full year to estimate, and then it would
18 take the next several outages to implement, which would
19 probably take about 12 years. And the customers would
20 lose out on the benefit of the nuclear megawatts as
21 opposed to natural gas, and would further put the state
22 at risk by depending on more natural gas as opposed to
23 maintaining some sort of fuel diversity. So that was a
24 conscious decision by senior executives.

25 The policy and strategy which the need filing

1 was based on, the PSC certainly understood that. That's
2 why they came up with nuclear cost recovery to start
3 with, was to create that advantage.

4 What comes with that is, when you're going to
5 fast track a modification, I can't give you certainty
6 around cost, because I'm doing the engineering and
7 planning and implementation in parallel phases. That's
8 the trade-off. It doesn't mean that the cost is out of
9 control. What it means is that it's hard for me to
10 answer the question and give you an estimate as if we
11 were performing a normal job.

12 Now, by the time of this condition report, the
13 EPU project feasibility study may not have captured the
14 full spectrum of modifications necessary. That is not
15 news to FPL senior management. They knew that. It was
16 a conscious decision. The scoping study was just that,
17 a scoping study, what are those types of things that
18 we're going to get into, those types of things that
19 we're going to have to engineer and plan for. So I just
20 want to put that in context.

21 And I can appreciate, and I don't mean any --
22 I'm trying to keep my answers brief, but at the same
23 time, I am trying to take a little bit of time and
24 explain how one of these major projects is put together.

25 And if I were the site vice president at

1 Turkey Point and my only concern was operations and you
2 asked me the exact same question, I would give you the
3 exact same answer when it comes to major construction
4 projects that you're fast tracking, whether it be to
5 benefit the customers or because it's an NRC-mandated
6 change, which we also have those, like the NRC security
7 orders that came after 9/11. We didn't get to do our
8 normal project process. It was seen as a safety
9 benefit, and therefore we fast tracked those
10 modifications, and we didn't have any certainty around
11 the cost around those. But it's the same process. That
12 one was done for safety; this one is done to benefit the
13 customers.

14 Q. Okay. Mr. Jones, one page over, page 6 of the
15 same exhibit --

16 A. Mr. Young, I just want to make sure that --
17 you know, as much as we, you know, spend communicating
18 with our employees, the project controls folks that
19 wrote that condition report and raised that flag were
20 doing exactly what I would expect with them to do. They
21 can't possibly know what the strategy of the senior
22 executives and the strategy of the Florida Legislature
23 was at the time. That's a little beyond their purview.
24 So that's exactly what I would expect them to do, is
25 say, "Hey, this isn't per our normal process, and we're

1 raising a flag." So I want to make sure that you don't
2 interpret what I say as meaning I look at the project
3 controls organization as having done something they
4 should not have done. They absolutely were following
5 the process.

6 Q. Very well. All right. Page 6, the fourth
7 full paragraph. And the paragraph starts, "A second
8 meeting to review the revised PCL forecast occurred in
9 February 2011." That's what the paragraph starts with.

10 A. A second meeting --

11 Q. 2009, excuse me.

12 A. I'm with you.

13 Q. In the middle of that paragraph, it reads, "A
14 forecast of approximately 785 MM for PSL, an increase of
15 approximately 129 million." Do you see that?

16 A. Yes, I do.

17 Q. Okay. I'm trying to find out what is meant by
18 "budget." Okay? Basically, I don't understand what is
19 meant by "budget" here, because it's not in the
20 document. Do you know?

21 A. I would say the word "budget" is used in error
22 in this sentence. And whether it came out of an EPU
23 project report or whatever the source was doesn't change
24 the fact that that word is in error. It would be
25 correct if it said "over total project forecast." That

1 would be correct, but not budget. Budget is year over
2 year and month over month. Does that make sense?

3 Q. Yes.

4 A. I don't have an approved budget yet for 2012,
5 if that helps you.

6 Q. Okay. So based on your -- I'm sorry. Go
7 ahead, Mr. Jones.

8 A. I'm done.

9 Q. Based on your work experience and as the EPU
10 manager, what does the term "budget" mean to you?

11 A. "Budget" means to me as I go through the
12 budget planning cycle here this year, whether it be for
13 the EPU -- well, you said for the EPU project, so for
14 the EPU project, we take our best known information as
15 we know it right now, and we put together a forecast for
16 what we think the spend will be in 2012. And 2012
17 happens to be our most difficult year to predict. It
18 has been since 2009. It's a little easier today,
19 because I'm no longer at 2 percent engineering. I'm at
20 60 percent engineering, but it's still a very
21 challenging chore.

22 So a budget means to me that I'm going to
23 provide that information, and it's going to get vetted
24 over the next many months, and around about October or
25 November is when I'll get final approval, after I've run

1 through a number of vetting sessions and challenges, on
2 what my budget is going to be for 2012 for the project.
3 And then it will be loaded in -- that's a term we use,
4 loaded into the system, those cash flows for those
5 months, and that's what I'll be held accountable to.

6 That's what a budget means to me. Just like
7 last year, we put that together and measured ourselves
8 against it, and that's what a budget is. It's a cash
9 flow for each one of my cost centers on the project on
10 month-to-month basis.

11 Actually, that's one of the things we walked
12 through the PSC audit staff with. We opened up our big
13 project spreadsheet for the St. Lucie plant, and we
14 picked several cost centers, like Westinghouse or Areva
15 or Bechtel, and we showed them, going back to day one,
16 the actual amounts spent in each fund. Those were in
17 black, and then for the going-forward months in red, the
18 numbers that we were attempting to predict what we were
19 going to spend all the way to the end of that project.

20 But the budget for 2012, that won't be
21 approved until toward the end of the year.

22 MR. YOUNG: Okay. Thank you, Mr. Jones.

23 What I would like to do now, Mr. McGlothlin,
24 is take a five-minute break, five- or ten-minute
25 break and come back at 4:00.

1 MR. MCGLOTHLIN: That's fine with me.

2 (Recess from 3:54 p.m. to 4:15 p.m.)

3 BY MR. YOUNG:

4 Q. Mr. Jones, if I can have you to turn to the
5 investigation report and staff's July 10, 2010
6 management audit report.

7 A. July 2010 audit report. I have it.

8 Q. All right. And specifically page 6 of that
9 report.

10 MR. YOUNG: While you're looking -- Joe, while
11 Mr. Jones is looking for that, since we're back on
12 the record, what I anticipate is hopefully I can be
13 done by 5:00, depending on the responses. Okay?

14 MR. MCGLOTHLIN: We're good with that.

15 A. Are you referring to the executive summary,
16 page 6?

17 Q. Yes.

18 A. All right. I'm there.

19 Q. Mr. Jones, this is a summary chart for the
20 period January 2009 through June 2010. On the left side
21 is a heading titled "Description." Could you please
22 read aloud for me the description of the third bullet?

23 A. It says, "Bechtel submits excessive man-hour
24 estimates. FPL asks for additional estimates."

25 Q. Does that activity correspond to the May 2009

1 time frame?

2 A. Yes.

3 Q. Do you have any reason to believe FPL would
4 disagree with the characterization of excessive in the
5 description?

6 A. FPL agrees with that characterization.

7 Q. Okay.

8 A. At that time.

9 Q. All right. Can you please look at the fifth
10 item down from the top?

11 A. And, Mr. Young, the reason I know that is, for
12 the scope that we had identified at that time, in our
13 review of what it would take to self-perform that, we
14 thought that their manpower estimates were in fact
15 excessive.

16 Now, fast forward to June 2011. We certainly
17 have more scope and design evolution and so on and so
18 forth. So while I will not say that view has completely
19 changed, certainly more hours and more resources are
20 required. We still to this day think that the way that
21 Bechtel operates and other EPC contractors operate, they
22 have a lot of overhead, and their lack of, I'll say,
23 experience or ability to perform major backfits on
24 operating nuclear facilities really challenges them and
25 causes them to have to bring more resources to bear.

1 But I don't want to pick on Bechtel, in that
2 if it was URS, Washington Group, or another, they would
3 still have that. You have to appreciate that other than
4 the security mods post 9/11, they don't do major
5 backfits anymore online. They do steam generator
6 replacements offline, things like that that are very
7 contained. And even though they're big construction
8 projects, they've been done over and over and over and
9 over in the industry. So I just wanted to keep it in
10 the context of time, what we knew and when we knew it.

11 Q. All right. Let's look at the fifth item down
12 from the top, scope, changes and contract renegotiation.
13 Do you see that?

14 A. I do.

15 Q. I'm not sure I'm reading this shorthand
16 description accurately. Is it your understanding that
17 the contract and scope change is a reference to the EPC
18 contract with Bechtel?

19 A. I'm not 100 percent positive what the staff
20 intended to communicate there. We were doing -- you
21 know, re-evaluating the scope every day. Scope changes
22 continue today. We have a scope control process that we
23 deploy.

24 And not that we do contract negotiations
25 frequently, but certainly we -- I would have to say

1 opportunities in contracts, I mean, we're amending
2 contracts right now with Siemens. So it's not every
3 day, but it's pretty frequent. It's just part of what
4 we do that's part of the project management.

5 Let me give you an idea. It's worth trying to
6 get Siemens in a box for what it's going to take to do
7 the planning for the Turkey Point Unit 3 fall outage,
8 and rather than them -- and their standard contract is,
9 they'll show up a certain time in advance of the outage.
10 We want them much sooner. We want them to have much
11 greater accountability and responsibility for the
12 integration that they have to do with Bechtel.

13 So we put together a spec, a contract, and
14 we're negotiating that with them now. Number one, we
15 want certainty around what the cost will be; and two,
16 contractually, we want to lock them in and make sure
17 it's clear to them that it's their accountability to
18 work with Bechtel to accomplish the work. So that would
19 be an example. Contract renegotiation, we're not
20 tearing up the contract and starting over, but it's
21 adjustments and amendments, and that's part of our core
22 business.

23 Q. Okay. Considering the EPU scope review and
24 changes FPL has assessed in 2009, 2010, and now 2011,
25 would you agree that these changes were largely under

1 FPL's control?

2 A. Yes, in the sense that all work is under our
3 control, and that as a part of project management, we
4 can at any given time decide to proceed with the project
5 or not to proceed with the project. When I have a
6 discovery such was one that one of the Commissioners
7 asked me about back in August about a certain steam
8 pressure drop in the system, I can choose to not add
9 that scope and not do that work, or I can choose to do
10 that work.

11 We make those decisions based on the economic
12 analysis of is it beneficial to our customers and does
13 it make sense for the megawatts. We don't -- so when
14 you say in control, it's in control in the sense that
15 I'm doing my engineering analysis. My engineering
16 analysis points me to what I need to do. And as long as
17 we're going to accomplish the project and deliver the
18 megawatts, then we're going to follow through on those
19 actions.

20 If through that process the modifications
21 become so big, so complex, so costly that it's not
22 feasible, then we'll stop. That's part of the deal.
23 But I'm building a car, you know, and I've got to put
24 the tires on it. It won't work without the tires.

25 Q. Okay. Mr. Jones, can you please comment on

1 the status and progress towards the NRC issuance of the
2 EPU, the LAR for Turkey Point later this year?

3 A. Yes. The Turkey Point license amendment
4 request for EPU or specific to the EPU is in the review
5 and approval process, and about three-quarters of the
6 branches have completed their review and provided what
7 we call their draft safety evaluations, and there's a
8 number of branches that are outstanding. And the NRC
9 schedule, they tentatively have it scheduled to go to
10 the ACRS late in the fourth quarter of this year for
11 review and approval, and every indication is that they
12 are making their intermediate milestones for that
13 approval.

14 So we, I think, during our project plan
15 forecast March 2012 for completion, or February 2012,
16 somewhere in there. I'm not exactly sure of that month,
17 but they are certainly on track to meet that.

18 Q. All right. Can you please comment briefly on
19 the status and progress towards an NRC decision to
20 accept and publish a review schedule for the St. Lucie
21 EPU LARs?

22 A. St. Lucie Unit 1 has been accepted. It's in
23 the review and approval process. The NRC asked for a
24 different analysis to be performed as a part of that,
25 and we committed to do that and have that to them by May

1 31st. We met our commitment, and it's back with the --
2 so we are awaiting the NRC to publish their schedule and
3 their commitment for Unit 1, and they've yet to do that.
4 We talk to them every week. The review is going on.

5 They are evaluating their resources and the
6 workload that is on -- and I apologize for the acronym,
7 the ACRS. That's the independent review board that's
8 appointed by the Commissioners. They're not employees
9 of the NRC that actually do the final review. It's
10 called the ACRS. And my most recent update is that the
11 NRC is still working on that schedule and looking at the
12 availability of the ACRS before they commit to do the
13 final on Unit 1.

14 Unit 2, the NRC is communicating if not by the
15 end of June, then early July to finalize their
16 acceptance, and then they'll start the review. But to
17 them, it's a lower priority than Unit 1 to get to a
18 resource plan and commit to a schedule on Unit 2.

19 Q. Okay. Mr. Jones, I'm going to try to frame
20 this in a yes or no type format, and if you need to
21 explain, please explain briefly for me.

22 Based on what you know today, do you believe a
23 prudent utility manager should have explicitly expressed
24 expectation of increased EPU total project costs during
25 the 2009 NCRC hearing?

1 MR. ANDERSON: You want to read that slowly?

2 A. I'm sorry. That one just kind of went over my
3 head. I'm sorry.

4 Q. Based on what you know today, do you believe a
5 prudent utility manager should have explicitly expressed
6 an expectation of increased EPU total project costs
7 during the 2009 NCRC hearing?

8 MR. ANDERSON: So you're asking him a question
9 not based upon what the company knew in 2009, but
10 based upon what the company knows in 2011; is that
11 right?

12 MR. YOUNG: Yes.

13 MR. ANDERSON: All right.

14 A. I'm still not sure, even with Bryan trying to
15 clarify, what you're asking me. And I don't want to
16 come off as trying to dodge your question here. If
17 you're asking me should the testimony on September the
18 9th been different, my answer is the same as it was last
19 year, and the answer is no.

20 And reason that answer is no is that within
21 that testimony, there was information that obviously
22 said things were changing and subject to change. And
23 the person providing the testimony September the 8th or
24 9th, or whatever day it was, absolutely knew what we
25 were doing on the project, absolutely knew that senior

1 management had not accepted the proposal from Bechtel,
2 absolutely knew that the project had been directed to
3 evaluate a self-perform option, absolutely knew the
4 project had been directed to find ways to, independent
5 of Bechtel or any other EPC, provide a means of
6 estimating project work that had little to no
7 engineering done, and had that been done before, and
8 what that success rate was, and was that feasible. So
9 that person providing that testimony absolutely knew
10 that that work was in progress, and that was going to
11 take months.

12 And in fact, we didn't finish and come up with
13 our nonbinding cost estimate revision until February or
14 March of 2010, which is evidence of what type of effort
15 it took to vet those numbers that were being discussed
16 in the summer of 2009.

17 And let me again state that the project
18 controls people did their job. As a project controls
19 person, if I tell you I'm going to bring in 500 people
20 and this is the rate, they do the spreadsheet, they do
21 the math, and that's the number you come up with.
22 That's not an issue here. The project controls people
23 got the algebra correct.

24 The fact is that we're not going to let
25 Bechtel bring in 3,000 people. We're not going to agree

1 to that. If you agree to a target price now, you're
2 locked in. Okay? You're locked in. It's to their
3 advantage to get you to agree to a figure and agree to a
4 number when there's so much that's undefined. Okay?
5 You've given away your ability to influence that
6 outcome. You don't do that, no matter of it's Bechtel
7 or Shaw or Washington Group.

8 What you do do is, you let them give their
9 indicative bid, and now you've got their view of how
10 they want to run this project and how many people they
11 think, and you say, "You know what? This is a time and
12 material project, and it has a target price provision,
13 and it's up to me whether or not I want to exercise it.
14 If I choose not to, I'm going to control your head
15 count. And for every body you want to bring in my door,
16 I control it. You cannot bring a single person on my
17 site unless you adequately justify it."

18 That's why when you look at the
19 month-over-month cost, it's dead on, because we
20 absolutely control them day over day, week over week,
21 month over month. The big debate is about what you're
22 going to spend in 2012. Okay?

23 Q. Mr. Jones, let me ask you this question.

24 MR. ANDERSON: Keino, he's not done with his
25 answer, please.

1 A. And so the big debate is about who's right or
2 what it's really going to take to accomplish this major
3 construction work at the back end of 2011 and 2012.

4 MR. YOUNG: I understand that. Bryan --
5 Mr. Jones, not to cut you off. Bryan, he did
6 answer my question. I'm trying to move forward.

7 MR. ANDERSON: I understand, but I don't think
8 he answered the question. You're interrupting him,
9 for the record, and I object.

10 MR. YOUNG: Hold on, Bryan. Hold on. You
11 have an opportunity to rebut.

12 MR. ANDERSON: No, sir. I'm entitled to have
13 my witness answer the question and not be
14 interrupted. He has answered questions for eight
15 hours today, Keino.

16 MR. YOUNG: I understand that. I understand
17 that. And he has answered my question. I have
18 asked the question, and he has answered it, and I
19 think he has explained it sufficiently for me.
20 Okay? Now, let me move forward. I'm trying to
21 meet a time and cut the questions down.

22 MR. ANDERSON: That's fine. I want to make
23 sure the court reporter got his answer and just
24 verify that she heard the answer so that it was
25 transcribed without the interruptions. And if

1 we're good, then we can move on. But the challenge
2 there, Keino, was -- and I apologize for getting
3 heated, but you were speaking over the witness with
4 a court reporter who is in another remote location,
5 and we're all very focused on having a good clear,
6 record here. So if whoever is with the court
7 reporter can just determine whether we have a --
8 you were able to hear adequately and have an
9 accurate record, I'm good.

10 MR. MCGLOTHLIN: I'm going to pose that
11 question to Mary Neel.

12 She's checking her notes so she can answer
13 your question.

14 (Discussion off the record.)

15 BY MR. YOUNG:

16 Q. Mr. Jones, you stated that you believe that
17 the actions were reasonable and prudent. What is your
18 understanding of -- your definition of prudence?

19 A. My definition of prudence is that when you
20 make a decision or you take action, at the point in time
21 that you've made your decision or taken your action,
22 that you've done so in a reasonable manner based on the
23 best available information at the time.

24 Q. Okay. Now, you used the word "absolute" in
25 there a couple of times on a previous question.

1 Prudence doesn't have anything to do with absolute;
2 correct?

3 Let me rephrase it. The word "absolute," in
4 terms of a standard of prudence, there's no word -- the
5 word "absolute" does not appear in the standard of
6 prudence; correct?

7 MR. ANDERSON: I'll object to the form.
8 That's an argumentative question as to a legal
9 standard of prudence.

10 A. Mr. Young, I'm not an attorney. You asked me
11 for my definition of prudence, and I gave you my
12 definition of prudence. I'll defer to the lawyers as
13 far as the legal definition.

14 Q. Okay. And I think you said you're not an
15 attorney; correct?

16 A. Yes, but I'm thinking about it.

17 Q. Don't do it. It's not worth it.

18 Mr. Jones, I only have a few more questions.
19 Okay? Mr. Jones, can you now turn to your May 2, 2011
20 testimony, prefiled testimony? It's dealing with the
21 nuclear power plant cost recovery for the years ending
22 December 2011 and 2012?

23 A. Keino, I have my testimony. Is there a page?

24 Q. Yes. On pages 21 and 22, you discuss the
25 non-power block engineering costs, and that includes

1 increase in scope for six dry cage storage -- excuse me.
2 Dry cask storage containment.

3 A. Yes, that's correct.

4 Q. On page 22, line 18 --

5 A. I'm with you.

6 Q. You stated that this category of costs is
7 approximately 1.1 million more than projected, primarily
8 due to the addition of the dry cask storage containers.
9 Did I read that correctly?

10 A. Yes, you did.

11 Q. Can you please explain why, briefly explain
12 why the dry cask storage containers are a necessary
13 expense at this time?

14 A. Yes. The reason is that we're going to have
15 -- as an as a result of the extended power uprate, we're
16 going to have to meet the new requirements imposed by
17 the Nuclear Regulatory Commission for spent fuel pool
18 criticality. We're going to have to create more space
19 between the fuel cells -- between the fuel elements,
20 excuse me. And so that requires us to offload more fuel
21 than we would have otherwise if we were not doing the
22 extended power uprate.

23 And real, real brief, Keino, before you
24 actually do a refueling outage, you have to place your
25 new fuel in your spent fuel pool, because you have to

1 handle all the fuel underwater to get it in and out of
2 the reactor. And the most reactive fuel is the fuel
3 that hasn't been expended. The EPU fuel has more
4 energy, so therefore -- it's more reactive is the way to
5 think of it. And when it comes out, it's going to be
6 more reactive than prior generations of spent fuel.

7 And given the new requirements imposed by
8 staff for additional conservatism for spent fuel pool
9 criticality, it's going to require us to offload more
10 fuel. And what that does is, you take the fuel that has
11 been there the longest, and you remove it from the pool
12 and put it in dry cask storage, and now that gives you
13 the ability -- think about a checkerboard. It gives you
14 the ability to space your fuel elements further apart
15 such that you will not have an inadvertent criticality
16 should there be what's referred to as a dilution event
17 in the spent fuel pool. The spent fuel pool has borated
18 water. Boron absorbs neutrons, and pure water helps
19 neutrons.

20 Q. Okay. Can you please turn to TOJ-24, page 10
21 of 16.

22 A. TOJ-24. I'm there.

23 Q. Okay. Do you see spent fuel pool?

24 A. Which page?

25 Q. Page 10 of 16.

1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
17
18
19
20
21
22
23
24
25

A. Yes.

Q. On the spent fuel pool -- excuse me. I'm going too fast. I'm sorry. You indicate for 2011 activity for which St. Lucie plant?

A. St. Lucie, 2011, the very last line?

Q. Yes.

A. You want to know for which plant that is?

Q. Yes.

A. That's going to be for both units.

Q. Okay.

A. Mr. Young, what has really occurred here is that the NRC, even though it's not a published regulation, published order, is evaluating any changes to spent fuel pools licensing basis based on an interim staff guidance document that was only issued at the end of 2010. And they're not approving any amendments, whether they be EPU or spent fuel pool or anything related to spent fuel pool criticality analysis if you don't comply with the new conservative analysis. Even though that goes against their published guidelines for a license amendment request, they are imposing that additional restriction.

So even though the spent fuel pool, we were well within our licensing basis for St. Lucie, we are having to add those additional margins to the spent fuel

1 pool criticality. And so there's modifications that
2 we're going to have to do now that we wouldn't have
3 otherwise had to do if we hadn't opened up our license
4 to the NRC for an extended power uprate.

5 Q. Okay. The third column over, contract, for
6 spent fuel pool it says TBD.

7 A. That means to be determined. At the time of
8 this filing, we did not have a contract or purchase
9 order in place for the modifications. We do know --
10 having done this type of modification before, we know
11 what needs to be done. In the case St. Lucie, it's
12 called Metamic inserts, and we have a good feel for what
13 that cost is, and so we've included that in our
14 forecast, but we do not have the contract locked down
15 yet.

16 Q. Okay. Based on that status of the contract,
17 is it reasonable to assume that this work will be
18 completed in 2011, given the status of the contract?

19 A. When you say work, the scope of the total
20 spent fuel pool modification involves the engineering
21 and the analysis for where to put the Metamic inserts,
22 which that's well under way. Then it also includes the
23 manufacture of the Metamic inserts themselves and
24 payment for those. Then there's the actual deployment
25 into the pools, which is really based on the refueling

1 outages.

2 So this is work that is going on right now,
3 the engineering piece of it, and we're about to -- the
4 manufacturer of the Metamic inserts, we're going through
5 the final approvals of that now. And I don't remember
6 off the top of my head when we actually insert them in
7 the pool. It's not -- I don't need to insert them in
8 the pool right away.

9 Q. All right.

10 A. But the cash flow for that project forecast
11 will be based on the engineering, the manufacture, the
12 progress payment for the manufacture, when the material
13 arrives onsite, and then the actual deployment in the
14 pool.

15 Q. Okay. Mr. Jones, on page 11 of this
16 testimony, the same testimony --

17 A. I'm there.

18 Q. You noted that the St. Lucie Unit 2 outage
19 lasted longer than planned. Do you see that?

20 A. That is correct.

21 Q. Can I have you read that aloud for me, please?

22 A. The question is, "Were there any unanticipated
23 schedule changes this year?"

24 "Answer: Yes. The EPU portion of the
25 St. Lucie Unit 2 spring outage lasted longer than

1 planned due to an error by Siemens, the vendor who is
2 performing the turbine generator work."

3 Q. Has FLP's collection effort achieved 100
4 percent of the repair costs?

5 A. I'm sorry. Could you repeat the question?

6 Q. On page 12 -- I'm sorry. On page 12, you
7 noted that FPL is attempting to require Siemens to
8 repair the damage at no cost to FPL.

9 A. Siemens did effect the repair. The machine is
10 in service. We got the additional megawatts, by the
11 way. We got a few more than expected, actually, which
12 is good news. And we are going through that commercial
13 process now to ensure that the hours they had to spend
14 on the project to effect the repairs, the materials, and
15 so on and so forth does not get charged to us. We are
16 going through that. It's a lengthy process. I
17 mentioned earlier that we keep book on a daily basis to
18 capture all the costs associated with that, and then we
19 get into commercial negotiations with Siemens over our
20 claim. And, of course, in a project like this, they'll
21 have claims against us as well.

22 Q. So would it be fair to say that FPL's
23 collection efforts have not achieved 100 percent of the
24 repair costs?

25 A. I would say it's in progress.

1 Q. How much has -- I'm sorry. Go ahead.

2 A. When it's in progress, you vet all the puts
3 and takes, you come to agreement, and that's when you
4 have the final settlement and you know. It's not like
5 I'm recovering 10 percent this week and 20 percent next
6 week. That's not how it works.

7 Q. Okay. How much has FPL included in the NCRC
8 that may be subject to adjustment due to FPL's ongoing
9 efforts to achieve 100 percent collection of the repair
10 costs?

11 A. This is 2011 costs, and so I don't know that I
12 can answer your question. Certainly the cost associated
13 with the repair is not part of nuclear cost recovery.
14 That is on the vendor to remedy per the contract, and
15 that's our position.

16 MR. YOUNG: Okay. Mr. Jones and Bryan?

17 MR. ANDERSON: Yes, Keino.

18 MR. YOUNG: I'm going to ask for a late-filed
19 exhibit on this, and that will be Late-filed
20 Exhibit Number 8. Even if the amount is zero, I
21 still want a late-filed exhibit on it just to
22 confirm what the amount is. Okay?

23 MS. CANO: May I ask a clarifying question,
24 Keino? Do you want the amount that's included in
25 the 2011 NCRC related to this incident, if any?

1 MR. YOUNG: Yes.

2 MR. ANDERSON: With that clarification, we'll
3 provide that.

4 THE WITNESS: Mr. Young, I also want to be
5 clear that the contract that we have with our major
6 vendors, these are the original equipment
7 manufacturers. They bring in several hundred
8 people to do this kind of work. They do it around
9 the world. They're the subject matter experts.
10 It's not prudent or reasonable for us to have that
11 kind of staff for an infrequent evolution for this.
12 With those procedures and processes, we provide
13 oversight and logistics of that, but I cannot
14 oversee 300 people. That's not practical either,
15 and it's not cost-effective.

16 On a large, complex project like this, or even
17 small jobs, we have humans involved, and mistakes
18 occur. That's part of the risk of doing business,
19 whether it be a project or normal operations and
20 maintenance. For the direct costs associated with
21 effecting the repair, the time, the material, the
22 labor, Siemens is not eligible for reimbursement
23 for that amount, and that's the amount I'm talking
24 about is not in nuclear cost recovery.

25 Outside the limit of that, that's a part of

1 the risk and a part of doing the project, no
2 different than if an engineer makes an error in a
3 calculation and we have to modify a piece of
4 structural steel when we find the error. That's
5 not performance that we can condone, but that is a
6 part of project risk, and that is -- as long as
7 that's reasonable and subject to prudence, that is
8 recoverable.

9 MR. YOUNG: I understand your position,
10 Mr. Jones, and I have no further questions.

11 I just want to clarify the late-filed exhibit.
12 It is Exhibit Number 8. And Bryan or Jessica,
13 however you want to name that late-filed exhibit is
14 fine with me.

15 MR. ANDERSON: Okay.

16 MR. YOUNG: So if you want to give the court
17 reporter a name for it so we can have it noted for
18 the record.

19 MR. ANDERSON: We came up with a name, Siemens
20 costs associated with rework.

21 MR. YOUNG: If I could add to that, included
22 in the NCRC 2011 hearing.

23 MR. ANDERSON: You can add that to it.

24 (Late-filed Deposition Exhibit Number 8 was
25 marked for identification.)

1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
17
18
19
20
21
22
23
24
25

MR. YOUNG: Okay. Mr. Jones, it's always a pleasure. I have no further questions.

THE WITNESS: Thank you. I hope you have didn't cut it short on my account. I'm more than happy to answer questions and try to provide insight into how all this works.

MR. ANDERSON: Well, FPL does not have redirect. I know our valiant court reporter is working very hard. We are going to ask for an expedited transcript. We would like to reserve signature and let the witness review. And with that, we thank everyone for their time.

MR. MCGLOTHLIN: And I don't remember if this is on the record or not, but FPL will review the transcript and notify us of any confidentiality claims, and we'll follow the procedure.

MR. YOUNG: This is Keino at the Commission. Our court reporter will contact the court reporter to order a copy.

MR. MCGLOTHLIN: All right. I think we're done.

(Deposition concluded at 4:57 p.m.)

1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
17
18
19
20
21
22
23
24
25

CERTIFICATE OF REPORTER

STATE OF FLORIDA:

COUNTY OF LEON:

I, MARY ALLEN NEEL, Registered Professional Reporter, do hereby certify that the foregoing proceedings were taken before me at the time and place therein designated; that a review of the transcript was requested; that my shorthand notes were thereafter translated under my supervision; and that the foregoing pages numbered 1 through 183 are a true and correct record of the aforesaid proceedings.

I FURTHER CERTIFY that I am not a relative, employee, attorney or counsel of any of the parties, nor relative or employee of such attorney or counsel, or financially interested in the foregoing action.

DATED THIS 30th day of June, 2011.

MARY ALLEN NEEL, RPR, FPR
2894-A Remington Green Lane
Tallahassee, Florida 32308
(850) 878-2221

CONFIDENTIAL TRANSCRIPT

ACCURATE STENOGRAPHY REPORTERS, INC.
2894-A Remington Green Lane
Tallahassee, Florida 32308
(850)878-2221

June 30, 2011

BRYAN J. ANDERSON, ESQUIRE
Florida Power & Light Company
700 Universe Boulevard
Juno Beach, Florida 33408-0420

Dear Mr. Anderson:

Re: Docket No. 110009-EI

Enclosed is your copy of the deposition of TERRY O. JONES taken in the above matter on June 22, 2011.

Since reading and signing was not waived, please make arrangements with the witness to read your copy of the transcript and make any corrections on the errata sheet on the following page.

Please forward the completed errata sheet to Joseph A. McGlothlin for attachment to the original transcript. You should also attach a copy of the errata sheet to your transcript.

Thank you for your cooperation in this matter.

Sincerely,

Mary A. Neel

cc: Joseph A. McGlothlin, Esq.

ERRATA SHEET

Under penalties of perjury, I declare that I have read the foregoing transcript of my deposition, pages 1 through 184, and hereby subscribe to same, including any corrections and/or amendments listed below.

July 8 2011
DATE

Terry Jones
TERRY C. JONES

PAGE/LINE	ERROR OR AMENDMENT	REASON FOR CHANGE
	<u>see attachment</u>	

Reporter: Mary A. Neel - Date of Deposition: 06/22/11
Re: Nuclear Cost Recovery Clause, Docket No. 110009-EI

TERRY JONES DEPOSITION ERRATA SHEET

<u>PAGE / LINE</u>	<u>ERROR OR AMENDMENT</u>	<u>REASON</u>
3 / Appearances	Change "Veisler" to "Beisler"	transcription error
19 / 18	Change "of" to "or"	transcription error
42 / 23	Change "down" to "them"	transcription error
50 / 8	Change "first" to "purpose of"	transcription error
56 / 5	Add "be performed" at end of line	grammatical correction
56 / 6	Change "operate a" to "in an operating"	grammatical correction
58 / 1-13	Delete "in this manner..." (line 1) through "...stands as it is. And" (line 13), and change "we" to "We" (line 13)	incorrect recollection
80 / 5, 7, 11, 15, 16	Change "Veisler" to "Beisler"	transcription error
92 / 2	Delete "of"	transcription error
107 / 1	Delete "and" before "feed pump"	transcription error
111 / 12	Delete "of"	transcription error
124 / 12	Change "MOBR" to "MOPR"	transcription error
138 / 19, 21	Change "container" to "containment"	transcription error
139 / 19	Change "value" to "valve"	transcription error
140 / 4	Change "subpoint" to "setpoint"	transcription error
140 / 23, 24	Change "DOJ" to "TOJ"	transcription error
143 / 15	Delete space in middle of word "that" and insert space before "I"	transcription error
149 / 24	Change "2001" to "2009"	transcription error
170 / 6	Change "of" to "if"	transcription error