

State of Florida



Public Service Commission

CAPITAL CIRCLE OFFICE CENTER • 2540 SHUMARD OAK BOULEVARD
TALLAHASSEE, FLORIDA 32399-0850

-M-E-M-O-R-A-N-D-U-M-

DATE: February 7, 2014
TO: Carlotta Stauffer, Commission Clerk, Office of Commission Clerk
FROM: Sonica C. Bruce, Economic Analyst, Division of Economics *[Signature]*
RE: Docket No. 130178-SU - Application for staff-assisted rate case in Polk County by Crooked Lake Sewerage Company.

The attached documents were sent to the Division of Economics on February 6, 2014. The Utility provided proposals for proforma items. Please incorporate the documents into the docket file.

RECEIVED-FPSC
14 FEB - 7 AM 9:24
COMMISSION
CLERK

Letter of Transmittal

Date: 2/5/14

To:

FLORIDA PUBLIC SERVICE COMMISSION
CAPTIAL CIRCLE OFFICE CENTER
2540 SHUMARD OAK BLVD
TALLAHASSEE, FL 32399

From:

CROOKED LAKE PARK SEWERAGE COMPANY
5578 COMMERCIAL BLVD
WINTER HAVEN, FL 33880

ENCLOSING QUOTES TO BE CONSIDERED FOR OUR PENDING SARC.

THANK YOU



DEB NULL

GARRARD BUILDING CONTRACTORS LLC.

Concrete Restoration Waterproofing Caulking Epoxy Injection Soil Stabilization

PROPOSAL

January 28, 2014

Project: CROOKED LAKE SLUDGE DRYING BED

Garrard Building Contractors LLC. Proposes to furnish labor and material to complete the scope of work for the project referenced above per H. L. Bennett and Associates drawing, sheet 1, titled "SLUDGE DRYING BED":

- **Construct a 20 foot by 40 foot sludge bed to include the following:**
 - Masonry wall perimeter total height 5'4"
 - Concrete footer to support masonry wall
 - Underground piping stubbed out 5' for connection by others
 - 30 mil poly pond liner
 - Aggregate and sand per plan
 - Bond Excluded
 - Change orders to be reviewed and negotiated prior to any c/o work commencing.
 - Garrard Not responsible for delays in schedule due to rain/weather delays, escorts, security, natural disaster, Etc.
 - This Proposal is good for 30 Days beyond Bid date.
 - Material will be ordered upon signed agreement and Contract received.
 - **Lump sum price \$31,750.00**

Please call if you have any questions.

Thank you in advance for the opportunity to price this project.

Thank You,

Dong Stern
863-207-0569



Proposal / Quotation

710 S Milwee Street, Longwood, FL 32750
Tel : 407-339-7134 Fax : 407-339-6618

Date **11/7/13**

Reference **13264**

Altair Environmental Group, LLC (Altair) is pleased to confirm the following proposal / quotation wholly subject to their **Standard Terms & Conditions of Business** as attached :

Client:	Consta Flow Inc. 1902 Barton Park Rd. #209 Auburndale, Fl 33823	Mr. Daniel Alexander 863-965-2599 danny@constaflow.com
----------------	--	---

Project:	Caloosa Lake Village; Lake Wales, Florida
-----------------	--

Services:	Sanitary Sewer System Mapping(Phase #1) and Cleaning/Internal Television Inspection(Phase #2) including a Complete Report of Findings including System Deficiencies, Recommended Rehabilitation Techniques and Associated Costs(includes all DVD video's)
------------------	--

Price:	Phase #1 Mapping(surface investigation).....\$4500.00 Phase #2 Cleaning/Internal Inspection(includes manholes) 30,000 l.f.(approx) x \$1.95.....\$58,500.00
---------------	--

The above price is based on the minimum stated quantities of ___ LF of Sanitary Sewer Stormwater Pipelines. Any additional LF over and above the stated minimum will be charged at \$ _____ per LF.

Special Conditions	Phase #1: Includes surface investigations to locate manholes and pipe runs Phase #2: Project footage estimate is an approximate and actual quantities are based on field task results
---------------------------	--

Client Responsibilities (at no cost to Altair):

- | | |
|---|--|
| <input checked="" type="checkbox"/> Local facilities or dumpsite for disposal of removed debris / waste material. | <input checked="" type="checkbox"/> Traffic control beyond traffic cones and permits where applicable. |
| <input checked="" type="checkbox"/> Water supply from nearest fire hydrant. | <input type="checkbox"/> Exposure of all manholes and access to all work areas without delay. |
| <input checked="" type="checkbox"/> Site area for storage of equipment. | |

Payment terms are to be within 15 days of invoice date, invoices will be submitted upon work completion or minimum monthly.

Submitted by: Don Layton/Estimator
(Title)



Signature on behalf of
Altair Environmental Group, LLC

parties or any other reason and the services are commenced or completed on the Clients written or verbal instruction due to emergency, urgency or some other reason, then these terms and conditions will be deemed to have been accepted by the Client as if such proposal or quotation had been signed.

CLIENT RESPONSIBILITIES: The Client will normally provide the following services, at no cost to ALTAIR for the duration of the project, unless agreed otherwise in writing by ALTAIR, a) Approved dumpsite and disposal for all materials to be removed from site of work, b) Access to site of work for ALTAIR personnel and equipment, without delay, c) All temporary site facilities including suitable storage space for equipment, d) Any special permits and/or licenses, without delay, e) Supply and access to all water required for the project from the nearest fire Hydrant, f) Work areas prepared and accessible, without delay, to enable the services to be provided, g) Authorized representative of the Client at the site of work, at all times services are being performed and with authority to accept the services as completed and / or hours worked and h) Location and exposure of all manholes in the project area.

11/7/13

Mr. Daniel Alexander
Consta Flow Inc.
1902 Barton Park Rd. #209
Auburndale, Fl 33823

Re: Crooked Lake Sewer - Caloosa Lake Village Sanitary Sewer System Program

Dear Mr. Alexander,

It was a pleasure meeting with you again, thanks for taking the time. As per our conversation, we are pleased to provide you with our cost proposal for Caloosa Lake Village. The program is two phase with phase one being a surface mapping of the system (this assists locating manholes, etc. before mobilizing with the clean/televise equipment). Phase two includes high pressure jet cleaning of the pipelines and manholes then providing closed circuit television inspection of the pipe lines and manholes. Following these field tasks the client is provided a complete Report of Findings with all system deficiencies, recommended rehab techniques and associated costs(sample log attached).

Please be advised that without a proper as-built plan actual pipe quantities for the inspection phase are rough estimates. After your review of the package, please feel free to contact should you have any questions or comments. We look forward to assisting you in the near future. Thank You.

Respectfully Submitted

Don Layton

Altair Environmental Group, L.L.C.

710 South Milwee Street • Longwood • Florida 32750-5150

Telephone: 407-339-7134 • Fax: 407-339-6618

E-Mail: admin@altairenvironmental.com Website: www.altairenvironmental.com