

William P. Cox Senior Attorney FILED 12/14/2020 DOCUMENT NO. 13466-2020 FPSC - COMMISSION CLERK

DOCKET NO. 20200257-EI

Florida Power & Light Company 700 Universe Boulevard Juno Beach, FL 33408-0420 (561) 304-5662 (561) 691-7135 (Facsimile)

December 14, 2020

-VIA ELECTRONIC FILING-

Adam Teitzman Commission Clerk Florida Public Service Commission 2540 Shumard Oak Boulevard Tallahassee, FL 32399-0850

Re: Docket No. ______ Florida Power & Light Company's 2020 Decommissioning Study

Dear Mr. Teitzman:

In compliance with Rule 25-6.04365, F.A.C., I am enclosing for filing on behalf of Florida Power & Light Company ("FPL") the Petition of Florida Power & Light Company for Approval of its 2020 Decommissioning Study. The 2020 Nuclear Decommissioning Study, including its Executive Summary, is attached to the Petition. The study results are based on estimates and assumptions that follow Nuclear Regulatory Commission ("NRC") requirements and industry guidelines for the development of the costs to remove and dismantle nuclear power plants decades into the future. Funds are maintained and interest reinvested in the decommissioning trusts as required by the NRC, Internal Revenue Service, Federal Energy Regulatory Commission and this Commission. Under federal law, these funds may only be used for nuclear decommissioning, are not available for any other use, and do not earn a return or profit for FPL. Key findings:

- (1) The trusts remain adequately funded so that FPL customers are not required to bear undue risk of incurring additional costs when the time comes to decommission FPL's nuclear power plants.
- (2) FPL customers have not contributed to the decommissioning trusts since 2005, and the study confirms that, as of December 31, 2020, the trusts continue to be adequately funded without FPL customer contributions.

Please feel free to contact me at 561-304-5662 if you have any questions about this transmittal.

Sincerely,

/s/ William P. Cox William P. Cox Senior Attorney Florida Bar No. 0093531

Enclosure

BEFORE THE FLORIDA PUBLIC SERVICE COMMISSION

In re: Petition of Florida Power & Light)	Docket No
Company for Approval of its 2020 Nuclear)	
Decommissioning Study)	Filed: December 14, 2020
)	

PETITION OF FLORIDA POWER & LIGHT COMPANY FOR APPROVAL OF ITS 2020 NUCLEAR DECOMMISSIONING STUDY

Florida Power & Light Company ("FPL"), pursuant to Rule 25-6.04365, Florida Administrative Code ("F.A.C."), petitions the Commission to approve FPL's updated study concerning the decommissioning of its nuclear generation units (the "2020 Decommissioning Study"). The 2020 Decommissioning Study is comprised of two separate volumes, for the St. Lucie and Turkey Point plant sites, which are attached hereto and incorporated herein by reference.

- 1. Pursuant to Rule 25-6.0435, F.A.C., each utility that owns a nuclear generating plant is required to file a Nuclear Decommissioning Study on a regular basis to ensure that there are sufficient funds on hand at the time of decommissioning to meet all required expenses. As shown in the 2020 Decommissioning Study, based on FPL's assumptions such as the rate of burial cost escalation and fund earnings assumptions, maintaining the current annual accrual of \$0 will satisfy FPL's retail share of the future cost of total nuclear decommissioning costs. Therefore, FPL requests no change to the accrual for nuclear decommissioning.
- 2. In addition, as required by the Commission in Order No. PSC-16-0250-PAA-EI, FPL has updated its estimates for the last core of nuclear fuel ("Last Core") and end of life materials and supplies ("EOL M&S") inventories as part of the 2020 Decommissioning Study. FPL requests no change in the accruals for Last Core and EOL M&S at this time. FPL will

address the updated estimates for Last Core and EOL M&S in its accruals as part of FPL's next general base rate proceeding.

WHEREFORE, FPL respectfully requests that the Commission approve its 2020 Decommissioning Study.

Respectfully submitted,

R. Wade Litchfield, Esq.
Vice President and General Counsel
William P. Cox, Esq.
Senior Attorney
Florida Power & Light Company
700 Universe Boulevard
Juno Beach, FL 33408-0420
Telephone: (561) 304-5639
Facsimile: (561) 691-7135

By: /s/ William P. Cox William P. Cox Fla. Bar No. 0093531

CERTIFICATE OF SERVICE Docket No. 2020

I HEREBY CERTIFY that a true and correct copy of Florida Power & Light Company's Petition for Approval of its 2020 Nuclear Decommissioning Study has been furnished by electronic service on December 14, 2020 to the following:

Mary Anne Helton, Esq.
Deputy General Counsel
Division of Legal Services
Florida Public Service Commission
2540 Shumard Oak Blvd
Tallahassee, Florida 32399-0850
mhelton@psc.state.fl.us

J. R. Kelly, Esq.
Office of Public Counsel
c/o The Florida Legislature
111 West Madison Street, Room 812
Tallahassee, Florida 32399
Kelly.jr@leg.state.fl.us

By: <u>/s/ William P. Cox</u> William P. Cox

Fla. Bar No. 0093531

FLORIDA POWER & LIGHT COMPANY

2020 DECOMMISSIONING STUDY

ST. LUCIE NUCLEAR UNIT NOS. 1 & 2

December 2020

TABLE OF CONTENTS

Section Numbers:

1	EXECUTIVE	SUM	MARY
---	------------------	------------	------

2 ASSUMPTIONS

3 SUPPORT SCHEDULE A

Nuclear Decommissioning Reserve Balance December 31, 2015 through October 31, 2020

4 SUPPORT SCHEDULE B

Nuclear Decommissioning Fund Balance December 31, 2015 through October 31, 2020

5 SUPPORT SCHEDULE C

Projected Fund and Reserve Balance at December 31, 2020

6 SUPPORT SCHEDULE D

Reconciliation of Projected Fund and Reserve Balance at December 31, 2020

7 SUPPORT SCHEDULE E

End-of-Life Materials and Supplies Inventory Expense Accrual Calculation

8 SUPPORT SCHEDULE F

End-of-Life Unamortized Nuclear Fuel Expense Accrual Calculation

9 SUPPORT SCHEDULE G

Inflation and Funding Analysis

10 SUPPORT SCHEDULE H

St Lucie Unit No 2 - FPL Ownership Percentage Cost Allocation Analysis

11 DECOMMISSIONING COST ANALYSIS:

ST LUCIE NUCLEAR PLANT UNITS 1 AND 2

Prepared by EnergySolutions, LLC

12 COMPARISON REPORT:

Comparative Analysis of Cost Studies 2015 & 2020 Cost Studies

EXECUTIVE SUMMARY

Overview

FPL's 2020 Nuclear Decommissioning Study results are based on estimates and assumptions that follow Nuclear Regulatory Commission ("NRC") requirements and industry guidelines for the development of the costs to remove and dismantle nuclear power plants years into the future. Funds are maintained and interest is reinvested in the decommissioning trusts as required by the NRC, Internal Revenue Service, Federal Energy Regulatory Commission ("FERC") and Florida Public Service Commission ("FPSC" or the "Commission"). Under federal law, these funds may only be used for nuclear decommissioning, are not available for any other use and do not earn a return or profit for FPL. The study is essentially a snapshot, which shows that based on current assumptions FPL's nuclear decommissioning trust funds are appropriately funded, i.e., the current fund balances exceed the expected costs of decommissioning on a present value basis. Compared to 2015, the currently calculated funding position has improved due in part to the Turkey Point license extension which will allow funds to grow for an additional twenty years as well as a slight decrease in future decommissioning costs. FPL customers have not contributed to the decommissioning trusts since 2005, and the study confirms that, as of December 31, 2020, the trusts continue to be adequately funded without additional FPL customer contributions.

Decommissioning studies represent the aggregation of numerous estimates for activities and costs that will not be incurred for at least 15 years. As such, they are highly dependent upon input assumptions that can and will change over time, such that future funding positions could differ from today's position. The 2020 Nuclear Decommissioning Study was prepared by EnergySolutions, LLC ("EnergySolutions"). As such adjustments to the underlying assumptions referenced above netted an overall reduction in cost of 23.5% for Turkey Point and 3.4% for St. Lucie between the 2020 and 2015 studies. The decrease in cost for Turkey Point is primarily a result of the license extension. A detailed analysis of the changes in assumptions is provided in the last section (Section 11 and 12) of each site reports. The current assumed long-term fund earnings rate of 4.0 percent is 0.3 percent higher than the assumption utilized in the 2015 study due to changes in the allocations in the investment portfolio plus the impact of the Turkey Point license extension. Such changes, regardless of direction, reaffirm the importance of maintaining adequate funding and the value of the periodic review of these studies as required by FPSC rule.

2020 Study Approach

The information contained in this 2020 Decommissioning Study is presented in compliance with Rule 25-6.04365, Florida Administrative Code, and prior Commission Orders. FPL contracted EnergySolutions, a company experienced in managing nuclear decommissioning activities and a leader in radioactive waste management and disposal, to prepare its 2020 site-specific nuclear decommissioning cost analysis and comparison reports, which are estimated based on NRC requirements, industry guidelines, and prior experience. EnergySolutions includes the most up-to-date actual decommissioning information available to ensure the methodology used to prepare the cost analysis is reasonable.

FPL selected the DECON (immediate dismantlement) decommissioning option for its units. The DECON method provides not only a lower cost, but also enables a coordinated sequence of decommissioning events, which allows for a one-time mobilization of contractor personnel and equipment. FPL's choice of the DECON method is consistent with the method in prior studies approved by the Commission for purposes of determining FPL's appropriate accrual and funding requirements.

Escalation Rate

The 2020 Decommissioning Study assumes that future decommissioning costs grow at an average rate of approximately 3.15 percent per year. This is a small decrease over the average escalation rate of 3.19 percent assumed in the 2015 study. While FPL believes that the current escalation rates are reasonable for the purpose of the 2020 Decommissioning Study, it should be noted that subsequent changes in the assumed escalation rate could increase, which would result in higher projected future decommissioning costs.

Spent Fuel Management

Consistent with prior studies and assumptions approved by the Commission, the decommissioning cost estimates include the cost associated with interim storage of spent nuclear fuel ("SNF") on site until such time the Department of Energy ("DOE") is able to remove SNF from the site. Consistent with the 2015 study, FPL reflects the reimbursements from the US. Government to cover the cost incurred for managing and storing SNF that would not have been incurred but for DOE's delay in SNF disposal. As such and for purposes of this study, the DOE is expected to make payments to FPL to cover spent fuel management costs incurred by FPL prior to 2063 for St. Lucie and 2059 for Turkey Point. The ultimate timing and amount of reimbursements will depend on many factors, including but not limited to, the DOE's ability to receive SNF and the Government's compliance with the terms of the Settlement Agreement.

Conclusion

The 2020 Decommissioning Study indicates that the trusts are at an adequate funding level given current assumptions and projections. FPL has earned its customers' trust by using careful, prudent investment strategies in all facets of its business including the management of its nuclear decommissioning trusts. Despite market volatility, the funds remain secure. As a result, FPL's current annual expense accrual requirements for decommissioning costs presented in this study support a zero accrual and funding requirement as of December 31, 2020.

In addition, as required by the Commission in Order Nos. FPSC-02-0055-PAA-EI and FPSC-10-0153-FOF-EI, FPL has updated its estimates for End-of-Life Nuclear Fuel Last Core and End-of-Life Materials and Supplies Inventory balances for each of its nuclear sites. This information is provided for informational purposes with this study. FPL is not requesting a change in accruals at this time. Rather, FPL believes that the results of these updated values should be addressed in FPL's next base rate proceeding and that the appropriate changes in accruals, if any, should be made at that time.

ASSUMPTIONS

Page 1 of 11

Assumptions Summary

Following is a summary of the assumptions used to derive the annual accrual, and funding and revenue requirements. These assumptions are more fully developed on the following pages.

	Unit No. 1	Unit No. 2
Decommissioning Method	SAFSTOR/ Integrated DECON (Prompt Removal/ Dismantling	DECON (Prompt Removal/ Dismantling)
Total Decommissioning Cost Per EnergySolutions, LLC (Current cost estimate in 2020 \$)	\$923,401,000	\$822,060,000
FPL's Cost of Decommissioning - Jurisdictional & net of Unit No. 2 Participants' obligation (Current cost estimate in 2020 \$)	\$884,079,000	\$680,377,000
Method of Funding (2020 – End)	Qualified/ Nonqualified	Qualified/ Nonqualified
Funding Periods (Years to License Expiration)	15.21	22.29
Assumed Fund Earnings rate	4.0%	4.0%
Average Escalation Rate for Decommissioning Costs (2020 – End)	3.15%	3.19%
FPL Ownership Allocation (%)	100%	86.45%
FPSC Jurisdictional Separation Factor (%)	95.74%	95.74%
Estimated Fund Balance: Qualified Fund (As of 12/31/20)	\$682,354,000	\$623,913,000
Estimated Fund Balance: Nonqualified Fund (As of 12/31/20)	\$188,063,000	\$91,606,000

<u>Unit No. 1</u>	Unit No. 2
N/A	\$30,746,340

Page 2 of 11

	Ollit No. 1	<u>OIIIt No. 2</u>
End of Life M & S Inventory Value: Net of Participants' obligation (As of 12/31/20)	N/A	\$30,746,340
End of Life Nuclear Fuel Last Core Value: Net of Participants' obligation (As of 12/31/20)	\$56,900,000	\$55,700,000
Year of Last Pick Up of Spent Fuel	2071	2071
Expected DOE Reimbursement (Current cost estimate in 2020 \$)	\$207,268,000	\$150,174,000

Decommissioning Methods

For purposes of this analysis, decommissioning is defined as the activity whereby nuclear facilities are removed safely from service and residual radioactivity is reduced to a level that permits release of the property for unrestricted use and termination of the operating license granted under Title 10 CFR Part 50. Decommissioning also includes the dismantlement, disposal and site restoration activities associated with the non-contaminated portion of the facilities. These activities are not required for termination of the operating license but are required to address other non-radiological requirements associated with the release of the site.

The Nuclear Regulatory Commission (NRC) has defined three acceptable decommissioning methods: Prompt Removal/Dismantling (DECON); Safe Storage/Deferred Decontamination (SAFSTOR); and Entombment (ENTOMB). The study utilizes the NRC terminology, but also includes the additional activities required to accommodate the non-contaminated portion of the facilities.

The DECON and SAFSTOR alternatives were both examined and are presented in the EnergySolutions Decommissioning Cost Analysis (Section 11) of this filing. The ENTOMB alternative was not considered, because it is considered impractical for a facility which generates significant amounts of long-lived radioactive material due to neutron activation. FPL selected an integrated DECON decommissioning option for St. Lucie Units 1 and 2. Due to the difference in the operating license period of Units 1 and 2, this option entails approximately 7 years of dormancy (SAFSTOR) for Unit 1 followed by prompt dismantlement (DECON) of both Units 1 and 2. The integrated DECON method provides not only a lower cost, but also enables a sequence of events, which allows for a one-time mobilization of contractor personnel and equipment. This method is consistent with the method in prior studies approved by the Commission for purposes of determining the appropriate accrual and funding requirements.

Page 3 of 11

Total Decommissioning Costs

Below are the total estimated costs of decommissioning the St. Lucie facility as provided by FPL's consultant, EnergySolutions, LLC in 2020 dollars.

St. Lucie Unit No. 1	
Labor	\$443,308,000
Equip & Materials	143,311,000
Transportation	56,142,000
Burial	193,616,000
Other	87,025,000
Total	\$923,401,000
St. Lucie Unit No. 2	
Labor	\$406,964,000
Equip & Materials	111,197,000
Transportation	54,503,000
Burial	185,856,000
Other	63,540,000
Total	\$822,060,000

Funding Method

In Docket No. 810100-EU, Order No. 10987 issued July 13, 1982, the FPSC ordered FPL to establish a funded reserve. Beginning in 1983 FPL began making contributions, on a net of tax basis, to an externally funded reserve. In 1986, the Treasury Department issued temporary regulations under Internal Revenue Code Section 468A relating to the deductibility of contributions made to a qualified decommissioning fund. These regulations, which were finalized in March of 1988, provide for an annual election by the taxpayer to make tax-deductible contributions to a qualified nuclear decommissioning fund. Qualified nuclear decommissioning funds have been established by FPL for each of the four nuclear units. FPL elected to make contributions to the qualified funds, to the maximum allowed, for the years 1984 through 1987, 1992 through 2004 and for the year to date period ended August 31, 2005. Per the Stipulation and Settlement Agreement approved by the Commission in FPSC Order No. FPSC-05-0902-S-EI, FPL suspended accruals effective September 1, 2005, and as such, no additional contributions to the funds have been made subsequent to that date.

Page 4 of 11

The funding analysis presented in Schedule G of this study indicates that no additional contributions to the qualified and nonqualified funds are projected to be required through the remainder of the funding period that ends with the expiration of the unit's operating license. Only the after-tax earnings of the trust fund investments are assumed to continue to be reinvested and accumulated in the respective funds. Future decommissioning expenditures are assumed to be distributed from the qualified and nonqualified funds in proportion to the balance accumulated at the time of expenditure.

Funding Period

The funding period, to the extent funding is required, is that period over which revenues are collected from ratepayers for purposes of decommissioning the St. Lucie Units. Funding periods for both units end on the last day of the month in which the operating license for the unit is due to expire. The operating license expiration dates for the St. Lucie units are as follows.

- St. Lucie Unit No. 1 March 1, 2036
- St. Lucie Unit No. 2 April 6, 2043

Based on the results of the funding analysis presented in Support Schedule G, no additional funding is required at this time.

Fund Earnings Rate

For purposes of this 2020 study update and funding analysis, the projected annual funds earnings rate, net of taxes and all other administrative costs charged to the trust funds, for Units 1 and 2 qualified and nonqualified fund investments, is assumed to be 4.0%. This assumption is based on a projected real long-term, after tax and net of fees, earnings rate of 2.0% plus an estimated long term average inflation rate of 2.0%. The long-term, after tax and net of fees earnings rate reflects the projection of continued adequacy of the funds and assumes a conservative investment strategy where the funds are moved to 100% fixed income prior to the first year of decommissioning and a more conservative all bonds & cash asset mix in the final years of decommissioning. FPL recognizes that over the long-term period there will likely be periods when the earned return may be greater or less than the assumed 4.0%. Consistent with prior Commission practice and Rule 25-6.04365 F.A.C. the assumptions presented in this 2020 study will be reviewed and updated as appropriate "at least once every five years".

The annual rates of change in CPI were taken from "The U. S. Economy, The 30 – Year Outlook, August 2020", published by Global Insight.

Page 5 of 11

Escalation Rate

The annual escalation rates used to estimate total future dismantlement costs from 2020 through the final year of decommissioning are as follows:

	Average Annual Escalation Rate
St. Lucie Unit No. 1	3.15%
St. Lucie Unit No. 2	3.19%

The above rates were derived by applying separate inflation indices to each of the major cost components of Labor, Materials and Equipment, Transportation, Burial, and Other.

Cost Component	<u>Inflation Index</u>
Labor	Compensation per Hour (Nonfarm)
Materials and Equipment	PPI - Intermediate Materials, Supplies, and Components
Transportation	GDP Deflator – Transportation Services
Burial	FPL Analysis & CPI
Other	GDP (Implicit)

For purposes of this 2020 study update, the inflation indices were obtained from "The U.S. Economy, The 30 – Year Outlook, August 2020", published by Global Insight except for the burial index.

The burial cost estimates are assumed to escalate at an average annual rate of 2.0%. This is a decrease of 1.2% from the rate assumed in the 2015 study. FPL has an agreement with EnergySolutions which provides for the long-term disposal of Class A waste generated during decommissioning. As such, burial costs for disposal of Class A waste is estimated based on the EnergySolutions agreement. In addition, the cost estimates for processed/conditioned (at off-site recycling center) disposal of Class A waste is assumed to be at a competitive rate comparable to the EnergySolutions pricing. Burial cost rates for Class B and Class C waste, not covered by the EnergySolutions Agreement, are less certain and based on rates equivalent to published Low Level Waste (LLW) Burial Site rates. The escalation rate applicable to Class B and C waste is assumed to be 1.5% which approximates the historical rate of change of the most recently published NRC NUREG 1307, Revision 17 which assumes the cost for disposal of Class B and C is the same as that for the Texas disposal facility located in states not affiliated with the Texas Compact. The resulting annual escalation rate of 2.0% is a weighted average rate for both St. Lucie and Turkey Point.

For a more detail calculation of the overall weighted average escalation rate and annual rate of change for each component please refer to Support Schedule G ("Inflation and Funding Analysis").

Page 6 of 11

FPL/Participant Ownership Share of Nuclear Units

The participants and their ownership interests in the St. Lucie facility are as follows:

	St. Lucie <u>Unit No. 1</u>	St. Lucie <u>Unit No. 2</u>
Florida Power & Light Company	100.0%	85.10449%
Orlando Utilities Commission	0.0	6.08951%
Florida Municipal Power Agency	<u>0.0</u>	<u>8.80600%</u>
Total	100.0%	<u>100.00000%</u>

For purposes of allocating decommissioning costs between FPL and Participants in the St. Lucie Unit No. 2, an adjustment was made to the ownership percentages to reflect the appropriate Common Facility cost obligation of participants.

This adjustment was necessary because the decommissioning cost study attributes common facility costs to St. Lucie No. 2. Because the Participants contractual obligation currently provides that they pay for only their ownership share times one-half of the common facility costs, to apply their ownership share to the total cost of decommissioning Unit No. 2 would overstate the Participants' cost obligation. This adjustment to the ownership percentage is reflected in what is termed a "Cost Allocation Factor" and represents the cost obligation of FPL and Participants as a percentage of the total costs of decommissioning. The "Cost Allocation Factor" calculation is given in Support Schedule H "Cost Allocation Analysis".

The Cost Allocation Factors for St. Lucie Unit No. 2 are:

	St. Lucie No. 2
Florida Power & Light Company	86.44612%
Participants	13.55388%
Total	100.00000%

Page 7 of 11

St. Lucie Unit No. 2 Participant Owners Funding Status

r articipant owners r anding status			\$ thousands	
<u>Participant</u>	Allocated <u>Share</u>	Allocated Costs 2020\$'s	Required at 12/31/2020 (a)	Amount Funded at 10/31/2020 ^(b)
Orlando Utilities Commission (OUC)	5.54103%	\$45,551	\$28,241	\$39,398
Florida Municipal Power Agency (FMPA)	8.01285%	<u>65,870</u>	<u>40,840</u>	<u>56,973</u>
Participant's Total	13.55388%	\$111,421	<u>\$69,081</u>	<u>\$96,371</u>
Florida Power and Light	86.44612%	710,639		
Total	<u>100.00000%</u>	<u>\$822,060</u>		

Notes:

⁽a) - At December 31, 2020, the funded balance should approximate 62% (37 yrs. / 60 yrs.) of decommissioning costs.

⁽b) - Excluding unrealized market gains/losses

Page 8 of 11

FPSC Jurisdictional Factor

The factor applicable to both units is 95.7416%.

Fund Balances

Estimated/actual fund balances (qualified and nonqualified) at December 31, 2020^(a) for each of the two St. Lucie Units are as Follows:

	Qualified	Nonqualified
Unit No. 1	\$682,354,000	\$188,063,000
Unit No. 2	\$623,913,000	\$91,606,000

⁽a) Excluding unrealized market gains/losses.

See support Schedule C ("Projected Fund and Reserve Balances") for detail composition and adjustments to the qualified and nonqualified fund balances.

End of Life Materials and Supplies Inventory Values

The decommissioning cost estimates contained in the EnergySolutions Decommissioning Cost Analysis (Section 11) of this study and in the funding analysis contained in Support Schedule G of this filing do not take into consideration the unrecovered value of any Materials and Supplies Inventories that will ultimately exist at the site following shut down of both units. Both FPL and this Commission have previously recognized that there will be a level of inventories that will remain at the end of life of Unit No. 2, the last unit to reach end of license, which must be recovered prior to the end of site operations. These inventories are unique and will have little value other than scrap value when the units are decommissioned. In Order No. FPSC-02-0055-PAA-EI, the Commission authorized FPL to begin recording the amortization of estimated end of life materials and supplies costs as a base rate fuel expense with a credit to a separate (unfunded) sub-account of Reserve Account 228. Additionally, the Commission directed the Company to address the costs associated with the materials and supplies in subsequent decommissioning studies so that the related annual accruals can be revised, if warranted. The annual expense/reserve accruals associated with End of Life Inventories are being accounted for, as directed by the Commission, in a separate (unfunded) sub-account of Reserve Account 228.

Page 9 of 11

As provided in Support Schedule E of this study, the Materials and Supplies inventory balance, less estimated salvage, that is anticipated to remain at the end of life of Unit No. 2, the last unit to reach end of license, is projected to be \$30,746,340 (Net of Participants' obligation). The actual balance accrued as of December 31, 2020 is \$9,067,554. FPL is not requesting a change in accruals at this time. Rather, FPL believes that the results of these updated values for End of Life Materials and Supplies should be addressed in FPL's next base rate proceeding and the appropriate changes in accruals, if any, be made at that time.

End of Life Last Core Nuclear Fuel Values

FPL recognizes that there will be unburned fuel that will remain in the fuel assemblies at the end of the last operating cycle of each nuclear unit when it ceases operation. In Docket No 981246-EI the Commission found that the cost associated with the Last Core were costs that should be considered a base rate future obligation and that amortization of this obligation over the remaining life span of each nuclear unit ratably allocates the costs to those customers receiving the benefit of the nuclear generation and avoids a burdensome expense at the time of unit shut down. In Order No. FPSC-02-0055-PAA-EI the Commission authorized FPL to begin recording the amortization of estimated Last Core costs as a base rate fuel expense with a credit to a separate (unfunded) sub-account of Reserve Account 228. Additionally, the Commission directed the Company to address the costs associated with the Last Core in subsequent decommissioning studies so that the related annual accruals can be revised, if warranted. The annual expense/reserve accruals associated with End of Life Nuclear Fuel Last Core values are accounted for, as directed by the Commission, in a separate (unfunded) sub-account of Reserve Account 228.

As provided in Support Schedule F of this study, the estimated cost of unburned fuel remaining in the reactor at the end of life (end of license) for each unit is:

• Unit No. 1 \$56,900,000

• Unit No. 2 (net of Participant's costs) \$55,700,000

The actual balances accrued as of December 31, 2020 are:

• Unit No. 1 \$40,639,303

• Unit No. 2 (net of Participant's costs) \$32,439,110

FPL is not requesting a change in accruals at this time. Rather, FPL believes that the results of these updated values for End of Life Nuclear Fuel Last Core should be addressed in FPL's next base rate proceeding and the appropriate changes in accruals, if any, be made at that time.

Page 10 of 11

Spent Nuclear Fuel Storage

The Nuclear Waste Policy Act of 1982 assigns to the Federal Government responsibility to provide for the permanent disposal of spent nuclear fuel (SNF) and high-level radioactive waste (HLW), and committed the DOE to begin acceptance of SNF/HLW not later than January 31, 1998 under terms of its Standard Disposal Contracts with waste generators. The DOE has not yet provided for SNF storage and is not accepting SNF as committed to under the contract.

In Docket No. 941350-EI, and No. 981246-EI, the FPSC recognized the impact on the decommissioning process and the potential costs of on-site dry fuel storage resulting from the inability of the DOE to provide for the timely removal of SNF. In Order Nos. PSC-95-1531-FOF-EI and PSC-02-0055-PAA-EI, the FPSC specifically approved the inclusion of costs associated with the dry storage of spent nuclear fuel following the end of each units operating license which were considered necessary to accommodate the timely decommissioning of each unit.

Consistent with the Commission's prior findings, this updated 2020 decommissioning study includes the costs relating to the construction, operation, and dismantlement of an on-site independent spent fuel storage installation (ISFSI) that is required to accommodate the timely decommissioning of the St. Lucie units. The potential cost impact of extended spent fuel storage that will exist subsequent to the license expiration of the St. Lucie nuclear units is presented in (Section 11) of the 2020 Decommissioning Cost Analysis for the St. Lucie Plant. The decommissioning cost estimates included in this filing are based on the EnergySolutions prepared Decommissioning Cost Analysis for the St. Lucie Plant, Units 1 and 2 dated November 2020.

In addition, FPL and certain nuclear plant joint owners signed a settlement agreement (spent fuel settlement agreement) with the U.S. Government in 2009 agreeing to dismiss with prejudice lawsuits filed against the U.S. Government seeking damages caused by the DOE's failure to dispose of spent nuclear fuel from FPL's nuclear plants. As such, the DOE is expected to continue to make payments to FPL to cover the costs incurred for managing and storing the spent fuel that it would not have incurred but for DOE's delay in performance.

Page 11 of 11

Below are the St. Lucie estimated costs of Decommissioning expected to be recovered from the DOE as provided by FPL's consultant, EnergySolutions, LLC in 2020 dollars.

St. Lucie Unit No. 1	
Labor	\$125,221,000
Equip & Materials	57,461,000
Other	24,585,000
Total	\$207,268,000
St. Lucie Unit No. 2	
Labor	\$104,812,000
Equip & Materials	29,282,000
Other	<u>16,080,000</u>
Total	\$150,174,000

Further discussion of the costs and assumptions regarding DOE reimbursement is contained in Section 5.0 of the Decommissioning Cost Analysis for the St. Lucie Plant, Units 1 and 2 dated November 2020. Consistent with prior Commission practice and Rule 25-6.04365 F.A.C., the assumptions presented in this 2020 decommissioning study related to DOE reimbursement will be reviewed and updated as appropriate "at least once every five years".

Annual Decommissioning Accrual Requirements

FPL's current annual expense accrual requirements for St Lucie Nuclear Plant Decommissioning costs presented in this study support a zero accrual and funding requirement as of December 31, 2020. The decommissioning costs estimates, funding analysis, and supporting assumptions presented in this study were prepared in a manner consistent with prior Commission approved studies, methodologies and practices.

SUPPORT SCHEDULE A Nuclear Decommissioning Reserve Balance December 31, 2015 through October 31, 2020

Support Schedule: Nuclear Decommissioning Reserve Balances (1) December 31, 2015 through October 31, 2020

\$000

<u>December 31, 2015</u>		Collected	to Reserve	Ending Balance
NONQUALIFIED				
Turkey Point Unit No. 3	\$284,009	\$0	\$9,261	\$293,270
Turkey Point Unit No. 4	304,290	0	9,925	314,215
St. Lucie Unit No. 1	255,915	0	8,344	264,259
St. Lucie Unit No. 2	124,580	0	4,077	128,658
TOTAL	\$968,795	\$0	\$31,607	\$1,000,402
<u>QUALIFIED</u>	0.412.26 7	# 0	016.470	# 420 0.46
Turkey Point Unit No. 3	\$413,367	\$0	\$16,479	\$429,846
Turkey Point Unit No. 4	473,635	0	18,879	492,514
St. Lucie Unit No. 1	535,493	0	21,345	556,838
St. Lucie Unit No. 2	489,737	0	19,499	509,236
TOTAL	\$1,912,231	\$0	\$76,202	\$1,988,434
TOTAL RESERVES				
Turkey Point Unit No. 3	\$697,375	\$0	\$25,740	\$723,116
Turkey Point Unit No. 4	777,925	0	28,804	806,729
St. Lucie Unit No. 1	791,408	0	29,689	821,097
St. Lucie Unit No. 2	614,317	0	23,576	637,894
TOTAL	\$2,881,026	\$0	\$107,810	\$2,988,836
December 31, 2016 NONQUALIFIED Turkey Point Unit No. 3	\$293,270	\$0	\$11,772	\$305,041
Turkey Point Unit No. 4	314,215	0	12,615	326,831
St. Lucie Unit No. 1	264,259	0	10,606	274,866
St. Lucie Unit No. 2	128,658	0	5,183	133,840
TOTAL	\$1,000,402	\$0	\$40,176	\$1,040,578
QUALIFIED	***	••	*****	****
Turkey Point Unit No. 3	\$429,846	\$0	\$16,640	\$446,486
Turkey Point Unit No. 4	492,514	0	19,057	511,571
St. Lucie Unit No. 1	556,838	0	21,541	578,379
St. Lucie Unit No. 2	509,236	0	19,685	528,921
TOTAL	\$1,988,434	\$0	\$76,923	\$2,065,357
TOTAL RESERVES				
Turkey Point Unit No. 3	\$723,116	\$0	\$28,411	\$751,527
Turkey Point Unit No. 4	806,729	0	31,672	838,402
St. Lucie Unit No. 1	821,097	0	32,148	853,245
St. Lucie Unit No. 2	637,894	0	24,868	662,761
TOTAL	\$2,988,836	\$0	\$117,099	\$3,105,935

Support Schedule: Nuclear Decommissioning Reserve Balances (1) December 31, 2015 through October 31, 2020

\$000

December 31, 2017	Beginning Balance	Revenues Collected	Earnings to Reserve	Ending Balance
NONQUALIFIED				
Turkey Point Unit No. 3	\$305,041	\$0	\$7,893	\$312,934
Turkey Point Unit No. 4	326,831	0	8,459	335,289
St. Lucie Unit No. 1	274,866	0	7,112	281,978
St. Lucie Unit No. 2	133,840	0	3,475	137,316
TOTAL	\$1,040,578	\$0	\$26,939	\$1,067,517
QUALIFIED				
	\$446,486	\$0	\$21,022	\$467.500
Turkey Point Unit No. 3 Turkey Point Unit No. 4	511,571	0	\$21,023 24,078	\$467,509 535,649
St. Lucie Unit No. 1	578,379	0	27,221	605,600
St. Lucie Unit No. 2	528,921	0	24,871	553,792
TOTAL	\$2,065,357	\$0	\$97,193	\$2,162,550
	, ,		. ,	. , ,
TOTAL RESERVES				
Turkey Point Unit No. 3	\$751,527	\$0	\$28,916	\$780,443
Turkey Point Unit No. 4	838,402	0	32,537	870,938
St. Lucie Unit No. 1	853,245	0	34,333	887,578
St. Lucie Unit No. 2	662,761	0	28,346	691,107
TOTAL	\$3,105,935	\$0	\$124,132	\$3,230,067
NONQUALIFIED Turkey Point Unit No. 3 Turkey Point Unit No. 4 St. Lucie Unit No. 1 St. Lucie Unit No. 2	\$312,934 335,289 281,978 137,316	\$0 0 0	\$8,190 8,777 7,379 3,606	\$321,124 344,066 289,357 140,921
TOTAL	\$1,067,517	\$0	\$27,951	\$1,095,468
QUALIFIED				, ,
Turkey Point Unit No. 3	\$467,509	\$0	\$15,703	\$483,212
Turkey Point Unit No. 4	535,649	0	17,986	553,635
St. Lucie Unit No. 1	605,600	0	20,335	625,935
St. Lucie Unit No. 2	553,792	0	18,576	572,367
TOTAL	\$2,162,550	\$0	\$72,600	\$2,235,150
TOTAL RESERVES				
Turkey Point Unit No. 3	\$780,443	\$0	\$23,892	\$804,336
Turkey Point Unit No. 4	870,938	0	26,763	897,701
St. Lucie Unit No. 1	887,578	0	27,714	915,292
St. Lucie Unit No. 2	691,107	0	22,181	713,289
TOTAL	\$3,230,067	\$0	\$100,551	\$3,330,618
	_			

Support Schedule: Nuclear Decommissioning Reserve Balances (1) December 31, 2015 through October 31, 2020

\$000

<u>December 31, 2019</u>	Beginning Balance	Revenues Collected	Earnings to Reserve	Ending Balance
<u>NONQUALIFIED</u>				
Turkey Point Unit No. 3	\$321,124	\$0	\$9,206	\$330,331
Turkey Point Unit No. 4	344,066	0	9,866	353,932
St. Lucie Unit No. 1	289,357	0	8,295	297,652
St. Lucie Unit No. 2	140,921	0	4,053	144,975
TOTAL	\$1,095,468	\$0	\$31,421	\$1,126,889
QUALIFIED				
Turkey Point Unit No. 3	\$483,212	\$0	\$22,002	\$505,214
Turkey Point Unit No. 4	553,635	0	25,198	578,833
St. Lucie Unit No. 1	625,935	0	28,486	654,421
St. Lucie Unit No. 2	572,367	0	26,028	598,395
TOTAL	\$2,235,150	\$0	\$101,713	\$2,336,863
TOTAL RESERVES				
Turkey Point Unit No. 3	\$804,336	\$0	\$31,208	\$835,544
Turkey Point Unit No. 4	897,701	0	35,064	932,765
St. Lucie Unit No. 1	915,292	0	36,781	952,073
St. Lucie Unit No. 2	713,289	0	30,081	743,370
TOTAL	\$3,330,618	\$0	\$133,135	\$3,463,752
October 31, 2020 NONQUALIFIED Turkey Point Unit No. 3 Turkey Point Unit No. 4 St. Lucie Unit No. 1 St. Lucie Unit No. 2 TOTAL	\$330,331 353,932 297,652 144,975 \$1,126,889	\$0 0 0 0 \$0	\$3,697 3,962 3,331 1,628 \$12,617	\$334,027 357,894 300,983 146,602 \$1,139,506
QUALIFIED				
Turkey Point Unit No. 3	\$505,214	\$0	\$17,976	\$523,190
Turkey Point Unit No. 4	578,833	0	20,589	599,422
St. Lucie Unit No. 1	654,421	0	23,277	677,698
St. Lucie Unit No. 2	598,395	0	21,265	619,660
TOTAL	\$2,336,863	\$0	\$83,107	\$2,419,970
TOTAL RESERVES				
Turkey Point Unit No. 3	\$835,544	\$0	\$21,673	\$857,217
Turkey Point Unit No. 4	932,765	0	24,550	957,316
St. Lucie Unit No. 1	952,073	0	26,608	978,681
St. Lucie Unit No. 2	743,370	0	22,892	766,262
TOTAL	\$3,463,752	\$0	\$95,724	\$3,559,476

SUPPORT SCHEDULE B
Nuclear Decommissioning Fund Balance
December 31, 2015 through October 31, 2020

Florida Power & Light Company 2020 Decommissioning Study Support Schedule: Nuclear Decommissioning Fund Balances (1) December 31, 2015 through October 31, 2020

	Beginning Balance	Contribution	Fund Earnings	Ending Balance
<u>December 31, 2015</u>				
NONQUALIFIED				
Turkey Point Unit No. 3	\$174,452	\$0	\$5,689	\$180,141
Turkey Point Unit No. 4	186,910	0	6,096	193,006
St Lucie Unit No. 1	157,196	0	5,126	162,321
St Lucie Unit No. 2	76,524	0	2,505	79,028
Total	\$595,081	\$0	\$19,415	\$614,496
<u>QUALIFIED</u>				
Turkey Point Unit No. 3	\$413,367	\$0	\$16,479	\$429,846
Turkey Point Unit No. 4	473,635	0	18,879	492,514
St Lucie Unit No. 1	535,493	0	21,345	556,838
St Lucie Unit No. 2	489,737	0	19,499	509,236
Total	\$1,912,231	\$0	\$76,202	\$1,988,434
<u>TOTAL</u>				
Turkey Point Unit No. 3	\$587,819	\$0	\$22,168	\$609,987
Turkey Point Unit No. 4	660,545	0	24,976	685,521
St Lucie Unit No. 1	692,689	0	26,470	719,159
St Lucie Unit No. 2	566,260	0	22,004	588,264
Total	\$2,507,313	\$0	\$95,617	\$2,602,930
<u>December 31, 2016</u>				
NONQUALIFIED				
Turkey Point Unit No. 3	\$180,141	\$0	\$7,231	\$187,372
Turkey Point Unit No. 4	193,006	0	7,749	200,755
St Lucie Unit No. 1	162,321	0	6,515	168,836
St Lucie Unit No. 2	79,028	0	3,183	82,212
Total	\$614,496	\$0	\$24,678	\$639,175
<u>QUALIFIED</u>				
Turkey Point Unit No. 3	\$429,846	\$0	\$16,640	\$446,486
Turkey Point Unit No. 4	492,514	0	19,057	511,571
St Lucie Unit No. 1	556,838	0	21,541	578,379
St Lucie Unit No. 2	509,236	0	19,685	528,921
Total	\$1,988,434	\$0	\$76,923	\$2,065,357
<u>TOTAL</u>				
Turkey Point Unit No. 3	\$609,987	\$0	\$23,871	\$633,857
Turkey Point Unit No. 4	685,521	0	26,806	712,327
St Lucie Unit No. 1	719,159	0	28,056	747,215
St Lucie Unit No. 2	588,264	0	22,868	611,132
Total	\$2,602,930	\$0	\$101,601	\$2,704,531

Florida Power & Light Company 2020 Decommissioning Study Support Schedule: Nuclear Decommissioning Fund Balances (1) December 31, 2015 through October 31, 2020

	Beginning Balance	Contribution	Fund Earnings	Ending Balance
<u>December 31, 2017</u>				
<u>NONQUALIFIED</u>				
Turkey Point Unit No. 3	\$187,372	\$0	\$4,848	\$192,220
Turkey Point Unit No. 4	200,755	0	5,196	205,951
St Lucie Unit No. 1	168,836	0	4,368	173,205
St Lucie Unit No. 2	82,212	0	2,135	84,346
Total	\$639,175	\$0	\$16,547	\$655,722
QUALIFIED				
Turkey Point Unit No. 3	\$446,486	\$0	\$21,023	\$467,509
Turkey Point Unit No. 4	511,571	0	24,078	535,649
St Lucie Unit No. 1	578,379	0	27,221	605,600
St Lucie Unit No. 2	528,921	0	24,871	553,792
Total	\$2,065,357	\$0	\$97,193	\$2,162,550
<u>TOTAL</u>				
Turkey Point Unit No. 3	\$633,857	\$0	\$25,872	\$659,729
Turkey Point Unit No. 4	712,327	0	29,274	741,600
St Lucie Unit No. 1	747,215	0	31,590	778,805
St Lucie Unit No. 2	611,132	0	27,005	638,138
Total	\$2,704,531	\$0	\$113,740	\$2,818,272
December 31, 2018				
NONQUALIFIED	0.100.000	4.0	0.000	\$100.4
Turkey Point Unit No. 3	\$192,220	\$0	\$6,255	\$198,475
Turkey Point Unit No. 4	205,951	0	6,704	212,655
St Lucie Unit No. 1	173,205	0	5,636	178,841
St Lucie Unit No. 2	84,346	0	2,754	87,100
Total	\$655,722	\$0	\$21,349	\$677,071
QUALIFIED	0.465.500	40	#15 F02	0.402.212
Turkey Point Unit No. 3	\$467,509	\$0	\$15,703	\$483,212
Turkey Point Unit No. 4	535,649	0	17,986	553,635
St Lucie Unit No. 1	605,600	0	20,335	625,936
St Lucie Unit No. 2	553,792	0	18,576	572,367
Total	\$2,162,550	\$0	\$72,600	\$2,235,150
TOTAL	0.50.500	Φ0	#21 050	0.01.007
Turkey Point Unit No. 3	\$659,729	\$0	\$21,958	\$681,687
Turkey Point Unit No. 4	741,600	0	24,690	766,290
St Lucie Unit No. 1	778,805	0	25,971	804,776
St Lucie Unit No. 2	638,138		21,330	\$2,012,220
Total	\$2,818,272	\$0	\$93,948	\$2,912,220

Florida Power & Light Company 2020 Decommissioning Study Support Schedule: Nuclear Decommissioning Fund Balances (1) December 31, 2015 through October 31, 2020

	Beginning Balance	Contribution	Fund Earnings	Ending Balance
<u>December 31, 2019</u>				
NONQUALIFIED				
Turkey Point Unit No. 3	\$198,475	\$0	\$6,888	\$205,363
Turkey Point Unit No. 4	212,655	0	7,382	220,037
St Lucie Unit No. 1	178,841	0	6,207	185,047
St Lucie Unit No. 2	87,100	0	3,033	90,133
Total	\$677,071	\$0	\$23,510	\$700,580
QUALIFIED				
Turkey Point Unit No. 3	\$483,212	\$0	\$22,002	\$505,214
Turkey Point Unit No. 4	553,635	0	25,198	578,833
St Lucie Unit No. 1	625,936	0	28,486	654,421
St Lucie Unit No. 2	572,367	0	26,028	598,395
Total	\$2,235,150	\$0	\$101,713	\$2,336,863
<u>TOTAL</u>				
Turkey Point Unit No. 3	\$681,687	\$0	\$28,890	\$710,577
Turkey Point Unit No. 4	766,290	0	32,580	798,870
St Lucie Unit No. 1	804,776	0	34,692	839,469
St Lucie Unit No. 2	659,467	0	29,060	688,528
Total	\$2,912,220	\$0	\$125,223	\$3,037,443
October 31, 2020				
NONQUALIFIED	#205.262	Φ0	# 2 7 00	Ф200 152
Turkey Point Unit No. 3	\$205,363	\$0	\$2,789	\$208,153
Turkey Point Unit No. 4	220,037	0	2,989	223,026
St Lucie Unit No. 1 St Lucie Unit No. 2	185,047	0	2,513	187,561
Total	90,133	<u> </u>	1,228 \$9,520	91,361
Total	\$700,580	\$0	\$9,320	\$710,100
QUALIFIED				
Turkey Point Unit No. 3	\$505,214	\$0	\$17,976	\$523,190
Turkey Point Unit No. 4	578,833	0	20,589	599,422
St Lucie Unit No. 1	654,421	0	23,277	677,699
St Lucie Unit No. 2	598,395	0	21,265	619,660
Total	\$2,336,863	\$0	\$83,107	\$2,419,970
<u>TOTAL</u>				
Turkey Point Unit No. 3	\$710,577	\$0	\$20,765	\$731,343
Turkey Point Unit No. 4	798,870	0	23,578	822,448
St Lucie Unit No. 1	839,469	0	25,790	865,259
St Lucie Unit No. 2	688,528	0	22,493	711,021
Total	\$3,037,443	\$0	\$92,627	\$3,130,070

SUPPORT SCHEDULE C
Projected Fund and Reserve Balance at December 31, 2020

Support Schedule: Projected Fund and Reserve Balance at December 31, 2020 $^{\rm (a)}$ \$000

	TURKEY POINT UNIT 3	TURKEY POINT UNIT 4	ST. LUCIE UNIT 1	ST. LUCIE UNIT 2	TOTALS
NON-QUALIFIED FUND				(Note 1)	
Actual Fund Balance @ 10/31/2020	\$208,153	\$223,026	\$187,561	\$91,361	\$710,100
Add: Estimate Income Nov. & Dec. 2020 (after-tax)	558	598	503	246	1,904
Est/Actual Fund Balance @ 12/31/2020	\$208,711	\$223,624	\$188,063	\$91,606	\$712,004
QUALIFIED FUND Actual Fund Balance @ 10/31/2020 Add: Estimate Income Nov. & Dec. 2020 (after-tax) Est/Actual Fund Balance @ 12/31/2020	\$523,190 3,595 \$526,785	\$599,422 4,118 \$603,540	\$677,699 4,655 \$682,354	\$619,660 4,253 \$623,913	\$2,419,970 16,621 \$2,436,591
Esta retual 1 and Bulance (b) 12/3 1/2020	ψ220,703	φουσ,σ.ιο	ψ00 2 ,55	Ψ023,513	Ψ2, 13 0,3 7 1
TOTAL FUND Actual Fund Balance @ 10/31/2020 Add: Estimate Income Nov. & Dec. 2020 (after-tax) Est/Actual Fund Balance @ 12/31/2020	\$731,343 4,153 \$735,496	\$822,448 4,716 \$827,163	\$865,259 5,158 \$870,417	\$711,021 4,499 \$715,519	\$3,130,070 18,525 \$3,148,595
NON-QUALIFIED RESERVE Actual Reserve Balance @ 10/31/2020	\$334,027	\$357,894	\$300,983	\$146,602	\$1,139,506
Add: Estimate Income Nov. & Dec. 2020	739	792	\$300,983 666	325	2,522
Est/Actual Reserve Balance@12/31/2020	\$334,766	\$358,686	\$301,649	\$146,928	\$1,142,029
QUALIFIED RESERVE					
Actual Reserve Balance @ 10/31/2020	\$523,190	\$599,422	\$677,698	\$619,660	\$2,419,970
Add: Estimate Income Nov. & Dec. 2020	3,595	4,118	4,655	4,253	16,621
Est/Actual Reserve Balance@12/31/2020	\$526,785	\$603,539	\$682,354	\$623,913	\$2,436,591
TOTAL RESERVE Actual Reserve Balance @ 10/31/2020 Add: Estimate Income Nov. & Dec. 2020 Est/Actual Reserve Balance@12/31/2020	\$857,217 4,334 \$861,551	\$957,316 4,910 \$962,225	\$978,681 \$984,003	\$766,262 4,578 \$770,841	\$3,559,476 19,144 \$3,578,620
	+1,001		Ţ. S.,005	Ţ J ,0.11	+=,=,0,0 = 0

⁽a) Balances exclude unrealized market gains/losses.

Note 1: Amounts for St Lucie Common are included with Unit No. 2

SUPPORT SCHEDULE D
Reconciliation of Projected Fund and Reserve Balance
at December 31, 2020

Support Schedule: Reconciliation of Projected Fund and Reserve Balance at December 31, 2020 (a) \$000

RECONCILIATION FUND/RESERVE Projected 12/31/2020

	TURKEY	TURKEY			
	POINT	POINT	ST. LUCIE	ST. LUCIE	
	UNIT 3	UNIT 4	UNIT 1	UNIT 2	TOTALS
NON-QUALIFIED				(Note 1)	
Projected Fund Balance @12/31/2020	\$208,711	\$223,624	\$188,063	\$91,606	\$712,004
Remeasurement of Deferred Tax - Federal (Note 2)	\$41,402	\$44,359	\$37,305	\$18,166	\$141,232
Remeasurement of Deferred Tax - State (Note 3)	(\$193)	(\$206)	(\$172)	(\$84)	(\$654)
Deferred Tax @ 12/31/2020	\$84,847	\$90,909	\$76,453	\$37,239	\$289,447
Projected Reserve Balance @ 12/31/2020	\$334,766	\$358,686	\$301,649	\$146,928	\$1,142,029
OUALIEIED					
QUALIFIED	#526 795	DC02 540	Φ.CΩ2 2.5.4	Φ.C22.012	#2 42 <i>C</i> 501
Projected Fund Balance @12/31/2020	\$526,785	\$603,540	\$682,354	\$623,913	\$2,436,591
Deferred Tax @ 12/31/2020	0	0	0	0	0
Projected Reserve Balance @ 12/31/2020	\$526,785	\$603,540	\$682,354	\$623,913	\$2,436,591
TOTAL					
Projected Fund Balance @12/31/2020	\$735,496	\$827,163	\$870,417	\$715,519	3,148,595
Re-measurement of Deferred Tax - Federal	\$41,402	\$44,359	\$37,305	\$18,166	141,232
Re-measurement of Deferred Tax - State	(193)	(206)	(172)	(84)	(654)
Deferred Tax @ 12/31/2020	84,847	90,909	76,453	37,239	289,447
Projected Reserve Balance @ 12/31/2020	\$861,551	\$962,226	\$984,003	\$770,840	\$3,578,620
DEFERRED TAXES					
Projected balance @ 12/31/2020					
NON-QUALIFIED FUND					
Balance @ 10/31/2020 (Fed & State)	\$84,659	\$90,708	\$76,284	\$37,156	\$288,808
Add: Tax on Earnings - November & December	187	201	169	82	639
Balance @ 12/31/2020 (Fed & State)	\$84,847	\$90,909	\$76,453	\$37,239	\$289,447

(a) Balances exclude unrealized market gains/losses.

Note (1): Amounts for St Lucie Common are included with Unit No. 2

Note (2): In December 2017, new tax reform legislation was signed into law which reduced the federal corporate income tax rate from 35% to 21% effective January 1, 2018. As a result, FPL remeasured its deferred tax assets to the new federal corporate tax rate of 21%, which resulted in a reduction of deferred tax assets by \$141 million. This amount was recorded as a regulatory asset.

Note (3): In 2019 the Florida corporate income tax rate was changed from 5.5% to 4.458%. The tax rate change was retroactive to Jan 1, 2018 and is for the periods of 2018 through 2021. The rate reverts back to 5.5% in 2022. Trust fund earnings are taxed at the current tax rate in effect, 4.458% for the periods of 2018 through 2021, while the deferred tax asset is recorded using 5.5% for the same period resulting in variances.

SUPPORT SCHEDULE E
End-of-Life Materials and Supplies Inventory
Expense Accrual Calculation

Florida Power and Light Company 2020 Decommissioning Study Support Schedule: End-of-Life Materials and Supplies Inventory

Line <u>Number</u>			St. Lucie <u>Unit 2</u>
1	Adjusted Ending Inventory Value @ End of License	\$	33,928,292
2	Estimated Salvage		(707,768)
3	Inventory Subject to Write-off	\$	33,220,523
4			
5	FPL's Ownership Share Net of Participants (1)	\$	30,746,340
6			
7	Actual Reserve Balance Accrued as of 12/31/20		9,067,554
8	D 11 4 4 1 D 1 614/21/20	Φ.	21 (50 50)
9	Remaining Amount to be Recovered as of 12/31/20	<u>\$</u>	21,678,786
10			
11			
12	Total Number of Months From:		
13	12/31/20 to End of License 4/6/2043		267.5
14			
15			
16	Note:		
17	(1) The Participants' obligation is assumed to be treated the same as "Commor	Fac	ility Cost"
18	which is calculated at one-half their ownership percentage. $(0.5 * 14.8955)$		
19	Therefore, FPL's ownership share is 92.552245%.	-	

SUPPORT SCHEDULE F
End-of-Life Unamortized Nuclear Fuel
Expense Accrual Calculation

Florida Power and Light Company 2020 Decommissioning Study Support Schedule: End-of-Life Unamortized Nuclear Fuel

Line <u>Number</u>		St. Lucie <u>Unit 1</u>	St. Lucie <u>Unit 2</u>
1	Estimated Cost of Unburned Fuel @ End of License		
2	FPL's Ownership Share Net of Participants	\$ 56,900,000	\$ 55,700,000
3			
4	Actual Reserve Balance at 12/31/2020	40,639,303	32,439,890
5			
6	Remaining Amount to be Recovered as of 12/31/2020	\$ 16,260,697	\$ 23,260,110
7			
8			
9	Total Number of Months From:		
10	12/31/20 to End of License:	182.5	267.5

SECTION 9

SUPPORT SCHEDULE G Inflation and Funding Analysis

Florida Power & Light Company 2020 Decommissioning Study Support Schedule : Inflation and Funding Analysis

INFLATION FORECAST

The U.S. Economy 30 Year Outlook (AUGUST 2020) GLOBAL INSIGHT

	PCJPGDP	PCJWSSNF	PCWPISOP2000	PCCSVTS	FPL (INTERNAL)		CPI
YEAR	GDP	HRLY COMP	PPI INT M&S	GDP Transport	Burial	СРІ	CPI MULTIPLIER
2020	0.9%	5.9%	-4.1%	-22.2%	2.0%	1.0%	1.000
2021	1.1%	0.5%	2.3%	18.0%	2.0%	1.7%	1.017
2022	1.2%	1.8%	2.5%	11.9%	2.0%	1.7%	1.034
2023	1.5%	2.2%	1.7%	9.6%	2.0%	0.8%	1.042
2024	1.8%	2.7%	1.8%	8.7%	2.0%	1.3%	1.056
2025	2.1%	3.3%	1.4%	6.2%	2.0%	2.0%	1.076
2026	2.3%	3.7%	1.3%	4.9%	2.0%	2.3%	1.101
2027	2.4%	4.0%	1.2%	4.3%	2.0%	2.5%	1.129
2028	2.5%	4.1%	1.1%	4.1%	2.0%	2.4%	1.156
2029	2.4%	4.1%	0.9%	4.4%	2.0%	2.3%	1.183
2030	2.4%	4.1%	0.8%	4.7%	2.0%	2.2%	1.210
2031	2.3%	4.0%	0.8%	4.3%	2.0%	2.1%	1.235
2032	2.3%	4.0%	1.1%	3.9%	2.0%	2.1%	1.261
2033	2.2%	4.0%	0.9%	3.8%	2.0%	2.0%	1.286
2034	2.2%	4.0%	1.0%	3.7%	2.0%	2.0%	1.312
2035	2.2%	4.0%	1.1%	3.5%	2.0%	2.0%	1.338
2036	2.1%	3.9%	1.1%	3.4%	2.0%	2.0%	1.365
2037	2.1%	3.9%	1.4%	3.2%	2.0%	2.0%	1.393
2038	2.1%	3.9%	1.5%	3.1%	2.0%	2.1%	1.421
2039	2.1%	3.9%	1.3%	3.1%	2.0%	2.0%	1.450
2040	2.1%	3.9%	1.4%	3.1%	2.0%	2.1%	1.480
2041	2.2%	3.9%	1.4%	3.1%	2.0%	2.1%	1.511
2042	2.2%	3.9%	1.4%	3.0%	2.0%	2.1%	1.542
2043	2.2%	3.9%	1.3%	3.0%	2.0%	2.1%	1.574
2044	2.2%	3.8%	1.4%	3.0%	2.0%	2.1%	1.607
2045	2.2%	3.8%	1.5%	3.0%	2.0%	2.1%	1.642
2046	2.2%	3.8%	1.5%	3.0%	2.0%	2.1%	1.677
2047	2.2%	3.8%	1.5%	3.0%	2.0%	2.2%	1.713
2048	2.3%	3.8%	1.6%	3.1%	2.0%	2.2%	1.750
2049	2.3%	3.8%	1.7%	3.1%	2.0%	2.2%	1.788
2050	2.3%	3.8%	1.7%	3.1%	2.0%	2.2%	1.828
2051	2.3%	3.8%	1.7%	3.1%	2.0%	2.2%	1.868
2052	2.3%	3.8%	1.7%	3.1%	2.0%	2.2%	1.909
2053	2.3%	3.8%	1.7%	3.1%	2.0%	2.2%	1.951
2054	2.3%	3.8%	1.7%	3.1%	2.0%	2.2%	1.994
2055	2.3%	3.8%	1.7%	3.1%	2.0%	2.2%	2.038
2056	2.3%	3.8%	1.7%	3.1%	2.0%	2.2%	2.083
2057	2.3%	3.8%	1.7%	3.1%	2.0%	2.2%	2.129
2058	2.3%	3.8%	1.7%	3.1%	2.0%	2.2%	2.176
2059	2.3%	3.8%	1.7%	3.1%	2.0%	2.2%	2.223
2060	2.3%	3.8%	1.7%	3.1%	2.0%	2.2%	2.272
2061	2.3%	3.8%	1.7%	3.1%	2.0%	2.2%	2.322
2062	2.3%	3.8%	1.7%	3.1%	2.0%	2.2%	2.374
2063	2.3%	3.8%	1.7%	3.1%	2.0%	2.2%	2.426
2064	2.3%	3.8%	1.7%	3.1%	2.0%	2.2%	2.479
2065	2.3%	3.8%	1.7%	3.1%	2.0%	2.2%	2.534
2066	2.3%	3.8%	1.7%	3.1%	2.0%	2.2%	2.590
2067	2.3%	3.8%	1.7%	3.1%	2.0%	2.2%	2.647
2068	2.3%	3.8%	1.7%	3.1%	2.0%	2.2%	2.705
2069	2.3%	3.8%	1.7%	3.1%	2.0%	2.2%	2.764
2070	2.3%	3.8%	1.7%	3.1%	2.0%	2.2%	2.825
2071	2.3%	3.8%	1.7%	3.1%	2.0%	2.2%	2.887
2072	2.3%	3.8%	1.7%	3.1%	2.0%	2.2%	2.951
2073	2.3%	3.8%	1.7%	3.1%	2.0%	2.2%	3.016
2074	2.3%	3.8%	1.7%	3.1%	2.0%	2.2%	3.082
2075	2.3%	3.8%	1.7%	3.1%	2.0%	2.2%	3.150

Florida Power & Light Company 2020 Decommissioning Study Support Schedule : Inflation and Funding Analysis

Support Schedule G Page 2 of 8

GENERAL ASSUMPTIONS

JURISDICTIONAL FACTOR = 95.7416%

FPL'S SHARE OF ST. LUCIE 2 COST (NET OF PARTICIPANTS) 86.44612%

CORPORATE TAX RATE 24.522%

ANNUAL MONTHLY EARNINGS RATE QUALIFIED FUND 4.000% 0.327374% EARNINGS RATE NON-QUALIFIED FUND 4.000% 0.327374%

	TP3	TP4	SL1	SL2
Adjusted QUALIFIED FUNDING % (at 12/31/20)	61.144%	62.723%	69.345%	80.939%
FUND BALANCES (\$000's)				
FUND BALANCES (\$000 S)				
A. QUALIFIED FUND BALANCE 10/31/20	523,190	599,422	677,699	619,660
B. CONTRIBUTIONS - Nov. & Dec. 2020	-	-	-	-
C. EARNINGS - Nov. & Dec. 2020	3,595	4,118	4,655	4,253
D. QUALIFIED FUND BALANCE 12/31/20	526,785	603,540	682,354	623,913
E. JURISDICTIONAL FACTOR	95.7416%	95.7416%	95.7416%	95.7416%
F. JURIS. QUAL. FUND BAL. 12/31/20	504,352	577,838	653,297	597,344
A. NON-QUALIFIED FUND BALANCE 10/31/20	208,153	223,026	187,561	91,361
B. CONTRIBUTIONS - Nov. & Dec. 2020	-	-	-	-
C. EARNINGS - Nov. & Dec. 2020	558	598	503	246
D. NON-QUALIFIED FUND BALANCE 12/31/20	208,711	223,624	188,063	91,606
E. JURISDICTIONAL FACTOR	95.7416%	95.7416%	95.7416%	95.7416%
F. JURIS. NON-QUAL. FUND BAL. 12/31/20	199,823	214,101	180,055	87,705
Juris Est/Actual Fund Palanca	704 175	701 020	922 251	695 040

 Juris. Est/Actual Fund Balance
 704,175
 791,939
 833,351
 685,049

 Juris. Est/Actual Reserve Balance
 824,863
 921,250
 942,100
 738,015

Support Schedule : Inflation and Funding Analysis

		Integrate	St. Lucie Nuclear ed DECON - Total (thousands, 202	Decommissioning C	Cost				Integrated Di	Lucie Nuclear Plan ECON - Total Deco thousands, Future do	mmissionin	g Cost		Average
		Equipment &							Equipment &					Tiverage
Year	Labor	Materials	Transportation	LLRW Disposal	Other	Yearly Totals	Year	Labor	Materials	Transportation	Burial	Other	Yearly Totals	Inflation Rate
2036	32,205	3,115	-	-	3,628	38,948	2036	54,892	3,840	-	-	5,035	63,768	3.13%
2037	34,682	2,930	-	-	4,408	42,020	2037	61,430	3,663	-	-	6,248	71,341	3.16%
2038	23,684	2,195	-	-	4,292	30,171	2038	43,588	2,784	-	-	6,214	52,586	3.13%
2039	19,676	1,812	-	-	4,265	25,754	2039	37,620	2,329	-	-	6,307	46,256	3.13%
2040	7,003	417	-	-	2,287	9,706	2040	13,908	543	-	-	3,454	17,905	3.11%
2041	7,003	417	-	-	2,287	9,706	2041	14,447	551	-	-	3,529	18,526	3.13%
2042	7,003	417	-	-	2,287	9,706	2042	15,005	558	-	-	3,605	19,169	3.14%
2043	7,003	417	-	-	2,287	9,706	2043	15,583	566	-	-	3,684	19,833	3.16%
2044	7,003	417	-	-	2,287	9,706	2044	16,180	574	- 14.052	-	3,765	20,518	3.17%
2045	29,380	15,987	4,353	-	6,012	55,732	2045	70,473	22,325	14,853	-	10,116	117,767	3.04%
2046 2047	35,615	25,881	1,204	2 702	8,663	71,364 77,982	2046 2047	88,679	36,684	4,231	- 6 552	14,902	144,496	2.75% 2.72%
	35,910	27,744	1,789	3,792	8,747			92,803	39,929	6,482	6,553	15,383	161,150	
2048 2049	48,878 53,729	19,397 21,876	3,474 4,844	11,058 14,371	5,815 4,452	88,622 99,273	2048 2049	131,096 149,555	28,355 32,508	12,973 18,645	19,502 25,864	10,457 8,188	202,384 234,760	2.99% 3.01%
2049	25,364	13,037	12,839	64,383	3,705	119,326	2049	73,264	19,709	50,966	118,245	6,969	269,153	2.75%
2050	23,304 14,411	3,465	14,219	49,451	3,703	85,052	2050	43,198	5,329	58,218	92,681	6,747	206,172	2.75%
2051	4,617	3, 4 63 857	11,250	33,750	2,048	52,521	2051	14,362	1,341	47,509	64,548	4,031	131,791	2.92%
2052	2,442	204	11,230	33,730	885	3,531	2052	7,883	325	47,509	-	1,781	9,989	3.20%
2053	2,442	79	-	-	822	3,196	2053	7,688	128	-	-	1,692	9,509	3.26%
2055	2,295	79	-	-	822	3,196	2055	7,088	130	-	-	1,731	9,840	3.27%
2056	2,295	79			822	3,196	2056	8,280	133	_	_	1,771	10,183	3.27%
2057	2,295	79	-		822	3,196	2057	8,592	135	-	_	1,812	10,539	3.28%
2058	2,295	79	_	_	822	3,196	2058	8,916	137	_	_	1,853	10,907	3.28%
2059	2,295	79	_	_	822	3,196	2059	9,253	140	_	_	1,896	11,288	3.29%
2060	2,295	79	_	_	822	3,196	2060	9,602	142	_	_	1,939	11,683	3.29%
2061	2,295	79	_	-	822	3,196	2061	9,964	145	_	_	1,983	12,092	3.30%
2062	2,295	79	_	_	822	3,196	2062	10,340	147	_	_	2,029	12,516	3.30%
2063	2,295	79	-	-	822	3,196	2063	10,731	150	-	-	2,075	12,956	3.31%
2064	2,295	79	_	-	822	3,196	2064	11,136	152	_	-	2,123	13,411	3.31%
2065	2,295	79	-	-	822	3,196	2065	11,556	155	-	-	2,172	13,882	3.32%
2066	2,295	79	-	-	822	3,196	2066	11,992	158	-	-	2,221	14,371	3.32%
2067	2,295	79	-	-	822	3,196	2067	12,444	160	-	-	2,272	14,877	3.33%
2068	2,295	79	-	-	822	3,196	2068	12,914	163	-	-	2,324	15,402	3.33%
2069	2,295	79	-	-	822	3,196	2069	13,401	166	-	-	2,378	15,945	3.33%
2070	2,580	79	1,085	8,406	894	13,043	2070	15,633	169	7,994	23,152	2,646	49,595	2.71%
2071	2,580	79	1,085	8,406	894	13,043	2071	16,223	172	8,246	23,626	2,706	50,974	2.71%
2072	1,498	-	-	-	171	1,669	2072	9,773	-	-	-	529	10,302	3.56%
2073	4,321	1,302	-	-	60	5,684	2073	29,263	2,926	-	-	191	32,380	3.34%
2074	-	-	-	-	-	-	2074	-	-	-	-	-	-	
Total	443,308	143,311	56,142	193,616	87,025	923,401	Total	1,179,647	207,521	230,117	374,171	158,760	2,150,216	3.15%

NOTE: The 2020 cash flows are inflated to the year of expenditure based on the indices provided on Support Schedule G, page 1 of 8

Support Schedule: Inflation and Funding Analysis

		DE	St. Lucie Nuclear CON - Total Deco (thousands, 202	mmissioning Cost					Average					
		Equipment &							Equipment &					Average
Year	Labor	Materials	Transportation	LLRW Disposal	Other	Yearly Totals	Year	Labor	Materials	Transportation	Burial	Other	Yearly Totals	Inflation Rate
2043	31,403	1,570	-	-	3,214	36,186	2043	69,880	2,130	-	-	5,178	77,189	3.35%
2044	47,799	1,603	-	-	4,354	53,755	2044	110,439	2,205	-	-	7,167	119,812	3.40%
2045	33,461	21,237	1,197	-	5,314	61,209	2045	80,261	29,657	4,085	-	8,942	122,945	2.83%
2046	42,655	5,768	6,960	-	8,581	63,964	2046	106,206	8,175	24,468	-	14,760	153,609	3.43%
2047	42,907	10,087	578	3,504	7,738	64,814	2047	110,886	14,518	2,093	6,055	13,609	147,160	3.08%
2048	47,539	20,614	1,166	6,843	6,226	82,388	2048	127,504	30,135	4,354	12,068	11,196	185,257	2.94%
2049	55,330	16,061	4,959	15,996	3,967	96,312	2049	154,011	23,866	19,086	28,788	7,295	233,047	3.09%
2050	32,115	13,708	10,414	41,796	3,077	101,109	2050	92,765	20,724	41,340	76,761	5,788	237,378	2.89%
2051	18,373	13,749	16,365	65,674	2,678	116,838	2051	55,073	21,147	67,005	123,085	5,153	271,463	2.76%
2052	7,815	4,726	10,695	35,232	2,375	60,842	2052	24,309	7,395	45,164	67,383	4,675	148,925	2.84%
2053	2,321	147	-	-	855	3,323	2053	7,492	234	-	-	1,722	9,448	3.22%
2054	2,214	59	-	-	824	3,096	2054	7,417	95	-	-	1,696	9,209	3.26%
2055	2,214	59	-	-	824	3,096	2055	7,697	97	-	-	1,735	9,529	3.26%
2056	2,214	59	-	-	824	3,096	2056	7,987	99	-	-	1,775	9,861	3.27%
2057	2,214	59	-	-	824	3,096	2057	8,289	100	-	-	1,816	10,205	3.28%
2058	2,214	59	-	-	824	3,096	2058	8,602	102	-	-	1,857	10,561	3.28%
2059	2,214	59	-	-	824	3,096	2059	8,926	104	-	-	1,900	10,930	3.29%
2060	2,214	59	-	-	824	3,096	2060	9,263	106	-	-	1,943	11,312	3.29%
2061	2,214	59	-	-	824	3,096	2061	9,613	108	-	-	1,988	11,708	3.30%
2062	2,214	59	-	-	824	3,096	2062	9,975	109	-	-	2,033	12,118	3.30%
2063	2,214	59	-	-	824	3,096	2063	10,352	111	-	-	2,080	12,543	3.31%
2064	2,214	59	-	-	824	3,096	2064	10,742	113	-	-	2,128	12,983	3.31%
2065	2,214	59	-	-	824	3,096	2065	11,148	115	-	-	2,176	13,440	3.32%
2066	2,214	59	-	-	824	3,096	2066	11,569	117	-	-	2,226	13,912	3.32%
2067	2,214	59	-	-	824	3,096	2067	12,005	119	-	-	2,277	14,402	3.32%
2068	2,214	59	-	-	824	3,096	2068	12,458	121	-	-	2,330	14,909	3.33%
2069	2,214	59	-	-	824	3,096	2069	12,928	124	-	-	2,383	15,435	3.33%
2070	2,499	59	1,085	8,406	896	12,944	2070	15,141	126	7,995	23,153	2,651	49,066	2.70%
2071	2,499	59	1,085	8,406	896	12,944	2071	15,713	128	8,246	23,627	2,712	50,425	2.70%
2072	2,892	-		-	194	3,086	2072	18,869	-	-	-	602	19,471	3.61%
2073	1,935	867	-	-	-	2,802	2073	13,101	1,949	-	-	-	15,050	3.22%
2074		-	-	-	-		2074	<u>-</u>		-	-	-	´-	
Total	406,964	111,197	54,503	185,856	63,540	822,060	Total	1,160,622	164,132	223,835	360,920	123,793	2,033,302	3.19%

NOTE: The 2020 cash flows are inflated to the year of expenditure based on the indices provided on Support Schedule G, page 1 of 8

Support Schedule: Inflation and Funding Analysis

	Costs	s Recovered fo	ated DE	CON Fuel Manag	gement				Costs Recove	cie Nuclear Integrated D red for Spen ousands, Futu	ECON nt Fuel M	anagemen	t
		`	ius, 2020 C	LLRW		Vaanle			`	ousanus, rutu	ire dollars	o)	
Year	Labor	Equipment & Materials	Enongr		Other	Yearly Totals	Year	Labor	Equipment & Materials	Transport	Durial	Other	Yearly Totals
2036	Labor	& Materials	Energy	Disposai	- Other	1 Otals	2036	Labor	& Materials	Transport	Duriai	- Other	rearry rotars
2030	12,314	2,431	-	-	631	15,376	2030	21,811	3,039	-	-	894	25,744
2037	11,687	2,366	-	_	768	14,821	2037	21,509	3,001	-	-	1,112	25,622
2040	6,321	1,567	_	-	740	8,628	2040	12,554	2,042	_	_	1,112	15,714
2040	4,896	312	-	-	1,187	6,395	2040	10,101	413	-	-	1,831	12,344
2041	4,896	312	_	-	1,187	6,395	2041	10,101	418	_	_	1,871	12,780
2042	4,896	312	_	-	1,187	6,395	2042	10,895	424			1,912	13,231
2043	4,896	312	_	_	1,187	6,395	2043	11,312	430		_	1,953	13,696
2045	4,896	312	_	_	1,187	6,395	2045	11,744	436	_	_	1,997	14,177
2046	7,396	22,812	_	_	1,187	31,395	2046	18,416	32,334	_	_	2,041	52,791
2047	18,225	23,615	_	_	1,435	43,275	2047	47,099	33,987	_	_	2,524	83,609
2048	2,295	79	_	_	822	3,196	2048	6,156	116	_	_	1,478	7,749
2049	2,295	79	_	_	822	3,196	2049	6,388	118	_	_	1,511	8,017
2050	2,295	79	_	_	822	3,196	2050	6,630	120	-	_	1,546	8,295
2051	2,295	79	_	_	822	3,196	2051	6,880	122	-	_	1,581	8,583
2052	2,295	79	_	_	822	3,196	2052	7,139	124	_	_	1,618	8,881
2053	2,295	79	_	_	822	3,196	2053	7,409	126	_	-	1,655	9,189
2054	2,295	79	_	_	822	3,196	2054	7,688	128	_	-	1,692	9,509
2055	2,295	79	_	-	822	3,196	2055	7,978	130	-	_	1,731	9,840
2056	2,295	79	_	-	822	3,196	2056	8,280	133	-	_	1,771	10,183
2057	2,295	79	-	-	822	3,196	2057	8,592	135	-	-	1,812	10,539
2058	2,295	79	-	-	822	3,196	2058	8,916	137	-	-	1,853	10,907
2059	2,295	79	-	-	822	3,196	2059	9,253	140	-	_	1,896	11,288
2060	2,295	79	-	-	822	3,196	2060	9,602	142	-	_	1,939	11,683
2061	2,295	79	-	-	822	3,196	2061	9,964	145	-	-	1,983	12,092
2062	2,295	79	-	-	822	3,196	2062	10,340	147	-	-	2,029	12,516
2063	2,295	79	-	-	822	3,196	2063	10,731	150	-	-	2,075	12,956
2064	-	-	-	-	-	-	2064	-	-	-	-	-	-
			•								•		
Total	125,221	57,461	-	-	24,585	207,268	Total	323,319	81,002	-	-	46,523	450,844

NOTE: The 2020 cash flows are inflated to the year of expenditure based on the indices provided on Support Schedule G, page 1 of a

Support Schedule: Inflation and Funding Analysis

		St. Lucie N	uclear Pla DECON	ant, Unit 2					St. Lu	cie Nuclear DECO		nit 2	
	Cost	s Recovered fo (thousan	or Spent l ids, 2020 d	-	gement				Costs Recove	red for Sper ousands, Futu		0	t
		Equipment		LLRW		Yearly			Equipment				
Year	Labor	& Materials	Energy	Disposal	Other	Totals	Year	Labor	& Materials	Transport	Burial	Other	Yearly Totals
2043	-	-	-	-	-	-	2043	-	-	-	-	-	=
2044	14,986	1,457	-	-	540	16,983	2044	34,624	2,005	-	-	889	37,519
2045	20,763	1,452	-	-	734	22,949	2045	49,803	2,028	-	-	1,235	53,066
2046	13,757	21,070	-	-	716	35,542	2046	34,253	29,864	-	-	1,232	65,349
2047	19,882	4,361	-	-	913	25,156	2047	51,381	6,277	-	-	1,605	59,263
2048	2,214	59	-	-	824	3,096	2048	5,938	86	-	-	1,481	7,505
2049	2,214	59	-	-	824	3,096	2049	6,163	87	-	-	1,515	7,765
2050	2,214	59	-	-	824	3,096	2050	6,395	89	-	-	1,549	8,034
2051	2,214	59	-	-	824	3,096	2051	6,637	91	-	-	1,585	8,312
2052	2,214	59	-	-	824	3,096	2052	6,887	92	-	-	1,621	8,601
2053	2,214	59	-	-	824	3,096	2053	7,147	94	-	-	1,658	8,899
2054	2,214	59	-	-	824	3,096	2054	7,417	95	-	-	1,696	9,209
2055	2,214	59	-	-	824	3,096	2055	7,697	97	-	-	1,735	9,529
2057	2,214	59	-	-	824	3,096	2057	8,289	100	-	-	1,816	10,205
2058	2,214	59	-	-	824	3,096	2058	8,602	102	-	-	1,857	10,561
2059	2,214	59	-	-	824	3,096	2059	8,926	104	-	-	1,900	10,930
2060	2,214	59	-	-	824	3,096	2060	9,263	106	-	-	1,943	11,312
2061	2,214	59	-	-	824	3,096	2061	9,613	108	-	-	1,988	11,708
2062	2,214	59	-	-	824	3,096	2062	9,975	109	-	-	2,033	12,118
2063	2,214	59	-	-	824	3,096	2063	10,352	111	-	-	2,080	12,543
2064	-	-	-	-	-	-	2064	-	-	-	-	-	-
Total	104,812	29,282	-	-	16,080	150,174	Total	297,350	41,744	-	-	33,194	372,288

NOTE: The 2020 cash flows are inflated to the year of expenditure based on the indices provided on Support Schedule G, page 1 of a

Florida Power & Light Company 2020 Decommissioning Study St Lucie Nuclear Units Support Schedule: Inflation and Funding Analysis

ST. LUCIE UNIT 1

NOMINAL ANNUAL 4.000% NOMINAL MONTHLY 0.327374% 0.327374% EARNINGS RATE QUALIFIED FUND EARNINGS RATE NON-QUALIFIED FUND

CORPORATE TAX RATE 24.522%

FPL'S SHARE OF COST (NET OF PARTICIPANTS) JURISDICTIONAL FACTOR 100.000% 95.7416%

Adjusted QUALIFIED % 69.345%

LICENSE ENDS 03/01/2036

				F	STIMATED										PV @	PV @
		ESTIMATED	ESTIMATED		DOE										4.0%	4.0%
	SPENDING	COST IN	COST IN		RECOVERY		JUI	RISDICTIONAL		QUALIFIED]	NON-QUAL	TAX	•	QUALIFIED	NON-QUAL
YEAR	CURVE	(\$2020)	NOMINAL \$		NOMINAL \$	NOMINAL \$		AMOUNT		AMOUNT		AMOUNT	SAVINGS		AMOUNT	AMOUNT
2036	4.2178%		63,767,767			\$ 63,767,767	\$	61,052,280	\$	42,336,537	\$, .,	\$, ,	\$	22,603,823	\$ 7,542,148
2037	4.5506%	42,020,015	71,341,062		25,743,818	45,597,243		43,655,530		30,272,808		10,101,035	3,281,687		15,541,250	5,185,601
2038	3.2674%	30,170,914	52,586,444		25,621,745	26,964,699		25,816,434		17,902,336		5,973,417	1,940,681		8,837,096	2,948,647
2039	2.7890%	25,753,545	46,256,097		18,908,639	27,347,458		26,182,894		18,156,456		6,058,209	1,968,229		8,617,824	2,875,483
2040	1.0512%	9,706,429	17,905,395		15,713,994	2,191,401		2,098,082		1,454,910		485,455	157,718		664,002	221,555
2041	1.0512%	9,706,429	18,526,232		12,344,478	6,181,754		5,918,510		4,104,175		1,369,427	444,908		1,801,050	600,951
2042	1.0512%	9,706,429	19,168,826		12,780,338	6,388,488		6,116,441		4,241,429		1,415,225	459,787		1,789,694	597,162
2043	1.0512%	9,706,429	19,833,054		13,230,957	6,602,097		6,320,953		4,383,248		1,462,545	475,161		1,778,399	593,393
2044	1.0512%	9,706,429	20,518,130		13,695,797	6,822,333		6,531,811		4,529,466		1,511,333	491,011		1,767,042	589,604
2045	6.0355%	55,732,234	117,767,302		14,177,020	103,590,282		99,178,994		68,775,402		22,948,078	7,455,514		25,798,809	8,608,210
2046	7.7283%	71,363,697	144,495,814		52,790,958	91,704,856		87,799,696		60,884,459		20,315,131	6,600,106		21,960,369	7,327,449
2047	8.4451%	77,982,124	161,149,613		83,609,463	77,540,150		74,238,180		51,480,263		17,177,262	5,580,655		17,854,208	5,957,359
2048	9.5974%	88,622,437	202,383,708		7,748,971	194,634,737		186,346,411		129,221,409		43,116,912	14,008,090		43,092,429	14,378,519
2049	10.7508%	99,272,829		\$	8,017,185	226,743,039		217,087,413		150,538,673		50,229,778	16,318,962		48,270,439	16,106,249
2050	12.9225%	119,326,450	269,152,547		8,294,955	260,857,592		249,749,233		173,187,923		57,787,083	18,774,227		53,397,070	17,816,837
2051	9.2107%	85,051,774	206,172,266		8,582,652	197,589,614		189,175,458		131,183,204		43,771,498	14,220,756		38,890,606	12,976,509
2052	5.6878%	52,521,270	131,791,113		8,880,639	122,910,473		117,676,454		81,602,415		27,228,028	8,846,011		23,261,416	7,761,566
2053	0.3824%	3,530,775	9,989,296		9,189,292	800,004		765,937		531,137		177,223	57,577		145,582	48,576
2054	0.3461%	3,195,920	9,509,000		9,509,000	(0)		(0)		(0)		(0)	(0)		(0)	(0)
2055	0.3461%	3,195,920	9,840,166		9,840,166	(0)		(0)		(0)		(0)	(0)		(0)	(0)
2056	0.3461%	3,195,920	\$ 10,183,210	\$	10,183,210	(0)		(0)		(0)		(0)	(0)		(0)	(0)
2057	0.3461%	3,195,920	10,538,565	\$	10,538,565	(0)		(0)		(0)		(0)	(0)		(0)	(0)
2058	0.3461%	3,195,920		\$	10,906,683	(0)		(0)		(0)		(0)	(0)		(0)	(0)
2059	0.3461%	3,195,920	11,288,029	\$	11,288,029	(0)		(0)		(0)		(0)	(0)		(0)	(0)
2060	0.3461%	3,195,920	11,683,090		11,683,090	(0)		(0)		(0)		(0)	(0)		(0)	(0)
2061	0.3461%	3,195,920	12,092,365	\$	12,092,365	(0)		(0)		(0)		(0)	(0)		(0)	(0)
2062	0.3461%	3,195,920	\$ 12,516,378	\$	12,516,378	(0)		(0)		(0)		(0)	(0)		(0)	(0)
2063	0.3461%	3,195,920	\$ 12,955,667	\$	12,955,667	(0)		(0)		(0)		(0)	(0)		(0)	(0)
2064	0.3461%	3,195,920	\$ 13,410,793	\$	-	13,410,793		12,839,708		8,903,660		2,970,857	965,190		1,585,264	528,950
2065	0.3461%	3,195,920	\$ 13,882,337	\$	-	13,882,337		13,291,171		9,216,726		3,075,317	999,128		1,577,889	526,489
2066	0.3461%	3,195,920	\$ 14,370,901	\$	-	14,370,901		13,758,930		9,541,093		3,183,547	1,034,291		1,570,596	524,056
2067	0.3461%	3,195,920	\$ 14,877,110	\$	-	14,877,110		14,243,583		9,877,174		3,295,686	1,070,723		1,563,384	521,650
2068	0.3461%	3,195,920	\$ 15,401,613	\$	-	15,401,613		14,745,750		10,225,400		3,411,878	1,108,472		1,556,252	519,270
2069	0.3461%	3,195,920	\$ 15,945,081	\$	-	15,945,081		15,266,075		10,586,218		3,532,271	1,147,586		1,549,199	516,916
2070	1.4125%	13,043,482	\$ 49,594,842	\$	-	49,594,842		47,482,895		32,926,884		10,986,612	3,569,399		4,633,228	1,545,955
2071	1.4125%	13,043,482	\$ 50,973,540	\$	-	50,973,540		48,802,883		33,842,226		11,292,032	3,668,625		4,578,873	1,527,819
2072	0.1807%	1,668,500	\$ 10,301,967	\$	-	10,301,967		9,863,268		6,839,657		2,282,167	741,445		889,817	296,902
2073	0.6155%	5,683,500	\$ 32,379,547	\$	-	32,379,547		31,000,696		21,497,348		7,172,954	2,330,394		2,689,168	897,286
2074	0.0000%	-	\$ -	\$	-	-		-		-		-	-		-	-
	100.0000%	923,401,492	\$ 2,150,215,772	\$	450,844,054	\$ 1,699,371,718	\$	1,627,005,673	S	1,128,242,635	\$	376,457,263	\$ 122,305,774	\$	358,264,778	\$ 119,541,111

	 QUALIFIED	NON-QUAL		TOTAL
NPV @12/31/20	\$ 358,264,778	\$ 119,541,111	S	477,805,889
LESS BALANCE @ 12/31/20	653,296,604	180,054,702		833,351,306
PV OF FUNDING REQUIREMENTS	\$ (295,031,826)	\$ (60,513,591)	\$	(355,545,417)

MONTHLY FUNDING REQUIREMENT ANNUAL FUNDING REQUIREMENT MONTHLY ACCRUAL ANNUAL ACCRUAL

Florida Power & Light Company 2020 Decommissioning Study St Lucie Nuclear Units Support Schedule: Inflation and Funding Analysis

ST. LUCIE UNIT 2

NOMINAL ANNUAL 4.000% NOMINAL MONTHLY 0.327374% 0.327374% EARNINGS RATE QUALIFIED FUND EARNINGS RATE NON-QUALIFIED FUND

CORPORATE TAX RATE 24.522%

FPL'S SHARE OF COST (NET OF PARTICIPANTS) JURISDICTIONAL FACTOR 86.446% 95.7416%

Adjusted QUALIFIED % 80.939%

LICENSE ENDS 04/06/2043

LICENSE	ENDS	04/06/2043				CTIMATED												DV.		DV.
		ESTIMATED	ECO	TIMATED	E	STIMATED DOE												PV @ 4.0%		PV @
	SPENDING	COST IN		TIMATED COST IN	ъ	ECOVERY		NET	ш	RISDICTIONAL		QUALIFIED	,	NON-QUAL		TAX	0	4.0% UALIFIED	N	4.0% ON-QUAL
YEAR	CURVE	(\$2020)		OMINAL \$		OMINAL \$		NOMINAL \$	JU	AMOUNT		AMOUNT	1	AMOUNT		SAVINGS		AMOUNT		MOUNT
2043	4.4019% \$			77,188,824			\$	77,188,824	\$?	51,708,261	\$	9,190,972		2,986,020		20,979,403 \$		3,729,019
2044	6.5391%	53,755,259		119,812,104		37,518,536	Ψ	82,293,568	Ψ	68,110,189	Ψ.	55,127,894	Ψ	9,798,800	Ψ	3,183,495	Ψ	21,506,575		3,822,722
2045	7.4458%	61,208,918		122,944,513		53,065,880		69,878,633		57,834,980		46,811,214		8,320,538		2,703,228		17,559,673		3,121,174
2046	7.7809%	63,963,685		153,609,279		65,348,547		88,260,732		73,048,905		59,125,255		10,509,318		3,414,332		21,325,843		3,790,598
2047	7.8843%	64,814,029		147,160,353		59,263,396		87,896,957		72,747,827		58,881,565		10,466,003		3,400,260		20,421,102		3,629,783
2048	10.0221%	82,388,064		185,257,096		7,505,355		177,751,741		147,116,049		119,074,665		21,165,126		6,876,258		39,708,718		7,058,093
2049	11.7160%	96,312,381		233,047,214		7,764,939		225,282,275		186,454,647		150,915,042		26,824,647		8,714,958		48,391,122		8,601,361
2050	12.2994%	101,108,688		237,377,637		8,033,752		229,343,885		189,816,235		153,635,887		27,308,268		8,872,080		47,368,812		8,419,649
2051	14.2129%	116,838,439		271,463,260		8,312,164		263,151,096		217,796,739		176,283,104		31,333,736		10,179,899		52,260,934		9,289,207
2052	7.4011%	60,841,783	\$	148,925,243	\$	8,600,525		140,324,718		116,139,611		94,002,560		16,708,643		5,428,408		26,796,176		4,762,931
2053	0.4042%	3,322,784	\$	9,447,522	\$	8,899,199		548,323		453,819		367,318		65,290		21,212		100,680		17,895
2054	0.3767%	3,096,480	\$	9,208,560	\$	9,208,560		(0)		(0)		(0)		(0)		(0)		(0)		(0)
2055	0.3767%	3,096,480	\$	9,529,000	\$	9,529,000		(0)		(0)		(0)		(0)		(0)		(0)		(0)
2056	0.3767%	3,096,480	\$	9,860,923	\$	9,860,923		(0)		(0)		(0)		(0)		(0)		(0)		(0)
2057	0.3767%	3,096,480	\$	10,204,749		10,204,749		(0)		(0)		(0)		(0)		(0)		(0)		(0)
2058	0.3767%	3,096,480	\$	10,560,912		10,560,912		(0)		(0)		(0)		(0)		(0)		(0)		(0)
2059	0.3767%	3,096,480	\$	10,929,864	\$	10,929,864		(0)		(0)		(0)		(0)		(0)		(0)		(0)
2060	0.3767%	3,096,480		11,312,073		11,312,073		(0)		(0)		(0)		(0)		(0)		(0)		(0)
2061	0.3767%	3,096,480		11,708,024		11,708,024		(0)		(0)		(0)		(0)		(0)		(0)		(0)
2062	0.3767%	3,096,480		12,118,219		12,118,219		(0)		(0)		(0)		(0)		(0)		(0)		(0)
2063	0.3767%	3,096,480		12,543,182		12,543,182		(0)		(0)		(0)		(0)		(0)		(0)		(0)
2064	0.3767%	3,096,480		12,983,453		-		12,983,453		10,745,742		8,697,525		1,545,956		502,260		1,548,563		275,252
2065	0.3767%	3,096,480		13,439,593		-		13,439,593		11,123,265		9,003,090		1,600,269		519,905		1,541,315		273,964
2066	0.3767%	3,096,480		13,912,184		-		13,912,184		11,514,405		9,319,676		1,656,541		538,187		1,534,148		272,690
2067	0.3767%	3,096,480		14,401,830		-		14,401,830		11,919,660		9,647,686		1,714,844		557,129		1,527,060		271,430
2068	0.3767%	3,096,480		14,909,156		-		14,909,156		12,339,548		9,987,541		1,775,252		576,755		1,520,051		270,184
2069	0.3767%	3,096,480		15,434,813		-		15,434,813		12,774,607		10,339,675		1,837,843		597,090		1,513,120		268,952
2070	1.5746%	12,944,042			\$	-		49,065,690		40,609,168		32,868,767		5,842,314		1,898,087		4,625,050		822,087
2071	1.5746%	12,944,042		50,425,210		-		50,425,210		41,734,374		33,779,500		6,004,194		1,950,680		4,570,386		812,371
2072	0.3754%	3,086,000		19,471,265		-		19,471,265		16,115,373		13,043,666		2,318,468		753,238		1,696,938		301,625
2073	0.3409%	2,802,000	\$	15,050,458	\$	-		15,050,458		12,456,496		10,082,198		1,792,077		582,221		1,261,212		224,176
2074	0.0000%	-	\$	-	\$	-		-	-	-	_	-	_	-	_	-	_	-		-
	100.0000% \$	822,060,215	S 2	,033,302,201	\$	372,287,799	\$	1,661,014,402	\$	1,374,736,891	5	1,112,702,089	S	197,779,100	\$	64,255,703	\$	337,756,882 \$		60,035,164

	Q	UALIFIED	N	NON-QUAL	TOTAL
NPV @12/31/20	\$	337,756,882	\$	60,035,164	\$ 397,792,046
LESS BALANCE @ 12/31/20		597,344,034		87,705,435	\$ 685,049,470
PV OF FUNDING REQUIREMENTS	\$	(259,587,152)	\$	(27,670,272)	\$ (287,257,423)
MONTHLY FUNDING REQUIREMENT		-		-	-
ANNUAL FUNDING REQUIREMENT		-		-	-
MONTHLY ACCRUAL		-		-	-
ANNUAL ACCRUAL		-		-	-

SECTION 10

SUPPORT SCHEDULE H
St Lucie Unit No 2 - FPL Ownership Percentage
Cost Allocation Analysis

Florida Power & Light Company 2020 Decommissioning Study St. Lucie Unit No. 2 - FPL Ownership Percentage Support Schedule : Cost Allocation Analysis (thousands 2020 Dollars)

			2020
			Base Case
1	St. Lucie Unit No. 2		\$822,060
2	St. Lucie Unit No. 2 Common Facilities (No.	ote 1)	148,085
3	St. Lucie Unit No. 2 Excluding Costs of Common Facilities	(L.1 - L.2)	\$673,975
4	St. Lucie Unit No. 2 Share of Costs of Common Facilities (Note 2)		74,043
5	Total costs Upon Which Allocation to Participants is Computed	(L. 3 + L. 4)	\$748,018
6	Participants Share of Total Costs (Note 3)		14.89551%
7	Total Costs Allocated to Participants	(L. 5 x L. 6)	\$111,421
8	Total Costs (line 1 above)		\$822,060
9	Percent of Total Applicable to Participants	(L. 7 / L. 8)	13.55388%
10	Percent of Total Applicable to FPL Ownership	100% - L. 9	86.44612%

Note:

- 1 Common (shared) facilities that are expected to be decommissioned at the same time as St. Lucie Unit No. 2 and are included with the decommissioning costs of Unit No. 2.
- 2 The Participants share of the common facilities has been calculated in compliance with the Participation Agreement which provides that the Participants pay for only their ownership share times one-half of the common facility costs.
- Allocation is based on ownership share of 8.80600% for Florida Municipal Power Agency and 6.08951% for Orlando Utilities Commission. (Total = 14.89551%)

Appendix G

Summary of Costs Shared Structures

(thousands, 2020 dollars)

	Unit 1	Unit 2	Total
Structures			
Contaminated Soil	68,949	63,636	132,585
Site Paving	1,299	1,299	2,598
Clean Concrete Processing	1,928	2,792	4,720
Security Improvements	1,144	1,144	2,288
Shared Miscellaneous Site Structures	-	5,063	5,063
Steam Generator Blowdown Facility	-	831	831
	73,320	74,765	148,085

SECTION 11

DECOMMISSIONING COST ANALYSIS: ST LUCIE NUCLEAR PLANT UNITS 1 AND 2 Prepared by EnergySolutions, LLC



2020 Decommissioning Cost Estimate of the St. Lucie Nuclear Plant, Units 1 and 2

Project No. 16	64086-01	Rev. 1
	Prepared for: Florida Power & Light Company	
	Prepared by: EnergySolutions, LLC 121 W. Trade Street, Suite 2700 Charlotte, NC 28202	
Authored By:	Ke K: LLLL Kevin M. Kirkley, Sr. Estimator	
Approved By:	Jake H. Oleksiak, Project Controls Manager	
		X New Report
		Title Change
		Report Revision
		Report Rewrite
	Effectiv Date:	November 19, 2020

Table of Contents

Section		<u> Page</u>
1.0	EXECUTIVE SUMMARY	5
2 .0	INTRODUCTION	9
	2.1 Study Objective	9
	2.2 Regulatory Framework	9
3.0	STUDY METHODOLOGY	12
	3.1 General Description	12
	3.2 Schedule Analysis	12
	3.3 Decommissioning Staff	13
	3.4 Waste Disposal	13
	3.5 Final Status Survey	
	3.6 Contingency	16
	3.7 Cost Reporting	17
4.0	SITE-SPECIFIC TECHNICAL APPROACH	18
	4.1 Facility Description	18
	4.2 Decommissioning Periods	18
	4.3 Decommissioning Staff	30
	4.4 Spent Fuel Management Staff	30
	4.5 Spent Fuel Shipments	30
5.0	BASES OF ESTIMATE AND KEY ASSUMPTIONS	31
6.0	STUDY RESULTS	36
	6.1 Scenario 1 - Unit 1 SAFSTOR, DECON both following Unit 2 Shutdown	37
	6.2 Scenario 2 - SAFSTOR	
7.0	REFERENCES	45

Tables

Table 1-1	Decommissioning Cost Summary	6
Table 1-2	Scenario 1 Cost Summary by Unit	7
Table 1-3	Scenario 2 Cost Summary by Unit	7
Table 1-4	Scenario 1 Schedule Summary	8
Table 1-5	Scenario 2 Schedule Summary	8
Table 6-1	Decommissioning Cost Summary	36
Table 6-2	Scenario 1 Cost Summary by Period & Unit	37
Table 6-3	Scenario 1 Cost Summary by Period & Cost Type	37
Table 6-4	Scenario 1 Schedule Summary	38
Table 6-5	Scenario 1 Project Staffing	
Table 6-6	Scenario 2 Cost Summary by Period & Unit	42
Table 6-7	Scenario 2 Cost Summary by Period & Cost Type	42
Table 6-8	Scenario 2 Schedule Summary	43
Table 6-9	Scenario 2 Project Staffing	

Appendices

Appendix A	List of Systems and Structures
Appendix B	Detailed Schedules
Appendix C	Detailed Cost Estimates
Appendix D	Detailed Staffing Tables
Appendix E	Waste Disposal Summaries
Appendix F	Annual Spending Tables
Appendix G	Shared Structures Cost Summary

Acronyms and Abbreviations

AIF Atomic Industrial Forum

ALARA As Low As Reasonably Achievable

BWR Boiling Water Reactor

CFR Code of Federal Regulations
CWS Circulating Water System

DAW Dry Active Waste

DCE Decommissioning Cost Estimate

DGC Decommissioning General Contractor

DOE U.S. Department of Energy

DSC Dry Storage Canister ES EnergySolutions

EPRI Electric Power Research Institute

FPL Florida Power & Light

FEMA Federal Emergency Management Agency

FSS Final Status Survey

GSA U.S. General Services Administration

GTCC Greater Than Class C

HP Health Physics

HSM Horizontal Storage Module

INPO Institute of Nuclear Power Operations
ISFSI Independent Spent Fuel Storage Installation

LLRW Low-Level Radioactive Waste

LOP Life-of-Plant

MARSSIM Multi-Agency Radiation Survey and Site Investigation Manual

MWt Megawatt thermal

NRC Nuclear Regulatory Commission

ORISE Oak Ridge Institute for Science and Education

PCB Polychlorinated Biphenyl

PSDAR Post-Shutdown Decommissioning Activities Report

PWR Pressurized Water Reactor
St. Lucie St. Lucie Nuclear Plant
WBS Work Breakdown Structure
WCS Waste Control Specialists LLC

UCF Unit Cost Factor

Document No. 164086-DCE-01

Rev. 1

1.0 EXECUTIVE SUMMARY

This report presents the 2020 Decommissioning Cost Estimate (DCE) Study of the St. Lucie Nuclear Plant, Units 1 and 2, hereinafter referred to as the 2020 Cost Study. The St. Lucie Nuclear Plant (St. Lucie) is owned and operated by Florida Power & Light Company (FPL). Unit 2 is jointly owned with Florida Municipal Power Agency and Orlando Utilities Commission.

This DCE has been performed to furnish an estimate, for financial planning purposes, of the costs for decommissioning St. Lucie Units 1 and 2 to the extent required to terminate the plant's operating license pursuant to 10 CFR 50.75(c), post-shutdown management of spent fuel until acceptance by the U.S. Department of Energy (DOE) pursuant to 10 CFR 50.54(bb), clean demolition of structures and restoration of the site, and Independent Spent Fuel Storage Installation (ISFSI) decommissioning pursuant to 10 CFR 72.30.

The study methodology follows the basic approach originally presented in the Atomic Industrial Forum/National Environmental Studies Project Report AIF/NESP-036, "Guidelines for Producing Commercial Nuclear Power Plant Decommissioning Cost Estimates," (Ref. No. 1). The report was prepared in accordance with Nuclear Regulatory Commission (NRC) Regulatory Guide 1.202, "Standard Format and Content of Decommissioning Cost Estimates for Nuclear Power Reactors," (Ref. No. 2). The estimate is based on compliance with current regulatory requirements and proven decommissioning technologies.

NRC requirements, set forth in Title 10 of the Code of Federal Regulations (CFR), differentiate between the post-shutdown costs associated with storage of spent fuel on site and those associated with the decommissioning of the facility. 10 CFR 50.75(c) requires funding by the licensee of the facility for the decommissioning program, but specifically excludes the cost of removal and disposal of spent fuel and the removal of clean structures. 10 CFR 50.75(c) also excludes the cost of site restoration activities that do not involve the removal of residual radioactivity necessary to terminate the NRC license, which restore the site to either "Brownfield" or "Greenfield" conditions depending on the desired end state. 10 CFR 50.54 (bb) requires funding by the licensee "for the management of all irradiated fuel at the reactor upon expiration of the reactor operating license until title to the irradiated fuel and possession of the fuel is transferred to the Secretary of Energy for its ultimate disposal in a repository."

Accordingly, the costs and schedules for all activities are segregated for regulatory purposes as follows: costs for "License Termination" (10 CFR 50.75(c)), costs for "Spent Fuel Management" (10 CFR 50.54(bb)), and costs for "Site Restoration".

This study analyzes two DCE scenarios, defined by FPL, as follows:

Scenario 1 – Unit 1 SAFSTOR, DECON both following Unit 2 Shutdown

- SAFSTOR Unit 1 when it is permanently shutdown in 2036
- DOE starts accepting fuel from the site in 2033
- Unit 1 transfers spent fuel from pool to DOE prior to shutdown beginning in 2033
- Unit 1 Fuel pool empty by 2046
- DECON methodology for Units 1 and 2 after Unit 2 is permanently shutdown in 2043
- Unit 2 transfers spent fuel from pool to DOE prior to shutdown beginning in 2034
- Unit 2 Fuel pool empty by 2046

Document No. 164086-DCE-01

Rev. 1

- Document No. 164086-DCE-01 Rev. 1
- All Dry Fuel transferred from ISFSI to DOE by 2071
- Decommissioning will be performed by FPL and a Decommissioning General Contractor (DGC)
- Class A LLRW will be disposed of at the ES Clive UT burial site
- Class B and Class C LLRW will be shipped and buried at the WCS Andrews County, TX burial site

Scenario 2 - SAFSTOR

- SAFSTOR Unit 1 when it is permanently shutdown in 2036
- DOE starts accepting fuel from the site in 2033
- Unit 1 transfers spent fuel from pool to DOE prior to shutdown beginning in 2033
- Unit 1 Fuel pool empty by 2046
- SAFSTOR Unit 2 after shutdown in 2043
- Unit 2 transfers spent fuel from pool to DOE prior to shutdown beginning in 2034
- Unit 2 Fuel pool empty by 2046
- All Dry Fuel transferred from ISFSI to DOE by 2071
- Decommissioning will be performed by FPL and a Decommissioning General Contractor (DGC)
- SAFSTOR period to end in 2089
- Decommissioning activities to complete by 2096 (excludes ISFSI decommissioning ISFSI decommissioning and demolition to complete by 2097)
- Class A LLRW will be disposed of at the ES Clive UT burial site
- Class B and Class C LLRW will be shipped and buried at the WCS Andrews, TX burial site

The cost estimate results are provided for each scenario in 2020 dollars and summarized in Table 1-1 below. This table provides License Termination costs (corresponding to 10 CFR 50.75(c) requirements), Spent Fuel Management costs (corresponding to 10 CFR 50.54(bb) requirements), and Site Restoration costs including activities such as clean building demolition and site grading etc.

Table 1-1

	FPL St. Lucie Units 1 and 2 Decommissioning Cost Summary				
		(t	housands of 2020 (dollars)	
So	cenario	License Termination	Spent Fuel	Site Restoration	Total
	1	1,254,740	427,313	63,409	1,745,462
	2	1,319,504	473,029	62,101	1,854,633

Table 1-2 below provides the cost estimate results for Scenario 1 separated into Unit 1, Unit 2 and Total.

Table 1-2

FPL St. Lucie Units 1 and 2 Scenario 1 Cost Summary by Unit (thousands of 2020 dollars)			
Unit 1 Unit 2 Total			
License Termination	651,106	603,633	1,254,740
Spent Fuel	243,383	183,930	427,313
Site Restoration	28,912	34,497	63,409
Total	923,401	822,060	1,745,462

Table 1-3 below provides the cost estimate results for Scenario 2 separated into Unit 1, Unit 2 and Total.

Table 1-3

FPL St. Lucie Units 1 and 2 Scenario 2 Cost Summary by Unit (thousands of 2020 dollars)			
Unit 1 Unit 2 Total			
License Termination	677,793	641,710	1,319,504
Spent Fuel	266,544	206,485	473,029
Site Restoration	28,188	33,913	62,101
Total	972,525	882,108	1,854,633

The estimate is based on site-specific plant systems and buildings inventories. These inventories, EnergySolutions' (ES) proprietary Unit Cost Factors (UCFs), historical data and execution strategy were used to generate required man-hours, waste volumes and classification, and estimated costs. Detailed project estimates are included in <u>Appendix C</u>.

The schedule reflects EnergySolutions' historical execution strategy and experience to sequence activity-dependent or distributed decommissioning elements such as planning and preparations, major component removal, building decontamination, building demolition, etc. A schedule for each scenario is summarized in Tables 1-4 and 1-5 below. Detailed project schedules are included in <u>Appendix B.</u>

Table 1-4 below provides a schedule summary for Scenario 1 based on a DECON scenario with Unit 1 Shutdown March 1, 2036 and Unit 2 Shutdown April 6, 2043.

Table 1-4

FPL DCE-01 St. Lucie Units 1 and 2 Scenario 1 Schedule Summary		
Year	Item	
2033	DOE starts accepting fuel from spent fuel pool	
2036	Unit 1 Shutdown	
2040	Unit 1 SAFSTOR period begins	
2043	Unit 2 Shutdown	
2046	Unit 1 Fuel Pool Empty	
2046	Unit 2 Fuel Pool Empty	
2046	Unit 1 SAFSTOR period ends	
2047	Start Demolition	
2053	Decommissioning and Site Restoration Complete	
2071	ISFSI Empty	
2073	ISFSI Decommissioning and Site Restoration Complete	

Table 1-5 below provides a schedule summary for Scenario 2 based on a SAFSTOR scenario with Unit 1 Shutdown March 1, 2036 and Unit 2 Shutdown April 6, 2043.

Table 1-5

FPL DCE-01 St. Lucie Units 1 and 2 Scenario 2 Schedule Summary		
Year	Item	
2033	DOE starts accepting fuel from spent fuel pool	
2036	Unit 1 Shutdown	
2040	Unit 1 SAFSTOR period begins	
2043	Unit 2 Shutdown	
2046	Unit 1 Fuel Pool Empty	
2046	Unit 2 Fuel Pool Empty	
2047	Unit 2 SAFSTOR period begins	
2071	ISFSI Empty	
2089	SAFSTOR Period ends	
2090	Start Demolition	
2096	Decommissioning and Site Restoration Complete	
2097	ISFSI Decommissioning and Site Restoration Complete	

2.0 INTRODUCTION

2.1 Study Objective

This report presents the 2020 Decommissioning Cost Estimate (DCE) Study of the St. Lucie Nuclear Plant, Units 1 and 2, hereinafter referred to as the 2020 Cost Study. The St. Lucie Nuclear Plant (St. Lucie) is owned and operated by FPL.

This DCE has been performed to furnish an estimate, for financial planning purposes, of the costs for decommissioning St. Lucie Units 1 and 2 to the extent required to terminate the plant's operating license pursuant to 10 CFR 50.75(c), post-shutdown management of spent fuel until acceptance by the U.S. Department of Energy (DOE) pursuant to 10 CFR 50.54(bb), clean demolition of structures and restoration of the site.

The study methodology follows the basic approach originally presented in the Atomic Industrial Forum/National Environmental Studies Project Report AIF/NESP-036, "Guidelines for Producing Commercial Nuclear Power Plant Decommissioning Cost Estimates," (Ref. No. 1). The report was prepared in accordance with Nuclear Regulatory Commission (NRC) Regulatory Guide 1.202, "Standard Format and Content of Decommissioning Cost Estimates for Nuclear Power Reactors," (Ref. No. 2). The estimate is based on compliance with current regulatory requirements and proven decommissioning technologies.

2.2 Regulatory Framework

Provisions of current laws and regulations affecting decommissioning, waste management and spent fuel management are as follows:

- 1. NRC regulations require a license for on-site storage of spent fuel. Wet storage in a spent fuel pool is authorized by a facility's 10 CFR Part 50 license (Ref. No. 3). On-site dry storage of spent fuel at an Independent Spent Fuel Storage Installation (ISFSI) is licensed by either: (a) the general license set forth in 10 CFR 72.210, which requires that a Part 50 license be in place; or (b) a site-specific ISFSI license issued pursuant to 10 CFR Part 72.
- 2. 10 CFR 50.75(c) requires funding by the licensee of the facility for the decommissioning program, but specifically excludes the cost of removal and disposal of spent fuel and the removal of clean structures.
- 3. 10 CFR 50.54 (bb) requires the licensee, within two years following permanent cessation of operation of the reactor or five years before expiration of the operating license, whichever occurs first, to submit written notification to the NRC for its review and preliminary approval of the program by which the licensee intends to manage and provide funding "for the management of all irradiated fuel at the reactor upon expiration of the reactor operating license until title to the irradiated fuel and possession of the fuel is transferred to the Secretary of Energy for its ultimate disposal in a repository." However, the NRC does not currently consider post-shutdown spent fuel management costs to be decommissioning costs.

Document No. 164086-DCE-01

Rev. 1

4. 10 CFR 72.30(b) requires that a licensee under Part 72 must submit a decommissioning funding plan that contains information that provides assurance that funds will be available to decommission the ISFSI.

Document No. 164086-DCE-01

Rev. 1

5. 10 CFR Part 961, Appendix E (Ref. No. 4), requires spent fuel to be cooled in the spent fuel pool for at least five years before it can be accepted by DOE.

Decommissioning Alternatives

The three basic methods for decommissioning are DECON, SAFSTOR, and ENTOMB, which are summarized as follows:

- 1. DECON: The equipment, structures, and portions of the facility and site that contain radioactive contaminants are promptly removed or decontaminated to a level that permits termination of the license after cessation of operations.
- 2. SAFSTOR: The facility is placed in a safe, stable condition and maintained in that state (safe storage). The facility is decontaminated and dismantled at the end of the storage period to levels that permit license termination. NRC regulations require decommissioning to be completed within 60 years of cessation of operation. Durations less than the regulatory-allowed maximum may be referred to as Modified SAFSTOR.
- 3. ENTOMB: Radioactive structures, systems, and components are encased in a structurally long-lived substance, such as concrete. The entombed structure is appropriately maintained and monitored until radioactivity decays to a level that permits termination of the license. Since entombment will exceed the requirement for decommissioning to be completed within 60 years of cessation of operation, NRC handles entombment requests on a case-by-case basis.

The selection of a preferred decommissioning alternative is influenced by a number of factors pertinent at the time of final plant shutdown. These factors include the cost of each decommissioning alternative, minimization of occupational radiation exposure, availability of a low-level waste disposal facility, availability of a high-level waste (spent fuel) repository, regulatory requirements, and public concerns.

Post-Shutdown Spent Fuel Management Alternatives

Selection of a decommissioning strategy and the associated schedule for completion is in part contingent upon an assumed start date for DOE acceptance of spent fuel and an assumed end date for completion of the transfer of all spent fuel assemblies projected to be generated during a power reactor's operating life. The basic options for long-term post-shutdown spent fuel management currently available to power plant operators are (1) wet storage consisting of continued maintenance and operation of the spent fuel pool, and (2) dry storage consisting of transfer of spent fuel from the fuel pool to on-site dry storage modules after a cooling period. Maintaining the spent fuel pool for an extended duration following cessation of operations prevents termination of the Part 50 license and typically has a higher annual maintenance and operating cost than the dry storage alternative. Transfer of spent fuel to an ISFSI requires additional capital expenditures for purchase and construction of the ISFSI and dismantlement and disposal of the ISFSI following completion of spent fuel transfer to DOE. In both cases the decommissioning and spent fuel management costs are significantly affected by the assumed start and end dates for DOE acceptance of spent fuel.

In January 2013, DOE released its "Strategy for Management and Disposal of Used Nuclear Fuel and High-Level Radioactive Waste" (Ref. No. 5). The DOE strategy contemplates building the capability to begin executing DOE's commitment to address waste disposal within the next ten years. Under this strategy, by 2021, operation would begin of a "pilot storage facility" with an "initial focus on accepting spent fuel from shutdown reactor sites." By 2025, a "larger interim storage facility" would be available and by 2048 a geologic repository would commence operations.

For purposes of this estimate, FPL has assumed the DOE pickup of commercial fuel to begin in 2030. The DOE starts accepting spent fuel from the St. Lucie facility in 2033 and the acceptance rate is consistent with the 2004 "Acceptance Priority Ranking & Annual Capacity Report" (Ref. No. 6), which is the most current information regarding the acceptance of spent fuel.

Note that nothing in this update, or in the assumptions and information provided by FPL, should be construed as any sort of admission or concession regarding the legal obligations of DOE. For example, and without limitation, the assumptions for DOE performance after 2021 utilized in this update do not include consolidation or acceleration via exchanges of acceptance allocations with other utilities, and DOE is also assumed to accept loaded and canistered fuel, although the government's stated positions with respect to such acceptance, including assertions in legal proceedings, have been inconsistent.

3.0 STUDY METHODOLOGY

3.1 General Description

EnergySolutions maintains a proprietary decommissioning cost model based upon the fundamental technical approach established in AIF/NESP-036, "Guidelines for Producing Commercial Nuclear Power Plant Decommissioning Cost Estimates," dated May 1986 (Ref. No. 1). The cost model has been continuously updated in accordance with regulatory requirements, EnergySolutions' actual project experience, and the latest industry technologies. The cost model includes elements for estimating distributed (direct costs) and undistributed costs. Distributed costs are activity specific and include planning and preparation costs as well as the decontamination, packaging, disposal, and removal of major components and systems. For example, the segmentation, packaging, and disposal of the reactor internals is a distributed cost. Undistributed costs, sometimes referred to as collateral costs, are typically time dependent costs such as utility and decommissioning general contractor staff, property taxes, insurance, regulatory fees and permits, energy costs, and security staff.

The methodology for preparing cost estimates for a selected decommissioning alternative requires development of a site-specific detailed work-activity sequence based upon the plant inventory. The activity sequence is used to define the labor, material, equipment, energy resources, and duration required for each activity. In the case of major components, individual work-activity sequence analyses are performed based on the physical and radiological characteristics of the component and the packaging, transportation, and disposal options available.

In addition to actual costs and UCF models the study also relies on information obtained for earlier decommissioning estimates from across the industry and from cost information derived for submitted proposals and bid results.

3.2 Schedule Analysis

Energy Solutions has established a Work Breakdown Structure (WBS) that typically defines decommissioning costs and the schedule into six primary periods to define the scope of work. Those periods are:

- Period 1 Shutdown and Transition
- Period 2 SAFSTOR
- Period 3 Decommissioning and License Termination
- Period 4 Site Restoration
- Period 5 Dry Fuel / GTCC Storage and Transfer
- Period 6 ISFSI Decommissioning

The work is broken down further into sub-periods as defined in Section 4.2 below.

Once the work activity durations are established, a time-phased schedule and cash-flow analysis are performed using EnergySolutions' integrated HardDollar estimating and scheduling tools to generate annual spending.

Document No. 164086-DCE-01

Rev. 1

Document No. 164086-DCE-01 Rev. 1

The schedule accounts for constraints such as spent fuel cooling periods and regulatory reviews. The schedule is typically delineated into periods that differentiate manpower requirements and undistributed costs.

3.3 Decommissioning Staff

EnergySolutions' philosophy towards decommissioning is to assume that the project will be performed in an efficiently planned and executed manner using project personnel experienced in decommissioning. These DCE scenarios assume that the decommissioning will be performed by a highly experienced and qualified DGC, with oversight and management of the decommissioning operations performed by the utility staff. It is also assumed that the utility staff will be supplemented by professional consulting engineering, particularly in the planning and preparation phase.

Staffing levels for each project period are based on the Atomic Industrial Forum (AIF) guidelines, Energy *Solutions'* project experience and industry practice. The sizes of the staffs are varied in each period in accordance with the requirements of the work activities. Staffing has been organized into the following departments or functional groups:

- Administration
- Engineering
- Health Physics / Radiation Protection
- Management
- Maintenance and Operations
- Quality Assurance
- Security Administration
- Security Guard Force
- Waste Operations
- DGC Staff

3.4 Waste Disposal

Waste management costs comprise a significant portion of the decommissioning cost estimate. Additionally, limited future access to disposal sites licensed for receipt of Class B and C wastes introduces a significant level of uncertainty with respect to the appropriateness of using existing rate structures to estimate disposal costs of these wastes. EnergySolutions' approach to estimating waste disposal costs is discussed in the following paragraphs.

Waste Classification

Regulations governing disposal of radioactive waste are stringent in order to ensure control of the waste and preclude adverse impact on public health and safety. At present, low-level radioactive waste (LLRW) disposal is controlled by NRC Regulation 10 CFR 61, which went into effect in December 1983. This regulation stipulates the criteria for the establishment and operation of shallow-land LLRW burial facilities. Embodied within this regulation are criteria and classifications for packaging LLRW such that it is acceptable for burial at licensed LLRW disposal sites.

For each waste classification, 10 CFR 61 stipulates specific criteria for physical and chemical properties that the LLRW must meet in order to be accepted at a licensed disposal site. The LLRW disposal criteria of 10 CFR 61 require that LLRW generators determine the proportional amount of a number of specific radioactive

isotopes present in each container of disposable LLRW. This requirement for isotopic analysis of each waste stream of disposable LLRW is met by employing a combination of analytical techniques such as computerized analyses based upon scaling factors, sample laboratory analyses, and direct assay methods. Having performed an isotopic analysis of each container of disposable LLRW, the waste must then be classified according to one of the classifications (Class A, B, C or Greater Than Class C (GTCC)) as defined in 10 CFR 61.

EnergySolutions' classification of LLRW resulting from decommissioning activities is based on AIF/NESP-036 (Ref. No. 1), NUREG/CR-0130 (Ref. No. 7), NUREG/CR-0672 (Ref. No. 8), and recent industry experience. The estimated curie content of the reactor vessel and internals at shutdown is derived from NUREG/CR-0130 for Pressurized Water Reactors (PWRs) and NUREG/CR-0672 for Boiling Water Reactors (BWRs) and adjusted for the different mass of components and period of decay.

Packaging

Selection of the type and quantity of containers required for Class B and C wastes is based on the most restrictive of either curie content, dose rate, container weight limit, or container volume limit. GTCC wastes from segmentation of the reactor vessel internals is packaged in fuel canisters. The selection of container type for Class A waste is based on the transportation mode (rail, truck, barge, etc.) and waste form. The quantity of Class A waste containers is determined by the most restrictive of either container weight limit or container volume limit. Large components, such as pressurizers, and reactor recirculation pumps, are shipped as their own container with shielding as required.

Custom container costs are obtained from manufacturers. Shielded transport cask and liner costs are obtained from EnergySolutions or other cask owners and operators.

Transportation

Transportation routes to processing and disposal facilities are determined based on available transportation modes (truck, rail, barge or combinations). Transportation costs for the selected routes and modes are obtained from vendor quotes or published tariffs whenever possible.

Class A Disposal Options and Rates

In accordance with the existing Life-of-Plant (LOP) Disposal Agreement (Ref. No. 9), all Class A waste that meets the Clive facility waste acceptance criteria may be disposed of at Clive. All reported waste disposal costs include packaging, transportation, and any applicable surcharges.

Class B and C Disposal Options and Rates

Currently, within the United States, there are only three operational commercial disposal facilities licensed to accept Class B and C LLRW: the Barnwell facility, operated by EnergySolutions in Barnwell, South Carolina, the U.S. Ecology facility in Richland, Washington, and the licensed facility in Andrews County, Texas operated by Waste Control Specialists (WCS). Barnwell only accepts waste from states within the Atlantic Compact, U.S. Ecology only accepts waste from states within the Northwest and Rocky Mountain Compacts. However, the WCS facility will accept waste from the Texas Compact (comprised of Texas and Vermont) and non-Compact generators. The Texas Compact Commission on March 23, 2012, approved amendments to rules allowing the import of non-compact generator LLRW for disposal at the Andrews County facility.

In accordance with the existing Life-of-Plant (LOP) Disposal Agreement, all Class B and C waste that meets the WCS facility waste acceptance criteria is to be disposed of at WCS, Andrews County, TX facility. All reported waste disposal costs include packaging, transportation, and any applicable surcharges.

Greater Than Class C (GTCC)

Wastes identified as 10 CFR 61 Class A, B, and C may be disposed of at a near-surface disposal facility. Certain components are highly activated and may exceed the radionuclide concentration limitations for 10 CFR 61 Class C waste. In accordance with 10 CFR 61, these components cannot be disposed of in a near-surface LLRW disposal facility and must be transferred to a geologic repository or a similar site approved by the NRC.

Highly activated sections of the reactor vessel internals will result in GTCC waste. Presently, a facility does not exist for the disposal of wastes exceeding 10 CFR 61 Class C limitations. EnergySolutions assumes that the DOE will accept this waste along with spent fuel. Although courts have held that DOE is obligated to accept and dispose of GTCC, issues regarding potential costs remain potentially unsettled. Therefore, EnergySolutions conservatively estimates a GTCC waste disposal cost. EnergySolutions assumes that the GTCC waste will be packaged in dry storage containers, and be shipped to a storage or disposal facility by DOE along with the spent fuel.

Additionally, EnergySolutions assumes shipping costs for GTCC waste to be equivalent to the commercial cost of shipping a Type B licensed, shielded cask such as the CNS 8-120B cask, which is owned and operated by EnergySolutions.

LLRW Volume Reduction

Based on current Class A LLRW disposal rates, EnergySolutions does not assume on-site volume reduction techniques such as waste compaction or an aggressive decontamination, survey and release effort. These activities are not currently considered to be cost effective over disposal.

Non-Radioactive Non-Hazardous Waste Disposal

EnergySolutions assumes that recyclable, non-radioactive scrap metal resulting from the decommissioning program will be transported to a scrap metal dealer. Concrete debris is assumed to be processed by size reduction, with removal of structural reinforcing steel, and used on site as engineered fill for voids. Asphalt from parking lots and roadways is assumed to be stockpiled on site and removed, at no cost to the project, by a recycler. All other demolition debris is removed from the site and disposed of at a local construction debris landfill.

Hazardous and Industrial Waste Disposal

Uncontaminated lead shielding remaining after shutdown is assumed to be removed from its installed locations and shipped off site by entities having a need for the material. The entities receive the lead at no charge in return for providing the removal and shipping services. Non-radioactive contaminated surfaces coated with lead-based paint will be removed as non-hazardous building demolition debris. All other chemicals and hazardous materials present at shutdown will be removed and properly disposed of during decommissioning.

3.5 Final Status Survey

The cost of performing a final status survey (FSS) is based on NUREG-1575, "Multi-Agency Radiation Survey and Site Investigation Manual (MARSSIM)" (Ref. No. 10). Estimates of MARSSIM Class I, II, and III survey designations are based on information furnished by FPL, radiological assumptions regarding contamination resulting from historic plant operations and from small and large component removal activities. The FSS activity cost calculation includes the in-place remote survey of underground metal and concrete pipe, soil, and groundwater sampling and analysis. Estimated costs for NRC and Oak Ridge Institute for Science and Education (ORISE) verification are also included, and the NRC review period is incorporated into the project schedule.

3.6 Contingency

Contingencies are applied to cost estimates primarily to allow for unknown or unplanned occurrences during the actual program, e.g., increased radioactive contamination over that expected, equipment breakdowns, weather delays, and labor strikes. This is consistent with the definition provided in the DOE Cost Estimating Guide, DOE G 430.1-1, 3-28-97 (DOE G) (Ref. No. 11). Contingency "covers costs that may result from incomplete design, unforeseen and unpredictable conditions, or uncertainties within the defined project scope. The amount of contingency will depend on the status of design, procurement, and construction; and the complexity and uncertainties of the component parts of the project. Contingency is not to be used to avoid making an accurate assessment of expected costs." EnergySolutions determines site-specific contingency factors to be applied to each estimate based on industry practices and actual project experience.

The DOE has established a recommended range of contingencies as a function of completeness of program design, DOE G. The ranges are:

	Contingency Range
Type of Estimate	as a % of Total Estimate
Planning Phase Estimate	20-30
Budget Estimate	15-25
Title I (Preliminary Design Estimate)	10-20
Title II (Definitive Design Estimate)	5-15

The approach in this estimate to assigning appropriate contingency rates is based upon adaptations of published values for the specific decommissioning activities as well as project experience and current industry practices. One source for such published information is AIF/NESP-036 "Guidelines for Producing Nuclear Plant Decommissioning Cost Estimates" (Ref. No. 1). The AIF guideline identifies contingencies for activities specific to a nuclear power plant decommissioning, such as reactor internals removal. The contingencies presented in the AIF guideline are based on the assumption that the estimated costs are not well known; therefore, the recommended contingencies are greater than they would be if the estimated costs were well known. With the exception of the system decontamination, reactor vessel and reactor internals removal, and disposal, the contingencies presented in the AIF guideline are consistent with the values for a Budget/Title I estimate. The system decontamination, reactor vessel and reactor internals removal, and disposal contingencies recommended in the AIF guideline are significantly higher than the ranges identified by the DOE, even for a planning phase document. This is due to the unique nature of these activities and the relatively small amount of historical data available at the time the AIF document was written.

Document No. 164086-DCE-01

Rev. 1

The application of contingency rates in this estimate are consistent with information presented in AIF guideline and DOE G. The decommissioning costs generated in the estimate are considered well known and, as such, the contingencies presented in AIF guideline were reduced for each category of costs. There have also been a number of large-scale decommissioning projects since AIF was published, including by Energy*Solutions*, providing substantial historical information that has been used in preparing this estimate, allowing for additional reduction in contingency costs.

The following table provides a summary of contingency values included in the Decommissioning Cost Estimate:

- 10% contingency on SAFSTOR staff and undistributed costs
- 15% contingency on non-rad build demolition and site restoration activities
- 15% contingency on dry fuel storage & ISFSI operations activities
- 15% contingency on dry fuel transfer to DOE
- 15% contingency on staff and undistributed costs
- 15% contingency on GTCC transportation and disposal
- 20% contingency on reactor vessel segmentation
- 20% contingency on large component and system removal
- 20% contingency on rad building interior and exterior demolition
- 20% contingency on final status surveys
- 20% contingency on wet fuel transfer to the DOE
- 20% contingency on remediation and disposal of contaminated soils
- 25% contingency on asbestos abatement

A reactor decommissioning program will be conducted under an NRC-approved Quality Assurance Program which meets the requirements of 10 CFR 50, Appendix B. However, the development of the Quality Assurance Program, the performance of work under that program, and the effort required to ensure compliance with the program, is already included in the detailed cost estimate. Therefore, EnergySolutions does not include quality assurance as an element of the contingency allowance. The same is true where radioactive contamination or activated materials are dealt with. The cost factors and associated calculations fully reflect the cost impact of that material, and a separate contingency is not required specifically due to working with contamination.

3.7 Cost Reporting

Total project costs are aggregated from the distributed activities (direct costs) and undistributed costs into the following categories:

- Labor
- Materials and Equipment
- Waste Transportation and Disposal
- Other Direct Costs

Other costs include property taxes, insurance, license fees, permits, and energy. Waste disposal costs are the summation of packaging, transportation, base disposal rate, and any applicable surcharges. Health physics (HP) supplies and small tool costs are calculated as a component of each distributed activity cost and included in the category of Material and Equipment, except for HP supplies for utility HP staff are calculated and reported as an undistributed line item. A contingency is then applied to each activity.

4.0 SITE-SPECIFIC TECHNICAL APPROACH

4.1 Facility Description

The St. Lucie Nuclear Plant is a nuclear-powered electrical generating facility consisting of two PWRs. St. Lucie is located on Hutchinson Island, midway between the Florida cities of Fort Pierce and Stuart. The plant site comprises approximately 1,132 acres, and approximately one quarter of the site is used for generating electricity.

Both Unit 1 and Unit 2 are two-loop Combustion Engineering PWRs with a current thermal output of 3,020 MWt and a design electrical rating of 1,062 MWe and 1,074 MWe, respectively. The current license expiration dates for Units 1 and 2 are in 2036 and 2043, respectively.

St. Lucie has an existing ISFSI supporting Units 1 and 2. The ISFSI is operated under the 10 CFR Part 72 general license using the manufacturer's Certificate of Compliance.

A list of the St. Lucie Unit 1 and 2 systems and structures included in the material inventory for this study is provided in Appendix A.

4.2 Decommissioning Periods

Energy Solutions has established a Work Breakdown Structure (WBS) that typically defines decommissioning cost estimates with six primary periods to define the scope of work. Those periods are:

- Period 1 Shutdown and Transition
- Period 2 SAFSTOR
- Period 3 Decommissioning and License Termination
- Period 4 Site Restoration
- Period 5 Dry Fuel / GTCC Storage and Transfer
- Period 6 ISFSI Decommissioning

The work is broken down further into sub-periods.

The project periods defined for this site-specific study and a summary of activities performed during each period are listed below.

SCENARIO 1 - Unit 1 SAFSTOR, DECON both following Unit 2 Shutdown

Period 1 – Shutdown and Transition:

<u>Period 1a – Planning Prior to Shutdown (by Plant Operations)</u>

Period 1b – Unit 1 Post-Shutdown Planning and Engineering:

- Administrative Activities in Preparation for SAFSTOR
- Prepare PSDAR and License Documents
- Engineering Activities in Preparation for SAFSTOR

Document No. 164086-DCE-01

Rev. 1

Period 1c – Unit 1 Post-Shutdown Deactivation and Modifications:

- Defuel Reactor Unit 1 (by Plant Operations)
- Fuel Sampling and Inspections (by Plant Operations)
- Spent Fuel Pool System Modifications
- Implement Cold and Dark
- Flush and Drain Non-Essential Systems
- Perform Pre-SAFSTOR Baseline Radiation Survey

Period 1d – Unit 1 Wet Fuel Transfer to DOE prior to SAFSTOR:

- Provide Transfer Casks (supplied by DOE)
- Procure Spent Fuel Loading and Transfer Equipment
- Procedures and Dry Runs
- Remove Fuel Assemblies from Pool and Load DOE Casks
- Dry, Close and Inspect DOE-supplied Casks
- Load Out Casks to DOE Transport
- Spent Fuel Transportation and Disposal (by DOE)

Period 1e – Unit 2 Post-Shutdown Planning and Engineering:

- Administrative Activities in Preparation for Decommissioning
- Preparation of PSDAR and Licensing Documents
- Engineering Activities in Preparation for Decommissioning

<u>Period 1f – Unit 2 Post-Shutdown Preparations and Deactivation:</u>

- Defuel Reactor Unit 2 (by Plant Operations)
- Fuel Sampling and Inspections (by Plant Operations)
- Spent Fuel Pool System Modifications

Period 1g – Unit 2 Wet Fuel Transfer to DOE prior to DECON:

- Provide Transfer Casks (supplied by DOE)
- Procure Spent Fuel Loading and Transfer Equipment
- Procedures and Dry Runs
- Remove Fuel Assemblies from Pool and Load DOE Casks
- Dry, Close and Inspect DOE-supplied Casks
- Load Out Casks to DOE Transport
- Spent Fuel Transportation and Disposal (by DOE)

<u>Period 1h – Unit 2 Wet Fuel Transfer to ISFSI prior to DECON:</u>

- Provide Transfer Casks
- Procedures and Dry Runs
- Remove Fuel Assemblies from Pool and Load Casks
- Dry, Close and Inspect Casks
- Load Out Casks to Transport

Period 1i – Undistributed Costs for Shutdown and Transition:

- Utility Staff
- Security Guard Force
- Property Taxes
- Insurance
- Corporate Support
- Utility Staff HP Supplies
- NRC Inspection Fees
- Licensing Fees
- Materials and Services
- Energy
- County Fees
- FEMA Fees
- ISFSI Operating Costs
- Spent Fuel Maintenance

Period 2 – SAFSTOR (Unit 1):

<u>Period 2a – Wet Fuel Transfer to DOE during SAFSTOR:</u>

- Provide Transfer Casks (supplied by DOE)
- Procure Spent Fuel Loading and Transfer Equipment (in Period 1)
- Procedures and Dry Runs (in Period 1)
- Remove Fuel Assemblies from Pool and Load Casks
- Dry, Close and Inspect Casks
- Load Out Casks to Transport

Period 2b – Wet Fuel Transfer to ISFSI during SAFSTOR:

- Purchase Transfer Casks
- Procure Spent Fuel Loading and Transfer Equipment (in Period 1)
- Procedures and Dry Runs
- Remove Fuel Assemblies from Pool and Load Casks
- Dry, Close and Inspect Casks
- Load Out Casks to Transport

Period 2c – Unit 1 Dormancy during Wet Fuel Transfer to DOE:

- Utility Staff
- Security Guard Force
- Property Taxes
- Insurance
- Corporate Support
- Utility Staff HP Supplies
- NRC Inspection Fees
- Licensing Fees
- County Fees

- FEMA Fees
- Emergency Planning Fees
- ISFSI Operating Costs
- Energy

Period 3 – Decommissioning and License Termination:

<u>Period 3a – Decommissioning Planning:</u>

- Decommissioning Planning and Design
- Prepare Integrated Work Sequence and Schedule
- Site Characterization
- Prepare Decommissioning Activity Specifications
- Prepare Detailed Work Procedures
- Prepare License Termination Plan
- Design Containment and Miscellaneous System Modifications
- Purchase Dry Storage Modules for GTCC Waste

<u>Period 3b – Decommissioning Transition and Preparations:</u>

- Mobilize Decommissioning General Contractor
- Flush and Drain Non-Essential Systems Unit 2
- Perform Asbestos Abatement of Pipe Insulation
- Implement Temporary Power Upgrades Unit 1
- Implement Cold and Dark and Install Temporary Power Unit 2
- Construct Miscellaneous Building Modifications, In-Plant Laydown Areas
- Modify Containment Access
- Transportation Infrastructure Modifications
- Procure Waste Handling and Processing Tents

<u>Period 3c – Reactor Vessel Removal:</u>

- Design and Procure Special Equipment
- Test Special Cutting and Handling Equipment and Train Operators
- Finalize Internals and Vessel Segmentation Details
- Segment, Package and Ship Reactor Internals
- Package and Ship Reactor Pressure Vessels

Period 3d – Large Component Removal:

- Heavy Lift / Transfer Equipment
- Remove and Dispose of Steam Generators
- Remove and Dispose of Pressurizer
- Remove and Dispose of Reactor Coolant Pipe
- Remove and Dispose of Reactor Coolant Pumps
- Large Component Disposal

Period 3e – Plant Decontamination and Interior Rad Demolition:

- Document No. 164086-DCE-01 Rev. 1
- Remove and Dispose of Spent Fuel Storage Racks
- Segment, Package and Dispose of Spent Fuel Pool Island Equipment
- Decon/Surgical Removal Containment Buildings
- Decon/Surgical Removal Fuel Buildings
- Decon/Surgical Removal Auxiliary Buildings
- Oversize Debris/Containerized/Processed Debris Disposal

<u>Period 3f – Rad Building Demolition</u>:

- Demolish Fuel Buildings
- Demolish Auxiliary Buildings
- Demolish Containment Buildings
- Contaminated Soil
- Debris Disposal

Period 3g – License Termination Activities:

- Final Status Survey for Structures
- Final Status Survey for Land Areas (included with Structures)

<u>Period 3h – Undistributed Costs for Decommissioning and License Termination:</u>

- Utility Staff
- Security Guard Force
- General Contractor Staff
- Property Taxes
- Insurance
- Corporate Support
- Utility Staff HP Supplies
- NRC Inspection Fees
- Licensing Fees
- Florida LLRW Inspection Fee
- Materials and Services
- Energy
- DGC HP Supplies

Period 4 – Site Restoration:

<u>Period 4a – Clean Building and Site Demolition</u>:

- Demolish Turbine Pedestal and Turbine Deck
- Demolish Intake and Circulating Water System (CWS)
- Demolish Tank Foundations
- Demolish Miscellaneous Site Structures
- Demolish Security Improvements
- Demolish Steam Generator Blowdown Treatment
- Clean Concrete Processing
- Demolish Site Paving
- Clean Debris Disposal / Recycle

Period 4b – Site Restoration:

- Procure Site Restoration Equipment
- Finish Grading and Re-Vegetate Site

Period 4c – Undistributed Costs for Site Restoration:

- Utility Staff
- Security Guard Force
- General Contractor Staff
- Property Taxes
- Insurance
- Corporate Support
- Energy
- Materials and Services

Period 5 – Dry Fuel / GTCC Storage and Transfer:

Period 5a – Dry Fuel Transfer to DOE during and after DECON:

- Procure Loading and Transfer Equipment (included in Period 1)
- Procedures and Dry Runs (included in Period 1)
- Remove Fuel Casks from ISFSI and Load DOE Transport
- Spent Fuel Transportation and Disposal (by DOE)

Period 5b – GTCC Waste Disposition:

- Remove GTCC Casks from ISFSI and Load Out
- GTCC Transportation and Disposal

<u>Period 5c – Undistributed Costs for Dry Fuel / GTCC Storage and Transfer:</u>

- Utility Staff
- Security Guard Force
- Property Taxes
- Insurance
- NRC Inspection Fees
- Licensing Fees
- ISFSI Operating Costs

Period 6 –ISFSI Decommissioning:

Period 6a – ISFSI D&D Planning and Preparations:

• Preparation and NRC Review of License Termination Plan

<u>Period 6b – ISFSI and Support Structure Clean Demolition:</u>

- Clean Demolition of ISFSI
- Demolition of ISFSI Support Structures

Document No. 164086-DCE-01

Period 6c – ISFSI Final Status Surveys:

- Verification Surveys
- Preparation of Final Report on Decommissioning and NRC Review

Period 6d – Undistributed Costs for ISFSI Decommissioning:

- Utility Staff
- Security Guard Force
- General Contractor Staff
- Property Taxes
- Insurance
- Energy
- County Fees
- FEMA Fees (Emergency Preparedness)

SCENARIO 2 – SAFSTOR

Period 1 – Shutdown and Transition:

<u>Period 1a – Planning Prior to Shutdown (by Plant Operations)</u>

Period 1b – Unit 1 Post-Shutdown Planning and Engineering:

- Administrative Activities in Preparation for SAFSTOR
- Prepare PSDAR and License Documents
- Engineering Activities in Preparation for SAFSTOR

<u>Period 1c – Unit 1 Post-Shutdown Deactivation and Modifications:</u>

- Defuel Reactor Unit 1 (by Plant Operations)
- Fuel Sampling and Inspections (by Plant Operations)
- Spent Fuel Pool System Modifications
- Implement Cold and Dark
- Flush and Drain Non-Essential Systems
- Perform Pre-SAFSTOR Baseline Radiation Survey

Period 1d – Unit 1 Wet Fuel Transfer to DOE prior to SAFSTOR:

- Provide Transfer Casks (supplied by DOE)
- Procure Spent Fuel Loading and Transfer Equipment
- Procedures and Dry Runs
- Remove Fuel Assemblies from Pool and Load DOE Casks
- Dry, Close and Inspect DOE-supplied Casks
- Load Out Casks to DOE Transport
- Spent Fuel Transportation and Disposal (by DOE)

Period 1e - Unit 2 Post-Shutdown Planning and Engineering:

- Administrative Activities in Preparation for Decommissioning
- Preparation of PSDAR and Licensing Documents
- Engineering Activities in Preparation for Decommissioning

Period 1f – Unit 2 Post-Shutdown Preparations and Deactivation:

- Defuel Reactor Unit 2 (by Plant Operations)
- Fuel Sampling and Inspections (by Plant Operations)
- Spent Fuel Pool System Modifications
- Implement Cold and Dark
- Perform Pre-SAFSTOR Baseline Radiation Survey

<u>Period 1g – Unit 2 Wet Fuel Transfer to DOE prior to SAFSTOR:</u>

- Provide Transfer Casks (supplied by DOE)
- Procure Spent Fuel Loading and Transfer Equipment
- Procedures and Dry Runs
- Remove Fuel Assemblies from Pool and Load DOE Casks
- Dry, Close and Inspect DOE-supplied Casks
- Load Out Casks to DOE Transport
- Spent Fuel Transportation and Disposal (by DOE)

Period 1h – Unit 2 Wet Fuel Transfer to ISFSI prior to SAFSTOR:

- Provide Transfer Casks
- Procedures and Dry Runs
- Remove Fuel Assemblies from Pool and Load Casks
- Dry, Close and Inspect Casks
- Load Out Casks to Transport

Period 1i – Undistributed Costs for Shutdown and Transition:

- Utility Staff
- Security Guard Force
- Property Taxes
- Insurance
- Corporate Support
- Utility Staff HP Supplies
- NRC Inspection Fees
- Licensing Fees
- Materials and Services
- Energy
- County Fees
- FEMA Fees
- ISFSI Operating Costs
- Spent Fuel Maintenance

Period 2 – SAFSTOR:

Period 2a – Unit 1 Wet Fuel Transfer to DOE during SAFSTOR:

- Provide Transfer Casks (supplied by DOE)
- Remove Fuel Assemblies from Pool and Load Casks
- Dry, Close and Inspect Casks
- Load Out Casks to Transport
- Spent Fuel Transportation and Disposal (by DOE)

Period 2b – Unit 1 Wet Fuel Transfer to ISFSI during SAFSTOR:

- Provide Transfer Casks
- Procedures and Dry Runs
- Remove Fuel Assemblies from Pool and Load Casks
- Dry, Close and Inspect Casks
- Load Out Casks to Transport
- Spent Fuel Transportation and Disposal (by DOE)

<u>Period 2c – Unit 1 Dormancy during Dry Fuel Storage</u>:

- Utility Staff
- Security Guard Force
- Property Taxes
- Insurance
- Corporate Support
- Utility Staff HP Supplies
- NRC Inspection Fees
- Licensing Fees
- County Fees
- FEMA Fees
- Materials and Services
- Roof Replacement
- Energy

Period 2d – Unit 2 Dormancy during Dry Fuel Storage:

- Utility Staff
- Security Guard Force
- Property Taxes
- Insurance
- Corporate Support
- Utility Staff HP Supplies
- NRC Inspection Fees
- Licensing Fees
- Materials and Services
- Energy

Document No. 164086-DCE-01 Rev. 1

Period 2e – Dormancy Only:

- Utility Staff
- Security Guard Force
- Property Taxes
- Insurance
- Corporate Support
- Utility Staff HP Supplies
- NRC Inspection Fees
- Licensing Fees
- Materials and Services
- Roof Replacement
- Energy

Period 3 – Decommissioning and License Termination:

<u>Period 3a – Decommissioning Planning:</u>

- Decommissioning Planning and Design
- Prepare Integrated Work Sequence and Schedule
- Planning and Design of Site Characterization
- Prepare Decommissioning Activity Specifications
- Prepare Detailed Work Procedures
- Prepare License Termination Plan
- Design Containment and Miscellaneous System Modifications
- Purchase Dry Storage Modules for GTCC Waste

<u>Period 3b – Decommissioning Transition and Preparations:</u>

- Mobilize Decommissioning General Contractor
- Perform Asbestos Abatement of Pipe Insulation
- Implement Temporary Power Upgrades Unit 1
- Construct Misc. Building Modifications, In-Plant Laydown Areas
- Modify Containment Access
- Transportation Infrastructure Modifications
- Procure Waste Handling and Processing Tents

Period 3c – Reactor Vessel Removal:

- Design and Procure Special Equipment
- Test Special Cutting and Handling Equipment and Train Operators
- Finalize Internals and Vessel Segmentation Details
- Segment, Package and Ship Reactor Internals
- Segment, Package and Ship Reactor Pressure Vessels

Period 3d – Large Component Removal:

- Heavy Lift / Transfer Equipment
- Remove and Dispose of Steam Generators

- Remove and Dispose of Pressurizer
- Remove and Dispose of Reactor Coolant Pipe
- Remove and Dispose of Reactor Coolant Pumps
- Large Component Disposal

Period 3e – Plant Decontamination and Interior Rad Demolition:

- Remove and Dispose of Spent Fuel Storage Racks
- Segment, Package and Dispose of Spent Fuel Pool Island Equipment
- Decon/Surgical Removal Containment Buildings
- Decon/Surgical Removal Fuel Buildings
- Decon/Surgical Removal Auxiliary Buildings
- Oversize Debris/Containerized/Processed Debris Disposal

Period 3f – Rad Building Demolition:

- Demolish Fuel Buildings
- Demolish Auxiliary Buildings
- Demolish Containment Buildings
- Contaminated Soil
- Debris Disposal

Period 3g – License Termination Activities:

- Final Status Survey for Structures
- Final Status Survey for Land Areas (included with Structures)

<u>Period 3h – Undistributed Costs for Decommissioning and License Termination:</u>

- Utility Staff
- Security Guard Force
- General Contractor Staff
- Property Taxes
- Insurance
- Corporate Support
- Utility Staff HP Supplies
- NRC Inspection Fees
- Licensing Fees
- Materials and Services
- Energy
- DGC HP Supplies

Period 4 – Site Restoration:

Period 4a – Clean Building and Site Demolition:

- Demolish Turbine Pedestal and Turbine Deck
- Demolish Intake and CWS
- Demolish Tank Foundations
- Demolish Miscellaneous Site Structures

- Demolish Security Improvements
- Demolish Steam Generator Blowdown Treatment
- Clean Concrete Processing
- Demolish Site Paving
- Clean Debris Disposal / Recycle

Period 4b - Site Restoration:

- Procure Site Restoration Equipment
- Finish Grading and Re-Vegetate Site

<u>Period 4c – Undistributed Costs for Site Restoration:</u>

- Utility Staff
- Security Guard Force
- General Contractor Staff
- Property Taxes
- Insurance
- Corporate Support
- Energy
- Materials and Services

Period 5 – Dry Fuel / GTCC Storage and Transfer:

Period 5a – Unit 1 - Dry Fuel Transfer to DOE during SAFSTOR:

Period 5a – Unit 2 - Dry Fuel Transfer to DOE during and after DECON:

- Procure Loading and Transfer Equipment (included in Period 1)
- Procedures and Dry Runs (included in Period 1)
- Remove Fuel Casks from ISFSI and Load DOE Transport
- Spent Fuel Transportation and Disposal (by DOE)

Period 5b – GTCC Waste Disposition:

- Remove GTCC Casks from ISFSI and Load Out
- GTCC Transportation and Disposal

Period 5c – Undistributed Costs for Dry Fuel / GTCC Storage and Transfer:

- Utility Staff
- Security Guard Force
- ISFSI Operating Costs

Period 6 –ISFSI Decommissioning:

Period 6a – ISFSI D&D Planning and Preparations:

• Preparation and NRC Review of License Termination Plan

Period 6b – ISFSI and Support Structure Clean Demolition:

• Clean Demolition of ISFSI

• Demolition of ISFSI Support Structures

Period 6c – ISFSI Final Status Surveys:

- Verification Surveys
- Preparation of Final Report on Decommissioning and NRC Review

Period 6d – Undistributed Costs for ISFSI Decommissioning:

- Utility Staff
- Security Guard Force
- General Contractor Staff
- Property Taxes
- Insurance
- Energy

4.3 Decommissioning Staff

EnergySolutions developed staffing based on the assumption that decommissioning will be performed by an experienced and qualified Decommissioning General Contractor (DGC), with oversight, management and security of the decommissioning operations performed by the utility staff. It is also assumed that the utility staff will be supplemented by professional consulting engineering, particularly in the planning and preparation period.

The sizes of the staffs are varied in each period in accordance with the requirements of the work activities. Details on the staff levels, by functional group, during each period are provided in detail in <u>Appendix D</u>.

4.4 Spent Fuel Management Staff

The largest spent fuel staff and security is in place while the spent fuel pool is operational during the minimum cooling period and the fuel assemblies are being transferred to either a DOE facility or dry storage. Once all spent fuel has been removed from the spent fuel pool, the staff and security levels are reduced. Details on the staff levels, by functional group, during each period are provided in <u>Appendix D</u>.

4.5 Spent Fuel Shipments

The spent fuel shipment schedules for this estimate are based on information from FPL regarding existing fuel inventory, planned transfers to dry storage and a projected date of 2033 for DOE's acceptance of spent fuel.

5.0 BASES OF ESTIMATE AND KEY ASSUMPTIONS

The bases of, and key assumptions for, this site-specific decommissioning estimate are presented below:

- 1. All cost data used in this study are in 2020 dollars.
- 2. Total and subtotal amounts are rounded.
- 3. The decommissioning will be performed under the current regulations. These regulations require a Post-Shutdown Decommissioning Activities Report (PSDAR) to be submitted prior to, or within, two years after permanent shutdown. Other revisions will be required for other licensing basis documents (e.g., Security, Emergency Planning, Fire Protection, Nuclear Safety, Quality Assurance Program, Fuel Debris issues, Spent Fuel Storage options).
- 4. The decommissioning will be performed using currently available technologies.
- 5. Fuel transfer operations are based on the DOE beginning to accept spent fuel starting in 2033.
- 6. All transformers on site following shutdown are assumed to be PCB-free; therefore, this study does not include costs for disposition of PCB contaminated transformers.
- 7. Cost for transportation of clean scrap metal to a recycler is included in the estimate; however, no credit is taken for the value of the scrap metal. Clean concrete debris is assumed to be processed by size reduction, with removal of structural reinforcing steel, and used on site as engineered fill for voids.
- 8. DGC staff salaries, including overhead and profit, were determined by using EnergySolutions' project experience and standard assumptions for these rates.
- 9. Certain professional personnel used for the planning and preparation activities, and DGC personnel, that are not based in the local economy, are assumed to be paid per diem based on area per diem rates from U.S. General Services Administration (GSA).
- 10. This study follows the occupational exposure principles of As Low As Reasonably Achievable (ALARA) through the use of productivity loss factors that incorporate such items as the use of respiratory protection and personnel protective clothing. These factors increase the work duration and cost.
- 11. The costs of all required safety analyses and safety measures for the protection of the general public, the environment, and decommissioning workers are included in the cost estimates. This reflects the requirements of:

10 CFR 20	Standards for Protection Against Radiation
10 CFR 50	Domestic Licensing of Production and Utilization Facilities
10 CFR 61	Licensing Requirements for Land Disposal of Radioactive Waste

Document No. 164086-DCE-01

10 CFR 71	Packaging of Radioactive Material for Transport
10 CFR 72	Licensing Requirements for the Independent Storage of Spent Nuclear Fuel and High-Level Radioactive Waste
29 CFR 1910	Occupational Safety and Health Standards
49 CFR 170-189	Department of Transportation Regulations Governing the Transport of Hazardous Materials
Reg. Guide 1.159	Assuring the Availability of Funds for Decommissioning Nuclear Reactors

Document No. 164086-DCE-01

- 12. Energy Solutions developed project schedules based on Unit 1 and Unit 2 shutdown dates of March 1, 2036, and April 6, 2043, respectively, and fuel shipping schedules provided by FPL.
- 13. Spent fuel in the fuel pools at the time of shutdown will be transferred directly to the DOE-provided transfer/shipping casks from 2033 through 2046. The 2020 Cost Analysis includes costs for transfer to the DOE beginning in 2036 for Unit 1 and 2043 for Unit 2. Costs prior to these dates are assumed to be paid from the plant operations budget. Remaining spent fuel in 2046 will be transferred from the spent fuel pool to the on-site ISFSI. The estimate includes purchase of transfer/shipping casks of the remaining spent fuel to be moved to the ISFSI.
- 14. Spent fuel canisters in the ISFSI at the time of shutdown will remain in dry storage until transfer to the DOE. The estimate includes transferring fuel from the existing ISFSI to the DOE-provided transfer/shipping casks during Period 5.
- 15. Costs for ISFSI security, operations and demolition for Units 1 and 2 are included in the estimate.
- 16. The estimate includes procurement of on-site fuel transfer equipment. It is assumed that equipment purchased for transfer equipment utilized during shipment from the spent fuel pool to the DOE will be utilized for the transfer of spent fuel to the ISFSI and is included in Period 1. It is assumed that this equipment will also be utilized for transfer/loading casks from the ISFSI to the DOE.
- 17. Based on FPL experience, the purchase of dry storage DSCs and HSMs required following shutdown are assumed to be 25% lower than for normal campaign costs due to volume discounts associated with the larger quantity of DSCs and HSMs required to transfer all fuel assemblies from the SFP to the pad.
- 18. As per FPL's settlement agreement, the DOE is expected to make payments to FPL to cover spent fuel management costs incurred by FPL prior to 2063 for St. Lucie.
- 19. The DOE is responsible to provide all transfer/shipping casks, containers, transportation and disposition of spent fuel shipped from the fuel pool and the ISFSI to a DOE designated off-site facility.

Document No. 164086-DCE-01

Rev. 1

21. All structures/systems shared between Unit 1 and Unit 2 are included in Unit 2 cost estimate.

20. The estimate is based on site-specific plant systems and building inventories previously included

- 22. License Termination costs include the complete demolition of the following buildings to a nominal depth of three feet below grade: Reactor Building, Auxiliary Building, and Fuel Handling Building.
- 23. The estimate is based on final site restoration, in which all remaining structures, with the exception of the switchyard and discharge diffuser, will be removed.
- 24. Foundations and building exterior walls are removed to a nominal depth of three feet below grade, surveyed and backfilled with appropriate fill material.
- 25. Intake piping will be left in place and sealed with a flowable concrete fill.

in the 2015 Cost Study, and includes any updates provided by FPL.

- 26. Clean concrete will be processed and utilized as backfill where needed to re-establish grade. The disturbed area of the site is to be graded and seeded.
- 27. Uncontaminated lead shielding remaining after shutdown was assumed to be removed from its installed locations and shipped off site by entities having a need for the material. The entities receive the lead at no charge in return for providing the removal and shipping services.
- 28. Any chemicals and hazardous materials present at shutdown are assumed to be removed and disposed of by the plant staff prior to decommissioning, as a normal part of plant operations.
- 29. Site-specific information regarding waste quantities of contaminated soil was provided by FPL and used as a basis for calculation of current costs for remediation and disposal.
- 30. All Class A waste is assumed to be disposed of at EnergySolutions' facility in Clive, Utah, in accordance with the existing LOP Disposal Agreement (Ref. No. 9) between EnergySolutions as allowed by the existing LOP and FPL dated January 1, 2007. A LOP agreement letter stating the 2020 price increase was also utilized to develop the waste disposal costs.
- 31. Class A waste includes Dry Active Waste (DAW) arising from the disposal of contaminated protective clothing and health physics supplies.
- 32. Class B and C waste disposal costs are based on disposal rates provided by FPL for the WCS Andrews, TX facility. All resins and filter waste is assumed to be Class B.
- 33. GTCC waste generated from the segmentation of the reactor internals will be stored in on-site canisters placed in the ISFSI until final disposition at a DOE facility. It is assumed that 12 GTCC canisters will be required for the St. Lucie units (6 canisters for Unit 1 and 6 canisters for Unit 2).
- 34. Vessel and internals curie estimates were derived from the values for the Reference PWR vessel and internals in NUREG/CR-0130. These values were adjusted for mass and decay period.

35. It is assumed that all Class A LLRW currently being accumulated on site will be removed to a low-level waste processing and/or disposal facility prior to the end of the operating life of the

Document No. 164086-DCE-01

Rev. 1

36. The spent fuel shipping schedules and transfer to dry storage costs for each scenario were developed by FPL and furnished to Energy*Solutions*.

plant. The disposition of such materials is assumed not to be a decommissioning cost.

- 37. St. Lucie currently has an existing ISFSI on site. Construction costs for any expansion of the ISFSI that may be required has not been included, but demolition has been included in the estimate and has been split between both units.
- 38. Energy*Solutions* has assumed that the 10 CFR Part 50 license for Units 1 and 2 will be terminated after DOE has taken possession of the spent fuel.
- 39. Emergency Preparedness fees were supplied by FPL. Per direction of FPL emergency preparedness fees are assumed to cease once all spent fuel is removed from the spent fuel pool.
- 40. NEIL and ANI insurance premiums are included based on the rate schedule provided by FPL. Insurance premiums have been reduced when major milestones have been completed.
- 41. Units 1 and 2 property taxes are included based on the rate schedule provided by FPL.
- 42. Energy costs have been estimated based on previous experience of similar projects utilizing energy rates provided by FPL.
- 43. Energy*Solutions* has included NRC inspection fees during each decommissioning period based on the type and level of activities being performed.
- 44. Energy Solutions has assumed that licensing fees will be reduced after shutdown.
- 45. Site operating expenses expected to be incurred during Unit 1 SAFSTOR and decommissioning are included in the estimate. These costs include materials and services, supplies, utilities, telecommunications equipment, non-process computers, and tools and equipment.
- 46. Utility staff and security positions, and average direct-burdened salary data were supplied by FPL.
- 47. Severance costs for Reductions-in-Force immediately following Unit 1 and Unit 2 permanently ceasing operations are excluded from the estimate.
- 48. Craft labor rates used a combination of the labor rates provided by FPL and 2019 RS Means rates escalated to 2020 costs.
- 49. The most recent NRC requirements for Security, Emergency Response, Fukushima, Cyber Security and any other regulatory changes have been included.

- Document No. 164086-DCE-01 Rev. 1
- 50. Undistributed staffing costs, taxes, and fees in Periods 3 and 4 is split 93% for License Termination and 7% Site Restoration with exception licensing and NRC fees (100% License Termination).
- 51. Estimate assumes that security staff for Unit 1 prior to Unit 2 shutdown is for spent fuel transfer only. Overall site security to be covered by Unit 2 security. Period 1 Unit 2 security post-shutdown is assumed to cover site security as well as spent fuel transfer.
- 52. Institute of Nuclear Power Operations (INPO) and Electric Power Research Institute (EPRI) dues are not included in this estimate.

6.0 STUDY RESULTS

The study results for each of the DCE scenarios are presented in this section.

The cost estimate results are provided in Table 6-1 below. This table provides License Termination costs (corresponding to 10 CFR 50.75(c) requirements); Spent Fuel Management costs (corresponding to 10 CFR 50.54(bb) requirements), and Site Restoration costs, including activities such as clean building demolition and site grading etc.

Table 6-1

FPL St. Lucie Units 1 and 2 Decommissioning Cost Summary (thousands of 2020 dollars)										
Scenario	License Termination	Spent Fuel	Site Restoration	Total						
1	1,254,740	427,313	63,409	1,745,462						
2	1,319,504	473,029	62,101	1,854,633						

Summary schedule tables are shown for each scenario below. Detailed schedules for each scenario are provided in <u>Appendix B.</u>

Summary cost tables are shown for each scenario below. Detailed estimates for each scenario are provided in <u>Appendix C</u>.

Detailed staffing tables for each scenario are provided in Appendix D.

Summary waste quantities are shown for each scenario below. Waste estimates for each scenario are provided in Appendix E.

Detailed annual spending tables for each scenario are provided in Appendix F.

The following sections provide study results by scenario.

Document No. 164086-DCE-01

Document No. 164086-DCE-01

6.1 Scenario 1 - Unit 1 SAFSTOR, DECON both following Unit 2 Shutdown

Cost Summary

Table 6-2 below provides the cost estimate results for Scenario 1 organized by period and separated into Unit 1, Unit 2 and Total.

Table 6-2

FPL St. Lucie Units 1 and 2 Scenario 1 - Cost Summary by Period & Unit (thousands of 2020 dollars) Period Item Description Unit 1 Unit 2 **Total Cost** 136,894 Period 1 **SHUTDOWN & TRANSITION** 192,259 329,153 Period 2 129,823 SAFSTOR 129,823 1,013,135 Period 3 **DECOMMISSIONING & LICENSE TERMINATION** 520,827 492,308 Period 4 SITE RESTORATION 28,912 34,497 63,409 Period 5 DRY FUEL / GTCC STORAGE & TRANSFER 99,594 196,703 97,109 Period 6 ISFSI DECOMMISSIONING 7,351 5,887 13,238 923,401 822,060 **GRAND TOTAL** 1,745,462

Table 6-3 below provides the cost estimate results for Scenario 1 organized by period and separated by cost type.

Table 6-3

	FPL St. Lucie Units 1 and 2 Scenario 1 - Cost Summary by Period & Cost Type (thousands of 2020 dollars)												
Period	Item Description	Labor Cost	Materials & Equipment	Waste Transport & Disposal	Other Direct Cost (ODC)	Contingency	Total Cost						
Period 1	SHUTDOWN & TRANSITION	223,517	33,539	-	28,541	43,557	329,153						
Period 2	SAFSTOR	57,755	42,112	-	14,633	15,325	129,823						
Period 3	DECOMMISSIONING & LICENSE TERMINATION	306,657	125,599	380,942	45,061	154,875	1,013,135						
Period 4	SITE RESTORATION	37,259	11,946	278	5,655	8,271	63,409						
Period 5	DRY FUEL / GTCC STORAGE & TRANSFER	98,987	3,000	32,896	36,006	25,813	196,703						
Period 6	ISFSI DECOMMISSIONING	9,255	1,886	-	371	1,727	13,238						
	GRAND TOTAL	733,429	218,081	414,116	130,267	249,568	1,745,462						

A detailed estimate is provided in Appendix C.

Schedule Summary

Table 6-4 below provides a schedule summary for Scenario 1 based on a DECON scenario with Unit 1 Shutdown March 1, 2036 and Unit 2 Shutdown April 6, 2043.

Table 6-4

	FPL DCE-01 St. Lucie Units 1 and 2 Scenario 1 Schedule Summary
Year	Item
2033	DOE starts accepting fuel from spent fuel pool
2036	Unit 1 Shutdown
2040	Unit 1 SAFSTOR period begins
2043	Unit 2 Shutdown
2046	Unit 1 Fuel Pool Empty
2046	Unit 2 Fuel Pool Empty
2046	Unit 1 SAFSTOR period ends
2047	Start Demolition
2053	Decommissioning and Site Restoration Complete
2071	ISFSI Empty
2073	ISFSI Decommissioning and Site Restoration Complete

A detailed schedule is provided in Appendix B.

Project Staffing

Table 6-5 below provides project staffing for Scenario 1 organized by period and staff group.

Table 6-5

Period 1 - Shutdown & Transition	2035	2036	2037	2038	2039	2040	2041	2042	2043	2044	2045	2046
Administration		8	8	7	2				12	12	7	4
Engineering		40	40	20	12				40	40	20	8
Health Physics/Rad Protection		30	30	24	6				30	30	24	20
Management		5	5	5	2				5	5	5	3
Maintenance & Operations		70	70	40	12				70	60	40	20
Quality Assurance		3	3	2	2				3	3	2	1
Utility Staff	-	156	156	98	36	-	-	-	160	150	98	56
General Contractor Staff	-	-	-		•	-	-	•	•		•	-

Period 2 - SAFSTOR	2038	2039	2040	2041	2042	2043	2044	2045	2046	2047
Administration		1	2	2	2	2	2	2	2	
Engineering		3	6	6	6	6	6	6	6	
Health Physics/Rad Protection		3	6	6	6	6	6	6	6	
Management		1	2	2	2	2	2	2	2	
Maintenance & Operations		3	6	6	6	6	6	6	6	
Quality Assurance		1	2	2	2	2	2	2	2	
Utility Staff	-	12	24	24	24	24	24	24	24	•
General Contractor Staff	-	-	-	-	-	-	•	-	-	-

Period 3 & 4 - License Term & Site Restoration	2044	2045	2046	2047	2048	2049	2050	2051	2052	2053	2054
Administration		4	4	10	12	12	12	12	7	2	
Engineering		4	6	16	20	20	20	20	7	2	
Health Physics/Rad Protection			4	8	24	24	24	24	16	4	
Management		1	1	4	5	5	4	4	4	2	
Maintenance & Operations				10	24	24	20	20	8	2	
Quality Assurance		1	1	2	3	3	2	2	2	1	
Utility Staff	-	10	16	50	88	88	82	82	44	13	-
Project Management		2	4	6	10	10	10	10	8	4	
Engineering		4	6	6	12	12	10	10	7	2	
Health Physics/Rad Protection			4	8	16	16	16	16	12	6	
Administration		2	3	6	12	12	12	12	8	4	
Maintenance & Operations					-	-	-	-	-	-	
Quality Assurance		1	1	2	4	4	4	4	3	2	
Waste Management			1	2	12	12	12	12	12	4	
General Contractor Staff	-	9	19	30	66	66	64	64	50	22	-

Period 5 - Dry Fuel / GTCC Storage & Transfer	2045	2046	2047	2048	2049	2050	2051	2052 / 2069	2070	2071	2072	2073
Administration												
Engineering		1	1	1	1	1	1	1	1	1	1	
Health Physics/Rad Protection			1	1	1	1	1	1	1	1	1	
Management												
Maintenance & Operations			2	2	2	2	2	2	2	2	1	
Quality Assurance			1	1	1	1	1	1	1	1	1	
Utility Staff	-	1	5	5	5	5	5	5	5	5	4	-
General Contractor Staff	-	-		-	-	-		-	-			-

Period 6 - ISFSI Decommissioning	2065	2066	2067	2068	2069	2070	2071	2072	2073
Administration									
Engineering									1
Health Physics/Rad Protection									1
Management									1
Maintenance & Operations									
Quality Assurance									1
Utility Staff	-	-	-	-	-	-	-	-	4
Project Management								1	1
Engineering								1	1
Health Physics/Rad Protection									1
Administration									1
Maintenance & Operations									
Quality Assurance								1	1
Waste Management								1	1
General Contractor Staff	-	-	-	-	-	-	-	4	6

Detailed staffing tables for each scenario are provided in Appendix D.

Waste Disposal Volumes

Waste disposal is a significant element of the decommissioning project. The estimated waste disposal quantities for Scenario 1 are shown in cubic feet of waste as follows:

Class A	4,651,030
Class B/C	3,740
GTCC	5,772

Waste disposal volumes and costs, itemized by packaging, transportation, surcharges and disposal costs by waste class and facility, are provided in <u>Appendix E</u>.

6.2 Scenario 2 - SAFSTOR

Cost Summary

Table 6-6 below provides the cost estimate results for Scenario 2 organized by period and separated into Unit 1, Unit 2 and Total.

Table 6-6

FPL St. Lucie Units 1 and 2 Scenario 2 - Cost Summary by Period & Unit

(thousands of 2020 dollars)

	·				
Period	Item Description	Unit 1	Unit 2	Total Cost	
Period 1	SHUTDOWN & TRANSITION	138,072	198,972	337,044	
Period 2	SAFSTOR	236,728	106,813	343,541	
Period 3	DECOMMISSIONING & LICENSE TERMINATION	480,446	457,938	938,384	
Period 4	SITE RESTORATION	28,188	33,913	62,101	
Period 5	DRY FUEL / GTCC STORAGE & TRANSFER	81,576	78,423	159,999	
Period 6	ISFSI DECOMMISSIONING	7,514	6,050	13,564	
	GRAND TOTAL	972,525	882,108	1,854,633	

Table 6-7 below provides the cost estimate results for Scenario 2 organized by period and separated by cost type.

Table 6-7

	Scenario 2 - Co	•	y Period & Co	st Type			
Period	(th	Labor Cost	20 dollars) Materials & Equipment	Waste Transport & Disposal	Other Direct Cost (ODC)	Contingency	Total Cost
Period 1	SHUTDOWN & TRANSITION	229,990	33,926	-	28,541	44,587	337,044
Period 2	SAFSTOR	131,511	63,668	-	113,609	34,754	343,541
Period 3	DECOMMISSIONING & LICENSE TERMINATION	303,785	124,405	331,831	35,374	142,990	938,384
Period 4	SITE RESTORATION	36,781	12,044	259	4,916	8,100	62,101
Period 5	DRY FUEL / GTCC STORAGE & TRANSFER	99,109	3,000	32,896	3,968	21,026	159,999
Period 6	ISFSI DECOMMISSIONING	9,255	1,886	•	654	1,769	13,564
_	GRAND TOTAL	810,431	238,930	364,986	187,062	253,225	1,854,633

A detailed estimate is provided in Appendix C.

Document No. 164086-DCE-01

Schedule Summary

Table 6-8 below provides a schedule summary for Scenario 2 based on a SAFSTOR scenario with Unit 1 Shutdown March 1, 2036 and Unit 2 Shutdown April 6, 2043.

Table 6-8

	FPL DCE-01 St. Lucie Units 1 and 2 Scenario 2 Schedule Summary
Year	Item
2033	DOE starts accepting fuel from spent fuel pool
2036	Unit 1 Shutdown
2040	Unit 1 SAFSTOR period begins
2043	Unit 2 Shutdown
2046	Unit 1 Fuel Pool Empty
2046	Unit 2 Fuel Pool Empty
2047	Unit 2 SAFSTOR period begins
2071	ISFSI Empty
2089	SAFSTOR Period ends
2090	Start Demolition
2096	Decommissioning and Site Restoration Complete
2097	ISFSI Decommissioning and Site Restoration Complete

A detailed schedule is provided in Appendix B.

Document No. 164086-DCE-01

Project Staffing

Table 6-9 below provides project staffing for Scenario 2 organized by period and staff group.

Table 6-9

Period 1 - Shutdown & Transition	2035	2036	2037	2038	2039	2040	2041	2042	2043	2044	2045	2046	2047
Administration		8	8	7	2				12	12	7	4	
Engineering		40	40	20	12				40	40	20	8	
Health Physics/Rad Protection		30	30	24	6				30	30	24	20	
Management		5	5	5	2				5	5	5	3	
Maintenance & Operations		70	70	40	12				70	60	40	20	
Quality Assurance		3	3	2	2				3	3	2	1	
Utility Staff	-	156	156	98	36			-	160	150	98	56	-
													_
General Contractor Staff	-	-	-	-	-	-	-	-	-	-	-	-	-

Period 2 - SAFSTOR	2038	2039	2040	2041	2042	2043	2044	2045	2046	2047	2048	2049	2050 / 2086	2087	2088	2089
Administration		1	2	2	2	2	2	2	2	1	1	1	1	1	1	1
Engineering		3	6	6	6	6	6	6	6	1	1	1	1	1	1	1
Health Physics/Rad Protection		3	6	6	6	6	6	6	6	1	1	1	1	1	1	1
Management		1	2	2	2	2	2	2	2							
Maintenance & Operations		3	6	6	6	6	6	6	6	3	3	3	3	3	3	3
Quality Assurance		1	2	2	2	2	2	2	2							
Utility Staff	-	12	24	24	24	24	24	24	24	6	6	6	6	6	6	6
General Contractor Staff	-	-	-	-	-	-	-	-	-	-	-		-			-

Period 3 & 4 - License Term & Site Restoration	2087	2088	2089	2090	2091	2092	2093	2094	2095	2096	2097
Administration		4	4	10	12	12	12	12	7	2	
Engineering		4	6	16	20	20	20	20	7	2	
Health Physics/Rad Protection			4	8	24	24	24	24	16	4	
Management		1	1	4	5	5	4	4	4	2	
Maintenance & Operations				10	24	24	20	20	8	2	
Quality Assurance		1	1	2	3	3	2	2	2	1	
Utility Staff	-	10	16	50	88	88	82	82	44	13	-
Project Management		2	4	6	10	10	10	10	8	4	
Engineering		4	6	6	12	12	10	10	7	2	
Health Physics/Rad Protection			4	8	16	16	16	16	12	6	
Administration		2	3	6	12	12	12	12	8	4	
Maintenance & Operations					-	-	-	-	-	-	
Quality Assurance		1	1	2	4	4	4	4	3	2	
Waste Management			1	2	12	12	12	12	12	4	
General Contractor Staff	-	9	19	30	66	66	64	64	50	22	-

Period 5 - Dry Fuel / GTCC Storage & Transfer	2045	2046	2047	2048	2049	2050 / 2069	2069	2070	2071	2072	2073
Administration											
Engineering		1	1	1	1	1	1	1	1	1	
Health Physics/Rad Protection			1	1	1	1	1	1	1	1	
Management											
Maintenance & Operations			2	2	2	2	2	2	2	1	
Quality Assurance			1	1	1	1	1	1	1	1	
Utility Staff	-	1	5	5	5	5	5	5	5	4	٠
General Contractor Staff	-	-	-	-	-	-	-	-	-	-	-

Period 6 - ISFSI Decommissioning	2090	2091	2092	2093	2094	2095	2096	2097	2098
Administration									
Engineering								1	
Health Physics/Rad Protection								1	
Management								1	
Maintenance & Operations									
Quality Assurance								1	
Utility Staff	-	-	-	-	-	-	-	4	
Project Management							1	1	
Engineering							1	1	
Health Physics/Rad Protection								1	
Administration								1	
Maintenance & Operations									
Quality Assurance							1	1	
Waste Management							1	1	
General Contractor Staff	-	-	-	-	-	-	4	6	-

Detailed staffing tables for each scenario are provided in Appendix D.

Waste Disposal Volumes

Waste disposal is a significant element of the decommissioning project. The estimated waste disposal quantities for Scenario 2 are shown in cubic feet of waste as follows:

Class A	4,133,459
Class B/C	2,288
GTCC	5,772

Waste disposal volumes and costs, itemized by packaging, transportation, surcharges and disposal costs by waste class and facility, are provided in $\underline{\mathsf{Appendix}}\,\mathsf{E}.$

7.0 REFERENCES

- 1. Atomic Industrial Forum, Inc., "Guidelines for Producing Commercial Nuclear Power Plant Decommissioning Cost Estimates," AIF/NESP-036, May 1986.
- 2. U.S. Nuclear Regulatory Commission, "Standard Format and Content of Decommissioning Cost Estimates for Nuclear Power Reactors," Regulatory Guide 1.202, February 2005.
- 3. U.S. Nuclear Regulatory Commission, "Domestic Licensing of Production and Utilization Facilities," 10 CFR Part 50, 2008.
- 4. Federal Register, Vol. 4, "Standard Contract for Disposal of Spent Nuclear Fuel and/or High-Level Radioactive Waste," NRC 10 CFR Part 961 (DOE), January 1, 1999.
- 5. U.S. Department of Energy, "Strategy for the Management and Disposal of Used Nuclear Fuel and High-Level Radioactive Waste," January 2013.
- 6. U.S. Department of Energy, "Acceptance Priority Ranking & Annual Capacity Report," DOE/RW-0567, July 2004.
- 7. U.S. Nuclear Regulatory Commission, "Technology, Safety and Costs of Decommissioning a Reference Pressurized Water Reactor Power Station," NUREG/CR-0130, June 1980. This original NUREG has been updated by NUREG/CR-5884 "Revised Analyses of Decommissioning for the Reference Pressurized Water Reactor Power Station."
- 8. U.S. Nuclear Regulatory Commission, "Technology, Safety and Costs of Decommissioning a Reference Boiling Water Reactor Power Station," NUREG/CR-0672, June 1980. This original NUREG has been updated by NUREG/CR-6174 "Revised Analyses of Decommissioning for the Reference Boiling Water Reactor Power Station."
- 9. Life-of-Plant Disposal Agreement, between Energy Solutions, LLC and FPL, dated January 1, 2007.
- 10. U.S. Nuclear Regulatory Commission, "Multi-Agency Radiation Survey and Site Investigation Manual (MARSSIM)," NUREG-1575, Rev. 1, August 2000.
- 11. U.S. Department of Energy, "Cost Estimating Guide," DOE G 430.1-1, March 1997.

Document No. 164086-DCE-01

APPENDIX A FPL - ST. LUCIE - UNITS 1 & 2 Plant Structures and Systems

St. Lucie -	Primary Plant Structures
Unit 1	Unit 2
Reactor	Reactor
Intake & CWS	Intake & CWS
Primary Water Tank & Pump	Primary Water Tank & Pump
Auxiliary Building	Auxiliary Building
Refueling Water Storage Tank	Steam Generator Blowdown
Turbine & Turbine Pedestal	Turbine & Turbine Pedestal
Fuel Handling Building	Fuel Handling Building
Misc Structures	Misc. Structures

St. Lucie - Pri	imary Plant Systems
Unit 1	Unit 2
Air Evacuation	Air Evacuation
Auxiliary Steam	Auxiliary Steam
Bulk Gas Supply	Bulk Gas Supply
Chemical & Volume Control	Chemical & Volume Control
Chemical Feed	Chemical Feed
Circulating & Intake Cooling Water	Circulating & Intake Cooling Water
Component Cooling	Component Cooling
Condensate	Condensate
Condensate Polishing	
Condensate Recovery	Condensate Recovery
Condenser Tube Cleaning	Condenser Tube Cleaning
Containment Spray & Refueling Water	Containment Spray & Refueling Water
Demin Makeup Water	Demin Makeup Water
Domestic - Makeup - Service Water	Domestic - Makeup - Service Water
Emergency Diesel Generator	Emergency Diesel Generator
Extraction Steam	Extraction Steam
Feedwater	Feedwater
Fire Protection	Fire Protection
Fuel Pool	Fuel Pool
HVAC	HVAC
Heater Drain & Vent	Heater Drain & Vent
Main Steam	Main Steam
Neutralization Basin Recirc	
Primary Water	Primary Water
RCP Oil	RCP Oil
Radiation Monitoring	Radiation Monitoring
Reactor Coolant	Reactor Coolant
Safety Injection	Safety Injection
Sampling	Sampling
Secondary Side Wet Layup	Secondary Side Wet Layup
Service & Instrument Air	Service & Instrument Air
SG Blowdown Cooling	SG Blowdown Cooling
	SG Blowdown Treatment Facility
	Sodium Hypochlorite
Turbine Cooling Water	Turbine Cooling Water
Turbine Lube Oil & Diesel Oil	Turbine Lube Oil & Diesel Oil
Waste Management	Waste Management
Water Treatment	Water Treatment

Appendix B-1 Florida Power and Light St. Lucie Units 1 & 2 Scenario 1 - Unit 1 SAFSTOR, DECON both following Unit 2 Shutdown 2030 | 2031 | 2032 | 2033 | 2034 | 2035 | 2036 | 2037 | 2038 | 2036 | 2037 | 2038 | 2038 | 2038 | 2039 | 2040 | 2041 | 2042 | 2043 | 2044 | 2045 | 2048 | 2045 | 2048 | 2045 | 2048 | 2049 | 2057 | 2058 | 2059 | 2053 | 2054 | 2055 | 2055 | 2059 | 2059 | 2060 | 2061 | 2062 | 2063 | 2064 | 2065 | 2066 | 2067 | 2068 | 2069 | 2069 | 2070 | 2071 | 2072 | 2073 | 2074 | 2075 | 2074 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 2075 | 207 Description MILESTONES Unit 1 Shutdown (2036) DOE Starts Accepting Fuel (2033) Unit 1 Zirc Fire Period Ends (2037) Unit 2 Shutdown (2043) Unit 2 Zirc Fire Period Ends (2044) Unit 1 Fuel Pool Empty (2046) Unit 2 Fuel Pool Empty (2046) Decommissioning & Site Restoration Complete (2053) ISFSI Empty (2071) ISFSI Decommissioning & Site Restoration Complete (2073) **PERIOD 1 - SHUTDOWN & TRANSITION** 1a. Planning Prior to Shutdown (by Plant Operations) 1b. Unit 1 Post Shutdown Planning & Engineering 1c. Unit 1 Post Shutdown Deactivation & Modifications 1d. Unit 1 Wet Fuel Transfer to DOE prior to SAFSTOR 1e. Unit 2 Post Shutdown Planning & Engineering 1f. Unit 2 Post Shutdown Deactivation & Modifications 1g Unit 2 Wet Fuel Transfer to DOE prior to DECON 1h Unit 2 Wet Fuel Transfer to ISFSI prior to DECON 1i. Undistributed Costs for Shutdown & Transition PERIOD 2 - UNIT 1 SAFSTOR 2a. Wet Fuel Transfer to DOE during SAFSTOR 2b. Wet Fuel Transfer to ISFSI during SAFSTOR 2c. Dormancy during Wet Fuel Transfer to DOE & ISFSI PERIOD 3 - DECOMMISSIONING & LICENSE TERMINATION 3a. Decommissioning Planning 3b. Decommissioning Transition & Preparations 3c. Reactor Vessel Removal 3d. Large Component Removal 3e. Plant Decontamination & Interior Rad Demolition 3f. Rad Building Demolition 3g. License Termination Activities 3h. Undistributed Costs for Decommissioning & License Termination PERIOD 4 - SITE RESTORATION 4a. Clean Building & Site Demolition 4b. Site Restoration 4c. Undistributed Costs for Site Restoration PERIOD 5 - DRY FUEL / GTCC STORAGE & TRANSFER 5a. Dry Fuel Transfer to DOE during and after DECON 5b. GTCC Waste Disposition 5c. Undistributed Costs for Dry Fuel / GTCC Storage & Transfer PERIOD 6 - ISFSI DECOMMISSIONING 6a. ISFSI D&D Planning & Preparations

Assumed by plant Operations

Included in estimate

Undistributed costs Included in estimate

6b. ISFSI and Support Structure Clean Demolition

6d. Undistributed Costs for ISFSI Decommissioning

6c. ISFSI Final Status Surveys

Florida Power and Light St. Lucie Units 1 & 2 Scenario 2 - SAFSTOR

Scenario 2 - SAFSTOR	2022	2024 202	2 2222	2021 55	25 22-		2022	2020	040 22	44 25	42 22.	2011	20.55	2046 20:-	20.00	2040 2055	207	2052	2052 25	4 225-	2056	2057 25-	0 2055	2000 -	061 25	-2 225	2 2000	2007	2000	C7 22	co 2000	2075	2074 -	072 25-	72 2075	207
Description	2030 2	2031 203	2033	2034 20	35 203	ь 2037	2038	2039 2	U4U 20	41 204	42 2043	2044	2045	2046 2047	2048	2049 2050	2051	2052 2	2053 20	4 2055	2056 2	2057 205	8 2059	2060 2	J61 206	2063	2064	2065 2	U66 206	57 206	אנ 2069	2070	2071 20	J/2 207	3 2074	2075
MILESTONES																									4				4	4		\blacksquare	4	4		
Unit 1 Shutdown (2036)	+				-	1		_	_		-								_		\bot	_		\vdash	+	-	++		+	\bot	+	\dashv	\dashv	+	+	
DOE Starts Accepting Fuel (2033)	++		7		\perp	_			_	_		$\vdash \vdash$								-	\vdash			$\vdash \vdash$	+		\longmapsto		+	\bot	+	\dashv	\dashv	+	+	_
Unit 1 Zirc Fire Period Ends (2037)	\vdash				_	•	1																		+		₩		_		\perp		_	\bot	\bot	
Unit 1 Fuel Pool Empty (2046)														•											\bot		\sqcup			4	\perp	$\vdash \downarrow$			$\perp \perp \downarrow$	
Unit 2 Shutdown (2043)											•																Ш				$\perp \perp \downarrow$	\sqcup			$\perp \perp \downarrow$	
Unit 2 Zirc Fire Period Ends (2044)												•															\sqcup				$\perp \perp \downarrow$	$\sqcup \downarrow$		\perp	\bot	
Unit 2 Fuel Pool Empty (2046)														•													\sqcup				$\perp \perp \downarrow$	$\sqcup \downarrow$		\perp	\bot	
ISFSI Empty (2071)																											Ш			╙	\perp	$\sqcup \downarrow$	•		Ш	
SAFSTOR Period Ends (2089)																									\perp		\sqcup				\perp	Ш		\bot	$\perp \downarrow \downarrow$	
Decommissioning & Site Restoration Complete (2096)																											Ш			┵	\perp	$ldsymbol{\sqcup}$			$oldsymbol{ol}}}}}}}}}}}}}}}}}}$	
ISFSI Decommissioning & Site Restoration Complete (2097)																									\bot		Ш			\perp		Ш	\bot		Ш	
PERIOD 1 - SHUTDOWN & TRANSITION																																				
1a. Planning Prior to Shutdown (by Plant Operations)																																				
1b. Unit 1 Post Shutdown Planning & Engineering																																1				
1c. Unit 1 Post Shutdown Deactivation & Modifications																																┌ॅ				
1d. Unit 1 Wet Fuel Transfer to DOE prior to SAFSTOR																																				
1e. Unit 2 Post Shutdown Planning & Engineering																														\top		\Box				
1f. Unit 2 Post Shutdown Deactivation & Modifications																														\top		\Box				
1g Unit 2 Wet Fuel Transfer to DOE prior to DECON							1 1																													
1h Unit 2 Wet Fuel Transfer to ISFSI prior to DECON																																i				
1i. Undistributed Costs for Shutdown & Transition																																i				
PERIOD 2 - UNIT 2 SAFSTOR																																				
2a. Unit 1 Wet Fuel Transfer to DOE during SAFSTOR																																П				
2b. Unit 1 Wet Fuel Transfer to ISFSI during SAFSTOR																																				
2c. Unit 1 Dormancy during Dry Fuel Storage																														丰						
2d. Unit 2 Dormancy during Dry Fuel Storage																									Ħ		Ħ	4	igspace =							
2e. Dormancy only																																1		4	#	_
PERIOD 3 - DECOMMISSIONING & LICENSE TERMINATION																																				
3a. Decommissioning Planning																																П			\Box	_
3b. Decommissioning Transition & Preparations																																1				
3c. Reactor Vessel Removal																																1				
3d. Large Component Removal																											T			\top	1	i			1	
3e. Plant Decontamination & Interior Rad Demolition						1																			\top				\top	\top	1 1	一	=	\top	$\dagger \dagger$	
3f. Rad Building Demolition						1														1					\top				\top	\top	1 1	$_{i}$	=	\top	$\dagger \dagger$	
3g. License Termination Activities					+	T			=																\top		+	-	\top	+	+ +	\dashv	-	\top	\dagger	
3h. Undistributed Costs for Decommissioning & License Termination					+	T			=																\top		+	-	\top	+	+ +	\dashv	-	\top	\dagger	
PERIOD 4 - SITE RESTORATION																														巾						
4a. Clean Building & Site Demolition																									\top					T						
4b. Site Restoration	+	_				1			\dashv		1					+			\dashv	1	f			++	+	1	+	=	+	+	++	一	+	+	+	
4c. Undistributed Costs for Site Restoration	+	_				1			\dashv		1					+			\dashv	1	f			++	+	1	+	=	+	+	++	一	+	+	+	
PERIOD 5 - DRY FUEL / GTCC STORAGE & TRANSFER																																				
5a. Dry Fuel Transfer to DOE during SAFSTOR																														+						
5c. GTCC Waste Disposition	++				+	+		\dashv	=	\dashv		\vdash													Ŧ			\top	T	Ŧ	1	$\overline{}$	\dashv	+	++	
5d. Undistributed Costs for Dry Fuel / GTCC Storage & Transfer	++				+	+		\dashv	=	\dashv		\vdash							\pm			+	+	\vdash	士			#	士	士			_	+	++	
PERIOD 6 - ISFSI DECOMMISSIONING																														T			7			
6a. ISFSI D&D Planning & Preparations																									+			7	#	+			#	#		
6b. ISFSI and Support Structure Clean Demolition	+ +		-		+				\dashv		+									-	1 1	-			+	-	+	-+	+	+	+	\dashv	+	+	+	
6c. ISFSI Final Status Surveys																									土				士	士		一		士		
6d. Undistributed Costs for ISFSI Decommissioning																																┌Т				
			-			•		-	•	•	-			•		•		-	•	-						•										_

Assumed by plant Operations
Included in estimate
Undistributed costs Included in estimate

Florida Power and Light St. Lucie Units 1 & 2 Scenario 2 - SAFSTOR

Scenario 2 - SAFSTOR																								
Description	2076	2077	2078	2079	2080	2081	2082	2083	2084	2085	2086	2087	2088	2089	2090	2091	2092	2093	2094	2095	2096	2097 2	.098	2099
MILESTONES																								
Unit 1 Shutdown (2036)																								
DOE Starts Accepting Fuel (2033)																								
Unit 1 Zirc Fire Period Ends (2037)																								
Unit 1 Fuel Pool Empty (2046)																								
Unit 2 Shutdown (2043)																								
Unit 2 Zirc Fire Period Ends (2044)																								
Unit 2 Fuel Pool Empty (2046)																								
ISFSI Empty (2071)																								
SAFSTOR Period Ends (2089)																								
Decommissioning & Site Restoration Complete (2096)																								
ISFSI Decommissioning & Site Restoration Complete (2097)																						•		
PERIOD 1 - SHUTDOWN & TRANSITION																								
1a. Planning Prior to Shutdown (by Plant Operations)																							\exists	\neg
1b. Unit 1 Post Shutdown Planning & Engineering																						\exists	寸	\exists
1c. Unit 1 Post Shutdown Deactivation & Modifications																						\exists	寸	コ
1d. Unit 1 Wet Fuel Transfer to DOE prior to SAFSTOR																						\top	寸	ヿ
1e. Unit 2 Post Shutdown Planning & Engineering																					ı	\top	寸	\exists
1f. Unit 2 Post Shutdown Deactivation & Modifications																					ı	\top	寸	\exists
1g Unit 2 Wet Fuel Transfer to DOE prior to DECON																						\top		
1h Unit 2 Wet Fuel Transfer to ISFSI prior to DECON																								_
1i. Undistributed Costs for Shutdown & Transition																								_
PERIOD 2 - UNIT 2 SAFSTOR																								
2a. Unit 1 Wet Fuel Transfer to DOE during SAFSTOR																							ヿ	コ
2b. Unit 1 Wet Fuel Transfer to ISFSI during SAFSTOR																						\top		
2c. Unit 1 Dormancy during Dry Fuel Storage																								
2d. Unit 2 Dormancy during Dry Fuel Storage																								
2e. Dormancy only																								
PERIOD 3 - DECOMMISSIONING & LICENSE TERMINATION																								
3a. Decommissioning Planning																								
3b. Decommissioning Transition & Preparations																								\neg
3c. Reactor Vessel Removal																						-	_	\neg
3d. Large Component Removal																T						-	_	\neg
3e. Plant Decontamination & Interior Rad Demolition																						_	_	\neg
3f. Rad Building Demolition																								\neg
3g. License Termination Activities																						_	_	\neg
3h. Undistributed Costs for Decommissioning & License Termination																						_	_	\neg
PERIOD 4 - SITE RESTORATION																								
4a. Clean Building & Site Demolition																								_
4b. Site Restoration																						\dashv	-	-
4c. Undistributed Costs for Site Restoration																						\dashv	-	-
PERIOD 5 - DRY FUEL / GTCC STORAGE & TRANSFER																								
5a. Dry Fuel Transfer to DOE during SAFSTOR																								
5c. GTCC Waste Disposition																						\dashv	\dashv	\dashv
5d. Undistributed Costs for Dry Fuel / GTCC Storage & Transfer																						\dashv	\dashv	\dashv
PERIOD 6 - ISFSI DECOMMISSIONING																								
6a. ISFSI D&D Planning & Preparations																						7	7	
6b. ISFSI and Support Structure Clean Demolition																						\dashv	\dashv	\dashv
6c. ISFSI Final Status Surveys																							ightharpoonup	
6d. Undistributed Costs for ISFSI Decommissioning																					i		ightharpoonup	
Assumed by plant Operations																							1	

Assumed by plant Operations

Included in estimate

Undistributed costs Included in estimate

Florida Power and Light

St. Lucie Unit 1

Scenario 1 - Unit 1 SAFSTOR, DECON both following Unit 2 Shutdown

Period	Item Number	Item Description	Labor Cost	Materials & Equipment	Waste Transportation & Disposal	Other Direct Cost (ODC)	Contingency	Total Cost (Estimated)	License Termination	Spent Fuel Management	Site Restoration
1a Total	Plannin	g Prior to Shutdown (by Plant Operations)	-	-	-	-	-	-	-	-	-
	1b.1	Admin Activities in Preparation for SAFSTOR - Unit 1	2,397	74	-	-	371	2,841	2,841	-	-
	1b.2	Prepare PSDAR and License Documents - Unit 1	382	12	-	-	59	453	453	-	-
	1b.3	Engineering Activities in Preparation for SAFSTOR - Unit 1	1,007	31	-	-	156	1,194	1,194	-	
1b Total	Unit 1 P	ost Shutdown Planning & Engineering	3,786	117	-	-	585	4,489	4,489	-	
	1c.1	Defuel Reactor Unit 1 (by Plant Operations)	_	_	_	_	_	-	_	_	
	1c.2	Fuel Sampling & Inspections (by Plant Operations)	_	_	_	_	_	_	_	_	
	1c.3	Spent Fuel Pool System Modifications - Unit 1	10,303	1,818	_	_	1,818	13,939	_	13,939	
	1c.4	Implement Cold & Dark - Unit 1	3,508	630		_	621	4,759		-	
	1c.5	Flush and Drain Non-Essential Systems - Unit 1	515	5		_	78	598		_	
	1c.6	Perform Pre-SAFSTOR Baseline Radiation Survey - Unit 1	1,264	39		_	195	1,499		824	
1c Total		Post Shutdown Deactivation & Modifications	15,589	2,493		-	2,712	20,795		14,763	
							·	·			
	1d.1	Provide Transfer Casks (supplied by DOE)	-	-	-	-	-	-	-	-	
	1d.2	Procure Spent Fuel Loading & Transfer Equipment	-	2,184	-	-	328	2,512	-	2,512	-
	1d.3	Procedures & Dry Runs	500	-	-	250	113	863	-	863	
	1d.4	Remove (224) Fuel Assemblies from Pool & Load DOE Casks	1,120	280	-	-	280	1,680	-	1,680	
	1d.5	Dry, Close & Inspect (7) DOE supplied Casks	560	140	-	-	140	840	-	840	
	1d.6	Load Out (7) Casks to DOE Transport	560	140	-	-	140	840	-	840	
	1d.7	Spent Fuel Transportation & Disposal (by DOE)	-	-	-	-	-	-	-	-	
1d Total	Unit 1 V	Vet Fuel Transfer to DOE prior to SAFSTOR	2,740	2,744	-	250	1,000	6,734	-	6,734	
1e Total	Unit 2 P	ost Shutdown Planning & Engineering	-	-	-	-	-	-	-	-	
1f Total	Unit 2 S	hutdown Preparations & Deactivation	-	-	-	-	-	-	-	-	
1g Total	Unit 2 V	Vet Fuel Transfer to DOE prior to DECON	-	-	-	-	-	-	-	-	•
1h Total	Unit 2 V	Vet Fuel Transfer to ISFSI prior to DECON	-	-	-	-	-	-	-	-	·
	1i.1	Utility Staff	64,707	-	-	-	9,706	74,414	59,531	14,883	
	1i.2	Security Guard Force	6,442	-	-	-	966	7,408	2,223	5,186	
	1i.3	General Contractor Staff	-	-	-	-	-	-	-	-	
	1i.4	Property Taxes	-	-	-	177	27	203	163	41	
	1i.5	Insurance	-	-	-	6,848	1,027	7,875	6,300	1,575	

Florida Power and Light

St. Lucie Unit 1

Scenario 1 - Unit 1 SAFSTOR, DECON both following Unit 2 Shutdown

		(triousarius or zozo dollars)									
Period	Item Number	Item Description	Labor Cost	Materials & Equipment	Waste Transportation & Disposal	Other Direct Cost (ODC)	Contingency	Total Cost (Estimated)	License Termination	Spent Fuel Management	Site Restoration
	1i.6	Corporate Support	1,325	-	-	-	199	1,524	457	1,067	-
	1i.7	Utility Staff HP Supplies	-	883	-	-	132	1,016	305	711	-
	1i.8	NRC Inspection Fee	-	-	-	2,224	334	2,558	2,558	-	-
	1i.9	Licensing Fees	-	-	-	688	103	791	791	-	-
	1i.10	Materials and Services	-	1,945	-	-	292	2,237	671	1,566	-
	1i.11	Energy	-	-	-	1,097	165	1,262	1,010	252	-
	1i.12	EPRI Membership Fees	-	-	-	-	-	-	-	-	-
	1i.13	NEI Membership Fees	-	-	-	-	-	-	-	-	-
	1i.14	County Fees	-	-	-	2,049	307	2,356	1,885	471	-
	1i.15	FEMA Fees	-	-	-	1,079	162	1,241	993	248	-
	1i.16	INPO Membership Fees	-	-	-	-	-	-	-	-	-
	1i.17	ISFSI Operating Costs	-	422	-	-	63	485	-	485	-
	1i.18	Spent Fuel Maintenance	1,180	131	-	-	197	1,507	-	1,507	-
1i Total	Undistri	ibuted Costs for Shutdown & Transition	73,654	3,381	-	14,162	13,680	104,877	76,885	27,992	-
Period 1	Total	SHUTDOWN & TRANSITION	95,770	8,735	-	14,412	17,978	136,894	87,405	49,489	-
	2a.1	Provide Transfer Casks (supplied by DOE)	-	-	-	-	-	-	-	-	-
	2a.2	Procure Spent Fuel Loading & Transfer Equipment	-	-	-	-	-	-	-	-	-
	2a.3	Procedures & Dry Runs	-	-	-	-	-	-	-	-	-
	2a.4	Remove (320) Fuel Assemblies from Pool & Load Casks	1,600	400	-	-	400	2,400		2,400	-
	2a.5	Dry, Close & Inspect (10)	800	200	-	-	200	1,200	-	1,200	-
	2a.6	Load Out (10) Casks to Transport	800	200	-	-	200	1,200	-	1,200	-
2a Total	Wet Fue	el Transfer to DOE during SAFSTOR	3,200	800	-	-	800	4,800	-	4,800	-
	21.4	B : 1 T (C) (44)		26.402			5 420	44.600		44.600	
	2b.1	Provide Transfer Casks (41)	-	36,193	-	-	5,429	41,622	-	41,622	-
	2b.2	Procure Spent Fuel Loading & Transfer Equipment	-	-	-	160	-		-	-	-
	2b.3	Procedures & Dry Runs Remove (1313) Fuel Assemblies from Real & Load Casks	335	1 640	-	168	75 1 640	578 0.840		578	-
	2b.4	Remove (1312) Fuel Assemblies from Pool & Load Casks	6,560	1,640		-	1,640	9,840 4,920		9,840	-
	2b.5 2b.6	Dry, Close & Inspect (41)	3,280	820 820		-	820 820	4,920 4,920		4,920 4,920	-
2b Total		Load Out (41) Casks to Transport el Transfer to ISFSI during SAFSTOR	3,280			168	820 8,784				-
ZD TOTAL	wetrue	er fransier to ispsi dufflig sapsion	13,455	39,473	-	108	8,784	61,880	-	61,880	-
	2c.1	Utility Staff	26,298	_	_	_	2,630	28,928	13,017	15,910	_
	2c.1 2c.2	Security Guard Force	11,274	-	<u>-</u>	-	1,127	12,401	13,017	12,401	_
	2c.2 2c.3	General Contractor Staff	11,274	-	<u>-</u>	-	1,12/ _	12,401	_	12,401	_
	2c.3 2c.4	Property Taxes	- -	-	<u>-</u>	221	22	243	109	134	-
	2c.4 2c.5	Insurance	-	-	-	8,560		9,416			-
	20.5	insurance	-	-	-	0,500	856	9,410	4,237	5,1/9	-

Florida Power and Light

St. Lucie Unit 1

Scenario 1 - Unit 1 SAFSTOR, DECON both following Unit 2 Shutdown

			(1104341143 01 2020 4011413)								
Period	Item Number	Item Description	Labor Cost	Materials & Equipment	Waste Transportation & Disposal	Other Direct Cost (ODC)	Contingency	Total Cost (Estimated)	License Termination	Spent Fuel Management	Site Restoration
	2c.6	Corporate Support	3,528	-	-	-	353	3,881	1,746	2,134	-
	2c.7	Utility Staff HP Supplies	-	165	-	-	17	182	82	100	-
	2c.8	NRC Inspection Fee	-	-	-	723	72	795	358	437	-
	2c.9	Licensing Fees	-	-	-	860	86	946	946	-	-
	2c.10	County Fees	-	-	-	2,561	256	2,817	1,268	1,549	-
	2c.11	FEMA Fees	-	-	-	1,349	135	1,483	668	816	-
	2c.12	EPRI Membership Fees	-	-	-	-	-	-	-	-	-
	2c.13	NEI Fees	-	-	-	-	-	-	-	-	-
	2c.14	INPO Membership Fees	-	-	-	-	-	-	-	-	-
	2c.15	Materials and Services	-	1,318	-	-	132	1,450	653	798	-
	2c.16	ISFSI Operating Costs	-	355	-	-	36	391	-	391	-
	2c.17	Energy	-	-	-	192	19	211	95	116	-
2c Total	Dormar	ncy during Wet Fuel Transfer to DOE & ISFSI	41,100	1,839	-	14,465	5,740	63,144	23,179	39,965	-
Period 2	Total	SAFSTOR	57,755	42,112	-	14,633	15,325	129,823	23,179	106,645	-
	3a.1	Decommissioning Planning and Design - Unit 1	1,493	45	-	-	231	1,769	1,769	-	-
	3a.2	Prepare Integrated Work Sequence and Schedule - Unit 1	161	5	-	-	25	191	191	-	-
	3a.3	Site Characterization - Unit 1	1,878	53	-	105	306	2,343	2,343	-	-
	3a.4	Prepare Decommissioning Activity Specifications - Unit 1	4,794	148	-	-	741	5,684	5,684	-	-
	3a.5	Prepare Detailed Work Procedures - Unit 1	4,213	130	-	-	652	4,995	4,995	-	-
	3a.6	Prepare License Termination Plan - Unit 1	965	-	-	667	245	1,877	1,877	-	-
	3a.7	Design Containment and Misc System Modifications - Unit 1	183	-	-	-	27	210	210	-	-
	3a.8	Purchase Dry Storage Modules for Unit 1 GTCC Waste	-	-	7,062	-	1,059	8,121	8,121	-	-
3a Total	Decom	missioning Planning	13,687	382	7,062	772	3,285	25,189	25,189	-	-
	3b.1	Mobilize Decommissioning General Contractor	-	-	-	1,300	195	1,495		-	-
	3b.2	Perform Asbestos Abatement of Pipe Insulation - Unit 1	3,371	104	-	-	869	4,344		-	-
	3b.3	Implement Temporary Power Upgrades - Unit 1	996	937	-	-	290	2,224		-	-
	3b.4	Construct Misc Building Modifications, In-Plant Laydown Areas	2,881	508		-	508	3,897		-	-
	3b.5	Modify Containment Access - Unit 1	2,137	377	-	<u>-</u>	377	2,892		-	-
	3b.6	Transportation Infrastructure Modifications	89	447	-	2,089	394	3,019		-	-
	3b.7	Procure Waste Handling & Processing Tents	-	-	-	1,739	261	2,000		-	-
3b Total	Decom	missioning Transition and Preparations	9,475	2,374	-	5,127	2,894	19,870	19,870	-	-
	2- 1	Decima and Dunasura Consist Faurinasa d		20.000			F 000	24.000	24.000		
	3c.1	Design and Procure Special Equipment	2 262	29,000	-	-	5,800	34,800		-	-
	3c.2	Test Special Cutting and Handling Equipment and Train Operators	2,263	-	-	70	467	2,800		-	-
	3c.3	Finalize Internals and Vessel Segmentation Details - Unit 1	525	-	-	-	105	630	630	-	-

Florida Power and Light

St. Lucie Unit 1

Scenario 1 - Unit 1 SAFSTOR, DECON both following Unit 2 Shutdown

				(110)	usarius or 2020 uoi	iidi 3 j					
Period	Item Number	Item Description	Labor Cost	Materials & Equipment	Waste Transportation & Disposal	Other Direct Cost (ODC)	Contingency	Total Cost (Estimated)	License Termination	Spent Fuel Management	Site Restoration
	3c.4	Segment, Package and Ship Reactor Internals - Unit 1	5,672	2,100	12,861	-	4,127	24,760	24,760	-	
	3c.5	Package and Ship Reactor Pressure Vessel - Unit 1	1,345	1,030	-	-	475	2,850	2,850	-	
3c Total	Reactor	Vessel Removal	9,804	32,130	12,861	70	10,973	65,839	65,839	-	
	3d.1	Heavy Lift / Transfer Equipment		3,245			649	3,893	3,893		
	3d.1 3d.2	Remove Steam Generators - Unit 1	1,368	163		_	306	1,836	*		
	3d.3	Remove Pressurizer - Unit 1	188	22		_	42	251	251	_	
	3d.4	Remove Reactor Coolant Pipe - Unit 1	506	35		_	108	649		_	
	3d.5	Remove Reactor Coolant Pumps - Unit 1	519	59		_	116	694			
	3d.5 3d.6	Large Component Disposal	-	-	14,614	_	2,923	17,537		_	
3d Total		omponent Removal	2,581	3,523		<u> </u>	4,143	24,861		<u> </u>	
Ju Total	Large CC	mponent Kemovai	2,301	3,323	17,017	<u>-</u>	7,173	24,801	24,801	<u>-</u>	
	3e.1	Remove and Dispose of Spent Fuel Storage Racks	66	20	-	-	17	102	102	_	
	3e.2	Segment, Package and Dispose of Spent Fuel Pool Island Equipment	207	20		-	45	272			
	3e.3	Decon/Surgical Removal Containment Building - Unit 1	1,066	130	_	-	239	1,435	1,435	-	
	3e.4	Decon/Surgical Removal Fuel Building	542	21		-	112	675	*	-	
	3e.5	Decon/Surgical Remvoal Auxiliary Building Unit 1	3,017	287		-	661	3,965			
	3e.6	Oversize Debris / Containerized Debris Disposal	-	-	3,885	-	777	4,661	•	-	
3e Total		econtamination & Interior Rad Demolition	4,897	477		-	1,852	11,110	11,110	-	
	3f.1	Demolish Fuel Building	247	538	-	-	157	942	942	-	
	3f.2	Demolish Auxiliary Building	1,552	4,131	-	-	1,137	6,820	6,820	-	
	3f.3	Demolish Unit 1 Containment Building	1,940	6,120	-	-	1,612	9,673	9,673	-	
	3f.4	Contaminated Soil	661	992	55,805	-	11,492	68,949	68,949	-	
	3f.5	Debris Disposal	-	-	100,085	-	20,017	120,103	120,103	-	
3f Total	Rad Buil	ding Demolition	4,402	11,781	155,890	-	34,415	206,488	206,488	-	
	2 a 1	Final Status Survey for Structures	5,753	54	_	227	1,207	7,240	7,240		
	3g.1 3g.2	Final Status Survey for Land Areas (Included with Structures)	5,755	-	- -	-	1,207	7,240	7,240	_	
3g Total	_	Termination Activities	5,753	54		227	1,207	7,240	7,240	<u>-</u>	
Jg Total	License	Termination Activities	3,733	34	<u> </u>	227	1,207	7,240	7,240	<u>-</u>	
	3h.1	Utility Staff	33,033	-	-	-	4,955	37,988	37,988	_	
	3h.2	Security Guard Force	1,994	-	-	-	299	2,293	*	-	
	3h.3	General Contractor Staff	67,660	-	-	-	10,149	77,809		-	
	3h.4	Property Taxes	-	-	-	288	43	331		-	
	3h.5	Insurance	-	-	-	7,541	1,131	8,673		-	
	3h.6	Corporate Support	4,813	-	-	-	722	5,535	•		
	3h.7	Utility Staff HP Supplies	-	5,180	_	_	777	5,957			

Florida Power and Light

St. Lucie Unit 1

Scenario 1 - Unit 1 SAFSTOR, DECON both following Unit 2 Shutdown

				(tilot	usarius or 2020 uoi	iiui 3 j					
Period	Item Number	Item Description	Labor Cost	Materials & Equipment	Waste Transportation & Disposal	Other Direct Cost (ODC)	Contingency	Total Cost (Estimated)	License Termination	Spent Fuel Management	Site Restoration
	3h.8	NRC Inspection Fee	-	-	-	890	133	1,023	1,023	-	-
	3h.9	Licensing Fees	-	-	-	1,376	206	1,582		-	-
	3h.10	County Fees	-	-	-	953	143	1,096	1,096	-	-
	3h.11	FEMA Fees	-	-	-	502	75	577	577	-	-
	3h.12	Materials and Services	-	2,043	-	-	306	2,349	2,349	-	-
	3h.13	Energy	-	-	-	3,319	498	3,817	3,817	-	-
	3h.14	DGC HP Supplies	-	5,132	-	-	770	5,902	5,902	-	-
	3h.15	Florida LLRW Inspection Fee	-	-	-	4,607	691	5,299	5,299		
	3h.16	EPRI Membership Fees	-	-	-	-	-	-	-	-	-
	3h.16	NEI Membership Fees	-	-	-	-	-	-	-	-	-
	3h.17	INPO Membership Fees	-	-	-	-	-	-	-	-	-
3h Total	Undistr	ibuted Costs for Decommissioning & License Termination	107,501	12,354	-	19,476	20,900	160,231	160,231	-	-
Period 3	Total	DECOMMISSIONING & LICENSE TERMINATION	158,099	63,074	194,312	25,672	79,669	520,827	520,827	-	-
	4a.1	Demo Turbine Pedastal and Turbine Deck	3,466	1,377	_	_	726	5,569	_	_	5,569
	4a.2	Demo Intake & CWS	1,776	1,184		_	444	3,405	_	_	3,405
	4a.3	Demo Tank Foundations	11	229		_	36	276	_	_	276
	4a.4	Demo Misc Site Structures	1,393	1,147	_	_	381	2,921	_	-	2,921
	4a.5	Security Improvements	536	459	_	_	149	1,144	_	_	1,144
	4a.6	Clean Concrete Processing	-	-	_	1,677	252	1,928	_	-	1,928
	4a.7	Demo Site Paving	339	791	-	-	169	1,299	_	-	1,299
	4a.8	Clean Debris Disposal / Recycle	-	-	138	-	21	159		-	159
4a Total		uilding & Site Demolition	7,520	5,187		1,677	2,178	16,700		-	16,700
	4b 1	Procure Site Restoration Equipment		735			110	946			946
	4b.1 4b.2	• •	- 690	/35	-	-	110 103	846 793		-	846 793
4b Total		Finish Grading and Re-Vegetate Site	690 690	735		<u> </u>	214	1,639		<u> </u>	1,639
40 TOTAL	Jite Nes	icolation	090	/33	<u>-</u>	<u>-</u>	214	1,039		<u>-</u>	1,039
	4c.1	Utility Staff	2,486	-	-	-	373	2,859	-	-	2,859
	4c.2	Security Guard Force	150	-	-	-	23	173	-	-	173
	4c.3	General Contractor Staff	5,093	-	-	-	764	5,857	-	-	5,857
	4c.4	Property Taxes	-	-	-	22	3	25		-	25
	4c.5	Insurance	-	-	-	568	85	653	-	-	653
	4c.6	Corporate Support	362	-	-	-	54	417	-	-	417
	4c.7	Energy	-	-	-	250	37	287	-	-	287
	4c.8	Materials and Services	-	154	-	-	23	177	-	-	177
	4c.9	County Fees	-	-	-	72	11	82	-	-	82

Florida Power and Light

St. Lucie Unit 1

Scenario 1 - Unit 1 SAFSTOR, DECON both following Unit 2 Shutdown

				(11101	usarius or 2020 uo	iiui 3 j					
Period	Item Number	Item Description	Labor Cost	Materials & Equipment	Waste Transportation & Disposal	Other Direct Cost (ODC)	Contingency	Total Cost (Estimated)	License Termination	Spent Fuel Management	Site Restoration
	4c.10	FEMA Fees	-	-	-	38	6	43	-	-	43
4c Total	Undistri	ibuted Costs for Site Restoration	8,091	154	-	949	1,379	10,573	-	-	10,573
Period 4	Total	SITE RESTORATION	16,301	6,076	138	2,625	3,771	28,912	-	-	28,912
	5a.1	Procure Loading & Transfer Equipment (included in Period 1)	-	-	-	-	-	-	-	-	-
	5a.2	Procedures & Dry Runs (included in Period 1)	-	-	-	-	-	-	-	-	-
	5a.3	Remove (86) Fuel Casks from ISFSI & Load DOE Transport	6,880	1,720	-	-	1,290	9,890	-	9,890	-
	5a.4	Spent Fuel Transportation & Disposal (by DOE)	-	-	-	-	-	-	-	-	-
5a Total	Dry Fue	el Transfer to DOE during and after DECON	6,880	1,720	-	-	1,290	9,890	-	9,890	-
	EL 4		400			120	100	700	700		
	5b.1	Remove GTCC Casks from ISFSI & Loadout	480	-	-	120	180	780		-	-
	5b.2	GTCC Transportation & Disposal	-	-	16,448	-	2,467	18,915		-	-
5b Total	GTCC W	Vaste Disposition	480	-	16,448	120	2,647	19,695	19,695	-	-
	5c.1	Utility Staff	9,318	_	_	_	1,398	10,716	_	10,716	
	5c.1	Security Guard Force	33,695	_	_	-	5,054	38,749		38,749	_
	5c.2 5c.3	General Contractor Staff	33,033		_	-	3,034	30,743	_	38,749	_
	5c.4	Property Taxes	_		_	906	136	1,042	_	1,042	_
	5c.4 5c.5	Insurance	_	_	_	9,740	1,461	11,201		11,201	_
	5c.6	NRC Inspection Fee	_	_	-	2,224	334	2,558		2,558	_
	5c.7	Licensing Fees	_		_	3,440	516	3,956		3,956	_
	5c.7	County Fees	-	-	-	3,440	210	3,930	_	5,930	_
	5c.8 5c.9	FEMA Fees	_		_	_	_		_	_	_
	5c.10	ISFSI Operating Costs	_	_	-	1,553	233	1,787	_	1,787	_
5c Total		ibuted Costs for Dry Fuel / GTCC Storage & Transfer	43,013	<u> </u>	<u> </u>	17,864	9,132	70,008	-	70,008	_
JC TOTAL	Olluisti	ibuted costs for Dry Fuer / Gree Storage & Transfer	43,013	<u> </u>	<u>-</u>	17,804	9,132	70,008	-	70,008	_
Period 5	Total	DRY FUEL / GTCC STORAGE & TRANSFER	50,373	1,720	16,448	17,984	13,069	99,594	19,695	79,898	-
	62.1	Preparation and NRC Review of License Termination Plan	67			96	241	188	_	188	
6a Total		&D Planning & Preparations	67	-	<u>-</u>	96		188		188	-
Ja IUlai	וטרטו טפ	xD Figuring & Ficharations	07	-	-	96	24	100	-	100	-
	6b.1	Clean Demolition of ISFSI	1,975	958	-	-	440	3,372	_	3,372	-
	6b.2	Demolition of ISFSI Support Structures	359	141		-	75	575		575	-
	6b.3		-	- · -	-	-	-	-	-	-	-
6b Total		d Support Structure Clean Demolition	2,334	1,099	-	-	515	3,947	-	3,947	-
				-				•		•	
	6c.1	Verification Surveys	122	33	-	-	23	178	-	178	-

Florida Power and Light

St. Lucie Unit 1

Scenario 1 - Unit 1 SAFSTOR, DECON both following Unit 2 Shutdown

Period	Item Number	Item Description	Labor Cost	Materials & Equipment	Waste Transportation & Disposal	Other Direct Cost (ODC)	Contingency	Total Cost (Estimated)	License Termination	Spent Fuel Management	Site Restoration
	6c.2	Preparation of Final Report on Decommissioning and NRC Review	67	-	-	-	10	77	-	77	-
6c Total	ISFSI Fir	nal Status Surveys	189	33	-	-	33	255	•	255	-
	6d.1	Utility Staff	318	-	-	-	48	365	-	365	-
	6d.2	Security Guard Force	152	-	-	-	23	175	-	175	-
	6d.3	General Contractor Staff	1,999	-	-	-	300	2,299	-	2,299	-
	6d.4	Property Taxes	-	-	-	44	7	51	-	51	-
	6d.5	Insurance	-	-	-	25	4	29	-	29	-
	6d.6	Energy	-	-	-	36	5	42	-	42	-
	6d.7	County Fees	-	-	-	-	-	-	-	-	-
	6d.8	FEMA Fees	-	-	-	-	-	-	-	-	-
6d Total	Undistr	ibuted Costs for ISFSI Decommissioning	2,469	-	-	106	386	2,960	-	2,960	-
Period 6	Total	ISFSI DECOMMISSIONING	5,059	1,131		202	959	7,351	-	7,351	-
GRAND	TOTAL		383,357	122,849	210,899	75,527	130,770	923,401	651,106	243,383	28,912

Florida Power and Light

St. Lucie Unit 2

Scenario 1 - Unit 1 SAFSTOR, DECON both following Unit 2 Shutdown

Rem Rem		-			(110	usarius or 2020 uo	iidi 3)						
La Total Planning Prior to Shutdown (by Plant Operations)	Period		Item Description			-		Contingency				Site Restoration	
Ib Total Unit 1 Post Shutdown Planning & Engineering		<u> </u>		•									
Li Total Unit 1 Post Shutdown Deactivation & Modifications	1a Total	Plannin	ng Prior to Shutdown (by Plant Operations)	-	-	-	-	-	-	-	-	-	
Li Total Unit 1 Post Shutdown Deactivation & Modifications													
Id Total Unit 1 Wet Fuel Transfer to DOE prior to SAFSTOR	1b Total	Unit 1 P	Post Shutdown Planning & Engineering	-	-	-	-	-	-	-	-	-	
Id Total Unit 1 Wet Fuel Transfer to DOE prior to SAFSTOR													
1e.1 Admin Activities in Preparation for Decommissioning - Unit 2 786 23	1c Total	Unit 1 F	Post Shutdown Deactivation & Modifications	-	-	-	-	-		-	-	-	
1e.1 Admin Activities in Preparation for Decommissioning - Unit 2 786 23													
1-2.2 Preparation of PSDAR and Licensing Documents - Unit 2 178 6 - - - 28 211 211 - - - - - - - - -	1d Total	Unit 1 V	Vet Fuel Transfer to DOE prior to SAFSTOR	-	-	-	-	-	-	•	-	-	
1-2.2 Preparation of PSDAR and Lucensing Documents - Unit 2													
1e.3 Engineering Activities in Preparation for Decommissioning - Unit 2 583 18 -		1e.1	Admin Activities in Preparation for Decommissioning - Unit 2	786	23	-	-	121	930	930	-	-	
1.547 1.54		1e.2	Preparation of PSDAR and Licensing Documents - Unit 2	178	6	-	-	28	211	211	-	-	
1f.1 Defuel Reactor Unit 2 (by Plant Operations)		1e.3	Engineering Activities in Preparation for Decommissioning - Unit 2	583	18	-	-	90	691	691	-	-	
1f.2 Fuel Sampling & Inspections (by Plant Operations)	1e Total	Unit 2 P	Post Shutdown Planning & Engineering	1,547	47	-	-	239	1,833	1,833	-	-	
1f.2 Fuel Sampling & Inspections (by Plant Operations)													
1f.3 Spent Fuel Pool System Modifications - Unit 2 6,868 1,212 - 1,212 9,292 - 9,292 1f Total Unit 2 Shutdown Preparations & Deactivation 6,868 1,212 - 1,212 9,292 - 9,292 1g.1 Provide Transfer Casks (supplied by DOE) -<		1f.1	Defuel Reactor Unit 2 (by Plant Operations)	-	-	-	-	-	-	-	-	-	
If Total Unit 2 Shutdown Preparations & Deactivation 6,868 1,212 - 1,212 9,292 - 9,292 Ig.1 Provide Transfer Casks (supplied by DOE) -		1f.2	Fuel Sampling & Inspections (by Plant Operations)	-	-	-	-	-	-	-	-	-	
1g.1 Provide Transfer Casks (supplied by DOE) - -		1f.3	Spent Fuel Pool System Modifications - Unit 2	6,868	1,212	-	-	1,212	9,292	-	9,292	-	
1g.2 Procure Spent Fuel Loading & Transfer Equipment - 1,463 - - 219 1,683 - 1,683 1g.3 Procedures & Dry Runs 335 - - 168 75 578 - 578 1g.4 Remove (256) Fuel Assemblies from Pool & Load DOE Casks 1,280 280 - - 312 1,872 - 1,872 1g.5 Dry, Close & Inspect (8) DOE supplied Casks 640 160 - - 160 960 - 960 1g.6 Load Out (8) Casks to DOE Transport 640 160 - - 160 960 - 960 1g.7 Spent Fuel Transportation & Disposal (by DOE) - <td>1f Total</td> <td>Unit 2 S</td> <td>hutdown Preparations & Deactivation</td> <td>6,868</td> <td>1,212</td> <td>-</td> <td>-</td> <td>1,212</td> <td>9,292</td> <td>•</td> <td>9,292</td> <td>-</td>	1f Total	Unit 2 S	hutdown Preparations & Deactivation	6,868	1,212	-	-	1,212	9,292	•	9,292	-	
1g.2 Procure Spent Fuel Loading & Transfer Equipment - 1,463 - - 219 1,683 - 1,683 1g.3 Procedures & Dry Runs 335 - - 168 75 578 - 578 1g.4 Remove (256) Fuel Assemblies from Pool & Load DOE Casks 1,280 280 - - 312 1,872 - 1,872 1g.5 Dry, Close & Inspect (8) DOE supplied Casks 640 160 - - 160 960 - 960 1g.6 Load Out (8) Casks to DOE Transport 640 160 - - 160 960 - 960 1g.7 Spent Fuel Transportation & Disposal (by DOE) - <td></td>													
1g.3 Procedures & Dry Runs 335 - 168 75 578 - 578 1g.4 Remove (256) Fuel Assemblies from Pool & Load DOE Casks 1,280 280 - - 312 1,872 - 1,872 1g.5 Dry, Close & Inspect (8) DOE supplied Casks 640 160 - - 160 960 - 960 1g.6 Load Out (8) Casks to DOE Transport 640 160 - - 160 960 - 960 1g.7 Spent Fuel Transportation & Disposal (by DOE) -<		1g.1	Provide Transfer Casks (supplied by DOE)	-	-	-	-	-	-	-	-	-	
1g.4 Remove (256) Fuel Assemblies from Pool & Load DOE Casks 1,280 280 312 1,872 - 1,872 1g.5 Dry, Close & Inspect (8) DOE supplied Casks 640 160		1g.2	Procure Spent Fuel Loading & Transfer Equipment	-	1,463	-	-	219	1,683	-	1,683	-	
1g.5 Dry, Close & Inspect (8) DOE supplied Casks 640 160 - - 160 960 - 960 1g.6 Load Out (8) Casks to DOE Transport 640 160 - - 160 960 - 960 1g.7 Spent Fuel Transportation & Disposal (by DOE) -		1g.3	Procedures & Dry Runs	335	-	-	168	75	578	-	578	-	
1g.6 Load Out (8) Casks to DOE Transport 640 160 - - 160 960 - 960 1g.7 Spent Fuel Transportation & Disposal (by DOE) - <t< td=""><td></td><td>1g.4</td><td>Remove (256) Fuel Assemblies from Pool & Load DOE Casks</td><td>1,280</td><td>280</td><td>-</td><td>-</td><td>312</td><td>1,872</td><td>-</td><td>1,872</td><td>-</td></t<>		1g.4	Remove (256) Fuel Assemblies from Pool & Load DOE Casks	1,280	280	-	-	312	1,872	-	1,872	-	
1g.7 Spent Fuel Transportation & Disposal (by DOE) -		1g.5	Dry, Close & Inspect (8) DOE supplied Casks	640	160	-	-	160	960	-	960	-	
Ig Total Unit 2 Wet Fuel Transfer to DOE prior to DECON 2,895 2,063 - 168 927 6,053 - 6,053 1h.1 Provide Transfer Casks (21) - 18,538 - - 2,781 21,318 - 21,318 1h.2 Procure Spent Fuel Loading & Transfer Equipment -		1g.6	Load Out (8) Casks to DOE Transport	640	160	-	-	160	960	-	960	-	
1h.1 Provide Transfer Casks (21) - 18,538 - - 2,781 21,318 - 21,318 1h.2 Procure Spent Fuel Loading & Transfer Equipment -		1g.7	Spent Fuel Transportation & Disposal (by DOE)	-	-	-	-	-	-	-	-	-	
1h.2 Procure Spent Fuel Loading & Transfer Equipment -	1g Total	Unit 2 V	Vet Fuel Transfer to DOE prior to DECON	2,895	2,063	-	168	927	6,053	ı	6,053	-	
1h.2 Procure Spent Fuel Loading & Transfer Equipment -													
1h.3 Procedures & Dry Runs 335 - - 168 75 578 - 578 1h.4 Remove (672) Fuel Assemblies from Pool & Load Casks 3,360 840 - - 840 5,040 - 5,040 1h.5 Dry, Close & Inspect (21) 1,680 420 - - 420 2,520 - 2,520 1h.6 Load Out (21) Casks to Transport 1,680 420 - - - 420 2,520 - 2,520 1h.7 Spent Fuel Transportation & Disposal (by DOE) - <t< td=""><td></td><td>1h.1</td><td>Provide Transfer Casks (21)</td><td>-</td><td>18,538</td><td>-</td><td>-</td><td>2,781</td><td>21,318</td><td>-</td><td>21,318</td><td>-</td></t<>		1h.1	Provide Transfer Casks (21)	-	18,538	-	-	2,781	21,318	-	21,318	-	
1h.4 Remove (672) Fuel Assemblies from Pool & Load Casks 3,360 840 - - 840 5,040 - 5,040 1h.5 Dry, Close & Inspect (21) 1,680 420 - - 420 2,520 - 2,520 1h.6 Load Out (21) Casks to Transport 1,680 420 - - 420 2,520 - 2,520 1h.7 Spent Fuel Transportation & Disposal (by DOE) - <t< td=""><td></td><td>1h.2</td><td>Procure Spent Fuel Loading & Transfer Equipment</td><td>-</td><td>-</td><td>-</td><td>-</td><td>-</td><td>-</td><td>-</td><td>-</td><td>-</td></t<>		1h.2	Procure Spent Fuel Loading & Transfer Equipment	-	-	-	-	-	-	-	-	-	
1h.5 Dry, Close & Inspect (21) 1,680 420 - - 420 2,520 - 2,520 1h.6 Load Out (21) Casks to Transport 1,680 420 - - 420 2,520 - 2,520 1h.7 Spent Fuel Transportation & Disposal (by DOE) -		1h.3	Procedures & Dry Runs	335	-	-	168	75	578	-	578	-	
1h.6 Load Out (21) Casks to Transport 1,680 420 - - 420 2,520 - 2,520 1h.7 Spent Fuel Transportation & Disposal (by DOE) - 31,976 - 31,976		1h.4	Remove (672) Fuel Assemblies from Pool & Load Casks	3,360	840	-	-	840	5,040	-	5,040	-	
1h.7 Spent Fuel Transportation & Disposal (by DOE) -		1h.5	Dry, Close & Inspect (21)	1,680	420	-	-	420	2,520	-	2,520	-	
1h Total Unit 2 Wet Fuel Transfer to ISFSI prior to DECON 7,055 20,218 - 168 4,536 31,976 - 31,976		1h.6	Load Out (21) Casks to Transport	1,680	420	-	-	420	2,520	-	2,520	-	
		<u>1</u> h.7	Spent Fuel Transportation & Disposal (by DOE)										
	1h Total	Unit 2 V	Vet Fuel Transfer to ISFSI prior to DECON	7,055	20,218	-	168	4,536	31,976	-	31,976	-	
1i.1 Utility Staff 67,101 10,065 77,167 61,733 15,433		1i.1	Utility Staff	67,101	-	-	-	10,065	77,167	61,733	15,433	-	

Florida Power and Light

St. Lucie Unit 2

Scenario 1 - Unit 1 SAFSTOR, DECON both following Unit 2 Shutdown

				tillot	isalius oi zozo uo	114131					
Period	Item Number	Item Description	Labor Cost	Materials & Equipment	Waste Transportation & Disposal	Other Direct Cost (ODC)	Contingency	Total Cost (Estimated)	License Termination	Spent Fuel Management	Site Restoration
	1i.2	Security Guard Force	40,615	_	Disposai -	-	6,092	46,707	14,012	32,695	_
	1i.3	General Contractor Staff		_	_	_	- 0,032		14,012	52,055	_
	1i.4	Property Taxes	_	_	_	177	27	203	163	41	_
	1i.5	Insurance	_	_	_	6,848	1,027	7,875	6,300	1,575	_
	1i.6	Corporate Support	881	-	_	-	132	1,013	304	709	_
	1i.7	Utility Staff HP Supplies	-	403	-	-	61	464	139	325	-
	1i.8	NRC Inspection Fee	-	-	-	2,224	334	2,558	2,558	_	-
	1i.9	Licensing Fees	_	-	-	688	103	791	791	_	-
	1i.10	Materials and Services	-	719	-	-	108	827	248	579	-
	1i.11	Energy	-	-	-	730	109	839	671	168	-
	1i.12	EPRI Membership Fees	-	-	-	-	-	-	-	-	-
	1i.13	NEI Membership Fees	-	-	-	-	-	-	-	-	-
	1i.14	County Fees	-	-	-	2,049	307	2,356	1,885	471	-
	1i.15	FEMA Fees	-	-	-	1,079	162	1,241	993	248	-
	1i.16	INPO Membership Fees	-	-	-	-	-	-	-	-	-
	1i.17	ISFSI Operating Costs	-	54	-	-	8	62	-	62	-
	1i.18	Spent Fuel Maintenance	784	87	-	-	131	1,002	-	1,002	-
1i Total	Undistri	ibuted Costs for Shutdown & Transition	109,382	1,263	-	13,794	18,666	143,105	89,797	53,308	-
Period 1	Total	SHUTDOWN & TRANSITION	127,747	24,803	-	14,129	25,580	192,259	91,630	100,629	-
Period 2	Total	SAFSTOR	-	-	-	-	-	-	1	-	-
	3a.1	Decommissioning Planning and Design - Unit 2	1,493	45	-	-	231	1,769	1,769	-	-
	3a.2	Site Characterization - Unit 2	1,409	53	-	105	235	1,803	1,803	-	-
	3a.3	Prepare Integrated Work Sequence and Schedule - Unit 2	161	5	-	-	25	191	191	-	-
	3a.4	Prepare Decommissioning Activity Specifications - Unit 2	2,156	67	-	-	333	2,556	2,556	-	-
	3a.5	Prepare License Termination Plan - Unit 2	965	-	-	667	245	1,877	1,877	-	-
	3a.6	Prepare Detailed Work Procedures for Decommissioning - Unit 2	1,748	54	-	-	270	2,072	2,072	-	-
	3a.7	Design Containment and Misc System Modifications - Unit 2	79	-	-	-	12	91	91	-	-
	3a.8	Purchase Dry Storage Modules for Unit 2 GTCC Waste	-	-	7,062	-	1,059	8,121	8,121	-	-
3a Total	Decomr	missioning Planning	8,010	224	7,062	772	2,410	18,478	18,478	-	-
	3b.1	Mobilize Decommissioning General Contractor	-	-	-	1,300	195	1,495	1,495	-	-
	3b.2	Flush and Drain Non-Essential Systems - Unit 2	515	5	-	-	78	598	598	-	-
	3b.3	Perform Asbestos Abatement of Pipe Insulation - Unit 2	-	-	-	-	-	-	-	-	-
	3b.4	Implement Cold and Dark & Install Temporary Power - Unit 2	4,504	1,568	-	-	911	6,983		-	-
	3b.5	Construct Misc Building Modifications, In-Plant Laydown Areas	2,881	508	_	_	508	3,897	3,897	_	_

Florida Power and Light

St. Lucie Unit 2

Scenario 1 - Unit 1 SAFSTOR, DECON both following Unit 2 Shutdown

(triousarius or 2020 dollars)											
Period	Item Number	Item Description	Labor Cost	Materials & Equipment	Waste Transportation & Disposal	Other Direct Cost (ODC)	Contingency	Total Cost (Estimated)	License Termination	Spent Fuel Management	Site Restoration
	3b.6	Modify Containment Access - Unit 2	2,137	377	-	-	377	2,892	2,892	-	-
	3b.7	Transportation Infrastructure Modifications	60	298	-	1,393	263	2,013	2,013	-	-
	3b.8	Procure Waste Handling & Processing Tents	-	-	-	1,476	221	1,697	1,697	-	-
3b Total	Decomn	nissioning Transition and Preparations	10,097	2,757	-	4,168	2,553	19,575	19,575	-	-
	3c.1	Design and Procure Special Equipment	-	27,050	-	-	5,410	32,460	32,460	-	-
	3c.2	Test Special Cutting and Handling Equipment and Train Operators	1,924	-	-	70	399	2,392	2,392	-	-
	3c.3	Finalize Internals and Vessel Segmentation Details - Unit 2	447	-	-	-	89	536	536	-	-
	3c.4	Segment, Package and Ship Reactor Internals - Unit 2	5,672	2,100	12,293	-	4,013	24,077	24,077	-	-
	3c.5	Package and Ship Reactor Pressure Vessel - Unit 2	1,345	1,030	-	-	475	2,850	2,850	-	-
3c Total	Reactor	Vessel Removal	9,386	30,180	12,293	70	10,386	62,315	62,315	-	-
	3d.1	Heavy Lift / Transfer Equipment		3,245	-	-	649	3,893	3,893	-	-
	3d.2	Remove and Dispose of Steam Generators - Unit 2	1,368	163	-	-	306	1,836	1,836	-	-
	3d.3	Remove and Dispose of Pressurizer - Unit 2	188	22	-	-	42	251	251	-	-
	3d.4	Remove and Dispose of Reactor Coolant Pipe - Unit 2	506	35	-	-	108	649	649	-	-
	3d.5	Remove and Dispose of Reactor Coolant Pumps - Unit 2	519	59	-	-	116	694	694	-	-
	3d.6	Large Component Disposal	-	-	14,495	-	2,899	17,394	17,394	-	-
3d Total	Large Co	emponent Removal	2,581	3,523	14,495	-	4,120	24,718	24,718	-	-
	3e.1	Remove and Dispose of Spent Fuel Storage Racks	66	20	-	-	17	102	102	-	-
	3e.2	Segment, Package and Dispose of Spent Fuel Pool Island Equipment	207	62	-	-	54	322	322	-	-
	3e.3	Decon/Surgical Removal Containment Building - Unit 2	1,066	130	-	-	239	1,435	1,435	-	-
	3e.4	Decon/Surgical Removal Fuel Building - Unit 2	542	21	-	-	112	675	675	-	-
	3e.5	Decon/Surgical Remvoal Auxiliary Building Unit 2	3,017	287	-	-	661	3,965	3,965	-	-
	3e.6	Oversize Debris / Containerized / Processed Debris Disposal	-	-	3,885	-	777	4,661	4,661	-	-
3e Total	Plant De	contamination & Interior Rad Demolition	4,897	519	3,885	-	1,860	11,161	11,161	-	-
	3f.1	Demolish Fuel Building	247	538	-	-	157	942	942	-	-
	3f.2	Demolish Auxiliary Building	1,552	4,131	-	-	1,137	6,820	6,820	-	-
	3f.3	Demolish Unit 2 Containment Building	1,940	6,120	-	-	1,612	9,673	9,673	-	-
	3f.4	Contaminated Soil	614	922	51,494	-	10,606	63,636	63,636	-	-
	3f.5	Debris Dispsoal			97,401		19,480	116,882	116,882		
3f Total	Rad Buil	ding Demolition	4,355	11,711	148,895	-	32,992	197,953	197,953	-	-
	3g.1	Final Status Survey for Structures	5,753	54	-	227	1,207	7,240	7,240	-	-
	3g.2	Final Status Survey for Land Areas (included with Structures)		-	-	-				-	
3g Total	License 7	Termination Activities	5,753	54	-	227	1,207	7,240	7,240	-	-

Florida Power and Light

St. Lucie Unit 2

Scenario 1 - Unit 1 SAFSTOR, DECON both following Unit 2 Shutdown

	(triousarius or 2020 dollars)										
Period	Item Number	Item Description	Labor Cost	Materials & Equipment	Waste Transportation & Disposal	Other Direct Cost (ODC)	Contingency	Total Cost (Estimated)	License Termination	Spent Fuel Management	Site Restoration
			•								•
	3h.1	Utility Staff	29,716	-	-	-	4,457	34,173	34,173	-	-
	3h.2	Security Guard Force	1,880	-	-	-	282	2,162	2,162	-	-
	3h.3	General Contractor Staff	67,660	-	-	-	10,149	77,809	77,809	-	-
	3h.4	Property Taxes	-	-	-	247	37	284	284	-	-
	3h.5	Insurance	-	-	-	4,357	654	5,011	5,011	-	-
	3h.6	Corporate Support	4,223	-	-	-	634	4,857	4,857	-	-
	3h.7	Utility Staff HP Supplies	-	6,677	-	-	1,002	7,679	7,679	-	-
	3h.8	NRC Inspection Fee	-	-	-	667	100	767	767	-	-
	3h.9	Licensing Fees	-	-	-	1,032	155	1,187	1,187	-	-
	3h.10	County Fees	-	-	-	-	-	-	-	-	-
	3h.11	FEMA Fees	-	-	-	-	-	-	-	-	-
	3h.12	Materials and Services	-	1,749	-	-	262	2,011	2,011	-	-
	3h.13	Energy	-	-	-	3,388	508	3,896	3,896	-	-
	3h.14	DGC HP Supplies	-	5,132	-	-	770	5,902	5,902	-	-
	3h.15	Florida LLRW Inspection Fee	-	-	-	4,461	669	5,130	5,130	-	-
	3h.16	EPRI Membership Fees	-	-	-	-	-	-	-	-	-
	3h.17	NEI Membership Fees	-	-	-	-	-	-	-	-	-
	3h.18	INPO Membership Fees	-	-	-	-	-	-	-	-	-
3h Total	Undistri	ibuted Costs for Decommissioning & License Termination	103,480	13,558	-	14,152	19,679	150,869	150,869	-	-
Period 3	Total	DECOMMISSIONING & LICENSE TERMINATION	148,558	62,525	186,630	19,389	75,206	492,308	492,308	-	-
	4a.1	Demo Turbine Pedastal and Turbine Deck	3,614	1,377	_	_	749	5,740	_	_	5,740
	4a.2	Demo Intake & CWS	1,830	1,220		_	457	3,507	_	_	3,507
	4a.3	Demo Primary Water Tank Foundation	1,830	92		_	15	118	_	_	118
	4a.4	Demo Misc Site Structures	5,795	1,147		_	1,041	7,984	_	_	7,984
	4a.5	Demo Security Improvements	536	459		_	149	1,144	_	_	1,144
	4a.6	Demo Steam Generator Blowdown Treatment	585	138		_	108	831	_	_	831
	4a.7	Clean Concrete Processing	-	136	- -	2,428	364	2,792	_	_	2,792
	4a.7 4a.8	Demo Site Paving	339	- 791		2,420	169	1,299	_	-	2,792 1,299
	4a.8 4a.9	Clean Debris Disposal / Recycle	339	791	140	-	21	1,299	_	-	1,293
4a Total		uilding & Site Demolition	12,709	5,223		2,428	3,075	23,574	<u> </u>	<u> </u>	23,574
70 IO(a)	Cicaii Di	anding a Site Demontion	12,103	3,223	140	2,720	3,073	23,374	_		23,374
	4b.1	Procure Site Restoration Equipment	-	490	-	-	74	564	-	-	564
	4b.2	Finish Grading and Re-Vegetate Site	460	26	-	-	73	558	-		558
4b Total	Site Res	toration	460	516	-	-	146	1,122	·	-	1,122

Florida Power and Light

St. Lucie Unit 2

Scenario 1 - Unit 1 SAFSTOR, DECON both following Unit 2 Shutdown

(thousands of 2020 dollars)											
Period	Item Number	Item Description	Labor Cost	Materials & Equipment	Waste Transportation & Disposal	Other Direct Cost (ODC)	Contingency	Total Cost (Estimated)	License Termination	Spent Fuel Management	Site Restoration
	4c.1	Utility Staff	2,237	-	-	-	336	2,572	-	-	2,572
	4c.2	Security Guard Force	142	-	-	-	21	163	-	-	163
	4c.3	General Contractor Staff	5,093	-	-	-	764	5,857	-	-	5,857
	4c.4	Property Taxes	-	-	-	19	3	21	-	-	21
	4c.5	Insurance	-	-	-	328	49	377	-	-	377
	4c.6	Corporate Support	318	-	-	-	48	366	-	-	366
	4c.7	Energy	-	-	-	255	38	293	-	-	293
	4c.8	Materials and Services	-	132	-	-	20	151	-	-	151
	4c.9	County Fees	-	-	-	-	-	-	-	-	-
	4c.10	FEMA Fees	-	-	-	_	-	-	-	-	-
4c Total	Undistr	ibuted Costs for Site Restoration	7,789	132	-	602	1,278	9,800	-	-	9,800
Period 4	Total	SITE RESTORATION	20,958	5,870	140	3,029	4,500	34,497	-	-	34,497
	5a.1	Procure Loading & Transfer Equipment (included in Period 1)	-	-	-	-	-	-	-	-	-
	5a.2	Procedures & Dry Runs (included in Period 1)	-	-	-	-	-	-	-	-	-
	5a.3	Remove (64) Fuel Casks from ISFSI & Load DOE Transport	5,120	1,280	-	-	960	7,360	-	7,360	-
	5a.4	Spent Fuel Transportation & Disposal (by DOE)	-	-	-	-	-	-	-	-	-
	5a.5	I	-	-	-	-	-	-	-	-	-
5a Total	Dry Fue	I Transfer to DOE during and after DECON	5,120	1,280	-	-	960	7,360	-	7,360	-
	Th 1	Damaya CTCC Casks from ISTSI 9 Landout	400			120	190	790	700		
	5b.1 5b.2	Remove GTCC Casks from ISFSI & Loadout	480	-	16 449	120	180 2,467	780 18,915	780 18,915	-	-
	5b.2 5b.3	GTCC Transportation & Disposal	-	-	16,448	-	2,407	10,915	10,913	-	-
5b Total		/aste Disposition	480	-	16,448	120	2,647	19,695	19,695	<u> </u>	<u>-</u>
30 TOTAL	GICC W	raste disposition	460	-	10,446	120	2,047	19,095	19,095	<u>-</u>	
	5c.1	Utility Staff	9,318	_	_	_	1,398	10,716	_	10,716	_
		Security Guard Force	33,695	_	_	_	5,054	38,749	_	38,749	_
	5c.3	General Contractor Staff	-	_	_	_	-	-	_	-	_
	5c.4	Property Taxes	_	-	-	906	136	1,042	_	1,042	_
	5c.5	Insurance	_	-	-	9,740	1,461	11,201		11,201	_
	5c.6	NRC Inspection Fee	-	-	-	2,224	334	2,558		2,558	_
	5c.7	Licensing Fees	-	-	-	3,440	516	3,956		3,956	_
	5c.8	County Fees	-	-	-	-,	-	-	-	-	-
	5c.9	FEMA Fees	-	-	-	_	-	-	-	-	-
	5c.10	ISFSI Maintenance	-	-	-	1,593	239	1,832	-	1,832	-
5c Total		ibuted Costs for Dry Fuel / GTCC Storage & Transfer	43,013	-	-	17,903	9,137	70,054	-	70,054	-
		· · · · · · · · · · · · · · · · · · ·	, , , , , , , , , , , , , , , , , , ,			<u>, </u>	,	,			

Florida Power and Light

St. Lucie Unit 2

Scenario 1 - Unit 1 SAFSTOR, DECON both following Unit 2 Shutdown

(tilousullus of 2020 dollurs)											
Period	Item Number	Item Description	Labor Cost	Materials & Equipment	Waste Transportation & Disposal	Other Direct Cost (ODC)	Contingency	Total Cost (Estimated)	License Termination	Spent Fuel Management	Site Restoration
Period 5	Total	DRY FUEL / GTCC STORAGE & TRANSFER	48,613	1,280	16,448	18,023	12,745	97,109	19,695	77,414	-
	6a.1	Preparation and NRC Review of License Termination Plan	45	-	-	64	16	125	-	125	-
6a Total	ISFSI D8	&D Planning & Preparations	45	-	-	64	16	125	-	125	-
	6b.1	Clean Demolition of ISFSI	1,316	638	-	-	293	2,248	-	2,248	-
	6b.2	Demolition of ISFSI Support Structures	240	94	-	-	50	384	-	384	-
6b Total	ISFSI an	d Support Structure Clean Demolition	1,556	732	-	-	343	2,632	-	2,632	-
	6c.1	Verification Surveys	81	22	-	-	15	119		119	-
	6c.2	Preparation of Final Report on Decommissioning and NRC Review	45	-	-	-	7	52	-	52	-
6c Total	ISFSI Fir	nal Status Surveys	126	22	-	-	22	170	-	170	-
	6d.1	Utility Staff	318	-	-	-	48	365	-	365	-
	6d.2	Security Guard Force	152	-	-	-	23	175	-	175	-
	6d.3	General Contractor Staff	1,999	-	-	-	300	2,299	-	2,299	-
	6d.4	Property Taxes	-	-	-	44	7	51	-	51	-
	6d.5	Insurance	-	-	-	25	4	29	-	29	-
	6d.6	Energy	-	-	-	36	5	42	-	42	-
	6d.7	County Fees	-	-	-	-	-	-	-	-	-
	6d.8	FEMA Fees	-	-	-	-	-	-	-	-	-
6d Total	Undistr	ibuted Costs for ISFSI Decommissioning	2,469	-	-	106	386	2,960	1	2,960	-
Period 6	Total	ISFSI DECOMMISSIONING	4,196	754	-	170	768	5,887	-	5,887	-
GRAND	TOTAL		350,072	95,233	203,217	54,740	118,798	822,060	603,633	183,930	34,497

Florida Power and Light St. Lucie Unit 1 Scenario 2 - SAFSTOR

		(thousands of 2020 dollars)											
Period	Item Number	Item Description	Labor Cost	Materials & Equipment	Waste Transportation & Disposal	Other Direct Cost (ODC)	Contingency	Total Cost (Estimated)	License Termination	Spent Fuel Management	Site Restoration		
1a Total	Plannin	ng Prior to Shutdown (by Plant Operations)	-	-	-	-	-	-	-	-	-		
	1b.1	Admin Activities in Preparation for SAFSTOR - Unit 1	2,397	74	1 -	_	371	2,841	2,841	_	_		
	1b.2	Prepare PSDAR and License Documents - Unit 1	418	13		_	65	495	495	_	_		
	1b.2	Engineering Activities in Preparation for SAFSTOR - Unit 1	2,356	73		_	364	2,794		_	_		
1b Total		Post Shutdown Planning & Engineering	5,171	160		-	800	6,130		-	_		
20 1000	<u> </u>		5,2.2					0,200	3,230				
	1c.1	Defuel Reactor Unit 1 (by Plant Operations)	-	-	-	-	-	-	-	-	-		
	1c.2	Fuel Sampling & Inspections (by Plant Operations)	-	-	-	-	-	-	-	-	-		
	1c.3	Spent Fuel Pool System Modifications - Unit 1	10,303	1,818	-	-	1,818	13,939	-	13,939	-		
	1c.4	Implement Cold & Dark - Unit 1	3,508	630	-	-	621	4,759	4,759	-	-		
	1c.5	Flush and Drain Non-Essential Systems - Unit 1	515	13	-	-	79	607	607	-	-		
	1c.6	Perform Pre-SAFSTOR Baseline Radiation Survey - Unit 1	1,210	37	7 -	-	187	1,434	646	789			
1c Total	Unit 1 I	Post Shutdown Deactivation & Modifications	15,535	2,499	-	-	2,705	20,739	6,012	14,728	-		
	1d.1	Provide Transfer Casks (supplied by DOE)	-	-	-	-	-	-	-	-	-		
	1d.2	Procure Spent Fuel Loading & Transfer Equipment	-	2,184	-	-	328	2,512		2,512	-		
	1d.3	Procedures & Dry Runs	500	-	-	250	113	863		863	-		
	1d.4	Remove (224) Fuel Assemblies from Pool & Load DOE Casks	1,120	280		-	280	1,680		1,680	-		
	1d.5	Dry, Close & Inspect (7) DOE supplied Casks	560	140		-	140	840		840	-		
	1d.6	Load Out (7) Casks to DOE Transport	560	140		-	140	840	-	840	-		
1 d Total	1d.7	Spent Fuel Transportation & Disposal (by DOE)	- 2.740	- 2 744		- 250	1 000	- C 724	-	- C 724			
1d Total	Unit I v	Vet Fuel Transfer to DOE prior to SAFSTOR	2,740	2,744	-	250	1,000	6,734	-	6,734	_		
1e Total	Unit 2 P	ost Shutdown Planning & Engineering	-	-	-	-	-	•	,	-	-		
1f Total	Unit 2 S	hutdown Preparations & Deactivation	_	-	_	_	_	-	_		_		
II Total	Omit 2 0	matao siii i reparationo a Deactivation											
1g Total	Unit 2 V	Vet Fuel Transfer to DOE prior to SAFSTOR	-	-	-	-	-	-	-	-	-		
1h Total	Unit 2 V	Vet Fuel Transfer to ISFSI prior to SAFSTOR	-	-	-	-	-	-	-	-	_		
	1i.1	Utility Staff	64,707	-	-	-	9,706	74,414	59,531	14,883	-		
	1i.2	Security Guard Force	6,442	-	-	-	966	7,408	2,223	5,186	-		
	1i.3	General Contractor Staff	-	-	-	-	-	-	-	-	-		
	1i.4	Property Taxes	-	-	-	177	27	203	163	41	-		
	1i.5	Insurance	-	-	-	6,848	1,027	7,875	6,300	1,575	-		

Florida Power and Light St. Lucie Unit 1

Scenario 2 - SAFSTOR

(triousarius or 2020 dollars)											
Period	Item Number	Item Description	Labor Cost	Materials & Equipment	Waste Transportation & Disposal	Other Direct Cost (ODC)	Contingency	Total Cost (Estimated)	License Termination	Spent Fuel Management	Site Restoration
	1i.6	Corporate Support	1,325	-	-	-	199	1,524	457	1,067	-
	1i.7	Utility Staff HP Supplies	-	883	-	-	132	1,016	305	711	-
	1i.8	NRC Inspection Fee	-	-	-	2,224	334	2,558	2,558	-	-
	1i.9	Licensing Fees	-	-	-	688	103	791	791	-	-
	1i.10	Materials and Services	-	1,945	-	-	292	2,237	671	1,566	-
	1i.11	Energy	-	-	-	1,097	165	1,262	1,010	252	-
	1i.12	EPRI Membership Fees	-	-	-	-	-	-	-	-	-
	1i.13	NEI Membership Fees	-	-	-	-	-	-	-	-	-
	1i.14	County Fees	-	-	-	2,049	307	2,356			-
	1i.15	FEMA Fees	-	-	-	1,079	162	1,241	993	248	-
	1i.16	INPO Membership Fees	-	-	-	-	-	-	-	-	-
	1i.17	ISFSI Operating Costs	-	67	-	-	10	77	-	77	-
	1i.18	Spent Fuel Maintenance	1,180	131	-	-	197	1,507		1,507	-
1i Total	Undistr	ibuted Costs for Shutdown & Transition	73,654	3,026	-	14,162	13,626	104,468	76,885	27,583	-
Period 1 To	tal	SHUTDOWN & TRANSITION	97,100	8,429	-	14,412	18,131	138,072	89,027	49,045	-
	2.4	D : T									
	2a.1	Provide Transfer Casks (supplied by DOE)	-	-	-	-	-	-	-	-	-
	2a.2	Procure Spent Fuel Loading & Transfer Equipment	-	-	-	-	-	-	-	-	-
	2a.3	Procedures & Dry Runs	1 600	-	-	-	-	2 400	-	2 400	-
	2a.4	Remove (320) Fuel Assemblies from Pool & Load Casks	1,600	400	-	-	400	2,400	-	2,400	-
	2a.5	Dry, Close & Inspect (10)	800	200	-	-	200	1,200	-	1,200	-
	2a.6	Load Out (10) Casks to Transport	800	200	-	-	200	1,200	-	1,200	-
2a Total	2a.7	Spent Fuel Transportation & Disposal (by DOE) Wet Fuel Transfer to DOE during SAFSTOR	3,200	800	-	-	800	4,800	-	4,800	
Za IOlai	Official	Net ruel Transier to DOE during SAFSTOR	3,200	800	-	-	800	4,600	-	4,800	-
	2b.1	Provide Transfer Casks (41)		36,193			5,429	41,622		41,622	
	2b.1 2b.2	Procure Spent Fuel Loading & Transfer Equipment		30,193	_	_	5,429	41,022	_	41,022	_
	2b.2	Procedures & Dry Runs	335	_	_	168	75	578	_	578	_
	2b.3 2b.4	Remove (1312) Fuel Assemblies from Pool & Load Casks	6,560	1,640	_	-	1,640			9,840	_
	2b.5	Dry, Close & Inspect (41)	3,280	820	_	_	820	4,920		4,920	_
	2b.6	Load Out (41) Casks to Transport	3,280	820	_	_	820	4,920		4,920	_
	2b.7	Spent Fuel Transportation & Disposal (by DOE)	5,200	-	_	_	- 1	7,320	_	-,320	_
2b Total		Wet Fuel Transfer to ISFSI during SAFSTOR	13,455	39,473	-	168	8,784	61,880		61,880	-
25 10001	O.IIIC I V	Section Control warms on or on	10,700	33,473		100	0,704	01,000		01,000	
	2c.1	Utility Staff	36,911	_	_	_	3,691	40,603	18,271	22,331	_
	2c.2	Security Guard Force	16,218	_	_	_	1,622	·		17,840	_
	2c.2	General Contractor Staff	-	_	_	_	- 1,022	17,040	_	±7,0 4 0	_
I	20.5	Seneral Contractor Start	_	_		_	_		I	_	_

Florida Power and Light St. Lucie Unit 1

Scenario 2 - SAFSTOR

Period	Item Number	Item Description	Labor Cost	Materials &	Waste Transportation & Disposal	Other Direct Cost (ODC)	Contingency	Total Cost (Estimated)	License Termination	Spent Fuel Management	Site Restoration
	2c.4	Property Taxes	-	-	-	1,414	141	1,555	700	855	-
	2c.5	Insurance	-	-	-	31,505	3,151	34,656	15,595	19,061	-
	2c.6	Corporate Support	9,222	-	-	-	922	10,145	4,565	5,580	-
	2c.7	Utility Staff HP Supplies	-	2,795	-	-	280	3,075	1,384	1,691	-
	2c.8	NRC Inspection Fee	-	-	-	3,725	373	4,098	1,844	2,254	-
	2c.9	Licensing Fees	-	-	-	5,504	550	6,054	2,724	3,330	-
	2c.10	County Fees	-	-	-	3,586	359	3,944	1,775	2,169	-
	2c.11	FEMA Fees	-	-	-	1,888	189	2,077	935	1,142	-
	2c.12	EPRI Membership Fees	-	-	-	-	-	-	-	-	-
	2c.13	NEI Fees	-	-	-	-	-	-	-	-	-
	2c.14	INPO Membership Fees	-	-	-	-	-	-	-	-	-
	2c.15	Materials and Services	-	5,560	-	-	556	6,116	2,752	3,364	-
	2c.16	Roof Replacement	-	42	-	-	4	46	21	25	-
	2c.17	Energy	-	-	-	2,944	294	3,239	1,457	1,781	-
2c Total	Unit 1 D	Pormancy during Dry Fuel Storage	62,352	8,397	-	50,566	12,132	133,447	52,023	81,424	-
2d Total	Unit 2 D	Pormancy during Dry Fuel Storage	-	-	-	-	-	-	-	-	-
	2e.1	Utility Staff	7,642	_	_	_	764	8,406	8,406	_	_
	2e.2	Security Guard Force	3,560	_	_	_	356	3,916	•		_
	2e.3	General Contractor Staff	-	_	-	_	-	-	-	_	_
	2e.4	Property Taxes	_	_	_	839	84	923	923	_	_
	2e.5	Insurance	_	_	-	8,790	879	9,669			_
	2e.6	Corporate Support	2,660	_	_	-	266	2,926			_
	2e.7	Utility Staff HP Supplies	_,000	974	-	_	97	1,071			_
	2e.8	NRC Inspection Fee	-	-	-	2,113	211	2,324	•		_
	2e.9	Licensing Fees	-	_	-	3,268	327	3,595	•		_
	2e.10	County Fees	_	_	_	-	-	-	-	_	_
	2e.11	FEMA Fees	-	_	-	_	-	-	_	-	-
	2e.12	EPRI Membership Fees	-	_	-	_	_	-	_	-	-
	2e.13	NEI Fees	-	_	-	-	-	-	-	-	-
	2e.14	INPO Membership Fees	-	_	-	_	_	-	_	_	_
	2e.15	Materials and Services	-	2,309	-	_	231	2,540	2,540	_	_
	2e.16	Roof Replacement	-	17	-	_	2	19	19		_
	2e.17	Energy	-	-	-	1,102	110	1,212	1,212		_
2e Total	Dorman		13,862	3,300		16,112	3,327	36,602			_
		, ,					-,- =-		55,562		
Period 2 To	tal	SAFSTOR	92,869	51,970	-	66,846	25,043	236,728	88,625	148,103	-

Florida Power and Light St. Lucie Unit 1

Scenario 2 - SAFSTOR

	(tilousarius of zozo dollars)										
Period	Item Number	Item Description	Labor Cost	Materials & Equipment	Waste Transportation & Disposal	Other Direct Cost (ODC)	Contingency	Total Cost (Estimated)	License Termination	Spent Fuel Management	Site Restoration
	3a.1	Decommissioning Planning and Design - Unit 1	1,493	45	-	-	231	1,769		-	-
	3a.2	Prepare Integrated Work Sequence and Schedule - Unit 1	161	5	-	-	25	191		-	-
	3a.3	Planning and Design of Site Characterization - Unit 1	1,878	53		105	306	2,343		-	-
	3a.4	Prepare Decommissioning Activity Specifications - Unit 1	5,041	156		-	780	5,977	•	-	-
	3a.5	Prepare Detailed Work Procedures - Unit 1	4,087	126	-	-	632	4,845	4,845	-	-
	3a.6	Prepare License Termination Plan - Unit 1	965	15	-	667	247	1,894	1,894	-	-
	3a.7	Design Containment and Misc System Modifications - Unit 1	183	-	-	-	27	210	210	-	-
	3a.8	Purchase Dry Storage Modules for Unit 1 GTCC Waste	-	-	7,062	-	1,059	8,121	8,121	-	-
3a Total	Decom	missioning Planning	13,808	401	7,062	772	3,306	25,350	25,350	-	-
	3b.1	Mobilize Decommissioning General Contractor		_		1,300	195	1,495	1,495		
	3b.1 3b.2	Perform Asbestos Abatement of Pipe Insulation - Unit 1	3,371	104	-	1,300		4,344		-	-
	3b.2 3b.3	Implement Temporary Power Upgrades - Unit 1	996	937		-	869 290	4,344 2,224		-	-
		Construct Misc Building Modifications, In-Plant Laydown Areas		508	-	-				-	-
	3b.4	,	2,881			-	508	3,897		-	-
	3b.5	Modify Containment Access - Unit 1	2,137	377		2.000	377	2,892		-	-
	3b.6	Transportation Infrastructure Modifications	89	447		2,089	394	3,019		-	-
Ob Tabel	3b.7	Procure Waste Handling & Processing Tents			<u>-</u>	1,739	261	2,000		<u>-</u>	-
3b Total	Decomi	missioning Transition and Preparations	9,475	2,374	-	5,127	2,894	19,870	19,870	-	-
	3c.1	Design and Procure Special Equipment	_	29,000	_	-	5,800	34,800	34,800	-	_
	3c.2	Test Special Cutting and Handling Equipment and Train Operators	2,263		_	70	467	2,800		_	_
	3c.3	Finalize Internals and Vessel Segmentation Details - Unit 1	525	_	_	-	105	630		_	_
	3c.4	Segment, Package and Ship Reactor Internals - Unit 1	5,672	2,100	8,974	_	3,349	20,094		_	_
	3c.5	Segment, Package and Ship RPV - Unit 1	1,345	1,030		_	475	2,850		_	_
3c Total		· Vessel Removal	9,804	32,130		70		61,173	-	-	-
					*						
	3d.1	Heavy Lift / Transfer Equipment		3,245	-	-	649	3,893	3,893	-	-
	3d.2	Remove and Dispose of Steam Generators - Unit 1	1,368	163	-	-	306	1,836	1,836	-	-
	3d.3	Remove and Dispose of Pressurizer - Unit 1	188	22	-	-	42	251	251	-	-
	3d.4	Remove and Dispose of Reactor Coolant Pipe - Unit 1	506	35	-	-	108	649	649	-	-
	3d.5	Remove and Dispose of Reactor Coolant Pumps - Unit 1	519	59	-	-	116	694	694	-	-
	3d.6	Large Component Disposal	-	-	15,209	-	3,042	18,251	18,251	-	-
3d Total	Large Co	omponent Removal	2,581	3,523	15,209	-	4,263	25,575	25,575	-	-
				_							
	3e.1	Remove and Dispose of Spent Fuel Storage Racks	66	20	-	-	17	102	102	-	-
	3e.2	Segment, Package and Dispose of Spent Fuel Pool Island Equipment	207	20	-	-	45	272	272	-	-
	3e.3	Decon/Surgical Removal Containment Building - Unit 1	1,066	130	-	-	239	1,435	1,435	-	-

Florida Power and Light St. Lucie Unit 1

Scenario 2 - SAFSTOR

Period	Item Number	Item Description	Labor Cost	Materials & Equipment	Waste Transportation & Disposal	Other Direct Cost (ODC)	Contingency	Total Cost (Estimated)	License Termination	Spent Fuel Management	Site Restoration
	3e.4	Decon/Surgical Removal Fuel Building	542	21	-	-	112	675	675	-	
	3e.5	Decon/Surgical Remvoal Auxiliary Building Unit 1	3,017	287	-	-	661	3,965	3,965	-	
	3e.6	Oversize Debris / Containerized Debris Disposal	-	-	3,885	-	777	4,661	4,661	-	
3e Total	Plant De	econtamination & Interior Rad Demolition	4,897	477	3,885	-	1,852	11,110	11,110	-	
	3f.1	Demolish Fuel Building	247	538	-	-	157	942	942	-	
	3f.2	Demolish Auxiliary Building	1,552	4,131	-	-	1,137	6,820	6,820	-	
	3f.3	Demolish Unit 1 Containment Building	1,940	6,120	-	-	1,612	9,673	9,673	-	
	3f.4	Contaminated Soil	661	992	55,805	-	11,492	68,949	68,949	-	
	3f.5	Debris Disposal	-	-	78,433	-	15,687	94,120	94,120	-	
3f Total	Rad Buil	lding Demolition	4,402	11,781	134,238	-	30,084	180,505	180,505	-	
	3g.1	Final Status Survey for Structures	5,753	54	-	227	1,207	7,240	7,240	-	
	3g.2	Final Status Survey for Land Areas (inlcuded in structures)	-	-	-	-	-	-	-	-	
3g Total	License	Termination Activities	5,753	54	-	227	1,207	7,240	7,240	-	
	3h.1	Utility Staff	31,375	-	-	-	4,706	36,081	36,081	-	
	3h.2	Security Guard Force	1,937	-	-	-	291	2,228	2,228	-	
	3h.3	General Contractor Staff	67,660	-	-	-	10,149	77,809	77,809	-	
	3h.4	Property Taxes	-	-	-	247	37	284	284	-	
	3h.5	Insurance	-	-	-	2,582	387	2,969	2,969	-	
	3h.6	Corporate Support	4,813	-	-	-	722	5,535	5,535	-	
	3h.7	Utility Staff HP Supplies	-	5,180	-	-	777	5,957	5,957	-	
	3h.8	NRC Inspection Fee	-	-	-	667	100	767	767	-	
	3h.9	Licensing Fees	-	-	-	1,032	155	1,187	1,187	-	
	3h.10	County Fees	-	-	-	-	-	-	-	-	
	3h.11	FEMA Fees	-	_	-	-	-	-	-	-	
	3h.12	Materials and Services	-	2,043	-	-	306	2,349	2,349	-	
	3h.13	Energy	-	_	-	3,319	498	3,817	3,817	-	
	3h.14	DGC HP Supplies	-	5,132	-	-	770	5,902		-	
	3h.15	Florida LLRW Inspection Fee	-	-	-	4,121	618	4,739			
	3h.16	EPRI Membership Fees	-	-	-	-	-	-	-	-	
	3h.16	NEI Membership Fees	-	-	-	-	-	-	-	-	
	3h.17	INPO Membership Fees	-	-	-	-	-	-	-	-	
3h Total		ibuted Costs for Decommissioning & License Termination	105,785	12,354	-	11,967	19,516	149,623	149,623	-	
levied 2 T-	+al	DECOMMUSCIONING & LICENSE TERMINATION	450 505	62.003	460.363	40.464	72 247	400 440	400 440		
Period 3 To	tal	DECOMMISSIONING & LICENSE TERMINATION	156,505	63,093	169,368	18,164	73,317	480,446	480,446	-	

Florida Power and Light St. Lucie Unit 1

Scenario 2 - SAFSTOR

(thousands of 2020 dollars)													
Period	Item Number	Item Description	Labor Cost	Materials & Equipment	Waste Transportation & Disposal	Other Direct Cost (ODC)	Contingency	Total Cost (Estimated)	License Termination	Spent Fuel Management	Site Restoration		
	4a.1	Demo Turbine Pedastal and Turbine Deck	3,466	1,377	-	-	726	5,569	-	-	5,569		
	4a.2	Demo Intake & CWS	1,776	1,184	-	-	444	3,405	-	-	3,405		
	4a.3	Demo Tank Foundations	11	229	-	-	36	276	-	-	276		
	4a.4	Demo Misc Site Structures	1,393	1,147	-	-	381	2,921	-	-	2,921		
	4a.5	Security Improvements	536	459	-	-	149	1,144	-	-	1,144		
	4a.6	Clean Concrete Processing	-	-	-	1,677	252	1,928	-	-	1,928		
	4a.7	Demo Site Paving	339	791	-	-	169	1,299	-	-	1,299		
	4a.8	Clean Debris Disposal / Recycle	-	-	123	-	19	142	-	-	142		
4a Total	Clean B	uilding & Site Demolition	7,520	5,187	123	1,677	2,176	16,683	-	-	16,683		
	4h 1	Dragova Cita Dagtavatian Equipment		725			110	946			0.47		
	4b.1	Procure Site Restoration Equipment	-	735	-	-	110		-	-	846		
4h Tatal	4b.2	Finish Grading and Re-Vegetate Site	690	725			103		-		793		
4b Total	Site Kes	storation	690	735	-	-	214	1,639	-	-	1,639		
	4c.1	Utility Staff	2,362	-	-	_	354	2,716	-	-	2,716		
	4c.2	Security Guard Force	146	_	-	_	22			-	168		
	4c.3	General Contractor Staff	5,093	_	-	_	764		_	-	5,857		
	4c.4	Property Taxes	-	_	-	19	3	21	_	-	21		
	4c.5	Insurance	-	_	-	194	29		_	-	223		
	4c.6	Corporate Support	362	-	-	_	54		-	-	417		
	4c.7	Energy	-	-	-	250	37	287	-	-	287		
	4c.8	Materials and Services	-	154	-	_	23		-	-	177		
	4c.9	County Fees	-	-	-	-	-	-	-	-	-		
	4c.10	FEMA Fees	-	-	-	-	-	-	-	-	-		
4c Total	Undistr	ibuted Costs for Site Restoration	7,962	154	-	463	1,287	9,866	-	-	9,866		
Period 4 To	tal	SITE RESTORATION	16,172	6,076	123	2,140	3,677	28,188		-	28,188		
renou 4 10	tai	SIL RESTORATION	10,172	0,070	123	2,140	3,077	28,188	-	-	20,100		
	5a.1	Procure Loading & Transfer Equipment (included in Period 1)	-	-	-	-	-	-	-	-	_		
	5a.2	Procedures & Dry Runs (included in Period 1)	-	-	-	_	-	-	-	-	-		
	5a.3	Remove (86) Fuel Casks from ISFSI & Load DOE Transport	6,880	1,720	-	_	1,290	9,890	-	9,890	-		
	5a.4	Spent Fuel Transportation & Disposal (by DOE)	-	-	-	-	-	-	-	, -	-		
5a Total		el Transfer to DOE during SAFSTOR	6,880	1,720	-	-	1,290	9,890	-	9,890	-		
	5b.1	Remove GTCC Casks from ISFSI & Loadout	480	-	-	120	180		780		-		
	5b.2	GTCC Transportation & Disposal	-	-	16,448	-	2,467				-		
5b Total	GTCC W	Vaste Disposition	480	-	16,448	120	2,647	19,695	19,695	-	-		

Florida Power and Light St. Lucie Unit 1

Scenario 2 - SAFSTOR

(triousarius or 2020 dollars)											
Period	Item Number	Item Description	Labor Cost	Materials & Equipment	Waste Transportation & Disposal	Other Direct Cost (ODC)	Contingency	Total Cost (Estimated)	License Termination	Spent Fuel Management	Site Restoration
	5c.1	Utility Staff	9,318	-	-	-	1,398	10,716	-	10,716	-
	5c.2	Security Guard Force	33,756	-	-	-	5,063	38,820	-	38,820	-
	5c.3	General Contractor Staff	-	-	-	-	-	-	-	-	-
	5c.4	Property Taxes	-	-	-	-	-	-	-	-	-
	5c.5	Insurance	-	-	-	-	-	-	-	-	-
	5c.6	Corporate Support	-	-	-	-	-	-	-	-	-
	5c.7	Utility Staff HP Supplies	-	-	-	-	-	-	-	-	-
	5c.8	NRC Inspection Fee	-	-	-	-	-	-	-	-	-
	5c.9	Licensing Fees	-	-	-	-	-	-	-	-	-
	5c.10	County Fees	-	-	-	-	-	-	-	-	-
	5c.11	FEMA Fees	-	-	-	-	-	-	-	-	-
	5c.12	Energy	-	-	-	-	-	-	-	-	-
	5c.13	Materials and Services	-	-	-	-	-	-	-	-	-
	5c.14	ISFSI Operating Costs	-	-	-	2,135	320	2,455	-		-
5c Total	Undistr	ibuted Costs for Dry Fuel / GTCC Storage & Transfer	43,075	-	-	2,135	6,781	51,991	-	51,991	-
Period 5 To	tal	DRY FUEL / GTCC STORAGE & TRANSFER	50,435	1,720	16,448	2,255	10,719	81,576	19,695	61,881	-
			-					100		4.00	
		Preparation and NRC Review of License Termination Plan	67	-		96		188	-		-
6a Total	ISFSI D8	&D Planning & Preparations	67	-	-	96	24	188	-	188	-
	Ch 1	Class Domalities of ICCCI	1.075	0.50			440	2 272		2 272	
	6b.1	Clean Demolition of ISFSI	1,975	958		-	440	3,372	-	3,372	-
Ch Total	6b.2	Demolition of ISFSI Support Structures	359	141		<u>-</u>	75 515	575	-		-
6b Total	isrsi an	d Support Structure Clean Demolition	2,334	1,099	-	-	212	3,947	-	3,947	-
	66.1	Verification Surveys	122	22			າວ	170		178	
	6c.1 6c.2	Preparation of Final Report on Decommissioning and NRC Review	67	33	·	-	23	178 77	-	77	-
6c Total		nal Status Surveys	189	33	<u>-</u>	<u> </u>	10 33		-		
oc rotar	13731 711	iai Status Sul Veys	103	33	-		33	233	-	233	-
	6d.1	Utility Staff	318	_	_	_	48	365	_	365	_
	6d.2	Security Guard Force	152	-	_		23	175		475	_
	6d.3	General Contractor Staff	1,999	_	_	_	300			2 200	_
	6d.4	Property Taxes	-,555	_	_	44	7	51	_	F.4	_
	6d.5	Insurance	-	_	_	25	, Д	29	_	29	_
	6d.6	Corporate Support	-	-	_	-	- 1		_	-	_
	6d.7	Utility Staff HP Supplies	_	_	_	_	_	_ [_	_	
	6d.8	Materials and Services	_	_	_	_	_	_ [_	_	_
	6d.9	Energy	_	_	_	36	5	42	_	42	
I	ou.5	LIICIBY	-	-	-	30	اد	42	·	42	- 1

Florida Power and Light St. Lucie Unit 1

Scenario 2 - SAFSTOR

Period	Item Number	Item Description	Labor Cost	Materials & Equipment	Waste Transportation & Disposal	Other Direct Cost (ODC)	Contingency	Total Cost (Estimated)	License Termination	Spent Fuel Management	Site Restoration
	6d.10	NRC Inspection Fee	-	-	-	56	8	64	-	64	-
	6d.11	Licensing Fees	-	-	-	86	13	99	-	99	-
	6d.12	County Fees	-	-	-	-	-	-	-	-	-
	6d.13	FEMA Fees	-	-	-	-	-	-	-	-	-
6d Total	Undistri	buted Costs for ISFSI Decommissioning	2,469	-	-	247	407	3,123	-	3,123	-
Period 6 Tot	al	ISFSI DECOMMISSIONING	5,059	1,131	-	343	980	7,514	-	7,514	-
							•	`			
GRAND TO	TAL		418,139	132,420	185,939	104,159	131,867	972,525	677,793	266,544	28,188

Florida Power and Light St. Lucie Unit 2 Scenario 2 - SAFSTOR

				(20	1381103 01 2020 00						
Period	Item Number	Item Description	Labor Cost	Materials & Equipment	Waste Transportation & Disposal	Other Direct Cost (ODC)	Contingency	Total Cost (Estimated)	License Termination	Spent Fuel Management	Site Restoration
1a Total	Dlannin	ng Prior to Shutdown (by Plant Operations)		-	-		_	_	_	_	_
Ta Total	Fiailiiii	ig Frior to Shutdown (by Flant Operations)	<u>-</u>	<u> </u>	<u>-</u>	<u>-</u>	_	_		<u>-</u>	_
1b Total	Unit 1 P	Post Shutdown Planning & Engineering	_	-	-	-	_	_	_	_	-
20 1000	<u> </u>										
1c Total	Unit 1 I	Post Shutdown Deactivation & Modifications	-	-	-	-	-	-	-	-	-
1d Total	Unit 1 V	Vet Fuel Transfer to DOE prior to SAFSTOR	-	-	-	-	-	-	-	-	-
	1e.1	Admin Activities in Preparation for Decommissioning - Unit 2	786	23	-	-	121	930	930	-	-
	1e.2	Preparation of PSDAR and Licensing Documents - Unit 2	178	6	-	-	28	211	211	-	-
	1e.3	Engineering Activities in Preparation for Decommissioning - Unit 2	1,008	31	-	-	156	1,196	1,196	-	-
1e Total	Unit 2 P	Post Shutdown Planning & Engineering	1,972	60	-	-	305	2,337	2,337	-	-
	1f.1	Defuel Reactor Unit 2 (by Plant Operations)	-	-	-	-	-	-	-	-	-
	1f.2	Fuel Sampling & Inspections (by Plant Operations)	-	-	-	-	-	-	-	-	-
	1f.3	Spent Fuel Pool System Modifications - Unit 2	6,868	1,212	-	-	1,212	9,292	-	9,292	-
	1f.4	Implement Cold & Dark - Unit 2	3,508	630	-	-	621	4,759	4,759	-	-
	1f.5	Perform Pre-SAFSTOR Baseline Radiation Survey - Unit 2	1,210	37	-	-	187	1,434		-	-
1f Total	Unit 2 S	hutdown Preparations & Deactivation	11,586	1,880	-	-	2,020	15,485	6,193	9,292	-
	1g.1	Provide Transfer Casks (supplied by DOE)	-	-	-	-	-	-	-	-	-
	1g.2	Procure Spent Fuel Loading & Transfer Equipment	-	1,463	-	-	219	1,683	-	1,683	-
	1g.3	Procedures & Dry Runs	335	-	-	168	75	578	-	578	-
	1g.4	Remove (256) Fuel Assemblies from Pool & Load DOE Casks	1,280	280	-	-	312	1,872	-	1,872	-
	1g.5	Dry, Close & Inspect (8) DOE supplied Casks	640	160	-	-	160	960	-	960	-
	1g.6	Load Out (8) Casks to DOE Transport	640	160	-	-	160	960	-	960	-
4 = 1 1	1g.7	Spent Fuel Transportation & Disposal (by DOE)	-	-	-	-	-	-	-	-	-
1g Total	Unit 2 V	Net Fuel Transfer to DOE prior to SAFSTOR	2,895	2,063	-	168	927	6,053	-	6,053	-
	1h 1	Dravida Transfer Casks (21)		10 520			2 704	24 240		21 210	
	1h.1	Provide Transfer Casks (21)	-	18,538	-	-	2,781	21,318	-	21,318	-
	1h.2	Procure Spent Fuel Loading & Transfer Equipment	-	-	-	160	-		-	-	-
	1h.3	Procedures & Dry Runs Romanyo (672) Fuel Assemblies from Roal & Load Casks	335	- 940	-	168	75 840	578 5.040	-	578 5.040	-
	1h.4	Remove (672) Fuel Assemblies from Pool & Load Casks	3,360	840	-	-	840	5,040		5,040	-
	1h.5	Dry, Close & Inspect (21)	1,680	420	-	-	420	2,520		2,520	-
	1h.6	Load Out (21) Casks to Transport	1,680	420	-	-	420	2,520	-	2,520	-
1h Total	1h.7	Spent Fuel Transportation & Disposal (by DOE) Vet Fuel Transfer to ISFSI prior to SAFSTOR	7 055	20 210	-	168	4 526	21 076	-	21 076	-
1h Total	UIIIL Z V	vet ruei mansier to isrsi prior to sarsitor	7,055	20,218	-	108	4,536	31,976	-	31,976	-

Florida Power and Light St. Lucie Unit 2

Scenario 2 - SAFSTOR

				(tnoi	usands of 2020 do	nars)					
Period	Item Number	Item Description	Labor Cost	Materials & Equipment	Waste Transportation & Disposal	Other Direct Cost (ODC)	Contingency	Total Cost (Estimated)	License Termination	Spent Fuel Management	Site Restoration
	1i.1	Utility Staff	67,101	_	_	_	10,065	77,167	61,733	15,433	_
	1i.2	Security Guard Force	40,615	_	_	_	6,092	46,707	14,012	32,695	_ !
	1i.3	General Contractor Staff	-	_	-	_	-	-		-	_
	1i.4	Property Taxes	-	-	-	177	27	203	163	41	_
	1i.5	Insurance	-	-	-	6,848	1,027	7,875	6,300	1,575	_ '
	1i.6	Corporate Support	881	-	-	, -	132	1,013	304	709	-
	1i.7	Utility Staff HP Supplies	-	403	-	-	61	464	139	325	-
	1i.8	NRC Inspection Fee	-	-	-	2,224	334	2,558	2,558	-	-
	1i.9	Licensing Fees	-	-	-	688	103	791	791	-	_ '
	1i.10	Materials and Services	-	719	-	-	108	827	248	579	_ !
	1i.11	Energy	-	-	-	730	109	839	671	168	- '
	1i.12	EPRI Membership Fees	-	-	-	-	-	-	-	-	-
	1i.13	NEI Membership Fees	-	-	-	-	-	-	-	-	-
	1i.14	County Fees	-	-	-	2,049	307	2,356	1,885	471	-
	1i.15	FEMA Fees	-	-	-	1,079	162	1,241	993	248	-
	1i.16	INPO Membership Fees	-	-	-	-	-	-	-	-	-
	1i.17	ISFSI Maintenance Cost	-	67	-	-	10	77	-	77	_ '
	1i.18	Spent Fuel Maintenance	784	87	-	-	131	1,002	-	1,002	
1i Total	Undistr	ibuted Costs for Shutdown & Transition	109,382	1,277	-	13,794	18,668	143,120	89,797	53,323	-
Davis d 4	T-4-1	CHUTDOWN & TRANSITION	422.000	25 407		44.420	26.455	400.073	00 220	100.644	
Period 1	Total	SHUTDOWN & TRANSITION	132,890	25,497	-	14,129	26,455	198,972	98,328	100,644	-
2a Total	Unit 1 V	Wet Fuel Transfer to DOE during SAFSTOR	-	-	-	-	-	-	-	-	-
2b Total	Unit 1 V	Wet Fuel Transfer to ISFSI during SAFSTOR	-	-	-	-	-	-	-	-	-
		<u> </u>									
2c Total	Unit 1 D	Dormancy during Dry Fuel Storage	-	-	-	-	-	-	-	-	-
	2d.1	Utility Staff	10,614	-	-	-	1,061	11,675	5,254	6,421	-
	2d.2	Security Guard Force	4,945	-	-	-	494	5,439		5,439	-
	2d.3	General Contractor Staff	-	-	-	-	-	-	-	-	-
	2d.4	Property Taxes	-	-	-	1,105	110	1,215	547	668	-
	2d.5	Insurance	-	-	-	19,522	1,952	21,474	9,663	11,811	-
	2d.6	Corporate Support	9,222	-	-	-	922	10,145	4,565	5,580	-
	2d.7	Utility Staff HP Supplies	-	2,795	-	-	280	3,075	1,384	1,691	-
									Ī		
	2d.8	NRC Inspection Fee	-	-	-	2,780	278	3,058	1,376	1,682	-

Florida Power and Light St. Lucie Unit 2

Scenario 2 - SAFSTOR

				(thoi	isands of 2020 do	liais)					
Period	Item Number	Item Description	Labor Cost	Materials & Equipment	Waste Transportation & Disposal	Other Direct Cost (ODC)	Contingency	Total Cost (Estimated)	License Termination	Spent Fuel Management	Site Restoration
	2d.10	County Fees	-	-	-	-	-	-	-	-	-
	2d.11	FEMA Fees	-	-	-	-	-	-	-	-	-
	2d.12	EPRI Membership Fees	-	-	-	-	-	-	-	-	-
	2d.13	NEI Fees	-	-	-	-	-	-	-	-	-
	2d.14	INPO Membership Fees	-	-	-	-	-	-	-	-	-
	2d.15	Materials and Services	-	5,602	-	-	560	6,162	2,773	3,389	-
	2d.16	Energy	-	-	-	2,944	294	3,239	1,457	1,781	-
2d Total	Unit 2 D	Pormancy during Dry Fuel Storage	24,781	8,397	-	30,650	6,383	70,211	29,147	41,064	-
	2e.1	Utility Staff	7,642	-	-	-	764	8,406	8,406	-	-
	2e.2	Security Guard Force	3,560	-	-	-	356	3,916	3,916	-	-
	2e.3	General Contractor Staff	-	-	-	-	-	-	-	-	-
	2e.4	Property Taxes	-	-	-	839	84	923	923	-	-
	2e.5	Insurance	-	-	-	8,790	879	9,669	9,669	-	-
	2e.6	Corporate Support	2,660	-	-	-	266	2,926	2,926	-	-
	2e.7	Utility Staff HP Supplies	-	974	-	-	97	1,071	1,071	-	-
	2e.8	NRC Inspection Fee	-	-	-	2,113	211	2,324	2,324	-	-
	2e.9	Licensing Fees	-	-	-	3,268	327	3,595	3,595	-	-
	2e.10	County Fees	-	-	-	-	-	-	-	-	-
	2e.11	FEMA Fees	-	-	-	-	-	-	-	-	-
	2e.12	EPRI Membership Fees	-	-	-	-	-	-	-	-	-
	2e.13	NEI Fees	-	-	-	-	-	-	-	-	-
	2e.14	INPO Membership Fees	-	-	-	-	-	-	-	-	-
	2e.15	Materials and Services	-	2,326	-	-	233	2,559	2,559	-	-
	2e.16	Energy	-	-	-	1,102	110	1,212	1,212	-	-
2e Total	Dormar	ncy only	13,862	3,300	-	16,112	3,327	36,602	36,602	-	-
Period 2	Total	SAFSTOR	38,642	11,698	-	46,763	9,710	106,813	65,749	41,064	-
	3a.1	Decommissioning Planning and Design - Unit 2	1,493	45		-	231	1,769	1,769	-	-
	3a.2	Planning and Design of Site Characterization - Unit 2	1,409	53	-	105	235	1,803	1,803	-	-
	3a.3	Prepare Integrated Work Sequence and Schedule - Unit 2	161	5	-	-	25	191	191	-	-
	3a.4	Prepare Decommissioning Activity Specifications - Unit 2	2,158	67	-	-	334	2,558			-
	3a.5	Prepare License Termination Plan - Unit 2	965	-	-	667	245	1,877	1,877	-	-
	3a.6	Prepare Detailed Work Procedures for Decommissioning - Unit 2	1,749	54	-	-	270	2,073	2,073	-	-
	3a.7	Design Containment and Misc System Modifications - Unit 2	79	-	-	-	12	91	91	-	-
	3a.8	Purchase Dry Storage Modules for Unit 2 GTCC Waste	-	-	7,062	-	1,059	8,121	8,121	-	-
3a Total	Decomr	missioning Planning	8,013	224	7,062	772	2,411	18,482	18,482	<u>-</u>	-

Florida Power and Light St. Lucie Unit 2

Scenario 2 - SAFSTOR

				(110)	1301103 01 2020 00	110131					
Period	Item Number	Item Description	Labor Cost	Materials & Equipment	Waste Transportation & Disposal	Other Direct Cost (ODC)	Contingency	Total Cost (Estimated)	License Termination	Spent Fuel Management	Site Restoration
	_										
	3b.1	Mobilize Decommissioning General Contractor	-	-	-	1,300	195	1,495	1,495	-	-
	3b.2	Perform Asbestos Abatement of Pipe Insulation - Unit 2	-	-	-	-	-	-	-	-	-
	3b.3	Implement Temporary Power Upgrades - Unit 2	996	937	-	-	290	2,224	2,224	-	-
	3b.4	Construct Misc Building Modifications, In-Plant Laydown Areas	3,287	102	-	-	508	3,897	3,897	-	-
	3b.5	Modify Containment Access - Unit 2	2,439	75	-	-	377	2,892	2,892	-	-
	3b.6	Transportation Infrastructure Modifications	60	298	-	1,393	263	2,013	2,013	-	-
	3b.7	Procure Waste Handling & Processing Tents	-	-	-	1,476	221	1,697	1,697		
3b Total	Decomr	missioning Transition and Preparations	6,782	1,412	-	4,168	1,854	14,217	14,217	-	-
	3c.1	Design and Procure Special Equipment	_	27,050	_	_	5,410	32,460	32,460	_	_
	3c.1	Test Special Cutting and Handling Equipment and Train Operators	1,924	27,030	_	70	399	2,392	2,392	_	_
	3c.3	Finalize Internals and Vessel Segmentation Details - Unit 2	447		_	70	89	536	536	_	_
	3c.4	Segment, Package and Ship Reactor Internals - Unit 2	5,672	2,100	8,999	_	3,354	20,125	20,125	_	_
	3c.5	Segment, Package and Ship RPV - Unit 2	1,345	1,030	-	_	475	2,850	2,850	_	_
3c Total		Vessel Removal	9,386	30,180	8,999	70	9,727	58,363	58,363	-	_
00100	1100001		2,000	20,200	3,555		0,: =:	20,000	20,000		
	3d.1	Heavy Lift / Transfer Equipment		3,245	-	-	649	3,893	3,893	-	-
	3d.2	Remove and Dispose of Steam Generators - Unit 2	1,368	163	-	-	306	1,836	1,836	-	-
	3d.3	Remove and Dispose of Pressurizer - Unit 2	188	22	-	-	42	251	251	-	-
	3d.4	Remove and Dispose of Reactor Coolant Pipe - Unit 2	506	35	-	_	108	649	649	-	-
	3d.5	Remove and Dispose of Reactor Coolant Pumps - Unit 2	519	59	-	-	116	694	694	-	-
	3d.6	Large Component Disposal	-	-	15,091	-	3,018	18,109	18,109	-	-
3d Total	Large Co	omponent Removal	2,581	3,523	15,091	-	4,239	25,433	25,433	-	-
	3e.1	Remove and Dispose of Spent Fuel Storage Racks	66	20	-	-	17	102	102	-	-
	3e.2	Segment, Package and Dispose of Spent Fuel Pool Island Equipment	207	62	-	-	54	322	322	-	-
	3e.3	Decon/Surgical Removal Containment Building - Unit 2	1,066	130	-	-	239	1,435	1,435	-	-
	3e.4	Decon/Surgical Removal Fuel Building - Unit 2	542	21	-	-	112	675	675	-	-
	3e.5	Decon/Surgical Remvoal Auxiliary Building Unit 2	3,017	287	-	-	661	3,965	3,965	-	-
	3e.6	Oversized Debris / Containerized Debris Disposal	-	-	3,885	-	777	4,661	4,661	-	
3e Total	Plant De	econtamination & Interior Rad Demolition	4,897	519	3,885	-	1,860	11,161	11,161	-	-
	25.1		2.1-								
	3f.1	Demolish Fuel Building	247	538	-	-	157	942	942	-	-
	3f.2	Demolish Auxiliary Building	1,552	4,131	-	-	1,137	6,820	6,820	-	-
	3f.3	Demolish Unit 2 Containment Building	1,940	6,120		-	1,612	9,673	9,673	-	-
	3f.4	Contaminated Soil	614	922	•	-	10,606	63,636		-	-
ı	3f.5	Debris Disposal	-	-	75,932	-	15,186	91,119	91,119	-	-

Florida Power and Light St. Lucie Unit 2

Scenario 2 - SAFSTOR

-				(tho	usands of 2020 do	iars)					
Period	Item Number	Item Description	Labor Cost	Materials & Equipment	Waste Transportation & Disposal	Other Direct Cost (ODC)	Contingency	Total Cost (Estimated)	License Termination	Spent Fuel Management	Site Restoration
3f Total	Rad Bui	lding Demolition	4,355	11,711	127,426	-	28,698	172,190	172,190	-	-
	3g.1	Final Status Survey for Structures	5,753	54	-	227	1,207	7,240	7,240	-	-
	3g.2	Final Status Survey for Land Areas (inlcuded in structures)	-	-	-	-	-	-	-	-	-
3g Total	License	Termination Activities	5,753	54	-	227	1,207	7,240	7,240	-	-
	2h 1	Hailian Canff	24 275				4.700	26 004	26.001		
	3h.1	Utility Staff	31,375	-	-	-	4,706	36,081	36,081	-	-
	3h.2	Security Guard Force	1,937	-	-	-	291	2,228		-	-
	3h.3	General Contractor Staff	67,660	-	-	- 247	10,149	77,809	77,809 284	-	-
	3h.4 3h.5	Property Taxes	-	-	-		37	284		-	-
	3h.6	Insurance Corporate Support	- 4,541	-	-	2,582	387 681	2,969 5,222	2,969 5,222	-	-
	3h.7	Utility Staff HP Supplies	4,541	- 6,677	-	-	1,002	7,679		-	-
	3h.8	NRC Inspection Fee	-	0,077	-	- 667	1002	7,079 767	7,079	-	-
	3h.9	Licensing Fees	-	-	-	1,032	155	1,187	1,187	-	-
	3h.10	County Fees	_		_	1,032	133	1,107	1,187	_	_
	3h.11	FEMA Fees	_	_	_	_	_	_	_	_	_
	3h.12	Materials and Services	_	1,880	_	_	282	2,162	2,162	_	_
	3h.13	Energy	_	-	-	3,507	526	4,033		_	_
	3h.14	DGC HP Supplies	_	5,132	_	-	770	5,902	5,902	-	_
	3h.15	Florida LLRW Inspection Fee	_	-	-	3,939	591	4,530		-	_
	3h.16	EPRI Membership Fees	_	_	_	-	-	-	-	-	_
	3h.17	NEI Membership Fees	-	-	-	_	_	-	-	-	-
	3h.18	INPO Membership Fees	-	-	-	-	-	-	-	-	-
3h Total		buted Costs for Decommissioning & License Termination	105,513	13,690	-	11,973	19,676	150,852	150,852	-	-
			•								
Period 3	Гotal	DECOMMISSIONING & LICENSE TERMINATION	147,280	61,312	162,463	17,210	69,673	457,938	457,938	-	-
	4a.1	Demo Turbine Pedastal and Turbine Deck	3,454	1,377	-	-	725	5,555	-	-	5,555
	4a.2	Demo Intake & CWS	1,830	1,220	-	-	457	3,507	-	-	3,507
	4a.3	Demo Primary Water Tank Foundation	11	92	-	-	15	118	-	-	118
	4a.4	Demo Misc Site Structures	5,795	1,147	-	-	1,041	7,984	-	-	7,984
	4a.5	Demo Security Improvements	536	459	-	-	149	1,144	-	-	1,144
	4a.6	Demo Steam Generator Blowdown Treatment	585	138	-	-	108	831	-	-	831
	4a.7	Clean Concrete Processing	-	-	-	2,428	364	2,792	-	-	2,792
	4a.8	Demo Site Paving	339	791	-	-	169	1,299	-	-	1,299
	4a.9	Clean Debris Disposal / Recycle	-	-	136	-	20	156		-	156
4a Total	Clean B	uilding & Site Demolition	12,549	5,223	136	2,428	3,050	23,385	-	-	23,385

Florida Power and Light St. Lucie Unit 2

Scenario 2 - SAFSTOR

				(1100	1381103 01 2020 00	ilai 3 j					
Period	Item Number	Item Description	Labor Cost	Materials & Equipment	Waste Transportation & Disposal	Other Direct Cost (ODC)	Contingency	Total Cost (Estimated)	License Termination	Spent Fuel Management	Site Restoration
			<u>'</u>								
	4b.1	Procure Site Restoration Equipment	-	490	-	-	74	564	-	-	564
	4b.2	Finish Grading and Re-Vegetate Site	460	26	-	_	73	558		-	558
4b Total	Site Res	storation	460	516	-	-	146	1,122	-	-	1,122
	4c.1	Utility Staff	2,362	-	-	-	354	2,716	-	-	2,716
	4c.2	Security Guard Force	146	-	-	-	22	168	-	-	168
	4c.3	General Contractor Staff	5,093	-	-	-	764	5,857	-	-	5,857
	4c.4	Property Taxes	-	-	-	19	3	21	-	-	21
	4c.5	Insurance	-	-	-	194	29	223	-	-	223
	4c.6	Corporate Support	-	-	-	-	-	-	-	-	-
	4c.7	Energy	-	-	-	136	20	157	-	-	157
	4c.8	Materials and Services	-	230	-	-	34	264	-	-	264
	4c.9	County Fees	-	-	-	-	-	-	-	-	-
	4c.10	FEMA Fees	-	-	-	-	-	-	-	-	-
4c Total	Undistri	ibuted Costs for Site Restoration	7,600	230	-	349	1,227	9,406	-	-	9,406
Davied 4	Tatal	CITE DECTORATION	20.500	F 000	126	2 777	4 422	22.012			22.042
Period 4	TOLAI	SITE RESTORATION	20,609	5,968	136	2,777	4,423	33,913	-	-	33,913
	Fo 1	Duraning Landing O. Tanasfer Freeings and /included in Davied 1)									
	5a.1	Procure Loading & Transfer Equipment (included in Period 1)	-	-	-	-	-	-	-	-	-
	5a.2	Procedures & Dry Runs (included in Period 1)	- - 120	1 200	-	-	- 060	7 260	-	7 260	-
	5a.3 5a.4	Remove (64) Fuel Casks from ISFSI & Load DOE Transport	5,120	1,280	-	-	960	7,360	-	7,360	-
5a Total		Spent Fuel Transportation & Disposal (by DOE) Il Transfer to DOE during SAFSTOR	5,120	1,280		<u> </u>	960	7,360		7,360	-
Sa TOLAI	DI y Fue	i Italisiei to DOE dufflig SAFSTON	5,120	1,200	-	-	960	7,300	-	7,300	-
	5b.1	Remove GTCC Casks from ISFSI & Loadout	480	_	_	120	180	780	780	_	_
	5b.1	GTCC Transportation & Disposal	480	_	16,448		2,467	18,915			
5b Total		/aste Disposition	480	_	16,448		2,647	19,695			_
35 10tai	Citc ii	auto Disposition	400		20,110	120	2,047	13,033	13,033		
	5c.1	Utility Staff	9,318	-	_	_	1,398	10,716	_	10,716	_
	5c.2	Security Guard Force	33,756	-	_	_	5,063	38,820		38,820	-
	5c.3	General Contractor Staff	-	-	_	-	-	-	_	-	_ [
	5c.4	Property Taxes	_	-	_	-	_	-	_	_	_ [
	5c. 1	Insurance	-	-	-	-	_	-	-	-	- [
	5c.6	Corporate Support	-	-	-	-	_	-	-	-	_ [
	5c.7	Utility Staff HP Supplies	_	-	_	_	_	_	_	-	_ [
	5c.8	NRC Inspection Fee	-	-	-	-	-	-	-	-	-
	5c.9	Licensing Fees	-	-	-	_	-	-	-	-	- [
•	_ J. J						I				1

Florida Power and Light St. Lucie Unit 2 Scenario 2 - SAFSTOR

				(1100	isanus or 2020 do	iiai 3)					
Period	Item Number	Item Description	Labor Cost	Materials & Equipment	Waste Transportation & Disposal	Other Direct Cost (ODC)	Contingency	Total Cost (Estimated)	License Termination	Spent Fuel Management	Site Restoration
	5c.10	County Fees	-	-	-	-	-	1	-	-	-
	5c.11	FEMA Fees	-	-	-	-	-	-	-	-	-
	5c.12	Energy	-	-	-	-	-	-	-	-	-
	5c.13	Materials and Services	-	-	-	-	-	-	-	-	-
	5c.14	ISFSI Operating Costs	-	-	-	1,593	239	1,832	-	1,832	-
5c Total	Undistr	ibuted Costs for Dry Fuel / GTCC Storage & Transfer	43,075	-	-	1,593	6,700	51,368	•	51,368	-
Period 5	Total	DRY FUEL / GTCC STORAGE & TRANSFER	48,675	1,280	16,448	1,713	10,307	78,423	19,695	58,728	-
	6a.1	Preparation and NRC Review of License Termination Plan	45	-	-	64	16	125	-	125	-
6a Total	ISFSI D8	&D Planning & Preparations	45	-	-	64	16	125	-	125	1
	6b.1	Clean Demolition of ISFSI	1,316	638	-	-	293	2,248	-	2,248	-
	6b.2	Demolition of ISFSI Support Structures	240	94	-	-	50	384	-	384	-
6b Total	ISFSI an	d Support Structure Clean Demolition	1,556	732	-	-	343	2,632	-	2,632	1
	6c.1	Verification Surveys	81	22	-	-	15	119	-	119	-
	6c.2	Preparation of Final Report on Decommissioning and NRC Review	45	-	-	-	7	52	-	52	-
6c Total	ISFSI Fir	nal Status Surveys	126	22	-	-	22	170	ı	170	1
	6d.1	Utility Staff	318	-	-	-	48	365	-	365	-
	6d.2	Security Guard Force	152	-	-	-	23	175	-	175	-
	6d.3	General Contractor Staff	1,999	-	-	-	300	2,299	-	2,299	-
	6d.4	Property Taxes	-	-	-	44	7	51	-	51	-
	6d.5	Insurance	-	-	-	25	4	29	-	29	-
	6d.6	Corporate Support	-	-	-	-	-	-	-	-	-
	6d.7	Utility Staff HP Supplies	-	-	-	-	-	-	-	-	-
	6d.8	Materials and Services	-	-	-	-	-	-	-	-	-
	6d.9	Energy	-	-	-	36	5	42	-	42	-
	6d.10	NRC Inspection Fee	-	-	-	56	8	64	-	64	-
	6d.11	Licensing Fees	-	-	-	86	13	99	-	99	-
	6d.12	County Fees	-	-	-	-	-	-	-	-	-
	6d.13	FEMA Fees							-		-
6d Total	Undistr	ibuted Costs for ISFSI Decommissioning	2,469	-	-	247	407	3,123	-	3,123	-
								_			
Period 6	Total	ISFSI DECOMMISSIONING	4,196	754	-	311	789	6,050	-	6,050	-
GRAND	TOTAL		392,291	106,510	179,047	82,903	121,358	882,108	641,710	206,485	33,913
					•	•	•	,		•	•

Appendix D-1
Florida Power and Light - St. Lucie Units 1 & 2

Scenario 1 - Unit 1 SAFSTOR, DECON both following Unit 2 Shutdown

Scenario 1 - Unit 1 SAFSTOR, DECON both follo	owing Ur	nit 2 Sh	utdown)																											
2020 Estimated Staff FTEs	2035	2036	2037	2038	2039	2040	2041	2042	2043	2044	2045	2046	2047	2048	2049	2050	2051	2052	2053	2054	2055	2056	2057	2058	2059	2060 / 2069	2070	2071	2072	2073	2074
		♦ U	NIT 1 SI	HUTDO	WN				♦ UI	NIT 2 S	HUTDO	WN						•	DEC	OMMISS	SIONING	& SITE F	RESTORA	ATION C	OMPLET	ГЕ					
U	NIT 1 ZIR	C FIRE E	NDS 🔷				UNI	T 2 ZIRO	C FIRE EN	IDS 🔷		4	UNIT	1 & 2 FL	JEL POC	L EMPT	Υ											•	ISFSI	EMPTY	
Period 1 - Shutdown & Transition	2035	2036	2037	2038	2039	2040	2041	2042	2043	2044	2045	2046	2047	2048	2049	2050	2051	2052	2053	2054	2055	2056	2057	2058	2059	2060 / 2069	2070	2071	2072	2073	2074
Administration		8	8	7	2				12	12	7	4				-	-	-								2000					
 Engineering		40	40	20	12				40	40	20	8																			
Health Physics/Rad Protection		30	30	24	6				30	30	24	20																			
Management		5	5	5	2				5	5	5	3																			
Maintenance & Operations		70	70	40	12				70	60	40	20																			
Quality Assurance		3	3	2	2				3	3	2	1																			
Utility Staff	-	156	156	98	36	-	-	-	160	150	98	56	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
-																													1		
General Contractor Staff	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	<u> </u>	-	-	-
Period 2 - SAFSTOR	2035	2036	2037	2038	2039	2040	2041	2042	2043	2044	2045	2046	2047	2048	2049	2050	2051	2052	2053	2054	2055	2056	2057	2058	2059	2060 / 2069	2070	2071	2072	2073	2074
Administration					1	2	2	2	2	2	2	2				-	-	-								2000					
 Engineering					3	6	6	6	6	6	6	6																			
Health Physics/Rad Protection					3	6	6	6	6	6	6	6																			
Management					1	2	2	2	2	2	2	2																			
Maintenance & Operations					3	6	6	6	6	6	6	6																			
Quality Assurance					1	2	2	2	2	2	2	2																			
Utility Staff	-	-	-	-	12	24	24	24	24	24	24	24	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	1 -
General Contractor Staff	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
Period 3 & 4 - License Term & Site Restoration	2035	2036	2037	2038	2039	2040	2041	2042	2043	2044	2045	2046	2047	2048	2049	2050	2051	2052	2053	2054	2055	2056	2057	2058	2059	2060 / 2069	2070	2071	2072	2073	2074
Administration											4	4	10	12	12	12	12	7	2							2003		-			
Engineering											4	6	16	20	20		20		2												
Health Physics/Rad Protection												4	8	24	24	24	24	16	4												
Management											1	1	4	5	5		4	4	2												
Maintenance & Operations													10	24	24	20	20	8	2												
Quality Assurance											1	1	2	3	3	2	2	2	1												
Utility Staff	-	-	-	-	-	-	-	-	-	-	10	16	50	88	88	82	82	44	13	-	-	-	-	-	-	-	-	-	-	-	1 -
-																												1	1		1
Project Management											2	4	6	10	10	10	10	8	4												
Engineering											4	6	6	12	12	10	10	7	2												
Health Physics/Rad Protection												4	8	16	16		16	12	6												
Administration											2	3	6	12	12	12	12		4												
Maintenance & Operations														-	-	-	-	-	-												
Quality Assurance											1	1	2	4	4	4	4	3	2												
Waste Management												1	2	12	12	12	12	12	4												
General Contractor Staff	-	-	-	-	-	-		-	-	-	9	19	30	66	66	64	64	-	22	-	-	-	-	-	-	-	-	-	-	-	-

Appendix D-1 Florida Power and Light - St. Lucie Units 1 & 2 Scenario 1 - Unit 1 SAFSTOR, DECON both following Unit 2 Shutdown 2060 / 2069 2036 2037 2038 2039 2040 2041 2042 2043 | 2044 | 2045 | 2046 | 2047 | 2048 | 2049 | 2050 | 2051 | 2052 2053 2054 2056 2057 2058 2059 2071 2072 2073 2074 2020 Estimated Staff FTEs 2055 2070 UNIT 1 SHUTDOWN **UNIT 2 SHUTDOWN** DECOMMISSIONING & SITE RESTORATION COMPLETE UNIT 1 ZIRC FIRE ENDS UNIT 2 ZIRC FIRE ENDS UNIT 1 & 2 FUEL POOL EMPTY ISFSI EMPTY 2060 / 2069 2037 2038 2039 2040 2041 2042 2043 2044 2045 2046 2047 Period 5 - Dry Fuel / GTCC Storage & Transfer 2035 2036 2048 2049 2050 2051 2052 2053 2054 2055 2056 2057 2058 2059 2070 2071 2072 2073 2074 Administration Engineering Health Physics/Rad Protection Management Maintenance & Operations 2 2 2 2 2 2 2 Quality Assurance **Utility Staff** 5 5 5 5 5 5 5 5 5 5 5 5 5 5 5 4 5 1 ------**General Contractor Staff** 2035 2036 2038 2039 2040 2041 2042 2043 2044 2045 2046 2047 2048 2049 2050 2051 2052 2053 2054 2058 Period 6 - ISFSI Decommissioning 2037 2055 2056 2057 2059 2070 2071 2072 2073 2074 Administration Engineering Health Physics/Rad Protection Management Maintenance & Operations Quality Assurance **Utility Staff** 4 Project Management Engineering Health Physics/Rad Protection Administration Maintenance & Operations Quality Assurance Waste Management **General Contractor Staff** 4 6

Appendix D-2
Florida Power and Light - St. Lucie Units 1 & 2

Scenario	2 -	ς۸	ECT	1	P
SCEHALIO		ЭА	гэі	u	n

Scenario 2 - SAFSTUR		•				,	•											•								1				
2020 Estimated Staff FTEs	2035	2036	2037	2038	2039	2040	2041	2042	2043	2044	2045	2046	2047	2048	2049	2050	2051	2052	2053	2054	2055	2056	2057	2058	2059	2060	2061	2062	2063	2064
		V U	INIT 1 SH	UTDOW	'N				♦ U	NIT 2 SH	IUTDOW	N																		
			•	UNIT 1	ZIRC FIRE	ENDS	UI	NIT 2 ZIR	C FIRE EN	NDS 🔷			UNIT 1	& UNIT 2	2 FUEL P	OOL EMP	TY													
			Ľ							Ľ		·																		
Period 1 - Shutdown & Transition	2035	2036	2037	2038	2039	2040	2041	2042	2043	2044	2045	2046	2047	2048	2049	2050	2051	2052	2053	2054	2055	2056	2057	2058	2059	2060	2061	2062	2063	2064
Administration		8	8	7	2				12	12	7	4				-	-	-												
Engineering		40	40	20	12				40	40	20	8																		
Health Physics/Rad Protection		30	30	24	6				30	30	24	20																		
Management		5	5	5	2				5	5	5	3																		
Maintenance & Operations		70	70	40	12				70	60	40	20																		
Quality Assurance		3	3	2	2				3	3	2	1																		
Utility Staff	-	156	156	98	36	-	-	-	160	150	98	56	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-		-
General Contractor Staff	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
Period 2 - SAFSTOR	2035	2036	2037	2038	2039	2040	2041	2042	2043	2044	2045	2046	2047	2048	2049	2050	2051	2052	2053	2054	2055	2056	2057	2058	2059	2060	2061	2062	2063	2064
Administration					1	2	2	2	2	2	2	2	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
Engineering					3	6	6	6	6	6	6	6	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
Health Physics/Rad Protection					3	6	6	6	6	6	6	6	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
Management					1	2	2	2	2	2	2	2																		
Maintenance & Operations					3	6	6	6	6	6	6	6	3	3	3	3	3	3	3	3	3	3	3	3	3	3	3	3	3	3
Quality Assurance					1	2	2	2	2	2	2	2																		
Utility Staff	_	_	_	_	12	24	24	24	24	24	24	24	6	6	6	6	6	6	6	6	6	6	6	6	6	6	6	6	6	6
,																	<u> </u>					Ť			Ť					Ť
General Contractor Staff		-	_	_	_	_	-	-	-	-	_	_	_	-	_	_	-	_	-	_	-	_	_	_	_	_	<u> </u>	-	-	_
											1					<u> </u>	1		<u> </u>			1			1		1	<u></u>		<u> </u>
Period 3 & 4 - License Term & Site Restoration	2035	2036	2037	2038	2039	2040	2041	2042	2043	2044	2045	2046	2047	2048	2049	2050	2051	2052	2053	2054	2055	2056	2057	2058	2059	2060	2061	2062	2063	2064
Administration																														
Engineering																														
Health Physics/Rad Protection																														
Management																														
Maintenance & Operations																														
Quality Assurance																														
Utility Staff	_	-	-	-	-	-	-	-	-	-	_	-	-	-	-	-	-	-	-	-	-		-	-		-	-	-		-
•																														
Project Management																														
Engineering																														
Health Physics/Rad Protection																														
Administration																														
Maintenance & Operations																														
Quality Assurance																														
Waste Management																											1			
General Contractor Staff					-	-										-	+	-	 			-		-	-		1	\vdash		-
General Contractor Stall	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-

Appendix D-2
Florida Power and Light - St. Lucie Units 1 &

Scenario 2 - SAFSTOR

Scenario 2 - SAFSTOR																									
2020 Estimated Staff FTEs	2065	2066	2067	2068	2069	2070	2071	2072	2073	2074	2075 / 2084	2085	2086	2087	2088	2089	2090	2091	2092	2093	2094	2095	2096	2097	2098
																DEC	OMMIS	SIONING	& SITE I	RESTORA	TION CC	MPLETE	. 🔷		
							4	ISFSI	EMPTY										IS	FSI DECC	OMMISS	ONING (COMPLET	TE	
Period 1 - Shutdown & Transition	2065	2066	2067	2068	2069	2070	2071	2072	2073	2074	2075 / 2084	2085	2086	2087	2088	2089	2090	2091	2092	2093	2094	2095	2096	2097	2098
Administration																									
Engineering																									
Health Physics/Rad Protection																									
Management																									
Maintenance & Operations																									
Quality Assurance																									
Utility Staff	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
General Contractor Staff	_	_	_	_		_		_		_		_		_	_	_			_		_	_	_	_	<u> </u>
General Contractor Stair	-	-	-	_	-	-	-	-	_	-	-	-	-	-	-	-	-	-	-	-	-	-		<u> </u>	<u> </u>
Period 2 - SAFSTOR	2065	2066	2067	2068	2069	2070	2071	2072	2073	2074	2075 / 2084	2085	2086	2087	2088	2089	2090	2091	2092	2093	2094	2095	2096	2097	2098
Administration	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1									
Engineering	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1									
Health Physics/Rad Protection	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1									
Management																									
Maintenance & Operations	3	3	3	3	3	3	3	3	3	3	3	3	3	3	3	3									
Quality Assurance																									
Utility Staff	6	6	6	6	6	6	6	6	6	6	6	6	6	6	6	6		_	_	_	_	_	_	_	_
General Contractor Staff	_	-	_	-	_	_	_	_	_						_	_		_	_	_	_	_	_	_	_
			1	1	1		I		l .					1					I	1	I				
Period 3 & 4 - License Term & Site Restoration	2065	2066	2067	2068	2069	2070	2071	2072	2073	2074	2075 / 2084	2085	2086	2087	2088	2089	2090	2091	2092	2093	2094	2095	2096	2097	2098
Administration															4	4	10	12	12	12	12	7	2		
Engineering															4	6	16	20	20	20	20	7	2		
Health Physics/Rad Protection																4	8	24	24	24	24	16	4		
Management															1	1	4	5	5	4	4	4	2		
Maintenance & Operations																	10	24	24	20	20	8	2		
Quality Assurance															1	1	2	3	3	2	2	2	1		
Utility Staff	-	-	-	-	-	-	-	-	-	-	-	-	-	-	10	16	50	88	88	82	82	44	13	-	-
Project Management															2	4	6	10	10	10	10	8	4		
Engineering															4	6	6	12	12	10	10	7	2		
Health Physics/Rad Protection																4	8	16	16	16	16	12	6		
Administration															2	3	6	12	12		12	8	4		
Maintenance & Operations																		-	-	-	-	-	-		
Quality Assurance															1	1	2	4	4	4	4	3	2		
																	1								1
Waste Management																1	2	12	12	12	12	12	4		

Appendix D-2
Florida Power and Light - St. Lucie Units 1 & 2

Scenario 2 - SAFSTOR

Scenario 2 - SAFSTOR																														
2020 Estimated Staff FTEs	2035	2036	2037	2038	2039	2040	2041	2042	2043	2044	2045	2046	2047	2048	2049	2050	2051	2052	2053	2054	2055	2056	2057	2058	2059	2060	2061	2062	2063	2064
		• •	JNIT 1 SH	HUTDOW	'N				• u	INIT 2 SH	UTDOW	'N																		
				UNIT 1	ZIRC FIRI	E ENDS	U	NIT 2 ZIF	C FIRE E	NDS 🔷			UNIT 1	& UNIT	2 FUEL P	OOL EMP	TY													
								ļ								ļ														1
Period 5 - Dry Fuel / GTCC Storage & Transfer	2035	2036	2037	2038	2039	2040	2041	2042	2043	2044	2045	2046	2047	2048	2049	2050	2051	2052	2053	2054	2055	2056	2057	2058	2059	2060	2061	2062	2063	2064
Administration																														
Engineering												1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
Health Physics/Rad Protection													1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
Management																														
Maintenance & Operations													2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2
Quality Assurance													1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
Utility Staff	-	-	-	-	-	-	-	-	-	-	-	1	5	5	5	5	5	5	5	5	5	5	5	5	5	5	5	5	5	5
																														<u> </u>
General Contractor Staff	-	-	-	-	-	-	-	-	-	-	-	-	-	-	_	-	-	-	-		-	-	-	-	-	-	-	-	-	-
Period 6 - ISFSI Decommissioning	2035	2036	2037	2038	2039	2040	2041	2042	2043	2044	2045	2046	2047	2048	2049	2050	2051	2052	2053	2054	2055	2056	2057	2058	2059	2060	2061	2062	2063	2064
Administration																														
Engineering																														
Health Physics/Rad Protection																														
Management																														
Maintenance & Operations																														
Quality Assurance																														
Utility Staff	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
				1	1							1				1	1	1				1		ı		1			1	_
Project Management																														
Engineering																														
Health Physics/Rad Protection																														
Administration																														
Maintenance & Operations																														
Quality Assurance																														
Waste Management																														
General Contractor Staff	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	_	-	-	-	-	-	-	-	-	-	-	-	-	-	-

Florida Power and Light - St. Lucie Units 1 &

Scenario 2 - SAFSTOR

Scenario 2 - SAFSTOR																									
2020 Estimated Staff FTEs	2065	2066	2067	2068	2069	2070	2071	2072	2073	2074	2075 / 2084	2085	2086	2087	2088	2089	2090	2091	2092	2093	2094	2095	2096	2097	2098
																DEC	COMMIS	SIONING	& SITE	RESTORA	TION CO	OMPLETE	•		
								ISFSI	EMPTY										15	FSI DEC	OMMISS	IONING	COMPLE	TE 🔷	
																									<u> </u>
Period 5 - Dry Fuel / GTCC Storage & Transfer	2065	2066	2067	2068	2069	2070	2071	2072	2073	2074	2075 / 2084	2085	2086	2087	2088	2089	2090	2091	2092	2093	2094	2095	2096	2097	2098
Administration																									
Engineering	1	1	1	1	1	1	1	1																	
Health Physics/Rad Protection	1	1	1	1	1	1	1	1																	
Management																									
Maintenance & Operations	2	2	2	2	2	2	2	1																	
Quality Assurance	1	1	1	1	1	1	1	1																	
Utility Staff	5	5	5	5	5	5	5	4	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
General Contractor Staff	-	-	-		-	-	-	-	-	-	-	-	-	-	-	-	-		-	-	-	-	-	-	-
Period 6 - ISFSI Decommissioning	2065	2066	2067	2068	2069	2070	2071	2072	2073	2074	2075 /	2085	2086	2087	2088	2089	2090	2091	2092	2093	2094	2095	2096	2097	2098
Administration	2000	2000	200.	2000	2000	20.0	2011		20.0	207.	2084	2000	2000	200.	2000	2000	2000	200.	2002	2000	200.	2000	2000	2001	
																								1	
Engineering																								1	
Health Physics/Rad Protection																								1	
Management Maintenance & Operations																								Į.	
Quality Assurance																								1	
Utility Staff		_			<u> </u>		_	_	_	_	<u> </u>	_		_		_	_				_	_	_	4	
Othity Stan		-		<u> </u>		_		-					-	-	-	-	-	<u> </u>		<u> </u>	-			4	⊥ -
Project Management																							1	1	
Engineering																							1	1	
Health Physics/Rad Protection																								1	
Administration																								1	
Maintenance & Operations																									
Quality Assurance																							1	1	
Waste Management																							1	1	
General Contractor Staff	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	4	6	1 -

Appendix E-1 - Waste Disposal Summary St. Lucie Unit 1

Scenario 1 - Unit 1 SAFSTOR, DECON both following Unit 2 Shutdown

2020 Dollars

F 104 -	Wests Fame	W4- O	Waste Weight	Waste Volume	Burial Volume	D		T	ransportation	D.	D	T - 4	-1.144- 04
Facility	Waste Form	Waste Class	(LBs)	(CF)	(CF)	Pac	ckaging Cost		Cost	ва	se Burial Cost	101	ai waste Cos
BC Facility													
WCS	Class BC	BC	165,890	1,322	1,870	\$	246,000	\$	1,257,407	\$	10,684,462	\$	12,187,869
	GTCC	GTCC	265,013	1,171	2,886	\$	7,062,000	\$	1,879,885	\$	14,568,239	\$	23,510,125
			430,903	2,493	4,756	\$	7,308,000	\$	3,137,292	\$	25,252,702	\$	35,697,994
Bear Creek													
	Containerized	Α	181,003	3,017	3,017	\$	-	\$	246,220	\$	427,367	\$	673,587
			181,003	3,017	3,017	\$	-	\$	246,220	\$	427,367	\$	673,587
Energy <i>Solutions</i>													
Clive	Debris	Α	104,609,142	1,267,102	1,267,493	\$	2,233,230	\$	13,930,009	\$	83,922,232	\$	100,085,471
Clive	Debris, Oversized	Α	903,394	15,957	15,960	\$	18,936	\$	119,390	\$	2,278,221	\$	2,416,546
Clive	Contaminated Soil	Α	104,669,850	1,045,756	1,046,699	\$	2,205,996	\$	13,755,932	\$	39,843,000	\$	55,804,928
Clive	Containerized	Α	146,854	1,259	1,484	\$	474,596	\$	484,142	\$	509,289	\$	1,468,027
Clive	Large Component	Α	2,272,329	28,397	28,397	\$	2,148,897	\$	1,446,394	\$	11,018,549	\$	14,613,841
			212,601,569	2,358,471	2,360,033	\$	7,081,655	\$	29,735,867	\$	137,571,291	\$	174,388,813
Other													
Local Landfill	Clean/Exempt	F	1,397,259	27,017	27,017	\$	-	\$	3,512	\$	62,950	\$	66,462
Local Scrap Metal Recycler	Recycled Metals	F	7,152,413	140,513	140,513	\$	-	\$	71,662	\$	-	\$	71,662
On Site- Reuse	Clean/Reuse	F	65,084,442	765,699	765,741	\$	-	\$	-	\$	-	\$	-
			73,634,115	933,229	933,271	\$	-	\$	75,174	\$	62,950	\$	138,123
Grand Total			286,847,589	3,297,210	3.301.077	\$	14,389,655	•	33.194.553	\$	163,314,310	•	210,898,518

Appendix E-1 - Waste Disposal Summary St. Lucie Unit 2 Scenario 1 - Unit 1 SAFSTOR, DECON both following Unit 2 Shutdown 2020 Dollars

			Waste Weight	Waste Volume	Burial Volume			Tr	ansportation				
Facility	Waste Form	Waste Class	(LBs)	(CF)	(CF)	Pac	kaging Cost		Cost	Ва	se Burial Cost	Tot	al Waste Cost
BC Facility													
WCS	Class BC	BC	190,782	1,321	1,870	\$	228,000	\$	1,203,662	\$	10,109,820	\$	11,541,482
	GTCC	GTCC	567,289	1,171	2,886	\$	7,062,000	\$	1,879,885	\$	14,568,239	\$	23,510,125
			758,071	2,492	4,756	\$	7,290,000	\$	3,083,547	\$	24,678,060	\$	35,051,607
Bear Creek													
	Containerized	А	142,652	3,463	3,463	\$	-	\$	274,630	\$	476,679	\$	751,309
			142,652	3,463	3,463	\$	-	\$	274,630	\$	476,679	\$	751,309
Energy <i>Solutions</i>													
Clive	Debris	Α	105,314,211	1,271,830	1,272,268	\$	2,229,666	\$	13,905,498	\$	81,266,248	\$	97,401,411
Clive	Debris, Oversized	Α	903,408	16,307	16,310	\$	18,936	\$	119,390	\$	2,278,221	\$	2,416,546
Clive	Contaminated Soil	Α	96,653,565	965,666	966,536	\$	2,035,576	\$	12,693,242	\$	36,765,000	\$	51,493,817
Clive	Containerized	Α	148,494	1,273	1,484	\$	474,596	\$	484,142	\$	509,289	\$	1,468,027
Clive	Large Component	Α	2,265,895	27,920	27,920	\$	2,064,524	\$	1,411,916	\$	11,018,549	\$	14,494,989
			205,285,573	2,282,996	2,284,518	\$	6,823,298	\$	28,614,187	\$	131,837,307	\$	167,274,792
Other													
Local Landfill	Clean/Exempt	F	1,397,259	27,017	23,300	\$	-	\$	3,029	\$	54,289	\$	57,318
Local Scrap Metal Recycler	Recycled Metals	F	7,854,582	160,773	161,352	\$	-	\$	82,290	\$	-	\$	82,290
On Site- Reuse	Clean/Reuse	F	64,403,676	758,862	757,694	\$	-	\$	-	\$	-	\$	-
			73,655,517	946,652	942,346	\$	-	\$	85,319	\$	54,289	\$	139,608
Grand Total			279,841,813	3,235,604	3,235,083		14,113,298		32,057,683		157,046,335		203,217,315

Appendix E-2 - Waste Disposal Summary St. Lucie Unit 1 Scenario 2 - SAFSTOR 2020 Dollars

			Waste Weight	Waste Volume	Burial Volume	_		Tr	ansportation				
Facility	Waste Form	Waste Class	(LBs)	(CF)	(CF)	Pac	ckaging Cost		Cost	Ва	se Burial Cost	lot	al Waste Cos
BC Facility													
WCS	Class BC	BC	114,109	1,327	1,144	\$	132,000	\$	969,313	\$	7,328,167	\$	8,429,480
	GTCC	GTCC	567,289	1,171	2,886	\$	7,062,000	\$	1,879,885	\$	14,568,239	\$	23,510,125
			681,398	2,498	4,030	\$	7,194,000	\$	2,849,198	\$	21,896,406	\$	31,939,604
Bear Creek													
	Processed Waste	Α	149,533	2,492	2,492	\$	-	\$	198,870	\$	345,181	\$	544,051
			149,533	2,492	2,492	\$	-	\$	198,870	\$	345,181	\$	544,051
Energy <i>Solution</i> s													
Clive	Debris	Α	80,680,299	987,767	988,117	\$	1,726,703	\$	10,771,458	\$	65,935,231	\$	78,433,392
Clive	Debris, Oversized	Α	870,347	15,670	15,673	\$	18,936	\$	119,390	\$	2,278,221	\$	2,416,546
Clive	Contaminated Soil	Α	104,669,850	1,077,186	1,078,157	\$	2,205,996	\$	13,755,932	\$	39,843,000	\$	55,804,928
Clive	Containerized	Α	145,628	1,248	1,460	\$	474,596	\$	484,142	\$	509,289	\$	1,468,027
Clive	Large Component	Α	2,234,271	27,443	27,443	\$	2,145,359	\$	1,444,949	\$	11,619,105	\$	15,209,413
			188,600,395	2,109,314	2,110,849	\$	6,571,590	\$	26,575,870	\$	120,184,847	\$	153,332,307
Other													
Local Landfill	Clean/Exempt	F	1,424,276	40,760	23,767	\$	-	\$	3,090	\$	55,376	\$	58,466
Local Scrap Metal Recycler	Recycled Metals	F	6,432,014	127,037	127,332	\$	-	\$	64,939	\$	-	\$	64,939
On Site- Reuse	Clean/Reuse	F	99,479,373	1,159,586	1,170,635	\$	-	\$	-	\$	-	\$	-
			107,335,663	1,327,383	1,321,734	\$	-	\$	68,029	\$	55,376	\$	123,405
Grand Total			296,766,989	3,441,687	3,439,105	\$	13.765.590	\$	29.691.967	\$	142,481,811	\$	185,939,368

Appendix E-2 - Waste Disposal Summary St. Lucie Unit 2 Scenario 2 - SAFSTOR 2020 Dollars

		Waste Weight	Waste Volume	Burial Volume	_		Tra	ansportation	_		_	
Waste Form	Waste Class	(LBs)	(CF)	(CF)	Pac	ckaging Cost		Cost	Bas	se Burial Cost	lot	al Waste Cos
		,	,	,	\$, ,	\$,	\$,, -	\$	8,429,480
GTCC	GTCC	567,289	1,171	2,886	\$	7,062,000	\$	1,879,885	\$	14,568,239	\$	23,510,125
		681,398	2,498	4,030	\$	7,194,000	\$	2,849,198	\$	21,896,406	\$	31,939,604
Processed Waste	Α	151,370	2,523	2,523	\$	-	\$	208,340	\$	361,619	\$	569,959
		151,370	2,523	2,523	\$	-	\$	208,340	\$	361,619	\$	569,959
Debris	Α	81,284,401	989,469	989,859	\$	1,723,139	\$	10,747,603	\$	63,461,730	\$	75,932,472
Debris, Oversized	Α	884,519	15,900	15,903	\$	18,936	\$	119,390	\$	2,278,221	\$	2,416,546
Contaminated Soil	Α	96,653,565	982,107	982,991	\$	2,035,576	\$	12,693,242	\$	36,765,000	\$	51,493,817
Containerized	Α	145,628	1,248	1,460	\$	474,596	\$	484,142	\$	509,289	\$	1,468,027
Large Component	Α	2,208,197	27,381	27,381	\$	2,060,987	\$	1,410,470	\$	11,619,105	\$	15,090,562
		181,176,310	2,016,104	2,017,595	\$	6,313,233	\$	25,454,847	\$	114,633,345	\$	146,401,425
Clean/Exempt	F	1,397,259	27,017	23,300	\$	-	\$	3,029	\$	54,289	\$	57,318
Recycled Metals	F	7,416,077	152,711	153,576	\$	-	\$	78,324	\$	-	\$	78,324
Clean/Reuse	F	99,321,815	1,157,733	1,168,518	\$	-	\$	-	\$	-	\$	-
		108,135,151	1,337,461	1,345,394	\$	-	\$	81,353	\$	54,289	\$	135,642
		000 444 000	0.050.500	2 202 511		40 507 000	•	00 500 500	•	400 045 050	•	179,046,630
	Debris Debris, Oversized Contaminated Soil Containerized Large Component Clean/Exempt Recycled Metals	Processed Waste A Debris A Debris, Oversized A Contaminated Soil A Containerized A Large Component A Clean/Exempt F Recycled Metals F	GTCC GTCC 567,289 681,398 681,398 Processed Waste A 151,370 Debris A 81,284,401 Debris, Oversized A 884,519 Contaminated Soil A 96,653,565 Containerized A 145,628 Large Component A 2,208,197 Tal,176,310 Clean/Exempt F 1,397,259 Recycled Metals F 7,416,077 Clean/Reuse F 99,321,815	GTCC GTCC 567,289 1,171 681,398 2,498 Processed Waste A 151,370 2,523 Debris A 81,284,401 989,469 Debris, Oversized A 884,519 15,900 Contaminated Soil A 96,653,565 982,107 Containerized A 145,628 1,248 Large Component A 2,208,197 27,381 181,176,310 2,016,104 Clean/Exempt F 1,397,259 27,017 Recycled Metals F 7,416,077 152,711 Clean/Reuse F 99,321,815 1,157,733 108,135,151 1,337,461	GTCC 567,289 1,171 2,886 681,398 2,498 4,030 Processed Waste A 151,370 2,523 2,523 Debris A 81,284,401 989,469 989,859 Debris, Oversized A 884,519 15,900 15,903 Contaminated Soil A 96,653,565 982,107 982,991 Containerized A 145,628 1,248 1,460 Large Component A 2,208,197 27,381 27,381 Tall,176,310 2,016,104 2,017,595 Clean/Exempt F 1,397,259 27,017 23,300 Recycled Metals F 7,416,077 152,711 153,576 Clean/Reuse F 99,321,815 1,157,733 1,168,518 108,135,151 1,337,461 1,345,394	GTCC GTCC 567,289 1,171 2,886 \$ Processed Waste A 151,370 2,523 2,523 \$ Debris A 81,284,401 989,469 989,859 \$ Debris, Oversized A 884,519 15,900 15,903 \$ Contaminated Soil A 96,653,565 982,107 982,991 \$ Containerized A 145,628 1,248 1,460 \$ Large Component A 2,208,197 27,381 27,381 \$ Clean/Exempt F 1,397,259 27,017 23,300 \$ Recycled Metals F 7,416,077 152,711 153,576 \$ Clean/Reuse F 99,321,815 1,157,733 1,168,518 \$ 108,135,151 1,337,461 1,345,394 \$	GTCC GTCC 567,289 1,171 2,886 \$ 7,062,000 Frocessed Waste A 151,370 2,523 2,523 \$ - Debris A 81,284,401 989,469 989,859 \$ 1,723,139 Debris, Oversized A 884,519 15,900 15,903 \$ 18,936 Contaminated Soil A 96,653,565 982,107 982,991 \$ 2,035,576 Containerized A 145,628 1,248 1,460 \$ 474,596 Large Component A 2,208,197 27,381 27,381 \$ 2,060,987 Telean/Exempt F 1,397,259 27,017 23,300 \$ - Recycled Metals F 7,416,077 152,711 153,576 \$ - Clean/Reuse F 99,321,815 1,157,733 1,166,518 \$ - 108,135,151 1,337,461 1,345,394 \$ -	GTCC GTCC 567,289 1,171 2,886 \$ 7,062,000 \$ Processed Waste A 151,370 2,523 2,523 \$ - \$ Debris A 81,284,401 989,469 989,859 \$ 1,723,139 \$ Debris, Oversized A 884,519 15,900 15,903 \$ 18,936 \$ Contaminated Soil A 96,653,565 982,107 982,991 \$ 2,035,576 \$ Containerized A 145,628 1,248 1,460 \$ 474,596 \$ Large Component A 2,208,197 27,381 27,381 \$ 2,060,987 \$ Clean/Exempt F 1,397,259 27,017 23,300 \$ - \$ Recycled Metals F 7,416,077 152,711 153,576 \$ - \$ Clean/Reuse F 99,321,815 1,157,733 1,168,518 \$ - \$ 108,135,151 1,337,461 1,345,394 \$ - \$	GTCC GTCC 567,289 1,171 2,886 \$ 7,062,000 \$ 1,879,885 Processed Waste A 151,370 2,523 2,523 \$ - \$ 208,340 Debris A 81,284,401 989,469 989,859 \$ 1,723,139 \$ 10,747,603 Debris, Oversized A 84,519 15,900 15,903 \$ 18,936 \$ 119,390 Contaminated Soil A 96,653,565 982,107 982,991 \$ 2,035,576 \$ 12,693,242 Containerized A 145,628 1,248 1,460 \$ 474,596 \$ 484,142 Large Component A 2,208,197 27,381 27,381 2,060,987 \$ 1,410,470 Recycled Metals F 1,397,259 27,017 23,300 \$ - \$ 3,029 Recycled Metals F 7,416,077 152,711 153,576 \$ - \$ 78,324 Clean/Reuse F 99,321,815 1,157,733 1,168,518 \$ - \$ - \$ 81,353	GTCC GTCC 567,289 1,171 2,886 \$ 7,062,000 \$ 1,879,885 \$ Processed Waste A 151,370 2,523 2,523 2,523 - \$ 208,340 \$ Debris A 81,284,401 989,469 989,859 \$ 1,723,139 \$ 10,747,603 \$ Debris, Oversized A 884,519 15,900 15,903 \$ 18,936 \$ 119,390 \$ Contaminated Soil A 96,653,565 982,107 982,991 \$ 2,035,576 \$ 12,693,242 \$ Containerized A 145,628 1,248 1,460 \$ 474,596 \$ 484,142 \$ Large Component A 2,208,197 27,381 27,381 \$ 2,660,987 \$ 1,410,470 \$ Recycled Metals F 1,397,259 27,017 23,300 \$ - \$ 3,029 \$ Clean/Reuse F 99,321,815 1,157,733 1,168,518 \$ - \$ - \$ 81,353 \$ Instruction F <td>GTCC GTCC 567,289 1,171 2,886 \$ 7,062,000 \$ 1,879,885 \$ 14,568,239 Processed Waste A 151,370 2,523 2,523 \$ - \$ 208,340 \$ 361,619 Debris A 81,284,401 989,469 989,859 \$ 1,723,139 \$ 10,747,603 \$ 63,461,730 Debris, Oversized A 884,519 15,900 15,903 \$ 18,936 \$ 119,390 \$ 2,278,221 Contaminated Soil A 96,653,565 982,107 982,991 \$ 2,035,576 \$ 12,693,242 \$ 36,765,000 Containerized A 145,628 1,248 1,460 \$ 474,596 \$ 484,142 \$ 509,289 Large Component A 2,208,197 27,381 27,381 \$ 2,060,987 \$ 1,410,470 \$ 11,619,105 Clean/Exempt F 1,397,259 27,017 23,300 - \$ 3,029 \$ 54,289 Clean/Reuse F 99,321,815 1,157,733 1,168,518 - * 78,324 * - 108,</td> <td>GTCC GTCC 567,289 1,171 2,886 \$ 7,062,000 \$ 1,879,885 \$ 14,568,239 \$ Processed Waste A 151,370 2,523 2,523 \$ - \$ 208,340 \$ 361,619 \$ Debris A 81,284,401 989,469 989,859 \$ 1,723,139 \$ 10,747,603 \$ 63,461,730 \$ Debris, Oversized A 81,284,401 989,469 989,859 \$ 1,723,139 \$ 10,747,603 \$ 63,461,730 \$ Contaminated Soil A 884,519 15,900 15,903 \$ 18,936 \$ 119,390 \$ 2,278,221 \$ Contaminated Soil A 96,653,565 982,107 982,991 \$ 2,035,576 \$ 12,693,242 \$ 36,765,000 \$ Containerized A 145,628 1,248 1,460 \$ 474,596 \$ 484,142 \$ 509,289 \$ Large Component A 2,208,197 27,381 2,381 2,080,987 \$ 1,410,470 \$ 11,619,105 \$ Recycled Metals F</td>	GTCC GTCC 567,289 1,171 2,886 \$ 7,062,000 \$ 1,879,885 \$ 14,568,239 Processed Waste A 151,370 2,523 2,523 \$ - \$ 208,340 \$ 361,619 Debris A 81,284,401 989,469 989,859 \$ 1,723,139 \$ 10,747,603 \$ 63,461,730 Debris, Oversized A 884,519 15,900 15,903 \$ 18,936 \$ 119,390 \$ 2,278,221 Contaminated Soil A 96,653,565 982,107 982,991 \$ 2,035,576 \$ 12,693,242 \$ 36,765,000 Containerized A 145,628 1,248 1,460 \$ 474,596 \$ 484,142 \$ 509,289 Large Component A 2,208,197 27,381 27,381 \$ 2,060,987 \$ 1,410,470 \$ 11,619,105 Clean/Exempt F 1,397,259 27,017 23,300 - \$ 3,029 \$ 54,289 Clean/Reuse F 99,321,815 1,157,733 1,168,518 - * 78,324 * - 108,	GTCC GTCC 567,289 1,171 2,886 \$ 7,062,000 \$ 1,879,885 \$ 14,568,239 \$ Processed Waste A 151,370 2,523 2,523 \$ - \$ 208,340 \$ 361,619 \$ Debris A 81,284,401 989,469 989,859 \$ 1,723,139 \$ 10,747,603 \$ 63,461,730 \$ Debris, Oversized A 81,284,401 989,469 989,859 \$ 1,723,139 \$ 10,747,603 \$ 63,461,730 \$ Contaminated Soil A 884,519 15,900 15,903 \$ 18,936 \$ 119,390 \$ 2,278,221 \$ Contaminated Soil A 96,653,565 982,107 982,991 \$ 2,035,576 \$ 12,693,242 \$ 36,765,000 \$ Containerized A 145,628 1,248 1,460 \$ 474,596 \$ 484,142 \$ 509,289 \$ Large Component A 2,208,197 27,381 2,381 2,080,987 \$ 1,410,470 \$ 11,619,105 \$ Recycled Metals F

Florida Power and Light - St. Lucie Units 1 & 2 SCENARIO 1 - Unit 1 SAFSTOR, DECON both following Unit 2 Shutdown Estimated Annual Spending

	1	0'1'		
Year	License Termination	Spent Fuel	Site Restoration	Total
2033	-	-	-	-
2034	-	-	-	-
2035	-	-	-	-
2036	23,572	15,376	-	38,948
2037	27,199	14,821	-	42,020
2038	19,509	10,662	-	30,171
2039	17,125	8,628	-	25,754
2040	3,311	6,395	-	9,706
2041	3,311	6,395	-	9,706
2042	3,311	6,395	-	9,706
2043	22,515	23,378	-	45,893
2044	34,118	29,344	-	63,462
2045	50,004	66,937	-	116,941
2046	66,896	68,431	-	135,327
2047	130,129	6,292	6,375	142,796
2048	146,732	6,292	17,987	171,011
2049	167,580	6,292	21,713	195,586
2050	204,520	6,292	9,623	220,435
2051	191,785	6,292	3,813	201,890
2052	103,733	6,292	3,338	113,363
2053	-	6,292	561	6,854
2054	-	6,292	-	6,292
2055	-	6,292	-	6,292
2056	-	6,292	-	6,292
2057	-	6,292	-	6,292
2058	-	6,292	-	6,292
2059	-	6,292	-	6,292
2060	-	6,292	-	6,292
2061	-	6,292	-	6,292
2062	-	6,292	-	6,292
2063	-	6,292	-	6,292
2064	-	6,292	•	6,292
2065	-	6,292	-	6,292
2066	-	6,292	•	6,292
2067	-	6,292	•	6,292
2068	-	6,292	-	6,292
2069	-	6,292	-	6,292
2070	19,695	6,292	-	25,987
2071	19,695	6,292	-	25,987
2072	-	4,754	-	4,754
2073	-	8,485	-	8,485
2074	-	-	-	-
Total	1,254,740	427,313	63,409	1,745,462

Florida Power and Light - St. Lucie Unit 1 SCENARIO 1 - Unit 1 SAFSTOR, DECON both following Unit 2 Shutdown Estimated Annual Spending

	12	0.1		
Year	License Termination	Spent Fuel	Site Restoration	Total
2033	-	-	-	-
2034	-	-	-	-
2035	-	-	-	-
2036	23,572	15,376	•	38,948
2037	27,199	14,821	-	42,020
2038	19,509	10,662	-	30,171
2039	17,125	8,628	-	25,754
2040	3,311	6,395	-	9,706
2041	3,311	6,395	-	9,706
2042	3,311	6,395	-	9,706
2043	3,311	6,395	-	9,706
2044	3,311	6,395	-	9,706
2045	24,337	31,395	-	55,732
2046	28,089	43,275	-	71,364
2047	72,071	3,196	2,715	77,982
2048	77,559	3,196	7,868	88,623
2049	85,642	3,196	10,435	99,273
2050	112,471	3,196	3,659	119,326
2051	79,884	3,196	1,972	85,052
2052	47,397	3,196	1,928	52,521
2053	-	3,196	335	3,531
2054	-	3,196	-	3,196
2055	-	3,196	•	3,196
2056	-	3,196	•	3,196
2057	-	3,196	ı	3,196
2058	-	3,196	•	3,196
2059	-	3,196	ı	3,196
2060	-	3,196	•	3,196
2061	-	3,196	•	3,196
2062	-	3,196	•	3,196
2063	-	3,196	•	3,196
2064	-	3,196	•	3,196
2065	-	3,196	•	3,196
2066	-	3,196	•	3,196
2067	-	3,196	•	3,196
2068	-	3,196	-	3,196
2069	-	3,196	-	3,196
2070	9,848	3,196	•	13,043
2071	9,848	3,196	•	13,043
2072	-	1,669	•	1,669
2073	-	5,683	-	5,683
2074	-	•	-	-
Total	651,106	243,383	28,912	923,401

Florida Power and Light - St. Lucie Unit 2 SCENARIO 1 - Unit 1 SAFSTOR, DECON both following Unit 2 Shutdown Estimated Annual Spending

Year	License Termination	Spent Fuel	Site Restoration	Total
2033	-	-	-	-
2034	-	-	-	-
2035	-	-	-	-
2036	-	-	-	-
2037	-	-	-	-
2038	-	-	-	-
2039	-	-	-	-
2040	-	-	-	-
2041	-	-	-	-
2042	-	-	-	-
2043	19,204	16,983	-	36,186
2044	30,806	22,949	-	53,755
2045	25,667	35,542	-	61,209
2046	38,808	25,156	-	63,964
2047	58,057	3,096	3,660	64,814
2048	69,173	3,096	10,119	82,388
2049	81,938	3,096	11,278	96,313
2050	92,048	3,096	5,964	101,109
2051	111,901	3,096	1,840	116,838
2052	56,336	3,096	1,410	60,842
2053	-	3,096	226	3,323
2054	-	3,096	-	3,096
2055	-	3,096	-	3,096
2056	-	3,096	-	3,096
2057	-	3,096	-	3,096
2058	-	3,096	-	3,096
2059	-	3,096	-	3,096
2060	-	3,096	-	3,096
2061	-	3,096	-	3,096
2062	-	3,096	-	3,096
2063	-	3,096	-	3,096
2064	-	3,096	-	3,096
2065	-	3,096	-	3,096
2066	-	3,096	-	3,096
2067	-	3,096	-	3,096
2068	-	3,096	-	3,096
2069	-	3,096	-	3,096
2070	9,848	3,096	-	12,944
2071	9,848	3,096	-	12,944
2072	-	3,086	-	3,086
2073	-	2,802	-	2,802
2074	-	-	-	-
Total	603,633	183,930	34,497	822,060

Florida Power and Light - St. Lucie Units 1 & 2 SCENARIO 2 - SAFSTOR Estimated Annual Spending

	License	Spent	Site					
Year	Termination	Fuel	Restoration	Total				
2033	-	-	-	-				
2034	-	-	-	-				
2035	-	-	-	-				
2036	24,556	15,264	-	39,819				
2037	27,698	14,679	ı	42,377				
2038	19,646	10,562	ı	30,209				
2039	17,124	8,541	•	25,665				
2040	3,577	6,829	•	10,406				
2041	3,577	6,829	-	10,406				
2042	3,577	6,829	•	10,406				
2043	26,530	23,814	-	50,344				
2044	36,527	29,783	-	66,311				
2045	26,066	67,375	-	93,441				
2046	23,513	68,868	-	92,381				
2047	2,245	8,004	-	10,249				
2048	2,245	8,004	-	10,249				
2049	2,245	8,004	-	10,249				
2050	2,245	8,004	-	10,249				
2051	2,245	8,004	-	10,249				
2052	2,245	8,004	-	10,249				
2053	2,245	8,004	-	10,249				
2054	2,245	8,004	-	10,249				
2055	2,245	8,004	-	10,249				
2056	2,245	8,004	-	10,249				
2057	2,245	8,004	-	10,249				
2058	2,245	8,004	-	10,249				
2059	2,245	8,004	-	10,249				
2060	2,245	8,004	-	10,249				
2061	2,245	8,004	-	10,249				
2062	2,245	8,004	-	10,249				
2063	2,245	8,004	-	10,249				
2064	2,245	8,004	-	10,249				
2065	2,245	8,004	-	10,249				
2066	2,245	8,004	-	10,249				
2067	2,245	8,004	-	10,249				
2068	2,245	8,004	-	10,249				
2069	2,245	8,004	-	10,249				
2070	2,245	8,004	-	10,249				
2071	2,245	8,004	-	10,249				

Florida Power and Light - St. Lucie Units 1 & 2 SCENARIO 2 - SAFSTOR Estimated Annual Spending

Year	License Termination	Spent Fuel	Site Restoration	Total
2072	4,067	ı uei	- Nestoration	4,067
2073	4,067	-	_	4,067
2074	4,067	_	-	4,067
2075	4,067	_	_	4,067
2076	4,067	-	-	4,067
2077	4,067	-	-	4,067
2078	4,067	-	-	4,067
2079	4,067	-	-	4,067
2080	4,067	-	-	4,067
2081	4,067	-	-	4,067
2082	4,067	-	-	4,067
2083	4,067	-	-	4,067
2084	4,067	-	-	4,067
2085	4,067	-	-	4,067
2086	4,067	-	-	4,067
2087	4,067	-	-	4,067
2088	9,268	-	-	9,268
2089	63,526	-	-	63,526
2090	105,323	-	2,418	107,741
2091	137,570	-	16,134	153,704
2092	146,822	-	20,485	167,307
2093	166,481	-	12,688	179,169
2094	184,561	1	6,131	190,692
2095	145,891	598	3,458	149,947
2096	26,469	12,101	787	39,357
2097	-	867	-	867
2098	-	-	-	-
Total	1,319,504	473,029	62,101	1,854,633

Florida Power and Light - St. Lucie Unit 1 SCENARIO 2 - SAFSTOR Estimated Annual Spending

Year	License Termination	Spent Fuel	Site Restoration	Total
2033	-	-	-	-
2034	-	-	-	-
2035	-	-	-	-
2036	24,556	15,264	-	39,819
2037	27,698	14,679	-	42,377
2038	19,646	10,562	-	30,209
2039	17,124	8,541	-	25,665
2040	3,577	6,829	-	10,406
2041	3,577	6,829	-	10,406
2042	3,577	6,829	-	10,406
2043	3,577	6,829	-	10,406
2044	3,577	6,829	-	10,406
2045	3,577	31,829	-	35,406
2046	3,577	43,709	-	47,286
2047	1,079	4,012	-	5,091
2048	1,079	4,012	-	5,091
2049	1,079	4,012	-	5,091
2050	1,079	4,012	-	5,091
2051	1,079	4,012	-	5,091
2052	1,079	4,012	-	5,091
2053	1,079	4,012	-	5,091
2054	1,079	4,012	-	5,091
2055	1,079	4,012	-	5,091
2056	1,079	4,012	-	5,091
2057	1,079	4,012	-	5,091
2058	1,079	4,012	•	5,091
2059	1,079	4,012	-	5,091
2060	1,079	4,012	•	5,091
2061	1,079	4,012	-	5,091
2062	1,079	4,012	-	5,091
2063	1,079	4,012	•	5,091
2064	1,079	4,012	-	5,091
2065	1,079	4,012	•	5,091
2066	1,079	4,012	-	5,091
2067	1,079	4,012	•	5,091
2068	1,079	4,012	•	5,091
2069	1,079	4,012	•	5,091
2070	1,079	4,012	•	5,091
2071	1,079	4,012	-	5,091

Florida Power and Light - St. Lucie Unit 1 SCENARIO 2 - SAFSTOR Estimated Annual Spending

Year	License Termination	Spent Fuel	Site Restoration	Total
2072	2,033	-	-	2,033
2073	2,033	-	-	2,033
2074	2,033	-	-	2,033
2075	2,033	-	-	2,033
2076	2,033	-	-	2,033
2077	2,033	-	-	2,033
2078	2,033	-	-	2,033
2079	2,033	-	-	2,033
2080	2,033	-	-	2,033
2081	2,033	-	-	2,033
2082	2,033	-	-	2,033
2083	2,033	-	-	2,033
2084	2,033			2,033
2085	2,033	•	•	2,033
2086	2,033	•	•	2,033
2087	2,033	•	-	2,033
2088	6,455	•	•	6,455
2089	38,251	•	•	38,251
2090	61,248		1,025	62,273
2091	70,706	•	6,423	77,129
2092	76,010	•	9,804	85,814
2093	83,644		6,167	89,811
2094	93,235	•	2,373	95,608
2095	63,939	315	1,945	66,199
2096	10,724	6,724	451	17,899
2097	-	476	-	476
2098	-	-	•	-
Total	677,793	266,544	28,188	972,525

Florida Power and Light - St. Lucie Unit 2 SCENARIO 2 - SAFSTOR Estimated Annual Spending

Year	License Termination	Spent Fuel	Site Restoration	Total
2033	-	-	-	-
2034	-	-	-	-
2035	-	-	-	-
2036	-	-	-	-
2037	-	-	-	-
2038	-	-	-	-
2039	-	-	-	-
2040	-	-	-	-
2041	-	-	-	-
2042	-	-	-	-
2043	22,953	16,985	-	39,938
2044	32,951	22,954	-	55,905
2045	22,489	35,546	-	58,035
2046	19,936	25,159	-	45,096
2047	1,166	3,992	-	5,157
2048	1,166	3,992	-	5,157
2049	1,166	3,992	-	5,157
2050	1,166	3,992	-	5,157
2051	1,166	3,992	-	5,157
2052	1,166	3,992	-	5,157
2053	1,166	3,992	-	5,157
2054	1,166	3,992	-	5,157
2055	1,166	3,992	-	5,157
2056	1,166	3,992	-	5,157
2057	1,166	3,992	-	5,157
2058	1,166	3,992	-	5,157
2059	1,166	3,992	-	5,157
2060	1,166	3,992	-	5,157
2061	1,166	3,992	-	5,157
2062	1,166	3,992	-	5,157
2063	1,166	3,992	-	5,157
2064	1,166	3,992	-	5,157
2065	1,166	3,992	-	5,157
2066	1,166	3,992	-	5,157
2067	1,166	3,992	-	5,157
2068	1,166	3,992	-	5,157
2069	1,166	3,992	-	5,157
2070	1,166	3,992	-	5,157
2071	1,166	3,992	-	5,157

Florida Power and Light - St. Lucie Unit 2 SCENARIO 2 - SAFSTOR Estimated Annual Spending

Year	License Termination	Spent Fuel	Site Restoration	Total
2072	2,033	-	-	2,033
2073	2,033	-	-	2,033
2074	2,033	-	-	2,033
2075	2,033	-	-	2,033
2076	2,033	-	-	2,033
2077	2,033	-	-	2,033
2078	2,033	-	-	2,033
2079	2,033	•		2,033
2080	2,033	•	•	2,033
2081	2,033	•	•	2,033
2082	2,033	•		2,033
2083	2,033	•	•	2,033
2084	2,033	•	•	2,033
2085	2,033	•	•	2,033
2086	2,033	•	•	2,033
2087	2,033	•		2,033
2088	2,813	•	•	2,813
2089	25,275	•	•	25,275
2090	44,074	•	1,394	45,468
2091	66,864	ı	9,711	76,575
2092	70,812	•	10,680	81,492
2093	82,838	•	6,521	89,359
2094	91,326	-	3,758	95,084
2095	81,952	283	1,513	83,748
2096	15,745	5,377	336	21,458
2097		391	-	391
2098	-	-	-	-
Total	641,710	206,485	33,913	882,108

Florida Power and Light Units 1 & 2 SCENARIO 1 - Unit 1 SAFSTOR, DECON both following Unit 2 Shutdown Estimated Annual Spending

Labor, Material/Equip, Waste, Other Direct Cost

Year	Labor	Material & Equipment	Waste Packaging & Transportation	Waste Disposal	Other Direct Cost	Total
2033	-	-	-	-	-	-
2034	-	-	-	-	-	-
2035	-	-	-	-	-	-
2036	32,205	3,115	-	-	3,628	38,948
2037	34,682	2,930	-	-	4,408	42,020
2038	23,684	2,195	-	-	4,292	30,171
2039	19,676	1,812	-	-	4,265	25,754
2040	7,003	417	-	-	2,287	9,706
2041	7,003	417	-	-	2,287	9,706
2042	7,003	417	-	-	2,287	9,706
2043	38,405	1,987	-	-	5,501	45,893
2044	54,802	2,020	-	-	6,640	63,462
2045	62,841	37,223	5,550	-	11,327	116,941
2046	78,270	31,649	8,164	-	17,244	135,327
2047	78,817	37,831	2,367	7,295	16,486	142,796
2048	96,417	40,011	4,640	17,901	12,041	171,011
2049	109,059	37,937	9,804	30,367	8,419	195,585
2050	57,478	26,745	23,253	106,178	6,781	220,435
2051	32,784	17,213	30,584	115,125	6,184	201,890
2052	12,432	5,582	21,945	68,982	4,422	113,363
2053	4,763	351	-	-	1,740	6,854
2054	4,509	138	-	-	1,645	6,292
2055	4,509	138	-	-	1,645	6,292
2056	4,509	138	-	-	1,645	6,292
2057	4,509	138	-	-	1,645	6,292
2058	4,509	138	-	-	1,645	6,292
2059	4,509	138	-	-	1,645	6,292
2060	4,509	138	-	-	1,645	6,292
2061	4,509	138	-	-	1,645	6,292
2062	4,509	138	-	-	1,645	6,292
2063	4,509	138	-	-	1,645	6,292
2064	4,509	138	-	-	1,645	6,292
2065	4,509	138	-	-	1,645	6,292
2066	4,509	138	-	-	1,645	6,292
2067	4,509	138	-	-	1,645	6,292
2068	4,509	138	-	-	1,645	6,292
2069	4,509	138	-	-	1,645	6,292
2070	5,079	138	2,169	16,812	1,789	25,988
2071	5,079	138	2,169	16,812	1,789	25,988
2072	4,389	-	-	-	365	4,755
2073	6,256	2,169	-	-	60	8,485
2074	<u>-</u>	-	-	-	-	-
Total	850,272	254,507	110,645	379,472	150,565	1,745,462

Florida Power and Light Unit 1 SCENARIO 1 - Unit 1 SAFSTOR, DECON both following Unit 2 Shutdown Estimated Annual Spending

Labor, Material/Equip, Waste, Other Direct Cost

Year	Labor	Material & Equipment	Waste Packaging & Transportation	Waste Disposal	Other Direct Cost	Total
2033	-	-	-	-	-	-
2034	-	-	-	-	-	-
2035	-	-	-	-	-	-
2036	32,205	3,115	-	-	3,628	38,948
2037	34,682	2,930	-	-	4,408	42,020
2038	23,684	2,195	-	-	4,292	30,171
2039	19,676	1,812	-	-	4,265	25,754
2040	7,003	417	-	-	2,287	9,706
2041	7,003	417	-	-	2,287	9,706
2042	7,003	417	-	-	2,287	9,706
2043	7,003	417	-	-	2,287	9,706
2044	7,003	417	-	-	2,287	9,706
2045	29,380	15,987	4,353	-	6,012	55,732
2046	35,615	25,881	1,204	-	8,663	71,364
2047	35,910	27,744	1,789	3,792	8,747	77,982
2048	48,878	19,397	3,474	11,058	5,815	88,622
2049	53,729	21,876	4,844	14,371	4,452	99,273
2050	25,364	13,037	12,839	64,383	3,705	119,326
2051	14,411	3,465	14,219	49,451	3,506	85,052
2052	4,617	857	11,250	33,750	2,048	52,521
2053	2,442	204	-	-	885	3,531
2054	2,295	79	-	-	822	3,196
2055	2,295	79	-	-	822	3,196
2056	2,295	79	-	-	822	3,196
2057	2,295	79	-	-	822	3,196
2058	2,295	79	-	-	822	3,196
2059	2,295	79	-	-	822	3,196
2060	2,295	79	-	-	822	3,196
2061	2,295	79	-	-	822	3,196
2062	2,295	79	-	-	822	3,196
2063	2,295	79	-	-	822	3,196
2064	2,295	79	-	-	822	3,196
2065	2,295	79	-	-	822	3,196
2066	2,295	79	-	-	822	3,196
2067	2,295	79	-	-	822	3,196
2068	2,295	79	-	-	822	3,196
2069	2,295	79	-	-	822	3,196
2070	2,580	79	1,085	8,406	894	13,043
2071	2,580	79	1,085	8,406	894	13,043
2072	1,498		-	-	171	1,669
2073	4,321	1,302	-	-	60	5,684
2074	-	<u> </u>	-	-		
Total	443,308	143,311	56,142	193,616	87,025	923,401

Florida Power and Light Unit 2

SCENARIO 1 - Unit 1 SAFSTOR, DECON both following Unit 2 Shutdown Estimated Annual Spending

Labor, Material/Equip, Waste, Other Direct Cost

Year	Labor	Material & Equipment	Waste Packaging & Transportation	Waste Disposal	Other Direct Cost	Total
2033	-	-	-	-	-	-
2034	-	-	-	-	-	-
2035	-	-	-	-	-	-
2036	-	-	-	-	-	-
2037	-	-	-	-	-	-
2038	-	-	-	-	-	-
2039	-	-	-	-	-	-
2040	-	-	-	-	-	-
2041	-	-	•	-	-	-
2042	-	-	•	-	-	-
2043	31,403	1,570	-	-	3,214	36,186
2044	47,799	1,603	-	-	4,354	53,755
2045	33,461	21,237	1,197	-	5,314	61,209
2046	42,655	5,768	6,960	-	8,581	63,964
2047	42,907	10,087	578	3,504	7,738	64,814
2048	47,539	20,614	1,166	6,843	6,226	82,388
2049	55,330	16,061	4,959	15,996	3,967	96,312
2050	32,115	13,708	10,414	41,796	3,077	101,109
2051	18,373	13,749	16,365	65,674	2,678	116,838
2052	7,815	4,726	10,695	35,232	2,375	60,842
2053	2,321	147	-	-	855	3,323
2054	2,214	59	-	-	824	3,096
2055	2,214	59	-	-	824	3,096
2056	2,214	59	-	-	824	3,096
2057	2,214	59	-	-	824	3,096
2058	2,214	59	-	-	824	3,096
2059	2,214	59	-	-	824	3,096
2060	2,214	59	-	-	824	3,096
2061	2,214	59	-	-	824	3,096
2062	2,214	59	-	-	824	3,096
2063	2,214	59		-	824	3,096
2064	2,214	59		-	824	3,096
2065	2,214	59	-	-	824	3,096
2066	2,214	59	-	-	824	3,096
2067	2,214	59	-	-	824	3,096
2068	2,214	59	-	-	824	3,096
2069	2,214	59	-	-	824	3,096
2070	2,499	59	1,085	8,406	896	12,944
2071	2,499	59	1,085	8,406	896	12,944
2072	2,892	-	-	-	194	3,086
2073	1,935	867	-	-	-	2,802
2074	-	-	_	-	-	-
Total	406,964	111,197	54,503	185,856	63,540	822,060

Florida Power and Light - St. Lucie Units 1 & 2

SCENARIO 2 - SAFSTOR

Estimated Annual Spending

Labor, Material/Equip, Waste, Other Direct Cost

Year	Labor	Material & Equipment	Waste Packaging & Transportation	Waste Disposal	Other Direct Cost	Total
2033	-	-	-	-	-	-
2034	-	-	-	-	-	-
2035	-	-	-	-	-	-
2036	33,138	3,054	-	-	3,628	39,819
2037	35,154	2,815	-	-	4,407	42,377
2038	23,811	2,106	-	-	4,291	30,209
2039	19,673	1,727	-	-	4,265	25,665
2040	6,761	417	-	-	3,228	10,406
2041	6,761	417	-	-	3,228	10,406
2042	6,761	417	-	-	3,228	10,406
2043	41,480	2,422	-	-	6,442	50,344
2044	56,453	2,275	-	-	7,582	66,311
2045	44,271	41,680	-	-	7,490	93,441
2046	53,891	30,458	-	-	8,033	92,381
2047	6,544	729	-	-	2,975	10,249
2048	6,544	729	-	-	2,975	10,249
2049	6,544	729	-	-	2,975	10,249
2050	6,544	729	-	-	2,975	10,249
2051	6,544	729	-	-	2,975	10,249
2052	6,544	729	-	-	2,975	10,249
2053	6,544	729	-	-	2,975	10,249
2054	6,544	729	-	-	2,975	10,249
2055	6,544	729	-	-	2,975	10,249
2056	6,544	729	-	-	2,975	10,249
2057	6,544	729	-	-	2,975	10,249
2058	6,544	729	-	-	2,975	10,249
2059	6,544	729	-	-	2,975	10,249
2060	6,544	729	-	-	2,975	10,249
2061	6,544	729	-	-	2,975	10,249
2062	6,544	729	-	-	2,975	10,249
2063	6,544	729	-	-	2,975	10,249
2064	6,544	729	-	-	2,975	10,249
2065	6,544	729	-	-	2,975	10,249
2066	6,544	729	-	-	2,975	10,249
2067	6,544	729	-	-	2,975	10,249
2068	6,544	729	-	-	2,975	10,249
2069	6,544	729	-	-	2,975	10,249
2070	6,544	729	-	-	2,975	10,249
2071	6,544	729	-	-	2,975	10,249
2072	1,694	403	-	-	1,969	4,067
2073	1,694	403	-	-	1,969	4,067
2074	1,694	403	-	-	1,969	4,067
2075	1,694	403	-	-	1,969	4,067

Florida Power and Light - St. Lucie Units 1 & 2

SCENARIO 2 - SAFSTOR

Estimated Annual Spending

Labor, Material/Equip, Waste, Other Direct Cost

Year	Labor	Material & Equipment	Waste Packaging & Transportation	Waste Disposal	Other Direct Cost	Total
2076	1,694	403	-	-	1,969	4,067
2077	1,694	403	-	-	1,969	4,067
2078	1,694	403	-	-	1,969	4,067
2079	1,694	403	-	-	1,969	4,067
2080	1,694	403	-	-	1,969	4,067
2081	1,694	403	-	-	1,969	4,067
2082	1,694	403	-	-	1,969	4,067
2083	1,694	403	-	-	1,969	4,067
2084	1,694	403	-	-	1,969	4,067
2085	1,694	403	-	-	1,969	4,067
2086	1,694	403	-	-	1,969	4,067
2087	1,694	403	-	-	1,969	4,067
2088	4,915	751	-	-	3,602	9,268
2089	35,627	3,297	14,293	-	10,309	63,526
2090	52,922	35,085	1,965	5,711	12,058	107,741
2091	86,644	44,022	3,150	10,553	9,335	153,704
2092	101,196	30,370	6,621	23,125	5,994	167,306
2093	74,062	27,336	15,367	58,509	3,895	179,169
2094	34,046	15,516	28,759	109,139	3,232	190,692
2095	12,616	4,554	26,735	103,418	2,624	149,947
2096	11,144	2,659	3,814	20,775	965	39,357
2097	678	63	-	-	126	867
2098	-	-	-	-		
Total	932,720	276,127	100,703	331,230	213,853	1,854,633

Florida Power and Light - St. Lucie Unit 1 SCENARIO 2 - SAFSTOR

Estimated Annual Spending

Labor, Material/Equip, Waste, Other Direct Cost

Year	Labor	Material & Equipment	Waste Packaging & Transportation	Waste Disposal	Other Direct Cost	Total
2033	-	-	-	-	-	-
2034	-	-	-	-	-	-
2035	-	-	•	-	-	-
2036	33,138	3,054	•	-	3,628	39,819
2037	35,154	2,815	•	-	4,407	42,377
2038	23,811	2,106	-	-	4,291	30,209
2039	19,673	1,727	-	-	4,265	25,665
2040	6,761	417	-	-	3,228	10,406
2041	6,761	417	-	-	3,228	10,406
2042	6,761	417	-	-	3,228	10,406
2043	6,761	417	-	-	3,228	10,406
2044	6,761	417	-	-	3,228	10,406
2045	6,761	25,417	-	-	3,228	35,406
2046	22,630	21,086	-	-	3,570	47,286
2047	3,269	295	-	-	1,528	5,091
2048	3,269	295	-	-	1,528	5,091
2049	3,269	295	-	-	1,528	5,091
2050	3,269	295	-	-	1,528	5,091
2051	3,269	295	-	-	1,528	5,091
2052	3,269	295	-	-	1,528	5,091
2053	3,269	295	-	-	1,528	5,091
2054	3,269	295	-	-	1,528	5,091
2055	3,269	295	-	-	1,528	5,091
2056	3,269	295	-	-	1,528	5,091
2057	3,269	295	-	-	1,528	5,091
2058	3,269	295	-	-	1,528	5,091
2059	3,269	295	-	-	1,528	5,091
2060	3,269	295	-	-	1,528	5,091
2061	3,269	295	-	-	1,528	5,091
2062	3,269	295	-	-	1,528	5,091
2063	3,269	295	-	-	1,528	5,091
2064	3,269	295	-	-	1,528	5,091
2065	3,269	295	-	-	1,528	5,091
2066	3,269	295	-	-	1,528	5,091
2067	3,269	295	-	-	1,528	5,091
2068	3,269	295	-	-	1,528	5,091
2069	3,269	295	-	-	1,528	5,091
2070	3,269	295	-	-	1,528	5,091
2071	3,269	295	-	-	1,528	5,091
2072	847	202	-	-	985	2,033
2073	847	202	-	-	985	2,033
2074	847	202	-	-	985	2,033
2075	847	202	-	-	985	2,033
2076	847	202	•	-	985	2,033

Florida Power and Light - St. Lucie Unit 1 SCENARIO 2 - SAFSTOR

Estimated Annual Spending

Labor, Material/Equip, Waste, Other Direct Cost

Year	Labor	Material & Equipment	Waste Packaging & Transportation	Waste Disposal	Other Direct Cost	Total
2077	847	202	- -		985	2,033
2078	847	202	-	-	985	2,033
2079	847	202	-	-	985	2,033
2080	847	202	-	-	985	2,033
2081	847	202	-	-	985	2,033
2082	847	202	-	-	985	2,033
2083	847	202	-	-	985	2,033
2084	847	202	-	-	985	2,033
2085	847	202	-	-	985	2,033
2086	847	202	-	-	985	2,033
2087	847	202	-	-	985	2,033
2088	3,654	528	-	-	2,272	6,455
2089	23,092	2,415	6,484	-	6,259	38,251
2090	28,660	21,836	1,588	4,367	5,822	62,273
2091	42,644	23,532	1,706	5,331	3,916	77,129
2092	49,608	14,126	4,255	15,042	2,783	85,814
2093	31,937	12,824	8,774	34,432	1,844	89,811
2094	17,388	4,815	15,038	56,801	1,566	95,608
2095	6,450	1,612	12,592	44,259	1,287	66,199
2096	6,158	1,667	814	8,775	486	17,899
2097	375	38	-	-	63	476
2098	-	-	-	-		-
Total	480,208	152,279	51,251	169,007	119,780	972,525

Florida Power and Light - St. Lucie Unit 2 SCENARIO 2 - SAFSTOR

Estimated Annual Spending

Labor, Material/Equip, Waste, Other Direct Cost

Year	Labor	Material & Equipment	Waste Packaging & Transportation	Waste Disposal	Other Direct Cost	Total
2033	-	-	-	-	-	-
2034	-	-	-	-	-	-
2035	-	-	-	-	-	-
2036	-	-	-	-	-	-
2037	-	-	•	-	-	-
2038	-	-	-	-	-	-
2039	-	-	-	-	-	-
2040	-	-	-	-	-	-
2041	-	-	-	-	-	-
2042	-	-	-	-	-	-
2043	34,719	2,005	-	-	3,214	39,938
2044	49,692	1,859	-	-	4,354	55,905
2045	37,510	16,263	-	-	4,262	58,035
2046	31,261	9,371	-	-	4,463	45,096
2047	3,276	434	-	-	1,447	5,157
2048	3,276	434	-	-	1,447	5,157
2049	3,276	434	-	-	1,447	5,157
2050	3,276	434	-	-	1,447	5,157
2051	3,276	434	-	-	1,447	5,157
2052	3,276	434	-	-	1,447	5,157
2053	3,276	434	-	-	1,447	5,157
2054	3,276	434	-	-	1,447	5,157
2055	3,276	434	-	-	1,447	5,157
2056	3,276	434	-	-	1,447	5,157
2057	3,276	434	-	-	1,447	5,157
2058	3,276	434	-	-	1,447	5,157
2059	3,276	434	-	-	1,447	5,157
2060 2061	3,276	434	-	-	1,447 1,447	5,157
2062	3,276	434	-	-		5,157
2062	3,276 3,276	434	-	-	1,447 1,447	5,157 5,157
2064	3,276	434	-	-	1,447	5,157
2065	3,276	434	-	-	1,447	5,157
2066	3,276	434	-	-	1,447	5,157
2067	3,276	434	-	-	1,447	5,157
2068	3,276	434	-	-	1,447	5,157
2069	3,276	434	-	-	1,447	5,157
2070	3,276	434	-	-	1,447	5,157
2071	3,276	434		-	1,447	5,157
2072	847	202	-	-	985	2,033
2073	847	202	_	-	985	2,033
2074	847	202	_	-	985	2,033
2075	847	202	_	-	985	2,033
2076	847	202		-	985	2,033

Florida Power and Light - St. Lucie Unit 2 SCENARIO 2 - SAFSTOR

Estimated Annual Spending

Labor, Material/Equip, Waste, Other Direct Cost

Year	Labor	Material & Equipment	Waste Packaging & Transportation	Waste Disposal	Other Direct Cost	Total
2077	847	202	-	-	985	2,033
2078	847	202	-	-	985	2,033
2079	847	202	-	-	985	2,033
2080	847	202	-	-	985	2,033
2081	847	202	-	-	985	2,033
2082	847	202	-	-	985	2,033
2083	847	202	-	-	985	2,033
2084	847	202	-	-	985	2,033
2085	847	202	-	-	985	2,033
2086	847	202	-	-	985	2,033
2087	847	202	-	-	985	2,033
2088	1,261	223	•	-	1,330	2,813
2089	12,534	882	7,808	-	4,050	25,275
2090	24,262	13,249	377	1,344	6,236	45,468
2091	43,999	20,491	1,444	5,222	5,419	76,574
2092	51,587	16,244	2,366	8,083	3,212	81,492
2093	42,125	14,512	6,593	24,077	2,051	89,359
2094	16,658	10,701	13,721	52,338	1,666	95,084
2095	6,167	2,943	14,143	59,159	1,337	83,748
2096	4,986	993	3,000	12,000	479	21,458
2097	303	25	-	-	63	391
2098	-	-	-	-	-	-
Total	452,512	123,848	49,453	162,223	94,073	882,108

Florida Power and Light Units 1 & 2 SCENARIO 1 - Unit 1 SAFSTOR, DECON both following Unit 2 Shutdown Estimated DOE Reimbursement

Labor, Material/Equip, Waste, Other Direct Cost

Year	Labor	Material & Equipment	Waste Transportation & Disposal	Other Direct Cost	Total
2033	-	-	-	-	-
2034	-	-	-	-	-
2035	-	-	-	-	-
2036	-	-	-	-	-
2037	12,314	2,431	-	631	15,376
2038	11,687	2,366	-	768	14,821
2039	8,076	1,841	-	745	10,662
2040	6,321	1,567	-	740	8,628
2041	4,896	312	-	1,187	6,395
2042	4,896	312	-	1,187	6,395
2043	4,896	312	-	1,187	6,395
2044	19,882	1,769	-	1,727	23,378
2045	25,659	1,765	-	1,921	29,344
2046	21,153	43,882	-	1,903	66,937
2047	38,107	27,977	-	2,348	68,431
2048	4,509	138	-	1,645	6,292
2049	4,509	138	-	1,645	6,292
2050	4,509	138	-	1,645	6,292
2051	4,509	138	-	1,645	6,292
2052	4,509	138	-	1,645	6,292
2053	4,509	138	-	1,645	6,292
2054	4,509	138	-	1,645	6,292
2055	4,509	138	-	1,645	6,292
2056	4,509	138	-	1,645	6,292
2057	4,509	138	-	1,645	6,292
2058	4,509	138	-	1,645	6,292
2059	4,509	138	-	1,645	6,292
2060	4,509	138	-	1,645	6,292
2061	4,509	138	-	1,645	6,292
2062	4,509	138	-	1,645	6,292
2063	4,509	138	-	1,645	6,292
2064	-	-	-	-	-
2065	-	-	-	-	-
2066	-	-	-	-	-
2067	-	-	-	-	-
2068	-	-	-	-	-
2069	-	-	-	-	-
2070	-	-	-	-	-
2071	-	-	-	-	-
2072	-	-	-	-	-
2073	-	-	-	-	-
2074	-	-	-	-	-
Total	230,033	86,743	-		357,441

Florida Power and Light Unit 1

SCENARIO 1 - Unit 1 SAFSTOR, DECON both following Unit 2 Shutdown Estimated DOE Reimbursement

Labor, Material/Equip, Waste, Other Direct Cost

, , , , , , , , , , , , , , , , , , ,					
Year	Labor	Material & Equipment	Waste Transportation & Disposal	Other Direct Cost	Total
2033	-	-	-	-	-
2034	-	-	-	-	-
2035	-	-	-	-	-
2036	-	-	-	-	-
2037	12,314	2,431	-	631	15,376
2038	11,687	2,366	-	768	14,821
2039	8,076	1,841	-	745	10,662
2040	6,321	1,567	-	740	8,628
2041	4,896	312	-	1,187	6,395
2042	4,896	312	-	1,187	6,395
2043	4,896	312	-	1,187	6,395
2044	4,896	312	-	1,187	6,395
2045	4,896	312	-	1,187	6,395
2046	7,396	22,812	-	1,187	31,395
2047	18,225	23,615	-	1,435	43,275
2048	2,295	79	-	822	3,196
2049	2,295	79	-	822	3,196
2050	2,295	79	-	822	3,196
2051	2,295	79	-	822	3,196
2052	2,295	79	_	822	3,196
2053	2,295	79	-	822	3,196
2054	2,295	79	-	822	3,196
2055	2,295	79	-	822	3,196
2056	2,295	79	-	822	3,196
2057	2,295	79	-	822	3,196
2058	2,295	79	-	822	3,196
2059	2,295	79	-	822	3,196
2060	2,295	79	-	822	3,196
2061	2,295	79	-	822	3,196
2062	2,295	79	-	822	3,196
2063	2,295	79	-	822	3,196
2064	-	-	-	-	-
2065	_	_	-	-	_
2066	_	_	-	-	-
2067	-		-	-	-
2068	_	_	-	-	_
2069	_	_	-	-	_
2070	-	<u> </u>	-		
2071	-		-		
2072	-	-	-		-
2072	-	<u> </u>	-	<u> </u>	
2073		<u> </u>	-		
Total	125,221	57,461	-	24,585	207,268
i Olai	120,221	37,401	•	24,505	201,200

Florida Power and Light Unit 2

SCENARIO 1 - Unit 1 SAFSTOR, DECON both following Unit 2 Shutdown Estimated DOE Reimbursement

Labor, Material/Equip, Waste, Other Direct Cost

Year	Labor	Material & Equipment	Waste Transportation & Disposal	Other Direct Cost	Total
2033	-	-	-	-	-
2034	-	-	-		-
2035	-	-	-		-
2036	-	-	-	-	-
2037	-	-	-	-	-
2038	-	-	-	-	-
2039	-	-	-	-	-
2040	-	-	-	-	-
2041	-	-	-	-	-
2042	-	-	-	-	-
2043	-	-	-	-	-
2044	14,986	1,457	-	540	16,983
2045	20,763	1,452	-	734	22,949
2046	13,757	21,070	-	716	35,542
2047	19,882	4,361	-	913	25,156
2048	2,214	59	-	824	3,096
2049	2,214	59	-	824	3,096
2050	2,214	59	-	824	3,096
2051	2,214	59	-	824	3,096
2052	2,214	59	-	824	3,096
2053	2,214	59	-	824	3,096
2054	2,214	59	-	824	3,096
2055	2,214	59	-	824	3,096
2056	2,214	59	-	824	3,096
2057	2,214	59	-	824	3,096
2058	2,214	59	-	824	3,096
2059	2,214	59	-	824	3,096
2060	2,214	59	•	824	3,096
2061	2,214	59	-	824	3,096
2062	2,214	59	-	824	3,096
2063	2,214	59	-	824	3,096
2064	-	-	-	-	-
2065	-	-	-	-	-
2066	-	-	-	-	-
2067	-	-	-	-	-
2068	-	-	-	-	-
2069	-	-	-	-	-
2070	-	-	-	-	-
2071	-	-	-	-	-
2072	-	-	-	-	-
2073	-	-	-		-
2074	-	-	-	-	-
Total	104,812	29,282	-	16,080	150,174

Florida Power and Light - St. Lucie Units 1 & 2 SCENARIO 2 - SAFSTOR

Estimated DOE Reimbursement

Labor, Material/Equip, Waste, Other Direct Cost

V	Laban	Material &	Waste	Other Direct	Total
Year	Labor	Equipment	Transportation & Disposal	Cost	Total
2033	-	-	-	-	•
2034	-	-	-	-	-
2035	-	-	-	-	-
2036	-	-	-	-	-
2037	12,297	2,336	-	631	15,264
2038	11,678	2,233	-	768	14,679
2039	8,071	1,747	-	745	10,562
2040	6,319	1,481	-	740	8,541
2041	4,762	287	-	1,781	6,829
2042	4,762	287	-	1,781	6,829
2043	4,762	287	-	1,781	6,829
2044	19,747	1,746	-	2,321	23,814
2045	25,524	1,744	-	2,515	29,783
2046	28,518	36,360	-	2,497	67,375
2047	30,462	35,437	-	2,969	68,868
2048	5,817	429	-	1,757	8,004
2049	5,817	429	-	1,757	8,004
2050	5,817	429	-	1,757	8,004
2051	5,817	429	-	1,757	8,004
2052	5,817	429	-	1,757	8,004
2053	5,817	429	-	1,757	8,004
2054	5,817	429	-	1,757	8,004
2055	5,817	429	-	1,757	8,004
2056	5,817	429	-	1,757	8,004
2057	5,817	429	-	1,757	8,004
2058	5,817	429	-	1,757	8,004
2059	5,817	429	-	1,757	8,004
2060	5,817	429	-	1,757	8,004
2061	5,817	429	-	1,757	8,004
2062	5,817	429	-	1,757	8,004
2063	5,817	429	-	1,757	8,004
2064	-	-	-	-	-
2065	-	-	-	-	-
2066	-	-	-	-	-
2067	-	-	-	-	-
2068	-	-	-	-	-
2069	-	-	-	-	-
2070	-	-	-	-	-

Florida Power and Light - St. Lucie Units 1 & 2 SCENARIO 2 - SAFSTOR

Estimated DOE Reimbursement

Labor, Material/Equip, Waste, Other Direct Cost

Year	Labor	Material & Equipment	Waste Transportation & Disposal	Other Direct Cost	Total
2071	-	-	-	-	-
2072	-	-	-	-	-
2073	-	-	-	-	-
2074	-	-	-	-	-
2075	-	-	-	-	-
2076	-	-	-	-	-
2077	-	-	-	-	-
2078	-	-	-	-	-
2079	-	-	-	-	-
2080	-	-	-	-	-
2081	-	-	-	-	-
2082	-	-	-	-	-
2083	-	-	-	-	-
2084	-	-	-	-	-
2085	-	-	-	-	-
2086	-	-	-	-	-
2087	-	-	-	-	-
2088	-	-	-	-	-
2089	-	-	-	-	-
2090	-	-	-	-	-
2091	-	-	-	-	-
2092	-	-	-	-	-
2093	-	-	-	-	-
2094	-	-	-	-	-
2095	-	-	-	-	-
2096	-	-	-	-	-
2097	-	-	-	-	-
2098	-	-	-	-	-
Total	249,977	90,816	-	46,637	387,430

Florida Power and Light - St. Lucie Unit 1 SCENARIO 2 - SAFSTOR

Estimated DOE Reimbursement

Labor, Material/Equip, Waste, Other Direct Cost

Year	Labor	Material & Equipment	Waste Transportation & Disposal	Other Direct Cost	Total
2033	-	-	-	-	-
2034	-	-	-	-	-
2035	-	-	-	-	-
2036	-	-	-	-	-
2037	12,297	2,336	-	631	15,264
2038	11,678	2,233	-	768	14,679
2039	8,071	1,747	-	745	10,562
2040	6,319	1,481	-	740	8,541
2041	4,762	287	-	1,781	6,829
2042	4,762	287	-	1,781	6,829
2043	4,762	287	-	1,781	6,829
2044	4,762	287	-	1,781	6,829
2045	4,762	287	-	1,781	6,829
2046	9,762	20,287	-	1,781	31,829
2047	15,580	26,073	-	2,056	43,709
2048	2,925	163	-	924	4,012
2049	2,925	163	-	924	4,012
2050	2,925	163	-	924	4,012
2051	2,925	163	-	924	4,012
2052	2,925	163	-	924	4,012
2053	2,925	163	-	924	4,012
2054	2,925	163	-	924	4,012
2055	2,925	163	-	924	4,012
2056	2,925	163	-	924	4,012
2057	2,925	163	-	924	4,012
2058	2,925	163	-	924	4,012
2059	2,925	163	-	924	4,012
2060	2,925	163	-	924	4,012
2061	2,925	163	-	924	4,012
2062	2,925	163	-	924	4,012
2063	2,925	163	-	924	4,012
2064	-	-	-	-	-
2065	-	-	-	-	-
2066	-	-	-	•	-
2067	-	-	-	-	-
2068	-	-	-	-	-
2069	-	-	-	-	-
2070	-	-	-	•	-

Florida Power and Light - St. Lucie Unit 1 SCENARIO 2 - SAFSTOR

Estimated DOE Reimbursement

Labor, Material/Equip, Waste, Other Direct Cost

Year	Labor	Material & Equipment	Waste Transportation & Disposal	Other Direct Cost	Total
2071	-	-	-	-	-
2072	-	-	-	-	-
2073	-	-	-	-	-
2074	-	-	-	-	-
2075	-	-	-	-	-
2076	-	-	-	-	-
2077	-	•	•	•	-
2078	-	-	-	-	-
2079	-	•	•	•	-
2080	-	•	•	•	-
2081	-	•	•	•	-
2082	-	•	•	•	-
2083	-	ı	•	ı	-
2084	-	ı	-	ı	-
2085	-	•	-	-	-
2086	-	ı	-	ı	-
2087	-	-	-	-	-
2088	-	ı	•	ı	-
2089	-	-	-	-	-
2090	-	-	-	-	-
2091	-	-	-	-	-
2092	-	-	-	-	-
2093	-	-	-	-	-
2094	-	-	-	-	-
2095	-	-	-	-	-
2096	-	-	-	-	-
2097	-	-	-	-	-
2098	-		-	-	-
Total	134,317	58,201	-	30,403	222,921

Florida Power and Light - St. Lucie Unit 2 SCENARIO 2 - SAFSTOR

Estimated DOE Reimbursement

Labor, Material/Equip, Waste, Other Direct Cost

Year	Labor	Material & Equipment	Waste Transportation & Disposal	Other Direct Cost	Total
2033	-	-	-	-	-
2034	-	-	-	-	-
2035	-	-	-	-	-
2036	-	-	-	-	-
2037	-	-	-	-	-
2038	-	-	-	-	-
2039	-	-	-	-	-
2040	-	-	-	-	-
2041	-	-	-	-	-
2042	-	-	-	-	-
2043	-	-	-	-	-
2044	14,986	1,459	-	540	16,985
2045	20,763	1,457	-	734	22,954
2046	18,757	16,073	-	716	35,546
2047	14,882	9,365	-	913	25,159
2048	2,892	266	-	833	3,992
2049	2,892	266	-	833	3,992
2050	2,892	266	-	833	3,992
2051	2,892	266	-	833	3,992
2052	2,892	266	-	833	3,992
2053	2,892	266	-	833	3,992
2054	2,892	266	-	833	3,992
2055	2,892	266	-	833	3,992
2056	2,892	266	-	833	3,992
2057	2,892	266	-	833	3,992
2058	2,892	266	-	833	3,992
2059	2,892	266	-	833	3,992
2060	2,892	266	-	833	3,992
2061	2,892	266	-	833	3,992
2062	2,892	266	-	833	3,992
2063	2,892	266	-	833	3,992
2064	-	-	-	-	-
2065	-	-	-	-	-
2066	-	-	-	-	-
2067	-	-	-	-	-
2068	-	-	-	-	-
2069	-	-	-	-	-
2070	-	-	-	-	-

Florida Power and Light - St. Lucie Unit 2 SCENARIO 2 - SAFSTOR

Estimated DOE Reimbursement

Labor, Material/Equip, Waste, Other Direct Cost

Year	Labor	Material & Equipment	Waste Transportation & Disposal	Other Direct Cost	Total
2071	-	-	-	-	-
2072	-	•	-	-	-
2073	-	-	-	-	-
2074	-	-	-	-	-
2075	-	-	-	-	-
2076	-	-	-	-	-
2077	-	-	-	-	-
2078	-	-	-	-	-
2079	-	-	-	-	-
2080	-	-	-	-	-
2081	-	-	-	-	-
2082	-	-	-	-	-
2083	-	-	-	-	-
2084	-	-	-	-	-
2085	-	-	-	-	-
2086	-	-	-	-	-
2087	-	-	-	-	-
2088	-	-	-	-	-
2089	-	-	-	-	-
2090	-	-	-	-	-
2091	-	-	-	-	-
2092	-	-	-	-	-
2093	-	•	-	-	-
2094	-	-	-	-	-
2095	-	-	-	-	-
2096	-	-	-	-	-
2097	-	•	-	-	-
2098	-	-	-	-	<u>-</u>
Total	115,661	32,616	-	16,234	164,510

Appendix G

Summary of Costs Shared Structures

	Unit 1	Unit 2	Total
Structures			
Contaminated Soil	68,949	63,636	132,585
Site Paving	1,299	1,299	2,598
Clean Concrete Processing	1,928	2,792	4,720
Security Improvements	1,144	1,144	2,288
Shared Miscellaneous Site Structures	-	5,063	5,063
Steam Generator Blowdown Facility	-	831	831
	73,320	74,765	148,085

SECTION 12

COMPARISON REPORT: Comparative Analysis of Cost Studies 2015 & 2020 Cost Studies



COMPARISON REPORT 2015 - 2020 of the St. Lucie Nuclear Plant, Units 1 and 2

Project No. 16	54086-01	Rev. 1
	Prepared for: Florida Power & Light Company	
	Prepared by: EnergySolutions, LLC 121 W. Trade Street, Suite 2700 Charlotte, NC 28202	
Authored By:	Kevin M. Kirkley, Sr. Estimator	
Approved By:	Jake H. Oleksiak, Project Controls Manager	Date 11/19/20 Date
		X New Report
		Title Change
		Report Revision
		Report Rewrite
	Effect Date:	11 1 40 0000

Table of Contents

SUMMARY	3
COMPARITIVE ANAYLSIS	5
Characterization / Surveys	6
Corporate Support (Fixed Overhead)	6
Decontamination & Removal	6
Energy	6
Florida LLRW Inspection Fee	6
INPO, NEI Fees	6
Insurance & Regulatory Fees	6
Misc Equipment / Site Services	7
Program Management	7
Property Taxes	7
Security	7
Spent Fuel Management	7
Spent Fuel Pool Isolation	8
Waste Packaging, Transportation & Disposal (Class A, B, & C)	8
Waste Packaging, transportation, & Disposal (GTCC)	8
CONCLUSION	10

SUMMARY

This document provides a comparative discussion on Decommissioning Cost Estimates (DCEs) prepared for the St. Lucie Nuclear Plant Units 1 and 2 (St. Lucie) in 2015 (by TLG Services, Inc.) and prepared in 2020 (by EnergySolutions). The estimates described in this document were constructed for a prompt decommissioning scenario (Prompt DECON) following the scheduled cessation of operations, recognizing that there is a seven-year offset in the scheduled shutdown dates for the two nuclear units. The scope of the two estimates is consistent, including cost subcategories for license termination, spent fuel management and site restoration activities.

The estimates were generated in 2015 and 2020 dollars, respectively. The 2020, or current estimate, was developed using the basic inventory and plant design information from the 2010 cost model. The data, estimating assumptions and site-specific considerations were reviewed for the 2015 analysis. The cost model was modified where new information was available, updated site-specific information was obtained, or experience from past decommissioning programs justified such changes.

The overall estimate to decommission St. Lucie (for the Integrated DECON alternative) decreased 3.4% over the five-year period between estimates or approximately a 0.7% decrease annually. The decrease (or increase) in the individual cost subcategories is shown in Table 1.

The cost elements were assigned to one of three subcategories: License Termination, Spent Fuel Management, and Site Restoration. Delegation of cost elements into these categories was for the purpose of comparison (e.g., with NRC financial guidelines) or to permit specific financial treatment [e.g., Asset Retirement Obligation (ARO) determinations]. In reality, there can be considerable interaction or overlap between the activities in the three subcategories.

2015 2020 Delta Percent **Annual Cost Subcategory** (\$1,000s) (\$1,000s) (\$1,000s) Change Change **License Termination** 1,208,237 1,254,740 0.8% 46,503 3.8% Spent Fuel Management 486,705 427,313 (59,392)-12.2% -2.6% -10.7% Site Restoration 111,537 63,409 (48,128)-43.1% Total 1,806,479 1,745,462 (61,017)-3.4% -0.7%

Table 1 – Cost Subcategory Comparison Between 2015 and 2020 Estimates

The subcategory License Termination was used to accumulate costs that are consistent with the NRC's definition of decommissioning in its financial assurance regulations (i.e., 10 CFR Part 50.75, Reporting and recordkeeping for decommissioning planning, etc.). The cost reported for this subcategory is generally sufficient to terminate the operating licenses for the two reactors, recognizing that there may be some additional cost impact from spent fuel management. The cost associated with St. Lucie License Termination activities increased 3.8% over the five years or approximately 0.8% increase annually. The primary driver is EnergySolutions' methodology of minimizing inefficient decontamination activity and removing buildings/structures as radiological in lieu of clean. Our experience has shown this method to reduce personnel exposure to dose, increase general site safety, and provide schedule certainty. Within the 2020 DCE are shifts in scope from the 2015 TLG study with the movement of the Reactor, Auxiliary Buildings, and the Fuel Handling Buildings to the License Termination subcategory from the Site

Restoration subcategory. The additional costs associated with the debris waste generated from this methodology is offset by the reduction in labor cost from avoiding extensive decontamination and survey efforts in structures. Disposal rates for all waste have been updated based on the 2020 LOP rates provided by FPL.

The Spent Fuel Management subcategory contains costs anticipated to be incurred once the nuclear units cease operation for the off-loading of the spent fuel from the pools either directly to the Department of Energy (DOE) or to an Independent Spent Fuel Storage Installation (ISFSI) for interim storage, and the eventual transfer of fuel from the ISFSI to the DOE. The 2020 DCE includes equipment and transfer costs only for shipment of spent fuel to the DOE prior to the cessation of the units, however any staffing costs that are deemed necessary for this work prior to cessation of the units is assumed to be covered by plant operating costs. Costs were also included for the operation of the ISFSI until such time that the transfer of all fuel from this facility to an off-site location (e.g., geologic repository or interim facility) is complete. The costs assigned to this subcategory decreased by 12.2% over the five years or approximately 2.6% decrease annually. A portion of this difference could be attributed to the number of canisters transferred directly to the DOE from the spent fuel pool (see Table 8). EnergySolutions assumes a certain split on allocated (undistributed) costs both in the Planning & Transition Period and the SAFSTOR period. It is unclear if this split on allocated costs is similar to what TLG utilized in the 2015 cost study. Also, the 2015 estimate includes the cost to expand the existing ISFSI (approximately \$0.8M), but the 2020 cost estimate does not. In addition, while the number of canisters to be purchased for spent fuel to be transferred to the ISFSI increased by 12 (as shown in Table 8), the cost is offset by the 25% reduction on costs due to the "bulk" purchase of the canisters. It is unclear if TLG included the transfer of spent fuel to the DOE from the Spent Fuel Pool prior the permanent shut down of the facility in the 2015 DCE. This cost has been excluded in the Energy Solutions 2020 DCE.

Site Restoration was used to capture costs associated with the dismantling and demolition of buildings and facilities demonstrated to be free from contamination. This includes structures never exposed to radioactive materials. Structures that have been exposed to radioactive material and require decontamination such as the Reactor Buildings, Auxiliary Buildings and the Fuel Handling Buildings are included in the License Termination subcategory of the 2020 DCE. Structures are removed to a depth of three feet below grade and backfilled to conform to local grade. The costs assigned to the Site Restoration subcategory decreased 43.1% decrease over the five years or approximately 10.7% decrease annually. The primary driver in this difference is the movement of the Reactor, Auxiliary Buildings, and the Fuel Handling Buildings to the License Termination subcategory. In addition, it is unclear how the TLG allocated costs (staffing, insurances, taxes, etc.) were derived. The majority of these costs in the 2020 study between Period 3 (License Termination) and Period 4 (Site Restoration) are split 93% to License Termination and 7% to Site Restoration.

COMPARATIVE ANAYLSIS

TLG completed a decommissioning cost analysis for St. Lucie in 2015. The analysis provided the Florida Power & Light Company (FPL), the owner and operator of the two nuclear units, with the projected costs (in 2015 dollars) to completely decontaminate and dismantle the station following the normal cessation of plant operations. For purposes of this comparison, this analysis is referred to as the 2015 estimate or previous analysis.

In 2020, Energy*Solutions* performed a new cost analysis for FPL. The current analysis uses the physical plant inventory and information provided by FPL to complete the current analysis. This data was reviewed, along with the assumptions from the previous analysis and other site-specific considerations. Based on experience from previous and ongoing decomissioning projects and previous proposal efforts, the St. Lucie cost analysis has been revised.

In 2015, the estimate to promptly decommission St. Lucie (Integrated DECON alternative) was estimated at approximately \$1,806.5 million (in 2015 dollars). The comparable cost in 2020 is \$1,745.5 million (in 2020 dollars). This represents a 3.4% decrease in the overall cost.

The decommissioning scope of the current cost estimate has not significantly changed from that evaluated presented in 2015.

In an attempt to compare the estimates, the costs have been broken down into 15 separate cost elements as shown in the Table 2 below. A brief description of the change and primary contributing cost element factor(s) to the change is detailed within the following narrative. As a general note to the below cost element comparisons: Energy *Solutions* has attempted to group the elements similarly to the 2010-2015 Comparison Report; however, it is unclear if all cost elements contain similar information/costs.

Table 2 – Cost Element Comparison Between 2015 and 2020 Estimates

Cost Flormant	2015	2020	Delta	Percent	Annual
Cost Element	(\$1,000s)	(\$1,000s)	(\$1,000s)	Change	Change
Characterization/Surveys	43,144	20,549	(22,595)	-52.4%	-13.8%
Corporate Support (Fixed Overhead)	19,387	17,592	(1,795)	-9.3%	-1.9%
Decontamination & Removal	243,751	253,063	9,312	3.8%	0.8%
Energy	46,828	10,690	(36,138)	-77.2%	-25.6%
Florida LLRW Inspection Fee	5,130	10,429	5,299	103.3%	15.2%
INPO, NEI Fees *	10,187	-	(10,187)	-100.0%	-100.0%
Insurance & Regulatory Fees	47,247	101,658	54,411	115.2%	16.6%
Misc. Equip/Site Services	16,783	9,203	(7,580)	-45.2%	-11.3%
Program Management	562,822	509,493	(53,329)	-9.5%	-2.0%
Property Taxes	10,493	3,495	(6,998)	-66.7%	-19.7%
Security	181,472	149,156	(32,316)	-17.8%	-3.8%
Spent Fuel Management	280,964	142,650	(138,314)	-49.2%	-12.7%
Spent Fuel Pool Isolation	21,250	23,231	1,981	9.3%	1.8%
Waste Packaging, Transportation &					
Disposal - Class A, B, C	285,103	440,182	155,079	54.4%	9.1%
Waste Packaging, Transportation &					
Disposal - GTCC	31,918	54,073	22,155	69.4%	11.1%
Total	1,806,479	1,745,462	(61,017)	-3.4%	-0.7%
* Items assumed to not be required po	st shutdown				

<u>Characterization / Surveys</u> – 52.4% decrease over the five years or approximately 13.8% decrease annually. The primary driver of this decrease is due to the methodology change. While additional costs associated with the debris waste generated from this methodology these costs are offset by the reduction in labor cost from avoiding extensive decontamination and survey efforts in structures. The 2020 estimate is based on previous experience for Site Characterizations, baseline surveys, and Final Status Surveys.

<u>Corporate Support (Fixed Overhead)</u> – Annual site costs provided increased from \$1.6 million in 2015 to \$1.8 million in 2020. However, the 2020 DCE accounts for a reduced staff and reduced site costs accordingly. These costs are applied across the Periods 1-4 in the DCE estimate.

<u>Decontamination & Removal</u> – 3.8% increase over the five years or approximately 0.8% increase annually. This increase, primarily due to escalation, was minimized due to change in methodology of decommissioning between TLG and Energy*Solutions*.

<u>Energy</u> – 77.2% reduction over the five year or approximately a 25.6% reduction annually. Based on discussions with FPL, the 2015 DCE utilized the heavy oil energy usage cost. The 2020 DCE utilizes the gas energy usage cost provided. For comparison the cost per kilowatt hour in the 2015 DCE was \$0.158 and the cost in the 2020 DCE is \$0.0338 per kilowatt hour.

<u>Florida LLRW Inspection Fee</u> – 103.3% increase over the five-year period or approximately a 25.6% increase annually. The change in methodology drove this increase. Due to additional waste being generated, additional inspection fees will be required.

<u>INPO</u>, <u>NEI Fees</u> – It is assumed that these are no longer required once the plant has permanently shut down.

Insurance & Regulatory Fees — 115.2% increase over the five-year period or approximately 16.5% annually. The primary driver of this increase is that the insurance cost is carried out until the spent fuel is removed from the site, this is for Periods 1-5. The 2015 TLG comparison report states that the Nuclear Property Insurance Premiums were significantly reduced after plant shutdown, however, in the 2020 DCE this rate was reduced at multiple decommissioning milestones. See Table 3 for the rates at shutdown. The reduction of insurance premiums is based on current and previous experience from other projects in the industry. In addition, Emergency Planning Fees (County & FEMA fees in the 2020 DCE) cease once all spent fuel is removed from the spent fuel pool.

The 2020 rates shown below in Table 3 do not contain contingency.

Table 3 – Insurance and Regulatory Comparison Between 2015 and 2020 Estimates

Annual Cost	2015	2020	
Nuclear Liability Insurance Premium (per unit)*	\$776,707	\$902,534	
Nuclear Property Insurance Premium (site)**	\$3,870,000	\$2,321,400	
NRC License Fee (per unit)	\$237,000	\$172,000	
Emergency Planning Fee (County & FEMA)***	\$917,488	\$1,563,868	
NRC Hourly Rate	\$268	\$278	

^{* 2020} rate assumes rate provide by FPL will be 50% at time of shutdown. Rate further reduced upon other decommissioning milestones.

<u>Misc. Equipment / Site Services</u> – 45.2% decrease over the five-year period or 11.3% decrease annually. The majority of the difference is due to the major construction equipment costs being included in the decontamination and removal portion of the 2020 estimate. It is unclear in the 2015 DCE where the construction equipment is included.

<u>Program Management</u> – 9.5% decrease over the five years or 2.0% decrease annually. Reduction is due to difference in staffing plan models from the 2015 to 2020 DCEs.

<u>Property Taxes</u> – 66.7% decrease over the five-year period or 19.7% decrease annually. The 2020 DCE assumes land only taxes will be paid post shutdown of Unit 1 and Unit 2. These costs were also adjusted for the time gap between when Unit 1 and Unit 2 shut down. This cost is carried until the ISFSI demolition is complete. It is unclear how property taxes were calculated in the 2015 TLG DCE.

<u>Security</u> – 17.8% decrease over the five-year period or 3.8% decrease annually. The main contributor to this decrease is the difference in security staffing.

<u>Spent Fuel Management</u> – 49.2% decrease over the five years or 12.7% decrease annually. The current 2015) analysis assumes that the DOE will begin the process of removing spent fuel from the St. Lucie site in 2033 (based upon a 2030 industry-wide start date), however, the DCE only includes spent fuel transferred after the units have permanently shut down. The process is expected to be completed by the year 2071. The schedule is slightly changed from the one presented in the 2015 DCE (Table 5).

A portion of this difference is due to the anticipated savings by FPL of 25% for the container material and equipment due to bulk purchasing. It is unclear if the comparison is comparing like items due to the major difference. The 2020 DCE costs include the ISFSI maintenance, spent fuel maintenance, all spent fuel transfers (both to DOE and ISFSI post shut down), and demolition of the ISFSI pad. Table 4 identifies a few of the major items included in the Spent Fuel Management comparison. The 2020 DCE assumes that no ISFSI expansion is required.

^{** 2020} rate shown is once plants are shutdown. Rate further reduced upon other decommissioning milestones

^{***} assumed no fee required once spent fuel is removed from the SFP

Table 4 – Spent Fuel Management Comparison Between 2015 and 2020 Estimates

Unit Costs (each)	2015	2020
Dry Storage Canister / Horizontal Storage Module	\$1,254,928	\$1,015,163
Loading / Transfer Cost	\$392,600	\$480,000
Pool to DOE Campaign Cost (Unit 1)	\$3,280,100	\$3,374,000
Pool to DOE Campaign Cost (Unit 2)*	-	\$2,261,000
Pool to ISFSI Cost**	\$3,280,100	-
ISFSI Unloading Cost	\$196,300	\$115,000
ISFSI Campaign Cost	\$820,025	-

^{*} Cost for Pool to DOE for Unit 2. Assumes 33% savings on equipment.

Table 5 – Spent Fuel Activity Comparison Between 2015 and 2020

Activity	2015	2020			
DOE Repository Opening	2030	030 2030			
Spent Fuel Transfer - Pool to DOE*	51 canisters 25 caniste				
Spent Fuel Transfer - Pool to ISFSI	50 canisters	62 canisters			
Spent Fuel Transfer - ISFSI to DOE	129 canisters	150 canisters			
Final Year of DOE Pickup	2073	2071			
ISFSI Operating Period					
(post unit 2 shutdown) (years)	30	28			
GTCC Canisters	14 canisters	12 canisters			
* 2020 quantity reflects quantity post shutdown of Units					

<u>Spent Fuel Pool Isolation</u> – 9.3% increase over the five years or 1.8% increase annually. Difference is primarily due to escalation between the years 2015 through 2020.

<u>Waste Packaging, Transportation & Disposal (Class A, B, & C)</u> – 54.4% increase over the five-year period or 9.1% increase annually. This increase is primarily due to the additional debris added due to methodology change. As shown in Table 6 the LLRW burial volume increased significantly due to the methodology change. In addition, the soil price increase is based on the updated Life-of-Plant agreement between Energy*Solutions* and FPL. TLG noted that disposal costs were discounted due to soil volume, Energy*Solutions* also discounted this rate slightly. Also, the Florida LLRW inspection fee is included in the waste costs.

Waste Packaging, Transportation & Disposal (GTCC) – 69.4% increase over the five-year period or 11.1% increase annually. Included in the 2020 DCE are 12 containers versus the 14 included in the 2015 DCE. The cost for disposal is approximately \$5,277 per cubic foot (including contingency) in the 2015 DCE as compared to approximately \$5,805 per cubic foot (including contingency) in the 2020 DCE. This delta can be attributed to the assumed escalation of the 2015 disposal costs. The transportation costs of the GTCC material is included in the disposal cost in the 2015 DCE, while the 2020 DCE includes approximately \$4.3M (including contingency) in transportation costs for GTCC in addition to the disposal cost. The packaging cost for GTCC between the 2015 DCE and 2020 DCE is significantly different. The

^{**} No fixed cost in 2020 DCE as the DCE assumes loading and transfer equipment for pool to DOE will be utilized for pool to ISFSI. Also, assumes a continuous operation, therefore no additional mobilization and demobilization will be required.

2015 DCE appears to include approximately \$2.8M (excluding contingency) where the 2020 DCE includes approximately \$14.1M (excluding contingency). The difference can be attributed to associated packaging cost captured in the other areas of the 2015 DCE (assumed to be included in the Reactor Vessel Internals packaging costs, but we are unable to verify the assumption).

Table 6 – Waste Comparison Between 2015 and 2020 Estimates

				Waste Volume (CF)	
Waste Class	Waste Form	Cost Basis	Class	2015	2020*
Low Level Radioactive Waste	Debris / Storm Drain **	Energy <i>Solutions</i>	Α	409,201	2,637,826
	Soil	Energy <i>Solutions</i>	А	1,969,897	2,013,205
	Debris	WCS	ВС	2,767	3,740
Greater than Class C (GTCC)	Modified Dry Storage Containers (DSCs)	Spent Fuel Equivalent	GTCC	5,772	5,772
Total Disposal Volume				2,387,637	4,660,543
Processed / Conditioned ***	Debris	Recycling Vendors	Α	332,863	-

^{* 2020} volume is burial volume.

^{**} Delta in Debris / Storm Drain due to differing Decommissioning methodology between TLG and EnergySolutions. Quantity includes additional concrete debris that will be removed as Class A, in lieu of clean.

^{***} Delta due to differing methodology between TLG and Energy Solutions.

CONCLUSION

The total cost to decommission the St. Lucie nuclear units decreased 3.4% over the five-year period between the 2015 and 2020 estimates or approximately 0.7% annually.

As shown in Table 1, License Termination costs (or the cost associated with "decommissioning" as defined by the NRC in its financial assurance regulations) increased 3.8% over the five-year period (for an average annual increase of 0.8%). The primary change in the cost increase is the result of the increase in the volume and cost for disposal of decommissioning waste streams (e.g. additional concrete debris generated due to change in methodology), as well as general increases in labor and material costs. In addition, the Reactor Buildings, Auxiliary Buildings, and Fuel Handling Buildings were moved from the Site Restoration subcategory to the License Termination subcategory.

The Spent Fuel Management subcategory contains costs associated with the interim storage of fuel at the St. Lucie site until such time that the DOE is able to take possession. The costs estimated for this activity decreased 12.2% from 2015. A portion of this difference could be attributed to the number of canisters transferred directly to the DOE from the spent fuel pool (see Table 5). EnergySolutions assumes a certain split on allocated (undistributed) costs both in the Planning & Transition Period and the SAFSTOR period. It is unclear if this split on allocated costs is similar to what TLG utilized in the 2015 cost study. Also, the 2015 estimate includes an expansion to the ISFSI, whereas the 2020 study does not. As noted in the spent fuel narrative, it is unclear if the TLG 2015 estimate included the spent fuel transfer to the DOE from the Spent Fuel Pool prior to shut down. This cost is excluded in the 2020 EnergySolutions DCE.

The Site Restoration subcategory showed a decrease of 43.1% over the five years. The primary contributor to this reduction is movement of the costs associated with the Reactor Buildings, Auxiliary Buildings, and Fuel Handling Buildings from the Site Restoration subcategory to the License Termination subcategory.

FLORIDA POWER & LIGHT COMPANY

2020 DECOMMISSIONING STUDY

TURKEY POINT NUCLEAR UNIT NOS. 3 & 4

December 2020

Florida Power & Light Company 2020 Decommissioning Study Turkey Point Nuclear Units

TABLE OF CONTENTS

Section Numbers:

- 1 EXECUTIVE SUMMARY
- **2** ASSUMPTIONS
- 3 SUPPORT SCHEDULE A

Nuclear Decommissioning Reserve Balance December 31, 2015 through October 31, 2020

4 SUPPORT SCHEDULE B

Nuclear Decommissioning Fund Balance December 31, 2015 through October 31, 2020

5 SUPPORT SCHEDULE C

Projected Fund and Reserve Balance at December 31, 2020

6 SUPPORT SCHEDULE D

Reconciliation of Projected Fund and Reserve Balance at December 31, 2020

7 SUPPORT SCHEDULE E

End-of-Life Materials and Supplies Inventory Expense Accrual Calculation

8 SUPPORT SCHEDULE F

End-of-Life Unamortized Nuclear Fuel Expense Accrual Calculation

9 SUPPORT SCHEDULE G

Inflation and Funding Analysis

10 DECOMMISSIONING COST ANALYSIS:

TURKEY POINT NUCLEAR PLANT UNITS 3 AND 4 Prepared by EnergySolutions, LLC

11 COMPARISON REPORT:

Comparative Analysis of Cost Studies 2015 & 2020 Cost Studies

SECTION 1

EXECUTIVE SUMMARY

Overview

FPL's 2020 Nuclear Decommissioning Study results are based on estimates and assumptions that follow Nuclear Regulatory Commission ("NRC") requirements and industry guidelines for the development of the costs to remove and dismantle nuclear power plants years into the future. Funds are maintained and interest is reinvested in the decommissioning trusts as required by the NRC, Internal Revenue Service, Federal Energy Regulatory Commission ("FERC") and Florida Public Service Commission ("FPSC" or the "Commission"). Under federal law, these funds may only be used for nuclear decommissioning, are not available for any other use and do not earn a return or profit for FPL. The study is essentially a snapshot, which shows that based on current assumptions FPL's nuclear decommissioning trust funds are appropriately funded, i.e., the current fund balances exceed the expected costs of decommissioning on a present value basis. Compared to 2015, the currently calculated funding position has improved due in part to the Turkey Point license extension which will allow funds to grow for an additional twenty years as well as a slight decrease in future decommissioning costs. FPL customers have not contributed to the decommissioning trusts since 2005, and the study confirms that, as of December 31, 2020, the trusts continue to be adequately funded without additional FPL customer contributions.

Decommissioning studies represent the aggregation of numerous estimates for activities and costs that will not be incurred for at least 15 years. As such, they are highly dependent upon input assumptions that can and will change over time, such that future funding positions could differ from today's position. The 2020 Nuclear Decommissioning Study was prepared by EnergySolutions, LLC ("EnergySolutions"). As such adjustments to the underlying assumptions referenced above netted an overall reduction in cost of 23.5% for Turkey Point and 3.4% for St. Lucie between the 2020 and 2015 studies. The decrease in cost for Turkey Point is primarily a result of the license extension. A detailed analysis of the changes in assumptions is provided in the last section (Section 11 and 12) of each site reports. The current assumed long-term fund earnings rate of 4.0 percent is 0.3 percent higher than the assumption utilized in the 2015 study due to changes in the allocations in the investment portfolio plus the impact of the Turkey Point license extension. Such changes, regardless of direction, reaffirm the importance of maintaining adequate funding and the value of the periodic review of these studies as required by FPSC rule.

2020 Study Approach

The information contained in this 2020 Decommissioning Study is presented in compliance with Rule 25-6.04365, Florida Administrative Code, and prior Commission Orders. FPL contracted EnergySolutions, a company experienced in managing nuclear decommissioning activities and a leader in radioactive waste management and disposal, to prepare its 2020 site-specific nuclear decommissioning cost analysis and comparison reports, which are estimated based on NRC requirements, industry guidelines, and prior experience. EnergySolutions includes the most up-to-date actual decommissioning information available to ensure the methodology used to prepare the cost analysis is reasonable.

FPL selected the DECON (immediate dismantlement) decommissioning option for its units. The DECON method provides not only a lower cost, but also enables a coordinated sequence of decommissioning events, which allows for a one-time mobilization of contractor personnel and equipment. FPL's choice of the DECON method is consistent with the method in prior studies approved by the Commission for purposes of determining FPL's appropriate accrual and funding requirements.

Escalation Rate

The 2020 Decommissioning Study assumes that future decommissioning costs grow at an average rate of approximately 3.15 percent per year. This is a small decrease over the average escalation rate of 3.19 percent assumed in the 2015 study. While FPL believes that the current escalation rates are reasonable for the purpose of the 2020 Decommissioning Study, it should be noted that subsequent changes in the assumed escalation rate could increase, which would result in higher projected future decommissioning costs.

Spent Fuel Management

Consistent with prior studies and assumptions approved by the Commission, the decommissioning cost estimates include the cost associated with interim storage of spent nuclear fuel ("SNF") on site until such time the Department of Energy ("DOE") is able to remove SNF from the site. Consistent with the 2015 study, FPL reflects the reimbursements from the US. Government to cover the cost incurred for managing and storing SNF that would not have been incurred but for DOE's delay in SNF disposal. As such and for purposes of this study, the DOE is expected to make payments to FPL to cover spent fuel management costs incurred by FPL prior to 2063 for St. Lucie and 2059 for Turkey Point. The ultimate timing and amount of reimbursements will depend on many factors, including but not limited to, the DOE's ability to receive SNF and the Government's compliance with the terms of the Settlement Agreement.

Conclusion

The 2020 Decommissioning Study indicates that the trusts are at an adequate funding level given current assumptions and projections. FPL has earned its customers' trust by using careful, prudent investment strategies in all facets of its business including the management of its nuclear decommissioning trusts. Despite market volatility, the funds remain secure. As a result, FPL's current annual expense accrual requirements for decommissioning costs presented in this study support a zero accrual and funding requirement as of December 31, 2020.

In addition, as required by the Commission in Order Nos. FPSC-02-0055-PAA-EI and FPSC-10-0153-FOF-EI, FPL has updated its estimates for End-of-Life Nuclear Fuel Last Core and End-of-Life Materials and Supplies Inventory balances for each of its nuclear sites. This information is provided for informational purposes with this study. FPL is not requesting a change in accruals at this time. Rather, FPL believes that the results of these updated values should be addressed in FPL's next base rate proceeding and that the appropriate changes in accruals, if any, should be made at that time.

ASSUMPTIONS

Page 1 of 9

Assumptions Summary

Following is a summary of the assumptions used to derive the annual accrual, and funding and revenue requirements. These assumptions are more fully developed on the following pages.

	Unit No. 3	<u>Unit No. 4</u>
Decommissioning Method	DECON (Prompt Removal/ Dismantling)	DECON (Prompt Removal/ Dismantling)
Total Decommissioning Cost Per EnergySolutions, LLC (Current cost estimate in 2020 \$)	\$652,646,000	\$708,547,000
FPL's Cost of Decommissioning - Jurisdictional (Current cost estimate in 2020 \$)	\$624,854,000	\$678,374,000
Method of Funding (2020 – End)	Qualified/ Nonqualified	Qualified/ Nonqualified
Funding Periods (Years to License Expiration)	31.54	32.29
Assumed Fund Earnings rate	4.0%	4.0%
Average Escalation Rate for Decommissioning Costs (2020 – End)	3.15%	3.13%
FPL Ownership Allocation (%)	100%	100%
FPSC Jurisdictional Separation Factor (%)	95.74%	95.74%
Estimated Fund Balance: Qualified Fund (As of 12/31/20)	\$526,785,000	\$603,540,000
Estimated Fund Balance: Nonqualified Fund (As of 12/31/20)	\$208,711,000	\$223,624,000

Page 2 of 9

	<u>Unit No. 3</u>	Unit No. 4
End of Life M & S Inventory Value: (As of 12/31/20)	N/A	\$42,881,138
End of Life Nuclear Fuel Last Core Value: (As of 12/31/20)	\$65,300,000	\$63,800,000
Year of Last Pick Up of Spent Fuel	2073	2073
Expected DOE Reimbursement (Current cost estimate in 2020 \$)	\$90,821,000	\$86,040,000

Decommissioning Methods

For purposes of this analysis, decommissioning is defined as the activity whereby nuclear facilities are removed safely from service and residual radioactivity is reduced to a level that permits release of the property for unrestricted use and termination of the operating license granted under Title 10 CFR Part 50. Decommissioning also includes the dismantlement, disposal and site restoration activities associated with the non-contaminated portion of the facilities. These activities are not required for termination of the operating license but are required to address other non-radiological requirements associated with the release of the site.

The Nuclear Regulatory Commission (NRC) has defined three acceptable decommissioning methods: Prompt Removal/Dismantling (DECON); Safe Storage/Deferred Decontamination (SAFSTOR); and Entombment (ENTOMB). The study utilizes the NRC terminology, but also includes the additional activities required to accommodate the non-contaminated portion of the facilities.

The DECON and SAFSTOR alternatives were both examined and are presented in the (EnergySolutions) Decommissioning Cost Analysis (Section 10) of this filing. The ENTOMB alternative was not considered, because it is considered impractical for a facility which generates significant amounts of long-lived radioactive material due to neutron activation. FPL selected the DECON decommissioning option for Turkey Point Units 3 and 4. The DECON method provides not only a lower cost, but also enables a sequence of events, which allows for a one-time mobilization of contractor personnel and equipment. This method is consistent with the method in prior studies approved by the Commission for purposes of determining the appropriate accrual and funding requirements.

Page 3 of 9

Total Decommissioning Costs

Below are the total estimated costs of decommissioning the Turkey Point facility as provided by FPL's consultant, EnergySolutions, LLC in 2020 dollars.

Turkey Point Unit No. 3	
Labor	\$358,772,000
Equip & Materials	102,330,000
Transportation	27,505,000
Burial	104,067,000
Other	<u>59,971,000</u>
Total	\$652,646,000
Turkey Point Unit No. 4	
Labor	\$346,399,000
Equip & Materials	119,049,000
Transportation	37,180,000
Burial	149,327,000
Other	56,592,000
Total	\$708,547,000

Funding Method

In Docket No. 810100-EU, Order No. 10987 issued July 13, 1982, the FPSC ordered FPL to establish a funded reserve. Beginning in 1983 FPL began making contributions, on a net of tax basis, to an externally funded reserve. In 1986, the Treasury Department issued temporary regulations under Internal Revenue Code Section 468A relating to the deductibility of contributions made to a qualified decommissioning fund. These regulations, which were finalized in March of 1988, provide for an annual election by the taxpayer to make tax-deductible contributions to a qualified nuclear decommissioning fund. Qualified nuclear decommissioning funds have been established by FPL for each of the four nuclear units. FPL elected to make contributions to the qualified funds, to the maximum allowed, for the years 1984 through 1987, 1992 through 2004 and for the year to date period ended August 31, 2005. Per the Stipulation and Settlement Agreement approved by the Commission in FPSC Order No. FPSC-05-0902-S-EI, FPL suspended accruals effective September 1, 2005, and as such, no additional contributions to the funds have been made subsequent to that date.

The funding analysis presented in Schedule G of this study indicates that no additional contributions

Page 4 of 9

to the qualified and nonqualified funds are projected to be required through the remainder of the funding period that ends with the expiration of the unit's operating license. Only the after-tax earnings of the trust fund investments are assumed to continue to be reinvested and accumulated in the respective funds. Future decommissioning expenditures are assumed to be distributed from the qualified and nonqualified funds in proportion to the balance accumulated at the time of expenditure.

Funding Period

The funding period, to the extent funding is required, is that period over which revenues are collected from ratepayers for purposes of decommissioning the Turkey Point Units. Funding periods for both units end on the last day of the month in which the operating license for the unit is due to expire. The operating license expiration dates for the Turkey Point units are as follows.

- Turkey Point Unit No. 3 July 19, 2052
- Turkey Point Unit No. 4 April 10, 2053

Based on the results of the funding analysis presented in Support Schedule G, no additional funding is required at this time.

Fund Earnings Rate

For purposes of this 2020 study update and funding analysis, the projected annual funds earnings rate, net of taxes and all other administrative costs charged to the trust funds, for Units 3 and 4 qualified and nonqualified fund investments, is assumed to be 4.0%. This assumption is based on a projected real long-term, after tax and net of fees, earnings rate of 2.0% plus an estimated long term average inflation rate of 2.0%. The long-term, after tax and net of fees earnings rate reflects the projection of continued adequacy of the funds and assumes a conservative investment strategy where the funds are moved to 100% fixed income prior to the first year of decommissioning and a more conservative all bonds & cash asset mix in the final years of decommissioning. FPL recognizes that over the long-term period there will likely be periods when the earned return may be greater or less than the assumed 4.0%. Consistent with prior Commission practice and Rule 25-6.04365 F.A.C., the assumptions presented in this 2020 decommissioning study will be reviewed and updated as appropriate "at least once every five years".

The annual rates of change in CPI were taken from "The U. S. Economy, The 30 – Year Outlook, August 2020", published by Global Insight.

Escalation Rate

Page 5 of 9

The annual escalation rates used to estimate total future dismantlement costs from 2020 through the final year of decommissioning are as follows:

	Average Annual Escalation Rate
Turkey Point Unit No. 3	3.15%
Turkey Point Unit No. 4	3.13%

The above rates were derived by applying separate inflation indices to each of the major cost components of Labor, Materials and Equipment, Transportation, Burial, and Other.

<u>Inflation Index</u>
Compensation per Hour (Nonfarm)
PPI - Intermediate Materials, Supplies, and Components
GDP Deflator – Transportation Services
FPL Analysis & CPI
GDP (Implicit)

For purposes of this 2020 study update, the inflation indices were obtained from "The U.S. Economy, The 30 – Year Outlook, August 2020", published by Global Insight except for the burial index.

The burial cost estimates are assumed to escalate at an average annual rate of 2.0%. This is a decrease of 1.2% from the rate assumed in the 2015 study. FPL has an agreement with EnergySolutions which provides for the long-term disposal of Class A waste generated during decommissioning. As such, burial costs for disposal of Class A waste is estimated based on the EnergySolutions agreement. In addition, the cost estimates for processed/conditioned (at off-site recycling center) disposal of Class A waste is assumed to be at a competitive rate comparable to the EnergySolutions pricing. Burial cost rates for Class B and Class C waste, not covered by the EnergySolutions Agreement, are less certain and based on rates equivalent to published Low Level Waste (LLW) Burial Site rates. The escalation rate applicable to Class B and C waste is assumed to be 1.5% which approximates the historical rate of change of the most recently published NRC NUREG 1307, Revision 17 which assumes the cost for disposal of Class B and C is the same as that for the Texas disposal facility located in states not affiliated with the Texas Compact. The resulting annual escalation rate of 2.0% is a weighted average rate for both St. Lucie and Turkey Point.

For a more detail calculation of the overall weighted average escalation rate and annual rate of change for each component please refer to Support Schedule G ("Inflation and Funding Analysis").

Page 6 of 9

FPSC Jurisdictional Factor

The factor applicable to both units is 95.7416%.

Fund Balances

Estimated/actual fund balances (qualified and nonqualified) at December 31, 2020^(a) for each of the two Turkey Point Units are as Follows:

	Qualified	<u>Nonqualified</u>
Unit No. 3	\$526,785,000	\$208,711,000
Unit No. 4	\$603,540,000	\$223,624,000

⁽a) Excluding unrealized market gains/losses.

See support Schedule C ("Projected Fund and Reserve Balances") for detail composition and adjustments to the qualified and nonqualified fund balances.

End of Life Materials and Supplies Inventory Values

The decommissioning cost estimates contained in the EnergySolutions Decommissioning Cost Analysis (Section 10) of this study and in the funding analysis contained in Support Schedule G of this filing do not take into consideration the unrecovered value of any Materials and Supplies Inventories that will ultimately exist at the site following shut down of both units. Both FPL and this Commission have previously recognized that there will be a level of inventories that will remain at the end of life of Unit No. 4, the last unit to reach end of license, which must be recovered prior to the end of site operations. These inventories are unique and will have little value other than scrap value when the units are decommissioned. In Order No. FPSC-02-0055-PAA-EI, the Commission authorized FPL to begin recording the amortization of estimated end of life materials and supplies costs as a base rate fuel expense with a credit to a separate (unfunded) sub-account of Reserve Account 228. Additionally, the Commission directed the Company to address the costs associated with the materials and supplies in subsequent decommissioning studies so that the related annual accruals can be revised, if warranted. The annual expense/reserve accruals associated with End of Life Inventories are being accounted for, as directed by the Commission, in a separate (unfunded) sub-account of Reserve Account 228.

Page 7 of 9

As provided in Support Schedule E of this study, the Materials and Supplies inventory balance, less estimated salvage, that is anticipated to remain at the end of life of Unit No. 4, the last unit to reach end of license, is projected to be \$42,881,138. The actual balance accrued as of December 31, 2020 is \$20,915,572. FPL is not requesting a change in accruals at this time. Rather, FPL believes that the results of these updated values for End of Life Materials and Supplies should be addressed in FPL's next base rate proceeding and the appropriate changes in accruals, if any, be made at that time.

End of Life Last Core Nuclear Fuel Values

FPL recognizes that there will be unburned fuel that will remain in the fuel assemblies at the end of the last operating cycle of each nuclear unit when it ceases operation. In Docket No 981246-EI the Commission found that the cost associated with the Last Core were costs that should be considered a base rate future obligation and that amortization of this obligation over the remaining life span of each nuclear unit ratably allocates the costs to those customers receiving the benefit of the nuclear generation and avoids a burdensome expense at the time of unit shut down. In Order No. FPSC-02-0055-PAA-EI the Commission authorized FPL to begin recording the amortization of estimated Last Core costs as a base rate fuel expense with a credit to a separate (unfunded) sub-account of Reserve Account 228. Additionally, the Commission directed the Company to address the costs associated with the Last Core in subsequent decommissioning studies so that the related annual accruals can be revised, if warranted. The annual expense/reserve accruals associated with End of Life Nuclear Fuel Last Core values are accounted for, as directed by the Commission, in a separate (unfunded) sub-account of Reserve Account 228.

As provided in Support Schedule F of this study, the estimated cost of unburned fuel remaining in the reactor at the end of life (end of license) for each unit is:

• Unit No. 3 \$65,300,000

• Unit No. 4 \$63,800,000

The actual balances accrued as of December 31, 2020 are:

• Unit No. 3 \$38,235,239

• Unit No. 4 \$33,626,367

Page 8 of 9

FPL is not requesting a change in accruals at this time. Rather, FPL believes that the results of these updated values for End of Life Nuclear Fuel Last Core should be addressed in FPL's next base rate proceeding and the appropriate changes in accruals, if any, be made at that time.

Spent Nuclear Fuel Storage

The Nuclear Waste Policy Act of 1982 assigns to the Federal Government responsibility to provide for the permanent disposal of spent nuclear fuel (SNF) and high-level radioactive waste (HLW), and committed the DOE to begin acceptance of SNF/HLW not later than January 31, 1998 under terms of its Standard Disposal Contracts with waste generators. The DOE has not yet provided for SNF storage and is not accepting SNF as committed to under the contract.

In Docket No. 941350-EI, and No. 981246-EI, the FPSC recognized the impact on the decommissioning process and the potential costs of on-site dry fuel storage resulting from the inability of the DOE to provide for the timely removal of SNF. In Order Nos. PSC-95-1531-FOF-EI and PSC-02-0055-PAA-EI, the FPSC specifically approved the inclusion of costs associated with the dry storage of spent nuclear fuel following the end of each units operating license which were considered necessary to accommodate the timely decommissioning of each unit.

Consistent with the Commission's prior findings, this updated 2020 decommissioning study includes the costs relating to the construction, operation, and dismantlement of an on-site independent spent fuel storage installation (ISFSI) that is required to accommodate the timely decommissioning of the Turkey Point units. The potential cost impact of extended spent fuel storage that will exist subsequent to the license expiration of the Turkey Point nuclear units is presented in (Section 10) of the 2020 Decommissioning Cost Analysis for the Turkey Point Plant. The decommissioning cost estimates included in this filing are based on the EnergySolutions prepared Decommissioning Cost Analysis for the Turkey Point Plant, Units 3 and 4 dated November, 2020.

In addition, FPL and certain nuclear plant joint owners signed a settlement agreement (spent fuel settlement agreement) with the U.S. Government in 2009 agreeing to dismiss with prejudice lawsuits filed against the U.S. Government seeking damages caused by the DOE's failure to dispose of spent nuclear fuel from FPL's nuclear plants. As such, the DOE is expected to continue to make payments to FPL to cover the costs incurred for managing and storing the spent fuel that it would not have incurred but for DOE's delay in performance.

Page 9 of 9

Below are the Turkey Point estimated costs of Decommissioning expected to be recovered from the DOE as provided by FPL's consultant, EnergySolutions, LLC in 2020 dollars.

Turkey Point Unit No. 3	
Labor	\$60,401,000
Equip & Materials	24,713,000
Other	<u>5,707,000</u>
Total	\$90,821,000
Turkey Point Unit No. 4	
Labor	\$53,116,000
Equip & Materials	28,033,000
Other	<u>4,891,000</u>
Total	\$86,040,000

Further discussion of the costs and assumptions regarding DOE reimbursement is contained in Section 5.0 of the Decommissioning Cost Analysis for the Turkey Point Plant, Units 3 and 4 dated November 2020. Consistent with prior Commission practice and Rule 25-6.04365 (FAC) the assumptions presented in this 2020 study related to DOE reimbursement will be reviewed and updated as appropriate "at least once every five years".

Annual Decommissioning Accrual Requirements

FPL's current annual expense accrual requirements for Turkey Point Nuclear Plant Decommissioning costs presented in this study support a zero accrual and funding requirement as of December 31, 2020. The decommissioning costs estimates, funding analysis, and supporting assumptions presented in this study were prepared in a manner consistent with prior Commission approved studies, methodologies and practices.

SUPPORT SCHEDULE A Nuclear Decommissioning Reserve Balance December 31, 2015 through October 31, 2020

Support Schedule: Nuclear Decommissioning Reserve Balances (1) December 31, 2015 through October 31, 2020

\$000

<u>December 31, 2015</u>	Beginning Balance	Revenues Collected	Earnings to Reserve	Ending Balance
NONQUALIFIED				
Turkey Point Unit No. 3	\$284,009	\$0	\$9,261	\$293,270
Turkey Point Unit No. 4	304,290	0	9,925	314,215
St. Lucie Unit No. 1	255,915	0	8,344	264,259
St. Lucie Unit No. 2	124,580	0	4,077	128,658
TOTAL	\$968,795	\$0	\$31,607	\$1,000,402
<u>QUALIFIED</u>				
Turkey Point Unit No. 3	\$413,367	\$0	\$16,479	\$429,846
Turkey Point Unit No. 4	473,635	0	18,879	492,514
St. Lucie Unit No. 1	535,493	0	21,345	556,838
St. Lucie Unit No. 2	489,737	0	19,499	509,236
TOTAL	\$1,912,231	\$0	\$76,202	\$1,988,434
TOTAL RESERVES				
Turkey Point Unit No. 3	\$697,375	\$0	\$25,740	\$723,116
Turkey Point Unit No. 4	777,925	0	28,804	806,729
St. Lucie Unit No. 1	791,408	0	29,689	821,097
St. Lucie Unit No. 2	614,317	0	23,576	637,894
TOTAL	\$2,881,026	\$0	\$107,810	\$2,988,836
<u>December 31, 2016</u>				
NONQUALIFIED				
Turkey Point Unit No. 3	\$293,270	\$0	\$11,772	\$305,041
Turkey Point Unit No. 4	314,215	0	12,615	326,831
St. Lucie Unit No. 1	264,259	0	10,606	274,866
St. Lucie Unit No. 2	128,658	0	5,183	133,840
TOTAL	\$1,000,402	\$0	\$40,176	\$1,040,578
<u>QUALIFIED</u>				
Turkey Point Unit No. 3	\$429,846	\$0	\$16,640	\$446,486
Turkey Point Unit No. 4	492,514	0	19,057	511,571
St. Lucie Unit No. 1	556,838	0	21,541	578,379
St. Lucie Unit No. 2	509,236	0	19,685	528,921
TOTAL	\$1,988,434	\$0	\$76,923	\$2,065,357
TOTAL RESERVES				
Turkey Point Unit No. 3	\$723,116	\$0	\$28,411	\$751,527
Turkey Point Unit No. 4	806,729	0	31,672	838,402
St. Lucie Unit No. 1	821,097	0	32,148	853,245
St. Lucie Unit No. 2	637,894	0	24,868	662,761
TOTAL	\$2,988,836	\$0	\$117,099	\$3,105,935

Support Schedule: Nuclear Decommissioning Reserve Balances (1) December 31, 2015 through October 31, 2020

\$000

December 31, 2017	Beginning Balance	Revenues Collected	Earnings to Reserve	Ending Balance
NONQUALIFIED				
Turkey Point Unit No. 3	\$305,041	\$0	\$7,893	\$312,934
Turkey Point Unit No. 4	326,831	0	8,459	335,289
St. Lucie Unit No. 1	274,866	0	7,112	281,978
St. Lucie Unit No. 2	133,840	0	3,475	137,316
TOTAL	\$1,040,578	\$0	\$26,939	\$1,067,517
QUALIFIED				
	\$446,486	\$0	\$21,022	\$467.500
Turkey Point Unit No. 3 Turkey Point Unit No. 4	511,571	0	\$21,023 24,078	\$467,509 535,649
St. Lucie Unit No. 1	578,379	0	27,221	605,600
St. Lucie Unit No. 2	528,921	0	24,871	553,792
TOTAL	\$2,065,357	\$0	\$97,193	\$2,162,550
	, ,		. ,	. , ,
TOTAL RESERVES				
Turkey Point Unit No. 3	\$751,527	\$0	\$28,916	\$780,443
Turkey Point Unit No. 4	838,402	0	32,537	870,938
St. Lucie Unit No. 1	853,245	0	34,333	887,578
St. Lucie Unit No. 2	662,761	0	28,346	691,107
TOTAL	\$3,105,935	\$0	\$124,132	\$3,230,067
NONQUALIFIED Turkey Point Unit No. 3 Turkey Point Unit No. 4 St. Lucie Unit No. 1 St. Lucie Unit No. 2	\$312,934 335,289 281,978 137,316	\$0 0 0	\$8,190 8,777 7,379 3,606	\$321,124 344,066 289,357 140,921
TOTAL	\$1,067,517	\$0	\$27,951	\$1,095,468
QUALIFIED		30		
Turkey Point Unit No. 3	\$467,509	\$0	\$15,703	\$483,212
Turkey Point Unit No. 4	535,649	0	17,986	553,635
St. Lucie Unit No. 1	605,600	0	20,335	625,935
St. Lucie Unit No. 2	553,792	0	18,576	572,367
TOTAL	\$2,162,550	\$0	\$72,600	\$2,235,150
TOTAL RESERVES				
Turkey Point Unit No. 3	\$780,443	\$0	\$23,892	\$804,336
Turkey Point Unit No. 4	870,938	0	26,763	897,701
St. Lucie Unit No. 1	887,578	0	27,714	915,292
St. Lucie Unit No. 2	691,107	0	22,181	713,289
TOTAL	\$3,230,067	\$0	\$100,551	\$3,330,618

Support Schedule: Nuclear Decommissioning Reserve Balances (1) December 31, 2015 through October 31, 2020

\$000

<u>December 31, 2019</u>	Beginning Balance	Revenues Collected	Earnings to Reserve	Ending Balance
<u>NONQUALIFIED</u>				
Turkey Point Unit No. 3	\$321,124	\$0	\$9,206	\$330,331
Turkey Point Unit No. 4	344,066	0	9,866	353,932
St. Lucie Unit No. 1	289,357	0	8,295	297,652
St. Lucie Unit No. 2	140,921	0	4,053	144,975
TOTAL	\$1,095,468	\$0	\$31,421	\$1,126,889
QUALIFIED				
Turkey Point Unit No. 3	\$483,212	\$0	\$22,002	\$505,214
Turkey Point Unit No. 4	553,635	0	25,198	578,833
St. Lucie Unit No. 1	625,935	0	28,486	654,421
St. Lucie Unit No. 2	572,367	0	26,028	598,395
TOTAL	\$2,235,150	\$0	\$101,713	\$2,336,863
TOTAL RESERVES				
Turkey Point Unit No. 3	\$804,336	\$0	\$31,208	\$835,544
Turkey Point Unit No. 4	897,701	0	35,064	932,765
St. Lucie Unit No. 1	915,292	0	36,781	952,073
St. Lucie Unit No. 2	713,289	0	30,081	743,370
TOTAL	\$3,330,618	\$0	\$133,135	\$3,463,752
October 31, 2020 NONQUALIFIED Turkey Point Unit No. 3 Turkey Point Unit No. 4 St. Lucie Unit No. 1 St. Lucie Unit No. 2 TOTAL	\$330,331 353,932 297,652 144,975 \$1,126,889	\$0 0 0 0 \$0	\$3,697 3,962 3,331 1,628 \$12,617	\$334,027 357,894 300,983 146,602 \$1,139,506
QUALIFIED				
Turkey Point Unit No. 3	\$505,214	\$0	\$17,976	\$523,190
Turkey Point Unit No. 4	578,833	0	20,589	599,422
St. Lucie Unit No. 1	654,421	0	23,277	677,698
St. Lucie Unit No. 2	598,395	0	21,265	619,660
TOTAL	\$2,336,863	\$0	\$83,107	\$2,419,970
TOTAL RESERVES				
Turkey Point Unit No. 3	\$835,544	\$0	\$21,673	\$857,217
Turkey Point Unit No. 4	932,765	0	24,550	957,316
St. Lucie Unit No. 1	952,073	0	26,608	978,681
St. Lucie Unit No. 2	743,370	0	22,892	766,262
TOTAL	\$3,463,752	\$0	\$95,724	\$3,559,476

SUPPORT SCHEDULE B
Nuclear Decommissioning Fund Balance
December 31, 2015 through October 31, 2020

Florida Power & Light Company 2020 Decommissioning Study Support Schedule: Nuclear Decommissioning Fund Balances (1) December 31, 2015 through October 31, 2020

	Beginning Balance	Contribution	Fund Earnings	Ending Balance
<u>December 31, 2015</u>				
NONQUALIFIED				
Turkey Point Unit No. 3	\$174,452	\$0	\$5,689	\$180,141
Turkey Point Unit No. 4	186,910	0	6,096	193,006
St Lucie Unit No. 1	157,196	0	5,126	162,321
St Lucie Unit No. 2	76,524	0	2,505	79,028
Total	\$595,081	\$0	\$19,415	\$614,496
<u>QUALIFIED</u>				
Turkey Point Unit No. 3	\$413,367	\$0	\$16,479	\$429,846
Turkey Point Unit No. 4	473,635	0	18,879	492,514
St Lucie Unit No. 1	535,493	0	21,345	556,838
St Lucie Unit No. 2	489,737	0	19,499	509,236
Total	\$1,912,231	\$0	\$76,202	\$1,988,434
<u>TOTAL</u>				
Turkey Point Unit No. 3	\$587,819	\$0	\$22,168	\$609,987
Turkey Point Unit No. 4	660,545	0	24,976	685,521
St Lucie Unit No. 1	692,689	0	26,470	719,159
St Lucie Unit No. 2	566,260	0	22,004	588,264
Total	\$2,507,313	\$0	\$95,617	\$2,602,930
<u>December 31, 2016</u>				
NONQUALIFIED				
Turkey Point Unit No. 3	\$180,141	\$0	\$7,231	\$187,372
Turkey Point Unit No. 4	193,006	0	7,749	200,755
St Lucie Unit No. 1	162,321	0	6,515	168,836
St Lucie Unit No. 2	79,028	0	3,183	82,212
Total	\$614,496	\$0	\$24,678	\$639,175
<u>QUALIFIED</u>				
Turkey Point Unit No. 3	\$429,846	\$0	\$16,640	\$446,486
Turkey Point Unit No. 4	492,514	0	19,057	511,571
St Lucie Unit No. 1	556,838	0	21,541	578,379
St Lucie Unit No. 2	509,236	0	19,685	528,921
Total	\$1,988,434	\$0	\$76,923	\$2,065,357
TOTAL				
Turkey Point Unit No. 3	\$609,987	\$0	\$23,871	\$633,857
Turkey Point Unit No. 4	685,521	0	26,806	712,327
St Lucie Unit No. 1	719,159	0	28,056	747,215
St Lucie Unit No. 2	588,264	0	22,868	611,132
Total	\$2,602,930	\$0	\$101,601	\$2,704,531

Florida Power & Light Company 2020 Decommissioning Study Support Schedule: Nuclear Decommissioning Fund Balances (1) December 31, 2015 through October 31, 2020

	Beginning Balance	Contribution	Fund Earnings	Ending Balance
<u>December 31, 2017</u>				
<u>NONQUALIFIED</u>				
Turkey Point Unit No. 3	\$187,372	\$0	\$4,848	\$192,220
Turkey Point Unit No. 4	200,755	0	5,196	205,951
St Lucie Unit No. 1	168,836	0	4,368	173,205
St Lucie Unit No. 2	82,212	0	2,135	84,346
Total	\$639,175	\$0	\$16,547	\$655,722
QUALIFIED				
Turkey Point Unit No. 3	\$446,486	\$0	\$21,023	\$467,509
Turkey Point Unit No. 4	511,571	0	24,078	535,649
St Lucie Unit No. 1	578,379	0	27,221	605,600
St Lucie Unit No. 2	528,921	0	24,871	553,792
Total	\$2,065,357	\$0	\$97,193	\$2,162,550
<u>TOTAL</u>				
Turkey Point Unit No. 3	\$633,857	\$0	\$25,872	\$659,729
Turkey Point Unit No. 4	712,327	0	29,274	741,600
St Lucie Unit No. 1	747,215	0	31,590	778,805
St Lucie Unit No. 2	611,132	0	27,005	638,138
Total	\$2,704,531	\$0	\$113,740	\$2,818,272
			_	
December 31, 2018				
<u>NONQUALIFIED</u>				
Turkey Point Unit No. 3	\$192,220	\$0	\$6,255	\$198,475
Turkey Point Unit No. 4	205,951	0	6,704	212,655
St Lucie Unit No. 1	173,205	0	5,636	178,841
St Lucie Unit No. 2	84,346	0	2,754	87,100
Total	\$655,722	\$0	\$21,349	\$677,071
QUALIFIED				
Turkey Point Unit No. 3	\$467,509	\$0	\$15,703	\$483,212
Turkey Point Unit No. 4	535,649	0	17,986	553,635
St Lucie Unit No. 1	605,600	0	20,335	625,936
St Lucie Unit No. 2	553,792	0	18,576	572,367
Total	\$2,162,550	\$0	\$72,600	\$2,235,150
TOTAL	Φ.C.5.0. 7.0.0	Φ0	#21 050	0.01.007
Turkey Point Unit No. 3	\$659,729	\$0	\$21,958	\$681,687
Turkey Point Unit No. 4	741,600	0	24,690	766,290
St Lucie Unit No. 1	778,805	0	25,971	804,776
St Lucie Unit No. 2	638,138	0	21,330	659,467
Total	\$2,818,272	\$0	\$93,948	\$2,912,220

Florida Power & Light Company 2020 Decommissioning Study Support Schedule: Nuclear Decommissioning Fund Balances (1) December 31, 2015 through October 31, 2020

	Beginning Balance	Contribution	Fund Earnings	Ending Balance
December 31, 2019				
NONQUALIFIED				
Turkey Point Unit No. 3	\$198,475	\$0	\$6,888	\$205,363
Turkey Point Unit No. 4	212,655	0	7,382	220,037
St Lucie Unit No. 1	178,841	0	6,207	185,047
St Lucie Unit No. 2	87,100	0	3,033	90,133
Total	\$677,071	\$0	\$23,510	\$700,580
QUALIFIED				
Turkey Point Unit No. 3	\$483,212	\$0	\$22,002	\$505,214
Turkey Point Unit No. 4	553,635	0	25,198	578,833
St Lucie Unit No. 1	625,936	0	28,486	654,421
St Lucie Unit No. 2	572,367	0	26,028	598,395
Total	\$2,235,150	\$0	\$101,713	\$2,336,863
<u>TOTAL</u>				
Turkey Point Unit No. 3	\$681,687	\$0	\$28,890	\$710,577
Turkey Point Unit No. 4	766,290	0	32,580	798,870
St Lucie Unit No. 1	804,776	0	34,692	839,469
St Lucie Unit No. 2	659,467	0	29,060	688,528
Total	\$2,912,220	\$0	\$125,223	\$3,037,443
October 31, 2020				
NONOLIALIEIED				
NONQUALIFIED Turkey Point Unit No. 3	\$205.262	\$0	\$2,789	\$208,153
Turkey Point Unit No. 4	\$205,363 220,037	0	2,989	223,026
St Lucie Unit No. 1	185,047	0	2,513	187,561
St Lucie Unit No. 2	90,133	0	1,228	91,361
Total	\$700,580	\$0	\$9,520	\$710,100
1000	\$700,200	Ψ	Ψ>,520	ψ/10,100
<u>QUALIFIED</u>				
Turkey Point Unit No. 3	\$505,214	\$0	\$17,976	\$523,190
Turkey Point Unit No. 4	578,833	0	20,589	599,422
St Lucie Unit No. 1	654,421	0	23,277	677,699
St Lucie Unit No. 2	598,395	0	21,265	619,660
Total	\$2,336,863	\$0	\$83,107	\$2,419,970
TOTAL				
Turkey Point Unit No. 3	\$710,577	\$0	\$20,765	\$731,343
Turkey Point Unit No. 4	798,870	0	23,578	822,448
St Lucie Unit No. 1	839,469	0	25,790	865,259
St Lucie Unit No. 2	688,528	0	22,493	711,021
Total	\$3,037,443	<u>\$0</u>	\$92,627	\$3,130,070

SUPPORT SCHEDULE C
Projected Fund and Reserve Balance at December 31, 2020

Support Schedule: Projected Fund and Reserve Balance at December 31, 2020 $^{\rm (a)}$ \$000

	TURKEY POINT UNIT 3	TURKEY POINT UNIT 4	ST. LUCIE UNIT 1	ST. LUCIE UNIT 2	TOTALS
NON-QUALIFIED FUND				(Note 1)	
Actual Fund Balance @ 10/31/2020	\$208,153	\$223,026	\$187,561	\$91,361	\$710,100
Add: Estimate Income Nov. & Dec. 2020 (after-tax)	558	598	503	246	1,904
Est/Actual Fund Balance @ 12/31/2020	\$208,711	\$223,624	\$188,063	\$91,606	\$712,004
QUALIFIED FUND Actual Fund Balance @ 10/31/2020 Add: Estimate Income Nov. & Dec. 2020 (after-tax) Est/Actual Fund Balance @ 12/31/2020	\$523,190 3,595 \$526,785	\$599,422 4,118 \$603,540	\$677,699 4,655 \$682,354	\$619,660 4,253 \$623,913	\$2,419,970 16,621 \$2,436,591
1307 Cital I and Balance (6, 12/31/2020	Ψ320,703	ψουσ,σ το	Ψ002,55 1	Ψ023,913	Ψ2,130,371
TOTAL FUND Actual Fund Balance @ 10/31/2020 Add: Estimate Income Nov. & Dec. 2020 (after-tax) Est/Actual Fund Balance @ 12/31/2020	\$731,343 4,153 \$735,496	\$822,448 4,716 \$827,163	\$865,259 5,158 \$870,417	\$711,021 4,499 \$715,519	\$3,130,070 18,525 \$3,148,595
NON-QUALIFIED RESERVE	¢224 027	\$2.57.90A	¢200.002	0146 602	¢1 120 50¢
Actual Reserve Balance @ 10/31/2020 Add: Estimate Income Nov. & Dec. 2020	\$334,027 739	\$357,894 792	\$300,983 666	\$146,602 325	\$1,139,506 2,522
Est/Actual Reserve Balance@12/31/2020	\$334,766	\$358,686	\$301,649	\$146,928	\$1,142,029
QUALIFIED RESERVE					
Actual Reserve Balance @ 10/31/2020	\$523,190	\$599,422	\$677,698	\$619,660	\$2,419,970
Add: Estimate Income Nov. & Dec. 2020	3,595	4,118	4,655	4,253	16,621
Est/Actual Reserve Balance@12/31/2020	\$526,785	\$603,539	\$682,354	\$623,913	\$2,436,591
TOTAL RESERVE Actual Reserve Balance @ 10/31/2020 Add: Estimate Income Nov. & Dec. 2020 Est. Actual Reserve Balance @ 12/31/2020	\$857,217 4,334 \$861,551	\$957,316 4,910 \$962,225	\$978,681 	\$766,262 4,578 \$770,841	\$3,559,476 19,144 \$3,578,620
Est/Actual Reserve Balance@12/31/2020	\$001,331	\$902,223	\$78 4, 003	\$110,841	\$3,378,02U

⁽a) Balances exclude unrealized market gains/losses.

Note 1: Amounts for St Lucie Common are included with Unit No. 2

SUPPORT SCHEDULE D
Reconciliation of Projected Fund and Reserve Balance
at December 31, 2020

Support Schedule: Reconciliation of Projected Fund and Reserve Balance at December 31, 2020 (a) \$000

RECONCILIATION FUND/RESERVE Projected 12/31/2020

	TURKEY	TURKEY			
	POINT	POINT	ST. LUCIE	ST. LUCIE	
	UNIT 3	UNIT 4	UNIT 1	UNIT 2	TOTALS
NON-QUALIFIED				(Note 1)	
Projected Fund Balance @12/31/2020	\$208,711	\$223,624	\$188,063	\$91,606	\$712,004
Remeasurement of Deferred Tax - Federal (Note 2)	\$41,402	\$44,359	\$37,305	\$18,166	\$141,232
Remeasurement of Deferred Tax - State (Note 3)	(\$193)	(\$206)	(\$172)	(\$84)	(\$654)
Deferred Tax @ 12/31/2020	\$84,847	\$90,909	\$76,453	\$37,239	\$289,447
Projected Reserve Balance @ 12/31/2020	\$334,766	\$358,686	\$301,649	\$146,928	\$1,142,029
OUALIEIED					
QUALIFIED	#526 795	DC02 540	Φ.CΩ2 2.5.4	Φ.C22.012	#2 42 <i>C</i> 501
Projected Fund Balance @12/31/2020	\$526,785	\$603,540	\$682,354	\$623,913	\$2,436,591
Deferred Tax @ 12/31/2020	0	0	0	0	0
Projected Reserve Balance @ 12/31/2020	\$526,785	\$603,540	\$682,354	\$623,913	\$2,436,591
TOTAL					
Projected Fund Balance @12/31/2020	\$735,496	\$827,163	\$870,417	\$715,519	3,148,595
Re-measurement of Deferred Tax - Federal	\$41,402	\$44,359	\$37,305	\$18,166	141,232
Re-measurement of Deferred Tax - State	(193)	(206)	(172)	(84)	(654)
Deferred Tax @ 12/31/2020	84,847	90,909	76,453	37,239	289,447
Projected Reserve Balance @ 12/31/2020	\$861,551	\$962,226	\$984,003	\$770,840	\$3,578,620
DEFERRED TAXES					
Projected balance @ 12/31/2020					
NON-QUALIFIED FUND					
Balance @ 10/31/2020 (Fed & State)	\$84,659	\$90,708	\$76,284	\$37,156	\$288,808
Add: Tax on Earnings - November & December	187	201	169	82	639
Balance @ 12/31/2020 (Fed & State)	\$84,847	\$90,909	\$76,453	\$37,239	\$289,447

(a) Balances exclude unrealized market gains/losses.

Note (1): Amounts for St Lucie Common are included with Unit No. 2

Note (2): In December 2017, new tax reform legislation was signed into law which reduced the federal corporate income tax rate from 35% to 21% effective January 1, 2018. As a result, FPL remeasured its deferred tax assets to the new federal corporate tax rate of 21%, which resulted in a reduction of deferred tax assets by \$141 million. This amount was recorded as a regulatory asset.

Note (3): In 2019 the Florida corporate income tax rate was changed from 5.5% to 4.458%. The tax rate change was retroactive to Jan 1, 2018 and is for the periods of 2018 through 2021. The rate reverts back to 5.5% in 2022. Trust fund earnings are taxed at the current tax rate in effect, 4.458% for the periods of 2018 through 2021, while the deferred tax asset is recorded using 5.5% for the same period resulting in variances.

SUPPORT SCHEDULE E
End-of-Life Materials and Supplies Inventory
Expense Accrual Calculation

Florida Power and Light Company 2020 Decommissioning Study Support Schedule: End-of-Life Materials and Supplies Inventory

Line <u>Number</u>		Turkey Point <u>Unit 4</u>
1	Adjusted Ending Inventory Value @ End of License	\$ 43,794,727
2	Estimated Salvage	(913,589)
3	Inventory Subject to Write-off	\$ 42,881,138
4		
5	FPL's Ownership Share 100%	\$ 42,881,138
6		
7	Actual Reserve Balance Accrued as of 12/31/20	20,915,572
8		
9	Remaining Amount to be Recovered as of 12/31/20	\$ 21,965,566
10		
11		
12	Total Number of Months From:	
13	12/31/20 to End of License 4/10/2053	387.5

SUPPORT SCHEDULE F
End-of-Life Unamortized Nuclear Fuel
Expense Accrual Calculation

Florida Power and Light Company 2020 Decommissioning Study Support Schedule: End-of-Life Unamortized Nuclear Fuel

Line <u>Number</u>		Turkey Point <u>Unit 3</u>	Turkey Point <u>Unit 4</u>
1	Estimated Cost of Unburned Fuel @ End of License		
2	FPL's Ownership Share (100%)	\$ 65,300,000	\$ 63,800,000
3			
4	Actual Reserve Balance at 12/31/2020	38,235,239	33,626,367
5			
6	Remaining Amount to be Recovered at 12/31/2020	\$ 27,064,761	\$ 30,173,633
7			
8			
9	Total Number of Months From:		
10	12/31/20 to End of License	378.5	387.5

SUPPORT SCHEDULE G Inflation and Funding Analysis

Florida Power & Light Company 2020 Decommissioning Study Support Schedule : Inflation and Funding Analysis

INFLATION FORECAST

The U.S. Economy 30 Year Outlook (AUGUST 2020) GLOBAL INSIGHT

	PCJPGDP	PCJWSSNF	PCWPISOP2000	PCCSVTS	FPL (INTERNAL)		CPI
YEAR	GDP	HRLY COMP	PPI INT M&S	GDP Transport	Burial	СРІ	CPI MULTIPLIER
2020	0.9%	5.9%	-4.1%	-22.2%	2.0%	1.0%	1.000
2021	1.1%	0.5%	2.3%	18.0%	2.0%	1.7%	1.017
2022	1.2%	1.8%	2.5%	11.9%	2.0%	1.7%	1.034
2023	1.5%	2.2%	1.7%	9.6%	2.0%	0.8%	1.042
2024	1.8%	2.7%	1.8%	8.7%	2.0%	1.3%	1.056
2025	2.1%	3.3%	1.4%	6.2%	2.0%	2.0%	1.076
2026	2.3%	3.7%	1.3%	4.9%	2.0%	2.3%	1.101
2027	2.4%	4.0%	1.2%	4.3%	2.0%	2.5%	1.129
2028	2.5%	4.1%	1.1%	4.1%	2.0%	2.4%	1.156
2029	2.4%	4.1%	0.9%	4.4%	2.0%	2.3%	1.183
2030	2.4%	4.1%	0.8%	4.7%	2.0%	2.2%	1.210
2031	2.3%	4.0%	0.8%	4.3%	2.0%	2.1%	1.235
2032	2.3%	4.0%	1.1%	3.9%	2.0%	2.1%	1.261
2033	2.2%	4.0%	0.9%	3.8%	2.0%	2.0%	1.286
2034	2.2%	4.0%	1.0%	3.7%	2.0%	2.0%	1.312
2035	2.2%	4.0%	1.1%	3.5%	2.0%	2.0%	1.338
2036	2.1%	3.9%	1.1%	3.4%	2.0%	2.0%	1.365
2037	2.1%	3.9%	1.4%	3.2%	2.0%	2.0%	1.393
2038	2.1%	3.9%	1.5%	3.1%	2.0%	2.1%	1.421
2039	2.1%	3.9%	1.3%	3.1%	2.0%	2.0%	1.450
2040	2.1%	3.9%	1.4%	3.1%	2.0%	2.1%	1.480
2041	2.2%	3.9%	1.4%	3.1%	2.0%	2.1%	1.511
2042	2.2%	3.9%	1.4%	3.0%	2.0%	2.1%	1.542
2043	2.2%	3.9%	1.3%	3.0%	2.0%	2.1%	1.574
2044	2.2%	3.8%	1.4%	3.0%	2.0%	2.1%	1.607
2045	2.2%	3.8%	1.5%	3.0%	2.0%	2.1%	1.642
2046	2.2%	3.8%	1.5%	3.0%	2.0%	2.1%	1.677
2047	2.2%	3.8%	1.5%	3.0%	2.0%	2.2%	1.713
2048	2.3%	3.8%	1.6%	3.1%	2.0%	2.2%	1.750
2049	2.3%	3.8%	1.7%	3.1%	2.0%	2.2%	1.788
2050	2.3%	3.8%	1.7%	3.1%	2.0%	2.2%	1.828
2051	2.3%	3.8%	1.7%	3.1%	2.0%	2.2%	1.868
2052	2.3%	3.8%	1.7%	3.1%	2.0%	2.2%	1.909
2053	2.3%	3.8%	1.7%	3.1%	2.0%	2.2%	1.951
2054	2.3%	3.8%	1.7%	3.1%	2.0%	2.2%	1.994
2055	2.3%	3.8%	1.7%	3.1%	2.0%	2.2%	2.038
2056	2.3%	3.8%	1.7%	3.1%	2.0%	2.2%	2.083
2057	2.3%	3.8%	1.7%	3.1%	2.0%	2.2%	2.129
2058	2.3%	3.8%	1.7%	3.1%	2.0%	2.2%	2.176
2059	2.3%	3.8%	1.7%	3.1%	2.0%	2.2%	2.223
2060	2.3%	3.8%	1.7%	3.1%	2.0%	2.2%	2.272
2061	2.3%	3.8%	1.7%	3.1%	2.0%	2.2%	2.322
2062	2.3%	3.8%	1.7%	3.1%	2.0%	2.2%	2.374
2063	2.3%	3.8%	1.7%	3.1%	2.0%	2.2%	2.426
2064	2.3%	3.8%	1.7%	3.1%	2.0%	2.2%	2.479
2065	2.3%	3.8%	1.7%	3.1%	2.0%	2.2%	2.534
2066	2.3%	3.8%	1.7%	3.1%	2.0%	2.2%	2.590
2067	2.3%	3.8%	1.7%	3.1%	2.0%	2.2%	2.647
2068	2.3%	3.8%	1.7%	3.1%	2.0%	2.2%	2.705
2069	2.3%	3.8%	1.7%	3.1%	2.0%	2.2%	2.764
2070	2.3%	3.8%	1.7%	3.1%	2.0%	2.2%	2.825
2071	2.3%	3.8%	1.7%	3.1%	2.0%	2.2%	2.887
2072	2.3%	3.8%	1.7%	3.1%	2.0%	2.2%	2.951
2073	2.3%	3.8%	1.7%	3.1%	2.0%	2.2%	3.016
2074	2.3%	3.8%	1.7%	3.1%	2.0%	2.2%	3.082
2075	2.3%	3.8%	1.7%	3.1%	2.0%	2.2%	3.150

Florida Power & Light Company 2020 Decommissioning Study Support Schedule : Inflation and Funding Analysis

Support Schedule G Page 2 of 8

GENERAL ASSUMPTIONS

JURISDICTIONAL FACTOR = 95.7416%

FPL'S SHARE OF ST. LUCIE 2 COST (NET OF PARTICIPANTS) 86.44612%

CORPORATE TAX RATE 24.522%

ANNUAL MONTHLY EARNINGS RATE QUALIFIED FUND 4.000% 0.327374% EARNINGS RATE NON-QUALIFIED FUND 4.000% 0.327374%

	TP3	TP4	SL1	SL2
Adjusted QUALIFIED FUNDING % (at 12/31/20)	61.144%	62.723%	69.345%	80.939%
FUND BALANCES (\$000's)				
FUND BALANCES (\$000 S)				
A. QUALIFIED FUND BALANCE 10/31/20	523,190	599,422	677,699	619,660
B. CONTRIBUTIONS - Nov. & Dec. 2020	-	-	-	-
C. EARNINGS - Nov. & Dec. 2020	3,595	4,118	4,655	4,253
D. QUALIFIED FUND BALANCE 12/31/20	526,785	603,540	682,354	623,913
E. JURISDICTIONAL FACTOR	95.7416%	95.7416%	95.7416%	95.7416%
F. JURIS. QUAL. FUND BAL. 12/31/20	504,352	577,838	653,297	597,344
A. NON-QUALIFIED FUND BALANCE 10/31/20	208,153	223,026	187,561	91,361
B. CONTRIBUTIONS - Nov. & Dec. 2020	-	-	-	-
C. EARNINGS - Nov. & Dec. 2020	558	598	503	246
D. NON-QUALIFIED FUND BALANCE 12/31/20	208,711	223,624	188,063	91,606
E. JURISDICTIONAL FACTOR	95.7416%	95.7416%	95.7416%	95.7416%
F. JURIS. NON-QUAL. FUND BAL. 12/31/20	199,823	214,101	180,055	87,705
Juris Est/Actual Fund Palance	704 175	701 020	922 251	695.040

 Juris. Est/Actual Fund Balance
 704,175
 791,939
 833,351
 685,049

 Juris. Est/Actual Reserve Balance
 824,863
 921,250
 942,100
 738,015

Support Schedule: Inflation and Funding Analysis

			urkey Point Nucle CON - Total Deco (thousands, 20	mmissioning Cost					Avionago					
		Equipment &							Equipment &					Average
Year	Labor	Materials	Transportation	LLRW Disposal	Other	Yearly Totals	Year	Labor	Materials	Transportation	Burial	Other	Yearly Totals	Inflation Rate
2052	10,954	1,126	-	-	2,274	14,354	2052	34,074.51	1,762.21	-	-	4,476.37	40,313	3.28%
2053	37,627	2,718	-	-	5,003	45,347	2053	121,462	4,327	-	-	10,073	135,863	3.38%
2054	21,953	1,870	-	-	4,754	28,577	2054	73,541	3,029	-	-	9,791	86,361	3.31%
2055	21,340	16,698	-	-	5,523	43,561	2055	74,185	27,516	-	-	11,636	113,337	2.77%
2056	42,576	4,771	4,645	-	8,933	60,925	2056	153,594	7,999	22,200	-	19,252	203,046	3.40%
2057	31,594	17,117	664	4,893	7,383	61,651	2057	118,275	29,196	3,271	10,356	16,277	177,376	2.90%
2058	35,477	17,787	1,304	7,024	3,876	65,469	2058	137,826	30,867	6,630	15,171	8,742	199,236	2.97%
2059	48,420	17,650	2,471	8,676	4,166	81,382	2059	195,206	31,161	12,960	19,121	9,609	268,058	3.10%
2060	43,447	10,895	7,676	27,972	2,924	92,914	2060	181,767	19,570	41,521	62,913	6,900	312,670	3.08%
2061	22,351	6,145	8,359	33,167	2,605	72,627	2061	97,040	11,229	46,638	76,123	6,287	237,317	2.93%
2062	11,619	2,769	2,385	8,796	2,389	27,958	2062	52,348	5,149	13,727	20,602	5,898	97,723	3.02%
2063	3,827	559	-	-	1,572	5,958	2063	17,895	1,058	-	-	3,970	22,922	3.18%
2064	2,236	94	-	-	867	3,198	2064	10,850	181	-	-	2,241	13,273	3.29%
2065	2,236	94	-	-	867	3,198	2065	11,260	184	-	-	2,292	13,737	3.29%
2066	2,236	94	-	-	867	3,198	2066	11,685	187	-	-	2,345	14,217	3.30%
2067	2,236	94	-	-	867	3,198	2067	12,126	191	-	-	2,399	14,715	3.30%
2068	2,236	94	-	-	867	3,198	2068	12,583	194	-	-	2,454	15,231	3.31%
2069	2,236	94	-	-	867	3,198	2069	13,058	197	-	-	2,510	15,766	3.31%
2070	2,236	94	-	-	867	3,198	2070	13,551	201	-	-	2,567	16,319	3.31%
2071	2,334	94	-	3,385	892	6,705	2071	14,674	205	-	9,513	2,702	27,094	2.78%
2072	2,626	96	-	6,774	994	10,489	2072	17,134	212	-	19,428	3,080	39,854	2.60%
2073	6,588	1,336	-	3,381	590	11,895	2073	44,612	3,002	-	9,897	1,869	59,380	3.08%
2074	386	39	-	-	23	448	2074	2,713	90	-	-	74	2,878	3.50%
2075	-	-	-	-	-	-	2075	-	-	-	-	-	-	
Total	358,772	102,330	27,505	104.067	59,971	652,646	Total	1,421,461	177,707	146,947	243,125	137,445	2,126,685	3.15%

NOTE: The 2020 cash flows are inflated to the year of expenditure based on the indices provided on Support Schedule G, page 1 of 8

Florida Power & Light Company 2020 Decommissioning Study Turkey Point Nuclear Units Support Schedule: Inflation and Funding Analysis

			urkey Point Nucle CON - Total Deco (thousands, 20	mmissioning Cost					Avionago					
		Equipment &							Equipment &					Average
Year	Labor	Materials	Transportation	LLRW Disposal	Other	Yearly Totals	Year	Labor	Materials	Transportation	Burial	Other	Yearly Totals	Inflation Rate
2053	19,611	1,954	-	-	3,529	25,093	2053	63,304.54	3,110.66	-	-	7,105.11	73,520	3.31%
2054	27,303	2,331	-	-	4,859	34,493	2054	91,461	3,776	-	-	10,009	105,246	3.34%
2055	23,262	21,937	-	-	6,470	51,669	2055	80,867	36,149	-	-	13,633	130,648	2.69%
2056	35,827	3,559	3,868	-	7,237	50,491	2056	129,246	5,966	18,485	-	15,598	169,296	3.42%
2057	32,202	11,965	1,401	3,750	6,980	56,299	2057	120,554	20,409	6,906	7,937	15,389	171,195	3.05%
2058	34,874	13,746	1,780	3,992	5,341	59,733	2058	135,482	23,854	9,053	8,621	12,044	189,055	3.08%
2059	48,696	19,347	2,539	10,778	4,689	86,049	2059	196,320	34,157	13,313	23,756	10,816	278,362	3.06%
2060	47,020	18,470	5,140	18,957	2,824	92,411	2060	196,718	33,175	27,802	42,637	6,664	306,997	3.05%
2061	31,130	16,283	14,003	66,744	2,542	130,702	2061	135,152	29,756	78,122	153,188	6,137	402,355	2.78%
2062	16,566	7,175	7,025	27,567	2,361	60,695	2062	74,639	13,339	40,427	64,566	5,831	198,801	2.87%
2063	3,252	439	1,424	3,999	1,532	10,647	2063	15,205	831	8,452	9,558	3,869	37,915	3.00%
2064	2,259	100	-	-	835	3,193	2064	10,959	192	-	-	2,158	13,308	3.30%
2065	2,259	100	-	-	835	3,193	2065	11,372	195	-	-	2,207	13,774	3.30%
2066	2,259	100	-	-	835	3,193	2066	11,801	199	-	-	2,258	14,257	3.31%
2067	2,259	100	-	-	835	3,193	2067	12,247	202	-	-	2,309	14,758	3.31%
2068	2,259	100	-	-	835	3,193	2068	12,709	205	-	-	2,362	15,277	3.31%
2069	2,259	100	-	-	835	3,193	2069	13,188	209	-	-	2,417	15,814	3.32%
2070	2,259	100	-	-	835	3,193	2070	13,686	213	-	-	2,472	16,371	3.32%
2071	2,356	100	-	3,385	860	6,700	2071	14,814	217	-	9,513	2,604	27,148	2.78%
2072	2,633	101	-	6,773	944	10,451	2072	17,182	224	-	19,428	2,922	39,756	2.60%
2073	5,555	917	-	3,382	555	10,409	2073	37,619	2,060	-	9,899	1,759	51,337	3.06%
2074	302	27	-	-	23	351	2074	2,121	61	-	-	74	2,256	3.50%
2075	-	-	-	-	-	-	2075	-	-	-	-	-	-	
Total	346,399	119,049	37,180	149,327	56,592	708,547	Total	1,396,647	208,501	202,559	349,103	130,637	2,287,447	3.13%

NOTE: The 2020 cash flows are inflated to the year of expenditure based on the indices provided on Support Schedule G, page 1 of 8

Support Schedule: Inflation and Funding Analysis

	Cost	s Recovered fo	DECON	Fuel Manag			Turkey Point Nuclear Plant, Unit 3 DECON Costs Recovered for Spent Fuel Management (thousands, Future dollars)											
		Equipment		LLRW		Yearly			Equipment									
Year	Labor	& Materials	Energy	Disposal	Other	Totals	Year	Labor	& Materials	Transport	Burial	Other	Yearly Totals					
2052	-	-	-	-	-	-	2052	-	-	-	-	-	-					
2053	6,377	1,000	-	-	385	7,762	2053	20,585	1,592	-	-	775	22,953					
2054	17,895	2,335	-	-	864	21,095	2054	59,947	3,782	-	-	1,780	65,510					
2055	10,545	1,662	-	-	817	13,024	2055	36,659	2,739	-	-	1,721	41,119					
2056	8,202	16,433	-	-	809	25,444	2056	29,589	27,551	-	-	1,743	58,883					
2057	12,909	3,094	-	-	1,097	17,100	2057	48,328	5,277	-	-	2,418	56,023					
2058	2,236	94	-	-	867	3,198	2058	8,688	163	-	-	1,956	10,807					
2059	2,236	94	-	-	867	3,198	2059	9,016	166	-	-	2,001	11,183					
2060	-	-	-	-	-	-	- 2060											
Total	60,401	24,713	-	-	5,707	90,821	Total	212,812	41,271	-	-	12,395	266,478					

NOTE: The 2020 cash flows are inflated to the year of expenditure based on the indices provided on Support Schedule G, page 1 of a

Support Schedule: Inflation and Funding Analysis

	Cost	s Recovered fo	DECON	Fuel Manaş			Turkey Point Nuclear Plant, Unit 4 DECON Costs Recovered for Spent Fuel Management (thousands, Future dollars)											
		Equipment	_	LLRW		Yearly			Equipment	_								
Year	Labor	& Materials	Energy	Disposal	Other	Totals	Year	Labor	& Materials	Transport	Burial	Other	Yearly Totals					
2052	-	-	-	-	-	-	2052	-	-	-	-	-	-					
2053	-	-	-	-	-	-	2053	-	-	-	-	-	-					
2054	10,684	1,730	-	-	603	13,017	2054	35,791	2,802	-	-	1,243	39,836					
2055	13,534	1,990	-	-	836	16,359	2055	47,047	3,279	-	-	1,761	52,086					
2056	9,308	21,535	-	-	795	31,638	2056	33,579	36,105	-	-	1,713	71,396					
2057	15,073	2,579	-	-	987	18,639	2057	56,430	4,398	-	-	2,175	63,003					
2058	2,259	100	-	_	835	3,193	2058	8,775	173	-	-	1,883	10,831					
2059	2,259	100	-	-	835	3,193	2059	9,106	176	-	-	1,926	11,208					
2060	-	-	-	-	-		- 2060											
Total	53,116	28,033	-	-	4,891	86,040	Total	190,726	46,932	-	-	10,702	248,360					

NOTE: The 2020 cash flows are inflated to the year of expenditure based on the indices provided on Support Schedule G, page 1 of a

Florida Power & Light Company 2020 Decommissioning Study Turkey Point Nuclear Units Support Schedule : Inflation and Funding Analysis

TURKEY POINT UNIT 3

24.522%

CORPORATE TAX RATE

FPL'S SHARE OF COST (NET OF PARTICIPANTS) 100.000% JURISDICTIONAL FACTOR 95.7416%

Adjusted QUALIFIED % 61.144%

LICENSE ENDS 07/19/2052

	ESTIMATED ESTIMATED DOE																PV @ 4.0%			PV @ 4.0%
	SPENDING	COST IN		COST IN	R	ECOVERY		NET	JU	RISDICTIONAL		OUALIFIED		NON-QUAL		TAX		QUALIFIED		NON-QUAL
YEAR	CURVE	(\$2020)		NOMINAL \$	N	OMINAL \$	ľ	NOMINAL \$		AMOUNT		AMOUNT		AMOUNT		SAVINGS		AMOUNT		AMOUNT
2052	2.1994% \$	14,354,167	\$	40,313,093	\$	-	\$	40,313,093	\$	38,596,400	\$	23,599,293	S	11,319,543	\$	3,677,564	\$	6,727,166	\$	3,226,726
2053	6.9482%	45,347,350	\$	135,862,684	\$	22,952,726		112,909,959		108,101,801		66,097,514		31,704,071		10,300,216		18,116,944		8,689,901
2054	4.3786%	28,576,683	\$	86,360,710	\$	65,509,790		20,850,920		19,963,004		12,206,133		5,854,745		1,902,126		3,216,952		1,543,030
2055	6.6745%	43,560,522	\$	113,337,089	\$	41,119,013		72,218,076		69,142,741		42,276,477		20,278,167		6,588,097		10,713,513		5,138,801
2056	9.3351%	60,925,202	\$	203,045,693	\$	58,882,848		144,162,845		138,023,815		84,392,961		40,479,592		13,151,261		20,563,925		9,863,611
2057	9.4462%	61,650,506	\$	177,376,398	\$	56,023,098		121,353,300		116,185,591		71,040,248		34,074,883		11,070,460		16,644,506		7,983,638
2058	10.0313%	65,469,003	\$	199,236,159	\$	10,807,412		188,428,747		180,404,697		110,306,229		52,909,048		17,189,420		24,850,386		11,919,638
2059	12.4696%	81,382,368	\$	268,058,386	\$	11,182,957		256,875,429		245,936,645		150,374,932		72,128,242		23,433,471		32,574,309		15,624,464
2060	14.2365%	92,914,049	\$	312,670,161	\$	-		312,670,161		299,355,415		183,037,180		87,794,887		28,523,348		38,124,639		18,286,713
2061	11.1280%	72,626,640	\$	237,316,655	\$	-		237,316,655		227,210,763		138,925,222		66,636,320		21,649,222		27,823,655		13,345,784
2062	4.2838%	27,958,217	\$	97,722,693	\$	-		97,722,693		93,561,269		57,206,885		27,439,627		8,914,757		11,016,612		5,284,184
2063	0.9129%	5,958,321	\$	22,922,314	\$	-		22,922,314		21,946,190		13,418,727		6,436,373		2,091,089		2,484,722		1,191,812
2064	0.4900%	3,197,818	\$	13,272,540	\$	-		13,272,540		12,707,342		7,769,748		3,726,806		1,210,788		1,383,375		663,544
2065	0.4900%	3,197,818	\$	13,736,531	\$	-		13,736,531		13,151,574		8,041,368		3,857,091		1,253,116		1,376,669		660,328
2066	0.4900%	3,197,818	\$	14,217,207	\$	-		14,217,207		13,611,781		8,322,756		3,992,060		1,296,965		1,370,041		657,148
2067	0.4900%	3,197,818	\$	14,715,179	\$	-		14,715,179		14,088,547		8,614,269		4,131,886		1,342,393		1,363,488		654,005
2068	0.4900%	3,197,818	\$	15,231,080	\$	-		15,231,080		14,582,480		8,916,278		4,276,746		1,389,456		1,357,011		650,898
2069	0.4900%	3,197,818	\$	15,765,569	\$	-		15,765,569		15,094,208		9,229,168		4,426,826		1,438,215		1,350,607		647,827
2070	0.4900%	3,197,818	\$	16,319,327	\$	-		16,319,327		15,624,385		9,553,338		4,582,316		1,488,731		1,344,275		644,790
2071	1.0273%	6,704,873	\$	27,093,749	\$	-		27,093,749		25,939,988		15,860,686		7,607,674		2,471,628		2,145,960		1,029,323
2072	1.6072%	10,489,418	\$	39,853,604	\$	-		39,853,604		38,156,478		23,330,309		11,190,523		3,635,647		3,035,197		1,455,850
2073	1.8226%	11,894,985	\$	59,379,899	\$	-		59,379,899		56,851,266		34,761,006		16,673,326		5,416,934		4,348,359		2,085,716
2074	0.0687%	448,490	\$	2,877,780	\$	-		2,877,780		2,755,233		1,684,653		808,054		262,526		202,633		97,194
2075	0.0000%	-	\$	-	\$	-		-		-		-		-		-		-		-
•	100.0000% \$	652,645,521	\$	2,126,684,500	\$	266,477,844	\$	1,860,206,656	S	1,780,991,616	\$	1,088,965,380	S	522,328,808	\$	169,697,428	\$	232,134,945	S	111,344,925

	QUALIFIED	NON-QUAL	TOTAL
NPV @12/31/20	\$ 232,134,945 \$	111,344,925 \$	343,479,870
LESS BALANCE @ 12/31/20	504,352,385	199,822,850	704,175,236
PV OF FUNDING REQUIREMENTS	\$ (272,217,441) \$	(88,477,925) \$	(360,695,365)
MONTHLY FUNDING REQUIREMENT	-	-	-
ANNUAL FUNDING REQUIREMENT	-	-	-
MONTHLY ACCRUAL	-	-	-
ANNUAL ACCRUAL	-	-	-

Florida Power & Light Company 2020 Decommissioning Study Turkey Point Nuclear Units Support Schedule : Inflation and Funding Analysis

TURKEY POINT UNIT 4

CORPORATE TAX RATE

FPL'S SHARE OF COST (NET OF PARTICIPANTS) 100.000% JURISDICTIONAL FACTOR 95.7416%

Adjusted QUALIFIED % 62.723%

LICENSE ENDS 04/10/2053

		ESTIMATED	1	ESTIMATED	E	STIMATED DOE								PV @ 4.0%	PV @ 4.0%
	SPENDING	COST IN		COST IN	R	ECOVERY		NET	ш	RISDICTIONAL	OUALIFIED	NON-QUAL	TAX	QUALIFIED	NON-QUAL
YEAR	CURVE	(\$2020)		NOMINAL \$		OMINAL \$]	NOMINAL \$	••	AMOUNT	AMOUNT	AMOUNT	SAVINGS	AMOUNT	AMOUNT
2053	3.5415%	\$ 25,093,029	\$	73,520,309	\$	-	\$	73,520,309	\$	70,389,520	\$ 44,150,633	\$ 19,804,634	\$ 6,434,253	\$ 12,101,431	\$ 5,428,335
2054	4.8681%	34,493,006	\$	105,245,719	\$	39,835,750		65,409,969		62,624,551	39,280,188	17,619,901	5,724,463	10,352,376	4,643,762
2055	7.2923%	51,669,035	\$	130,648,293	\$	52,086,494		78,561,799		75,216,324	47,178,164	21,162,693	6,875,467	11,955,677	5,362,954
2056	7.1259%	50,490,667	\$	169,295,740	\$	71,396,367		97,899,373		93,730,426	58,790,821	26,371,778	8,567,827	14,325,484	6,425,978
2057	7.9457%	56,298,721	\$	171,194,893	\$	63,002,855		108,192,038		103,584,788	64,971,802	29,144,379	9,468,607	15,222,688	6,828,436
2058	8.4303%	59,732,890	\$	189,054,716	\$	10,830,848		178,223,869		170,634,383	107,027,524	48,009,300	15,597,560	24,111,742	10,815,796
2059	12.1444%	86,048,684	\$	278,362,094	\$	11,208,159		267,153,936		255,777,453	160,432,070	71,964,959	23,380,423	34,752,892	15,589,093
2060	13.0423%	92,411,134	\$	306,996,581	\$	-		306,996,581		293,923,439	184,358,493	82,697,627	26,867,319	38,399,854	17,225,010
2061	18.4465%	130,701,899	\$	402,355,476	\$	-		402,355,476		385,221,570	241,623,698	108,385,060	35,212,812	48,391,893	21,707,135
2062	8.5661%	60,694,950	\$	198,801,202	\$	-		198,801,202		190,335,452	119,384,685	53,552,348	17,398,419	22,990,497	10,312,840
2063	1.5026%	10,646,502	\$	37,915,392	\$	-		37,915,392		36,300,803	22,769,063	10,213,511	3,318,229	4,216,107	1,891,217
2064	0.4507%	3,193,394	\$	13,307,970	\$	-		13,307,970		12,741,263	7,991,741	3,584,853	1,164,669	1,422,900	638,270
2065	0.4507%	3,193,394	\$	13,774,315	\$	-		13,774,315		13,187,750	8,271,793	3,710,475	1,205,482	1,416,118	635,227
2066	0.4507%	3,193,394	\$	14,257,459	\$	-		14,257,459		13,650,319	8,561,931	3,840,623	1,247,765	1,409,413	632,220
2067	0.4507%	3,193,394	\$	14,758,017	\$	-		14,758,017		14,129,562	8,862,528	3,975,461	1,291,573	1,402,784	629,246
2068	0.4507%	3,193,394	\$	15,276,628	\$	-		15,276,628		14,626,088	9,173,966	4,115,163	1,336,960	1,396,230	626,306
2069	0.4507%	3,193,394	\$	15,813,955	\$	-		15,813,955		15,140,534	9,496,643	4,259,906	1,383,985	1,389,749	623,399
2070	0.4507%	3,193,394	\$	16,370,685	\$	-		16,370,685		15,673,556	9,830,972	4,409,876	1,432,708	1,383,342	620,525
2071	0.9457%	6,700,394	\$	27,148,278	\$	-		27,148,278		25,992,196	16,303,164	7,313,105	2,375,927	2,205,828	989,467
2072	1.4750%	10,451,384	\$	39,756,107	\$	-		39,756,107		38,063,133	23,874,455	10,709,356	3,479,322	3,105,988	1,393,252
2073	1.4691%	10,409,218	\$	51,337,301	\$	-		51,337,301		49,151,154	30,829,228	13,829,056	4,492,870	3,856,521	1,729,918
2074	0.0496%	351,490	\$	2,256,348	\$	-		2,256,348		2,160,264	1,354,989	607,807	197,468	162,980	73,108
2075	0.0000%	-	\$	-	\$	-		-		-	-	-	-	-	-
·	100.0000%	708,546,759	\$	2,287,447,481	\$	248,360,471	\$	2,039,087,009	\$	1,952,254,528	\$ 1,224,518,551	\$ 549,281,871	\$ 178,454,106	\$ 255,972,494	\$ 114,821,495

	(QUALIFIED	NON-QUAL		TOTAL
NPV @12/31/20	\$	255,972,494	\$ 114,821,495	S	370,793,989
LESS BALANCE @ 12/31/20		577,838,404	214,100,960	\$	791,939,364
PV OF FUNDING REQUIREMENTS	\$	(321,865,909)	\$ (99,279,465)	\$	(421,145,375)
A COMMAND ALL DAVIS DAVIS DEL CALIFORNIA COMMANDA COMMAND					

24.522%

SECTION 10

DECOMMISSIONING COST ANALYSIS: TURKEY POINT NUCLEAR PLANT UNITS 3 AND 4 Prepared by EnergySolutions, LLC



2020 Decommissioning Cost Estimate of the Turkey Point Nuclear Plant, Units 3 and 4

Project No. 16	54086-02	Rev. 1
	Prepared for: Florida Power & Light Company	
	Prepared by: EnergySolutions, LLC 121 W. Trade Street, Suite 2700 Charlotte, NC 28202	
Authored By:	Kein M. Kirkley, Sr. Estimator	
Approved By:	Jake H. Oleksiak, Project Controls Manager	11/19/20 Date
		X New Report
		Title Change
		Report Revision
	Effectiv	Report Rewrite
	Effective Postor	/e November 19, 2020

Table of Contents

<u>Section</u>		<u>Page</u>	
1.0	EXECUTIVE SUMMARY		
2.0	INTRODUCTION	9	
	2.1 Study Objective	9	
	2.2 Regulatory Framework		
3.0	STUDY METHODOLOGY	12	
	3.1 General Description	12	
	3.2 Schedule Analysis	12	
	3.3 Decommissioning Staff	13	
	3.4 Waste Disposal	13	
	3.5 Final Status Survey		
	3.6 Contingency		
	3.7 Cost Reporting		
4.0	SITE-SPECIFIC TECHNICAL APPROACH	19	
	4.1 Facility Description	19	
	4.2 Decommissioning Periods	19	
	4.3 Decommissioning Staff	30	
	4.4 Spent Fuel Management Staff	31	
	4.5 Spent Fuel Shipments		
5.0	BASES OF ESTIMATE AND KEY ASSUMPTIONS	32	
6.0	STUDY RESULTS	35	
	6.1 Scenario 1 – DECON both after Unit 4 Shutdown		
	6.2 Scenario 2 – SAFSTOR	41	
7.0	DEFEDENCES	45	

Tables

Table 1-1	Decommissioning Cost Summary	6
Table 1-2	Scenario 1 Cost Summary by Unit	7
Table 1-3	Scenario 2 Cost Summary by Unit	7
Table 1-4	Scenario 1 Schedule Summary	8
Table 1-5	Scenario 2 Schedule Summary	8
Table 6-1	Decommissioning Cost Summary	35
Table 6-2	Scenario 1 Cost Summary by Period & Unit	36
Table 6-3	Scenario 1 Cost Summary by Period & Cost Type	36
Table 6-4	Scenario 1 Schedule Summary	37
Table 6-5	Scenario 1 Project Staffing	37
Table 6-6	Scenario 2 Cost Summary by Period & Unit	40
Table 6-7	Scenario 2 Cost Summary by Period & Cost Type	40
Table 6-8	Scenario 2 Schedule Summary	41
Table 6-9	Scenario 2 Project Staffing	

Appendices

Appenaix A	List of Systems and Structure
Appendix B	Detailed Schedules
Appendix C	Detailed Cost Estimates
Appendix D	Detailed Staffing Tables
Appendix E	Waste Disposal Summaries
Appendix F	Annual Spending Tables

Acronyms and Abbreviations

AIF Atomic Industrial Forum

ALARA As Low As Reasonably Achievable

BWR Boiling Water Reactor
CFR Code of Federal Regulations
CWS Circulating Water System

DAW Dry Active Waste

DCE Decommissioning Cost Estimate
DGC Decommissioning General Contractor

DOE U.S. Department of Energy

DSC Dry Storage Canister

EPRI Electric Power Research Institute

ES Energy*Solutions*

FEMA Federal Emergency Management Agency

FPL Florida Power & Light Company

FSS Final Status Survey

GSA U.S. General Services Administration

GTCC Greater Than Class C

HP Health Physics

HSM Horizontal Storage Module

INPO Institute of Nuclear Power Operations
ISFSI Independent Spent Fuel Storage Installation

LLRW Low-Level Radioactive Waste

LOP Life-of-Plant

MARSSIM Multi-Agency Radiation Survey and Site Investigation Manual

MWt Megawatt thermal

Turkey Point Nuclear Plant
NRC Nuclear Regulatory Commission

ORISE Oak Ridge Institute for Science and Education

PCB Polychlorinated Biphenyl

PSDAR Post-Shutdown Decommissioning Activities Report

PWR Pressurized Water Reactor
WBS Work Breakdown Structure
WCS Waste Control Specialists LLC

UCF Unit Cost Factor

Document No. 164086-DCE-02

1.0 EXECUTIVE SUMMARY

This report presents the 2020 Decommissioning Cost Estimate (DCE) Study of the Turkey Point Nuclear Plant, Units 3 and 4, hereinafter referred to as the 2020 Cost Study. The Turkey Point Nuclear Plant (Turkey Point) is owned and operated by Florida Power & Light Company (FPL).

This DCE has been performed to furnish an estimate, for financial planning purposes, of the costs for decommissioning Turkey Point Units 3 and 4 to the extent required to terminate the plant's operating license pursuant to 10 CFR 50.75(c); post-shutdown management of spent fuel until acceptance by the U.S. Department of Energy (DOE) pursuant to 10 CFR 50.54(bb); and clean demolition of structures and restoration of the site.

The study methodology follows the basic approach originally presented in the Atomic Industrial Forum/National Environmental Studies Project Report AIF/NESP-036, "Guidelines for Producing Commercial Nuclear Power Plant Decommissioning Cost Estimates," (Ref. No. 1). The report was prepared in accordance with Nuclear Regulatory Commission (NRC) Regulatory Guide 1.202, "Standard Format and Content of Decommissioning Cost Estimates for Nuclear Power Reactors," (Ref. No. 2). The estimate is based on compliance with current regulatory requirements and proven decommissioning technologies.

NRC requirements, set forth in Title 10 of the Code of Federal Regulations (CFR), differentiate between the post-shutdown costs associated with storage of spent fuel on site and those associated with the decommissioning of the facility. 10 CFR 50.75(c) requires funding by the licensee of the facility for the decommissioning program, but specifically excludes the cost of removal and disposal of spent fuel and the removal of clean structures. 10 CFR 50.75(c) also excludes the cost of site restoration activities that do not involve the removal of residual radioactivity necessary to terminate the NRC license, which restore the site to either "Brownfield" or "Greenfield" conditions depending on the desired end state. 10 CFR 50.54 (bb) requires funding by the licensee "for the management of all irradiated fuel at the reactor upon expiration of the reactor operating license until title to the irradiated fuel and possession of the fuel is transferred to the Secretary of Energy for its ultimate disposal in a repository."

Accordingly, the costs and schedules for all activities are segregated for regulatory purposes as follows: costs for "License Termination" (10 CFR 50.75(c)); costs for "Spent Fuel Management" (10 CFR 50.54(bb)); and costs for "Site Restoration".

This study analyzes two DCE scenarios, defined by FPL, as follows:

Scenario 1 – DECON both following Unit 4 Shutdown

- Unit 3 Shutdown July 19, 2052
- Unit 4 Shutdown April 10, 2053
- DECON Methodology after Unit 4 is permanently shutdown in 2053
- Transfer spent fuel from pool to DOE prior to shutdown beginning in 2031
- Fuel pools empty by 2056
- All Dry Fuel transferred from ISFSI to DOE by 2073
- Decommissioning will be performed by FPL and a Decommissioning General Contractor (DGC)

Document No. 164086-DCE-02

- Class A LLRW will be disposed of at the ES Clive UT burial site
- Class B and C LLRW will be shipped and buried at the WCS Andrews County, TX burial site

Scenario 2 - SAFSTOR

- Unit 3 Shutdown July 19, 2052
- Unit 4 Shutdown April 10, 2053
- SAFSTOR Methodology
- Transfer spent fuel from pool to DOE prior to shutdown beginning in 2031
- Fuel pools empty by 2056
- All Dry Fuel transferred from ISFSI to DOE by 2073
- Decommissioning will be performed by FPL and a Decommissioning General Contractor (DGC)
- SAFSTOR period ends in 2105
- Decommissioning activities to complete by 2112 (excludes ISFSI decommissioning ISFSI decommissioning and demolition to complete by 2113)
- Class 'A' LLRW will be disposed of at the ES Clive UT burial site
- Class 'B' and 'C' LLRW will be shipped and buried at the WCS Andrews, TX burial site

The cost estimate results are provided for each scenario in 2020 dollars and summarized in Table 1-1 below. This table provides License Termination costs (corresponding to 10 CFR 50.75(c) requirements), Spent Fuel Management costs (corresponding to 10 CFR 50.54(bb) requirements), and Site Restoration costs including activities such as clean building demolition and site grading etc.

Table 1-1

FPL Turkey Point Units 3 and 4 Decommissioning Cost Summary				
	(t	housands of 2020 o	dollars)	
Scenario	License Termination	Spent Fuel	Site Restoration	Total
1	1,018,355	282,949	59,888	1,361,192
2	1,202,419	338,557	60,108	1,601,084

Document No. 164086-DCE-02

Table 1-2 below provides the cost estimate results for Scenario 1 separated into Unit 3, Unit 4 and Total.

Table 1-2

FPL Turkey Point Units 3 and 4 Scenario 1 Cost Summary by Unit (thousands of 2020 dollars)			
	Unit 3	Unit 4	Total
License Termination	484,062	534,293	1,018,355
Spent Fuel	144,704	138,245	282,949
Site Restoration	23,879	36,009	59,888
Total	652,645	708,547	1,361,192

Table 1-3 below provides the cost estimate results for Scenario 2 separated into Unit 3, Unit 4 and Total.

Table 1-3

FPL Turkey Point Units 3 and 4 Scenario 2 Cost Summary by Unit (thousands of 2020 dollars)			
	Unit 3	Unit 4	Total
License Termination	573,137	629,282	1,202,419
Spent Fuel	172,524	166,033	338,557
Site Restoration	24,029	36,079	60,108
Total	769,690	831,394	1,601,084

The estimate is based on site-specific plant systems and buildings inventories. These inventories, Energy*Solutions'* (ES) proprietary Unit Cost Factors (UCFs), historical data and execution strategy were used to generate required man-hours, waste volumes and classification, and estimated costs. Detailed project estimates are included in <u>Appendix C</u>.

The schedule reflects EnergySolutions' historical execution strategy to sequence activity-dependent or distributed decommissioning elements such as planning and preparations, major component removal, building decontamination, building demolition, etc. A schedule for each scenario is summarized in Tables 1-4 and 1-5 below. Detailed project schedules are included in <u>Appendix B.</u>

Table 1-4 below provides a schedule summary for Scenario 1 based on a DECON scenario with Unit 3 Shutdown in 2052 and Unit 4 Shutdown in 2053.

Table 1-4

FPL DCE-02 Turkey Point Units 3 & 4 Scenario 1 Schedule Summary		
Year	Item	
2031	DOE starts accepting fuel from spent fuel pool	
2052	Unit 3 Shutdown	
2053	Unit 4 Shutdown	
2056	Unit 3 Fuel Pool Empty	
2056	Unit 4 Fuel Pool Empty	
2057	Start Demolition	
2063	Decommissioning and Site Restoration Complete	
2073	ISFSI Empty	
2074	ISFSI Decommissioning and Site Restoration Complete	

Table 1-5 below provides a schedule summary for Scenario 2 based on a SAFSTOR scenario with Unit 3 Shutdown in 2052 and Unit 4 Shutdown in 2053.

Table 1-5

	FPL DCE-02 Turkey Point Units 3 & 4 Scenario 2 Schedule Summary
Year	Item
2031	DOE starts accepting fuel
2052	Unit 3 Shutdown
2053	Unit 4 Shutdown
2056	Unit 3 Fuel Pool Empty
2056	Unit 4 Fuel Pool Empty
2056	SAFSTOR Period Begins
2073	ISFSI Empty
2105	SAFSTOR Period Ends
2106	Start Demolition
2112	Decommissioning and Site Restoration Complete
2113	ISFSI Decommissioning and Site Restoration Complete

2.0 INTRODUCTION

2.1 Study Objective

This report presents the 2020 Decommissioning Cost Estimate (DCE) Study of the Turkey Point Nuclear Plant, Units 3 and 4, hereinafter referred to as the 2020 Cost Study. The Turkey Point Nuclear Plant (Turkey Point) is owned and operated by FPL.

This update has been performed to furnish an estimate, for financial planning purposes, of the costs for decommissioning Turkey Point Units 3 and 4 to the extent required to terminate the plant's operating license pursuant to 10 CFR 50.75(c); post-shutdown management of spent fuel until acceptance by the U.S. Department of Energy (DOE) pursuant to 10 CFR 50.54(bb); and clean demolition of structures and restoration of the site.

The study methodology follows the basic approach originally presented in the Atomic Industrial Forum/National Environmental Studies Project Report AIF/NESP-036, "Guidelines for Producing Commercial Nuclear Power Plant Decommissioning Cost Estimates," (Ref. No. 1). The report was prepared in accordance with Nuclear Regulatory Commission (NRC) Regulatory Guide 1.202, "Standard Format and Content of Decommissioning Cost Estimates for Nuclear Power Reactors," (Ref. No. 2). The estimate is based on compliance with current regulatory requirements and proven decommissioning technologies.

2.2 Regulatory Framework

Provisions of current laws and regulations affecting decommissioning, waste management and spent fuel management are as follows:

- 1. NRC regulations require a license for on-site storage of spent fuel. Wet storage in a spent fuel pool is authorized by a facility's 10 CFR Part 50 license (Ref. No. 3). On-site dry storage of spent fuel at an Independent Spent Fuel Storage Installation (ISFSI) is licensed by either: (a) the general license set forth in 10 CFR 72.210, which requires that a Part 50 license be in place; or (b) a site-specific ISFSI license issued pursuant to 10 CFR Part 72.
- 2. 10 CFR 50.75(c) requires funding by the licensee of the facility for the decommissioning program, but specifically excludes the cost of removal and disposal of spent fuel and the removal of clean structures.
- 3. 10 CFR 50.54 (bb) requires the licensee, within two years following permanent cessation of operation of the reactor or five years before expiration of the operating license, whichever occurs first, to submit written notification to the NRC for its review and preliminary approval of the program by which the licensee intends to manage and provide funding "for the management of all irradiated fuel at the reactor upon expiration of the reactor operating license until title to the irradiated fuel and possession of the fuel is transferred to the Secretary of Energy for its ultimate disposal in a repository." However, the NRC does not currently consider post-shutdown spent fuel management costs to be decommissioning costs.
- 4. 10 CFR 72.30(b) requires that a licensee under Part 72 must submit a decommissioning funding plan that contains information that provides assurance that funds will be available to decommission the ISFSI.

Document No. 164086-DCE-02

5. 10 CFR Part 961, Appendix E (Ref. No. 4), requires spent fuel to be cooled in the spent fuel pool for at least five years before it can be accepted by DOE.

Decommissioning Alternatives

The three basic methods for decommissioning are DECON, SAFSTOR, and ENTOMB, which are summarized as follows:

- 1. DECON: The equipment, structures, and portions of the facility and site that contain radioactive contaminants are promptly removed or decontaminated to a level that permits termination of the license after cessation of operations.
- 2. SAFSTOR: The facility is placed in a safe, stable condition and maintained in that state (safe storage). The facility is decontaminated and dismantled at the end of the storage period to levels that permit license termination. NRC regulations require decommissioning to be completed within 60 years of cessation of operation. Durations less than the regulatory-allowed maximum may be referred to as Modified SAFSTOR.
- 3. ENTOMB: Radioactive structures, systems, and components are encased in a structurally long-lived substance, such as concrete. The entombed structure is appropriately maintained and monitored until radioactivity decays to a level that permits termination of the license. Since entombment will exceed the requirement for decommissioning to be completed within 60 years of cessation of operation, NRC handles entombment requests on a case-by-case basis.

The selection of a preferred decommissioning alternative is influenced by a number of factors pertinent at the time of final plant shutdown. These factors include the cost of each decommissioning alternative, minimization of occupational radiation exposure, availability of a low-level waste disposal facility, availability of a high-level waste (spent fuel) repository, regulatory requirements, and public concerns.

Post-Shutdown Spent Fuel Management Alternatives

Selection of a decommissioning strategy and the associated schedule for completion is in part contingent upon an assumed start date for DOE acceptance of spent fuel and an assumed end date for completion of the transfer of all spent fuel assemblies projected to be generated during a power reactor's operating life. The basic options for long-term post-shutdown spent fuel management currently available to power plant operators are (1) wet storage consisting of continued maintenance and operation of the spent fuel pool, and (2) dry storage consisting of transfer of spent fuel from the fuel pool to on-site dry storage modules after a cooling period. Maintaining the spent fuel pool for an extended duration following cessation of operations prevents termination of the Part 50 license and typically has a higher annual maintenance and operating cost than the dry storage alternative. Transfer of spent fuel to an ISFSI requires additional capital expenditures for purchase and construction of the ISFSI and dismantlement and disposal of the ISFSI following completion of spent fuel transfer to DOE. In both cases the decommissioning and spent fuel management costs are significantly affected by the assumed start and end dates for DOE acceptance of spent fuel.

In January 2013, DOE released its "Strategy for Management and Disposal of Used Nuclear Fuel and High-Level Radioactive Waste" (Ref. No. 5). The DOE Strategy contemplates building the capability to begin executing DOE's commitment to address waste disposal within the next ten years. Under this strategy, by 2021, operation would begin of a "pilot storage facility" with an "initial focus on accepting spent fuel from

Document No. 164086-DCE-02

shutdown reactor sites." By 2025, a "larger interim storage facility" would be available and by 2048 a geologic repository would commence operations.

For purposes of this estimate, FPL has assumed the DOE pickup of commercial fuel to begin in 2030. The DOE starts accepting spent fuel from the Turkey Point facility in 2031 and the acceptance rate is consistent with the 2004 "Acceptance Priority Ranking & Annual Capacity Report" (Ref. No. 6), which is the most current information regarding the acceptance of spent fuel.

Note that nothing in this update, or in the assumptions and information provided by FPL, should be construed as any sort of admission or concession regarding the legal obligations of DOE. For example, and without limitation, the assumptions for DOE performance after 2021 utilized in this update do not include consolidation or acceleration via exchanges of acceptance allocations with other utilities, and DOE is also assumed to accept loaded and canistered fuel, although the government's stated positions with respect to such acceptance, including assertions in legal proceedings, have been inconsistent.

Document No. 164086-DCE-02

3.0 STUDY METHODOLOGY

3.1 General Description

EnergySolutions maintains a proprietary decommissioning cost model based upon the fundamental technical approach established in AIF/NESP-036, "Guidelines for Producing Commercial Nuclear Power Plant Decommissioning Cost Estimates," dated May 1986 (Ref. No. 1). The cost model has been continuously updated in accordance with regulatory requirements, EnergySolutions' actual project experience, and the latest industry technologies. The cost model includes elements for estimating distributed (direct costs) and undistributed costs. Distributed costs are activity specific and include planning and preparation costs as well as the decontamination, packaging, disposal, and removal of major components and systems. For example, the segmentation, packaging, and disposal of the reactor internals is a distributed cost. Undistributed costs, sometimes referred to as collateral costs, are typically time dependent costs such as utility and decommissioning general contractor staff, property taxes, insurance, regulatory fees and permits, energy costs, and security staff.

The methodology for preparing cost estimates for a selected decommissioning alternative requires development of a site-specific detailed work-activity sequence based upon the plant inventory. The activity sequence is used to define the labor, material, equipment, energy resources, and duration required for each activity. In the case of major components, individual work-activity sequence analyses are performed based on the physical and radiological characteristics of the component and the packaging, transportation, and disposal options available.

In addition to actual costs and UCF models the study also relies on information obtained for earlier decommissioning estimates from across the industry and from cost information derived for submitted proposals and bid results.

3.2 Schedule Analysis

Energy Solutions has established a Work Breakdown Structure (WBS) that typically defines decommissioning costs and the schedule into six primary periods to define the scope of work. Those periods are:

- Period 1 Shutdown and Transition
- Period 2 SAFSTOR
- Period 3 Decommissioning and License Termination
- Period 4 Site Restoration
- Period 5 Dry Fuel / GTCC Storage and Transfer
- Period 6 ISFSI Decommissioning

The work is broken down further into sub-periods as defined in Section 4.2 below.

Once the work activity durations are established, a time-phased schedule and cash-flow analysis are performed using EnergySolutions' integrated HardDollar estimating and scheduling tools to generate annual spending.

Document No. 164086-DCE-02

The schedule accounts for constraints such as spent fuel cooling periods and regulatory reviews. The schedule is typically delineated into periods that differentiate manpower requirements and undistributed costs.

3.3 Decommissioning Staff

EnergySolutions' philosophy towards decommissioning is to assume that the project will be performed in an efficiently planned and executed manner using project personnel experienced in decommissioning. These DCE scenarios assume that the decommissioning will be performed by a highly experienced and qualified DGC, with oversight and management of the decommissioning operations performed by the utility staff. It is also assumed that the utility staff will be supplemented by professional consulting engineering, particularly in the planning and preparation phase.

Staffing levels for each project period are based on the Atomic Industrial Forum (AIF) guidelines, EnergySolutions' project experience and industry practice. The sizes of the staffs are varied in each period in accordance with the requirements of the work activities. Staffing has been organized into the following departments or functional groups:

- Administration
- Engineering
- Health Physics/Radiation Protection
- Management
- Maintenance and Operations
- Quality Assurance
- Security Administration
- Security Guard Force
- Waste Operations
- DGC Staff

3.4 Waste Disposal

Waste management costs comprise a significant portion of the decommissioning cost estimate. Additionally, limited future access to disposal sites licensed for receipt of Class B and C wastes introduces a significant level of uncertainty with respect to the appropriateness of using existing rate structures to estimate disposal costs of these wastes. Energy*Solutions'* approach to estimating waste disposal costs is discussed in the following paragraphs.

Waste Classification

Regulations governing disposal of radioactive waste are stringent in order to ensure control of the waste and preclude adverse impact on public health and safety. At present, low-level radioactive waste (LLRW) disposal is controlled by NRC Regulation 10 CFR 61, which went into effect in December 1983. This regulation stipulates the criteria for the establishment and operation of shallow-land LLRW burial facilities. Embodied within this regulation are criteria and classifications for packaging LLRW such that it is acceptable for burial at licensed LLRW disposal sites.

For each waste classification, 10 CFR 61 stipulates specific criteria for physical and chemical properties that the LLRW must meet in order to be accepted at a licensed disposal site. The LLRW disposal criteria of 10 CFR 61 require that LLRW generators determine the proportional amount of a number of specific radioactive

Document No. 164086-DCE-02

isotopes present in each container of disposable LLRW. This requirement for isotopic analysis of each waste stream of disposable LLRW is met by employing a combination of analytical techniques such as computerized analyses based upon scaling factors, sample laboratory analyses, and direct assay methods. Having performed an isotopic analysis of each container of disposable LLRW, the waste must then be classified according to one of the classifications (Class A, B, C or Greater Than Class C (GTCC)) as defined in 10 CFR 61.

EnergySolutions' classification of LLRW resulting from decommissioning activities is based on AIF/NESP-036 (Ref. No. 1), NUREG/CR-0130 (Ref. No.7), NUREG/CR-0672 (Ref. No. 8), and recent industry experience. The estimated curie content of the reactor vessel and internals at shutdown is derived from NUREG/CR-0130 for Pressurized Water Reactors (PWRs) and NUREG/CR-0672 for Boiling Water Reactors (BWRs) and adjusted for the different mass of components and period of decay.

Packaging

Selection of the type and quantity of containers required for Class B and C wastes is based on the most restrictive of either curie content, dose rate, container weight limit, or container volume limit. GTCC wastes from segmentation of the reactor vessel internals is packaged in fuel canisters. The selection of container type for Class A waste is based on the transportation mode (rail, truck, barge, etc.) and waste form. The quantity of Class A waste containers is determined by the most restrictive of either container weight limit or container volume limit. Large components, such as pressurizers, and reactor recirculation pumps, are shipped as their own container with shielding as required.

Custom container costs are obtained from manufacturers. Shielded transport cask and liner costs are obtained from EnergySolutions or other cask owners and operators.

Transportation

Transportation routes to processing and disposal facilities are determined based on available transportation modes (truck, rail, barge or combinations). Transportation costs for the selected routes and modes are obtained from vendor quotes or published tariffs whenever possible.

Class A Disposal Options and Rates

In accordance with the existing Life-of-Plant (LOP) Disposal Agreement (Ref. No. 9), all Class A waste that meets the Clive facility waste acceptance criteria may be disposed of at Clive. All reported waste disposal costs include packaging, transportation, and any applicable surcharges.

Class B and C Disposal Options and Rates

Currently, within the United States, there are only three operational commercial disposal facilities licensed to accept Class B and C LLRW: the Barnwell facility, operated by EnergySolutions in Barnwell, South Carolina, the U.S. Ecology facility in Richland, Washington, and the licensed facility in Andrews County, Texas operated by Waste Control Specialists (WCS). Barnwell only accepts waste from states within the Atlantic Compact, U.S. Ecology only accepts waste from states within the Northwest and Rocky Mountain Compacts. However, the WCS facility will accept waste from the Texas Compact (comprised of Texas and Vermont) and non-

Document No. 164086-DCE-02

Compact generators. The Texas Compact Commission on March 23, 2012, approved amendments to rules allowing the import of non-compact generator LLRW for disposal at the Andrews County facility.

In accordance with the existing Life-of-Plant (LOP) Disposal Agreement, all Class B and C waste that meets the WCS facility waste acceptance criteria is to be disposed of at WCS, Andrews County, TX facility. All reported waste disposal costs include packaging, transportation, and any applicable surcharges.

Greater Than Class C (GTCC)

Wastes identified as 10 CFR 61 Class A, B, and C may be disposed of at a near-surface disposal facility. Certain components are highly activated and may exceed the radionuclide concentration limitations for 10 CFR 61 Class C waste. In accordance with 10 CFR 61, these components cannot be disposed of in a near-surface LLRW disposal facility and must be transferred to a geologic repository or a similar site approved by the NRC.

Highly activated sections of the reactor vessel internals will result in GTCC waste. Presently, a facility does not exist for the disposal of wastes exceeding 10 CFR 61 Class C limitations. EnergySolutions assumes that the DOE will accept this waste along with spent fuel. Although courts have held that DOE is obligated to accept and dispose of GTCC, issues regarding potential costs remain potentially unsettled. Therefore, EnergySolutions conservatively estimates a GTCC waste disposal cost. EnergySolutions assumes that the GTCC waste will be stored in dry storage containers, and be shipped to a storage or disposal facility by DOE along with the spent fuel.

Additionally, EnergySolutions assumes shipping costs for GTCC waste to be equivalent to the commercial cost of shipping a Type B licensed, shielded cask such as the CNS 8-120B cask, which is owned and operated by EnergySolutions.

LLRW Volume Reduction

Based on current Class A LLRW disposal rates, EnergySolutions does not assume on-site volume reduction techniques such as waste compaction or an aggressive decontamination, survey and release effort. These activities are not currently considered to be cost effective over disposal.

Non-Radioactive Non-Hazardous Waste Disposal

EnergySolutions assumes that recyclable, non-radioactive scrap metal resulting from the decommissioning program will be transported to a scrap metal dealer. Concrete debris is assumed to be processed by size reduction, with removal of structural reinforcing steel, and used on site as engineered fill for voids. Asphalt from parking lots and roadways is assumed to be stockpiled on site and removed, at no cost to the project, by a recycler. All other demolition debris is removed from the site and disposed of at a local construction debris landfill.

Hazardous and Industrial Waste Disposal

Uncontaminated lead shielding remaining after shutdown was assumed to be removed from its installed locations and shipped off site by entities having a need for the material. The entities receive the lead at no charge in return for providing the removal and shipping services. Non-radioactive contaminated surfaces coated with lead-based paint will be removed as non-hazardous building demolition debris. All other

Document No. 164086-DCE-02

chemicals and hazardous materials present at shutdown will be removed and properly disposed of during decommissioning.

3.5 Final Status Survey

The cost of performing a final status survey (FSS) is based on NUREG-1575, "Multi-Agency Radiation Survey and Site Investigation Manual (MARSSIM)" (Ref. No. 10). Estimates of MARSSIM Class I, II and III survey designations are based on information furnished by FPL, radiological assumptions regarding contamination resulting from historic plant operations and from small and large component removal activities. The FSS activity cost calculation includes the in-place remote survey of underground metal and concrete pipe, soil, and groundwater sampling and analysis. Estimated costs for NRC and Oak Ridge Institute for Science and Education (ORISE) verification are also included, and the NRC review period is incorporated into the project schedule.

3.6 Contingency

Contingencies are applied to cost estimates primarily to allow for unknown or unplanned occurrences during the actual program, e.g., increased radioactive contamination over that expected, equipment breakdowns, weather delays, and labor strikes. This is consistent with the definition provided in the DOE Cost Estimating Guide, DOE G 430.1-1, 3-28-97 (DOE G) (Ref. No. 11). Contingency "covers costs that may result from incomplete design, unforeseen and unpredictable conditions, or uncertainties within the defined project scope. The amount of contingency will depend on the status of design, procurement, and construction; and the complexity and uncertainties of the component parts of the project. Contingency is not to be used to avoid making an accurate assessment of expected costs." Energy*Solutions* determines site-specific contingency factors to be applied to each estimate based on industry practices and actual project experience.

The DOE has established a recommended range of contingencies as a function of completeness of program design, DOE G. The ranges are:

	Contingency Range
Type of Estimate	as a % of Total Estimate
Planning Phase Estimate	20-30
Budget Estimate	15-25
Title I (Preliminary Design Estimate)	10-20
Title II (Definitive Design Estimate)	5-15

The approach in this estimate to assigning appropriate contingency rates is based upon adaptations of published values for the specific decommissioning activities as well as project experience and current industry practices. One source for such published information is AIF/NESP-036 "Guidelines for Producing Nuclear Plant Decommissioning Cost Estimates" (Ref. No. 1). The AIF guideline identifies contingencies for activities specific to a nuclear power plant decommissioning, such as reactor internals removal. The contingencies presented in the AIF guideline are based on the assumption that the estimated costs are not well known; therefore, the recommended contingencies are greater than they would be if the estimated costs were well known. With the exception of the system decontamination, reactor vessel and reactor internals removal, and disposal, the contingencies presented in the AIF guideline are consistent with the values for a Budget/Title I estimate. The system decontamination, reactor vessel and reactor internals removal, and disposal contingencies recommended in the AIF guideline are significantly higher than the ranges identified by the DOE, even for a planning phase document. This is due to the unique nature of these

Document No. 164086-DCE-02

activities and the relatively small amount of historical data available at the time the AIF document was written.

The application of contingency rates in this estimate are consistent with information presented in AIF guideline and DOE G. The decommissioning costs generated in the estimate are considered well known and, as such, the contingencies presented in AIF guideline were reduced for each category of costs. There have also been a number of large-scale decommissioning projects since AIF was published, including by Energy*Solutions*, providing substantial historical information that has been used in preparing this estimate, allowing for additional reduction in contingency costs.

The following table provides a summary of contingency values included in the Decommissioning Cost Estimate:

- 10% contingency on SAFSTOR staff and undistributed costs
- 15% contingency on non-rad build demolition and site restoration activities
- 15% contingency on dry fuel storage & ISFSI operations activities
- 15% contingency on dry fuel transfer to DOE
- 15% contingency on staff and undistributed costs
- 15% contingency on GTCC transportation and disposal
- 20% contingency on reactor vessel segmentation
- 20% contingency on large component and system removal
- 20% contingency on rad building interior and exterior demolition
- 20% contingency on final status surveys
- 20% contingency on wet fuel transfer to the DOE
- 20% contingency on remediation and disposal of contaminated soils
- 25% contingency on asbestos abatement

A reactor decommissioning program will be conducted under an NRC-approved Quality Assurance Program which meets the requirements of 10 CFR 50, Appendix B. However, the development of the quality assurance program, the performance of work under that program, and the effort required to ensure compliance with the program, is already included in the detailed cost estimate. Therefore, EnergySolutions does not include quality assurance as an element of the contingency allowance. The same is true where radioactive contamination or activated materials are dealt with. The cost factors and associated calculations fully reflect the cost impact of that material, and a separate contingency is not required specifically due to working with contamination.

3.7 Cost Reporting

Total project costs are aggregated from the distributed activities (Direct Costs) and undistributed costs into the following categories:

- Labor
- Materials and Equipment
- Waste Transportation and Disposal
- Other Direct Costs

Other costs include property taxes, insurance, license fees, permits, and energy. Waste disposal costs are the summation of packaging, transportation, base disposal rate, and any applicable surcharges. Health

Document No. 164086-DCE-02

physics (HP) supplies and small tool costs are calculated as a component of each distributed activity cost and included in the category of Material and Equipment, with the exception that HP supplies for the utility HP staff are calculated and reported as an undistributed line item. A contingency is then applied to each activity.

4.0 SITE-SPECIFIC TECHNICAL APPROACH

4.1 Facility Description

Turkey Point Nuclear Plant is a nuclear-powered electrical generating facility consisting of two PWRs. The plant is located near Homestead, Florida, 25 miles south of Miami, Florida. The plant is situated on an 11,000-acre tract of land which is dominated by protected mangrove swamps. The cooling canals encompass an additional 6,800 acres.

Both Unit 3 and Unit 4 are three-loop Westinghouse PWRs with a current thermal output of 2,644 MWt and a design electrical rating of 844 MWe and 840 MWe, respectively. The current license expiration dates for Units 3 and 4 are in 2052 and 2053, respectively.

Turkey Point has an existing ISFSI supporting Units 3 and 4. The ISFSI is operated under the 10 CFR Part 72 general license using the manufacturer's Certificate of Compliance.

A list of the Turkey Point systems and structures included in the material inventory for this study is provided in <u>Appendix A</u>.

4.2 Decommissioning Periods

Energy Solutions has established a Work Breakdown Structure (WBS) that typically defines decommissioning cost estimates with six primary periods to define the scope of work. Those periods are:

- Period 1 Shutdown and Transition
- Period 2 SAFSTOR
- Period 3 Decommissioning and License Termination
- Period 4 Site Restoration
- Period 5 Dry Fuel / GTCC Storage and Transfer
- Period 6 ISFSI Decommissioning

The work is broken down further into sub-periods.

The project periods defined for this site-specific study and a summary of activities performed during each period are listed below.

SCENARIO 1 – DECON both following Unit 4 Shutdown:

Period 1 – Shutdown and Transition:

<u>Period 1a – Planning Prior to Shutdown (by Plant Operations)</u>

Period 1b – Unit 3 Post-Shutdown Planning and Engineering:

- Administrative Activities in Preparation for Decommissioning
- Prepare PSDAR and License Documents
- Engineering Activities in Preparation for Decommissioning

Document No. 164086-DCE-02

Period 1c – Unit 3 Post-Shutdown Deactivation and Modifications:

- Defuel Reactor Unit 3 (by Plant Operations)
- Fuel Sampling and Inspections (by Plant Operations)
- Spent Fuel Pool System Modifications

Period 1d – Unit 3 Wet Fuel Transfer to DOE prior to DECON:

- Provide Transfer Casks (supplied by DOE)
- Procure Spent Fuel Loading and Transfer Equipment
- Procedures and Dry Runs
- Remove Fuel Assemblies from Pool and Load DOE Casks
- Dry, Close and Inspect DOE-supplied Casks
- Load Out Casks to DOE Transport
- Spent Fuel Transportation and Disposal (by DOE)

Period 1e – Unit 3 Wet Fuel Transfer to ISFSI prior to Shutdown:

- Purchase Transfer Casks
- Procedures and Dry Runs
- Remove Fuel Assemblies from Pool and Load Casks
- Dry, Close and Inspect Casks
- Load Out Casks to Transport

<u>Period 1f – Unit 4 Post-Shutdown Planning and Engineering:</u>

- Administrative Activities in Preparation for Decommissioning
- Preparation of PSDAR and Licensing Documents
- Engineering Activities in Preparation for Decommissioning

Period 1g – Unit 4 Post-Shutdown Preparations and Deactivation:

- Defuel Reactor Unit 4 (by Plant Operations)
- Fuel Sampling and Inspections (by Plant Operations)
- Spent Fuel Pool System Modifications

<u>Period 1h – Unit 4 Wet Fuel Transfer to DOE prior to DECON:</u>

- Provide Transfer Casks (supplied by DOE)
- Procure Spent Fuel Loading and Transfer Equipment
- Procedures and Dry Runs
- Remove Fuel Assemblies from Pool and Load DOE Casks
- Dry, Close and Inspect DOE-supplied Casks
- Load Out Casks to DOE Transport
- Spent Fuel Transportation and Disposal (by DOE)

Period 1i – Unit 4 Wet Fuel Transfer to ISFSI prior to DECON:

- Provide Transfer Casks
- Procedures and Dry Runs
- Remove Fuel Assemblies from Pool and Load Casks

Document No. 164086-DCE-02

- Dry, Close and Inspect Casks
- Load Out Casks to Transport

Period 1j – Undistributed Costs for Shutdown and Transition:

- Utility Staff
- Security Guard Force
- Property Taxes
- Insurance
- Corporate Support
- Utility Staff HP Supplies
- NRC Inspection Fees
- Licensing Fees
- Materials and Services
- Energy
- County and FEMA Fees
- ISFSI Operating Costs
- Spent Fuel Maintenance

Period 2 – SAFSTOR (not included in Scenario 1):

Period 3 – Decommissioning and License Termination:

Period 3a – Decommissioning Planning:

- Decommissioning Planning and Design
- Prepare Integrated Work Sequence and Schedule
- Site Characterization
- Prepare Decommissioning Activity Specifications
- Prepare Detailed Work Procedures
- Prepare License Termination Plan
- Design Containment and Miscellaneous System Modifications
- Purchase Dry Storage Modules for GTCC Waste

Period 3b – Decommissioning Transition and Preparations:

- Mobilize Decommissioning General Contractor
- Perform Asbestos Abatement of Pipe Insulation
- Implement Cold and Dark and Install Temporary Power
- Construct Misc. Building Modifications, In-Plant Laydown Areas
- Modify Containment Access
- Transportation Infrastructure Modifications
- Procure Waste Handling and Processing Tents

Period 3c – Reactor Vessel Removal:

- Design and Procure Special Equipment
- Test Special Cutting and Handling Equipment and Train Operators
- Finalize Internals and Vessel Segmentation Details

- Document No. 164086-DCE-02 Rev. 1
- Segment, Package and Ship Reactor Internals
- Segment, Package and Ship RPV
- Package and Ship Reactor Pressure Vessels

Period 3d – Large Component Removal:

- Heavy Lift / Transfer Equipment
- Remove and Dispose of Steam Generators
- Remove and Dispose of Pressurizer
- Remove and Dispose of Reactor Coolant Pipe
- Remove and Dispose of Reactor Coolant Pumps
- Package, Ship and Dispose

<u>Period 3e – Plant Decontamination and Interior Rad Demolition:</u>

- Remove and Dispose of Spent Fuel Storage Racks
- Segment, Package and Dispose of Spent Fuel Pool Island Equipment
- Decon/Surgical Removal Containment Buildings
- Decon/Surgical Removal Fuel Buildings
- Decon/Surgical Removal Auxiliary Building
- Decon/Surgical Removal Radwaste Building
- Package, Dispose and Ship

Period 3f – Rad Building Demolition:

- Demolish Fuel Buildings
- Demolish Auxiliary Building
- Demolish Radwaste Building
- Demolish Containment Buildings
- Demolish LLW Storage Building
- Contaminated Soil
- Debris Disposal

Period 3g – License Termination Activities:

- Final Status Survey for Structures
- Final Status Survey for Land Areas (included with Structures)

<u>Period 3h – Undistributed Costs for Decommissioning and License Termination:</u>

- Utility Staff
- Security Guard Force
- General Contractor Staff
- Property Taxes
- Insurance
- Corporate Support
- Utility Staff HP Supplies
- NRC Inspection Fees
- Licensing Fees
- Florida LLRW Inspection Fee

- Licenses and Permits
- Materials and Services
- Energy
- DGC HP Supplies

Period 4 – Site Restoration:

<u>Period 4a – Clean Building and Site Demolition</u>:

- Demolish Turbine Pedestal and Turbine Deck
- Demolish Sealwell
- Demolish Intake and Circulating Water System (CWS)
- Demolish Tank Foundations
- Demolish Miscellaneous Site Structures
- Demolish Security Improvements
- Demolish Maintenance Facility
- Demolish Control Building
- Clean Concrete Processing
- Demolish Site Paving
- Clean Debris Disposal / Recycle

Period 4b – Site Restoration:

- Procure Site Restoration Equipment
- Finish Grading and Re-Vegetate Site

Period 4c – Undistributed Costs for Site Restoration:

- Utility Staff
- Security Guard Force
- General Contractor Staff
- Property Taxes
- Insurance
- Corporate Support
- Energy
- Materials and Services
- Licenses and Permits

Period 5 – Dry Fuel / GTCC Storage and Transfer:

Period 5a – Dry Fuel Transfer to DOE during and after DECON:

- Procure Loading and Transfer Equipment (included in Period 1)
- Procedures and Dry Runs (included in Period 1)
- Remove Fuel Casks from ISFSI and Load DOE Transport
- Spent Fuel Transportation and Disposal (by DOE)

Period 5b – GTCC Waste Disposition:

- Remove GTCC Casks from ISFSI and Load Out
- GTCC Transportation and Disposal

<u>Period 5c – Undistributed Costs for Dry Fuel / GTCC Storage and Transfer:</u>

- Utility Staff
- Security Guard Force
- Property Taxes
- Insurance
- NRC Inspection Fees
- Licensing Fees
- Licenses and Permits
- Materials and Services
- ISFSI Operating Costs

Period 6 –ISFSI Decommissioning:

Period 6a – ISFSI D&D Planning and Preparations:

• Preparation and NRC Review of License Termination Plan

<u>Period 6b – ISFSI and Support Structure Clean Demolition:</u>

- Clean Demolition of ISFSI
- Demolition of ISFSI Support Structures

<u>Period 6c – ISFSI Final Status Surveys</u>:

- Verification Surveys
- Preparation of Final Report on Decommissioning and NRC Review

<u>Period 6d – Undistributed Costs for ISFSI Decommissioning:</u>

- Utility Staff
- Security Guard Force
- General Contractor Staff
- Property Taxes
- Insurance
- Materials and Services
- Energy

Document No. 164086-DCE-02

Licenses and Permits

SCENARIO 2 – SAFSTOR

Period 1 - Shutdown and Transition:

Period 1a – Planning Prior to Shutdown (by Plant Operations):

Period 1b – Unit 3 Post-Shutdown Planning and Engineering:

- Administrative Activities in Preparation for Decommissioning
- Prepare PSDAR and License Documents
- Engineering Activities in Preparation for Decommissioning

Period 1c – Unit 3 Post-Shutdown Deactivation and Modifications:

- Defuel Reactor Unit 3 (by Plant Operations)
- Fuel Sampling and Inspections (by Plant Operations)
- Spent Fuel Pool System Modifications
- Implement Cold and Dark
- Perform Pre-SAFSTOR Baseline Radiation Survey

<u>Period 1d – Unit 3 Wet Fuel Transfer to DOE prior to SAFSTOR:</u>

- Provide Transfer Casks (supplied by DOE)
- Procure Spent Fuel Loading and Transfer Equipment
- Procedures and Dry Runs
- Remove Fuel Assemblies from Pool and Load DOE Casks
- Dry, Close and Inspect DOE-supplied Casks
- Load Out Casks to DOE Transport
- Spent Fuel Transportation and Disposal (by DOE)

Period 1e – Unit 3 Wet Fuel Transfer to ISFSI prior to SAFSTOR:

- Purchase Transfer Casks
- Procedures and Dry Runs
- Remove Fuel Assemblies from Pool and Load Casks
- Dry, Close and Inspect Casks
- Load Out Casks to Transport

<u>Period 1f – Unit 4 Post-Shutdown Planning and Engineering:</u>

- Administrative Activities in Preparation for Decommissioning
- Preparation of PSDAR and Licensing Documents
- Engineering Activities in Preparation for Decommissioning

<u>Period 1g – Unit 4 Post-Shutdown Preparations and Deactivation:</u>

- Defuel Reactor Unit 4 (by Plant Operations)
- Fuel Sampling and Inspections (by Plant Operations)
- Spent Fuel Pool System Modifications
- Implement Cold and Dark

Document No. 164086-DCE-02

Perform Pre-SAFSTOR Baseline Radiation Survey

Period 1h – Unit 4 Wet Fuel Transfer to DOE prior to DECON:

- Provide Transfer Casks (supplied by DOE)
- Procure Spent Fuel Loading and Transfer Equipment
- Procedures and Dry Runs
- Remove Fuel Assemblies from Pool and Load DOE Casks
- Dry, Close and Inspect DOE-supplied Casks
- Load Out Casks to DOE Transport
- Spent Fuel Transportation and Disposal (by DOE)

Period <u>1i – Unit 4 Wet Fuel Transfer to ISFSI prior to SAFSTOR</u>:

- Provide Transfer Casks
- Procedures and Dry Runs
- Remove Fuel Assemblies from Pool and Load Casks
- Dry, Close and Inspect Casks
- Load Out Casks to Transport

<u>Period 1j – Undistributed Costs for Shutdown and Transition:</u>

- Utility Staff
- Security Guard Force
- Property Taxes
- Insurance
- Corporate Support
- Utility Staff HP Supplies
- NRC Inspection Fees
- Licensing Fees
- Materials and Services
- Energy
- County and FEMA Fees
- Licenses and Permits
- ISFSI Operating Costs
- Spent Fuel Maintenance

Period 2 – SAFSTOR:

Period 2a - Dormancy during Dry Fuel Storage:

- Utility Staff
- Security Guard Force
- Property Taxes
- Insurance
- Corporate Support
- Utility Staff HP Supplies
- NRC Inspection Fees
- Licensing Fees

Document No. 164086-DCE-02

- Licenses and Permits
- Materials and Services
- Energy
- Roof Replacement

Period 2b – Dormancy Only:

- Utility Staff
- Security Guard Force
- Property Taxes
- Insurance
- Corporate Support
- Utility Staff HP Supplies
- NRC Inspection Fees
- Licensing Fees
- Licenses and Permits
- Materials and Services
- Energy
- Roof Replacement

Period 3 – Decommissioning and License Termination:

Period 3a – Decommissioning Planning:

- Decommissioning Planning and Design
- Site Characterization
- Prepare Integrated Work Sequence and Schedule
- Prepare Decommissioning Activity Specifications
- Prepare License Termination Plan
- Prepare Detailed Work Procedures
- Design Containment and Miscellaneous System Modifications
- Purchase Dry Storage Modules for GTCC Waste

<u>Period 3b – Decommissioning Transition and Preparations</u>:

- Mobilize Decommissioning General Contractor
- Perform Asbestos Abatement of Pipe Insulation
- Implement Temporary Power Upgrades
- Construct Misc. Building Modifications, In-Plant Laydown Areas
- Modify Containment Access
- Transportation Infrastructure Modifications
- Procure Waste Handling and Processing Tents

<u>Period 3c – Reactor Vessel Removal</u>:

- Design and Procure Special Equipment
- Test Special Cutting and Handling Equipment and Train Operators
- Finalize Internals and Vessel Segmentation Details
- Segment, Package and Ship Reactor Internals

- Segment, Package and Ship RPV
- Package, Ship and Dispose

Period 3d – Large Component Removal:

- Heavy Lift / Transfer Equipment
- Remove and Dispose of Steam Generators
- Remove and Dispose of Pressurizer
- Remove and Dispose of Reactor Coolant Pipe
- Remove and Dispose of Reactor Coolant Pumps
- Package, Ship and Dispose

Period 3e – Plant Decontamination and Interior Rad Demolition:

- Remove and Dispose of Spent Fuel Storage Racks
- Segment, Package and Dispose of Spent Fuel Pool Island Equipment
- Decon/Surgical Removal Containment Buildings
- Decon/Surgical Removal Fuel Buildings
- Decon/Surgical Removal Auxiliary Building
- Decon/Surgical Removal Radwaste Building
- Package, Ship and Dispose

Period 3f – Rad Building Demolition:

- Demolish Fuel Buildings
- Demolish Auxiliary Building
- Demolish Radwaste Building
- Demolish Containment Buildings
- Demolish LLW Storage Building
- Contaminated Soil
- Debris Disposal

Period 3g – License Termination Activities:

- Final Status Survey for Structures
- Final Status Survey for Land Areas (included with Structures)

Period 3h – Undistributed Costs for Decommissioning and License Termination:

- Utility Staff
- Security Guard Force
- General Contractor Staff
- Property Taxes
- Insurance
- Corporate Support
- Utility Staff HP Supplies
- NRC Inspection Fees
- Licensing Fees
- Florida LLRW Inspection Fee
- Licenses and Permits

Document No. 164086-DCE-02 Rev. 1

- Materials and Services
- Energy
- DGC HP Supplies

Period 4 – Site Restoration:

Period 4a – Clean Building and Site Demolition:

- Demolish Turbine Pedestal and Turbine Deck
- Demolish Sealwell
- Demolish Intake and CWS
- Demolish Tank Foundations
- Demolish Miscellaneous Site Structures
- Demolish Security Improvements
- Demolish Maintenance Facility
- Demolish Control Building
- Clean Concrete Processing
- Demolish Site Paving
- Clean Debris Disposal / Recycle

Period 4b - Site Restoration:

- Procure Site Restoration Equipment
- Finish Grading and Re-Vegetate Site

Period 4c – Undistributed Costs for Site Restoration:

- Utility Staff
- Security Guard Force
- General Contractor Staff
- Property Taxes
- Insurance
- Corporate Support
- Energy
- Materials and Services
- Licenses and Permits

Period 5 – Dry Fuel / GTCC Storage and Transfer:

Period 5a – Dry Fuel Transfer to DOE during and after DECON:

- Procure Loading and Transfer Equipment (included in Period 1)
- Procedures and Dry Runs (included in Period 1)
- Remove Fuel Casks from ISFSI and Load DOE Transport
- Spent Fuel Transportation and Disposal (by DOE)

Period 5b – GTCC Waste Disposition:

- Remove GTCC Casks from ISFSI and Load Out
- GTCC Transportation and Disposal

Period 5c – Undistributed Costs for Dry Fuel / GTCC Storage and Transfer:

- Utility Staff
- Security Guard Force
- ISFSI Operating Costs

Period 6 –ISFSI Decommissioning:

Period 6a – ISFSI D&D Planning and Preparations:

• Preparation and NRC Review of License Termination Plan

<u>Period 6b – ISFSI and Support Structure Clean Demolition:</u>

- Clean Demolition of ISFSI
- Demolition of ISFSI Support Structures

Period 6c – ISFSI Final Status Surveys:

- Verification Surveys
- Preparation of Final Report on Decommissioning and NRC Review

Period 6d – Undistributed Costs for ISFSI Decommissioning:

- Utility Staff
- Security Guard Force
- General Contractor Staff
- Property Taxes
- Insurance
- Materials and Services
- Energy
- Licenses and Permits

4.3 Decommissioning Staff

EnergySolutions developed staffing based on the assumption that decommissioning will be performed by an experienced and qualified Decommissioning General Contractor, with oversight, management and security of the decommissioning operations performed by the utility staff. It is also assumed that the utility staff will be supplemented by professional consulting engineering, particularly in the planning and preparation period.

Document No. 164086-DCE-02

4.4 Spent Fuel Management Staff

The largest spent fuel staff and security is in place while the fuel pool is operational during the minimum cooling period and the fuel assemblies are being transferred to either a DOE facility or dry storage. Once all spent fuel has been removed from the spent fuel pool, the staff and security levels are reduced. Details on the staff levels, by functional group, during each period are provided in <u>Appendix D</u>.

4.5 Spent Fuel Shipments

The spent fuel shipment schedules for this estimate are based on information from FPL regarding existing fuel inventory, planned transfers to dry storage and a projected date of 2031 for DOE's acceptance of spent fuel.

Document No. 164086-DCE-02

5.0 BASES OF ESTIMATE AND KEY ASSUMPTIONS

The bases of, and key assumptions for, this site-specific decommissioning estimate are presented below:

- 1. All cost data used in this study are in 2020 dollars.
- 2. Total and subtotal amounts are rounded.
- 3. The decommissioning will be performed under the current regulations. These regulations require a Post-Shutdown Decommissioning Activities Report (PSDAR) to be submitted prior to, or within, two years after permanent shutdown. Other revisions will be required for other licensing basis documents (e.g., Security, Emergency Planning, Fire Protection, Nuclear Safety, Quality Assurance Program, Fuel Debris issues, Spent Fuel Storage options).
- 4. The decommissioning will be performed using currently available technologies.
- 5. Fuel transfer operations are based on the DOE beginning to accept spent fuel starting in 2031.
- 6. All transformers on site following shutdown are assumed to be PCB-free; therefore, this study does not include costs for disposition of PCB contaminated transformers.
- 7. Cost for transportation of clean scrap metal to a recycler is included in the estimate; however, no credit is taken for the value of the scrap metal. Clean concrete debris is assumed to be processed by size reduction, with removal of structural reinforcing steel, and used on site as engineered fill for voids.
- 8. DGC staff salaries, including overhead and profit, were determined by using EnergySolutions' project experience and standard assumptions for these rates.
- 9. Certain professional personnel used for the planning and preparation activities, and DGC personnel, that are not based in the local economy are assumed to be paid per diem based on area per diem rates from U.S. General Services Administration (GSA).
- 10. This study follows the occupational exposure principles of As Low As Reasonably Achievable (ALARA) through the use of productivity loss factors that incorporate such items as the use of respiratory protection and personnel protective clothing. These factors increase the work duration and cost.
- 11. The costs of all required safety analyses and safety measures for the protection of the general public, the environment, and decommissioning workers are included in the cost estimates. This reflects the requirements of:

10 CFR 20	Standards for Protection Against Radiation
10 CFR 50	Domestic Licensing of Production and Utilization Facilities
10 CFR 61	Licensing Requirements for Land Disposal of Radioactive Waste
10 CFR 71	Packaging of Radioactive Material for Transport

Document No. 164086-DCE-02

10 CFR 72	Licensing Requirements for the Independent Storage of Spent Nuclear Fuel and High-Level Radioactive Waste
29 CFR 1910	Occupational Safety and Health Standards
49 CFR 170-189	Department of Transportation Regulations Governing the Transport of Hazardous Materials
Reg. Guide 1.159	Assuring the Availability of Funds for Decommissioning Nuclear Reactors

Document No. 164086-DCE-02

- 12. Energy Solutions developed project schedules based on Unit 3 and Unit 4 shutdown dates of 2052 and 2053, respectively, and fuel shipping schedules provided by FPL.
- 13. Spent fuel in the fuel pools at the time of shutdown will be transferred directly to the DOE-provided transfer/shipping casks from 2031 through 2056. The 2020 Cost Analysis includes costs for transfer to the DOE beginning in 2053 for Unit 3 and 2054 for Unit 4. Costs prior to these dates are assumed to be paid from the plant operations budget. Remaining spent fuel in 2056 will be transferred from the spent fuel pool to the on-site ISFSI. The estimate includes purchase of transfer/shipping casks of the remaining spent fuel to be moved to the ISFSI.
- 14. Spent fuel canisters in the ISFSI at the time of shutdown will remain in dry storage until transfer to the DOE. The estimate includes transferring fuel from the existing ISFSI to the DOE-provided transfer/shipping casks during Period 5.
- 15. Costs for ISFSI security, operations and demolition for Units 3 and 4 are included in the estimate.
- 16. The estimate includes procurement of on-site fuel transfer equipment. It is assumed that equipment purchased for transfer equipment utilized during shipment from the spent fuel pool to the DOE will be utilized for the transfer of spent fuel to the ISFSI and is included in Period 1. It I assumed that this equipment will also be utilized for transfer/loading casks from the ISFSI to the DOE.
- 17. Based on FPL experience, the purchase of dry storage DSCs and HSMs required following shutdown are assumed to be 25% lower than for normal campaign costs due to volume discounts associated with the larger quantity of DSCs and HSMs required to transfer all fuel assemblies from the SFP to the Pad.
- 18. As per FPL's settlement agreement, the DOE is expected to make payments to FPL to cover spent fuel management costs incurred by FPL prior to 2059 for Turkey Point.
- 19. The DOE is responsible to provide all transfer/shipping casks, containers, transportation and disposition of spent fuel shipped from the fuel pool and the ISFSI to a DOE designated off-site facility.
- 20. The estimate is based on site-specific plant systems and building inventories previously included in the 2015 Cost Study, and includes any updates provided by FPL.
- 21. All structures/systems shared between Unit 3 and Unit 4 are included in Unit 4 cost estimate.

22. License Termination costs include the complete demolition of the following buildings to a nominal depth of three feet below grade: Reactor Building, Auxiliary Building, LLW Storage Building, Radwaste Building, and Fuel Handling Building.

Document No. 164086-DCE-02

- 23. The estimate is based on final site restoration, in which all remaining structures, with the exception of the switchyard and any structures associated with Turkey Point Units 3 and 4 will be removed. Intake and Discharge canals also will remain in place.
- 24. Foundations and building exterior walls are removed to a nominal depth of three feet below grade, surveyed and backfilled with appropriate fill material.
- 25. Clean concrete will be processed and utilized as backfill where needed to re-establish grade.

 The disturbed area of the site is to be graded and seeded.
- 26. Uncontaminated lead shielding remaining after shutdown was assumed to be removed from its installed locations and shipped off site by entities having a need for the material. The entities receive the lead at no charge in return for providing the removal and shipping services.
- 27. Any chemicals and hazardous materials present at shutdown are assumed to be removed and disposed of by the plant staff prior to decommissioning, as a normal part of plant operations.
- 28. All Class A waste is assumed to be disposed of at EnergySolutions' facility in Clive, Utah, in accordance with the existing LOP Disposal Agreement (Ref. No. 9) between EnergySolutions and FPL dated January 1, 2007. A LOP agreement letter stating the 2020 price increase was also utilized to develop the waste disposal costs.
- 29. Class A waste includes Dry Active Waste (DAW) arising from the disposal of contaminated protective clothing and health physics supplies.
- 30. Class B and C waste disposal costs are based on disposal rates provided by FPL for the WCS Andrews, TX facility. All resins and filter waste is assumed to be Class B.
- 31. GTCC waste generated from the segmentation of the reactor internals will be stored in on-site canisters placed in the ISFSI until final disposition at a DOE facility. It is assumed that 8 GTCC canisters will be required for the Turkey Point units (4 canisters for Unit 3 and 4 canisters for Unit 4).
- 32. Vessel and internals curie estimates were derived from the values for the Reference PWR vessel and internals in NUREG/CR-0130. These values were adjusted for mass and decay period.
- 33. It is assumed that all Class A LLRW currently being accumulated on site will be removed to a low-level waste processing and/or disposal facility prior to the end of the operating life of the plant. The disposition of such materials is assumed not to be a decommissioning cost.
- 34. The spent fuel shipping schedules and transfer to dry storage costs for each scenario were developed by FPL and furnished to EnergySolutions.

35. Turkey Point currently has an existing ISFSI on site. Construction costs for any expansion of the ISFSI that may be required has not been included, but demolition has been included in the estimate and has been split between both units.

Document No. 164086-DCE-02

Rev. 1

- 36. Energy Solutions has assumed that the 10 CFR Part 50 license for Units 3 and 4 will be terminated after DOE has taken possession of the spent fuel.
- 37. Emergency Preparedness fees were supplied by FPL. Per direction of FPL emergency preparedness fees are assumed to cease once all spent fuel is removed from the spent fuel pool.
- 38. NEIL and ANI insurance premiums are included based on the rate schedule provided by FPL. Insurance premiums have been reduced when major milestones have been completed.
- 39. Units 3 and 4 property taxes are included based on the rate schedule provided by FPL.
- 40. Energy costs have been estimated based on previous experience of similar projects utilizing energy rates provided by FPL.
- 41. Energy*Solutions* has included NRC inspection fees during each decommissioning period based on the type and level of activities being performed.
- 42. EnergySolutions has assumed that licensing fees will be reduced after shutdown.
- 43. Utility staff and security positions, and average direct-burdened salary data were supplied by FPL.
- 44. Severance costs for Reductions-in-Force immediately following Unit 3 and Unit 4 permanently ceasing operations are excluded from the estimate.
- 45. Craft labor rates used in the estimate are based on 2019 RS Means rates escalated to 2020 costs.
- 46. The most recent NRC requirements for Security, Emergency Response, Fukushima, Cyber Security and any other regulatory changes have been included.
- 47. Undistributed staffing costs, taxes, and fees in Periods 3 and 4 is split 93% for License Termination and 7% Site Restoration with exception licensing and NRC fees (100% License Termination).
- 48. Institute for Nuclear Power Operations (INPO) and Electric Power Research Institute (EPRI) dues are not included in this estimate.
- 49. County fees are assumed to be constant throughout the life of the decommissioning project.

6.0 STUDY RESULTS

The study results for each of the DCE scenarios are presented in this section.

The cost estimate results are provided in Table 6-1 below. This table provides License Termination costs (corresponding to 10 CFR 50.75(c) requirements); Spent Fuel Management costs (corresponding to 10 CFR 50.54(bb) requirements) and Site Restoration costs, including activities such as clean building demolition and site grading etc.

Table 6-1

FPL Turkey Point Units 3 and 4 Decommissioning Cost Summary										
(thousands of 2020 dollars)										
Scenario	License Termination	Spent Fuel	Site Restoration	Total						
1	1,018,355	282,949	59,888	1,361,192						
2	1,202,419	338,557	60,108	1,601,084						

Summary schedule tables are shown for each scenario below. Detailed schedules for each scenario are provided in <u>Appendix B.</u>

Summary cost tables are shown for each scenario below. Detailed estimates for each scenario are provided in <u>Appendix C</u>.

Detailed staffing tables for each scenario are provided in Appendix D.

Summary waste quantities are shown for each scenario below. Waste estimates for each scenario are provided in <u>Appendix E</u>.

Detailed annual spending tables for each scenario are provided in Appendix F.

The following sections provide study results by scenario.

6.1 Scenario 1 – DECON both after Unit 4 Shutdown

Cost Summary

Table 6-2 below provides the cost estimate results for Scenario 1 organized by period and separated into Unit 3, Unit 4 and Total.

Table 6-2

	FPL Turkey Point Units 3 and 4 Scenario 1 - Cost Summary by Period & Unit (thousands of 2020 dollars)											
Period	Item Description	Unit 3	Unit 4	Total Cost								
Period 1	SHUTDOWN & TRANSITION	157,154	134,981	292,135								
Period 2	SAFSTOR	-	-	-								
Period 3	DECOMMISSIONING & LICENSE TERMINATION	397,306	464,936	862,242								
Period 4	SITE RESTORATION	23,879	36,009	59,888								
Period 5	DRY FUEL / GTCC STORAGE & TRANSFER	66,792	66,720	133,512								
Period 6	ISFSI DECOMMISSIONING	7,514	5,901	13,415								
	GRAND TOTAL	652,645	708,547	1,361,192								

Table 6-3 below provides the cost estimate results for Scenario 1 organized by period and separated by cost type.

Table 6-3

	FPL Turkey Point Units 3 and 4 Scenario 1 - Cost Summary by Period & Cost Type (thousands of 2020 dollars)											
Period	(tr	Labor Cost	Materials & Equipment	Waste Transport & Disposal	Other Direct Cost (ODC)	Contingency	Total Cost					
Period 1	SHUTDOWN & TRANSITION	171,834	46,863	-	34,307	39,131	292,135					
Period 2	SAFSTOR	-	-	-	-	-	-					
Period 3	DECOMMISSIONING & LICENSE TERMINATION	324,927	124,874	245,937	36,602	129,902	862,242					
Period 4	SITE RESTORATION	34,435	12,900	216	4,526	7,811	59,888					
Period 5	DRY FUEL / GTCC STORAGE & TRANSFER	65,133	2,780	23,492	24,588	17,519	133,512					
Period 6	ISFSI DECOMMISSIONING	9,358	1,932	-	376	1,750	13,415					
_	GRAND TOTAL	605,687	189,349	269,645	100,398	196,113	1,361,192					

A detailed estimate is provided in Appendix C.

Document No. 164086-DCE-02

Summary Schedule

Table 6-4 below provides a schedule summary for Scenario 1 based on a DECON scenario with Unit 3 Shutdown in 2052 and Unit 4 Shutdown in 2053.

Table 6-4

	FPL DCE-02 Turkey Point Units 3 & 4 Scenario 1 Schedule Summary
Year	Item
2031	DOE starts accepting fuel from spent fuel pool
2052	Unit 3 Shutdown
2053	Unit 4 Shutdown
2056	Unit 3 Fuel Pool Empty
2056	Unit 4 Fuel Pool Empty
2057	Start Demolition
2063	Decommissioning and Site Restoration Complete
2073	ISFSI Empty
2074	ISFSI Decommissioning and Site Restoration Complete

A detailed schedule is provided in Appendix B.

Project Staffing

Table 6-5 below provides project staffing for Scenario 1 organized by period and staff group.

Table 6-5

Period 1 - Shutdown & Transition	2050	2051	2052	2053	2054	2055	2056	2057	2058	2059	2060
Administration	-	-	6	12	12	7	4				
Engineering			20	40	40	20	8				
Health Physics/Rad Protection			20	30	30	24	20				
Management			3	5	5	5	3				
Maintenance & Operations			40	70	60	40	20				
Quality Assurance			2	3	3	2	1				
Utility Staff	-	•	91	160	150	98	56	•	•	•	•
General Contractor Staff	-	-	•	•	•	•	•	•	•	•	

Document No. 164086-DCE-02

Period 3 & 4 - License Term & Site Restoration	2054	2055	2056	2057	2058	2059	2060	2061	2062	2063	2064	2065
Administration		4	4	10	12	12	12	12	7	2		
Engineering		4	6	16	20	20	20	20	7	2		
Health Physics/Rad Protection			4	8	24	24	24	24	16	4		
Management		1	1	4	5	5	4	4	4	2		
Maintenance & Operations				10	24	24	20	20	8	2		
Quality Assurance		1	1	2	3	3	2	2	2	1		
Utility Staff	-	10	16	50	88	88	82	82	44	13	•	-
Project Management		2	4	6	10	10	10	10	8	4		
Engineering		4	6	6	12	12	10	10	7	2		
Health Physics/Rad Protection			4	8	16	16	16	16	12	6		
Administration		2	3	6	12	12	12	12	8	4		
Maintenance & Operations					-	-	-	-	-	-		
Quality Assurance		1	1	2	4	4	4	4	3	2		
Waste Management			1	2	12	12	12	12	12	4		
General Contractor Staff	-	9	19	30	66	66	64	64	50	22	-	-

Period 5 - Dry Fuel / GTCC Storage & Transfer	2055	2056	2057	2058	2059	2060	2061 / 2070	2071	2072	2073
Administration										
Engineering		1	1	1	1	1	1	1	1	1
Health Physics/Rad Protection			1	1	1	1	1	1	1	1
Management										
Maintenance & Operations			2	2	2	2	2	2	2	2
Quality Assurance			1	1	1	1	1	1	1	1
Utility Staff	-	1	5	5	5	5	5	5	5	5
General Contractor Staff	-	-	-	-	-	-	-	-	-	-

Period 6 - ISFSI Decommissioning	2070	2071	2072	2073	2074	2075
Administration						
Engineering					1	
Health Physics/Rad Protection					1	
Management					1	
Maintenance & Operations						
Quality Assurance					1	
Utility Staff	-	-	-	-	4	-
Project Management				1	1	
Engineering				1	1	
Health Physics/Rad Protection					1	
Administration					1	
Maintenance & Operations						
Quality Assurance				1	1	
Waste Management				1	1	
General Contractor Staff	-	-	-	4	6	-

Detailed staffing tables for each scenario are provided in Appendix D.

Waste Disposal Volumes

Waste disposal is a significant element of the decommissioning project. The estimated waste disposal quantities for Scenario 1 are shown in cubic feet of waste as follows:

Class A	2,430,666
Class B/C	4,150
GTCC	4,122

Waste disposal volumes and costs, itemized by packaging, transportation, surcharges and disposal costs by waste class and facility, are provided in <u>Appendix E</u>.

Document No. 164086-DCE-02

6.2 Scenario 2 – SAFSTOR

Cost Summary

Table 6-6 below provides the cost estimate results for Scenario 2 organized by period and separated into Unit 3, Unit 4 and Total.

Table 6-6

FPL Turkey Point Units 3 and 4 Scenario 2 - Cost Summary by Period & Unit (thousands of 2020 dollars) Unit 3 Period **Item Description** Unit 4 **Total Cost** Period 1 **SHUTDOWN & TRANSITION** 162,015 139,221 301,236 279,886 Period 2 SAFSTOR 137,347 142,539 Period 3 **DECOMMISSIONING & LICENSE TERMINATION** 384,184 452,636 836,820 Period 4 SITE RESTORATION 36,079 60,108 24,029 Period 5 DRY FUEL / GTCC STORAGE & TRANSFER 54,315 54,731 109,046 7,800 13,987 Period 6 ISFSI DECOMMISSIONING 6,187 **GRAND TOTAL** 769,690 831,394 1,601,084

Table 6-7 below provides the cost estimate results for Scenario 2 organized by period and separated by cost type.

Table 6-7

	FPL Turkey Point Units 3 and 4 Scenario 2 - Cost Summary by Period & Cost Type (thousands of 2020 dollars)										
Period	Period Item Description Labor Cost Materials Waste Transport Direct Equipment & Disposal Cost (ODC) Total C										
Period 1	SHUTDOWN & TRANSITION	178,735	48,818	-	33,366	40,318	301,236				
Period 2	SAFSTOR	113,853	29,582	-	108,736	27,716	279,886				
Period 3	DECOMMISSIONING & LICENSE TERMINATION	321,342	122,553	231,600	35,363	125,961	836,820				
Period 4	SITE RESTORATION	34,700	12,889	228	4,452	7,840	60,108				
Period 5	DRY FUEL / GTCC STORAGE & TRANSFER	65,133	1,800	23,492	4,294	14,328	109,046				
Period 6	ISFSI DECOMMISSIONING	9,358	1,932	-	873	1,824	13,987				
	GRAND TOTAL	723,120	217,573	255,320	187,083	217,987	1,601,084				

A detailed estimate is provided in Appendix C.

Document No. 164086-DCE-02

Summary Schedule

Table 6-8 below provides a schedule summary for Scenario 2 based on a SAFSTOR scenario with Unit 3 Shutdown in 2052 and Unit 4 Shutdown in 2053.

Table 6-8

	FPL DCE-02 Turkey Point Units 3 & 4 Scenario 2 Schedule Summary
Year	Item
2031	DOE starts accepting fuel
2052	Unit 3 Shutdown
2053	Unit 4 Shutdown
2056	Unit 3 Fuel Pool Empty
2056	Unit 4 Fuel Pool Empty
2056	SAFSTOR Period Begins
2073	ISFSI Empty
2105	SAFSTOR Period Ends
2106	Start Demolition
2112	Decommissioning and Site Restoration Complete
2113	ISFSI Decommissioning and Site Restoration Complete

A detailed schedule is provided in Appendix B.

Project Staffing

Table 6-9 below provides project staffing for Scenario 2 organized by period and staff group.

Table 6-9

Period 1 - Shutdown & Transition	2050	2051	2052	2053	2054	2055	2056	2057	2058	2059	2060
Administration	-	-	6	12	12	7	4				
Engineering			20	40	40	20	8				
Health Physics/Rad Protection			20	30	30	24	20				
Management			3	5	5	5	3				
Maintenance & Operations			40	70	60	40	20				
Quality Assurance			2	3	3	2	1				
Utility Staff	-	-	91	160	150	98	56	-	-		-
General Contractor Staff	-	-	-	-	-	-	-	-	-	-	-

Document No. 164086-DCE-02

Period 2 - SAFSTOR	2055	2056	2057	2058	2059	2060 / 2099	2100	2101	2102	2103	2104	2105	2106
Administration		1	1	1	1	1	1	1	1	1	1	1	
Engineering		1	1	1	1	1	1	1	1	1	1	1	
Health Physics/Rad Protection		1	1	1	1	1	1	1	1	1	1	1	
Management													
Maintenance & Operations		3	3	3	3	3	3	3	3	3	3	3	
Quality Assurance													
Utility Staff	-	6	6	6	6	6	6	6	6	6	6	6	-
General Contractor Staff	-	-	-	-	•	-			-		•		

Period 3 & 4 - License Term & Site Restoration	2103	2104	2105	2106	2107	2108	2109	2110	2111	2112	2113
Administration		4	4	10	12	12	12	12	7	2	
Engineering		4	6	16	20	20	20	20	7	2	
Health Physics/Rad Protection			4	8	24	24	24	24	16	4	
Management		1	1	4	5	5	4	4	4	2	
Maintenance & Operations				10	24	24	20	20	8	2	
Quality Assurance		1	1	2	3	3	2	2	2	1	
Utility Staff	-	10	16	50	88	88	82	82	44	13	•
Project Management		2	4	6	10	10	10	10	8	4	
Engineering		4	6	6	12	12	10	10	7	2	
Health Physics/Rad Protection			4	8	16	16	16	16	12	6	
Administration		2	3	6	12	12	12	12	8	4	
Maintenance & Operations					-	-	-	-	-	-	
Quality Assurance		1	1	2	4	4	4	4	3	2	
Waste Management			1	2	12	12	12	12	12	4	
General Contractor Staff	-	9	19	30	66	66	64	64	50	22	-

Period 5 - Dry Fuel / GTCC Storage & Transfer	2055	2056	2057	2058	2059	2060 / 2069	2070	2071	2072	2073	2074	2075
Administration												
Engineering		1	1	1	1	1	1	1	1	1		
Health Physics/Rad Protection			1	1	1	1	1	1	1	1		
Management												
Maintenance & Operations			2	2	2	2	2	2	2	2		
Quality Assurance			1	1	1	1	1	1	1	1		
Utility Staff	-	1	5	5	5	5	5	5	5	5	•	•
General Contractor Staff	-	-	-	-	-	-	-	-	-	-	-	-

Period 6 - ISFSI Decommissioning	2107	2108	2109	2110	2111	2112	2113	2114	2115
Administration									
Engineering							1		
Health Physics/Rad Protection							1		
Management							1		
Maintenance & Operations									
Quality Assurance							1		
Utility Staff	-	-	-	-	-	-	4	-	-
Project Management						1	1		
Engineering						1	1		
Health Physics/Rad Protection							1		
Administration							1		
Maintenance & Operations									
Quality Assurance						1	1		
Waste Management						1	1		
General Contractor Staff	-	-	-	-	-	4	6	-	-

Detailed staffing tables for each scenario are provided in Appendix D.

Waste Disposal Volumes

Waste disposal is a significant element of the decommissioning project. The estimated waste disposal quantities for Scenario 2 are shown in cubic feet of waste as follows:

Class A	2,390,095
Class B/C	2,686
GTCC	4,122

Waste disposal volumes and costs, itemized by packaging, transportation, surcharges and disposal costs by waste class and facility, are provided in <u>Appendix E</u>.

7.0 REFERENCES

- 1. Atomic Industrial Forum, Inc., "Guidelines for Producing Commercial Nuclear Power Plant Decommissioning Cost Estimates," AIF/NESP-036, May 1986.
- 2. U.S. Nuclear Regulatory Commission, "Standard Format and Content of Decommissioning Cost Estimates for Nuclear Power Reactors," Regulatory Guide 1.202, February 2005.
- 3. U.S. Nuclear Regulatory Commission, "Domestic Licensing of Production and Utilization Facilities," 10 CFR Part 50, 2008.
- 4. Federal Register, Vol. 4, "Standard Contract for Disposal of Spent Nuclear Fuel and/or High-Level Radioactive Waste," NRC 10 CFR Part 961 (DOE), January 1, 1999.
- 5. U.S. Department of Energy, "Strategy for the Management and Disposal of Used Nuclear Fuel and High-Level Radioactive Waste," January 2013.
- 6. U.S. Department of Energy, "Acceptance Priority Ranking & Annual Capacity Report," DOE/RW-0567, July 2004.
- 7. U.S. Nuclear Regulatory Commission, "Technology, Safety and Costs of Decommissioning a Reference Pressurized Water Reactor Power Station," NUREG/CR-0130, June 1980. This original NUREG has been updated by NUREG/CR-5884 "Revised Analyses of Decommissioning for the Reference Pressurized Water Reactor Power Station."
- 8. U.S. Nuclear Regulatory Commission, "Technology, Safety and Costs of Decommissioning a Reference Boiling Water Reactor Power Station," NUREG/CR-0672, June 1980. This original NUREG has been updated by NUREG/CR-6174 "Revised Analyses of Decommissioning for the Reference Boiling Water Reactor Power Station."
- 9. Life-of-Plant Disposal Agreement, between Energy Solutions, LLC and FPL, dated March 26, 2020.
- 10. U.S. Nuclear Regulatory Commission, "Multi-Agency Radiation Survey and Site Investigation Manual (MARSSIM)," NUREG-1575, Rev. 1, August 2000.
- 11. U.S. Department of Energy, "Cost Estimating Guide," DOE G 430.1-1, March 1997.

Document No. 164086-DCE-02

APPENDIX A

FPL - Turkey Point - UNITS 3 & 4 Plant Structures and Systems

Turkey Point - Primary Plant Structures										
Unit 3	Unit 4									
Reactor	Reactor									
Turbine & Turbine Pedestal	Auxiliary Building									
Fuel Handling Building	Control Building									
Sealwell	Intake Structure									
Misc Structures	Radwaste Building									
	LLW Storage Building									
	Maintenance Facility									
	Sealwell									
	Turbine & Turbine Pedestal									
	Fuel Handling Building									

Misc. Structures


	Wilse. Structures
Turkey Point -	Primary Plant Systems
Unit 3	Unit 4
Amertap	Amertap
Auxiliary Feedwater	Auxiliary Feedwater
Auxiliary Steam	Auxiliary Steam
Breathing Air	Breathing Air
Chemical & Volume Control	Chemical & Volume Control
Circulating Water	Circulating Water
Component Cooling Water	Component Cooling Water
Condensate	Condensate
Condensate Polishing	Condensate Polishing
Condensate Recovery	Condensate Recovery
,	
Condensate Storage	Condensate Storage
Condenser	Condenser Containment Boot Assident
Containment Post Accident	Containment Post Accident
Containment Spray	Containment Spray
EDG Engine & Oil	EDG Engine & Oil
Extraction Steam	Extraction Steam
Feedwater	Feedwater
Fire Protection	Fire Protection
Generator	Generator
HVAC	HVAC
Instrument Air	Instrument Air
Intake Cooling Water	Intake Cooling Water
Main Steam	Main Steam
Primary & Secondary Wet Layup	Nitrogen & Hydrogen
Primary Water Makeup	Primary & Secondary Wet Layup
Reactor Coolant	Primary Water Makeup
Refueling Equipment	Reactor Coolant
Residual Heat Removal	Refueling Equipment
Safety Injection	Residual Heat Removal
Sampling	Safety Injection
Screen Wash	Sampling
Service Water	Screen Wash
Spent Fuel Pool Cooling	Service Water
Turbine Lube Oil	Spent Fuel Pool Cooling
Turbine Plant Chemical Addition	Turbine Lube Oil
Turbine Plant Cooling Water	Turbine Plant Chemical Addition
Turbine Steam	Turbine Plant Cooling Water
Waste Disposal	Turbine Steam
114310 21300341	Waste Disposal
	Waste Disposal Water Treatment
	water freatment

Appendix B-1 - Schedule Florida Power and Light Turkey Point Units 3 & 4 Scenario 1 - Prompt DECON following Unit 4 Shutdown Description MILESTONES Unit 3 Shutdown (2052) DOE Starts Accepting Fuel (2031) Unit 3 Zirc Fire Period Ends (2053)


Unit 3 Fuel Pool Empty (2056) Unit 4 Shutdown (2053) Unit 4 Zirc Fire Period Ends (2054) Unit 4 Fuel Pool Empty (2056) Decommissioning & Site Restoration Complete (2063) ISFSI Empty (2073) ISFSI Decommissioning & Site Restoration Complete (2073) PERIOD 1 - SHUTDOWN & TRANSITION 1a. Planning Prior to Shutdown (by Plant Operations) 1b. Unit 3 Post Shutdown Planning & Engineering 1c. Unit 3 Post Shutdown Deactivation & Modifications 1d. Unit 3 Wet Fuel Transfer to DOE prior to DECON 1e. Unit 3 Wet Fuel Transfer to ISFSI prior to DECON 1f. Unit 4 Post Shutdown Planning & Engineering 1g. Unit 4 Post Shutdown Deactivation & Modifications 1h. Unit 4 Wet Fuel Transfer to DOE prior to DECON 1i. Unit 4 Wet Fuel Transfer to ISFSI prior to DECON 1j. Undistributed Costs for Shutdown & Transition PERIOD 2 - SAFSTOR PERIOD 3 - DECOMMISSIONING & LICENSE TERMINATION 3a. Decommissioning Planning 3b. Decommissioning Transition & Preparations 3c. Reactor Vessel Removal 3d. Large Component Removal 3e. Plant Decontamination & Interior Rad Demolition 3f. Rad Building Demolition 3g. License Termination Activities 3h. Undistributed Costs for Decommissioning & License Termination PERIOD 4 - SITE RESTORATION 4a. Clean Building & Site Demolition 4b. Site Restoration 4c. Undistributed Costs for Site Restoration PERIOD 5 - DRY FUEL / GTCC STORAGE & TRANSFER 5a. Dry Fuel Transfer to DOE 5b. GTCC Waste Disposition 5c. Undistributed Costs for Dry Fuel / GTCC Storage & Transfer PERIOD 6 - ISFSI DECOMMISSIONING 6a. ISFSI D&D Planning & Preparations 6b. ISFSI and Support Structure Clean Demolition 6c. ISFSI Final Status Surveys 6d. Undistributed Costs for ISFSI Decommissioning

Assumed by plant Operations Included in estimate Undistributed costs Included in estimate Florida Power and Light Turkey Point UnitS 3 & 4 Scenario 2 - SAFSTOR

Scenario 2 - SAFSTOR	1		T				.1.	1					1_	11					г					_1		_1_		_	.1.	1	Ι	T						I I		_
Description	2030	2031	2032 203	3 2034	4 2035	2036	2037	2038 2	2039 2	040 204	41 20	2043	2044	2045	2046	2047	2048	2049 2	2050 2	2051 2	:052 2	2053 2	2054 205	5 205	6 205	/ 205	8 2059	2060	2061	2062	2063	2064	2065	2066 2	.067 20	68 206	69 2070	2071	2072	2073
MILESTONES				4																													4	4	4	4				
Unit 3 Shutdown (2052)			+	4	ــــــــــــــــــــــــــــــــــــــ										\vdash	\vdash				•	•						4	<u>—</u>				1		_	$-\!\!\!\!+$		<u> </u>		${oldsymbol{\sqcup}}$	—
DOE Starts Accepting Fuel (2031)		-	1	4	\bot		1				1				\dashv	ightharpoonup								-		<u> </u>	4			<u> </u>	ļ	\sqcup	_	\dashv	\perp	_	<u> </u>		\sqcup	
Unit 3 Zirc Fire Period Ends (2053)			 	\bot	\bot										\vdash	\sqcup						-					┷	<u>—</u>						_			'		igspace	ь—
Unit 3 Fuel Pool Empty (2039)			\bot	\bot	\bot										\vdash	\sqcup									<u> </u>		┷	<u>—</u>				$\perp \perp \downarrow$		_			'		\sqcup	—
Unit 4 Shutdown (2053)			$oxed{oxed}$		\perp																^	•						<u> </u>									'		Ш	—
Unit 4 Zirc Fire Period Ends (2054)			$oxed{oxed}$		\perp																		•					<u></u>									'		Ш	Ь—
Unit 4 Fuel Pool Empty (2056)																									<u> </u>			<u></u>											Ш	
ISFSI Empty (2073)																												<u></u>											Ш	
SAFSTOR Period Ends (2105)																ı												<u> </u>												
Decommissioning & Site Restoration Complete (2112)																																								1
ISFSI Decommissioning & Site Restoration Complete (2113)																																								
PERIOD 1 - SHUTDOWN & TRANSITION																																								
1a. Planning Prior to Shutdown (by Plant Operations)																ı																								
1b. Unit 3 Post Shutdown Planning & Engineering				1	1											ıΠ								1				Ī					\exists	\top	\top	\top	1		П	
1c. Unit 3 Post Shutdown Deactivation & Modifications				\top	\top	1					1		t		\Box	\sqcap								1		1	1		1			\Box	\dashv	\top	\top	\top	1		П	
1d. Unit 3 Wet Fuel Transfer to DOE prior to SAFSTOR				\pm	\pm																		_	ļ								1 1			1		+			
1e. Unit 3 Wet Fuel Transfer to ISFSI prior to SAFSTOR			++	+	+																						+						\dashv	-	\dashv	+	+		\Box	
1f. Unit 4 Post Shutdown Planning & Engineering			++	+	+		1	1			-				-	\vdash											+-	$\overline{}$				+	\dashv	+	+	+	+		\vdash	
1g. Unit 4 Post Shutdown Deactivation & Modifications			 	+	+			\vdash	-		-	-			\dashv	ightharpoonup						_		+	+		+	\vdash				+-+	\dashv	+	+	+	+		\vdash	_
1h. Unit 4 Wet Fuel Transfer to DOE prior to SAFSTOR			\vdash	\pm	_			\vdash				-												_			+-	_				+	\dashv	+	\dashv	+	+'		\vdash	_
			\vdash	干	干	+	\vdash	\vdash	\dashv		+	+	H	H	\exists	\dashv	\dashv	-	\dashv	+	+			+			+	\vdash				+	\dashv	+	+	+			\vdash	_
1i. Unit 4 Wet Fuel Transfer to ISFSI prior to SAFSTOR				+	+						-				\dashv	\vdash					_			£			+-	\vdash				1	\dashv	+	-	_			\vdash	_
1j. Undistributed Costs for Shutdown & Transition			_	_	_																						+							_	_	+			\vdash	
PERIOD 2 - SAFSTOR				+-	4-																						_						_	_	_	_	_			_
2a. Dormancy during Dry Fuel Storage				+	+						-				\dashv	\vdash										Т	干					\vdash	\equiv	干	Ŧ	干	干	 	\vdash	
2b. Dormancy Only				+																							+							\rightarrow		\blacksquare				
PERIOD 3 - DECOMMISSIONING & LICENSE TERMINATION			-	4	4																						+-	\vdash					-	-	+	+	#		H	_
3a. Decommissioning Planning				+-	+											\vdash											+					+-+	\dashv		-	+			\vdash	_
3b. Decommissioning Transition & Preparations			+-+	+	+			-			-				\dashv	\dashv								-	-		+					+	\dashv	-	\dashv	+	-		$\vdash \vdash$	_
3c. Reactor Vessel Removal			+-+	+	+			-			-				\dashv	\dashv								-	-		+					+	\dashv	-	\dashv	+	-		$\vdash \vdash$	_
3d. Large Component Removal			++	+	+			-	_		-				\dashv	\vdash					_			+	-	-	$+\!-$	 				+	\dashv	_	$-\!\!\!\!+$	+			\vdash	_
3e. Plant Decontamination & Interior Rad Demolition			\vdash	_	┿			-				-				\vdash											+	<u>—</u>				1	_	_	-	+			$\vdash \vdash$	_
3f. Rad Building Demolition			+-	+	+											\vdash								-			+	<u>—</u>				$\perp \rightarrow$	_	_	\dashv	\dashv	<u> </u>		\longmapsto	—
3g. License Termination Activities			+-	4	ــــــــــــــــــــــــــــــــــــــ										\vdash	\vdash												—				1		_	$-\!\!\!\!+$	$-\!$	<u> </u>		\vdash	
3h. Undistributed Costs for Decommissioning & License Termination					┷																							<u>—</u>							_	_			\square	_
PERIOD 4 - SITE RESTORATION				4	4																						4	\blacksquare							4	4	42			
4a. Clean Building & Site Demolition			$\perp \perp \perp$		┷										\Box	\sqcup											┷	<u> </u>												ь—
4b. Site Restoration			$\perp \perp \perp$		┷										\Box	\sqcup											┷	<u> </u>												ь—
4c. Undistributed Costs for Site Restoration			$\perp \perp$		\perp																							<u>L</u>									'		Ш	ш
PERIOD 5 - DRY FUEL / GTCC STORAGE & TRANSFER																																								
5a. Dry Fuel Transfer to DOE																																								
5b. GTCC Waste Disposition									\prod																			L											ĹŢ	
5c. Undistributed Costs for Dry Fuel / GTCC Storage & Transfer			$oxed{oxed}$							$oxed{oxed}$	\int					ĹŢ					T														J	卓				
PERIOD 6 - ISFSI DECOMMISSIONING																																								
6a. ISFSI D&D Planning & Preparations													L													Ι	1	L												L
6b. ISFSI and Support Structure Clean Demolition					1											厂												L												
6c. ISFSI Final Status Surveys																1												1											П	
00.10.0.1.11110.10.10.10.10.10.10.10.10.						_	_					_			'						_			_	_	_						-	-	-	-	_				



Florida Power and Light Turkey Point UnitS 3 & 4 Scenario 2 - SAFSTOR 2074 2075 2076 2077 2078 2079 2080 2081 2082 2083 2084 2082 2083 2084 2085 2086 2087 2088 2089 2090 2091 2092 2093 2094 2095 2096 2097 2098 2099 2100 2101 2102 2103 2104 2105 2106 2107 2108 2109 2110 2111 2112 2113 2114 2115 Description MILESTONES Unit 3 Shutdown (2052) DOE Starts Accepting Fuel (2031) Unit 3 Zirc Fire Period Ends (2053) Unit 3 Fuel Pool Empty (2039) Unit 4 Shutdown (2053) Unit 4 Zirc Fire Period Ends (2054) Unit 4 Fuel Pool Empty (2056) ISFSI Empty (2073) SAFSTOR Period Ends (2105) Decommissioning & Site Restoration Complete (2112) ISFSI Decommissioning & Site Restoration Complete (2113) PERIOD 1 - SHUTDOWN & TRANSITION 1a. Planning Prior to Shutdown (by Plant Operations) 1b. Unit 3 Post Shutdown Planning & Engineering 1c. Unit 3 Post Shutdown Deactivation & Modifications 1d. Unit 3 Wet Fuel Transfer to DOE prior to SAFSTOR 1e. Unit 3 Wet Fuel Transfer to ISFSI prior to SAFSTOR 1f. Unit 4 Post Shutdown Planning & Engineering 1g. Unit 4 Post Shutdown Deactivation & Modifications 1h. Unit 4 Wet Fuel Transfer to DOE prior to SAFSTOR 1i. Unit 4 Wet Fuel Transfer to ISFSI prior to SAFSTOR 1j. Undistributed Costs for Shutdown & Transition PERIOD 2 - SAFSTOR 2a. Dormancy during Dry Fuel Storage 2b. Dormancy Only PERIOD 3 - DECOMMISSIONING & LICENSE TERMINATION 3a. Decommissioning Planning 3b. Decommissioning Transition & Preparations 3c. Reactor Vessel Removal 3d. Large Component Removal 3e. Plant Decontamination & Interior Rad Demolition 3f. Rad Building Demolition 3g. License Termination Activities 3h. Undistributed Costs for Decommissioning & License Termination PERIOD 4 - SITE RESTORATION 4a. Clean Building & Site Demolition 4b. Site Restoration 4c. Undistributed Costs for Site Restoration PERIOD 5 - DRY FUEL / GTCC STORAGE & TRANSFER 5a. Dry Fuel Transfer to DOE 5b. GTCC Waste Disposition 5c. Undistributed Costs for Dry Fuel / GTCC Storage & Transfer PERIOD 6 - ISFSI DECOMMISSIONING 6a. ISFSI D&D Planning & Preparations 6b. ISFSI and Support Structure Clean Demolition 6c. ISFSI Final Status Surveys 6d. Undistributed Costs for ISFSI Decommissioning



Florida Power and Light Turkey Point Unit 3

Scenario 1 - Prompt DECON following Unit 4 Shutdown

	Item		Labor	Materials &	Waste	Other Direct		Total Cost	License	Spent Fuel	Site
Period	Number	Item Description	Cost	Equipment	Transportation & Disposal	Cost (ODC)	Contingency	(Estimated)	Termination	Management	Restoration
					Disposai						
1a Total	Planning	g Prior to Shutdown (by Plant Operations)	-	-	-	-	-	-	-	-	-
	41-4	Advis Astistics in Bases antique for Bases and in the 12	2.652	0.2			440	2.446	2.146		
	1b.1	Admin Activities in Preparation for Decommissioning - Unit 3	2,653	82	-	-	410	3,146	3,146	-	-
	1b.2	Prepare PSDAR and License Documents - Unit 3	444	14	-	-	69	527	527	-	-
1h Total	1b.3	Engineering Activities in Preparation for Decommissioning - Unit 3	1,064	52 148	<u>-</u>	26 26	171 650	1,314	1,314 4,986		-
1b Total	Unit 3 Po	ost Shutdown Planning & Engineering	4,161	148	-	20	650	4,986	4,980	-	-
	1c.1	Defuel Reactor Unit 3 (by Plant Operations)	_	_	-	_	_	_	-	_	_
	1c.2	Fuel Sampling & Inspections (by Plant Operations)	_	_	_	_	_	_	_	-	_
	1c.3	Spent Fuel Pool System Modifications - Unit 3	11,345	1,212	_	_	1,884	14,441	_	14,441	_
1c Total		Post Shutdown Deactivation & Modifications	11,345	1,212	-	-	1,884	14,441	-	14,441	-
			,	,			,	,		•	
	1d.1	Provide Transfer Casks (supplied by DOE)	-	-	-	-	-	-	-	-	-
	1d.2	Procure Spent Fuel Loading & Transfer Equipment	-	2,184	-	-	328	2,512	-	2,512	-
	1d.3	Procedures & Dry Runs	500	-	-	250	113	863	-	863	-
	1d.4	Remove (448) Fuel Assemblies from Pool & Load DOE Casks	2,240	560	-	-	560	3,360	-	3,360	-
	1d.5	Dry, Close & Inspect (14) DOE supplied Casks	1,120	280	-	-	280	1,680	-	1,680	-
	1d.6	Load Out (14) Casks to DOE Transport	1,120	280	-	-	280	1,680	-	1,680	-
	1d.7	Spent Fuel Transportation & Disposal (by DOE)	-	-	-	-	-	-	-	-	-
1d Total	Unit 3 W	Vet Fuel Transfer to DOE prior to DECON	4,980	3,304	-	250	1,560	10,094	-	10,094	-
	4 - 4	Post of Transfer Code		42.244			4.006	45 227		45.227	
	1e.1	Purchase Transfer Casks	-	13,241	-	-	1,986	15,227	-	15,227	-
	1e.2	Procure Spent Fuel Loading & Transfer Equipment	-	-	-	-	112	-	-	-	-
	1e.3	Procedures & Dry Runs Remove (464) Fuel Assemblies from Pool & Load DOE Casks	500	-	-	250	113	863	-	863	-
	1e.4 1e.5	, ,	2,400 1,200	600 300	-	-	600 300	3,600 1,800	-	3,600 1,800	-
	1e.5 1e.6	Dry, Close & Inspect (15) DOE supplied Casks Load Out (15) Casks to DOE Transport	1,200	300	-	-	300	1,800	_	1,800	-
	1e.0 1e.7	Spent Fuel Transportation & Disposal (by DOE)	1,200	300	- -	_	300	1,800	_	1,800	_
1e Total		Vet Fuel Transfer to ISFSI prior to Shutdown	5,300	14,441	-	250	3,299	23,290		23,290	-
			2,000	,,			0,200				
1f Total	Unit 4 Po	ost Shutdown Planning & Engineering	-	-	-	-	_	-	-	-	-
1g Total	Unit 4 Sh	hutdown Preparations & Deactivation	-	-	-	-	-	-	-	-	-
1h Total	Unit 4 W	Vet Fuel Transfer to DOE prior to DECON	-	-	-	-	-	-	-	-	-
1: Tatal	11mi+ 4 14	Job Fried Transfer to ISESI major to DECON									
1i Total	Unit 4 W	/et Fuel Transfer to ISFSI prior to DECON	-	-	•	•	-	-	-	-	-

Florida Power and Light Turkey Point Unit 3

Scenario 1 - Prompt DECON following Unit 4 Shutdown

				(thot	usands of 2020 do	lidis)					
Period	Item Number	Item Description	Labor Cost	Materials & Equipment	Waste Transportation & Disposal	Other Direct Cost (ODC)	Contingency	Total Cost (Estimated)	License Termination	Spent Fuel Management	Site Restoration
	1j.1	Utility Staff	44,454				6,668	51,122	40,897	10,224	
	1j.1 1j.2	Security Guard Force	21,113		_	_	3,167	24,280	· ·	16,996	_
	1j.2 1j.3	General Contractor Staff	21,113	_	_	_	3,107	24,200	7,204	10,550	_
	1j.4	Property Taxes	_	_	_	67	10	77	62	15	_
	1j.5	Insurance	-	_	_	10,251	1,538	11,788		2,358	_
	1j.6	Corporate Support	2,932	_	-	-	440	3,372	*	2,360	_
	1j.7	Utility Staff HP Supplies	-	903	-	-	135	1,038	· ·	727	_
	1j.8	NRC Inspection Fee	-	-	-	2,780	417	3,197		-	_
	1j.9	Licensing Fees	-	-	-	860	129	989		_	_
	1j.10	Materials and Services	-	1,639	_	-	246	1,885		1,320	_
	1j.11	Energy	-	-	-	1,428	214	1,643		329	_
	1j.12	EPRI Membership Fees	-	-	-	-	-	-	-	-	_
	1j.13	NEI Membership Fees	-	-	-	-	-	-	-	-	_
	1j.14	County & FEMA Fees	-	-	-	2,828	424	3,252	2,601	650	_
	1j.15	Licenses & Permits	-	-	-	85	13	97	78	19	-
	1j.16	INPO Membership Fees	-	-	-	-	-	-	-	-	-
	1j.17	ISFSI Operating Costs	20	61	-	-	12	93	-	93	-
	1j.18	Spent Fuel Maintenance	985	328	-	-	197	1,510	-	1,510	-
1j Total	Undistr	ibuted Costs for Shutdown & Transition	69,504	2,931	-	18,299	13,610	104,344	67,742	36,602	-
Period 1	Total	SHUTDOWN & TRANSITION	95,290	22,037	-	18,825	21,003	157,154	72,728	84,426	1
Period 2	Total	SAFSTOR	-	-	-	-	-	-	-	-	-
	3a.1	Decommissioning Planning and Design - Unit 3	1,523	46	-	_	235	1,804	1,804	_	_
	3a.2	Prepare Integrated Work Sequence and Schedule - Unit 3	164	5		-	25	195	195	_	_
	3a.3	Site Characterization - Unit 3	1,953	53	_	105	317	2,429		-	_
	3a.4	Prepare Decommissioning Activity Specifications - Unit 3	5,096	158		-	788	6,042		-	-
	3a.5	Prepare Detailed Work Procedures - Unit 3	4,479	139		-	693	, 5,310	-	-	-
	3a.6	Prepare License Termination Plan - Unit 3	984	-	-	667	248	1,899		-	-
	3a.7	Design Containment and Misc System Modifications - Unit 3	195	-	-	-	29	224		-	-
	3a.8	Purchase Dry Storage Modules for Unit 3 GTCC Waste	-	-	4,708	-	706	5,414		-	-
3a Total		missioning Planning	14,395	400		772	3,041	23,317		-	-
	3b.1	Mobilize Decommissioning General Contractor	-	-	-	1,693	254	1,947	1,947	-	-
	3b.2	Perform Asbestos Abatement of Pipe Insulation - Unit 3	3,465	182	-	-	912	4,559	4,559	-	-
	3b.3	Implement Cold and Dark & Install Temporary Power - Unit 3	4,669	1,568	-	-	936	7,172	7,172	-	-

Florida Power and Light Turkey Point Unit 3

Scenario 1 - Prompt DECON following Unit 4 Shutdown

				(21.10	3381103 01 2020 00						
Period	Item Number	Item Description	Labor Cost	Materials & Equipment	Waste Transportation & Disposal	Other Direct Cost (ODC)	Contingency	Total Cost (Estimated)	License Termination	Spent Fuel Management	Site Restoration
	3b.4	Construct Misc Building Modifications, In-Plant Laydown Areas	2,996	508	-	-	526	4,030	4,030	-	-
	3b.5	Modify Containment Access - Unit 3	2,223	377	-	-	390	2,990	2,990	-	-
	3b.6	Transportation Infrastructure Modifications	93	447	-	2,089	394	3,023	3,023	-	-
	3b.7	Procure Waste Handling & Processing Tents	-	-	-	1,739	261	2,000	2,000	-	-
3b Total	Decomn	nissioning Transition and Preparations	13,445	3,082	-	5,521	3,672	25,721	25,721	-	-
	3c.1	Design and Procure Special Equipment	-	29,000	-	-	5,800	34,800	34,800	-	-
	3c.2	Test Special Cutting and Handling Equipment and Train Operators	2,263	-	-	72	467	2,802	2,802	-	-
	3c.3	Finalize Internals and Vessel Segmentation Details - Unit 3	538	-	-	-	108	646	646	-	-
	3c.4	Segment, Package and Ship Reactor Internals - Unit 3	5,879	2,100	-	-	1,596	9,575	9,575	-	-
	3c.5	Segment, Package and Ship RPV - Unit 3	1,394	1,030	-	-	485	2,909	2,909	-	-
	3c.6	Package and Ship Reactor Pressure Vessel - Unit 3	-	-	16,724	-	3,345	20,069	20,069	-	-
3c Total	Reactor	Vessel Removal	10,074	32,130	16,724	72	11,800	70,800	70,800	-	-
	3d.1	Heavy Lift / Transfer Equipment		3,245	-	-	649	3,893	3,893	-	-
	3d.2	Remove and Dispose of Steam Generators - Unit 3	1,417	163	-	-	316	1,895	1,895	-	-
	3d.3	Remove and Dispose of Pressurizer - Unit 3	195	22	-	-	43	259	259	-	-
	3d.4	Remove and Dispose of Reactor Coolant Pipe - Unit 3	522	36	-	-	112	670	670	-	-
	3d.5	Remove and Dispose of Reactor Coolant Pumps - Unit 3	537	59	-	-	119	716	716	-	-
	3d.7	Package, Ship, & Dispose	-	-	11,062	-	2,212	13,274	13,274	-	-
3d Total	Large Co	omponent Removal	2,671	3,524	11,062	-	3,451	20,708	20,708	-	-
	3e.1	Remove and Dispose of Spent Fuel Storage Racks	68	20	-	-	18	106	106	-	-
	3e.2	Segment, Package and Dispose of Spent Fuel Pool Island Equipment	214	20	-	-	47	281	281	-	-
	3e.3	Decon/Surgical Removal Containment Building - Unit 3	1,095	130	-	-	245	1,470	1,470	-	-
	3e.4	Decon/Surgical Removal Fuel Building	553	21	-	-	115	688	688	-	-
	3e.5	Decon/Surgical Remvoal Auxiliary Building (with Unit 4)	-	-	-	-	-	-	-	-	-
	3e.6	Package, Dispose, & Ship	-	-	3,569	-	714	4,283	4,283	-	-
3e Total	Plant De	econtamination & Interior Rad Demolition	1,930	191	3,569	-	1,138	6,828	6,828	-	-
	3f.1	Demolish Fuel Building	257	538	-	-	159	953	953	-	-
	3f.2	Demolish Auxiliary Building (with Unit 4)	-	-	-	-	-	-	-	-	-
	3f.3	Demolish Unit 3 Containment Building	2,019	6,120	-	-	1,628	9,767	9,767	-	-
	3f.4	Contaminated Soil	397	596	17,930	-	3,785	22,709	22,709	-	-
	3f.5	Debris Disposal			46,283		9,257	55,539	55,539		
3f Total	Rad Buil	ding Demolition	2,673	7,254	64,213	-	14,828	88,968	88,968	-	-
	3g.1	Final Status Survey for Structures	5,897	67	-	227	1,238	7,428	7,428	-	-

Florida Power and Light Turkey Point Unit 3

Scenario 1 - Prompt DECON following Unit 4 Shutdown

				(110)	usanus or 2020 do	iiai 3 j					
Period	Item Number	Item Description	Labor Cost	Materials & Equipment	Waste Transportation & Disposal	Other Direct Cost (ODC)	Contingency	Total Cost (Estimated)	License Termination	Spent Fuel Management	Site Restoration
	3g.2	Final Status Survey for Land Areas (included with structures)	-	-	-	-	-	-	-	-	
3g Total	License	Termination Activities	5,897	67	-	227	1,238	7,428	7,428	-	-
	3h.1	Utility Staff	29,716	-	-	-	4,457	34,174	34,174	-	-
	3h.2	Security Guard Force	1,951	-	-	-	293	2,244	2,244	-	-
	3h.3	General Contractor Staff	67,660	-	-	-	10,149	77,809	77,809	-	-
	3h.4	Property Taxes	-	-	-	75	11	86	86	-	-
	3h.5	Insurance	-	-	-	5,428	814	6,242	6,242	-	-
	3h.6	Corporate Support	11,033	-	-	-	1,655	12,688	12,688	-	-
	3h.7	Utility Staff HP Supplies	-	4,732	-	-	710	5,441	5,441	-	-
	3h.8	NRC Inspection Fee	-	-	-	667	100	767	767	-	-
	3h.9	Licensing Fees	-	-	-	1,032	155	1,187	1,187	-	-
	3h.10	County & FEMA Fees	-	-	-	-	-	-	-	-	-
	3h.11	Licenses & Permits	-	-	-	95	14	109	109	-	-
	3h.12	Materials and Services	-	1,648	-	-	247	1,895	1,895	-	-
	3h.13	Energy	-	-	-	2,541	381	2,923	2,923	-	-
	3h.14	DGC HP Supplies	-	5,132	-	-	770	5,902	5,902	-	-
	3h.15	Florida LLRW Inspection Fee	-	-	-	1,798	270	2,068	2,068	-	-
	3h.16	EPRI Membership Fees	-	-	-	-	-	-	-	-	-
	3h.17	NEI Membership Fees	-	-	-	-	-	-	-	-	-
	3h.18	INPO Membership Fees	-	-	-	-	-	-	-	-	<u>-</u>
3h Total	Undistri	buted Costs for Decommissioning & License Termination	110,361	11,511	-	11,636	20,026	153,535	153,535	-	-
_											
Period 3	Total	DECOMMISSIONING & LICENSE TERMINATION	161,446	58,160	100,276	18,227	59,195	397,306	397,306	-	-
	4a.1	Demo Turbine Pedastal and Turbine Deck	3,647	1,506			773	5,927			E 02-
	4a.1 4a.2	Demo Sealwell	113	251		-	55	418	_	-	5,927 418
	4a.2 4a.3	Demo Tank Foundations	113	251		-	39	302	_	-	302
	4a.3 4a.4	Demo Misc Site Structures	206	502		-	106	814		-	814
	4a.4 4a.5	Security Improvements	667	1,255		_	288	2,210		_	2,210
	4a.5 4a.6	Clean Concrete Processing		1,233	_	1,306	196	1,502		_	1,502
	4a.0 4a.7	Demo Site Paving	220	330	-	1,300	83	633	_	-	633
	4a.7 4a.8	Clean Debris Disposal/Recycle	220	330	101	-	15	117	_	-	117
4a Total		uilding & Site Demolition	4,864	4,096		1,306	1,555	11,922	-		11,922
a iolai	Cicali Bi	unung a site demonition	4,004	4,030	101	1,300	1,555	11,922	•	-	11,522
	4b.1	Procure Site Restoration Equipment	-	735	-	-	110	846	-	-	846
	4b.2	Finish Grading and Re-Vegetate Site	715		-	-	107	822	-	-	822
4b Total	Site Res		715	735	-	-	218	1,668	-	-	1,668

Florida Power and Light Turkey Point Unit 3

Scenario 1 - Prompt DECON following Unit 4 Shutdown

			(thousands of 2020 dollars)									
Period	Item Number	Item Description	Labor Cost	Materials & Equipment	Waste Transportation & Disposal	Other Direct Cost (ODC)	Contingency	Total Cost (Estimated)	License Termination	Spent Fuel Management	Site Restoration	
	4c.1	Utility Staff	2,237	_	_	_	336	2,572	_	_	2,572	
	4c.1	Security Guard Force	147	_	_	_	22	169		_	169	
	4c.3	General Contractor Staff	5,093	_	_	_	764	5,857		_	5,857	
	4c.4	Property Taxes	-	_	_	6	1	5,057	_	_	6	
	4c.5	Insurance	_	_	-	409	61	470	_	_	470	
	4c.6	Corporate Support	830	_	_	-	125	955	_	_	955	
	4c.7	Energy	-	_	_	135	20	156	_	_	156	
	4c.8	Materials and Services	-	84		-	13	96		-	96	
	4c.9	County & FEMA Fees	-	-	-	-	-	-	-	_	-	
	4c.10	Licenses & Permits	-	-	-	7	1	8	-	-	8	
4c Total		ibuted Costs for Site Restoration	8,307	84	-	557	1,342	10,289	-	-	10,289	
Period 4	Total	SITE RESTORATION	13,886	4,915	101	1,862	3,115	23,879	-	-	23,879	
	5a.1	Procure Loading & Transfer Equipment (included in Period 1)	-	-	-	-	-	-	-	-	-	
	5a.2	Procedures & Dry Runs (included in Period 1)	-	-	-	-	-	-	-	-	-	
	5a.3	Remove (43) Fuel Casks from ISFSI & Load DOE Transport	3,440	860	-	-	645	4,945	-	4,945	-	
	5a.4	Spent Fuel Transportation & Disposal (by DOE)	-	-	-	-	-	-	-	-	-	
5a Total	Dry Fue	l Transfer to DOE during and after DECON	3,440	860	-	-	645	4,945	-	4,945	-	
	5b.1	Remove GTCC Casks from ISFSI & Loadout	320	-	-	80	120	520			-	
	5b.2	GTCC Transportation & Disposal	-	-	11,746.22	-	1,762	13,508			-	
5b Total	GTCC W	aste Disposition	320	-	11,746	80	1,882	14,028	14,028	-	-	
	5c.1	Utility Staff	5,897	-	-	-	885	6,781	-	6,781	-	
	5c.2	Security Guard Force	22,749	-	-	-	3,412	26,162	-	26,162	-	
	5c.3	General Contractor Staff	-	-	-	-	-	-	-	-	-	
	5c.4	Property Taxes	-	-	-	148	22	170		170	-	
	5c.5	Insurance	-	-	-	6,918	1,038	7,956	-	7,956	-	
	5c.6	Corporate Support	-	-	-	-	-	-	-	-	-	
	5c.7	Utility Staff HP Supplies	-	-	-	-	-	-	-	-	-	
	5c.8	NRC Inspection Fee	-	-	-	1,112	167	1,279		1,279	-	
	5c.9	Licensing Fees	-	-	-	1,720	258	1,978	-	1,978	-	
	5c.10	County & FEMA Fees	-	-	-	-	-	-	-	-	-	
	5c.11	Licenses & Permits	-	-	-	169	25	195	-	195	-	
	5c.12	Energy	-	-	-	-	-	-	-	-	-	
	5c.13	Materials and Services	-	490	-	-	74	564	-	564	-	

Florida Power and Light Turkey Point Unit 3

Scenario 1 - Prompt DECON following Unit 4 Shutdown

Period	Item Number	Item Description	Labor Cost	Materials & Equipment	Waste Transportation & Disposal	Other Direct Cost (ODC)	Contingency	Total Cost (Estimated)	License Termination	Spent Fuel Management	Site Restoration
	5c.14	ISFSI Operating Costs	-	-	-	2,378	357	2,734	-	2,734	-
5c Total	Undistr	ibuted Costs for Dry Fuel / GTCC Storage & Transfer	28,646	490	-	12,445	6,237	47,819	-	47,819	-
Period 5	Total	DRY FUEL / GTCC STORAGE & TRANSFER	32,406	1,350	11,746	12,525	8,764	66,792	14,028	52,764	-
	6a.1	Preparation and NRC Review of License Termination Plan	71	_	_	96	25	192	_	192	-
6a Total		&D Planning & Preparations	71	-	-	96	25		-	192	-
	6b.1	Clean Demolition of ISFSI	2,073	958	-	-	455	3,486	-	3,486	-
	6b.2	Demolition of ISFSI Support Structures	377	141		-	78	596		596	-
6b Total	ISFSI an	nd Support Structure Clean Demolition	2,451	1,099	-	-	532	4,082	-	4,082	-
	6c.1	Verification Surveys	128	33	-	-	24	185	-	185	-
	6c.2	Preparation of Final Report on Decommissioning and NRC Review	71	-	-	-	11	81		81	-
6c Total	ISFSI Fir	nal Status Surveys	199	33	-	-	35	266	-	266	-
	6d.1	Utility Staff	304	-	-	-	46	350	-	350	-
	6d.2	Security Guard Force	153	-	-	-	23	176		176	-
	6d.3	General Contractor Staff	1,999	-	-	-	300	2,299	-	2,299	-
	6d.4	Property Taxes	-	-	-	13	2	15	-	15	-
	6d.5	Insurance	-	-	-	25	4	29	-	29	-
	6d.6	Corporate Support	-	-	-	-	-	-	-	-	-
	6d.7 6d.8	Utility Staff HP Supplies Materials and Services	-	23	-	-	-	-	-	-	-
	6d.9	Energy	-	23	-	35	5	26 41	_	26 41	-
	6d.10	NRC Inspection Fee	_	_	_	-	-	41	_	41	_
	6d.11	Licensing Fees	_	_	_	_	_	_	_	_	_
	6d.12	County & FEMA Fees	-	_	_	-	_	_	_	_	_ [
	6d.13	Licenses & Permits	-	_	_	34	5	39	_	39	_
6d Total		ibuted Costs for ISFSI Decommissioning	2,456	23		108	388		-	2,974	_
		<u> </u>	,					,		,	
Period 6	Total	ISFSI DECOMMISSIONING	5,176	1,154	-	204	980	7,514	-	7,514	-
GRAND	TOTAL		308,203	87,617	112,124	51,644	93,057	652,645	484,062	144,704	23,879

Florida Power and Light

Turkey Point Unit 4

Scenario 1 - Prompt DECON both following Unit 4 Shutdown

Period	Item Number	Item Description	Labor Cost	Materials & Equipment	Waste Transportation & Disposal	Other Direct Cost (ODC)	Contingency	Total Cost (Estimated)	License Termination	Spent Fuel Management	Site Restoration
1a Total	Plannii	ng Prior to Shutdown (by Plant Operations)	-	-	-	-	-	-	-	-	-
1b Total	Unit 3 F	Post Shutdown Planning & Engineering	-	-	-	-	-	-	-	-	-
1c Total	Unit 3	Post Shutdown Deactivation & Modifications	-	-	-	-	-	-	-	-	-
1d Total	Unit 3 \	Wet Fuel Transfer to DOE prior to SAFSTOR	-	-	-	-	-	-	-	-	-
1e Total	Linit 2 \	Vet Fuel Transfer to ISFSI prior to SAFSTOR									
Te iotai	Ullit 3 V	vet ruei transier to isrsi prior to sarsion		<u>-</u>	-	-	-	-	-	-	
	1f.1	Admin Activities in Preparation for Decommissioning - Unit 4	1,137	2	-	-	171	1,310	1,310	-	-
	1f.2	Preparation of PSDAR and Licensing Documents - Unit 4	191	6	-	-	30	226	226	-	-
	1f.3	Engineering Activities in Preparation for Decommissioning - Unit 4	455	42	-	-	75	571	571	-	=
1f Total	Unit 4 F	Post Shutdown Planning & Engineering	1,783	50	-	-	275	2,108	2,108	-	-
	1g.1	Defuel Reactor Unit 4 (by Plant Operations)	-	-	-	-	-	-	-	-	-
	1g.2	Fuel Sampling & Inspections (by Plant Operations)	7 1 4 2	- 1 212	-	-	1 252		-	-	-
1g Total	1g.3	Spent Fuel Pool System Modifications - Unit 4 Shutdown Preparations & Deactivation	7,143 7,143	1,212 1,212		-	1,253 1,253	9,608 9,608	-	9,608 9,608	
1g Total	Offic 4 S	mutuowii Freparations & Deactivation	7,143	1,212	<u> </u>	<u> </u>	1,233	3,008		3,008	_
	1h.1	Provide Transfer Casks (supplied by DOE)	_	-	_	_	_	-	-	-	-
	1h.2	Procure Spent Fuel Loading & Transfer Equipment	_	1,463	-	-	219	1,683	-	1,683	-
	1h.3	Procedures & Dry Runs	335	-	-	168	75	578	-	578	-
	1h.4	Remove (352) Fuel Assemblies from Pool & Load DOE Casks	1,760	440	-	-	440	2,640	-	2,640	-
	1h.5	Dry, Close & Inspect (11) DOE supplied Casks	880	220	-	-	220	1,320	-	1,320	-
	1h.6	Load Out (11) Casks to DOE Transport	880	220	-	-	220	1,320	-	1,320	-
	1h.7	Spent Fuel Transportation & Disposal (by DOE)	-	-	-	-	-	-	-	-	<u>-</u>
1h Total	Unit 4 \	Wet Fuel Transfer to DOE prior to DECON	3,855	2,343	-	168	1,175	7,541	-	7,541	-
	1i.1	Provide Transfer Casks (19)	_	16,772	_	_	2,516	19,288	<u>-</u>	19,288	_
	1i.2	Procure Spent Fuel Loading & Transfer Equipment	_	-	-	_	-	-	_	-	_
	1i.3	Procedures & Dry Runs	335	_	-	168	75	578	-	578	-
	1i.4	Remove (592) Fuel Assemblies from Pool & Load Casks	3,040	760	-	-	760	4,560	-	4,560	-
	1i.5	Dry, Close & Inspect (19)	1,520	380	-	-	380	2,280		2,280	-
	1i.6	Load Out (19) Casks to Transport	1,520	380	-	-	380	2,280	-	2,280	-
	1i.7	Spent Fuel Transportation & Disposal (by DOE)	-		-	-	-	-	-	-	
1i Total	Unit 4 \	Net Fuel Transfer to ISFSI prior to DECON	6,415	18,292	-	168	4,111	28,986	-	28,986	-
	1j.1	Utility Staff	31,915	_	_	<u>-</u>	4,787	36,703	29,362	7,341	_
	1j.2	Security Guard Force	20,871		- -	- -	3,131			16,801	
	∸յ.∠	Security Saula Force	20,071				3,131	27,002	7,201	10,001	

Florida Power and Light

Turkey Point Unit 4

Scenario 1 - Prompt DECON both following Unit 4 Shutdown

				(4		,					
Period	Item Number	Item Description	Labor Cost	Materials & Equipment	Waste Transportation & Disposal	Other Direct Cost (ODC)	Contingency	Total Cost (Estimated)	License Termination	Spent Fuel Management	Site Restoration
	1j.3	General Contractor Staff	-	-	-	-	-	-	-	-	-
	1j.4	Property Taxes	-	-	-	54	8	62	49	12	-
	1j.5	Insurance	-	-	-	8,201	1,230	9,431	7,545	1,886	-
	1j.6	Corporate Support	3,236	-	-	-	485	3,721	1,116	2,605	-
	1j.7	Utility Staff HP Supplies	-	948	-	-	142	1,090	327	763	-
	1j.8	NRC Inspection Fee	-	-	-	2,224	334	2,558	2,558	-	-
	1j.9	Licensing Fees	-	-	-	688	103	791	791	-	-
	1j.10	Materials and Services	-	1,770	-	-	265	2,035	610	1,424	-
	1j.11	Energy	-	-	-	1,650	248	1,898	1,518	380	-
	1j.12	EPRI Membership Fees	-	-	-	-	-	-	-	_	-
	1j.13	NEI Membership Fees	-	-	-	-	-	-	-	-	-
	1j.14	County & FEMA Fees	-	-	-	2,262	339	2,601	2,081	520	-
	1j.15	Licenses & Permits	-	-	-	68	10	78	62	16	-
	1j.16	INPO Membership Fees	-	-	-	-	-	-	-	-	-
	1j.17	ISFSI Operating Costs	22	66	-	-	13	102	-	102	-
	1j.18	Spent Fuel Maintenance	1,305	145	-	-	217	1,667	-	1,667	-
1j Total	Undistr	ibuted Costs for Shutdown & Transition	57,349	2,929	-	15,147	11,314	86,738	53,221	33,517	-
Period 1 To	tal	SHUTDOWN & TRANSITION	76,545	24,826	-	15,482	18,128	134,981	55,329	79,652	-
Period 2 To	tal	SAFSTOR	-	-	-	-	-	-	-	-	-
	3a.1	Decommissioning Planning and Design - Unit 4	1,523	46	-	-	235	1,804	1,804	-	-
	3a.2	Site Characterization - Unit 4	1,953	53	-	105	317	2,429	2,429	-	-
	3a.3	Prepare Integrated Work Sequence and Schedule - Unit 4	164	5	-	-	25	195	195	-	-
	3a.4	Prepare Decommissioning Activity Specifications - Unit 4	2,181	67	-	-	337	2,586		-	-
	3a.5	Prepare License Termination Plan - Unit 4	984	-	-	667	248	1,899		-	-
	3a.6	Prepare Detailed Work Procedures for Decommissioning - Unit 4	1,917	59	-	-	296	2,273		-	-
	3a.7	Design Containment and Misc System Modifications - Unit 4	83	-	-	-	12	96	96	-	-
	3a.8	Purchase Dry Storage Modules for Unit 4 GTCC Waste	-	-	4,708	-	706	5,414		-	-
3a Total	Decom	missioning Planning	8,807	231	4,708	772	2,178	16,695	16,695	-	-
	3b.1	Mobilize Decommissioning General Contractor	-	-	-	1,693	254	1,947	1,947	-	-
	3b.2	Perform Asbestos Abatement of Pipe Insulation - Unit 4	3,465	182	-	-	912	4,559		-	-
	3b.3	Implement Cold and Dark & Install Temporary Power - Unit 4	4,669	1,568	-	-	936	7,172		-	-
	3b.4	Construct Misc Building Modifications, In-Plant Laydown Areas	2,996		-	-	526	4,030		-	-
	3b.5	Modify Containment Access - Unit 4	2,223	377	-	-	390	2,990		-	-
	3b.6	Transportation Infrastructure Modifications	62	298	-	1,393	263	2,015	2,015	-	-
	3b.7	Procure Waste Handling & Processing Tents	-		-	1,476	221	1,697	1,697	_	
3b Total	Decomr	missioning Transition and Preparations	13,414	2,933	-	4,562	3,501	24,411	24,411	-	-

Florida Power and Light

Turkey Point Unit 4

Scenario 1 - Prompt DECON both following Unit 4 Shutdown

			-	(111)	Jusanus on 2020 dona	13)					
Period	Item Number	Item Description	Labor Cost	Materials & Equipment	Waste Transportation & Disposal	Other Direct Cost (ODC)	Contingency	Total Cost (Estimated)	License Termination	Spent Fuel Management	Site Restoration
	3c.1	Design and Procure Special Equipment	-	27,050	-	-	5,410	32,460		-	-
	3c.2	Test Special Cutting and Handling Equipment and Train Operators	1,924	-	-	72	399	2,394	•	-	-
	3c.3	Finalize Internals and Vessel Segmentation Details - Unit 4	458	-	-	-	92	549	549	-	-
	3c.4	Segment, Package and Ship Reactor Internals - Unit 4	5,879	2,100	-	-	1,596	9,575		-	-
	3c.5	Segment, Package and Ship RPV - Unit 4	1,394	1,030	-	-	485	2,909	2,909	-	-
	3c.6	Package and Ship Reactor Pressure Vessel - Unit 4			16,724	-	3,345	20,069		-	-
3c Total	Reactor	Vessel Removal	9,654	30,180	16,724	72	11,326	67,956	67,956	-	-
	3d.1	Heavy Lift / Transfer Equipment		3,245	-	-	649	3,893	3,893	-	-
	3d.2	Remove and Dispose of Steam Generators - Unit 4	1,417	163	-	-	316	1,895		-	-
	3d.3	Remove and Dispose of Pressurizer - Unit 4	195	22	-	-	43	259	259	-	-
	3d.4	Remove and Dispose of Reactor Coolant Pipe - Unit 4	522	36	-	-	112	670	670	-	-
	3d.5	Remove and Dispose of Reactor Coolant Pumps - Unit 4	537	59	-	-	119	716	716	-	-
	3d.6	Package, Ship, & Dispose	-	-	11,062	-	2,212	13,274	13,274	-	-
3d Total	Large Co	omponent Removal	2,671	3,524	11,062	-	3,451	20,708	20,708	-	-
	3e.1	Remove and Dispose of Spent Fuel Storage Racks	68	20	-	-	18	106	106	-	-
	3e.2	Segment, Package and Dispose of Spent Fuel Pool Island Equipment	214	20	-	-	47	281	281	-	-
	3e.3	Decon/Surgical Removal Containment Building - Unit 4	1,095	130	-	-	245	1,470	1,470	-	-
	3e.4	Decon/Surgical Removal Fuel Building	553	21	-	-	115	688	688	-	-
	3e.5	Decon/Surgical Remvoal Auxiliary Building Unit 4	6,132	574	-	-	1,341	8,048	8,048	-	-
	3e.6	Decon/Surgical Radwaste Building	334	84	-	-	84	502	502	-	-
	3e.7	Package, Dispose, & Ship	-	-	3,880	-	776	4,656	4,656	-	-
3e Total	Plant Do	econtamination & Interior Rad Demolition	8,396	850	3,880	-	2,625	15,751	15,751	-	-
	26.4		257	530			450	053	052		
	3f.1	Demolish Fuel Building	257	538	-	-	159	953	953	-	-
	3f.2	Demolish Auxiliary Building	2,019	5,508	-	-	1,505	9,033	9,033	-	-
	3f.4	Demolish Radwaste Building Demolish	531	1,476	-	-	401	2,409		-	-
	3f.5	Unit 4 Containment Building Demolish	2,019	6,120	-	-	1,628	9,767		-	-
	3f.6	LLW Storage Building Contaminated	655	1,550	-	-	441	2,647	2,647	-	-
	3f.7	Soil	397	596	17,930	-	3,785	22,709		-	-
	3f.8	Debris Disposal	-	-	91,357	-	18,271	109,628	-	-	-
3f Total	Rad Bui	lding Demolition	5,878	15,789	109,287	-	26,191	157,145	157,145	-	-
	3g.1	Final Status Survey for Structures	5,897	67	_	227	1,238	7,428	7,428		
	3g.1 3g.2	Final Status Survey for Structures Final Status Survey for Land Areas (included with structures)	5,637				1,230	7,420	7,420	-	-
2a Total		Termination Activities	5,897	67	-	227	1,238	7,428	7,428	-	-
3g Total	License	Termination Activities	5,637	67	-	221	1,238	7,428	7,428	-	-
	3h.1	Utility Staff	29,716	-	-	-	4,457	34,174	34,174	-	-

Florida Power and Light

Turkey Point Unit 4

Scenario 1 - Prompt DECON both following Unit 4 Shutdown

				`		-					
Period	Item Number	Item Description	Labor Cost	Materials & Equipment	Waste Transportation & Disposal	Other Direct Cost (ODC)	Contingency	Total Cost (Estimated)	License Termination	Spent Fuel Management	Site Restoration
	3h.2	Security Guard Force	1,951	-	-	-	293	2,244	2,244	-	-
	3h.3	General Contractor Staff	67,660	-	-	-	10,149	77,809		-	-
	3h.4	Property Taxes	-	-	-	75	11	86	86	-	-
	3h.5	Insurance	-	-	-	5,428	814	6,242	6,242	-	-
	3h.6	Corporate Support	9,436	-	-	-	1,415	10,851	10,851	-	-
	3h.7	Utility Staff HP Supplies	-	5,925	-	-	889	6,814	6,814	-	-
	3h.8	NRC Inspection Fee	-	-	-	667	100	767	767	-	-
	3h.9	Licensing Fees	-	-	-	1,032	155	1,187	1,187	-	-
	3h.10	County & FEMA Fees	-	-	-	-	-	-	-	-	-
	3h.11	Licenses & Permits	-	-	-	95	14	109	109	-	-
	3h.12	Materials and Services	-	2,082	-	-	312	2,394	2,394	-	-
	3h.13	Energy	-	-	-	2,500	375	2,875	2,875	-	-
	3h.14	DGC HP Supplies	-	5,132	-	-	770	5,902	5,902	-	-
	3h.15	Florida LLRW Inspection Fee	-	-	-	2,945	442	3,387	3,387		
	3h.16	EPRI Membership Fees	-	-	-	-	-	-	-	-	-
	3h.17	NEI Membership Fees	-	-	-	-	-	-	-	-	-
	3h.18	INPO Membership Fees	-	-	-	-	-	-	-	-	-
3h Total	Undistr	ibuted Costs for Decommissioning & License Termination	108,764	13,139	-	12,742	20,197	154,842	154,842	-	-
Period 3 To	otal	DECOMMISSIONING & LICENSE TERMINATION	163,480	66,714	145,661	18,374	70,707	464,936	464,936	-	-
	4a.1	Demo Turbine Pedastal and Turbine Deck									
			3.647	1.506	_	<u>-</u>	773	5 927	_	<u>-</u>	5 927
	4a.2		3,647 2.854	1,506 1.830	-	- -	773 703	5,927 5,386	- -	-	5,927 5.386
	4a.2 4a.3	Demo Intake & CWS	2,854	1,830	- - -	- -	703	5,386	- - -	- - -	5,386
	4a.3	Demo Intake & CWS Demo Primary Water Tank Foundation	2,854 11	1,830 126	- - -	- - -	703 20	5,386 157	- - -	- - -	5,386 157
	4a.3 4a.4	Demo Intake & CWS Demo Primary Water Tank Foundation Demo Misc Site Structures	2,854 11 3,065	1,830 126 1,506	- - - -	- - - -	703 20 686	5,386 157 5,257	- - - -	- - - -	5,386 157 5,257
	4a.3 4a.4 4a.5	Demo Intake & CWS Demo Primary Water Tank Foundation Demo Misc Site Structures Demo Security Improvements	2,854 11 3,065 667	1,830 126 1,506 459	- - - -	-	703 20 686 169	5,386 157 5,257 1,295	- - - -	- - - -	5,386 157 5,257 1,295
	4a.3 4a.4 4a.5 4a.6	Demo Intake & CWS Demo Primary Water Tank Foundation Demo Misc Site Structures Demo Security Improvements Demo Maintenance Facility	2,854 11 3,065 667 937	1,830 126 1,506 459 753	- - - - -	-	703 20 686 169 254	5,386 157 5,257 1,295 1,944	- - - - -	- - - - -	5,386 157 5,257 1,295 1,944
	4a.3 4a.4 4a.5 4a.6 4a.7	Demo Intake & CWS Demo Primary Water Tank Foundation Demo Misc Site Structures Demo Security Improvements Demo Maintenance Facility Demo Control Building	2,854 11 3,065 667 937 145	1,830 126 1,506 459 753 251	- - - - - -	-	703 20 686 169 254 59	5,386 157 5,257 1,295 1,944 456	- - - -	- - - - -	5,386 157 5,257 1,295 1,944 456
	4a.3 4a.4 4a.5 4a.6 4a.7 4a.8	Demo Intake & CWS Demo Primary Water Tank Foundation Demo Misc Site Structures Demo Security Improvements Demo Maintenance Facility Demo Control Building Demo Sealwell	2,854 11 3,065 667 937	1,830 126 1,506 459 753	- - - - - -	- - - - -	703 20 686 169 254 59	5,386 157 5,257 1,295 1,944 456 418	- - - - -	- - - - - -	5,386 157 5,257 1,295 1,944 456 418
	4a.3 4a.4 4a.5 4a.6 4a.7 4a.8 4a.9	Demo Intake & CWS Demo Primary Water Tank Foundation Demo Misc Site Structures Demo Security Improvements Demo Maintenance Facility Demo Control Building Demo Sealwell Clean Concrete Processing	2,854 11 3,065 667 937 145 113	1,830 126 1,506 459 753 251 251	- - - - - - -	-	703 20 686 169 254 59 55 308	5,386 157 5,257 1,295 1,944 456 418 2,362	- - - - -	- - - - - -	5,386 157 5,257 1,295 1,944 456 418 2,362
	4a.3 4a.4 4a.5 4a.6 4a.7 4a.8 4a.9 4a.10	Demo Intake & CWS Demo Primary Water Tank Foundation Demo Misc Site Structures Demo Security Improvements Demo Maintenance Facility Demo Control Building Demo Sealwell Clean Concrete Processing Demo Site Paving	2,854 11 3,065 667 937 145 113	1,830 126 1,506 459 753 251	- - - - - - 114	- - - - -	703 20 686 169 254 59 55 308 168	5,386 157 5,257 1,295 1,944 456 418 2,362 1,285	- - - - -	- - - - - - -	5,386 157 5,257 1,295 1,944 456 418 2,362 1,285
4a Total	4a.3 4a.4 4a.5 4a.6 4a.7 4a.8 4a.9 4a.10 4a.11	Demo Intake & CWS Demo Primary Water Tank Foundation Demo Misc Site Structures Demo Security Improvements Demo Maintenance Facility Demo Control Building Demo Sealwell Clean Concrete Processing	2,854 11 3,065 667 937 145 113	1,830 126 1,506 459 753 251 251	- - - - - - - 114	- - - - - 2,054	703 20 686 169 254 59 55 308	5,386 157 5,257 1,295 1,944 456 418 2,362	- - - - - - -	- - - - - - - -	5,386 157 5,257 1,295 1,944 456 418 2,362
4a Total	4a.3 4a.4 4a.5 4a.6 4a.7 4a.8 4a.9 4a.10 4a.11	Demo Intake & CWS Demo Primary Water Tank Foundation Demo Misc Site Structures Demo Security Improvements Demo Maintenance Facility Demo Control Building Demo Sealwell Clean Concrete Processing Demo Site Paving Clean Debris Disposal/Recycle	2,854 11 3,065 667 937 145 113 - 447 -	1,830 126 1,506 459 753 251 251 - 670 - 7,352		- - - - - 2,054 - - - 2,054	703 20 686 169 254 59 55 308 168 17	5,386 157 5,257 1,295 1,944 456 418 2,362 1,285 131 24,618	- - - - - - -	- - - - - - - -	5,386 157 5,257 1,295 1,944 456 418 2,362 1,285 131 24,618
4a Total	4a.3 4a.4 4a.5 4a.6 4a.7 4a.8 4a.9 4a.10 4a.11 Clean B	Demo Intake & CWS Demo Primary Water Tank Foundation Demo Misc Site Structures Demo Security Improvements Demo Maintenance Facility Demo Control Building Demo Sealwell Clean Concrete Processing Demo Site Paving Clean Debris Disposal/Recycle suilding & Site Demolition	2,854 11 3,065 667 937 145 113 - 447 -	1,830 126 1,506 459 753 251 251 - 670 - 7,352		- - - - 2,054 - - 2,054	703 20 686 169 254 59 55 308 168 17 3,211	5,386 157 5,257 1,295 1,944 456 418 2,362 1,285 131 24,618	- - - - - - -	- - - - - - - -	5,386 157 5,257 1,295 1,944 456 418 2,362 1,285 131 24,618
	4a.3 4a.4 4a.5 4a.6 4a.7 4a.8 4a.9 4a.10 4a.11 Clean B	Demo Intake & CWS Demo Primary Water Tank Foundation Demo Misc Site Structures Demo Security Improvements Demo Maintenance Facility Demo Control Building Demo Sealwell Clean Concrete Processing Demo Site Paving Clean Debris Disposal/Recycle suilding & Site Demolition Procure Site Restoration Equipment Finish Grading and Re-Vegetate Site	2,854 11 3,065 667 937 145 113 - 447 - 11,886	1,830 126 1,506 459 753 251 251 - 670 - 7,352 490 26	114 - -	- - - - 2,054 - - 2,054	703 20 686 169 254 59 55 308 168 17 3,211	5,386 157 5,257 1,295 1,944 456 418 2,362 1,285 131 24,618	- - - - - - - - -	- -	5,386 157 5,257 1,295 1,944 456 418 2,362 1,285 131 24,618
4a Total 4b Total	4a.3 4a.4 4a.5 4a.6 4a.7 4a.8 4a.9 4a.10 4a.11 Clean B	Demo Intake & CWS Demo Primary Water Tank Foundation Demo Misc Site Structures Demo Security Improvements Demo Maintenance Facility Demo Control Building Demo Sealwell Clean Concrete Processing Demo Site Paving Clean Debris Disposal/Recycle suilding & Site Demolition	2,854 11 3,065 667 937 145 113 - 447 -	1,830 126 1,506 459 753 251 251 - 670 - 7,352 490 26		- - - - 2,054 - - 2,054	703 20 686 169 254 59 55 308 168 17 3,211	5,386 157 5,257 1,295 1,944 456 418 2,362 1,285 131 24,618	- - - - - - - - -	- - - - - - - - - -	5,386 157 5,257 1,295 1,944 456 418 2,362 1,285 131 24,618
	4a.3 4a.4 4a.5 4a.6 4a.7 4a.8 4a.9 4a.10 4a.11 Clean B	Demo Intake & CWS Demo Primary Water Tank Foundation Demo Misc Site Structures Demo Security Improvements Demo Maintenance Facility Demo Control Building Demo Sealwell Clean Concrete Processing Demo Site Paving Clean Debris Disposal/Recycle suilding & Site Demolition Procure Site Restoration Equipment Finish Grading and Re-Vegetate Site	2,854 11 3,065 667 937 145 113 - 447 - 11,886	1,830 126 1,506 459 753 251 251 - 670 - 7,352 490 26	114 - -	- - - - 2,054 - - 2,054	703 20 686 169 254 59 55 308 168 17 3,211	5,386 157 5,257 1,295 1,944 456 418 2,362 1,285 131 24,618	- - - - - - - - -	- -	5,386 157 5,257 1,295 1,944 456 418 2,362 1,285

Florida Power and Light

Turkey Point Unit 4

Scenario 1 - Prompt DECON both following Unit 4 Shutdown

Period	Item Number	Item Description	Labor Cost	Materials & Equipment	Waste Transportation & Disposal	Other Direct Cost (ODC)	Contingency	Total Cost (Estimated)	License Termination	Spent Fuel Management	Site Restoration
	4c.3	General Contractor Staff	5,093	-	-	-	764	5,857	-	-	5,857
	4c.4	Property Taxes	-	-	-	6	1	6	-	-	(
	4c.5	Insurance	-	-	-	409	61	470	-	-	470
	4c.6	Corporate Support	710	-	-	-	107	817	-	-	817
	4c.7	Energy	-	-	-	188	28	216	-	-	216
	4c.8	Materials and Services	-	116	-	-	17	134	-	-	134
	4c.9	County & FEMA Fees	-	-	-	-	-	-	-	-	-
	4c.10	Licenses & Permits	-	<u>-</u>	<u>-</u>	7	1	8	-	-	{
4c Total	Undistr	ibuted Costs for Site Restoration	8,187	116	-	609	1,337	10,249	-	-	10,249
Period 4 To	tal	SITE RESTORATION	20,550	7,985	114	2,664	4,697	36,009	-	-	36,009
	Fo. 1	Dragues Loading & Transfer Fautinment (included in Daried 1)									
	5a.1 5a.2	Procure Loading & Transfer Equipment (included in Period 1) Procedures & Dry Runs (included in Period 1)	-	-	-	-	-	-	-	-	-
	5a.2 5a.3	Remove (47) Fuel Casks from ISFSI & Load DOE Transport	3,760	940	_	- -	705	- 5,405	_	5,405	_
	5a.3 5a.4	Spent Fuel Transportation & Disposal (by DOE)	3,700	-	_	- -	703	3,403	_	3,403	_
5a Total		el Transfer to DOE during and after DECON	3,760	940	-	-	705	5,405	-	5,405	
Ju Total	Diyiuc	Transier to bot during and area become	3,700	340			703	3,403		3,403	
	5b.1	Remove GTCC Casks from ISFSI & Loadout	320	-	-	80	120	520	520) -	-
	5b.2	GTCC Transportation & Disposal	-	-	11,746	-	1,762	13,508			-
5b Total	GTCC W	/aste Disposition	320	-	11,746	80	1,882	14,028	14,028		-
	5c.1	Utility Staff	5,897	-	-	-	885	6,781	-	6,781	-
	5c.2	Security Guard Force	22,749	-	-	-	3,412	26,162	-	26,162	-
	5c.3	General Contractor Staff	-	-	-	-	-	-	-	-	-
	5c.4	Property Taxes	-	-	-	148	22	170	-	170	
	5c.5	Insurance	-	-	-	6,918	1,038	7,956	-	7,956	-
	5c.6	Corporate Support	-	-	-	-	-	-	-	-	-
	5c.7	Utility Staff HP Supplies	-	-	-	-	-	-	-	-	-
	5c.8	NRC Inspection Fee	-	-	-	1,112	167	1,279		_,	
	5c.9	Licensing Fees	-	-	-	1,720	258	1,978	-	1,978	-
	5c.10	County & FEMA Fees	-	-	-	-	-	-	-	-	-
	5c.11	Licenses & Permits	=	-	-	169	25	195	-	195	-
	5c.12	Energy	-	-	-	-	-	-	_	-	-
	5c.13	Materials and Services	-	490	-	1 015	74	564	_	564	
5c Total	5c.14 Undistr	ISFSI Operating Costs ibuted Costs for Dry Fuel / GTCC Storage & Transfer	28,646	490	-	1,915 11,983	287 6,168	2,203 47,287	-	2,203 47,287	
			20,040	750		11,503	0,100	41,201		77,207	
Period 5 To	tal	DRY FUEL / GTCC STORAGE & TRANSFER	32,726	1,430	11,746	12,063	8,755	66,720	14,028	52,692	

Florida Power and Light

Turkey Point Unit 4

Scenario 1 - Prompt DECON both following Unit 4 Shutdown

Period	Item Number	Item Description	Labor Cost	Materials & Equipment	Waste Transportation & Disposal	Other Direct Cost (ODC)	Contingency	Total Cost (Estimated)	License Termination	Spent Fuel Management	Site Restoration
		Preparation and NRC Review of License Termination Plan	45	-	-	64	16	125			
6a Total	ISFSI D8	&D Planning & Preparations	45	-	-	64	16	125	-	125	-
	6b.1	Clean Demolition of ISFSI	1,316	638	-	-	293	2,248	_	2,248	_
	6b.2	Demolition of ISFSI Support Structures	240	94		-	50	384	-	384	-
6b Total	ISFSI an	d Support Structure Clean Demolition	1,556	732		-	343	2,632	-	2,632	-
	6c.1	Verification Surveys	81	22	-	-	15	119	-	119	
	6c.2	Preparation of Final Report on Decommissioning and NRC Review	45	-	-	-	7	52	-	52	
6c Total	ISFSI Fir	nal Status Surveys	126	22	-	-	22	170	-	170	-
	6d.1	Utility Staff	304	-	-	-	46	350	-	350	-
	6d.2	Security Guard Force	153	-	-	-	23	176	-	176	-
	6d.3	General Contractor Staff	1,999	-	-	-	300	2,299	-	2,299	-
	6d.4	Property Taxes	, -	-	-	13	2	15		15	-
	6d.5	Insurance	-	-	-	25	4	29	-	29	-
	6d.6	Corporate Support	-	-	-	-	-	-	-	-	-
	6d.7	Utility Staff HP Supplies	-	-	-	-	_	-	-	-	-
	6d.8	Materials and Services	-	23	-	-	3	26	-	26	-
	6d.9	Energy	-	-	-	35	5	41	-	41	-
	6d.10	NRC Inspection Fee	-	-	-	-	-	-	-	-	-
	6d.11	Licensing Fees	-	-	-	-	-	-	-	-	-
	6d.12	County & FEMA Fees	-	-	-	-	-	-	-	-	-
	6d.13	Licenses & Permits	-	-	-	34	5	39	-	39	
6d Total	Undistr	ibuted Costs for ISFSI Decommissioning	2,456	23	-	108	388	2,974	-	2,974	-
Period 6 Tot	al	ISFSI DECOMMISSIONING	4,183	777	-	172	770	5,901	-	5,901	-
CDAND TO				404 500		40.771	400.075	700	F04 222	400.517	26.22
GRAND TO	IAL		297,484	101,732	157,521	48,754	103,056	708,547	534,293	138,245	36,009

Florida Power and Light Turkey Point Unit 3 Scenario 2 - SAFSTOR

			(thousands of 2020 dollars)								
Period	Item Number	Item Description	Labor Cost	Materials & Equipment	Waste Transportation & Disposal	Other Direct Cost (ODC)	Contingency	Total Cost (Estimated)	License Termination	Spent Fuel Management	Site Restoration
1a Total	Plannin	ng Prior to Shutdown (by Plant Operations)	-	-	-	-	-	-	-	-	-
	1b.1	Admin Activities in Preparation for Decommissioning - Unit 3	2,102	82	_	_	328	2,511	2,511	_	_
	1b.2	Prepare PSDAR and License Documents - Unit 3	444	14		_	69	527	*	_	_
	1b.2 1b.3	Engineering Activities in Preparation for Decommissioning - Unit 3	1,064	52		26	171	1,314		_	_
1b Total		Post Shutdown Planning & Engineering	3,610	148		26		4,352		<u> </u>	<u> </u>
ID TOTAL	Onicsr	ost Shutuown Flamming & Engineering	3,010	140	<u>-</u>	20	308	7,332	7,332	<u>-</u>	
	1c.1	Defuel Reactor Unit 3 (by Plant Operations)	-	-	-	-	-	-	-	-	-
	1c.2	Fuel Sampling & Inspections (by Plant Operations)	-	-	-	-	-	-	-	-	-
	1c.3	Spent Fuel Pool System Modifications - Unit 3	11,345	1,212	-	-	1,884	14,441	-	14,441	-
	1c.4	Implement Cold & Dark - Unit 3	3,508	630	-	-	621	4,759	4,759	-	-
	1c.5	Perform Pre-SAFSTOR Baseline Radiation Survey - Unit 3	445	-	-	-	67	512	230	281	-
1c Total	Unit 3 F	Post Shutdown Deactivation & Modifications	15,298	1,842	-	-	2,571	19,711	4,989	14,722	-
	1d.1	Provide Transfer Casks (supplied by DOE)	-	-	-	-	-	-	-	-	-
	1d.2	Procure Spent Fuel Loading & Transfer Equipment	-	2,184		-	328	2,512	-	2,512	-
	1d.3	Procedures & Dry Runs	500	-	-	250	113	863	-	863	-
	1d.4	Remove (448) Fuel Assemblies from Pool & Load DOE Casks	2,240	560	-	-	560	3,360	-	3,360	-
	1d.5	Dry, Close & Inspect (14) DOE supplied Casks	1,120	280	-	-	280	1,680	-	1,680	-
	1d.6	Load Out (14) Casks to DOE Transport	1,120	280	-	-	280	1,680		1,680	-
	1d.7	Spent Fuel Transportation & Disposal (by DOE)	-	-	-	-	-	-	-	-	-
1d Total	Unit 3 V	Vet Fuel Transfer to DOE prior to SAFSTOR	4,980	3,304	-	250	1,560	10,094	-	10,094	-
	1e.1	Purchase Transfer Casks	-	13,241		-	1,986	15,227	-	15,227	-
	1e.2	Procure Spent Fuel Loading & Transfer Equipment	-	-	-	-	-	-	-	-	-
	1e.3	Procedures & Dry Runs	500	-	-	250	113	863	-	863	-
	1e.4	Remove (464) Fuel Assemblies from Pool & Load DOE Casks	2,400	600	-	-	600	3,600	-	3,600	-
	1e.5	Dry, Close & Inspect (15) DOE supplied Casks	1,200	300	-	-	300	1,800	-	1,800	-
	1e.6	Load Out (15) Casks to DOE Transport	1,200	300	-	-	300	1,800	-	1,800	-
1e Total	Unit 3 V	Vet Fuel Transfer to ISFSI prior to Shutdown	5,300	14,441		250	3,299	23,290	-	23,290	-
1f Total	Unit 4 P	ost Shutdown Planning & Engineering	-	-	-	-	-	-	-	-	-
1g Total	Unit 4 S	hutdown Preparations & Deactivation	-	-	-	-	-	-	-	-	-
1h Total	Unit 4 W	Vet Fuel Transfer to DOE prior to DECON	-	-	-	-	-	_	-	-	_
		·									

Florida Power and Light Turkey Point Unit 3 Scenario 2 - SAFSTOR

	· · · · · ·			(tho	usands of 2020 do	liars)					
Period	Item Number	Item Description	Labor Cost	Materials & Equipment	Waste Transportation & Disposal	Other Direct Cost (ODC)	Contingency	Total Cost (Estimated)	License Termination	Spent Fuel Management	Site Restoration
1i Total	Unit 4 V	Vet Fuel Transfer to ISFSI prior to SAFSTOR	-	-	-	-	-	-	-	-	-
	1j.1	Utility Staff	44,454	-	-	-	6,668	51,122		10,224	-
	1j.2	Security Guard Force	21,113	-	-	-	3,167	24,280	7,284	16,996	-
	1j.3	General Contractor Staff	-	-	-	-	-	-	-	-	-
	1j.4	Property Taxes	-	-	-	67	10	77	62	15	-
	1j.5	Insurance	-	-	-	10,251	1,538	11,788		2,358	-
	1j.6	Corporate Support	2,933	-	-	-	440	3,373		2,361	-
	1j.7	Utility Staff HP Supplies	-	1,077	-	-	162	1,238		867	-
	1j.8	NRC Inspection Fee	-	-	-	2,780	417	3,197	3,197	-	-
	1j.9	Licensing Fees	-	-	-	860	129	989	989	-	-
	1j.10	Materials and Services	-	2,020	-	-	303	2,323		1,626	-
	1j.11	Energy	-	-	-	1,069	160	1,229	983	246	-
	1j.12	EPRI Membership Fees	-	-	-	-	-	-	-	-	-
	1j.13	NEI Membership Fees	-	-	-	-	-	-	-	-	-
	1j.14	County Fees & FEMA Fees	-	-	-	2,828	424	3,252	2,601	650	-
	1j.15	Licenses & Permits	-	-	-	85	13	97	78	19	-
	1j.16	INPO Membership Fees	-	-	-	-	-	-	-	-	-
	1j.17	ISFSI Operating Costs	20	60	-	-	12	92	-	92	-
	1j.18	Spent Fuel Maintenance	985	328	-	-	197	1,510	-	1,510	_
1j Total	Undistr	ibuted Costs for Shutdown & Transition	69,504	3,485	-	17,939	13,639	104,568	67,603	36,965	-
Dania d 1	T-4-1	CHUITDOWN C TRANSITION	00.503	22 224		40.465	24 627	462.045	76.044	05 074	
Period 1	iotai	SHUTDOWN & TRANSITION	98,692	23,221	. -	18,465	21,637	162,015	76,944	85,071	-
	20.1	Heilieu Ceaff	7 222				722	9.055	2 625	4.420	
	2a.1	Utility Staff	7,323	-	-	-	732	8,055		4,430	-
	2a.2 2a.3	Security Guard Force	3,441	-	-	-	344	3,785	-	3,785	-
		General Contractor Staff	-	-	-	- 220	22	251	112	120	-
	2a.4 2a.5	Property Taxes Insurance	-	-	-	228 16 537	23 1,654	251 18,190		138 10,005	-
	2a.5 2a.6	Corporate Support	- 17,506	-	-	16,537	1,054	18,190 19,257		10,005	-
	2a.6 2a.7	Utility Staff HP Supplies	17,500	- 2,805		-	281	3,086		1,697	-
	2a.7 2a.8		-	2,603		1,890	189	2,079	*	1,097 1,144	-
		NRC Inspection Fee	-	-	-		439	3,363			-
	2a.9 2a.10	Licensing Fees County Fees & FEMA Fees	-	-	-	2,924 -	439	3,303	1,513 -	1,849	-
		County Fees & FEMA Fees Licenses & Permits	-	-		288	- 29	317		- 174	-
	2a.11		-	-	-	288	29	31/	143	1/4	-
	2a.12 2a.13	EPRI Membership Fees NEI Fees	-	-	-	-	-	-	_	-	-
			-	-	-	-	-	-	_	-	-
	2a.14	INPO Membership Fees	-	-	-	-	-	-	-	-	-

Florida Power and Light Turkey Point Unit 3 Scenario 2 - SAFSTOR

Period			(thousands of 2020 dollars) Waste								
N	Item Iumber	Item Description	Labor Cost	Materials & Equipment	Waste Transportation & Disposal	Other Direct Cost (ODC)	Contingency	Total Cost (Estimated)	License Termination	Spent Fuel Management	Site Restoration
7	2a.15	Materials and Services	-	6,413	-	-	641	7,054	3,174	3,880	-
Ĩ.	2a.16	Energy	-	-	-	2,765	277	3,042	1,369	1,673	-
	2a.17	Roof Replacement	-	_	-		-	-	-	-	-
2a Total [Dorman	cy during Dry Fuel Storage	28,270	9,218	-	24,632	6,358	68,479	29,112	39,366	-
	2b.1	Utility Staff	13,019	-	-	-	1,302	14,320	14,320	-	-
	2b.2	Security Guard Force	6,363	-	-	-	636	6,999	6,999	-	-
	2b.3	General Contractor Staff	-	-	-	-	-	-	-	-	-
	2b.4	Property Taxes	-	-	-	429	43	472	472	-	-
	2b.5	Insurance	-	-	-	18,526	1,853	20,378	20,378	-	-
	2b.6	Corporate Support	8,728	-	-	-	873	9,601	9,601	-	-
	2b.7	Utility Staff HP Supplies	-	1,141	-	-	114	1,255	1,255	-	-
	2b.8	NRC Inspection Fee	-	-	-	3,558	356	3,914	3,914	-	-
	2b.9	Licensing Fees	-	-	-	5,504	550	6,054	6,054	-	-
2	2b.10	County Fees & FEMA Fees	-	-	-	-	-	-	-	-	-
2	2b.11	Licenses & Permits	-	-	-	543	54	597	597	-	-
2	2b.12	EPRI Membership Fees	-	-	-	-	-	-	-	-	-
2	2b.13	NEI Fees	-	-	-	-	-	-	-	-	-
2	2b.14	INPO Membership Fees	-	-	-	-	-	-	-	-	-
2	2b.15	Materials and Services	-	3,632	-	-	363	3,995	3,995	-	-
2	2b.16	Energy	-	-	-	1,165	117	1,282	1,282	-	-
2	2b.17	Roof Replacement	-	-	-	-	-	-	-	-	-
2b Total	Dorman	cy Only	28,109	4,773	-	29,725	6,261	68,869	68,869	-	-
Period 2 To	otal S	SAFSTOR	56,379	13,991	-	54,358	12,619	137,347	97,981	39,366	-
	3a.1	Decommissioning Planning and Design - Unit 3	1,523	46	_	_	235	1,804	1,804	_	_
	3a.2	Prepare Integrated Work Sequence and Schedule - Unit 3	164	5		_	255	1,804		_	_
	3a.3	Site Characterization - Unit 3	1,953	53		105	317	2,429	2,429	_	_
	3a.4	Prepare Decommissioning Activity Specifications - Unit 3	5,359	166		103	829	6,354	6,354	-	_
	3a.5	Prepare Detailed Work Procedures - Unit 3	4,344	134		_	672	5,150		-	_
	3a.6	Prepare License Termination Plan - Unit 3	1,004		·	667	251	1,921	1,921	-	-
	3a.7	Design Containment and Misc System Modifications - Unit 3	195	_	-	-	231	224	224	-	-
	3a.7	Purchase Dry Storage Modules for Unit 3 GTCC Waste	193	-	4,708	-	706	5,414	5,414	-	-
		nissioning Planning	14,542	404		772	3,064	23,490		-	<u> </u>
Sa rotai L			17,372	707	7,700	112	3,004	23,430	23,430		
	3b.1	Mobilize Decommissioning General Contractor	_	_	_	1,693	254	1,947	1,947	_	_
	3b.2	Perform Asbestos Abatement of Pipe Insulation - Unit 3	3,465	182	_	_,055	912	4,559		_	_

Florida Power and Light Turkey Point Unit 3 Scenario 2 - SAFSTOR

			(thousands of 2020 dollars)								
Period	Item Number	Item Description	Labor Cost	Materials & Equipment	Waste Transportation & Disposal	Other Direct Cost (ODC)	Contingency	Total Cost (Estimated)	License Termination	Spent Fuel Management	Site Restoration
	3b.3	Implement Temporary Power Upgrades - Unit 3	1,033	937	-	-	296	2,266	2,266	-	-
	3b.4	Construct Misc Building Modifications, In-Plant Laydown Areas	2,996	508	-	-	526	4,030	4,030	-	-
	3b.5	Modify Containment Access - Unit 3	2,223	377	-	-	390	2,990	2,990	-	-
	3b.6	Transportation Infrastructure Modifications	93	447	-	2,089	394	3,023	3,023	-	-
	3b.7	Procure Waste Handling & Processing Tents	-	-	-	1,739	261	2,000	2,000	-	-
3b Total	Decomr	missioning Transition and Preparations	9,809	2,452	-	5,521	3,032	20,814	20,814	-	-
	3c.1	Design and Procure Special Equipment	-	29,000	-	-	5,800	34,800	34,800	-	
	3c.2	Test Special Cutting and Handling Equipment and Train Operators	2,263	-	-	72	467	2,802	2,802	-	-
	3c.3	Finalize Internals and Vessel Segmentation Details - Unit 3	538	-	-	-	108	646	646	-	
	3c.4	Segment, Package and Ship Reactor Internals - Unit 3	5,879	2,100	-	-	1,596	9,575	9,575	-	
	3c.5	Segment, Package and Ship RPV - Unit 3	1,394	1,030	-	-	485	2,909	2,909	-	
	3c.6	Package, Ship & Dispose	-	-	10,753	-	2,151	12,904	12,904	-	
3c Total	Reactor	Vessel Removal	10,074	32,130	10,753	72	10,606	63,635	63,635	-	
	3d.1	Heavy Lift / Transfer Equipment		3,245	-	-	649	3,893	3,893	-	-
	3d.2	Remove and Dispose of Steam Generators - Unit 3	1,417	163	-	-	316	1,895	1,895	-	
	3d.3	Remove and Dispose of Pressurizer - Unit 3	195	22	-	-	43	259	259	-	
	3d.4	Remove and Dispose of Reactor Coolant Pipe - Unit 3	522	36	-	-	112	670	670	-	
	3d.5	Remove and Dispose of Reactor Coolant Pumps - Unit 3	537	59	-	-	119	716	716	-	
	3d.6	Package, Ship, & Dispose	-	-	10,447	-	2,089	12,536	12,536	-	
3d Total	Large Co	omponent Removal	2,671	3,524	10,447	-	3,328	19,970	19,970	-	
	3e.1	Remove and Dispose of Spent Fuel Storage Racks	68	20	-	-	18	106		-	
	3e.2	Segment, Package and Dispose of Spent Fuel Pool Island Equipment	214	20	-	-	47	281	281	-	
	3e.3	Decon/Surgical Removal Containment Building - Unit 3	1,095	130		-	245	1,470	*	-	
	3e.4	Decon/Surgical Removal Fuel Building	553	21	-	-	115	688	688	-	
	3e.5	Decon/Surgical Remvoal Auxiliary Building (with Unit 4)	-	-	-	-	-	-	-	-	
	3e.6	Package, Ship, and Dispose	-	-	4,770	-	954	5,724		-	
3e Total	Plant De	econtamination & Interior Rad Demolition	1,930	191	4,770	-	1,378	8,270	8,270	-	
	3f.1	Demolish Fuel Building	257	538	-	-	159	953	953	-	-
	3f.2	Demolish Auxiliary Building (with Unit 4)	-	-	-	-	-	-	-	-	-
	3f.3	Demolish Unit 3 Containment Building	2,019	6,120		-	1,628	9,767		-	
	3f.4	Contaminated Soil	397	596		-	3,443	20,660		-	
	3f.5	Debris Disposal	-		45,615		9,123	54,738		-	
3f Total	D . I D .	lding Demolition	2,673	7,254	61,837	_	14,353	86,117	86,117	-	

Florida Power and Light Turkey Point Unit 3 Scenario 2 - SAFSTOR

				(00	Waste						
Period	Item	Item Description	Labor	Materials &	Transportation &	Other Direct	Contingency	Total Cost	License	Spent Fuel	Site
	Number		Cost	Equipment	Disposal	Cost (ODC)		(Estimated)	Termination	Management	Restoration
	3g.1	Final Status Survey for Structures	5,868	55	-	227	1,230	7,379	7,379	-	-
	3g.2	Final Status Survey for Land Areas (included with structures)	-	-	-	-	-	_	-	-	-
3g Total	License	Termination Activities	5,868	55	-	227	1,230	7,379	7,379	-	-
	3h.1	Utility Staff	29,716	-	-	-	4,457	34,174	34,174	-	-
	3h.2	Security Guard Force	1,951	-	-	-	293	2,244	2,244	-	-
	3h.3	General Contractor Staff	67,660	-	-	-	10,149	77,809	77,809	-	-
	3h.4	Property Taxes	-	-	-	87	13	100	100	-	-
	3h.5	Insurance	-	-	-	3,769	565	4,334	4,334	-	-
	3h.6	Corporate Support	12,917	-	-	-	1,938	14,855	14,855	-	-
	3h.7	Utility Staff HP Supplies	-	4,616	-	-	692	5,308	5,308	-	-
	3h.8	NRC Inspection Fee	-	-	-	778	117	895	895	-	-
	3h.9	Licensing Fees	-	-	-	1,204	181	1,385	1,385	-	-
	3h.10	County Fees & FEMA Fees	-	-	-	-	-	- '	-	-	-
	3h.11	Licenses & Permits	-	-	-	110	17	127	127	-	-
	3h.12	Florida LLRW Inspection Fee	-	-	-	1,742	261	2,003	2,003	-	-
	3h.13	Materials and Services	-	1,385	-	-	208	1,592	1,592	-	-
	3h.14	Energy	-	-	-	3,287	493	3,780	3,780	-	-
	3h.15	DGC HP Supplies	-	5,132	-	-	770	5,902	5,902	-	-
	3h.16	EPRI Membership Fees	-	-	-	-	-	- '	-	-	-
	3h.17	NEI Membership Fees	-	-	-	-	-	- '	-	-	-
	3h.18	INPO Membership Fees	-	-	-	-	-	_	-	-	-
3h Total	Undistri	ibuted Costs for Decommissioning & License Termination	112,245	11,132	-	10,978	20,153	154,509	154,509	-	-
Period 3	Total	DECOMMISSIONING & LICENSE TERMINATION	159,812	57,143	92,515	17,570	57,144	384,184	384,184		
Periou 3	TOtal	DECOMMISSIONING & LICENSE TERMINATION	159,612	57,145	92,515	17,570	57,144	304,104	304,104	-	-
	4a.1	Demo Turbine Pedastal and Turbine Deck	3,647	1,506	_	_	773	5,927	_	_	5,927
	4a.2	Demo Sealwell	113	251	_	-	55			_	418
	4a.3	Demo Tank Foundations	11	251	_	-	39			_	302
	4a.4	Demo Misc Site Structures	206	1,255		-	219			_	1,680
	4a.5	Security Improvements	667	502		-	175	1,344		_	1,344
	4a.6	Clean Concrete Processing	-	-	-	1,306				_	1,502
	4a.7	Demo Site Paving	220	330		-	83	633		_	633
	4a.8	Clean Debris Disposal/Recycle	-	-	100	-	15			-	115
4a Total		uilding & Site Demolition	4,864	4,096		1,306				_	11,920
		· ·	,	, = = =		,	,				,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,
	4b.1	Procure Site Restoration Equipment	-	735	-	-	110	846	-	-	846

Florida Power and Light Turkey Point Unit 3 Scenario 2 - SAFSTOR

	(thousands of 2020 dollars)											
Period	Item Number	Item Description	Labor Cost	Materials & Equipment	Waste Transportation & Disposal	Other Direct Cost (ODC)	Contingency	Total Cost (Estimated)	License Termination	Spent Fuel Management	Site Restoration	
4b Total	Site Res	storation	715	735	-	-	218	1,668	-	-	1,668	
	4c.1	Utility Staff	2,237	-	-	-	336	2,572	-	-	2,572	
	4c.2	Security Guard Force	147	-	-	-	22	169	-	-	169	
	4c.3	General Contractor Staff	5,093	-	-		764	5,857	-	-	5,857	
	4c.4	Property Taxes	-	-	-	7	1	8	-	-	8	
	4c.5	Insurance	-	-	-	284	43	326	-	-	326	
	4c.6	Corporate Support	972	-	-	-	146	1,118	-	-	1,118	
	4c.7	Energy	-	-	-	247	37	285	-	-	285	
	4c.8	Materials and Services	-	84	-	-	13	97	-	-	97	
	4c.9	County Fees & FEMA Fees	-	-	-	-	-	- 10	-	-	-	
4e Total	4c.10	Licenses & Permits	- 0.440	-	<u>-</u>	8	1 262	10 440		-	10 440	
4c Total	Undistr	ibuted Costs for Site Restoration	8,449	84	-	546	1,362	10,440	-	-	10,440	
Period 4	Total	SITE RESTORATION	14,027	4,915	100	1,852	3,134	24,029	-	-	24,029	
				.,0 = 0			3,23 .	,0_0			,e_e	
	5a.1	Procure Loading & Transfer Equipment (included in Period 1)	-	_	_	-	-	_	_	-	_	
	5a.2	Procedures & Dry Runs (included in Period 1)	-	-	-	_	-	_	-	-	-	
	5a.3	Remove (43) Fuel Casks from ISFSI & Load DOE Transport	3,440	860	-	-	645	4,945	-	4,945	-	
	5a.4	Spent Fuel Transportation & Disposal (by DOE)	-	-	-	_	-	-	-	-	-	
5a Total	Dry Fue	el Transfer to DOE during and after DECON	3,440	860	-	-	645	4,945	-	4,945	-	
	5b.1	Remove GTCC Casks from ISFSI & Loadout	320	-	-	80	120	520	520	-	-	
	5b.2	GTCC Transportation & Disposal	-	-	11,746	-	1,762	13,508	13,508	-	-	
5b Total	GTCC W	Vaste Disposition	320	-	11,746	80	1,882	14,028	14,028	-	-	
	5c.1	Utility Staff	5,897	-	-	-	885	6,781	-	6,781	-	
	5c.2	Security Guard Force	22,749	-	-	-	3,412	26,162	-	26,162	-	
	5c.3	General Contractor Staff	-	-	-	-	-	-	-	-	-	
	5c.4	Property Taxes	-	-	-	-	-	-	-	-	-	
	5c.5	Insurance	-	-	-	-	-	-	-	-	-	
	5c.6	Corporate Support	-	-	-	-	-	-	-	-	-	
	5c.7	Utility Staff HP Supplies	-	-	-	-	-	-	-	-	-	
	5c.8	NRC Inspection Fee	-	-	-	-	-	-	-	-	-	
	5c.9	Licensing Fees	-	-	-	-	-	-	-	-	-	
	5c.10 5c.11	County Fees & FEMA Fees	-	-	-	-	-	-	-	-	-	
	5c.11	Licenses & Permits	-	-	-	-	-	-	-	-	-	
I	JC.12	Energy	-	-	-	-	-	-	-	-	-	

Florida Power and Light Turkey Point Unit 3 Scenario 2 - SAFSTOR

	(triousarius or 2020 dollars)										
Period	Item Number	Item Description	Labor Cost	Materials & Equipment	Waste Transportation & Disposal	Other Direct Cost (ODC)	Contingency	Total Cost (Estimated)	License Termination	Spent Fuel Management	Site Restoration
	5c.13	Materials and Services	-	-	-	-	-	-	-	-	-
	5c.14	ISFSI Operating Costs	-	-	-	2,086	313	2,399	-	2,399	-
5c Total	Undistr	ributed Costs for Dry Fuel / GTCC Storage & Transfer	28,646	-	-	2,086	4,610	35,342	-	35,342	-
_											
Period 5	Total	DRY FUEL / GTCC STORAGE & TRANSFER	32,406	860	11,746	2,166	7,137	54,315	14,028	40,287	-
	6a.1	Preparation and NRC Review of License Termination Plan	71	-	-	96	25	192	-	192	-
6a Total	ISFSI D	&D Planning & Preparations	71	-	-	96	25	192		192	-
		<u> </u>									
	6b.1	Clean Demolition of ISFSI	2,073	958	-	-	455	3,486	-	3,486	-
	6b.2	Demolition of ISFSI Support Structures	377	141	_	-	78	596	-	596	-
6b Total	ISFSI ar	nd Support Structure Clean Demolition	2,451	1,099	-	-	532	4,082	-	4,082	-
	6c.1	Verification Surveys	128	33	-	-	24	185	-	185	-
	6c.2	Preparation of Final Report on Decommissioning and NRC Review	71	-		-	11	81		81	-
6c Total	ISFSI Fi	inal Status Surveys	199	33	-	-	35	266	-	266	-
	6d.1	Utility Staff	304	-	-	-	46	350		350	-
	6d.2	Security Guard Force	153	-	-	-	23	176		176	-
	6d.3	General Contractor Staff	1,999	-	-	-	300	2,299		2,299	-
	6d.4	Property Taxes	-	-	-	13	2	15		15	-
	6d.5	Insurance	-	-	-	25	4	29	-	29	-
	6d.6	Corporate Support	-	-	-	-	-	-	-	-	-
	6d.7	Utility Staff HP Supplies	-	-	-	-	-	-	-	-	-
	6d.8	Materials and Services	-	23	-	-	3	26		26	-
	6d.9	Energy	-	-	-	160	24	184		184	-
	6d.10	NRC Inspection Fee	-	-	-	56	8	64		64	-
	6d.11	Licensing Fees	-	-	-	86	13	99	-	99	-
	6d.12	County Fees & FEMA Fees	-	-	-	-	-	-	-	-	-
CATAL	6d.13	Licenses & Permits	- 2.450	-	-	17	3	20		20	-
6d Total	Undistr	ributed Costs for ISFSI Decommissioning	2,456	23	-	357	425	3,260	-	3,260	-
Period 6	Total	ISFSI DECOMMISSIONING	5,176	1,154	<u>-</u>	453	1,017	7,800		7,800	
1 61100 0	Total	ISI SI DECOMMISSIONING	3,170	1,134	-	433	1,017	7,800	-	7,800	-
GRAND	TOTAL		366,492	101,285	104,362	94,863	102,689	769,690	573,137	172,524	24,029
			,-3-		== :,= 0=	,		,	,_0.	,	= -,-==

Florida Power and Light Turkey Point Unit 4 Scenario 2 - SAFSTOR

	(tribusarius di 2020 dollars)										
Period	Item Number	Item Description	Labor Cost	Materials & Equipment	Waste Transportation & Disposal	Other Direct Cost (ODC)	Contingency	Total Cost (Estimated)	License Termination	Spent Fuel Management	Site Restoration
1a Total	Dlannin	g Prior to Shutdown (by Plant Operations)		_		_	_	_	_		_
1a iotai	riaiiiiii	g Frior to Shutdown (by Frant Operations)			<u>-</u>		_	_			
1b Total	Unit 3 P	ost Shutdown Planning & Engineering	-	-	-	-	-	-	-	-	-
1c Total	Unit 3 P	Post Shutdown Deactivation & Modifications	-	-	-	-	-	-	-	-	-
1d Total	Unit 3 W	et Fuel Transfer to ISFSI prior to SAFSTOR	-	-	-	-	-	-	-	-	-
1e Total	Unit 4 W	/et Fuel Transfer to DOE prior to Shutdown (by Plant Operations)	-	-	-	-	-	-	-	-	-
	1f.1	Admin Activities in Preparation for Decommissioning - Unit 4	900	2	-	-	135	1,038		-	-
	1f.2	Preparation of PSDAR and Licensing Documents - Unit 4	191	4	-	-	29	224	224	-	-
	1f.3	Engineering Activities in Preparation for Decommissioning - Unit 4	455	42	-	-	75	571	571	-	-
1f Total	Unit 4 P	ost Shutdown Planning & Engineering	1,546	48	-	-	239	1,833	1,833	-	-
	4 . 4										
	1g.1	Defuel Reactor Unit 4 (by Plant Operations)	-	-	-	-	-	-	-	-	-
	1g.2	Fuel Sampling & Inspections (by Plant Operations)	-	- 4 242	-	-	1 264	- 0.607	-	-	-
	1g.3	Spent Fuel Pool System Modifications - Unit 4	7,211	1,212	-	-	1,264	9,687	4.750	9,687	-
	1g.4	Implement Cold & Dark - Unit 4	3,508	630	-	-	621	4,759	4,759 512		-
1g Total	1g.6	Perform Pre-SAFSTOR Baseline Radiation Survey - Unit 4	445	1 9/12	-	<u>-</u>	67	512			-
1g Total	Unit 4 3	hutdown Preparations & Deactivation	11,164	1,842	-	-	1,951	14,958	5,2/1	9,687	-
	1h.1	Provide Transfer Casks (supplied by DOE)	_	_	_	_	_	_	_	_	_
	1h.2	Procure Spent Fuel Loading & Transfer Equipment	_	1,463	_	_	219	1,683	_	1,683	_
	1h.3	Procedures & Dry Runs	335	-	_	168	75	578	_	578	_
	1h.4	Remove (352) Fuel Assemblies from Pool & Load DOE Casks	1,760	440	_	-	440	2,640	_	2,640	_
	1h.5	Dry, Close & Inspect (11) DOE supplied Casks	880	220	_	_	220	1,320		1,320	_
	1h.6	Load Out (11) Casks to DOE Transport	880	220	-	_	220	1,320		1,320	-
	1h.7	Spent Fuel Transportation & Disposal (by DOE)	-	_	-	-	-	-	-	-	-
1h Total		/et Fuel Transfer to DOE prior to DECON	3,855	2,343	-	168	1,175	7,541	-	7,541	-
		·	,	•				,		•	
	1i.1	Provide Transfer Casks (19)	-	16,772	-	-	2,516	19,288	-	19,288	-
	1i.2	Procure Spent Fuel Loading & Transfer Equipment	-	-	-	-	-	-	-	-	-
	1i.3	Procedures & Dry Runs	335	-	-	168	75	578	-	578	-
	1i.4	Remove (592) Fuel Assemblies from Pool & Load Casks	3,040	760	-	-	760	4,560	-	4,560	-
	1i.5	Dry, Close & Inspect (19)	1,520	380	-	-	380	2,280	-	2,280	-
	1i.6	Load Out (19) Casks to Transport	1,520	380	-	-	380	2,280		2,280	
1i Total	Unit 4 W	/et Fuel Transfer to ISFSI prior to SAFSTOR	6,415	18,292	-	168	4,111	28,986	-	28,986	-

Florida Power and Light Turkey Point Unit 4 Scenario 2 - SAFSTOR

		(triousarius di 2020 dollars)									
Period	Item Number	Item Description	Labor Cost	Materials & Equipment	Waste Transportation & Disposal	Other Direct Cost (ODC)	Contingency	Total Cost (Estimated)	License Termination	Spent Fuel Management	Site Restoration
	4:4	Audit Co. ff	24.045				4.707	26.702	20.262	7 244	
	1j.1	Utility Staff	31,915	-	-	-	4,787	36,703	29,362	7,341	-
	1j.2	Security Guard Force	20,871	-	-	-	3,131	24,002	7,201	16,801	-
	1j.3	General Contractor Staff	-	-	-	-	-	-	-	-	-
	1j.4	Property Taxes	-	-	-	54	4 220	62	49	12	-
	1j.5	Insurance	2 226	-	-	8,201	1,230	9,431	7,545	1,886	-
	1j.6	Corporate Support	3,236	-	-	-	485	3,721	1,116	2,605	-
	1j.7	Utility Staff HP Supplies	-	691	-	- 2 224	104	795	238	556	-
	1j.8	NRC Inspection Fee	-	-	-	2,224	334	2,558	2,558	-	-
	1j.9	Licensing Fees	-	-	-	688	103	791	791	-	-
	1j.10	Materials and Services	-	1,981	-	-	297	2,278	683	1,594	-
	1j.11	Energy	-	-	-	1,069	160	1,229	983	246	-
	1j.12	EPRI Membership Fees	-	-	-	-	-	-	-	-	-
	1j.13	NEI Membership Fees	-	-	-	-	-	-	-	-	-
	1j.14	County & FEMA Fees	-	-	-	2,262	339	2,601	2,081	520	-
	1j.15	Licenses & Permits	-	-	-	68	10	78	62	16	-
	1j.16	INPO Membership Fees	-	-	-	-	-	-	-	-	-
	1j.17	ISFSI Operating Costs	20	60	-	-	12	92	-	92	-
	1j.18	Spent Fuel Maintenance	1,020	340	-	-	204	1,564	-	1,564	-
1j Total	Undistr	ibuted Costs for Shutdown & Transition	57,063	3,071	-	14,565	11,205	85,904	52,670	33,233	-
Period 1	Total	SHUTDOWN & TRANSITION	80,043	25,597	-	14,900	18,681	139,221	59,774	79,447	-
	2a.1	Utility Staff	7,323	_	_	_	732	8,055	3,625	4,430	-
	2a.2	Security Guard Force	3,441	_	_	_	344	3,785	-	3,785	-
	2a.3	General Contractor Staff	-	_	_	_	-	-	_	-	_
	2a.4	Property Taxes	_	_	_	228	23	251	113	138	_
	2a.5	Insurance	_	_	_	16,537	2,480	19,017	8,558	10,459	_
	2a.6	Corporate Support	17,223	_	_	-	1,722	18,946	8,526	10,420	_
	2a.7	Utility Staff HP Supplies		2,787	_	-	279	3,065	1,379	1,686	_
	2a.7	NRC Inspection Fee	_	-	_	1,890	189	2,079	936	1,144	-
	2a.9	Licensing Fees	_	_	_	2,924	439	3,363	1,513	1,849	_
	2a.10	County Fees & FEMA Fees	_	_	-	-	-33	5,505	-	-	_
	2a.10 2a.11	Licenses & Permits	_	_	_	288	29	317	143	- 174	_
	2a.11 2a.12	EPRI Membership Fees	_	_	_	-	_	517	-	-	_
	2a.12 2a.13	NEI Fees				-	_	_	_	_	
	2a.13 2a.14	INPO Membership Fees	_	_	_	_	_ [_	_	_	_
	2a.14 2a.15	Materials and Services	_	6,302	_	_	630	6,933	3,120	3,813	_
	Za.13	iviateriais aliu services	-	0,302	-	-	030	0,933	5,120	5,615	-

Florida Power and Light Turkey Point Unit 4 Scenario 2 - SAFSTOR

	(thousands of 2020 dollars)											
Period	Item Number	Item Description	Labor Cost	Materials & Equipment	Waste Transportation & Disposal	Other Direct Cost (ODC)	Contingency	Total Cost (Estimated)	License Termination	Spent Fuel Management	Site Restoration	
	2a.16	Energy	-	-	-	2,714	271	2,985	1,343	1,642	-	
	2a.17	Roof Replacement	102	153	-	-	26	281	127	155	-	
2a Total	Dorman	cy During Dry Fuel Storage	28,089	9,243	-	24,581	7,164	69,077	29,381	39,695	-	
	2a.1	Utility Staff	13,019	-	-	-	1,302	14,320	14,320	-	-	
	2a.2	Security Guard Force	6,363	-	-	-	636	6,999	6,999	-	-	
	2a.3	General Contractor Staff	-	-	-	-	-	-	-	-	-	
	2a.4	Property Taxes	-	-	-	429	43	472	472	-	-	
	2a.5	Insurance	-	-	-	18,526	2,779	21,305	21,305	-	-	
	2c.6	Corporate Support	9,126	-	-	-	913	10,038	10,038	-	-	
	2c.7	Utility Staff HP Supplies	-	1,243	-	-	124	1,367	1,367	-	-	
	2a.8	NRC Inspection Fee	-	-	-	3,558	534	4,092	4,092	-	-	
	2a.9	Licensing Fees	-	-	-	5,504	826	6,330	6,330	-	-	
	2a.10	County Fees & FEMA Fees	-	-	-	-	-	-	-	-	-	
	2a.11	Licenses & Permits	-	-	-	543	54	597	597	-	-	
	2a.12	EPRI Membership Fees	-	-	-	-	-	-	-	-	-	
	2a.13	NEI Fees	-	-	-	-	-	-	-	-	-	
	2a.14	INPO Membership Fees	-	-	-	-	-	-	-	-	-	
	2a.15	Materials and Services	-	3,788	-	-	379	4,167	4,167	-	-	
	2a.16	Energy	-	-	-	1,238	124	1,361	1,361	-	-	
	2a.17	Roof Replacement	878	1,316	-	-	219	2,414	2,414	-	-	
2b Total	Dorman	cy Only	29,385	6,348	-	29,798	7,932	73,463	73,463	-	-	
	_											
Period 2	Total	SAFSTOR	57,474	15,590	-	54,379	15,097	142,539	102,844	39,695	-	
	2.4		4.500	4.6			225	4 004	4 004			
	3a.1	Decommissioning Planning and Design - Unit 4	1,523	46	-	- 105	235	1,804		-	-	
	3a.2	Site Characterization - Unit 4	1,953	53	-	105	317	2,429		-	-	
	3a.3	Prepare Integrated Work Sequence and Schedule - Unit 4	164	5	-	-	25	195		-	-	
	3a.4	Prepare Decommissioning Activity Specifications - Unit 4	2,294	71	-	-	355	2,719		-	-	
	3a.5	Prepare License Termination Plan - Unit 4	984	-	-	667	248	1,899		-	-	
	3a.6	Prepare Detailed Work Procedures for Decommissioning - Unit 4	1,859	57	-	-	287	2,204		-	-	
	3a.7	Design Containment and Misc System Modifications - Unit 4	83	-	4 700	-	12	96	96	-	-	
2a Tatal	3a.8	Purchase Dry Storage Modules for Unit 4 GTCC Waste	- 0.001	-	4,708	772	706	5,414		-	-	
3a Total	Decomr	nissioning Planning	8,861	232	4,708	772	2,186	16,759	16,759	-	-	
	3b.1	Mobilize Decommissioning General Contractor	-	_	_	1,693	254	1,947	1,947	-	_	
	3b.1	Perform Asbestos Abatement of Pipe Insulation - Unit 4	3,465	182	_	-,055	912	4,559		_	_	
	3b.3	Implement Temporary Power Upgrades - Unit 4	1,033	937		-	296	2,266		_	_	
	30.3	implement remporary rower opgrades - office	1,033	337	-	-	230	2,200	۷,۷00	-	-	

Florida Power and Light Turkey Point Unit 4 Scenario 2 - SAFSTOR

				ttilot	isanus oi zuzu uu	iiai 3)	-				
Period	Item Number	Item Description	Labor Cost	Materials & Equipment	Waste Transportation & Disposal	Other Direct Cost (ODC)	Contingency	Total Cost (Estimated)	License Termination	Spent Fuel Management	Site Restoration
	3b.4	Construct Misc Building Modifications, In-Plant Laydown Areas	2,996	508	-	-	526	4,030	4,030	-	-
	3b.5	Modify Containment Access - Unit 4	2,223	377	-	-	390	2,990	2,990	-	-
	3b.6	Transportation Infrastructure Modifications	62	298	-	1,393	263	2,015	2,015	-	-
	3b.7	Procure Waste Handling & Processing Tents	-	-	-	1,476	221	1,697	1,697	-	-
3b Total	Decomn	missioning Transition and Preparations	9,778	2,303	-	4,562	2,861	19,504	19,504	-	-
	3c.1	Design and Procure Special Equipment	-	27,050	-	-	5,410	32,460	32,460	-	-
	3c.2	Test Special Cutting and Handling Equipment and Train Operators	1,924	-	-	73	399	2,396	2,396	-	-
	3c.3	Finalize Internals and Vessel Segmentation Details - Unit 4	458	-	-	-	92	549	549	-	-
	3c.4	Segment, Package and Ship Reactor Internals - Unit 4	5,879	2,100	-	-	1,596	9,575	9,575	-	-
	3c.5	Segment, Package and Ship RPV - Unit 4	1,394	1,030	-	-	485	2,909	2,909	-	-
	3c.6	Package, Ship & Dispose			10,753	-	2,151	12,904	12,904	-	-
3c Total	Reactor	· Vessel Removal	9,654	30,180	10,753	73	10,132	60,792	60,792	-	-
	3d.1	Heavy Lift / Transfer Equipment		3,245	-	-	649	3,893		-	-
	3d.2	Remove and Dispose of Steam Generators - Unit 4	1,417	163	-	-	316	1,895	1,895	-	-
	3d.3	Remove and Dispose of Pressurizer - Unit 4	195	22	-	-	43	259	259	-	-
	3d.4	Remove and Dispose of Reactor Coolant Pipe - Unit 4	522	36	-	-	112	670	670	-	-
	3d.5	Remove and Dispose of Reactor Coolant Pumps - Unit 4	537	59	-	-	119	716	716	-	-
	3d.6	Package, Ship, & Dispose			11,055	-	2,211	13,266	13,266	-	-
3d Total	Large Co	omponent Removal	2,671	3,524	11,055	-	3,450	20,700	20,700	-	-
	3e.1	Remove and Dispose of Spent Fuel Storage Racks	68	20	-	-	18	106	106	-	-
	3e.2	Segment, Package and Dispose of Spent Fuel Pool Island Equipment	214	20	-	-	47	281	281	-	-
	3e.3	Decon/Surgical Removal Containment Building - Unit 4	1,095	130	-	-	245	1,470		-	-
	3e.4	Decon/Surgical Removal Fuel Building	553	21	-	-	115	688	688	-	-
	3e.5	Decon/Surgical Remvoal Auxiliary Building Unit 4	6,132	574	-	-	1,341	8,048		-	-
	3e.6	Decon/Surgical Radwaste Building	334	84	-	-	84	502		-	-
	3e.7	Package, Dispose, & Ship	-	-	4,952	-	990	5,942		-	-
3e Total	Plant De	econtamination & Interior Rad Demolition	8,397	849	4,952	-	2,839	17,037	17,037	-	-
	3f.1	Demolish Fuel Building	257	538		-	159	953	953	-	-
	3f.2	Demolish Auxiliary Building	2,019	5,508		-	1,505	9,033		-	-
	3f.3	Demolish Radwaste Building	531	1,476		-	401	2,409		-	-
	3f.4	Demolish Unit 4 Containment Building	2,019	6,120		-	1,628	9,767	9,767	-	-
	3f.5	Demolish LLW Storage Building	655	1,550		-	441	2,647		-	-
	3f.6	Contaminated Soil	397	596	•	-	3,785	22,709		-	-
	3f.7	Debris Disposal	-	-	89,687	-	17,937	107,624	107,624	-	-

Florida Power and Light Turkey Point Unit 4 Scenario 2 - SAFSTOR

				(11101	isanus or 2020 do	iiais)					
Period	Item Number	Item Description	Labor Cost	Materials & Equipment	Waste Transportation & Disposal	Other Direct Cost (ODC)	Contingency	Total Cost (Estimated)	License Termination	Spent Fuel Management	Site Restoration
3f Total	Rad Bui	lding Demolition	5,878	15,789	107,617	-	25,857	155,141	155,141	-	-
	3g.1	Final Status Survey for Structures	5,897	67	-	227	1,238	7,428	7,428	-	-
	3g.2	Final Status Survey for Land Areas (included with structures)	-	-	-	-	-	-	-	-	-
3g Total	License	Termination Activities	5,897	67	-	227	1,238	7,428	7,428	-	-
	3h.1	Utility Staff	29,716	-	-	-	4,457	34,174	34,174	-	-
	3h.2	Security Guard Force	1,951	-	-	-	293	2,244	2,244	-	-
	3h.3	General Contractor Staff	67,660	-	-	-	10,149	77,809	77,809	-	-
	3h.4	Property Taxes	-	-	-	87	13	100	100	-	-
	3h.5	Insurance	-	-	-	3,769	565	4,334	4,334	-	-
	3h.6	Corporate Support	11,068	-	-	-	1,660	12,728	12,728	-	-
	3h.7	Utility Staff HP Supplies	-	5,673	-	-	851	6,524	6,524	-	-
	3h.8	NRC Inspection Fee	-	-	-	778	117	895	895	-	-
	3h.9	Licensing Fees	-	-	-	1,204	181	1,385	1,385	-	-
	3h.10	County & FEMA Fees	-	-	-	-	-	-	-	-	-
	3h.11	Licenses & Permits	-	-	-	110	17	127	127	-	-
	3h.12	Florida LLRW Inspection Fee	-	-	-	2,922	438	3,361	3,361	-	-
	3h.13	Materials and Services	-	1,661	-	-	249	1,910	1,910	-	-
	3h.14	Energy	-	-	-	3,288	493	3,781	3,781	-	-
	3h.15	DGC HP Supplies	-	5,132	-	-	770	5,902	5,902	-	-
	3h.16	EPRI Membership Fees	-	-	-	-	-	-	-	-	-
	3h.17	NEI Membership Fees	-	-	-	-	-	-	-	-	-
	3h.18	INPO Membership Fees	-	-	-	-	-	-	-	-	-
	3h.19	Emergency Preparedness Fees	-	-	-	-	-	-	-	-	-
3h Total	Undistri	ibuted Costs for Decommissioning & License Termination	110,396	12,466	-	12,159	20,253	155,274	155,274	-	-
	_										
Period 3	Total	DECOMMISSIONING & LICENSE TERMINATION	161,530	65,411	139,085	17,793	68,817	452,636	452,636	-	-
	4a.1	Demo Turbine Pedastal and Turbine Deck	3,647	1,506		-	773	5,927	-	-	5,927
	4a.2	Demo Intake & CWS	2,854	1,830		-	703	5,386	-	-	5,386
	4a.3	Demo Primary Water Tank Foundation	11	126		-	20	157	-	-	157
	4a.4	Demo Misc Site Structures	3,065	1,506		-	686	5,257	-	-	5,257
	4a.5	Demo Security Improvements	667	459		-	169	1,295	-	-	1,295
	4a.6	Demo Maintenance Facility	937	753	-	-	254	1,944	-	-	1,944
	4a.7	Demo Control Building	145	251	-	-	59	456	-	-	456
	4a.9	Demo Sealwell	113	251	-	-	55	418		-	418
	4a.10	Clean Concrete Processing	-	-	-	2,054	308	2,362	-	-	2,362

Florida Power and Light Turkey Point Unit 4 Scenario 2 - SAFSTOR

	-			(tho	usands of 2020 do	llars)					
Period	Item Number	Item Description	Labor Cost	Materials & Equipment	Waste Transportation & Disposal	Other Direct Cost (ODC)	Contingency	Total Cost (Estimated)	License Termination	Spent Fuel Management	Site Restoration
	4a.11	Demo Site Paving	447	670	-	-	168	1,285	-	-	1,285
	4a.12	Clean Debris Disposal/Recycle	-	-	127	-	19	147	-	-	147
4a Total	Clean B	uilding & Site Demolition	11,886	7,352	127	2,054	3,213	24,633	-	-	24,633
	4b.1	Procure Site Restoration Equipment	-	490	-	-	74	564	-	-	564
	4b.2	Finish Grading and Re-Vegetate Site	477	26	-	-	75	578	-	-	578
4b Total	Site Res	storation	477	516	-	-	149	1,142	-	-	1,142
	4c.1	Utility Staff	2,237	-	-	-	336	2,572	-	-	2,572
	4c.2	Security Guard Force	147	-	-	-	22	169	-	-	169
	4c.3	General Contractor Staff	5,093	-	-	-	764	5,857	-	-	5,857
	4c.4	Property Taxes	-	-	-	7	1	8	-	-	8
	4c.5	Insurance	-	-	-	284	43	326	-	-	326
	4c.6	Corporate Support	833	-	-	-	125	958	-	-	958
	4c.7	Energy	-	-	-	247	37	285	-	-	285
	4c.8	Materials and Services	-	105	-	-	16	121	-	-	121
	4c.9	County & FEMA Fees	-	-	-	-	-	-	-	-	-
	4c.10	Licenses & Permits	-	-	-	8	1	10	-	-	10
4c Total	Undistr	ibuted Costs for Site Restoration	8,309	105	-	546	1,344	10,304	-	-	10,304
							. =	0.0.000			
Period 4	Total	SITE RESTORATION	20,673	7,973	127	2,600	4,706	36,079	-	-	36,079
	5a.1	Dragues Loading & Transfer Fauinment (included in Deried 1)									
	5a.1 5a.2	Procure Loading & Transfer Equipment (included in Period 1) Procedures & Dry Runs (included in Period 1)	-	-	-	-	-	-	_	-	-
		Remove (47) Fuel Casks from ISFSI & Load DOE Transport	2.760	- 040	-	-	705	- - 40F	_	- - 40-	-
	5a.3		3,760	940		-	705	5,405	-	5,405	-
5a Total	5a.4	Spent Fuel Transportation & Disposal (by DOE) Il Transfer to DOE during and after DECON	3,760	940	-		705	5,405	-	- E 40E	-
Sa TOLAI	Dry rue	er transfer to DOE during and after DECON	3,760	940	-	-	705	5,405	-	5,405	-
	5b.1	Remove GTCC Casks from ISFSI & Loadout	320	_	_	80	120	520	520	_	_
	5b.1 5b.2	GTCC Transportation & Disposal	520	_	44 746	-	1,762	13,508			_
5b Total		Vaste Disposition	320	-	44 = 44	80		14,028			
35 Total	GICC W	raste disposition	320		11,740		1,002	14,020	14,020		
	5c.1	Utility Staff	5,897	_	_	-	885	6,781	_	6,781	_
	5c.2	Security Guard Force	22,749	_	_	-	3,412	26,162	_	26,162	_
	5c.3	General Contractor Staff	-	_	_	_	5,712	20,102	_	20,102	_
	5c.4	Property Taxes	_	_	_	_	_	_	_	_	_
	5c.5	Insurance	_	_	_	_	_ [_ [_	_	_
	5c.6	Corporate Support		_	_		_ [_	_	_
I	50.0	Corporate Support	-	-	-	-	- 1	- 1	·	-	-

Florida Power and Light Turkey Point Unit 4 Scenario 2 - SAFSTOR

				(tilo	usanus or 2020 uo	liais)					
Period	Item Number	Item Description	Labor Cost	Materials & Equipment	Waste Transportation & Disposal	Other Direct Cost (ODC)	Contingency	Total Cost (Estimated)	License Termination	Spent Fuel Management	Site Restoration
	5c.7	Utility Staff HP Supplies	-	-	-	-	-	-	-	-	-
	5c.8	NRC Inspection Fee	-	-	-	-	-	-	-	-	-
	5c.9	Licensing Fees	-	-	-	-	-	-	-	-	-
	5c.10	County & FEMA Fees	-	-	-	-	-	-	-	-	-
	5c.11	Licenses & Permits	-	-	-	-	-	-	-	-	-
	5c.12	Energy	-	-	-	-	-	-	-	-	-
	5c.13	Materials and Services	-	-	-	-	-	-	-	-	-
	5c.14	ISFSI Operating Costs	-	-	-	2,048	307	2,355	-	2,355	-
5c Total	Undistri	ibuted Costs for Dry Fuel / GTCC Storage & Transfer	28,646	-	-	2,048	4,604	35,298	-	35,298	-
Period 5	Total	DRY FUEL / GTCC STORAGE & TRANSFER	32,726	940	11,746	2,128	7,191	54,731	14,028	40,703	-
	6a.1	Preparation and NRC Review of License Termination Plan	45	-	_	64	16	125	_	125	_
6a Total		&D Planning & Preparations	45		-	64	16	125	-	125	-
	101 01 0 0	,									
	6b.1	Clean Demolition of ISFSI	1,316	638	-	-	293	2,248	-	2,248	-
	6b.2	Demolition of ISFSI Support Structures	240	94		-	50	384		384	-
6b Total	ISFSI and	d Support Structure Clean Demolition	1,556	732	-	-	343	2,632	-	2,632	-
			-					-		-	
	6c.1	Verification Surveys	81	22	-	-	15	119	-	119	-
	6c.2	Preparation of Final Report on Decommissioning and NRC Review	45	-	-	-	7	52	-	52	-
6c Total	ISFSI Fin	nal Status Surveys	126	22	-	-	22	170	•	170	-
	6d.1	Utility Staff	304	-	-	-	46	350	-	350	-
	6d.2	Security Guard Force	153	-	-	-	23	176	-	176	-
	6d.3	General Contractor Staff	1,999	-	-	-	300	2,299	-	2,299	-
	6d.4	Property Taxes	-	-	-	13	2	15	-	15	-
	6d.5	Insurance	-	-	-	25	4	29	-	29	-
	6d.6	Corporate Support	-	-	-	-	-	-	-	-	-
	6d.7	Utility Staff HP Supplies	-	-	-	-	-	-	-	-	-
	6d.8	Materials and Services	-	23	-	-	3	26	-	26	-
	6d.9	Energy	-	-	-	160	24	184	-	184	-
	6d.10	NRC Inspection Fee	-	-	-	56	8	64	-	64	-
	6d.11	Licensing Fees	-	-	-	86	13	99	-	99	-
	6d.12	County & FEMA Fees	-	-	-	-	-	-	-	-	-
	6d.13	Licenses & Permits		-	-	17	3	20	-	20	-
6d Total	Undistri	ibuted Costs for ISFSI Decommissioning	2,456	23	-	357	425	3,260	-	3,260	-

Florida Power and Light Turkey Point Unit 4 Scenario 2 - SAFSTOR

Period	Item Number	Item Description	Labor Cost	Materials & Equipment	Waste Transportation & Disposal	Other Direct Cost (ODC)	Contingency	Total Cost (Estimated)	License Termination	Spent Fuel Management	Site Restoration
Period 6	Total	ISFSI DECOMMISSIONING	4,183	777	-	421	807	6,187	•	6,187	-
GRAND	TOTAL		356,628	116,289	150,959	92,220	115,298	831,394	629,282	166,033	36,079

Florida Power and Light - Turkey Point Units 3 & 4

Scenario 1 - Prompt DECON following Unit 4 Shutdown

2020 Estimated Staff FTEs	2048	2049	2050	2051	2052	2053	2054	2055	2056	2057	2058	2059	2060	2061	2062	2063	2064	2065	2066	2067	2068	2069	2070	2071	2072	2073	2074	2075	2076
		UNIT	3 SHUT	DOWN		♦ ui	NIT 4 SH	UTDOW	/N																		 [
					ZIRC	FIRE EN	NDS 🔷			FUEL	POOL EN	МРТY				DE	COMMI	SSIONIN	G & SIT	E RESTO	DRATIO	N COMP	LETE			ISI	FSI EMPT	Y	
							Ľ									Ľ										·			
Period 1 - Shutdown & Transition	2048	2049	2050	2051	2052	2053	2054	2055	2056	2057	2058	2059	2060	2061	2062	2063	2064	2065	2066	2067	2068	2069	2070	2071	2072	2073	2074	2075	2076
Administration			-	-	6	12	12	7	4																		ļ		
Engineering					20	40	40	20	8																		ļ		
Health Physics/Rad Protection					20	30	30	24	20																				
Management					3	5	5	5	3																				
Maintenance & Operations					40	70	60	40	20																		İ		
Quality Assurance					2	3	3	2	1																		<u> </u>		
Utility Staff	-	-	-	-	91	160	150	98	56	-	-	-	-	۲	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
																											<u> </u>		
General Contractor Staff	-	-	-	-	-	-	-	-	-	-	-	-	-		-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
		•	•	-				•													•	-	•						
Period 2 - SAFSTOR	2048	2049	2050	2051	2052	2053	2054	2055	2056	2057	2058	2059	2060	2061	2062	2063	2064	2065	2066	2067	2068	2069	2070	2071	2072	2073	2074	2075	2076
Utility Staff	-	-	-	-	-	-	-	•	-	-	-	-	-	•	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
																											<u> </u>		
General Contractor Staff	-	-	-	-	-	-	-	-	-	-	-	-	-	•	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
Period 3 & 4 - License Term & Site Restoration	2048	2049	2050	2051	2052	2053	2054	2055	2056	2057	2058	2059	2060	2061	2062	2063	2064	2065	2066	2067	2068	2069	2070	2071	2072	2073	2074	2075	2076
Administration								4	4	10	12	12	12	12	7	2											1		
Engineering								4	6	16	20	20	20	20	7	2											1		
Health Physics/Rad Protection									4	8	24	24	24	24	16	4											1		
Management								1	1	4	5	5	4	4	4	2											1		
Maintenance & Operations										10	24	24	20	20	8	2											1		
Quality Assurance								1	1	2	3	3	2	2	2	1											<u> </u>		
Utility Staff	-	-	-	-	-	-	-	10	16	50	88	88	82	82	44	13	-	-	-	-	-	-	-	-	-	-	-	-	-
																											1		
Project Management								2	4	6	10	10	10	10	8	4											1		
Engineering								4	6	6	12	12	10	10	7	2											1		
Health Physics/Rad Protection									4	8	16	16	16	16	12	6											1		
Administration								2	3	6	12	12	12	12	8	4													
Maintenance & Operations											-	-	-	-	-	-											i		
Quality Assurance								1	1	2	4	4	4	4	3	2											 i		
Waste Management									1	2	12	12	12	12	12	4											i		
General Contractor Staff	-	-	-	-	-	-	-	9	19	30	66	66	64	64	50	22	-	-	-	-	-	-	-	-	-	-	-	-	-

Florida Power and Light - Turkey Point Units 3 & 4

Scenario 1 - Prompt DECON following Unit 4 Shutdown

2020 Estimated Staff FTEs	2048	2049	2050	2051	2052	2053	2054	2055	2056	2057	2058	2059	2060	2061	2062	2063	2064	2065	2066	2067	2068	2069	2070	2071	2072	2073	2074	2075 2076
		UNIT	3 SHUT	DOWN	•	♦ UI	NIT 4 SH	UTDOW	'N																			
					ZIRC	FIRE EN	IDS 🔷			FUEL	POOL EI	MPTY				DE	соммі	SSIONIN	IG & SIT	E RESTO	DRATIO	N COMP	PLETE			15	FSI EMPT	Υ
Period 5 - Dry Fuel / GTCC Storage & Transfer	2048	2049	2050	2051	2052	2053	2054	2055	2056	2057	2058	2059	2060	2061	2062	2063	2064	2065	2066	2067	2068	2069	2070	2071	2072	2073	2074	2075 2076
Administration																												
Engineering									1	1	1	1	1	1	1	1	1	1	1	1	1	1		1 1	1	1		
Health Physics/Rad Protection										1	1	1	1	1	1	1	1	1	1	1	1	1		1 1	1	1		
Management												-			-					-					-			
Maintenance & Operations										2	2	2	2	2	2	2	2	2	2	2	2	2		2 2	2	2		
Quality Assurance										1	1	1	1	1	1	1	1	1	1	1	1	1		1 1	1	1		
Utility Staff	-	-	-	-	-	-	-	-	1	5	5	5	5	5	5	5	5	5	5	5	5	5		5 5	5 5	5	-	
General Contractor Staff	-	-	-	-	-	-	-	-	-	-	-	-	-	-		-	-		-	-	-	-	-	-	-	-	-	
				•	•			l.			•		<u> </u>		•		•		l.	•		•		•	•	1		•
Period 6 - ISFSI Decommissioning	2048	2049	2050	2051	2052	2053	2054	2055	2056	2057	2058	2059	2060	2061	2062	2063	2064	2065	2066	2067	2068	2069	2070	2071	2072	2073	2074	2075 2076
Administration																												
Engineering																											1	
Health Physics/Rad Protection																											1	
Management																											1	
Maintenance & Operations																												
Quality Assurance																											1	
Utility Staff	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	4	
					1	ı											,										_	
Project Management																										1	1	
Engineering																										1	1	
Health Physics/Rad Protection																											1	
Administration																											1	
Maintenance & Operations																												
Quality Assurance																										1	1	
Waste Management																										1	1	
General Contractor Staff	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	4	6	

Appendix D-2
Florida Power and Light - Turkey Point Units 3 & 4
Scenario 2 - SAFSTOR

Scenario 2 - SAFSTOR																											
2020 Estimated Staff FTEs	2048	2049	2050	2051	2052	2053	2054	2055	2056	2057	2058	2059	2060	2061	2062	2063	2064	2065	2066	2067	2068	2069	2070	2071	2072	2073	2074
		UNIT	3 SHUT	DOWN	•	◆ UI	NIT 4 SH	HUTDO	WN																		
					ZIRC	FIRE EN	NDS 🔷			FUEL	POOL EI	MPTY												IS	FSI EMP	TY	
Period 1 - Shutdown & Transition	2048	2049	2050	2051	2052	2053	2054	2055	2056	2057	2058	2059	2060	2061	2062	2063	2064	2065	2066	2067	2068	2069	2070	2071	2072	2073	2074
	2040	2049	2000	2001					2000	2007	2000	2009	2000	2001	2002	2003	2004	2003	2000	2007	2000	2009	2070	2071	2012	2073	2074
Administration			-	-	6	12	12	7	4																		
Engineering					20	40	40	20	8																		-
Health Physics/Rad Protection					20	30	30	24	20																		
Management					3	5	5	5	3																		
Maintenance & Operations					40	70	60	40	20																		
Quality Assurance					2	3	3	2	1																<u> </u>	<u> </u>	_
Utility Staff	-	-	-	-	91	160	150	98	56	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
General Contractor Staff	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
	20.40	0040	0050	2254								0050	2222					2225					0070	0074	2072	0070	0074
Period 2 - SAFSTOR	2048	2049	2050	2051	2052	2053	2054	2055	2056	2057	2058	2059	2060	2061	2062	2063	2064	2065	2066	2067	2068	2069	2070	2071	2072	2073	2074
Administration			-	-	-				1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
Engineering									1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
Health Physics/Rad Protection									1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
Management																											
Maintenance & Operations									3	3	3	3	3	3	3	3	3	3	3	3	3	3	3	3	3	3	3
Quality Assurance																											
Utility Staff	-	-	-	-	-	-	-	-	6	6	6	6	6	6	6	6	6	6	6	6	6	6	6	6	6	6	6
																									<u> </u>	ــــــ	<u> </u>
General Contractor Staff	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
Period 3 & 4 - License Term & Site Restoration	2048	2049	2050	2051	2052	2053	2054	2055	2056	2057	2058	2059	2060	2061	2062	2063	2064	2065	2066	2067	2068	2069	2070	2071	2072	2073	2074
Administration																											
Engineering																											
Health Physics/Rad Protection																											
Management																											
Maintenance & Operations																											
Quality Assurance																											
Utility Staff		+-			_	_	_	_	-	_		_		_	_	-	_	_		_	_		-		-	 _	-
Othicy Staff	-	 	-	-	-	<u> </u>	-	-	-	-	-	-	-	-	-	-	<u> </u>	-	-	<u> </u>	-	-	+-	-	-	┢	+
Project Management																											1
Engineering																											
Health Physics/Rad Protection																											
Administration																											
Maintenance & Operations																											
																										1	1
Quality Assurance																											-
Waste Management			+		ļ	_	ļ	ļ	_			_	 	ļ			_		ļ	_	ļ		 	_	₩	₩	+
General Contractor Staff	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-

Appendix D-2
Florida Power and Light - Turkey Point Units 3 & 4

Scenario 2 - SAFSTOR

Scenario 2 - SAFSTOR																											
2020 Estimated Staff FTEs	2075 / 2089	2090	2091	2092	2093	2094	2095	2096	2097	2098	2099	2100	2101	2102	2103	2104	2105	2106	2107	2108	2109	2110	2111	2112	2113	2114	2115
																					ISFSI	DEMOL	ITION C	OMPLE1	TE 🔷		
																	DECO	MMISSI	ONING	& SITE F	RESTORA	ATION C	OMPLET	TE 🔷			
Period 1 - Shutdown & Transition	2075 / 2089	2090	2091	2092	2093	2094	2095	2096	2097	2098	2099	2100	2101	2102	2103	2104	2105	2106	2107	2108	2109	2110	2111	2112	2113	2114	2115
Administration																											
Engineering																											
Health Physics/Rad Protection																											
Management																											
Maintenance & Operations																											
Quality Assurance																											
Utility Staff	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
General Contractor Staff			1																	<u> </u>							
General Contractor Staff	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
Period 2 - SAFSTOR	2075 / 2089	2090	2091	2092	2093	2094	2095	2096	2097	2098	2099	2100	2101	2102	2103	2104	2105	2106	2107	2108	2109	2110	2111	2112	2113	2114	2115
Administration	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1										
Engineering	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1										
Health Physics/Rad Protection	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1										
Management																											
Maintenance & Operations	3	3	3	3	3	3	3	3	3	3	3	3	3	3	3	3	3										
Quality Assurance																											
Utility Staff	6	6	6	6	6	6	6	6	6	6	6	6	6	6	6	6	6	-	-	_	_	-	_	-	-	_	_
•																											
General Contractor Staff	-	_	-	-	_	-	-	_	-	_	_	-	_	_	-	-	-	_	-	_	_	-	_	-	-	_	_
	<u> </u>	1				1	1															1	<u>I</u>				<u>I</u>
Period 3 & 4 - License Term & Site Restoration	2075 / 2089	2090	2091	2092	2093	2094	2095	2096	2097	2098	2099	2100	2101	2102	2103	2104	2105	2106	2107	2108	2109	2110	2111	2112	2113	2114	2115
Administration																4	4	10	12	12	12	12	7	2			
Engineering																4	6	16	20	20	20	20	7	2			
Health Physics/Rad Protection																	4	8	24	24	24	24	16	4			
Management																1	1	4	5	5	4	4	4	2			
Maintenance & Operations																		10	24	24	20	20	8	2			
Quality Assurance																1	1	2	3	3	2	2	2	1			
Utility Staff	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	10	16	50	88	88	82	82	44	13	-	-	-
Project Management																2		6	10					4			
Engineering																4	6	6	12					2			
Health Physics/Rad Protection																	4	8	16					6			
Administration																2	3	6	12	12	12	12	8	4			
Maintenance & Operations																			-	-	-	-	-	-			
Quality Assurance																1	1	2	4	4	4	4	3	2			
Waste Management																	1	2	12	12	12	12	-	4			
General Contractor Staff	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	9	19	30	66	66	64	64	50	22	-	-	-

Appendix D-2
Florida Power and Light - Turkey Point Units 3 & 4

_		_			
Scena	arin	7.	. ςΔ	FST	OF

Scenario 2 - SAFSTOR																_								_			
2020 Estimated Staff FTEs	2048	2049	2050	2051	2052	2053	2054	2055	2056	2057	2058	2059	2060	2061	2062	2063	2064	2065	2066	2067	2068	2069	2070	2071	2072	2073	2074
		UNIT	3 SHUT	DOWN		◆ UI	NIT 4 SI	HUTDO	WN																	,	
					ZIRO	C FIRE EN	NDS 🔷			FUEL	POOL EN	MPTY												ISI	FSI EMP	TY	
Period 5 - Dry Fuel / GTCC Storage & Transfer	2048	2049	2050	2051	2052	2053	2054	2055	2056	2057	2058	2059	2060	2061	2062	2063	2064	2065	2066	2067	2068	2069	2070	2071	2072	2073	2074
Administration																											
Engineering									1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	
Health Physics/Rad Protection										1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	
Management																											
Maintenance & Operations										2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	
Quality Assurance										1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	
Utility Staff	-	-	-	-	-	-	-	-	1	5	5	5	5	5	5	5	5	5	5	5	5	5	5	5	5	5	-
General Contractor Staff	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
Period 6 - ISFSI Decommissioning	2048	2049	2050	2051	2052	2053	2054	2055	2056	2057	2058	2059	2060	2061	2062	2063	2064	2065	2066	2067	2068	2069	2070	2071	2072	2073	2074
Administration																											
Engineering																											
Health Physics/Rad Protection																											
Management																											
Maintenance & Operations																											
Quality Assurance																											
Utility Staff	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
			ı							l						ı	l	l	l	ı				ı			1
Project Management																											
Engineering																											
Health Physics/Rad Protection																											
Administration																										ļ	
Maintenance & Operations																											ļ
Quality Assurance																											
Waste Management																										 '	
General Contractor Staff	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-

Appendix D-2 Florida Power and Light - Turkey Point Units 3 & 4

_		_			
Scena	arin	7.	. ςΔ	FST	OF

Scenario 2 - SAFSTOR																											
2020 Estimated Staff FTEs	2075 / 2089	2090	2091	2092	2093	2094	2095	2096	2097	2098	2099	2100	2101	2102	2103	2104	2105	2106	2107	2108	2109				2113	2114	2118
																					ISFS	I DEMOL	LITION C	OMPLET	TE 🔷		
																	DECO	MMISSI	ONING	& SITE F	RESTOR	ATION C	COMPLET	TE 🔷			
Period 5 - Dry Fuel / GTCC Storage & Transfer	2075 / 2089	2090	2091	2092	2093	2094	2095	2096	2097	2098	2099	2100	2101	2102	2103	2104	2105	2106	2107	2108	2109	2110	2111	2112	2113	2114	2115
Administration																											
Engineering																											
Health Physics/Rad Protection																											
Management																											
Maintenance & Operations																											
Quality Assurance																											
Utility Staff	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
Our and Our transfer Otals			1																				—				—
General Contractor Staff	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
Period 6 - ISFSI Decommissioning	2075 / 2089	2090	2091	2092	2093	2094	2095	2096	2097	2098	2099	2100	2101	2102	2103	2104	2105	2106	2107	2108	2109	2110	2111	2112	2113	2114	2115
Administration																											
Engineering																									1		
Health Physics/Rad Protection																									1		
Management																									1		
Maintenance & Operations																											
Quality Assurance																									1		
Utility Staff	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	4	-	-
		1				1					1				1	1		1							l .		
Project Management																								1	1		-
Engineering																								1	1		
Health Physics/Rad Protection																									1		ļ
Administration																									1		
Maintenance & Operations																											
Quality Assurance																								1	1		ļ
Waste Management				1																			<u> </u>	1	1		<u> </u>
General Contractor Staff	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	_	-	-	-	-	-	4	6	-	-

Appendix E-1 - Waste Disposal Summary Turkey Point Unit 3 Scenario 1 - Prompt DECON following Unit 4 Shutdown 2020 Dollars

			Waste Weight	Waste Volume	Burial Volume			Tr	ansportation				
Facility	Waste Form	Waste Class	(LBs)	(CF)	(CF)	Pac	kaging Cost		Cost	Bas	se Burial Cost	Tota	al Waste Cost
BC Facility													
WCS	Class BC	ВС	245,911	1,412	2,075	\$	282,000	\$	1,715,383	\$	14,726,947	\$	16,724,330
	GTCC	GTCC	407,628	901	2,061	\$	4,708,000	\$	1,342,496	\$	10,403,722	\$	16,454,218
			653,539	2,313	4,136	\$	4,990,000	\$	3,057,879	\$	25,130,669	\$	33,178,548
Bear Creek													
	Containerized	Α	225,284	2,717	2,717	\$	-	\$	217,810	\$	378,056	\$	595,866
			225,284	2,717	2,717	\$	-	\$	217,810	\$	378,056	\$	595,866
Energy <i>Solutions</i>													
Clive	Debris	Α	45,337,048	554,734	554,907	\$	978,630	\$	6,586,248	\$	38,717,951	\$	46,282,829
Clive	Debris, Oversized	Α	850,165	14,095	14,098	\$	18,840	\$	130,412	\$	2,278,221	\$	2,427,472
Clive	Contaminated Soil	Α	32,877,700	328,481	328,777	\$	692,370	\$	4,669,279	\$	12,568,500	\$	17,930,149
Clive	Containerized	Α	46,597	360	376	\$	180,627	\$	179,624	\$	185,196	\$	545,447
Clive	Large Component	Α	1,964,843	20,274	20,274	\$	1,842,447	\$	1,205,872	\$	8,013,694	\$	11,062,013
			81,076,353	917,944	918,432	\$	3,712,914	\$	12,771,434	\$	61,763,562	\$	78,247,910
Other													
Local Landfill	Clean/Exempt	F	1,232,426	23,332	23,332	\$	-	\$	3,033	\$	54,364	\$	57,397
Local Scrap Metal Recycler	Recycled Metals	F	4,564,427	86,408	86,408	\$	-	\$	44,068	\$	-	\$	44,068
On Site- Reuse	Clean/Reuse	F	61,795,906	671,592	727,200	\$	-	\$	-	\$	-	\$	-
			67,592,759	781,332	836,940	\$	-	\$	47,101	\$	54,364	\$	101,465
Grand Total			149.547.935	1.704.307	1,762,225	\$	8.702.914	\$	16.094.224	\$	87.326.650	¢	112,123,788

Appendix E-1 - Waste Disposal Summary Turkey Point Unit 4 Scenario 1 - Prompt DECON following Unit 4 Shutdown 2020 Dollars

			Waste Weight	Waste Volume	Burial Volume			Tr	ansportation				
Facility	Waste Form	Waste Class	(LBs)	(CF)	(CF)	Pac	kaging Cost		Cost	Bas	se Burial Cost	Tot	al Waste Cost
BC Facility													
WCS	Class BC	ВС	245,911	1,532	2,075	\$	282,000	\$	1,715,383	\$	14,726,947	\$	16,724,330
	GTCC	GTCC	407,628	901	2,061	\$	4,708,000	\$	1,342,496	\$	10,403,722	\$	16,454,218
			653,539	2,433	4,136	\$	4,990,000	\$	3,057,879	\$	25,130,669	\$	33,178,548
Bear Creek													
	Containerized	Α	335,454	4,144	4,144	\$	-	\$	331,450	\$	575,302	\$	906,752
			335,454	4,144	4,144	\$	-	\$	331,450	\$	575,302	\$	906,752
Energy <i>Solutions</i>													
Clive	Debris	Α	93,321,478	1,141,458	1,141,847	\$	1,991,280	\$	13,423,163	\$	75,942,257	\$	91,356,700
Clive	Debris, Oversized	Α	904,841	14,096	14,099	\$	18,840	\$	130,412	\$	2,278,221	\$	2,427,472
Clive	Contaminated Soil	Α	32,877,700	328,481	328,777	\$	692,370	\$	4,669,279	\$	12,568,500	\$	17,930,149
Clive	Containerized	Α	46,597	360	376	\$	180,627	\$	179,624	\$	185,196	\$	545,447
Clive	Large Component	Α	1,964,843	20,274	20,274	\$	1,842,447	\$	1,205,872	\$	8,013,694	\$	11,062,013
			129,115,460	1,504,670	1,505,373	\$	4,725,564	\$	19,608,349	\$	98,987,869	\$	123,321,781
Other													
Local Landfill	Clean/Exempt	F	1,232,426	23,332	20,567	\$	-	\$	2,674	\$	47,920	\$	50,594
Local Scrap Metal Recycler	Recycled Metals	F	5,753,932	124,026	124,416	\$	-	\$	63,452	\$	-	\$	63,452
On Site- Reuse	Clean/Reuse	F	136,848,466	1,421,972	1,610,259	\$	-	\$	-	\$	-	\$	-
			143,834,824	1,569,330	1,755,241	\$	-	\$	66,126	\$	47,920	\$	114,046
Grand Total			273.939.276	3.080.577	3.268.895		9.715.564		23.063.804		124.741.760		157.521.127

Appendix E-2 - Waste Disposal Summary Turkey Point Unit 3 Scenario 2 - SAFSTOR 2020 Dollars

			Waste Weight	Waste Volume	Burial Volume			Tr	ansportation				
Facility	Waste Form	Waste Class	(LBs)	(CF)	(CF)	Pac	kaging Cost		Cost	Bas	se Burial Cost	Tot	al Waste Cos
BC Facility													
WCS	Class BC	ВС	151,559	1,444	1,343	\$	168,000	\$	1,258,171	\$	9,326,758	\$	10,752,929
	GTCC	GTCC	407,628	901	2,061	\$	4,708,000	\$	1,342,496	\$	10,403,722	\$	16,454,218
			559,187	2,345	3,404	\$	4,876,000	\$	2,600,667	\$	19,730,480	\$	27,207,147
Bear Creek													
	Processed Waste	Α	82,738	1,379	1,379	\$	-	\$	113,640	\$	197,247	\$	310,887
			82,738	1,379	1,379	\$	-	\$	113,640	\$	197,247	\$	310,887
Energy <i>Solution</i> s													
Clive	Debris	Α	44,716,687	542,890	543,032	\$	969,210	\$	6,521,042	\$	38,124,682	\$	45,614,934
Clive	Debris, Oversized	Α	2,118,671	25,836	25,841	\$	28,260	\$	195,617	\$	3,417,331	\$	3,641,209
Clive	Contaminated Soil	Α	29,912,700	298,858	299,127	\$	626,430	\$	4,224,586	\$	11,371,500	\$	16,222,516
Clive	Containerized	Α	71,322	611	632	\$	270,940	\$	269,436	\$	277,794	\$	818,170
Clive	Large Component	Α	1,892,553	22,314	22,314	\$	1,832,840	\$	1,171,712	\$	7,442,145	\$	10,446,696
			78,711,933	890,509	890,946	\$	3,727,680	\$	12,382,392	\$	60,633,453	\$	76,743,525
Other													
Local Landfill	Clean/Exempt	F	1,232,426	23,332	20,567	\$	-	\$	2,674	\$	47,920	\$	50,594
Local Scrap Metal Recycler	Recycled Metals	F	4,571,145	96,866	97,200	\$	-	\$	49,572	\$	-	\$	49,572
On Site- Reuse	Clean/Reuse	F	61,795,906	719,334	727,200	\$	-	\$	-	\$	-	\$	-
		_	67,599,477	839,532	844,967	\$	-	\$	52,246	\$	47,920	\$	100,166
Grand Total			146.953.335	1.733.765	1.740.695	\$	8.603.680	\$	15.148.944	\$	80.609.099	¢	104,361,724

Appendix E-2 - Waste Disposal Summary Turkey Point Unit 4 Scenario 2 - SAFSTOR 2020 Dollars

Facility	Waste Form	Waste Class	Waste Weight (LBs)	Waste Volume (CF)	Burial Volume (CF)	Pac	kaging Cost	Tr	ansportation Cost	Bas	se Burial Cost	Tot	al Waste Cost
BC Facility			, ,	, ,	. ,		0 0						
WCS	Class BC	BC	151,559	1,444	1,343	\$	168,000	\$	1,258,171	\$	9,326,758	\$	10,752,929
	GTCC	GTCC	407,628	901	2,061	\$	4,708,000	\$	1,342,496	\$	10,403,722	\$	16,454,218
			559,187	2,345	3,404	\$	4,876,000	\$	2,600,667	\$	19,730,480	\$	27,207,147
Bear Creek													
	Processed Waste	Α	134,389	2,257	2,257	\$	-	\$	179,930	\$	312,307	\$	492,237
			134,389	2,257	2,257	\$	-	\$	179,930	\$	312,307	\$	492,237
Energy <i>Solutions</i>													
Clive	Debris	Α	92,245,252	1,119,433	1,119,765	\$	1,967,730	\$	13,260,148	\$	74,459,086	\$	89,686,964
Clive	Debris, Oversized	Α	2,111,297	25,836	25,841	\$	28,260	\$	195,617	\$	3,417,331	\$	3,641,209
Clive	Contaminated Soil	Α	32,877,700	328,481	328,777	\$	692,370	\$	4,669,279	\$	12,568,500	\$	17,930,149
Clive	Containerized	Α	71,322	611	632	\$	270,940	\$	269,436	\$	277,794	\$	818,170
Clive	Large Component	Α	1,908,461	20,498	20,498	\$	1,837,550	\$	1,204,117	\$	8,013,694	\$	11,055,362
			129,214,032	1,494,859	1,495,513	\$	4,796,850	\$	19,598,597	\$	98,736,406	\$	123,131,854
Other													
Local Landfill	Clean/Exempt	F	1,232,426	23,332	20,567	\$	-	\$	2,674	\$	47,920	\$	50,594
Local Scrap Metal Recycler	Recycled Metals	F	6,123,518	150,514	150,660	\$	-	\$	76,837	\$	-	\$	76,837
On Site- Reuse	Clean/Reuse	F	136,898,566	1,422,562	1,610,682	\$	-	\$	-	\$	-	\$	-
			144,254,510	1,596,408	1,781,909	\$	-	\$	79,510	\$	47,920	\$	127,431
Grand Total			274,162,118	3.095.869	3,283,083		9,672,850	\$	22.458.704	\$	118,827,113	e	150,958,668

Florida Power and Light - Turkey Point Units 3 & 4 SCENARIO 1 - PROMPT DECON Estimated Annual Spending

Year	License Termination	Spent Fuel	Site Restoration	Total
2050	-	-	-	-
2051	-	-	-	-
2052	6,592	7,762	-	14,354
2053	36,328	34,112	-	70,440
2054	33,686	29,383	-	63,070
2055	38,148	57,082	-	95,230
2056	75,678	35,738	-	111,416
2057	111,558	6,391	-	117,949
2058	108,716	6,391	10,094	125,201
2059	145,403	6,391	15,637	167,431
2060	162,857	6,391	16,077	185,325
2061	184,872	6,391	12,065	203,329
2062	78,156	6,391	4,106	88,653
2063	8,304	6,391	1,909	16,605
2064	-	6,391	-	6,391
2065	-	6,391		6,391
2066	-	6,391	-	6,391
2067	-	6,391	-	6,391
2068	-	6,391		6,391
2069	-	6,391	•	6,391
2070	-	6,391	•	6,391
2071	7,014	6,391	•	13,405
2072	14,028	6,913	•	20,941
2073	7,014	15,290	ı	22,304
2074	-	800	ı	800
2075	-	-	-	-
Total	1,018,355	282,949	59,888	1,361,192

Florida Power and Light - Turkey Point Unit 3 SCENARIO 1 - PROMPT DECON Estimated Annual Spending

Year	License Termination	Spent Fuel	Site Restoration	Total
2050	-	-	-	-
2051	-	-	-	-
2052	6,592	7,762	-	14,354
2053	24,253	21,095	-	45,347
2054	15,552	13,024	-	28,577
2055	18,117	25,444	-	43,561
2056	43,825	17,100	-	60,925
2057	58,453	3,198	-	61,650
2058	58,891	3,198	3,380	65,469
2059	71,369	3,198	6,816	81,382
2060	82,846	3,198	6,870	92,914
2061	65,889	3,198	3,540	72,627
2062	22,573	3,198	2,187	27,958
2063	1,674	3,198	1,086	5,958
2064	-	3,198		3,198
2065	-	3,198	•	3,198
2066	-	3,198	•	3,198
2067	-	3,198	•	3,198
2068	-	3,198	•	3,198
2069	-	3,198	•	3,198
2070	-	3,198	•	3,198
2071	3,507	3,198	•	6,705
2072	7,014	3,475	-	10,489
2073	3,507	8,388	•	11,895
2074	-	448	-	448
2075	-	-	-	-
Total	484,062	144,704	23,879	652,645

Florida Power and Light - Turkey Point Unit 4 SCENARIO 1 - PROMPT DECON Estimated Annual Spending

Year	License Termination	Spent Fuel	Site Restoration	Total
2050	-	-	-	-
2051	-	-	-	-
2052	-	-	-	-
2053	12,076	13,017	-	25,093
2054	18,134	16,359	-	34,493
2055	20,031	31,638	-	51,669
2056	31,852	18,639	-	50,491
2057	53,105	3,193	-	56,299
2058	49,826	3,193	6,714	59,733
2059	74,034	3,193	8,821	86,049
2060	80,011	3,193	9,207	92,411
2061	118,983	3,193	8,525	130,702
2062	55,583	3,193	1,919	60,695
2063	6,630	3,193	823	10,647
2064	-	3,193		3,193
2065	-	3,193	•	3,193
2066	-	3,193		3,193
2067	-	3,193	•	3,193
2068	-	3,193	•	3,193
2069	-	3,193	•	3,193
2070	-	3,193	•	3,193
2071	3,507	3,193	•	6,700
2072	7,014	3,437	ı	10,451
2073	3,507	6,902	ı	10,409
2074		351	•	351
2075	-	-	-	-
Total	534,293	138,245	36,009	708,547

Florida Power and Light - Turkey Point Units 3 & 4 SCENARIO 2 - SAFSTOR Estimated Annual Spending

Year	License	Spent	Site	Total
	Termination	Fuel	Restoration	TOtal
2050	-	-	•	-
2051	-	-	-	-
2052	7,928	7,872	•	15,800
2053	40,444	34,340	-	74,784
2054	35,808	29,441	-	65,249
2055	27,750	57,118	-	84,868
2056	24,791	35,744	-	60,535
2057	3,441	9,559	-	13,000
2058	3,441	9,559	-	13,000
2059	3,441	9,559	-	13,000
2060	3,441	9,559	-	13,000
2061	3,441	9,559	ı	13,000
2062	3,441	9,559	ı	13,000
2063	3,441	9,559	1	13,000
2064	3,441	9,559	ı	13,000
2065	3,441	9,559	1	13,000
2066	3,441	9,559	ı	13,000
2067	3,441	9,559	•	13,000
2068	3,441	9,559	1	13,000
2069	3,441	9,559	•	13,000
2070	3,441	9,559	1	13,000
2071	3,441	9,559	•	13,000
2072	3,441	9,559	•	13,000
2073	3,441	7,105	1	10,546
2074	4,448	-	ı	4,448
2075	4,448	-	•	4,448
2076	4,448	-	1	4,448
2077	4,448	-	ı	4,448
2078	4,448	-	-	4,448
2079	4,448	-	•	4,448
2080	4,448	-	-	4,448
2081	4,448	-	-	4,448
2082	4,448	-	-	4,448
2083	4,448	-	-	4,448
2084	4,448	-	-	4,448
2085	4,448	-	-	4,448
2086	4,448	-	-	4,448
2087	4,448	-	-	4,448
2088	4,448	-	-	4,448

Florida Power and Light - Turkey Point Units 3 & 4 SCENARIO 2 - SAFSTOR Estimated Annual Spending

Year	License Termination	Spent Fuel	Site Restoration	Total
2089	4,448	-	-	4,448
2090	4,448	-	-	4,448
2091	4,448	-	-	4,448
2092	4,448	-	-	4,448
2093	4,448	-	-	4,448
2094	4,448	-	-	4,448
2095	4,448	-	-	4,448
2096	4,448	-	-	4,448
2097	4,448	-	-	4,448
2098	4,448	-	-	4,448
2099	4,448	-	-	4,448
2100	4,448	-	-	4,448
2101	4,448	-	-	4,448
2102	4,448	-	-	4,448
2103	4,448	-	-	4,448
2104	8,805	-	-	8,805
2105	52,146	-	-	52,146
2106	79,727	-	-	79,727
2107	131,319	-	5,847	137,167
2108	134,788	-	18,504	153,292
2109	154,720	-	16,573	171,293
2110	184,753	-	13,190	197,943
2111	104,749	-	4,122	108,871
2112	22,759	3,578	1,871	28,208
2113	-	10,411	-	10,411
Total	1,202,419	338,557	60,108	1,601,084

Florida Power and Light - Turkey Point Unit 3 SCENARIO 2 - SAFSTOR Estimated Annual Spending

Year	License Termination	Spent Fuel	Site Restoration	Total
2050	-	-	-	-
2051	-	-	-	-
2052	7,928	7,872	-	15,800
2053	26,028	21,344	-	47,372
2054	16,373	13,157	-	29,530
2055	13,987	25,534	-	39,521
2056	12,628	17,164	-	29,792
2057	1,713	4,757	-	6,470
2058	1,713	4,757	-	6,470
2059	1,713	4,757	-	6,470
2060	1,713	4,757	-	6,470
2061	1,713	4,757	-	6,470
2062	1,713	4,757	-	6,470
2063	1,713	4,757	-	6,470
2064	1,713	4,757	-	6,470
2065	1,713	4,757	-	6,470
2066	1,713	4,757	-	6,470
2067	1,713	4,757	-	6,470
2068	1,713	4,757	-	6,470
2069	1,713	4,757	-	6,470
2070	1,713	4,757	-	6,470
2071	1,713	4,757	-	6,470
2072	1,713	4,757	-	6,470
2073	1,713	3,537	-	5,249
2074	2,152	-	-	2,152
2075	2,152	-	-	2,152
2076	2,152	-	-	2,152
2077	2,152	-	-	2,152
2078	2,152	-	-	2,152
2079	2,152	-	-	2,152
2080	2,152	-	-	2,152
2081	2,152	-	-	2,152
2082	2,152	-	-	2,152
2083	2,152	-	-	2,152
2084	2,152	-	-	2,152
2085	2,152	-	-	2,152
2086	2,152	-	-	2,152
2087	2,152	-	-	2,152
2088	2,152	-	-	2,152

Florida Power and Light - Turkey Point Unit 3 SCENARIO 2 - SAFSTOR Estimated Annual Spending

Year	License Termination	Spent Fuel	Site Restoration	Total
2089	2,152	-	-	2,152
2090	2,152	-	-	2,152
2091	2,152	-	-	2,152
2092	2,152	-	-	2,152
2093	2,152	-	-	2,152
2094	2,152	-	-	2,152
2095	2,152	-	-	2,152
2096	2,152	-	-	2,152
2097	2,152	-	-	2,152
2098	2,152	-	-	2,152
2099	2,152	-	-	2,152
2100	2,152	-	-	2,152
2101	2,152	-	-	2,152
2102	2,152	-	-	2,152
2103	2,152	-	-	2,152
2104	6,509	-	-	6,509
2105	32,022	-	-	32,022
2106	52,972	-	-	52,972
2107	62,709	-	1,989	64,698
2108	65,449	-	7,277	72,726
2109	68,302	-	6,874	75,176
2110	83,874	-	4,619	88,493
2111	26,609	-	2,201	28,810
2112	4,069	1,822	1,068	6,958
2113	-	5,978		5,978
Total	573,137	172,524	24,029	769,690

Florida Power and Light - Turkey Point Unit 4 SCENARIO 2 - SAFSTOR Estimated Annual Spending

Year	License Termination	Spent Fuel	Site Restoration	Total
2050	-	-	-	-
2051	-	-	-	-
2052	-	-	-	-
2053	14,416	12,996	-	27,412
2054	19,435	16,284	-	35,720
2055	13,763	31,584	-	45,347
2056	12,163	18,581	-	30,743
2057	1,728	4,802	-	6,530
2058	1,728	4,802	-	6,530
2059	1,728	4,802	-	6,530
2060	1,728	4,802	-	6,530
2061	1,728	4,802	-	6,530
2062	1,728	4,802	_	6,530
2063	1,728	4,802	-	6,530
2064	1,728	4,802	-	6,530
2065	1,728	4,802	-	6,530
2066	1,728	4,802	-	6,530
2067	1,728	4,802	-	6,530
2068	1,728	4,802	-	6,530
2069	1,728	4,802	-	6,530
2070	1,728	4,802	-	6,530
2071	1,728	4,802	-	6,530
2072	1,728	4,802	-	6,530
2073	1,728	3,568	-	5,297
2074	2,296	-	-	2,296
2075	2,296	-	-	2,296
2076	2,296	-	-	2,296
2077	2,296	-	-	2,296
2078	2,296	-	-	2,296
2079	2,296	-	-	2,296
2080	2,296	-	-	2,296
2081	2,296	-	-	2,296
2082	2,296	-	-	2,296
2083	2,296	-	-	2,296
2084	2,296	-	-	2,296
2085	2,296	-	-	2,296
2086	2,296	-	-	2,296
2087	2,296	-	-	2,296
2088	2,296	-	-	2,296

Florida Power and Light - Turkey Point Unit 4 SCENARIO 2 - SAFSTOR Estimated Annual Spending

Year	License Termination	Spent Fuel	Site Restoration	Total
2089	2,296	-	-	2,296
2090	2,296	•		2,296
2091	2,296	•	•	2,296
2092	2,296	-	-	2,296
2093	2,296	-	-	2,296
2094	2,296	-	-	2,296
2095	2,296	-	-	2,296
2096	2,296	-	-	2,296
2097	2,296	-	-	2,296
2098	2,296	-	-	2,296
2099	2,296	•		2,296
2100	2,296	-	-	2,296
2101	2,296	•		2,296
2102	2,296	•	•	2,296
2103	2,296	•	•	2,296
2104	2,296	•		2,296
2105	20,124	•	•	20,124
2106	26,755	-	-	26,755
2107	68,611	•	3,858	72,469
2108	69,339	-	11,227	80,566
2109	86,418	-	9,699	96,117
2110	100,879	-	8,571	109,450
2111	78,140	-	1,921	80,061
2112	18,691	1,756	803	21,249
2113	-	4,433	-	4,433
Total	629,282	166,033	36,079	831,394

Florida Power and Light - Turkey Point Units 3 & 4 SCENARIO 1 - PROMPT DECON

Estimated Annual Spending

Labor, Material/Equip, Waste, Other Direct Cost

Year	Labor	Material & Equipment	Waste Packaging & Transportation	Waste Disposal	Other Direct Cost	Total
2050	-	-		-	-	-
2051	-	-	-	-	-	-
2052	10,954	1,126	-	-	2,274	14,354
2053	57,237	4,672	-	-	8,531	70,440
2054	49,256	4,201	-	-	9,613	63,070
2055	44,602	38,634	-	-	11,993	95,230
2056	78,403	8,330	8,512	-	16,170	111,416
2057	63,796	29,082	2,065	8,643	14,363	117,949
2058	70,351	31,533	3,084	11,016	9,217	125,202
2059	97,116	36,997	5,010	19,454	8,854	167,431
2060	90,467	29,365	12,816	46,930	5,748	185,325
2061	53,481	22,428	22,362	99,910	5,147	203,329
2062	28,185	9,944	9,411	36,363	4,750	88,653
2063	7,080	999	1,424	3,999	3,104	16,605
2064	4,495	194	•	-	1,703	6,391
2065	4,495	194	•	•	1,703	6,391
2066	4,495	194	•	•	1,703	6,391
2067	4,495	194	•	-	1,703	6,391
2068	4,495	194	-	-	1,703	6,391
2069	4,495	194	•	•	1,703	6,391
2070	4,495	194	•	•	1,703	6,391
2071	4,689	194	•	6,769	1,752	13,405
2072	5,259	197	-	13,547	1,938	20,941
2073	12,143	2,253	-	6,763	1,145	22,304
2074	688	66	-	-	46	800
2075	-	-	-	-	-	-
2076	-	-	-	-	-	-
Total	705,172	221,379	64,684	253,394	116,563	1,361,192

Florida Power and Light - Turkey Point Unit 3 SCENARIO 1 - PROMPT DECON

Estimated Annual Spending

Labor, Material/Equip, Waste, Other Direct Cost

Year	Labor	Material & Equipment	Waste Packaging & Transportation	Waste Disposal	Other Direct Cost	Total
2050	-	-		-	-	-
2051	-	-	-	-	-	-
2052	10,954	1,126	-	-	2,274	14,354
2053	37,627	2,718	-	-	5,003	45,347
2054	21,953	1,870	-	-	4,754	28,577
2055	21,340	16,698	-	-	5,523	43,561
2056	42,576	4,771	4,645	-	8,933	60,925
2057	31,594	17,117	664	4,893	7,383	61,651
2058	35,477	17,787	1,304	7,024	3,876	65,469
2059	48,420	17,650	2,471	8,676	4,166	81,382
2060	43,447	10,895	7,676	27,972	2,924	92,914
2061	22,351	6,145	8,359	33,167	2,605	72,627
2062	11,619	2,769	2,385	8,796	2,389	27,958
2063	3,827	559	-	-	1,572	5,958
2064	2,236	94	-	-	867	3,198
2065	2,236	94	-	-	867	3,198
2066	2,236	94	-	-	867	3,198
2067	2,236	94	-	-	867	3,198
2068	2,236	94	-	-	867	3,198
2069	2,236	94	-	-	867	3,198
2070	2,236	94	-	-	867	3,198
2071	2,334	94	-	3,385	892	6,705
2072	2,626	96	-	6,774	994	10,489
2073	6,588	1,336	-	3,381	590	11,895
2074	386	39		-	23	448
2075	-	-	-	-	-	-
2076	-	-	-	-	-	-
Total	358,772	102,330	27,505	104,067	59,971	652,646

Florida Power and Light - Turkey Point Unit 4 SCENARIO 1 - PROMPT DECON Estimated Annual Spending

Labor, Material/Equip, Waste, Other Direct Cost

Year	Labor	Material & Equipment	Waste Packaging & Waste Disposal Transportation		Other Direct Cost	Total	
2050	-	-		-	-	-	
2051	-	-		-	-	-	
2052	-	•	-	-	•	-	
2053	19,611	1,954	-	-	3,529	25,093	
2054	27,303	2,331	•	-	4,859	34,493	
2055	23,262	21,937	-	-	6,470	51,669	
2056	35,827	3,559	3,868	-	7,237	50,491	
2057	32,202	11,965	1,401	3,750	6,980	56,299	
2058	34,874	13,746	1,780	3,992	5,341	59,733	
2059	48,696	19,347	2,539	10,778	4,689	86,049	
2060	47,020	18,470	5,140	18,957	2,824	92,411	
2061	31,130	16,283	14,003	66,744	2,542	130,702	
2062	16,566	7,175	7,025	27,567	2,361	60,695	
2063	3,252	439	1,424	3,999	1,532	10,647	
2064	2,259	100	-	-	835	3,193	
2065	2,259	100	-	-	835	3,193	
2066	2,259	100	-	-	835	3,193	
2067	2,259	100	-	-	835	3,193	
2068	2,259	100	-	-	835	3,193	
2069	2,259	100	-	-	835	3,193	
2070	2,259	100	•	-	835	3,193	
2071	2,356	100	-	3,385	860	6,700	
2072	2,633	101	-	6,773	944	10,451	
2073	5,555	917	-	3,382	555	10,409	
2074	302	27	-	-	23	351	
2075	-	•	-	-	-	-	
2076	-	-	-	-	-	-	
Total	346,399	119,049	37,180	149,327	56,592	708,547	

Florida Power and Light - Turkey Point Units 3 & 4 SCENARIO 2 - SAFSTOR

Estimated Annual Spending

Labor, Material/Equip, Waste, Other Direct Cost

Year	Labor	Material & Equipment	Waste Packaging & Transportation	Waste Disposal	Other Direct Cost	Total
2050	-	-	-	-	-	-
2051	-	-	-	-	-	-
2052	12,150	1,394	-	-	2,255	15,800
2053	60,940	5,598	-	-	8,247	74,784
2054	51,212	4,750	-	-	9,287	65,249
2055	39,562	36,188	-	-	9,118	84,868
2056	42,350	8,583	-	-	9,602	60,535
2057	8,069	1,335	-	-	3,597	13,000
2058	8,069	1,335	-	-	3,597	13,000
2059	8,069	1,335	-	-	3,597	13,000
2060	8,069	1,335	-	-	3,597	13,000
2061	8,069	1,335	-	-	3,597	13,000
2062	8,069	1,335	-	-	3,597	13,000
2063	8,069	1,335		-	3,597	13,000
2064	8,069	1,335	-	-	3,597	13,000
2065	8,069	1,335		-	3,597	13,000
2066	8,069	1,335	-	-	3,597	13,000
2067	8,069	1,335	-	-	3,597	13,000
2068	8,069	1,335	-	-	3,597	13,000
2069	8,069	1,335	-	-	3,597	13,000
2070	8,069	1,335	-	-	3,597	13,000
2071	8,069	1,335	-	-	3,597	13,000
2072	8,069	1,335	-	-	3,597	13,000
2073	5,847	1,265	-	-	3,434	10,546
2074	1,996	386	-	-	2,066	4,448
2075	1,996	386	-	-	2,066	4,448
2076	1,996	386	-	-	2,066	4,448
2077	1,996	386	-	-	2,066	4,448
2078	1,996	386	-	-	2,066	4,448
2079	1,996	386	-	-	2,066	4,448
2080	1,996	386	-	-	2,066	4,448
2081	1,996	386	-	-	2,066	4,448
2082	1,996	386	-	-	2,066	4,448
2083	1,996	386	-	-	2,066	4,448
2084	1,996	386	-	-	2,066	4,448
2085	1,996	386	-	-	2,066	4,448
2086	1,996	386	-	-	2,066	4,448
2087	1,996	386	_	-	2,066	4,448
2088	1,996	386	-	-	2,066	4,448
2089	1,996	386	_	-	2,066	4,448
2090	1,996	386	_	-	2,066	4,448
2091	1,996	386	_	-	2,066	4,448
2092	1,996	386	-	-	2,066	4,448

Florida Power and Light - Turkey Point Units 3 & 4 SCENARIO 2 - SAFSTOR

Estimated Annual Spending

Labor, Material/Equip, Waste, Other Direct Cost

Year	Labor	Material & Equipment	Waste Packaging & Transportation	Waste Disposal	Other Direct Cost	Total
2093	1,996	386	-	-	2,066	4,448
2094	1,996	386	-	-	2,066	4,448
2095	1,996	386	-	-	2,066	4,448
2096	1,996	386	-	-	2,066	4,448
2097	1,996	386	-	-	2,066	4,448
2098	1,996	386	-	-	2,066	4,448
2099	1,996	386	-	-	2,066	4,448
2100	1,996	386	-	-	2,066	4,448
2101	1,996	386	-	-	2,066	4,448
2102	1,996	386		-	2,066	4,448
2103	1,996	386	-	-	2,066	4,448
2104	5,523	487		-	2,795	8,805
2105	36,910	2,253	4,617	-	8,367	52,146
2106	36,836	20,301	7,385	3,104	12,100	79,727
2107	76,621	43,479	2,203	7,278	7,585	137,167
2108	83,557	29,370	5,680	22,184	7,501	148,293
2109	93,819	26,635	9,345	36,572	4,923	171,293
2110	57,858	22,219	20,968	95,833	3,566	200,443
2111	22,881	13,793	12,571	56,764	2,863	108,872
2112	10,554	1,336	2,950	14,042	1,826	30,707
2113	7,806	2,195	•	-	410	10,411
2114	-	-	-	-	-	-
2115	-	-	•	-	-	-
Total	833,394	252,795	65,719	235,777	213,398	1,601,084

Florida Power and Light - Turkey Point Unit 3 SCENARIO 2 - SAFSTOR

Estimated Annual Spending

Labor, Material/Equip, Waste, Other Direct Cost

Year	Labor	Material & Equipment	Waste Packaging & Transportation	Waste Disposal	Other Direct Cost	Total
2050	-	-	-	-	-	-
2051	-	-	-	-	-	-
2052	12,150	1,394	-	-	2,255	15,800
2053	39,268	3,251	•	-	4,853	47,372
2054	22,723	2,145	•	-	4,661	29,530
2055	18,122	16,774	-	-	4,625	39,521
2056	21,574	3,303	-	-	4,914	29,792
2057	4,014	661	-	-	1,795	6,470
2058	4,014	661	-	-	1,795	6,470
2059	4,014	661	-	-	1,795	6,470
2060	4,014	661	-	-	1,795	6,470
2061	4,014	661	-	-	1,795	6,470
2062	4,014	661	-	-	1,795	6,470
2063	4,014	661	-	-	1,795	6,470
2064	4,014	661	-	-	1,795	6,470
2065	4,014	661	-	-	1,795	6,470
2066	4,014	661	-	-	1,795	6,470
2067	4,014	661	-	-	1,795	6,470
2068	4,014	661	-	-	1,795	6,470
2069	4,014	661	-	-	1,795	6,470
2070	4,014	661	-	-	1,795	6,470
2071	4,014	661	-	-	1,795	6,470
2072	4,014	661	-	-	1,795	6,470
2073	2,910	628	-	-	1,711	5,249
2074	966	164	-	-	1,022	2,152
2075	966	164	-	-	1,022	2,152
2076	966	164	-	-	1,022	2,152
2077	966	164	-	-	1,022	2,152
2078	966	164	-	-	1,022	2,152
2079	966	164	-	-	1,022	2,152
2080	966	164	-	-	1,022	2,152
2081	966	164	-	-	1,022	2,152
2082	966	164	-	-	1,022	2,152
2083	966	164	-	-	1,022	2,152
2084	966	164	-	-	1,022	2,152
2085	966	164	-	-	1,022	2,152
2086	966	164	-	-	1,022	2,152
2087	966	164	•	-	1,022	2,152
2088	966	164	-	-	1,022	2,152
2089	966	164	-	-	1,022	2,152
2090	966	164	-	-	1,022	2,152
2091	966	164	-	-	1,022	2,152
2092	966	164	-	-	1,022	2,152
2093	966	164	-	-	1,022	2,152

Florida Power and Light - Turkey Point Unit 3 SCENARIO 2 - SAFSTOR

Estimated Annual Spending

Labor, Material/Equip, Waste, Other Direct Cost

Year	Labor	Material & Equipment	Waste Packaging & Transportation	Waste Disposal	Other Direct Cost	Total
2094	966	164	-	-	1,022	2,152
2095	966	164	-	-	1,022	2,152
2096	966	164	-	-	1,022	2,152
2097	966	164	-	-	1,022	2,152
2098	966	164	-	-	1,022	2,152
2099	966	164	-	-	1,022	2,152
2100	966	164	-	-	1,022	2,152
2101	966	164	-	-	1,022	2,152
2102	966	164	-	-	1,022	2,152
2103	966	164	-	-	1,022	2,152
2104	4,493	265	-	-	1,751	6,509
2105	21,022	1,585	4,617	-	4,799	32,022
2106	24,039	17,479	1,975	3,104	6,375	52,972
2107	37,928	19,516	930	3,532	2,792	64,698
2108	37,006	17,368	2,229	7,765	3,360	67,727
2109	44,739	8,806	3,706	15,668	2,258	75,176
2110	25,466	5,491	10,764	47,617	1,655	90,993
2111	8,059	1,651	3,084	14,676	1,340	28,811
2112	4,595	976	500	2,494	892	9,458
2113	4,459	1,314	-	-	205	5,978
2114	-	-	-	-	-	-
2115	-	-	-	-	-	-
Total	421,764	117,450	27,804	94,855	107,816	769,690

Florida Power and Light - Turkey Point Unit 4 **SCENARIO 2 - SAFSTOR**

Estimated Annual Spending Labor, Material/Equip, Waste, Other Direct Cost

Year	Labor	Material & Equipment	Waste Packaging & Transportation	Waste Disposal	Other Direct Cost	Total
2050	-	-	-	-	-	-
2051	-	-	-	-	-	-
2052	-	-	-	-	-	-
2053	21,672	2,346	-	-	3,394	27,412
2054	28,488	2,605	-	-	4,626	35,720
2055	21,440	19,414	-	-	4,493	45,347
2056	20,775	5,280	-	-	4,688	30,743
2057	4,055	673	-	-	1,802	6,530
2058	4,055	673	-	-	1,802	6,530
2059	4,055	673	-	-	1,802	6,530
2060	4,055	673	-	-	1,802	6,530
2061	4,055	673	-	-	1,802	6,530
2062	4,055	673	-	-	1,802	6,530
2063	4,055	673	-	-	1,802	6,530
2064	4,055	673	-	-	1,802	6,530
2065	4,055	673	-	-	1,802	6,530
2066	4,055	673	-	-	1,802	6,530
2067	4,055	673	-	-	1,802	6,530
2068	4,055	673	-	-	1,802	6,530
2069	4,055	673	-	_	1,802	6,530
2070	4,055	673	-	-	1,802	6,530
2071	4,055	673	-	-	1,802	6,530
2072	4,055	673	-	-	1,802	6,530
2073	2,937	638	-	-	1,722	5,297
2074	1,029	222	-	-	1,044	2,296
2075	1,029	222	-	-	1,044	2,296
2076	1,029	222	-	-	1,044	2,296
2077	1,029	222	-	-	1,044	2,296
2078	1,029	222	-	-	1,044	2,296
2079	1,029	222	-	-	1,044	2,296
2080	1,029	222	-	-	1,044	2,296
2081	1,029	222	-	-	1,044	2,296
2082	1,029	222	-	-	1,044	2,296
2083	1,029	222	-	-	1,044	2,296
2084	1,029	222	-	-	1,044	2,296
2085	1,029	222	-	-	1,044	2,296
2086	1,029	222	-	-	1,044	2,296
2087	1,029	222	-	-	1,044	2,296
2088	1,029	222	-	-	1,044	2,296
2089	1,029	222	_	-	1,044	2,296
2090	1,029	222	_	-	1,044	2,296
2091	1,029	222	-	_	1,044	2,296
2092	1,029	222	_	_	1,044	2,296

Florida Power and Light - Turkey Point Unit 4 SCENARIO 2 - SAFSTOR

Estimated Annual Spending

Labor, Material/Equip, Waste, Other Direct Cost

Year	Labor	Material & Equipment	Waste Packaging & Transportation	Waste Disposal	Other Direct Cost	Total
2093	1,029	222	-	-	1,044	2,296
2094	1,029	222	-	-	1,044	2,296
2095	1,029	222	-	-	1,044	2,296
2096	1,029	222	-	-	1,044	2,296
2097	1,029	222	-	-	1,044	2,296
2098	1,029	222	-	-	1,044	2,296
2099	1,029	222	-	-	1,044	2,296
2100	1,029	222	-	-	1,044	2,296
2101	1,029	222	-	-	1,044	2,296
2102	1,029	222	-	-	1,044	2,296
2103	1,029	222	-	-	1,044	2,296
2104	1,029	222	-	-	1,044	2,296
2105	15,888	669	-	-	3,567	20,124
2106	12,798	2,822	5,411	-	5,725	26,755
2107	38,693	23,962	1,274	3,746	4,794	72,469
2108	46,552	12,002	3,452	14,420	4,141	80,566
2109	49,080	17,829	5,639	20,905	2,665	96,117
2110	32,392	16,727	10,205	48,216	1,911	109,450
2111	14,822	12,141	9,487	42,087	1,524	80,061
2112	5,958	359	2,450	11,548	934	21,249
2113	3,347	881	-	-	205	4,433
2114	-	-	-	-	-	-
2115	-	-	-	-		-
Total	411,630	135,345	37,915	140,922	105,582	831,394

Florida Power and Light - Turkey Point Units 3 & 4 **SCENARIO 1 - PROMPT DECON Estimated DOE Reimbursement**

Labor, Material/Equip, Waste, Other Direct Cost

Year	Labor	Material & Equipment	Waste Transportation & Disposal	Other Direct Cost	Total
2050	-	-	-	-	-
2051	-	-	-	-	-
2052	-	-	-	-	-
2053	6,377	1,000	-	385	7,762
2054	28,579	4,065	-	1,468	34,112
2055	24,079	3,652	-	1,653	29,383
2056	17,510	37,969	-	1,603	57,082
2057	27,983	5,672	-	2,083	35,738
2058	4,495	194	-	1,703	6,391
2059	4,495	194	-	1,703	6,391
2060	-	-	-	-	-
2061	-	-	-	-	-
2062	-	-	-	-	-
2063	-	-	-	-	-
2064	-	-	-	-	-
2065	-	-	-	-	-
2066	-	-	-	-	-
2067	-	-	-	-	-
2068	-	-	-	-	-
2069	-	-	-	-	-
2070	-	-	-	-	-
2071	-	-	-	-	-
2072	-	-	-	-	-
2073	-	-	-	-	-
2074	-	-	-	-	-
2075	-	-	-	-	-
2076	_	-	-	•	-
Total	113,518	52,745	-	10,597	176,860

Florida Power and Light - Turkey Point Unit 3 SCENARIO 1 - PROMPT DECON Estimated DOE Reimbursement

Labor, Material/Equip, Waste, Other Direct Cost

Year	Labor	Material & Equipment	Waste Transportation & Disposal	Other Direct Cost	Total
2050	-	-	-	-	-
2051	-	-	-	-	-
2052	-	-	-	-	-
2053	6,377	1,000	-	385	7,762
2054	17,895	2,335	-	864	21,095
2055	10,545	1,662	-	817	13,024
2056	8,202	16,433	-	809	25,444
2057	12,909	3,094	-	1,097	17,100
2058	2,236	94	-	867	3,198
2059	2,236	94	-	867	3,198
2060	-	-	-	-	-
2061	-	-	-	-	-
2062	-	-	-	-	-
2063	-	-	-	-	-
2064	-	-	-	-	-
2065	-	-	-	-	-
2066	-	-	-	-	-
2067	-	-	-	-	-
2068	-	-	-	-	-
2069	-	-	-	-	-
2070	-	-	-	-	-
2071	-	-	-	-	-
2072	-	-	-	-	-
2073	-	-	-	-	-
2074	-	-	-	-	-
2075	-	-	-	-	-
2076		-	-	-	-
Total	60,401	24,713	-	5,707	90,821

Florida Power and Light - Turkey Point Unit 4 SCENARIO 1 - PROMPT DECON Estimated DOE Reimbursement

Labor, Material/Equip, Waste, Other Direct Cost

Year	Labor	Material & Equipment	Waste Transportation & Disposal	Other Direct Cost	Total
2050	-	-	-	-	-
2051	-	-	-	-	-
2052	-	-	-	-	-
2053	-	-	-	-	-
2054	10,684	1,730	-	603	13,017
2055	13,534	1,990	-	836	16,359
2056	9,308	21,535	-	795	31,638
2057	15,073	2,579	-	987	18,639
2058	2,259	100	-	835	3,193
2059	2,259	100	-	835	3,193
2060	-	-	-	-	-
2061	-	-	-	-	-
2062	-	-	-	-	-
2063	-	-	-	-	-
2064	-	-	-	-	-
2065	-	-	-	-	-
2066	-	-	-	-	-
2067	-	-	-	-	-
2068	-	-	-	-	-
2069	-	-	-	-	-
2070	-	-	-	-	-
2071	-	-	-	-	-
2072	-	-	-	-	-
2073	-	-	-	-	-
2074	-	-	-	-	-
2075	-	-	-	-	-
2076	-	<u>-</u>	-	<u>-</u>	-
Total	53,116	28,033	-	4,891	86,040

Florida Power and Light - Turkey Point Units 3 & 4 SCENARIO 2 - SAFSTOR

Estimated DOE Reimbursement

Labor, Material/Equip, Waste, Other Direct Cost

			VA/ 1 -		
Year	Labor	Material & Equipment	Waste Transportation & Disposal	Other Direct Cost	Total
2050	-	-	-	-	•
2051	•	-	-	-	•
2052	-	-	-	-	•
2053	6,471	1,019	-	381	7,872
2054	28,670	4,259	-	1,411	34,340
2055	24,039	3,814	-	1,588	29,441
2056	19,963	35,600	-	1,555	57,118
2057	25,414	8,291	-	2,040	35,744
2058	6,648	794	-	2,117	9,559
2059	6,648	794	-	2,117	9,559
2060	-	-	-	-	•
2061	-	-	-	-	-
2062	-	-	-	-	-
2063	-	-	-	-	•
2064	-	-	-	-	-
2065	-	-	-	-	-
2066	-	-	-	-	-
2067	-	-	-	-	-
2068	-	-	-	-	-
2069	-	-	-	-	-
2070	-	-	-	-	-
2071	-	-	-	-	•
2072	-	-	-	-	-
2073	-	-	-	-	-
2074	-	-	-	-	-
2075	-	-	-	-	-
2076	-		-	-	-
2077	-	-	-	-	-
2078	-	-	-	-	•
2079	-	-	-	-	-
2080	-	-	-	-	-
2081	-	-	-	-	-
2082	-	-	-	-	-
2083	-	-	-	-	-
2084	-	-	-	-	-
2085	-	-	-	-	-
2086	-	-	-	-	-
2087	-	-	-	-	-

Florida Power and Light - Turkey Point Units 3 & 4 SCENARIO 2 - SAFSTOR

Estimated DOE Reimbursement

Labor, Material/Equip, Waste, Other Direct Cost

Year	Labor	Material & Equipment	Waste Transportation & Disposal	Other Direct Cost	Total
2088	-	-	-	-	-
2089	-	-	-	-	-
2090	-	-	-	-	-
2091	-	-	-	-	-
2092	-	-	-	-	-
2093	-	-	-	-	-
2094	-	-	-	-	-
2095	-	-	-	-	-
2096	-	-	-	-	-
2097	-	-	-	-	-
2098	-	-	-	-	-
2099	-	-	-	-	-
2100	-	-	-	-	-
2101	-	-	-	-	-
2102	-	-	-	-	-
2103	-	-	-	-	-
2104	-	-	-	-	-
2105	-	-	-	-	-
2106	-	-	-	-	-
2107	-	-	-	-	-
2108	-	-	-	-	-
2109	-	-	-	-	-
2110	-	-	-	-	-
2111	-	-	-	-	-
2112	-	-	-	-	-
2113	-	-	-	-	-
2114	-	-	-	-	-
2115	-	-	-	-	-
Total	117,853	54,571	-	11,210	183,634

Florida Power and Light - Turkey Point Unit 3 SCENARIO 2 - SAFSTOR

Estimated DOE Reimbursement

Labor, Material/Equip, Waste, Other Direct Cost

			Waste		
Year	Labor	Material & Equipment	Transportation & Disposal	Other Direct Cost	Total
2050	-	-	-	-	-
2051	-	-	-	ı	-
2052	-	•	•	ı	-
2053	6,471	1,019	•	381	7,872
2054	18,012	2,497	-	834	21,344
2055	10,597	1,761	-	799	13,157
2056	8,221	16,521	-	792	25,534
2057	12,909	3,172	•	1,082	17,164
2058	3,307	393	-	1,058	4,757
2059	3,307	393	-	1,058	4,757
2060	-	-	-	•	-
2061	-	-	-	•	-
2062	-	-	-	-	-
2063	-	-	-	•	-
2064	-	-	-	-	-
2065	-	-	-	-	-
2066	-	-	-	-	-
2067	-	-	-	-	-
2068	-	-	-	-	-
2069	-	-	-	-	-
2070	-	-	-	-	-
2071	-	-	-	-	-
2072	-	-	-	-	-
2073	-	-	-	-	-
2074	-	-	-	-	-
2075	-	-	-	-	-
2076	-	<u> </u>	-	-	-
2077	-	-	-	-	-
2078	-	-	-	-	-
2079	-	-	-	-	-
2080	-	-	-	-	-
2081	-	-	-	-	-
2082	-	-	-	-	-
2083	-	-	-	-	-
2084	-	-	-	-	-
2085	-	-	-	-	-
2086	-	-	-	-	-
2087	-	-	-	-	-

Florida Power and Light - Turkey Point Unit 3 SCENARIO 2 - SAFSTOR

Estimated DOE Reimbursement

Labor, Material/Equip, Waste, Other Direct Cost

Year	Labor	Material & Equipment	Waste Transportation & Disposal	Other Direct Cost	Total
2088	-	-	-	-	-
2089	-	-	-	-	-
2090	-	-	-	-	-
2091	-	-	-	-	-
2092	-	•	•	•	-
2093	-	-	-	-	-
2094	-	•	•	•	-
2095	-	-	-	-	-
2096	-	•	•	•	-
2097	•	•	•	•	-
2098	-	•	•	•	-
2099	•	•	•	•	-
2100	-	•	•	ı	-
2101	-	•	-	ı	-
2102	-	-	-	-	-
2103	-	•	-	ı	-
2104	-	-	-	-	-
2105	-	•	•	ı	-
2106	-	-	-	-	-
2107	-	-	-	-	-
2108	-	-	-	-	-
2109	-	-	-	-	-
2110	-	-	-	-	-
2111	-	-	-	•	-
2112	-	-	-	-	-
2113	-	-	-	-	-
2114	-	-	-	-	-
2115	-		-	-	-
Total	62,823	25,757	-	6,005	94,585

Florida Power and Light - Turkey Point Unit 4 SCENARIO 2 - SAFSTOR

Estimated DOE Reimbursement

Labor, Material/Equip, Waste, Other Direct Cost

			10/		
Year	Labor	Material & Equipment	Waste Transportation & Disposal	Other Direct Cost	Total
2050	-	-	-	-	-
2051	-	-	-	-	-
2052	-	-	-	-	-
2053	-	-	-	-	-
2054	10,658	1,762	-	577	12,996
2055	13,443	2,053	-	789	16,284
2056	11,743	19,078	-	763	31,584
2057	12,505	5,118	-	958	18,581
2058	3,341	401	-	1,059	4,802
2059	3,341	401	-	1,059	4,802
2060	-	-	-	-	-
2061	-	-	-	-	-
2062	-	-	-	-	-
2063	-	-	-	-	•
2064	-	-	-	-	-
2065	-	-	-	-	-
2066	-	-	-	-	-
2067	-	-	-	-	-
2068	-	-	-	-	-
2069	-	-	-	-	-
2070	-	-	-	-	-
2071	-	-	-	-	-
2072	-	-	-	-	-
2073	-	-	-	-	-
2074	-	-	-	-	-
2075	-	-	-	-	-
2076	-	-	-	-	-
2077	-	-	-	-	-
2078	-	-	-	-	-
2079	-	-	-	-	-
2080	-	-	-	-	-
2081	-	-	-	-	-
2082	-	-	-	-	-
2083	-	-	-	-	-
2084	-	-	-	-	-
2085	-	-	-	-	-
2086	-	-	-	-	-
2087	-	-	-	-	-

Florida Power and Light - Turkey Point Unit 4 SCENARIO 2 - SAFSTOR

Estimated DOE Reimbursement

Labor, Material/Equip, Waste, Other Direct Cost

Year	Labor	Material & Equipment	Waste Transportation & Disposal	Other Direct Cost	Total
2088	-	-	-	-	-
2089	-	-	-	-	-
2090	-	-	-	-	-
2091	-	-	-	-	-
2092	-	-	-	-	-
2093	-	-	-	-	-
2094	-	•	-	-	-
2095	-	-	-	-	-
2096	-	•	-	-	-
2097	•	•	-	-	-
2098	-	•	-	-	-
2099	•	•	-	-	-
2100	-	ı	-	-	•
2101	-	•	-	-	•
2102	-	•	-	-	-
2103	-	•	-	-	-
2104	-	•	-	-	-
2105	-	ı	-	-	-
2106	-	-	-	-	-
2107	-	-	-	-	-
2108	-	-	-	-	-
2109	-	-	-	-	-
2110	-	ı	-	-	•
2111	-	ı	-	-	ı
2112	-	ı	-	-	ı
2113	-	ı	-	-	ı
2114	-	•	-	-	-
2115	-	•	-	-	-
Total	55,030	28,814	-	5,205	89,050

SECTION 11

COMPARISON REPORT: Comparative Analysis of Cost Studies 2015 & 2020 Cost Studies



COMPARISON REPORT 2015 - 2020 of the Turkey Point Nuclear Plant, Units 3 and 4

Project No. 16	4086-01	Rev. 1
	Prepared for: Florida Power & Light Company	
	Prepared by: EnergySolutions, LLC 121 W. Trade Street, Suite 2700 Charlotte, NC 28202	
Authored By:	Kevin M. Kirkley, Sr. Estimator Jake H. Oleksiak, Project Controls Manager	1V19/2020 Date 11/19/20 Date
		X New Report Title Change Report Revision Report Rewrite
	Effective Date:	November 19, 2020

Table of Contents

SUMMARY	3
COMPARITIVE ANAYLSIS	5
Characterization / Surveys	6
Corporate Support (Fixed Overhead)	6
Decontamination & Removal	6
Energy	6
Florida LLRW Inspection Fee	6
INPO, NEI Fees	6
Insurance & Regulatory Fees	6
Misc Equipment / Site Services	7
Program Management	7
Property Taxes	7
Security	7
Spent Fuel Management	7
Spent Fuel Pool Isolation	8
Waste Packaging, Transportation & Disposal (Class A, B, & C)	8
Waste Packaging, transportation, & Disposal (GTCC)	8
CONCLUSION	10

SUMMARY

This document provides a comparative discussion on decommissioning cost estimates prepared for the Turkey Point Nuclear Plant (Turkey Point) in 2015 (by TLG Services, Inc.) and prepared in 2020 (Energy Solutions). The estimates described in this document were constructed for a prompt decommissioning scenario (Prompt DECON) following the scheduled cessation of operations, recognizing that there is approximately a one year offset in the scheduled shutdown dates for the two nuclear units. The scope of the two estimates is consistent, including cost subcategories for license termination, spent fuel management and site restoration activities.

The estimates were generated in 2015 and 2020 dollars, respectively. The 2020, or current estimate, was developed using the basic inventory and plant design information from the 2010 cost model. The data, estimating assumptions and site-specific considerations were reviewed for the 2015 analysis. The cost model was modified where new information was available, updated site-specific information was obtained, or experience from past decommissioning programs justified such changes.

The overall estimate to decommission Turkey Point (for the Prompt DECON alternative) decreased 23.5% over the five-year period between estimates or approximately a 5.2% decrease annually. The decrease in the individual cost subcategories is shown in Table 1.

The cost elements were assigned to one of three subcategories: License Termination, Spent Fuel Management, and Site Restoration. Delegation of cost elements into these categories was for the purpose of comparison (e.g., with NRC financial guidelines) or to permit specific financial treatment (e.g., Asset Retirement Obligation (ARO) determinations). In reality, there can be considerable interaction or overlap between the activities in the three subcategories.

Cost Subsetagemy	2015	2020	Delta	Percent	Annual
Cost Subcategory	(\$1,000s)	(\$1,000s)	(\$1,000s)	Change	Change
License Termination	1,205,581	1,018,355	(187,226)	-15.5%	-3.3%
Spent Fuel Management	479,670	282,949	(196,721)	-41.0%	-10.0%
Site Restoration	94,298	59,888	(34,410)	-36.5%	-8.7%
Total	1,779,549	1,361,192	(418,357)	-23.5%	-5.2%

Table 1 – Cost Subcategory Comparison Between 2015 and 2020 Estimates

The subcategory License Termination was used to accumulate costs that are consistent with the NRC's definition of decommissioning in its financial assurance regulations (i.e., 10 CFR Part 50.75, Reporting and recordkeeping for decommissioning planning, etc.). The cost reported for this subcategory is generally sufficient to terminate the operating licenses for the two reactors, recognizing that there may be some additional cost impact from spent fuel management. The cost associated with Turkey Point License Termination activities decreased 15.5% over the five years or approximately 3.3% decrease annually. The primary driver is EnergySolutions' methodology of minimizing inefficient decontamination activity and removing buildings/structures as radiological in lieu of clean. Our experience has shown this method to reduce personnel exposure to dose, increase general site safety, and provide schedule certainty. Within the 2020 DCE are shifts in scope from the 2015 TLG study with the movement of the

Reactor Buildings, Auxiliary Building, Fuel Handling Buildings, and the Radwaste Building to the License Termination subcategory from the Site Restoration subcategory. The additional debris waste generated from this methodology is offset by the labor decrease in previously mentioned high decontamination areas. Disposal rates for all waste have been updated based on the 2020 Life-of-Plant (LOP) rates provided by FPL.

The Spent Fuel Management subcategory contains costs anticipated to be incurred once the nuclear units cease operation for the off-loading of the pools either directly to the Department of Energy (DOE) or to the Independent Spent Fuel Storage Installation (ISFSI) for interim storage, and the eventual transfer of fuel from the ISFSI to the DOE. The 2020 DCE includes equipment and transfer costs only for shipment of spent fuel to the DOE prior to the cessation of the units, however any staffing costs that is deemed necessary for this work prior to cessation of the units is assumed to be covered by plant operating costs. Costs were also included for the operation of the ISFSI until such time that the transfer of all fuel from this facility to an off-site location (e.g., geologic repository or interim facility) is complete. The costs assigned to this subcategory decreased by 41.0% over the five years or approximately 10.0% decrease annually. The primary driver in the difference is the reduction of the ISFSI operating period. Due to the operating license extension the ISFSI operating period post shutdown of Unit 4 decreased by 20 years. Another major contributor to this difference is the quantity of spent fuel containers that was to be purchased in the 2015 estimate (60) as compared to the number required to be purchased in the 2020 estimate (34). Also, the 2015 estimate includes the cost to expand the existing ISFSI (approximately \$0.4M), but the 2020 cost estimate does not. In addition, it is unclear if TLG included the movement of spent fuel loading campaign to the DOE from the Spent Fuel Pool prior to shut down in the 2015 DCE. This cost is excluded in the Energy Solutions 2020 DCE.

Site Restoration was used to capture costs associated with the dismantling and demolition of buildings and facilities demonstrated to be free from contamination. This includes structures never exposed to radioactive materials. Structures that have been exposed to radioactive material and require decontamination such as the Reactor Buildings, Auxiliary Building, Fuel Handling Buildings, and the Radwaste Building are included in the License Termination subcategory of the 2020 DCE. Structures are removed to a depth of three feet below grade and backfilled to conform to local grade. The costs assigned to the Site Restoration subcategory decreased 36.5% decrease over the five years or approximately 8.7% decrease annually. The primary driver in this difference is the movement of the Reactor Buildings, Auxiliary Building, Fuel Handling Buildings, and the Radwaste Building to the License Termination subcategory. In addition, it is unclear on how the TLG allocated costs (staffing, insurances, taxes, etc.) are derived. The majority of these costs in the 2020 study between Period 3 and Period 4 (License Termination and Site Restoration) are split 93% to License Termination and 7% to Site Restoration.

COMPARATIVE ANAYLSIS

TLG completed a decommissioning cost analysis for Turkey Point in 2015. The analysis provided the Florida Power & Light Company (FPL), the owner and operator of the nuclear units, with the projected costs (in 2015 dollars) to completely decontaminate and dismantle the station following the normal cessation of plant operations. For purposes of this comparison, this analysis is referred to as the 2015 estimate or previous analysis.

In 2020, EnergySolutions performed a new cost analysis for FPL. The current analysis uses the physical plant inventory, and information provided by FPL to complete the current analysis. This data was reviewed, along with the assumptions from the previous analysis and other site-specific considerations. Based on experience from previous and on-going decomissioning projects and previous proposal efforts, the Turkey Point cost analysis has been revised. In 2015, the estimate to promptly decommission Turkey Point (DECON alternative) was estimated at approximately \$1,779.6 million (in 2015 dollars). The comparable cost in 2020 is \$1,361.2 million (in 2020 dollars). This represents a 23.5% decrease in the overall cost.

The decommissioning scope of the current cost estimate has not significantly changed from that evaluated presented in 2015. To compare the estimates, the costs have been broken down into 15 separate cost elements as shown in the Table 2 below. A brief description of the change and primary contributing factor(s) to the change is detailed within the following narrative. As a general note to the below cost element comparisons: Energy*Solutions* has attempted to group the elements similarly to the 2010-2015 Comparison Report; however, it is unclear if all cost elements contain similar information/costs.

Table 2 – Cost Element Comparison Between 2015 and 2020 Estimates

Cost Floment	2015	2020	Delta	Percent	Annual
Cost Element	(\$1,000s)	(\$1,000s)	(\$1,000s)	Change	Change
Characterization/Surveys	37,306	20,151	(17,155)	-46.0%	-11.6%
Cooperate Support (Fixed Overhead)	29,643	32,405	2,762	9.3%	1.8%
Decontamination & Removal	205,071	244,732	39,661	19.3%	3.6%
Energy	40,588	9,792	(30,796)	-75.9%	-24.8%
Florida LLRW Inspection Fee	1,074	5,455	4,380	407.7%	38.4%
INPO, NEI Fees*	7,619	-	(7,619)	-100.0%	-100.0%
Insurance & Regulatory Fees	46,349	75,299	28,950	62.5%	10.2%
Misc. Equip/Site Services	14,679	9,620	(5,059)	-34.5%	-8.1%
Program Management	572,181	415,943	(156,238)	-27.3%	-6.2%
Property Taxes	2,589	694	(1,895)	-73.2%	-23.1%
Security	231,286	105,783	(125,503)	-54.3%	-14.5%
Spent Fuel Management	289,358	95,600	(193,758)	-67.0%	-19.9%
Spent Fuel Pool Isolation	21,250	24,049	2,799	13.2%	2.5%
Waste Packaging, Transportation &					
Disposal - Class A, B, C	248,128	283,825	35,697	14.4%	2.7%
Waste Packaging, Transportation &					
Disposal - GTCC	32,428	37,845	5,417	16.7%	3.1%
Total	1,779,550	1,361,192	(418,358)	-23.5%	-5.2%
* Items assumed to not be required post sl	nutdown				

<u>Characterization / Surveys</u> – 46.0% decrease over the five years or approximately 11.6% decrease annually. The primary driver of this decrease is due to the methodology change. While additional costs associated with the debris waste generated from this methodology these costs are offset by the reduction in labor cost from avoiding extensive decontamination and survey efforts in structures. The 2020 estimate is based on previous experience for Site Characterizations, baseline surveys, and Final Status Surveys.

<u>Corporate Support (Fixed Overhead)</u> – Annual site costs provided decreased from \$3.6 million in 2015 to \$3.3 million in 2020, based on the information provided by FPL. However, the 2020 DCE accounts for a reduced staff and reduced site costs accordingly. These costs are applied across the Periods 1-4 in the DCE estimate.

<u>Decontamination & Removal</u> – 19.3% increase over the five years or approximately 3.6% increase annually. This increase is potentially due to the movement of equipment into this element as opposed to the Misc. Equipment / Site Services cost element. In addition, escalation is a contributor to this increase. The increase is minimized due to a change in methodology of decommissioning between TLG and EnergySolutions.

<u>Energy</u> – 75.9% reduction over the five-year or approximately a 24.8% reduction annually. Based on discussions with FPL, the 2015 DCE utilized the heavy oil energy usage cost. The 2020 DCE utilizes the Gas energy usage cost provided. For comparison the cost per kilowatt hour in the 2015 DCE was \$0.158 and the cost in the 2020 DCE is \$0.0338 per kilowatt hour.

<u>Florida LLRW Inspection Fee</u> – 407.7% increase over the five year period or approximately a 38.4% increase annually. The change in methodology drove this increase. Due to additional waste being generated, additional inspection fees will be required.

<u>INPO</u>, <u>NEI Fees</u> – It is assumed that these are no longer required once the plant has permanently shut down.

Insurance & Regulatory Fees – 62.5% increase over the five-year period. The primary driver of this increase is that the insurance cost is carried out until the spent fuel is removed from the site, this is for Periods 1-5. A portion of this reduction is due to the 20-year license extension in which the costs would be carried under the plants operating budget. The 2015 TLG comparison report states that the Nuclear Property Insurance Premiums were significantly reduced after plant shutdown; however, in the 2020 DCE this rate was reduced at multiple decommissioning milestones. See Table 3 below for rates at shutdown. The reduction of insurance premiums is based on current and previous experience from other projects in the industry. In addition, Emergency Planning Fees (County & FEMA fees in the 2020 DCE) cease once all spent fuel is removed from the spent fuel pool. Also, a portion of this reduction is due to the 20-year license extension in which the costs would be carried under the plants operating budget.

The 2020 rates shown below in Table 3 do not contain contingency.

Table 3 - Insurance and Regulatory Comparison Between 2015 and 2020 Estimates

Annual Cost	2015	2020
Nuclear Liability Insurance Premium (per unit)*	\$1,183,342	\$1,389,009
Nuclear Property Insurance Premium (site)**	\$4,134,000	\$2,511,320
NRC License Fee (per unit)	\$237,000	\$172,000
Emergency Planning Fee (County & FEMA)***	\$917,488	\$1,131,076
NRC Hourly Rate	\$268	\$278

^{* 2020} rate assumes rate provide by FPL will be 50% at time of shutdown. Rate further reduced upon other decommissioning milestones.

Misc. Equipment / Site Services – 34.5% decrease over the five-year period or 8.1% decrease annually. Majority of the difference is due to the major construction equipment has been included in the decontamination and removal portion of the DCE. It is unclear in the 2015 DCE where the construction equipment is included.

<u>Program Management</u> – 27.3% decrease over the five years or 6.2% decrease annually. Reduction is due to difference in staffing plan models from the 2015 to 2020 DCEs. In addition, to the staffing differences, the reduction of 20 years of staffing required during ISFSI only operations is a major contributor to the decrease.

<u>Property Taxes</u> – 73.2% decrease over the five-year period or 23.1% decrease annually. The 2020 DCE assumes land only taxes will be paid post shutdown of both Unit 3 and Unit 4. This cost is carried until the ISFSI demolition is complete. The 20-year reduction in time between shutdown and ISFSI demolition is a contributor to this difference. It is unclear how property taxes were calculated in the 2015 TLG DCE.

<u>Security</u> – 54.3% decrease over the five-year period or 14.5% decrease annually. The main contributor to this decrease is due to the 20-year reduction of the ISFSI operation due to the operating license extension. The difference in security staffing is another key contributor to this decrease.

<u>Spent Fuel Management</u> – 67.0% decrease over the five years or 19.9% decrease annually. The current analysis assumes that the DOE will begin the process of removing spent fuel from the Turkey Point site in 2031 (based upon a 2030 industry-wide start date), however, the DCE only includes spent fuel transferred after the units have permanently shut down. The process is expected to be completed by the year 2073. The schedule is slightly changed from 2015 DCE (Table 5).

A portion of this difference is due to the anticipated savings by FPL of 25% for the container material and equipment due to bulk purchasing. It is unclear if the comparison is comparing like items due to the major difference, although it is known that one major contributor is the 20-year reduction of the ISFSI Operating Period post shutdown of Unit 4. The 2020 DCE costs include the ISFSI maintenance, spent fuel

^{** 2020} rate shown is once plants are shutdown. Rate further reduced upon other decommissioning milestones

^{***} assumed no fee required once spent fuel is removed from the spent fuel pool

maintenance, all spent fuel transfer (both to DOE and ISFSI), and demolition of the ISFSI pad. Table 4 identifies a few of the major items included in the Spent Fuel Management comparison. The 2020 DCE assumes that no ISFSI expansion is required. Table 5 identifies key dates and quantities of the shipping campaigns.

Table 4 – Spent Fuel Management Comparison Between 2015 and 2020 Estimates

Unit Costs (each)	2015	2020
Dry Storage Canister / Horizontal Storage Module	\$1,254,928	\$1,015,163
Loading / Transfer Cost	\$392,600	\$480,000
Pool to DOE Campaign Cost (Unit 3)	\$3,280,100	\$3,374,000
Pool to DOE Campaign Cost (Unit 4)*	-	\$2,261,000
Pool to ISFSI Cost**	\$3,280,100	-
ISFSI Unloading Cost	\$196,300	\$115,000
ISFSI Campaign Cost	\$820,025	

^{*} Cost for Pool to DOE for Unit 4. Assumes 33% savings on equipment.

Table 5 - Spent Fuel Activity Comparison Between 2015 and 2020

Activity	2015	2020	
DOE Repository Opening	2030	2030	
DOE Begin Transfer from Site	2031	2031	
Spent Fuel Transfer - Pool to DOE	24 canisters	25 canisters	
Spent Fuel Transfer - Pool to ISFSI	60 canisters	34 canisters	
Spent Fuel Transfer - ISFSI to DOE	120 canisters	90 canisters	
Final Year of DOE Pickup	2072	2073	
ISFSI Operating Period			
(post unit 4 shutdown) (years)	40 years	20 years	
GTCC Canisters	10 canisters	8 canisters	

<u>Spent Fuel Pool Isolation</u> – 13.2% increase over the five years or 2.5% increase annually. Difference is primarily due to escalation between the years 2015 through 2020.

<u>Waste Packaging, Transportation & Disposal (Class A, B, & C)</u> – 14.4% increase over the five-year period or 2.7% increase annually. Increase is primarily due to the additional debris and soil due to methodology change. As shown in Table 6 the LLRW burial volume increased significantly due to the methodology change. In addition, the soil price increase based on the updated life of plant agreement between Energy*Solutions* and FPL. TLG noted that disposal costs were discounted due to soil volume. Energy*Solutions* also discounted this rate by approximately 40%.

<u>Waste Packaging, transportation, & Disposal (GTCC)</u> – 16.7% increase over the five-year period or 3.1% increase annually. Included in the 2020 DCE is 8 containers versus the 10 included in the 2015 DCE. The cost for disposal is approximately \$7,272 per cubic foot (including contingency) in the 2015 DCE as compared to approximately \$5,805 per cubic foot (including contingency) in the 2020 DCE. The primary

^{**} No fixed cost in 2020 DCE as the DCE assumes loading and transfer equipment for pool to DOE will be utilized for pool to ISFSI. Also, assumes a continuous operation, therefore no additional mobilization and demobilization will be required.

delta in the disposal is due the 2015 cost study includes transportation, while the 2020 study includes transportation as a separate cost. The transportation costs of the GTCC material in the 2020 DCE is approximately \$3.1M (including contingency). In addition, the packaging cost for GTCC between the 2015 DCE and 2020 DCE is significantly different. The 2015 DCE appears to include approximately \$2.0M (excluding contingency) where the 2020 DCE includes approximately \$9.4M (excluding contingency). The difference can be attributed to associated packaging cost captured in the other areas of the 2015 DCE (assumed to be included in the Reactor Vessel Internals packaging costs, but we are unable to verify the assumption).

Table 6 - Waste Comparison Between 2015 and 2020 Estimates

				Waste Volume (CF)	
Waste Class	Waste Form	Cost Basis	Class	2015	2020*
Low Level Radioactive Waste	Debris / Storm Drain **	Energy <i>Solutions</i>	А	327,035	1,773,112
	Soil***	EnergySolutions	А	162,654	657,554
	Debris	WCS	BC	4,149	4,150
Greater than Class C (GTCC)	Modified Dry Storage Containers (DSCs)	Spent Fuel Equivalent	GTCC	4,123	4,122
Total Disposal Volume				497,961	2,438,938
Processed / Conditioned ****	Debris	Recycling Vendors	А	252,292	-

^{* 2020} volume is burial volume.

^{**} Delta in Debris / Storm Drain due to differing Decommissioning methodology between TLG and EnergySolutions.

^{***} Soil delta due to assumed cross contamination during the decommissioning and demolition process.

^{****} Delta due to differing methodology between TLG and Energy Solutions.

CONCLUSION

The total cost to decommission the Turkey Point nuclear units decreased 23.5% over the five-year period between estimates or approximately 5.2% decrease annually.

As shown in Table 1, License Termination costs (or the cost associated with "decommissioning" as defined by the NRC in its financial assurance regulations) decreased 15.5 % over the five-year period (for an average annual decrease of 3.3% annually). The primary change is the methodology in which decommissioning and demolition is being performed. While this change results in additional waste (additional concrete and soil), to increase cost, it is offset by the reduced staffing and labor required. Also, the difference in staffing (utility, security, and DGC) between the 2015 and 2020 DCEs plays a significant role in this cost difference. Also, the Reactor Buildings, Auxiliary Building, Fuel Handling Buildings, and Radwaste Building were moved from the Site Restoration subcategory to the License Termination subcategory.

The Spent Fuel Management subcategory contains costs associated with the interim storage of fuel at the Turkey Point site until such time that the DOE is able to take possession. The costs estimated for this activity decreased 41.0% from 2015. The primary contributor to this reduction is the 20-year reduction of the ISFSI Operating Period post shutdown of Unit 4. This 20-year reduction, reduces staff, security, and all other allocated costs. Another key contributor is the quantity of spent fuel canisters required to be purchased. The 2015 DCE required 60 canisters, where the 2020 DCE required 34 canisters. Also, of note the 2020 DCE canisters are assumed to include a 25% discount for "bulk" purchasing. In addition, it is unclear if the TLG 2015 estimate included the spent fuel transfer to the DOE from the Spent Fuel Pool prior to shut down. This cost is excluded in the 2020 Energy Solutions DCE.

Site restoration (used to capture costs associated with the dismantling and demolition of buildings and facilities demonstrated to be free from contamination) showed a decrease of 36.5% over the five years. The primary contributor to this reduction is the movement of the costs for the Reactor Buildings, Auxiliary Building, Fuel Handling Buildings, and the Radwaste Building from the Site Restoration subcategory to the License Termination subcategory.