



**CITY OF
MOUNT
DORA**

PUBLIC WORKS AND UTILITIES

City Hall
510 N. Baker St.
Mount Dora, FL 32757

Office of the City Manager
352-735-7126
Fax: 352-735-4801

Finance Department
352-735-7118
Fax: 352-735-1406

Human Resources
352-735-7106
Fax: 352-735-9457

Planning and Development
352-735-7112
Fax: 352-735-7191

City Hall Annex
900 N. Donnelly St.
Mount Dora, FL 32757

Parks and Recreation
352-735-7183
Fax: 352-735-3681

Public Safety Complex
1300 N. Donnelly St.
Mount Dora, FL 32757

Police Department
352-735-7130
Fax: 352-383-4623

Fire Department
352-735-7140
Fax: 352-383-0881

Public Works Complex
1250 N. Highland St.
Mount Dora, FL 32757
352-735-7151
Alt. Tel: 352-735-7105
Fax: 352-735-1539
Alt. Fax: 352-735-2892

W. T. Bland Public Library
1995 N. Donnelly St.
Mount Dora, FL 32757
352-735-7180
Fax: 352-735-0074

Website:
www.cityofmountdora.com

VIA EMAIL (pbuys@psc.state.fl.us)

February 10, 2026

Penelope Buys
Florida Public Service Commission
2540 Shumard Oak Boulevard
Tallahassee, FL 32399-0850
Email: pbuys@psc.state.fl.us

Subject: Storm Hardening Report for City of Mount Dora, pursuant to Rule 25-6.0343, FAC

Dear Ms. Buys:

Pursuant to Rule 25-6.0343, Florida Administrative Code, attached is the Storm Hardening Report for 2025 for the City of Mount Dora.

The City is submitting this report to you via email and electronically through the PSC Clerk's office as well.

<https://secure.floridapsc.com/ClerkOffice/EfilingPublic>

Please verify receipt of this report by an email response to me at my email address shown below.

Submitted on behalf of:

Steven G. Langley
Electric Utility Director

Please contact me if you have any questions.

Wayne R. Zimmerman

Deputy Electric Director
401 Limit Avenue
Mount Dora, FL 32757
zimmermanw@ci.mount-dora.fl.us
Office: (352) 735-7151 extension 1818

**City of Mount Dora Report to the Florida Public Service Commission Pursuant to
Rule 25-6.0343, F.A.C.
Calendar Year 2025**

1) Introduction

- a) City of Mount Dora
- b) 401 Limit Avenue
Mount Dora, FL 32757
- c) Contact information: Name, title, phone, fax, email

Mr. Steve Langley
Electric Utility Director

Phone: (352) 735-7155, ex 1815

Fax: (352) 735-1539

Email: langleys@mountdora.gov

2) Number of meters served in calendar year 2025

The City of Mount Dora has approximately 6623 customers.

3) Standards of Construction

a) National Electric Safety Code Compliance

Construction standards, policies, guidelines, practices, and procedures at the City of Mount Dora comply with the National Electrical Safety Code (NESC), (ANSI C-2). For electrical facilities constructed on or after January 1, 2017, the 2017 NESC applies. The edition of the NESC in effect at the time of the facility's initial construction governs electrical facilities constructed prior to January 1, 2017.

b) Extreme Wind Loading Standards

Construction standards, policies, guidelines, practices, and procedures at the City of Mount Dora are guided by the extreme wind loading standards as specified by <http://windspeed.atcouncil.org/> as recommended by the NESC for:

- a) New construction.
- b) Major planned work, including expansion, rebuild, or relocation of existing facilities, assigned on or after December 10, 2006.
- c) Targeted critical infrastructure facilities and major thoroughfares.

c) Flooding and Storm Surges

The City of Mount Dora is in the process of evaluating our standards, policies, guidelines, practices and procedures that address the effects of flooding and storm surges on underground facilities and supporting overhead facilities. Through the Florida Municipal Electric Association, The City of Mount Dora participates in the Public Utility Research Center's (PURC) study on the conversion of overhead electric facilities to underground and the effectiveness of undergrounding facilities in preventing storm damage and outages. We continue to evaluate and address the effects of flooding and storm surge but we feel that it is important to wait for the results of this research to justify the effort and cost of converting overhead to underground. The City is a non-coastal utility, however recognizes many of the Lakes and Drainage within our service territory have potential within these issues.

d) Safe and Efficient Access of New and Replacement Distribution Facilities

Electrical construction standards, policies, guidelines, practices, and procedures at the City of Mount Dora provide for placement of new and replacement distribution facilities so as to facilitate safe and efficient access for installation and maintenance. Wherever new facilities are placed (i.e. front, back or side of property), all facilities are installed so that City's facilities are accessible by its crews and vehicles to ensure proper maintenance/repair is performed as expeditiously and safely as possible. The City decides on a case-by-case basis whether existing facilities need to be relocated. If it is determined that facilities need to be relocated, they will be placed in the safest, most accessible area available.

e. Attachments by Others

Electrical construction standards, policies, guidelines, practices, and procedures at the City of Mount Dora include written safety, pole reliability, and designate compliance to pole loading capacity, and engineering standards and procedures for attachments by others to the utility's electric transmission and distribution poles. We inspect these attachments on an 8 year cycle.

4. Facility Inspections

- a) **Describe the utility's policies, guidelines, practices, and procedures for inspecting transmission and distribution lines, poles, and structures including, but not limited to, pole inspection cycles and pole selection process.**

The City electric system consists of distribution lines, poles, and structures – it owns no transmission facilities. Since its service territory is relatively small, the Electric Department has been able to make visual inspections of its six distribution feeders on an annual basis. Wood poles are visually inspected for cracks and a sounding technique is used to determine potential wood rot. On December 5, 2017, the City engaged a contractor to inspect and treat all wood poles in the electric service territory. This project was completed in 2019 and the City used the inspection results to establish a replacement priority. The City also makes comprehensive field inspections of its distribution lines, poles, and structures. The program consists of an annual field inspection of all six of the City's six distribution feeders, documented with a field report that identifies the following situations:

1. Pole Maintenance Items
2. Vegetation Maintenance
3. Transformer Maintenance
4. CATV Joint Use Attachment
5. Communications Joint Use Attachment

Once the field inspection reports have been completed, City staff goes back to each pole and makes the identified repairs. The City typically schedules the annual field inspections during the first quarter to enable a majority of repairs to be completed before hurricane season. If a third-party pole attachment appears damaged or does not meet NESC clearance requirements, the City notifies the respective party in writing.

To supplement the annual field inspections, the City makes additional inspections before the arrival of adverse weather events, such as hurricanes and tropical storms. The pre-storm inspections utilize the same inspection form as the annual field inspection. Some of the City's distribution lines are attached to 69 kV transmission poles owned by Duke Energy. Any observed problems with the transmission poles are reported directly to Duke Energy. The City utilizes a GIS mapping system for its electric distribution system. The GIS system is now being used to map and manage all of the City's distribution facilities including wood and concrete poles, attached hardware, pole attachments by other entities, and underground electrical facilities.

The City also makes comprehensive field inspections of its distribution lines, poles, and structures. The program consists of an annual field inspection of all six of the City's six distribution feeders, documented with a field report that identifies and reports resolution to any anomalies detected.

b) Describe the number and percentage of transmission and distribution inspections planned and completed for 2025.

The City completed its annual field inspections of its six distribution system during 2025. The City owns no transmission facilities so no inspections were made.

c) Describe the number and percentage of transmission poles and structures and distribution poles failing inspection in 2025 and the reason for the failure.

Pole inspections are conducted by the City on an eight (8) year cycle. The past inspection was completed in 2019 with all corrective measures being complete. The City is in the process of acquiring a pole-inspection contractor to begin inspections in the Fiscal Year beginning October 1, 2026.

d) Describe the number and percentage of transmission poles and structures and distribution poles, by pole type and class of structure, replaced or for which remediation was taken after inspection in 2025, including a description of the remediation taken.

The City remediated all of the issues identified in the annual field inspection and has replaced installed additional poles shown in the data below.

The City attaches its distribution circuits to certain Duke Energy 69 kV transmission poles that are within the City's electric service area. Of the 90 transmission poles, 34 are wood. Duke Energy has an on-going program of replacing its older wood poles with steel poles. While these transmission poles are not owned by the City, the pole replacement program improves the ability of the City's distribution system to better withstand storm events since its distribution circuits attach to the poles. Moreover, hardening the two Duke Energy 69 kV transmission circuits that feed the Mount Dora Substation improves overall reliability.

The following table lists all wood poles that were replaced / installed with concrete, fiberglass, or steel poles in 2025:

Description	Number of Poles at 1/01/25				Wood Pole Replacements Count	Added Poles Count	Removed Poles Count	Number of Poles at 12/30/2025	
	Original Count	Inventory Adjustment ⁽¹⁾	Revised Count	% of Total Poles				Count	% of Total Poles
Wood Poles									
25 foot	143	0	143	4.9%		0	0	143	4.8%
30 foot	640	0	640	21.9%		0	0	640	21.7%
35 foot	39	0	39	1.3%		0	0	39	1.3%
40 foot	446	0	446	15.3%		4	0	450	15.2%
45 foot	458	0	458	15.7%		0	0	458	15.5%
50/55 foot	0	0	0	0.0%		0	0	0	0.0%
Duke Energy Transmission ⁽²⁾	34	0	34	1.2%		0	0	34	1.2%
Total Wood Poles	1,750	0	1,760	60.0%	0	4	0	1,764	59.7%
Concrete/Fiberglass/Steel Poles									
30 foot	470	0	470	40.2%		0	0	470	39.4%
35 foot	0	0	0	0.0%		0	0	0	0.0%
40 foot	235	0	235	20.1%		2	0	237	19.9%
45 foot	390	0	390	33.4%		0	0	390	32.7%
50/55 foot	28	0	28	2.4%		0	(1)	27	2.3%
Duke Energy Transmission ⁽²⁾	56	0	56	4.8%		12	0	68	5.7%
Total Concrete/Fiber/Steel	1,169	0	1,179	40.0%	0	14	(1)	1,192	40.3%
Total Poles:	2,919	0	2,939	100.0%	0	18	(1)	2,956	100.0%
(1) The number of poles in the table were adjusted to reflect field inventory updates for the GIS mapping system. (2) Duke Energy Transmission Poles within the City's electric service area.									

5. Vegetation Management

- a) Describe the utility’s policies, guidelines, practices, and procedures for vegetation management, including programs addressing appropriate planting, landscaping, and problem tree removal practices for vegetation management outside of road right-of-ways or easements, and an explanation as to why the utility believes its vegetation management practices are sufficient.

The City's Electric Division trims trees on a 24 month cycle using an outside contractor. This contractor focuses on clearing vegetation that could adversely impact the reliability of the City’s electric distribution system and to insure compliance with the NESC. In addition to the contractor crew, the City employs one two-man crew that is continuously trimming trees and reducing vegetative growth throughout other parts of the City. In some situations, the City crew assists the contractor crew in trimming or removing large trees.

The City routinely removes limbs from trees located outside road right-of-ways or easements that could create clearance problems for its overhead distribution circuits. The City has also removed entire trees in such locations if those trees threaten overhead distribution circuits (usually dead trees in danger of falling).

The City believes that its vegetation management practices result in high reliability because it trims trees on a 24 month cycle, which is much more frequent than the practices of other Florida

electric utilities. The City owns no transmission facilities.

b) Describe the quantity, level, and scope of vegetation management planned and completed for transmission and distribution facilities in 2025.

The City Electric Division trimmed approximately 16.4 miles of distribution lines in maintaining a 24 month cycle for Circuits M597, M595 and M596. The City utilized an outside contractor to trim these three circuits. The City also removed limbs from trees located outside road right-of-ways or easements that could create clearance problems for its overhead distribution circuits. The City owns no transmission facilities.

CITY OF MOUNT DORA					
VEGETATION LINE CLEARANCE SCHEDULE					
24 Month Trim Cycle for Six (6) distribution circuits					
CIRCUIT	MILES	CYCLE YEAR		CYCLE YEAR	
		1	2	1	2
		2024	2025	2026	2027
M597	8.2		8.2	8.2	
M598	7.4	7.4		7.4	
M593	9.2	9.2		9.2	
M594	3.5	3.5			3.5
M595	8.0		8.0		8.0
M596	8.4		8.4		8.4
Total Miles	36.5	20.1	16.4	16.6	19.9

6. Storm Hardening Research

The City of Mount Dora is a member of the Florida Municipal Electric Association (FMEA), which is participating with all of Florida’s electric utilities in storm hardening research through the Public Utility Research Center at the University of Florida. Under separate cover, FMEA will provide the FPSC with a report of research activities. For further information, contact Amy Zubaly, Executive Director, FMEA, 850-224-3314, ext. 1001, or azubaly@flpublicpower.com.