




Withlacoochee River Electric Cooperative, Inc. (WREC)

2013 Hurricane Preparedness

Florida PSC Hurricane Preparedness Workshop

April 3, 2013



System Statistics

•	Miles of Transmission Line	64
•	Miles of Overhead Distribution Line	7,099
•	Miles of Underground Distribution Line	3,634
•	Number of Substations	53
•	Number of Services Connected	217,210

Meters Served by County (March 31, 2013)

Pasco 97,363

Hernando 78,619

Citrus 24,688

• Polk 517

• Sumter <u>932</u>


Total Active Meters 202,109

Standards of Construction

- NESC 2012 Compliance
- Prior 2012 Compliance to standard at time
- RUS bulletins, drawings and engineering specifications
- WREC Construction & Operations Manual
- Pole Foreman calculates pole strength capabilities & clearances of specified spans and compare results (extreme wind loading)

Flooding & Storm Surges

- Stainless Steel pad mounted equipment
- Strand-filled Jacketed cable inside duct



Safe & Efficient Access / Attachments by Others

- 2012 Relocated approx. 30,000' of OH primary lines from rear lot line to street. (estimate 4 yr. completion time frame)
- Joint use agreements specify compliance with NESC & RUS requirements. Clearance and loading evaluated per each attachment request.

Facility Inspections

- 2012 approx. 2,800 miles of line inspected or addressed by line patrol, rear to front relocation, voltage conversion & S.T.A.R program
- Transmission = 62 miles patrolled annually (aerial and ground)
- Substations inspected monthly
- Pole inspection on schedule for 8 year cycle
- Monthly/Annually maintenance on equipment (control panels, relays and etc.)
- Annual Infrared of Critical Infrastructure

Vegetation Management

- Aggressive VMP implemented in 2004 to increase both horizontal & vertical clearances and problem tree removal
- Currently on a three (3) year cycle for all distribution lines
- Transmission lines are trimmed annually as needed
- ROW service orders are generated and completed for cycle busters (1,334 in 2012)

Storm Preparedness

Annual Activities:

- ERP Reviewed and Updated
- Roundtable Discussion of ERP
- Participate in Seminole & County EOC drills
- Internal Resources Pre-assigned
- Contractor Storm Restoration Contract
- FECA Mutual Aid Agreement

Communications

- Personnel Assigned to County EOC's
- Web Based Graphical Outage Map
- Daily updates from Manager of PR

FECA

Local EOC's

Local Media

Cooperative Website

Vulnerability Concerns

- Coastal Flooding Raised pad mounted equipment
- Insufficient Outside Crews Enter storm restoration contract
- Heavy Right-of Way Increased clearances on distribution lines in rural wooded areas
- Multiple Storms Conversion allows for back feed of any substation (80 % completed - 4 yr. completion)

WREC Emergency Restoration Plan



ERP

The Primary Objective of this plan is to:

- Evacuate employees and equipment from areas subject to storm surge.
- Protect the public from exposure to hazardous conditions caused by the disaster.
- Limit damage to Cooperative property.
- Provide for the orderly restoration and repair of the Cooperative's transmission and distribution system.

Restoration Procedures

Objective:

To establish uniformly implemented methods for expediting power restoration while maintaining the highest level of safety.



Damage Assessments

General Assessment (ball park)

- Detailed Assessment (bird dogging)
- Assessment Teams pre-identified
- HQ Engineers assigned to districts

Priority Accounts

- Medical facilities, Shelters, Jails
- Major intersections
- County administration buildings
- Water, Sewer plants
- Restaurants, Grocery Stores, Pharmacies
- Hotel, Motels

Crew Briefings

- Hold each morning at 6:00
 A. M. during restoration period.
- Discuss work hours, safety hazards, work progression and feedback from field personnel.
- Invite General Foremen of contract crews to attend.



FOREIGN CREWS




Circuit maps will be made available to all foreign crews due to their unfamiliarity of WREC's system.



Line Patrol

 All substations, transmission and distribution lines shall be inspected and/or patrolled prior to energizing.



Outage Management System

- Dispatch assigned for night duty
 (3:00 P.M 6:00 A.M.)
- Primary objective to update OMS.
- Identify outage areas with high consumer density.



Additional Topics

- Drills Major storm in March tested system.
 Meeting scheduled for April to discuss means of improvement
- The company removes problem trees at company expense – no replacement program
- Total of 200,446 poles on system and installed/replaced 26,000 since starting storm hardening (approx. 70% of wood poles are CCA)
- Company is on target to meet storm hardening goals

Additional Topics

- Hurricane Sandy caused extreme flooding to some of our costal service area. We have raised pad mounted equipment.
- Roundtable discussion scheduled in April outcome will determine any revisions to plan.
- Critical Infrastructure improvements are identified in 2 yr. work plans (2012-2014)

QUESTIONS ?